

RECEIVED

By Alameda County Environmental Health at 3:40 pm, Jun 21, 2013



ARCADIS U.S., Inc.
100 Montgomery Street, Suite 300
San Francisco, CA 94104
Tel 415.374.2744
Fax 415.374.2745
www.arcadis-us.com

Results of DPE Test and SPH Removal
Former BP Service Station #11132
3201 35th Avenue
Oakland, California
ACEH Case #RO0000014

ENVIRONMENT

"I declare that to the best of my knowledge at the present time, that the information and/or recommendations contained in the attached document are true and correct."

Date:
June 12, 2013

Submitted by:

Contact:
Hollis E. Phillips

ARCADIS U.S., Inc

Phone:
415.432.6903

Email:
Hollis.phillips@arcadis-us.com

Hollis E. Phillips, PG
Project Manager

Our ref:
GP09BPNA.C112



Imagine the result



Dilan Roe, P.E.
Hazardous Materials Specialist
Alameda County Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, CA 94502-6577

Subject:
Results of DPE Test and SPH Removal
Former BP Station #11132
3201 35th Avenue, Oakland, California
ACEH Case #RO0000014

Dear Ms. Roe:

ARCADIS U.S., Inc. (ARCADIS) has prepared this letter to provide a summary of recent field activities at the Former BP Station #11132 located at 3201 35th Avenue, in Oakland, California (Site). A dual-phase extraction (DPE) pilot test was conducted in November 2012 as proposed in the "Site Remedial Strategy Update," submitted on June 23, 2011 and in the "Proposal for DPE" letter submitted on July 6, 2012, to evaluate the potential effectiveness of DPE as a remedy at the Site during seasonal groundwater elevation lows. During baseline water level gauging prior to DPE startup separate phase hydrocarbon (SPH) was observed at well OW-1. The product was removed and the DPE pilot test was conducted. Following completion of the DPE pilot test ARCADIS conducted monthly SPH bail-down activities for three consecutive months to remove SPH and evaluate SPH mobility at monitoring wells OW-1 and MW-10, as described in the letter submitted on January 11, 2013 (ARCADIS 2013).

DPE Pilot Test Summary

On November 12, 2012, ARCADIS mobilized a trailer-mounted DPE unit to the Site with Mako Industries (Mako) to initiate field activities. Following review of health and safety procedures and site setup, ARCADIS conducted baseline depth-to-water (DTW) readings at all monitoring wells on-site and identified 0.99 feet of SPH in well OW-1. The presence of SPH was not anticipated at OW-1, as it is not routinely monitored as part of the semiannual groundwater monitoring program; therefore, system startup was temporarily postponed while SPH removal (bailing) was conducted. Approximately half a gallon of SPH/water mixture was bailed and stored

ARCADIS
100 Montgomery Street
Suite 300
San Francisco
California 94104
Tel 415.374.2744
Fax 415.374.2745
www.arcadis-us.com

ENVIRONMENT

Date:
June 12, 2013

Contact:
Hollis Phillips

Phone:
415.432.6903

Email:
Hollis.Phillips@arcadis-us.com

Our ref:
GP09BPNA.C112

in a 55-gallon drum. Field notes from DPE field activities are included as **Attachment A**.

Following system setup and initial bailing activities, startup of the DPE system was further delayed until November 15, 2012 due to two malfunctioning/improperly sized submersible pumps intended to support dewatering. ARCADIS determined the use of a stinger would be sufficient to support dewatering and soil vapor extraction simultaneously. Baseline DTW and vacuum readings were collected from all wells on-site prior to startup. Monitoring wells MW-2 and MW-10 were initially selected as extraction locations; however, health and safety concerns and access restrictions at MW-10 due to placement within an active bus stop limited DPE to MW-2. During DPE activities, air and water were extracted from monitoring well MW-2 using a 1.5-inch diameter stinger and directed to a water knockout tank. Extracted vapors were treated by a thermal oxidizer prior to discharge to the atmosphere and extracted groundwater was transferred to an on-site holding tank pending analysis and off-site disposal. Approximately 16,100 gallons of water at an average flowrate of 2.2 gallons per minute (gpm) were extracted during the course of the DPE event, as shown in **Table 1**.

Throughout pilot test activities, pressure, air velocity, and total volatile organic compounds (VOC) measurements were collected at the oxidizer inlet to evaluate mass removal rate from MW-2. Results included in **Table 2** indicate that mass removal rates from MW-2 varied from 0.9 to 1.5 pounds of VOCs removed per day (lb/day). The concentration of VOCs extracted from MW-2 did not increase significantly over the course of the test, indicating that submerged source mass was not sufficiently exposed to increase VOC concentrations and mass removal rates.

The radius of influence (ROI) of DPE at the Site was measured by monitoring induced vacuum and DTW at selected response wells (VE-1, VM-2, AS-1, VM-1, OW-1, and RW-1) surrounding MW-2 at periodic intervals during the test. Field data included in **Table 3** indicate that vacuum response was observed in all wells, with exceptionally high vacuum response at VM-1 and VM-2. This is likely due to the fact that VM-1 and VM-2 are located approximately 7 and 16 feet from MW-2, respectively, and screened almost entirely in the vadose zone. The vacuum response observed at AS-1 and RW-1, which are located approximately 25 feet from MW-2 suggests that an ROI of at least 25 feet was obtained. DTW observations at the monitoring locations also indicated substantial influence. DTW measurements observed at AS-1 and RW-1 increased by 4 feet at each location, suggesting water table drawdown.

Review of mass removal rates and response well data collected during the 5-day DPE pilot test suggest that although the water table was lowered by approximately 4

feet and vacuum was induced as far as 25 feet from the extraction well, sufficient submerged source mass was not exposed to remove a significant amount of mass. Additionally, the average water extraction rate of 2.2 gpm does not make DPE a cost effective remedial strategy.

SPH Bail-down activities

Throughout DPE operations, DTW and depth-to-product (DTP) measurements were collected at OW-1 to monitor the SPH thickness during dewatering. As shown in **Table 3**, the SPH thickness remained constant between 0.35 and 0.43 feet throughout the duration of the test. SPH thickness did not increase as the water table was lowered, indicating that additional drainable SPH does not exist below the static water table near OW-1.

To further characterize SPH mobility, three bail-down events were conducted on a monthly basis during the first quarter of 2013. Field notes from SPH bail-down events are included as **Attachment B** and the data are summarized in **Table 4**. The SPH bailing events consisted of measuring initial thickness, removing SPH/water from the well until no measurable thickness is remaining, and measuring the final thickness of SPH immediately after bailing and again before leaving the site to determine if recharge occurred. Monitoring was conducted at locations MW-10 and OW-1, where both SPH and sheen have historically been observed. In the first event following DPE operations, conducted on January 17, 2013, the initial product thickness at OW-1 was observed to be 0.10 feet, approximately 2 months after the end of the DPE test. SPH was removed from OW-1 using a disposable bailer and the SPH/water mixture was placed in 55-gallon drum temporarily staged in the remediation compound on-site. Upon departure during the first bailing event, SPH was observed to have recharged to a thickness of 0.01 feet. During the second bailing event, conducted on February 20, 2013, SPH was observed in OW-1 at a thickness of 0.02 feet, indicating a recharge of approximately 0.01 feet over a one month period. SPH recharge was not observed upon departure during the second event. During the third bailing event, conducted on March 8, 2013, SPH was observed in OW-1 at a thickness of 0.01 feet indicating a recharge of approximately 0.01 feet over a one month period. Similar to the second event, SPH recharge was not observed upon departure. Additionally, during the February and March bailing events, the water table was nearly 3 feet lower than the January event. The lower water table exposed more smear zone soils and, therefore, would have increased the potential for drainable SPH to enter the well if it was present. As indicated in field forms in **Attachment B**, SPH was not observed at MW-10 during any of the bailing events. Following completion of the bailing events, the drum containing the SPH/water mixture was properly disposed of offsite.

Baseline and departure readings from each bailing event indicate that the rate of SPH recharge at OW-1 decreased with each successive event. The decreasing rate of recharge, minimal SPH thickness, and lower water table observed during the final two bailing events indicates that drainable SPH has been removed to the extent practicable.

Conclusions

Results from the DPE pilot test indicate that although DPE effectively lowered the water table and propagated a vacuum within the subsurface, sufficient submerged source mass was not exposed in order to achieve effective mass removal rates. Additionally, the average water extraction rate of 2.2 gpm does not make DPE a cost effective remedial strategy. Monitoring of SPH thickness during DPE activities and subsequent bail-down activities at OW-1 indicate that drainable SPH has been removed to the extent practicable at OW-1.

ARCADIS is currently compiling historical site data in order to complete the Low Threat Closure (LTC) checklists provided by ACEH on May 31, 2013. Based on the results of the LTC checklists, ARCADIS will present a revised site strategy. If you have any questions or comments regarding the contents of this letter, please contact Hollis Phillips of ARCADIS at 415.432.6903 or by e-mail at Hollis.Phillips@arcadis-us.com.

Sincerely,
ARCADIS



Hollis Phillips P.G.
Project Manager

Attachments

Figure 1	Site Plan
Table 1	Cumulative Water Removed
Table 2	System Data and Mass Removal Rates
Table 3	Response Well Data
Table 4	SPH Bail-down data at OW-1
Attachment A	Field Forms – DPE Pilot Test
Attachment B	Field Forms – SPH Bail-down

References:

ARCADIS US, Inc. 2011 (ARCADIS). *Site Remedial Strategy Update, Former BP Station #11132, 3201 35th Avenue, Oakland, California, ACEH Case #RO0000014.* June.

ARCADIS US, Inc. 2012 (ARCADIS). *Proposal for DPE, Former BP Station #11132, 3201 35th Avenue, Oakland, California, ACEH Case #RO0000014.* July.

ARCADIS US, Inc. 2013 (ARCADIS). *Proposed Additional Remedial Activities, Former BP Service Station No. 11132, 3201 35th Avenue, Oakland, California, ACEH Case #RO0000014.* January.

Table 1
Cumulative Water Removed
Results of DPE Test and LNAPL Removal
Former BP Station No. 11132
3201 E 35th Avenue, Oakland, California

Date	Time	Totalizer	Cumulative Volume (gal)	Average Flowrate (gpm)	Notes
11/15/2012	10:00	257,171	---	---	Baseline
11/15/2012	12:00	257,419	248	2.1	
11/15/2012	17:00	258,084	913	2.2	
11/16/2012	9:00	260,055	2,884	2.1	
11/16/2012	15:30	260,996	3,825	2.4	
11/17/2012	9:25	263,208	6,037	2.1	
11/17/2012	16:19	264,085	6,914	2.1	
11/18/2012	9:30	266,234	9,063	2.1	
11/18/2012	15:45	267,076	9,905	2.2	
11/19/2012	9:15	269,347	12,176	2.2	
11/19/2012	15:00	270,125	12,954	2.3	
11/20/2012	8:30	272,439	15,268	2.2	
11/20/2012	15:00	273,280	16,109	2.2	

Notes:

gal gallons
gpm gallons per minute

Table 2
System Data and Mass Removal Rates
Results of DPE Test and LNAPL Removal

Former BP Station No. 11132
 3201 E 35th Avenue, Oakland, California

		Blower Inlet				Dilution Line				Oxidizer Inlet Line					
		Pipe flow diam (in): 3 Pipe Flow Area (ft ²): 0.049				Pipe flow diam (in): 2 Pipe Flow Area (ft ²): 0.022				Pipe flow diam (in): 3 Pipe Flow Area (ft ²): 0.049					
Date	Time	Vacuum (in Hg)	Velocity (ft/min)	Flow Rate (ACFM)	Flow Rate (SCFM)	Vacuum (in Hg)	Velocity (ft/min)	Flow Rate (ACFM)	Flow Rate (SCFM)	Pressure (in H ₂ O)	Velocity (ft/min)	PID (ppm _v)	Flow Rate (ACFM)	Flow Rate (SCFM)	Mass Removal (lbs/day)
11/15/2012	10:40	---	---	---	---	CLOSED				0.12	303	656	14.9	14.9	0.9
11/15/2012	11:50	---	---	---	---	CLOSED				0.12	460	728	22.6	22.6	1.5
11/15/2012	17:00	---	---	---	---	CLOSED				0.20	397	773	19.5	19.5	1.4
11/16/2012	9:00	---	---	---	---	CLOSED				0.20	393	743	19.3	19.3	1.3
11/16/2012	15:30	---	---	---	---	CLOSED				0.23	407	649	20.0	20.0	1.2
11/17/2012	9:25	---	---	---	---	CLOSED				0.21	451	604	22.1	22.1	1.2
11/17/2012	16:19	---	---	---	---	CLOSED				0.36	430	665	21.1	21.1	1.3
11/18/2012	9:30	---	---	---	---	CLOSED				0.35	410	658	20.1	20.1	1.2
11/18/2012	15:45	---	---	---	---	CLOSED				0.39	426	660	20.9	20.9	1.2
11/19/2012	9:15	---	---	---	---	CLOSED				0.32	420	612	20.6	20.6	1.1
11/19/2012	15:00	---	---	---	---	CLOSED				0.82	402	590	19.7	19.8	1.0
11/20/2012	8:30	---	---	---	---	CLOSED				0.80	430	600	21.1	21.1	1.1
11/20/2012	15:00	---	---	---	---	CLOSED				0.80	418	605	20.5	20.6	1.1

Notes:

- not measured
- ACFM actual cubic feet per minute
- in inches
- in Hg inches of mercury
- in H₂O inches of water
- ft² square feet
- ft/min feet per minute
- lbs/day pounds per day
- ppm_v parts per million by volume
- SCFM standard cubic feet per minute

Flow and Emission Equations

$ACFM (ft^3/min) = Velocity (ft/min) \times Flow Area (ft^2)$

$$SCFM_{25C} = ACFM \times \frac{P_{abs} + P_g}{P_{abs}} \times \frac{537}{460 + T}$$

Mass Removal (lb/day) = SCFM (ft³/min) x VOCs (ppmv) x 6.23x10⁻⁸ [(lb/ft³)/(ppmv)] x 1440 (min/day)

where:

- P_{abs} = Atmospheric Pressure at Sea Level (1 atm = 406.8 in H₂O)
- P_g = Gauge/Line Pressure - equivalent to zero if atmospheric discharge
- T = Airstream Temperature, degrees Fahrenheit (°F)

Table 3
Reponse Well Data
Results of DPE Test and LNAPL Removal
Former BP Station No. 11132
3201 E 35th Avenue, Oakland, California

Location ID:		VE-1		VM-2		AS-1		VM-1		RW-1		OW-1				Notes
Date	Time	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	DTP (ft bTOC)	Product thickness (feet)	
11/15/2012	1000	0.00	18.94	0.00	16.91	0.28	19.85	0.00	17.22	0.02	19.32	0.00	20.35	19.96	0.39	Baseline
11/15/2012	1100	0.07	18.94	5.60	17.29	6.71	22.07	0.15	17.22	0.43	19.99	0.00	22.22	21.83	0.39	
11/15/2012	1200	0.08	18.94	6.84	17.40	6.71	22.65	0.12	17.22	0.32	20.40	0.00	22.74	22.35	0.39	
11/15/2012	1700	0.17	18.96	8.17	17.50	6.25	23.28	0.23	17.26	0.06	21.85	0.00	23.41	23.03	0.38	
11/16/2012	900	0.24	19.05	11.58	17.77	5.80	24.05	0.43	17.30	0.12	22.98	0.00	24.21	23.82	0.39	
11/16/2012	1530	0.27	19.06	11.75	17.78	4.77	24.25	1.01	17.10	0.11	23.25	0.00	24.31	23.88	0.43	
11/17/2012	925	0.66	19.10	45.86	18.82	2.36	24.65	1.96	17.21	1.96	23.12	0.61	24.50	24.11	0.39	
11/17/2012	1619	0.73	19.15	34.77	18.42	4.51	24.40	14.65	17.93	2.76	23.22	0.02	24.52	24.14	0.38	
11/18/2012	930	0.87	19.19	43.39	18.80	5.37	24.36	33.17	18.72	0.00	23.40	1.24	24.41	24.05	0.36	
11/18/2012	1545	0.84	19.21	46.45	18.94	6.06	24.40	37.69	18.94	0.02	23.45	0.64	24.46	24.10	0.36	
11/19/2012	915	0.89	19.27	48.10	19.05	7.63	24.46	34.81	18.90	0.32	23.52	1.42	24.52	24.17	0.35	
11/19/2012	1500	0.84	19.30	48.74	19.05	6.49	24.42	31.78	18.81	0.04	23.55	1.78	24.52	24.14	0.38	
11/20/2012	830	0.84	19.38	45.64	19.12	4.60	24.45	30.28	19.52	0.04	23.55	2.78	24.53	24.20	0.33	
11/20/2012	1500	0.95	19.44	26.74	19.22	3.23	24.45	25.83	19.50	0.41	23.56	1.63	24.53	24.21	0.32	

Notes:

- DTP depth to product
- DTW depth to water
- ft bTOC measured from top of temporary riser pipe (~1 foot above top of well casing)
- in H₂O inches of water

Table 4
LNAPL Bail-down Data at OW-1
Results of DPE Test and LNAPL Removal
Former BP Station No. 11132
3201 E 35th Avenue, Oakland, California

Date	Time	Phase	DTW (ft bTOC)	DTP (ft bTOC)	Product thickness (feet)	Notes
1/17/2013	13:55	pre-bailing	15.00	14.90	0.10	
1/17/2013	14:10	post-bailing	14.10	--	--	
1/17/2013	14:35	departure	15.03	15.02	0.01	
2/20/2013	7:46	pre-bailing	17.79	17.77	0.02	
2/20/2013	7:55	post-bailing	18.59	--	--	
2/20/2013	8:25	departure	17.79	--	--	
3/8/2013	7:49	pre-bailing	17.98	17.97	0.01	
3/8/2013	8:04	post-bailing	18.4	--	--	
3/8/2013	8:22	departure	17.98	--	--	

Notes:

DTP depth to product
DTW depth to water
ft bTOC measured from top of temporary riser pipe (~1 foot above top of well casing)
gal gallons


Site Visit Report

ARCADIS Project Number: GPO9BNA.C176		Dates of Site Visit: 11/12/12	
ARCADIS Project Name: BP 11132		Location of Project: 3201 35 th Ave, Oakland, CA	
ARCADIS Personnel Present: E Mantor		Other Persons Present: Rob/Moro	
Purpose of Site Visit: DPE pilot			
Date & Time:		Activities:	
0730	Arrive on-site conduct A&S meeting		
0800	DISCUSS with station attendant Gas delivery Thursday or Friday 9-10 pm.		
0835	Backup trailer + get positioned; set up cones		
0820	Mob to equipos to pickup PID.		
0950	Back on-site w/ equipment; propane delivery		
1015	Tank; fencing + Fedex (pump) drop off.		
1100	Background PID for air monitoring MW-2 = 2.5 ppm VM-2 = 417 ppm VE-1 = 490 ppm As-1: 0.0 ppm OW-1 = 250 ppm VM-1 = 50 ppm VOCs in breathing zone = 0.0 ppm @ VM-2 + VE-1		
1120	E Mantor off site to get traffic control		
1215	Back on-site; propane fill truck on-site		
1230	Baseline DTW; product at OW-1 ~ 2 dark amber, very sticky 2' on tape		
1400	Rob back on-site; put in down-hole piping VE-1 ≈ 19.3' of tubing VM-2 ≈ 19.5' of tubing VM-2 ≈ 19.4' of tubing As-1 ≈ 29.5'		
1430	Mob to E-ville to get barrels		
1500	Back on-site; Bail OW-1 Open remediation compound; LNAPL bailing drums on-site DTP: 19.06 DTW = 20.05' Bail ≈ 24" NAPL		
1600	Past bailing: DTP = 19.30 DTW = 19.40'		
1845	Stop work; Find RW-1; too late to start unit; postpone		
Weather: Sunny 70's		Signature & Date:	
		Eqpt Billing Log to Accounting	
		Date:	Initials:

1730 Make offsite
1745 pickup chain & Locks for compound
1800 Security on-site
1840 Lock up; Demob

Casey: 916-223-8641

Site Visit Report

ARCADIS Project Number: GPO977NA C112. Keoo		Dates of Site Visit: 11/13/12 / 11/14/12	
ARCADIS Project Name: B8/1132		Location of Project: Oakland CA	
ARCADIS Personnel Present: A. Shah		Other Persons Present: Rob from Make	
Purpose of Site Visit: DPE Pilot			
Date & Time:		Activities:	
0800		Make onsite to complete Setup	
0945		AS onsite H&S tailgate	
		Baseline at ON-1: $PTW = 19.82$ (w/ riser) $SPT = 0.42$ feet	
1000		Start dewatering MW-2 w/ pump	
1100		Determine pump is not capable of 3 GPM. Phone rental company to send replacement. Discuss w/ D. Evans & H. Phillips, decide to wait for new pump.	
1130		Demob Equipment	
1215		Leave Site, AS to Eville for shipments.	
11/14/12			
0800		AS to pickup Equipment	
0900		Make onsite. Tim Hess & Don Johnson onsite	
0945		H&S Tailgate Site Setup	
1000		Gas Delivery	
1020		Begin Dewatering	
1045		Gas Delivery Complete	
1050		Begin VE	
1100		Pump not providing sufficient flow Begin troubleshooting	
1200		Determine proper improper pump. Discuss w/ D. Evans. Says to shutdown & demob. Make	
1300		Discuss w/ HEP & K. Houston. Decide to start tmrw w/ Stinger	
Weather:		Make offsite.	
		Signature & Date: 	
		Eqpt Billing Log to Accounting	
		Date: Initials:	

Site Visit Report

Date & Time:	Activities:
11/15/12.	
0830	AS onsite
0930	Make onsite (Heavy traffic due to accident)
0945	OW-1: DTP=19.96, DTW=20.35 (no change in SPH from 11/13/12) (K.H. Baseline) Start totalizer 25717
1010	Start system
	Set stinger at 31 ft bTOL
1040	System Readings
1100	MW readings
1115	Test float switch on KO tank & Storage tank
	Test Auto Dialer All functioning
1130	Confirm readings w/ K.H. Thumbs up!!
1200	Round of Readings ~2.5 gpm.
1230	AS & Make offsite
1700	AS onsite
	Round of Readings, ~2 gpm H ₂ O
1730	AS offsite
11/16/12	
0845	AS onsite, water pickup ~4 AM
	Round of Readings, ~2 gpm H ₂ O
0930	AS offsite.
1300	AS/MD onsite
1530	System Readings, ~2.1 gpm H ₂ O
1600	AS/MD offsite
11/17/12	
	0930 MD ON SITE - RAINING
	Round of readings
	10:40 OFF SITE
	16:15 - MD ON-SITE
	Round of Readings.
	1700 - DEPARTED SITE

Site Visit Report

ARCADIS Project Number: 6009384-1132		Dates of Site Visit:	
ARCADIS Project Name:		Location of Project:	
ARCADIS Personnel Present:		Other Persons Present:	
Purpose of Site Visit:			
Date & Time:		Activities:	
11-18-12/0930		MD ON SITE ~ 2 GPM H ₂ O ROUND OF READINGS NOTED INCREASE VAC READINGS ON VM-1 + VM-2 10:10 - DEPARTED SITE	
1610		MD ON SITE ROUND OF READINGS	
1045		MD OFF SITE	
11-19-12		09:15 MD ON SITE ROUND OF READINGS ~ 2 GPM H ₂ O	
10:00		MD OFF SITE	
1500		MD ON SITE ROUND OF READINGS	
1530		MD OFF SITE	
11-20-12		0830 MD ON SITE - ROUND OF READINGS ~ 2 GPM H ₂ O - PRODUCE @ 50% 0900 DEPARTED SITE	
Weather:		Signature & Date:	
		Eqpt Billing Log to Accounting Date: Initials:	

DPE Pilot Test Field Data Forms

Supplemental Pilot Test Information (mark all that apply)

- Yes No Is an AS pilot test being conducted concurrently?
- Yes No Are baseline geochemistry data being collected?
- Yes No Are air samples being collected?

TOTAL VOC EMISSION RATE (E):

$$E \text{ (lb/min)} = \text{SCFM (ft}^3/\text{min)} \times \text{VOCs (ppmv)} \times 6.23 \times 10^{-8} \text{ [(lb/ft}^3\text{)/(ppmv)]}$$

$$E \text{ (lb/day)} = \text{SCFM (ft}^3/\text{min)} \times \text{VOCs (ppmv)} \times 6.23 \times 10^{-8} \text{ [(lb/ft}^3\text{)/(ppmv)]} \times 1440 \text{ (min/day)}$$

Flow and Emission Equations

$$ACFM \text{ (ft}^3/\text{min)} = \text{Velocity (ft/min)} \times \text{Flow Area (ft}^2\text{)}$$

$$SCFM_{25} = ACFM \times \left(\frac{P_{abs} + P_g}{P_{abs}} \right) \left(\frac{537}{460 + T} \right)$$

where:

P_{abs} = Atmospheric Pressure at Sea Level (1 atm = 406.8 in H₂O)

P_g = Gauge/Line Pressure - equivalent to zero if atmospheric discharge

T = Airstream Temperature, degrees Fahrenheit (°F)

Extraction Well Information

Extraction Well ID:	MW-2		
Well Diameter:	2		inches
Water Level (static):			ft bTOC (before test)
Screen Dpth (top):	10		ft bTOC
Screen Dpth (bot):	35		ft bTOC
Well Depth:	31.4		ft bTOC

Monitoring Well Information

Monitoring Well ID:	VM-1	VM-2	OW-1	SVE-1	AS-1	RN-2		
Well Diameter:	2	2	2	2	2	6		
Water Level (static):				19.94				
Screen Dpth (top):	10	10	10	10		20		
Screen Dpth (bot):	20	20	40	20		40		
Well Depth:								
Distance From MW-12:								

Site Name/Location:

BP 11132

Field Team:

A. Shah
Rob from Mako

Site Elevation: _____ ft aMSL

Patm: _____ in H₂O

CROSS SECTIONAL FLOW AREAS

Pipe Diam (inches)	Flow Area (in ²)	Flow Area (ft ²)
0.25	0.0491	0.0003
0.50	0.1963	0.0014
0.75	0.4418	0.0031
1.0	0.785	0.005
2.0	3.142	0.022
3.0	7.069	0.049
4.0	12.566	0.087
5.0	19.635	0.136

CONVERSION FACTORS

volume: 1 gal = 0.1337 ft³

1 gal = 3.785 L

pressure: 1 atm = 14.7psi

1 atm = 29.921 in Hg

1 atm = 33.9 ft H₂O

1 atm = 406.8 in H₂O

1 in Hg = 13.6 in H₂O

mass: 1 lb = 454 g

1 lb = 0.454 Kg

1 gal (H₂O) = 8.34 lbs

power: 1 hp = 550 ft-lb/sec

1 hp = 0.746 kW

time: 1 day = 1440 min

1 day = 8640 sec

1 yr = 525600 min

temp: °F = 32° + [(9/5) x °C]

DPE Pilot Test Field Data Forms-Extraction Wells

Staff: AS Site: 1132

Date: 11/15/12

Extraction Wellheads																		
Date:	Pipe Flow Diam (in): <u>3</u>				Pipe Flow Diam (in): _____				Pipe Flow Diam (in): _____									
Start Time	Pipe Flow Area (ft ²): _____				Pipe Flow Area (ft ²): _____				Pipe Flow Area (ft ²): _____									
Field Measurements																		
Time (hh:mm)	Casing Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Stinger Depth (ft)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Stinger Depth (ft)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Stinger Depth (ft)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Stinger Depth (ft)		
11/12/12 1000	Begin dewatering w/ pump				11/19/12 1500				16					18				
1070	Begin dewatering w/ pump																	
1055	Begin VE																	
	Wrong Pump, shutdown																	
11/15/12 1010	Begin dewatering w/ stinger				11/20/12 08:30 1500				17					18				
	Stinger set at 31 ft BOC								17					18				
1040	10.5	Use oxidizer inlet	Use oxidizer inlet	14														
1140	11.5			16														
1700	12			17														
11/16/12 0900	13			17														
1530	12			16														
11/17/12 0925	17			17														
1619	16			19														
11-18-12 0930	16			18														
1545	18			18														
11-19-12	17			18														

DPE Pilot Test Field Data Forms-Monitoring Wells

Staff: AS Site: 11132
Date: 11/15/12

Date: <u>11/15/12</u>	System Inlet			Dilution Line			Oxidizer Inlet Line			Blower Outlet (Vent Stack)		
	Pipe Flow Diam (in): _____			Pipe Flow Diam (in): _____			Pipe Flow Diam (in): <u>3</u>			Pipe Flow Diam (in): _____		
Start Time: <u>10:10</u>	Pipe Flow Area (ft ²): _____			Pipe Flow Area (ft ²): _____			Pipe Flow Area (ft ²): _____			Pipe Flow Area (ft ²): _____		
	Field Measurements			Field Measurements			Field Measurements			Field Measurements		
Time (hh:mm)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)	Vacuum, P _g (in Hg)	Velocity (ft/min)	PID (ppmv)
	<u>Same as EW</u>			<u>NO DILUTION</u>								
<u>10:40</u>							<u>0.12</u>	<u>363</u>	<u>656</u>			
<u>11:50</u>							<u>0.12</u>	<u>460</u>	<u>728</u>			
<u>17:00</u>							<u>0.20</u>	<u>397</u>	<u>773</u>			
<u>11/16/12</u>												
<u>09:00</u>							<u>0.20</u>	<u>393</u>	<u>743</u>			
<u>15:30</u>							<u>0.23</u>	<u>407</u>	<u>649</u>			
<u>11/17/12</u>												
<u>09:20</u>							<u>0.21</u>	<u>451</u>	<u>604</u>			
<u>16:19</u>							<u>0.36</u>	<u>430</u>	<u>645</u>			
<u>11-18-12</u>												
<u>09:30</u>							<u>0.35</u>	<u>410</u>	<u>658</u>			
<u>16:10</u>							<u>0.39</u>	<u>426</u>	<u>660</u>			
<u>11-19-12</u>												
<u>09:15</u>							<u>0.32</u>	<u>420</u>	<u>612</u>			
<u>15:00</u>							<u>0.82</u>	<u>402</u>	<u>590</u>			
<u>11-20-12</u>												
<u>08:30</u>							<u>0.80</u>	<u>430</u>	<u>600</u>			
<u>15:00</u>							<u>0.80</u>	<u>418</u>	<u>605</u>			

Cumulative Liquid Volumes (gal)	
Water	Totalizer
	<u>257171</u>
	<u>259419</u>
	<u>258084</u>
	<u>260055</u>
	<u>260996</u>
	<u>263208</u>
	<u>264085</u>
	<u>266234</u>
	<u>267076</u>
	<u>269347</u>
	<u>270125</u>
	<u>272439</u>
	<u>273210</u>

Total Operational Runtime: _____

Notes:

DPE Pilot Test Field Data Forms-Monitoring Wells

 Staff: AS

 Site: 11132

 Date: 11/15/12

 Date: 11/15/12
~~11/15/12~~

 Start Time: 10:00

ROI Monitoring Well Measurements

DTW = 19.96

Time (hh:mm)	VF-1		VM-2		AS-1		VM-1		OW-1		ZU-1		OW-1	
	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)	Vacuum (in H ₂ O)	DTW (ft bTOC)
1000	0	18.94	0	16.91	-0.28	21.65	0	17.22	0	20.35	0.02	19.32	19.96	
1100	0.07	18.94	5.60	17.29	-6.71	22.07	0.15	17.22	0	22.22	0.43	19.99	21.83	
1200	0.08	18.94	6.84	17.40	6.71	22.65	0.12	17.22	0	22.74	0.32	20.40	22.35	
1700	0.17	18.96	8.17	17.50	6.25	23.28	0.23	17.26	0	23.41	0.06	21.85	23.03	
0900	0.24	19.05	11.58	17.77	5.80	24.05	0.43	17.30	0	24.21	0.12	22.98	23.82	
1530	0.27	19.06	11.75	17.78	4.77	24.25	2.00	17.40	0	24.28	0.11	23.25	23.88	
									0					
05:20	0.16	19.10	-45.86	18.82	2.36	24.65	1.96	17.21	-0.61	24.50	1.96	22.12	24.11	
14:25	0.73	19.15	-34.77	18.42	-4.51	24.40	-14.65	17.93	-0.02	24.52	-2.76	22.22	24.14	
11-18-12														
09:42	0.87	19.19	-43.39	18.80	5.37	24.36	-32.17	18.72	-1.24	24.41	0	23.40	24.05	
			DTW → 20.89				DTW 20.71							
1610	0.84	19.21	-46.45	18.94	6.06	24.40	-37.69	18.94	0.04	24.46	0.02	23.45	24.10	
11-19-12														
09:15	0.89	19.27	48.10	19.05	-7.63	24.46	-31.81	18.90	1.42	24.52	0.32	23.52	24.17	
1500	0.84	19.30	48.74	19.05	-6.49	24.42	-31.78	18.81	1.78	24.52	0.04	23.52	24.14	
11-20-12														
08:20	0.84	19.38	49.64	19.12	-4.60	24.45	-30.28	19.52	2.78	24.53	0.04	23.55	24.20	
1500	0.45	19.44	-26.74	19.22	-3.23	24.45	-25.83	19.50	1.63	24.53	0.41	23.56	24.21	



GROUNDWATER MONITORING SITE SHEET

Project: Armadis 11132 Project No.: 09-88-655 Date: 1/17/13
 Field Representative: JR/AM Elevation: _____
 Formation recharge rate is historically: High Low (circle one)
 W. L. Indicator ID #: _____ Oil/Water Interface ID #: _____ (List #s of all equip used.)

WELL ID RECORD					WELL GAUGING RECORD					LAB ANALYSES			
Well ID	Well Sampling Order	As-Built Well Diameter (inches)	As-Built Well Screen Interval (ft)	Previous Depth to Water (ft)	Time (24:00)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)*	Depth to Water (ft)	Well Total Depth (ft)				
OW-1					1355	14.90	0.10	15.00					
MW-10					1424	-	-	15.31		NO SCREEN; BAILER IS STAINED FROM WELL WALLS			
<u>Post Bailing</u>													
OW-1					1410	-	-	15.39					
MW-10					-	-	-	-					
<u>Departure</u>													
OW-1					1435	15.02	0.01	15.03					
MW-10					1430	-	-	15.36					

* Device used to measure LNAPL thickness: Bailer Oil/Water Interface Meter (circle one)
 If bailer used, note bailer dimensions (inches): Entry Diameter _____ Chamber Diameter _____

Signature: [Handwritten Signature]



GROUNDWATER MONITORING SITE SHEET

Page ____ of ____

Project: ARRACLES 11132

Project No.: 09-88-655

Date: 2-20-13

Field Representative: JR


Elevation: _____

Formation recharge rate is historically: High Low (circle one)

W. L. Indicator ID #: _____ Oil/Water Interface ID #: _____ (List #s of all equip used.)

WELL ID RECORD					WELL GAUGING RECORD					LAB ANALYSES			
Well ID	Well Sampling Order	As-Built Well Diameter (inches)	As-Built Well Screen Interval (ft)	Previous Depth to Water (ft)	Time (24:00)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)*	Depth to Water (ft)	Well Total Depth (ft)				
<u>PRE</u>													
<u>OW-1</u>					<u>0746</u>	<u>17.77</u>	<u>0.02</u>	<u>17.79</u>					
<u>MW-10</u>					<u>0810</u>	<u>-</u>	<u>-</u>	<u>17.02</u>					
<u>POST</u>													
<u>OW-1</u>					<u>0755</u>	<u>-</u>	<u>-</u>	<u>18.59</u>					
<u>MW-10</u>					<u>-</u>	<u>-</u>	<u>-</u>	<u>-</u>					
<u>Departure</u>													
<u>OW-1</u>					<u>0825</u>	<u>-</u>	<u>-</u>	<u>17.79</u>					
<u>MW-10</u>					<u>-</u>	<u>-</u>	<u>-</u>	<u>-</u>					

* Device used to measure LNAPL thickness: Bailer Oil/Water Interface Meter (circle one)
 If bailer used, note bailer dimensions (inches): Entry Diameter _____ Chamber Diameter _____

Signature: 



DAILY REPORT

Page 1 of 1

Project: Arcadis 11132 Project No.: 09-88-655

Field Representative(s): Alex Martinez Day: Friday Date: 3/8/13

Time Onsite: From: 0730 To: 0830 ; From: To: ; From: To:

- Checked items: Signed HASP, Safety Glasses, Hard Hat, UST Emergency System Shut-off Switches Located, Proper Level of Barricading. Unchecked items: Steel Toe Boots, Safety Vest, Proper Gloves. Other PPE: (describe)

Weather: Sunny

Equipment In Use: Bailers

Visitors: None

Table with 2 columns: TIME and WORK DESCRIPTION. Handwritten entries: 0730 Arrived onsite; 0740 Set up for product bailing & measurement; 0830 Completed fieldwork & offsite.

Signature: Alex Martinez



GROUNDWATER MONITORING SITE SHEET

Project: Arcadis 11132 Project No.: 07-88-655 Date: 3/8/13

Field Representative: AM Elevation: -

Formation recharge rate is historically: High Low (circle one)

W. L. Indicator ID #: - Oil/Water Interface ID #: - (List #s of all equip used.)

WELL ID RECORD					WELL GAUGING RECORD					NOTES
Well ID	Well Sampling Order	As-Built Well Diameter (inches)	As-Built Well Screen Interval (ft)	Previous Depth to Water (ft)	Time (24:00)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)*	Depth to Water (ft)	Well Total Depth (ft)	
<u>Pre</u>										
OW-1					0749	17.97	0.01	17.98		Approximately 1/2 gallon purged Strong HC/gasoline odor
MW-10					0814	-	-	17.21		
<u>Post</u>										
OW-1					0804	-	-	18.40		
MW-10					-	-	-	-		
<u>Departure</u>										
OW-1					0822	-	-	17.98		
MW-10					-	-	-	-		

* Device used to measure LNAPL thickness: Bailer Oil/Water Interface Meter (circle one)
 If bailer used, note bailer dimensions (inches): Entry Diameter _____ Chamber Diameter _____

Signature: Alex Mack