



January 4, 2013

Roya C. Kambin
Project Manager
Marketing Business Unit

**Chevron Environmental
Management Company**
6101 Bollinger Canyon Road
San Ramon, CA 94583
Tel (925) 790-6270
RKLG@chevron.com

Mr. Mark Detterman
Alameda County Health Agency
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502

RECEIVED

By Alameda County Environmental Health at 11:06 am, Jan 07, 2013

RE: Fourth Quarter 2012 Groundwater Monitoring Report

1400 Powell Street, Emeryville, California
Fuel Leak Case No.: RO0000067

Dear Mr. Detterman,

I declare under penalty of perjury that to the best of my knowledge the information and/or recommendations contained in the attached report is/are true and correct.

If you have any questions or need additional information, please contact me at (925) 790-6270.

Sincerely,

A handwritten signature in black ink, appearing to read "Roya Kambin".

Roya Kambin
Union Oil of California – Project Manager

Attachment
Fourth Quarter 2012 Monitoring Report



ARCADIS U.S., Inc.
100 Montgomery Street
Suite 300
San Francisco
California 94104
Tel 415.374.2744
Fax 415.374.2745
www.arcadis-us.com

Mr. Mark Detterman
Alameda County Environmental Health
1131 Harbor Bay Parkway
Suite 250
Alameda, California 94502-6577

ENVIRONMENT

Subject:
Fourth Quarter 2012 Groundwater Monitoring Report

Dear Mr. Detterman:

Date:
January 4, 2013

On behalf of Chevron Environmental Management Company, for itself and as Attorney-in-Fact for Union Oil Company of California (hereinafter "EMC"), ARCADIS U.S., Inc (ARCADIS) is pleased to submit the enclosed Quarterly Groundwater Monitoring Report for the following facility:

Contact:
Leah M. Ackerman

<u>Facility No.</u>	<u>Case No.</u>	<u>Location</u>
3737	RO0000067	1400 Powell Street Emeryville, California

Phone:
415.432.6912

Email:
Leah.Ackerman@
arcadis-us.com

If you have any questions, please contact Leah Ackerman at 415.432.6912.

Our ref:
B0047937.0001

Sincerely,

ARCADIS



Leah Ackerman, P.E.
Project Engineer

Copies:
Ms. Roya Kambin, EMC (electronic copy)
Mr. Najmeddin Revan, Property Owner

**UNION OIL OF CALIFORNIA
QUARTERLY MONITORING REPORT
FOURTH QUARTER 2012
JANUARY 4, 2013**

Facility No.: 3737 Address: 1400 Powell Street, Emeryville, California

Consulting Company/Contact Person/Phone No.: ARCADIS / Leah Ackerman/ 415.432.6912

Primary Agency/Contact Person/Regulatory ID No.: Alameda County Environmental Health / Mr. Mark Detterman / Case No. RO 0000067

WORK PERFORMED DURING THIS REPORTING PERIOD (Fourth Quarter – 2012) :

1. TRC Solutions (TRC) conducted groundwater monitoring and sampling on October 28, 2012. Field data sheets and general procedures are included as **Attachment A**. Six (6) monitoring wells (MW-1A through MW-3A in the shallow zone and MW-1B through MW-3B in the deep zone) were gauged, purged, and sampled during this monitoring event.

All collected groundwater samples were analyzed for total petroleum hydrocarbons as gasoline (TPH-g) by Environmental Protection Agency (EPA) Method 8260B; benzene, toluene, ethylbenzene, and total xylenes (BTEX, collectively), full scan of volatile organic compounds (VOCs) including oxygenates (methyl tertiary butyl ether [MTBE] and tertiary butyl alcohol [TBA]); 1,2-dibromoethane (EDB) and 1,2-dichloroethane (EDC), diisopropyl ether (DIPE), tert-butyl ethyl ether (ETBE), tert-amyl methyl ether (TAME), and ethanol by EPA Method 8260B; total petroleum hydrocarbons as diesel (TPH-d) and total petroleum hydrocarbons as motor oil (TPH-mo) by EPA Method 8015B with silica gel clean-up.

The site location map, the site plan, and the groundwater contour and hydrocarbon concentration maps are presented on **Figures 1** through **4**. Current Groundwater Gauging and Analytical Results are summarized in **Table 1**, Historical Groundwater Gauging and Analytical Results are summarized in **Table 2**, and Historical Groundwater Results from Antea are included as **Attachment B**. A copy of the laboratory analytical report and chain-of-custody documentation is included as **Attachment C**.

WORK PROPOSED FOR THE NEXT REPORTING PERIOD (First Quarter – 2013):

1. Perform groundwater monitoring and related reporting during first quarter 2013.

Current Phase of Project:	<u>Groundwater Monitoring</u>
Site Use:	<u>Active Service Station</u>
Frequency of Sampling:	<u>Groundwater – Quarterly (MW-1A through MW-3A), Semiannually (All monitoring wells)</u>
Frequency of Monitoring:	<u>Groundwater – Quarterly (MW-1A through MW-3A), Semiannually (All monitoring wells)</u>
Measurable Separate-Phase Hydrocarbons (SPH) this quarter:	<u>None</u>
Cumulative SPH Recovered to Date:	<u>None</u>
SPH Recovered This Quarter:	<u>None</u>
Bulk Soil Removed to Date:	<u>Six cubic yards</u>
Bulk Soil Removed this Quarter:	<u>None</u>
Water Wells or Surface Waters within a 2000' Radius and Their Respective Directions:	<u>None</u>
Groundwater Use Designation:	<u>Municipal and Domestic</u>
Current Remediation Techniques:	<u>None</u>

**UNION OIL OF CALIFORNIA
QUARTERLY MONITORING REPORT
FOURTH QUARTER 2012
JANUARY 4, 2013**

Facility No.: 3737 Address: 1400 Powell Street, Emeryville, California

Permits for Discharge (No.): None

Approximate Depth to Groundwater: Shallow Zone: 4.37 (MW-3A) – 5.68 (MW-2A) feet below top of casing
Deep Zone: 4.10 (MW-3B) – 5.44 (MW-1B) feet below top of casing

Approximate Groundwater Elevation: Shallow Zone: 13.25 (MW-2A) – 14.25 (MW-3A) feet above mean sea level
Deep Zone: 13.44 (MW-1B) – 14.47 (MW-3B) feet above mean sea level
Measured Estimated

Groundwater Gradient (Shallow Zone): 0.01 ft/ft (Magnitude) West- southwest (Direction)

Groundwater Gradient (Deep Zone): 0.007 ft/ft (Magnitude) Southwest (Direction)

DISCUSSION:

Groundwater conditions at the six (6) monitoring wells sampled during the fourth quarter 2012 remained generally consistent with previous quarters. The maximum concentration of TPH-d (180 micrograms per liter [$\mu\text{g/L}$]) and TAME (1.9 $\mu\text{g/L}$) were detected in the sample collected from MW-1A. The maximum concentrations of TPH-g (1,600 $\mu\text{g/L}$), toluene (3.9 $\mu\text{g/L}$), and ethylbenzene (27 $\mu\text{g/L}$) were detected in the sample collected from MW-3A. The maximum concentrations of benzene (150 $\mu\text{g/L}$), total xylenes (5.4 $\mu\text{g/L}$), MTBE (270 $\mu\text{g/L}$), and TBA (2,100 $\mu\text{g/L}$) were detected in the samples collected from MW-2A. EDB, DIPE, ETBE, and ethanol were not detected in any of the monitoring wells.

Groundwater elevations across the site in the shallow water-bearing zone vary by approximately one foot and create a hydraulic gradient of 0.01 foot per foot in the west-southwest direction. Groundwater elevations across the site in the deeper water-bearing zone vary by approximately one foot and create a hydraulic gradient of 0.007 foot per foot in the southwestern direction.

CONCLUSIONS AND RECOMMENDATIONS:

Dissolved hydrocarbon constituent concentrations have remained relatively consistent with previous quarters. ARCADIS recommends continued groundwater monitoring and reporting.

**UNION OIL OF CALIFORNIA
QUARTERLY MONITORING REPORT
FOURTH QUARTER 2012
JANUARY 4, 2013**

Facility No.: 3737 Address: 1400 Powell Street, Emeryville, California

ATTACHMENTS:

- Figure 1: Site Location Map
- Figure 2: Site Plan
- Figure 3: Groundwater Elevation Contour and Hydrocarbon Concentration Map (Shallow Zone)
- Figure 4: Groundwater Elevation Contour and Hydrocarbon Concentration Map (Deep Zone)

- Table 1: Current Groundwater Gauging and Analytical Results
- Table 2: Historical Groundwater Gauging and Analytical Results

- Attachment A: Field Data Sheets and General Procedures
- Attachment B: Historical Groundwater Results from Antea
- Attachment C: Laboratory Report and Chain-of-Custody Documentation


ARCADIS

Figures

CITY: PATALUMA, CA DIV/GROUP: ENV DB: J. HARRIS
 G:\ENV\CA\388\B\RETURN-TO-PATALUMA-CA\16047937\00000002\4012\47937N01.dwg LAYOUT: 1 SAVED: 12/27/2012 9:42 AM ACADVER: 18.1S (LMS TECH) PAGESETUP: --- PLOTSTYLETABLE: ARCADIS.CTB PLOTTED: 12/27/2012 9:43 AM BY: MURESAN, ELENA
 XREFS: IMAGES: PROJECTNAME: 47937A02.jpg



REFERENCE: BASE MAP USGS 7.5. MIN. TOPO. QUAD., OAKLAND WEST, CALIFORNIA, 1993.



Approximate Scale: 1 in. = 2000 ft.



UNION OIL
 FORMER 76 SERVICE STATION 3737
 1400 POWELL STREET
 EMERYVILLE, CALIFORNIA

SITE LOCATION MAP



FIGURE
1


CITY: PETALUMA, CA DIV/GROUP: ENV DB: J. HARRIS G:\ENV\CAD\Costal\Area\RETURN\TOP\petalum-ca\B0047937\000000002\4012\47937B01.dwg LAYOUT: 2 SAVED: 8/15/2012 6:36 AM ACADVER: 18.1S (LMS TECH) PAGES: 18 PAGES: 18 PLOTSTYLETABLE: ARCADIS_PETALUMA.CTB PLOTTED: 12/27/2012 9:44 AM BY: MURESAN, ELENA XREFS: IMAGES: PROJECTNAME: 47937A02




- LEGEND**
- PROPERTY BOUNDARY
 - LOT LINE
 - MW-1A MONITORING WELL LOCATION (SHALLOW ZONE)
 - MW-1B MONITORING WELL LOCATION (DEEP ZONE)
 - TCW-1 TANK CAVITY WELL
 - OW-11 DEWATERING WELL (OFFSITE)
 - TR-12/TRCPT-8 APPROXIMATE BORING LOCATION BY TREADWELL AND ROLLO (OFFSITE), 2000-2010
 - D-1 HISTORICAL BORING LOCATION (ONSITE)
 - CPT-1 CPT BORING LOCATION, 2009
 - MWT-1 TEMPORARY MONITORING WELL LOCATION
 - APPROXIMATE LOCATION OF SITE FEATURES ON 1951 SANBORN MAP

NOTE:

- TEMPORARY MONITORING WELL LOCATIONS, BUILDING, CURB, PLANTER, AND PARKING AREAS SURVEYED PROVIDED BY MUIR CONSULTING, INC. 8/1/12. HORIZONTAL DATUM NAD83, VERTICAL DATUM NAVD88. ALL OTHER FEATURES AND LOCATIONS ARE APPROXIMATE AND WERE PROVIDED BY CRA, DATED 1/27/2011, AT A SCALE OF 1"=20'.



UNION OIL FORMER 76 SERVICE STATION 35-1780 1400 POWELL STREET EMERYVILLE, CALIFORNIA	
SITE PLAN	
	FIGURE 2



MW-2A	
Constituent	Result
TPH-d	91
TPH-g	1,300
Benzene	150
MTBE	270

MW-3A	
Constituent	Result
TPH-d	130
TPH-g	1,600
Benzene	54
MTBE	2.8

MW-1A	
Constituent	Result
TPH-d	180
TPH-g	1,500
Benzene	13
MTBE	52

LEGEND

- PROPERTY BOUNDARY
- LOT LINE
- MW-1A MONITORING WELL LOCATION (SHALLOW ZONE)
- MW-1B MONITORING WELL LOCATION (DEEP ZONE)
- TCW-1 TANK CAVITY WELL
- OW-11 DEWATERING WELL (OFFSITE)
- TR-12/TRCPT-8 APPROXIMATE BORING LOCATION BY TREADWELL AND ROLLO (OFFSITE), 2000-2010
- D-1 HISTORICAL BORING LOCATION (ONSITE)
- CPT-1 CPT BORING LOCATION, 2009
- MWT-1 TEMPORARY MONITORING WELL LOCATION
- APPROXIMATE LOCATION OF SITE FEATURES ON 1951 SANBORN MAP
- GROUNDWATER ELEVATION CONTOUR (FT MSL; DASHED WHERE INFERRED)
- (14.25) GROUNDWATER ELEVATION IN FEET RELATIVE TO MEAN SEA LEVEL (MSL)
- 0.01 FT/FT APPROXIMATE GROUNDWATER FLOW DIRECTION AND GRADIENT MEASURED IN FOOT PER FOOT (FT/FT)


NOTE:

- TEMPORARY MONITORING WELL LOCATIONS, BUILDING, CURB, PLANTER, AND PARKING AREAS SURVEYED PROVIDED BY MUIR CONSULTING, INC. 8/1/12. HORIZONTAL DATUM NAD83, VERTICAL DATUM NAVD88. ALL OTHER FEATURES AND LOCATIONS ARE APPROXIMATE AND WERE PROVIDED BY CRA, DATED 1/27/2011, AT A SCALE OF 1"=20'.



UNION OIL
 FORMER 76 SERVICE STATION 35-1780
 1400 POWELL STREET
 EMERYVILLE, CALIFORNIA

GROUNDWATER ELEVATION CONTOUR AND HYDROCARBON CONCENTRATION MAP (SHALLOW ZONE) OCTOBER 28, 2012



MW-2B	
Constituent	Result
TPH-d	<40
TPH-g	<50
Benzene	<0.50
MTBE	1.7

MW-3B	
Constituent	Result
TPH-d	<40
TPH-g	<50
Benzene	<0.50
MTBE	<0.50

MW-1B	
Constituent	Result
TPH-d	<40
TPH-g	<50
Benzene	<0.50
MTBE	0.63

- LEGEND**
- PROPERTY BOUNDARY
 - LOT LINE
 - MW-1A MONITORING WELL LOCATION (SHALLOW ZONE)
 - MW-1B MONITORING WELL LOCATION (DEEP ZONE)
 - TCW-1 TANK CAVITY WELL
 - OW-11 DEWATERING WELL (OFFSITE)
 - TR-12/TRCPT-8 APPROXIMATE BORING LOCATION BY TREADWELL AND ROLLO (OFFSITE), 2000-2010
 - D-1 HISTORICAL BORING LOCATION (ONSITE)
 - CPT-1 CPT BORING LOCATION, 2009
 - MWT-1 TEMPORARY MONITORING WELL LOCATION
 - APPROXIMATE LOCATION OF SITE FEATURES ON 1951 SANBORN MAP
 - GROUNDWATER ELEVATION CONTOUR (FT MSL; DASHED WHERE INFERRED)
 - (14.47) GROUNDWATER ELEVATION IN FEET RELATIVE TO MEAN SEA LEVEL (MSL)
 - 0.007 FT/FT APPROXIMATE GROUNDWATER FLOW DIRECTION AND GRADIENT MEASURED IN FOOT PER FOOT (FT/FT)

NOTE:

- TEMPORARY MONITORING WELL LOCATIONS, BUILDING, CURB, PLANTER, AND PARKING AREAS SURVEYED PROVIDED BY MUIR CONSULTING, INC. 8/1/12. HORIZONTAL DATUM NAD83, VERTICAL DATUM NAVD88. ALL OTHER FEATURES AND LOCATIONS ARE APPROXIMATE AND WERE PROVIDED BY CRA, DATED 1/27/2011, AT A SCALE OF 1"=20'.



UNION OIL
 FORMER 76 SERVICE STATION 35-1780
 1400 POWELL STREET
 EMERYVILLE, CALIFORNIA

**GROUNDWATER ELEVATION CONTOUR AND
 HYDROCARBON CONCENTRATION MAP
 (DEEP ZONE) OCTOBER 28, 2012**

ARCADIS

FIGURE
4

ARCADIS

Tables

Table 1
Current Groundwater Gauging and Analytical Results
76 Station 3737
1400 Powell Street, Emeryville, California

Well ID	Date Sampled	TOC (feet AMSL)	DTW (feet bgs)	LPH Thickness (feet)	GW Elevation (feet AMSL)	Previous Quarter GWE (feet AMSL)	Change in Elevation (feet)	TPH-Motor Oil (8015B/FFP)	TPH-d (8015B/FFP)	TPH-g (Luft-GC/MS)	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	TBA	EDB	EDC	DIPE	ETBE	TAME	Ethanol	Comments
MW-1A	10/28/2012	18.74	5.32	0.00	13.42	13.17	-0.25	<100	180	1,500	13	0.72	2.8	1.7	52	120	<0.50	<0.50	<0.50	<0.50	1.9	<250	A52
MW-1B	10/28/2012	18.88	5.44	0.00	13.44	11.98	-1.46	<100	<40	<50	<0.50	<0.50	<0.50	<1.0	0.63	<10	<0.50	23	<0.50	<0.50	<0.50	<250	
MW-2A	10/28/2012	18.93	5.68	0.00	13.25	11.60	-1.65	<100	91	1,300	150	<2.5	14	5.4	270	2,100	<2.5	<2.5	<2.5	<2.5	<2.5	<1,200	A01
MW-2B	10/28/2012	19.10	5.22	0.00	13.88	13.82	-0.06	<100	<40	<50	<0.50	<0.50	<0.50	<1.0	1.7	<10	<0.50	<0.50	<0.50	<0.50	<0.50	<250	
MW-3A	10/28/2012	18.62	4.37	0.00	14.25	14.12	-0.13	<100	130	1,600	54	3.9	27	4.4	2.8	<20	<1.0	<1.0	<1.0	<1.0	<1.0	<500	A01
MW-3B	10/28/2012	18.57	4.10	0.00	14.47	14.21	-0.26	<100	<40	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<10	<0.50	<0.50	<0.50	<0.50	<0.50	<250	

Note

Analytical results given in micrograms per liter (µg/l)

Standard Abbreviations

- not analyzed, measured, or collected
- < not detected at or above laboratory detection limit
- bgs below ground surface
- AMSL above mean sealevel
- DTW depth to water
- GW groundwater
- LPH liquid-phase hydrocarbons
- TOC top of casing (surveyed reference elevation)

Analytes

- MTBE methyl tertiary butyl ether
- TBA tertiary butyl alcohol
- EDB 1,2-dibromoethane
- EDC 1,2-dichloroethane (same as ethylene dichloride)
- ETBE ethyl tertiary butyl ether
- TAME tertiary amyl methyl ether
- DIPE di-isopropyl ether
- TPH-g total purgable petroleum hydrocarbons
- TPH-d total petroleum hydrocarbons as diesel
- TPH-Motor Oil total petroleum hydrocarbons as motor oil
- 8260B EPA Method 8260B for TPH-g and Volatile Organic Compounds
- 8015B/FFP EPA Method 8015B with silica gel clean-up for TPH-d and TPH-motor oil
- A01 PQL's and MDL's are raised due to sample dilution.
- A52 Chromatogram not typical of diesel

Table 2
Historical Groundwater Gauging and Analytical Results
76 Station 3737
1400 Powell Street, Emeryville, California

Note

Analytical results given in micrograms per liter ($\mu\text{g/l}$)

Standard Abbreviations

--	not analyzed, measured, or collected
<	not detected at or above laboratory detection limit
bgs	below ground surface
AMSL	above mean sealevel
DTW	depth to water
GW	groundwater
LPH	liquid-phase hydrocarbons
TOC	top of casing (surveyed reference elevation)

Analytes

MTBE	methyl tertiary butyl ether
TBA	tertiary butyl alcohol
EDB	1,2-dibromoethane
EDC	1,2-dichloroethane (same as ethylene dichloride)
ETBE	ethyl tertiary butyl ether
TAME	tertiary amyl methyl ether
DIPE	di-isopropyl ether
TPH-g	total purgable petroleum hydrocarbons
TPH-d	total petroleum hydrocarbons as diesel
TPH-Motor Oil	total petroleum hydrocarbons as motor oil
8260B	EPA Method 8260B for TPH-g and Volatile Organic Compounds
8015B/FFP	EPA Method 8015B with silica gel clean-up for TPH-d and TPH-motor oil
A01	PQL's and MDL's are raised due to sample dilution.
A52	Chromatogram not typical of diesel

ARCADIS

Attachment A

Field Data Sheets and General Procedures



123 Technology Drive
Irvine, California 92618

949.727.9336 PHONE
949.727.7399 FAX

www.TRCsolutions.com

DATE: November 13, 2012

TO: Leah Ackerman, ARCADIS
Andrea Valdivia, ARCADIS
Tamera Rogers, ARCADIS
Angeline Tan, ARCADIS

SITE: Unocal Site 3737
Facility 351780
1400 Powell Street, Emeryville, CA

RE: Transmittal of Groundwater Monitoring Data

Please find attached the field data sheets, chain of custody (COC) forms, and technical services request (TSR) form for the monitoring event that was completed on October 28, 2012. Field measurements and collection of samples submitted to the laboratory were completed in general accordance with our usual groundwater monitoring protocol which is also attached for your reference.

Please call me at 949-341-7440 if you have questions.

Sincerely,

A handwritten signature in black ink, appearing to read "Anju Farfan", written in a cursive style.

Anju Farfan
Groundwater Program Operations Manager

GENERAL FIELD PROCEDURES

Groundwater Gauging and Sampling Assignments

For each site, TRC technicians are provided with a Technical Service Request (TSR) that specifies activities required to complete the groundwater gauging and sampling assignment for the site. TSRs are based on client directives, instructions from the primary environmental consultant for the site, regulatory requirements, and TRC's previous experience with the site.

Fluid Level Measurements (Gauging)

Initial site activities include determination of well locations based on a site map provided with the TSR. Well boxes are opened and caps are removed. Indications of well or well box damage or of pressure buildup in the well are noted.

Fluid levels in each well are measured using a coated cloth tape equipped with an electronic interface probe, which distinguishes between liquid phase hydrocarbon (LPH) and water. The depth to LPH (if it is present), to water, and to the bottom of the well are measured from the top of the well casing (surveyors mark or notch if present) to the nearest 0.01 foot. Unless otherwise instructed, a well with less than 0.67 foot between the measured top of water and the measured bottom of the well casing is considered dry, and is not sampled. If the well contains 0.67 foot or more of water, an attempt is made to bail and/or sample as specified on the TSR.

Unless otherwise instructed, a well that is found to contain a measureable amount of LPH (0.01 foot) is not purged or sampled. Instead, one casing volume of fluid is bailed from the well and the well is re-sealed.

Purging and Groundwater Parameter Measurement

TSR instructions may specify that a well not be purged (no-purge sampling), be purged using low-flow methods, or be purged using conventional pump and/or bail methods. Conventional purging generally consists of pumping or bailing until a minimum of three casing volumes of water have been removed or until the well has been pumped dry. Pumping is generally accomplished using submersible electric or pneumatic diaphragm pumps. The pump intake is initially set at about 5 feet below the level of water in the casing, and is lowered as needed to compensate for falling water level. Pump depths are recorded in Field Notes.

During conventional purging, three groundwater parameters (temperature, pH, and conductivity) are measured after removal of each casing volume. Stabilization of these parameters, to within 10 percent, confirm that sufficient purging has been completed. In some cases, the TSR indicates that other parameters are also to be measured during purging. TRC commonly measures dissolved oxygen (DO), oxidation-reduction potential (ORP), and/or turbidity. Instruments used for groundwater parameter measurements are calibrated daily according to manufacturer's instructions.

Low-flow purging utilizes a bladder or peristaltic pump to remove water from the well at a low rate. Groundwater parameters specified by the TSR are measured continuously, using a flow cell, until they become stable in general accordance with EPA guidelines.

Groundwater Sample Collection

After wells are purged, or not purged, according to TSR instructions, samples are collected for laboratory analysis. For wells that have been purged using conventional pump or bail methods, sampling is conducted after the well has recovered to 80 percent of its original volume or after two hours if the well does not recover to at least 80 percent. If there is insufficient recharge of water in the well after two hours, the well is not sampled.

GENERAL FIELD PROCEDURES

Samples are collected by lowering a new, disposable polyethylene bottom-fill bailer to just below the water level in the well. The bailer is retrieved and the water sample is carefully transferred to containers specified for the laboratory analytical methods indicated by the TSR. Particular care is given to containers for volatile organic analysis (VOAs) which require filling to zero headspace and fitting with Teflon-sealed caps.

Sample containers are labeled with project number (or site number), well designation, sample date, sample time, and the sampler's initials, and placed in an insulated chest with ice. Samples remain chilled prior to and during transport to a state-certified laboratory for analysis. Sample container descriptions and requested analyses are entered onto a chain-of-custody form in order to provide instructions to the laboratory. The chain-of-custody form accompanies the samples during transportation to provide a continuous record of possession from the field to the laboratory. If a freight or overnight carrier transports the samples, the carrier is noted on the form.

For wells that have been purged using low-flow methods, sample containers are filled from the effluent stream of the bladder or peristaltic pump. In some cases, if so specified by the TSR, samples are taken from the sample ports of actively pumping remediation wells.

Sequence of Gauging, Purging and Sampling

The sequence in which monitoring activities are conducted is specified on the TSR. In general, wells are gauged beginning with the least affected well and ending with the well that has the highest concentration based on previous analytic results. After all gauging for the site is completed, wells are purged and/or sampled from the least-affected to the most-affected well. If wells must be gauged or sampled out of order, alternate interface probes and/or pumps are utilized and are noted in field documentation.

Decontamination

In order to reduce the possibility of cross contamination between wells, strict isolation and decontamination procedures are observed. Portable pumps are not used in wells with LPH. Technicians wear nitrile gloves during all gauging, purging, and sampling activities. Gloves are changed between wells and more often if warranted. Any equipment that could come in contact with fluids are either dedicated a particular well, decontaminated prior to each use, or discarded after a single use. Decontamination consists of washing in a solution of Liquinox and water and rinsing twice. The final rinse is in deionized water.

Purge Water Disposal

Purge water is generally collected in labeled drums for disposal as non-hazardous waste. Drums may be left on site for disposal by others, or transported to a collection location at a TRC field office, in either Fullerton, California or Concord, California, for eventual transfer to a licensed treatment or recycling facility. Alternatively, purge water may be collected directly from the site by a licensed vacuum truck company, or may be treated on site by an active remediation system, if so directed.

Exceptions

Additional tasks or non-standard procedures, if any, that may be requested or required for a particular site, are documented in field notes on the following pages.

FIELD MONITORING DATA SHEET

Technician: Braley

Job #/Task #: 189791, 2035, 1780

Date: 10/28/12

Site # 3737

Project Manager AF

Page 1 of 1

Well #	TOC	Time Gauged	Total Depth	Depth to Water	Depth to Product	Product Thickness (feet)	Time Sampled	Misc. Well Notes
MW-3B	✓	0750	23.80	4.10	-	-	1132	2"
MW-1B	✓	0800	21.70	5.44	-	-	1206	2"
MW-2B	✓	0808	23.58	5.22	-	-	1230	2"
MW-1A	✓	0816	9.70	5.32	-	-	1137	2"
MW-3A	✓	0824	9.22	4.37	-	-	1125	2"
MW-2A	✓	0833	10.15	5.68	-	-	0904	2"

FIELD DATA COMPLETE QA/QC COC WELL BOX CONDITION SHEETS

MANIFEST DRUM INVENTORY TRAFFIC CONTROL



1 - Field Mon Data Sheet(1).xls 9/26/2012

GROUNDWATER SAMPLING FIELD NOTES

Technician: Braided

Site: 3737

Project No.: 189791.1035.1780

Date: 10/28/12

Well No. MW-2A

Purge Method: HB

Depth to Water (feet): 5.68

Depth to Product (feet): —

Total Depth (feet): 10.15

LPH & Water Recovered (gallons): —

Water Column (feet): 4.47

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 6.57

1 Well Volume (gallons): 1

Time Start	Time Stop	Pump Depth (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
Pre-Purge									
0905	0910		1	2496	21.7	6.45			
			2	—	—	—			
			3	—	—	—			
Static at Time Sampled			Total Gallons Purged			Sample Time			
8.38			300 1			0904			
Comments: Pre-Purge Sample 0904 Dry 1 bl. Did not recharge used Pre-sampler									

Well No. MW-3A

Purge Method: HB

Depth to Water (feet): 4.37

Depth to Product (feet): —

Total Depth (feet): 9.22

LPH & Water Recovered (gallons): —

Water Column (feet): 4.85

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 5.34

1 Well Volume (gallons): 1

Time Start	Time Stop	Pump Depth (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
Pre-Purge									
0914	0919		1	1256	23.8	6.72			
			2	1220	24.7	6.43			
				3	—	—	—		
Static at Time Sampled			Total Gallons Purged			Sample Time			
5.10			2			1125			
Comments: Dry 2 bls									



GROUNDWATER SAMPLING FIELD NOTES

Technician: Basilio

Site: 3737

Project No.: 189791.0035.1780

Date: 10/28/12

Well No. MW-1A

Purge Method: HB

Depth to Water (feet): 5.32

Depth to Product (feet): —

Total Depth (feet): 9.70

LPH & Water Recovered (gallons): —

Water Column (feet): 4.38

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 6.19

1 Well Volume (gallons): 1

Time Start	Time Stop	Pump Depth (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
Pre-Purge									
0922			1	927.1	21.9	6.89			
	0927		2	863.0	21.6	6.76			
			3	—	—	—			
Static at Time Sampled			Total Gallons Purged			Sample Time			
5.42			2			1137			
Comments: <u>Dry at 2 hrs</u>									

Well No. MW-3B

Purge Method: 5/6

Depth to Water (feet): 4.10

Depth to Product (feet): —

Total Depth (feet): 23.80

LPH & Water Recovered (gallons): —

Water Column (feet): 19.70

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 8.04

1 Well Volume (gallons): 4

Time Start	Time Stop	Pump Depth (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
Pre-Purge									
0945			4	1293	21.2	7.39			
	0948		8	—	—	—			
			12	—	—	—			
Static at Time Sampled			Total Gallons Purged			Sample Time			
5.44			6			1152			
Comments: <u>Dry at 6 hrs.</u>									

GROUNDWATER SAMPLING FIELD NOTES

Technician: B. Paul

Site: 3737

Project No.: 189791.0035

Date: 12/28/12

Well No. MW-1B

Purge Method: Sub

Depth to Water (feet): 5.44

Depth to Product (feet): —

Total Depth (feet): 21.70

LPH & Water Recovered (gallons): —

Water Column (feet): 16.26

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 8.69

1 Well Volume (gallons): 3

Time Start	Time Stop	Pump Depth (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, °C)	pH	D.O. (mg/L)	ORP	Turbidity
Pre-Purge									
0958			3	1224	22.0	6.99			
	1002		6	—	—	—			
			9	—	—	—			
Static at Time Sampled			Total Gallons Purged			Sample Time			
8.52			4			1206			
Comments: <u>Dry at 4</u>									

Well No. MW-2B

Purge Method: Sub

Depth to Water (feet): 5.22

Depth to Product (feet): —

Total Depth (feet): 23.58

LPH & Water Recovered (gallons): —

Water Column (feet): 18.36

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 8.89

1 Well Volume (gallons): 4

Time Start	Time Stop	Pump Depth (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, °C)	pH	D.O. (mg/L)	ORP	Turbidity
Pre-Purge									
1008			4	1023	22.3	7.21			
	1012		8	—	—	—			
			12	—	—	—			
Static at Time Sampled			Total Gallons Purged			Sample Time			
7.77			4			1230			
Comments: <u>Dry at 4 HS</u>									

WELL BOX CONDITION REPORT

SITE NO. 3737
ADDRESS 1400 Powell Street
DATE 10/28/12

PERFORMED BY: [Signature]
PAGE 1 of 1

Well Name	Current Well Box Size	# of Ears	# of Skipped Ears	# of Broken Ears	# of Broken Bolts	# of Missing Bolts	Seal Damaged	Missing Lid	Broken Lid	Well Box Is Exposed	Well Box Is Below Grade	Unable to Access	Unable to Locate	Foundation Damaged	Paved Over	Street Well	Saw Cut Needed	System Well	USA Marked Well	Comments	
MW-3B	12"	2																			
MW-1B	12"	2												✓							
MW-2B	12"	2																			
MW-1A	12"	2												✓							
MW-3A	12"	2																			
MW-2A	12"	2																			



CHAIN OF CUSTODY FORM

Union Oil Company of California ■ 6101 Bollinger Canyon Road ■ San Ramon, CA 94583

COC 1 of 1

Union Oil Site ID: <u>2497</u>				Union Oil Consultant: <u>TRC</u>		ANALYSES REQUIRED											
Site Global ID: <u>060</u>				Consultant Contact: <u>Molly Meyers</u>		TPH - Diesel by EPA 8015 <u>refrigerant</u> TPH - G by GC/MS <u>2600</u> BTEX/MTBE/OXYS by EPA 8260B Ethanol by EPA 8260B <u>refrigerant</u> EPA 8260B Full List with OXYS <u>refrigerant</u> <u>Molly Meyers 2/6/12</u> <u>refrigerant laboratory</u>	Turnaround Time (TAT): Standard <input type="checkbox"/> 24 Hours <input type="checkbox"/> 48 Hours <input type="checkbox"/> 72 Hours <input type="checkbox"/> Special Instructions										
Site Address: <u>1000</u>				Consultant Phone No.: <u>615</u>													
Union Oil PM: <u>Molly Meyers</u>				Sampling Company: TRC													
Union Oil PM Phone No.: <u>615</u>				Sampled By (PRINT): <u>Molly Meyers</u>													
Charge Code: NWRB-0 <u>123</u> -0- LAB				Sampler Signature: <u>[Signature]</u>		BC Laboratories, Inc. Project Manager: Molly Meyers 4100 Atlas Court, Bakersfield, CA 93308 Phone No. 661-327-4911											
This is a LEGAL document. ALL fields must be filled out CORRECTLY and COMPLETELY.																	
SAMPLE ID																	
Field Point Name	Matrix	DTW	Date (yyymmdd)	Sample Time	# of Containers	TPH - Diesel by EPA 8015	TPH - G by GC/MS	BTEX/MTBE/OXYS by EPA 8260B	Ethanol by EPA 8260B	EPA 8260B Full List with OXYS					Notes / Comments		
<u>MW-1A</u>	<u>W-S-A</u>		<u>121025</u>	<u>1127</u>	<u>5</u>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>							
<u>MW-2A</u>	<u>W-S-A</u>		↓	<u>0904</u>	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>							
<u>MW-2A</u>	<u>W-S-A</u>		↓	<u>1125</u>	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>							
<u>MW-1B</u>	<u>W-S-A</u>		↓	<u>1206</u>	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>							
<u>MW-2B</u>	<u>W-S-A</u>		↓	<u>1230</u>	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>							
<u>MW-3B</u>	<u>W-S-A</u>		↓	<u>1132</u>	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>							
	<u>W-S-A</u>																
	<u>W-S-A</u>																
	<u>W-S-A</u>																
	<u>W-S-A</u>																
	<u>W-S-A</u>																
	<u>W-S-A</u>																
Relinquished By: <u>[Signature]</u> Company: <u>TRC</u> Date / Time: <u>12/29/12</u>				Relinquished By: _____ Company: _____ Date / Time: _____				Relinquished By: _____ Company: _____ Date / Time: _____									
Received By: <u>[Signature]</u> Company: <u>TRC</u> Date / Time: <u>12/29/12 1325</u>				Received By: _____ Company: _____ Date / Time: _____				Received By: _____ Company: _____ Date / Time: _____									

TRC SOLUTIONS
TECHNICAL SERVICES REQUEST FORM

17-Sep-12

Site ID: 3737
Address 1400 Powell Street
City: Emeryville
Cross Street: Peladeau Street

Project No.: 189791.0035.1780 / 00TA01
Client: Roya Kambin
Contact #: 925-790-6270
PM: Leah Ackerman Arcadis
PM Contact #: 925-296-7828

Total number of wells: 6 **Min. Well Diameter (in.):** **# of Techs, # of Hrs:** 1, 6
Depth to Water (ft.): **Max. Well Diameter (in.):** **Travel Time (hrs):**
Max. Well Depth (ft.): **Hotel PO#:**

ACTIVITIES:	Frequency	Notes	Hotel PO#:
Gauging:	<input checked="" type="checkbox"/> Quarterly		
Purge/Sampling:	<input checked="" type="checkbox"/> Quarterly		
No Purge/Sample	<input type="checkbox"/>		

RELATED ACTIVITIES	Note
Drums:	<input checked="" type="checkbox"/>
Other Activities:	<input type="checkbox"/>
Traffic Control:	<input checked="" type="checkbox"/> MWT-1 thru MWT-4

PERMIT INFORMATION:

NOTIFICATIONS:

Station Owner/Operator: Mr. Najmeddin Ravan, 510-653-2251. He is at the station until noon.

SITE INFORMATION:

The site is currently a Chevron station. It can only be sampled on a Sunday per the access agreement.

Prior to gauging, uncap all wells and allow to equilibrate for 15 minutes.

Well MW-2A does not recharge quickly.

- collect a no purge sample (these will be submitted if the well does not recharge after purging)
- then purge and sample the well
- if the well recharges after purging, please collect post-purge samples (submit these to the laboratory and discard the pre-purge samples)

TRC SOLUTIONS
TECHNICAL SERVICES REQUEST FORM

17-Sep-12

Site ID: 3737
Address 1400 Powell Street
City: Emeryville
Cross Street: Peladeau Street

Project No.: 189791.0035.1780 / 00TA01
Client: Roya Kambin
Contact #: 925-790-6270
PM: Leah Ackerman Arcadis
PM Contact #: 925-296-7828

LAB INFORMATION:

Global ID: T06019745736

Lab WO: 351780

Lab Used: BC

Lab Notes: Lab Analyses:
TPH-G by 8260B, BTEX/MTBE/OXYS by 8260B, EDB/EDC by 8260B, Ethanol by 8260B [Containers: 3 voas w/ HCl]
TPH-Diesel by 8015 w/ silica gel cleanup, TPH-Motor Oil by 8015 w/ silica gel cleanup [Container: two 1L ambers
unpreserved]

TRC SOLUTIONS
TECHNICAL SERVICES REQUEST FORM

17-Sep-12

Site ID.: 3737
Address 1400 Powell Street
City: Emeryville
Cross Street Peladeau Street

Well IDs	Benz.	MTBE	Gauging				Sampling				Field Measurements			Comments
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Pre-Purge	Post-Purge	Type	
MW-3B	0	0	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
MW-1B	0	0.72	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
MW-2B	0	2.1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
MW-1A	10	35	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
MW-3A	77	0	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
MW-2A	120	280	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		

ARCADIS

Attachment B

Historical Groundwater Results from Antea

Table 2
Summary of Current Groundwater Analytical Data
Chevron Branded Service Station No. 3737
1400 Powell Street
Emeryville, California

Sample ID	Date	Time	Depth to Water	TOC Elevation	Groundwater Elevation	TPH-G (µg/L)	TPH-D (µg/L)	TPH-MO (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Xylenes (µg/L)	MTBE (µg/L)	TAME (µg/L)	TBA (µg/L)	DIPE (µg/L)	Ethanol (µg/L)	ETBE (µg/L)	EDB (µg/L)	1,2-DCA (µg/L)	n-Butyl-benzene (µg/L)	sec-Butyl-benzene (µg/L)	Chloroform (µg/L)	Isopropyl-benzene (µg/L)	p-Isopropyl-toluene (µg/L)	Napthalene (µg/L)	n-Propyl-benzene (µg/L)	1,2,4-Trimethyl-benzene (µg/L)	1,3,5-Trimethyl-benzene (µg/L)
MW-1A	1/26/2011	2:20	5.8	18.743	12.94	960	450	<200	8.4	<0.50	1.9	1.6	50	1.4	62	<0.50	<250	<0.50	<0.50	<0.50	2.2	1.2	<0.50	4.2	1.8	1.8	7.3	1.0	1.2
MW-1B	1/26/2011	1:20	9.46	18.884	9.42	<50	<50	<200	<0.50	<0.50	<0.50	<1.0	0.66	<0.50	<10	<0.50	<250	<0.50	<0.50	24	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
MW-2A	1/26/2011	10:33	8.02	18.925	10.91	2,500	1,200	<1000	100	2.2	28	9.0	140	<0.50	1,300	<0.50	<250	<0.50	<0.50	<0.50	6.6	3.9	2.5	14	7.6	17	23	2.5	2.4
MW-2B	1/26/2011	2:10	5.51	19.099	13.59	<50	<50	<200	0.55	<0.50	<0.50	<1.0	3.4	<0.50	<10	<0.50	<250	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
MW-3A	1/26/2011	2:30	4.75	18.616	13.87	3,100	830	<200	160	<5.0	96	<10	<5.0	<5.0	<100	<5.0	<2500	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	40	9.2	<5.0	54	<5.0	<5.0
MW-3B	1/26/2011	1:35	7.33	18.571	11.24	<50	57	<200	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<10	<0.50	<250	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
COMP	1/26/2011	1:15	NA	NA	NA	1,200	350	<200	13	0.57	5.4	1.5	6.0	<0.50	92	<0.50	15,000	<0.50	<0.50	3.6	5.3	2.3	<0.50	4.0	2.9	5.6	8.4	0.60	0.52
ESL	--	--	--	--	--	100	100	100	1	40	30	20	5	NA	12	NA	NA	NA	0.05	0.5	NA	NA	70	NA	NA	17	NA	NA	NA

Notes:

Depth to water measured in feet below top of casing
Groundwater elevation measured in feet above mean sea level
Bold concentrations indicate detection above laboratory reporting limit
(µg/L) micrograms per liter
TPH-D Total Petroleum Hydrocarbons as Diesel
TPH-MO Total Petroleum Hydrocarbons as Motor Oil
TPH-G Total Petroleum Hydrocarbons as Gasoline
MTBE methyl tertiary butyl ether
TBA tertiary buty alcohol
ETBE ethyl tertiary butyl ether
DIPE di-isopropyl ether
TAME tertiary amyl ethyl ether
EDB ethylene dibromide
1,2-DCA 1,2-dichloroethane
ESL Regional Water Quality Control Board - San Francisco Region Environmental Screening Level
A52 Data Qualifier: Chromatogram not typical of diesel
ESL based on residential land use, shallow soil, and groundwater as a potential drinking resource.
TPH-D and TPH-MO analysis by Environmental Protection Agency (EPA) Test Method 8015 with Silica Gel Cleanup
All other analyses by EPA Method 8260B.
Samples were analyzed for a full VOC Scan by EPA Method 8260B with oxygenates and lead scavengers. All Oxygenates and lead scavenger data are summarized, only VOCs with detections are presented in table.
Data qualifiers regarding sample dilution, surrogate recovery, or quality control are not presented in table. Please refer to laboratory reports for full explanation of qualifiers.

ARCADIS

Attachment C

Laboratory Report and Chain-of-Custody Documentation



Date of Report: 08/10/2012

Leah Ackerman

Arcadis

2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Project: 3737
BC Work Order: 1214106
Invoice ID: B127493

Enclosed are the results of analyses for samples received by the laboratory on 7/31/2012. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Contact Person: Molly Meyers
Client Service Rep

Authorized Signature

Certifications: CA ELAP #1186; NV #CA00014



Table of Contents

Sample Information

Chain of Custody and Cooler Receipt form.....	4
Laboratory / Client Sample Cross Reference.....	7

Sample Results

1214106-01 - MWT-1-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	11
Total Petroleum Hydrocarbons.....	12
Total Petroleum Hydrocarbons (Silica Gel Treated).....	13
1214106-02 - MWT-2-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	14
Total Petroleum Hydrocarbons.....	15
Total Petroleum Hydrocarbons (Silica Gel Treated).....	16
1214106-03 - MWT-3-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	17
Total Petroleum Hydrocarbons.....	18
Total Petroleum Hydrocarbons (Silica Gel Treated).....	19
1214106-04 - MWT-4-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	20
Total Petroleum Hydrocarbons.....	21
Total Petroleum Hydrocarbons (Silica Gel Treated).....	22
1214106-05 - MW-1A-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	23
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated).....	24
1214106-06 - MW-1B-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	25
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated).....	26
1214106-07 - MW-2A-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	27
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated).....	28
1214106-08 - MW-2B-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	29
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated).....	30
1214106-09 - MW-3A-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	31
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated).....	32
1214106-10 - MW-3B-W-120729	
Volatile Organic Analysis (EPA Method 8260).....	33
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated).....	34

Quality Control Reports

Volatile Organic Analysis (EPA Method 8260)	
Method Blank Analysis.....	35
Laboratory Control Sample.....	36
Precision and Accuracy.....	37
Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)	
Method Blank Analysis.....	38
Laboratory Control Sample.....	39
Precision and Accuracy.....	40
Total Petroleum Hydrocarbons	
Method Blank Analysis.....	41
Laboratory Control Sample.....	42
Precision and Accuracy.....	43
Total Petroleum Hydrocarbons (Silica Gel Treated)	
Method Blank Analysis.....	44
Laboratory Control Sample.....	45



Table of Contents

	Precision and Accuracy.....	46
Notes		
	Notes and Definitions.....	47



[Signature]

12-14106

CHAIN OF CUSTODY FORM

Union Oil Company of California ■ 6101 Bollinger Canyon Road ■ San Ramon, CA 94583

COC 1 of 1

CHK BY *[Signature]* DISTRIBUTION SUB-OUT

Union Oil Site ID: <u>3737</u>	Union Oil Consultant: <u>Arcadis</u>	ANALYSES REQUIRED Turnaround Time (TAT): Standard <input checked="" type="checkbox"/> 24 Hours <input type="checkbox"/> 48 Hours <input type="checkbox"/> 72 Hours <input type="checkbox"/> Special Instructions Notes / Comments
Site Global ID: <u>T06019745736</u>	Consultant Contact: <u>Leah Ackerman</u>	
Site Address: <u>1400 Powell St Emeryville</u>	Consultant Phone No.: <u>925-296-7828</u>	
Union Oil PM: <u>Roya Kamboj</u>	Sampling Company: <u>TRC</u>	
Union Oil PM Phone No.:	Sampled By (PRINT): <u>Beaulieu</u>	
Charge Code: <u>NWRTB-0 351780-0-LAB</u>	Sampler Signature: <i>[Signature]</i>	
This is a LEGAL document. <u>ALL</u> fields must be filled out CORRECTLY and COMPLETELY. BC Laboratories, Inc. Project Manager: Molly Meyers 4100 Atlas Court, Bakersfield, CA 93308 Phone No. 661-327-4911		

SAMPLE ID					Sample Time	# of Containers	TPH - Diesel by EPA 8015	TPH - G by SEMS 8260B	BTX/M/TB/E/OXYS by EPA 8260B	Ethanol by EPA 8260B 819/8260B	EPA 8260B Full List with OXYS	BTEX / MTBE by 8260B w/511cc. gal	TPH - Diesel by 8015 2.0 liter. gal	TPH - Motor Oil by 8015 Clean-30	Notes / Comments
Field Point Name	Matrix	DTW	Date (yyymmdd)												
1 MWT-1	W-S-A		12-07-29	1120	5	X	X					X	X		
2 MWT-2	W-S-A			1024	6	X						X			
3 MWT-3	W-S-A			0944	6	X						X			
4 MWT-4	W-S-A			0842	6	X						X			
5 MW-1A	W-S-A			1220	5			X	X				X		
6 MW-1B	W-S-A			1420	5			X	X				X		
7 MW-2A	W-S-A			1254	5			X	X				X		
8 MW-2B	W-S-A			1436	5			X	X				X		
9 MW-3A	W-S-A			1203	5			X	X				X		
10 MW-3B	W-S-A		V	1410	5		V	X	X			V	X		
	W-S-A														
	W-S-A														

Relinquished By: <i>[Signature]</i> TRC Date / Time: <u>7/29/12</u> <i>Placed Samples Refrigerator 1400</i>	Relinquished By: <u>Jenny Boyan BCLAB</u> Date / Time: <u>7-31-12 1830</u>	Relinquished By: <u>R. Ruy</u> Date / Time: <u>7-31-12 2130</u>
Received By: <u>Jenny Boyan BCLAB</u> Date / Time: <u>7-31-12 1420</u>	Received By: <u>R. Ruy BCL</u> Date / Time: <u>7-31-12 1830</u>	Received By: <u>KOM = BCL</u> Date / Time: <u>7-31-12 2130</u>

All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation. The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Chain of Custody and Cooler Receipt Form for 1214106 Page 2 of 3

BC LABORATORIES INC. COOLER RECEIPT FORM Rev. No. 12 12/30/10 Page 1 of 2

Submission #: 12-14106

SHIPPING INFORMATION
 Federal Express UPS Hand Delivery
 BC Lab Field Service Other (Specify) _____

SHIPPING CONTAINER
 Ice Chest None
 Box Other (Specify) _____

Refrigerant: Ice Blue Ice None Other Comments: _____

Custody Seals: Ice Chest Containers None Comments: _____
 Intact? Yes No Intact? Yes No

All samples received? Yes No All samples containers intact? Yes No Description(s) match COC? Yes No

COC Received YES NO
 Emissivity: 0.95 Container: Q+A Thermometer ID: 177 Date/Time: 1-31-12
 Temperature: (A) 0.4 °C / (C) 0.2 °C Analyst Init: JNW 2130

SAMPLE CONTAINERS	SAMPLE NUMBERS									
	1	2	3	4	5	6	7	8	9	10
QT GENERAL MINERAL/ GENERAL PHYSICAL										
PT PE UNPRESERVED										
QT INORGANIC CHEMICAL METALS										
PT INORGANIC CHEMICAL METALS										
PT CYANIDE										
PT NITROGEN FORMS										
PT TOTAL SULFIDE										
2oz. NITRATE / NITRITE										
PT TOTAL ORGANIC CARBON										
PT TOX										
PT CHEMICAL OXYGEN DEMAND										
PA PHENOLICS										
40ml VOA VIAL TRAVEL BLANK										
40ml VOA VIAL	A 13	A 13	A 13	A 13	A 13	A 13	A 13	A 13	A 13	A 13
QT EPA 413.1, 413.2, 418.1										
PT ODOR										
RADIOLOGICAL										
BACTERIOLOGICAL										
40 ml VOA VIAL- 504										
QT EPA 508/608/8080										
QT EPA 515.1/8150										
QT EPA 525										
QT EPA 525 TRAVEL BLANK										
100ml EPA 547										
100ml EPA 531.1										
QT EPA 548										
QT EPA 549										
QT EPA 632										
QT EPA 8015M										
QT AMBER	B, C	B C D	B A	B						
8 OZ. JAR										
32 OZ. JAR										
SOIL SLEEVE										
PCB VIAL										
PLASTIC BAG										
FERROUS IRON										
ENCORE										

Comments: _____
 Sample Numbering Completed By: UAM Date/Time: 8/1/12 0530
 A = Actual / C = Corrected

IC:\MyDDCS\Word\Perfect\LAB_DDCC\FORMS\SAMREC.ZI



Chain of Custody and Cooler Receipt Form for 1214106 Page 3 of 3

BC LABORATORIES INC. COOLER RECEIPT FORM Rev. No. 12 12/30/10 Page 2 of 2

Submission #: 12-14106

SHIPPING INFORMATION
 Federal Express UPS Hand Delivery
 BC Lab Field Service Other (Specify) _____

SHIPPING CONTAINER
 Ice Chest None
 Box Other (Specify) _____

Refrigerant: Ice Blue Ice None Other Comments: _____

Custody Seals: Ice Chest Containers None Comments: _____
 Intact? Yes No Intact? Yes No

All samples received? Yes No All samples containers intact? Yes No Description(s) match COC? Yes No

COC Received YES NO
 Emissivity: 0.95 Container: QA Thermometer ID: 177 Date/Time: 1-31-12
 Temperature: (A) 2.5 °C / (C) 2.3 °C Analyst Init: JWW 2130

SAMPLE CONTAINERS	SAMPLE NUMBERS									
	1	2	3	4	5	6	7	8	9	10
QT GENERAL MINERAL/ GENERAL PHYSICAL										
PT PE UNPRESERVED										
QT INORGANIC CHEMICAL METALS										
PT INORGANIC CHEMICAL METALS										
PT CYANIDE										
PT NITROGEN FORMS										
PT TOTAL SULFIDE										
2oz. NITRATE / NITRITE										
PT TOTAL ORGANIC CARBON										
PT TOX										
PT CHEMICAL OXYGEN DEMAND										
PA PHENOLICS										
40ml VOA VIAL TRAVEL BLANK										
40ml VOA VIAL										
QT EPA 413.1, 413.2, 418.1										
PT ODOR										
RADIOLOGICAL										
BACTERIOLOGICAL										
40 ml VOA VIAL- 504										
QT EPA 508/608/8080										
QT EPA 515.1/8150										
QT EPA 525										
QT EPA 525 TRAVEL BLANK										
100ml EPA 547										
100ml EPA 531.1										
QT EPA 548										
QT EPA 549										
QT EPA 632										
QT EPA 8015M										
QT AMBER			D	CD	3C	BC	BC	BC	BC	BC
8 OZ. JAR										
32 OZ. JAR										
SOIL SLEEVE										
PCB VIAL										
PLASTIC BAG										
FERROUS IRON										
ENCORE										

Comments: _____
 Sample Numbering Completed By: JWW Date/Time: 3/1/12 0530
 A = Actual / C = Corrected

IC:\MyDDCS\Word\Perfec\LAB_DOCS\FORMS\ESAMR1C21



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Information
------------	---------------------------

1214106-01	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MWT-1-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 11:20 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MWT-1 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--

1214106-02	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MWT-2-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 10:24 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MWT-2 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--

1214106-03	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MWT-3-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 09:44 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MWT-3 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Information
------------	---------------------------

1214106-04	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MWT-4-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 08:42 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MWT-4 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--

1214106-05	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MW-1A-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 12:20 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MW-1A Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--

1214106-06	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MW-1B-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 14:20 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MW-1B Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Information
------------	---------------------------

1214106-07	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MW-2A-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 12:54 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MW-2A Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--

1214106-08	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MW-2B-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 14:36 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MW-2B Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--

1214106-09	COC Number: --- Project Number: 3737 Sampling Location: --- Sampling Point: MW-3A-W-120729 Sampled By: TRCI	Receive Date: 07/31/2012 21:30 Sampling Date: 07/29/2012 12:03 Sample Depth: --- Lab Matrix: Water Sample Type: Water Delivery Work Order: Global ID: T06019745736 Location ID (FieldPoint): MW-3A Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	--	--



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Information
------------	---------------------------

1214106-10	COC Number: ---	Receive Date: 07/31/2012 21:30
	Project Number: 3737	Sampling Date: 07/29/2012 14:10
	Sampling Location: ---	Sample Depth: ---
	Sampling Point: MW-3B-W-120729	Lab Matrix: Water
	Sampled By: TRCI	Sample Type: Water
		Delivery Work Order:
		Global ID: T06019745736
		Location ID (FieldPoint): MW-3B
		Matrix: W
		Sample QC Type (SACode): CS
	Cooler ID:	



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-01	Client Sample Name: 3737, MWT-1-W-120729, 7/29/2012 11:20:00AM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	7.7	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	3.5	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	31	ug/L	0.50	EPA-8260	ND		1
Toluene	2.3	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	6.3	ug/L	1.0	EPA-8260	ND		1
t-Butyl alcohol	71	ug/L	10	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	2500	ug/L	250	Luft-GC/MS	ND	A01	2
1,2-Dichloroethane-d4 (Surrogate)	107	%	75 - 125 (LCL - UCL)	EPA-8260			1
1,2-Dichloroethane-d4 (Surrogate)	99.6	%	75 - 125 (LCL - UCL)	EPA-8260			2
Toluene-d8 (Surrogate)	109	%	80 - 120 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	99.6	%	80 - 120 (LCL - UCL)	EPA-8260			2
4-Bromofluorobenzene (Surrogate)	126	%	80 - 120 (LCL - UCL)	EPA-8260		S09	1
4-Bromofluorobenzene (Surrogate)	105	%	80 - 120 (LCL - UCL)	EPA-8260			2

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 14:41	JMC	MS-V12	1	BVH0130
2	EPA-8260	08/01/12	08/01/12 18:29	JMC	MS-V12	5	BVH0130



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

BCL Sample ID: 1214106-01	Client Sample Name: 3737, MWT-1-W-120729, 7/29/2012 11:20:00AM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	1100	ug/L	200	EPA-8015B/TPH d	ND	A01,A52	1
Tetracosane (Surrogate)	97.4	%	30 - 150 (LCL - UCL)	EPA-8015B/TPH d		A01	1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/02/12	08/09/12 00:00	MK1	GC-5	4.950	BVH0592



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-01	Client Sample Name: 3737, MWT-1-W-120729, 7/29/2012 11:20:00AM						
Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	450	ug/L	40	EPA-8015B/TPH d	ND	A52	1
Tetracosane (Surrogate)	88.3	%	28 - 139 (LCL - UCL)	EPA-8015B/TPH d			1
Capric acid (Reverse Surrogate)	0	%	0 - 2 (LCL - UCL)	EPA-8015B/TPH d			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/03/12	08/08/12 22:42	MK1	GC-5	1	BVH0608



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-02	Client Sample Name: 3737, MWT-2-W-120729, 7/29/2012 10:24:00AM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	70	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	62	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	11	ug/L	0.50	EPA-8260	ND		1
Toluene	1.6	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	8.8	ug/L	1.0	EPA-8260	ND		1
t-Butyl alcohol	89	ug/L	10	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	3000	ug/L	250	Luft-GC/MS	ND	A01	2
1,2-Dichloroethane-d4 (Surrogate)	106	%	75 - 125 (LCL - UCL)	EPA-8260			1
1,2-Dichloroethane-d4 (Surrogate)	102	%	75 - 125 (LCL - UCL)	EPA-8260			2
Toluene-d8 (Surrogate)	99.3	%	80 - 120 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	104	%	80 - 120 (LCL - UCL)	EPA-8260			2
4-Bromofluorobenzene (Surrogate)	127	%	80 - 120 (LCL - UCL)	EPA-8260		S09	1
4-Bromofluorobenzene (Surrogate)	112	%	80 - 120 (LCL - UCL)	EPA-8260			2

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 14:24	JMC	MS-V12	1	BVG2132
2	EPA-8260	08/01/12	08/01/12 18:11	JMC	MS-V12	5	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

BCL Sample ID: 1214106-02	Client Sample Name: 3737, MWT-2-W-120729, 7/29/2012 10:24:00AM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	780	ug/L	40	EPA-8015B/TPH d	ND	A52	1
Tetracosane (Surrogate)	85.7	%	30 - 150 (LCL - UCL)	EPA-8015B/TPH d			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/02/12	08/08/12 19:59	MK1	GC-5	1	BVH0592



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-02	Client Sample Name: 3737, MWT-2-W-120729, 7/29/2012 10:24:00AM						
Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	ND	ug/L	40	EPA-8015B/TPH d	ND	A52	1
Tetracosane (Surrogate)	7.2	%	28 - 139 (LCL - UCL)	EPA-8015B/TPH d		S09	1
Capric acid (Reverse Surrogate)	0	%	0 - 2 (LCL - UCL)	EPA-8015B/TPH d			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/03/12	08/09/12 00:43	MK1	GC-5	1	BVH0608



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-03	Client Sample Name: 3737, MWT-3-W-120729, 7/29/2012 9:44:00AM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	1.3	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	0.63	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	1.9	ug/L	0.50	EPA-8260	ND		1
Toluene	0.65	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	2.4	ug/L	1.0	EPA-8260	ND		1
t-Butyl alcohol	17	ug/L	10	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	2100	ug/L	250	Luft-GC/MS	ND	A01	2
1,2-Dichloroethane-d4 (Surrogate)	106	%	75 - 125 (LCL - UCL)	EPA-8260			1
1,2-Dichloroethane-d4 (Surrogate)	106	%	75 - 125 (LCL - UCL)	EPA-8260			2
Toluene-d8 (Surrogate)	105	%	80 - 120 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	102	%	80 - 120 (LCL - UCL)	EPA-8260			2
4-Bromofluorobenzene (Surrogate)	116	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	110	%	80 - 120 (LCL - UCL)	EPA-8260			2

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 14:06	JMC	MS-V12	1	BVG2132
2	EPA-8260	08/01/12	08/01/12 17:54	JMC	MS-V12	5	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

BCL Sample ID: 1214106-03	Client Sample Name: 3737, MWT-3-W-120729, 7/29/2012 9:44:00AM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	900	ug/L	200	EPA-8015B/TPH d	ND	A01,A52	1
Tetracosane (Surrogate)	100	%	30 - 150 (LCL - UCL)	EPA-8015B/TPH d		A01	1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/02/12	08/09/12 00:14	MK1	GC-5	5	BVH0592



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-03	Client Sample Name: 3737, MWT-3-W-120729, 7/29/2012 9:44:00AM						
Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	640	ug/L	40	EPA-8015B/TPH d	ND	A52	1
Tetracosane (Surrogate)	122	%	28 - 139 (LCL - UCL)	EPA-8015B/TPH d			1
Capric acid (Reverse Surrogate)	0	%	0 - 2 (LCL - UCL)	EPA-8015B/TPH d			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/03/12	08/08/12 23:08	MK1	GC-5	1	BVH0608

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.
All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-04	Client Sample Name: 3737, MWT-4-W-120729, 7/29/2012 8:42:00AM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	530	ug/L	6.2	EPA-8260	ND	A01	1
Ethylbenzene	100	ug/L	6.2	EPA-8260	ND	A01	1
Methyl t-butyl ether	0.78	ug/L	0.50	EPA-8260	ND		2
Toluene	5.8	ug/L	0.50	EPA-8260	ND		2
Total Xylenes	61	ug/L	1.0	EPA-8260	ND		2
t-Butyl alcohol	560	ug/L	10	EPA-8260	ND		2
Total Purgeable Petroleum Hydrocarbons (C6-C12)	2800	ug/L	620	Luft-GC/MS	ND	A01	1
1,2-Dichloroethane-d4 (Surrogate)	103	%	75 - 125 (LCL - UCL)	EPA-8260			1
1,2-Dichloroethane-d4 (Surrogate)	102	%	75 - 125 (LCL - UCL)	EPA-8260			2
Toluene-d8 (Surrogate)	96.8	%	80 - 120 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	97.6	%	80 - 120 (LCL - UCL)	EPA-8260			2
4-Bromofluorobenzene (Surrogate)	107	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	128	%	80 - 120 (LCL - UCL)	EPA-8260		S09	2

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 17:36	JMC	MS-V12	12.500	BVG2132
2	EPA-8260	08/01/12	08/01/12 13:49	JMC	MS-V12	1	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

BCL Sample ID: 1214106-04	Client Sample Name: 3737, MWT-4-W-120729, 7/29/2012 8:42:00AM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	1500	ug/L	200	EPA-8015B/TPH d	ND	A01,A52	1
Tetracosane (Surrogate)	109	%	30 - 150 (LCL - UCL)	EPA-8015B/TPH d		A01	1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/02/12	08/09/12 00:28	MK1	GC-5	4.800	BVH0592



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-04	Client Sample Name: 3737, MWT-4-W-120729, 7/29/2012 8:42:00AM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Diesel Range Organics (C12 - C24)	690	ug/L	40	EPA-8015B/TPH d	ND	A52	1
Tetracosane (Surrogate)	88.5	%	28 - 139 (LCL - UCL)	EPA-8015B/TPH d			1
Capric acid (Reverse Surrogate)	0	%	0 - 2 (LCL - UCL)	EPA-8015B/TPH d			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/TPHd	08/03/12	08/08/12 23:20	MK1	GC-5	1	BVH0608



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-05	Client Sample Name: 3737, MW-1A-W-120729, 7/29/2012 12:20:00PM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	10	ug/L	0.50	EPA-8260	ND		1
1,2-Dibromoethane	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dichloroethane	ND	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	0.80	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	35	ug/L	0.50	EPA-8260	ND		1
Toluene	ND	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	1.9	ug/L	1.0	EPA-8260	ND		1
t-Amyl Methyl ether	1.2	ug/L	0.50	EPA-8260	ND		1
t-Butyl alcohol	80	ug/L	10	EPA-8260	ND		1
Diisopropyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Ethanol	ND	ug/L	250	EPA-8260	ND		1
Ethyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	1400	ug/L	50	Luft-GC/MS	ND		1
1,2-Dichloroethane-d4 (Surrogate)	105	%	75 - 125 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	103	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	108	%	80 - 120 (LCL - UCL)	EPA-8260			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 13:31	JMC	MS-V12	1	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-05	Client Sample Name: 3737, MW-1A-W-120729, 7/29/2012 12:20:00PM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
TPH - Diesel (FFP)	220	ug/L	40	EPA-8015B/FFP	ND	A52	1
TPH - Motor Oil	ND	ug/L	100	EPA-8015B/FFP	ND	A57	1
Tetracosane (Surrogate)	83.5	%	37 - 134 (LCL - UCL)	EPA-8015B/FFP			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/FFP	08/03/12	08/09/12 00:06	MWB	GC-13	1	BVH0624



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-06	Client Sample Name: 3737, MW-1B-W-120729, 7/29/2012 2:20:00PM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dibromoethane	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dichloroethane	27	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	ND	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	0.72	ug/L	0.50	EPA-8260	ND		1
Toluene	ND	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	ND	ug/L	1.0	EPA-8260	ND		1
t-Amyl Methyl ether	ND	ug/L	0.50	EPA-8260	ND		1
t-Butyl alcohol	ND	ug/L	10	EPA-8260	ND		1
Diisopropyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Ethanol	ND	ug/L	250	EPA-8260	ND		1
Ethyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	ND	ug/L	50	Luft-GC/MS	ND		1
1,2-Dichloroethane-d4 (Surrogate)	103	%	75 - 125 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	99.3	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	97.1	%	80 - 120 (LCL - UCL)	EPA-8260			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 13:14	JMC	MS-V12	1	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-06	Client Sample Name: 3737, MW-1B-W-120729, 7/29/2012 2:20:00PM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
TPH - Diesel (FFP)	ND	ug/L	40	EPA-8015B/FFP	ND		1
TPH - Motor Oil	ND	ug/L	100	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate)	91.7	%	37 - 134 (LCL - UCL)	EPA-8015B/FFP			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/FFP	08/03/12	08/09/12 00:28	MWB	GC-13	1	BVH0624



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-07	Client Sample Name: 3737, MW-2A-W-120729, 7/29/2012 12:54:00PM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	120	ug/L	2.5	EPA-8260	ND	A01	1
1,2-Dibromoethane	ND	ug/L	0.50	EPA-8260	ND		2
1,2-Dichloroethane	ND	ug/L	0.50	EPA-8260	ND		2
Ethylbenzene	12	ug/L	0.50	EPA-8260	ND		2
Methyl t-butyl ether	280	ug/L	2.5	EPA-8260	ND	A01	1
Toluene	1.9	ug/L	0.50	EPA-8260	ND		2
Total Xylenes	1.4	ug/L	1.0	EPA-8260	ND		2
t-Amyl Methyl ether	ND	ug/L	0.50	EPA-8260	ND		2
t-Butyl alcohol	2300	ug/L	10	EPA-8260	ND		2
Diisopropyl ether	ND	ug/L	0.50	EPA-8260	ND		2
Ethanol	ND	ug/L	250	EPA-8260	ND		2
Ethyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		2
Total Purgeable Petroleum Hydrocarbons (C6-C12)	1900	ug/L	50	Luft-GC/MS	ND		2
1,2-Dichloroethane-d4 (Surrogate)	104	%	75 - 125 (LCL - UCL)	EPA-8260			1
1,2-Dichloroethane-d4 (Surrogate)	106	%	75 - 125 (LCL - UCL)	EPA-8260			2
Toluene-d8 (Surrogate)	99.1	%	80 - 120 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	103	%	80 - 120 (LCL - UCL)	EPA-8260			2
4-Bromofluorobenzene (Surrogate)	98.7	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	105	%	80 - 120 (LCL - UCL)	EPA-8260			2

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 17:19	JMC	MS-V12	5	BVG2132
2	EPA-8260	08/01/12	08/01/12 12:57	JMC	MS-V12	1	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-07	Client Sample Name: 3737, MW-2A-W-120729, 7/29/2012 12:54:00PM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
TPH - Diesel (FFP)	310	ug/L	40	EPA-8015B/FFP	ND	A52	1
TPH - Motor Oil	ND	ug/L	100	EPA-8015B/FFP	ND	A57	1
Tetracosane (Surrogate)	92.3	%	37 - 134 (LCL - UCL)	EPA-8015B/FFP			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/FFP	08/03/12	08/09/12 00:50	MWB	GC-13	1	BVH0624

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.
All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-08	Client Sample Name: 3737, MW-2B-W-120729, 7/29/2012 2:36:00PM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dibromoethane	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dichloroethane	ND	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	ND	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	2.1	ug/L	0.50	EPA-8260	ND		1
Toluene	ND	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	ND	ug/L	1.0	EPA-8260	ND		1
t-Amyl Methyl ether	ND	ug/L	0.50	EPA-8260	ND		1
t-Butyl alcohol	ND	ug/L	10	EPA-8260	ND		1
Diisopropyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Ethanol	ND	ug/L	250	EPA-8260	ND		1
Ethyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	ND	ug/L	50	Luft-GC/MS	ND		1
1,2-Dichloroethane-d4 (Surrogate)	100	%	75 - 125 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	97.7	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	98.2	%	80 - 120 (LCL - UCL)	EPA-8260			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 12:39	JMC	MS-V12	1	BVG2132



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-08	Client Sample Name: 3737, MW-2B-W-120729, 7/29/2012 2:36:00PM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
TPH - Diesel (FFP)	ND	ug/L	40	EPA-8015B/FFP	ND		1
TPH - Motor Oil	ND	ug/L	100	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate)	87.2	%	37 - 134 (LCL - UCL)	EPA-8015B/FFP			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/FFP	08/03/12	08/09/12 01:13	MWB	GC-13	1	BVH0624

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.
All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-09	Client Sample Name: 3737, MW-3A-W-120729, 7/29/2012 12:03:00PM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	77	ug/L	0.50	EPA-8260	ND		1
1,2-Dibromoethane	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dichloroethane	0.94	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	14	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Toluene	2.1	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	2.2	ug/L	1.0	EPA-8260	ND		1
t-Amyl Methyl ether	ND	ug/L	0.50	EPA-8260	ND		1
t-Butyl alcohol	ND	ug/L	10	EPA-8260	ND		1
Diisopropyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Ethanol	ND	ug/L	250	EPA-8260	ND		1
Ethyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	1900	ug/L	250	Luft-GC/MS	ND	A01	2
1,2-Dichloroethane-d4 (Surrogate)	112	%	75 - 125 (LCL - UCL)	EPA-8260			1
1,2-Dichloroethane-d4 (Surrogate)	99.6	%	75 - 125 (LCL - UCL)	EPA-8260			2
Toluene-d8 (Surrogate)	110	%	80 - 120 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	102	%	80 - 120 (LCL - UCL)	EPA-8260			2
4-Bromofluorobenzene (Surrogate)	118	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	108	%	80 - 120 (LCL - UCL)	EPA-8260			2

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 12:22	JMC	MS-V12	1	BVG2132
2	EPA-8260	08/01/12	08/01/12 17:01	JMC	MS-V12	5	BVG2132

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-09	Client Sample Name: 3737, MW-3A-W-120729, 7/29/2012 12:03:00PM
----------------------------------	---

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
TPH - Diesel (FFP)	160	ug/L	40	EPA-8015B/FFP	ND	A52	1
TPH - Motor Oil	ND	ug/L	100	EPA-8015B/FFP	ND	A57	1
Tetracosane (Surrogate)	81.8	%	37 - 134 (LCL - UCL)	EPA-8015B/FFP			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/FFP	08/03/12	08/09/12 01:35	MWB	GC-13	1	BVH0624



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 1214106-10	Client Sample Name: 3737, MW-3B-W-120729, 7/29/2012 2:10:00PM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
Benzene	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dibromoethane	ND	ug/L	0.50	EPA-8260	ND		1
1,2-Dichloroethane	ND	ug/L	0.50	EPA-8260	ND		1
Ethylbenzene	ND	ug/L	0.50	EPA-8260	ND		1
Methyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Toluene	ND	ug/L	0.50	EPA-8260	ND		1
Total Xylenes	ND	ug/L	1.0	EPA-8260	ND		1
t-Amyl Methyl ether	ND	ug/L	0.50	EPA-8260	ND		1
t-Butyl alcohol	ND	ug/L	10	EPA-8260	ND		1
Diisopropyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Ethanol	ND	ug/L	250	EPA-8260	ND		1
Ethyl t-butyl ether	ND	ug/L	0.50	EPA-8260	ND		1
Total Purgeable Petroleum Hydrocarbons (C6-C12)	ND	ug/L	50	Luft-GC/MS	ND		1
1,2-Dichloroethane-d4 (Surrogate)	103	%	75 - 125 (LCL - UCL)	EPA-8260			1
Toluene-d8 (Surrogate)	103	%	80 - 120 (LCL - UCL)	EPA-8260			1
4-Bromofluorobenzene (Surrogate)	99.7	%	80 - 120 (LCL - UCL)	EPA-8260			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8260	08/01/12	08/01/12 12:04	JMC	MS-V12	1	BVG2132

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

BCL Sample ID: 1214106-10	Client Sample Name: 3737, MW-3B-W-120729, 7/29/2012 2:10:00PM
----------------------------------	--

Constituent	Result	Units	PQL	Method	MB Bias	Lab Quals	Run #
TPH - Diesel (FFP)	ND	ug/L	40	EPA-8015B/FFP	ND		1
TPH - Motor Oil	ND	ug/L	100	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate)	54.8	%	37 - 134 (LCL - UCL)	EPA-8015B/FFP			1

Run #	Method	Prep Date	Run Date/Time	Analyst	Instrument	Dilution	QC Batch ID
1	EPA-8015B/FFP	08/03/12	08/09/12 01:58	MWB	GC-13	1	BVH0624



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
-------------	--------------	-----------	-------	-----	-----	-----------

QC Batch ID: BVG2132

Benzene	BVG2132-BLK1	ND	ug/L	0.50		
1,2-Dibromoethane	BVG2132-BLK1	ND	ug/L	0.50		
1,2-Dichloroethane	BVG2132-BLK1	ND	ug/L	0.50		
Ethylbenzene	BVG2132-BLK1	ND	ug/L	0.50		
Methyl t-butyl ether	BVG2132-BLK1	ND	ug/L	0.50		
Toluene	BVG2132-BLK1	ND	ug/L	0.50		
Total Xylenes	BVG2132-BLK1	ND	ug/L	1.0		
t-Amyl Methyl ether	BVG2132-BLK1	ND	ug/L	0.50		
t-Butyl alcohol	BVG2132-BLK1	ND	ug/L	10		
Diisopropyl ether	BVG2132-BLK1	ND	ug/L	0.50		
Ethanol	BVG2132-BLK1	ND	ug/L	250		
Ethyl t-butyl ether	BVG2132-BLK1	ND	ug/L	0.50		
Total Purgeable Petroleum Hydrocarbons (C6-I	BVG2132-BLK1	ND	ug/L	50		
1,2-Dichloroethane-d4 (Surrogate)	BVG2132-BLK1	102	%	75 - 125 (LCL - UCL)		
Toluene-d8 (Surrogate)	BVG2132-BLK1	102	%	80 - 120 (LCL - UCL)		
4-Bromofluorobenzene (Surrogate)	BVG2132-BLK1	95.5	%	80 - 120 (LCL - UCL)		

QC Batch ID: BVH0130

Benzene	BVH0130-BLK1	ND	ug/L	0.50		
Ethylbenzene	BVH0130-BLK1	ND	ug/L	0.50		
Methyl t-butyl ether	BVH0130-BLK1	ND	ug/L	0.50		
Toluene	BVH0130-BLK1	ND	ug/L	0.50		
Total Xylenes	BVH0130-BLK1	ND	ug/L	1.0		
t-Butyl alcohol	BVH0130-BLK1	ND	ug/L	10		
Total Purgeable Petroleum Hydrocarbons (C6-I	BVH0130-BLK1	ND	ug/L	50		
1,2-Dichloroethane-d4 (Surrogate)	BVH0130-BLK1	106	%	75 - 125 (LCL - UCL)		
Toluene-d8 (Surrogate)	BVH0130-BLK1	99.3	%	80 - 120 (LCL - UCL)		
4-Bromofluorobenzene (Surrogate)	BVH0130-BLK1	97.6	%	80 - 120 (LCL - UCL)		

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Laboratory Control Sample

Constituent	QC Sample ID	Type	Result	Spike Level	Units	Percent Recovery	Control Limits		Lab
							RPD	RPD	
QC Batch ID: BVG2132									
Benzene	BVG2132-BS1	LCS	24.620	25.000	ug/L	98.5	70	130	
Toluene	BVG2132-BS1	LCS	22.810	25.000	ug/L	91.2	70	130	
1,2-Dichloroethane-d4 (Surrogate)	BVG2132-BS1	LCS	10.100	10.000	ug/L	101	75	125	
Toluene-d8 (Surrogate)	BVG2132-BS1	LCS	10.040	10.000	ug/L	100	80	120	
4-Bromofluorobenzene (Surrogate)	BVG2132-BS1	LCS	10.660	10.000	ug/L	107	80	120	
QC Batch ID: BVH0130									
Benzene	BVH0130-BS1	LCS	27.780	25.000	ug/L	111	70	130	
Toluene	BVH0130-BS1	LCS	27.250	25.000	ug/L	109	70	130	
1,2-Dichloroethane-d4 (Surrogate)	BVH0130-BS1	LCS	9.9700	10.000	ug/L	99.7	75	125	
Toluene-d8 (Surrogate)	BVH0130-BS1	LCS	9.7800	10.000	ug/L	97.8	80	120	
4-Bromofluorobenzene (Surrogate)	BVH0130-BS1	LCS	10.740	10.000	ug/L	107	80	120	



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Precision & Accuracy

Table with columns: Constituent, Type, Source Sample ID, Source Result, Result, Spike Added, Units, RPD, Percent Recovery, Control Limits RPD, Control Limits Percent Recovery, Lab Quals. Includes QC Batch ID: BVG2132 and QC Batch ID: BVH0130.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BVH0624						
TPH - Diesel (FFP)	BVH0624-BLK1	ND	ug/L	40		
TPH - Motor Oil	BVH0624-BLK1	ND	ug/L	100		
Tetracosane (Surrogate)	BVH0624-BLK1	88.6	%	37 - 134 (LCL - UCL)		



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

Quality Control Report - Laboratory Control Sample

Constituent	QC Sample ID	Type	Result	Spike Level	Units	Percent Recovery	RPD	Control Limits		Lab	Quals
								Percent Recovery	RPD		
QC Batch ID: BVH0624											
TPH - Diesel (FFP)	BVH0624-BS1	LCS	337.12	500.00	ug/L	67.4		52	128		
Tetracosane (Surrogate)	BVH0624-BS1	LCS	22.809	20.000	ug/L	114		37	134		



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Purgeable Aromatics and Total Petroleum Hydrocarbons (Silica Gel Treated)

Quality Control Report - Precision & Accuracy

Constituent	Type	Source Sample ID	Source Result	Result	Spike Added	Units	RPD	Percent		Lab Quals
								Recovery	RPD	
QC Batch ID: BVH0624		Used client sample: N								
TPH - Diesel (FFP)	MS	1213312-46	ND	300.48	500.00	ug/L		60.1		50 - 127
	MSD	1213312-46	ND	313.07	500.00	ug/L	4.1	62.6	24	50 - 127
Tetracosane (Surrogate)	MS	1213312-46	ND	19.343	20.000	ug/L		96.7		37 - 134
	MSD	1213312-46	ND	20.324	20.000	ug/L	4.9	102		37 - 134



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BVH0592						
Diesel Range Organics (C12 - C24)	BVH0592-BLK1	ND	ug/L	40		
Tetracosane (Surrogate)	BVH0592-BLK1	121	%	30 - 150 (LCL - UCL)		



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

Quality Control Report - Laboratory Control Sample

Constituent	QC Sample ID	Type	Result	Spike Level	Units	Percent Recovery	RPD	Control Limits		Lab
								Percent Recovery	RPD	
QC Batch ID: BVH0592										
Diesel Range Organics (C12 - C24)	BVH0592-BS1	LCS	423.42	500.00	ug/L	84.7		50 - 140		
Tetracosane (Surrogate)	BVH0592-BS1	LCS	21.255	20.000	ug/L	106		30 - 150		



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons

Quality Control Report - Precision & Accuracy

Constituent	Type	Source Sample ID	Source Result	Result	Spike Added	Units	RPD	Percent Recovery	Control Limits		Lab Quals
									RPD	Percent Recovery	
QC Batch ID: BVH0592		Used client sample: N									
Diesel Range Organics (C12 - C24)	MS	1210608-96	ND	489.97	500.00	ug/L		98.0		50 - 140	
	MSD	1210608-96	ND	350.42	500.00	ug/L	33.2	70.1	30	50 - 140	Q02
Tetracosane (Surrogate)	MS	1210608-96	ND	23.775	20.000	ug/L		119		30 - 150	
	MSD	1210608-96	ND	18.466	20.000	ug/L	25.1	92.3		30 - 150	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BVH0608						
Diesel Range Organics (C12 - C24)	BVH0608-BLK1	ND	ug/L	40		
Tetracosane (Surrogate)	BVH0608-BLK1	93.6	%	28 - 139 (LCL - UCL)		
Capric acid (Reverse Surrogate)	BVH0608-BLK1		%	0 - 2 (LCL - UCL)		



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

Quality Control Report - Laboratory Control Sample

Constituent	QC Sample ID	Type	Result	Spike Level	Units	Percent Recovery	RPD	Control Limits		Lab	Quals
								Percent Recovery	RPD		
QC Batch ID: BVH0608											
Diesel Range Organics (C12 - C24)	BVH0608-BS1	LCS	253.11	500.00	ug/L	50.6		48 - 125			
Tetracosane (Surrogate)	BVH0608-BS1	LCS	16.751	20.000	ug/L	83.8		28 - 139			
Capric acid (Reverse Surrogate)	BVH0608-BS1	LCS	ND	100.00	ug/L			0 - 2			



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Total Petroleum Hydrocarbons (Silica Gel Treated)

Quality Control Report - Precision & Accuracy

Constituent	Type	Source Sample ID	Source Result	Result	Spike Added	Units	RPD	Percent		Lab Quals
								Recovery	RPD	
QC Batch ID: BVH0608		Used client sample: N								
Diesel Range Organics (C12 - C24)	MS	1213312-47	ND	221.87	500.00	ug/L		44.4		36 - 130
	MSD	1213312-47	ND	296.41	500.00	ug/L	28.8	59.3	30	36 - 130
Tetracosane (Surrogate)	MS	1213312-47	ND	14.174	20.000	ug/L		70.9		28 - 139
	MSD	1213312-47	ND	22.030	20.000	ug/L	43.4	110		28 - 139
Capric acid (Reverse Surrogate)	MS	1213312-47	ND	ND	100.00	ug/L				0 - 2
	MSD	1213312-47	ND	ND	100.00	ug/L				0 - 2



Arcadis
2999 Oak Rd, Suite 300
Walnut Creek, CA 94597

Reported: 08/10/2012 10:07
Project: 3737
Project Number: 351780
Project Manager: Leah Ackerman

Notes And Definitions

- MDL Method Detection Limit
- ND Analyte Not Detected at or above the reporting limit
- PQL Practical Quantitation Limit
- RPD Relative Percent Difference
- A01 PQL's and MDL's are raised due to sample dilution.
- A52 Chromatogram not typical of diesel.
- A57 Chromatogram not typical of motor oil.
- Q02 Matrix spike precision is not within the control limits.
- S09 The surrogate recovery on the sample for this compound was not within the control limits.