

# AMERICAN BRASS & IRON FOUNDRY

7825 San Leandro Street • Oakland, CA 94621 • (510) 632-3467 Fax No. (510) 632-8035

September 22, 1992

Mr. Barney Chan Hazardous Materials Specialists ALAMEDA COUNTY HEALTH AGENCY Division of Hazardous Materials 80 Swan Way, Room 200 Oakland, CA 94621

Subject: Report on Removal of 12,000 Gallon Capacity

Underground Diesel Fuel Storage Tank,

American Brass & Iron Foundry,

Oakland, California

Dear Mr. Chan:

In accordance with Alameda County Health Agency and Tri-Regional Board Staff Recommendations for Underground Storage Tank Removal Procedures, please find enclosed American Brass & Iron Foundry's closure report for the removal of an on site 12,000 gallon storage tank.

The closure report reflects a portion of the initial underground storage tank closure plan submitted to Alameda County Health Agency on August 1, 1991. It is our intention to address all groundwater monitoring programs at the completion of the overall tank removal project at AB&I. Information on soil geology and groundwater contamination for surrounding property locations are being reviewed in order to fully evaluate a soil groundwater investigation.

If you require further information or have additional questions, please feel free in contacting me at (510) 632-3467 ext. 211.

Sincerely,

Dave Robinson Environmental Engineering Manager

cc: Lester Feldman, Regional Water Quality Control Board

John Sturman, Levine\*Fricke Consultants



### TABLE OF CONTENTS

1.0	INTR	ODUCTION1
2.0	SITE	HISTORY1
3.0	GENE	RAL DESCRIPTION OF CLOSURE ACTIVITIES2
4.0	CLOS	URE ACTIVITIES
	Α.	DESCRIPTION OF TANK AND MATERIALS
	В.	DESCRIPTION OF EXCAVATION AND TANK REMOVAL3
	С.	DESCRIPTION OF SAMPLING METHODS4
5.0	REME	DIATION ACTIVITIES
	Α.	EXCAVATION OF CONTAMINATED SOIL4
	В.	SAMPLING METHODS5
	С.	STORAGE OF CONTAMINATED SOIL6
	D.	EXCAVATION BACKFILL PROCEDURES6
6.0	GENE	RAL FIELD OBSERVATION7
7.0	LABO	RATORY ANALYSIS7
8.0	SOIL	/ WATER QUALITY RESULTS8
9.0	CONC	LUSION / RECOMMENDATIONS8
FIGU	n n c	
F T G O	KES	
	1.0	SITE LOCATION MAP10
	2.0	TANK LAYOUT11
	3.0	SAMPLING LOCATION AND FINAL EXCAVATION LAYOUT12



# TABLE OF CONTENTS (Con't)

TABLES	
1.0	SUMMARY OF ANALYSIS RESULTS13
APPENDIX	A
A. B.	ORIGINAL UST CLOSURE PLAN EXCAVATION PERMIT
APPENDIX	В
A. B. C.	FIRE INSPECTOR NOTES LEVINE*FRICKE FIELD NOTES DISPOSAL MANIFEST
APPENDIX	С

LABORATORY ANALYSIS



# REMOVAL OF 12,000 GALLON CAPACITY UNDERGROUND DIESEL FUEL STORAGE TANK AMERICAN BRASS & IRON FACILITY OAKLAND, CALIFORNIA

#### 1.0 INTRODUCTION

This report describes American Brass and Iron's removal program for one 12,000 gallon capacity underground diesel fuel storage tank from the facility located at 7825 San Leandro Street in Oakland, California; refer to Figure 1 for location details. This tank removal is the last of four UST removals as called out by AB&I's current on-site tank closure program.

Throughout the tank removal process, AB&I solicited assistance from various support groups including, Levine\*Fricke, Quanteo Laboratories, Oakland, Fire Department, Alameda County Health Services, H & H Environmental and Walts Excavation Services. Levine\*Fricke Consultants were the main contributors in assisting with the interpretation and conclusions for addressing this tank removal process.

#### 2.0 SITE HISTORY

AB&I has owned and operated at the present location since 1930. The main operation consists of the manufacturing of Gray Iron in the form of various sand castings, including an assortment of sizes pertaining to soil sewer pipe. The company has maintained operations in a progressive management style in order to remain competitive in the market place.

Throughout AB&I's progression, various equipment were purchased in order to increase efficiently and decrease manpower. The foundry operations are extremely dependent upon the operation of heavy equipment for transportation of raw materials and final products. AB&I has chosen to use diesel fuel as the main fuel supply for the equipment including their facility backup generator.

The tank in question, which was removed, was the primary storage tank for the Diesel Fuel #2. The tank was originally installed in the early 1970's for the sole purpose of storing diesel fuel. To our knowledge the tank was maintained for this purpose, the addition of any other material would have contaminated the fuel and stifled the operation at the plant.



#### 3.0 GENERAL DESCRIPTION OF CLOSURE ACTIVITIES

The overall tank removal program was managed by AB&I with direct assistance and involvement by all of the above mentioned parties. The tank was a 12,000 gallon, 1/4" thick steel tank, which was located on the northwest corner of the production facility. Refer to Figure 2 for details on tank location. The actual operation began on May 23, 1991. This tank removal was the fourth of a series of four tanks to be removed on site at 7825 San Leandro Street, Oakland. Refer to Appendix A for the original closure plan.

The tank was located beneath a 6" reinforced concrete pad with one building support column approximate 10' from the longitudinal side of the tank. The operation entailed the removal of the concrete pad of an area of 20' by 30' using a large motorized hydraulic pin digger to allow room for the removal of the tank. Soil was removed above and around the tank and the tank was removed, along with the minor piping system. Various soil samples were taken to determine if contamination was present and to what extent. On site a PID meter was used during the operation for indicating the potential contamination concentration of excavated soil. A water sample was also taken, although the water in the pit was not allowed sufficient time to flush to eliminate the mixing action created by the excavation work.

Once the tank had been removed, further excavation work was attempt to eliminate as much suspected an contamination as possible and secondly to determine both the lateral and vertical extent of the contamination. The excavation hole was greatly increased in an attempt to remove any contaminated soil from around the tank. The hole was enlarged as much as possible and was back filled with clean fill rock. Due to the location and the proposed use, the area was resurfaced with concrete and reinforced with steel mesh. The tank was manifested and disposed of through H & H Ship Service Company. A detailed account of each phase of the project is specified in the proceeding sections.

#### 4.0 CLOSURE ACTIVITIES

#### A. Description of Tank and Materials

The excess Diesel Fuel #2 was transferred to an above ground fuel tank (convault) for future use and the UST was Pump Dry. The inside of the tank was high pressure rinsed, using a steam generating machine. Approximately 150 gallons of rinsate was collected and pumped into a collection area. The fuel was



#### A. Description of Tank and Materials (con't.)

separated from the water and sent to California Oil Recyclers for further treatment. The tank had been originally wrapped with tar and tar paper which had remained intact. Piping for the UST was relatively minor due to the fuel dispenser being close by and above ground. The fuel dispenser was removed along with all above ground piping prior to removal of the surface concrete pad.

#### B. Description of Excavation and Tank Removal

On May 20, 1992, a Bobcat hydraulic pin digger, along with a jack hammer were rented, in order to adequately break through and remove a reinforced concrete pad. The original concrete pad consisted of a section approximately 30 feet by 25 feet, allowing ample room for the removal process and any required excavation area. This particular portion of the project was extremely time consuming and consisted of virtually a weeks worth of operation. Included in this stage of the operation was the set up of a transfer pump and piping. In addition all electrical conduits were removed prior to the removal of the concrete.

The initial excavation included the over-burden soil above and around the sides of the tank. The actual excavation process began on June 3, 1992. All excavated soil was removed and piled away from the actual excavation activities.

During the operations the fill, product, and vent piping were removed and set aside for subsequent removal from the site. Three tank port holes were open and 250 pounds of pelletized dry ice was placed into the tank at each end and in the center part. Combustible gasses and oxygen concentrations were measured in the tank using a combustible gas meter. The air inside the tank was drawn to the meter through tubing that was lowered approximately 5 feet into the tank. Inspector Brunelle; with the Oakland Fire Department, witnessed and approved the removal of the tank. The final meter readings indicated that the combustible gases were below 10% of the Lower Explosion Limit (LEL) and the oxygen content at 1.5%. Refer to Appendix B for information.

The tank port holes were sealed with wood plugs and the tank was lifted out using AB&I's crawler crane. Once out, the tank was placed directly onto a "low boy" trailer along with support piping for disposal with H & H Ship Service. The tank was manifested and recorded under EPA Manifest number 91510000. A copy of this manifest is included in Appendix B.



#### C. Description of Sampling Methods

Once the tank was removed from the site, along with all piping appurtenant to the tank, one initial soil sample was taken at the east end of the tank at approximately 12 feet, directly below the tank. Due to the extensive excavation, we chose to take a water sample at the end of the excavation process. The Photoinization Detector (PID) meter was used throughout the process as an approximation potential contamination. Although the use of a PID meter for diesel is poor, it will give a preliminary indication of possible contamination.

Soil samples were collected using a backhoe. The backhoe operator was directed to remove portions of native soil (not tank bedding material) at the desired depth and location with the backhoe bucket. After raising the backhoe bucket to the ground surface, soil samples were collected by driving 2-inch diameter brass liners into the desired portion of soil in the backhoe bucket. After filling the tube completely to minimize headspace, the ends of the tube were enclosed with plastic caps over aluminum foil and sealed with cloth tape. Samples were labelled and placed in a chilled ice chest.

The sampling process was performed solely by Mr. Michael Stoll with Levine\*Fricke Consultants, this included all sampling materials and suggested sampling locations. The sampling locations were chosen to best represent potential soil contamination and to determine the effects of the excavation process.

#### 5.0 REMEDIATION ACTIVITIES

#### A. Excavation of Contaminated Soil

A Photoinization Detector (PID) was used simply as a way to screen the soil samples encountered in the excavation process for Volatile Organic Compounds (VOC). It was understood that diesel fuel has limited volatile properties and the PID meter would indicate a fraction of the actual concentration in the soil. This process was used as an indication of possible contamination and not a verification of the actual contamination concentration. Originally the soil surrounding the tank was excavated using a backhoe to a distance of 3-6 feet from the sides of the tank in determining the lateral extent of potential diesel fuel affected soil. On June 4, 1992, approximately 180 cubic yards of soil were removed under the observation of Levin\*Fricke.



### A. Excavation of Contaminated Soil (con't)

The excavated soil surrounding the tank consisted of fine sand, gravel, foundry sand and various pieces of glass. The general characteristics of the excavated soil was somewhat of a conglomerate of material which appeared to be from past foundry practices.

The excavated material on the east end of the tank had both a diesel odor and a greenish discoloration. This section was directly below the former dispenser location. It appears from the excavation that the contamination was centralized on the east end, with the west end appearing to be clean. Additional removal of the concrete pad was necessary in order to continue excavating in the south easterly direction. The excavation on the east end actually extended approximately 4 feet beyond the edge of the concrete in order to remove contaminated soil down to the water table.

The excavation process was aborted due to the level of contamination and difficulty in removing the concrete surface structure. On June 5, 1992, the excavation was stopped, for it appeared that virtually all the contaminated soil had been removed. Figure 4 illustrates the UST removal and excavation area. The sampling process was the next step for determining the outcome of results of the excavation.

#### B. Sampling Methods

The excavation process continued until it appeared that the soil was unaffected by diesel fuel, using the PID meter, soil odor and discoloration as indicators. Samples of the remaining native soils were collected to confirm soil quality around the perimeter of the excavation. Effort on the far east side required extensive excavation in order to eliminate potential contaminant soil. Although the excavation area was somewhat irregular, the sampling locations were chosen to best identify the contamination of the subsurface area.

All sampling was performed by Michael Stoll, Senior Geologist, with Levine\*Fricke Consultants, using the same methodology as stated previously in a prior section. A series of six soil samples were taken to best represent the investigation. Each sample was tested for extractable hydrocarbons as diesel using EPA 3550(GCFID) and BTXE using method EPA 8020(5080). Soil samples collected during the excavation were labelled DEW1-E-9, DEW2-N-9, DEW3-N-8.5, DEW4-W-8, DEW5-S-8.5 and DEW6-S-9.



#### B. Sampling Methods (con't.)

In addition to soil sampling, a groundwater sample was taken. The sample was labelled D-Groundwater and was also tested for extractable hydrocarbons as diesel in milligrams per liter using method EPA 8020 (BTEX Water Matrix). During the excavation process it was evident that the water mixed with the contaminated soil to generate an obvious contaminated solution. Although the water was allowed to settle, the samples did not appear representative of the actual groundwater contamination level. Provided in Figure  ${\bf Q}$  is a sampling location map representing all sample locations with respect to the UST and the excavation area.

#### C. Storage of Contaminated Soil

All excavated soil was removed from the excavation site and was transported at the north end of the property. The material was placed on a concrete pad inside a covered building. The stock pile was divided into two piles based upon the excavation of the material. Extreme care was taken to segregate the soil in order to reduce the amount of material requiring treatment. Due to the contamination being diesel, aeration does not appear to be a viable remediation option. Samples of the unaffected soil were recently taken and submitted to NET Laboratories for analysis. All sampling protocols were compliant with EPA SW-846 sampling guidelines.

#### D. Excavation Backfill Procedures

On June 5, 1992 the back filling of the excavated area was conducted by AB&I personnel using front end loaders. This portion of the project was important not only from the standpoint of implementing clean soil into the excavated area but equally important was that the backfill process was done correctly to support heavy traffic of large operating equipment.

The backfill consisted of clean soil and gravel, layered to generate effective drainage and foundation support. A motorized soil compactor was used to enhance the compaction of the soil. The excavated section was covered with reinforced concrete approximately 10 inches thick.



#### 6.0 GENERAL FIELD OBSERVATIONS

The storage tank was in surprisingly good condition with the outside tar wrap still intact and no apparent damage to the outside of the tank. The tank and piping appeared to be without any visible leaking or contamination of any soil directly in contact with the surface.

Using the PID meter and visual observations, the excavated soil surrounding the tank, in general, appeared to be relatively unaffected by any potential solvent contamination. Due to the size of the tank, the excavation was fairly extensive, reaching depths of 11 feet. All field notes of the project are located in Appendix A. These included both Levine\*Fricke Consultants and Alameda County Health Services.

Water seepage into the excavation was observed at a depth of about 9-10 feet, with standing water collecting in the east end corner. Based on prior field observation from previous removals of UST here on site, it is expected that static groundwater is at a depth of about 10 to 13 feet below ground surface. The groundwater conditions were extremely poor due mainly to the excavation process which created a mixing action of the soil and water. Because of time restraints and pump equipment malfunctions the water was unable to sufficiently flush in order to take a representative sample. The visible observation of the sample indicated that a poor representative sample was chosen based on the amount of debris in the water from the excavation efforts.

#### 7.0 LABORATORY ANALYSIS

All soil and water samples were taken by Mr. Michael Stoll of Levine\*Fricke using EPA sampling methods during the excavation. The samples were submitted to Quanteo Laboratories Analytical with the Chain of Custody being directly from Mr. Michael Stoll.

Results of the laboratory analysis, along with the Chain of Custody are provided in Appendix C. The soil samples collected from the excavation indicated that the soil below and around the former tank was virtually unaffected by diesel fuel contamination, with limits ranging from 0 to 2.0 milligrams per kilogram (mg/kg). Accessible soil immediately below the former tank were excavated to a depth of approximately 13 feet providing an adequate assessment in fully understanding potential vertical contamination.



#### 7.0 LABORATORY ANALYSIS (con't.)

The analysis for TPH-Diesel indicated affected soil on the south east section of the excavation. Demonstrating some hydrocarbon contamination. Although the contamination level was fairly minor, limits for Benzene, Toluene, Ethylbenzene and Xylenes were non detected for all samples. All laboratory analysis results are located in Appendix C.

As expected, the water sample indicated a higher level for the TPH-Diesel analysis, but continued a non detect level for the BTEX testing. The contamination level for TPD-Diesel was 6.8 milligrams per liter: refer to Table 1 for details.

#### 8.0 SOIL / WATER QUALITY RESULTS

The soil analysis results demonstrating the soil was unaffected by diesel fuel contamination caused from leakage of the storage tank and piping connections. The southeast corner was the only indication of soil contamination with a level of 2 milligrams per kilogram. As depicted by the sampling layout map, sufficient samples were taken to determine both the lateral and vertical contamination level surrounding the UST excavation. Among other parameters the down gradient direction for this area was considered in choosing sampling locations.

The water analysis indicated a higher level of contamination level for all compounds in question than was expected or indicated from both visible observations and soil analysis results. The high levels are more than likely a direct result of the extensive excavation process and the stringent project time frames. As indicated by the soil/water analysis results, it appears the water sample was not representative of the water quality which exist.

#### 9.0 CONCLUSION / RECOMMENDATION

A 12,000 gallon underground diesel fuel storage tank was removed from the site and approximately 180 cubic yards of excavated soil were removed. The tank removal went according to plan with the aid of the crawler crane, which allowed us to remove the tank and load onto a "low boy" for direct disposal. The tank appears to be in good shape with the outside wrap material in tack. The excavation process was larger than originally anticipated but resulted in the virtual elimination of soil contamination surround the prior UST location.



### 9.0 CONCLUSION / RECOMMENDATION (con't.)

Overall the soil was found, for all purposes, to be relatively unaffected by diesel fuel contamination both beneath and on the sides of the former storage tank. The tank and underground piping appeared to be intact and was not the cause of the contamination. From the location of the contamination and the minimum vertical depth at which contamination was discovered, it was evident the contamination was probably a direct result of poor vehicles fuel filling practices. The highest concentration was near the ground surface versus the lowest concentration at groundwater level.

As indicated by the water analysis contamination levels, in conjunction with soil analysis and visible observation of the removal process, it is apparent with the inconsistent results from the water sample taken was not representative. It is our judgement additional water samples must be taken to best qualify the water quality and the potential impact of contamination generated from the underground storage tank.

Based upon our review of the work performed, sampling and analysis procedures, and the results obtained, it is our opinion that the work was performed in compliance with applicable tank closure requirements.

It is our recommendation that a monitoring well be installed in the down gradient direction and a shallow groundwater monitoring program be established in order to access the extent of any potential groundwater contamination.



Dave Robinson, REA No. 03815, exp. 6/30/93

#### TABLE 1

Soil and Water Quality Results American Brass & Iron Foundry 12,000 Gallon Diesel Tank Removal 7825 San Leandro Street Oakland, CA

Sample Number	Date Collected	Depth (feet)	Extractable Hydrocarbons as Diesel (mg/kg)	Benzene		il Matrix) EPA 8020 <u>Ethylbenzene</u>	Xylenes, Total	
Soil Samples (res	ults in milligrams p	er kilogram [mg/k	g])					
DEW 1-E-9	6-5-92	9	ND	N D	ND	ND	ND	
DEW 2-N-9	6-5-92	9	MD	ND	ND	ND	ND	
DEW 3-N-8.5	6-5-92	8.5	QM	-	-	_	-	
DEW 4-W-8	6-5-92	8	MD	ND	ND	ND	ND	
DEW 5-5-8.5	6-5-92	8.5	ND	-	-	_	-	
DEW 6-5-9	6-5-92	9	2	ND	ND	ND	ND	
Water Samples (results in milligrams per liter [mg/I])								
D-Groundwater	6~5-92	10	6.8	ND	ND	ND	ND	

#### NOTES:

All samples were analyzed by Quanteo Laboratories.




FIGURE 1.0 Site Location Map





FIGURE 2.0

Tank Layout





### FIGURE 3.0

Sampling Location and Final Excavation Layout




Figure 2: PLAN SHOWING FORMER TANK AND SOIL SAMPLE LOCATIONS



# APPENDIX A

A. Original UST Closure Plan
B. Excavation Permit

# ALAMEDA COUNTY HEALTH CARE SERVICES AGENCY DEPARTMENT OF ENVIRONMENTAL HEALTH HAZARDOUS MATERIALS DIVISION 80 SWAN WAY, ROOM 200 DEPARTMENT OF ENVIRONMENTAL HEALTH ATO - 27th Street, Third Floor Oakland, CA 918.2 Telephone: (4.5) 874-7737 This han been reviewed and found to be acceeded with lower Chinges as equirements of State and Environments of State and Found to be acceeded by the Chinges as equirements of State and Found to be acceeded by the Chinges as equirements of State and Found to be acceeded by the State of State and State a 94621 OAKLAND, CA The doing the no ed thum a els birdhoor earth of the to all contractors and eraftemen involved with Darney Charr

الم درسات سائر باط ،

submitted to this Decartment and to the Fire and nno or alterations of these plans and specifications s meet the requirements of State and local laws. his Dearmant at east 48 hours prior to Decorrant to determina insport on

Removal of Tank and Piping

y required inspections:

with accepted plans and all applicable laws and a parmit to operate is dependent First 'scaction

THERE IS A FINANCIAL PENALTY FOR NOT

UNDERGROUND TANK CLOSURE PLAN Complete according to attached instructions

1.	Business Name	AMERICAN B	RASS AND	DIRON	FOUNDRY	·		
	Business Owner _	ALLAN BOSC	ACCI		7-1			
2.	Site Address	7825 SAN L	EANDRO :	STREET				
	City OAKLAND			Zip 9	4621	Phone	(510)	632-3467
3.	Mailing Address						•	
	City OAKLAND			Zip _	94621	Phone	(510)	632-3467
4.	Land Owner AL				···			
	Address 7825 SA	N LEANDRO S	GT. ci	ty, st	ate OAKI	JAND, C	A Zip	94621
5.	Generator name u				manifes	ted		
(	PA I.D. No. und	er which to	ank will	be ma	nifeste	d CAD O	217745	59

. Contractor	SAME AS OWNER	
Address		
		Phone
License Typ	e	ID#
Consultant _	LEVINE-FRICKE	
Address	1900 POWELL STREET	, 12th FLOOR
City	EMERYVILLE	Phone (510) 632-3467
Contact Personal John Mame John (415)		Title SENIOR PROJECT
		GEOTECHNICAL ENGINEER er this plan1
Length of pig	oing being removed un	nder this plan APP. 10 FT.
Total number	of tanks at facility	
State Registe instructions)	red Hazardous Waste	Transporters/Facilities (see
** Undergroun	d tanks are hazardou as hazardou	s waste and must be handled **
a) Product/R	esidual Sludge/Rinsa	te Transporter
Name EVE	RGREEN ENVIRONMENTAL	SVCS. EPA I.D. No. CAD 980695761
Hauler L	icense No.	License Exp. Date
Address	6880 SMITH ROAD	- Date
City	NEWARK	StateCAzip94560 .
b) Product/Re	esidual Sludge/Rinsat	te Disposal Site
Name EV	ERGREEN ENVIRONMENTA	AL EPA I.D. No. CAD 980887418
- radiess	OSSU SMITH ROAD	
city	NEWARK	Ştate <u>CA</u> Zip <u>94560</u>

c) Tank and Piping Transporter	
Name H & H SHIP SERVICE	
Hauler License No. 0334 License Exp. Date 1/31/92	. <u>68</u> 2
Address 220 CHINA BASIN STREET	
City SAN FRANCISCO State CA Zip 94107	
d) Tank and Piping Disposal Site	<del></del>
Name SAME AS TRANSPORTER	
Name SAME AS TRANSPORTER EPA I.D. No Address	1-77-C-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1
City State Zip	***************************************
11. Experienced Sample Collector	
Name JOHN STURMAN	
Company LEVINE-FRICKE	-
Address 1900 POWELL STREET	<del></del>
City EMERYVILLE State CA Zip 94608 Phone (510) 652	
	-4500 
12. Laboratory	
Name BC ANALYTICAL	•
Address 1255 POWELL STREET	<del></del>
City EMERYVILLE State CA 2ip 94608  State Certification No. 1353	
State Certification No. 1353	<del></del>
13. Have tanks or pipes leaked in the past? Yes [ ] No [X] . If yes, describe.	и <del>нтинуции</del> ,
	<del></del>

- 14. Describe methods to be used for rendering tank inert
  - 1) PRODUCT AND SLUDGE REMOVAL
  - 2) RINSING PIPING AND TANKS
  - 3) DRY ICE

Before tanks are pumped out and inerted, all associated piping must be flushed out into the tanks. All accessible associated piping must then be removed. Inaccessible piping must be plugged.

The Bay Area Air Quality Management District (771-6000), along with local Fire and Building Departments, must also be contacted for tank removal permits. Fire departments typically require the use of explosion proof combustible gas meters to verify tank inertness. It is the contractor's responsibility to bring a working combustible gas meter on site to verify tank inertness.

# 15. Tank History and Sampling Information

Та	nk	Material to		
Capacity	Use History (see instructions)	be sampled (tank contents, soil, ground-water, etc.)	Location and Depth of Samples	
10,000 GA	REGULAR DIESEL STOKEN, INSTALLATION DATE UNKNOWN. PRSENTLY IN SERVICE.	SOIL, GROUNDWATER IF SOIL IS CONTA- MINATED OR IF GROUNDWATER IS PRESENT IN THE EXCAVATION.	SOIL-1" INTO NATIVE SOIL WATER - AT STATIC WATER LEVEL IN EXCAVATION.  I sple at lach and of tank	

One soil sample must be collected for every 20 feet of piping that is removed. A ground water sample must be collected should any ground vater be present in the excavation.

C41-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-	Excavated/Stockpiled Soil
Stockpiled Soil Volume (Estimated)	Sampling Plan  Hochpile must be charactured pursuan to disposal melled

Stockpiled soil must be placed on bermed plastic and must be completely covered by plastic sheeting.

16. Chemical methods and associated detection limits to be used for analyzing samples

The Tri-Regional Board recommended minimum verification analyses and practical quantitation reporting limits should be followed. See attached Table 2.

Contaminant		·	•
Sought	EPA, DHS, or Other Sample Preparation Method Number	EPA, DHS, or Other Analysis Method Number	Method Detection Limit
TPH GASOLINE DICSEL	epa 5 <del>030-</del> 3550	EPA METHOD 8015	10 PPM (SOIL) 0.050 PPM (WATE
BTXE	SAME	EPA METHOD 8020	0.005 PPM(SOIL) 0.005 PPM WATER
		· ·.	

17. Submit Site Health and Safety Plan (See Instructions)

18. Submit Worker's Compensation Certificate copy

Name of Insurer SELF INSURED TO \$400,000. TRANSAMERICA

INSURANCE COMPANY THEREAFTER

- 19. Submit Plot Plan (See Instructions)
- 20. Enclose Deposit (See Instructions)
- 21. Report any leaks or contamination to this office within 5 days of discovery. The report shall be made on an Underground Storage Tank Unauthorized Leak/Contamination Site Report form. (see Instructions)
- 22. Submit a closure report to this office within 60 days of the tank removal. This report must contain all the information listed in item 22 of the instructions.

I declare that to the best of my knowledge and belief the statements and information provided above are correct and true.

I understand that information in addition to that provided above may be needed in order to obtain an approval from the Department of Environmental Health and that no work is to begin on this project until this plan is approved.

I understand that any changes in design, materials or equipment will void this plan if prior approval is not obtained.

I understand that all work performed during this project will be done in compliance with all applicable OSHA (Occupational Safety and Health Administration) requirements concerning personnel health and safety. I understand that site and worker safety are solely the responsibility of the property owner or his agent and that this responsibility is not shared nor assumed by the County of Alameda.

Once I have received my stamped, accepted closure plan, I will contact the project Hazardous Materials Specialist at least three working days in advance of site work to schedule the required inspections.

Signature of Contractor
Name (please type) DAVE ROBINSON
Signature Jan //e
Date
Signature of Site Owner or Operator
Name (please Type) ALLAN BOSCACCI
Signature Illa Doseaco
Date

CITY OF OAKLAND

Permit to Excavate and Install, Repair, Or Remove Inflammable Liquid Tanks, No. 20.58 Street 400 feet San Leandro Street the West side of

San Leandro" of Jank Street Owner American Brass & Iron Marsh 7825 San Leandro Policent John Fehringer

egrees to remove tents on discontinuence of 200 or when notified by the City Authorities.

**1** 

Dreinege Division Engineering Dept

**EXCAVATING PERMIT** 

Issued is accordance with Ord. No. 278 CMS, Sec. 6-1.04

square feet of digging or removal granted.

special deposit is hereby actnowledged.

CERTIFICATE OF TANK AND EQUIPMENT INSPECTION

\$

GENERAL DEPOSIT. The receipt of \$ 200

BUREAU OF PERMITS AND LICENSES.

\* 80.00 ck#16258 \_rec#666159

nspection Fee Paid 🕏

NO LICE

Before Covering Tanks, Above Certificate Must Be Signed. Sen ready for Inspection northy Res Prevention Survey. 273-3851 Received Gr 30hn

THIS PERMIT MUST BE LEFT ON THE WORK AS AUTHORITY THEREFOR

58.68.846.671

		BACKARA LICE	; {;						
	i j	UNDERGROUND STORAGE TANK UNAUTH	IORIZ	ED RELEAS	E (ĽEAK)	/ CONTAMI	NATION S	TE REPO	ORT.
	EME	REPORT BEEN FILED ? YES A NO		FOR LOCAL A	GENCY USE		rus Condid MOSIC		roma da la
		DRY DATE  5 2 9 9 9 2		DISTRIBUTION S	HOWN ON THE	NSTRUCTION SHE	ET ON THE BACK	PAGE OF THIS	FORM
	;;	NAME OF INDIVIOUAL FILING REPORT  JOHN; FEHRINGER	PHON (51	O) 632-34		NATURE /			ME TO NOTE OF
	8 E	REPRESENTING AND OWNER/OPERATOR REGIONAL LOCAL AGENCY OTHER	BOARD			33 a TRO	N PAHAN	Sandarin Dalla in the sandaring of	
		ADDRESS 7825 SAN LEANDRO STREE	3000	OAKLAND,	CALI	FORNIA 9	4621	A CHECK	The state of the s
SIBLE	<u>,</u>	AMERICAN BRASS & IRON	KNOWN	CONTACT PERS			STATE PHON	E L	71P
RESPON	PAR	ADDRESS 7825 SAN LEANDRO STREE		OAKLA	ND. C	LIFORNI	N 94621	0 ) 032- 1 aasaa	240/
-	;;	FACILITY NAME (IF APPLICABLE)  AMERICAN BRASS & IRON	······································	OPERATOR	CITY	- 1/2	STATE PHON	1, 14 kg, 1934 kg, 1	ZIP
	2	ADDRESS 7825 SAN LEANDRO STREET	• • •	CLIFF	<del></del>	····		0)632-	3467
	STED	CROSS STREET	· · · · · ·	OAKLAND,	CALLE	ORNIA 9	621 COUNTY		21 <b>P</b>
	<u>:</u>	TOTAL AVENUE  LOCAL AGENCY AGENCY NAME	, 1	验理长月色	: A .		自身精神		
FNT	SCIES	ALAMEDA COUNTY HEALTH CARE ST	vcs.	CONTACT PERS	on Arney	CHAN 44	PHON <b>51</b> (	271	-4320
2	¥	REGIONAL BOARD CALIF. REGNL. WATER (CONTROL BRD SAN FRAN. REGION	UAL	MR. ED	DY SO		PHON		· ·····
		REGULAR GASOLINE, UNLEADED GA	NAME ASOL	INE NE	A.()		QUANTIT	Y LOST (GALL	ONS)
SUBS	NA NA	DIESEL FUEL. 1-1-1 TRICHLOROE	AHT:	NE TENTO	1 113		dedict		UNKNOWN
-		DATE DISCOVERED HOW DISCOVERED	, INV	ENTORY CONTROL		BSURFACE MONITO	PRING .	NUISANCE C	UNKNOWN
		DATE DISCHARGE BEGAN	TAN	K REMOVAL (S)		HER CHECK ALI	THAT APPLY)	"判款機助性	, ,
	SVEHY	Manager 21 (4) (4) (4) (5) (4) (7) (7) (5) (4) (5) (6) (6) (6) (6) (6) (6) (6) (7)	<u>: #`1;</u>	REMOVE C	ONTENTS [	CLOSE TANK & F	IEMOVE	REPAIR PI	, , , .
$\vdash$	┈	SOURCE OF DISCHARGE	γ ,	REPLACE	4 20 1	CLOSE TANK & F	TELL IN PLACE	CHANGE P	ROCEDURE
OURCE	CAUSE	TANK LEAK UNKNOWN	[] o/	ERFILL (ME)	, Lan (Ru	PTURE/FAILURE	SPILL		
<b>!</b>	<u> 1.</u>	CHECK ONE ONLY		PRAOSION A THE		KNOWN A MA	OTHE	n spinetis	
H	7	CHECK ONE ONLY	ATER '	DRINKING W	ATER - (CHEC	(特別の人名)の K ONLY IF WATER	WELLS HAVE AC	TUALLY BEEN	AFFECTED)
CURRENT	STATUS	O ACTION TAKEN  PRELIMINARY SITE ASS  LEAK BEING CONFIRMED  PRELIMINARY SITE ASS  CASE CLOSED (CLEANU	essment Essment	UNDERWAY /	ITTED (A)	POSTICLE	N CHARACTERIZ ANUP MONITORI UNDERWAY	NO IN PROGR	E <b>89</b>
N		CHECK APPROPRIATE ACTION(S)  [SEE BACK FOR DETAILS]  EXCAVATE & DISH	OSE (ED)	REA	NOVE FREE PA	ODUCT (FP)	ENHANC	ED BIO DEGRA	ADATION (IT)
REMEDIAL	ACTO	CONTAINMENT BARRIER (CB)  CONTAINMENT BARRIER (CB)  CONTAINMENT BARRIER (CB)		N 12.58	IP & TREAT GE ATMENT AT H	ROUNDWATER (GT) DOKUP (HU)		SUPPLY (RS) IL (VS)	
	+	THIS UNAUTHORIZED RELEASE FOR	M Te	1888 2069		The section of the se	,	भून विकास	
COMMENTS			-1-6	3000 GAL	LON UN	LEADED G	NXS REM	. 41-5	FROM.   50
8	}	1-10000 GALLON DIESEL FUEL.		SEE TO SEE	-1-1 T	RICHLOPO	ETHANE.	and Val	
		\$'		$V_{1H} = O_{-O}$	<del></del>		·	2.474	HSC 05 (8/90)

Page 15 or

1. 1. 1. 1. 1.

\*

ACKNOWLEDGMENT  Bay Area Air Quality Management District acknowledges receipt of your Tank emoval/Contaminated Soil Excavation Notification Form received on 5/28/92 Blg.						
SPECIFIC LOCATION OF PROJECT UNDERGROUN  TANK REMOVAL	ONTAMINATED SOIL EXCAVATION					
SCHEDULED STARTUP DATE 6/3/92	SCHEDULED STARTUP DATE 6/3/92					
VAPORS REMOVED BY:	STOCKPILES WILL BE COVERED? YES NO					
[X] WATER WASH	ALTERNATIVE METHOD OF AERATION (DESCRIBE BELOW):					
[/] VAPOR FREEING (CO <sup>2</sup> ) [ ] VENTILATION	(MAY REQUIRE PERMIT)					
CONTRA	CTOR INFORMATION					
NAME AMERICAN BRASS IRON CONTACT DAVE ROBINSON  DRESS 7825 SAN LEANDRO ST PHONE (510) 632-3467  CITY, STATE, ZIP DAKLAND, CALIFORNIA 94621						
	TANT INFORMATION IF APPLICABLE)					
NAME LEVINE FRICKE	CONTACT JULIE SHARP					
ADDRESS 1900 POWELL ST., 12th FLC	DRPHONE (510) 652-4500					
CITY, STATE, ZIP EMERY VILLE, CALIFO	RNIA 9460B					
FOR OFFICE USE ONLY						
DATE RECEIVED FAX	BY(ipit.)					
DATE POSTMARKED 5/28/92	BY					
cc: INSPECTOR NO. 553	DATE 6/1/92 BY By					
HRDATE: CONTACT NAME	DATEBY					
AQMD N #	DATA ENTRY 6: 1:92 (init.)					
on the state of th	See reverse for instructions  A File R					

# STATE OF CALIFORNIA STATE WATER RESOURCES CONTROL BOARD

# UNDERGROUND STORAGE TANK PERMIT APPLICATION - FORM A



COMPLETE THIS FORM 1	FOR EACH FACILITY/SITE			
MARK ONLY 1 NEW PERMIT 3 RENEWAL PERMIT ONE ITEM 2 INTERIM PERMIT 4 AMENDED PERMIT	5 CHANGE OF INFORMATION 7 PERMANENTLY CLOSED SITE 6 TEMPORARY SITE CLOSURE			
I. FACILITY/SITE INFORMATION & ADDRESS - (MUST BE COMPLE	ETED)			
DBA OR FACILITY NAME	NAME OF OPERATOR			
AMERICAN BRASE & IRON FOUNDRY	ALLAN BOSCACCI NEAREST CROSS STREET   PARCEL   (OPTIONAL)			
7825 SAN LEANOZO STREET	NEAREST CROSS STREET PARCEL # (OPTIONAL)  HEGEN BERGER			
CITY NAME	STATE ZIP CODE SITE PHONE # WITH AREA CODE			
CAKLANO.	CA 94621 (S10)632-3467			
TO INDICATE CORPORATION INDIVIDUAL PARTNERSHIP L	OCAL-AGENCY COUNTY-AGENCY STATE-AGENCY FEDERAL-AGENCY STRICTS			
TYPE OF BUSINESS 1 GAS STATION 2 DISTRIBUTOR  3 FARM 4 PROCESSOR 5 OTHER	RESERVATION * OF TANKS AT SITE E, P. A. I. D. * (optional)			
	ORTRUST LANDS / CAD 021774559			
EMERGENCY CONTACT PERSON (PRIMARY)	EMERGENCY CONTACT PERSON (SECONDARY) - optional			
DAYS: NAME (LAST, FIRST)  PHONE # WITH AREA CODE  (SID 489-5312.	DAYS: NAME (LAST, FIRST)  [S10]			
NIGHTS: NAME (LAST, FIRST) PHONE # WITH AREA CODE	FEHRUNCER TOHN PHONE WITH ABEA CODE			
ROBINSON, DAUE (SIO) 489-5312	FEHZINGER, JOHN (SIG) PHONE * WITH AREA CODE			
II. PROPERTY OWNER INFORMATION - (MUST BE COMPLETED)				
MAME ALLAN BOSCACCI	CARE OF ADDRESS INFORMATION			
MAILING OR STREET ADDRESS	✓ box to Indicate INDIVIDUAL LOCAL-AGENCY STATE-AGENCY			
7825 SAN LEANORO GTREET	CORPORATION PARTNERSHIP COUNTY-AGENCY FEDERAL-AGENCY			
OAKLAND C	STATE ZIP CODE PHONE * WITH AREA CODE  CA CIAGO (510) 632 -346.7			
	CA 94621 (510)632-3467			
III. TANK OWNER INFORMATION - (MUST BE COMPLETED)	CARE OF ADDRESS INFORMATION			
AHAN ROSCACCI	CHAE OF AUDICESS INFORMATION			
MAILING OR STREET ADDRESS	✓ box to indicate INDIVIDUAL LOCAL-AGENCY STATE-AGENCY			
CITY NAME	CORPORATION FARTNERSHIP COUNTY-AGENCY FEDERAL-AGENCY  STATE ZIP CODE PHONE WITH AREA CODE			
DAKLAND	STATE ZIP CODE PHONE * WITH AREA CODE (510) 632-3467			
IV. BOARD OF EQUALIZATION UST STORAGE FEE ACCOUNT NUI				
TY (TK) HQ 4 4 -	•			
V. PETROLEUM UST FINANCIAL RESPONSIBILITY - (MUST BE CO	MPI FTFD) - IDENTIFY THE METHOD(S) LIGED			
✓ box to Indicate	GUARANTEE 3 INSURANCE 4 SURETY BOND			
[_] 5 LETTER OF CREDIT	EXEMPTION 99 OTHER			
	on and billing will be sent to the tank owner unless box I or II is checked.			
CHECK ONE BOX INDICATING WHICH ABOVE ADDRESS SHOULD BE USED FOR LEGAL NOT	IFICATIONS AND BILLING: I. III. III.			
THIS FORM HAS BEEN COMPLETED UNDER PENALTY OF PERJURY, A	ND TO THE BEST OF MY KNOWLEDGE, IS TRUE AND CORRECT			
	CANT'S TITLE DATE MONTH/DAY/YEAR			
	1.ENG. MANAGER 5/28/92			
LOCAL AGENCY USE ONLY				
COUNTY # JURISDICTION	FACILITY #			
LOCATION CODE · OPTIONAL CENSUS TRACT • · OPTIONAL	SUPVISOR - DISTRICT CODE - OPTIONAL			
ı l	•			

#### STATE OF CALIFORNIA

#### STATE WATER RESOURCES CONTROL BOARD

# **UNDERGROUND STORAGE TANK PERMIT APPLICATION - FORM B**



# COMPLETE A SEPARATE FORM FOR EACH TANK SYSTEM.

MARK ONLY 1 NEW PERMIT 3 RENEWAL PERMIT 5 CHANGE OF INFORMATION 7 PERMANENTLY CLOSED ON SITE ONE ITEM 2 INTERIM PERMIT 4 AMENDED PERMIT 6 TEMPORARY TANK CLOSURE 8 TANK REMOVED
DBA OR FACILITY NAME WHERE TANK IS INSTALLED:
I. TANK DESCRIPTION COMPLETE ALL ITEMS - SPECIFY IF UNKNOWN
A. OWNER'S TANK I.D.#  B. MANUFACTURED BY: N/CA
C. DATE INSTALLED (MO/DAY/YEAR) 1982 (ESU.) D. TANK CAPACITY IN GALLONS: 10,000
II. TANK CONTENTS IF A-1 IS MARKED, COMPLETE ITEM C.
A. I MOTOR VEHICLE FUEL 4 OIL 8. C. 14 REGULAR UNLEADED 4 GASAHOL 7 METHANOL UNLEADED 5 JET FUEL 96 AVIATION GAS 2 PETROLEUM 95 UNKNOWN 2 WASTE 2 LEADED 99 OTHER (DESCRIBE IN ITEM D. BELOW)
D. IF (A.1) IS NOT MARKED, ENTER NAME OF SUBSTANCE STORED  C. A. S. #:
III. TANK CONSTRUCTION MARK ONE ITEM ONLY IN BOXES A. B. AND C. AND ALL THAT APPLIES IN BOX D
A. TYPE OF 1 DOUBLE WALL SINGLE WALL WITH EXTERIOR LINER 95 UNKNOWN  SYSTEM 2 SINGLE WALL 4 SECONDARY CONTAINMENT (VAULTED TANK) 99 OTHER
B. TANK
C. INTERIOR LINING B GLASS LINING B UNLINED B LINING MATERIAL COMPATIBLE WITH 100% METHANOL?  YES NO
D. CORROSION 1 POLYETHYLENE WRAP 2 COATING 3 VINYL WRAP 4 FIBERGLASS REINFORCED PLASTIC PROTECTION 5 CATHODIC PROTECTION 91 NONE 50 UNKNOWN 99 DTHER
IV. PIPING INFORMATION CIRCLE A IF ABOVE GROUND OR U IF UNDERGROUND, BOTH IF APPLICABLE
A. SYSTEM TYPE (AU) 1 SUCTION A U 2 PREBSURE A U 3 GRAVITY A U 99 OTHER
B. CONSTRUCTION (AU 1 SINGLE WALL AU 2 DOUBLE WALL AU 3 LINED TRENCH AU 95 UNKNOWN AU 99 OTHER
C. MATERIAL AND CORROSION A U 8 ALUMINUM A U 8 CONCRETE A U 7 STEEL W/ COATING A U 8 100% METHANOL COMPATIBLE W/FRP PROTECTION A U 9 GALVANIZED STEEL A U 10 CATHODIC PROTECTION A U 90 OTHER
D. LEAK DETECTION 1 AUTOMATIC LINE LEAK DETECTOR 2 LINE TIGHTNESS TESTING 3 INTERSTITIAL -99 OTHER VISUAL
V. TANK LEAK DETECTION
VISUAL CHECK 2 INVENTORY RECONCILIATION 3 VAPOR MONITORING 4 AUTOMATIC TANK GAUGING 5 GROUND WATER MONITORING 5 TANK TESTING 7 INTERSTITIAL MONITORING 91 NONE 95 UNKNOWN 99 OTHER
VI. TANK CLOSURE INFORMATION
1. ESTIMATED DATE LAST USED (MO/DAY/YR)  2. ESTIMATED QUANTITY OF SUBSTANCE REMAINING O GALLONS  3. WAS TANK FILLED WITH INERT MATERIAL?  NO [X]
THIS FORM HAS BEEN COMPLETED UNDER PENALTY OF PERJURY, AND TO THE BEST OF MY KNOWLEDGE, IS TRUE AND CORRECT  APPLICANTS NAME  [PRINTED & BIGNATURE] DAVE ROBINSON  DATE  5/28/92
LOCAL AGENCY USE ONLY THE STATE I.D. NUMBER IS COMPOSED OF THE FOUR NUMBERS BELOW
STATE I.D.#  COUNTY # JURISDICTION # FACILITY # TANK #
PERMIT NUMBER PERMIT APPROVED BY/DATE PERMIT EXPIRATION DATE

# AMERICAN BRASS & IRON FOUNDRY

SITE HEALTH AND SAFETY PLAN

MAY 1, 1992

SITE HEALTH AND SAFETY PLAN FOR (company name)

AMERICAN	BRASS	AND	IRON	FOUNDRY

SITE 10 000 GAL DIESEL TANK PROJECT NUMBER -
ORIGINAL SITE HEALTH & SAFETY PLAN: Yes (X) No ( ) REVISION #
PLAN PREPARED BY JOHN FEHRINGER DATE 5/20/92
PLAN APPROVED BY DATE
1. KEY PERSONNEL AND RESPONSIBILITIES
PROJECT MANAGER DAVE ROBINSON PHONE #610 632-3467
HEALTH AND SAFETY RESPONSIBILITIES ASSESS POTENTIAL
HEALTH AND SAFETY HAZARDS AT SITE, MODIFY HSP IF
NECESSARY, REQUIRE MEDICAL ATTENTION, IF NECESSARY,
DENY UN AUTHORIZED ENTRY
SITE HEALTH AND SAFETY OFFICER JOHN FEHRINGER
PHONE # (570) 632-3467
HEALTH AND SAFETY RESPONSIBILITIES IN FORM SITE WORKERS OF
EXPECTED HAZARDS, ORDER SITE EVACUATION OR SHUT
DOWN, IF NECESSARY, MODIFY HSP, IF NECESSARY, REQUIRE
MEDICAL ATTENTION, IF NECESSARY, DENY UNAUTHORIZED ENTRY
FIELD TEAM MEMBERS JULIE SH'ARP, EWALD SCHMIDT
VICTOR SEVILLA, EDVARDO GONZALEZ

	AMEDA COUNTY HEALTH CARE SERVICES
CI	TY OF GAKLAND FIRE DEPARTMENT
ЈОВ	HAZARD ANALYSIS
	CHEMICAL HAZARDS (INCLUDING HAZARDOUS MATERIALS PRESENT
	ON SITE) POSSIBLE SOIL CONTAMUNATION WITH
	DIESEL - BENZENE, TOLUENE, ETHYLBENZENE
	XYLENE
	CHARACTERISTICS OF MATERIALS LISTED ABOVE
	MATERIAL #1 DIESEL FUEL
	CORROSIVE ( ) IGNITABLE (火) TOXIC (↓)
	REACTIVE ( ) VOLATILE ( ) RADIOACTIVE ( )
	BIOLOGICAL AGENT ( ) GASOLINE VAPOR ( )
	EXPOSURE ROUTES: INHALATION (X) INGESTION (X)
	EYE CONTACT (X) SKIN AND MUCOUS MEMBRANE (X)
	MATERIAL #2 BENZENE
	CORROSIVE ( ) IGNITABLE ( ) TOXIC (*)
	REACTIVE ( ) VOLATILE (X) RADIOACTIVE ( )
	BIOLOGICAL AGENT ( ) GASOLINE VAPOR ( )
	EXPOSURE ROUTES: INHALATION (X) INGESTION ()
	THORDITON ( )

MATERIAL #3 TOWENE
CORROSIVE ( ) IGNITABLE ( ) TOXIC (X)
REACTIVE ( ) VOLATILE (X) RADIOACTIVE ( )
BIOLOGICAL AGENT ( ) GASOLINE VAPOR ( )
EXPOSURE ROUTES: INHALATION ( $X$ ) INGESTION ()
EYE CONTACT ( ) SKIN AND MUCOUS MEMBRANE (X)
MATERIAL #4 ETHYLTSEN-ZENE
CORROSIVE ( ) IGNITABLE ( ) TOXIC ()
REACTIVE ( ) VOLATILE (X) RADIOACTIVE ( )
BIOLOGICAL AGENT ( ) GASOLINE VAPOR ( )
EXPOSURE ROUTES: INHALATION (X) INGESTION ()
EYE CONTACT ( ) SKIN AND MUCOUS MEMBRANE ( )
MATERIAL #5 XYLENE
CORROSIVE ( ) IGNITABLE ( ) TOXIC (X)
REACTIVE ( ) VOLATILE ( )
BIOLOGICAL AGENT ( ) GASOLINE VAPOR (人)
EXPOSURE ROUTES: INHALATION (X) INGESTION ()
EYE CONTACT (X) SKIN AND MUCOUS MEMBRANE ( )
PHYSICAL AND OTHER HAZARDS

HAZARDS OF SPECIFIC TASKS (e. g. cave-ins, explosions, traffic, back injuries)

TASK #1 EXCAUATE SOIL
HAZARDS CAUE -IN, INJURY TO SITE WORKERS
PRECAUTIONARY MEASURES NOTSODY ALLOWED IN PIT, MACHINERY A SAFE DISTANCE FROM PIT, CAUTION OPERATING MACHINERY AROUND SITE WORK
TASK #2 TRANSFERRING EXCAUATED SOIL
HAZARDS COLLISION WITH SITE WORKERS, COLLISION WITH SURROUNDING TRAFFIC
PRECAUTIONARY MEASURES OPERATE MACHINERY  SATELY, SITE WELL-MARKED WITH  CAUTION TAYE, E1C.
TASK #3 BACK TILLING
HAZARDS SAME AS TASKS LAND Z
PRECAUTIONARY MEASURES SAME AS TASKS LAND Z

TASK #4	
HAZARDS	
	•
PRECAUTIONARY MEASURES	
TASK #5	
HAZARDS	
PRECAUTIONARY MEASURES	

# 3. WORK REQUIREMENTS

MONITORING PLAN (PID for VOC's, CGA, etc.)

PHOTOIONIZATION DETECTOR TO DETECT AMBIENT

AIR CONCENTRATIONS OF VOLATILE ORGANIC

COMPOUNDS, COMBUSTIBLE GAS ANALYZER TO

DETERMINE CONCENTRATION OF COMBUSTIBLE GASES

AND OXYGEN IN TANK PRIOR TO REMOVAL

rubber gloves, respirators for organic vapors, steel toed safety shoes, hearing protection, polyethylene-coated coveralls, etc.)
HARD HATS, SAFETY GLASSES, RESPIRATORS FOR
ORGANIC VAPORS, RUBBER GLOVES, HEARING
PROTECTION AS MEEDED
ACTION LEVELS (VOC,s, benzene, LEL, etc.)
IF AMBIENT AIR CONCENTRATION OF YOU'S IN
BREATHING POPLE > ZSPPM, WORK SHOULD TEMP-
ORAPILY GIOP VHTIL VOC'S KZEPPM, COMBUSTIBLE
GASES AS PER FIRE DEPART MENT REQUIREMENTS
SIGNS, etc.)  10 POUND, ZO ISC RATED FIRE EXTINGUISHER  ON SITE, NO SMOKING SIGNS
NOISE (e. g. earplugs around jack hammering, heavy machinery, etc.)
ENRPLUES AROUND UNCK HAMMERING
ETE WASH III CORE ROOM

WORK AREA DEFINITION

METHOD OF DESIGNATION (fencing, caution tape, signs, security measures, etc.)

PIT, PLANT SECURITY

ENTRY PROCEDURES (requirements for visitors, including entry permission, safety equipment)

DESIGNATED TEAM MEMBER ON SITE AT ALL TIMES, PERMISSION REQUIRED FOR VISITOR EMIRY

DECONTAMINATION PROCEDURES (PPE, tools, equipment)

CONTAMINATED PERSONAL PROTECTIVE EQUIPMENT,
TROWS, EQUIPMENT SHOULD BE CLEANED OR
DISPOSED OF ACCORDING TO DISPOSAL CAWS.

#### 4. EMERGENCY PROCEDURES

### GENERAL INJURIES

Step 1: Administer first aid, if appropriate. Step 2: Obtain outside emergency assistance, if

appropriate.

Step 3: Notify SSO and Project Manager.

#### TREATMENTS

FIRE: Use fire extinguisher. Activate available alarms if necessary. Call fire department if necessary.

SKIN EXPOSURE: Skin exposure to many toxic materials can often be minimized by washing the affected area with soap and water. Call an ambulance if necessary.

EYE EXPOSURE: Flush eyes with water. Call an ambulance if necessary.

CHEMICAL SPILL: Call fire department and National Response Center for Toxic Chemical and Oil Spills.

INHALATION: Move victim to fresh air. Call ambulance if necessary.

SWALLOWING: Call ambulance service if necessary. Call Poison Control Center for information.

# EMERGENCY PHONE NUMBERS

Ambulance
Fire Department 91(
Police Department 911
Hospital (name, address, emergency and other phone)
HUMANA HOSPITAL (510) 357-8450 (EMERGENCY)
13855 EAST 14th STREET (510) 357-6500
54N LEANDRO, CA 94587
National Response Center (800) 424-8802
CHEMTREC(801) 424 - 9300
Poison Control Center (800)523-2222
California Office of Emergency Services (200) 852-7550
Regional Water Quality Control Board (805) 549 - 3147

### 5. TRAINING PROGRAM

Prior to commencing work activities, a safety briefing will be held to discuss the contents of this health and safety plan as well as any other safety items.

Training also includes appropriate requirements indicated by 29 CFR 1910.120 (e).

#### 6. MEDICAL MONITORING

Appropriate medical monitoring is required as designated by 29 CFR 1910.120 (f).



# APPENDIX B

A. Fire Inspector Notes
B. Levine\*Fricke Field Notes
C. Disposal Manifest

Jan Standard	CITY OF OAKLAND REPORT OF FIRE INSPECTION ADDRESS 7825 San Landa							ENGINE CO.		
	NAME GENERAL INSPECTION		PERMIT OTHER		HAZARD NOTED		HAZA			
	NOTICE LEF		1st NOTICE		2nd NOTICE		ABAT	ED U		
Ì	DATE		Vio	LATION			O.F.C.	CONTACTED		
	6-392 William Tans Renew					~2~	_			
		10,000	s <u>A.</u>	lel	220	_ /	89			
1		Haulas	1 by	4/44	k #	300	29	3 2		
1		1)0. Hol	es voto	e in	Tark		. ,	ノ		
4										
į	A REINSPEC	TION WILL BE MA	DE WITHIN		DAYS.					
4	338-5 (Rev. 5	-77)		PECTOR B	BUREAU - PHON	IE 273-38	51	208		
ŧ								-		



# **LEVINE-FRICKE**

CONSULTING FAGINEERS AND HYDROGEOLOGISTS

DRAFT

September 25, 1991

LF 2408

Mr. Barney Chan Hazardous Materials Specialist Department of Environmental Health Alameda County Health Care Services 80 Swan Way, Room 200 Oakland, California 94621

Subject: Filing of Unauthorized Storage Tank Release Report Underground Tank Closure
American Brass & Iron Facility
7825 San Leandro Avenue

Oakland, California 94621

Dear Barney:

This letter documents our recent telephone conversation concerning filing of an Unauthorized Storage Tank Release Report for the subject site.

During our conversation on September 5, 1991, you indicated that American Brass & Iron (AB&I) does not need to file a report at this time, even though some gasoline-affected soil and ground water were encountered when the former 8,000-gallon gasoline storage tank was removed from the site. You stated that AB&I should file a report upon completion of its current underground tank closure project, which includes removal of four underground tanks. As I stated in our conversation, AB&I intends to complete this project by November 1991.

Because the Alameda County Department of Environmental Health is the lead implementing agency for the State of California's Underground Storage Tank Program, we are recommending to AB&I that they report the tank leak in accordance with our agreement, as stated above.

If you have any questions, please contact me. Thank you for your cooperation in working with us on this matter.


Sincerely,

John Sturman Senior Project Geotechnical Engineer

Tellor Project Geotechnical Engineer

cc: Mr. John Fehringer, American Brass & Iron 1900 Powell Street 12th Floor Emeryville California 94608 (415) 652-4500

FAX (415) 652-2246



**EXPLANATION** 

- Soil sample location (depth in feet is last number)
- **X** Excavation water sample location

0 5 10 FEET

Figure 2: PLAN SHOWING FORMER TANK AND SOIL SAMPLE LOCATIONS

LEVINE • FRICKE

PAGE	OF
DATE	6-3-92

REPORT #  PROJECT: 2408.01  WEATHER  DWNER: ABI	HH forms on Fri
SITE CONDITION  CONTRACTOR: -ABI TEMPERATURE  - Copy Pictures for DANC - Dava will give me copy of country of 1  Fre Pro Brandle - Marlon - Cakling  Country - Borney Chyn  WORK FORCE  SUPER- WORKERS	TOPF  Hith forms on Fri  I FI) . Inspector
SITE CONDITION  CONTRACTOR: -ABI TEMPERATURE  - Copy Pictures for DANC - Dava will give me copy of country of 1  Fre Pro Brandle - Marlon - Cakling  Country - Borney Chyn  WORK FORCE  SUPER- WORKERS	TOPF  Hith forms on Fri  I FI) . Inspector
CONTRACTOR: -ABI TEMPERATURE  - Copy Pictures for DANR - Dava will give me copy of country of 1  Fre Pro Brandle - Marlon - Oakling  Country - Borney Chyn  WORK FORCE  SUPER- WORKERS	HH form, on Fri 1 F1). Inspector
Topy Pictures for DANE - Dave will give me copy of rounty of 1  Fre Pour Brandle - Marlon - Oakline  Canty - Borney Chyn  WORK FORCE  SUPER- WORKFORCE	HH forms on Fri 1 F1). Inspector
Fre Por Brandle, - Marlon - Oakling  Conty - Borney Chyn  WORK FORCE  SUPER- WORKERS	FD. Inspector
WORK FORCE SUPER- WORKERS	REMARKS
SUPER- WORKERS	REMARKS
	REMARKS
EQUIPMENT	1111
Lase 580E backthe	HAH Lowboy
Crang - Bucyn Erie (magnet also to scrap	
Desire 344E Load /	
ACTIVITIES 8:30 Arrived on site; tank is unrove	red - water in pit look, potroleun-al
ABI purging water from pit - putting in	55-99/100 diun, (3)
Piping all removed	
Tank recently (last year) pressure tested	
ou Stockpite of recently exposably material has	15-50 ppmon PID
- Disposion reportedly removed point to 1. F	bidence
11.70 Fire of County on site - Listing tout.	
Oily product (Black) in East End of	, ,
No sign of corrosion / pitting on tank (in	
condition; proceeded to load onto H+1+ low	/
11:35 Purging G-W from fant exception into	ī
- Began over excavation in E area; soil is black!	green with PID 20-40ppm.
- Dave requested to take soil + 9-w samples	
has had time to over owner affocted soil . Co	schty Said oft. Stockpite
will be sampled then for I told Dan that 1	7 night be good to either
use a dill rigotor grab some samples nour - recove	they will not need to
dean up Site to MD and that a Mondoring We	11 is likely any way, also 3
copies: That any soils he exacates he will need to disance.	
bioschebation of soil and that he wants to get to	of. Vacc said he will try


LEVINE+FRICKE DAILY CONSTRUCTION M TH F S REPORT # DAY PROJECT: 2408.01 WEATHER \_ OWNER: SITE CONDITIONS CONTRACTOR: TEMPERATURE VISITORS WORK FORCE SUPER-WORKERS REMARKS VISORS EQUIPMENT ACTIVITIES sampling (6-w + soil). (ounty + Dave +I do not know what site clean up is for liesel. I also martined that the given backfill sand could be a native color-but may also be representative of petroleum. Pitwill be over exequated in the N+S directors in East End. Soil not be Further excacated in Edirection. There is also much spots of green sand in Western end of pit - I will have them dig up before I leave site. .. Eastern and has black/yeen disbred soil, Wart and has slight gren sand hereath tank a Eastern end has black product (01/4) Worker and has slight sheen 20m - Scooled in Wast wall of exception - no PID + smelly/looks clear - also scopped gron backfill sand in bottomof Worken excellenter - no slight (0-4ppm) PID but smell of dicre ! I cocommended that Dave excelak the grain sand now because if will be monitoring no range in requiry it (as he inlanded to do) of trying to overexionak walls, Dave agreed.

Planto return to Site (in Gunty also) - Antiday bace or John Will leans

me a message on time frame tomorrow SIGNI

2:05 Left She Tank gone.

PAGE Z OF A



REPORT #	CTION	DAY	M T	W T	H F	s
PROJECT: 2408.01			Sunay			
ANT		ATHERE CONDITIONS	Suno	e/baci	kf. 11	
contractor: ABC		MPERATURE				
VISITORS	, 					
WORK FORCE		<u></u>			<del></del>	
	SUPER- VISORS	WORKERS		REMARKS	9	··· <u>·</u>
						<del></del>
**************************************				· · · · · · · · · · · · · · · · · · ·		<u></u> .
EQUIPMENT	<del></del>	<u> </u>			······································	<del></del>
Buck hoe						
					· · · · · · · · · · · · · · · · · · ·	
ACTIVITIES 7.27 Arrived On	-site. John F	corings +	are write	ig fon 1	Dave to	o ch
Status, Dane sind county does 8:30 finished gran 6-te	Apr Man to b	Pat 10-10	et the at	time c	7/s	MINH
visible product in execu	' 1		. 7			
WALL SAMPLES,						
1 at 9' in W/ liftery	Silly Clag	- NOPIL ]	at slig	ht di	escloc	ر مل
	<u> </u>	- No PI)				
20 2 at 9' 1.	17		1000	Ja ∕		
3 ot 8.179	(,	- 100 PID				
3 at 8.79 " 4 at 8 fbsq "		1 - No Di				
5 at 8.79"  4 at 8 fbsq " 5 at 8.5 (bg "	(					
3 at 8.5/9"  4 at 8 fbsq "		"-Noh		6	· Back	heo
5 at 8,59 "  S at 8,50 p "  6 at 9/9.5 fby "		" - No h	dorod	(B#	'- Back 1-Hend	
Sat 8.79"  4 at 8 fbsq "  5 at 8.5 Mbg "  6 at 9/9.5 fby "  9.45 Finished Sumpling	; ABI bego	11 - No Di	dorod	(BH	1-14 and	Auger
Sat 8.199  4 at 8 fbsq "  5 at 8.5 fbg "  6 at 9/9.5 fbg "  9.45 finished sumpling  ~200 cy stockpiled on rong	; ABI bego	11 - No Di	dorod	(BH	1-14 and	Auger
Sat 8.79"  4 at 8 fbsq "  5 at 8.5 Mbg "  6 at 9/9.5 fby "  9.45 finished sumpling	, ABI bego rte w/roof-	- to be an	d or od	(BH HA	1-14 and	Auger


L	E۷	/11	٧F	.F	PI	C	ĸ	F


PAGE	2 of 5
DATE	6-5-92

DAILY CONS	STRUCTION	ſ	S M T	W TH F S
		DAY		X
PROJECT: 408.0		WEATHER		
OWNER:		SITE CONDITIO	ons	
CONTRACTOR:				
VISITORS				•
WORK FORCE	<del></del>		· · · · · · · · · · · · · · · · · · ·	
	SUP VISC			REMARKS
EQUIPMENT		<u> </u>		
	<del>// </del>			
			······································	
ACTIVITIES - Backfille All san ple	I w/ stockpiled soil	from letore (VI	K Sumples) - Oc	que knew resultiwoen
All sample	collected in N	ation detro	gray Sil	Ly clay
ounts mé	W [] * · ·	(	exc.mill	wull depth bsg
1 0	EWI-E-9 (T	PHB/BIX DE TON	EWIL	-9
2	1EW2-N-9 (TI	PHU/BINE		
	EW3-N-8.5	(7181)		•
		DHIPRIXE)		
5	EW5-5-8,5/1	DH DATE		
		PHO/BIXE)		
		H D/BJKE	· · · · · · · · · · · · · · · · · · ·	
45 43/				
45-1-31	<u>v</u>			
2 5 13 5	orio 6-kg	x 9.5-10'	i. Fead	(bsy.)
	0.19 0.0	at 9- 1	n Wend	<del>- 038//</del>
2 1 1 2		<u> </u>	y WERO	<del> </del>
	TONAY	101 in F and	<del></del>	
		10 in End		**************************************

COPIES: 11:45 took simples to Quantage

SIGNED:





20. Facility Owner or Operator Certification of receipt of hazardous materials covered by this manifest except as noted in item 19, Printed/Typed Name

Signature

DO NOT WRITE BELOW THIS LINE.

TSDF SENDS THIS COPY TO GENERATOR WITHIN 30 DAYS,

**CUSTOMER NUMBER** PURCHASE ORDER NO. DATE DELIVERY NUMBER 210293 BY ACCEPTING THIS ORDER, CUSTOMER AGREES TO ALL OF THE TERMS AND CONDITIONS SET FORTH HEREIN, INCLUDING THOSE PRINTED ON THE REVERSE SIDE. **Abel Carbonic** ACCEPTED-BY: SHIPPED TO 20 SOLID 22 SLICES 21 HALF 29 WET ICE . 24 AIRPORT A STATE OF THE STA UNIT The real of the state of the DESCRIPTION CODE DRY ICE ORM-A UN1845

# ALAMEDA COUNTY, DEPARTMENT OF ENVIRONMENTAL HEALTH

80 Swan Way, #200 Oakland, CA 94621 (415) 271-4320

# **Hazardous Materials Division Inspection Form**

Site ID# Site Name	AB+I Today's Date 6393
Site Address	81.5 Sah Ipadeo St EPA ID#
City	Zlp <u>94 6 ? (</u> Phone
MAX Amt. Stored > 500lbs/55g/200c Hazardous Waste generated per mont	II. Business Plans, Acute Hazardous Materials III. Underground Tanks
The marked items represent violation	s of the Calif. Administration Code (CAC) or the Health & Safety Code (HS&C)
1. Waste iD	Comments:
6. Records 65492 7. Correct 66484 8. Copy sent 66492 9. Exception 66484 10. Copies Rec'd 66492	Mader Box de OFD rome +
11. freatment	7 Jerhanger & D Polymon of ABIT poly
	Tala ta trapped of Considerates anopped
- 19. Prepared 67140 20. Name Ust 67141 21. Copies 67141 22. Emg. Coord. Trng. 67144	in the description of the transport
	More 3x daying of cit water company
B TRANSPORTER (Title 22) 32, Applic./Insurance	prior to sampling a sample of
	- Balance
	hinson Barney Chan
Title:	Inspector: <u>Darney Chan</u> Signature: <u>Sanna Chan</u>

# ALAMEDA COUNTY, DEPARTMENT OF ENVIRONMENTAL HEALTH

80 Swan Way, #200 Oakland, CA 94621 (415) 271-4320

# Hazardous Materials Division Inspection Form

Site ID#	Site Nam	ө	AB+I	Today's Date	6,392
Site Address		7825	Son lear Oro St	EPA ID#	1 ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) (
City			Zip <b>94</b>	Phone	i de esta politica
MAX Amt. Stored > 5001t Hazardous Waste genera			Inspection Categories:  1. Haz. Mat/Waste GEN  11. Business Plans, Acute  11. Underground Tanks	IERATOR/TRANSPORTER Hazardous Materials	
The marked Items repres	ent violation	s of the Call	f. Administration Code (CAC) or th	ne Health & Safety Code	(HS&C)
A GENERATOR (Title 22)  1. Waste ID 2. EPA ID	* 66471 66472	Commen	its;		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
3. > 90 days 4. Label dates 5. Blennial	66508 66508 66493	Petr	. Cppwx 10' × 30'	X 13 dep	
6. Records 7. Correct 8. Copy sent 9. Exception 10. Copies Rec'd	65492 66484 66492 66484 66492	CNIA		on order of	n. navara
11, Treatment 12, On-site Disp. (H.S.&C.) 13, Ex Haz, Waste	66371 " 26189.5 66570	1B+T	will over co cause	le the past	and to
14. Communications 15. Alsie Space 16. Local Authority 17. Maintenance 18. Training	67121 67124 67126 67120 67105	Cirgo.	ent cloon prior	orans of Damp delerment of	rea day
19. Prepared 20. Name List 21. Copies 22. Emg. Coord. Ting.	67140 67141 67141 67144	marile	e ( port and GW)	10.10 he taken	after On
23. Condition 24. Compatibility 25. Maintenance 26. trapection 27. Buffer Zone 28. Tank inspection 29. Containment 30. Safe Storage 31. Freeboard	67241 67242 67243 67244 67246 67259 67245 67261 67257	Cy, ST	s approx-4 feet	Acopdr.	
TRANSPORTER (Title 22)	66428 66448 66465				
35. Vehicles 36. EPA ID ≠± 37. Correct 38. HW Delivery 39. Records	66465 66531 66541 66543 66544				
40. Name/ Covers 41, Recyclobles	66545 66800				
Contact:	Palm	105	and the same and the same are then	15 C1	
Title:			Inspector:	B. Char	
Signature: 1			Signature	E.Cla	



# APPENDIX C

A. Laboratory Analysis

<u>ಇಗಿಗಳಿಸಲಿತಲಾಶ</u>ಗತ

476 PØ2

DRAFT

## FORMERLY MED-TOX

ع ⊬،ځد⊍ټحد∪باط

PAGE 1 OF 10

LEVINE-FRICKE 1900 POWELL STREET 12TH FLOOR

EMERYVILLE, CA 94608 ATTN: MICHAEL STOLL

CLIENT PROJ. ID: 2408.01 C.O.C. SERIAL NO: 10826

REPORT DATE: 06/17/92

DATE SAMPLED: 06/05/92

DATE RECEIVED: 06/05/92

QUANTEQ JOB NO: 9206070

ANALYSIS OF: WATER AND SOIL SAMPLES

Client Sample Id.	Quanteq Lab Id.	Extractable Hydrocarbons as Diesel (mg/kg)	Extractable Hydrocarbons as Diesel (mg/L)
DEWI-E-9 DEW2-N-9 DEW3-N-8.5 DEW4-W-8 DEW5-S-8.5 DEW6-S-9 D-GROUNDWATER	01A 02A 03A 04A 05A 06A 07A	ND ND ND ND ND 2	6.8
Detection Lim	it	1	0.05
Method: Instrument:	c	3550 GCFID	3520 GCFID
Date Extracte Date Analyzed		06/15/92 06/15/92	06/12/92 06/16/92

Andrew Bradeen, Manager Organic Laboratory

2163363636364

476 PØ3

PAGE 2 OF

# LEVINE-FRICKE

CLIENT ID: DEW1-E-9 CLIENT PROJ. ID: 2408.01 DATE SAMPLED: 06/05/92 DATE RECEIVED: 06/05/92 REPORT DATE: 06/16/92

QUANTEQ LAB NO: 9206070-01A QUANTEQ JOB NO: 9206070 DATE ANALYZED: 06/08/92

INSTRUMENT: H

BTEX (SOIL MATRIX) METHOD: EPA 8020 (5030)

COMPOUND	CAS #	CONCENTRATION (ug/kg)	DETECTION LIMIT (ug/kg)
Benzene	71-43-2	GN	5
Toluene	108-88-3	ND	5
Ethylbenzene	100-41-4	ND	5
Xylenes, Total	1330-20-7	ND	5

JUN 17 '92 09:53

476 P04

PAGE 3 OF

# LEVINE-FRICKE

CLIENT ID: DEW2-N-9 CLIENT PROJ. ID: 2408.01 DATE SAMPLED: 06/05/92 DATE RECEIVED: 06/05/92 REPORT DATE: 06/16/92 QUANTEQ LAB NO: 9206070-02A QUANTEQ JOB NO: 9206070 DATE ANALYZED: 06/08/92

INSTRUMENT: H

BTEX (SOIL MATRIX) METHOD: EPA 8020 (5030)

COMPOUND	CAS #	CONCENTRATION (ug/kg)	DETECTION LIMIT (ug/kg)		
Benzene	71-43-2	ND	5		
Toluene	108-88-3	ND	5		
Ethylbenzene	100-41-4	ND	5		
Xylenes, Total	1330-20-7	ND	5		

JUN 17 '92 09:53

QUANTEQ

476 P05

PAGE 4 OF

## LEVINE-FRICKE

CLIENT ID: DEW4-W-8 CLIENT PROJ. ID: 2408.01 DATE SAMPLED: 06/05/92 DATE RECEIVED: 06/05/92 REPORT DATE: 06/16/92 QUANTEQ LAB NO: 9206070-04A QUANTEQ JOB NO: 9206070 DATE ANALYZED: 06/08/92 INSTRUMENT: H

BTEX (SOIL MATRIX) METHOD: EPA 8020 (5030)

COMPOUND	CAS #	CONCENTRATION (ug/kg)	DETECTION LIMIT (ug/kg)	
Benzene	71-43-2	ND	5	
Toluene	108-88-3	ND	5	
Ethy1benzene	100-41-4	ND	5	
Xylenes, Total	1330-20-7	ND	5	

JUN 17 '92 09:54

PAGE 5 OF

# LEVINE-FRICKE

CLIENT ID: DEW6-S-9 CLIENT PROJ. ID: 2408.01 DATE SAMPLED: 06/05/92 DATE RECEIVED: 06/05/92 REPORT DATE: 06/16/92

QUANTEQ LAB NO: 9206070-06A QUANTEQ JOB NO: 9206070 DATE ANALYZED: 06/08/92 INSTRUMENT: H

BTEX (SOIL MATRIX) METHOD: EPA 8020 (5030)

COMPOUND	CAS #	CONCENTRATION (ug/kg)	DETECTION LIMIT (ug/kg)		
Benzene	71-43-2	ND .	5		
Toluene	108-88-3	ND	5		
Ethylbenzene	100-41-4	ND	5		
Xylenes, Total	1330-20-7	ND	5		

JUN 17 '92 09:54

476 PØ7

PAGE 6 OF

# LEVINE-FRICKE

CLIENT ID: D-GROUNDWATER CLIENT PROJ. ID: 2408.01 DATE SAMPLED: 06/05/92 DATE RECEIVED: 06/05/92 REPORT DATE: 06/16/92 QUANTEQ LAB NO: 9206070-07C QUANTEQ JOB NO: 9206070 DATE ANALYZED: 06/08/92

INSTRUMENT: G

BTEX (WATER MATRIX) METHOD: EPA 8020 (5030)

COMPOUND	CAS #	CONCENTRATION (ug/L)	DETECTION LIMIT (ug/L)		
Benzene	71-43-2	ND	0.3		
Toluene	108-88-3	ND	0.3		
Ethylbenzene	100-41-4	ND	0.3		
Xylenes, Total	1330-20-7	ND	1		

R-3,5-1 R-1,5-A CHAIN OF CUSTODY / ANALYSES REQUEST FORM

9206070

Project No.: 2468.01			Project Location: Oakland, CA			Date	6-5-	92	Serial No.: 10826							
Project Name	e: A	no ca	Brass + Iro	3	Projec	t Lo	catio	n: C	Da Kla	.d, C	<u> </u>					
Sampler (Sign	ature)	: Mu	had Sto AMPLES	tl					A	NALYS	ES	_/_	/ , /	/ Sample ハエ	ers:	
		S		100 05			/&``	G <sup>N</sup>		/E/		\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	/5i/_			
SAMPLE NO.	DATE	TIME	LAB SAMPLE NO.	NO. OF CON- TAINERS	SAMPLE TYPE		Q. C	<u>/ 1</u>	<u>/ v</u>	( ) ( )		//	<u> </u>	R	EMARKS	
DEWI-E-9	6-5-9	2	OIA	1	Soil	<u> </u>	<u> </u>	X							2	<del></del>
DEW 2-N-9			02A	1		<u> </u>	<u> </u>	X	X				Neg	gular 1	and It	<u> </u>
DEW3-N-8.5			03A				ļ	X							A. '. 1	C 1/
DEW4-W-8			04A				<del> </del>	X	X			+	Nesi	illy to:	Michael	11045
1EW5-5-8.5			05A	<u> </u>		<u> </u>	<u> </u>	X	<u> </u>							
DEW6-\$.9			06A		X	<u> </u>	<u> </u>	X	X			++				
D-Grandmak	<u>. X</u>	8:20	07A-D	4	Water	1	-	X	X			-	2   60	ie R: 1/	our die	. †-
	·	<u>                                     </u>	<u> </u>	7	ια <b>Δ</b> - Δ -		,	-		<b></b>						Brasi + I
		<del> </del>		1	Amber	•		<b>4</b> 9	1				Cott	78	25 Son Le	andro Steet
		-			1 110	1	1	†	1						Tland, (A	
		<del>                                     </del>	<del>                                     </del>			<del> </del>								Attn	: Dave Rol	14504
	<del></del>			1	1			1							2-8035	
								<u> </u>					Pero	Wangemer	it w/Po	din Byer
			· ex			<u> </u>		<u> </u>								
				<u> </u>	<u> </u>		<u> </u>	<u> </u>				1 1			DATE	TIME
RELINQUISHED ( (Signature)	3Y: 2	Nela	1 Stall		DATE 6-5-	97	TIME 12分	2	RECEIV (Signa	ED BY: (	Nina	. All	lisa	<i>v</i>		2 11242
RELINQUISHED I		0-20			DATE		TIME		RECEIV (Signa	ED BY:	$Q_{-}$	0	- ψ		DATE	TIME
(Signature) RELINQUISHED	BY:				DATE		TIME	_	RECEIV	ED BY:					DATE	TIME
(Signature)					DATE		TIME		(Signa	MMENTS:						
METHOD OF SHI	PMENT:			<u> </u>		1								0.150		
Sample Collector: LEVINE-FRICKE 1900 Powell Street, 12th Flo						Anal					Robin By					
		<b>. p</b>	Emeryville,	Ca 946		100f			-		Qua	rteg,	Pleas	ent Hill	,(A	<b>.</b>
Shioning Com	(White)		(415) 652- b Copy (Green)		le Copy	(Yello	ω) <sub></sub>		Id Cop	y (Pink)					FORM	NO. 86/COC/AR
Shipping	funirel	Lo	in cohi farcant			_						-	-			