

File No. 8-90-421-SI

QUARTERLY GROUNDWATER MONITORING AND
SAMPLING FOR PLAZA CAR WASH PROPERTY
LOCATED AT 400 SAN PABLO AVENUE
ALBANY, CALIFORNIA
DECEMBER 26, 1995

PREPARED FOR:
MR. MURRAY STEVENS
KAMUR INDUSTRIES, INC.
2351 SHORELINE DRIVE
ALAMEDA, CALIFORNIA 94501

BY:
SOIL TECH ENGINEERING, INC.
298 BROKAW ROAD
SANTA CLARA, CALIFORNIA 95050

SOIL TECH ENGINEERING, INC.

LIST OF TABLES

TABLE 1 ... GROUNDWATER MONITORING DATA.

TABLE 2 ... WATER ANALYTICAL RESULTS.

LIST OF FIGURES

FIGURE 1 ... SITE VICINITY MAP SHOWING 400 SAN PABLO AVENUE,
ALBANY, CALIFORNIA.

FIGURE 2 ... SITE PLAN SHOWING LOCATIONS OF MONITORING WELLS,
DIRECTION OF GROUNDWATER FLOW AND CONTOUR LINES.

LIST OF APPENDICES

APPENDIX "A" ... TABLE 1 AND TABLE 2.


APPENDIX "B" ... FIGURE 1 AND FIGURE 2.

APPENDIX "B" ... STANDARD OPERATING PROCEDURES.

APPENDIX "C" ... ANALYTICAL TEST REPORT OF WATER SAMPLES AND
CHAIN-OF-CUSTODY RECORDS.

SOIL TECH ENGINEERING, INC.

TABLE OF CONTENTS	<u>Page No.</u>
LETTER OF TRANSMITTAL	1
BACKGROUND	1-2
GROUNDWATER MONITORING	2
GROUNDWATER SAMPLING	3
GROUNDWATER FLOW	3
ANALYTICAL RESULTS	3-4
DISCUSSION	4
RECOMMENDATION	4
LIMITATIONS	5-6
 <u>APPENDIX "A"</u>	
TABLE 1 - GROUNDWATER MONITORING DATA	T1-T9
TABLE 2 - WATER ANALYTICAL RESULTS	T10-T16
 <u>APPENDIX "A"</u>	
FIGURE 1 - VICINITY MAP	M1
FIGURE 2 - SITE PLAN	M2
 <u>APPENDIX "B"</u>	
GROUNDWATER SAMPLING	SOP1
 <u>APPENDIX "C"</u>	
PRIORITY ENVIRONMENTAL LABS ANALYTICAL REPORT AND CHAIN-OF-CUSTODY	



SOIL TECH ENGINEERING

Soil, Foundation and Geological Engineers

298 BROKAW ROAD, SANTA CLARA, CA 95050 ■ (408) 496-0265 OR (408) 496-0266

December 26, 1995

File No. 8-90-421-SI

Mr. Murray Stevens
Kamur Industries, Inc.
2351 Shoreline Drive
Alameda, California 94501

**SUBJECT: QUARTERLY GROUNDWATER MONITORING AND
SAMPLING FOR PLAZA CAR WASH PROPERTY**
Located at 400 San Pablo Avenue, in
Albany, California

Dear Mr. Stevens:

This report presents the results of quarterly groundwater monitoring and sampling conducted by Soil Tech Engineering, Inc. (STE), on November 30, 1995, at the subject site (Figure 1).

BACKGROUND:

Currently there are four monitoring wells (MW-2, MW-3, STMW-1 and STMW-2) located on-site (see Figure 2). Wells STMW-1 and STMW-2 were installed by STE, and on-site wells MW-2 & MW-3 were installed by other consultants. This quarterly well monitoring and sampling was conducted in accordance with STE's recommendations made in the report entitled "Report of Supplemental Subsurface

Investigations", dated May 14, 1991. During this quarter's reporting period, the following field activities were performed:

- Monitored the depth-to-static groundwater for on-site monitoring wells STMW-1, STMW-2, MW-2 and MW-3.
- Purged on-site monitoring wells STMW-1, STMW-2, MW-2 and MW-3 prior to sampling.
- Submitted water samples to a State-Certified laboratory to be analyzed for Total Petroleum Hydrocarbons as gasoline (TPHg) and for aromatic hydrocarbons: Benzene, Toluene, Ethylbenzene, and Total Xylenes (BTEX).
- Reviewed results and prepared a report of the investigation.

GROUNDWATER MONITORING:

On November 30, 1995, STE staff monitored the four on-site wells to measure water depth and check for the presence of sheen and/or odor. During monitoring of the wells, no sheen or odor were detected in monitoring well MW-2. Thick brown sheen spots and mild petroleum odor were detected in monitoring well STMW-1. Rain-bow sheen spots and light petroleum odor were present in monitoring wells STMW-2 and MW-3. After purging of the wells, no sheen was observed in any of the wells. Table 1 summarizes the depth to the groundwater and observations made. The static shallow groundwater levels ranged from 5.64 to 7.34 feet below ground surface during the recent quarterly sampling event.

GROUNDWATER SAMPLING:

Following groundwater monitoring, the wells were purged at least four well volumes and sampled in accordance with STE's Standard Operating Procedures (Appendix "C"), which follows State and local guidelines for sampling and monitoring wells. The samples were submitted to a California State-Certified laboratory for analysis, accompanied by chain-of-custody. The samples were analyzed for TPHg and for BTEX per modified EPA Methods 5030/8025 and 602.

GROUNDWATER FLOW:

The water elevation data were used to determine groundwater direction. Table 1 summarizes the groundwater elevations. The local groundwater flow direction was in southwesterly direction as of November 30, 1995 (Figure 2).

ANALYTICAL RESULTS:

The four on-site wells continued to show the presence of low levels of Benzene, Toluene, Ethylbenzene and Total Xylenes (BTEX). Monitoring well STMW-1 detected TPHg at 67 milligrams per liter (mg/L); Benzene at 0.8 mg/L; Toluene at 0.91 mg/L; Ethylbenzene at 0.39 mg/L and Total Xylenes at 1.5 mg/L. Monitoring well STMW-2 detected TPHg at 66 mg/L and BTEX at (0.66 mg/L, 0.51 mg/L, 0.37 mg/L and 1.5 mg/L), respectively. Well MW-2 detected TPHg at 0.12

mg/L and BEX at 0.0093 mg/L, 0.0005 mg/L, 0.0035 mg/L, but Toluene was below laboratory detection limit in well MW-2. Well MW-3 detected TPHg at 100 mg/L and BTEX at 1.3 mg/L, 0.51 mg/L, 0.25 mg/L and 2.4 mg/L, respectively.

The results of laboratory are tabulated in Table 2. The chain-of-custody records and certified analytical report are included in Appendix "D".

DISCUSSION:

A comparison of the recent analytical results with the August 18, 1995 results showed a decrease in TPHg concentrations in wells MW-2 (from 1.8 to 0.12 mg/L), STMW-1 (from 300 to 67 mg/L) and STMW-2 (from 210 to 66 mg/L). TPHg concentrations increased in well MW-3 (from 33 to 100 mg/L).

Monitoring well MW-2 showed a slight decrease of BTEX concentrations. Monitoring well MW-3 showed an increase of BTEX levels. Monitoring wells STMW-1 and STMW-2 a decrease of BEX concentrations and a slight increase of Toluene in this quarter.

RECOMMENDATION:

We recommend continuing quarterly monitoring of on-site wells until interim groundwater treatment is initiated. This quarterly report should be submitted to Alameda County Health Department (ACHD) and the Regional Water Quality Control Board (RWQCB).

LIMITATIONS:

This report and the associated work have been provided in accordance with the general principles and practices currently employed in the environmental consulting profession. The contents of this report reflect the conditions of the site at this particular time. The findings of this report are based on:

- 1) The observations of field personnel.
- 2) The results of laboratory analyses performed by a state-certified laboratory.

It is possible that variations in the soil and groundwater could exist beyond the points explored in this investigation. Also, changes in groundwater conditions of a property can occur with the passage of time due to variations in rainfall, temperature, regional water usage and other natural processes or the works of man on this property or adjacent properties.

The services that STE provided have been in accordance with generally accepted environmental professional practices for the nature and conditions of the work completed in the same or similar localities, at the time the work was performed.


Per your request, this report will be submitted to ACEHD and RWQCB.


File No. 8-90-421-SI


If you have any questions or require additional information,
please feel free to contact our office at your convenience.

Sincerely,

SOIL TECH ENGINEERING, INC.


NOORI AMELI
PROJECT ENGINEER


LAWRENCE KOO, P. E.
C. E. #34928


FRANK HAMEDI-FARD
GENERAL MANAGER

SOIL TECH ENGINEERING, INC.

6

File MNo. 8-90-421-SI

A P P E N D I X "A"

SOIL TECH ENGINEERING, INC.

TABLE 1
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
3/11/91	STMW-1 (100.62)	5.29	95.33	None	None
	STMW-2 (100.63)	5.25	95.38	None	Mild
	MW-2 (99.39)	4.92	95.07	None	Mild
	MW-3 (100.09)	4.67	95.42	Trace	Moderate
	OTMW-5 (100.87)	5.02	95.85	None	Mild
7/03/91	STMW-1 (100.62)	5.83	94.79	None	Mild
	STMW-2 (100.63)	4.75	95.88	None	Mild
	MW-2 (99.39)	5.83	93.53	None	Mild
	MW-3 (100.09)	7.75	94.55	Light	Strong
	OTMW-5 (100.87)	5.65	95.12	None	Mild

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
11/04/91	STMW-1 (100.62)	5.83	94.79	None	Mild
	STMW-2 (100.63)	5.92	94.71	None	Mild
	MW-2 (99.39)	4.79	94.57	None	Mild
	MW-3 (100.09)	5.67	94.42	Trace	Strong
	OTMW-5 (100.87)	5.77	95.10	None	Mild
1/20/92	STMW-1 (100.62)	5.79	94.84	Light	Mild
	STMW-2 (100.63)	5.88	94.75	None	Mild
	MW-2 (99.39)	4.60	94.76	None	Mild
	MW-3 (100.09)	5.54	94.55	Light	Strong
	OTMW-5 (100.87)	5.58	95.29	None	Mild

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
5/07/92	STMW-1 (100.62)	5.80	94.82	None	Mild
	STMW-2 (100.63)	5.70	94.92	None	Mild
	MW-2 (99.39)	4.42	94.94	None	Mild
	MW-3 (100.09)	5.18	94.91	Rainbow	Strong
	OTMW-5 (100.87)	5.43	95.44	None	Mild
8/17/92	STMW-1 (100.62)	5.77	94.85	None	Mild
	STMW-2 (100.63)	5.71	94.92	None	None
	MW-2 (99.39)	4.43	94.96	None	Mild
	MW-3 (100.09)	5.24	94.85	Rainbow	Mild
	OTMW-5 (100.87)	5.45	95.42	None	None
	OTMW-6	4.88	NA	None	None

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
12/10/92	STMW-1 (100.62)	6.61	94.01	Light	Mild
	STMW-2 (100.63)	6.39	94.24	Light	Mild
	MW-2 (99.39)	4.94	94.45	None	Mild
	MW-3 (100.09)	4.42	95.67	Light	Strong
	OTMW-5 (100.87)	7.30	93.57	None	Mild
3/18/93	STMW-1 (100.62)	6.68	93.94	Light	Mild
	STMW-2 (100.63)	6.50	94.13	Light	Mild
	MW-2 (99.39)	5.11	94.28	None	Light Sewage
	MW-3 (100.09)	5.39	94.70	Thick	Strong
	OTMW-5 (100.87)	7.11	93.76	None	Light Sewage

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
7/13/93	STMW-1 (100.62)	7.13	93.49	Light Rain- bow	Strong Petroleum
	STMW-2 (100.63)	6.95	93.68	None	Septic
	MW-2 (99.39)	5.53	93.86	Rainbow	Light Petroleum
	MW-3 (100.09)	6.07	94.02	Light Rain- bow	Strong Petroleum
	OTMW-5 (100.87)	7.45	93.42	None	None
10/11/93	STMW-1 (100.62)	7.26	93.36	None Measurable	Strong Petroleum
	STMW-2 (100.63)	7.09	93.54	None Measurable	Strong Petroleum
	MW-2 (99.39)	5.64	93.75	None	None
	MW-3 (100.09)	6.34	93.75	None Measurable	Strong Petroleum
	OTMW-5 (100.87)	7.65	93.22	None	None

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
1/07/94	STMW-1 (100.62)	7.15	93.47	None Measurable	Strong Petroleum
	STMW-2 (100.63)	6.93	93.70	Rainbow	Mild Petroleum
	MW-2 (99.39)	5.52	93.87	None	None
	MW-3 (100.09)	6.34	93.75	None Measurable	Strong Petroleum
	OTMW-5 (100.87)	7.67	93.20	None	None
4/06/94	STMW-1 (100.62)	7.10	93.52	None	Strong Petroleum
	STMW-2 (100.63)	6.84	93.79	None	Strong Petroleum
	MW-2 (99.39)	5.82	93.57	None	None
	MW-3 (100.09)	6.14	93.95	None	None
	OTMW-5 (100.87)	7.72	93.15	None	None

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
8/03/94	STMW-1 (100.62)	5.70	94.92	None	Strong Petroleum
	STMW-2 (100.63)	7.10	93.53	None	Mild Petroleum
	MW-2 (99.39)	7.47	91.92	None	None
	MW-3 (100.09)	6.34	93.75	Sheen with Grease	Moderate Petroleum
11/08/94	STMW-1 (100.62)	6.47	94.15	Brown Non- Measurable	Strong Petroleum
	STMW-2 (100.63)	6.19	94.44	Rainbow	Mild Petroleum
	MW-2 (99.39)	4.69	94.70	None	Mild Sewerage
	MW-3 (100.09)	3.89	96.20	Brown Non- Measurable	Strong Petroleum

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
2/16/95	STMW-1 (100.62)	6.96	93.66	Rainbow Non- Measurable	Strong Petroleum
	STMW-2 (100.63)	6.72	93.91	Rainbow	Mild Petroleum
	MW-2 (99.39)	5.31	94.08	None	None
	MW-3 (100.09)	5.90	94.19	Brown Non- Measurable	Strong Petroleum
5/19/95	STMW-1 (100.62)	6.84	93.78	Brown Non- Measurable	Strong Petroleum
	STMW-2 (100.63)	6.61	94.02	Brown	Light Petroleum
	MW-2 (99.39)	5.17	94.22	None	Mild Sewerage
	MW-3 (100.09)	4.15	95.94	Brown Non- Measurable	Strong Petroleum

TABLE 1 CONT'D
GROUNDWATER MONITORING DATA
(Measured in Feet)

Date	Well No./ Elevation	Depth-to- Water	Groundwater Elevation	Sheen	Odor
8/18/95	STMW-1 (96.81)	7.36	89.45	Brown Non- Measurable	Strong Petroleum
	STMW-2 (96.79)	7.09	89.70	Brown	Light Petroleum
	MW-2 (95.22)	5.65	89.57	None	Light Sewerage
	MW-3 (95.62)	6.08	89.54	Brown	Mild Petroleum
11/30/95	STMW-1 (96.81)	7.34	89.47	Thick Brown	Mild Petroleum
	STMW-2 (96.79)	7.07	89.72	Rainbow	Light Petroleum
	MW-2 (95.22)	5.64	89.58	None	None
	MW-3 (95.62)	6.26	89.36	Rainbow	Light Petroleum

NA - Not Applicable

TABLE 2
WATER ANALYTICAL RESULTS
IN
MILLIGRAMS PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
3/13/91	STMW-1	0.85	0.1	0.007	ND	0.15
	STMW-2	0.17	0.001	0.0017	ND	0.028
	MW-2	25	2.6	4.4	ND	5.8
	MW-3	47	9.1	9.9	0.27	8.11
	OTMW-5	0.12	0.046	0.012	0.001	0.004
7/03/91	STMW-1	5.1	1.8	0.5	0.095	0.56
	STMW-2	1.8	0.64	0.048	0.044	0.094
	MW-2	21	2.8	3.2	ND	4.3
	MW-3	140	12	4.5	1.2	4.0
	OTMW-5	0.81	0.32	0.043	0.016	0.043
11/04/91	STMW-1	2.05	0.76	0.054	ND	0.056
	STMW-2	2.14	1.00	0.057	0.003	0.019
	MW-2	3.58	1.7	0.119	0.009	0.056
	MW-3	102.7	38.87	19.1	5.8	46
	OTMW-5	0.97	0.1	0.019	0.005	0.013

TABLE 2 CONT'D
 WATER ANALYTICAL RESULTS
 IN
 MILLIGRAMS PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
1/20/92	STMW-1	4.6	0.59	0.036	ND	0.19
	STMW-2	14	0.12	0.0006	0.0006	0.08
	MW-2	0.38	0.38	0.0013	ND	0.034
	MW-3	510	27	27	5.8	46
	OTMW-5	0.09	0.0007	0.0007	ND	0.011
5/07/92	STMW-1	4.4	0.066	0.053	0.004	0.16
	STMW-2	1.7	0.032	0.017	0.0086	0.048
	MW-2	10	0.062	0.032	0.044	0.16
	MW-3	43	0.25	0.23	0.43	1.1
	OTMW-5	0.18	0.027	0.014	0.0082	0.035
8/17/92	STMW-1	2.7	0.031	0.018	0.019	0.067
	STMW-2	16	0.18	0.22	0.21	0.62
	MW-2	6.0	0.048	0.027	0.065	0.18
	MW-3	140	2.5	2.4	1.7	5.5
	OTMW-5	0.087	0.012	0.0098	0.004	0.042
	OTMW-6	ND	ND	ND	ND	ND

TABLE 2 CONT'D
 WATER ANALYTICAL RESULTS
 IN
 MILLIGRAM PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
12/10/92	STMW-1	35	0.054	0.079	0.083	0.22
	STMW-2	44	0.084	0.096	0.12	0.35
	MW-2	7.2	0.015	0.023	0.032	0.082
	MW-3	94	0.4	0.41	0.43	1.1
	OTMW-5	0.54	0.0047	0.0045	0.0064	0.019
3/18/93	STMW-1	19	0.049	0.052	0.055	0.18
	STMW-2	9.2	0.022	0.031	0.04	0.11
	MW-2	1.4	0.0083	0.011	0.013	0.048
	MW-3	51	0.092	0.13	0.16	0.59
	OTMW-5	0.57	0.006	0.0076	0.011	0.029
7/13/93	STMW-1	17	0.034	0.043	0.048	0.17
	STMW-2	9.3	0.018	0.024	0.026	0.089
	MW-2	2.4	0.0047	0.0062	0.0068	0.025
	MW-3	80	0.16	0.21	0.23	0.82
	OTMW-5	3.5	0.0068	0.00086	0.0095	0.036

TABLE 2 CONT'D
 WATER ANALYTICAL RESULTS
 IN
 MILLIGRAM PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
12/10/92	STMW-1	35	0.054	0.079	0.083	0.22
	STMW-2	44	0.084	0.096	0.12	0.35
	MW-2	7.2	0.015	0.023	0.032	0.082
	MW-3	94	0.4	0.41	0.43	1.1
	OTMW-5	0.54	0.0047	0.0045	0.0064	0.019
3/18/93	STMW-1	19	0.049	0.052	0.055	0.18
	STMW-2	9.2	0.022	0.031	0.04	0.11
	MW-2	1.4	0.0083	0.011	0.013	0.048
	MW-3	51	0.092	0.13	0.16	0.59
	OTMW-5	0.57	0.006	0.0076	0.011	0.029
7/13/93	STMW-1	17	0.034	0.043	0.048	0.17
	STMW-2	9.3	0.018	0.024	0.026	0.089
	MW-2	2.4	0.0047	0.0062	0.0068	0.025
	MW-3	80	0.16	0.21	0.23	0.82
	OTMW-5	3.5	0.0068	0.00086	0.0095	0.036

TABLE 2 CONT'D
 WATER ANALYTICAL RESULTS
 IN
 MILLIGRAM PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
10/11/93	STMW-1	51	2.1	2.4	0.53	2.6
	STMW-2	62	2.8	3.9	0.67	4.4
	MW-2	0.41	0.043	0.0026	0.0045	0.012
	MW-3	180	14.0	8.8	0.32	9.4
	OTMW-5	ND	ND	ND	ND	ND
1/07/94	STMW-1	29	1.5	1.6	0.45	2.5
	STMW-2	22	1.1	1.0	0.28	1.8
	MW-2	0.24	0.025	0.0031	ND	0.02
	MW-3	120	9.5	4.6	0.23	7.8
	OTMW-5	1.5	0.2	0.098	0.005	0.057
4/06/94	STMW-1	20.0	1.1	0.56	0.3	1.6
	STMW-2	6.6	0.49	0.14	0.062	0.33
	MW-2	3.0	0.12	0.023	0.022	0.19
	MW-3	96.0	6.0	3.1	0.095	6.2
	OTMW-5	0.57	0.072	0.036	0.0024	0.022

TABLE 2 CONT'D
 WATER ANALYTICAL RESULTS
 IN
 MILLIGRAM PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
8/03/94	STMW-1	43.0	1.0	1.7	0.64	4.7
	STMW-2	4.0	0.25	0.052	0.055	0.24
	MW-2	0.5	0.057	0.001	0.017	0.025
	MW-3	200.0	6.5	3.7	1.5	18.0
11/18/94	STMW-1	92.0	9.0	12.0	1.6	9.1
	STMW-2	10.0	0.73	0.79	0.2	1.3
	MW-2	8.0	0.65	0.085	0.5	1.04
	MW-3	86.0	7.4	8.5	2.2	12.0
2/16/95	STMW-1	150.0	0.85	0.54	0.4	1.2
	STMW-2	37.0	0.23	0.088	0.092	0.32
	MW-2	0.66	0.0064	0.001	0.0056	0.0089
	MW-3	59.0	0.28	0.12	0.12	0.57

TABLE 2 CONT'D
WATER ANALYTICAL RESULTS
IN
MILLIGRAM PER LITER (mg/L)

Date	Well No.	TPHg	B	T	E	X
5/19/95	STMW-1	59.0	0.4	0.33	0.17	0.61
	STMW-2	9.3	0.04	0.016	0.022	0.068
	MW-2	1.9	0.011	0.01	0.023	0.026
	MW-3	12.0	0.15	0.068	0.069	0.16
8/18/95	STMW-1	300.0	0.88	0.78	0.54	1.7
	STMW-2	210.0	0.72	0.55	0.52	1.4
	MW-2	1.8	0.015	0.0016	0.015	0.02
	MW-3	33.0	0.074	0.028	0.038	0.1
11/30/95	STMW-1	67.0	0.8	0.91	0.39	1.5
	STMW-2	66.0	0.66	0.51	0.37	1.5
	MW-2	0.12	0.0093	ND	0.0005	0.0035
	MW-3	100.0	1.3	0.51	0.25	2.4
	SDWS	NL	0.001	0.100*	0.68	1.75

TPHg - Total Petroleum Hydrocarbons as gasoline
 BTEX - Benzene, Toluene, Ethylbenzene, Total Xylenes
 SDWS - State Drinking Water Standard
 ND - Not Detected (Below Laboratory Detection Limit)
 NL - No MCL Levels
 * - Action Level not Enforceable-Health Based Advisory Levels


File MNo. 8-90-421-SI

A P P E N D I X "B"

SOIL TECH ENGINEERING, INC.



Thomas Brothers Map 1993 Edition
San Francisco, Alameda,
and Contra Costa Counties



Street Flow Line

SAN PABLO AVENUE

C. EL. Casing Elevation
W. EL. Water Elevation
Monitoring Well

DIRECTION OF GROUNDWATER FLOW		
400 SAN PABLO AVENUE, ALBANY, CALIFORNIA		
SCALE: 1"=30'	PROJECT NO. 8-90-421-SI	FIGURE 2
DRAWN BY N.A.		11/30/95
SOIL TECH ENGINEERING, INC. 298 BROXAW ROAD, SANTA CLARA, CALIFORNIA 95050		

File MNo. 8-90-421-SI

A P P E N D I X "C"

SOIL TECH ENGINEERING, INC.

GROUNDWATER SAMPLING

Prior to collection of groundwater samples, all of the sampling equipment (i.e. bailer, cables, bladder pump, discharge lines and etc...) was cleaned by pumping TSP water solution followed by distilled water.

The groundwater sample was collected when the first groundwater level was encountered in the boring.

Forty milliliter (ml.), glass volatile organic analysis (VOA) vials with Teflon septa were used as sample containers. The groundwater sample was decanted into each VOA vial in such a manner that there was a meniscus at the top. The cap was quickly placed over the top of the vial and securely tightened. The VOA vial was then inverted and tapped to see if air bubbles were present. If none were present, the sample was labeled and refrigerated for delivery under chain-of-custody to the laboratory. The label information would include a sample identification number, job identification number, date, time, type of analysis requested, and the sampler's name.



PRIORITY ENVIRONMENTAL LABS

Environmental Analytical Laboratory

December 02, 1995

PEL # 9511108

SOIL TECH ENGINEERING

Attn: Noori Ameli

Re: Four water samples for Gasoline/BTEX analysis.

Project name: 400 San Pablo Ave., - Albany

Project number: 8-90-421-SI

Date sampled: Nov 30, 1995


Date submitted: Nov 30, 1995

Date extracted: Nov 30-Dec 01, 1995

Date analyzed: Nov 30-Dec 01, 1995

RESULTS:

SAMPLE I.D.	Gasoline (ug/L)	Benzene (ug/L)	Toluene (ug/L)	Ethyl Benzene (ug/L)	Total Xylene (ug/L)
MW-2	120	9.3	N.D.	0.5	3.5
MW-3	100000	1300	510	250	2400
STMW-1	67000	800	910	390	1500
STMW-2	66000	660	510	370	1500
Blank	N.D.	N.D.	N.D.	N.D.	N.D.
Spiked Recovery	101.3%	81.6%	89.7%	80.6%	94.0%
Detection limit	50	0.5	0.5	0.5	0.5
Method of Analysis	5030 / 8015	602	602	602	602


David Duong
 Laboratory Director

PROJ. NO. 8-93-421-31 NAME 400 San Pablo AVE. ALBANY

SAMPLERS: (Signature) N. Ameli

CON-TAINER

ANALYSES REQUESTED (2) TPHG/BTEX


PEL # 9511108
INV # 26600

NO.	DATE	TIME	SOIL	WATER	LOCATION	CON-TAINER	ANALYSES REQUESTED (2) TPHG/BTEX															
1	11/3/95	13 ³⁰		✓	STMW-1	1	✓															
2	11/3/95	11 ⁵²		✓	STMW-2	1	✓															
3	11/3/95	10 ²⁵		✓	MW-2	1	✓															
4	11/3/95	11 ¹⁰		✓	MW-3	1	✓															

Relinquished by: (Signature) N. Ameli Date / Time Received by: (Signature) Relinquished by: (Signature) Date / Time Receive by: (Signature)

Relinquished by: (Signature) Date / Time Received by: (Signature) Relinquished by: (Signature) Date / Time Received by: (Signature)

Relinquished by: (Signature) Date / Time 11/3/95 3:35 PM Received for Laboratory by: (Signature) Date / Time Remarks



SOIL TECH ENGINEERING

Soil, Foundation and Geological Engineers

298 BROKAW ROAD, SANTA CLARA, CA 95050 ■ (408) 866-0919 ■ (415) 791-6406



PROJ. NO. 8-90-421-SI NAME 400 San Pablo AVE. ALBANY

SAMPLERS: (Signature) N. Ameli


ANALYSES REQUESTED @ TPHG/BTE & X

CON-TAINER

REMARKS

NO.	DATE	TIME	SOIL	WATER	LOCATION	CON-TAINER												
1	11/30/95	13 ³⁰	✓	✓	STMW-1	1	✓											
2	11/30/95	11 ⁵⁵	✓	✓	STMW-2	1	✓											
3	11/30/95	10 ²⁵	✓	✓	MW-2	1	✓											
4	11/30/95	11 ¹⁵	✓	✓	MW-3	1	✓											

Relinquished by: (Signature) N. Ameli	Date / Time	Received by: (Signature)	Relinquished by: (Signature)	Date / Time	Received by: (Signature)
Relinquished by: (Signature)	Date / Time	Received by: (Signature)	Relinquished by: (Signature)	Date / Time	Received by: (Signature)
Relinquished by: (Signature)	Date / Time 11/30/95 3:35 PM	Received for Laboratory by: (Signature) D. Anderson	Date / Time	Remarks	



SOIL TECH ENGINEERING
Soil, Foundation and Geological Engineers