
٠,

January 8, 2001 Via facsimile Hard copy to follow in regular mail

Mr. Larry Seto Alameda County Health Care Services Agency 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502-6577

Re:

Agency Response



Dear Mr. Seto:

On behalf of Equiva Services LLC, Cambria Environmental Technology, Inc. (Cambria) is responding to the Alameda County Health Care Services Agency (ACHCSA) letter dated November 15, 2000. Cambia's responses to questions in your letter are given below.

1) What is the status of the original monitoring wells S-1, S-2, and S-3? If they are closed, how and when were they closed?

According to a Phase I Preliminary Site Assessment prepared by Geostrategies Inc. (GSI) on June 30, 1993, wells S-1, S-2, and S-3 were destroyed during onsite construction activities in approximately 1987. The site has been a paved parking lot since at least 1984. Cambria does not have a report of well destruction. However, correspondence from EMCON Associates to Gettler-Ryan, Inc. dated June 26, 1986, transmitted instructions that the wells were to perforated at depth and grouted with neat cement to the surface.

2) Were the underground storage tanks (USTs) and associated product piping removed from the site?

Yes. Based on GSI's 1993 Phase I report, GSI reviewed the City of Oakland building permits and found that Shell Oil Company (now Equilon) had obtained permits to demolish the service station and remove the USTs and associated piping in accordance with existing regulations. All USTs and fueling facilities were reportedly removed from the site in 1980.

Oakland, CA San Ramon, CA Sonoma, CA

Cambria Environmental Technology, Inc.

1144 65th Street Suite B Oakland, CA 94608 Tel (510) 420-0700 Fax (510) 420-9170

3) Were any soil or groundwater samples taken during the tank removal? Were the samples analyzed by a State certified laboratory? Please provide me with copies of any laboratory results.

It is unknown whether a UST and piping removal report exists. However, soil conditions in the former UST, piping and dispenser areas are represented by data from soil borings L1 (S-1) through L7 (S-7), S-8 through S-10, and B-1 Through B-9. Analytical data from these borings are summarized in Attachment B



4) When were monitoring wells S-4, S-5, and S-6 installed? Please submit a copy of the well logs and monitoring well construction design to this office.

Wells S-1 through S-7 were installed from August 25 through September 10, 1981 by Groundwater Technology, Inc. (GTI). Copies of all soil boring/well logs and a map indicating their locations are included as Attachment A. Note: The GTI logs use the designation "L" for each well instead of "S" as currently used by Cambria. Laboratory reports for samples collected during this investigation are included as Attachment B.

5) Are all of the monitoring wells screened at the same depths?

No. Well construction details of all site wells are presented in Table 1. Well S-7 was reportedly destroyed during freeway construction (Interstate-880) although Cambria does not have records detailing the well destruction. All wells currently existing at the site are shown on Figure 1.

6) Has a conduit study been performed for this site?

A conduit study has not been performed for this site to date.

7) Do you have any knowledge of any upgradient site from the subject facility that may be a potential source?

Figure 1 shows potential offsite sources of MTBE identified in an August 12, 1996 correspondence titled *Offsite Source Investigation*, prepared by Enviros. No other potential offsite MTBE sources have been identified by Cambria, including any sources which are directly upgradient from the subject site. The only potential upgradient source identified by Enviros, the Blue and White Cab Company, was identified by name only and, at that time, was not included on the RWQCB's LUSTIS list which identifies known UST release sites. Therefore, it is unknown whether the Blue and White Cab Company site is an upgradient source.

ADDITIONAL INFORMATION

The following information was originally presented in our October 2, 2000 correspondence to your office:

Historical MTBE Use In Gasoline Products Sold at the Subject Facility: On September 30, 1997, Shell Oil Products Company (now Equilon Enterprises LLC) issued correspondence titled Response to San Francisco Bay Regional Water Quality Control Board Request for Chemical Constituents of Gasoline Data. According to this document, Shell/Equilon utilizes the Shell Martinez Refining Company (SMRC) as the primary source for refined gasoline products in the San Francisco Bay area (Bay Area). MTBE use in refined gasoline products from the SMRC did not begin until November 1991.

9

Gasoline underground storage tanks (USTs) at the subject facility were in operation until site demolition in 1980 when they were removed along with gasoline station improvements. The site has not been used as a gasoline sales facility since that time. The USTs formerly onsite were removed approximately 10 years prior to the use of MTBE in gasoline at SMRC. Therefore, it is not likely that MTBE in groundwater is associated with, or eminating from, the subject facility.

MTBE Reported in Groundwater: MTBE was first reported in groundwater at the site using EPA Method 8020 on October 2, 1996. EPA Method 8020 uses gas chromatography to screen for MTBE but is subject to false-positive detections in the presence of elevated hydrocarbon concentrations. EPA Method 8260 uses mass spectrometry coupled with gas chromatography and provides a more accurate measure of MTBE. No MTBE was detected using method 8260 in samples collected from wells S-8 in October 1996, and wells S-5 and S-6 in November 1999. The first confirmation of MTBE in wells associated with the site was during the July 2000 sampling event in wells S-5 and S-6 at 253 parts per billion (ppb) and 72.7 ppb, respectively (these analyses were run outside of the EPA recommended holding time by the lab).

The most recent groundwater samples were collected from wells S-5, S-6, and S-8 on October 12, 2000. No MTBE was indicated by either EPA Method 8020 or 8260, although elevated hydrocarbon concentrations resulted in higher than normal laboratory detection limits. Analytical results will be presented in the fourth quarter 2000 groundwater monitoring report.

CLOSING

We hope this correspondence adequately addresses your concerns regarding this site. Please call Troy Buggle at (510) 420-3333 if you have any questions or comments.

Sincerely,

Cambria Environmental Technology, Inc.

Troy A. Buggle

Project Environmental Scientist

DUBPHAN BOYCK

Sterkan A. Bork, C.E.G., C.HG.

Associate Hydrogeologist

1 - Groundwater Elevation Contour and Potential Offsite Sources - July 19, 2000 Figure:

Table: 1 - Well Construction Details

Attachment: A - Soil Boring/Well Construction Logs

B - Site Assessment Analytical Data

Karen Petryna, Equiva Services LLC, P.O. Box 7869, Burbank, California 91510-7869 cc:

Leah Goldberg, Hanson, Bridgett, Marcus, Vlahos, & Rudy, 333 Market Street, Suite

No. EG 2058 CERTIFIED ENGINEERING **GEOLOGIST**

2300, San Francisco, California 94105-2173

Wells Fargo Bank National Association, Tr. (Property Owners), c/o Pacific Property,

364 Bush Street, San Francisco, CA 94104-2805

Barney Chan, ACHCSA, 1131 Harbor Bay Parkway, Suite 250, Alameda, CA 94502-

6577

Table 1. Well Construction Specifications - Former Shell-branded Service Station, 461 8th Street Oakland, California Incident # 97093399

Well ID	Depth	Diameter	Screened	Groundwater
	(ft bgs)		Interval (ft bgs)	Depth Range****
		-11		
S1 (L1)*	30'	4"	20' to 30'	UNK
S2 (L2)*	30'	4"	20' to 30'	UNK
S3 (L3)*	30'	4"	20' to 30'	UNK
S4 (L4)	30'	4"	20' to 30'	13-23'
S5 (L5)	37' ***	4"	20' to 30'	15-23'
S6 (L6)	40' 4"		20' to 40'	18-22'
S7 (L7)**	40'	4"	20' to 40'	UNK
S8	30'	4"	10' to 30'	21-25'
S9	30'	30' 4" 10' to 30'		21-24'
S10	36.5'	4"	10' to 36.5'	23-26'

Notes and Abbreviations:


UNK - Unknown

^{*} Wells destroyed during construction?

^{**} Well abandoned during Interstate 880 construction.

^{***} Quarterly monitoring field notes indicate S5 total depth to be approximately 40-41fbg.

^{****} Groundwater depth ranges are approximate





BROWN AND CALDWELL

CONSULTING ENGINEERS

O. H. CALDWELL PE Chairman T. V. LUTGE, PE President R. C. ABERLEY, PE Exec Vice Pres S. A. FISHER, Vice Pres

ENVIRONMENTAL SCIENCES DIVISION

September 30, 1981

Mr. Terry Cowhey, President Cowhey Pacific Drilling Pier 33 San Francisco, CA 94111

705-4

Dear Mr. Cowhey:

Enclosed are the results from the gasoline fingerprinting work performed on soil samples received for the period of 8/25-9/10/81.

In spite of reported field observations and extensive attempts by our laboratory personnel, no gasoline aliphatic or aromatic hydrocarbons were observed above our detection limit of 250 ppm. The sample handling and analytical methodologies employed in our laboratory are described below. Dr. Steve Havlicek, our technical director, reviewed these methods with the staff members who performed the analytical work to give you the best possible effort. One item which has just recently come to our attention is that if aluminum foil is used to line the caps in order to protect against possible absorbtion of the gasoline on plastic or cardboard liner, the foil must be cut to size and not permitted to hang out over the edges of the container. We have noted a very surprising amount of leakage around foil liners which are not cut to size and plan to be more specific in providing instructions regarding the use of such liners in the future.

This or other sampling/sealing problems may explain why no gasoline oders were noted in the samples as received. We are willing to work more closely with you in your field investigations to help you get to the root of this problem. Perhaps a down hole charcoal tube sampling may be more productive. The sample handling and methodologies are described below.

Sample Handling

Samples were collected in the field by Cowhey drilling personnel. Upon receipt at the laboratory, they were assigned a Brown and Caldwell log number for sample control purposes, then immediately refrigerated. Samples were brought to our

BROWN AND CALDWELL

1255 POWELL STREET EMERYVILLE, CA 94608 (415) 428-2300

Mr. Terry Cowhey September 30, 1981 Page two

laboratory on seven different occasions. Holding times before analysis ranged from 2 to 5 days for each sample. Samples were kept refrigerated and capped until that time.

Analytical Methodologies

Several separate techniques were employed in an attempt to confirm the presence of gasoline in the soil. Liquid/Liquid Extractions were conducted using three separate solvents; cyclohexane, hexadecane, and freon. Fifty (50) grams of soil were extracted in each case with 25 mL of solvent. These extracts were then analyzed by gas chromatography utilizing a flame ionization detection. We also used a purge and trap technique by placing 5 grams of soil into a warmed sparging vessel, then analyzing by gas chromatography photoionization detection. This method employs the same type of detection which you used in your field testing. Best results were seen with the Liquid/Liquid Extraction, hexadecane technique, and was subsequently used to screen all of the samples.

Samples were spiked with gasoline at 54 and 540 ppm of gasoline. The low level spike was not detected. The high level spike had a recovery of 83 percent.

We share your concern regarding the negative results and are eager to work with you to improve sample integrity and detectibility.

Very truly yours,

BROWN AND CALDWELL!

Edward Wilson Laboratory Director

EW:ms

BG

BROWN AND CALDWELL

CONSULTING ENGINEERS

D. H. CALDWELL, PE Cheirman T. V. LUTGE, PE President R. C. ABERLEY, PE Exec Vice Pres S. A. FISHER, Vice Pres

ENVIRONMENTAL SCIENCES DIVISION

September 30, 1981

Mr. Terry Cowhey Cowhey Pacific Drilling P.O. Box 11252 Santa Rosa, CA 94506

Page 1 of 2

705-4

TRANSMITTAL OF GASOLINE FINGERPRINTING RESULTS

Date Sampled: As Noted Date Received: As Noted

Log No.	Sample Description/Identification	Results
79D1	Gas Standard; 8/25/81	Standard
79D2	Soil Sample L-1; 8/25/81	None Detected
79M2 -	Soil Sample L-2; 8/26/81	None Detected
80D1	Soil Sample L-3 #1; 8/28/81	None Detected
80D2	Soil Sample L-3 #2; 8/28/81	None Detected
80D3	Soil Sample L-3 #3; 8/28/81	None Detected
81A1	Soil Sample L-4 #1; 8/31/81	None Detected
81A2	Soil Sample L-3 #4; 8/31/81	None Detected
81A3	Gasoline Pump East Oakland; Police Department; 8/31/81	Standard
82W1	Soil Sample L-5 #1; 9/3/81	None Detected
82W2	Soil Sample L-5 #2; 9/3/81	None Detected
82W3	Soil Sample L-6 #1; 9/3/81	None Detected
84E1	Soil Sample L-6 #1; 9/8/81	None Detected
84E2	Soil Sample L-6 #2; 9/8/81	None Detected
84E3	Soil Sample L-6 #3; 9/8/81	None Detected
84E4	Soil Sample L-6 #4; 9/8/81	None Detected

BROWN AND CALDWELL

1255 POWELL STREET EMERYVILLE, CA 94608 (415) 428-2300


Mr. Terry Cowhey September 30, 1981 Page two


Log No.	Sample Description/Identification	Results
85M1	Soil Sample L-7 #1; 9/10/81	None Detected
85M2	Soil Sample L-7 #2; 9/10/81	None Detected
85M3	Soil Sample L-7 #3; 9/10/81	None Detected

Positive identifications would have been made if the concentration of gasoline had been greater than 250 ppm.

Reported	by:		_		. :-	
•		Edward	Wi	lson		
		Laborator	r D	i		

cc Mr. James Ballerino, Cowhey Pacific Drilling





EXPLANATION Exploratory Soil Boring <1/<2/<0.0025/10.0* **EIGHTH STREET** TPH-G/TPH-D/Benzene/Depth in ft. Concentrations in parts per milliom (ppm). Oil & Grease in ppm. <1/<2/<0.0025/5.0 <1/<2/<0.0025/5.0' 15/13/<0.0025/10.0' <1/<4/<0.0025/9.0 <1/50/<0.0025/10.0 <1/<4.1/<0.0025/15.0 B-6 <1/<2/<0.0025/5.0 B-2 <1/<2/<0.0025/18.5⁷ -<1/<2/<0,0025/5.0° <1/<2/<0.0025/15.0 <1/<2/<0.0025/20.0' <1/31/<0.0025/5. 14/410/0.24/10.0 B-5 B-9 <1/<2/<0.0025/54*/5.0 <1/<1/<0.0025/5.0 <1/<2/<0.0025/<50*/9.75 <1/<2/<0.0025/14.5 Scale in Feet Base Map: GeoStrategies, Inc. Site Plan 9/93 PLATE SOIL ANALYTICAL MAP enviros_® Former Shell Service Station 461 Eighth Street E493216 Oakland, California D Drawn By: DML/JLP Date: 8-4-94 Date: 8-15 99 Approved By:

TABLE 1 SOIL ANALYTICAL DATA

Former Shell Service Station 461 Eighth Street Oakland, California WIC 204-5508-6205

						<u> </u>			
CANTE	e vani e	DEPTH	TRUC	COLL IN	DENZENE	TOLYENE	ETHYL	VVERNES	OIL &
SAMPLE DATE	SAMPLE NO.	(FT.)	TPH-G (PPM)	TPH-D (<u>PPM)</u>	BENZENE (PPM)	TOLUENE (PPM)	(PPM)	XYLENES (PPM)	GREASE (PPM)
7/6/94	B1-5.0	5.0	<1	28a	< 0.0025	< 0.0025	<0.0025	< 0.0025	
7/6/94	B1-10.0	10.0	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/6/94	B2-5.0	5.0	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/6/94	B2-15.0	15.0	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/6/94	B2-20.0	20.0	<1	<2	< 0.0025	0.0028b	< 0.0025	0.003b	•
7/6/94	B3-10.0	10.0	<1	`^ 50a	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/6/94	B3-15.0	15.0	<1	4.1	< 0.0025	< 0.0025	< 0.0025	0.025	
7/6/94	B4-5.0	5.0	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/6/94	B4-10.0	10.0	15	13c	< 0.0025	0.037	0.027	0.21	
7/7/94	B5-5.0	5.0	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	54
7/7/94	B5-9.75	9.75	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	<50
7/7/94	B6-5.0	5.0	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/7/94	B6-18.5	18.5	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/7/94	B7-5.0	5.0	<1	31a	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/7/94	B7-10.0	10.0	14	410c	0.24	0.89	0.31	2.0	
7/7/94	B8-5.0	5.0	<i< td=""><td><2</td><td>< 0.0025</td><td>< 0.0025</td><td>< 0.0025</td><td>< 0.0025</td><td></td></i<>	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
<i>7/7/</i> 94	B8-9.0	9.0	<1	<4	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/7/94	B9-5.0	5.0	<1	<1	< 0.0025	< 0.0025	< 0.0025	< 0.0025	
7/7/94	B9-14.5	14.5	<1	<2	< 0.0025	< 0.0025	< 0.0025	< 0.0025	

Abbreviations:

TPH-G = Total Petroleum Hydrocarbons calculated as Gasoline.

TPH-D = Total Petroleum Hydrocarbons calculated as Diesel.

PPM = Parts Per Million.

< x =Not Detected at detection limit of x


--- = Not Analyzed

Notes:

a = The politive result appears to be a heavier hydrocarbon than Diesel.

b = Positive result confirmed by secondary column or GC/MS analysis.

c = The positive result appears to be a lighter hydrocarbon than Diesel.



EXPLANATION Monitoring Well Location ND/0.014/21.5' TPH-Gasoline/Benzene/Depth **EIGHTH STREET** in feet. Concentrations in parts per million (ppm). Note: Soils sampled on Dec. 7 & 8, 1994. ND/ND/6.5' ND/ND/11.5' ND/0.014/21.5' ND/ND/6.5' 760/0.0032/11.5' ND/ND/16.5' _ _ _ ND/ND/21.5' BROADWAY S-9 ND/ND/6.5' ND/ND/11.5' ND/ND/21.5' Scale in Feet Base Map: GeoStrategies, Inc. Site Plan 9/93 **PLATE** SOIL CHEMICAL ANALYTICAL MAP enviros_® Former Shell Service Station 461 Eighth Street Oakland, California 95 216.05 Date: 14-Feb-95 Drawn By: JWN Date: 1-18-95 Approved By:

TABLE 1 SOIL CHEMICAL ANALYTICAL DATA

FORMER SHELL SERVICE STATION 461 8TH STREET, OAKLAND, CALIFORNIA WIC 204-5508-6205

WELL NUMBER	SAMPLE NO.	DEPTH (FT)	SAMPLE : DATE	TPH G (PPM)	BENZENE (PPM)	TOLUENE (PPM)	ETHYL BENZENE (PPM)	XYLENES (PPM)
S-8	S-8-6.5	6.5	7-Dec-94	<1	< 0.0025	<0.0025	<0.0025	<0.0025
	S-8-11.5	11.5	7-Dec-94	<1	< 0.0025	< 0.0025	< 0.0025	< 0.0025
	S-8-21.5	21.5	7-Dec-94	<1	0.014	< 0.0025	< 0.0025	< 0.0025
S-9	S-9-6.5	6.5	7-Dec-94	<1	< 0.0025	<0.0025	<0.0025	< 0.0025
	S-9-11.5	11.5	7-Dec-94	<1	< 0.0025	< 0.0025	< 0.0025	< 0.0025
	S-9-21.5	21.5	7-Dec-94	<1	< 0.0025	< 0.0025	< 0.0025	<0.0025
S-10	S-10-6.5	6.5	7-Dec-94	<1	< 0.0025	< 0.0025	<0.0025	<0.0025
	S-10-11.5	11.5	7-Dec-94	760	0.0032	0.028	6.4	6.9
	S-10-16.5	16.5	7-Dec-94	<1	< 0.0025	< 0.0025	0.0031	<0.0025
	S-10-21.5	21.5	7-Dec-94	<1	< 0.0025	< 0.0025	< 0.0025	<0.0025

Abbreviations:

FT = Measurements in feet

TPH-G = Total Petroleum Hydrodarbons calculated as Gasoline.

PPM = Parts Per Million.

= Not Detected at detection limit of x



ATTACHMENT A

Soil Boring/Well Construction Logs

1

=
GROUNDWATER
 TECHNOLOGY, INC.

Table 1A

ŊΩ	IL	1	IN	G	٠	l	nr.

ray	= 11U.	<u> </u>	וע	1
ation:	L-	1		 -

: <u>Bart/</u> :	Snell
Oakland, Ca	alifornia

Equip. Used: LDH Hughes 50' Auger

Geo1	ogist:	J. Ba	lleri	no t	1				.—
Time	Diam	Bar	At	from	rval to	4	Description of Rock Cuttings	Remarks (e.g. Soft Spots)	SAMPLE #
300	12"			0	41		Artificial Fill -	silt, sand and clay some small Pieces of brick	
				4	7'		Yellow-brown to brown sand		· ·
				7'	10'		Becoming moist, plastic, c	layey sand	
				10'	17'		Increasing in clay: clayey	sand	
	ļ				17'	Lowered Gas	Tech probe: reads 40%	What is you	
				18'	22'	Damp brown	sand yellow & red streaks s		J
				22'	241	continues 1	t. brown sand - water table	begins @ 23'	
300	12"			24'	30'	cont'd sand	and water		2
					!	<u> </u>	Hole cased w/4" PVC; 10'	of .020" screen and 20' of unslotte	PVC
							Gravel packed w/ pea gra	vel	
					1				Sample No. L
				i				į.	
							·		_
									p
	1			,					

,
GROUNDWATER TECHNOLOGY, INC.

Table 1B

DRILLING LOG

Page	No.	1	of	1

Well [Designa	tion:	<u> </u>	2	
·Drille	er: 🔣	Powe1	1		
	Heed:			50 '	Auger

Project: <u>Bart/Shell</u> Name: <u>Oakland, California</u> Date: <u>8/26/81</u>						Well Designation: <u>L- 2</u> Oriller: <u>Powell</u> Equip. Used: LDH Hughes 50' Aug					
Geo1	ogist:		1	🗍 Inter		.	Description of				
Time	Diam	Bar	At	from	to to	, <u>, , , , , , , , , , , , , , , , , , </u>	Rock Cuttings Remarks (e.g. Soft Spots)	SAMPLE #			
0945	12"	 		0	6'		Artificial fill: brown sand- concrete, asphalt and rock				
		,		6'	7'		begin clayey sand: light brown to yellow brown, damp				
				7'	10'		well sorted brown sand, some darker streaks				
				10'	12'		small fraction of clay binder				
				12'	15		loose, unconsolidated uniform sand - moist	5)			
				15'	16'	Gas detecto	r reads 14% slight gasoline smell				
				16'	18'	·	cont'd brown, uniform sand, damp	sample no. L-2			
				18'	19'	gas detecto	r reads greater than 100% - purged with nitrogen				
				19'	23'	no smell co	nt'd damp brown sand - (well sorted)				
				23'	24	begin water	seepage				
				24 '	26'	hole caving	from water				
1530	12"			26'	30 '	hole kept o	pen only to 26'				
				<u> </u>	1		cased with 4" PVC 10' of slotted .020" screen 20' of regular P	VC;			
							gravel packed.				
						Note:	It was necessary to drive casing 4' into sand due to caved con	dition			
							at bottom of hole.				
	ž.					1					



Table 1C

DRILLING LOG

Well Designation: <u>L-3</u>
Driller: <u>Powell</u>

Equip. Used: LDH Hughes 50' Auger

Project: Bart/Shell
Name: Oakland, California
Date: 8-27-81

Geologist: J. Ballerino

Geol	gist:	J. Ba	lleri	<u>no</u> Inte	mu n 1				.
Time	Diam	Bar	At	from	to.	Pressure	Description of Rock Cuttings	Remarks (e.g. Soft Spots)	SAMPLE #
900	12"			0	41		Sand, silt and clay, fill, b	its of debris and rock	
				4'	6'		begin uniform grained, dam	p yellow brown sand	
				6'	9'		some clayey sand		
				9'	11'		cont'd brown sand slight g	asoline smeļl	<u> </u>
							detector reads: 10%		
				11'	12'		damp, uniform sand - some	gray sand	L-3 #1
<u></u>				12'	14'		slight gasoline smell(thin	1mm seam on water of gasoline)	#2
<u></u>				14'	16'		gas detector reads: 10% sa	nd	
				16'	18 1/2	1	gas detector reads: 40% sa	nd	#3
				18 1/2	19 1/2	•	slightly stiff w/ clay - s	and 9.5.	
				19 1/2	21'		some gray sand mostly brow	n sand	
							stronger gasoline smell	•	#4
				21'	27		water infiltration	į.	
				27'	30'		caving in water-logged sar	d -re drill	
							several passes to 37' - ca	sing lowered	
- 1 _ 1 _ 1 _ 1 _ 1 _ 1							10' of slotted 4" PVC; 20	of reg. PVC	-
20	12"				1		Gravel packed -		
	1		}						

	·
	GROUNDWATER TECHNOLOGY, INC.

Bart/Shell

Name: Oakland, California

Project:

Date: 8/31/81

Table 1D

DRILLING LOG

Page No.	1	of	1	
----------	---	----	---	--

Well Designation:	L- 4
Driller: Powell	

Equip. Used: LDH Hughes 50' Auger &

Barrel

Geolo	gist:	J. Ba	llerin	10	_		•		Barrel
Time			1	Inter from	rval , to		Description of Rock Cuttings	Remarks (e.g. Soft Spots)	SAMPLE #
00	12"			0	4'		Fill: sand-silt-clay, rock	, debris, concrete and bricks	
				4'	7'		light brown sand (backfill	?) some clayey sand	
					!		slightly moist clayey sand	- gas detector: Nil	
	•			71	13'		cont'd moist sand - some g	ray sand mixed	
					1 !		detector reads: 3%	•	
				13'	16'		cont'd moist sand - minor	clay detector reads: 5%	
				16'	21'		brown moist sand - layered	gray sand	
				21'	23'		cont'd sand - spoon sample	- wet	L-4 #1
		-		23'	24'		bucket grinding put on aug	er - clear	
				24'	31'	•	caving from water at 22' -	9-5, 7	
					!		cont'd drilling out to 35'	+ · J	
					f f	·	able to place 30' of casin	3:	,
					1		10' slotted PVC @ .020"		
					•		20' regular PVC		
500	12"				!		Gravel packed - no evidenc	of gasoline	.*
					!		·		
					 				
		-			 				



Project: <u>Bart/Shell</u>
Name: <u>Oakland, California</u>
Date: <u>9/2/81</u>

Table 1E

DRILLING LOG

Page No.	1 of	1
----------	------	---

Well D	esigna	tion:	<u>L- 5</u>	i	
Drille	r:	Powe1	1		
			Hughes	50'	Auger

Geologist: J. Ballerino

	l i		1	📊 Inter			Description of	1	ı
ime	Diam	Bar	At	from	to	<u> </u>	Rock Cuttings	Remarks (e.g. Soft Spots)	SAMPLE #
0	12"			0	5'		Inside drop inlet - storm	drain broadway	
		·	<u></u>				invert elev: -5' below st	eet level	· · · · · · · · · · · · · · · · · · ·
· 		`		5'	71		fill sand - gas detector:	7%	
				7'	13'		moist brown sand; gas dete	ctor: 10%	
		-		13'	14'		begin wet sand - smells of	gasoline	
				14'	15'		gas detector: 15%		#1
				15'	19'		spoon sample-loose sand		
					19'		detector reads: 50%		#2
				19'	22'		sand saturated with gasoli	ne; reads: 80% (4.5)	
				22'	23'		encountered water - begin	revert	
				23'	27'		caving sand - revert not h	olding well	
				27'	32'		cont'd sand - in water tal	le	
							strong gasoline fumes		
				32'	40'		becoming more compact sand		<u> </u>
							some clay- (gray to gray-g	reen)	
				40'	42'		dense, stiff clay- bay mud	- bottom hole	
							cased with 20' slotted PVC	.020" (4")	
)	12"					-	17' regular PVC & gravel p		<u> </u>
	·			~				wat at at	

	GROUNDWATER TECHNOLOGY, INC.

Project: <u>Bart/Shell</u>

Table 1F

DRILLING LOG

Page	No.	L	of	1

UG		
	 Well Designation: $L-6$	
	Driller: Powell	

Equip. Used: LDH Hughes 50' Auger

Name: Oakland, California
Date: 9-3-81 & 9-8-81

Geologist: J. Ballerino

	ī	J. Bai	1	📊 Inter		1	Description of	1
Time	Diam	Bar	At	from	to		Rock Cuttings Remarks (e.g. Soft Spots)	SAMPLE #
000	12"			0	2'		Street concrete and old cobblestones	
				2'	4'	i	mixed fill and cobbles	
					-41		begin brown sand -	
				41	10'		sand fill some small pieces brick and rock	
				10'	16'		cont'd sand and clayey sand - moist	
					16'		slight gasoline smell ? - stopped	#1
0	·				! ! !		hole 9-3-81 to prepare revert	,
0	12"	9-8-81		16'	20'		cont'd sand, gas detector reads: 35%	#2 0
				20 '	24'		slightly clayey sand	
					24'	,	top of water table - caving sand (q,5)	#3
				24'	30'		revert introduced	
				30'	34'		wet gray-brown clayey sand	#4
				34'	40'		sand to clay - top of bay mud	
				40'	42'		stiff, dense clay - bay mud	
					1 1 1		placed 40' of casing: 20' slotted PVC .020'	
					1		and 20' reg. PVC - collar of casing 2" below street level	
00	12"						Gravel-packed	
					1			<u> </u>

	9	•
		GROUNDWATER
	السحط	TECHNOLOGY, INC.

Project: <u>Bart/Shell</u>
Name: <u>Oakland, California</u>
Date: 9-10-81

Table 1G

DRILLING LOG

Page No.	1	of	1
----------	---	----	---

Well Designation:	L- 7
Driller: Powell	


Equip. Used: LDH Hughes 50' Auger


Geologist: J. Ballerino							Equip. Used: LDH Hugh	es 50 Auger			
Time	Diam	Bar	At	Inte	rval , to	1	Description of	1			
1.030	12"	i		0	5'	<u> </u>	Rock Cuttings Remarks (e.g. Soft Spots)	SAMPLE #			
1030	12	,		 	1		2" asphalt - damp, loose light brown sand				
	-		ļ	5'	12'	· · · · · · · · · · · · · · · · · · ·	cont'd loose brown sand				
	<u> </u>	<u>, </u>	ļ	12'	16'		gas-detector: Nil - moist sand				
	<u> </u>			16'	17'		spoon sample - no gasoline smell	#1			
				17'	18'		wet sand becoming slightly clayey-mottled				
					18'		top of water table caving sand				
				18'	24'		cont'd caving - placed revert				
					24'		much water - "quicksand"	#2 ^			
				24'	34'		cont'd slow drilling with revert				
					34'	·	sand - brown - some gray revert "weak"	#3			
				34 '	40'		becoming clayey sand - (no gasoline smell)				
.700	12"			40'	41'	-1	end hole in clayey sand - gray to brown	1			
						· · · · · · · · · · · · · · · · · · ·	cased with 20' slotted PVC .020" (4")				
							and 20' regular PVC				
<u> </u>						·	Gravel packed				
								-			


		.
		GROUNDWATER TECHNOLOGY, INC.
	CON	 IA ABAUNDWATER AEAÍ AAIST


Project:	Shell - Bart
Date:	

te:						CONSU	LTING GROU	INDWATER G	EOLOGISTS			Wall.			.*
JCT THICK	NESS KE	<u>Y</u>				_				•		Well: _	<u></u>		-
ight odo			D	epth to	water me	asured i	n Monito	ring Well	Ls				•		
in film ight odo oduct or			1	/ 2	3	/ 4	./ 5	6	7 7	7	7	7	7		7
oduct or wage odo		ELEV.	33.541	32.69'/3	1.94'	31.94'/	28.96'	28.10'	20.04'/	7	$\overline{}$		'/	'	/
.wage out	_					No Ele	ote: ev. is	. /		tal Dept	th /				
				. /	01/07.5	/stre	eet grade			Drilled			/ '		
] Date	Note	30.4	45 / 30.3	31.3	8 / 27.5	5'/20.8	40.3	5' / 38.5)5/						/
8-28-81	DŢW	23.75	22.40	22.72		~~									
	DTOP	23.75	22.40	22.72	,	1	1.			51	11 1		,	 	-
	Product Thick	01,	02	02		 	 	 	<u> </u>	1 2 N	old sh	مها جرا	ematics		4
<u> </u>			 		 	<u> </u>	<u> </u>	<u> </u>		م کی	ells of	3 165			
	Elev. of water	9.79	10.3'	9.22'		<u> </u>				W	re are	Seneu	v set?		۶
]					,	, .		<u> </u>		
9-14	DTW	23.82	22.58'	22.83'	24.5'	21.01'	21.48'	12.62'							-
•	DTOP	23.82'	22.58'	22.831	24.5'	21.01'	21.48'	12.62'							
	Product Thick	01	01	01	0	01	03	. 03		ļ 					1
	Elev. of	9.72'	10.11'	9.11'	7.44'	7.95'	6.62'	7.42'			`				1
													,		7
10-2	DTW	23.83'	22.63	22.75	24.61	21.20'	21.51'	14.72'			·				1
	DTOP	23.83'	22.63	22.75	24.6'	21.20'	21.51'	14.72							1
	Product Thick	01	01	02	04	01	0	0 3						_	1
	Elev. of	9.71'	10.06'	9.16'	7.34'	7.76'	6.59'	5.32'							1
					<u> </u>	j		j –							1
			 	 -		 	 								1
1	1	l		[<u> </u>		1	1	l l		<u> </u>		[ه پستین	ــــــــــــــــــــــــــــــــــــــ











ATTACHMENT B

Site Assessment Analytical Data

1