



**Shell Oil Products US**

September 4, 2003

Scott Seery  
Alameda County Health Care Services Agency  
1131 Harbor Bay Parkway, Suite 250  
Alameda, California 94502-6577

Alameda County  
SEP 09 2003  
Environmental Health

**Subject: Shell-branded Service Station**  
4226 First Street  
Pleasanton, California

Dear Mr. Seery:

Attached for your review and comment is a copy of the *Third Quarter 2003 Monitoring Report* for the above referenced site. Upon information and belief, I declare, under penalty of perjury, that the information contained in the attached document is true and correct.

As always, please feel free to contact me directly at (559) 645-9306 with any questions or concerns.

Sincerely,

**Shell Oil Products US**

*Karen Petryna*

Karen Petryna  
Sr. Environmental Engineer

September 4, 2003

Scott Seery  
Alameda County Health Care Services Agency  
1131 Harbor Bay Parkway, Suite 250  
Alameda, California 94502-6577

Re: **Third Quarter 2003 Monitoring Report**  
Shell-branded Service Station  
4226 First Street  
Pleasanton, California  
Incident #98995840  
Cambria Project #245-0523-002



Dear Mr. Seery:

On behalf of Equilon Enterprises LLC dba Shell Oil Products US, Cambria Environmental Technology, Inc. (Cambria) is submitting this groundwater monitoring report in accordance with the reporting requirements of 23 CCR 2652d.

## **THIRD QUARTER 2003 ACTIVITIES**

**Groundwater Monitoring:** Blaine Tech Services, Inc. (Blaine) of San Jose, California gauged and sampled the site wells, calculated groundwater elevations, and compiled the analytical data. Cambria prepared a site vicinity map (Figure 1) and a groundwater elevation contour map (Figure 2). Blaine's report, presenting the laboratory report and supporting field documents, is included as Attachment A.

**Oxygen Releasing Compound (ORC):** Cambria will oversee ORC installation in wells MW-1 and MW-2 to enhance natural biological degradation of hydrocarbons.

## **ANTICIPATED FOURTH QUARTER 2003 ACTIVITIES**

**Groundwater Monitoring:** Blaine will gauge and sample all site wells and tabulate the data. Cambria will prepare a monitoring report.

**Cambria  
Environmental  
Technology, Inc.**

5900 Hollis Street  
Suite A  
Emeryville, CA 94608  
Tel (510) 420-0700  
Fax (510) 420-9170

**CLOSING**


We appreciate the opportunity to work with you on this project. Please call Matt Derby at (510) 420-3332 if you have any questions or comments.

Sincerely,  
**Cambria Environmental Technology, Inc**



Anni Kreml  
Senior Staff Scientist

Matthew W. Derby, P.E.  
Senior Project Engineer



Figures: 1 - Vicinity Map  
2 - Groundwater Elevation Contour Map

Attachment: A - Blaine Groundwater Monitoring Report and Field Notes

cc: Karen Petryna, Shell Oil Products US, P.O. Box 7869, Burbank, CA 91510-7869  
Douglas E & Mary M Safreno, 1627 Vineyard Avenue, Pleasanton, CA 94566-6389

G:\Pleasanton 4226 First\Qm\3q03\3q03qm.doc




FIGURE 1



### Shell-branded Service Station

4226 First Street  
Pleasanton, California  
Incident #98995840



C A M B R I A

### Vicinity Map




FIGURE  
**2**

**Shell-branded Service Station**  
 4226 First Street  
 Pleasanton, California  
 Incident #98995840



C A M B R I A

**Groundwater Elevation  
Contour Map**

July 29, 2003

D:\PLEASANTON\GIZMOS\FST\F04\F04R0306.MXD

**ATTACHMENT A**  
**Blaine Groundwater Monitoring Report**  
**and Field Notes**

**BLAINE**  
TECH SERVICES, INC.



1680 ROGERS AVENUE  
SAN JOSE, CA 95112-1105  
(408) 573-7771 FAX  
(408) 573-0555 PHONE  
CONTRACTOR'S LICENSE #746684  
www.blainetech.com

August 13, 2003

Karen Petryna  
Shell Oil Products US  
P.O. Box 7869  
Burbank, CA 91510-7869

Third Quarter 2003 Groundwater Monitoring at  
Shell-branded Service Station  
4226 First Street  
Pleasanton, CA

Monitoring performed on July 29, 2003

---

Groundwater Monitoring Report 030729-MM-3

This report covers the routine monitoring of groundwater wells at this Shell-branded facility. In accordance with standard procedures that conform to Regional Water Quality Control Board requirements, routine field data collection includes depth to water, total well depth, thickness of any separate immiscible layer, water column volume, calculated purge volume (if applicable), elapsed evacuation time (if applicable), total volume of water removed (if applicable), and standard water parameter instrument readings. Sample material is collected, contained, stored, and transported to the laboratory in conformance with EPA standards. Purgewater (if applicable) is, likewise, collected and transported to the Martinez Refining Company.

Basic field information is presented alongside analytical values excerpted from the laboratory report in the cumulative table of **WELL CONCENTRATIONS**. The full analytical report for the most recent samples and the field data sheets are attached to this report.

At a minimum, Blaine Tech Services, Inc. field personnel are certified on completion of a forty-hour Hazardous Materials and Emergency Response training course per 29 CFR 1910.120. Field personnel are also enrolled in annual eight-hour refresher courses.

Blaine Tech Services, Inc. conducts sampling and documentation assignments of this type as an independent third party. Our activities at this site consisted of objective data and sample collection only. No interpretation of analytical results, defining of hydrological conditions or formulation of recommendations was performed.

Please call if you have any questions.

Yours truly,

Leon Gearhart  
Project Coordinator

LG/jt

attachments: Cumulative Table of WELL CONCENTRATIONS  
Certified Analytical Report  
Field Data Sheets

cc: Anni Kreml  
Cambria Environmental Technology, Inc.  
5900 Hollis Street, Suite A  
Oakland, CA 94608



**WELL CONCENTRATIONS**  
**Shell-branded Service Station**  
**4226 First Street**  
**Pleasanton, CA**

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft)	GW Elevation (MSL)
---------	------	----------------	-------------	-------------	-------------	-------------	---------------------	---------------------	--------------	---------------------------	--------------------------

MW-1	06/16/1999	NA	NA	NA	NA	NA	NA	NA	371.20	37.81	333.39
MW-1	06/30/1999	89.0	5.89	<0.500	<0.500	0.652	<5.00	NA	371.20	33.65	337.55
MW-1	09/24/1999	1,560	473	<10.0	<10.0	22.8	<2.50	NA	371.20	37.04	334.16
MW-1	12/08/1999	1,020	375	<5.00	<5.00	15.2	<50.0	NA	371.20	36.79	334.41
MW-1	02/10/2000	523	106	<5.00	<5.00	31.8	2.90	NA	371.20	34.90	336.30
MW-1	05/17/2000	<50.0	<0.500	<0.500	<0.500	<0.500	37.0	29.5	371.20	32.55	338.65
MW-1	08/03/2000	808	290	<2.50	<2.50	8.90	<12.5	NA	371.20	39.13	332.07
MW-1	10/31/2000	507	250	0.962	<0.500	23.5	3.76	NA	371.20	37.91	333.29
MW-1	03/01/2001	<50.0	<0.500	<0.500	<0.500	<0.500	74.6	NA	371.20	39.60	331.60
MW-1	05/30/2001	780	280	<2.0	<2.0	11	NA	<2.0	371.20	39.53	331.67
MW-1	08/02/2001	1,900	580	<2.5	<2.5	12	NA	<25	371.20	39.61	331.59
MW-1	12/06/2001	840	190	<0.50	<0.50	13	NA	<5.0	371.20	39.63	331.57
MW-1	02/05/2002	2,700	650	<2.5	<2.5	7.2	NA	<25	371.20	35.53	335.67
MW-1	06/17/2002	2,500	550	<2.0	<2.0	5.9	NA	<20	371.20	39.29	331.91
MW-1	07/25/2002	690	130	<0.50	<0.50	4.4	NA	18	371.20	39.39	331.81
MW-1	11/14/2002	400	31	<0.50	<0.50	2.7	NA	27	371.20	40.00	331.20
MW-1	02/12/2003	840	0.85	<0.50	<0.50	<0.50	NA	40	371.20	32.92	338.28
MW-1	05/14/2003	680	190	<2.5	<2.5	<5.0	NA	95	371.20	32.57	338.63
<b>MW-1</b>	<b>07/29/2003</b>	<b>870</b>	<b>190</b>	<b>&lt;2.5</b>	<b>&lt;2.5</b>	<b>&lt;5.0</b>	<b>NA</b>	<b>150</b>	<b>371.20</b>	<b>33.82</b>	<b>337.38</b>

MW-2	02/03/2000	NA	NA	NA	NA	NA	NA	NA	372.40	32.65	339.75
MW-2	02/07/2000	NA	NA	NA	NA	NA	NA	NA	372.40	35.51	336.89
MW-2	02/10/2000	<50.0	<0.500	<0.500	<0.500	<0.500	2.61	NA	372.40	36.62	335.78
MW-2	05/17/2000	120	4.09	<0.500	<0.500	<0.500	29.0	NA	372.40	32.14	340.26
MW-2	08/03/2000	<50.0	0.692	<0.500	<0.500	<0.500	40.5	36.6b	372.40	32.42	339.98
MW-2	10/31/2000	<50.0	<0.500	<0.500	<0.500	<0.500	57.4	44.8c	372.40	33.02	339.38
MW-2	03/01/2001	173	1.64	1.65	2.86	3.97	127	167	372.40	32.54	339.86
MW-2	05/30/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	170	372.40	32.42	339.98
MW-2	08/02/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	160	372.40	32.55	339.85

**WELL CONCENTRATIONS**  
**Shell-branded Service Station**  
**4226 First Street**  
**Pleasanton, CA**

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft)	GW Elevation (MSL)
MW-2	12/06/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	170	372.40	33.15	339.25
MW-2	02/05/2002	<50	0.72	<0.50	<0.50	1.7	NA	170	372.40	32.29	340.11
MW-2	06/17/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	260	372.40	32.63	339.77
MW-2	07/25/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	280	372.40	32.80	339.60
MW-2	11/14/2002	120	13	9.0	3.8	14	NA	430	372.40	33.31	339.09
MW-2	02/12/2003	<100	<1.0	<1.0	<1.0	<1.0	NA	430	372.40	32.15	340.25
MW-2	05/14/2003	<250	<2.5	<2.5	<2.5	<5.0	NA	470	372.40	32.01	340.39
<b>MW-2</b>	<b>07/29/2003</b>	<b>&lt;250</b>	<b>&lt;2.5</b>	<b>&lt;2.5</b>	<b>&lt;2.5</b>	<b>&lt;5.0</b>	<b>NA</b>	<b>670</b>	<b>372.40</b>	<b>32.51</b>	<b>339.89</b>
MW-3	02/03/2000	NA	NA	NA	NA	NA	NA	NA	375.05	32.06	342.99
MW-3	02/07/2000	NA	NA	NA	NA	NA	NA	NA	375.05	32.57	342.48
MW-3	02/10/2000	180	5.12	<0.500	<0.500	0.714	26.8	21.5a	375.05	32.77	342.28
MW-3	05/17/2000	1,360	414	<5.00	<5.00	17.6	<25.0	NA	375.05	31.00	344.05
MW-3	08/03/2000	<50.0	0.536	<0.500	<0.500	<0.500	22.0	NA	375.05	31.03	344.02
MW-3	10/31/2000	<50.0	<0.500	<0.500	<0.500	<0.500	31.1	NA	375.05	31.28	343.77
MW-3	03/01/2001	384	172	0.815	<0.500	8.00	5.16	NA	375.05	31.21	343.84
MW-3	05/30/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	110	375.05	31.02	344.03
MW-3	08/02/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	93	375.05	30.94	344.11
MW-3	12/06/2001	110	<0.50	<0.50	<0.50	2.3	NA	180	375.05	31.28	343.77
MW-3	02/05/2002	<50	0.89	0.60	<0.50	2.1	NA	130	375.05	31.12	343.93
MW-3	06/17/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	72	375.05	31.21	343.84
MW-3	07/25/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	81	375.05	30.96	344.09
MW-3	11/14/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	60	375.05	31.44	343.61
MW-3	02/12/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	43	375.05	31.28	343.77
MW-3	05/14/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	24	375.05	31.20	343.85
<b>MW-3</b>	<b>07/29/2003</b>	<b>&lt;50</b>	<b>&lt;0.50</b>	<b>&lt;0.50</b>	<b>&lt;0.50</b>	<b>&lt;1.0</b>	<b>NA</b>	<b>21</b>	<b>375.05</b>	<b>31.29</b>	<b>343.76</b>
TB-1	02/12/2003	Well inaccessible		NA	NA	NA	NA	NA	NA	NA	NA
TB-1	02/28/2003	NA	NA	NA	NA	NA	NA	NA	NA	12.54	NA

**WELL CONCENTRATIONS**  
**Shell-branded Service Station**  
**4226 First Street**  
**Pleasanton, CA**

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)
TB-1	05/14/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<5.0	NA	12.31	NA
TB-2	02/12/2003	Well inaccessible		NA	NA	NA	NA	NA	NA	NA	NA
TB-2	02/28/2003	NA	NA	NA	NA	NA	NA	NA	NA	12.56	NA
TB-2	05/14/2003	Insufficient water		NA	NA	NA	NA	NA	NA	12.54	NA
TB-3	02/12/2003	Well dry	NA	NA	NA	NA	NA	NA	NA	NA	NA
TB-3	02/28/2003	Well dry	NA	NA	NA	NA	NA	NA	NA	NA	NA
TB-3	05/14/2003	Well dry	NA	NA	NA	NA	NA	NA	NA	NA	NA
TB-4	02/12/2003	Well dry	NA	NA	NA	NA	NA	NA	NA	NA	NA
TB-4	02/28/2003	Well dry	NA	NA	NA	NA	NA	NA	NA	NA	NA
TB-4	05/14/2003	Well dry	NA	NA	NA	NA	NA	NA	NA	NA	NA

Abbreviations:

TPPH = Total petroleum hydrocarbons as gasoline by EPA Method 8260B; prior to May 30, 2001, analyzed by EPA Method 8015.

BTEX = Benzene, toluene, ethylbenzene, xylenes by EPA Method 8260B; prior to May 30, 2001, analyzed by EPA Method 8020.

MTBE = Methyl-tertiary-butyl ether

TOC = Top of Casing Elevation

GW = Groundwater

ug/L = Parts per billion

MSL = Mean sea level

ft = Feet

<n = Below detection limit

NA = Not applicable

**WELL CONCENTRATIONS**  
**Shell-branded Service Station**  
**4226 First Street**  
**Pleasanton, CA**

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)
---------	------	----------------	-------------	-------------	-------------	-------------	---------------------	---------------------	--------------	----------------------------	--------------------------

Notes:

a = Sample was analyzed outside of the EPA recommended holding time.

b = Concentration is an estimate value above the linear quantitation range.

c = The result reported was generated out of time. The sample was originally run within hold time, but needed to be re-analyzed.

Well MW-1 surveyed on May 4, 1999, by Virgil Chavez Land Surveying of Vallejo, California.

Site surveyed on March 19, 2000, by Virgil Chavez Land Surveying of Vallejo, California.

Site surveyed on January 15, 2002, by Virgil Chavez Land Surveying of Vallejo, California.

**Blaine Tech Services, Inc.**

August 12, 2003

1680 Rogers Avenue  
San Jose, CA 95112-1105  
Attn.: Leon Gearhart  
Project#: 030729-MM3  
Project: 98995840  
Site: 4226 First Street, Pleasanton

Dear Mr. Gearhart,


Attached is our report for your samples received on 07/30/2003 13:20  
This report has been reviewed and approved for release. Reproduction of this report  
is permitted only in its entirety.

Please note that any unused portion of the samples will be discarded after  
09/13/2003 unless you have requested otherwise.

We appreciate the opportunity to be of service to you. If you have any questions,  
please call me at (925) 484-1919.

You can also contact me via email. My email address is: [tgranicher@stl-inc.com](mailto:tgranicher@stl-inc.com)

Sincerely,



Tod Granicher  
Project Manager

**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue

San Jose, CA 95112-1105

Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3

98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

**Samples Reported**

Sample Name	Date Sampled	Matrix	Lab #
MW-1	07/29/2003 13:11	Water	1
MW-2	07/29/2003 13:35	Water	2
MW-3	07/29/2003 13:25	Water	3

Severn Trent Laboratories, Inc.

STL San Francisco \* 1220 Quarry Lane, Pleasanton, CA 94566

Tel 925 484 1919 Fax 925 484 1096 \* www.stl-inc.com \* CA DHS ELAP# 2496

08/08/2003 15:09

**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue

San Jose, CA 95112-1105

Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3

98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

Prep(s): 5030B	Test(s): 8260FAB
Sample ID: MW-1	Lab ID: 2003-07-0884 - 1
Sampled: 07/29/2003 13:11	Extracted: 8/8/2003 01:28
Matrix: Water	QC Batch#: 2003/08/07-2C.65
Analysis Flag: o ( See Legend and Note Section )	

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	870	250	ug/L	5.00	08/08/2003 01:28	
Benzene	190	2.5	ug/L	5.00	08/08/2003 01:28	
Toluene	ND	2.5	ug/L	5.00	08/08/2003 01:28	
Ethylbenzene	ND	2.5	ug/L	5.00	08/08/2003 01:28	
Total xylenes	ND	5.0	ug/L	5.00	08/08/2003 01:28	
Methyl tert-butyl ether (MTBE)	150	2.5	ug/L	5.00	08/08/2003 01:28	
<b>Surrogates(s)</b>						
1,2-Dichloroethane-d4	109.4	76-130	%	5.00	08/08/2003 01:28	
Toluene-d8	104.6	78-115	%	5.00	08/08/2003 01:28	

**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue  
San Jose, CA 95112-1105  
Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3  
98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

Prep(s): 5030B	Test(s): 8260FAB
Sample ID: MW-2	Lab ID: 2003-07-0884 - 2
Sampled: 07/29/2003 13:35	Extracted: 8/8/2003 01:51
Matrix: Water	QC Batch#: 2003/08/07-2C.65
Analysis Flag: o ( See Legend and Note Section )	

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	ND	250	ug/L	5.00	08/08/2003 01:51	
Benzene	ND	2.5	ug/L	5.00	08/08/2003 01:51	
Toluene	ND	2.5	ug/L	5.00	08/08/2003 01:51	
Ethylbenzene	ND	2.5	ug/L	5.00	08/08/2003 01:51	
Total xylenes	ND	5.0	ug/L	5.00	08/08/2003 01:51	
Methyl tert-butyl ether (MTBE)	670	2.5	ug/L	5.00	08/08/2003 01:51	
<b>Surrogates(s)</b>						
1,2-Dichloroethane-d4	104.5	76-130	%	5.00	08/08/2003 01:51	
Toluene-d8	106.6	78-115	%	5.00	08/08/2003 01:51	



**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue

San Jose, CA 95112-1105

Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3

98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

Prep(s):	5030B	Test(s):	8260FAB
Sample ID:	MW-3	Lab ID:	2003-07-0884 - 3
Sampled:	07/29/2003 13:25	Extracted:	8/8/2003 02:13
Matrix:	Water	QC Batch#:	2003/08/07-2C-65

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	ND	50	ug/L	1.00	08/08/2003 02:13	
Benzene	ND	0.50	ug/L	1.00	08/08/2003 02:13	
Toluene	ND	0.50	ug/L	1.00	08/08/2003 02:13	
Ethylbenzene	ND	0.50	ug/L	1.00	08/08/2003 02:13	
Total xylenes	ND	1.0	ug/L	1.00	08/08/2003 02:13	
Methyl tert-butyl ether (MTBE)	21	0.50	ug/L	1.00	08/08/2003 02:13	
<b>Surrogates(s)</b>						
1,2-Dichloroethane-d4	98.7	76-130	%	1.00	08/08/2003 02:13	
Toluene-d8	107.5	78-115	%	1.00	08/08/2003 02:13	

**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue  
San Jose, CA 95112-1105  
Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3  
98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

Batch QC Report					
Prep(s): 5030B				Test(s): 8260FAB	
Method Blank		Water		QC Batch # 2003/08/07-2C.65	
MB: 2003/08/07-2C.65-059				Date Extracted: 08/07/2003 20:59	

Compound	Conc.	RL	Unit	Analyzed	Flag
Gasoline	ND	50	ug/L	08/07/2003 20:59	
Benzene	ND	0.5	ug/L	08/07/2003 20:59	
Toluene	ND	0.5	ug/L	08/07/2003 20:59	
Ethylbenzene	ND	0.5	ug/L	08/07/2003 20:59	
Total xylenes	ND	1.0	ug/L	08/07/2003 20:59	
Methyl tert-butyl ether (MTBE)	ND	0.5	ug/L	08/07/2003 20:59	
<b>Surrogates(s)</b>					
1,2-Dichloroethane-d4	90.9	76-130	%	08/07/2003 20:59	
Toluene-d8	104.0	78-115	%	08/07/2003 20:59	

**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue

San Jose, CA 95112-1105

Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3

98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

Batch QC Report									
Prep(s): 5030B					Test(s): 8260FAB				
Laboratory Control Spike			Water			QC Batch # 2003/08/07-2C.65			
LCS	2003/08/07-2C.65-060		Extracted: 08/07/2003			Analyzed: 08/07/2003 20:13			
LCSD	2003/08/07-2C.65-036		Extracted: 08/07/2003			Analyzed: 08/07/2003 20:36			

Compound	Conc. ug/L		Exp.Conc.	Recovery %		RPD	Ctrl.Limits %		Flags	
	LCS	LCSD		LCS	LCSD		%	Rec.	RPD	LCS
Benzene	31.8	26.1	25	127.2	104.4	19.7	69-129	20		
Toluene	31.3	26.3	25	125.2	105.2	17.4	70-130	20		
Methyl tert-butyl ether (MTBE)	25.4	22.8	25	101.6	91.2	10.8	65-165	20		
<b>Surrogates(s)</b>										
1,2-Dichloroethane-d4	501	476	500	100.2	95.2		76-130			
Toluene-d8	546	515	500	109.2	103.0		78-115			

**Gas/BTEX/MTBE by 8260B (C6-C12)**

Blaine Tech Services, Inc.

Attn.: Leon Gearhart

1680 Rogers Avenue

San Jose, CA 95112-1105

Phone: (408) 573-0555 Fax: (408) 573-7771

Project: 030729-MM3

98995840

Received: 07/30/2003 13:20

Site: 4226 First Street, Pleasanton

**Legend and Notes**

**Analysis Flag**

o

Reporting limits were raised due to high level of analyte present in the sample.

Lab Identification (if necessary):

Address:

City, State, Zip:

Shell Project Manager to be Invoiced:

Karen Petryna

- SCIENCE & ENGINEERING
- TECHNICAL SERVICES
- CRMT HOUSTON

2003-07-0884

INCIDENT NUMBER (S&E ONLY)

9 8 9 9 5 8 4 0

SAP or CRMT NUMBER (S/CRMT)

DATE: 7/29/03

PAGE: 1 of 1

10470

**CAMPUS COMPANY:** Blaine Tech Services  
**LOG CODE:** BTSS  
**SITE ADDRESS (Street and City):** 4226 First Street, Pleasanton  
**GLOBAL ID NO.:** T0600101259  
**ADDRESS:** 1680 Rogers Avenue, San Jose, CA 95112  
**BCF DELIVERABLE TO (Responsible Party or Company):** Ann Kroml  
**PHONE NO.:** 510-420-3336  
**E-MAIL:** ShellOaklandEDF@cambria-env.com  
**CONSULTANT PROJECT NO.:** STS: 030729-AM-3  
**CONTACT PERSON (Print):** MIKE McNAMARA  
**LAB USE ONLY:**

**TURNAROUND TIME (BUSINESS DAYS):**  
 10 DAYS  5 DAYS  72 HOURS  48 HOURS  24 HOURS  LESS THAN 24 HOURS

LA - RWQCB REPORT FORMAT  LIST AGENCY

**GC/MS MTBE CONFIRMATION:** HIGHEST \_\_\_\_\_ HIGHEST per BORING \_\_\_\_\_ ALL \_\_\_\_\_

**SPECIAL INSTRUCTIONS OR NOTES:** CHECK BOX IF EDD IS NOT NEEDED

REQUESTED ANALYSIS

LAB USE ONLY	Field Sample Identification	SAMPLING		MATRIX	NO. OF CONT.	TPH - Gas, Purgeable	BTEX	MTBE (R03 RB - Sppt RL)	MTBE (R260B - 0.5ppb RL)	Oxygenates (S) by (R260B)	Ethanol (R260B)	Methanol	1,2-DCA (R260B)	EDB (R260B)	TPH - Diesel, Extractable (R05m)
		DATE	TIME												
	Mh-1	7/29/03	1314	GL	3	X	X	X	X						
	Mh-2		1325		3	X	X	X	X						
	Mh-3		1325		3	X	X	X	X						

FIELD NOTES:  
Container/Preservative or PID Readings or Laboratory Notes

6.0 °C

TEMPERATURE ON RECEIPT °C

**Relinquished by (Signature):** [Signature] **Received by (Signature):** David Chen  
**Relinquished by (Signature):** David Chen **Received by (Signature):** [Signature] STV SF  
**Relinquished by (Signature):** [Signature] **Received by (Signature):** [Signature]

**Date:** 7-30 **Time:** 1:20  
**Date:** 7-30 **Time:** 3:55

DISTRIBUTION: White with final report, Green to P/Fs, Yellow and Pink to Client.

OS&O Graphics (714) 858-5702

# WELL GAUGING DATA

Project # 030724-MM3 Date 7/29/03 Client Shell

Site 4226 First St., Pleasanton

Well ID	Well Size (in.)	Sheen / Odor	Depth to Immiscible Liquid (ft.)	Thickness of Immiscible Liquid (ft.)	Volume of Immiscibles Removed (ml)	Depth to water (ft.)	Depth to well bottom (ft.)	Survey Point: TOB or TOC
Mw-1	2					33.82	57.22	TOC
Mw-2	4					32.51	45.87	↵
Mw-3	4					31.29	34.61	↵

## SHELL WELL MONITORING DATA SHEET

BTS #: 030724-MM3	Site: 4226 First St., Pleasanton
Sampler: MM	Date: 7/27/03
Well I.D.: MW-1	Well Diameter: (2) 3 4 6 8
Total Well Depth (TD): 57.22	Depth to Water (DTW): 33.82
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 23.4 + 33.82 = 38.50	

Purge Method: Bailer      Water      Sampling Method: Bailer  
 Disposable Bailer      Peristaltic      Disposable Bailer  
 Positive Air Displacement      Extraction Pump      Extraction Port  
 Electric Submersible      Other \_\_\_\_\_      Dedicated Tubing

$3.7 \text{ (Gals.)} \times 3 = 11.1 \text{ Gals.}$	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius<sup>2</sup> * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius <sup>2</sup> * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius <sup>2</sup> * 0.163														
1 Case Volume      Specified Volumes      Calculated Volume																	

Time	Temp (°F)	pH	Cond (mS or μS)	Turbidity (NTUs)	Gals. Removed	Observations
1258	74.7	6.5	1663	529	3.7	cloudy (tan)
1302	72.6	6.5	1712	427	7.4	" "
1306	72.5	6.5	1722	270	11.1	Slightly cloudy

Did well dewater?    Yes    No    Gallons actually evacuated: 11.1

Sampling Date: 7/29/03    Sampling Time: 1311    Depth to Water: 48.40 *Site departure*

Sample I.D.: MW-1    Laboratory: STL    Other \_\_\_\_\_

Analyzed for: (TPH-G) (BTEX) (MTBE) TPH-D    Other: \_\_\_\_\_

EB I.D. (if applicable): \_\_\_\_\_ @ \_\_\_\_\_ Time    Duplicate I.D. (if applicable): \_\_\_\_\_

Analyzed for: TPH-G    BTEX    MTBE    TPH-D    Other: \_\_\_\_\_

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

## SHELL WELL MONITORING DATA SHEET

BTS #: 030729-MM3	Site: 4226 First St. Pleasanton
Sampler: MM	Date: 7/27/03
Well I.D.: MW-2	Well Diameter: 2 3 <u>4</u> 6 8
Total Well Depth (TD): 45.87	Depth to Water (DTW): 32.51
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: <sup>13.26</sup> 35.18	

Purge Method: Bailer      Waterra      Sampling Method: Bailer  
 Disposable Bailer      Peristaltic      Disposable Bailer  
 Positive Air Displacement      Extraction Pump      Extraction Port  
Electric Submersible      Other \_\_\_\_\_      Dedicated Tubing

Other: \_\_\_\_\_

8.7 (Gals.) X 3 = 26.1 Gals.  
 Case Volume      Specified Volumes      Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius <sup>2</sup> * 0.163

Time	Temp (°F)	pH	Cond (mS or <u>µS</u> )	Turbidity (NTUs)	Gals. Removed	Observations
1240	74.0	6.5	1224	19	9.0	clear
1242	72.1	6.5	1233	34	18.0	"
1244	72.3	6.5	1248	19	27.0	"
						DTW = 43.70

Did well dewater? Yes No Gallons actually evacuated: 27.0

Sampling Date: 7/24/03      Sampling Time: 1335      Depth to Water: 40.89 *site departure*

Sample I.D.: MW-2      Laboratory: STL      Other: \_\_\_\_\_

Analyzed for: TPH-G BTEX MTBE TPH-D      Other: \_\_\_\_\_

EB I.D. (if applicable): \_\_\_\_\_ @ \_\_\_\_\_ Time      Duplicate I.D. (if applicable): \_\_\_\_\_

Analyzed for: TPH-G BTEX MTBE TPH-D      Other: \_\_\_\_\_

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV



## SHELL WELL MONITORING DATA SHEET

BTS #: 030724-MM3	Site: 4226 First St., Pleasanton
Sampler: MM	Date: 7/29/03
Well I.D.: MW-3	Well Diameter: 2 3 (4) 6 8
Total Well Depth (TD): 34.61	Depth to Water (DTW): 31-29
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 31.95	

Purge Method:  Bailer       Waterra      Sampling Method:  Bailer  
 Disposable Bailer       Peristaltic       Disposable Bailer  
 Positive Air Displacement       Extraction Pump       Extraction Port  
 Electric Submersible      Other \_\_\_\_\_       Dedicated Tubing

$2.2 \text{ (Gals.)} \times 3 = 6.6 \text{ Gals.}$ 1 Case Volume      Specified Volumes      Calculated Volume	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius<sup>2</sup> * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius <sup>2</sup> * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius <sup>2</sup> * 0.163														

Time	Temp (°F)	pH	Cond (mS or μS)	Turbidity (NTUs)	Gals. Removed	Observations
1230	82.4	6.7	974	95	2.5	clear
			dewatered @ 3.0 gals			DTW = 33.00
1327	75.5	6.7	1015	41		clear

Did well dewater?  Yes      No      Gallons actually evacuated: 3.0

Sampling Date: 7/29/03      Sampling Time: 1325      Depth to Water: 32.84 *site defective*

Sample I.D.: MW-3      Laboratory:  STL      Other \_\_\_\_\_

Analyzed for:  TPH-G     BTEX     MTBE    TPH-D    Other: \_\_\_\_\_

EB I.D. (if applicable): \_\_\_\_\_      Duplicate I.D. (if applicable): \_\_\_\_\_

Analyzed for: TPH-G    BTEX    MTBE    TPH-D    Other: \_\_\_\_\_

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV