

RECEIVED

1:59 pm, May 12, 2008

Alameda County
Environmental Health



Shell Oil Products US

May 8, 2008

Re: **Semi-Annual Monitoring Report – First Quarter 2008**
Former Shell-branded Service Station
15275 Washington Avenue
San Leandro, California

Dear Mr. Wickham:

I declare, under penalty of perjury, that the information and/or recommendations contained in the attached document or report is true and correct to the best of my knowledge.

Sincerely,
Shell Oil Products US

A handwritten signature in black ink, appearing to read "Denis L. Brown".

Denis L. Brown
Project Manager

May 8, 2008
DELTA Project SCA152751
SAP: 129460

Mr. Jerry Wickham
Alameda County Health Care Services Agency
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502-6577

**Re: SEMI-ANNUAL GROUNDWATER MONITORING REPORT-
FIRST QUARTER 2008
Former Shell-Branded Service Station
15275 Washington Avenue
San Leandro, California**



Dear Mr. Wickham:


On behalf of Shell Oil Products (SHELL), Delta Consultants, Inc. (DELTA) has prepared this *First Quarter 2008 Semi-Annual Groundwater Monitoring Report* for the above referenced site. The sampling activities at the site were conducted by Blaine Tech Services, Inc. under contract to SHELL and included the collection of groundwater samples and static water level measurements. A DELTA staff member, under the supervision of a California Registered Civil Engineer or a California Professional Geologist, performed the data evaluation.

This semi-annual report represents DELTA's professional opinions based upon the currently available information and is arrived at in accordance with currently acceptable professional standards. This report is based upon a specific scope of work requested by the client. The Contract between DELTA and its client outlines the scope of work, and only those tasks specifically authorized by that contract or outlined in this report were performed. This report is intended only for the use of DELTA's Client and anyone else specifically listed on this report. DELTA will not and cannot be liable for unauthorized reliance by any other third party. Other than as contained in this paragraph, DELTA makes no express or implied warranty as to the contents of this report.


Mr. Jerry Wickham
Alameda County Health Care Services
May 8, 2008
Page 2

If you have any questions regarding this site, please contact Mr. Richard Garlow (DELTA) at (408) 826-1880 or Mr. Denis Brown (SHELL) at (707) 865-0251.

Sincerely,
Delta Consultants



Richard A. Garlow, M.S., PG
Project Manager



Attachment: First Quarter 2008 Semi-annual Groundwater Monitoring Report

cc: Denis Brown, Shell Oil Products US, Carson
Mike Bakaldin, San Leandro Fire Department, San Leandro
Jonathan Redding, Wendell, Rosen, Black & Dean, Oakland
Richard Waxman, Wendell, Rosen, Black & Dean, Oakland
Salel Enterprises c/o Foothill Hardware, Oakland

May 8, 2008

SHELL QUARTERLY STATUS REPORT

Station Address: 15275 Washington Avenue, San Leandro, CA
DELTA Project No.: SCA152751
SHELL Project Manager / Phone No.: Denis Brown / (707) 865-0251
DELTA Site Manager / Phone No.: Richard Garlow / (408) 826-1880
Primary Agency / Regulatory ID No.: Alameda County Health Care Services Agency (ACHCSA) /
Jerry Wickham
Other Agencies to Receive Copies: San Leandro Fire Department / Mike Bakaldin

WORK PERFORMED THIS QUARTER (FIRST – 2008):

1. Semi-annual groundwater monitoring and sampling. Submitted status report.
2. Obtained access agreement, meet with property owners.

WORK PROPOSED FOR NEXT QUARTER (SECOND – 2008):

1. Conduct soil vapor sample investigation.

Current Phase of Project: Groundwater monitoring
Site Use: Former Shell-branded Service Station
Frequency of Sampling: Semi-annual (S-3 and S-7 through S-9)
Annual (S-1, S-5, S-10, S-13, and S-16 through S-19)
Frequency of Monitoring: Semi-annual
Is Separate Phase Hydrocarbon Present On-site (Well #'s): Yes No
Cumulative SPH Recovered to Date: NA
SPH Recovered This Quarter : None
Groundwater Removed this Quarter: None
Sensitive Receptor(s) and Respective Direction(s): No municipal wells are located within a half mile from the site.
Site Lithology: Silt, silty sand, and clay were encountered to the total depth explored, with minor sand interbeds noted.
Current Remediation Techniques: None
Permits for Discharge: None
Approximate Depth to Groundwater: 4.72 to 6.10 feet below top of well casing
Groundwater Gradient: South at approximately 0.012 ft/ft; generally consistent with previous data
Current Agency Correspondence: ACHCSA letter dated August 31, 2007

May 8, 2008

SHELL QUARTERLY STATUS REPORT

Site History:

Case Opening	1985 – four on-site wells installed, TPH-G detected in groundwater, as well as separate phase product in one well.
On-Site Assessment	1985-1987 – on-site wells and soil borings
Off-Site Assessment	1988-1991 – off-site wells installed 1997 – on- and off-site soil vapor survey
Passive Remediation	Natural attenuation since source and tank removal in 1987
Active Remediation	1987 – over 700 cubic yards of petroleum hydrocarbon impacted soil was excavated during UST and dispenser removal. 1998-1999 – Soil vapor extraction system removed 1,410 pounds of vapor-phase hydrocarbons from the site
Closure	Evaluate closure request following soil vapor survey
Summary of Unusual Activity:	TPH-G and benzene concentrations increased in Well S-9, but remain well below the historic highs.

Discussion:

Soil vapor investigation will be conducted to evaluate the effectiveness of past soil vapor extraction and natural attenuation in lowering soil vapor hydrocarbon (particularly benzene) levels at the site. Following the soil vapor sampling investigation, a Sensitive Receptor Survey will be conducted, a Site Conceptual Model will be developed, especially to evaluate elevated hydrocarbon levels remaining in off-site well S-9 and a Tier I/Tier II Risk Based Corrective Action evaluation will be completed.

ATTACHED:

- Table 1 – Groundwater Gauging and Analytical Data
- Figure 1 – Site Map Location
- Figure 2 – Groundwater Elevation Contour Map
- Figure 3 – Hydrocarbon Distribution in Groundwater Map
- Appendix A – Field Data Sheets
- Appendix B – Field Procedures
- Appendix C – Laboratory Report and Chain-of-Custody Document

TABLE

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-1	7/8/1985	520	NA	NA	NA	NA	NA	NA	21.55	NA	NA	NA	NA
S-1	9/6/1988	<50	<0.5	<1	<1	<0.3	NA	NA	21.55	NA	NA	NA	NA
S-1	11/16/1988	<50	<0.5	<1	<1	<0.3	NA	NA	21.55	8.01	13.54	NA	NA
S-1	2/27/1989	<50	0.5	<1	<1	<0.3	NA	NA	21.55	NA	NA	NA	NA
S-1	5/4/1989	<50	1.0	<1	<1	<0.3	NA	NA	21.55	NA	NA	NA	NA
S-1	8/10/1989	<50	0.7	<1	<1	<0.3	NA	NA	21.55	7.93	13.62	NA	NA
S-1	10/10/1989	<50	<0.5	<1	<1	<0.3	NA	NA	21.55	8.09	13.46	NA	NA
S-1	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.55	7.73	13.82	NA	NA
S-1	4/18/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.55	7.91	13.64	NA	NA
S-1	7/23/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.55	7.72	13.83	NA	NA
S-1	10/18/1990	80	5	<0.5	<0.5	3.0	NA	NA	21.55	8.55	13.00	NA	NA
S-1	1/28/1991	<50	4.5	<0.5	<0.5	2.0	NA	NA	21.55	8.52	13.03	NA	NA
S-1	4/25/1991	80a	3.7	<0.5	0.7	2.0	NA	NA	21.55	7.18	14.37	NA	NA
S-1	7/9/1991	200	16	<0.5	1.3	5.8	NA	NA	21.55	8.22	13.33	NA	NA
S-1	10/8/1991	<50	2.3	<0.5	<0.5	<0.5	NA	NA	21.55	8.70	12.85	NA	NA
S-1	2/5/1992	160	8.9	<0.5	2.1	6.0	NA	NA	21.55	8.14	13.41	NA	NA
S-1	4/28/1992	<50	2.4	<0.5	<0.5	0.9	NA	NA	21.55	7.52	14.03	NA	NA
S-1	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.55	8.28	13.27	NA	NA
S-1	10/26/1992	57	3.0	1.6	1.4	1.7	NA	NA	21.55	8.74	12.81	NA	NA
S-1	1/14/1993	490	53	1.2	20	33	NA	NA	21.55	5.91	15.64	NA	NA
S-1	4/16/1993	240	20	<0.5	15	240	NA	NA	21.55	6.66	14.89	NA	NA
S-1	7/23/1993	<50	0.5	<0.5	<0.5	<0.5	NA	NA	21.55	7.53	14.02	NA	NA
S-1	10/27/1993	60	5.9	<0.5	2.5	1.7	NA	NA	21.55	8.20	13.35	NA	NA
S-1	1/27/1994	<50	2.1	<0.5	<0.5	0.63	NA	NA	21.55	7.26	14.29	NA	NA
S-1	5/5/1994	57	3.9	<0.5	1.9	1.9	NA	NA	21.27	7.38	13.89	NA	NA
S-1	7/26/1994	<50	2.2	<0.3	<0.3	<0.6	NA	NA	21.27	7.86	13.41	NA	NA
S-1	10/28/1994	<50	0.8	<0.3	<0.3	0.8	NA	NA	21.27	7.86	13.41	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-1	1/2/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.27	6.85	14.42	NA	NA
S-1	4/14/1995	NA	NA	NA	NA	NA	NA	NA	21.27	6.08	15.19	NA	NA
S-1	7/28/1995	60	2.2	<0.5	1.3	1.2	NA	NA	21.27	6.79	14.48	NA	NA
S-1	10/17/1995	60	2.6	<0.5	1.2	1.3	NA	NA	21.27	7.04	14.23	NA	NA
S-1	1/11/1996	<50	2.0	<0.5	<0.5	<0.5	<2	NA	21.27	6.40	14.87	NA	NA
S-1	4/2/1996	NA	NA	NA	NA	NA	NA	NA	21.27	5.84	15.43	NA	NA
S-1	7/9/1996	NA	NA	NA	NA	NA	NA	NA	21.27	6.50	14.77	NA	NA
S-1	10/10/1996	NA	NA	NA	NA	NA	NA	NA	21.27	7.31	13.96	NA	NA
S-1	1/9/1997	<50	<0.50	<0.50	<0.50	<0.50	6.7	NA	21.27	5.50	15.77	NA	NA
S-1	4/8/1997	NA	NA	NA	NA	NA	NA	NA	21.27	7.03	14.24	NA	NA
S-1	7/21/1997	NA	NA	NA	NA	NA	NA	NA	21.27	7.00	14.27	NA	NA
S-1	10/8/1997	NA	NA	NA	NA	NA	NA	NA	21.27	7.51	13.76	NA	NA
S-1	1/15/1998	420	16	<0.50	4.6	3.9	26	NA	21.27	5.43	15.84	NA	NA
S-1	4/14/1998	NA	NA	NA	NA	NA	NA	NA	21.27	5.55	15.72	NA	NA
S-1	7/14/1998	NA	NA	NA	NA	NA	NA	NA	21.33	6.38	14.95	NA	NA
S-1	10/20/1998	NA	NA	NA	NA	NA	NA	NA	21.33	7.48	13.85	NA	NA
S-1	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	2.53	NA	21.33	6.37	14.96	NA	NA
S-1	4/8/1999	NA	NA	NA	NA	NA	NA	NA	21.33	5.93	15.40	NA	NA
S-1	7/23/1999	NA	NA	NA	NA	NA	NA	NA	21.33	7.20	14.13	NA	NA
S-1	10/26/1999	NA	NA	NA	NA	NA	NA	NA	21.33	7.61	13.72	NA	NA
S-1	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	4.73	NA	21.33	7.76	13.57	NA	NA
S-1	4/14/2000	NA	NA	NA	NA	NA	NA	NA	21.33	6.35	14.98	NA	NA
S-1	7/12/2000	NA	NA	NA	NA	NA	NA	NA	21.33	7.05	14.28	NA	NA
S-1	11/1/2000	NA	NA	NA	NA	NA	NA	NA	21.33	6.51	14.82	NA	NA
S-1	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	21.33	7.49	13.84	NA	NA
S-1	4/24/2001	NA	NA	NA	NA	NA	NA	NA	21.33	6.85	14.48	NA	NA
S-1	7/2/2001	NA	NA	NA	NA	NA	NA	NA	21.33	7.65	13.68	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

S-1	11/2/2001	NA	NA	NA	NA	NA	NA	NA	21.33	7.84	13.49	NA	NA
S-1	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.33	6.16	15.17	NA	NA
S-1	4/1/2002	NA	NA	NA	NA	NA	NA	NA	21.33	6.57	14.76	NA	NA
S-1	7/11/2002	NA	NA	NA	NA	NA	NA	NA	21.33	7.52	13.81	NA	NA
S-1	10/28/2002	NA	NA	NA	NA	NA	NA	NA	21.33	7.99	13.34	NA	NA
S-1	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	5.6	21.33	6.46	14.87	NA	NA
S-1	4/30/2003	NA	NA	NA	NA	NA	NA	NA	21.33	6.18	15.15	NA	NA
S-1	7/1/2003	NA	NA	NA	NA	NA	NA	NA	21.33	7.38	13.95	NA	NA
S-1	10/8/2003	NA	NA	NA	NA	NA	NA	NA	21.33	7.87	13.46	NA	NA
S-1	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.33	6.90	14.43	NA	NA
S-1	7/13/2004	NA	NA	NA	NA	NA	NA	NA	21.33	7.83	13.50	NA	NA
S-1	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.33	5.68	15.65	NA	NA
S-1	7/19/2005	NA	NA	NA	NA	NA	NA	NA	21.33	6.35	14.98	NA	NA
S-1	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	21.33	6.05	15.28	NA	NA
S-1	7/25/2006	NA	NA	NA	NA	NA	NA	NA	21.33	7.12	14.21	NA	NA
S-1	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.33	6.75	14.58	NA	NA
S-1	7/24/2007	NA	NA	NA	NA	NA	NA	NA	21.33	7.73	13.60	NA	NA
S-1	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	21.33	6.10	15.23	NA	NA

S-3	9/6/1988	96000	3400	9500	2700	17000	NA	NA	21.14	NA	NA	NA	NA
S-3	11/16/1988	70000	4600	8400	2500	13000	NA	NA	21.14	7.76	13.38	NA	NA
S-3	2/27/1989	32000	2400	3100	1500	6400	NA	NA	21.14	NA	NA	NA	NA
S-3	5/4/1989	47000	4400	300	2400	15000	NA	NA	21.14	NA	NA	NA	NA
S-3	8/10/1989	110000	5700	5700	3200	19000	NA	NA	21.14	7.92	13.22	NA	NA
S-3	10/10/1989	52000	4600	3300	2600	15000	NA	NA	21.14	8.00	13.14	NA	NA
S-3	1/25/1990	420000	5200	4100	6700	34000	NA	NA	21.14	7.54	13.60	NA	NA
S-3	4/18/1990	58000	3800	1400	2400	12000	NA	NA	21.14	7.74	13.40	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-3	7/23/1990	49000	3400	1800	2300	12000	NA	NA	21.14	7.55	13.59	NA	NA
S-3	10/18/1990	44000	3500	650	2400	11000	NA	NA	21.14	8.47	12.67	NA	NA
S-3	1/28/1991	64000	40900	570	1940	8090	NA	NA	21.14	8.38	12.76	NA	NA
S-3	4/25/1991	120000	3900	3600	2400	8900	NA	NA	21.14	6.91	14.23	NA	NA
S-3	7/9/1991	50000	3600	2300	1800	10000	NA	NA	21.14	8.07	13.07	NA	NA
S-3	10/8/1991	130000	3600	1000	2800	8400	NA	NA	21.14	8.61	12.53	NA	NA
S-3	2/5/1992	150000	2500	670	2700	10000	NA	NA	21.14	7.80	13.34	NA	NA
S-3	4/28/1992	120000	2200	1200	2000	5800	NA	NA	21.14	7.27	13.87	NA	NA
S-3	7/27/1992	190000	1400	<1250	<1250	3400	NA	NA	21.14	8.10	13.04	NA	NA
S-3	10/26/1992	950000	2000	8400	16000	36000	NA	NA	21.14	8.62	12.52	NA	NA
S-3	1/14/1993	41000	2700	2500	1800	6900	NA	NA	21.14	5.16	15.98	NA	NA
S-3	4/16/1993	40000	930	2800	1900	14000	NA	NA	21.14	7.18	13.96	NA	NA
S-3	7/23/1993	87000	1600	<5	1300	4000	NA	NA	21.14	7.34	13.80	NA	NA
S-3	10/27/1993	36000	2200	<500	1500	3200	NA	NA	21.14	8.03	13.11	NA	NA
S-3	1/27/1994	190000	3200	3100	4100	15000	NA	NA	21.14	6.79	14.35	NA	NA
S-3	5/5/1994	36000	1100	490	1600	4700	NA	NA	20.48	6.75	13.73	NA	NA
S-3	7/26/1994	18000	1039	170.5	845.4	967.5	NA	NA	20.48	7.30	13.18	NA	NA
S-3	10/28/1994	25869	467.9	294	546.2	343.3	NA	NA	20.48	8.36	12.12	NA	NA
S-3	1/2/1995	23000	850	260	900	2100	NA	NA	20.48	6.36	14.12	NA	NA
S-3	4/14/1995	33000	720	670	1600	6600	NA	NA	20.48	5.87	14.61	NA	NA
S-3	7/28/1995	12000	540	<10	580	780	NA	NA	20.48	6.33	14.15	NA	NA
S-3	10/17/1995	Well inaccessible		NA	NA	NA	NA	NA	20.48	6.48	14.00	NA	NA
S-3	1/11/1996	16000	520	290	740	2600	<200	NA	20.48	5.80	14.68	NA	NA
S-3	4/2/1996	NA	NA	NA	NA	NA	NA	NA	20.48	5.00	15.48	NA	NA
S-3	7/9/1996	NA	NA	NA	NA	NA	NA	NA	20.48	5.93	14.55	NA	NA
S-3	10/10/1996	NA	NA	NA	NA	NA	NA	NA	20.48	6.73	13.75	NA	NA
S-3	1/9/1997	30000	420	330	1500	6300	<500	NA	20.48	4.72	15.76	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-3	4/8/1997	NA	NA	NA	NA	NA	NA	NA	20.48	6.63	13.85	NA	NA
S-3	7/21/1997	NA	NA	NA	NA	NA	NA	NA	20.48	6.18	14.30	NA	NA
S-3	10/8/1997	NA	NA	NA	NA	NA	NA	NA	20.48	6.83	13.65	NA	NA
S-3	1/15/1998	21000	300	51	770	2800	<100	NA	20.48	4.30	16.18	NA	NA
S-3 (D)	1/15/1998	14000	330	63	920	3400	<250	NA	20.48	NA	NA	NA	NA
S-3	4/14/1998	NA	NA	NA	NA	NA	NA	NA	20.48	4.37	16.11	NA	NA
S-3	7/14/1998	NA	NA	NA	NA	NA	NA	NA	20.48	5.47	15.01	NA	NA
S-3	10/20/1998	Well inaccessible		NA	NA	NA	NA	NA	20.48	NA	NA	NA	NA
S-3	1/22/1999	40000	313	194	2200	8800	<40.0	NA	20.48	5.71	14.77	NA	NA
S-3	4/8/1999	NA	NA	NA	NA	NA	NA	NA	20.48	4.95	15.53	NA	NA
S-3	7/23/1999	NA	NA	NA	NA	NA	NA	NA	20.48	6.78	13.70	NA	NA
S-3	10/26/1999	NA	NA	NA	NA	NA	NA	NA	20.48	7.25	13.23	NA	NA
S-3	1/3/2000	39700	150	61.8	1690	7720	445	NA	20.48	7.46	13.02	NA	NA
S-3	4/14/2000	NA	NA	NA	NA	NA	NA	NA	20.48	5.64	14.84	NA	NA
S-3	7/12/2000	Well inaccessible		NA	NA	NA	NA	NA	20.48	NA	NA	NA	NA
S-3	11/1/2000	NA	NA	NA	NA	NA	NA	NA	20.48	6.72	13.76	NA	NA
S-3	1/3/2001	25000	89.0	<50.0	1270	5180	<250	NA	20.48	7.14	13.34	NA	NA
S-3	4/24/2001	Well inaccessible		NA	NA	NA	NA	NA	20.48	NA	NA	NA	NA
S-3	7/2/2001	NA	NA	NA	NA	NA	NA	NA	20.48	7.28	13.20	NA	3.2
S-3	11/2/2001	NA	NA	NA	NA	NA	NA	NA	20.48	7.64	12.84	NA	3.5
S-3	1/16/2002	Well inaccessible		NA	NA	NA	NA	NA	20.48	NA	NA	NA	NA
S-3	4/1/2002	NA	NA	NA	NA	NA	NA	NA	20.48	5.99	14.49	NA	3.8
S-3	7/11/2002	NA	NA	NA	NA	NA	NA	NA	20.48	7.21	13.27	NA	0.7
S-3	10/28/2002	NA	NA	NA	NA	NA	NA	NA	20.85	7.90	12.95	NA	e
S-3	1/23/2003	28000	60	13	970	3700	NA	<50	20.85	6.00	14.85	NA	0.3
S-3	4/30/2003	NA	NA	NA	NA	NA	NA	NA	20.85	5.34	15.51	NA	1.0
S-3	7/1/2003	NA	NA	NA	NA	NA	NA	NA	20.85	7.28	13.57	NA	1.0

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-3	10/8/2003	NA	NA	NA	NA	NA	NA	NA	20.85	7.63	13.22	NA	26.9
S-3	1/22/2004	3200	5.7	<2.5	16	320	NA	NA	20.85	6.53	14.32	NA	0.5
S-3	7/13/2004	Well inaccessible		NA	NA	NA	NA	NA	20.85	NA	NA	NA	NA
S-3	7/21/2004	3100	4.1	<2.5	10	130	NA	NA	20.85	7.64	13.21	NA	2.2
S-3	1/20/2005	93	<0.50	<0.50	1.3	1.8	NA	NA	20.85	5.78	15.07	NA	0.8
S-3	7/19/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.85	6.35	14.50	NA	NA
S-3	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	20.85	5.55	15.30	NA	NA
S-3	7/25/2006	100	<1.00	<1.00	<1.00	<3.00	NA	NA	20.85	7.09	13.76	NA	NA
S-3	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.85	6.53	14.32	NA	NA
S-3	7/24/2007	590 g,h	0.99	<1.0	0.25 i	0.99 i	NA	NA	20.85	7.44	13.41	NA	NA
S-3	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	20.85	5.41	15.44	NA	NA

S-5	1/8/1987	7800	380	510	NA	1000	NA	NA	21.41	NA	NA	NA	NA
S-5	9/6/1988	7000	2600	60	400	700	NA	NA	21.41	NA	NA	NA	NA
S-5	11/16/1988	3000	660	60	120	220	NA	NA	21.41	NA	NA	NA	NA
S-5	2/27/1989	5700	2000	220	260	320	NA	NA	21.41	NA	NA	NA	NA
S-5	5/4/1989	9000	3000	600	630	1700	NA	NA	21.41	NA	NA	NA	NA
S-5	8/10/1989	5100	1100	<50	270	400	NA	NA	21.41	8.28	13.13	NA	NA
S-5	10/10/1989	15000	3300	160	830	2200	NA	NA	21.41	8.32	13.09	NA	NA
S-5	1/25/1990	12000	2400	360	570	1400	NA	NA	21.41	8.20	13.21	NA	NA
S-5	4/18/1990	5200	1100	40	300	460	NA	NA	21.41	8.32	13.09	NA	NA
S-5	7/23/1990	5500	1300	140	320	730	NA	NA	21.41	8.03	13.38	NA	NA
S-5	10/18/1990	12000	3200	40	720	900	NA	NA	21.41	9.03	12.38	NA	NA
S-5	1/28/1991	2550	410	15	110	60	NA	NA	21.41	8.80	12.61	NA	NA
S-5	4/25/1991	67000	5100	3100	2800	11000	NA	NA	21.41	7.40	14.01	NA	NA
S-5	7/9/1991	4900	480	36	360	1000	NA	NA	21.41	8.52	12.89	NA	NA
S-5	10/8/1991	6600	370	7.0	190	380	NA	NA	21.41	9.00	12.41	NA	NA

TABLE 1
GROUNDWATER GAUGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-5	2/5/1992	44000	4800	850	2700	8400	NA	NA	21.41	8.11	13.30	NA	NA
S-5	4/28/1992	33000	1400	320	1600	5200	NA	NA	21.41	7.70	13.71	NA	NA
S-5	7/27/1992	20000	2400	<25	1800	2300	NA	NA	21.41	8.52	12.89	NA	NA
S-5	10/26/1992	21000	1600	140	1500	2800	NA	NA	21.41	9.02	12.39	NA	NA
S-5	1/14/1993	54000	1900	1000	2700	16000	NA	NA	21.41	5.22	16.19	NA	NA
S-5	4/16/1993	42000	2000	1300	4300	18000	NA	NA	21.41	7.04	14.37	NA	NA
S-5	7/23/1993	46000	2500	2200	3400	11000	NA	NA	21.41	7.75	13.66	NA	NA
S-5	10/27/1993	6500	990	31	1100	1000	NA	NA	21.41	8.49	12.92	NA	NA
S-5	1/27/1994	34000	1800	580	2900	9700	NA	NA	21.41	7.04	14.37	NA	NA
S-5	5/5/1994	24000	670	70	1400	2700	NA	NA	21.03	7.20	13.83	NA	NA
S-5	7/27/1994	4700	193.6	33.1	332.3	281.2	NA	NA	21.03	7.72	13.31	NA	NA
S-5	10/28/1994	3200	167.3	18	238.7	104.5	NA	NA	21.03	7.82	13.21	NA	NA
S-5	1/2/1995	18000	1300	220	3400	10000	NA	NA	21.03	6.65	14.38	NA	NA
S-5	4/14/1995	NA	NA	NA	NA	NA	NA	NA	21.03	5.99	15.04	NA	NA
S-5	7/28/1995	25000	440	74	1700	4500	NA	NA	21.03	6.77	14.26	NA	NA
S-5 (D)	7/28/1995	25000	450	<50	1700	4600	NA	NA	21.03	NA	NA	NA	NA
S-5	10/17/1995	18000	360	24	1300	2200	NA	NA	21.03	7.00	14.03	NA	NA
S-5	1/11/1996	41000	420	180	1600	9500	<200	NA	21.03	6.22	14.81	NA	NA
S-5	4/2/1996	NA	NA	NA	NA	NA	NA	NA	21.03	5.44	15.59	NA	NA
S-5	7/9/1996	NA	NA	NA	NA	NA	NA	NA	21.03	6.41	14.62	NA	NA
S-5	10/10/1996	NA	NA	NA	NA	NA	NA	NA	21.03	7.19	13.84	NA	NA
S-5	1/9/1997	38000	130	43	160	6200	<125	NA	21.03	5.03	16.00	NA	NA
S-5 (D)	1/9/1997	36000	130	<50	160	5600	<250	NA	21.03	NA	NA	NA	NA
S-5	4/8/1997	NA	NA	NA	NA	NA	NA	NA	21.03	7.20	13.83	NA	NA
S-5	7/21/1997	NA	NA	NA	NA	NA	NA	NA	21.03	6.82	14.21	NA	NA
S-5	10/8/1997	NA	NA	NA	NA	NA	NA	NA	21.03	7.31	13.72	NA	NA
S-5	1/15/1998	49000	62	<50	93	4100	<250	NA	21.03	4.58	16.45	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-5	4/14/1998	NA	NA	NA	NA	NA	NA	NA	21.03	4.94	16.09	NA	NA
S-5	7/14/1998	NA	NA	NA	NA	NA	NA	NA	21.27	5.36	15.91	NA	NA
S-5	10/20/1998	NA	NA	NA	NA	NA	NA	NA	21.27	7.53	13.74	NA	NA
S-5	1/22/1999	2550	9.09	<0.500	1.93	112	4.40	NA	21.27	6.35	14.92	NA	NA
S-5	4/8/1999	NA	NA	NA	NA	NA	NA	NA	21.27	5.37	15.90	NA	NA
S-5	7/23/1999	NA	NA	NA	NA	NA	NA	NA	21.27	6.43	14.84	NA	NA
S-5	10/26/1999	NA	NA	NA	NA	NA	NA	NA	21.27	7.51	13.76	NA	NA
S-5	1/3/2000	3310	39.0	<10.0	293	21.7	<50.0	NA	21.27	7.78	13.49	NA	NA
S-5	4/14/2000	NA	NA	NA	NA	NA	NA	NA	21.27	6.15	15.12	NA	NA
S-5	7/12/2000	NA	NA	NA	NA	NA	NA	NA	21.27	7.05	14.22	NA	NA
S-5	11/1/2000	NA	NA	NA	NA	NA	NA	NA	21.27	6.00	15.27	NA	NA
S-5	1/3/2001	516	3.65	0.968	18.0	4.02	18.4	NA	21.27	7.48	13.79	NA	NA
S-5	4/24/2001	NA	NA	NA	NA	NA	NA	NA	21.27	6.58	14.69	NA	NA
S-5	7/2/2001	NA	NA	NA	NA	NA	NA	NA	21.27	7.60	13.67	NA	NA
S-5	11/2/2001	NA	NA	NA	NA	NA	NA	NA	21.27	7.94	13.33	NA	NA
S-5	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.27	5.88	15.39	NA	NA
S-5	4/1/2002	NA	NA	NA	NA	NA	NA	NA	21.27	6.27	15.00	NA	NA
S-5	7/11/2002	NA	NA	NA	NA	NA	NA	NA	21.27	7.53	13.74	NA	NA
S-5	10/28/2002	NA	NA	NA	NA	NA	NA	NA	21.27	8.11	13.16	NA	NA
S-5	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.27	6.22	15.05	NA	NA
S-5	4/30/2003	NA	NA	NA	NA	NA	NA	NA	21.27	5.48	15.79	NA	NA
S-5	7/1/2003	NA	NA	NA	NA	NA	NA	NA	21.27	7.32	13.95	NA	NA
S-5	10/8/2003	NA	NA	NA	NA	NA	NA	NA	21.27	7.91	13.36	NA	NA
S-5	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.27	6.68	14.59	NA	NA
S-5	7/13/2004	NA	NA	NA	NA	NA	NA	NA	21.27	8.17	13.10	NA	NA
S-5	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.27	5.30	15.97	NA	NA
S-5	7/19/2005	NA	NA	NA	NA	NA	NA	NA	21.27	6.35	14.92	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

S-5	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	21.27	5.83	15.44	NA	NA
S-5	7/25/2006	NA	NA	NA	NA	NA	NA	NA	21.27	7.35	13.92	NA	NA
S-5	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.27	6.82	14.45	NA	NA
S-5	7/24/2007	NA	NA	NA	NA	NA	NA	NA	21.27	7.70	13.57	NA	NA
S-5	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	21.27	5.83	15.44	NA	NA

S-6	11/16/1988	50	0.7	<1	<1	<3	NA	NA	22.02	8.58	13.44	NA	NA
S-6	2/27/1989	<50	<0.5	<1	<1	<3	NA	NA	22.02	NA	NA	NA	NA
S-6	5/4/1989	<50	<0.5	<1	<1	<3	NA	NA	22.02	NA	NA	NA	NA
S-6	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	22.02	8.54	13.48	NA	NA
S-6	10/10/1989	<50	<0.5	<1	<1	<3	NA	NA	22.02	8.58	13.44	NA	NA
S-6	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	22.02	8.31	13.71	NA	NA
S-6	4/18/1990	<50	<0.5	0.6	<0.5	1.0	NA	NA	22.02	8.43	13.59	NA	NA
S-6	7/23/1990	<50	<0.5	0.9	<0.5	1.8	NA	NA	22.02	8.24	13.78	NA	NA
S-6	10/18/1990	<50	<0.5	0.7	<0.5	0.8	NA	NA	22.02	9.20	12.82	NA	NA
S-6	1/28/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.02	9.10	12.92	NA	NA
S-6	4/25/1991	<50	<0.5	<0.5	<0.5	0.7	NA	NA	22.02	7.74	14.28	NA	NA
S-6	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.02	8.81	13.21	NA	NA
S-6	10/8/1991	<50	0.7	<0.5	<0.5	<0.5	NA	NA	22.02	9.26	12.76	NA	NA
S-6	2/2/1992	NA	NA	NA	NA	NA	NA	NA	22.02	8.47	13.55	NA	NA
S-6	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.02	7.91	14.11	NA	NA
S-6	7/27/1992	NA	NA	NA	NA	NA	NA	NA	22.02	8.83	13.19	NA	NA
S-6	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.02	9.29	12.73	NA	NA
S-6	1/13/1994	NA	NA	NA	NA	NA	NA	NA	22.02	9.43	12.59	NA	NA
S-6	4/16/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.02	7.12	14.90	NA	NA
S-6	7/23/1993	NA	NA	NA	NA	NA	NA	NA	22.02	8.14	13.88	NA	NA
S-6	10/27/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.02	8.75	13.27	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-6	1/27/1994	NA	NA	NA	NA	NA	NA	NA	22.02	7.87	14.15	NA	NA
S-6	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.40	7.71	13.69	NA	NA
S-6	7/26/1994	NA	NA	NA	NA	NA	NA	NA	21.40	8.10	13.30	NA	NA
S-6	10/28/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	21.40	8.04	13.36	NA	NA
S-6	1/2/1995	NA	NA	NA	NA	NA	NA	NA	21.40	7.07	14.33	NA	NA
S-6	4/14/1995	<50	<0.5	1.3	<0.5	<0.5	NA	NA	21.40	6.29	15.11	NA	NA
S-6	7/28/1995	NA	NA	NA	NA	NA	NA	NA	21.40	6.91	14.49	NA	NA
S-6	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.40	7.20	14.20	NA	NA
S-6	1/11/1996	NA	NA	NA	NA	NA	NA	NA	21.40	6.60	14.80	NA	NA
S-6	1/22/2004	Unable to locate		NA	NA	NA	NA	NA	21.40	NA	NA	NA	NA
S-7	11/16/1988	100	5.1	15	2.0	13	NA	NA	21.47	8.24	13.23	NA	NA
S-7	2/27/1989	50	0.5	3.0	1.0	11	NA	NA	21.47	NA	NA	NA	NA
S-7	5/4/1989	<50	<0.5	<1	<1	<3	NA	NA	21.47	NA	NA	NA	NA
S-7	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	21.47	8.18	13.29	NA	NA
S-7	10/10/1989	<50	<0.5	<1	<1	<3	NA	NA	21.47	8.35	13.12	NA	NA
S-7	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.47	7.95	13.52	NA	NA
S-7	4/18/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.47	8.06	13.41	NA	NA
S-7	7/23/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	7.89	13.58	NA	NA
S-7	10/18/1990	<50	<0.5	0.5	0.5	4.1	NA	NA	21.47	8.83	12.64	NA	NA
S-7	1/28/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	8.77	12.70	NA	NA
S-7	4/25/1991	60	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	7.25	14.22	NA	NA
S-7	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	8.41	13.06	NA	NA
S-7	10/8/1991	NA	NA	NA	NA	NA	NA	NA	21.47	8.95	12.52	NA	NA
S-7	2/5/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	8.04	13.43	NA	NA
S-7	10/8/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	8.95	12.52	NA	NA
S-7	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	7.45	14.02	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-7	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	8.48	12.99	NA	NA
S-7	10/26/1992	570	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	9.95	11.52	NA	NA
S-7	1/14/1993	56	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	5.84	15.63	NA	NA
S-7	4/16/1993	110	28	<0.5	<0.5	1.8	NA	NA	21.47	6.38	15.09	NA	NA
S-7	7/23/1993	80	0.48	<0.5	<0.5	0.8	NA	NA	21.47	7.72	13.75	NA	NA
S-7	10/27/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	7.79	13.68	NA	NA
S-7	1/27/1994	70a	<0.5	<0.5	<0.5	<0.5	NA	NA	21.47	7.85	13.62	NA	NA
S-7	5/5/1994	92	2.1	<0.5	<0.5	<0.5	NA	NA	20.85	9.45	11.40	NA	NA
S-7	7/26/1994	88	<0.3	<0.3	<0.3	<0.6	NA	NA	20.85	7.64	13.21	NA	NA
S-7	10/28/1994	60	<0.3	0.5	<0.3	<0.6	NA	NA	20.85	7.68	13.17	NA	NA
S-7	1/2/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.85	6.95	13.90	NA	NA
S-7	4/14/1995	NA	NA	NA	NA	NA	NA	NA	20.85	5.82	15.03	NA	NA
S-7	7/28/1995	170	1.7	<0.5	<0.5	2.2	NA	NA	20.85	6.32	14.53	NA	NA
S-7	10/17/1995	100	<0.5	0.6	<0.5	<0.5	NA	NA	20.85	7.07	13.78	NA	NA
S-7	1/11/1996	80	0.6	<0.5	<0.5	<0.5	54	NA	20.85	6.10	14.75	NA	NA
S-7	4/2/1996	NA	NA	NA	NA	NA	NA	NA	20.85	6.14	14.71	NA	NA
S-7	7/9/1996	NA	NA	NA	NA	NA	NA	NA	20.85	6.40	14.45	NA	NA
S-7	10/10/1996	NA	NA	NA	NA	NA	NA	NA	20.85	6.70	14.15	NA	NA
S-7	1/9/1997	130	1.4	<0.50	<0.50	0.56	70	NA	20.85	5.25	15.60	NA	NA
S-7	4/8/1997	NA	NA	NA	NA	NA	NA	NA	20.85	7.15	13.70	NA	NA
S-7	7/21/1997	NA	NA	NA	NA	NA	NA	NA	20.85	6.67	14.18	NA	NA
S-7	10/8/1997	NA	NA	NA	NA	NA	NA	NA	20.85	7.26	13.59	NA	NA
S-7	1/15/1998	<50	<0.50	<0.50	<0.50	<0.50	39	NA	20.85	5.51	15.34	NA	NA
S-7	4/14/1998	NA	NA	NA	NA	NA	NA	NA	20.85	5.45	15.40	NA	NA
S-7	7/14/1998	NA	NA	NA	NA	NA	NA	NA	21.03	6.48	14.55	NA	NA
S-7	10/20/1998	NA	NA	NA	NA	NA	NA	NA	21.03	7.37	13.66	NA	NA
S-7	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	97.8	NA	21.03	6.21	14.82	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-7	4/8/1999	NA	NA	NA	NA	NA	NA	NA	21.03	5.30	15.73	NA	NA
S-7	7/23/1999	NA	NA	NA	NA	NA	NA	NA	21.03	7.12	13.91	NA	NA
S-7	10/26/1999	NA	NA	NA	NA	NA	NA	NA	21.03	7.54	13.49	NA	NA
S-7	1/3/2000	615	8.73	2.90	4.00	7.17	17.0	NA	21.03	7.73	13.30	NA	NA
S-7	4/14/2000	NA	NA	NA	NA	NA	NA	NA	21.03	6.27	14.76	NA	NA
S-7	7/12/2000	NA	NA	NA	NA	NA	NA	NA	21.03	6.97	14.06	NA	NA
S-7	11/1/2000	NA	NA	NA	NA	NA	NA	NA	21.03	6.43	14.60	NA	NA
S-7	1/3/2001	460	6.68	<0.500	0.712	0.596	10.2	NA	21.03	7.27	13.76	NA	NA
S-7	4/24/2001	NA	NA	NA	NA	NA	NA	NA	21.03	6.75	14.28	NA	NA
S-7	7/2/2001	NA	NA	NA	NA	NA	NA	NA	21.03	7.55	13.48	NA	NA
S-7	11/2/2001	NA	NA	NA	NA	NA	NA	NA	21.03	7.80	13.23	NA	NA
S-7	1/16/2002	360	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.03	6.11	14.92	NA	NA
S-7	4/1/2002	NA	NA	NA	NA	NA	NA	NA	21.03	6.54	14.49	NA	NA
S-7	7/11/2002	NA	NA	NA	NA	NA	NA	NA	21.03	7.37	13.66	NA	NA
S-7	10/28/2002	NA	NA	NA	NA	NA	NA	NA	21.01	7.97	13.04	NA	NA
S-7	1/23/2003	160	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.01	6.45	14.56	NA	NA
S-7	4/30/2003	NA	NA	NA	NA	NA	NA	NA	21.01	6.14	14.87	NA	NA
S-7	7/1/2003	NA	NA	NA	NA	NA	NA	NA	21.01	7.28	13.73	NA	NA
S-7	10/8/2003	NA	NA	NA	NA	NA	NA	NA	21.01	7.78	13.23	NA	NA
S-7	1/22/2004	140	<0.50	<0.50	0.51	<1.0	NA	NA	21.01	6.93	14.08	NA	NA
S-7	7/13/2004	150	<0.50	<0.50	<0.50	<1.0	NA	17	21.01	7.88	13.13	NA	NA
S-7	1/20/2005	200 a	<0.50	<0.50	<0.50	<1.0	NA	NA	21.01	5.68	15.33	NA	NA
S-7	7/19/2005	140 a	<0.50	<0.50	<0.50	<1.0	NA	NA	21.01	6.18	14.83	NA	NA
S-7	1/27/2006	69.8	<0.500	<0.500	<0.500	<0.500	NA	NA	21.01	6.11	14.90	NA	NA
S-7	7/25/2006	78.6	<1.00	<1.00	<1.00	<3.00	NA	NA	21.01	7.01	14.00	NA	NA
S-7	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.01	6.70	14.31	NA	NA
S-7	7/24/2007	63 g,h	<0.50	<1.0	<1.0	<1.0	NA	NA	21.01	7.54	13.47	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-7	1/15/2008	160 g,h	<0.50	<1.0	<1.0	<1.0	NA	NA	21.01	6.08	14.93	NA	NA
S-8	11/16/1988	210	5.0	<1	1.0	5.0	NA	NA	20.72	7.76	12.96	NA	NA
S-8	2/27/1989	<50	2.4	<1	<1	<3	NA	NA	20.72	NA	NA	NA	NA
S-8	5/4/1989	<50	7.5	<1	2.0	<3	NA	NA	20.72	NA	NA	NA	NA
S-8	8/10/1989	<50	0.6	<1	<1	<3	NA	NA	20.72	7.79	12.93	NA	NA
S-8	10/10/1989	<50	<0.5	<1	<1	<3	NA	NA	20.72	7.84	12.88	NA	NA
S-8	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	20.72	7.47	13.25	NA	NA
S-8	4/18/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	20.72	7.59	13.13	NA	NA
S-8	7/23/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.72	7.49	13.23	NA	NA
S-8	10/18/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.72	8.44	12.28	NA	NA
S-8	1/28/1991	<50	55	0.5	<0.5	1.4	NA	NA	20.72	8.28	12.44	NA	NA
S-8	4/25/1991	130a	19	<0.5	1.3	1.1	NA	NA	20.72	6.72	14.00	NA	NA
S-8	7/9/1991	200	33	<0.5	1.8	2.8	NA	NA	20.72	7.98	12.74	NA	NA
S-8	10/8/1991	580	95	2.2	4.9	6.5	NA	NA	20.72	8.55	12.17	NA	NA
S-8	2/5/1992	90a	18	<0.5	6.2	1.8	NA	NA	20.72	7.50	13.22	NA	NA
S-8	4/28/1992	<50	5.9	<0.5	2.5	<0.5	NA	NA	20.72	7.14	13.58	NA	NA
S-8	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.72	8.06	12.66	NA	NA
S-8	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.72	8.58	12.14	NA	NA
S-8	1/14/1993	270	74	0.9	25	5.5	NA	NA	20.72	5.32	15.40	NA	NA
S-8	4/16/1993	1100	420	<0.5	200	20	NA	NA	20.72	5.76	14.96	NA	NA
S-8	7/23/1993	160	23	<0.5	1.2	1.5	NA	NA	20.72	7.29	13.43	NA	NA
S-8	10/27/1993	420	650	0.7	11	1.7	NA	NA	20.72	7.93	12.79	NA	NA
S-8	1/27/1994	290	65	<1	6.9	2.4	NA	NA	20.72	6.31	14.41	NA	NA
S-8	5/5/1994	120	13	<0.5	<0.5	<0.5	NA	NA	20.32	6.84	13.48	NA	NA
S-8	7/26/1994	115	12.2	1.3	<0.3	2.7	NA	NA	20.32	7.42	12.90	NA	NA
S-8	10/28/1994	733	75.9	3.2	4.9	4.2	NA	NA	20.32	7.56	12.76	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-8	1/2/1995	290	54	<0.5	10	<0.5	NA	NA	20.32	6.19	14.13	NA	NA
S-8	4/14/1995	230	68	<0.5	10	2.4	NA	NA	20.32	5.54	14.78	NA	NA
S-8	7/28/1995	290	44	<0.5	8.0	<0.5	NA	NA	20.32	6.28	14.04	NA	NA
S-8	10/17/1995	190	24	<0.5	1.0	0.9	NA	NA	20.32	6.64	13.68	NA	NA
S-8	1/11/1996	400	85	1.1	13	3.4	2.3	NA	20.32	5.96	14.36	NA	NA
S-8	4/2/1996	300	110	0.7	4.9	0.9	<2	NA	20.32	5.21	15.11	NA	NA
S-8	7/9/1996	<50	5.4	<0.50	0.63	<0.50	<2.5	NA	20.32	6.05	14.27	NA	NA
S-8	10/10/1996	150	0.53	0.66	2.3	1.0	8.9	NA	20.32	6.83	13.49	NA	NA
S-8	1/9/1997	240	27	<0.50	2.4	<0.50	5.8	NA	20.32	4.51	15.81	NA	NA
S-8	4/8/1997	220	27	0.62	1.9	0.71	5.7	NA	20.32	6.50	13.82	NA	NA
S-8	7/21/1997	1200	140	2.8	21	5.0	27	NA	20.32	6.36	13.96	NA	NA
S-8 (D)	7/21/1997	1200	120	<2.0	19	3.9	25	NA	20.32	NA	NA	NA	NA
S-8	10/8/1997	690	92	1.4	25	2.0	<2.5	NA	20.32	6.83	13.49	NA	NA
S-8 (D)	10/8/1997	700	95	1.3	26	1.9	<2.5	NA	20.32	NA	NA	NA	NA
S-8	1/15/1998	460	110	1.0	3.4	1.7	<5.0	NA	20.32	4.30	16.02	NA	NA
S-8	4/14/1998	780	190	2.9	15	3.4	<2.5	NA	20.32	4.68	15.64	NA	NA
S-8	7/14/1998	1600	240	<5.0	36	<5.0	<25	NA	20.36	6.36	14.00	NA	NA
S-8	10/20/1998	700	55	<5.0	<5.0	<5.0	49	NA	20.36	6.91	13.45	NA	NA
S-8	1/22/1999	<50.0	5.83	<0.500	0.919	<0.500	<2.00	NA	20.36	5.97	14.39	NA	NA
S-8	4/8/1999	684	10.6	1.3	9.75	1.0	10.5	NA	20.36	5.01	15.35	NA	NA
S-8	7/23/1999	1540	86.5	5.20	5.30	6.35	<25.0	NA	20.36	6.61	13.75	NA	NA
S-8	10/26/1999	1680	116	<2.50	22.4	5.58	<12.5	NA	20.36	6.95	13.41	NA	NA
S-8	1/3/2000	Well inaccessible		NA	NA	NA	NA	NA	20.36	NA	NA	NA	NA
S-8	4/14/2000	Well inaccessible		NA	NA	NA	NA	NA	20.36	NA	NA	NA	NA
S-8	7/12/2000	Well inaccessible		NA	NA	NA	NA	NA	20.36	NA	NA	NA	NA
S-8	11/1/2000	2300	118	12.4	51.7	<2.50	<12.5	NA	20.36	5.68	14.68	NA	NA
S-8	1/3/2001	263	4.34	0.620	<0.500	0.643	5.40	NA	20.36	6.95	13.41	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-8	4/24/2001	680	12	<0.50	0.86	<0.50	NA	<0.50	20.36	6.25	14.11	NA	NA
S-8	7/2/2001	330	2.5	<0.50	0.86	<0.50	NA	<5.0	20.36	7.00	13.36	NA	NA
S-8	11/2/2001	1300	71	0.84	14	1.7	NA	<5.0	20.36	7.44	12.92	NA	NA
S-8	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.36	5.67	14.69	NA	NA
S-8	4/1/2002	330	2.2	<0.50	<0.50	<0.50	NA	<5.0	20.36	5.99	14.37	NA	NA
S-8	7/11/2002	1400	55	0.83	5.3	0.71	NA	<5.0	20.36	6.94	13.42	NA	NA
S-8	10/28/2002	660	6.2	0.63	0.76	<0.50	NA	<0.50	20.36	7.50	12.86	NA	1.1
S-8	1/23/2003	1600	30	0.56	6.7	<0.50	NA	<5.0	20.36	5.99	14.37	NA	NA
S-8	4/30/2003	890	13	<0.50	0.59	<1.0	NA	<5.0	20.36	5.30	15.06	NA	NA
S-8	7/1/2003	1800	68	1.3	2.6	1.2	NA	<0.50	20.36	6.87	13.49	NA	1.0
S-8	10/8/2003	220	1.3	<0.50	<0.50	<1.0	NA	<0.50	20.36	7.27	13.09	NA	NA
S-8	1/22/2004	1000	6.7	<0.50	0.61	<1.0	NA	NA	20.36	6.50	13.86	NA	NA
S-8	7/13/2004	2000	100	1.7	5.7	<2.0	NA	<1.0	20.36	7.41	12.95	NA	NA
S-8	1/20/2005	380	4.3	<0.50	<0.50	<1.0	NA	NA	20.36	5.02	15.34	NA	NA
S-8	7/19/2005	120	1.2	<0.50	<0.50	<1.0	NA	NA	20.36	5.82	14.54	NA	NA
S-8	1/27/2006	494	2.42	<0.500	<0.500	<0.500	NA	NA	20.36	5.51	14.85	NA	NA
S-8	7/25/2006	382	2.05	<1.00	<1.00	<3.00	NA	NA	20.36	6.66	13.70	NA	NA
S-8	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.36	6.13	14.23	NA	NA
S-8	7/24/2007	210 g,h	1.2	<1.0	<1.0	<1.0	NA	NA	20.36	6.92	13.44	NA	NA
S-8	1/15/2008	560 g,h	5.3	<1.0	0.31 i	<1.0	NA	NA	20.36	5.32	15.04	NA	NA

S-9	11/16/1988	1400	69	3.0	52	180	NA	NA	20.96	7.78	13.18	NA	NA
S-9	2/27/1989	1600	240	4.0	130	180	NA	NA	20.96	NA	NA	NA	NA
S-9	5/4/1989	2600	470	10	240	480	NA	NA	20.96	NA	NA	NA	NA
S-9	8/10/1989	520	73	<10	40	<30	NA	NA	20.96	7.82	13.14	NA	NA
S-9	10/10/1989	380	82	<1	46	13	NA	NA	20.96	7.87	13.09	NA	NA
S-9	1/25/1990	750	140	1.2	69	75	NA	NA	20.96	7.41	13.55	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-9	4/18/1990	680	150	1.7	50	37	NA	NA	20.96	7.65	13.31	NA	NA
S-9	7/23/1990	490	94	1.2	32	24	NA	NA	20.96	7.58	13.38	NA	NA
S-9	10/18/1990	390	140	0.7	3.3	24	NA	NA	20.96	8.46	12.50	NA	NA
S-9	1/28/1991	1040	450	4.6	85	97	NA	NA	20.96	8.29	12.67	NA	NA
S-9	4/25/1991	5800	880	9.0	360	500	NA	NA	20.96	6.09	14.87	NA	NA
S-9	7/9/1991	1400	220	2.8	82	100	NA	NA	20.96	7.82	13.14	NA	NA
S-9	10/8/1991	890	960	<2.5	16	29	NA	NA	20.96	8.55	12.41	NA	NA
S-9	2/5/1992	950	240	<2.5	28	55	NA	NA	20.96	6.96	14.00	NA	NA
S-9	4/28/1992	1400a	290	3.0	100	81	NA	NA	20.96	6.76	14.20	NA	NA
S-9	7/27/1992	890	190	<2.5	66	68	NA	NA	20.96	8.10	12.86	NA	NA
S-9	10/26/1992	650	160	<2.5	63	89	NA	NA	20.96	8.53	12.43	NA	NA
S-9	1/13/1993	19000	2400	38	1700	2200	NA	NA	20.96	6.80	14.16	NA	NA
S-9	4/16/1993	10000	1500	<5	1100	990	NA	NA	20.96	6.28	14.68	NA	NA
S-9	7/23/1993	1100	400	<5	260	160	NA	NA	20.96	7.26	13.70	NA	NA
S-9	10/27/1993	2500	400	<5	190	110	NA	NA	20.96	8.00	12.96	NA	NA
S-9	1/27/1994	4800	990	16	630	490	NA	NA	20.96	5.96	15.00	NA	NA
S-9	5/5/1994	3700	480	<5	21	120	NA	NA	20.68	6.99	13.69	NA	NA
S-9	7/26/1994	1000	124.6	<0.3	35.8	28.6	NA	NA	20.68	7.56	13.12	NA	NA
S-9	10/28/1994	979	80.3	7.0	21.7	29.2	NA	NA	20.68	7.78	12.90	NA	NA
S-9	1/2/1995	3900	540	2.4	350	150	NA	NA	20.68	6.29	14.39	NA	NA
S-9	4/14/1995	5100	1000	<10	380	230	NA	NA	20.68	5.69	14.99	NA	NA
S-9	7/28/1995	4600	680	<10	120	47	NA	NA	20.68	6.61	14.07	NA	NA
S-9	10/17/1995	1600	150	<0.5	42	15	NA	NA	20.68	7.00	13.68	NA	NA
S-9	1/11/1996	6800	1100	12	720	95	24	NA	20.68	6.20	14.48	NA	NA
S-9	4/2/1996	6000	1300	8.3	430	99	49	NA	20.68	5.19	15.49	NA	NA
S-9 (D)	4/2/1996	6500	1200	8.3	410	90	<20	NA	20.68	NA	NA	NA	NA
S-9	7/9/1996	3400	680	6.7	54	31	<25	NA	20.68	6.43	14.25	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-9 (D)	7/9/1996	3300	730	<5.0	58	28	<25	NA	20.68	NA	NA	NA	NA
S-9	10/10/1996	6600	1200	<10	160	<10	70	NA	20.68	7.08	13.60	NA	NA
S-9 (D)	10/10/1996	6100	1000	<10	200	15	65	NA	20.68	NA	NA	NA	NA
S-9	1/9/1997	12000	1400	<25	1000	39	<125	NA	20.68	5.03	15.65	NA	NA
S-9	4/8/1997	6600	920	10	230	26	150	NA	20.68	6.78	13.90	NA	NA
S-9	7/21/1997	7800	860	13	260	14	87	NA	20.68	6.77	13.91	NA	NA
S-9	10/8/1997	4600	320	<10	61	<10	28	NA	20.68	6.92	13.76	NA	NA
S-9	1/15/1998	9300	1000	<10	730	24	<50	NA	20.68	4.50	16.18	NA	NA
S-9	4/14/1998	12000	1200	<2.5	960	<2.5	<12	NA	20.68	4.35	16.33	NA	NA
S-9 (D)	4/14/1998	12000	1200	<2.5	930	<2.5	<12	NA	20.68	NA	NA	NA	NA
S-9	7/14/1998	12000	1700	<25	990	39	<125	NA	20.68	5.95	14.73	NA	NA
S-9 (D)	7/14/1998	11000	1800	<25	650	<25	<125	NA	20.68	NA	NA	NA	NA
S-9	10/20/1998	14000	1600	<25	560	<25	340	NA	20.68	7.03	13.65	NA	NA
S-9 (D)	10/20/1998	11000	1100	<10	230	<10	100	NA	20.68	NA	NA	NA	NA
S-9	1/22/1999	9900	1030	26.7	819	27.5	46.8	NA	20.68	6.01	14.67	NA	NA
S-9	4/8/1999	17900	1450	<50.0	1610	73.8	<500	NA	20.68	5.25	15.43	NA	NA
S-9	7/23/1999	12200	1020	<20.0	536	<20.0	<200	NA	20.68	6.71	13.97	NA	NA
S-9	10/26/1999	9580	1170	11.9	566	23.1	<50.0	NA	20.68	7.27	13.41	NA	NA
S-9	10/26/1999	9580	1170	11.9	566	23.1	<50.0	NA	20.68	7.27	13.41	NA	NA
S-9	1/3/2000	9660	689	<50.0	640	<50.0	<250	NA	20.68	7.47	13.21	NA	NA
S-9	4/14/2000	14000	1040	<50.0	1210	<50.0	<250	NA	20.68	5.75	14.93	NA	NA
S-9	7/12/2000	13200	1360	33.9	552	26.8	<100	NA	20.68	6.63	14.05	NA	NA
S-9	11/1/2000	9120	928	13.5	468	<10.0	<50.0	NA	20.68	5.50	15.18	NA	NA
S-9	1/3/2001	355	19.8	0.732	2.23	0.630	5.09	NA	20.68	7.11	13.57	NA	NA
S-9	4/24/2001	3500	300	1.7	150	1.7	NA	<1.0	20.68	6.30	14.38	NA	NA
S-9	7/2/2001	88	3.8	<0.50	<0.50	<0.50	NA	<5.0	20.68	8.18	12.50	NA	2.6
S-9	11/2/2001	210	9.5	<0.50	<0.50	<0.50	NA	<5.0	20.68	8.40	12.28	NA	16.4

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-9	1/16/2002	15000	520	4.9	580	7.1	NA	<20	20.68	5.71	14.97	NA	0.5
S-9	4/1/2002	15000	530	5.1	920	7.8	NA	<25	20.68	5.99	14.69	NA	3.0
S-9	7/11/2002	10000	520	5.3	97	5.8	NA	<25	20.68	6.99	13.69	NA	0.5
S-9	10/28/2002	11000	580	6.2	65	5.3	NA	<2.5	20.70	7.63	13.07	NA	1.0
S-9	1/23/2003	9300	400	5.6	320	6.5	NA	<5.0	20.70	5.96	14.74	NA	0.5
S-9	4/30/2003	180	4.2	<0.50	3.7	<1.0	NA	<5.0	20.70	5.20	15.50	NA	7.0
S-9	7/1/2003	2200	71	0.94	6.4	<1.0	NA	<0.50	20.70	7.78	12.92	NA	0.9
S-9	10/8/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<0.50	20.70	7.38	13.32	NA	16.2
S-9	1/22/2004	1400	26	<1.0	14	12	NA	NA	20.70	6.51	14.19	NA	0.7
S-9	7/13/2004	1900	36	<1.0	2.0	<2.0	NA	<1.0	20.70	8.51	12.19	NA	17.1
S-9	1/20/2005	3600	60	1.2	50	<2.0	NA	NA	20.70	5.80	14.90	NA	0.4
S-9	7/19/2005	2800	42	1.4	18	<2.0	NA	NA	20.70	7.50	13.20	NA	NA
S-9	1/27/2006	16800	152	4.74	165	6.77	NA	NA	20.70	6.40	14.30	NA	NA
S-9	7/25/2006	22500	79.3	2.32	27.2	<3.00	NA	NA	20.70	6.92	13.78	NA	NA
S-9	1/4/2007	5800	82	3.2	110	<5.0	NA	NA	20.70	6.40	14.30	NA	NA
S-9	7/24/2007	8900 g,h	91	3.4 i	22	<10	NA	NA	20.70	7.19	13.51	NA	NA
S-9	1/15/2008	11,000 g,h	68	3.5 i	68	4.5 i	NA	NA	20.70	5.20	15.50	NA	NA

S-10	11/16/1988	330	0.5	<1	1.0	11	NA	NA	20.86	7.91	12.95	NA	NA
S-10	2/27/1989	140	<0.5	<3	2.0	6.0	NA	NA	20.86	NA	NA	NA	NA
S-10	5/3/1989	220	<0.5	1.0	2.0	7.0	NA	NA	20.86	NA	NA	NA	NA
S-10	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	20.86	7.94	12.92	NA	NA
S-10	10/9/1989	170	<0.5	<1	<1	<3	NA	NA	20.86	7.99	12.87	NA	NA
S-10	1/25/1990	<50	<0.5	<0.5	1.1	4.0	NA	NA	20.86	7.56	13.30	NA	NA
S-10	4/18/1990	<50	<0.5	0.9	<0.5	2.0	NA	NA	20.86	7.71	13.15	NA	NA
S-10	7/23/1990	590	<0.5	<0.5	1.9	19	NA	NA	20.86	7.64	13.22	NA	NA
S-10	10/18/1990	140	<0.5	0.7	<0.5	7.0	NA	NA	20.86	8.58	12.28	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-10	1/28/1991	<50	<0.5	<0.5	<0.5	0.5	NA	NA	20.86	8.35	12.51	NA	NA
S-10	4/25/1991	<50	<0.5	<0.5	1.1	0.8	NA	NA	20.69	6.91	13.78	NA	NA
S-10	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	8.14	12.55	NA	NA
S-10	10/8/1991	140	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	8.70	11.99	NA	NA
S-10	2/5/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	7.57	13.12	NA	NA
S-10	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	7.20	13.49	NA	NA
S-10	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	8.17	12.52	NA	NA
S-10	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	8.68	12.01	NA	NA
S-10	1/13/1993	88	<0.5	0.6	0.6	<0.5	NA	NA	20.69	3.78	16.91	NA	NA
S-10	4/16/1993	80	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	6.46	14.23	NA	NA
S-10	7/23/1993	<50	1.5	<0.5	0.7	2.7	NA	NA	20.69	7.38	13.31	NA	NA
S-10	10/27/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.69	8.09	12.60	NA	NA
S-10	1/27/1994	270	1.1	1.3	2.0	7.4	NA	NA	20.69	5.81	14.88	NA	NA
S-10	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.15	6.82	13.33	NA	NA
S-10	7/26/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	20.15	7.40	12.75	NA	NA
S-10	10/28/1994	<50	2.4	<0.3	0.5	0.8	NA	NA	20.15	7.62	12.53	NA	NA
S-10	1/2/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.15	6.13	14.02	NA	NA
S-10	4/14/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.15	5.60	14.55	NA	NA
S-10	7/28/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.15	6.44	13.71	NA	NA
S-10	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.15	6.85	13.30	NA	NA
S-10	1/11/1996	<50	<0.5	<0.5	<0.5	<0.5	<2	NA	20.15	6.08	14.07	NA	NA
S-10	4/2/1996	NA	NA	NA	NA	NA	NA	NA	20.15	5.21	14.94	NA	NA
S-10	7/9/1996	NA	NA	NA	NA	NA	NA	NA	20.15	6.20	13.95	NA	NA
S-10	10/10/1996	NA	NA	NA	NA	NA	NA	NA	20.15	6.92	13.23	NA	NA
S-10	1/9/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.15	4.64	15.51	NA	NA
S-10	4/8/1997	NA	NA	NA	NA	NA	NA	NA	20.15	5.82	14.33	NA	NA
S-10	7/21/1997	NA	NA	NA	NA	NA	NA	NA	20.15	6.48	13.67	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-10	10/8/1997	NA	NA	NA	NA	NA	NA	NA	20.15	5.48	14.67	NA	NA
S-10	1/15/1998	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.15	3.01	17.14	NA	NA
S-10	4/14/1998	NA	NA	NA	NA	NA	NA	NA	20.15	4.30	15.85	NA	NA
S-10	7/14/1998	NA	NA	NA	NA	NA	NA	NA	20.15	5.84	14.31	NA	NA
S-10	10/20/1998	NA	NA	NA	NA	NA	NA	NA	20.15	6.89	13.26	NA	NA
S-10	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<2.00	NA	20.15	6.00	14.15	NA	NA
S-10	4/8/1999	NA	NA	NA	NA	NA	NA	NA	20.15	4.41	15.74	NA	NA
S-10	7/23/1999	NA	NA	NA	NA	NA	NA	NA	20.15	6.48	13.67	NA	NA
S-10	10/26/1999	NA	NA	NA	NA	NA	NA	NA	20.15	7.07	13.08	NA	NA
S-10	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.15	7.27	12.88	NA	NA
S-10	4/14/2000	NA	NA	NA	NA	NA	NA	NA	20.15	5.75	14.40	NA	NA
S-10	7/12/2000	NA	NA	NA	NA	NA	NA	NA	20.15	6.17	13.98	NA	NA
S-10	11/1/2000	NA	NA	NA	NA	NA	NA	NA	20.15	5.63	14.52	NA	NA
S-10	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.15	6.89	13.26	NA	NA
S-10	4/24/2001	NA	NA	NA	NA	NA	NA	NA	20.15	6.20	13.95	NA	NA
S-10	7/2/2001	NA	NA	NA	NA	NA	NA	NA	20.15	6.80	13.35	NA	NA
S-10	11/2/2001	NA	NA	NA	NA	NA	NA	NA	20.15	7.40	12.75	NA	NA
S-10	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.15	5.66	14.49	NA	NA
S-10	4/1/2002	NA	NA	NA	NA	NA	NA	NA	20.15	5.63	14.52	NA	NA
S-10	7/11/2002	NA	NA	NA	NA	NA	NA	NA	20.15	6.72	13.43	NA	NA
S-10	10/28/2002	NA	NA	NA	NA	NA	NA	NA	20.14	7.50	12.64	NA	NA
S-10	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.14	5.97	14.17	NA	NA
S-10	4/30/2003	NA	NA	NA	NA	NA	NA	NA	20.14	5.24	14.90	NA	NA
S-10	7/1/2003	NA	NA	NA	NA	NA	NA	NA	20.14	6.82	13.32	NA	NA
S-10	10/8/2003	NA	NA	NA	NA	NA	NA	NA	20.14	7.06	13.08	NA	NA
S-10	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.14	6.50	13.64	NA	NA
S-10	7/13/2004	NA	NA	NA	NA	NA	NA	NA	20.14	7.49	12.65	NA	NA

TABLE 1
GROUNDWATER GAUGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-10	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.14	5.09	15.05	NA	NA
S-10	7/19/2005	NA	NA	NA	NA	NA	NA	NA	20.14	6.00	14.14	NA	NA
S-10	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	20.14	5.61	14.53	NA	NA
S-10	7/25/2006	NA	NA	NA	NA	NA	NA	NA	20.14	6.61	13.53	NA	NA
S-10	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.14	6.29	13.85	NA	NA
S-10	7/24/2007	NA	NA	NA	NA	NA	NA	NA	20.14	6.82	13.32	NA	NA
S-10	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	20.14	5.33	14.81	NA	NA
S-11	11/16/1988	<50	<0.5	<1	<1	<3	NA	NA	21.26	8.62	12.64	NA	NA
S-11	2/27/1989	<50	<0.5	<1	<1	<3	NA	NA	21.26	NA	NA	NA	NA
S-11	5/3/1989	<50	<0.5	<1	<1	<3	NA	NA	21.26	NA	NA	NA	NA
S-11	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	21.26	8.65	12.61	NA	NA
S-11	10/9/1989	<50	<0.5	<1	<1	<3	NA	NA	21.26	8.64	12.62	NA	NA
S-11	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.26	8.43	12.83	NA	NA
S-11	4/18/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.26	8.42	12.84	NA	NA
S-11	7/23/1990	<50	<0.5	0.6	<0.5	1.1	NA	NA	21.26	8.23	13.03	NA	NA
S-11	10/18/1990	<50	<0.5	<0.5	<0.5	0.5	NA	NA	21.26	9.20	12.06	NA	NA
S-11	1/28/1991	63	<0.5	3.3	0.9	7.0	NA	NA	21.26	9.13	12.13	NA	NA
S-11	4/25/1991	<50	<0.5	<0.5	0.8	<0.5	NA	NA	21.26	7.53	13.73	NA	NA
S-11	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.26	8.85	12.41	NA	NA
S-11	10/8/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.26	9.34	11.92	NA	NA
S-11	2/5/1991	NA	NA	NA	NA	NA	NA	NA	21.26	8.50	12.76	NA	NA
S-11	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.26	7.80	13.46	NA	NA
S-11	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.26	8.80	12.46	NA	NA
S-11	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.26	9.42	11.84	NA	NA
S-11	1/13/1993	NA	NA	NA	NA	NA	NA	NA	21.26	6.52	14.74	NA	NA
S-11	4/16/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.26	6.86	14.40	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

S-11	7/23/1993	NA	NA	NA	NA	NA	NA	NA	21.26	8.07	13.19	NA	NA
S-11	10/27/1993	Well inaccessible		NA	NA	NA	NA	NA	21.26	NA	NA	NA	NA
S-11	1/27/1994	NA	NA	NA	NA	NA	NA	NA	21.26	NA	NA	NA	NA
S-11	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.24	7.73	13.51	NA	NA
S-11	7/26/1994	NA	NA	NA	NA	NA	NA	NA	21.24	8.30	12.94	NA	NA
S-11	10/28/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	21.24	8.30	12.94	NA	NA
S-11	1/2/1995	NA	NA	NA	NA	NA	NA	NA	21.24	7.25	13.99	NA	NA
S-11	4/14/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.24	6.99	14.25	NA	NA
S-11	7/28/1995	NA	NA	NA	NA	NA	NA	NA	21.24	7.21	14.03	NA	NA
S-11	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.24	7.41	13.83	NA	NA
S-11	1/11/1996	NA	NA	NA	NA	NA	NA	NA	21.24	6.80	14.44	NA	NA
S-11	7/21/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	21.24	7.28	13.96	NA	NA
S-11	03/18/2002 d	NA	NA	NA	NA	NA	NA	NA	21.27	NA	NA	NA	NA
S-11	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	0.57	21.27	7.55	13.72	NA	NA

S-12	11/16/1988	50	3.5	<1	<1	<3	NA	NA	21.05	NA	NA	NA	NA
S-12	2/27/1989	<50	0.8	<1	<1	<3	NA	NA	21.05	NA	NA	NA	NA
S-12	5/3/1989	<50	<0.5	<1	<1	<3	NA	NA	21.05	NA	NA	NA	NA
S-12	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	21.05	8.32	12.73	NA	NA
S-12	10/9/1989	<50	<0.5	<1	<1	<1	NA	NA	21.05	8.32	12.73	NA	NA
S-12	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	21.05	8.18	12.87	NA	NA
S-12	4/18/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.05	13.00	NA	NA
S-12	7/23/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	7.92	13.13	NA	NA
S-12	10/18/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.90	12.15	NA	NA
S-12	1/28/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.54	12.51	NA	NA
S-12	4/25/1991	90	5.4	<0.5	1.1	0.7	NA	NA	21.05	7.08	13.97	NA	NA
S-12	7/9/1991	<50	2.9	<0.5	<0.5	<0.5	NA	NA	21.05	8.42	12.63	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-12	10/8/1991	50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.80	12.25	NA	NA
S-12	2/5/1992	50a	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.07	12.98	NA	NA
S-12	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.33	12.72	NA	NA
S-12	7/27/1992	94	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	8.55	12.50	NA	NA
S-12	10/26/1992	86	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	9.03	12.02	NA	NA
S-12	1/14/1993	120	2.0	<0.5	<0.5	<0.5	NA	NA	21.05	6.38	14.67	NA	NA
S-12	4/16/1993	60	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	6.56	14.49	NA	NA
S-12	7/23/1993	90	<0.5	<0.5	<0.5	<0.5	NA	NA	21.05	7.76	13.29	NA	NA
S-12	10/27/1993	Well inaccessible		NA	NA	NA	NA	NA	21.05	NA	NA	NA	NA
S-12	1/27/1994	Well inaccessible		NA	NA	NA	NA	NA	21.05	NA	NA	NA	NA
S-12	5/5/1994	<50	2.0	<0.5	<0.5	<0.5	NA	NA	20.71	7.49	13.22	NA	NA
S-12	7/26/1994	128	<0.3	<0.3	<0.3	<0.6	NA	NA	20.71	7.92	12.79	NA	NA
S-12	10/28/1994	167	<0.3	<0.3	<0.3	<0.6	NA	NA	20.71	7.78	12.93	NA	NA
S-12	1/2/1995	50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.71	7.33	13.38	NA	NA
S-12	4/14/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.71	6.47	14.24	NA	NA
S-12	7/28/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.71	6.90	13.81	NA	NA
S-12	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.71	7.16	13.55	NA	NA
S-12	1/11/1996	<50	<0.5	<0.5	<0.5	<0.5	82	NA	20.71	6.65	14.06	NA	NA
S-12	7/21/1997	<50	<0.50	<0.50	<0.50	<0.50	45	NA	20.71	6.95	13.76	NA	NA
S-12	03/18/2002 d	NA	NA	NA	NA	NA	NA	NA	20.73	NA	NA	NA	NA
S-12	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	0.58	20.73	7.30	13.43	NA	NA
S-13	5/3/1989	150	4.9	4.0	2.0	14	NA	NA	20.57	NA	NA	NA	NA
S-13	8/10/1989	110	2.9	<1	<1	<3	NA	NA	20.57	8.00	12.57	NA	NA
S-13	10/9/1989	77	1.4	<1	<1	<3	NA	NA	20.57	7.95	12.62	NA	NA
S-13	1/25/1990	51	0.5	<0.5	<0.5	<1	NA	NA	20.57	7.79	12.78	NA	NA
S-13	4/18/1990	85	8.7	<0.5	<0.5	<1	NA	NA	20.57	7.73	12.84	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-13	7/23/1990	80	0.8	<0.5	<0.5	<0.5	NA	NA	20.57	7.63	12.94	NA	NA
S-13	10/18/1990	130	<0.5	<0.5	<0.5	<5	NA	NA	20.57	8.58	11.99	NA	NA
S-13	1/28/1991	<50	<0.5	0.9	1.2	1.0	NA	NA	20.57	8.39	12.18	NA	NA
S-13	4/25/1991	440a	3.8	<0.5	<0.5	0.6	NA	NA	20.57	7.00	13.57	NA	NA
S-13	7/9/1991	320a	0.6	<0.5	<0.5	<0.5	NA	NA	20.57	8.12	12.45	NA	NA
S-13	10/8/1991	310	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	8.69	11.88	NA	NA
S-13	2/5/1992	NA	NA	NA	NA	NA	NA	NA	20.57	7.62	12.95	NA	NA
S-13	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	7.15	13.42	NA	NA
S-13	7/27/1992	NA	NA	NA	NA	NA	NA	NA	20.57	8.20	12.37	NA	NA
S-13	10/26/1992	180	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	8.73	11.84	NA	NA
S-13	1/13/1993	NA	NA	NA	NA	NA	NA	NA	20.57	5.06	15.51	NA	NA
S-13	4/16/1993	240	4.8	<0.5	1.3	<0.5	NA	NA	20.57	6.38	14.19	NA	NA
S-13	7/23/1993	NA	NA	NA	NA	NA	NA	NA	20.57	7.45	13.12	NA	NA
S-13	10/27/1993	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
S-13	1/27/1994	NA	NA	NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
S-13	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.16	6.91	13.25	NA	NA
S-13	7/26/1994	NA	NA	NA	NA	NA	NA	NA	20.16	7.52	12.64	NA	NA
S-13	10/28/1994	368	<0.3	<0.3	<0.3	<0.6	NA	NA	20.16	7.68	12.48	NA	NA
S-13	1/2/1995	NA	NA	NA	NA	NA	NA	NA	20.16	6.37	13.79	NA	NA
S-13	4/14/1995	NA	NA	NA	NA	NA	NA	NA	20.16	5.81	14.35	NA	NA
S-13	7/28/1995	NA	NA	NA	NA	NA	NA	NA	20.16	6.73	13.43	NA	NA
S-13	10/17/1995	<50	1.0	<0.5	<0.5	<0.5	NA	NA	20.16	6.94	13.22	NA	NA
S-13	1/11/1996	NA	NA	NA	NA	NA	NA	NA	20.16	6.20	13.96	NA	NA
S-13	4/2/1996	<50	<0.5	<0.5	<0.5	<0.5	<2	NA	20.16	5.28	14.88	NA	NA
S-13	7/9/1996	NA	NA	NA	NA	NA	NA	NA	20.16	6.35	13.81	NA	NA
S-13	10/10/1996	<50	<0.50	<0.50	<0.50	<0.50	210	160	20.16	7.04	13.12	NA	NA
S-13	1/9/1997	NA	NA	NA	NA	NA	NA	NA	20.16	5.19	14.97	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-13	4/8/1997	<50	<0.50	<0.50	<0.50	<0.50	81	NA	20.16	6.62	13.54	NA	NA
S-13	7/21/1997	NA	NA	NA	NA	NA	NA	NA	20.16	6.76	13.40	NA	NA
S-13	10/8/1997	<50	<0.50	<0.50	<0.50	<0.50	110	NA	20.16	7.05	13.11	NA	NA
S-13	1/15/1998	NA	NA	NA	NA	NA	NA	NA	20.16	5.27	14.89	NA	NA
S-13	4/14/1998	<50	<0.50	<0.50	<0.50	<0.50	3.2	NA	20.16	5.24	14.92	NA	NA
S-13	7/14/1998	NA	NA	NA	NA	NA	NA	NA	20.16	5.48	14.68	NA	NA
S-13	10/20/1998	NA	NA	NA	NA	NA	NA	NA	20.16	7.08	13.08	NA	NA
S-13	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	92.2	NA	20.16	6.65	13.51	NA	NA
S-13	4/8/1999	NA	NA	NA	NA	NA	NA	NA	20.16	5.61	14.55	NA	NA
S-13	7/23/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<5.00	NA	20.16	6.78	13.38	NA	NA
S-13	10/26/1999	NA	NA	NA	NA	NA	NA	NA	20.16	7.33	12.83	NA	NA
S-13	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.16	7.51	12.65	NA	NA
S-13	4/14/2000	NA	NA	NA	NA	NA	NA	NA	20.16	6.08	14.08	NA	NA
S-13	7/12/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.16	6.50	13.66	NA	NA
S-13	11/1/2000	NA	NA	NA	NA	NA	NA	NA	20.16	6.10	14.06	NA	NA
S-13	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	21.2	23.9	20.16	7.09	13.07	NA	NA
S-13	4/24/2001	Well inaccessible		NA	NA	NA	NA	NA	20.16	NA	NA	NA	NA
S-13	7/2/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.16	7.13	13.03	NA	NA
S-13	11/2/2001	NA	NA	NA	NA	NA	NA	NA	20.16	7.38	12.78	NA	NA
S-13	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	5.9	20.16	6.02	14.14	NA	NA
S-13	4/1/2002	NA	NA	NA	NA	NA	NA	NA	20.16	6.26	13.90	NA	NA
S-13	7/11/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.16	7.00	13.16	NA	NA
S-13	10/28/2002	NA	NA	NA	NA	NA	NA	NA	20.19	7.70	12.49	NA	NA
S-13	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	110	20.19	6.41	13.78	NA	NA
S-13	4/30/2003	NA	NA	NA	NA	NA	NA	NA	20.19	6.12	14.07	NA	NA
S-13	7/1/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<0.50	20.19	7.65	12.54	NA	1.4
S-13	10/8/2003	NA	NA	NA	NA	NA	NA	NA	20.19	7.32	12.87	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

S-13	1/22/2004	<250	<2.5	<2.5	<2.5	<5.0	NA	NA	20.19	6.60	13.59	NA	NA
S-13	7/13/2004	NA	NA	NA	NA	NA	NA	NA	20.19	6.60	13.59	NA	e
S-13	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.19	6.56	13.63	NA	NA
S-13	7/19/2005	NA	NA	NA	NA	NA	NA	NA	20.19	6.15	14.04	NA	NA
S-13	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	20.19	6.42	13.77	NA	NA
S-13	7/25/2006	NA	NA	NA	NA	NA	NA	NA	20.19	7.51	12.68	NA	NA
S-13	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.19	6.85	13.34	NA	NA
S-13	7/24/2007	NA	NA	NA	NA	NA	NA	NA	20.19	7.39	12.80	NA	NA
S-13	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	20.19	6.00	14.19	NA	NA

S-14	5/3/1989	5300	750	400	200	800	NA	NA	20.44	NA	NA	NA	NA
S-14	8/10/1989	1800	540	140	42	50	NA	NA	20.44	7.58	12.86	NA	NA
S-14	10/9/1989	1000	360	60	20	30	NA	NA	20.44	7.62	12.82	NA	NA
S-14	1/25/1990	640	160	77	17	39	NA	NA	20.44	7.82	12.62	NA	NA
S-14	4/18/1990	1200	200	110	30	96	NA	NA	20.44	7.37	13.07	NA	NA
S-14	7/23/1990	5000	430	340	140	660	NA	NA	20.44	7.28	13.16	NA	NA
S-14	10/18/1990	1800	770	13	17	120	NA	NA	20.44	8.10	12.34	NA	NA
S-14	1/28/1991	720	200	36	21	78	NA	NA	20.44	8.04	12.40	NA	NA
S-14	4/25/1991	14000	930	430	250	970	NA	NA	20.44	6.40	14.04	NA	NA
S-14	7/9/1991	160	30	5.3	5	16	NA	NA	20.44	7.69	12.75	NA	NA
S-14	10/8/1991	5400	81	57	95	380	NA	NA	20.44	8.24	12.20	NA	NA
S-14	2/2/1992	NA	NA	NA	NA	NA	NA	NA	20.44	7.20	13.24	NA	NA
S-14	4/28/1992	2000	270	140	48	170	NA	NA	20.44	9.75	10.69	NA	NA
S-14	10/26/1992	920	33	12	25	88	NA	NA	20.44	8.32	12.12	NA	NA
S-14	1/13/1993	NA	NA	NA	NA	NA	NA	NA	20.44	5.07	15.37	NA	NA
S-14	4/16/1993	4500	1100	29	91	170	NA	NA	20.44	5.86	14.58	NA	NA
S-14	7/23/1993	NA	NA	NA	NA	NA	NA	NA	20.44	7.06	13.38	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

S-14	10/27/1993	Well inaccessible		NA	NA	NA	NA	NA	20.44	NA	NA	NA	NA
S-14	1/27/1994	NA	NA	NA	NA	NA	NA	NA	20.44	NA	NA	NA	NA
S-14	5/5/1994	810	250	<2.5	9.4	19	NA	NA	19.99	6.48	13.51	NA	NA
S-14	7/26/1994	NA	NA	NA	NA	NA	NA	NA	19.99	7.04	12.95	NA	NA
S-14	10/28/1994	5385	290.6	85.8	49.7	186.2	NA	NA	19.99	7.07	12.92	NA	NA
S-14	1/2/1995	NA	NA	NA	NA	NA	NA	NA	19.99	5.95	14.04	NA	NA
S-14	4/14/1995	1600	40	4.7	11	20	NA	NA	19.99	5.22	14.77	NA	NA
S-14	7/28/1995	NA	NA	NA	NA	NA	NA	NA	19.99	6.21	13.78	NA	NA
S-14	10/17/1995	1200	37	<0.5	7.8	11	NA	NA	19.99	6.30	13.69	NA	NA
S-14	1/11/1996	NA	NA	NA	NA	NA	NA	NA	19.99	5.70	14.29	NA	NA
S-14	7/21/1997	220	71	0.71	1.3	1.3	100	NA	19.99	6.14	13.85	NA	NA
S-14	03/18/2002 d	NA	NA	NA	NA	NA	NA	NA	20.01	NA	NA	NA	NA
S-14	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	55	20.01	6.20	13.81	NA	NA

S-15	5/3/1989	<50	<0.5	<1	<1	<3	NA	NA	22.22	NA	NA	NA	NA
S-15	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	22.22	8.48	13.74	NA	NA
S-15	10/9/1989	<50	<0.5	<1	<1	<3	NA	NA	22.22	8.46	13.76	NA	NA
S-15	1/25/1990	<50	<0.5	<1	<1	<1	NA	NA	22.22	8.34	13.88	NA	NA
S-15	4/18/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	22.22	8.45	13.77	NA	NA
S-15	7/23/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	8.22	14.00	NA	NA
S-15	10/18/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	9.11	13.11	NA	NA
S-15	1/28/1991	<50	<0.5	0.6	<0.5	0.8	NA	NA	22.22	9.13	13.09	NA	NA
S-15	4/25/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	7.83	14.39	NA	NA
S-15	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	8.93	13.29	NA	NA
S-15	10/8/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	9.26	12.96	NA	NA
S-15	2/5/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	8.60	13.62	NA	NA
S-15	4/28/1992	50	0.8	0.9	<0.5	1.4	NA	NA	22.22	8.09	14.13	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-15	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	8.83	13.39	NA	NA
S-15	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	9.31	12.91	NA	NA
S-15	1/14/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	22.22	6.64	15.58	NA	NA
S-15	4/16/1993	<50	0.6	1.0	<0.5	0.7	NA	NA	22.22	7.14	15.08	NA	NA
S-15	7/23/1993	<50	1.2	<0.5	<0.5	1.6	NA	NA	22.22	8.23	13.99	NA	NA
S-15	10/27/1993	Well inaccessible		NA	NA	NA	NA	NA	22.22	NA	NA	NA	NA
S-15	1/27/1994	Well inaccessible		NA	NA	NA	NA	NA	22.22	NA	NA	NA	NA
S-15	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.42	7.57	13.85	NA	NA
S-15	7/26/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	21.42	8.16	13.26	NA	NA
S-15	10/28/1994	<50	0.3	<0.3	<0.3	<0.6	NA	NA	21.42	7.87	13.55	NA	NA
S-15	1/2/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.42	7.02	14.40	NA	NA
S-15	4/14/1995	NA	NA	NA	NA	NA	NA	NA	21.42	6.19	15.23	NA	NA
S-15	7/28/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.42	6.72	14.70	NA	NA
S-15	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.42	7.04	14.38	NA	NA
S-15	1/11/1996	<50	<0.5	<0.5	<0.5	<0.5	<2	NA	21.42	6.40	15.02	NA	NA
S-15	03/18/2002 d	NA	NA	NA	NA	NA	NA	NA	21.47	NA	NA	NA	NA
S-15	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	<0.50	21.47	7.07	14.40	NA	NA
S-16	5/4/1994	380	44	3.0	2.0	<3	NA	NA	21.82	NA	NA	NA	NA
S-16	8/10/1989	<50	0.6	<1	<1	<3	NA	NA	21.82	8.36	13.46	NA	NA
S-16	10/10/1989	<5	<0.5	<1	<1	<3	NA	NA	21.82	8.23	13.59	NA	NA
S-16	1/25/1990	240	160	3.3	0.8	11	NA	NA	21.82	7.88	13.94	NA	NA
S-16	4/18/1990	<50	1.0	<0.5	<0.5	<1	NA	NA	21.82	8.19	13.63	NA	NA
S-16	7/23/1990	<50	1.1	<0.5	<0.5	<0.5	NA	NA	21.82	8.09	13.73	NA	NA
S-16	10/18/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.82	8.90	12.92	NA	NA
S-16	1/28/1991	<50	<0.5	0.6	<0.5	0.9	NA	NA	21.82	8.55	13.27	NA	NA
S-16	4/25/1991	60	21	0.5	3.2	4.8	NA	NA	21.82	7.48	14.34	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-16	7/9/1991	<50	1.0	<0.5	<0.5	<0.5	NA	NA	21.82	8.48	13.34	NA	NA
S-16	10/8/1991	50	17	1.4	1.2	5.5	NA	NA	21.82	8.95	12.87	NA	NA
S-16	2/5/1992	150	65	0.7	<0.5	8.4	NA	NA	21.82	8.20	13.62	NA	NA
S-16	4/28/1992	<50	13	<0.5	<0.5	<0.5	NA	NA	21.82	7.80	14.02	NA	NA
S-16	7/27/1992	510	130	<2.5	<0.5	21	NA	NA	21.82	8.29	13.53	NA	NA
S-16	10/26/1992	<50	<0.5	<0.5	<2.5	<0.5	NA	NA	21.82	9.02	12.80	NA	NA
S-16	1/13/1993	100	25	1.9	<0.5	8.4	NA	NA	21.82	5.78	16.04	NA	NA
S-16	4/16/1993	150	56	1.8	4.6	12	NA	NA	21.82	6.80	15.02	NA	NA
S-16	7/23/1993	<50	0.9	<0.5	<0.5	<0.5	NA	NA	21.82	7.67	14.15	NA	NA
S-16	10/27/1993	<50	1.5	<0.5	<0.5	<0.5	NA	NA	21.82	8.52	13.30	NA	NA
S-16	1/27/1994	140	85	<1	<1	13	NA	NA	21.82	7.20	14.62	NA	NA
S-16	5/5/1994	71	25	<0.5	<0.5	4.2	NA	NA	21.24	7.76	13.48	NA	NA
S-16	7/26/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	21.24	7.84	13.40	NA	NA
S-16	10/28/1994	<50	11.5	<0.3	<0.3	1.8	NA	NA	21.24	7.97	13.27	NA	NA
S-16	1/2/1995	70	64	<0.5	<0.5	4.0	NA	NA	21.24	6.49	14.75	NA	NA
S-16	4/14/1995	NA	NA	NA	NA	NA	NA	NA	21.24	6.08	15.16	NA	NA
S-16	7/28/1995	<50	1.7	<0.5	<0.5	<0.5	NA	NA	21.24	7.00	14.24	NA	NA
S-16	10/17/1995	<50	4.6	<0.5	<0.5	<0.5	NA	NA	21.24	7.15	14.09	NA	NA
S-16	1/11/1996	80	17	0.7	<0.5	2.9	<2	NA	21.24	6.30	14.94	NA	NA
S-16	4/2/1996	NA	NA	NA	NA	NA	NA	NA	21.24	5.84	15.40	NA	NA
S-16	7/9/1996	NA	NA	NA	NA	NA	NA	NA	21.24	6.72	14.52	NA	NA
S-16	10/10/1996	NA	NA	NA	NA	NA	NA	NA	21.24	7.41	13.83	NA	NA
S-16	1/9/1997	80	18	<0.50	1.7	4.8	<2.5	NA	21.24	5.60	15.64	NA	NA
S-16	4/8/1997	NA	NA	NA	NA	NA	NA	NA	21.24	7.34	13.90	NA	NA
S-16	7/21/1997	NA	NA	NA	NA	NA	NA	NA	21.24	7.20	14.04	NA	NA
S-16	10/8/1997	NA	NA	NA	NA	NA	NA	NA	21.24	7.34	13.90	NA	NA
S-16	1/15/1998	650	160	2.7	8.7	62	<12	NA	21.24	4.79	16.45	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-16	4/14/1998	NA	NA	NA	NA	NA	NA	NA	21.24	5.27	15.97	NA	NA
S-16	7/14/1998	NA	NA	NA	NA	NA	NA	NA	21.24	6.32	14.92	NA	NA
S-16	10/20/1998	NA	NA	NA	NA	NA	NA	NA	21.24	6.94	14.30	NA	NA
S-16	1/22/1999	Well inaccessible		NA	NA	NA	NA	NA	21.24	NA	NA	NA	NA
S-16	4/8/1999	NA	NA	NA	NA	NA	NA	NA	21.24	5.80	15.44	NA	NA
S-16	7/23/1999	NA	NA	NA	NA	NA	NA	NA	21.24	6.62	14.62	NA	NA
S-16	10/26/1999	NA	NA	NA	NA	NA	NA	NA	21.24	7.42	13.82	NA	NA
S-16	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	21.24	7.34	13.90	NA	NA
S-16	4/14/2000	NA	NA	NA	NA	NA	NA	NA	21.24	6.27	14.97	NA	NA
S-16	7/12/2000	NA	NA	NA	NA	NA	NA	NA	21.24	7.02	14.22	NA	NA
S-16	11/1/2000	NA	NA	NA	NA	NA	NA	NA	21.24	6.79	14.45	NA	NA
S-16	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	3.05	NA	21.24	7.18	14.06	NA	NA
S-16	4/24/2001	NA	NA	NA	NA	NA	NA	NA	21.24	6.85	14.39	NA	NA
S-16	7/2/2001	NA	NA	NA	NA	NA	NA	NA	21.24	7.51	13.73	NA	NA
S-16	11/2/2001	NA	NA	NA	NA	NA	NA	NA	21.24	7.68	13.56	NA	NA
S-16	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.24	6.40	14.84	NA	NA
S-16	4/1/2002	NA	NA	NA	NA	NA	NA	NA	21.24	6.33	14.91	NA	NA
S-16	7/11/2002	NA	NA	NA	NA	NA	NA	NA	21.24	7.39	13.85	NA	NA
S-16	10/28/2002	NA	NA	NA	NA	NA	NA	NA	21.30	8.00	13.30	NA	NA
S-16	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	21.30	6.36	14.94	NA	NA
S-16	4/30/2003	NA	NA	NA	NA	NA	NA	NA	21.30	6.03	15.27	NA	NA
S-16	7/1/2003	NA	NA	NA	NA	NA	NA	NA	21.30	7.28	14.02	NA	NA
S-16	10/8/2003	NA	NA	NA	NA	NA	NA	NA	21.30	7.77	13.53	NA	NA
S-16	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.30	6.80	14.50	NA	NA
S-16	7/13/2004	NA	NA	NA	NA	NA	NA	NA	21.30	7.94	13.36	NA	NA
S-16	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.30	5.62	15.68	NA	NA
S-16	7/19/2005	NA	NA	NA	NA	NA	NA	NA	21.30	6.53	14.77	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-16	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	21.30	6.05	15.25	NA	NA
S-16	7/25/2006	NA	NA	NA	NA	NA	NA	NA	21.30	7.19	14.11	NA	NA
S-16	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	21.30	6.89	14.41	NA	NA
S-16	7/24/2007	NA	NA	NA	NA	NA	NA	NA	21.30	7.60	13.70	NA	NA
S-16	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	21.30	5.82	15.48	NA	NA
S-17	5/3/1989	<50	<0.5	<1	<1	<3	NA	NA	20.95	NA	NA	NA	NA
S-17	8/10/1989	<50	<0.5	<1	<1	<3	NA	NA	20.95	8.13	12.82	NA	NA
S-17	10/9/1989	<50	<0.5	<1	<1	<3	NA	NA	20.95	8.18	12.77	NA	NA
S-17	1/25/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	20.95	7.60	13.35	NA	NA
S-17	4/18/1990	<50	<0.5	<0.5	<0.5	<1	NA	NA	20.95	7.95	13.00	NA	NA
S-17	7/23/1990	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	7.87	13.08	NA	NA
S-17	10/18/1990	390	10	62	22	110	NA	NA	20.95	8.71	12.24	NA	NA
S-17	1/28/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	8.54	12.41	NA	NA
S-17	4/25/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	7.15	13.80	NA	NA
S-17	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	8.24	12.71	NA	NA
S-17	10/8/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	8.86	12.09	NA	NA
S-17	2/5/1992	NA	NA	NA	NA	NA	NA	NA	20.95	7.74	13.21	NA	NA
S-17	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	7.41	13.54	NA	NA
S-17	7/27/1992	NA	NA	NA	NA	NA	NA	NA	20.95	8.34	12.61	NA	NA
S-17	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	8.87	12.08	NA	NA
S-17	1/13/1993	NA	NA	NA	NA	NA	NA	NA	20.95	3.43	17.52	NA	NA
S-17	4/16/1993	130	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	6.70	14.25	NA	NA
S-17	7/23/1993	NA	NA	NA	NA	NA	NA	NA	20.95	7.53	13.42	NA	NA
S-17	10/27/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.95	8.29	12.66	NA	NA
S-17	1/27/1994	NA	NA	NA	NA	NA	NA	NA	20.95	5.78	15.17	NA	NA
S-17	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.45	6.99	13.46	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-17	7/26/1994	NA	NA	NA	NA	NA	NA	NA	20.45	7.62	12.83	NA	NA
S-17	10/28/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	20.45	7.91	12.54	NA	NA
S-17	1/2/1995	NA	NA	NA	NA	NA	NA	NA	20.45	6.33	14.12	NA	NA
S-17	4/14/1995	NA	NA	NA	NA	NA	NA	NA	20.45	5.53	14.92	NA	NA
S-17	7/28/1995	NA	NA	NA	NA	NA	NA	NA	20.45	6.75	13.70	NA	NA
S-17	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.45	7.15	13.30	NA	NA
S-17	1/11/1996	NA	NA	NA	NA	NA	NA	NA	20.45	6.37	14.08	NA	NA
S-17	4/2/1996	<50	<0.5	<0.5	<0.5	<0.5	<2	NA	20.45	5.31	15.14	NA	NA
S-17	7/9/1996	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	6.30	14.15	NA	NA
S-17	10/10/1996	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	7.80	12.65	NA	NA
S-17	1/9/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	4.80	15.65	NA	NA
S-17	4/8/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	6.83	13.62	NA	NA
S-17 (D)	4/8/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	NA	NA	NA	NA
S-17	7/21/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	6.78	13.67	NA	NA
S-17	10/8/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	6.80	13.65	NA	NA
S-17	1/15/1998	380	<0.50	<0.50	<0.50	0.94	<2.5	NA	20.45	2.91	17.54	NA	NA
S-17	4/14/1998	160	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	4.47	15.98	NA	NA
S-17	7/14/1998	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	6.45	14.00	NA	NA
S-17	10/20/1998	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.45	7.11	13.34	NA	NA
S-17	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<2.00	NA	20.45	6.01	14.44	NA	NA
S-17	4/8/1999	145	<0.500	<0.500	<0.500	<0.500	<5.00	NA	20.45	4.69	15.76	NA	NA
S-17	7/23/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<5.00	NA	20.45	6.60	13.85	NA	NA
S-17	10/26/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.45	6.68	13.77	NA	NA
S-17	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.45	7.20	13.25	NA	NA
S-17	4/14/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.45	5.88	14.57	NA	NA
S-17	7/12/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.45	6.45	14.00	NA	NA
S-17	11/1/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.45	5.45	15.00	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-17	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.45	7.22	13.23	NA	NA
S-17	4/24/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<0.50	20.45	6.10	14.35	NA	NA
S-17	7/2/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.45	6.95	13.50	NA	NA
S-17	11/2/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.45	7.50	12.95	NA	NA
S-17	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.45	5.76	14.69	NA	NA
S-17	4/1/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.45	6.02	14.43	NA	NA
S-17	7/11/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.45	6.97	13.48	NA	NA
S-17	10/28/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<0.50	20.44	7.60	12.84	NA	0.9
S-17	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.44	5.77	14.67	NA	NA
S-17	4/30/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<5.0	20.44	5.35	15.09	NA	NA
S-17	7/1/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<0.50	20.44	6.95	13.49	NA	1.1
S-17	10/8/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<0.50	20.44	7.01	13.43	NA	NA
S-17	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.44	6.57	13.87	NA	NA
S-17	7/13/2004	NA	NA	NA	NA	NA	NA	NA	20.36 f	7.71	12.65	NA	NA
S-17	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.36 f	5.09	15.27	NA	NA
S-17	7/19/2005	NA	NA	NA	NA	NA	NA	NA	20.36	6.30	14.06	NA	NA
S-17	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	20.36	5.50	14.86	NA	NA
S-17	7/25/2006	NA	NA	NA	NA	NA	NA	NA	20.36	6.84	13.52	NA	NA
S-17	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.36	6.15	14.21	NA	NA
S-17	7/24/2007	NA	NA	NA	NA	NA	NA	NA	20.36	6.92	13.44	NA	NA
S-17	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	20.36	5.05	15.31	NA	NA

S-18	5/31/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	NA	NA	NA	NA
S-18	7/9/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	8.23	12.80	NA	NA
S-18	10/8/1991	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	8.84	12.19	NA	NA
S-18	2/5/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	7.67	13.36	NA	NA
S-18	4/28/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	7.40	13.63	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-18	7/27/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	8.38	12.65	NA	NA
S-18	10/26/1992	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	8.83	12.20	NA	NA
S-18	1/13/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	5.86	15.17	NA	NA
S-18	4/16/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	4.88	16.15	NA	NA
S-18	7/23/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	7.56	13.47	NA	NA
S-18	10/27/1993	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	21.03	8.30	12.73	NA	NA
S-18	1/27/1994	<50	1.9	<0.5	<0.5	<0.5	NA	NA	21.03	6.84	14.19	NA	NA
S-18	5/5/1994	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	7.05	13.52	NA	NA
S-18	7/26/1994	<500	<3	1.1	<0.3	1.8	NA	NA	20.57	7.62	12.95	NA	NA
S-18	10/28/1994	<50	<0.3	<0.3	<0.3	<0.6	NA	NA	20.57	8.01	12.56	NA	NA
S-18	1/2/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	6.26	14.31	NA	NA
S-18	4/14/1995	NA	NA	NA	NA	NA	NA	NA	20.57	4.85	15.72	NA	NA
S-18	7/28/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	5.80	14.77	NA	NA
S-18	10/17/1995	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	20.57	7.22	13.35	NA	NA
S-18	1/11/1996	<50	<0.5	<0.5	<0.5	<0.5	<2	NA	20.57	6.40	14.17	NA	NA
S-18	4/2/1996	NA	NA	NA	NA	NA	NA	NA	20.57	4.80	15.77	NA	NA
S-18	7/9/1996	NA	NA	NA	NA	NA	NA	NA	20.57	5.74	14.83	NA	NA
S-18	10/10/1996	NA	NA	NA	NA	NA	NA	NA	20.57	6.06	14.51	NA	NA
S-18	1/9/1997	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.57	4.70	15.87	NA	NA
S-18	4/8/1997	NA	NA	NA	NA	NA	NA	NA	20.57	6.62	13.95	NA	NA
S-18	7/21/1997	NA	NA	NA	NA	NA	NA	NA	20.57	6.94	13.63	NA	NA
S-18	10/8/1997	NA	NA	NA	NA	NA	NA	NA	20.57	6.88	13.69	NA	NA
S-18	1/15/1998	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.57	3.60	16.97	NA	NA
S-18	4/14/1998	NA	NA	NA	NA	NA	NA	NA	20.57	4.28	16.29	NA	NA
S-18	7/14/1998	NA	NA	NA	NA	NA	NA	NA	20.57	6.13	14.44	NA	NA
S-18	10/20/1998	NA	NA	NA	NA	NA	NA	NA	20.57	7.20	13.37	NA	NA
S-18	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<2.00	NA	20.57	6.00	14.57	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-18	4/8/1999	NA	NA	NA	NA	NA	NA	NA	20.57	4.95	15.62	NA	NA
S-18	7/23/1999	NA	NA	NA	NA	NA	NA	NA	20.57	6.03	14.54	NA	NA
S-18	10/26/1999	NA	NA	NA	NA	NA	NA	NA	20.57	7.39	13.18	NA	NA
S-18	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.57	7.54	13.03	NA	NA
S-18	4/14/2000	NA	NA	NA	NA	NA	NA	NA	20.57	4.41	16.16	NA	NA
S-18	7/12/2000	NA	NA	NA	NA	NA	NA	NA	20.57	5.31	15.26	NA	NA
S-18	11/1/2000	NA	NA	NA	NA	NA	NA	NA	20.57	6.42	14.15	NA	NA
S-18	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	3.67	NA	20.57	7.30	13.27	NA	NA
S-18	4/24/2001	NA	NA	NA	NA	NA	NA	NA	20.57	6.83	13.74	NA	NA
S-18	7/2/2001	NA	NA	NA	NA	NA	NA	NA	20.57	7.23	13.34	NA	NA
S-18	11/2/2001	Unable to locate		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
S-18	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.57	6.15	14.42	NA	NA
S-18	4/1/2002	NA	NA	NA	NA	NA	NA	NA	20.57	6.06	14.51	NA	NA
S-18	7/11/2002	NA	NA	NA	NA	NA	NA	NA	20.57	6.98	13.59	NA	NA
S-18	10/28/2002	NA	NA	NA	NA	NA	NA	NA	20.63	7.66	12.97	NA	NA
S-18	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.63	6.18	14.45	NA	NA
S-18	4/30/2003	NA	NA	NA	NA	NA	NA	NA	20.63	5.32	15.31	NA	NA
S-18	7/1/2003	NA	NA	NA	NA	NA	NA	NA	20.63	7.20	13.43	NA	NA
S-18	10/8/2003	NA	NA	NA	NA	NA	NA	NA	20.63	7.48	13.15	NA	NA
S-18	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.63	6.74	13.89	NA	NA
S-18	7/13/2004	NA	NA	NA	NA	NA	NA	NA	20.63	7.87	12.76	NA	NA
S-18	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.63	5.33	15.30	NA	NA
S-18	7/19/2005	NA	NA	NA	NA	NA	NA	NA	20.63	6.55	14.08	NA	NA
S-18	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	20.63	5.89	14.74	NA	NA
S-18	7/25/2006	NA	NA	NA	NA	NA	NA	NA	20.63	7.10	13.53	NA	NA
S-18	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.63	6.60	14.03	NA	NA
S-18	7/24/2007	NA	NA	NA	NA	NA	NA	NA	20.63	7.13	13.50	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-18	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	20.63	5.25	15.38	NA	NA
S-19	10/20/1998	<50	<0.50	<0.50	<0.50	<0.50	<2.5	NA	20.11	6.41	13.70	NA	NA
S-19	1/22/1999	<50.0	<0.500	<0.500	<0.500	<0.500	90.6	NA	20.11	5.42	14.69	NA	NA
S-19	4/8/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<5.00	NA	20.11	4.61	15.50	NA	NA
S-19	7/23/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<5.00	NA	20.11	5.86	14.25	NA	NA
S-19	10/26/1999	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.11	6.28	13.83	NA	NA
S-19	1/3/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.11	6.62	13.49	NA	NA
S-19	4/14/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.11	4.31	15.80	NA	NA
S-19	7/12/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.11	5.46	14.65	NA	NA
S-19	11/1/2000	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	NA	20.11	5.05	15.06	NA	NA
S-19	1/3/2001	<50.0	<0.500	<0.500	<0.500	<0.500	9.61	NA	20.11	6.00	14.11	NA	NA
S-19	4/24/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<0.50	20.11	5.58	14.53	NA	NA
S-19	7/2/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.11	6.34	13.77	NA	3.4
S-19	11/2/2001	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.11	6.57	13.54	NA	3.4
S-19	1/16/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.11	5.05	15.06	NA	0.5
S-19	4/1/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.11	5.13	14.98	NA	3.3
S-19	7/11/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.11	5.50	14.61	NA	0.5
S-19	10/28/2002	<50	<0.50	<0.50	<0.50	<0.50	NA	<0.50	20.10	6.35	13.75	NA	0.6
S-19	1/23/2003	<50	<0.50	<0.50	<0.50	<0.50	NA	<5.0	20.10	5.15	14.95	NA	0.3
S-19	4/30/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<5.0	20.10	4.90	15.20	NA	0.5
S-19	7/1/2003	<50	<0.50	<0.50	<0.50	<1.0	NA	<0.50	20.10	5.50	14.60	NA	1.7
S-19	10/8/2003	58	<0.50	<0.50	<0.50	<1.0	NA	<0.50	20.10	6.63	13.47	NA	0.4
S-19	1/22/2004	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.10	5.67	14.43	NA	0.6
S-19	7/13/2004	NA	NA	NA	NA	NA	NA	NA	20.10	6.82	13.28	NA	1.0
S-19	1/20/2005	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.10	4.75	15.35	NA	0.6
S-19	7/19/2005	NA	NA	NA	NA	NA	NA	NA	20.10	5.15	14.95	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
S-19	1/27/2006	<50.0	<0.500	<0.500	<0.500	<0.500	NA	NA	20.10	4.85	15.25	NA	NA
S-19	7/25/2006	NA	NA	NA	NA	NA	NA	NA	20.10	6.14	13.96	NA	NA
S-19	1/4/2007	<50	<0.50	<0.50	<0.50	<1.0	NA	NA	20.10	5.75	14.35	NA	NA
S-19	7/24/2007	NA	NA	NA	NA	NA	NA	NA	20.10	6.39	13.71	NA	NA
S-19	1/15/2008	<50 g	<0.50	<1.0	<1.0	<1.0	NA	NA	20.10	4.72	15.38	NA	NA
SR-1	3/22/1989	5400	1100	230	350	1300	NA	NA	21.45	NA	NA	NA	NA
SR-1	1/25/1990	2200	470	120	110	510	NA	NA	21.45	7.53	13.92	NA	NA
SR-1	4/18/1990	1000	130	47	47	220	NA	NA	21.45	8.17	13.28	NA	NA
SR-1	7/23/1990	3200	470	320	170	870	NA	NA	21.45	7.58	13.87	NA	NA
SR-1	10/18/1990	1300	280	6.6	110	130	NA	NA	21.45	8.81	12.64	NA	NA
SR-1	1/28/1991	110	120	12	51	110	NA	NA	21.45	8.37	13.08	NA	NA
SR-1	4/25/1991	NA	NA	NA	NA	NA	NA	NA	21.45	6.91	14.54	NA	NA
SR-1	7/9/1991	1400	200	27	130	340	NA	NA	21.45	8.11	13.34	NA	NA
SR-1	10/8/1991	980	79	1.5	44	52	NA	NA	21.45	8.63	12.82	NA	NA
SR-1	2/5/1991	3800	580	36	320	400	NA	NA	21.45	7.68	13.77	NA	NA
SR-1	4/28/1992	38000	1800	460	1900	750	NA	NA	21.45	7.27	14.18	NA	NA
SR-1	7/27/1992	NA	NA	NA	NA	NA	NA	NA	21.45	8.11	13.34	0.01	NA
SR-1	10/26/1992	1800	370	10	130	130	NA	NA	21.45	8.63	12.82	NA	NA
SR-1	1/13/1993	47000	1000	1100	1700	13000	NA	NA	21.45	5.46	15.99	NA	NA
SR-1	4/16/1993	25000	1700	430	2400	8300	NA	NA	21.45	6.28	15.17	NA	NA
SR-1	7/23/1993	33000	2400	2000	3800	14000	NA	NA	21.45	7.34	14.11	NA	NA
SR-1	10/27/1993	2300	340	<12.5	270	440	NA	NA	21.45	8.04	13.41	NA	NA
SR-1	1/27/1994	36000	2000	1700	3000	11000	NA	NA	21.45	6.68	14.77	NA	NA
SR-1	5/5/1994	43000	1500	130	2900	12000	NA	NA	20.57	6.81	13.76	NA	NA
SR-1	7/26/1994	13600	682.7	39.2	996.6	2516	NA	NA	20.57	7.38	13.19	NA	NA
SR-1	10/28/1994	8462	301.5	29.3	384.7	2019	NA	NA	20.57	7.48	13.09	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
SR-1	1/2/1995	13000	400	120	2500	10000	NA	NA	20.57	6.34	14.23	NA	NA
SR-1	4/14/1995	43000	690	370	2500	12000	NA	NA	20.57	5.29	15.28	NA	NA
SR-1	7/28/1995	35000	760	120	2300	8100	NA	NA	20.57	6.36	14.21	NA	NA
SR-1	10/17/1995	9700	310	12	610	1200	NA	NA	20.57	6.62	13.95	NA	NA
SR-1 (D)	10/17/1995	8300	230	9.6	680	840	NA	NA	20.57	NA	NA	NA	NA
SR-1	1/11/1996	18000	410	170	1200	4400	42	NA	20.57	5.66	14.91	NA	NA
SR-1 (D)	1/11/1996	17000	420	180	1100	4000	42	NA	20.57	NA	NA	NA	NA
SR-1	4/2/1996	NA	NA	NA	NA	NA	NA	NA	20.57	5.14	15.43	NA	NA
SR-1	7/9/1996	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
SR-1	10/10/1996	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
SR-1	1/9/1997	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
SR-1	4/8/1997	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
SR-1	7/21/1997	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
SR-1	10/8/1997	NA	NA	NA	NA	NA	NA	NA	20.57	6.94	13.63	NA	NA
SR-1	1/15/1998	8100	82	<25	36	2300	<125	NA	20.57	4.30	16.27	NA	NA
SR-1	4/14/1998	Well inaccessible		NA	NA	NA	NA	NA	20.57	NA	NA	NA	NA
SR-1	7/14/1998	NA	NA	NA	NA	NA	NA	NA	20.28	6.48	13.80	NA	NA
SR-1	10/20/1998	NA	NA	NA	NA	NA	NA	NA	20.28	6.61	13.67	NA	NA
SR-1	1/22/1999	Well inaccessible		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	4/8/1999	NA	NA	NA	NA	NA	NA	NA	20.28	0.97	19.31	NA	NA
SR-1	7/23/1999	Well dry	NA	NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	10/26/1999	Well dry	NA	NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	4/14/2000	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	7/12/2000	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	11/1/2000	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	1/3/2001	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	4/24/2001	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

SR-1	7/2/2001	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	11/2/2001	Well dry	NA	NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	1/16/2002	Well dry	NA	NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	4/1/2002	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	7/11/2002	Obstruction in well		NA	NA	NA	NA	NA	20.28	NA	NA	NA	NA
SR-1	10/28/2002	Obstruction in well		NA	NA	NA	NA	NA	20.27	NA	NA	NA	NA
SR-1	1/23/2003	Obstruction in well		NA	NA	NA	NA	NA	20.27	NA	NA	NA	NA
SR-1	4/30/2003	Obstruction in well		NA	NA	NA	NA	NA	20.27	NA	NA	NA	NA
SR-1	7/1/2003	Obstruction in well		NA	NA	NA	NA	NA	20.27	NA	NA	NA	NA
SR-1	10/8/2003	Well dry	NA	NA	NA	NA	NA	NA	20.27	NA	NA	NA	NA

SV-1	04/15/1998 b	NA	NA	NA	NA	NA	NA	NA	NA	6.02	NA	NA	NA
SV-1	04/15/1998 c	NA	NA	NA	NA	NA	NA	NA	NA	7.15	NA	NA	NA
SV-1	03/18/2002 d	NA	NA	NA	NA	NA	NA	NA	21.31	NA	NA	NA	NA
SV-1	1/22/2004	3000	15	<2.5	34	11	NA	<2.5	21.31	6.67	14.64	NA	NA

Abbreviations:

TPPH = Total petroleum hydrocarbons as gasoline by EPA Method 8260B; prior to April 24, 2001, analyzed by EPA Method 8015.

BTEX = Benzene, toluene, ethylbenzene, xylenes by EPA Method 8260B; prior to April 24, 2001, analyzed by EPA Method 8020.

MTBE = Methyl tertiary butyl ether

TOC = Top of Casing Elevation

SPH = Separate-Phase Hydrocarbons

GW = Groundwater

DO = Dissolved Oxygen

ug/L = Parts per billion

MSL = Mean sea level

ppm = Parts per million

ft. = Feet

TABLE 1
GROUNDWATER GUAGING ANALYTICAL DATA
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Well ID	Date	TPPH (ug/L)	B (ug/L)	T (ug/L)	E (ug/L)	X (ug/L)	MTBE 8020 (ug/L)	MTBE 8260 (ug/L)	TOC (MSL)	Depth to Water (ft.)	GW Elevation (MSL)	SPH Thickness (ft.)	DO Reading (ppm)
---------	------	----------------	-------------	-------------	-------------	-------------	------------------------	------------------------	--------------	----------------------------	--------------------------	---------------------------	------------------------

<n = Below detection limit

(D) = Duplicate sample

NA = Not applicable

Notes:

a = Chromatogram pattern indicated an unidentified hydrocarbon.

b = Pre-development sample

c = Post-development sample

d = Survey date only.

e = DO reading not taken.

f = TOC lowered 0.08 feet due to wellhead maintenance on June 3, 2004.

g = Analyzed by EPA Method 8015B (M).

h = The sample chromatographic pattern for TPH does not match the chromatographic pattern of the specified standard. Quantitation of the unknown hydrocarbon(s) in the sample was based upon the specified standard.

i = Analyte was detected at a concentration below the reporting limit and above the laboratory method detection limit. Reported value is estimated.

Site surveyed March 18, 2002 by Virgil Chavez Land Surveying of Vallejo, CA.



FIGURES

DRAWING NUMBER
SCA152751

APPROVED BY

CHECKED BY

DRAWN BY
J.F.F.



SHELL OIL PRODUCTS US
SHELL SERVICE STATION
SAN LEANDRO, CALIFORNIA

FIGURE 1
SITE LOCATION MAP

15275 WASHINGTON AVENUE
SAN LEANDRO, CALIFORNIA


PROJECT NUMBER SCA152751

APPROVED BY

CHECKED BY

DRAWN BY J.F.F. 4/14/2008

SCALE IN FEET 0 25 50




DELTA CONSULTANTS

SHELL OIL PRODUCTS US
FORMER SHELL-BRANDED SERVICE STATION
SAN LEANDRO, CALIFORNIA


FIGURE 2
GROUNDWATER ELEVATION CONTOUR
MAP
1/15/2008
15275 WASHINGTON AVENUE
SAN LEANDRO, CALIFORNIA

PROJECT NUMBER SCA152751
 APPROVED BY
 CHECKED BY
 DRAWN BY J.F.F. 4/4/2008



- LEGEND**
- S-6 GROUNDWATER MONITORING WELL LOCATION AND DESIGNATION
 - S-1 GROUNDWATER MONITORING WELL MODIFIED FOR SOIL VAPOR EXTRACTION
 - SV-1 SOIL VAPOR EXTRACTION WELL LOCATION AND DESIGNATION
 - TPH-g TOTAL PETROLEUM HYDROCARBONS AS GASOLINE
 - ND< NOT DETECTED ABOVE LIMIT NOTED
 - μg/L MICROGRAMS PER LITER
 - 0.012 ft/ft APPROXIMATE GROUNDWATER GRADIENT DIRECTION (ft/ft)
 - h THE SAMPLE CHROMATOGRAPHIC PATTERN FOR TPH DOES NOT MATCH THE PATTERN OF THE SPECIFIED STANDARD. QUANTIFICATION OF THE UNKNOWN HYDROCARBON(S) WAS BASED UPON THE SPECIFIED STANDARD.

0 25 50
 SCALE IN FEET



DELTA CONSULTANTS

SHELL OIL PRODUCTS US
 FORMER SHELL-BRANDED SERVICE STATION
 SAN LEANDRO, CALIFORNIA

FIGURE 3
 HYDROCARBON DISTRIBUTION
 IN GROUNDWATER MAP
 1/15/2008
 15275 WASHINGTON AVENUE
 SAN LEANDRO, CALIFORNIA

APPENDIX A

FIELD DATA SHEETS

SHELL WELLHEAD INSPECTION FORM

(FOR SAMPLE TECHNICIAN)

Site Address 15275 Washington Ave, San Leandro Date 1/15/08
 Job Number 080115-KF2 Technician KF Page 1 of 1

Well ID	Well Inspected - No Corrective Action Required	Well Box Meets Compliance Requirements *See Below	Water Bailed From Wellbox	Cap Replaced	Lock Replaced	Well Not Inspected (explain in notes)	New Deficiency Identified	Previously Identified Deficiency Persists	Notes
S-1	X	X							
S-3									3/4 tabs stripped
S-5								X	1/4 bolts missing
S-7	X	X							
S-8									4/4 bolts missing
S-9	X	X							
S-10	X	X							
S-13	X								christie box
S-16	X	X							
S-17	X	X							
S-18						broken cap			broken cap (still securable)
S-19	X	X							christie box
S-19		X	X						

*Well box must meet all three criteria to be compliant: 1) WELL IS SECURABLE BY DESIGN (12" or less) 2) WELL IS MARKED WITH THE WORDS "MONITORING WELL" (12" or less) 3) WELL TAG IS PRESENT, SECURE, AND CORRECT

Notes: _____

WELL GAUGING DATA

Project # 080115-KF2 Date 1/15/08 Client Shell

Site 15275 Washington Ave, San Leandro

Well ID	Time	Well Size (in.)	Sheen / Odor	Depth to Immiscible Liquid (ft.)	Thickness of Immiscible Liquid (ft.)	Volume of Immiscibles Removed (ml)	Depth to water (ft.)	Depth to well bottom (ft.)	Survey Point: TOB or TOC	Notes
S-1	1432	3					6.10	19.71		
S-3	1512	2					5.41	20.97		
S-5	1354	4					5.83	17.96		
S-7	1442	3					6.08	23.79		
S-8	1453	3					5.32	23.87		
S-9	1501	3					5.20	17.55		
S-10	1320	3					5.33	17.73		
S-13	1230	3					6.00	23.20		
S-16	1414	3					5.82	23.31		
S-17	1145	3					5.05	23.72		
S-18	1121	3					5.25	17.61		
S-19	1230	3					6.00	23.20	↓	
S-19	1303	3					4.72	20.12		

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KR, KF	Date: 1/15/08
Well I.D.: S-1	Well Diameter: 2 2 6 8
Total Well Depth (TD): 19.71	Depth to Water (DTW): 6.10
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Waterra Sampling Method: Bailer
 Disposable Bailer Peristaltic Disposable Bailer
 Positive Air Displacement Extraction Pump Extraction Port
 Electric Submersible Other _____ Dedicated Tubing

Other: _____

_____ (Gals.) X _____	=	_____ Gals.
1 Case Volume	Specified Volumes	Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1435	61.3	7.93	280.5	145	—	Clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1435 Depth to Water: —

Sample I.D.: S-1 Laboratory: STL Other: CalScience

Analyzed for: TPH-G BTEX MTBE TPH-D Other: SEE LOC

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 08015-KF2	Site: 97093412
Sampler: KF, KR	Date: 1/15/08
Well I.D.: S-3	Well Diameter: (2) 3 4 6 8
Total Well Depth (TD): 20.97	Depth to Water (DTW): 5.41
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: (PVE) Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Disposable Bailer Positive Air Displacement Electric Submersible Water Peristaltic Extraction Pump Other _____

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing Other: _____

(Gals.) X _____ = _____ Gals.
 1 Case Volume Specified Volumes Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or µS)	Turbidity (NTUs)	Gals. Removed	Observations
1516	60.0	60.8 7.26	1037	24.1	—	clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1516 Depth to Water: —

Sample I.D.: S-3 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see LSC

EB I.D. (if applicable): @ _____ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF	Date: 1/15/08
Well I.D.: S-5	Well Diameter: 2 3 4 6 8 _____
Total Well Depth (TD): 17.96	Depth to Water (DTW): 5.83
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Watera Sampling Method: Bailer
 Disposable Bailer Peristaltic Disposable Bailer
 Positive Air Displacement Extraction Pump Extraction Port
 Electric Submersible Other _____ Dedicated Tubing

Other: _____

_____ (Gals.) X	_____ = _____	_____ Gals.
1 Case Volume	Specified Volumes	Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1358	62.9	7.41	964	154	—	clear w/sediment

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1358 Depth to Water: —

Sample I.D.: S-5 Laboratory: STL Other: CalScience

Analyzed for: TPH-G BTEX MTBE TPH-D Other: SEE CDC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF, KR	Date: 1/15/08
Well I.D.: 5-7	Well Diameter: 2 (3) 4 6 8
Total Well Depth (TD): 23.79	Depth to Water (DTW): 6.08
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Disposable Bailer Positive Air Displacement Electric Submersible

Water: Waterra Peristaltic Extraction Pump Other

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing

Other: _____

$\frac{\text{_____ (Gals.)} \times \text{_____}}{\text{Specified Volumes}} = \text{_____ Gals.}$ 1 Case Volume Calculated Volume	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1445	59.3	7.39	1119	173		

Did well dewater? Yes No Gallons actually evacuated: _____

Sampling Date: 1/15/08 Sampling Time: 1445 Depth to Water: _____

Sample I.D.: 5-7 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see loc

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF, KR	Date: 1/15/08
Well I.D.: S-8	Well Diameter: 2 (3) 4 6 8
Total Well Depth (TD): 23.87	Depth to Water (DTW): 5.32
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Waterra Disposable Bailer Peristaltic Positive Air Displacement Extraction Pump Electric Submersible Other _____

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing

Other: _____

_____ (Gals.) X _____ = _____ Gals.
 1 Case Volume Specified Volumes Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1455	61.8	7.42	865.7	34	—	clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1455 Depth to Water: —

Sample I.D.: S-8 Laboratory: STL Other: CalScience

Analyzed for: TPH-G BTEX MTBE TPH-D Other: SEC LOC

EB I.D. (if applicable): @ _____ Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97693412
Sampler: ICF, KR	Date: 1/15/08
Well I.D.: S-9	Well Diameter: 2 <u>3</u> 4 6 8
Total Well Depth (TD): 17.55	Depth to Water (DTW): 5.20
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Disposable Bailer Positive Air Displacement Electric Submersible

Water Peristaltic Extraction Pump Other _____

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing

Other: _____

_____ (Gals.) X _____ = _____ Gals.
I Case Volume Specified Volumes Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1505	63.2	7.32	925	8.4	—	clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1505 Depth to Water: —

Sample I.D.: S-9 Laboratory: STL Other: Cal Services

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see CDC

EB I.D. (if applicable): @ _____ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF	Date: 1/15/08
Well I.D.: S-10	Well Diameter: 2 <u>3</u> 4 6 8
Total Well Depth (TD): 17.73	Depth to Water (DTW): 5.33
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Waterra Sampling Method: Bailer
 Disposable Bailer Peristaltic Disposable Bailer
 Positive Air Displacement Extraction Pump Extraction Port
 Electric-Submersible Other _____ Dedicated Tubing

$\frac{\text{(Gals.) X}}{\text{Specified Volumes}} = \text{Calculated Volume Gals.}$	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1330	61.9	7.72	817	196	—	clear w/ debris

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1330 Depth to Water: —

Sample I.D.: S-10 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: See CDC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: <u>080115-KF2</u>	Site: <u>97093412</u>
Sampler: <u>KF</u>	Date: <u>1/15/08</u>
Well I.D.: <u>S-13</u>	Well Diameter: 2 <u>3</u> 4 6 8
Total Well Depth (TD): <u>23.20</u>	Depth to Water (DTW): <u>6.00</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: ~~Bailer~~ ~~Disposable Bailer~~ ~~Positive Air Displacement~~ ~~Electric Submersible~~ ~~Waterra~~ ~~Peristaltic~~ ~~Extraction Pump~~ ~~Other~~

Sampling Method: Bailer
 Disposable Bailer
 Extraction Port
 Dedicated Tubing
 Other: _____

$\frac{\text{--- (Gals.)} \times \text{---}}{\text{--- Specified Volumes}} = \text{--- Gals.}$ <p>1 Case Volume Specified Volumes Calculated Volume</p>	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F)	pH	Cond. (mS or µS)	Turbidity (NTUs)	Gals. Removed	Observations
1235	66.6	7.68	917	4.2	---	clear

Did well dewater? Yes No Gallons actually evacuated: ---

Sampling Date: 1/15/08 Sampling Time: 1235 Depth to Water: ---

Sample I.D.: S-13 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see COC

EB I.D. (if applicable): @ _____ Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF	Date: 1/15/08
Well I.D.: S-16	Well Diameter: 2 (3) 4 6 8
Total Well Depth (TD): 23-31	Depth to Water (DTW): 5.82
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: ~~Bailer~~ ~~Disposable Bailer~~ ~~Positive Air Displacement~~ ~~Electric Submersible~~ ~~Water~~ ~~Peristaltic~~ ~~Extraction Pump~~ ~~Other~~

Sampling Method: ~~Bailer~~ ~~Disposable Bailer~~ ~~Extraction Port~~ ~~Dedicated Tubing~~

Other: _____

$\frac{\text{_____ (Gals.)} \times \text{_____}}{\text{Specified Volumes}} = \text{_____ Gals.}$ I Case Volume Calculated Volume	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1420	53.8	7.45	#. 1257	56.2	—	clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1420 Depth to Water: —

Sample I.D.: S-16 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see COC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF	Date: 1/15/08
Well I.D.: S-17	Well Diameter: 2 (3) 4 6 8
Total Well Depth (TD): 23.72	Depth to Water (DTW): 5.05
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: ~~Bailer~~ ~~Disposable Bailer~~ ~~Positive Air Displacement~~ ~~Electric Submersible~~ ~~Water~~ ~~Peristaltic~~ ~~Extraction Pump~~ ~~Other~~

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing

Other: _____

$\frac{\text{Gals.} \times \text{Specified Volumes}}{\text{1 Case Volume}} = \text{Calculated Volume Gals.}$	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F)	pH	Cond. (mS or µS)	Turbidity (NTUs)	Gals. Removed	Observations
1150	61.6	7.57	958	17.6	—	clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1150 Depth to Water: —

Sample I.D.: S-17 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see COC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF	Date: 1/15/08
Well I.D.: S-18	Well Diameter: 2 <u>3</u> 4 6 8
Total Well Depth (TD): 17.61	Depth to Water (DTW): 5.25
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVO</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: ~~Bailer~~ ~~Disposable Bailer~~ ~~Positive Air Displacement~~ ~~Electric Submersible~~ ~~Waterra~~ ~~Peristaltic~~ ~~Extraction Pump~~ ~~Other~~

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing Other: _____

(Gals.) X	=	Gals.
1 Case Volume	Specified Volumes	Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1130	62.1	7.83	1598	9.8	—	clear

Did well dewater? Yes No Gallons actually evacuated: —

Sampling Date: 1/15/08 Sampling Time: 1130 Depth to Water: —

Sample I.D.: S-18 Laboratory: STL Other: Cal Science

Analyzed for: TPH-G BTEX MTBE TPH-D Other: See CEC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

SHELL WELL MONITORING DATA SHEET

BTS #: 080115-KF2	Site: 97093412
Sampler: KF	Date: 1/15/08
Well I.D.: S-19	Well Diameter: 2 3 4 6 8 _____
Total Well Depth (TD): 20.12	Depth to Water (DTW): 4.72
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: _____	

Purge Method: Bailer Waterra Sampling Method: Bailer
 Disposable Bailer Peristaltic Disposable Bailer
 Positive Air Displacement Extraction Pump Extraction Port
 Electric Submersible Other _____ Dedicated Tubing

$\frac{\text{_____ (Gals.)} \times \text{_____}}{\text{Specified Volumes}} = \text{_____ Gals.}$ 1 Case Volume Calculated Volume	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1308	62.7	7.62	1234	790	—	cloudy

Did well dewater? Yes No Gallons actually evacuated: _____

Sampling Date: 1/15/08 Sampling Time: 1308 Depth to Water: _____

Sample I.D.: S-19 Laboratory: STL Other: calScience

Analyzed for: TPH-G BTEX MTBE TPH-D Other: see woc

EB I.D. (if applicable): @ _____ Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

APPENDIX B

FIELD PROCEDURES

BLAINE
TECH SERVICES INC.

GROUNDWATER SAMPLING SPECIALISTS
SINCE 1985

February 6, 2008

Denis Brown
Shell Oil Products US
20945 South Wilmington Avenue
Carson, CA 90810

First Quarter 2008 Groundwater Monitoring at
Former Shell Service Station
15275 Washington Boulevard
San Leandro, CA

Monitoring performed on January 15, 2008

Groundwater Monitoring Report **080115-KF-2**

This report covers the routine monitoring of groundwater wells at this former Shell facility. In accordance with standard procedures that conform to Regional Water Quality Control Board requirements, routine field data collection includes depth to water, total well depth, thickness of any separate immiscible layer, water column volume, calculated purge volume (if applicable), elapsed evacuation time (if applicable), total volume of water removed (if applicable), and standard water parameter instrument readings. Sample material is collected, contained, stored, and transported to the laboratory in conformance with EPA standards. Purgewater (if applicable) is, likewise, collected and transported to the Martinez Refining Company.

Basic field information is presented alongside analytical values excerpted from the laboratory report in the cumulative table of **WELL CONCENTRATIONS**. The full analytical report for the most recent samples and the field data sheets are attached to this report.

At a minimum, Blaine Tech Services, Inc. field personnel are certified on completion of a forty-hour Hazardous Materials and Emergency Response training course per 29 CFR 1910.120. Field personnel are also enrolled in annual eight-hour refresher courses.

Blaine Tech Services, Inc. conducts sampling and documentation assignments of this type as an independent third party. Our activities at this site consisted of objective data and sample collection only. No interpretation of analytical results, defining of hydrological conditions or formulation of recommendations was performed.

Please call if you have any questions.

Yours truly,

Mike Ninokata
Project Manager

MN/ss

attachments: Cumulative Table of WELL CONCENTRATIONS
Certified Analytical Report
Field Data Sheets

cc: Joe Rounds
Delta Environmental
175 Bernal Rd., Suite 200
San Jose, CA 95119

BLAINE TECH SERVICES, INC. METHODS AND PROCEDURES FOR THE ROUTINE MONITORING OF GROUNDWATER WELLS AT SHELL SITES

Blaine Tech Services, Inc. performs environmental sampling and documentation as an independent third party. We specialize in groundwater monitoring assignments and intentionally limit the scope of our services to those centered on the generation of objective information.

To avoid conflicts of interest, Blaine Tech Services, Inc. personnel do not evaluate or interpret the information we collect. As a state licensed contractor (C-57 well drilling –water – 746684) performing strictly technical services, we do not make any professional recommendations and perform no consulting of any kind.

SAMPLING PROCEDURES OVERVIEW

SAFETY

All groundwater monitoring assignments performed for Shell comply with Shell's safety guidelines, 29 CFR 1910.120 and SB-198 Injury and Illness Prevention Program (IIPP). All Field Technicians receive the full 40-hour 29CFR 1910.120 OSHA SARA HAZWOPER course, medical clearance and on-the-job training prior to commencing any work on any Shell site.

INSPECTION AND GAUGING

Wells are inspected prior to evacuation and sampling. The condition of the wellhead is checked and noted according to a wellhead inspection checklist.

Standard measurements include the depth to water (DTW) and the total well depth (TD) obtained with industry standard electronic water level indicators that are graduated in increments of hundredths of a foot.

The water in each well is inspected for the presence of immiscibles. When free product is suspected, its presence is confirmed using an electronic interface probe (e.g. MMC). No samples are collected from a well containing over two-hundredths of a foot (0.02') of product.

EVACUATION

Depth to water measurements are collected by our personnel prior to purging and minimum purge volumes are calculated anew for each well based on the height of the water column and the diameter of the well. Expected purge volumes are never less than three case volumes and are set at no less than four case volumes in some jurisdictions.

Well purging devices are selected on the basis of the well diameter and the total volume to be evacuated. In most cases the well will be purged using an electric submersible pump (i.e. Grundfos) suspended near (but not touching) the bottom of the well.

PARAMETER STABILIZATION

Well purging completion standards include minimum purge volumes, but additionally require stabilization of specific groundwater parameters prior to sample collection. Typical groundwater parameters used to measure stability are electrical conductivity, pH, and temperature. Instrument readings are obtained at regular intervals during the evacuation process (no less than once per case volume).

Stabilization standards for routine quarterly monitoring of fuel sites include the following: Temperature is considered to have stabilized when successive readings do not fluctuate more than +/- 1 degree Celsius. Electrical conductivity is considered stable when successive readings are within 10%. pH is considered to be stable when successive readings remain constant or vary no more than 0.2 of a pH unit.

DEWATERED WELLS

Normal evacuation removes no less than three case volumes of water from the well. However, less water may be removed in cases where the well dewateres and does not immediately recharge.

MEASURING RECHARGE

Upon completion of well purging, a depth to water measurement is collected and notated to ensure that the well has recharged to within 80% of its static, pre-purge level prior to sampling.

Wells that do not immediately show 80% recharge or dewatered wells will be allowed a minimum of 2 hours to recharge prior to sampling. The water level at time of sampling will be noted.

PURGEWATER CONTAINMENT

All non-hazardous purgewater evacuated from each groundwater monitoring well is captured and contained in on-board storage tanks on the Sampling Vehicle and/or special water hauling trailers. Effluent from the decontamination of reusable apparatus (sounders, electric pumps and hoses etc.), consisting of groundwater combined with deionized water and non-phosphate soap, is also captured and pumped into effluent tanks.

Non-hazardous purgewater is transported under standard Bill of Lading documentation to a Blaine Tech Services, Inc. facility before being transported to a Shell approved disposal facility.

SAMPLE COLLECTION DEVICES

All samples are collected using a stainless steel, Teflon or disposable bailers.

SAMPLE CONTAINERS

Sample material is decanted directly from the sampling bailer into sample containers provided by the laboratory that will analyze the samples. The transfer of sample material from the bailer to the sample container conforms to specifications contained in the USEPA T.E.G.D. The type of sample container, material of construction, method of closure and filling requirements are specific to the intended analysis. Chemicals needed to preserve the sample material are commonly placed inside the sample containers by the laboratory or glassware vendor prior to delivery of the bottle to our personnel. The laboratory sets the number of replicate containers.

TRIP BLANKS

Trip Blanks, if requested, are taken to the site and kept inside the sample cooler for the duration of the event. They are turned over to the laboratory for analysis with the samples from that site.

DUPLICATES

Duplicates, if requested, may be collected at a site. The Field Technician uses their discretion in choosing the well at which the Duplicate is collected, typically one suspected of containing measurable contaminants. The Duplicate sample is labeled "DUP" and the time of collection is omitted from the COC, thus rendering the sample blind.

SAMPLE STORAGE

All sample containers are promptly placed in food grade ice chests for storage in the field and transport (direct or via our facility) to the designated analytical laboratory. These ice chests contain quantities of restaurant grade ice as a refrigerant material. The samples are maintained in either an ice chest or a refrigerator until relinquished into the custody of the laboratory or laboratory courier.

DOCUMENTATION CONVENTIONS

A label must be affixed to all sample containers. In most cases these labels are generated by our office personnel and are partially preprinted. Labels can also be hand written by our field personnel. The site is identified with the store number and site address, as is the particular groundwater well from which the sample is drawn (e.g. MW-1, MW-2, S-1 etc.). The time and date of sample collection along with the initials of the person who collects the sample are handwritten onto the label.

Chain of Custody records are created using client specific preprinted forms following USEPA specifications.

Bill of Lading records are contemporaneous records created in the field at the site where the non-hazardous purgewater is generated. Field Technicians use preprinted Bill of Lading forms.

DECONTAMINATION

All equipment is brought to the site in clean and serviceable condition and is cleaned after use in each well and before subsequent use in any other well. Equipment is decontaminated before leaving the site.

The primary decontamination device is a commercial steam cleaner. The steam cleaner is de-tuned to function as a hot pressure washer that is then operated with high quality deionized water that is produced at our facility and stored onboard our sampling vehicle. Cleaning is facilitated by the use of proprietary fixtures and devices included in the patented workstation (U.S. Patent 5,535,775) that is incorporated in each sampling vehicle. The steam cleaner is used to decon reels, pumps and bailers.

Any sensitive equipment or parts (i.e. Dissolved Oxygen sensor membrane, water level indicator, etc.) that cannot be washed using the high pressure water, will be sprayed with a non-phosphate soap and deionized water solution and rinsed with deionized water.

DISSOLVED OXYGEN READINGS

Dissolved Oxygen readings are taken pre- and/or post-purge using YSI meters (e.g. YSI Model 54, 58 or 95) or HACH field test kits.

The YSI meters are equipped with a stirring device that enables them to collect accurate in-situ readings. The probe/stirring devices are modified to allow downhole measurements to be taken from wells with diameters as small as two inches. The probe and reel is decontaminated between wells as described above. The meter is calibrated between wells as per the instructions in the operating manual. The probe and stirrer is lowered into the water column. The reading is allowed to stabilize prior to collection.

OXYIDATON REDUCTION POTENTIAL READINGS


All readings are obtained with either Corning or Myron-L meters (e.g. Corning ORP-65 or a Myron-L Ultrameter GP). The meter is cleaned between wells as described above. The meter is calibrated at the start of each day according to the instruction manual.

FERROUS IRON MEASUREMENTS

All field measurements are collected at time of sampling with a HACH test kit.

APPENDIX C

LABORATORY REPORT AND CHAIN-OF-CUSTODY DOCUMENT



January 25, 2008

Michael Ninokata
Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Subject: **Calscience Work Order No.: 08-01-1262**
Client Reference: 15275 Washington, San Leandro, CA

Dear Client:

Enclosed is an analytical report for the above-referenced project. The samples included in this report were received 1/18/2008 and analyzed in accordance with the attached chain-of-custody.


Unless otherwise noted, all analytical testing was accomplished in accordance with the guidelines established in our Quality Systems Manual, applicable standard operating procedures, and other related documentation. The original report of subcontracted analysis, if any, is provided herein, and follows the standard Calscience data package. The results in this analytical report are limited to the samples tested and any reproduction thereof must be made in its entirety.


If you have any questions regarding this report, please do not hesitate to contact the undersigned.

Sincerely,

A handwritten signature in black ink, appearing to read 'Danielle Gonsman', with a horizontal line extending to the right.

Calscience Environmental
Laboratories, Inc.
Danielle Gonsman
Project Manager





Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8015B (M)

Project: 15275 Washington, San Leandro, CA

Page 1 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-1	08-01-1262-1-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 14:37	080118B01

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
<u>Surrogates:</u>	<u>REC (%)</u>	<u>Control Limits</u>		<u>Qual</u>	
1,4-Bromofluorobenzene	96	38-134			

S-3	08-01-1262-2-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 15:11	080118B01
-----	----------------	----------	---------	-------	----------	-------------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
<u>Surrogates:</u>	<u>REC (%)</u>	<u>Control Limits</u>		<u>Qual</u>	
1,4-Bromofluorobenzene	87	38-134			

S-5	08-01-1262-3-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 15:44	080118B01
-----	----------------	----------	---------	-------	----------	-------------------	-----------


Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
<u>Surrogates:</u>	<u>REC (%)</u>	<u>Control Limits</u>		<u>Qual</u>	
1,4-Bromofluorobenzene	95	38-134			

S-7	08-01-1262-4-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 16:18	080118B01
-----	----------------	----------	---------	-------	----------	-------------------	-----------

Comment(s): -The sample chromatographic pattern for TPH does not match the chromatographic pattern of the specified standard. Quantitation of the unknown hydrocarbon(s) in the sample was based upon the specified standard.

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	160	50	1		ug/L
<u>Surrogates:</u>	<u>REC (%)</u>	<u>Control Limits</u>		<u>Qual</u>	
1,4-Bromofluorobenzene	97	38-134			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8015B (M)

Project: 15275 Washington, San Leandro, CA

Page 2 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-8	08-01-1262-5-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 16:52	080118B01

Comment(s): -The sample chromatographic pattern for TPH does not match the chromatographic pattern of the specified standard. Quantitation of the unknown hydrocarbon(s) in the sample was based upon the specified standard.

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	560	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	104	38-134			

S-9	08-01-1262-6-E	01/15/08	Aqueous	GC 30	01/21/08	01/22/08 5:51	080121B05
-----	----------------	----------	---------	-------	----------	------------------	-----------


Comment(s): -The sample chromatographic pattern for TPH does not match the chromatographic pattern of the specified standard. Quantitation of the unknown hydrocarbon(s) in the sample was based upon the specified standard.

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	11000	1200	25		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	103	38-134			

S-10	08-01-1262-7-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 18:32	080118B01
------	----------------	----------	---------	-------	----------	-------------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	94	38-134			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8015B (M)

Project: 15275 Washington, San Leandro, CA

Page 3 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-13	08-01-1262-8-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 19:06	080118B01

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	98	38-134			

S-16	08-01-1262-9-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 19:40	080118B01
------	----------------	----------	---------	-------	----------	-------------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	93	38-134			


S-17	08-01-1262-10-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 20:14	080118B01
------	-----------------	----------	---------	-------	----------	-------------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	96	38-134			

S-18	08-01-1262-11-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 20:47	080118B01
------	-----------------	----------	---------	-------	----------	-------------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	94	38-134			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8015B (M)

Project: 15275 Washington, San Leandro, CA

Page 4 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-19	08-01-1262-12-D	01/15/08	Aqueous	GC 30	01/18/08	01/18/08 21:21	080118B01

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	92	38-134			


Method Blank	099-12-436-1,369	N/A	Aqueous	GC 30	01/18/08	01/18/08 9:34	080118B01
--------------	------------------	-----	---------	-------	----------	---------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	98	38-134			

Method Blank	099-12-436-1,381	N/A	Aqueous	GC 30	01/21/08	01/22/08 2:29	080121B05
--------------	------------------	-----	---------	-------	----------	---------------	-----------

Parameter	Result	RL	DF	Qual	Units
TPH as Gasoline	ND	50	1		ug/L
Surrogates:	REC (%)	Control Limits		Qual	
1,4-Bromofluorobenzene	91	38-134			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B
Units: ug/L

Project: 15275 Washington, San Leandro, CA

Page 1 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-1	08-01-1262-1-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 17:54	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	104	74-140				1,2-Dichloroethane-d4	111	74-146			
Toluene-d8	100	88-112				1,4-Bromofluorobenzene	103	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-3	08-01-1262-2-B	01/15/08	Aqueous	GC/MS S	01/21/08	01/21/08 15:03	080121L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	102	74-140				1,2-Dichloroethane-d4	106	74-146			
Toluene-d8	99	88-112				1,4-Bromofluorobenzene	98	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-5	08-01-1262-3-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 18:25	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.


Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	103	74-140				1,2-Dichloroethane-d4	108	74-146			
Toluene-d8	103	88-112				1,4-Bromofluorobenzene	102	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-7	08-01-1262-4-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 18:56	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	105	74-140				1,2-Dichloroethane-d4	112	74-146			
Toluene-d8	103	88-112				1,4-Bromofluorobenzene	100	74-110			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B
Units: ug/L

Project: 15275 Washington, San Leandro, CA

Page 2 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-8	08-01-1262-5-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 19:27	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	5.3	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	0.31	1.0	0.23	1	J	o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	103	74-140				1,2-Dichloroethane-d4	105	74-146			
Toluene-d8	106	88-112				1,4-Bromofluorobenzene	99	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-9	08-01-1262-6-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 19:57	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	68	2.5	0.70	5		p/m-Xylene	3.4	5.0	2.7	5	J
Ethylbenzene	68	5.0	1.1	5		o-Xylene	1.1	5.0	0.84	5	J
Toluene	3.5	5.0	1.4	5	J						
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	111	74-140				1,2-Dichloroethane-d4	118	74-146			
Toluene-d8	103	88-112				1,4-Bromofluorobenzene	97	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-10	08-01-1262-7-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 20:28	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.


Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	103	74-140				1,2-Dichloroethane-d4	106	74-146			
Toluene-d8	103	88-112				1,4-Bromofluorobenzene	98	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-13	08-01-1262-8-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 14:18	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	101	74-140				1,2-Dichloroethane-d4	106	74-146			
Toluene-d8	100	88-112				1,4-Bromofluorobenzene	98	74-110			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B
Units: ug/L

Project: 15275 Washington, San Leandro, CA

Page 3 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-16	08-01-1262-9-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 20:59	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	102	74-140				1,2-Dichloroethane-d4	108	74-146			
Toluene-d8	101	88-112				1,4-Bromofluorobenzene	99	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-17	08-01-1262-10-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 21:30	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	104	74-140				1,2-Dichloroethane-d4	110	74-146			
Toluene-d8	101	88-112				1,4-Bromofluorobenzene	98	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-18	08-01-1262-11-C	01/15/08	Aqueous	GC/MS Z	01/22/08	01/22/08 22:01	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.


Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	107	74-140				1,2-Dichloroethane-d4	112	74-146			
Toluene-d8	100	88-112				1,4-Bromofluorobenzene	98	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
S-19	08-01-1262-12-C	01/15/08	Aqueous	GC/MS Z	01/23/08	01/23/08 17:15	080123L03

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	104	74-140				1,2-Dichloroethane-d4	103	74-146			
Toluene-d8	100	88-112				1,4-Bromofluorobenzene	97	74-110			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Analytical Report



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B
Units: ug/L

Project: 15275 Washington, San Leandro, CA

Page 4 of 4

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
Method Blank	099-10-006-24,146	N/A	Aqueous	GC/MS S	01/21/08	01/21/08 14:00	080121L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	102	74-140				1,2-Dichloroethane-d4	103	74-146			
Toluene-d8	98	88-112				1,4-Bromofluorobenzene	96	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
Method Blank	099-10-006-24,162	N/A	Aqueous	GC/MS Z	01/22/08	01/22/08 12:46	080122L01

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.


Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	105	74-140				1,2-Dichloroethane-d4	107	74-146			
Toluene-d8	99	88-112				1,4-Bromofluorobenzene	96	74-110			

Client Sample Number	Lab Sample Number	Date Collected	Matrix	Instrument	Date Prepared	Date/Time Analyzed	QC Batch ID
Method Blank	099-10-006-24,180	N/A	Aqueous	GC/MS Z	01/23/08	01/23/08 13:39	080123L03

Comment(s): -Results were evaluated to the MDL, concentrations \geq to the MDL but $<$ RL, if found, are qualified with a "J" flag.

Parameter	Result	RL	MDL	DF	Qual	Parameter	Result	RL	MDL	DF	Qual
Benzene	ND	0.50	0.14	1		p/m-Xylene	ND	1.0	0.54	1	
Ethylbenzene	ND	1.0	0.23	1		o-Xylene	ND	1.0	0.17	1	
Toluene	ND	1.0	0.27	1							
Surrogates:	REC (%)	Control Limits		Qual		Surrogates:	REC (%)	Control Limits		Qual	
Dibromofluoromethane	103	74-140				1,2-Dichloroethane-d4	108	74-146			
Toluene-d8	100	88-112				1,4-Bromofluorobenzene	98	74-110			

RL - Reporting Limit , DF - Dilution Factor , Qual - Qualifiers



Quality Control - Spike/Spike Duplicate




Blaine Tech Services, Inc. 1680 Rogers Avenue San Jose, CA 95112-1105	Date Received: 01/18/08 Work Order No: 08-01-1262 Preparation: EPA 5030B Method: EPA 8015B (M)
-----------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------


Project 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	MS/MSD Batch Number
08-01-1114-1	Aqueous	GC 30	01/18/08	01/18/08	080118S01

<u>Parameter</u>	<u>MS %REC</u>	<u>MSD %REC</u>	<u>%REC CL</u>	<u>RPD</u>	<u>RPD CL</u>	<u>Qualifiers</u>
TPH as Gasoline	103	94	68-122	9	0-18	

RPD - Relative Percent Difference , CL - Control Limit





Quality Control - Spike/Spike Duplicate



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105


Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8015B (M)


Project 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	MS/MSD Batch Number
08-01-1369-4	Aqueous	GC 30	01/21/08	01/22/08	080121S03

<u>Parameter</u>	<u>MS %REC</u>	<u>MSD %REC</u>	<u>%REC CL</u>	<u>RPD</u>	<u>RPD CL</u>	<u>Qualifiers</u>
TPH as Gasoline	98	93	68-122	6	0-18	

RPD - Relative Percent Difference , CL - Control Limit





Quality Control - Spike/Spike Duplicate



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105


Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B


Project 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	MS/MSD Batch Number
S-3	Aqueous	GC/MS S	01/21/08	01/21/08	080121S01

Parameter	MS %REC	MSD %REC	%REC CL	RPD	RPD CL	Qualifiers
Benzene	96	96	88-118	0	0-7	
Carbon Tetrachloride	94	97	67-145	3	0-11	
Chlorobenzene	97	98	88-118	1	0-7	
1,2-Dibromoethane	105	106	70-130	0	0-30	
1,2-Dichlorobenzene	100	102	86-116	2	0-8	
1,1-Dichloroethene	90	90	70-130	1	0-25	
Ethylbenzene	100	101	70-130	2	0-30	
Toluene	96	96	87-123	0	0-8	
Trichloroethene	96	94	79-127	2	0-10	
Vinyl Chloride	73	72	69-129	0	0-13	
Methyl-t-Butyl Ether (MTBE)	110	111	71-131	1	0-13	
Tert-Butyl Alcohol (TBA)	91	91	36-168	1	0-45	
Diisopropyl Ether (DIPE)	99	100	81-123	1	0-9	
Ethyl-t-Butyl Ether (ETBE)	111	110	72-126	1	0-12	
Tert-Amyl-Methyl Ether (TAME)	111	111	72-126	0	0-12	
Ethanol	71	66	53-149	5	0-31	

RPD - Relative Percent Difference, CL - Control Limit





Quality Control - Spike/Spike Duplicate



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105


Date Received: 01/18/08
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B


Project 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	MS/MSD Batch Number
S-13	Aqueous	GC/MS Z	01/22/08	01/22/08	080122S01

Parameter	MS %REC	MSD %REC	%REC CL	RPD	RPD CL	Qualifiers
Benzene	95	98	88-118	4	0-7	
Carbon Tetrachloride	98	100	67-145	1	0-11	
Chlorobenzene	97	103	88-118	6	0-7	
1,2-Dibromoethane	104	111	70-130	6	0-30	
1,2-Dichlorobenzene	99	102	86-116	3	0-8	
1,1-Dichloroethene	98	101	70-130	3	0-25	
Ethylbenzene	101	107	70-130	6	0-30	
Toluene	99	102	87-123	3	0-8	
Trichloroethene	96	101	79-127	5	0-10	
Vinyl Chloride	89	90	69-129	1	0-13	
Methyl-t-Butyl Ether (MTBE)	91	98	71-131	8	0-13	
Tert-Butyl Alcohol (TBA)	77	90	36-168	15	0-45	
Diisopropyl Ether (DIPE)	97	103	81-123	6	0-9	
Ethyl-t-Butyl Ether (ETBE)	92	99	72-126	7	0-12	
Tert-Amyl-Methyl Ether (TAME)	101	108	72-126	6	0-12	
Ethanol	73	83	53-149	9	0-31	

RPD - Relative Percent Difference , CL - Control Limit





Quality Control - Spike/Spike Duplicate




Blaine Tech Services, Inc.	Date Received:	01/18/08
1680 Rogers Avenue	Work Order No:	08-01-1262
San Jose, CA 95112-1105	Preparation:	EPA 5030B
	Method:	EPA 8260B


Project 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	MS/MSD Batch Number
08-01-1051-4	Aqueous	GC/MS Z	01/23/08	01/23/08	080123S02

Parameter	MS %REC	MSD %REC	%REC CL	RPD	RPD CL	Qualifiers
Benzene	94	99	88-118	5	0-7	
Carbon Tetrachloride	100	102	67-145	2	0-11	
Chlorobenzene	96	102	88-118	6	0-7	
1,2-Dibromoethane	105	109	70-130	4	0-30	
1,2-Dichlorobenzene	100	102	86-116	1	0-8	
1,1-Dichloroethene	99	101	70-130	2	0-25	
Ethylbenzene	102	106	70-130	4	0-30	
Toluene	99	103	87-123	4	0-8	
Trichloroethene	100	100	79-127	0	0-10	
Vinyl Chloride	92	91	69-129	1	0-13	
Methyl-t-Butyl Ether (MTBE)	98	100	71-131	2	0-13	
Tert-Butyl Alcohol (TBA)	87	86	36-168	1	0-45	
Diisopropyl Ether (DIPE)	96	97	81-123	1	0-9	
Ethyl-t-Butyl Ether (ETBE)	95	98	72-126	2	0-12	
Tert-Amyl-Methyl Ether (TAME)	103	107	72-126	4	0-12	
Ethanol	70	66	53-149	3	0-31	

RPD - Relative Percent Difference, CL - Control Limit





Quality Control - LCS/LCS Duplicate




Blaine Tech Services, Inc.	Date Received:	N/A
1680 Rogers Avenue	Work Order No:	08-01-1262
San Jose, CA 95112-1105	Preparation:	EPA 5030B
	Method:	EPA 8015B (M)

Project: 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	LCS/LCSD Batch Number
099-12-436-1,369	Aqueous	GC 30	01/18/08	01/18/08	080118B01

Parameter	LCS %REC	LCSD %REC	%REC CL	RPD	RPD CL	Qualifiers
TPH as Gasoline	108	108	78-120	0	0-10	

RPD - Relative Percent Difference , CL - Control Limit



Quality Control - LCS/LCS Duplicate



Blaine Tech Services, Inc.
 1680 Rogers Avenue
 San Jose, CA 95112-1105


Date Received: N/A
 Work Order No: 08-01-1262
 Preparation: EPA 5030B
 Method: EPA 8015B (M)


Project: 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	LCS/LCSD Batch Number
099-12-436-1,381	Aqueous	GC 30	01/21/08	01/22/08	080121B05

Parameter	LCS %REC	LCSD %REC	%REC CL	RPD	RPD CL	Qualifiers
TPH as Gasoline	94	101	78-120	8	0-10	

RPD - Relative Percent Difference , CL - Control Limit





Quality Control - LCS/LCS Duplicate



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105


Date Received: N/A
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B

Project: 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	LCS/LCSD Batch Number
099-10-006-24,146	Aqueous	GC/MS S	01/21/08	01/21/08	080121L01

Parameter	LCS %REC	LCSD %REC	%REC CL	RPD	RPD CL	Qualifiers
Benzene	97	98	84-120	0	0-8	
Carbon Tetrachloride	97	97	63-147	0	0-10	
Chlorobenzene	100	100	89-119	0	0-7	
1,2-Dibromoethane	109	106	80-120	3	0-20	
1,2-Dichlorobenzene	102	104	89-119	2	0-9	
1,1-Dichloroethene	91	91	77-125	0	0-16	
Ethylbenzene	106	105	80-120	1	0-20	
Toluene	97	97	83-125	0	0-9	
Trichloroethene	96	97	89-119	1	0-8	
Vinyl Chloride	74	75	63-135	1	0-13	
Methyl-t-Butyl Ether (MTBE)	110	105	82-118	4	0-13	
Tert-Butyl Alcohol (TBA)	104	87	46-154	17	0-32	
Diisopropyl Ether (DIPE)	100	98	81-123	2	0-11	
Ethyl-t-Butyl Ether (ETBE)	109	107	74-122	1	0-12	
Tert-Amyl-Methyl Ether (TAME)	109	110	76-124	0	0-10	
Ethanol	80	72	60-138	10	0-32	

RPD - Relative Percent Difference, CL - Control Limit



Quality Control - LCS/LCS Duplicate



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105


Date Received: N/A
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B

Project: 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	LCS/LCSD Batch Number
099-10-006-24,162	Aqueous	GC/MS Z	01/22/08	01/22/08	080122L01

Parameter	LCS %REC	LCSD %REC	%REC CL	RPD	RPD CL	Qualifiers
Benzene	98	92	84-120	6	0-8	
Carbon Tetrachloride	101	95	63-147	6	0-10	
Chlorobenzene	99	96	89-119	3	0-7	
1,2-Dibromoethane	103	99	80-120	4	0-20	
1,2-Dichlorobenzene	101	96	89-119	4	0-9	
1,1-Dichloroethene	104	98	77-125	5	0-16	
Ethylbenzene	105	100	80-120	5	0-20	
Toluene	102	95	83-125	6	0-9	
Trichloroethene	102	95	89-119	8	0-8	
Vinyl Chloride	95	87	63-135	8	0-13	
Methyl-t-Butyl Ether (MTBE)	94	94	82-118	1	0-13	
Tert-Butyl Alcohol (TBA)	93	80	46-154	15	0-32	
Diisopropyl Ether (DIPE)	98	97	81-123	0	0-11	
Ethyl-t-Butyl Ether (ETBE)	94	94	74-122	0	0-12	
Tert-Amyl-Methyl Ether (TAME)	104	99	76-124	5	0-10	
Ethanol	97	89	60-138	9	0-32	

RPD - Relative Percent Difference, CL - Control Limit



Quality Control - LCS/LCS Duplicate



Blaine Tech Services, Inc.
1680 Rogers Avenue
San Jose, CA 95112-1105

Date Received: N/A
Work Order No: 08-01-1262
Preparation: EPA 5030B
Method: EPA 8260B

Project: 15275 Washington, San Leandro, CA

Quality Control Sample ID	Matrix	Instrument	Date Prepared	Date Analyzed	LCS/LCSD Batch Number
099-10-006-24,180	Aqueous	GC/MS Z	01/23/08	01/23/08	080123L03

Parameter	LCS %REC	LCSD %REC	%REC CL	RPD	RPD CL	Qualifiers
Benzene	108	111	84-120	3	0-8	
Carbon Tetrachloride	120	122	63-147	2	0-10	
Chlorobenzene	110	111	89-119	1	0-7	
1,2-Dibromoethane	112	113	80-120	1	0-20	
1,2-Dichlorobenzene	106	108	89-119	2	0-9	
1,1-Dichloroethene	118	121	77-125	2	0-16	
Ethylbenzene	119	119	80-120	0	0-20	
Toluene	113	118	83-125	4	0-9	
Trichloroethene	113	118	89-119	5	0-8	
Vinyl Chloride	104	105	63-135	1	0-13	
Methyl-t-Butyl Ether (MTBE)	97	103	82-118	6	0-13	
Tert-Butyl Alcohol (TBA)	105	115	46-154	9	0-32	
Diisopropyl Ether (DIPE)	102	102	81-123	0	0-11	
Ethyl-t-Butyl Ether (ETBE)	97	100	74-122	2	0-12	
Tert-Amyl-Methyl Ether (TAME)	106	111	76-124	4	0-10	
Ethanol	107	125	60-138	15	0-32	

RPD - Relative Percent Difference , CL - Control Limit

Work Order Number: 08-01-1262

<u>Qualifier</u>	<u>Definition</u>
*	See applicable analysis comment.
1	Surrogate compound recovery was out of control due to a required sample dilution, therefore, the sample data was reported without further clarification.
2	Surrogate compound recovery was out of control due to matrix interference. The associated method blank surrogate spike compound was in control and, therefore, the sample data was reported without further clarification.
3	Recovery of the Matrix Spike (MS) or Matrix Spike Duplicate (MSD) compound was out of control due to matrix interference. The associated LCS and/or LCSD was in control and, therefore, the sample data was reported without further clarification.
4	The MS/MSD RPD was out of control due to matrix interference. The LCS/LCSD RPD was in control and, therefore, the sample data was reported without further clarification.
5	The PDS/PDSD associated with this batch of samples was out of control due to a matrix interference effect. The associated batch LCS/LCSD was in control and, hence, the associated sample data was reported with no further corrective action required.
A	Result is the average of all dilutions, as defined by the method.
B	Analyte was present in the associated method blank.
C	Analyte presence was not confirmed on primary column.
E	Concentration exceeds the calibration range.
H	Sample received and/or analyzed past the recommended holding time.
J	Analyte was detected at a concentration below the reporting limit and above the laboratory method detection limit. Reported value is estimated.
N	Nontarget Analyte.
ND	Parameter not detected at the indicated reporting limit.
Q	Spike recovery and RPD control limits do not apply resulting from the parameter concentration in the sample exceeding the spike concentration by a factor of four or greater.
U	Undetected at the laboratory method detection limit.
X	% Recovery and/or RPD out-of-range.
Z	Analyte presence was not confirmed by second column or GC/MS analysis.



LAB:

- TA - Irvine, California
- TA - Morgan Hill, California
- TA - Sacramento, California
- TA - Nashville, Tennessee
- Calsciense
- Other _____



SHELL Chain Of Custody Record

NAME OF PERSON TO BILL: Denis Brown

ENVIRONMENTAL SERVICES CHECK BOX TO VERIFY IF NO INCIDENT # APPLIES

NETWORK DEV / FE BILL CONSULTANT

COMPLIANCE RMT/CRMT

INCIDENT # (ES ONLY): 9 7 0 9 3 4 1 2

DATE: 1/15/08

PAGE: 1 of 2

SAMPLING COMPANY: **Blaine Tech Services** LOG CODE: **BTSS** SITE ADDRESS: Street and City: **15275 Washington, San Leandro** State: **CA** GLOBAL ID NO.: **T0600101226**

ADDRESS: **1680 Rogers Avenue, San Jose, CA 95112** EDI DELIVERABLE TO (Name, Company, Office Location): **Jon Suing, Delta, Monrovia Office** PHONE NO.: **626.256.6662** E-MAIL: **jsuing@deltaenv.com** CONSULTANT PROJECT NO.: **080115-KF2**

PROJECT CONTACT (Hardcopy or PDF Report to): **Michael Ninokata** SAMPLER NAME(S) (Print): **K. Cordes** LAB USE ONLY: **08-01-1262**

TELEPHONE: **408-573-0555** FAX: **408-573-7771** E-MAIL: **mninokata@blainetech.com**

TAT (STD IS 10 BUSINESS DAYS / RUSH IS CALENDAR DAYS): RESULTS NEEDED ON WEEKEND

STD 5 DAY 3 DAY 2 DAY 24 HOURS

LA - RWQCB REPORT FORMAT UST AGENCY: _____

REQUESTED ANALYSIS

FIELD NOTES:
Container/Preservative or PID Readings or Laboratory Notes

TEMPERATURE ON RECEIPT C°

CC Rich Garlow rgarlow@deltaenv.com with final report.

LAB USE ONLY	Field Sample Identification	SAMPLING		MATRIX	NO. OF CONT.	TPH - Gas, Purgeable (8260B)	TPH - Diesel, Extractable (8015M)	BTEX (8260B)	5 Oxygenates (8260B) (MTBE, TBA, DIPE, TAME, ETBE)	MTBE (8260B)	TBA (8260B)	DIPE (8260B)	TAME (8260B)	ETBE (8260B)	1,2 DCA (8260B)	EDB (8260B)	Ethanol (8260B)	Methanol (8015M)	TPH-motor oil (8015M)	TDS (160.1)	Total Iron (6010B)	Total Lead (6010B)	Total Oil and Grease (1664A)	
		DATE	TIME																					
1	S-1	1/15/08	1435	W	5	X	X																	
2	S-3		1516		5	X	X																	
3	S-5		1358		5	X	X																	
4	S-7		1445		5	X	X																	
5	S-8		1455		5	X	X																	
6	S-9		1505		5	X	X																	
7	S-10		1330		5	X	X																	
8	S-13		1235		5	X	X																	
9	S-16		1420		5	X	X																	
W	S-17		1150		5	X	X																	

Relinquished by: (Signature) <i>[Signature]</i>	Received by: (Signature) <i>[Signature]</i>	Date: 1/15/08	Time: 1640
Relinquished by: (Signature) <i>[Signature]</i>	Received by: (Signature) <i>[Signature]</i>	Date: 1/17/08	Time: 1630
Relinquished by: (Signature) <i>[Signature]</i>	Received by: (Signature) <i>[Signature]</i>	Date: 1/18/08	Time: 0915

02

LAB:

- TA - Irvine, California
- TA - Morgan Hill, California
- TA - Sacramento, California
- TA - Nashville, Tennessee
- Calscience
- Other: _____



SHELL Chain Of Custody Record

NAME OF PERSON TO BILL: Denis Brown		INCIDENT # (ES ONLY)	
<input checked="" type="checkbox"/> ENVIRONMENTAL SERVICES <input type="checkbox"/> NETWORK DEV / FE <input type="checkbox"/> COMPLIANCE		<input type="checkbox"/> CHECK BOX TO VERIFY IF NO INCIDENT # APPLIES <div style="font-size: 24px; font-weight: bold; text-align: center;">9 7 0 9 3 4 1 2</div>	
<input type="checkbox"/> BILL CONSULTANT <input type="checkbox"/> RMT/CRMT		DATE: <u>1/15/08</u> PAGE: <u>2</u> of <u>2</u>	

SAMPLING COMPANY: Blaine Tech Services ADDRESS: 1680 Rogers Avenue, San Jose, CA 95112 PROJECT CONTACT (Hardcopy or PDF Report to): Michael Ninokata TELEPHONE: 408-573-0555 FAX: 408-573-7771 E-MAIL: mninokata@blainetech.com		LOG CODE: BTSS SITE ADDRESS: Street and City 15275 Washington, San Leandro State: CA GLOBAL ID NO.: T0600101226	
EDI DELIVERABLE TO (Name, Company, Office Location): Jon Sulng, Delta, Monrovia Office SAMPLER NAME(S) (Print): <div style="font-size: 24px; font-family: cursive;">K. Cordes</div>		PHONE NO.: 626.256.6662 E-MAIL: jsulng@deltaenv.com CONSULTANT PROJECT NO.: 08015-KF2 BTS #: _____	


TAT (STD IS 10 BUSINESS DAYS / RUSH IS CALENDAR DAYS):
 STD 5 DAY 3 DAY 2 DAY 24 HOURS RESULTS NEEDED ON WEEKEND

<input type="checkbox"/> LA - RWQCB REPORT FORMAT <input type="checkbox"/> UST AGENCY: _____		REQUESTED ANALYSIS												FIELD NOTES: Container/Preservative or PID Readings or Laboratory Notes TEMPERATURE ON RECEIPT °					
SPECIAL INSTRUCTIONS OR NOTES: <input type="checkbox"/> EDD NOT NEEDED <input type="checkbox"/> SHELL CONTRACT RATE APPLIES <input type="checkbox"/> STATE REIMB RATE APPLIES <input checked="" type="checkbox"/> RECEIPT VERIFICATION REQUESTED CC Rich Garlow rgarlow@deltaenv.com with final report.		TPH - Gas, Purgeable (8260B)	TPH - Diesel, Extractable (8015M)	BTEX (8260B)	5 Oxygenates (8260B) (MTBE, TBA, DIPE, TAME, ETBE)	MTBE (8260B)	TBA (8260B)	DIPE (8260B)	TAME (8260B)	ETBE (8260B)	1,2 DCA (8260B)	EDB (8260B)	Ethanol (8260B)			Methanol (8015M)	TPH-motor oil (8015M)	TDS (160.1)	Total Iron (6010B)

LAB USE ONLY	Field Sample Identification		SAMPLING		MATRIX	NO. OF CONT.	TPH - Gas, Purgeable (8260B)	TPH - Diesel, Extractable (8015M)	BTEX (8260B)	5 Oxygenates (8260B) (MTBE, TBA, DIPE, TAME, ETBE)	MTBE (8260B)	TBA (8260B)	DIPE (8260B)	TAME (8260B)	ETBE (8260B)	1,2 DCA (8260B)	EDB (8260B)	Ethanol (8260B)	Methanol (8015M)	TPH-motor oil (8015M)	TDS (160.1)	Total Iron (6010B)	Total Lead (6010B)	Total Oil and Grease (1664A)	TEMPERATURE ON RECEIPT °	
			DATE	TIME																						
11	S-18		1/15/08	1130	W	5	X	X																		
12	S-19		1/15/08	1308	W	5	X	X																		

Relinquished by: (Signature)	Received by: (Signature)	Date: <u>1/15/08</u>	Time: <u>1640</u>
Relinquished by: (Signature)	Received by: (Signature)	Date: <u>1/17/08</u>	Time: <u>1630</u>
Relinquished by: (Signature)	Received by: (Signature)	Date: <u>1/18/08</u>	Time: <u>0915</u>

Page 22 of 23



WORK ORDER #: 08 - 01 - 1262

Cooler 1 of 1

SAMPLE RECEIPT FORM

CLIENT: Blaine Tech

DATE: 01/10/08

TEMPERATURE – SAMPLES RECEIVED BY:

CALSCIENCE COURIER:

- Chilled, cooler with temperature blank provided.
- Chilled, cooler without temperature blank.
- Chilled and placed in cooler with wet ice.
- Ambient and placed in cooler with wet ice.
- Ambient temperature.
- °C Temperature blank.

LABORATORY (Other than Calscience Courier):

- °C Temperature blank.
- °C IR thermometer.
- Ambient temperature.

Initial: NC

CUSTODY SEAL INTACT:

Sample(s): _____ Cooler: _____ No (Not Intact) : _____ Not Present:

Initial: NC

SAMPLE CONDITION:

	Yes	No	N/A
Chain-Of-Custody document(s) received with samples.....	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sampler's name indicated on COC.....	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sample container label(s) consistent with custody papers.....	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sample container(s) intact and good condition.....	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Correct containers and volume for analyses requested.....	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Proper preservation noted on sample label(s).....	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
VOA vial(s) free of headspace.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tedlar bag(s) free of condensation.....	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Initial: NC

COMMENTS:
