



A Report Prepared For:

Pacific Electric Motor Company  
1009 66th Avenue  
Oakland, California 94601

Attention: Mr. Rand Perry

**QUARTERLY MONITORING REPORT  
FOURTH QUARTER 1999  
PACIFIC ELECTRIC MOTOR COMPANY  
1009 66TH AVENUE  
OAKLAND, CALIFORNIA**

*#565*

**JANUARY 6, 2000**

By:

Keary D. Knickerbocker  
Staff Environmental Scientist

William W. Mast, R.G.  
Associate Engineer

**618.0101.004**

ENVIRONMENTAL  
PROTECTION  
00 JAN 11 PM 12:05

**TABLE OF CONTENTS**

---

LIST OF TABLES ..... III  
LIST OF ILLUSTRATIONS ..... III  
1.0 INTRODUCTION ..... 1  
2.0 BACKGROUND INFORMATION ..... 1  
3.0 WATER-LEVEL MEASUREMENTS..... 3  
4.0 GROUNDWATER SAMPLING ..... 3  
5.0 DISCUSSION OF MONITORING RESULTS ..... 4  
    5.1 Water-Level Measurements..... 5  
    5.2 Groundwater Chemistry..... 5  
6.0 REFERENCES ..... 6

TABLES

ILLUSTRATIONS

APPENDICES A - GROUNDWATER SAMPLING REPORT

B - LABORATORY REPORTS AND CHAIN-OF-CUSTODY RECORDS

DISTRIBUTION

## LIST OF TABLES

---

Table 1	Monitoring Well Completion Details
Table 2	Water-Level Elevation Data
Table 3	Analytical Results for Groundwater Samples

## LIST OF ILLUSTRATIONS

---

Plate 1	Site Location Map
Plate 2	Site Plan and Monitoring Well Location Map
Plate 3	Water-Level Elevation Map

## 1.0 INTRODUCTION

This report presents the results of quarterly groundwater monitoring performed by PES Environmental, Inc. (PES) during the fourth quarter of 1999 at Pacific Electric Motor Company (PEM) in Oakland, California (Plate 1). The current groundwater monitoring program consists of measuring the depth to groundwater in four onsite monitoring wells, and purging and sampling the monitoring wells (Wells MW-1, MW-2, MW-3, and MW-4) on a quarterly basis.

The purpose of the groundwater monitoring program is to: (1) evaluate the presence of petroleum hydrocarbons in groundwater; and (2) monitor water-level variations at the site. The quarterly monitoring program was performed in accordance with the sampling program specified in the Alameda County Environmental Health Services (ACEHS) December 1, 1998 letter *Additional Soil and Groundwater Investigation Report, 1009-66th Ave., Oakland, CA 94601* (ACEHS, 1998b) and the procedures outlined in PES' proposal dated December 11, 1998 (PES, 1998b).

## 2.0 BACKGROUND INFORMATION

The site is located in a residential and light industrial area in Oakland, California and is presently used to repair large electric motors. PEM formerly operated a 2,000-gallon steel gasoline underground storage tank (UST) on the east side of the warehouse building (Plate 2). The tank was reportedly installed in approximately 1975 (ENVIRON, 1997). In February 1995, the UST was removed by W. A. Craig, Inc. (WAC). Observations at the time of removal indicated that the tank was in good condition and no holes were evident. However, free-phase gasoline product was observed on the water surface in the tank excavation. Soil samples collected from the UST excavation and associated piping trenches detected total petroleum hydrocarbons as gasoline (TPH-g) at concentrations up to 10,000 milligrams per kilogram.

In April 1995, WAC performed a soil investigation consisting of nine soil borings to delineate the lateral and vertical extent of the petroleum hydrocarbons in soil. On the basis of the results of the soil investigation, WAC prepared and implemented a remediation program to remove soil affected by petroleum hydrocarbons. Approximately 1,500 cubic yards of soil were excavated and stockpiled onsite, and 116,000 gallons of petroleum hydrocarbon-affected water were pumped from the excavation and disposed. A dewatering sump installed by WAC during soil excavation was later converted to groundwater monitoring well WAC-1 (Plate 2). Because of its uncertain construction, ACEHS stated that no monitoring of Well WAC-1 is required (ACEHS, 1997). WAC summarized the results of their remediation program in a report entitled *Excavation and Sampling Report, Pacific Electric Motor Co., 1009 66<sup>th</sup> Avenue, Oakland, California*, dated May 12, 1997 (WAC, 1997).

ENVIRON, Inc. (ENVIRON) installed and sampled three shallow monitoring wells (MW-1, MW-2, MW-3) in June 1997 to evaluate groundwater conditions in the vicinity of the former UST. Well completion details are summarized in Table 1. The well installation program and associated soil and groundwater sampling program was summarized in the ENVIRON report *Soil and Ground Water Investigation, Summary Report, Pacific Electric Motor Co., 1009-66th Avenue, Oakland, California*, dated July 17, 1997 (ENVIRON, 1997). ENVIRON concluded that the remediation performed had successfully removed the source of the petroleum hydrocarbons (i.e., the former UST), and that residual concentrations of petroleum hydrocarbons in soil and groundwater were present only in the immediate vicinity of the former UST.

In September 1998 PES conducted additional soil and groundwater sampling in the vicinity of the former UST, as requested by the ACEHS in a May 13, 1998 letter to PEM (ACEHS, 1998a). Two soil borings were drilled within the backfill of the former UST excavation, and one monitoring well was installed downgradient of the former UST. Petroleum hydrocarbons were generally not detected in the excavation backfill, although groundwater samples collected from both soil borings indicated the presence of methyl tert-butyl ether (MTBE), a gasoline

additive. Elevated petroleum hydrocarbons were found in soil and groundwater downgradient of the UST excavation during installation and groundwater sampling of monitoring well MW-4. On the basis of the elevated concentrations of petroleum hydrocarbons, PES recommended four quarters of additional groundwater monitoring. The additional investigation was summarized in the PES report *Results of Additional Soil and Groundwater Investigation, 1009 66<sup>th</sup> Avenue, Oakland, California*, dated November 11, 1998 (PES, 1998a).

### 3.0 WATER-LEVEL MEASUREMENTS

Water levels in four onsite groundwater monitoring wells (Wells MW-1, MW-2, MW-3, and MW-4) were measured by Blaine Tech Services, Inc. (Blaine Tech) of San Jose, California, under the direct supervision of PES, prior to sampling on November 15, 1999. Depth-to-water in the monitoring wells was measured from the top-of-casing (TOC) reference benchmark to a precision of 0.01-feet using an electronic water-level indicator/interface probe. Depth-to-water measurements were converted to water-level elevations by subtracting the depth to water from the TOC elevation referenced to a site datum established by ENVIRON (ENVIRON, 1997). Free product was not observed in any of the monitoring wells.

To prevent cross-contamination between wells, the portion of the water-level indicator that was submerged in the well was cleaned between well measurements using a phosphate-free detergent/deionized water solution and double rinsed with deionized water.

### 4.0 GROUNDWATER SAMPLING

On November 15, 1999, Blaine Tech, under the direct supervision of PES, collected groundwater samples from Wells MW-1, MW-2, MW-3, and MW-4. Groundwater samples were collected from each well after removing approximately three well volumes of water with

disposable bailers. During well purging, the discharged water was monitored for pH, temperature, electrical conductivity, and turbidity.

Following purging, samples were collected from the wells using a stainless steel or Teflon disposable bailer and transferred to the appropriate laboratory sample containers. The sample containers were filled slowly to minimize sample volatilization and to ensure that the sample was free of air bubbles. The samples were labeled to designate sample number, time and date collected, and analysis required. The samples were immediately placed in a chilled, thermally-insulated cooler. To prevent cross-contamination between wells, the pump and stainless steel bailer were decontaminated using a high-pressure steam cleaner prior to initial use and after sampling at each well. Sampling procedures are documented in the groundwater sampling report prepared by Blaine Tech, included in Appendix A.

Groundwater samples were transported under chain-of-custody protocol to a state-certified laboratory. Entech Analytical Labs of Sunnyvale, California analyzed samples for: (1) total petroleum hydrocarbons quantified as gasoline (TPH-g) using EPA Test Method 8015 Modified; (2) benzene, toluene, ethylbenzene, and total xylenes (BTEX) using EPA Test Method 8020; and (3) methyl tert-butyl ether (MTBE) using EPA Test Method 8020. Detected concentrations of MTBE were confirmed using EPA Test Method 8260. The laboratory reports and chain-of-custody records are included in Appendix B.

## **5.0 DISCUSSION OF MONITORING RESULTS**

This section presents a summary of water-level measurements and groundwater analyses results from the November 1999 sampling event.

### 5.1 Water-Level Measurements

Depth-to-water measurements during the November 1999 event ranged from 5.92 feet (MW-2) to 6.35 feet (MW-3) below TOC. Groundwater water-level elevations ranged from 93.58 feet (MW-3) to 94.37 feet (MW-1) referenced to site datum established by ENVIRON (ENVIRON, 1997). Historical and current depth-to-water measurements and calculated water-level elevations are presented in Table 2.

Plate 3 presents water-level elevation contours developed from water levels measured on November 15, 1999. The water-level elevation contours indicate that groundwater flow is generally to the west-southwest. The observed flow direction is consistent with that observed during the July 1999 monitoring event. The groundwater gradient is approximately 0.005 foot per foot (ft/ft).

### 5.2 Groundwater Chemistry

A summary of current and historical laboratory chemical results for petroleum hydrocarbons is presented in Table 3. The analytical laboratory reports and chain-of-custody forms are presented in Appendix B.

During the current monitoring period petroleum hydrocarbon compounds were detected in groundwater samples from Wells MW-1 and MW-4.

At Well MW-1, TPH-gas, benzene, ethyl benzene, and xylenes were detected at concentrations of 3,600, 120, 150, and 620 micrograms per liter ( $\mu\text{g/L}$ ), respectively. The detected concentrations of petroleum hydrocarbons are higher than those observed during the July 1999 sampling event, but within the range of historically observed concentrations.

No petroleum hydrocarbon compounds were detected in the samples collected from Wells MW-2 and MW-3 in November 1999. Petroleum hydrocarbons were first detected at low



concentrations in samples from Wells MW-2 and MW-3 in January and April 1999, respectively, but were not detected in the July 1999 third quarter sampling event.

At Well MW-4, TPH-g, benzene, toluene, ethyl benzene, and xylenes were detected at concentrations of 63,000, 8,500, 2,400, 1,400 and 4,000  $\mu\text{g/L}$ , respectively. MTBE was detected at a concentration of 57,000  $\mu\text{g/L}$  using EPA Test Methods 8020 and confirmed at a concentration of 58,000  $\mu\text{g/L}$  using EPA Test Method 8260. Petroleum hydrocarbon concentrations have fluctuated greatly over the past year; however, concentrations from the current sampling event are lower than those observed in April and July 1999.

Current data from the downgradient monitoring wells (MW-2 and MW-3), consistent with that of the July 1999 event, appear to indicate that the petroleum hydrocarbon plume associated with the former UST is limited to minimal lateral migration and remains localized. Current data from Well MW-4 indicates a decrease in petroleum hydrocarbon concentrations since the July 1999 sampling event, while petroleum hydrocarbon concentrations in samples from Well MW-1 have increased.

## 6.0 REFERENCES

Alameda County Environmental Health Services (ACEHS), 1997. *Soil and Groundwater Investigation for Pacific Electric Motor Co., 1009-66th Ave., Oakland, CA 94601*. August 19.

\_\_\_\_\_, 1998a. *Evaluation of Residual Health Risks at Pacific Electric Motor Company, 1009 66<sup>th</sup> Avenue, Oakland, CA 94601*. May 13.

\_\_\_\_\_, 1998b. *Additional Soil and Groundwater Investigation Report, 1009 66th Ave., Oakland, 94601*. December 1.

ENVIRON Corporation, 1997. *Soil and Groundwater Investigation, Summary Report, Pacific Electric Motor Co., 1009-66th Avenue, Oakland, California*. July 17.

PES Environmental, Inc. (PES), 1998a. *Results of Additional Soil and Groundwater Investigation, 1009 66<sup>th</sup> Avenue, Oakland, California*. November 11.

\_\_\_\_\_, 1998b. *Proposal, Quarterly Groundwater Sampling, Pacific Electric Motor Company, Oakland, California.* December 11.

W. A. Craig, Inc. (WAC), 1997. *Excavation and Sampling Report, Pacific Electric Motor Co., 1009 66th Avenue, Oakland, California.* May 12. (Partial)

**Table 1. Monitoring Well Completion Details  
 Quarterly Monitoring Report  
 Fourth Quarter 1999  
 Pacific Electric Motor Company  
 1009 66th Avenue, Oakland, California**

Well Number	Date Installed	Installed By	TOC Elevation (feet*)	Boring Diameter (inches)	Casing Diameter (inches)	Total Depth Boring (feet bgs)	Total Depth of Casing (feet bgs)	Screened Interval Depth (feet bgs)	
								Top	Bottom
MW-1	6/10/97	ENVIRON	101.04	8	2	26.5	25.5	5	25
MW-2	6/10/97	ENVIRON	100.12	8	2	25.5	25.5	5	25
MW-3	6/10/97	ENVIRON	100.23	8	2	25.5	25.5	5	25
MW-4	9/14/98	PES	100.32	8	2	25.0	25.0	15	25

**Notes:**

\* = Referenced to site datum established by ENVIRON (1997).

bgs = Below ground surface.

**Table 2. Water-Level Elevation Data  
Quarterly Monitoring Report  
Fourth Quarter 1999  
Pacific Electric Motor Company  
1009 66th Avenue, Oakland, California**

Well Number	Date	Measured By	Top of Casing Elevation (feet*)	Depth to Water (feet BTOC)	Water-level Elevation (feet*)
MW-1	6/19/97	ENVIRON	100.67	5.87	94.80
	7/1/97	ENVIRON	100.67	5.88	94.79
	9/29/97	PES	100.67	6.45	94.22
	12/16/97	PES	100.67	3.42	97.25
	3/10/98	PES	100.67	3.06	97.61
	10/1/98	PES	100.67	6.36	94.31
	1/19/99	PES	100.67	5.33	95.34
	4/15/99	PES	100.67	3.23	97.44
	5/6/99	PES	100.67	4.36	96.31
	7/30/99	PES	100.67	5.49	95.18
11/15/99	PES	100.67	6.30	94.37	
MW-2	6/19/97	ENVIRON	99.85	5.30	94.55
	7/1/97	ENVIRON	99.85	5.37	94.48
	9/29/97	PES	99.85	6.05	93.80
	12/16/97	PES	99.85	3.81	96.04
	3/10/98	PES	99.85	2.89	96.96
	10/1/98	PES	99.85	5.83	94.02
	1/19/99	PES	99.85	5.26	94.59
	4/15/99	PES	99.85	3.19	96.66
	5/6/99	PES	99.85	3.91	95.94
	7/30/99	PES	99.85	4.79	95.06
11/15/99	PES	99.85	5.92	93.93	
MW-3	6/19/97	ENVIRON	99.93	5.50	94.43
	7/1/97	ENVIRON	99.93	5.52	94.41
	9/29/97	PES	99.93	6.16	93.77
	12/16/97	PES	99.93	5.52	94.41
	3/10/98	PES	99.93	3.11	96.82
	10/1/98	PES	99.93	5.96	93.97
	1/19/99	PES	99.93	5.45	94.48
	4/15/99	PES	99.93	3.85	96.08
	5/6/99	PES	99.93	4.12	95.81
	7/30/99	PES	99.93	5.14	94.79
11/15/99	PES	99.93	6.35	93.58	
MW-4	10/1/98	PES	100.32	6.32	94.00
	1/19/99	PES	100.32	5.59	94.73
	4/15/99	PES	100.32	7.71 #	92.61 #
	5/6/99	PES	100.32	4.50	95.82
	7/30/99	PES	100.32	5.18	95.14
11/15/99	PES	100.32	6.27	94.05	

Notes:

\* = Referenced to site datum established by ENVIRON (1997).

BTOC = Below top of casing.

# = Anomalous data, not used for water-level elevation contouring.

**Table 3. Analytical Results for Groundwater Samples  
Quarterly Monitoring Report  
Fourth Quarter 1999  
Pacific Electric Motor Company  
1009 66th Avenue, Oakland, California**

Sample Location	Date Sampled	Sampled By	TPH-g (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl- benzene (µg/L)	Xylenes (µg/L)	MTBE EPA 8020 (µg/L)	MTBE EPA 8260 (µg/L)
MW-1	6/19/97	ENVIRON	18,000	3,300	200	1,100	4,900	<250	--
	9/29/97	PES	29,000	4,800	<25	2,000	3,500	<250	--
	12/16/97	PES	<50	1.3	<0.5	0.6	0.7	<5	--
	3/10/98	PES	190	2.0	<0.5	5.7	1.7	<5	--
	1/19/99	PES	1,000	40	<0.5	18	68	8.3	6.9
	4/15/99	PES	<50	0.92	0.9	0.7	0.87	<5.0	--
	7/30/99	PES	1,400	60	<0.5	63	120	13	<5.0
	11/15/99	PES	3,600	120	<0.5	150	620	<5.0	--
MW-2	6/19/97	ENVIRON	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
	9/29/97	PES	<50	<0.5	<0.5	<0.5	<0.5	<5	--
	12/16/97	PES	<50	<0.5	<0.5	<0.5	<0.5	<5	--
	3/10/98	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
	1/19/99	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	<5.0
	4/15/99	PES	<50	0.75	0.64	<0.5	0.74	<5.0	--
	7/30/99	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
	11/15/99	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
MW-3	6/19/97	ENVIRON	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
	9/29/97	PES	<50	<0.5	<0.5	<0.5	<0.5	<5	--
	12/16/97	PES	<50	<0.5	<0.5	<0.5	<0.5	<5	--
	3/10/98	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
	1/19/99	PES	<50	0.78	<0.5	<0.5	<0.5	8.7	<5.0
	4/15/99	PES	<50	5.4	3.9	1.7	5.6	23	25
	7/30/99	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
	11/15/99	PES	<50	<0.5	<0.5	<0.5	<0.5	<5.0	--
MW-4	9/15/98	PES	170,000	26,000	32,000	2,900	18,000	26,000	--
	1/19/99	PES	2,600	1,700	3.8	25	29	13,000	16,000
	4/15/99	PES	210,000	28,000	15,000	3,700	19,000	52,000	67,000
	7/30/99	PES	91,000	16,000	7,500	2,300	8,500	68,000	67,000
	11/15/99	PES	63,000	8,500	2,400	1,400	4,000	57,000	58,000


**Notes:**

TPH-g = Total petroleum hydrocarbons quantified as gasoline (EPA 8015M).

MTBE = Methyl tert-butyl ether (EPA 8020; detected concentrations were confirmed by EPA 8260.)

µg/L = Micrograms per liter.

&lt;50 = Not detected at or above the indicated laboratory reporting limit.



**PROJECT SITE**



Scale in Feet

Oakland Map, California State Automobile Association, 1997.

*~1700' from Fitchburg well field  
1/4 mi = 1320'*



**PES Environmental, Inc.**  
Engineering & Environmental Services

**Site Location Map**

Quarterly Groundwater Monitoring - Fourth Quarter 1999  
Pacific Electric Motor Company  
1009 66th Avenue, Oakland, California

PLATE

**1**

618.00101.004

61800101004\_V1.CDR

*[Signature]*

01/00

JOB NUMBER



DRAWING NUMBER

REVIEWED BY

DATE



**Explanation**



⊕ Monitoring Well Location



Drawing modified from ENVIRON, 1997.

**Explanation**

-  Monitoring Well Location
- 94.37 Water-Level Elevation (in feet, referenced to site datum.
-  Groundwater contour (in feet referenced to site datum; dashed where inferred)
- Water levels measured on November 15, 1999.



Drawing modified from ENVIRON, 1997



**APPENDIX A**

**GROUNDWATER SAMPLING REPORT**

BLAINE  
TECH SERVICES INC.



1680 ROGERS AVENUE  
SAN JOSE, CALIFORNIA 95112-1105  
(408) 573-7771 FAX  
(408) 573-0555 PHONE

RECEIVED NOV 24 1999

November 22, 1999

PES Environmental, Inc.  
1682 Novato Blvd., Suite 100  
Novato, CA 94947

ATTN: Will Mast

Site:  
Pacific Electric Motor Company  
1099 66th Ave.  
Oakland, California

Date:  
November 15, 1999

## GROUNDWATER SAMPLING REPORT 991115-I-2

---

Blaine Tech Services, Inc. performs specialized environmental sampling and documentation as an independent third party. In order to avoid compromising the objectivity necessary for the proper and disinterested performance of this work, Blaine Tech Services, Inc. does not participate in the interpretation of analytical results, or become involved with the marketing or installation of remedial systems.

This report deals with the groundwater well sampling performed by our firm in response to your request. Data collected in the course of our work at the site are presented in the TABLE OF WELL MONITORING DATA. This information was collected during our inspection, well evacuation and sample collection. Measurements include the total depth of the well and the depth to water. Water surfaces were further inspected for the presence of immiscibles. A series of electrical conductivity, pH, turbidity, and temperature readings were obtained during well evacuation and at the time of sample collection.

## STANDARD PRACTICES

---

### Evacuation and Sampling Equipment

As shown in the TABLE OF WELL MONITORING DATA, the wells at this site were evacuated according to a protocol requirement for the removal of three case volumes of water, before sampling. The wells were evacuated using disposable bailers.

Samples were collected using bailers.

**Bailers:** A bailer, in its simplest form, is a hollow tube which has been fitted with a check valve at the lower end. The device can be lowered into a well by means of a cord. When the bailer enters the water, the check valve opens and liquid flows into the interior of the bailer. The bottom check valve prevents water from escaping when the bailer is drawn up and out of the well.

Two types of bailers are used in groundwater wells at sites where fuel hydrocarbons are of concern. The first type of bailer is made of a clear material such as acrylic plastic and is used to obtain a sample of the surface and the near surface liquids, in order to detect the presence of visible or measurable fuel hydrocarbon floating on the surface. The second type of bailer is made of Teflon or stainless steel, and is used as an evacuation and/or sampling device.

Bailers are inexpensive and relatively easy to clean. Because they are manually operated, variations in operator technique may have a greater influence than would be found with more automated sampling equipment. Also, where fuel hydrocarbons are involved, the bailer may include near surface contaminants that are not representative of water deeper in the well.

### Decontamination

All apparatus is brought to the site in clean and serviceable condition. The equipment is decontaminated after each use and before leaving the site.

### Effluent Materials

The evacuation process creates a volume of effluent water which must be contained. Blaine Tech Services, Inc. will place this water in appropriate containers of the client's choice or bring new 55 gallon DOT 17 E drums to the site, which are appropriate for the containment of the effluent materials. The determination of how to properly dispose of the effluent water must usually await the results of laboratory analyses of the sample collected from the groundwater well. If that sample does not establish whether or not the effluent water is contaminated, or if effluent from more than one source has been combined in the same container, it may be necessary to conduct additional analyses on the effluent material.

## **Sampling Methodology**

Samples were obtained by standardized sampling procedures that follow an evacuation and sample collection protocol. The sampling methodology conforms to both State and Regional Water Quality Control Board standards and specifically adheres to EPA requirements for apparatus, sample containers and sample handling as specified in publication SW 846 and T.E.G.D. which is published separately.

## **Sample Containers**

Sample containers are supplied by the laboratory performing the analyses.

## **Sample Handling Procedures**

Following collection, samples are promptly placed in an ice chest containing ice or an inert ice substitute such as Blue Ice or Super Ice. The samples are maintained in either an ice chest or a refrigerator until delivered into the custody of the laboratory.

## **Sample Designations**

All sample containers are identified with both a sampling event number and a discrete sample identification number. Please note that the sampling event number is the number that appears on our chain of custody. It is roughly equivalent to a job number, but applies only to work done on a particular day of the year rather than spanning several days, as jobs and projects often do.

## **Chain of Custody**

Samples are continuously maintained in an appropriate cooled container while in our custody and until delivered to the laboratory under our standard chain of custody. If the samples are taken charge of by a different party (such as another person from our office, a courier, etc.) prior to being delivered to the laboratory, appropriate release and acceptance records are made on the chain of custody (time, date and signature of person accepting custody of the samples).

## **Hazardous Materials Testing Laboratory**

The samples obtained at this site were analyzed at Entech in Sunnyvale, California. Entech is certified by the California Department of Health Services under the Environmental Laboratory Accreditation Program (ELAP), and is listed as ELAP #I-2346.

## Personnel

All Blaine Tech Services, Inc. personnel receive 29 CFR 1910.120(e)(2) training as soon after being hired as is practical. In addition, many of our personnel have additional certifications that include specialized training in level B supplied air apparatus and the supervision of employees working on hazardous materials sites. Employees are not sent to a site unless we are confident they can adhere to any site safety provisions in force at the site and unless we know that they can follow the written provisions of an SSP and the verbal directions of an SSO.

In general, employees sent to a site to perform groundwater well sampling will assume an OSHA level D (wet) environment exists unless otherwise informed. The use of gloves and double glove protocols protects both our employees and the integrity of the samples being collected. Additional protective gear and procedures for higher OSHA levels of protection are available.

## Reportage

Submission to the Regional Water Quality Control Board and the local implementing agency should include copies of the sampling report, the chain of custody and the certified analytical report issued by the Hazardous Materials Testing Laboratory.

Please call if we can be of any further assistance.

  
\_\_\_\_\_  
William Jones

WRJ/pb

attachments: table of well monitoring data  
chain of custody

### TABLE OF WELL MONITORING DATA

Well I.D.	MW-1			MW-2			MW-3			MW-4		
Date Sampled	11/15/99			11/15/99			11/15/99			11/15/99		
Well Diameter (in.)	2			2			2			2		
Total Well Depth (ft.)	24.96			24.88			24.60			24.57		
Depth To Water (ft.)	6.30			5.92			6.35			6.27		
Free Product (In.)	NONE			NONE			NONE			NONE		
Reason If Not Sampled	--			--			--			--		
1 Case Volume (gal.)	2.9			3.0			2.9			2.9		
Did Well Dewater?	NO			NO			NO			NO		
Gallons Actually Evacuated	9.00			9.00			9.00			9.00		
Purging Device	BAILER			BAILER			BAILER			BAILER		
Sampling Device	BAILER			BAILER			BAILER			BAILER		
Time	10:51	10:55	10:59	9:30	9:35	9:39	10:01	10:05	10:09	10:30	10:34	10:38
Temperature (Fahrenheit)	67.8	67.9	67.9	65.0	65.2	65.2	65.1	65.5	65.8	70.5	70.3	69.8
pH	7.2	7.1	7.1	7.2	7.2	7.2	7.2	7.1	7.1	6.8	6.8	6.8
Conductivity (micromhos/cm)	840	690	690	1156	1147	1135	2950	3580	3770	6820	7150	7133
Nephelometric Turbidity Units	71	95	>200	>200	>200	>200	>200	>200	>200	62	44	39
Dissolved Oxygen (D.O) (mg/L)	--			--			--			--		
Oxidation Reduction Potential (mV)	--			--			--			--		
BTS Chain of Custody	991115-I2			991115-I2			991115-I2			991115-I2		
BTS Sample I.D.	MW-1			MW-2			MW-3			MW-4		
DOHS HMTL Laboratory	ENTECH			ENTECH			ENTECH			ENTECH		
Analysis	TPH-G, BTEX, MTBE			TPH-G, BTEX, MTBE			TPH-G, BTEX, MTBE			TPH-G, BTEX, MTBE		



**APPENDIX B**

**LABORATORY REPORTS  
AND  
CHAIN-OF-CUSTODY RECORDS**



# Entech Analytical Labs, Inc.

CA ELAP# I-2346

525 Del Rey Avenue, Suite E • Sunnyvale, CA 94086 • (408) 735-1550 • Fax (408) 735-1554

November 22, 1999

Will Mast  
 PES Environmental, Inc.  
 1682 Novato Boulevard, Suite 100  
 Novato, CA 94947

**Order:** 17583

**Date Collected:** 11/15/99

**Project Name:**

**Date Received:** 11/15/99

**Project Number:**

**P.O. Number:**

**Project Notes:**

On November 15, 1999, 4 samples were received under documented chain of custody. Results for the following analyses are attached:

<u>Matrix</u>	<u>Test</u>	<u>Method</u>
Liquid	BTEX	EPA 8020
	MTBE	EPA 8020
	TPH as Gasoline	EPA 8015 MOD. (Purgeable)

Chemical analysis of these samples has been completed. Summaries of the data are contained on the following pages. USEPA protocols for sample storage and preservation were followed.

Entech Analytical Labs, Inc. is certified by the State of California (#I-2346). If you have any questions regarding procedures or results, please call me at 408-735-1550.

Sincerely,



Michelle L. Anderson  
 Lab Director

# Entech Analytical Labs, Inc.

CA ELAP# 1-2346

525 Del Rey Avenue, Suite E • Sunnyvale, CA 94086 • (408) 735-1550 • Fax (408) 735-1554

PES Environmental, Inc.  
1682 Novato Blvd., Suite 100  
Novato, CA 94947  
Attn: Will Mast

Date: 11/22/99  
Date Received: 11/15/99  
Project:  
PO #:  
Sampled By: Client

## Certified Analytical Report

### Liquid Sample Analysis:

Sample ID	MW-1			MW-2			MW-3				
Sample Date	11/15/99			11/15/99			11/15/99				
Sample Time	11:03			9:42			10:12				
Lab #	17583-001			17583-002			17583-003				
	Result	DF	DLR	Result	DF	DLR	Result	DF	DLR	PQL	Method
Results in µg/Liter:											
Analysis Date	11/16/99			11/16/99			11/17/99				
TPH-Gas	3,600	5.0	250	ND	1.0	50	ND	1.0	50	50	8015M
MTBE	ND	5.0	25	ND	1.0	5.0	ND	1.0	5.0	5.0	8020
Benzene	120	5.0	2.5	ND	1.0	0.50	ND	1.0	0.50	0.50	8020
Toluene	ND	5.0	2.5	ND	1.0	0.50	ND	1.0	0.50	0.50	8020
Ethyl Benzene	150	5.0	2.5	ND	1.0	0.50	ND	1.0	0.50	0.50	8020
Xylenes (total)	620	5.0	2.5	ND	1.0	0.50	ND	1.0	0.50	0.50	8020

DF=Dilution Factor

ND= None Detected above DLR

PQL=Practical Quantitation Limit

DLR=Detection Reporting Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #I-2346)

  
Michelle L. Anderson, Lab Director

Environmental Analysis Since 1983

# Entech Analytical Labs, Inc.

CA ELAP# I-2346

525 Del Rey Avenue, Suite E • Sunnyvale, CA 94086 • (408) 735-1550 • Fax (408) 735-1554

PES Environmental, Inc.  
1682 Novato Blvd., Suite 100  
Novato, CA 94947  
Attn: Will Mast

Date: 11/22/99  
Date Received: 11/15/99  
Project:  
PO #:  
Sampled By: Client

## Certified Analytical Report

### Liquid Sample Analysis:

Sample ID	MW-4										
Sample Date	11/15/99										
Sample Time	10:41										
Lab #	17583-004										
	Result	DF	DLR							PQL	Method
<b>Results in µg/Liter:</b>											
Analysis Date	11/18/99										
TPH-Gas	63,000	500	25000							50	8015M
MTBE	57,000	500	2500							5.0	8020
Benzene	8,500	500	250							0.50	8020
Toluene	2,400	500	250							0.50	8020
Ethyl Benzene	1,400	500	250							0.50	8020
Xylenes (total)	4,000	500	250							0.50	8020

DF=Dilution Factor      ND= None Detected above DLR      PQL=Practical Quantitation Limit      DLR=Detection Reporting Limit

• Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #I-2346)

  
Michelle L. Anderson, Lab Director

Environmental Analysis Since 1983

## QUALITY CONTROL RESULTS SUMMARY

METHOD: Gas Chromatography

Laboratory Control Sample

QC Batch #: GBG1991116

Matrix: Liquid

Units: µg/Liter

Date Analyzed: 11/16/99

Quality Control Sample: Blank Spike

PARAMETER	Method #	MB µg/Liter	SA µg/Liter	SR µg/Liter	SP µg/Liter	SP % R	SPD µg/Liter	SPD %R	RPD	QC LIMITS	
										RPD	%R
Benzene	8020	<0.50	6.6	ND	7.2	108	7.2	109	0.4	25	77-129
Toluene	8020	<0.50	29.0	ND	27	94	28	95	1.0	25	82-122
Ethyl Benzene	8020	<0.50	5.7	ND	5.4	95	5.4	95	0.0	25	77-114
Xylenes	8020	<0.50	30.6	ND	30	99	30	100	0.7	25	85-125
Gasoline	8015	<50.0	500	ND	439	88	436	87	0.8	25	75-125
aaa-TFT(S.S.)-PID	8020			100%	103%		103%				65-135
aaa-TFT(S.S.)-FID	8015			87%	95%		95%				65-135

## Definition of Terms:

- na: Not Analyzed in QC batch
- MB: Method Blank
- SA: Spike Added
- SR: Sample Result
- RPD(%): Duplicate Analysis - Relative Percent Difference
- SP: Spike Result
- SP (%R): Spike % Recovery
- SPD: Spike Duplicate Result
- SPD (%R): Spike % Recovery
- nc: Not Calculated

Entech Analytical Labs, Inc.

525 Del Rey Avenue, Suite E  
Sunnyvale, CA 94086

**QUALITY CONTROL RESULTS SUMMARY**

METHOD: Gas Chromatography

Laboratory Control Sample

QC Batch #: GBG4991118

Matrix: Liquid

Units: µg/Liter

Date Analyzed: 11/18/99

Quality Control Sample: Blank Spike

PARAMETER	Method #	MB µg/Liter	SA µg/Liter	SR µg/Liter	SP µg/Liter	SP % R	SPD µg/Liter	SPD %R	% RPD	QC LIMITS	
										RPD	%R
Benzene	8020	<0.50	5.6	ND	5.1	92	4.8	86	6.4	25	70-130
Toluene	8020	<0.50	31	ND	30	95	30	94	0.1	25	70-130
Ethyl Benzene	8020	<0.50	6.1	ND	5.7	94	5.5	90	3.7	25	70-130
Xylenes	8020	<0.50	35	ND	33	96	33	94	1.9	25	70-130
Gasoline	8015	<50.0	500	ND	477	95	459	92	3.9	25	70-130
aaa-TFT(S.S.)-FID	8020			104%	103%		100%				65-135
aaa-TFT(S.S.)-PID	8015			111%	111%		108%				65-135

Definition of Terms:

- na: Not Analyzed in QC batch
- MB: Method Blank
- SA: Spike Added
- SR: Sample Result
- RPD(%): Duplicate Analysis - Relative Percent Difference
- SP: Spike Result
- SP (%R): Spike % Recovery
- SPD: Spike Duplicate Result
- SPD (%R): Spike % Recovery
- nc: Not Calculated

Entech Analytical Labs, Inc.

525 Del Rey Avenue, Suite E  
Sunnyvale, CA 94086

**QUALITY CONTROL RESULTS SUMMARY**

METHOD: Gas Chromatography

Laboratory Control Sample

QC Batch #: GBG4991117

Matrix: Liquid

Units: µg/Liter

Date Analyzed: 11/17/99

Quality Control Sample: Blank Spike

PARAMETER	Method #	MB µg/Liter	SA µg/Liter	SR µg/Liter	SP µg/Liter	SP % R	SPD µg/Liter	SPD %R	% RPD	QC LIMITS	
										RPD	%R
Benzene	8020	<0.50	5.6	ND	5.2	93	5.1	90	3.1	25	70-130
Toluene	8020	<0.50	31	ND	30	95	30	95	0.3	25	70-130
Ethyl Benzene	8020	<0.50	6.1	ND	5.6	92	5.6	91	0.6	25	70-130
Xylenes	8020	<0.50	35	ND	33	95	33	94	0.8	25	70-130
Gasoline	8015	<50.0	500	ND	450	90	446	89	1.0	25	70-130
aaa-TFT(S.S.)-FID	8020			104%	100%		100%				65-135
aaa-TFT(S.S.)-PID	8015			108%	102%		102%				65-135

Definition of Terms:

- na: Not Analyzed in QC batch
- MB: Method Blank
- SA: Spike Added
- SR: Sample Result
- RPD(%): Duplicate Analysis - Relative Percent Difference
- SP: Spike Result
- SP (%R): Spike % Recovery
- SPD: Spike Duplicate Result
- SPD (%R): Spike % Recovery
- nc: Not Calculated

# BLAINE

TECH SERVICES INC.

1680 ROGERS AVENUE  
 SAN JOSE, CALIFORNIA 95112-1105  
 FAX (408) 573-7771  
 PHONE (408) 573-0555

## CONDUCT ANALYSIS TO DETECT

LAB ENTECH DHS # \_\_\_\_\_  
 ALL ANALYSES MUST MEET SPECIFICATIONS AND DETECTION LIMITS SET BY CALIFORNIA DHS AND  
 EPA  RWQCB REGION \_\_\_\_\_  
 LIA  
 OTHER

CHAIN OF CUSTODY  
BTS # 991115-I 2  
 CLIENT PES  
 SITE PACIFIC ELECTRIC MOTOR  
1099 66TH AVE  
OAKLAND, CA

C = COMPOSITE ALL CONTAINERS  
 (BOD) (BOD) (BOD) / TP-1-G / BTEX / MTBE \*

SAMPLE I.D.		MATRIX		CONTAINERS		C	17583	ADD'L INFORMATION	STATUS	CONDITION	LAB SAMPLE #
		S	W	TOTAL							
MW-1	11-15-99	W	3	1103	X		-001				
MW-2	↓	↓	↓	942	X		-002				
MW-3	↓	↓	↓	1012	X		-003				
MW-4	↓	↓	↓	1041	X		-004				

SPECIAL INSTRUCTIONS  
 INVOICE & REPORT TO  
 PES  
 ATTN: WILL MARR  
 PJS #  
 \* CONFIRM MTBE HITS BY 8240/8260

SAMPLING COMPLETED DATE 11-15-99 TIME 1103 SAMPLING PERFORMED BY Patrick Flaherty RESULTS NEEDED NO LATER THAN Pee chart

RELEASED BY Patrick Flaherty DATE \_\_\_\_\_ TIME \_\_\_\_\_ RECEIVED BY David Horn DATE 11/15/99 TIME 15:25

RELEASED BY \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_ RECEIVED BY \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_

RELEASED BY \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_ RECEIVED BY \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_

SHIPPED VIA \_\_\_\_\_ DATE SENT \_\_\_\_\_ TIME SENT \_\_\_\_\_ COOLER # \_\_\_\_\_

# Entech Analytical Labs, Inc.

CA ELAP# I-2346

525 Del Rey Avenue, Suite E • Sunnyvale, CA 94086 • (408) 735-1550 • Fax (408) 735-1554

December 01, 1999

Will Mast  
PES Environmental, Inc.  
1682 Novato Boulevard, Suite 100  
Novato, CA 94947

RECEIVED DEC 21 1999  
RECEIVED DEC 21 1999

**Order:** 17583

**Date Collected:** 11/15/99

**Project Name:**

**Date Received:** 11/15/99

**Project Number:**

**P.O. Number:**

**Project Notes:**


On November 15, 1999, 1 sample was received under documented chain of custody. Results for the following analyses are attached:

<u>Matrix</u>	<u>Test</u>	<u>Method</u>
Liquid	MTBE by EPA 8260B	EPA 8260B

Chemical analysis of these samples has been completed. Summaries of the data are contained on the following pages. USEPA protocols for sample storage and preservation were followed.

Entech Analytical Labs, Inc. is certified by the State of California (#I-2346). If you have any questions regarding procedures or results, please call me at 408-735-1550.

Sincerely,



Michelle L. Anderson  
Lab Director



# Entech Analytical Labs, Inc.

CA ELAP# I-2346

525 Del Rey Avenue, Suite E • Sunnyvale, CA 94086 • (408) 735-1550 • Fax (408) 735-1554

PES Environmental, Inc.  
1682 Novato Boulevard, Suite 100  
Novato, CA 94947  
Attn: Will Mast

Date: 12/1/99  
Date Received: 11/15/99  
Project Name:  
Project Number:  
P.O. Number:  
Sampled By: Blaine Tech

## Certified Analytical Report

Order ID: 17583

Lab Sample ID: 17583-004

Client Sample ID: MW-4

Sample Time: 10:41 AM

Sample Date: 11/15/99

Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Analysis Date	QC Batch ID	Method
Methyl-t-butyl Ether	58000		1000	5	5000	µg/L	11/29/99	WMS991129	EPA 8260B
	Surrogate			Surrogate Recovery			Control Limits (%)		
	4-Bromofluorobenzene			95			65 - 135		
	Dibromofluoromethane			83			65 - 135		
	Toluene-d8			102			65 - 135		


DF = Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #I-2346)

  
Michelle L. Anderson, Laboratory Director

Page 1 of 1

Environmental Analysis Since 1983

Entech Analytical Labs, Inc.

525 Del Rey Avenue, Suite E  
Sunnyvale, CA 94086

QUALITY CONTROL RESULTS SUMMARY

Volatile Organic Compounds  
Laboratory Control Sample

QC Batch #: WMS991129  
Matrix: Liquid  
Units: µg/L

Date analyzed: 11/29/99  
Spiked Sample: Blank Spike

PARAMETER	Method #	SA µg/L	SR µg/L	SP µg/L	SP %R	SPD µg/L	SPD %R	RPD	QC LIMITS	
									RPD	%R
1,1- Dichloroethene	8240/8260	40	ND	35.9	90	42.4	106	16.6	25	50-150
Methyl-tert-butyl ether	8240/8260	40	ND	37.6	94	37.4	94	0.5	25	50-150
Benzene	8240/8260	40	ND	40.4	101	38.5	96	4.8	25	50-150
Trichloroethene	8240/8260	40	ND	39.0	98	38.0	95	2.6	25	50-150
Toluene	8240/8260	40	ND	41.7	104	38.0	95	9.3	25	50-150
Chlorobenzene	8240/8260	40	ND	40.1	100	37.4	94	7.0	25	50-150
<i>Surrogates</i>										
Dibromofluoromethane	8240/8260		114%	82%		95%				65-135
MTBE-d3	8240/8260		125%	94%		111%				65-135
Toluene -d8	8240/8260		96%	101%		103%				65-135
4-Bromofluorobenzene	8240/8260		87%	104%		107%				65-135

Definition of Terms:

- na: Not Analyzed in QC batch
- SA: Spike Added
- SR: Sample Result
- RPD(%): Duplicate Analysis - Relative Percent Difference
- SP: Spike Result
- SP (%R): Spike % Recovery
- SPD: Spike Duplicate Result
- SPD (%R): Spike Duplicate % Recovery



**DISTRIBUTION**

**QUARTERLY MONITORING REPORT  
FOURTH QUARTER 1999  
PACIFIC ELECTRIC MOTOR COMPANY  
1009 66TH AVENUE  
OAKLAND, CALIFORNIA**

**JANUARY 6, 2000**

**COPY NO. \_\_\_\_\_**

		<u>Copy No.</u>
1 Copy	Pacific Electric Motor Company 137 Fiesta Circle Orinda, California 94563  Attention: Mr. Steve Boyd	1
2 Copies	Pacific Electric Motor Company 129 Natalie Drive Moraga, California 94556-2422  Attention: Mr. Rand Perry	2 - 3
2 Copies	Alameda County Health Care Service Agency Department of Environmental Health 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502-6577  Attention: Mr. Barney Chan	4 - 5
3 Copies	PES Job File	6 - 8
1 Copy	Unbound Original	9