



76 Broadway
Sacramento, California 95818

RECEIVED

10:22 am, Feb 24, 2009

Alameda County
Environmental Health

October 24, 2008

Paresh Khatari
Alameda County Health Agency
1131 Harbor Bay parkway, Suite250
Alameda, California 94502-577

Re: ***Semi Annual Report—Second and Third Quarter 2008***
76 Service Station # 6419/5748 RO # 0459
6401 Dublin Blvd.
Dublin CA

Dear Mr. Khatari:

I declare under penalty of perjury that to the best of my knowledge the information and/or recommendations contained in the attached report is/are true and correct.

If you have any questions or need additional information, please call me at (916) 558-7666.

Sincerely,

Terry L. Grayson
Site Manager
Risk Management & Remediation

October 22, 2008

Mr. Barney Chan
Alameda County Health Care Services
1131 Harbor Bay Parkway
Alameda, California 94502-6577

Re: Quarterly Summary Report – Third Quarter 2008

76 Service Station No. 5748
6401 Dublin Boulevard
Dublin, California



Dear Mr. Chan,

On behalf of ConocoPhillips Company (ConocoPhillips), Delta Consultants (Delta) is submitting the subject report and forwarding a copy of TRC's *Semi-Annual Monitoring Report April through September 2008*, dated September 22, 2008 for the above site. TRC has uploaded a copy of their report to the GeoTracker database.


Please contact me at (916) 503-1260 if you have questions.

Sincerely,
Delta Consultants

A handwritten signature in black ink, appearing to read "John Reay".

John Reay, P.G.

Senior Project Manager
California Registered Professional Geologist



Enclosure

cc: Mr. Bill Borgh- ConocoPhillips (electronic copy only)

QUARTERLY STATUS REPORT
Third Quarter 2008

76 Service Station No. 5748
6401 Dublin Boulevard
Dublin, California

County: Alameda

SITE DESCRIPTION

The subject site is an active service station located on the western corner of Dublin Boulevard and Dougherty Road in Dublin, California. The site is bounded to the southeast by Dublin Boulevard, to the northeast by Dougherty Road, and to the northwest and southwest by a shopping center parking lot. Properties in the immediate site vicinity are commercial, including service stations and retail shopping facilities.

Current aboveground sit facilities consist of two dispenser islands, a car wash, and a station building/convenience store. Two 12,000-gallon gasoline underground storage tanks (USTs) are located in the common pit immediately east of the station building.

SITE BACKGROUND AND ACTIVITY

September 1993 Two 10,000 galloon gasoline USTs, one 55-gallon waste oil UST, and the associated product piping were removed from the site with confirmation sampling. Groundwater was observed entering the UST excavation. Concentrations of petroleum hydrocarbons in confirmation soil samples beneath the fuel USTs were non-detect to low. Concentrations of petroleum hydrocarbons and volatile organic compounds (VOCs) in confirmation soil samples beneath the waste oil UST were non-detect to low, and concentrations of metals were considered background levels. Petroleum hydrocarbon and lead concentrations in confirmation soil samples from the dispenser islands were non-detect, and low, respectively. Petroleum hydrocarbon and lead concentrations in confirmation soil samples from the piping trenches were non-detect, and low, respectively.

February 1994 Three onsite monitoring wells were installed.

June 1999 Four onsite monitoring wells were installed to a depth of approximately 19 feet below ground surface (bgs).

November 1999 A four-inch diameter groundwater observation and extraction well (TPW-1) was installed in the gasoline UST pit backfill to allow purging of methyl tertiary butyl ether (MTBE) impacted groundwater.

September 2001 Two offsite monitoring wells were installed to a depth of 20 feet bgs.

October 2003 Site environmental consulting responsibilities were transferred to TRC.

December 2004 Offsite monitoring wells MW-8 and MW-9 were abandoned due to construction activities planned at those locations by Pin Brothers Fine Homes.

January 12, 2006 Onsite monitoring wells MW-2, MW-4, MW-6, and MW-7 were abandoned at the request of the City of Dublin in anticipation of street widening on both Dougherty Road and Dublin Boulevard.

SENSITIVE RECEPTORS

July 3, 2007 TRC completed a sensitive receptor survey for the site. According to California Department of Water Resources (DWR) and the Zone 7 Water Agency records, four water supply wells were located within a one-half mile distance of the site. Three of the wells are listed by the Zone 7 water Agency as water supply wells and are located approximately 1,940 feet east, 2,175 feet north, and 2,070 feet northwest of the Site. One well is listed by the Zone 7 Water Agency as an abandoned water supply well and is located approximately 2,440 feet west-southwest of the Site.

Three surface water bodies were identified within a one-half mile distance of the Site. San Ramon Creek is located approximately 2,145 feet northwest of the site, and unnamed canal is located approximately 625 feet southwest of the Site, and the Chabot Canal is located approximately 1,650 feet east of the Site.

GROUNDWATER MONITORING AND SAMPLING

Three remaining onsite wells are currently monitored semi-annually during the first and third quarters. The groundwater flow direction was reported northwest at a gradient of 0.005 feet per foot (ft/ft). This is consistent with the gradient of 0.007 northwest during the previous sampling event (March 27, 2007). Reported historical groundwater flow at the site is southwest.

Groundwater concentrations are reported as follows.

TPH-G Detected in one of the three sampled wells with a maximum concentration of 360 µg/L in well MW-5, a decrease from a maximum concentration of 580 µg/L in this well during the previous sampling event.

Benzene Not reported above laboratory reporting limits in any sampled well. This is consistent with the previous sampling event.

MTBE Detected in all three of the sampled wells with a maximum concentration of 840 µg/L in well MW-5, a decrease from a maximum concentration of 1,400 µg/L in this well during the previous sampling event.

REMEDIATION STATUS

September 2003 Approximately 19,000 gallons of groundwater were removed from the UST excavation and properly disposed offsite. A hydrocarbon sheen was observed on the surface of the groundwater in the southwest corner of the excavation. Approximately 850 cubic yards of excavated soil was properly disposed offsite. Two 12,000-gallon and one 520-gallon double-wall glasteel replacement USTs were installed in the same pit.

July 1998 A soil vapor extraction test was conducted. Approximately 0.53 pounds of TPH-g and 6.5 pounds of MTBE (approximately 1 gallon of gasoline/additive) were extracted during the four day test. The effective radius of influence was thought to be less than 40 feet.

December 1999 through December 2002 Approximately 649,600 gallons of groundwater containing an estimated 130.21 pounds of MTBE were removed from the tank pit observation and extraction well. Batch extractions were ended February 5, 2003, based on asymptotic levels of cumulative pounds of MTBE removed. The purged groundwater was transported to, treated, and disposed of at the Conoco Phillips refinery located in Rodeo, California.

Remediation is not currently being conducted at the site.

CHARACTERIZATION STATUS

Site assessment appears complete along the southeastern corner of the site through the borings and samplings of MW-4, MW-5, MW-8, MW-9. The plume is concentrated in the area around MW-5. It is likely that the plume, particularly the MTBE component, is now largely present offsite. Further assessment is therefore needed offsite and in the vicinity of the destroyed wells to support an effort of site closure.

RECENT CORRESPONDENCE

No correspondence has been received or sent regarding this site during third quarter

THIS QUARTER ACTIVITIES (Third Quarter 2008)

- Monitoring and sampling of the groundwater monitoring well network was conducted by TRC on September 22, 2008.
- TRC prepared the *Semi-Annual Monitoring Report, April through September*, dated September 22, 2008.

NEXT QUARTER ACTIVITIES (Fourth Quarter 2008)

- TRC will perform will prepare a quarterly monitoring report.

CONSULTANT: Delta Consultants

5748



21 Technology Drive
Irvine, CA 92618

949.727.9336 PHONE
949.727.7399 FAX

www.TRCSolutions.com

RECEIVED

OCT 01 2008

DATE: September 22, 2008

TO: ConocoPhillips Company
76 Broadway
Sacramento, CA 95818

ATTN: MR. TERRY GRAYSON

SITE: 76 STATION 6419
6401 DUBLIN BOULEVARD
DUBLIN, CALIFORNIA

RE: SEMI-ANNUAL MONITORING REPORT
APRIL THROUGH SEPTEMBER 2008

Dear Mr. Grayson:

Please find enclosed our Semi-Annual Monitoring Report for 76 Station 6419, located at 6401 Dublin Boulevard, Dublin, California. If you have any questions regarding this report, please call us at (949) 727-9336.

Sincerely,

TRC

A handwritten signature in black ink, appearing to read "Anju Farfan".

Anju Farfan
Groundwater Program Operations Manager

CC: Ms. Caitlin Morgan, Delta Consultants (2 copies)

Enclosures
20-0400/6419R11.QMS


**SEMI-ANNUAL MONITORING REPORT
APRIL THROUGH SEPTEMBER 2008**


76 STATION 6419
6401 Dublin Boulevard
Dublin, California

Prepared For:

Mr. Terry Grayson
ConocoPhillips Company
76 Broadway
Sacramento, California 95818

By:





Senior Project Geologist, Irvine Operations

Date: 9/19/08



LIST OF ATTACHMENTS

Summary Sheet	Summary of Gauging and Sampling Activities
Tables	Table Key Contents of Tables Table 1: Current Fluid Levels and Selected Analytical Results Table 1a: Additional Current Analytical Results Table 2: Historic Fluid Levels and Selected Analytical Results Table 2a: Additional Historic Analytical Results Table 2b: Additional Historic Analytical Results
Figures	Figure 1: Vicinity Map Figure 2: Groundwater Elevation Contour Map Figure 3: Dissolved-Phase TPH-G (GC/MS) Concentration Map Figure 4: Dissolved-Phase Benzene Concentration Map Figure 5: Dissolved-Phase MTBE Concentration Map
Graphs	Groundwater Elevations vs. Time Benzene Concentrations vs. Time
Field Activities	General Field Procedures Field Monitoring Data Sheet - 09/02/08 Groundwater Sampling Field Notes - 09/02/08
Laboratory Reports	Official Laboratory Reports Quality Control Reports Chain of Custody Records
Statements	Purge Water Disposal Limitations

Summary of Gauging and Sampling Activities
April 2008 through September 2008
76 Station 6419
6401 Dublin Boulevard
Dublin, CA

Project Coordinator: **Terry Grayson**
Telephone: **916-558-7666**

Water Sampling Contractor: **TRC**
Compiled by: **Christina Carrillo**

Date(s) of Gauging/Sampling Event: **09/02/08**

Sample Points

Groundwater wells: **3** onsite, **0** offsite Points gauged: **3** Points sampled: **3**
Purging method: **Bailer/submersible pump**
Purge water disposal: **Veolia/Rodeo Unit 100**
Other Sample Points: **0** Type: **--**

Liquid Phase Hydrocarbons (LPH)

Sample Points with LPH: **0** Maximum thickness (feet): **--**
LPH removal frequency: **--** Method: **--**
Treatment or disposal of water/LPH: **--**

Hydrogeologic Parameters

Depth to groundwater (below TOC): Minimum: **7.37 feet** Maximum: **7.84 feet**
Average groundwater elevation (relative to available local datum): **322.68 feet**
Average change in groundwater elevation since previous event: **-0.71 feet**
Interpreted groundwater gradient and flow direction:
 Current event: **0.005 ft/ft, northwest**
 Previous event: **0.007 ft/ft, northwest (03/27/08)**

Selected Laboratory Results

Sample Points with detected **Benzene**: **0** Sample Points above MCL (1.0 µg/l): **--**
 Maximum reported benzene concentration: **--**

Sample Points with **TPH-G by GC/MS** **1** Maximum: **360 µg/l (MW-5)**
Sample Points with **MTBE 8260B** **3** Maximum: **840 µg/l (MW-5)**

Notes:

TABLES

TABLE KEY

STANDARD ABBREVIATIONS

-	=	not analyzed, measured, or collected
LPH	=	liquid-phase hydrocarbons
Trace	=	less than 0.01 foot of LPH in well
µg/l	=	micrograms per liter (approx. equivalent to parts per billion, ppb)
mg/l	=	milligrams per liter (approx. equivalent to parts per million, ppm)
ND<	=	not detected at or above laboratory detection limit
TOC	=	top of casing (surveyed reference elevation)

ANALYTES

BTEX	=	benzene, toluene, ethylbenzene, and (total) xylenes
DIPE	=	di-isopropyl ether
ETBE	=	ethyl tertiary butyl ether
MTBE	=	methyl tertiary butyl ether
PCB	=	polychlorinated biphenyls
PCE	=	tetrachloroethene
TBA	=	tertiary butyl alcohol
TCA	=	trichloroethane
TCE	=	trichloroethene
TPH-G	=	total petroleum hydrocarbons with gasoline distinction
TPH-G (GC/MS)	=	total petroleum hydrocarbons with gasoline distinction utilizing EPA Method 8260B
TPH-D	=	total petroleum hydrocarbons with diesel distinction
TRPH	=	total recoverable petroleum hydrocarbons
TAME	=	tertiary amyl methyl ether
1,1-DCA	=	1,1-dichloroethane
1,2-DCA	=	1,2-dichloroethane (same as EDC, ethylene dichloride)
1,1-DCE	=	1,1-dichloroethene
1,2-DCE	=	1,2-dichloroethene (cis- and trans-)

NOTES

1. Elevations are in feet above mean sea level. Depths are in feet below surveyed top-of-casing.
2. Groundwater elevations for wells with LPH are calculated as: $\text{Surface Elevation} - \text{Measured Depth to Water} + (\text{Dp} \times \text{LPH Thickness})$, where Dp is the density of the LPH, if known. A value of 0.75 is used for gasoline and when the density is not known. A value of 0.83 is used for diesel.
3. Wells with LPH are generally not sampled for laboratory analysis (see General Field Procedures).
4. Comments shown on tables are general. Additional explanations may be included in field notes and laboratory reports, both of which are included as part of this report.
5. A "J" flag indicates that a reported analytical result is an estimated concentration value between the method detection limit (MDL) and the practical quantification limit (PQL) specified by the laboratory.
6. Other laboratory flags (qualifiers) may have been reported. See the official laboratory report (attached) for a complete list of laboratory flags.
7. Concentration graphs based on tables (presented following Figures) show non-detect results prior to the Second Quarter 2000 plotted at fixed values for graphical display. Non-detect results reported since that time are plotted at reporting limits stated in the official laboratory report.
8. Groundwater vs. Time graphs may be corrected for apparent level changes due to resurvey.

REFERENCE

TRC began groundwater monitoring and sampling for 76 Station 6419 in October 2003. Historical data compiled prior to that time were provided by Gettler-Ryan Inc.

Contents of Tables 1 and 2
Site: 76 Station 6419

Current Event

Table 1	Well/ Date	Depth to Water	LPH Thickness	Ground- water Elevation	Change in Elevation	TPH-G (8015M)	TPH-G (GC/MS)	Benzene	Toluene	Ethyl- benzene	Total Xylenes	MTBE (8021B)	MTBE (8260B)
---------	---------------	-------------------	------------------	-------------------------------	------------------------	------------------	------------------	---------	---------	-------------------	------------------	-----------------	-----------------

Table 1a	Well/ Date	Ethanol (8260B)
----------	---------------	--------------------

Historic Data

Table 2	Well/ Date	Depth to Water	LPH Thickness	Ground- water Elevation	Change in Elevation	TPH-G (8015M)	TPH-G (GC/MS)	Benzene	Toluene	Ethyl- benzene	Total Xylenes	MTBE (8021B)	MTBE (8260B)
---------	---------------	-------------------	------------------	-------------------------------	------------------------	------------------	------------------	---------	---------	-------------------	------------------	-----------------	-----------------

Table 2a	Well/ Date	TPH-D	TBA	Ethanol (8260B)	Ethylene- dibromide (EDB)	1,2-DCA (EDC)	DIPE	ETBE	TAME	Cadmium (dissolved)	Chromium (total)	Lead (total)	Nickel (total)
----------	---------------	-------	-----	--------------------	---------------------------------	------------------	------	------	------	------------------------	---------------------	-----------------	-------------------

Table 2b	Well/ Date	Zinc (total)	Post-purge Dissolved Oxygen	Pre-purge Dissolved Oxygen
----------	---------------	-----------------	-----------------------------------	----------------------------------

Table 1
CURRENT FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
September 2, 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl- benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
			(Screen Interval in feet: 4.0-19.0)											
MW-1 09/02/08	330.17	7.37	0.00	322.80	-0.78	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	16	
			(Screen Interval in feet: 4.0-20.0)											
MW-3 09/02/08	330.59	7.84	0.00	322.75	-0.76	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	50	
			(Screen Interval in feet: 4.0-19.0)											
MW-5 09/02/08	330.18	7.70	0.00	322.48	-0.58	--	360	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	840	

Table 1 a
ADDITIONAL CURRENT ANALYTICAL RESULTS
76 Station 6419

Date Sampled	Ethanol (8260B) (µg/l)
MW-1 09/02/08	ND<250
MW-3 09/02/08	ND<250
MW-5 09/02/08	ND<250

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-1						(Screen Interval in feet: 4.0-19.0)								
03/14/94	330.45	7.27	0.00	323.18	--	1800	--	17	ND	ND	ND	--	--	
08/25/94	330.45	8.57	0.00	321.88	-1.30	9200	--	48	ND	540	ND	--	--	
09/30/94	330.45	8.78	0.00	321.67	-0.21	--	--	--	--	--	--	--	--	
10/20/94	330.45	8.98	0.00	321.47	-0.20	--	--	--	--	--	--	--	--	
11/18/94	330.45	7.69	0.00	322.76	1.29	5100	--	33	ND	560	38	--	--	
12/20/94	330.45	7.58	0.00	322.87	0.11	--	--	--	--	--	--	--	--	
01/17/95	330.45	6.03	0.00	324.42	1.55	--	--	--	--	--	--	--	--	
02/15/95	330.45	6.29	0.00	324.16	-0.26	3300	--	13	ND	180	5.2	--	--	
03/13/95	330.45	5.64	0.00	324.81	0.65	--	--	--	--	--	--	--	--	
04/06/95	330.45	5.62	0.00	324.83	0.02	--	--	--	--	--	--	--	--	
05/17/95	330.45	6.26	0.00	324.19	-0.64	130	--	0.75	ND	1.5	ND	--	--	
06/15/95	330.45	6.75	0.00	323.70	-0.49	--	--	--	--	--	--	--	--	
08/25/95	330.45	7.91	0.00	322.54	-1.16	490	--	9.1	ND	21	2	--	--	
11/28/95	330.45	9.03	0.00	321.42	-1.12	1400	--	18	3	98	3.6	--	--	
02/26/96	330.45	5.77	0.00	324.68	3.26	560	--	9.3	ND	22	ND	1300	--	
08/23/96	330.45	7.78	0.00	322.67	-2.01	ND	--	ND	ND	ND	ND	640	--	
02/17/97	330.23	5.73	0.00	324.50	1.83	120	--	1	0.95	ND	ND	280	--	
08/18/97	330.23	7.38	0.00	322.85	-1.65	ND	--	ND	ND	ND	ND	100	--	
02/02/98	330.23	5.10	0.00	325.13	2.28	ND	--	130	ND	ND	ND	32000	--	
08/24/98	330.23	6.73	0.00	323.50	-1.63	ND	--	ND	ND	ND	ND	26000	24000	
02/10/99	330.23	5.46	0.00	324.77	1.27	ND	--	ND	ND	ND	ND	84000	100000	
04/12/99	330.23	6.38	0.00	323.85	-0.92	ND	--	ND	ND	ND	ND	140000	120000	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-1 continued														
05/21/99	330.21	5.95	0.00	324.26	0.41	--	--	--	--	--	--	--	--	
08/02/99	330.21	6.75	0.00	323.46	-0.80	ND	--	ND	ND	ND	ND	91000	140000	
02/11/00	330.21	6.44	0.00	323.77	0.31	ND	--	ND	ND	ND	ND	38000	39000	
07/26/00	330.18	7.08	0.00	323.10	-0.67	146	--	ND	ND	ND	ND	30900	42800	
02/02/01	330.18	6.99	0.00	323.19	0.09	ND	--	ND	ND	ND	ND	5380	6430	
05/16/01	--	--	--	--	--	--	--	--	--	--	--	--	--	
08/24/01	330.18	7.72	0.00	322.46	--	ND<50	--	8.3	ND<0.50	ND<0.50	ND<0.50	10000	6600	
10/11/01	330.17	7.72	0.00	322.45	-0.01	--	--	--	--	--	--	--	--	
02/06/02	330.17	6.43	0.00	323.74	1.29	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	450	420	
07/30/02	330.17	7.45	0.00	322.72	-1.02	--	ND<1000	ND<10	ND<10	ND<10	ND<20	--	2400	
02/17/03	330.17	6.18	0.00	323.99	1.27	--	ND<250	ND<2.5	ND<2.5	ND<2.5	ND<5.0	--	600	
08/18/03	330.17	6.25	0.00	323.92	-0.07	--	3900	ND<20	ND<20	ND<20	ND<40	--	2700	
02/24/04	330.17	5.59	0.00	324.58	0.66	--	ND<1000	ND<10	ND<10	ND<10	ND<20	--	1400	
09/17/04	330.17	7.08	0.00	323.09	-1.49	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	14	
03/22/05	330.17	5.29	0.00	324.88	1.79	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	100	
09/29/05	330.17	--	--	--	--	--	--	--	--	--	--	--	--	Dry well
01/09/06	330.17	7.05	0.00	323.12	--	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	2.8	
09/27/06	330.17	8.05	0.00	322.12	-1.00	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	1.4	
03/29/07	330.17	8.38	0.00	321.79	-0.33	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	ND<0.50	
09/21/07	330.17	9.93	0.00	320.24	-1.55	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	1.5	
03/27/08	330.17	6.59	0.00	323.58	3.34	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	ND<0.50	
09/02/08	330.17	7.37	0.00	322.80	-0.78	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	16	

MW-2

(Screen Interval in feet: 4.0-20.0)



Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-2 continued														
03/14/94	330.40	7.23	0.00	323.17	--	ND	--	ND	2.8	1.1	8	--	--	
08/25/94	330.40	8.41	0.00	321.99	-1.18	ND	--	ND	ND	ND	ND	--	--	
09/30/94	330.40	8.73	0.00	321.67	-0.32	--	--	--	--	--	--	--	--	
10/20/94	330.40	8.92	0.00	321.48	-0.19	--	--	--	--	--	--	--	--	
11/18/94	330.40	7.67	0.00	322.73	1.25	ND	--	ND	ND	ND	ND	--	--	
12/20/94	330.40	7.48	0.00	322.92	0.19	--	--	--	--	--	--	--	--	
01/17/95	330.40	6.00	0.00	324.40	1.48	--	--	--	--	--	--	--	--	
02/15/95	330.40	6.16	0.00	324.24	-0.16	ND	--	ND	ND	ND	ND	--	--	
03/13/95	330.40	5.59	0.00	324.81	0.57	--	--	--	--	--	--	--	--	
04/06/95	330.40	5.51	0.00	324.89	0.08	--	--	--	--	--	--	--	--	
05/17/95	330.40	6.15	0.00	324.25	-0.64	ND	--	ND	ND	ND	ND	--	--	
06/15/95	330.40	6.61	0.00	323.79	-0.46	--	--	--	--	--	--	--	--	
08/25/95	330.40	7.45	0.00	322.95	-0.84	ND	--	ND	ND	ND	ND	--	--	
11/28/95	330.40	8.85	0.00	321.55	-1.40	ND	--	ND	ND	ND	ND	--	--	
02/26/96	330.40	5.49	0.00	324.91	3.36	ND	--	ND	ND	ND	ND	--	--	
08/23/96	330.40	7.44	0.00	322.96	-1.95	--	--	--	--	--	--	--	--	SAMPLED ANNUALLY
02/17/97	330.27	5.64	0.00	324.63	1.67	ND	--	ND	ND	ND	ND	ND	--	
08/18/97	330.27	7.40	0.00	322.87	-1.76	--	--	--	--	--	--	--	--	
02/02/98	330.27	5.09	0.00	325.18	2.31	ND	--	ND	ND	ND	ND	62	--	
08/24/98	330.27	6.70	0.00	323.57	-1.61	--	--	--	--	--	--	--	--	
02/10/99	330.27	5.56	0.00	324.71	1.14	ND	--	ND	ND	ND	ND	130	--	
05/21/99	330.30	5.98	0.00	324.32	-0.39	--	--	--	--	--	--	--	--	
08/02/99	330.30	6.72	0.00	323.58	-0.74	ND	--	ND	ND	ND	ND	120	--	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-2 continued														
02/11/00	330.30	6.43	0.00	323.87	0.29	ND	--	ND	ND	ND	ND	39	--	
07/26/00	330.24	7.03	0.00	323.21	-0.66	ND	--	ND	ND	ND	ND	89.9	--	
02/02/01	330.24	6.81	0.00	323.43	0.22	ND	--	ND	ND	ND	ND	20.1	--	
05/16/01	--	--	--	--	--	--	--	--	--	--	--	--	--	
08/24/01	330.24	7.57	0.00	322.67	--	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	36	--	
10/11/01	330.24	7.62	0.00	322.62	-0.05	--	--	--	--	--	--	--	--	
02/06/02	330.24	6.40	0.00	323.84	1.22	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	23	21	
07/30/02	330.24	7.12	0.00	323.12	-0.72	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	11	
02/17/03	330.24	6.17	0.00	324.07	0.95	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	25	
08/18/03	330.24	6.36	0.00	323.88	-0.19	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	ND<2	
02/24/04	330.24	5.87	0.00	324.37	0.49	--	ND<100	ND<1.0	ND<1.0	ND<1.0	ND<2.0	--	100	
09/17/04	330.24	7.22	0.00	323.02	-1.35	--	120	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	70	
03/22/05	330.24	5.55	0.00	324.69	1.67	--	110	ND<0.50	1.3	0.68	2.4	--	29	
09/29/05	330.24	8.26	0.00	321.98	-2.71	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	23	
01/09/06	330.24	7.41	0.00	322.83	0.85	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	25	
09/27/06	--	--	--	--	--	--	--	--	--	--	--	--	--	Destroyed on 1/12/06
MW-3 (Screen Interval in feet: 4.0-20.0)														
03/14/94	331.11	7.93	0.00	323.18	--	150	--	ND	ND	ND	ND	--	--	
08/25/94	331.11	9.20	0.00	321.91	-1.27	130	--	ND	ND	ND	ND	--	--	
09/30/94	331.11	9.43	0.00	321.68	-0.23	--	--	--	--	--	--	--	--	
10/20/94	331.11	9.64	0.00	321.47	-0.21	--	--	--	--	--	--	--	--	
11/18/94	331.11	8.39	0.00	322.72	1.25	130	--	ND	ND	ND	ND	--	--	
12/20/94	331.11	8.20	0.00	322.91	0.19	--	--	--	--	--	--	--	--	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-3 continued														
01/17/95	331.11	6.72	0.00	324.39	1.48	--	--	--	--	--	--	--	--	
02/15/95	331.11	6.93	0.00	324.18	-0.21	130	--	ND	ND	ND	ND	--	--	
03/13/95	331.11	6.30	0.00	324.81	0.63	--	--	--	--	--	--	--	--	
04/06/95	331.11	8.20	0.00	322.91	-1.90	--	--	--	--	--	--	--	--	
05/17/95	331.11	6.88	0.00	324.23	1.32	99	--	ND	ND	ND	ND	--	--	
06/15/95	331.11	7.35	0.00	323.76	-0.47	--	--	--	--	--	--	--	--	
08/25/95	331.11	8.20	0.00	322.91	-0.85	ND	--	ND	ND	ND	ND	--	--	
11/28/95	331.11	9.52	0.00	321.59	-1.32	ND	--	ND	ND	ND	ND	--	--	
02/26/96	331.11	6.25	0.00	324.86	3.27	ND	--	ND	ND	ND	ND	--	--	
08/23/96	331.11	7.98	0.00	323.13	-1.73	--	--	--	--	--	--	--	--	SAMPLED ANNUALLY
02/17/97	330.68	6.07	0.00	324.61	1.48	ND	--	ND	ND	ND	ND	68	--	
08/18/97	330.68	7.82	0.00	322.86	-1.75	--	--	--	--	--	--	--	--	
02/02/98	330.68	5.50	0.00	325.18	2.32	ND	--	ND	ND	ND	ND	100	--	
08/24/98	330.68	7.12	0.00	323.56	-1.62	--	--	--	--	--	--	--	--	
02/10/99	330.68	5.80	0.00	324.88	1.32	ND	--	ND	ND	ND	ND	92	--	
05/21/99	330.49	6.16	0.00	324.33	-0.55	--	--	--	--	--	--	--	--	
08/02/99	330.49	6.95	0.00	323.54	-0.79	ND	--	ND	ND	ND	ND	140	--	
02/11/00	330.49	6.71	0.00	323.78	0.24	ND	--	ND	ND	ND	ND	46	--	
07/26/00	330.60	7.35	0.00	323.25	-0.53	ND	--	ND	ND	ND	ND	927	--	
02/02/01	330.60	7.17	0.00	323.43	0.18	ND	--	ND	ND	ND	ND	2240	--	
05/16/01	--	--	--	--	--	--	--	--	--	--	--	--	--	
08/24/01	330.60	7.88	0.00	322.72	--	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	2500	--	
10/11/01	330.59	7.83	0.00	322.76	0.04	--	--	--	--	--	--	--	--	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-3 continued														
02/06/02	330.59	6.73	0.00	323.86	1.10	ND<1000	--	ND<10	ND<10	ND<10	ND<10	4300	3300	
07/30/02	330.59	7.38	0.00	323.21	-0.65	--	ND<2500	ND<25	ND<25	ND<25	ND<50	--	4900	
02/17/03	330.59	6.49	0.00	324.10	0.89	--	ND<2500	ND<25	ND<25	ND<25	ND<50	--	4400	
08/18/03	330.59	6.70	0.00	323.89	-0.21	--	4400	ND<20	ND<20	ND<20	ND<40	--	3300	
02/24/04	330.59	6.11	0.00	324.48	0.59	--	ND<2500	ND<25	ND<25	ND<25	ND<50	--	3000	
09/17/04	330.59	7.61	0.00	322.98	-1.50	--	ND<1300	ND<13	ND<13	ND<13	ND<25	--	2300	
03/22/05	330.59	5.79	0.00	324.80	1.82	--	ND<1300	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	1600	
09/29/05	330.59	9.24	0.00	321.35	-3.45	--	680	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	1600	
01/09/06	330.59	7.74	0.00	322.85	1.50	--	410	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	1200	
09/27/06	330.59	8.54	0.00	322.05	-0.80	--	780	ND<5.0	ND<5.0	ND<5.0	ND<5.0	--	1500	
03/29/07	330.59	8.82	0.00	321.77	-0.28	--	230	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	230	
09/21/07	330.59	9.38	0.00	321.21	-0.56	--	140	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	160	
03/27/08	330.59	7.08	0.00	323.51	2.30	--	84	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	98	
09/02/08	330.59	7.84	0.00	322.75	-0.76	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	50	
MW-4 (Screen Interval in feet: 4.0-19.0)														
05/21/99	330.36	6.43	0.00	323.93	--	ND	--	ND	ND	ND	ND	960	910	
08/02/99	330.36	7.34	0.00	323.02	-0.91	ND	--	10	ND	13	11	ND	--	
02/11/00	330.36	6.92	0.00	323.44	0.42	ND	--	ND	ND	ND	ND	2700	--	
07/26/00	330.35	7.68	0.00	322.67	-0.77	ND	--	ND	ND	ND	ND	3710	--	
02/02/01	330.35	7.40	0.00	322.95	0.28	ND	--	ND	ND	ND	ND	5340	--	
08/24/01	330.35	8.14	0.00	322.21	-0.74	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	7800	--	
10/11/01	330.35	8.29	0.00	322.06	-0.15	--	--	--	--	--	--	--	--	
02/06/02	330.35	7.28	0.00	323.07	1.01	ND<100	--	ND<1.0	ND<1.0	ND<1.0	ND<1.0	2300	3100	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-4 continued														
07/30/02	330.35	7.76	0.00	322.59	-0.48	--	ND<500	ND<5.0	ND<5.0	5.8	ND<10	--	1600	
02/17/03	330.35	6.85	0.00	323.50	0.91	--	ND<1000	ND<10	ND<10	ND<10	ND<20	--	2200	
08/18/03	330.35	7.30	0.00	323.05	-0.45	--	2000	ND<10	ND<10	ND<10	ND<20	--	1400	
02/24/04	330.35	6.55	0.00	323.80	0.75	--	ND<2000	ND<20	ND<20	ND<20	ND<40	--	2000	
09/17/04	330.35	8.00	0.00	322.35	-1.45	--	340	ND<2.5	ND<2.5	ND<2.5	ND<5.0	--	610	
03/22/05	330.35	6.37	0.00	323.98	1.63	--	ND<200	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	290	
09/29/05	330.35	9.43	0.00	320.92	-3.06	--	84	ND<0.50	ND<0.50	0.53	ND<1.0	--	57	
01/09/06	330.35	7.97	0.00	322.38	1.46	--	100	ND<0.50	ND<0.50	1.5	ND<1.0	--	150	
09/27/06	--	--	--	--	--	--	--	--	--	--	--	--	--	Destroyed on 1/12/06
MW-5 (Screen Interval in feet: 4.0-19.0)														
05/21/99	330.20	5.99	0.00	324.21	--	ND	--	ND	ND	ND	ND	32	33	
08/02/99	330.20	6.83	0.00	323.37	-0.84	ND	--	ND	ND	ND	ND	230	--	
02/11/00	330.20	6.34	0.00	323.86	0.49	ND	--	ND	ND	ND	ND	98	--	
07/26/00	330.20	7.06	0.00	323.14	-0.72	ND	--	ND	ND	ND	ND	25.9	--	
02/02/01	330.20	6.81	0.00	323.39	0.25	ND	--	ND	ND	ND	ND	18	--	
08/24/01	330.20	7.60	0.00	322.60	-0.79	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	18	--	
10/11/01	330.18	7.34	0.00	322.84	0.24	--	--	--	--	--	--	--	--	
02/06/02	330.18	6.55	0.00	323.63	0.79	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	7.7	7.9	
07/30/02	330.18	7.15	0.00	323.03	-0.60	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	4.6	
02/17/03	330.18	6.27	0.00	323.91	0.88	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	2.8	
08/18/03	330.18	6.57	0.00	323.61	-0.30	--	75	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	3.8	
02/24/04	330.18	5.88	0.00	324.30	0.69	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	3.3	
09/17/04	330.18	7.41	0.00	322.77	-1.53	--	ND<50	ND<0.50	ND<0.50	ND<0.50	1.4	--	6.0	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-5 continued														
03/22/05	330.18	5.58	0.00	324.60	1.83	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	5.8	
09/29/05	330.18	9.42	0.00	320.76	-3.84	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	7.8	
01/09/06	330.18	7.93	0.00	322.25	1.49	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	14	
09/27/06	330.18	8.60	0.00	321.58	-0.67	--	300	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	860	
03/29/07	330.18	8.82	0.00	321.36	-0.22	--	520	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	690	
09/21/07	330.18	9.66	0.00	320.52	-0.84	--	300	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	490	
03/27/08	330.18	7.12	0.00	323.06	2.54	--	580	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	1400	
09/02/08	330.18	7.70	0.00	322.48	-0.58	--	360	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	840	
MW-6 (Screen Interval in feet: 4.0-19.0)														
05/21/99	330.49	6.24	0.00	324.25	--	ND	--	ND	ND	ND	ND	2200	2300	
08/02/99	330.49	7.10	0.00	323.39	-0.86	ND	--	ND	ND	ND	ND	ND	--	
02/11/00	330.49	6.60	0.00	323.89	0.50	ND	--	ND	ND	ND	ND	2500	--	
07/26/00	330.49	7.31	0.00	323.18	-0.71	ND	--	ND	ND	ND	ND	4280	--	
02/02/01	330.49	7.02	0.00	323.47	0.29	ND	--	ND	ND	ND	ND	1990	--	
08/24/01	330.49	7.84	0.00	322.65	-0.82	ND<200	--	ND<2.0	ND<2.0	ND<2.0	ND<2.0	1100	--	
10/11/01	330.47	8.03	0.00	322.44	-0.21	--	--	--	--	--	--	--	--	
02/06/02	330.47	6.78	0.00	323.69	1.25	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	610	680	
07/30/02	330.47	7.40	0.00	323.07	-0.62	--	180	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	160	
02/17/03	330.47	6.49	0.00	323.98	0.91	--	ND<250	ND<2.5	ND<2.5	ND<2.5	ND<5.0	--	400	
08/18/03	330.47	6.81	0.00	323.66	-0.32	--	320	ND<1.0	ND<1.0	ND<1.0	ND<2.0	--	280	
02/24/04	330.47	6.11	0.00	324.36	0.70	--	130	ND<1.0	ND<1.0	ND<1.0	ND<2.0	--	200	
09/17/04	330.47	7.64	0.00	322.83	-1.53	--	110	ND<1.0	ND<1.0	ND<1.0	ND<2.0	--	200	
03/22/05	330.47	5.81	0.00	324.66	1.83	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	83	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-6 continued														
09/29/05	330.47	9.19	0.00	321.28	-3.38	--	110	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	140	
01/09/06	330.47	7.65	0.00	322.82	1.54	--	100	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	160	
09/27/06	--	--	--	--	--	--	--	--	--	--	--	--	--	Destroyed on 1/12/06
MW-7 (Screen Interval in feet: 4.0-19.0)														
05/21/99	330.43	6.13	0.00	324.30	--	ND	--	ND	ND	ND	ND	22	22	
08/02/99	330.43	6.92	0.00	323.51	-0.79	ND	--	ND	ND	ND	ND	31	--	
02/11/00	330.43	6.50	0.00	323.93	0.42	ND	--	ND	ND	ND	ND	20	--	
07/26/00	330.43	7.18	0.00	323.25	-0.68	ND	--	ND	ND	ND	ND	17.9	--	
02/02/01	330.43	6.95	0.00	323.48	0.23	ND	--	ND	ND	ND	ND	ND	--	
08/24/01	330.43	7.72	0.00	322.71	-0.77	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	4.4	--	
10/11/01	330.41	7.87	0.00	322.54	-0.17	--	--	--	--	--	--	--	--	
02/06/02	330.41	6.62	0.00	323.79	1.25	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	3.9	3.2	
07/30/02	330.41	--	0.00	--	--	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	4.3	
02/17/03	330.41	--	0.00	--	--	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	4.7	
08/18/03	330.41	6.64	0.00	323.77	--	--	76	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	6.3	
02/24/04	330.41	6.01	0.00	324.40	0.63	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	6.2	
09/17/04	330.41	7.45	0.00	322.96	-1.44	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	8.7	
03/22/05	330.41	5.73	0.00	324.68	1.72	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	9.4	
09/29/05	330.41	8.94	0.00	321.47	-3.21	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	11	
01/09/06	330.41	7.43	0.00	322.98	1.51	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	7.6	
09/27/06	--	--	--	--	--	--	--	--	--	--	--	--	--	Destroyed on 1/12/06
MW-8 (Screen Interval in feet: --)														
10/11/01	329.97	7.57	0.00	322.40	--	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<2.5	ND<2.0	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
March 1994 Through September 2008
76 Station 6419

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8021B) (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-8 continued														
02/06/02	329.97	6.35	0.00	323.62	1.22	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<2.5	ND<1.0	
07/30/02	329.97	6.95	0.00	323.02	-0.60	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	ND<2.0	
02/17/03	329.97	6.11	0.00	323.86	0.84	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	ND<2.0	
08/18/03	329.97	6.33	0.00	323.64	-0.22	--	53	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	ND<2	
02/24/04	329.97	13.37	0.00	316.60	-7.04	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	ND<2.0	
09/17/04	329.97	7.23	0.00	322.74	6.14	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	4.0	
03/22/05	329.97	--	--	--	--	--	--	--	--	--	--	--	--	Abandoned
MW-9 (Screen Interval in feet: --)														
10/11/01	329.51	7.12	0.00	322.39	--	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	22	15	
02/06/02	329.51	5.94	0.00	323.57	1.18	ND<50	--	ND<0.50	ND<0.50	ND<0.50	ND<0.50	19	14	
07/30/02	329.51	6.53	0.00	322.98	-0.59	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	9	
02/17/03	329.51	5.63	0.00	323.88	0.90	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	4.9	
08/18/03	329.51	5.99	0.00	323.52	-0.36	--	57	ND<0.50	ND<0.50	ND<0.50	ND<1	--	6.2	
02/24/04	329.51	5.27	0.00	324.24	0.72	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	5.6	
09/17/04	329.51	6.80	0.00	322.71	-1.53	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	--	4.8	
03/22/05	329.51	--	--	--	--	--	--	--	--	--	--	--	--	Abandoned

Table 2 a
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6419

Date Sampled	Ethylene-dibromide								Cadmium (dissolved) (mg/l)	Chromium (total) (mg/l)	Lead (total) (mg/l)	Nickel (total) (mg/l)
	TPH-D (µg/l)	TBA (µg/l)	Ethanol (8260B) (µg/l)	(EDB) (µg/l)	1,2-DCA (EDC) (µg/l)	DIPE (µg/l)	ETBE (µg/l)	TAME (µg/l)				
MW-1												
03/14/94	810	--	--	--	--	--	--	--	ND	0.000012	ND	0.00003
08/25/94	910	--	--	--	--	--	--	--	ND	ND	0.024	ND
11/18/94	910	--	--	--	--	--	--	--	ND	0.067	ND	0.067
02/15/95	660	--	--	--	--	--	--	--	ND	ND	ND	ND
05/17/95	200	--	--	--	--	--	--	--	ND	ND	ND	0.021
07/26/00	--	ND	--	ND	ND	ND	ND	ND	--	--	--	--
08/24/01	--	ND<1000	ND<25000	ND<100	ND<100	ND<100	ND<100	ND<100	--	--	--	--
02/06/02	--	ND<100	ND<2500	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<5.0	--	--	--	--
07/30/02	--	ND<2000	ND<10000	ND<40	ND<40	ND<40	ND<40	ND<40	--	--	--	--
02/17/03	--	ND<500	ND<2500	ND<10	ND<10	ND<10	ND<10	ND<10	--	--	--	--
08/18/03	--	ND<4000	ND<20000	ND<80	ND<80	ND<80	ND<80	ND<80	--	--	--	--
02/24/04	--	ND<2000	ND<10000	ND<40	ND<40	ND<40	ND<40	ND<40	--	--	--	--
09/17/04	--	470	ND<50	ND<0.5	ND<0.5	ND<1.0	ND<0.5	ND<0.5	--	--	--	--
03/22/05	--	ND<5.0	ND<50	ND<0.50	ND<0.5	ND<0.5	ND<0.5	ND<0.5	--	--	--	--
01/09/06	--	ND<10	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	--	--	--	--
09/27/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
03/29/07	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/21/07	--	--	ND<250	--	--	--	--	--	--	--	--	--
03/27/08	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/02/08	--	--	ND<250	--	--	--	--	--	--	--	--	--
MW-2												
02/06/02	--	ND<20	ND<500	ND<1.0	ND<1.0	ND<1.0	ND<1.0	ND<1.0	--	--	--	--
08/18/03	--	--	ND<500	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<1000	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<50	--	--	--	--	--	--	--	--	--

Table 2 a
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6419

Date Sampled	TPH-D (µg/l)	TBA (µg/l)	Ethanol (8260B) (µg/l)	Ethylene- dibromide (EDB) (µg/l)	1,2-DCA (EDC) (µg/l)	DIPE (µg/l)	ETBE (µg/l)	TAME (µg/l)	Cadmium (dissolved) (mg/l)	Chromium (total) (mg/l)	Lead (total) (mg/l)	Nickel (total) (mg/l)
MW-2 continued												
03/22/05	--	--	ND<50	--	--	--	--	--	--	--	--	--
09/29/05	--	--	ND<250	--	--	--	--	--	--	--	--	--
01/09/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
MW-3												
02/06/02	--	ND<670	ND<17000	ND<33	ND<33	ND<33	ND<33	ND<33	--	--	--	--
08/18/03	--	--	ND<20000	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<25000	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<1300	--	--	--	--	--	--	--	--	--
03/22/05	--	--	ND<1300	--	--	--	--	--	--	--	--	--
09/29/05	--	--	ND<250	--	--	--	--	--	--	--	--	--
01/09/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/27/06	--	--	ND<2500	--	--	--	--	--	--	--	--	--
03/29/07	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/21/07	--	--	ND<250	--	--	--	--	--	--	--	--	--
03/27/08	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/02/08	--	--	ND<250	--	--	--	--	--	--	--	--	--
MW-4												
02/06/02	--	ND<500	ND<12000	ND<25	ND<25	ND<25	ND<25	ND<25	--	--	--	--
08/18/03	--	--	ND<10000	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<20000	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<250	--	--	--	--	--	--	--	--	--
03/22/05	--	--	ND<200	--	--	--	--	--	--	--	--	--
09/29/05	--	--	ND<250	--	--	--	--	--	--	--	--	--
01/09/06	--	--	ND<250	--	--	--	--	--	--	--	--	--

Table 2 a
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6419

Date Sampled									Cadmium (dissolved) (mg/l)	Chromium (total) (mg/l)	Lead (total) (mg/l)	Nickel (total) (mg/l)
	TPH-D (µg/l)	TBA (µg/l)	Ethanol (8260B) (µg/l)	Ethylene- dibromide (EDB) (µg/l)	1,2-DCA (EDC) (µg/l)	DIPE (µg/l)	ETBE (µg/l)	TAME (µg/l)				
MW-5												
02/06/02	--	ND<20	ND<500	ND<1.0	ND<1.0	ND<1.0	ND<1.0	ND<1.0	--	--	--	--
08/18/03	--	--	ND<500	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<500	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<50	--	--	--	--	--	--	--	--	--
03/22/05	--	--	ND<50	--	--	--	--	--	--	--	--	--
09/29/05	--	--	ND<250	--	--	--	--	--	--	--	--	--
01/09/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/27/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
03/29/07	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/21/07	--	--	ND<250	--	--	--	--	--	--	--	--	--
03/27/08	--	--	ND<250	--	--	--	--	--	--	--	--	--
09/02/08	--	--	ND<250	--	--	--	--	--	--	--	--	--
MW-6												
05/21/99	--	ND<170	--	--	--	ND<8.3	ND<8.3	ND<8.3	--	--	--	--
02/06/02	--	ND<170	ND<4200	ND<8.3	ND<8.3	ND<8.3	ND<8.3	ND<8.3	--	--	--	--
08/18/03	--	--	ND<1000	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<1000	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<100	--	--	--	--	--	--	--	--	--
03/22/05	--	--	ND<50	--	--	--	--	--	--	--	--	--
09/29/05	--	--	ND<250	--	--	--	--	--	--	--	--	--
01/09/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
MW-7												
02/06/02	--	ND<20	ND<500	ND<1.0	ND<1.0	1.4	ND<1.0	ND<1.0	--	--	--	--
08/18/03	--	--	ND<500	--	--	--	--	--	--	--	--	--

Table 2 a
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6419

Date Sampled			Ethylene-						Cadmium	Chromium	Lead	Nickel
	TPH-D (µg/l)	TBA (µg/l)	Ethanol (8260B) (µg/l)	dibromide (EDB) (µg/l)	1,2-DCA (EDC) (µg/l)	DIPE (µg/l)	ETBE (µg/l)	TAME (µg/l)	(dissolved) (mg/l)	(total) (mg/l)	(total) (mg/l)	(total) (mg/l)
MW-7 continued												
02/24/04	--	--	ND<500	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<50	--	--	--	--	--	--	--	--	--
03/22/05	--	--	ND<50	--	--	--	--	--	--	--	--	--
09/29/05	--	--	ND<250	--	--	--	--	--	--	--	--	--
01/09/06	--	--	ND<250	--	--	--	--	--	--	--	--	--
MW-8												
10/11/01	--	ND<20	ND<500	ND<2.0	ND<2.0	ND<2.0	ND<2.0	ND<2.0	--	--	--	--
02/06/02	--	ND<20	ND<500	ND<1.0	ND<1.0	ND<1.0	ND<1.0	ND<1.0	--	--	--	--
08/18/03	--	--	ND<500	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<500	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<50	--	--	--	--	--	--	--	--	--
MW-9												
10/11/01	--	ND<20	ND<500	ND<2.0	ND<2.0	ND<2.0	ND<2.0	ND<2.0	--	--	--	--
02/06/02	--	ND<20	ND<500	ND<1.0	ND<1.0	ND<1.0	ND<1.0	ND<1.0	--	--	--	--
08/18/03	--	--	ND<500	--	--	--	--	--	--	--	--	--
02/24/04	--	--	ND<500	--	--	--	--	--	--	--	--	--
09/17/04	--	--	ND<50	--	--	--	--	--	--	--	--	--

Table 2 b
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6419


Date Sampled	Zinc (total) (mg/l)	Post-purge Dissolved Oxygen (mg/l)	Pre-purge Dissolved Oxygen (mg/l)
MW-1			
03/14/94	0.039	--	--
02/15/95	--	4.3	--
05/17/95	--	1.2	--
08/25/95	--	2.71	--
11/28/95	--	3.25	--
02/26/96	--	1.41	5.23
08/23/96	--	--	3.83
02/17/97	--	0.78	0.82
08/18/97	--	2.35	1.28
05/16/01	--	--	1.54
08/24/01	--	3.1	--
MW-2			
02/15/95	--	1.9	--
02/26/96	--	0.43	0.62
08/23/96	--	--	2.04
02/17/97	--	0.82	0.9
08/18/97	--	--	1.16
05/16/01	--	--	1.47
08/24/01	--	2.6	--
MW-3			
02/15/95	--	2.6	--
03/13/95	--	1.13	--
08/25/95	--	1.86	--
11/28/95	--	6.81	--

Table 2 b
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6419

Date Sampled	Zinc (total) (mg/l)	Post-purge Dissolved Oxygen (mg/l)	Pre-purge Dissolved Oxygen (mg/l)
MW-3 continued			
02/26/96	--	1.11	16.83
08/23/96	--	--	3.29
02/17/97	--	0.8	0.8
08/18/97	--	--	1.43
05/16/01	--	2.6	1.65
08/24/01	--	2.60	--
MW-4			
08/24/01	--	2.3	--
MW-5			
08/24/01	--	2.1	--
MW-6			
08/24/01	--	2.7	--
MW-7			
08/24/01	--	2.7	--


FIGURES

PS=1:1 L:\QMS VICINITY MAP SD6419.mxd Nov 16, 2007 - 8:15am cuong



SOURCE:

United States Geological Survey
7.5 Minute Topographic Map:
Dublin Quadrangle



SCALE 1:24,000



PROJECT: 154771


FACILITY:


76 STATION 6419
6401 DUBLIN BOULEVARD
DUBLIN, CALIFORNIA

VICINITY MAP


FIGURE 1

LEGEND

MW-5  Monitoring Well with Groundwater Elevation (feet)


MW-9  Abandoned Monitoring Well

322.80  Groundwater Elevation Contour

 General Direction of Groundwater Flow



L:\Graphics\GMS NORTH-SOUTH\6000\6419+ \6419-GMS.dwg Sep 17, 2008 - 9:51am bschmidt



DUBLIN BOULEVARD

DOUGHERTY ROAD

NOTES:

Contour lines are interpretive and based on fluid levels measured in monitoring wells. Elevations are in feet above mean sea level. UST = underground storage tank.

SCALE (FEET)



PROJECT: 154771




FACILITY:
76 STATION 6419
6401 DUBLIN BOULEVARD
DUBLIN, CALIFORNIA


**GROUNDWATER ELEVATION
CONTOUR MAP
September 2, 2008**

FIGURE 2

MS-1.30 6419-003

LEGEND

- MW-5  Monitoring Well with Dissolved-Phase TPH-G (GC/MS) Concentration (µg/l)
- MW-9  Abandoned Monitoring Well
-  100 Dissolved-Phase TPH-G (GC/MS) Contour (µg/l)



NOTES:

Contour lines are interpretive and based on laboratory analysis results of groundwater samples. TPH-G (GC/MS) = total petroleum hydrocarbons with gasoline distinction utilizing EPA Method 8260B. µg/l = micrograms per liter. ND = not detected at limit indicated on official laboratory report. UST = underground storage tank.

SCALE (FEET)



L:\Graphics\QMS NORTH-SOUTH\6000\6419+ \6419-QMS.dwg Sep 17, 2008 - 9:44am bschmidt

MS-1:30 6419-003




PROJECT: 154771
 FACILITY:
 76 STATION 6419
 6401 DUBLIN BOULEVARD
 DUBLIN, CALIFORNIA


**DISSOLVED-PHASE TPH-G (GC/MS)
 CONCENTRATION MAP
 September 2, 2008**

FIGURE 3

LEGEND

MW-5  Monitoring Well with Dissolved-Phase Benzene Concentration ($\mu\text{g/l}$)


MW-9  Abandoned Monitoring Well



L: \Graphics\QMS NORTH-SOUTH\6000\6419+\6419-QMS.dwg Sep 17, 2008 - 9:45am bschmidt

NOTES:

$\mu\text{g/l}$ = micrograms per liter. ND = not detected at limit indicated on official laboratory report.
UST = underground storage tank.




MS-1:30 6419-003



PROJECT: 154771
FACILITY:
76 STATION 6419
6401 DUBLIN BOULEVARD
DUBLIN, CALIFORNIA


**DISSOLVED-PHASE BENZENE
CONCENTRATION MAP**
September 2, 2008
FIGURE 4

LEGEND

MW-5  Monitoring Well with Dissolved-Phase MTBE Concentration ($\mu\text{g/l}$)

MW-9  Abandoned Monitoring Well


 Dissolved-Phase MTBE Contour ($\mu\text{g/l}$)



NOTES:

Contour lines are interpretive and based on laboratory analysis results of groundwater samples. MTBE = methyl tertiary butyl ether. $\mu\text{g/l}$ = micrograms per liter. UST = underground storage tank. Results obtained using EPA Method 8260B.

SCALE (FEET)



L:\Graphics\GMS NORTH-SOUTH\6000\6419+ \6419-GMS.dwg Sep 17, 2008 - 9:49am bschmidt

MS-1:30 6419-003



PROJECT: 154771


FACILITY:
76 STATION 6419
6401 DUBLIN BOULEVARD
DUBLIN, CALIFORNIA

**DISSOLVED-PHASE MTBE
CONCENTRATION MAP**
September 2, 2008

FIGURE 5


GRAPHS

Groundwater Elevations vs. Time
76 Station 6419




Elevations may have been corrected for apparent changes due to resurvey

Groundwater Elevations vs. Time
76 Station 6419











Elevations may have been corrected for apparent changes due to resurvey

Groundwater Elevations vs. Time
76 Station 6419




Elevations may have been corrected for apparent changes due to resurvey

Benzene Concentrations vs Time 76 Station 6419



Benzene Concentrations vs Time
76 Station 6419



GENERAL FIELD PROCEDURES

Groundwater Monitoring and Sampling Assignments

For each site, TRC technicians are provided with a Technical Service Request (TSR) that specifies activities required to complete the groundwater monitoring and sampling assignment for the site. TSRs are based on client directives, instructions from the primary environmental consultant for the site, regulatory requirements, and TRC's previous experience with the site.

Fluid Level Measurements

Initial site activities include determination of well locations based on a site map provided with the TSR. Well boxes are opened and caps are removed. Indications of well or well box damage or of pressure buildup in the well are noted.

Fluid levels in each well are measured using a coated cloth tape equipped with an electronic interface probe, which distinguishes between liquid phase hydrocarbon (LPH) and water. The depth to LPH (if it is present), to water, and to the bottom of the well are measured from the top of the well casing (surveyors mark or notch if present) to the nearest 0.01 foot. Unless otherwise instructed, a well with less than 0.67 foot between the measured top of water and the measured bottom of the well casing is considered dry, and is not sampled. If the well contains 0.67 foot or more of water, an attempt is made to bail and/or sample as specified on the TSR.

Wells that are found to contain LPH are not purged or sampled. Instead, one casing volume of fluid is bailed from the well and the well is re-sealed. Bailed fluids are placed in a container separate from normal purge water, and properly disposed.

Purging and Groundwater Parameter Measurement

TSR instructions may specify that a well not be purged (no-purge sampling), be purged using low-flow methods, or be purged using conventional pump and/or bail methods. Conventional purging generally consists of pumping or bailing until a minimum of three casing volumes of water have been removed or until the well has been pumped dry. Pumping is generally accomplished using submersible electric or pneumatic diaphragm pumps.

During conventional purging, three groundwater parameters (temperature, pH, and conductivity) are measured after removal of each casing volume. Stabilization of these parameters, to within 10 percent, confirm that sufficient purging has been completed. In some cases, the TSR indicates that other parameters are also to be measured during purging. TRC commonly measures dissolved oxygen (DO), oxidation-reduction potential (ORP), and/or turbidity. Instruments used for groundwater parameter measurements are calibrated daily according to manufacturer's instructions.

Low-flow purging utilizes a bladder or peristaltic pump to remove water from the well at a low rate. Groundwater parameters specified by the TSR are measured continuously until they become stable in general accordance with EPA guidelines.

Purge water is generally collected in labeled drums for disposal. Drums may be left on site for disposal by others, or transported to a collection location for eventual transfer to a licensed treatment or recycling facility. In some cases, purge water may be collected directly from the site by a licensed vacuum truck company, or may be treated on site by an active remediation system, if so directed.

Groundwater Sample Collection

After wells are purged, or not purged, according to TSR instructions, samples are collected for laboratory analysis. For wells that have been purged using conventional pump or bail methods, sampling is conducted after the well has recovered to 80 percent of its original volume or after two hours if the well does not recover to at least 80 percent. If there is insufficient recharge of water in the well after two hours, the well is not sampled.

Samples are collected by lowering a new, disposable, ½-inch to 4-inch polyethylene bottom-fill bailer to just below the water level in the well. The bailer is retrieved and the water sample is carefully transferred to containers specified for the laboratory analytical methods indicated by the TSR. Particular care is given to containers for volatile organic analysis (VOAs) which require filling to zero headspace and fitting with Teflon-sealed caps.

After filling, all containers are labeled with project number (or site number), well designation, sample date, sample time, and the sampler's initials, and placed in an insulated chest with ice. Samples remain chilled prior to and during transport to a state-certified laboratory for analysis. Sample container descriptions and requested analyses are entered onto a chain-of-custody form in order to provide instructions to the laboratory. The chain-of-custody form accompanies the samples during transportation to provide a continuous record of possession from the field to the laboratory. If a freight or overnight carrier transports the samples, the carrier is noted on the form.

For wells that have been purged using low-flow methods, sample containers are filled from the effluent stream of the bladder or peristaltic pump. In some cases, if so specified by the TSR, samples are taken from the sample ports of actively pumping remediation wells.

Sequence of Gauging, Purging and Sampling

The sequence in which monitoring activities are conducted is specified on the TSR. In general, wells are gauged beginning with the least affected well and ending with the well that has the highest concentration based on previous analytic results. After all gauging for the site is completed, wells are purged and/or sampled from the least-affected to the most-affected well.

Decontamination

In order to reduce the possibility of cross contamination between wells, strict isolation and decontamination procedures are observed. Portable pumps are not used in wells with LPH. Technicians wear nitrile gloves during all gauging, purging, and sampling activities. Gloves are changed between wells and more often if warranted. Any equipment that could come in contact with fluids are either dedicated a particular well, decontaminated prior to each use, or discarded after a single use. Decontamination consists of washing in a solution of Liqui-nox and water and rinsing twice. The final rinse is in deionized water.

Exceptions

Additional tasks or non-standard procedures, if any, that may be requested or required for a particular site, and noted on the site TSR, are documented in field notes on the following pages.

FIELD MONITORING DATA SHEET

Technician: Andrew Vidrers

Job #/Task #: 154711/FM20

Date: ^{4v} ~~04/01~~ 04/02/08

Site # 6419

Project Manager A. Collins

Page 1 of 1

Well #	TOC	Time Gauged	Total Depth	Depth to Water	Depth to Product	Product Thickness (feet)	Time Sampled	Misc. Well Notes
MW-1	✓	0528	9.28	7.37	—	—	0600	2"
MW-3	✓	0532	10.43	7.84	—	—	0621	2"
MW-5	✓	0537	14.32	7.70	—	—	0638	2"

FIELD DATA COMPLETE QA/QC COC WELL BOX CONDITION SHEETS

MANIFEST DRUM INVENTORY TRAFFIC CONTROL



GROUNDWATER SAMPLING FIELD NOTES

Technician: Andrew Valors

Site: 6A19

Project No.: 154771

Date: 09/02/08

Well No. MW-1

Purge Method: HB

Depth to Water (feet): 7.37

Depth to Product (feet):

Total Depth (feet): 9.28

LPH & Water Recovered (gallons):

Water Column (feet): 1.91

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 7.75

1 Well Volume (gallons): 1

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (uS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
0540			1	1531	21.7	6.76			
			2	1513	23.0	6.65			
	0551		3	1523	23.3	6.74			
Static at Time Sampled			Total Gallons Purged			Sample Time			
7.71			3			0600			
Comments:									

Well No. MW-3

Purge Method: Sub

Depth to Water (feet): 7.84

Depth to Product (feet):

Total Depth (feet): 18.43

LPH & Water Recovered (gallons):

Water Column (feet): 10.59

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 9.96

1 Well Volume (gallons): 2

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (uS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
0611			2	3049	21.4	7.06			
			4	2993	21.9	6.94			
	0615		6	2951	21.8	6.88			
Static at Time Sampled			Total Gallons Purged			Sample Time			
9.96			6			0621			
Comments:									



GROUNDWATER SAMPLING FIELD NOTES

Technician: Andrew Vidners

Site: 6A19

Project No.: 154771

Date: 09/02/08

Well No. AW-5

Purge Method: Sub

Depth to Water (feet): 7.70

Depth to Product (feet): _____

Total Depth (feet): 14.32

LPH & Water Recovered (gallons):

Water Column (feet): 11.62

Casing Diameter (Inches): 2

80% Recharge Depth(feet): 10.02

1 Well Volume (gallons): 2

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (uS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
0629			2	2806	18.9	7.07			
			4	2363	20.4	6.98			
	0633		6	2605	20.4	6.92			
Static at Time Sampled			Total Gallons Purged		Sample Time				
9.62			6		0638				
Comments:									

Well No. _____

Purge Method: _____

Depth to Water (feet): _____

Depth to Product (feet): _____

Total Depth (feet): _____

LPH & Water Recovered (gallons): _____

Water Column (feet): _____

Casing Diameter (Inches): _____

80% Recharge Depth(feet): _____

1 Well Volume (gallons): _____

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (uS/cm)	Temperature (F, C)	pH	D.O. (mg/L)	ORP	Turbidity
Static at Time Sampled			Total Gallons Purged		Sample Time				
Comments:									





Laboratories, Inc.

Environmental Testing Laboratory Since 1949

Date of Report: 09/10/2008

Anju Farfan

TRC

21 Technology Drive
Irvine, CA 92618

RE: 6419

BC Work Order: 0811617

Enclosed are the results of analyses for samples received by the laboratory on 9/3/2008. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Contact Person: Molly Meyers
Client Service Rep

Authorized Signature

TRC
21 Technology Drive
Irvine, CA 92618

Project: 6419
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Information					
0811617-01	COC Number:	---		Receive Date:	09/03/2008 23:00	Delivery Work Order:
	Project Number:	6419		Sampling Date:	09/02/2008 06:00	Global ID: T0600101443
	Sampling Location:	MW-1		Sample Depth:	---	Matrix: W
	Sampling Point:	MW-1		Sample Matrix:	Water	Sample QC Type (SACode): CS
	Sampled By:	TRCI				Cooler ID:
0811617-02	COC Number:	---		Receive Date:	09/03/2008 23:00	Delivery Work Order:
	Project Number:	6419		Sampling Date:	09/02/2008 06:21	Global ID: T0600101443
	Sampling Location:	MW-3		Sample Depth:	---	Matrix: W
	Sampling Point:	MW-3		Sample Matrix:	Water	Sample QC Type (SACode): CS
	Sampled By:	TRCI				Cooler ID:
0811617-03	COC Number:	---		Receive Date:	09/03/2008 23:00	Delivery Work Order:
	Project Number:	6419		Sampling Date:	09/02/2008 06:38	Global ID: T0600101443
	Sampling Location:	MW-5		Sample Depth:	---	Matrix: W
	Sampling Point:	MW-5		Sample Matrix:	Water	Sample QC Type (SACode): CS
	Sampled By:	TRCI				Cooler ID:

TRC
21 Technology Drive
Irvine, CA 92618

Project: 6419
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 0811617-01		Client Sample Name: 6419, MW-1, MW-1, 9/2/2008 6:00:00AM											
Constituent	Result	Units	PQL	MDL	Method	Prep Date	Run Date/Time	Analyst	Instru-ment ID	Dilution	QC Batch ID	MB Bias	Lab Quals
Benzene	ND	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
Ethylbenzene	ND	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
Methyl t-butyl ether	16	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
Toluene	ND	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
Total Xylenes	ND	ug/L	1.0		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
Ethanol	ND	ug/L	250		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
Total Purgeable Petroleum Hydrocarbons	ND	ug/L	50		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009	ND	
1,2-Dichloroethane-d4 (Surrogate)	109	%	76 - 114 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009		
Toluene-d8 (Surrogate)	94.8	%	88 - 110 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009		
4-Bromofluorobenzene (Surrogate)	103	%	86 - 115 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 11:36	mwb	MS-V13	1	BRI0009		

TRC 21 Technology Drive Irvine, CA 92618	Project: 6419 Project Number: [none] Project Manager: Anju Farfan	Reported: 09/10/2008 12:30
------------------------------------------------	-------------------------------------------------------------------------	----------------------------

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID:	Client Sample Name: 6419, MW-3, MW-3, 9/2/2008 6:21:00AM												
Constituent	Result	Units	PQL	MDL	Method	Prep Date	Run Date/Time	Analyst	Instru- ment ID	Dilution	QC Batch ID	MB Bias	Lab Quals
Benzene	ND	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
Ethylbenzene	ND	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
Methyl t-butyl ether	50	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
Toluene	ND	ug/L	0.50		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
Total Xylenes	ND	ug/L	1.0		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
Ethanol	ND	ug/L	250		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
Total Purgeable Petroleum Hydrocarbons	ND	ug/L	50		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009	ND	
1,2-Dichloroethane-d4 (Surrogate)	109	%	76 - 114 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009		
Toluene-d8 (Surrogate)	96.3	%	88 - 110 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009		
4-Bromofluorobenzene (Surrogate)	99.2	%	86 - 115 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 11:53	mwb	MS-V13	1	BRI0009		



TRC
21 Technology Drive
Irvine, CA 92618

Project: 6419
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 0811617-03		Client Sample Name: 6419, MW-5, MW-5, 9/2/2008 6:38:00AM											
Constituent	Result	Units	PQL	MDL	Method	Prep Date	Run Date/Time	Analyst	Instru- ment ID	Dilution	QC Batch ID	MB Bias	Lab Quals
Benzene	ND	ug/L	0.50		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009	ND	
Ethylbenzene	ND	ug/L	0.50		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009	ND	
Methyl t-butyl ether	840	ug/L	12		EPA-8260	09/05/08	09/05/08 15:47	mwb	MS-V13	25	BRI0009	ND	A01
Toluene	ND	ug/L	0.50		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009	ND	
Total Xylenes	ND	ug/L	1.0		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009	ND	
Ethanol	ND	ug/L	250		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009	ND	
Total Purgeable Petroleum Hydrocarbons	360	ug/L	50		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009	ND	A90
1,2-Dichloroethane-d4 (Surrogate)	113	%	76 - 114 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 15:47	mwb	MS-V13	25	BRI0009		
1,2-Dichloroethane-d4 (Surrogate)	91.8	%	76 - 114 (LCL - UCL)		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009		
Toluene-d8 (Surrogate)	98.9	%	88 - 110 (LCL - UCL)		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009		
Toluene-d8 (Surrogate)	99.6	%	88 - 110 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 15:47	mwb	MS-V13	25	BRI0009		
4-Bromofluorobenzene (Surrogate)	101	%	86 - 115 (LCL - UCL)		EPA-8260	09/05/08	09/08/08 20:46	mwb	MS-V13	1	BRI0009		
4-Bromofluorobenzene (Surrogate)	99.0	%	86 - 115 (LCL - UCL)		EPA-8260	09/05/08	09/05/08 15:47	mwb	MS-V13	25	BRI0009		

TRC
21 Technology Drive
Irvine, CA 92618

Project: 6419
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Precision & Accuracy

Constituent	Batch ID	QC Sample Type	Source Sample ID	Source Result	Result	Spike Added	Units	RPD	Percent Recovery	Control Limits	
										RPD	Percent Recovery Lab Quals
Benzene	BRI0009	Matrix Spike	0809520-96	0	27.440	25.000	ug/L		110		70 - 130
		Matrix Spike Duplicate	0809520-96	0	26.880	25.000	ug/L	1.8	108	20	70 - 130
Toluene	BRI0009	Matrix Spike	0809520-96	0	28.430	25.000	ug/L		114		70 - 130
		Matrix Spike Duplicate	0809520-96	0	28.190	25.000	ug/L	0.9	113	20	70 - 130
1,2-Dichloroethane-d4 (Surrogate)	BRI0009	Matrix Spike	0809520-96	ND	9.8500	10.000	ug/L		98.5		76 - 114
		Matrix Spike Duplicate	0809520-96	ND	9.8900	10.000	ug/L		98.9		76 - 114
Toluene-d8 (Surrogate)	BRI0009	Matrix Spike	0809520-96	ND	9.7600	10.000	ug/L		97.6		88 - 110
		Matrix Spike Duplicate	0809520-96	ND	9.7800	10.000	ug/L		97.8		88 - 110
4-Bromofluorobenzene (Surrogate)	BRI0009	Matrix Spike	0809520-96	ND	9.5100	10.000	ug/L		95.1		86 - 115
		Matrix Spike Duplicate	0809520-96	ND	9.6500	10.000	ug/L		96.5		86 - 115

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.
All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.
4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com
Certifications: California - ELAP Certification Number 1186; Nevada Administrative Code - NAC-445A

TRC
21 Technology Drive
Irvine, CA 92618

Project: 6419
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Laboratory Control Sample

Constituent	Batch ID	QC Sample ID	QC Type	Result	Spike Level	PQL	Units	Percent Recovery	RPD	Control Limits		Lab Quals
										Percent Recovery	RPD	
Benzene	BRI0009	BRI0009-BS1	LCS	27.500	25.000	0.50	ug/L	110		70 - 130		
Toluene	BRI0009	BRI0009-BS1	LCS	28.270	25.000	0.50	ug/L	113		70 - 130		
1,2-Dichloroethane-d4 (Surrogate)	BRI0009	BRI0009-BS1	LCS	9.8400	10.000		ug/L	98.4		76 - 114		
Toluene-d8 (Surrogate)	BRI0009	BRI0009-BS1	LCS	9.8700	10.000		ug/L	98.7		88 - 110		
4-Bromofluorobenzene (Surrogate)	BRI0009	BRI0009-BS1	LCS	9.4100	10.000		ug/L	94.1		86 - 115		

TRC
 21 Technology Drive
 Irvine, CA 92618

Project: 6419
 Project Number: [none]
 Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Method Blank Analysis

Constituent	Batch ID	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
Benzene	BRI0009	BRI0009-BLK1	ND	ug/L	0.50		
Ethylbenzene	BRI0009	BRI0009-BLK1	ND	ug/L	0.50		
Methyl t-butyl ether	BRI0009	BRI0009-BLK1	ND	ug/L	0.50		
Toluene	BRI0009	BRI0009-BLK1	ND	ug/L	0.50		
Total Xylenes	BRI0009	BRI0009-BLK1	ND	ug/L	1.0		
Ethanol	BRI0009	BRI0009-BLK1	ND	ug/L	250		
Total Purgeable Petroleum Hydrocarbons	BRI0009	BRI0009-BLK1	ND	ug/L	50		
1,2-Dichloroethane-d4 (Surrogate)	BRI0009	BRI0009-BLK1	103	%	76 - 114 (LCL - UCL)		
Toluene-d8 (Surrogate)	BRI0009	BRI0009-BLK1	97.8	%	88 - 110 (LCL - UCL)		
4-Bromofluorobenzene (Surrogate)	BRI0009	BRI0009-BLK1	106	%	86 - 115 (LCL - UCL)		

TRC
21 Technology Drive
Irvine, CA 92618

Project: 6419
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/10/2008 12:30

Notes And Definitions

MDL Method Detection Limit
ND Analyte Not Detected at or above the reporting limit
PQL Practical Quantitation Limit
RPD Relative Percent Difference
A01 PQL's and MDL's are raised due to sample dilution.
A90 TPPH does not exhibit a "gasoline" pattern. TPPH is entirely due to MTBE.

Submission #: 0811617

SHIPPING INFORMATION

Federal Express UPS Hand Delivery BC Lab Field Service Other (Specify) _____

SHIPPING CONTAINER

Ice Chest None Box Other (Specify) _____

Refrigerant: Ice Blue Ice None Other Comments: _____

Custody Seals Ice Chest Containers None Comments: _____

All samples received? Yes No All samples containers intact? Yes No Description(s) match COC? Yes No

COC Received

YES NO

Emissivity: .97 Container: 67A Thermometer ID: 48

Temperature: A 0.2 °C / C 0.0 °C

Date/Time 9-3-8 2312

Analyst Init ALN

SAMPLE CONTAINERS	SAMPLE NUMBERS									
	1	2	3	4	5	6	7	8	9	10
QT GENERAL MINERAL/ GENERAL PHYSICAL										
PT PE UNPRESERVED										
QT INORGANIC CHEMICAL METALS										
PT INORGANIC CHEMICAL METALS										
PT CYANIDE										
PT NITROGEN FORMS										
PT TOTAL SULFIDE										
2oz. NITRATE / NITRITE										
PT TOTAL ORGANIC CARBON										
PT TOX										
PT CHEMICAL OXYGEN DEMAND										
PTA PHENOLICS										
40ml VOA VIAL TRAVEL BLANK										
40ml VOA VIAL	A3	A3	A3							
QT EPA 413.1, 413.2, 418.1										
PT ODOR										
RADIOLOGICAL										
BACTERIOLOGICAL										
40 ml VOA VIAL- 504										
QT EPA 508/608/8080										
QT EPA 515.1/8150										
QT EPA 525										
QT EPA 525 TRAVEL BLANK										
100ml EPA 547										
100ml EPA 531.1										
QT EPA 548										
QT EPA 549										
QT EPA 632										
QT EPA 8015M										
QT AMBER										
8 OZ. JAR										
32 OZ. JAR										
SOIL SLEEVE										
PCB VIAL										
PLASTIC BAG										
FERROUS IRON										
ENCORE										

Comments: _____
Sample Numbering Completed By: CTE Date/Time: 11/4/08 1:05

A = Actual / C = Corrected

BC LABORATORIES, INC.

4100 Atlas Court Bakersfield, CA 93308
 (661) 327-4911 FAX (661) 327-1918

CHAIN OF CUSTODY

#0811627 **Analysis Requested**

Bill to: Conoco Phillips/ TRC		Consultant Firm: TRC		MATRIX (GW) Ground-water (S) Soil (WW) Waste-water (SL) Sludge	BTEX/MTBE by 8021B, Gas by 8015	TPH GAS by 8015M	TPH DIESEL by 8015	8260 full list w/ oxygenates	BTEX/MTBE BY 8260B	ETHANOL by 8260B	TPH -G by GC/MS	Turnaround Time Requested
Address: 6401 Dublin Blvd.		21 Technology Drive Irvine, CA 92618-2302 Attn: Anju Farfan										
City: Dublin		4-digit site#: 6419										
State: CA Zip:		Workorder # 02527-4509118579										
Conoco Phillips Mgr: Terry Grayson		Project #: 154771										
Sampler Name: Andrew Vidreng												

Lab#	Sample Description	Field Point Name	Date & Time Sampled									
-1		MW-1	09/02/08 0600	GW					X	X	X	STD
-2		MW-3	↓ 0621	↓					↓	↓	↓	↓
-3		MW-5	↓ 0638	↓					↓	↓	↓	↓

CHK BY	DISTRIBUTION
<i>[Signature]</i>	<i>[Signature]</i>
SUB OUT	<input type="checkbox"/>

Comments: Run 8 OXys by 8260 on 8260 MTBE kit on MW-1 ONLY GLOBAL ID: T060010443	Relinquished by: (Signature)	Received by:	Date & Time
	Relinquished by: (Signature)	Received by:	Date & Time
	Relinquished by: (Signature)	Received by:	Date & Time

STATEMENTS

Purge Water Disposal

Non-hazardous groundwater produced during purging and sampling of monitoring was accumulated at TRC's groundwater monitoring facility at Concord, California, for transportation by a licensed carrier, to the ConocoPhillips Refinery at Rodeo, California. Disposal at the Rodeo facility was authorized by ConocoPhillips in accordance with "ESD Standard Operating Procedures – Water Quality and Compliance", as revised on February 7, 2003. Documentation of compliance with ConocoPhillips requirements is provided by an ESD Form R-149, which is on file at TRC's Concord Office. Purge water suspected of containing potentially hazardous material, such as liquid-phase hydrocarbons, was accumulated separately in a drum for transportation and disposal by others.

Limitations

The fluid level monitoring and groundwater sampling activities summarized in this report have been performed under the responsible charge of a California Registered Geologist or Registered Civil Engineer and have been conducted in accordance with current practice and the standard of care exercised by geologists and engineers performing similar tasks in this area. No warranty, express or implied, is made regarding the conclusions and professional opinions presented in this report. The conclusions are based solely upon an analysis of the observed conditions. If actual conditions differ from those described in this report, our office should be notified.