

HQ Bay Area Office 950 Tower Lane, Ste. 1225 Foster City, CA 94404 Sacramento Office 1415 L Street, Ste. 450 Sacramento, CA 95814

January 21, 2016

AntonDev.com

Alameda County Department of Environmental Health 1131 Harbor Bay Parkway Alameda, California 94502-6577 RECEIVED

By Alameda County Environmental Health 2:58 pm, Jan 25, 2016

Attention: Mr. Mark Detterman, PG, CEG, Senior Hazardous Materials Specialist

TRANSMITTAL LETTER WORK PLAN FOR SUPPLEMENTAL PRE-CONSTRUCTION SUBSURFACE INVESTIGATION 6701, 6705, AND 6707 SHELLMOUND STREET EMERYVILLE, CALIFORNIA Fuel Leak Case No. RO0000548 Geotracker Global ID T0600100894

Dear Mr. Detterman:

Submitted herewith for your review is the *Work Plan for Supplemental Pre-Construction Subsurface Investigation, 6701, 6705, and 6707 Shellmound Street, Emeryville, California* dated January 21, 2016, prepared by PES Environmental, Inc.

I declare, under penalty of perjury, that the information and/or recommendations contained in the above-referenced document for the subject property are true and correct to the best of my knowledge.

Very truly yours,

ANTON EMERYVILLE, LLC

Rachel Green Development Manager



January 21, 2016

1448.001.01.025

Alameda County Environmental Health 1131 Harbor Bay Parkway Alameda, California 94502-6577

Attention: Mr. Mark Detterman, P.G., C.HG.

WORK PLAN FOR SUPPLEMENTAL PRE-CONSTRUCTION SUBSURFACE INVESTIGATION 6701, 6705, AND 6707 SHELLMOUND STREET EMERYVILLE, CALIFORNIA FUEL LEAK CASE NO. RO0000548 GEOTRACKER GLOBAL ID T0600100894

Dear Mr. Detterman:

On behalf of Anton Emeryville, LLC (Anton), PES Environmental, Inc. (PES) has prepared this Work Plan for Supplemental Pre-Construction Subsurface Investigation (the Supplemental Investigation Work Plan) at the property located at 6701, 6705, and 6707 Shellmound Street, Emeryville, California (collectively, the subject property or site; Plates 1 and 2). On November 30 through December 3, 2015, PES performed pre-construction subsurface investigation activities in accordance with the *Revised Work Plan for Pre-Construction Subsurface Investigation* dated August 28, 2015 (Revised Pre-Construction Work Plan), with the objective of characterizing soil gas and soil which may remain in-place beneath future landscaped areas, future residential and multi-use areas of the future development, or be disturbed by future intrusive earthwork activities conducted during proposed redevelopment activities at the site. During a meeting on January 6, 2016 between Alameda County Environmental Health Department (ACEH), Anton, and PES, ACEH requested additional characterization of soil gas, soil, and groundwater beneath select areas of the site based on the results of the investigation. A site plan showing the proposed development and proposed soil gas, soil, and grab groundwater sampling locations is presented as Plate 3.

PES Environmental, Inc.

Mr. Mark Detterman January 21, 2016 Page 2

The subject property is currently listed as an open Spills, Leaks, Investigation and Cleanup (SLIC) case with ACEH as the lead environmental regulatory agency. The case is listed under Mike Roberts Color Production (6707 Bay Street), and the database lists other solvents and non-petroleum hydrocarbons as the potential contaminants of concern. PES is assisting Anton in working with ACEH to obtain SLIC case closure as part of the site redevelopment process.

The results of the pre-construction subsurface investigation conducted in November and December 2015 indicate the presence of elevated concentrations of volatile organic compounds (VOCs), primarily vinyl chloride and benzene, beneath the site, with the most elevated levels of vinyl chloride identified beneath the southwestern portion of the warehouse building (see Plate 2). The observed concentrations of vinyl chloride in soil vapor are consistent with an on-site source; however, the investigation results did not identify a source of the vinyl chloride in site soil. Additionally, groundwater sampling was not part of the November and December 2015 scope of work and is a component of the proposed scope of work.

The objective of the proposed supplemental pre-construction subsurface investigation is to further evaluate the subsurface for the presence of VOCs, particularly vinyl chloride, to identify potential on- or off-site sources and provide data in support of developing remedial or mitigation measures appropriate for the proposed development, as warranted. The supplemental investigation will focus primarily on the southwestern portion of the site, where concentrations of VOCs indicative of a potential source were identified during the November and December 2015 investigation.

BACKGROUND INFORMATION

Please refer to the Revised Pre-Construction Work Plan for Background Information, including current site and vicinity characteristics, as well as a discussion of subsurface conditions.

SCOPE OF WORK

The scope of work to be conducted is presented below. The scope of work includes collection and analysis of soil gas samples from 14 locations, soil samples from 23 locations, and a grab groundwater sample from one location at the site. As shown on Plate 2, the locations are focused within the vicinity of previous soil gas samples SV22 and SV25, in which the highest levels of vinyl chloride in soil gas were detected. Where feasible, soil gas and soil samples will be collected from the same boring.

Mr. Mark Detterman January 21, 2016 Page 3

Field Planning Activities

Prior to initiating field activities at the site, PES will update our site-specific Health and Safety Plan (HASP). The HASP will comply with applicable federal and California Occupational Safety and Health Administration (OSHA) guidelines. A drilling permit will be obtained from the Alameda County Public Works Agency, Water Resources Section (ACPWA).

Underground Service Alert will be contacted to schedule visits by public and private utility companies to locate their underground utilities. In addition, a private underground utility locating service will be contracted to conduct a subsurface electromagnetic survey to screen the proposed sampling locations for the presence of subsurface utilities.

Soil Vapor, Soil, and Grab Groundwater Sampling Activities

Soil vapor, soil, and/or grab groundwater sampling will be conducted using a limited-access direct push technology drill rig at 23 locations at the site, as shown on Plate 3, including:

- One soil boring to be advanced co-located with previous sample location SV22, where elevated concentrations of vinyl chloride were detected in soil vapor during the November and December 2015 investigation, to evaluate potential on-site source areas within the vadose zone and potential impact to groundwater;
- Eight 5-foot soil vapor probes to be installed in the southwestern portion of the warehouse building to further define the extent of vinyl chloride in soil vapor in the vicinity of previous sample locations SV22 and SV25 where elevated concentrations of vinyl chloride were detected in soil vapor during the November and December 2015 investigation;
- Five shallow soil borings to be advanced within the existing warehouse building to evaluate potential on-site vadose zone source areas in the vicinity of previous sample locations SV22 and SV25 where elevated concentrations of vinyl chloride were detected in soil vapor during the November and December 2015 investigation;
- Four soil vapor probes to be installed at 5 and 10 feet bgs within the alleyway located immediately south of the existing warehouse building to further define the extent of vinyl chloride in soil vapor near the southern property boundary;
- Four shallow soil borings to be advanced within the alleyway located immediately south of the existing warehouse building to evaluate potential on-site vadose zone source areas near the southern property boundary;

Mr. Mark Detterman January 21, 2016 Page 4

- One 10-foot soil vapor probe to be installed in the northwestern portion of the site to further define the extent of vinyl chloride in deeper soil vapor near the northwestern site boundary; and
- One 10-foot semi-permanent soil vapor probe to be installed in the eastern portion of the site, co-located with previous sample location SV7, to re-assess soil vapor conditions at 10 feet bgs where laboratory reporting limits for vinyl chloride have previously been above applicable screening levels¹.

Soil vapor probe installation and sampling will be conducted in accordance with the procedures outlined in the *Advisory – Active Soil Gas Investigations* published by the Department of Toxic Substances Control, the Regional Water Quality Control Board, Los Angeles Region and the RWQCB dated July 2015 as described in the Revised Pre-Construction Work Plan.

At each location scheduled for shallow soil sampling (including each soil vapor sampling location), the boring will be advanced to between approximately 5 and 10 feet below ground surface (bgs). Soil cores will be collected continuously from each location and soil samples will be collected for lithologic description, field screening for VOCs, and possible chemical analysis in accordance with the methods described in the Revised Pre-Construction Work Plan. At a minimum, soil samples will be collected for analysis at depths immediately below the surface pavement or building slab and aggregate base material, if present, and at 5 feet bgs. Additional soil samples will be collected for analysis at select locations at a depth of 10 feet bgs and additional depth intervals if warranted based on field screening results and/or lithology.

At the location scheduled for grab groundwater sampling, the boring will be advanced to approximately 5 feet below first-encountered groundwater (anticipated to be present at a depth between approximately 10 and 12 feet bgs) and a temporary well will be installed using one-inch diameter polyvinyl chloride (PVC) casing. The grab groundwater samples will be collected using a new disposable polyethylene bailer or equivalent. During sample collection PES will attempt to minimize, to the best extent practicable, the amount of sediment entering the sample container.

¹ If elevated laboratory reporting limits are necessitated due to high concentrations of non-target analytes, PES will instruct the laboratory to perform additional analytical runs within the target concentration range to attempt to achieve reporting limits below applicable site screening levels, where feasible.

PES Environmental, Inc.

Mr. Mark Detterman January 21, 2016 Page 5

The soil and grab groundwater samples will be placed in an ice-chilled, insulated cooler and transported to TestAmerica Laboratories, Inc. (TestAmerica) under chain-of-custody protocol. PES anticipates submitting a total of 48 soil samples for analysis for VOCs including MEK, MIBK, and naphthalene by U.S. Environmental Protection Agency (U.S. EPA) Test Method 8260B (collected in accordance with U.S. EPA Method 5035 using Terracore[™] samplers) and one grab groundwater sample for analysis for VOCs including MEK, MIBK, and naphthalene by U.S. EPA Test Method 8260B and 1,4-dioxane by U.S. EPA Test Method 8270 SIM.

Upon completion of soil and grab groundwater sampling, each borehole will be filled from the bottom of the borehole to the ground surface with neat cement grout (using a tremie pipe for borings containing more than six inches of water) in accordance with ACPWA requirements, and the ground surface will be restored to match existing conditions. Reusable downhole drilling and sampling equipment will be decontaminated using a high-pressure, hot water wash or Alconox[™] wash and triple rinse prior to collecting each soil sample.

Handling, Storage, and Disposal of Investigation-Derived Waste

Investigation-derived waste (IDW) generated during the supplemental pre-construction subsurface investigation will be temporarily stored on the site. The IDW will be stored in secured, labeled 55-gallon steel drums until proper off-site management in accordance with applicable State and Federal laws can be arranged. The IDW will be disposed or recycled based on the results of the laboratory analyses.

Reporting

A description of the methods and procedures of the above-referenced scope of work will be presented in a report along with the results of the sampling activities and the November and December 2015 pre-construction investigation. The report will also provide tabulated data, illustrations showing select contaminant concentrations, laboratory analytical reports, findings of the completed scope of work, and recommendations, as appropriate. Additionally, the report will include updated geologic cross-sections showing the proposed development, including locations of the building foundation, residential units, and utility trenches, to the extent practicable based on available information.

The soil gas soil, and grab groundwater sampling results will be submitted electronically to the State Water Resources Control Board Geotracker database and ACEH file transfer protocol (ftp) site.

Mr. Mark Detterman January 21, 2016 Page 6

SCHEDULE

The project schedule has been developed as follows: (1) field preparation activities are tentatively scheduled for January 27 and 29, 2016; (2) the soil gas, soil, and groundwater supplemental investigation is tentatively scheduled for February 1 through 3, 2016, weather permitting; (3) waste disposal to be conducted within approximately four weeks following receipt of the IDW sampling laboratory results; and (4) a report is expected to be submitted to ACEH by approximately February 12, 2016.

Please call Kyle Flory at (415) 899-1600 if you have any questions or comments regarding this document.

SELECTIONAL GEO

Na. 9125

FIEOFCALIF

Very truly yours,

PES ENVIRONMENTAL, INC.

Morgan G. Jones, P.G. **Project Geologist**


Kyle S. Flory, P.G.


Principal Geologist


Attachments: Plate 1 – Site Location Map Plate 2 - Site Plan Showing Soil Vapor Analytical Results - Vinyl Chloride Plate 3 - Site Plan Showing Proposed Soil Vapor, Soil, and Grab Groundwater Sample Locations Attachment A - Summary of Soil Vapor Analytical Results

cc: Rachel Green - Anton Emeryville, LLC

PLATES








Explanation

	Approximate Property Boundary
SG-5 🔶	Soil, Soil Gas and Groundwater Sampling Location - Destroyed (Environ, 2013)
SG-3 🚸	Soil Gas and Soil Sampling Location - Destroyed (Environ, 2013)
SV1 🔶	Soil Vapor Sampling Location (PES, April 2015)
SSV1 -	Sub-Slab Vapor Sampling Location (PES, April 2015)
<u> </u>	Assumed Former Drain Line Location
? — 55 —	Approximate Location of Existing Sewer Line (queried where uncertain)
	Existing Building Outline
SV7 🔶	Soil Vapor Sampling Location
· · · ·	Future Driveway - Grasscrete
·**	Future Driveway - Decomposed Granite
0 0 0 0 0	Future Planter/Infiltration Gallery
	Future Concrete Walkway
A A'	
A A	Hydrogeologic Cross Section Location (Arrows show direction of view)
	(Allows show direction of view)
83/57	Vinyl Chloride concentration at
	5-feet and 10-feet below ground surface (ft bgs) shown in micrograms per cubic meter (μ g/m ³)
ND(5.0)	Not detected at or above the indicated laboratory
	reporting limit
NS	Not Sampled
•	Exceeds residential ESL for Soil Gas (16 μ g/m ³)
	Notes:
	 SV7 sampled only at 10-ft bgs. SV47 sampled only at 5-ft bgs.
	3. Sample depths for SV-15 are 5-ft and 8-ft bgs.
	•

0 50 SCALE IN FEET

Basemap: Luk and Associates, 2015


Site Plan Showing Soil Vapor Analytical Results - Vinyl Chloride Work Plan for Supplemental Pre-Construction Subsurface Investigation 6701, 6705, and 6707 Shellmound Street Emeryville, California



PES Environmental, In Engineering & Environmental Service	C. Ses	Site Plan Showing Proposed Soil Vapor, Soil, and Grab Groundwater Sample Locations Work Plan for Supplemental Pre-Construction Subsurface Investigation 6701, 6705, and 6707 Shellmound Street Emeryville, California
1448.001.01.019 144800101019_WPPCSI_3	MGJ	
JOB NUMBER DRAWING NUMBER	REVIEWED BY	

Explanation

	Explanation
	Approximate Property Boundary
SG-5 🔶	Soil, Soil Gas and Groundwater Sampling Location - Destroyed (Environ, 2013)
SG-3 🗇	Soil Gas and Soil Sampling Location - Destroyed (Environ, 2013)
SV1 🔶	Soil Vapor Sampling Location (PES, April 2015)
SSV1 -	Sub-Slab Vapor Sampling Location (PES, April 2015)
<u> </u>	Assumed Former Drain Line Location
? — 55 —	Approximate Location of Existing Sewer Line (queried where uncertain)
	Existing Building Outline
SV7 🔶	Soil Vapor Sampling Location
* * *	Future Driveway - Grasscrete
·	Future Driveway - Decomposed Granite
	Future Planter/Infiltration Gallery
	Future Concrete Walkway
A A' ▲ ▲	Hydrogeologic Cross Section Location (Arrows show direction of view)
•	Proposed Soil and Grab Groundwater Sample Location
۲	Proposed Soil Sampling Location
\diamond	Proposed Soil Vapor Sampling Location
5 0 ¹⁰	Proposed Soil Vapor and Soil Sampling Location (target depths shown in feet below ground surface)



Basemap: Luk and Associates, 2015

PLATE 3

Α'

PES Environmental, Inc.

ATTACHMENT A

SUMMARY OF SOIL VAPOR ANALYTICAL RESULTS

Attachment A Summary of Soil Vapor Analytical Results Pre-Construction Subsurface Investigation 6701, 6705, and 6707 Shellmound Street, Emeryville, California

Sample Location	Sample ID	Sample Depth (feet bgs)	Date Sampled	PCE (µg/m ³)	TCE (μg/m ³)	cis-1,2-DCE (µg/m ³)	trans-1,2- DCE (μg/m³)	Vinyl chloride (µg/m³)	1,1,1-TCA (μg/m ³)	1,1,2,2- ΡCA (μg/m³)	MEK (µg/m³)	MIBK (µg/m ³)	Acetone (μg/m³)	Benzene (μg/m ³)	Toluene (μg/m³)	Ethylbenzene (µg/m³)	m,p-Xylene (µg/m³)	o-Xylene (µg/m³)	1,2,4- TMB (µg/m ³)	1,3,5-TMB (μg/m ³)	4-Ethyltoluene (μg/m ³)	Carbon disulfide (µg/m³)	Chloroform (µg/m³)	Other VOCs (μg/m³)	Carbon Dioxide (% v/v)	Methane (% v/v)	Oxygen (% v/v)	Helium (% v/v)
SV5	SV5-5	5.0	12/2/2015	< 2.7	< 2.1	< 1.6	< 1.6	< 1.0	< 1.6	< 2.7	55	< 1.6	120	12	8.9	2.6	25	3.8	8.5	3.2	< 2.0	3.9	7.2	ND	4.1	< 0.96	17	1.5
	SV5-10 SV6-5	10.0	12/2/2015 12/2/2015	< 4.6 < 4.6	< 3.6 < 3.7	< 2.7 5.4	< 2.7 < 2.7	< 1.7 < 1.7	< 2.8	< 4.6 < 4.7	43	< 2.8 < 2.8	76 270	< 2.1 31	2.9 16	< 2.9	< 5.8	< 2.9 < 3.0	< 6.6	< 3.3 < 3.4	< 3.3 < 3.4	< 4.2 120	10 21	ND				< 0.17 < 0.17
SV6	SV6-10	5.0 10.0	12/2/2015	< 6.2	< 4.9	< 3.6	< 3.6	< 2.3	< 3.7	< 6.3	73 12	< 3.8	37	< 2.9	< 3.5	3.2 < 4.0	9.3 < 8.0	< 4.0	< 6.7 < 9	< 4.5	< 4.5	< 5.7	< 3.4	3.9 (Freon 21) 4.8 (Freon 21)				0.57
SV7	SV7-10	10.0	12/2/2015	< 2,100	< 1,700	< 1,300	< 1,300	< 810	< 1,300	< 2,200	< 1,900	88,000	< 9,400	< 1,000	< 1,200	< 1,400	< 2,700	< 1,400	< 3,100	< 1,600	< 1,600	< 2,000	< 1,200	ND				< 0.17
SV8	SV8-5	5.0	12/3/2015	7.8	< 2.1	7.0	9.1	110	< 1.6	< 2.7	4.0	< 1.6	76	11	13	< 1.7	5.4	1.9	< 3.9	< 2.0	< 2.0	33	< 1.5	2.9 (CM), 3.2 (MC)	1.0	0.69	1.4	< 0.10
300	SV8-10	10.0	12/3/2015	< 8.6	< 6.8	< 5.0	< 5.0	7.8	< 5.2	< 8.7	35	< 5.2	200	4.8	9.7	< 5.5	< 11	< 5.5	< 12	< 6.2	< 6.2	18	< 4.6	ND	2.2	1.6	4.3	< 0.19
SV9	SV9-5	5.0	12/2/2015	< 12	< 9.9	< 7.3	< 7.3	< 4.7	< 7.5	< 13	100	840	500	8.2	23	< 8.0	20	< 8.0	< 18	< 9.0	< 9.0	< 11	< 6.7	ND			<u> </u>	0.93
	SV9-10	10.0	12/2/2015	< 5.4	< 4.3	< 3.2	< 3.2	< 2.0	< 3.3	< 5.5	48	140	160	< 2.6	3.9	< 3.5	7.5	3.9	< 7.9	< 3.9	< 3.9	< 5.0	< 2.9	ND				0.67
SV10	SV10-5	5.0	12/2/2015	< 21	< 16	22	< 12	< 7.8	< 12	< 21	67	300	630	30	26	< 13	< 26	< 13	< 30	< 15	< 15	< 19	< 11	ND	3.3	2.4	1.8	0.76
	SV10-10 SV11-5	10.0 5.0	12/2/2015 12/3/2015	59 < 16	< 6.6 < 13	4.8 43	< 4.9 < 9.5	< 3.1 < 6.1	< 5.0 < 9.8	< 8.5 < 16	41 81	68 < 9.8	180 330	150 84	11 13	< 5.3 < 10	< 11 27	5.9 < 10	< 12 < 24	7.1 < 12	< 6.1 < 12	< 7.7 170	< 4.5 < 8.8	ND ND	5.3 3.6	< 0.96 2.5	1.7 2.3	0.71 0.44
SV11	SV11-0	10.0	12/3/2015	< 42	< 33	43 < 24	< 24	< 16	< 25	< 42	140	< 25	770	900	85	< 27	< 53	< 27	< 61	< 30	< 30	< 38	< 23	ND	1.7	6.1	1.9	< 0.19
	SV12-5	5.0	12/3/2015	< 13	< 10	< 7.7	< 7.7	< 5.0	< 8.0	< 13	37	< 8.0	300	40	15	< 8.4	< 17	< 8.4	< 19	< 9.6	< 9.6	63	< 7.1	ND				0.56
SV12	SV12-10	10.0	12/3/2015	< 11	< 8.3	< 6.2	< 6.2	< 4.0	< 6.4	< 11	58	< 6.4	190	7.1	7.8	< 6.7	< 13	< 6.7	< 15	< 7.6	< 7.6	26	< 5.7	ND				0.64
SV13	SV13-5	5.0	12/2/2015	< 19	< 15	< 11	< 11	< 7.3	< 12	< 20	65	< 12	380	17	48	< 12	160	< 12	< 28	< 14	< 14	31	< 10	ND	1.1	13	1.6	0.90
3113	SV13-10	10.0	12/2/2015	< 12	< 9.8	< 7.3	< 7.3	< 4.7	< 7.5	< 13	55	< 7.5	420	36	67	8.4	27	8.5	< 18	< 9.0	< 9.0	44	< 6.7	ND	< 1.0	15	1.8	< 0.20
SV14	SV14-5	5.0	12/2/2015	< 26	< 21	< 15	< 15	< 9.8	< 16	< 26	96	< 16	590	83	32	< 17	< 33	< 17	< 38	< 19	< 19	140	< 14	ND	2.0	< 0.96	19	< 0.19
	SV14-10	10.0	12/2/2015	< 26	< 20	< 15	< 15	< 9.7	< 16	< 26	64	< 16	530	610	71	28	110	23	< 37	< 19	< 19	< 24	< 14	ND	1.9	13	1.7	1.2
SV15	SV15-5	5.0	12/2/2015	< 62	< 49	< 36	< 36	< 23	< 37	< 63	56	310	2,400	39	< 34	< 40	< 79	< 40	< 90	< 45	< 45	71	< 33	ND			<u>⊢</u>	< 0.18
	SV15-8 SV16-5	8.0 5.0	12/2/2015 12/2/2015	< 18 < 31	< 14 < 25	24 < 18	< 10 < 18	< 6.6 < 12	< 11 < 19	< 18 < 31	< 15 64	< 11 < 19	460 630	120 59	49 43	19 < 20	54 < 40	22 < 20	< 25 < 45	< 13 < 22	< 13 < 22	190 28	< 9.5 < 17	ND ND	 5.6	 39	 1.3	< 0.19 < 0.18
SV16	SV16-10	10.0	12/2/2015	< 12	< 9.5	13	< 7.0	5.4	< 7.2	< 12	77	< 7.2	590	< 5.6	20	8.9	27	× 20 8.5	< 17	< 8.7	< 8.7	< 11	< 6.4	9 (1,1-DCA)	2.3	27	1.3	0.81
	SV17-5	5.0	12/1/2015	< 18	< 14	< 10	< 10	< 6.7	< 11	< 18	93	< 11	400	130	120	24	130	26	< 26	< 13	< 13	120	31	ND				< 0.20
SV17	SV17-10	10.0	12/1/2015	< 67	< 53	< 39	< 39	< 25	< 40	120	< 58	< 40	< 290	4,200	180	< 43	< 86	< 43	< 97	< 49	< 49	< 62	< 36	ND				< 0.20
SV18	SV18-5	5.0	12/2/2015	< 17	< 14	29	< 10	83	< 10	< 18	100	< 11	780	210	32	< 11	43	< 11	< 25	< 13	< 13	120	< 9.4	ND			İ	< 0.18
3010	SV18-10	10.0	12/2/2015	< 11	< 8.9	< 6.6	< 6.6	57	< 6.8	< 11	72	< 6.8	380	84	39	8.9	27	9.2	< 16	< 8.2	< 8.2	280	< 6.1	20 (CM)				0.29
SV19	SV19-5	5.0	12/1/2015	< 19	< 15	14	< 11	650	< 11	< 19	150	< 11	760	300	59	< 12	68	13	< 28	< 14	< 14	66	< 10	ND	9.7	52	0.96	< 0.17
	SV19-10	10.0	12/1/2015	< 20	34	170	< 12	47	< 12	< 20	44	< 12	180	760	53	< 13	45	12	< 29	< 14	< 14	110	< 11	ND	1.8	75	0.87	< 0.18
SV20	SV20-5	5.0	12/1/2015	< 57	< 45	< 33	< 33	23	< 35	< 58	110	< 35	960	120	58	< 37	< 73	< 37	< 83	< 41	< 41	120	< 31	ND	5.0	20	2.3	< 0.17
	SV20-10 SV21-5	10.0 5.0	12/1/2015 12/1/2015	< 13 < 20	< 11 17	25 70	< 7.9 < 12	19 48	< 8.1 < 12	< 14 < 20	54 83	< 8.1 < 12	230 620	110 62	65 54	9.9 < 13	40 < 26	11 < 13	< 19 < 29	< 9.7 < 14	< 9.7 < 14	60 120	< 7.3 23	7.9 (MC) ND	5.1	22	1.6	< 0.17 < 0.19
SV21	SV21-5	10.0	12/1/2015	< 14	20	70	< 8.2	40 140	< 8.5	< 14	64	< 8.5	290	42	48	< 9.0	67	< 9	< 20	< 14	< 10	260	< 7.6	ND				< 0.19
	SV22-5	5.0	12/1/2015	< 2,600	< 2,000	< 1,500	< 1,500	83,000	< 1,500	< 2,600	< 2,200	< 1,500	< 11,000	< 1,200	< 1,400	< 1,600	< 3,300	< 1,600	< 3,700	< 1,900	< 1,900	< 2,400	< 1,400	ND	11	35	1.4	< 0.19
SV22	SV22-10	10.0	12/1/2015	< 1,200	< 940	1,500	1,200	35,000	< 710	< 1,200	< 1,000	< 710	< 5,200	< 560	< 660	< 760	< 1,500	< 760	< 1,700	< 860	< 860	< 1,100	< 640	ND	< 0.87	44	1.3	0.41
SV23	SV23-5	5.0	11/30/2015	< 17	< 13	110	33	14	< 10	< 17	47	< 10	210	970	35	16	36	11	< 25	< 12	< 12	18	< 9.1	18 (1,4-DCB)	10	< 1.0	2.0	< 0.20
3723	SV23-10	10.0	11/30/2015	< 9.8	< 7.7	< 5.7	< 5.7	< 3.7	< 5.9	< 9.9	110	< 5.9	410	27	34	< 6.3	18	6.0	< 14	< 7.1	< 7.1	9.0	8.5	ND	5.2	< 0.98	11	< 0.20
SV24	SV24-5	5.0	11/30/2015	< 12	< 9.5	< 7.0	< 7.0	< 4.5	< 7.3	< 12	120	< 7.3	560	12	32	< 7.7	18	< 7.7	< 17	< 8.7	< 8.7	< 11	< 6.5	ND				< 0.19
	SV24-10	10.0	11/30/2015	< 12	< 9.3	< 6.8	< 6.8	< 4.4	< 7.1	< 12	100	< 7.1	490	100	110	95	280	180	190	76	61	74	< 6.3	ND				< 0.19
SV25	SV25-5 SV25-10	5.0 10.0	12/1/2015 12/1/2015	< 130 < 260	< 100 300	130	< 77	7,300 11,000	< 79 < 160	< 130 < 270	< 110 < 230	< 79 < 160	1,200 < 1200	110 160	< 73 < 150	< 84 < 170	< 170 < 340	< 84 < 170	< 190 < 380	< 95 < 190	< 95 < 190	< 120 < 240	< 71 < 140	ND ND				< 0.19 < 0.17
	SV25-10	5.0	12/1/2015	< 6.4	5.8	2,100 28	210 < 3.7	14	< 3.9	< 6.5	< 230 63	< 3.9	290	240	< 150 35	18	< 340 120	18	< 380 17	< 190 10	< 4.6	130	< 3.5	ND	 1.4	2.3	 9.5	< 0.17
SV26	SV20-5 SV26-10	10.0	12/1/2015	< 42	< 33	26	< 24	72	< 25	< 42	63 < 36	< 25	< 180	30	25	< 27	120	45	180	82	38	< 38	< 22	56 (CB)	2.8	3.3	9.5 1.8	< 0.18
0) (27	SV27-5	5.0	11/30/2015	< 4.3	5.3	< 2.5	< 2.5	< 1.6	< 2.6	< 4.4	26	< 2.6	180	7.8	44	< 2.8	15	2.8	< 6.3	< 3.1	< 3.1	9.8	< 2.3	4.7 (2-Hexanone)				< 0.16
SV27	SV27-10	10.0	11/30/2015	< 7.7	< 6.1	8.2	< 4.5	10	< 4.6	< 7.8	11	< 4.7	110	9.8	15	< 4.9	10	< 4.9	< 11	< 5.6	< 5.6	16	< 4.2	ND				< 0.16
SV28R	SV28R-5	5.0	12/3/2015	< 11	< 8.4	11	< 6.2	23	< 6.4	< 11	33	< 6.4	220	18	110	82	420	64	46	35	8.3	17	< 5.7	ND	1.0	13	2.0	0.58
00201	SV28R-10	10.0	12/3/2015	< 2.7	< 2.1	1.7	< 1.6	83	< 1.6	< 2.7	< 2.4	< 1.6	27	< 1.3	< 1.5	< 1.7	< 3.5	< 1.7	< 3.9	< 2.0	< 2.0	< 2.5	< 1.5	7.5 (DCFM)	< 0.97	21	1.4	< 0.19
SV29	SV29-5	5.0	11/30/2015	< 5.1	< 4.0	< 3.0	< 3.0	< 1.9	< 3.1	< 5.2	31	< 3.1	210	10	27	11	200	5.8	7.3	< 3.7	< 3.7	30	14	ND				< 0.19
	SV29-10	10.0	11/30/2015	< 5.0	6.2	< 2.9	< 2.9	< 1.9	< 3.0	< 5.0	30	< 3.0	160	35	21	8.0	47	7.8	7.1	5.1	< 3.6	63	< 2.7	3.4 (MC)				< 0.18
SV30	SV30-5	5.0	12/1/2015	< 5.7	110	6.7	3.4	< 2.1	< 3.4	< 5.8	22	< 3.4	110	12	11	< 3.6	11	< 3.6	< 8.3	< 4.1	< 4.1	41	7.3	ND				< 0.17
	SV30-10 SV31-5	10.0 5.0	12/1/2015 12/1/2015	< 12 < 4.6	23 13	28 < 2.7	13 < 2.7	33 < 1.7	< 7.4	< 12 < 4.7	30 13	< 7.4 < 2.8	130 75	67 13	24 19	8.0 4.0	21 14	8.6 6.3	< 18 < 6.7	< 8.9 < 3.4	< 8.9 < 3.4	97 21	6.8 8.5	33 (1,1-DCE), 10 (Freon 11) 3.5 (MC)				< 0.18 < 0.17
SV31	SV31-5 SV31-10	10.0	12/1/2015	< 4.0	23	< 1.6	2.8	< 1.7	< 1.6	< 4.7	4.8	< 1.6	38	13	19	4.0	22	6.6	< 3.9	< 3.4	< 3.4	11	0.5 11	4 (CM)				< 0.17
	SV32-5	5.0	12/1/2015	< 8.8	11	< 5.1	< 5.1	< 3.3	< 5.3	< 8.9	22	< 5.3	150	14	16	< 5.6	< 11	< 5.6	< 13	< 6.4	< 6.4	8.0	19	ND				< 0.16
SV32	SV32-10	10.0	12/1/2015	< 19	< 15	< 11	< 11	< 7.2	< 12	< 19	49	< 12	330	43	17	< 12	< 24	< 12	< 28	< 14	< 14	< 18	< 10	ND				< 0.17
L				ı	ı			ı		ı – – – – – – – – – – – – – – – – – – –			1		í	۰	1				ı	ı	ı	ı			. <u> </u>	

Attachment A Summary of Soil Vapor Analytical Results Pre-Construction Subsurface Investigation 6701, 6705, and 6707 Shellmound Street, Emeryville, California

Sample Location	Sample ID	Sample Depth (feet bgs)	Date Sampled	PCE (µg/m³)	TCE (µg/m ³)	cis-1,2-DCE (µg/m ³)	trans-1,2- DCE (μg/m³)	Vinyl chloride (µg/m³)	1,1,1-TCA (μg/m³)	1,1,2,2- PCA (μg/m ³)	MEK (µg/m ³)	MIBK (µg/m ³)	Acetone (µg/m³)	Benzene (µg/m³)	Toluene (μg/m³)	Ethylbenzene (µg/m ³)	m,p-Xylene (µg/m ³)	o-Xylene (µg/m³)	1,2,4- TMB (μg/m ³)	1,3,5-TMB (µg/m ³)	4-Ethyltoluene (μg/m³)	Carbon disulfide (µg/m³)	Chloroform (µg/m³)	Other VOCs (µg/m³)	Carbon Dioxide (% v/v)	Methane (% v/v)	Oxygen (% v/v)	Helium (% v/v)
SV33	SV33-5	5.0	12/1/2015	< 22	< 18	< 13	< 13	< 8.5	< 14	< 23	34	< 14	230	37	20	< 14	30	< 14	< 33	< 16	< 16	24	< 12	ND			-	< 0.17
0,000	SV33-10	10.0	12/1/2015	< 46	< 37	< 27	< 27	47	< 28	430	< 40	970	< 200	< 22	65	70	350	80	< 67	< 34	< 34	< 43	< 25	ND		-		< 0.17
SV36	SV36-5	5.0	12/1/2015	< 7.9	< 6.3	< 4.6	< 4.6	3.0	< 4.8	21	16	8.3	77	5.7	9.0	< 5.1	< 10	5.0	< 11	< 5.7	< 5.7	< 7.2	< 4.3	ND	3.6	< 1.2	17	< 0.23
0100	SV36-10	10.0	12/1/2015	< 58	< 46	< 34	< 34	< 22	< 35	2,500	< 51	370	< 260	150	41	210	< 75	250	< 85	< 42	< 42	53	< 31	170 (BC)	2.0	11	10	< 0.17
SV38	SV38-5	5.0	11/30/2015	< 17	< 13	< 9.7	< 9.7	25	< 10	< 17	85	< 10	460	18	24	< 11	< 21	< 11	< 24	< 12	< 12	110	48	ND	0.99	13	2.4	< 0.18
0100	SV38-10	10.0	11/30/2015	< 40	< 32	160	54	1,800	< 24	< 41	78	< 24	310	150	30	< 26	< 52	< 26	< 59	< 29	< 29	320	< 22	ND	< 0.89	67	1.6	< 0.18
SV39	SV39-5	5.0	12/1/2015	< 7.5	< 6.0	< 4.4	< 4.4	< 2.8	< 4.6	< 7.6	61	< 4.6	290	17	17	39	23	4.8	< 11	< 5.5	< 5.5	110	4.1	ND	< 0.96	< 0.96	24	0.19
	SV39-10	10.0	12/1/2015	< 8.1	9.0	38	63	7.5	< 4.9	< 8.2	49	< 4.9	200	130	71	99	220	65	62	43	23	140	< 4.4	ND	< 0.94	3.4	22	< 0.19
SV40	SV40-5	5.0	12/1/2015	< 17	13	42	10	24	< 10	27	29	38	180	25	14	< 11	< 22	< 11	< 25	< 12	< 12	43	< 9.2	ND				< 0.19
	SV40-10	10.0	12/1/2015	< 62	< 49	< 36	< 36	110	< 38	640	< 54	73	< 270	50	< 35	< 40	160	130	< 90	< 45	< 45	< 57	< 34	ND				< 0.18
SV43	SV43-5	5.0	12/1/2015	< 8.5	< 6.7	< 5.0	< 5.0	< 3.2	< 5.1	< 8.6	17	21	76	25	9.1	< 5.4	< 11	< 5.4	< 12	< 6.2	< 6.2	15	12	ND				< 0.19
	SV43-10	10.0	12/1/2015	< 3	< 2.4	1.8	< 1.8	< 1.1	< 1.8	7.5	15	< 1.8	42	5.1	4.9	< 1.9	5.3	1.9	< 4.4	< 2.2	< 2.2	6.5	< 1.6	3.3 (BC)				< 0.18
SV44	SV44-5	5.0	12/1/2015	< 4.5	< 3.6	< 2.6	< 2.6	< 1.7	< 2.7	< 4.6	49	< 2.7	220	50	17	30	22	13	16	3.7	6.9	60	< 2.4	17 (NAPH)	< 0.83	< 0.83	24	< 0.17
	SV44-10	10.0	12/1/2015	< 5.9	< 4.7	21	< 3.5	3.1	< 3.6	< 6.0	28	< 3.6	130	5.6	4.7	< 3.8	< 7.6	< 3.8	< 8.6	< 4.3	< 4.3	26	< 3.2	ND	9.3	0.92	2.3	< 0.16
SV45	SV45-5	5.0	12/1/2015	< 12	< 9.2	6.6	< 6.8	< 4.4	< 7.0	< 12	110	< 7.0	540	51	14	10	50	15	< 17	< 8.4	< 8.4	45	22	ND	5.8	< 0.90	14	0.34
0140	SV45-10	10.0	12/1/2015	< 4.9	< 3.9	9.5	< 2.9	< 1.8	< 2.9	< 4.9	76	< 2.9	170	16	8.3	6.0	33	12	9.7	4.4	< 3.5	7.7	4.9	3.4 (BC)	11	< 0.90	4.0	0.36
SV47	SV47-5	5.0	12/3/2015	< 7.2	< 5.7	8.8	< 4.2	< 2.7	5.7	< 7.2	38	< 4.3	250	13	24	< 4.6	11	< 4.6	< 10	< 5.2	< 5.2	22	< 3.9	ND				< 0.21
	Residential L	and Use ESL	. (Soil Gas) ¹	210	300	3,700	31,000	16	2,600,000	21	2,600,000	1,600,000	16,000,000	42	160,000	490	52,000	52,000	NE	NE	NE	NE	230	NE	NE	NE	NE	NE

Notes: Detections are shown in bold. Results equal to or exceeding applicable regulatory screening levels are shaded.

PCE = Tetrachloroethene.

TCE = Trichloroethene.

DCE = Dichloroethene.

TCA = Trichloroethane.

PCA = Tetrachloroethane

MEK = 2-Butanone

MIBK = 4-Methyl-2-pentanone

TMB = Trimethylbenzene.

CB = Chlorobenzene. CM = Chloromethane.

DCA = Dichloroethane.

DCB = Dichlorobenzene

BC = Benzyl chloride

Freon 11 = Trichlorofluoromethane

Freon 21 = Dichlorofluoromethane TCD = Carbon Dioxide

MC = Methylene Chloride

NAPH = Naphthalene

VOCs = Volatile organic compounds.

bgs = Below ground surface.

 μ g/m³ = Micrograms per cubic meter.

% v/v = Percent by volume.

< 2.9 = Not detected at or above the indicated laboratory method reporting limit.

ND = Not detected at or above the respective laboratory method reporting limits.

NE = Not established.

-- = Not applicable/not analyzed.
 1. ESL = December 2013 Regional Water Quality Control Board, San Francisco Bay Region (RWQCB) Environmental Screening Levels (ESLs), Table E-2 Soil Gas Screening Levels for Evaluation of Potential Vapor

Intrusion.