

ALAMEDA COUNTY
HEALTH CARE SERVICES

AGENCY
DAVID J. KEARS, Agency Director



ENVIRONMENTAL HEALTH SERVICES
ENVIRONMENTAL PROTECTION
1131 Harbor Bay Parkway, Suite 250
Alameda, CA 94502-6577
(510) 567-6700
FAX (510) 337-9335

June 30, 2008

Mr. Robert Aldenhuisen
RMC Pacific Materials d.b.a. CEMEX
5180 Golden Foothill Parkway, Suite 200
El Dorado Hills, CA 95762-9608

Subject: Fuel Leak Case No. RO0002603 and Geotracker Global ID T0600171421, Eliot Aggregate Plant,
1544 Stanley Blvd., Pleasanton, CA 94566 – Case Closure

Dear Mr. Aldenhuisen:

This letter transmits the enclosed underground storage tank (UST) case closure letter in accordance with Section 25296.10 of the Health and Safety Code. We are also transmitting to you the enclosed case closure summary. These documents confirm the completion of the investigation and cleanup of the reported release at the subject site. The subject fuel leak case is closed. This case closure letter and the case closure summary can also be viewed on the State Water Resources Control Board's Geotracker website (<http://geotracker.swrcb.ca.gov>) and the Alameda County Environmental Health website (<http://www.acgov.org/aceh/index.htm>).

If you have any questions, please call Jerry Wickham at (510) 567-6791. Thank you.

Sincerely,


Donna L. Drogo, P.E.
LOP and Toxics Program Manager

Enclosures:

1. Remedial Action Completion Certificate
2. Case Closure Summary

cc:

Ms. Cherie McCaulou (w/enc)
SF- Regional Water Quality Control Board
1515 Clay Street, Suite 1400
Oakland, CA 94612

Mr. Toru Okamoto (w/enc)
State Water Resources Control Board
UST Cleanup Fund
P.O. Box 944212
Sacramento, CA 94244-2120

Ms. Danielle Stefani (w/enc)
Livermore-Pleasanton Fire Department
3560 Nevada Street
Pleasanton, CA 94566

Ms. Cheryl Dizon, QIC 80201 (w/enc)
Zone 7 Water Agency
100 North Canyons Parkway
Livermore, CA 94551

City of Pleasanton Planning and Community
Development (w/enc.)
200 Old Bernal Avenue
P.O. Box 520
Pleasanton, CA 94566-0802

Jerry Wickham (w/orig enc), D. Drogos (w/enc), File (w/enc)

ALAMEDA COUNTY
HEALTH CARE SERVICES

AGENCY
DAVID J. KEARS, Agency Director



ENVIRONMENTAL HEALTH SERVICES
ENVIRONMENTAL PROTECTION
1131 Harbor Bay Parkway, Suite 250
Alameda, CA 94502-6577
(510) 567-6700
FAX (510) 337-9335

REMEDIAL ACTION COMPLETION CERTIFICATION

June 30, 2008

Mr. Robert Aldenhuisen
RMC Pacific Materials d.b.a. CEMEX
5180 Golden Foothill Parkway, Suite 200
El Dorado Hills, CA 95762-9608

Subject: Fuel Leak Case No. RO0002603 and Geotracker Global ID T0600171421, Eliot Aggregate Plant,
1544 Stanley Blvd., Pleasanton, CA 94566 – Case Closure


Dear Mr. Aldenhuisen:

This letter confirms the completion of a site investigation and remedial action for the underground storage tanks formerly located at the above-described location. Thank you for your cooperation throughout this investigation. Your willingness and promptness in responding to our inquiries concerning the former underground storage tank(s) are greatly appreciated.

Based on information in the above-referenced file and with the provision that the information provided to this agency was accurate and representative of site conditions, this agency finds that the site investigation and corrective action carried out at your underground storage tank(s) site is in compliance with the requirements of subdivisions (a) and (b) of Section 25296.10 of the Health and Safety Code and with corrective action regulations adopted pursuant to Section 25299.3 of the Health and Safety Code and that no further action related to the petroleum release(s) at the site is required.

This notice is issued pursuant to subdivision (h) of Section 25296.10 of the Health and Safety Code. Please contact our office if you have any questions regarding this matter.

Sincerely,



Ariu Levi
Director
Alameda County Environmental Health

**CASE CLOSURE SUMMARY
LEAKING UNDERGROUND FUEL STORAGE TANK - LOCAL OVERSIGHT PROGRAM**

I. AGENCY INFORMATION

Date: April 29, 2008

| | |
|--|--|
| Agency Name: Alameda County Environmental Health | Address: 1131 Harbor Bay Parkway |
| City/State/Zip: Alameda, CA 94502-6577 | Phone: (510) 567-6791 |
| Responsible Staff Person: Jerry Wickham | Title: Senior Hazardous Materials Specialist |

II. CASE INFORMATION

| Site Facility Name: RMC Pacific Materials/Eliot Aggregate | | |
|---|---|-------------------------|
| Site Facility Address: 1544 Stanley Boulevard, Pleasanton, CA 94566 | | |
| RB Case No.: --- | Local Case No.: --- | LOP Case No.: RO0002603 |
| URF Filing Date: 01/09/2004 | Geotracker ID: T0600171421 | APN: 946-1350-009-09 |
| Responsible Parties | Addresses | Phone Numbers |
| Robert Aldenhuysen, RMC Pacific Materials dba CEMEX | 5180 Golden Foothill Parkway, Suite 200, El Dorado Hills, CA 95762-9608 | 925-426-2261 |
| | | |
| | | |

| Tank I.D. No | Size in Gallons | Contents | Closed In Place/Removed? | Date |
|--------------|-----------------|----------|--------------------------|------------|
| 1 | 10,000 gallons | Gasoline | Removed | 01/11/2007 |
| 2 | 10,000 gallons | Diesel | Removed | 01/11/2007 |
| | | | | --- |
| | | | | |
| Piping | | | Repaired/upgraded | 11/20/2003 |

III. RELEASE AND SITE CHARACTERIZATION INFORMATION

| | |
|--|---|
| Cause and Type of Release: Unknown. No holes, cracks, or other signs of failure were observed in the tanks during removal. | |
| Site characterization complete? Yes | Date Approved By Oversight Agency: ---- |

| | | |
|--|---------------------------|---|
| Monitoring wells installed? No | Number: 0 | Proper screened interval? NA |
| Highest GW Depth Below Ground Surface: 55 feet bgs | Lowest Depth: 61 feet bgs | Flow Direction: Presumed to west towards Shadow Cliffs Lake |
| Most Sensitive Current Use: Drinking water source. | | |

| | |
|--|---|
| <p>Summary of Production Wells in Vicinity: The nearest water supply well (3S/1E 14K2) is located approximately 500 feet east of the former gasoline UST and 425 feet north of the former diesel UST. Well 3S/1E 14K2 is 508 feet deep and is screened from 120 to 480 feet bgs. Water supply well 3S/1E 14J1 is located approximately 1,400 feet east of the former diesel UST and 1,900 feet southeast north of the former gasoline UST. Based on the upgradient or cross gradient locations of the wells and the apparent absence of an impact to groundwater from the fuel release, the wells are not expected to be receptors for the site.</p> | |
| Are drinking water wells affected? No | Aquifer Name: Amador Subbasin of Livermore-Amador Groundwater Basin |
| Is surface water affected? No | Nearest SW Name: Shadow Cliffs Lake is approximately 250 feet west of the former gasoline tank and approximately 550 feet west of the former diesel tank. |
| Off-Site Beneficial Use Impacts (Addresses/Locations): None | |
| Reports on file? Yes | Where are reports filed? Alameda County Environmental Health and Livermore-Pleasanton Fire Department |

| TREATMENT AND DISPOSAL OF AFFECTED MATERIAL | | | |
|---|-------------------------|--|--------------|
| Material | Amount (Include Units) | Action (Treatment or Disposal w/Destination) | Date |
| Tank | Two 10,000-gallon tanks | Tanks were transported to Ecology Control industries in Richmond, CA for disposal. | 01/11/2007 |
| Piping | Not reported | Piping was transported to Ecology Control industries in Richmond, CA for disposal. | 01/11/2007 |
| Free Product | --- | --- | --- |
| Soil | Two 55-gallon drums | Off-site disposal destination not reported. | Not reported |
| Groundwater | --- | --- | --- |

MAXIMUM DOCUMENTED CONTAMINANT CONCENTRATIONS BEFORE AND AFTER CLEANUP
 (Please see Attachments 1 through 6 for additional information on contaminant locations and concentrations)

| Contaminant | Soil (ppm) | | Water (ppb) | |
|-------------------|------------|------------|-------------|---------|
| | Before | After | Before | After |
| TPH (Gas) | 2,300 | <0.05 | <50 | <50 |
| TPH (Diesel) | 12 | <0.05 | <50 | <50 |
| Oil and Grease | NA | NA | NA | NA |
| Benzene | 12 | <0.0005 | <0.5 | <0.5 |
| Toluene | 110 | <0.0005 | <2 | <2 |
| Ethylbenzene | 53 | <0.0005 | <0.5 | <0.5 |
| Xylenes | 260 | <0.0005 | <0.5 | <0.5 |
| Lead | NA | NA | NA | NA |
| MTBE | 71(1) | <0.0005(2) | <0.5(3) | <0.5(3) |
| Other (8240/8270) | NA(4) | NA(4) | NA(4) | NA(4) |

- (1) DIPE, ETBE, TAME, EDB, and EDC <0.005 ppm; TBA <0.01 ppm in soil.
 (2) DIPE, ETBE, EDB, and EDC <0.0005 ppm; TAME and TBA <0.002 ppm in soil.
 (3) DIPE, ETBE, EDB, and EDC <0.5 ppb; TAME and TBA <2 ppb in groundwater.
 (4) No analysis for other VOCs or SVOCs.

Site History and Description of Corrective Actions:

This fuel leak case is for unauthorized releases from one former gasoline underground storage tank (UST) and one former diesel UST located at the Eliot Aggregate Plant in Pleasanton, CA. The former gasoline UST was approximately 60 feet northwest of the scalehouse office and the diesel UST was approximately 50 feet north of the Shop Building. The two USTs are approximately 600 feet apart. The Eliot Aggregate Plant is an active industrial facility that is bordered by Stanley Boulevard on the north and former quarried areas now filled with water to the west, south, and east. Shadow Cliffs Lake, which is operated by the East Bay Regional Park District, is west of the facility.

In November 2003, the gasoline and diesel fuel dispensers were upgraded with under-dispenser containment sumps. A soil sample collected beneath the gasoline dispenser contained 2,300 ppm of total petroleum hydrocarbons as gasoline (TPHg), 12 ppm of benzene, 110 ppm of toluene, 53 ppm of ethylbenzene, 260 ppm of xylenes and 71 ppm of MTBE. Contaminated gravelly fill with staining or odor was removed and placed in two 55-gallon drums for off-site disposal. RMC Pacific Materials requested that further investigation of the fuel release beneath the dispensers be postponed until the USTs were removed.

The gasoline and diesel USTs were removed on January 11, 2007. TPH as diesel was detected in two of the three soil samples collected from the diesel tank pit and stockpile at concentrations of 1.4 and 12 ppm, respectively. No other fuel hydrocarbons were detected in the three soil samples collected from the diesel tank pit. Fuel hydrocarbons were not detected in any of the four soil samples collected from the gasoline tank pit or stockpile.

Two direct push borings were advanced at the site on March 3, 2008. One soil boring was drilled northwest and within five feet of the former gasoline UST and the second boring was drilled west of the former diesel UST. No hydrocarbon odors, staining, or free product was observed in the continuously cored soil. Soil samples collected from the soil borings did not contain detectable concentrations of fuel hydrocarbons, oxygenates, or lead scavengers. Grab groundwater samples were collected from the borings at depths of approximately 55 to 65 feet bgs. TPH as gasoline, TPH as diesel, BTEX, fuel oxygenates, 1,2-dichloroethane, and ethylene dibromide were not detected in the groundwater samples.

Previous Releases at Eliot Aggregate Plant

Previous unauthorized releases of petroleum hydrocarbons that are separate from the above referenced case have occurred at Eliot Aggregate Plant. Fuel leak case RO0000613 (Geotracker Global ID T0600171421) was closed on June 25, 1993. Spills, Leaks, Investigations, and Cleanup case RO2690 (Geotracker Global ID T06019735827) was closed on February 16, 2001.



IV. CLOSURE

| | | |
|---|--------------------------|--------------------|
| Does completed corrective action protect existing beneficial uses per the Regional Board Basin Plan? Yes | | |
| Does completed corrective action protect potential beneficial uses per the Regional Board Basin Plan? Yes | | |
| Does corrective action protect public health for current land use? Alameda County Environmental Health staff does not make specific determinations concerning public health risk. However, based upon the information available in our files to date, it does not appear that the release would present a risk to human health based upon current and projected future land use and conditions. | | |
| Site Management Requirements: None | | |
| Should corrective action be reviewed if land use changes? No | | |
| Was a deed restriction or deed notification filed? No | | Date Recorded: -- |
| Monitoring Wells Decommissioned: NA | Number Decommissioned: 0 | Number Retained: 0 |
| List Enforcement Actions Taken: None | | |
| List Enforcement Actions Rescinded: -- | | |

V. ADDITIONAL COMMENTS, DATA, ETC.

| |
|---|
| <p>Considerations and/or Variances:</p> <p>None.</p> <p>Conclusion:</p> <p>Alameda County Environmental Health staff believe that the levels of residual contamination do not pose a significant threat to water resources, public health and safety, and the environment based upon the information available in our files to date. No further investigation or cleanup is necessary. ACEH staff recommend case closure for this site.</p> |
|---|

VI. LOCAL AGENCY REPRESENTATIVE DATA

| | |
|--|---|
| Prepared by: Jerry Wickham | Title: Senior Hazardous Materials Specialist |
| Signature:  | Date: 05/06/08 |
| Approved by: Donna L. Drogos, P.E. | Title: Supervising Hazardous Materials Specialist |
| Signature:  | Date: 05/06/08 |

| |
|---|
| This closure approval is based upon the available information and with the provision that the information provided to this agency was accurate and representative of site conditions. |
|---|

VII. REGIONAL BOARD NOTIFICATION

| | |
|--|------------------------------|
| Regional Board Staff Name: Cherie McCaulou | Title: Engineering Geologist |
| RB Response: Concur, based solely upon information contained in this case closure summary. | Date Submitted to RB: |
| Signature: <i>Cher McCaulou</i> | Date: 5/13/08 |


VIII. MONITORING WELL DECOMMISSIONING

| | | |
|---|---|--------------------|
| Date Requested by ACEH: NA | Date of Well Decommissioning Report: NA | |
| All Monitoring Wells Decommissioned: NA | Number Decommissioned: 0 | Number Retained: 0 |
| Reason Wells Retained: NA | | |
| Additional requirements for submittal of groundwater data from retained wells: NA | | |
| ACEH Concurrence - Signature: <i>Jay Wickham</i> | Date: 06/25/08 | |

Attachments:

1. Plant Vicinity Map (1 page)
2. Site Map Showing Former Underground Storage Tank Locations and Elliot Fuel System Removals Figure (2 pages)
3. Site Map Showing Location of Newly Installed Temporary Boreholes and Figure 1: Site Vicinity Map (2 pages)
4. Soil Analytical Data (3 pages)
5. Groundwater Analytical Data (1 page)
6. Boring Logs (6 pages)

This document and the related CASE CLOSURE LETTER & REMEDIAL ACTION COMPLETION CERTIFICATE shall be retained by the lead agency as part of the official site file.



CEMEX

FIGURE 1 - Plant Vicinity Map

| | | | |
|-----------|-----------------------|------|-------|
| 7/16/2007 | Eliot Drill Project 1 | R.A. | Rev.1 |
|-----------|-----------------------|------|-------|








Figure 2: Site Map Showing Former Underground Storage Tank Locations




Eliot Fuel System Removals

1544 Stanley Blvd. Pleasanton, California 94566

5180 Golden Foothill Parkway, Suite 200, El Dorado Hills, CA. 95762-9608

| DATE | SCALE | DRAWN | FILE | REV. |
|---------|--------------|-------|--------------------|------|
| 3/29/07 | Not to Scale | RA | ELIOT UST Removals | 4 |



◆ Locations of Installed Soil Borings

Figure 3: Site Map Showing Location of Newly Installed Temporary Boreholes





approximate scale in feet




Figure 1: Site Vicinity Map

Table 1
March 3, 2008
Soil Analytical Results, TPH-g, TPH-d, BTEX, & MtBE
1544 Stanley Blvd., Pleasanton, CA

| Well | Sample | TPH-g (µg/L) | TPH-d (µg/L) | Benzene (µg/L) | Toluene (µg/L) | Ethyl- Benzene (µg/L) | Total Xylenes (µg/L) | MtBE* (µg/L) EPA 8260B | TBA (µg/L) | DIPE (µg/L) | ETBE (µg/L) | TAME (µg/L) | 1,2- DCA (µg/L) | EDB (µg/L) |
|------|-----------|-----------------|-----------------|-------------------|-------------------|-----------------------------|----------------------------|---------------------------------|---------------|----------------|----------------|----------------|-----------------------|---------------|
| SB-1 | 10 ft bgs | <50.0 | <50.0 | <0.5 | <2.0 | <0.5 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 |
| | 60 ft bgs | <50.0 | <50.0 | <0.5 | <2.0 | <0.5 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 |
| SB-2 | 15 ft bgs | <50.0 | <50.0 | <0.5 | <2.0 | <0.5 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 |
| | 50 ft bgs | <50.0 | <50.0 | <0.5 | <2.0 | <0.5 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 |

<: Not detected above laboratory reporting limits.

Units = µg / kg



Table 1
Eliot Aggregate Plant
Results of Analysis
Fuel Tank Excavations - Soil Sampling

| Sample Date | Sample ID | Sample Depth ¹ | Benzene (mg/Kg) | Toluene (mg/Kg) | Ethyl-benzene (mg/Kg) | Xylene (mg/Kg) | MTBE (mg/Kg) | TAME (mg/Kg) | TBA (mg/Kg) | DIPE (mg/Kg) | ETBE (mg/Kg) | Diesel (mg/Kg) |
|-------------|-----------|---------------------------|-----------------|-----------------|-----------------------|----------------|--------------|--------------|-------------|--------------|--------------|----------------|
| 1/11/2007 | C-1 | 10.5 | ND | ND | ND | ND | ND | ND | ND | ND | ND | 1.4 |
| 1/11/2007 | C-2 | 10.5 | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| 1/11/2007 | SP-1 | Composite | ND | ND | ND | ND | ND | ND | ND | ND | ND | 12 |
| 1/11/2007 | C-3 | 13 | ND | ND | ND | ND | ND | ND | ND | ND | ND | NA |
| 1/11/2007 | C-4 | 13 | ND | ND | ND | ND | ND | ND | ND | ND | ND | NA |
| 1/11/2007 | C-5 | 4 | ND | ND | ND | ND | ND | ND | ND | ND | ND | NA |
| 1/11/2007 | SP-2 | Composite | ND | ND | ND | ND | ND | ND | ND | ND | ND | NA |

Notes:

¹ = Feet below surface grade

NA = Not analyzed.

ND = Non-detect; below detection limits of laboratory for that analyte.

Table 2
Eliot Aggregate Plant
Results of Analysis - Gas/BTEX Compounds
Gasoline System
Under Dispenser Soil Sampling (Historic)

| Sample Date | Sample ID | Sample Depth ¹ | Gasoline (mg/Kg) | Benzene (mg/Kg) | Toluene (mg/Kg) | Ethyl-benzene (mg/Kg) | Xylene (mg/Kg) | MTBE (mg/Kg) |
|-------------|-----------|---------------------------|------------------|-----------------|-----------------|-----------------------|----------------|--------------|
| 11/20/2003 | G-1 | 3 | 2300 | 12 | 110 | 53 | 260 | 71 |

Notes:

¹ = feet below surface grade

Table 2
March 3, 2008
Groundwater Analytical Results, TPH-g, TPH-d, BTEX, & MtBE
1544 Stanley Blvd., Pleasanton, CA

| Well | TPH-g (µg/L) | TPH-d (µg/L) | Benzene (µg/L) | Toluene (µg/L) | Ethyl- Benzene (µg/L) | Total Xylenes (µg/L) | MtBE* (µg/L) EPA 8260B | TBA (µg/L) | DIPE (µg/L) | ETBE (µg/L) | TAME (µg/L) | 1,2-DCA (µg/L) | EDB (µg/L) |
|------|-----------------|-----------------|-------------------|-------------------|-----------------------------|----------------------------|---------------------------------|---------------|----------------|----------------|----------------|-------------------|---------------|
| SB-1 | <50.0 | <50.0 | <0.5 | <2.0 | <0.5 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 |
| SB-2 | <50.0 | <50.0 | <0.5 | <2.0 | <0.5 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 | <2.0 | <0.5 | <0.5 |

<: Not detected above laboratory reporting limits.





PROJECT:3042

DATE DRILLED: March 8, 2008

SITE LOCATION: 1544 Stanley Blvd., Pleasanton

CASING ELEVATION: N/A

DRILLER: WDC Exploration & Wells

DEPTH TO GW: 60 Feet

DRILLING METHOD: HSA

T.O.C. TO SCREEN: N/A

BORING DIAMETER: 8"

SCREEN LENGTH: N/A

LOGGED BY: E. Hightower

APPROVED BY: Mansour Sephr Ph.D., P.E.

| PID ppm | DEPTH | GRAPHIC LOG | SOIL CLASS | GEOLOGIC DESCRIPTION | SPLIT SPOON CORE | SAMPLED | GW LEVEL | BLOWCOUNTS | WELL DIAGRAM |
|---------|-------|-------------|------------|--|------------------|---------|----------|------------------|--------------|
| | 5 | | GR | PEA GRAVEL: Dark gray, moist, loose, fine-grained gravel, no PHC odor | | | | | |
| | 10 | | SW | SANDY GRAVEL: Brown, loose, moist, coarse-grained gravel, fine-to medium grained sand, no PHC odor | | X | | 10 10/ 10" | |
| | 15 | | | | | | | | |
| | 20 | | | | | | | | |
| | 25 | | | | | | | | |

COMMENTS:





PROJECT: 3042

DATE DRILLED: March 3, 2008

SITE LOCATION: 1544 Stanley Blvd.,
Pleasanton

CASING ELEVATION: N/A

DRILLER: WDC

DEPTH TO GW: 60 Ft.

DRILLING METHOD: HSA

T.O.C. TO SCREEN: N/A

BORING DIAMETER: 8"

SCREEN LENGTH: N/A

LOGGED BY: E. Hightower

APPROVED BY: M. Sepehr, Ph.D., P.E.

| PID ppm | DEPTH | GRAPHIC LOG | SOIL CLASS | GEOLOGIC DESCRIPTION | SPLIT SPOON CORE | SAMPLED | GW LEVEL | BLOWCOUNTS | WELL DIAGRAM |
|---------|-------|-------------|------------|---|---------------------|---------|----------|------------|-----------------|
| | | | | | | | | | |
| | 30 | | SW | SILTY GRAVEL: Brown, loose, moist, coarse-grained gravel, No PHC odor | | | | | |
| | 35 | | SW | SILTY GRAVEL: As above, no PHC odor | | | | | |
| | 45 | | CL/SC | SANDY CLAY: Dark brown, soft, moist, fine- to coarse-grained sand, some coarse-grained gravel, no PHC odor | | | | | |
| | 50 | | | | | | | | |

COMMENTS:



PROJECT: 3042

DATE DRILLED: March 3, 2008

SITE LOCATION: 1544 Stanley Blvd.,
Pleasanton

CASING ELEVATION: N/A

DRILLER: WDC

DEPTH TO GW: 60 Ft

DRILLING METHOD: HSA

T.O.C. TO SCREEN: N/A

BORING DIAMETER: 8"

SCREEN LENGTH: N/A

LOGGED BY: E. Hightower

APPROVED BY: M. Sepehr, Ph.D., P.E.

| PID ppm | DEPTH | GRAPHIC LOG | SOIL CLASS | GEOLOGIC DESCRIPTION | SPLIT SPOON CORE | SAMPLED | GW LEVEL | BLOWCOUNTS | WELL DIAGRAM |
|---------|-------|-------------|------------|--|---------------------|---------|----------|-----------------|-----------------|
| | 55 | | CL/SC | SANDY CLAY: Dark brown, soft, moist, fine- to coarse-grained sand, some coarse-grained gravel, No PHC odor | | X | ▽ | 23 35/ 40 | |
| | 60 | | | | | | | | |
| | 65 | | | | | | | | |
| | 70 | | | | | | | | |
| | 75 | | | | | | | | |

COMMENTS: TD @ 65'



PROJECT: 3042

DATE DRILLED: March 3, 2008

SITE LOCATION: 1544 Stanley Blvd.,
Pleasanton

CASING ELEVATION: N/A

DRILLER: WDC

DEPTH TO GW: 55 Ft.

DRILLING METHOD: HSA

T.O.C. TO SCREEN: N/A

BORING DIAMETER: 8"

SCREEN LENGTH: N/A

LOGGED BY: E. Hightower

APPROVED BY: Mansour Sepehr, Ph.D., P.E.

| PID ppm | DEPTH | GRAPHIC LOG | SOIL CLASS | GEOLOGIC DESCRIPTION | SPLIT SPOON CORE | SAMPLED | GW LEVEL | BLOWCOUNTS | WELL DIAGRAM |
|---------|-------|-------------|------------|--|---------------------|---------|----------|-----------------|-----------------|
| | 5 | | GR | PEA GRAVEL: Dark gray, moist, loose, fine-grained gravel, no PHC odor | | | | | |
| | 15 | | SW | SANDY GRAVEL: Dark gray, loose, moist, fine- to coarse-grained sand, fine- to coarse-grained gravel, no PHC odor | | X | | 11 23/ 30 | |
| | 20 | | SC | SANDY CLAY: Dark Brown, soft, moist, fine- to coarse-grained sand, some coarse-grained gravel, no PHC odor | | | | | |
| | 25 | | | | | | | | |

COMMENTS:



PROJECT: 3042

DATE DRILLED: March 3, 2008

SITE LOCATION: 1544 Stanley Blvd.
Pleasanton

CASING ELEVATION: N/A

DRILLER: WDC

DEPTH TO GW: 55 Ft.

DRILLING METHOD: HSA

T.O.C. TO SCREEN: N/A

BORING DIAMETER: 8"

SCREEN LENGTH: N/A

LOGGED BY: E. Hightower

APPROVED BY: M. Sepehr, Ph.D., P.E.

| PID ppm | DEPTH | GRAPHIC LOG | SOIL CLASS | GEOLOGIC DESCRIPTION | SPLIT SPOON CORE | SAMPLED | GW LEVEL | BLOWCOUNTS | WELL DIAGRAM | | |
|---------|-------|-------------|------------|--|------------------|---------|----------|------------|--------------|--|--|
| | 30 | | SC | SANDY CLAY: Dark Brown, soft, moist, fine- to coarse-grained sand, some coarse-grained gravel, no PHC odor | | | | | | | |
| | 35 | | | | | | | | | | |
| | 40 | | | | | | | | | | |
| | 45 | | | | | | | | | | |
| | 50 | | | | | | | | | | |

COMMENTS:



PROJECT: 3042

DATE DRILLED: March 3, 2008

SITE LOCATION: 1544 Stanley Blvd.,
Pleasanton

CASING ELEVATION: N/A

DRILLER: WDC

DEPTH TO GW: 55 Ft

DRILLING METHOD: HSA

T.O.C. TO SCREEN: N/A

BORING DIAMETER: 8"

SCREEN LENGTH: N/A

LOGGED BY: E. Hightower

APPROVED BY: M. Sepehr, Ph.D., P.E.

| PID ppm | DEPTH | GRAPHIC LOG | SOIL CLASS | GEOLOGIC DESCRIPTION | SPLIT SPOON CORE | SAMPLED | GW LEVEL | BLOWCOUNTS | WELL DIAGRAM |
|---------|-------|-------------|------------|--|------------------|---------|----------|------------|--------------|
| | 55 | | SW | SANDY GRAVEL: Dark gray, loose, moist, fine- to coarse-grained sand, fine- to coarse-grained gravel, no PHC odor | X | | ▽ | | |
| | 60 | | | | | | | | |
| | 65 | | | | | | | | |
| | 70 | | | | | | | | |
| | 75 | | | | | | | | |

COMMENTS: TD @ 60 Ft.