

RECEIVED

By Alameda County Environmental Health 3:17 pm, Jan 25, 2017

January 20, 2016

Subject: Baker Road Redevelopment
20785 and 20957 Baker Road (Case #RO0003234)
Castro Valley, California

ACKNOWLEDGEMENT STATEMENT

I have read and acknowledge the content, recommendations and/or conclusions contained in the attached document or report submitted on my behalf to ACDEH's FTP server and the State Water Resources Control Board's GeoTracker website.



Todd Deutscher
Catalyst Development Partners

Project No.
13255.000.000

August 31, 2016

Mr. Todd Deutscher
Catalyst Development Partners
18 Crow Canyon Court, Suite 190
San Ramon, CA 94583

Subject: 20785 Baker Road
Castro Valley, California

PHASE II ENVIRONMENTAL SITE ASSESSMENT

Reference: ENGEO, Phase I Environmental Site Assessment, 20785 Baker Road, Castro Valley, California, Project Number 13255.000.000, August 23, 2016 (DRAFT).

Dear Mr. Deutscher:

We are pleased to submit the findings from our phase II environmental site assessment conducted at the subject property (Property) in Castro Valley, California (Property). The purpose of the phase II assessment was to evaluate potential environmental concerns identified in the Phase I ESA conducted for the Property (Reference), associated with the past uses on the Property.

BACKGROUND

Site Description

The Property is located southwest of Baker Road, northeast of Rutledge Road, and southeast of Castro Valley Boulevard in Castro Valley, California (Figure 1). The Property, measuring approximately 0.56 acres in area, is identified with Assessor's Parcel Number (APN) 84A-16-5-9.

The Property, 20785 Baker Road, features two remnant building foundation slabs, a house, and part of the neighboring property south of the chain link fence that is a majority dirt- or asphalt-covered with overgrown vegetation.

Multi-family housing is present in the vicinity to the north and south of the Property. An automotive shop is present to the west, and multi-family housing occupies the properties to the east of Baker Road.

Previous Studies

ENGEO, Phase I Environmental Site Assessment, 20785 Baker Road, Castro Valley, California, Project Number 13255.000.000, August 23, 2016 (DRAFT).

ENGEO conducted a concurrent phase I environmental site assessment for the Property in August 2016. The Property was reportedly used as a corporation yard/storage area for heavy equipment. Prior to development in the 1950s, the Property appeared to be under cultivation for row crops surrounding the single-family residential structures.

Based on the findings of the ENGEO phase I assessment and previous assessments of the Property, the following potential environmental concerns were identified for the Property:

- Although the former leaking USTs at the parcel to the south were removed and a case closure was subsequently granted, information in the former case file indicated that potential risks via vapor intrusion may not have been adequately assessed during past characterization activities.
- Historical records for the Property indicated the Property was under agricultural cultivation in the past. Recalcitrant agricultural chemicals could be present in near-surface soils.
- Lead-based paint and/or asbestos-containing building materials may be present within structures at the Property.

A phase II environmental assessment was recommended for the Property to evaluate potential impacts to near surface soil due to the past agricultural activity.

SITE CHARACTERIZATION

Field sampling activities performed on August 19 and August 25, 2016 included soil sampling on the Property. Soil and soil gas sampling were performed in the parcel to the south of the Property that showed impacts from for USTs and agricultural activity on the parcel.

Prior to drilling, an ENGEO representative contacted the USA North Service Alert to be notified of the location of underground utilities at the site. In addition, ENGEO retained a private utility locator to mark the boring locations. A C-57 licensed drilling contractor was retained to advance soil and soil gas borings (Figure 2). A boring permit was obtained from the Alameda County Public Works Agency (ACPWA). Details pertaining to each of these tasks are presented below.

Task 1 – Soil Sampling

Soil samples were collected from a total of six locations across the Property. The soil borings, S-2 and S-3, were advanced to a total depth of 2 feet below ground surface using a Geoprobe® direct-push rig. Continuous soil cores were retrieved from each boring. Soil samples were collected at approximate depths of 3 to 9 inches and 12 to 18 inches below the ground surface from each of the borings. The remaining soil borings were advanced to 9 inches using a hand auger. Samples were collected at the approximate depth of 3 to 9 inches below the ground surface.

For samples collected using the Geoprobe®, the sample sleeves were sealed using Teflon® sheets secured by tight-fitting plastic end caps. The remaining samples were collected in 4-ounce glass jars. Upon collection of samples, a sample label was placed on the sample including a unique sample number, sample location, time/date collected, lab analysis and the sampler's identification. The soil samples were placed in an ice-cooled chest and submitted under documented chain-of-custody to Torrent Laboratory, Inc., a State-certified laboratory based in Milpitas, California. Soil samples from each boring were analyzed for the following:

- Organochlorine pesticides (EPA Method 8081)
- Lead and arsenic (EPA Method 6010)

The deeper samples from locations S-2 and S-3 were held by the laboratory pending the results of the shallower samples. The borings were filled with grout upon completion of sampling.

ANALYTICAL RESULTS

Soil Sampling

Locations S-7 and S-8 were the only sampling locations that exhibited low levels of detectable concentrations of organochlorine pesticides. The analytes that were detected includes gamma-Chlordane, alpha-Chlordane, 4,4-DDE, dieldrin, 4,4-DDT, Heptachlor Epoxide and Chlordane. All collected soil samples exhibited detectable lead concentrations; the detected concentrations ranged between 6.49 and 49.6 milligrams per kilogram (mg/kg). These concentrations are below the respective screening level assuming a residential land use scenario¹.

Detected arsenic concentrations in the collected soil samples ranged between 3.88 and 27.3 mg/kg. This is in excess of the respective arsenic screening level assuming a residential land use scenario and is in excess of expected background concentrations observed in the San Francisco Bay Area.

Table A provides a summary of the laboratory analyses for the soil samples. The laboratory results are presented in their entirety in Appendix A.

DISCUSSION & CONCLUSION

Review of the laboratory test results found detectable concentrations of lead, arsenic and select organochlorine pesticides in surface soils. Given the reported arsenic and pesticide concentrations, it appears the surface soil at the Property has been impacted from historic agricultural activities. The presence of the pesticide-impacted soil will likely necessitate mitigation to allow for residential re-development of the Property. Additional sampling should be considered to better define the lateral extent and depth of the soil impact at the Property, and an excavation and off-site disposal program should be considered. The impacted soils likely would be classified for disposal at a Class II landfill disposal facility.

¹ Regional Water Quality Control Board, Soil Human Health Risk Screening Levels Residential Land Use, Shallow Soil, Table S-1, February 2016 (Revision 3).


VOCs were detected in soil gas samples collected at 20957 Baker Road. As discussed, TPH-gasoline, ethylbenzene, and naphthalene were detected in soil gas concentrations in excess of odor nuisance and/or human risk levels. Given the presence of these elevated concentrations, a mitigation program, either in the form of environmental remediation (e.g., impacted soil removal, soil vapor extraction), or the use of a vapor intrusion mitigation system (VIMS), will likely be necessary to facilitate residential development at 20957 Baker Road. Please note that additional soil and soil gas characterization should be considered at 20785 Baker Road to help determine the extent of impact.

Given the presence of soil impact and potential presence of soil gas impact at the Property, consideration should be given to reviewing and selecting the remediation/mitigation program alternatives under the oversight of a regulatory agency. The specific framework and timing of the remedial approaches should also be discussed with an oversight agency as appropriate.

If you have any questions regarding this report, please contact us.

Sincerely,

ENGEO Incorporated


Jeffrey A. Adams, PhD, PE






Shawn Munger, CHG

Attachments: Figures 1 and 2
Table A
Appendix A – Laboratory Analysis Report

FIGURES

Figure 1 – Vicinity Map
Figure 2 – Site Plan

COPYRIGHT © 2016 BY ENGeo INCORPORATED. THIS DOCUMENT MAY NOT BE REPRODUCED IN WHOLE OR IN PART BY ANY MEANS WHATSOEVER, NOR MAY IT BE QUOTED OR EXCERPTED WITHOUT THE EXPRESS WRITTEN CONSENT OF ENGeo INCORPORATED.



BASE MAP SOURCE: GOOGLE EARTH MAPPING SERVICE



VICINITY MAP
20785 BAKER ROAD
CASTRO VALLEY, CALIFORNIA

PROJECT NO.: 13255.000.000

SCALE: AS SHOWN


DRAWN BY: LL

CHECKED BY: JA

FIGURE NO.

1

COPYRIGHT © 2016 BY EN GEO INCORPORATED. THIS DOCUMENT MAY NOT BE REPRODUCED IN WHOLE OR IN PART BY ANY MEANS WHATSOEVER, NOR MAY IT BE QUOTED OR EXCERPTED WITHOUT THE EXPRESS WRITTEN CONSENT OF EN GEO INCORPORATED.




EXPLANATION

ALL LOCATIONS ARE APPROXIMATE

S-8 SOIL SAMPLE (EN GEO, 2016)

BASE MAP SOURCE: GOOGLE EARTH MAPPING SERVICE

	<p>SITE PLAN</p> <p>20785 BAKER ROAD</p> <p>CASTRO VALLEY, CALIFORNIA</p>	<p>PROJECT NO.: 13255.000.000</p>	<p>FIGURE NO.</p>
		<p>SCALE: AS SHOWN</p>	<p>2</p>
		<p>DRAWN BY: LL CHECKED BY: JA</p>	

TABLES

Table A – Summary of Soil Analytical Results

TABLE A - SUMMARY OF SOIL LABORATORY ANALYSIS

Soil Sample	Date Collected	Arsenic	Lead	gamma-Chlordane	alpha-Chlordane	4,4-DDE	Dieldrin	4,4-DDT	Chlordane	Heptachlor Epoxide	Other OCPs
		mg/kg	mg/kg	µg/kg	µg/kg	µg/kg	µg/kg	µg/kg	µg/kg	µg/kg	µg/kg
RWQCB Environmental Screening Levels ¹		0.067	80	-	-	-	3.80E-02	1.90E+00	4.80E-01	6.70E-02	N/A
S-2@3-9"	8/19/2016	27.3	6.49	ND	ND	ND	ND	ND	ND	ND	ND
S-3@3-9"	8/19/2016	17.9	14.1	ND	ND	ND	ND	ND	ND	ND	ND
S-5@3-9"	8/24/2016	13.1	48.4	ND	ND	ND	ND	ND	ND	ND	ND
S-6@3-9"	8/24/2016	7.51	9.71	ND	ND	ND	ND	ND	ND	ND	ND
S-7@3-9"	8/24/2016	3.88	49.6	9.71	8.55	26.6	36.8	87.9	73.1	ND	ND
S-8@3-9"	8/24/2016	13.5	43.1	ND	ND	1.9	ND	8.03	ND	0.78	ND

Notes:

N/A- Not Applicable

ND- Not Detected

¹ Regional Water Quality Control Board, Soil Human Health Risk Screening Levels (Residential Land Use), Table S-1, February 2016 (Revision 3).

APPENDIX A

Laboratory Analysis Report



Engeo (San Ramon)
2010 Crow Canyon Place, #250
San Ramon, California 94583
Tel: (925) 866-9000
Fax: (925) 866-0199
RE: 20957 Baker Rd

Work Order No.: 1608182

Dear Divya Bhargava:

Torrent Laboratory, Inc. received 3 sample(s) on August 19, 2016 for the analyses presented in the following Report.

All data for associated QC met EPA or laboratory specification(s) except where noted in the case narrative.

Torrent Laboratory, Inc. is certified by the State of California, ELAP #1991. If you have any questions regarding these test results, please feel free to contact the Project Management Team at (408)263-5258; ext 204.

A handwritten signature in blue ink, appearing to read "Patti L. Sandroock", is written over a light blue horizontal line.

Patti L Sandroock
QA Officer

August 22, 2016

Date



Date: 8/22/2016

Client: Engeo (San Ramon)

Project: 20957 Baker Rd

Work Order: 1608182

CASE NARRATIVE

No issues encountered with the receiving, preparation, analysis or reporting of the results associated with this work order.

Unless otherwise indicated in the following narrative, no results have been method and/or field blank corrected.

Reported results relate only to the items/samples tested by the laboratory.

This report shall not be reproduced, except in full, without the written approval of Torrent Analytical, Inc.



Sample Result Summary

Report prepared for: Divya Bhargava
 Engeo (San Ramon)

Date Received: 08/19/16

Date Reported: 08/22/16

SG-1

1608182-001

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results ug/m3</u>
Acetone	ETO15	35	14	420	8500
2-Hexanone	ETO15	35	23	72	95
Ethyl Benzene	ETO15	35	22	76	3500
m,p-Xylene	ETO15	35	34	76	17000
o-Xylene	ETO15	35	11	76	5200
1,2,4-Trimethylbenzene	ETO15	35	21	86	88
TPH-Gasoline	TO-15	35	1400	6200	88100

SG-2

1608182-002

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results ug/m3</u>
Ethyl Benzene	ETO15	10	6.3	22	210
m,p-Xylene	ETO15	10	9.8	22	1100
o-Xylene	ETO15	10	3.0	22	370
1,2,4-Trichlorobenzene	ETO15	10	22	37	160
Acetone	ETO15	50	20	600	4900
TPH-Gasoline	TO-15	10	400	1800	15300

SG-3

1608182-003

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results ug/m3</u>
Acetone	ETO15	50	20	600	2500
2-Hexanone	ETO15	50	33	100	170
Ethyl Benzene	ETO15	50	31	110	3700
m,p-Xylene	ETO15	50	49	110	20000
o-Xylene	ETO15	50	15	110	7800
1,3,5-Trimethylbenzene	ETO15	50	15	120	2300
1,2,4-Trimethylbenzene	ETO15	50	30	120	5700
Naphthalene	ETO15	50	64	130	130
TPH-Gasoline	TO-15	50	2000	8800	245000



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-1	Lab Sample ID: 1608182-001A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 13:00	Certified Clean WO # :
Canister/Tube ID: A7464	Received PSI : 1.7
Collection Volume (L):	Corrected PSI : 12.2
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
Dichlorodifluoromethane	ETO15	35.00	55	87	ND	ND		08/19/16	20:06	BA	419413
1,1-Difluoroethane	ETO15	35.00	12	470	ND	ND		08/19/16	20:06	BA	419413
1,2-Dichlorotetrafluoroethane	ETO15	35.00	990	2000	ND	ND		08/19/16	20:06	BA	419413
Chloromethane	ETO15	35.00	72	140	ND	ND		08/19/16	20:06	BA	419413
Vinyl Chloride	ETO15	35.00	7.9	45	ND	ND		08/19/16	20:06	BA	419413
1,3-Butadiene	ETO15	35.00	12	39	ND	ND		08/19/16	20:06	BA	419413
Bromomethane	ETO15	35.00	23	68	ND	ND		08/19/16	20:06	BA	419413
Chloroethane	ETO15	35.00	28	46	ND	ND		08/19/16	20:06	BA	419413
Trichlorofluoromethane	ETO15	35.00	19	98	ND	ND		08/19/16	20:06	BA	419413
1,1-Dichloroethene	ETO15	35.00	29	69	ND	ND		08/19/16	20:06	BA	419413
Freon 113	ETO15	35.00	36	130	ND	ND		08/19/16	20:06	BA	419413
Carbon Disulfide	ETO15	35.00	13	54	ND	ND		08/19/16	20:06	BA	419413
2-Propanol (Isopropyl Alcohol)	ETO15	35.00	45	430	ND	ND		08/19/16	20:06	BA	419413
Methylene Chloride	ETO15	35.00	25	61	ND	ND		08/19/16	20:06	BA	419413
Acetone	ETO15	35.00	14	420	8500	3,571.43	E	08/19/16	20:06	BA	419413
trans-1,2-Dichloroethene	ETO15	35.00	17	69	ND	ND		08/19/16	20:06	BA	419413
Hexane	ETO15	35.00	16	62	ND	ND		08/19/16	20:06	BA	419413
MTBE	ETO15	35.00	16	63	ND	ND		08/19/16	20:06	BA	419413
tert-Butanol	ETO15	35.00	22	53	ND	ND		08/19/16	20:06	BA	419413
Diisopropyl ether (DIPE)	ETO15	35.00	26	73	ND	ND		08/19/16	20:06	BA	419413
1,1-Dichloroethane	ETO15	35.00	19	71	ND	ND		08/19/16	20:06	BA	419413
ETBE	ETO15	35.00	11	73	ND	ND		08/19/16	20:06	BA	419413
cis-1,2-Dichloroethene	ETO15	35.00	29	69	ND	ND		08/19/16	20:06	BA	419413
Chloroform	ETO15	35.00	34	85	ND	ND		08/19/16	20:06	BA	419413
Vinyl Acetate	ETO15	35.00	26	62	ND	ND		08/19/16	20:06	BA	419413
Carbon Tetrachloride	ETO15	35.00	39	110	ND	ND		08/19/16	20:06	BA	419413
1,1,1-Trichloroethane	ETO15	35.00	28	96	ND	ND		08/19/16	20:06	BA	419413
2-Butanone (MEK)	ETO15	35.00	14	52	ND	ND		08/19/16	20:06	BA	419413
Ethyl Acetate	ETO15	35.00	17	63	ND	ND		08/19/16	20:06	BA	419413
Tetrahydrofuran	ETO15	35.00	16	52	ND	ND		08/19/16	20:06	BA	419413
Benzene	ETO15	35.00	15	56	ND	ND		08/19/16	20:06	BA	419413
TAME	ETO15	35.00	24	73	ND	ND		08/19/16	20:06	BA	419413



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-1	Lab Sample ID: 1608182-001A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 13:00	Certified Clean WO # :
Canister/Tube ID: A7464	Received PSI : 1.7
Collection Volume (L):	Corrected PSI : 12.2
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
1,2-Dichloroethane (EDC)	ETO15	35.00	15	71	ND	ND		08/19/16	20:06	BA	419413
Trichloroethylene	ETO15	35.00	28	94	ND	ND		08/19/16	20:06	BA	419413
1,2-Dichloropropane	ETO15	35.00	27	81	ND	ND		08/19/16	20:06	BA	419413
Bromodichloromethane	ETO15	35.00	26	120	ND	ND		08/19/16	20:06	BA	419413
1,4-Dioxane	ETO15	35.00	63	130	ND	ND		08/19/16	20:06	BA	419413
trans-1,3-Dichloropropene	ETO15	35.00	37	79	ND	ND		08/19/16	20:06	BA	419413
Toluene	ETO15	35.00	26	66	ND	ND		08/19/16	20:06	BA	419413
4-Methyl-2-Pentanone (MIBK)	ETO15	35.00	26	72	ND	ND		08/19/16	20:06	BA	419413
cis-1,3-Dichloropropene	ETO15	35.00	15	79	ND	ND		08/19/16	20:06	BA	419413
Tetrachloroethylene	ETO15	35.00	51	120	ND	ND		08/19/16	20:06	BA	419413
1,1,2-Trichloroethane	ETO15	35.00	20	96	ND	ND		08/19/16	20:06	BA	419413
Dibromochloromethane	ETO15	35.00	39	150	ND	ND		08/19/16	20:06	BA	419413
1,2-Dibromoethane (EDB)	ETO15	35.00	26	130	ND	ND		08/19/16	20:06	BA	419413
2-Hexanone	ETO15	35.00	23	72	95	23.17		08/19/16	20:06	BA	419413
Ethyl Benzene	ETO15	35.00	22	76	3500	806.45		08/19/16	20:06	BA	419413
Chlorobenzene	ETO15	35.00	21	81	ND	ND		08/19/16	20:06	BA	419413
1,1,1,2-Tetrachloroethane	ETO15	35.00	29	120	ND	ND		08/19/16	20:06	BA	419413
m,p-Xylene	ETO15	35.00	34	76	17000	3,917.05		08/19/16	20:06	BA	419413
o-Xylene	ETO15	35.00	11	76	5200	1,198.16		08/19/16	20:06	BA	419413
Styrene	ETO15	35.00	16	75	ND	ND		08/19/16	20:06	BA	419413
Bromoform	ETO15	35.00	46	180	ND	ND		08/19/16	20:06	BA	419413
1,1,2,2-Tetrachloroethane	ETO15	35.00	29	120	ND	ND		08/19/16	20:06	BA	419413
4-Ethyl Toluene	ETO15	35.00	19	86	ND	ND		08/19/16	20:06	BA	419413
1,3,5-Trimethylbenzene	ETO15	35.00	11	86	ND	ND		08/19/16	20:06	BA	419413
1,2,4-Trimethylbenzene	ETO15	35.00	21	86	88	17.89		08/19/16	20:06	BA	419413
1,4-Dichlorobenzene	ETO15	35.00	26	110	ND	ND		08/19/16	20:06	BA	419413
1,3-Dichlorobenzene	ETO15	35.00	47	110	ND	ND		08/19/16	20:06	BA	419413
1,2-Dichlorobenzene	ETO15	35.00	37	110	ND	ND		08/19/16	20:06	BA	419413
Hexachlorobutadiene	ETO15	35.00	65	190	ND	ND		08/19/16	20:06	BA	419413
1,2,4-Trichlorobenzene	ETO15	35.00	75	130	ND	ND		08/19/16	20:06	BA	419413
Naphthalene	ETO15	35.00	45	92	ND	ND		08/19/16	20:06	BA	419413
(S) 4-Bromofluorobenzene	ETO15	35.00	65	135	93 %			08/19/16	20:06	BA	419413



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	SG-1	Lab Sample ID:	1608182-001A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Air
Project Number:	13255.000.000	Certified Clean WO # :	
Date/Time Sampled:	08/19/16 / 13:00	Received PSI :	1.7
Canister/Tube ID:	A7464	Corrected PSI :	12.2
Collection Volume (L):			
SDG:			

Prep Method: TO15-GRO	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1841	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
TPH-Gasoline	TO-15	35.00	1400	6200	88100	25,028.41	x	08/19/16	18:37	BA	419423

NOTE: x-not a match to Gas reference std but within C5-C12 quantitation range (possibly aged gasoline)



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-2	Lab Sample ID: 1608182-002A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 11:30	Certified Clean WO # :
Canister/Tube ID: 6116	Received PSI : 13.4
Collection Volume (L):	Corrected PSI :
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
Dichlorodifluoromethane	ETO15	10.00	16	25	ND	ND		08/19/16	18:18	BA	419413
1,1-Difluoroethane	ETO15	10.00	3.5	140	ND	ND		08/19/16	18:18	BA	419413
1,2-Dichlorotetrafluoroethane	ETO15	10.00	280	560	ND	ND		08/19/16	18:18	BA	419413
Chloromethane	ETO15	10.00	20	41	ND	ND		08/19/16	18:18	BA	419413
Vinyl Chloride	ETO15	10.00	2.3	13	ND	ND		08/19/16	18:18	BA	419413
1,3-Butadiene	ETO15	10.00	3.4	11	ND	ND		08/19/16	18:18	BA	419413
Bromomethane	ETO15	10.00	6.6	19	ND	ND		08/19/16	18:18	BA	419413
Chloroethane	ETO15	10.00	8.1	13	ND	ND		08/19/16	18:18	BA	419413
Trichlorofluoromethane	ETO15	10.00	5.6	28	ND	ND		08/19/16	18:18	BA	419413
1,1-Dichloroethene	ETO15	10.00	8.3	20	ND	ND		08/19/16	18:18	BA	419413
Freon 113	ETO15	10.00	10	38	ND	ND		08/19/16	18:18	BA	419413
Carbon Disulfide	ETO15	10.00	3.7	16	ND	ND		08/19/16	18:18	BA	419413
2-Propanol (Isopropyl Alcohol)	ETO15	10.00	13	120	ND	ND		08/19/16	18:18	BA	419413
Methylene Chloride	ETO15	10.00	7.0	17	ND	ND		08/19/16	18:18	BA	419413
trans-1,2-Dichloroethene	ETO15	10.00	4.8	20	ND	ND		08/19/16	18:18	BA	419413
Hexane	ETO15	10.00	4.6	18	ND	ND		08/19/16	18:18	BA	419413
MTBE	ETO15	10.00	4.4	18	ND	ND		08/19/16	18:18	BA	419413
tert-Butanol	ETO15	10.00	6.2	15	ND	ND		08/19/16	18:18	BA	419413
Diisopropyl ether (DIPE)	ETO15	10.00	7.4	21	ND	ND		08/19/16	18:18	BA	419413
1,1-Dichloroethane	ETO15	10.00	5.4	20	ND	ND		08/19/16	18:18	BA	419413
ETBE	ETO15	10.00	3.3	21	ND	ND		08/19/16	18:18	BA	419413
cis-1,2-Dichloroethene	ETO15	10.00	8.3	20	ND	ND		08/19/16	18:18	BA	419413
Chloroform	ETO15	10.00	9.7	24	ND	ND		08/19/16	18:18	BA	419413
Vinyl Acetate	ETO15	10.00	7.6	18	ND	ND		08/19/16	18:18	BA	419413
Carbon Tetrachloride	ETO15	10.00	11	31	ND	ND		08/19/16	18:18	BA	419413
1,1,1-Trichloroethane	ETO15	10.00	7.9	27	ND	ND		08/19/16	18:18	BA	419413
2-Butanone (MEK)	ETO15	10.00	3.9	15	ND	ND		08/19/16	18:18	BA	419413
Ethyl Acetate	ETO15	10.00	4.8	18	ND	ND		08/19/16	18:18	BA	419413
Tetrahydrofuran	ETO15	10.00	4.5	15	ND	ND		08/19/16	18:18	BA	419413
Benzene	ETO15	10.00	4.4	16	ND	ND		08/19/16	18:18	BA	419413
TAME	ETO15	10.00	6.7	21	ND	ND		08/19/16	18:18	BA	419413
1,2-Dichloroethane (EDC)	ETO15	10.00	4.2	20	ND	ND		08/19/16	18:18	BA	419413



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-2	Lab Sample ID: 1608182-002A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 11:30	Certified Clean WO # :
Canister/Tube ID: 6116	Received PSI : 13.4
Collection Volume (L):	Corrected PSI :
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
Trichloroethylene	ETO15	10.00	8.1	27	ND	ND		08/19/16	18:18	BA	419413
1,2-Dichloropropane	ETO15	10.00	7.6	23	ND	ND		08/19/16	18:18	BA	419413
Bromodichloromethane	ETO15	10.00	7.4	34	ND	ND		08/19/16	18:18	BA	419413
1,4-Dioxane	ETO15	10.00	18	36	ND	ND		08/19/16	18:18	BA	419413
trans-1,3-Dichloropropene	ETO15	10.00	11	23	ND	ND		08/19/16	18:18	BA	419413
Toluene	ETO15	10.00	7.5	19	ND	ND		08/19/16	18:18	BA	419413
4-Methyl-2-Pentanone (MIBK)	ETO15	10.00	7.5	21	ND	ND		08/19/16	18:18	BA	419413
cis-1,3-Dichloropropene	ETO15	10.00	4.2	23	ND	ND		08/19/16	18:18	BA	419413
Tetrachloroethylene	ETO15	10.00	15	34	ND	ND		08/19/16	18:18	BA	419413
1,1,2-Trichloroethane	ETO15	10.00	5.8	27	ND	ND		08/19/16	18:18	BA	419413
Dibromochloromethane	ETO15	10.00	11	43	ND	ND		08/19/16	18:18	BA	419413
1,2-Dibromoethane (EDB)	ETO15	10.00	7.4	38	ND	ND		08/19/16	18:18	BA	419413
2-Hexanone	ETO15	10.00	6.5	21	ND	ND		08/19/16	18:18	BA	419413
Ethyl Benzene	ETO15	10.00	6.3	22	210	48.39		08/19/16	18:18	BA	419413
Chlorobenzene	ETO15	10.00	6.0	23	ND	ND		08/19/16	18:18	BA	419413
1,1,1,2-Tetrachloroethane	ETO15	10.00	8.4	34	ND	ND		08/19/16	18:18	BA	419413
m,p-Xylene	ETO15	10.00	9.8	22	1100	253.46		08/19/16	18:18	BA	419413
o-Xylene	ETO15	10.00	3.0	22	370	85.25		08/19/16	18:18	BA	419413
Styrene	ETO15	10.00	4.6	21	ND	ND		08/19/16	18:18	BA	419413
Bromoform	ETO15	10.00	13	52	ND	ND		08/19/16	18:18	BA	419413
1,1,2,2-Tetrachloroethane	ETO15	10.00	8.2	34	ND	ND		08/19/16	18:18	BA	419413
4-Ethyl Toluene	ETO15	10.00	5.5	25	ND	ND		08/19/16	18:18	BA	419413
1,3,5-Trimethylbenzene	ETO15	10.00	3.0	25	ND	ND		08/19/16	18:18	BA	419413
1,2,4-Trimethylbenzene	ETO15	10.00	6.0	25	ND	ND		08/19/16	18:18	BA	419413
1,4-Dichlorobenzene	ETO15	10.00	7.5	30	ND	ND		08/19/16	18:18	BA	419413
1,3-Dichlorobenzene	ETO15	10.00	13	30	ND	ND		08/19/16	18:18	BA	419413
1,2-Dichlorobenzene	ETO15	10.00	11	30	ND	ND		08/19/16	18:18	BA	419413
Hexachlorobutadiene	ETO15	10.00	19	53	ND	ND		08/19/16	18:18	BA	419413
1,2,4-Trichlorobenzene	ETO15	10.00	22	37	160	21.56		08/19/16	18:18	BA	419413
Naphthalene	ETO15	10.00	13	26	ND	ND		08/19/16	18:18	BA	419413
(S) 4-Bromofluorobenzene	ETO15	10.00	65	135	99 %			08/19/16	18:18	BA	419413



SAMPLE RESULTS

Report prepared for: Divya Bhargava
 Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-2	Lab Sample ID: 1608182-002A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 11:30	Certified Clean WO # :
Canister/Tube ID: 6116	Received PSI : 13.4
Collection Volume (L):	Corrected PSI :
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
Acetone	ETO15	50.00	20	600	4900	2,058.82		08/19/16	20:31	BA	419413
(S) 4-Bromofluorobenzene	ETO15	50.00	65	135	97 %			08/19/16	20:31	BA	419413

Prep Method: TO15-GRO	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1841	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
TPH-Gasoline	TO-15	10.00	400	1800	15300	4,346.59	x	08/19/16	18:18	BA	419423

NOTE: x-not a match to Gas reference std but within C5-C12 quantitation range (possibly aged gasoline)



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-3	Lab Sample ID: 1608182-003A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 12:20	Certified Clean WO # :
Canister/Tube ID: 6321	Received PSI : 13.2
Collection Volume (L):	Corrected PSI :
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
Dichlorodifluoromethane	ETO15	50.00	78	120	ND	ND		08/19/16	20:55	BA	419413
1,1-Difluoroethane	ETO15	50.00	17	680	ND	ND		08/19/16	20:55	BA	419413
1,2-Dichlorotetrafluoroethane	ETO15	50.00	1400	2800	ND	ND		08/19/16	20:55	BA	419413
Chloromethane	ETO15	50.00	100	210	ND	ND		08/19/16	20:55	BA	419413
Vinyl Chloride	ETO15	50.00	11	64	ND	ND		08/19/16	20:55	BA	419413
1,3-Butadiene	ETO15	50.00	17	55	ND	ND		08/19/16	20:55	BA	419413
Bromomethane	ETO15	50.00	33	97	ND	ND		08/19/16	20:55	BA	419413
Chloroethane	ETO15	50.00	41	66	ND	ND		08/19/16	20:55	BA	419413
Trichlorofluoromethane	ETO15	50.00	28	140	ND	ND		08/19/16	20:55	BA	419413
1,1-Dichloroethene	ETO15	50.00	41	99	ND	ND		08/19/16	20:55	BA	419413
Freon 113	ETO15	50.00	51	190	ND	ND		08/19/16	20:55	BA	419413
Carbon Disulfide	ETO15	50.00	19	78	ND	ND		08/19/16	20:55	BA	419413
2-Propanol (Isopropyl Alcohol)	ETO15	50.00	64	620	ND	ND		08/19/16	20:55	BA	419413
Methylene Chloride	ETO15	50.00	35	87	ND	ND		08/19/16	20:55	BA	419413
Acetone	ETO15	50.00	20	600	2500	1,050.42		08/19/16	20:55	BA	419413
trans-1,2-Dichloroethene	ETO15	50.00	24	99	ND	ND		08/19/16	20:55	BA	419413
Hexane	ETO15	50.00	23	88	ND	ND		08/19/16	20:55	BA	419413
MTBE	ETO15	50.00	22	90	ND	ND		08/19/16	20:55	BA	419413
tert-Butanol	ETO15	50.00	31	76	ND	ND		08/19/16	20:55	BA	419413
Diisopropyl ether (DIPE)	ETO15	50.00	37	100	ND	ND		08/19/16	20:55	BA	419413
1,1-Dichloroethane	ETO15	50.00	27	100	ND	ND		08/19/16	20:55	BA	419413
ETBE	ETO15	50.00	16	100	ND	ND		08/19/16	20:55	BA	419413
cis-1,2-Dichloroethene	ETO15	50.00	42	99	ND	ND		08/19/16	20:55	BA	419413
Chloroform	ETO15	50.00	48	120	ND	ND		08/19/16	20:55	BA	419413
Vinyl Acetate	ETO15	50.00	38	88	ND	ND		08/19/16	20:55	BA	419413
Carbon Tetrachloride	ETO15	50.00	55	160	ND	ND		08/19/16	20:55	BA	419413
1,1,1-Trichloroethane	ETO15	50.00	40	140	ND	ND		08/19/16	20:55	BA	419413
2-Butanone (MEK)	ETO15	50.00	19	74	ND	ND		08/19/16	20:55	BA	419413
Ethyl Acetate	ETO15	50.00	24	90	ND	ND		08/19/16	20:55	BA	419413
Tetrahydrofuran	ETO15	50.00	22	74	ND	ND		08/19/16	20:55	BA	419413
Benzene	ETO15	50.00	22	80	ND	ND		08/19/16	20:55	BA	419413
TAME	ETO15	50.00	34	100	ND	ND		08/19/16	20:55	BA	419413



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID: SG-3	Lab Sample ID: 1608182-003A
Project Name/Location: 20957 Baker Rd	Sample Matrix: Air
Project Number: 13255.000.000	
Date/Time Sampled: 08/19/16 / 12:20	Certified Clean WO # :
Canister/Tube ID: 6321	Received PSI : 13.2
Collection Volume (L):	Corrected PSI :
SDG:	

Prep Method: TO15-P	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1833	Prep Analyst: BALI	

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
1,2-Dichloroethane (EDC)	ETO15	50.00	21	100	ND	ND		08/19/16	20:55	BA	419413
Trichloroethylene	ETO15	50.00	40	130	ND	ND		08/19/16	20:55	BA	419413
1,2-Dichloropropane	ETO15	50.00	38	120	ND	ND		08/19/16	20:55	BA	419413
Bromodichloromethane	ETO15	50.00	37	170	ND	ND		08/19/16	20:55	BA	419413
1,4-Dioxane	ETO15	50.00	90	180	ND	ND		08/19/16	20:55	BA	419413
trans-1,3-Dichloropropene	ETO15	50.00	53	110	ND	ND		08/19/16	20:55	BA	419413
Toluene	ETO15	50.00	38	94	ND	ND		08/19/16	20:55	BA	419413
4-Methyl-2-Pentanone (MIBK)	ETO15	50.00	37	100	ND	ND		08/19/16	20:55	BA	419413
cis-1,3-Dichloropropene	ETO15	50.00	21	110	ND	ND		08/19/16	20:55	BA	419413
Tetrachloroethylene	ETO15	50.00	73	170	ND	ND		08/19/16	20:55	BA	419413
1,1,2-Trichloroethane	ETO15	50.00	29	140	ND	ND		08/19/16	20:55	BA	419413
Dibromochloromethane	ETO15	50.00	56	210	ND	ND		08/19/16	20:55	BA	419413
1,2-Dibromoethane (EDB)	ETO15	50.00	37	190	ND	ND		08/19/16	20:55	BA	419413
2-Hexanone	ETO15	50.00	33	100	170	41.46		08/19/16	20:55	BA	419413
Ethyl Benzene	ETO15	50.00	31	110	3700	852.53		08/19/16	20:55	BA	419413
Chlorobenzene	ETO15	50.00	30	120	ND	ND		08/19/16	20:55	BA	419413
1,1,1,2-Tetrachloroethane	ETO15	50.00	42	170	ND	ND		08/19/16	20:55	BA	419413
m,p-Xylene	ETO15	50.00	49	110	20000	4,608.29		08/19/16	20:55	BA	419413
o-Xylene	ETO15	50.00	15	110	7800	1,797.24		08/19/16	20:55	BA	419413
Styrene	ETO15	50.00	23	110	ND	ND		08/19/16	20:55	BA	419413
Bromoform	ETO15	50.00	65	260	ND	ND		08/19/16	20:55	BA	419413
1,1,2,2-Tetrachloroethane	ETO15	50.00	41	170	ND	ND		08/19/16	20:55	BA	419413
4-Ethyl Toluene	ETO15	50.00	27	120	ND	ND		08/19/16	20:55	BA	419413
1,3,5-Trimethylbenzene	ETO15	50.00	15	120	2300	467.48		08/19/16	20:55	BA	419413
1,2,4-Trimethylbenzene	ETO15	50.00	30	120	5700	1,158.54		08/19/16	20:55	BA	419413
1,4-Dichlorobenzene	ETO15	50.00	37	150	ND	ND		08/19/16	20:55	BA	419413
1,3-Dichlorobenzene	ETO15	50.00	67	150	ND	ND		08/19/16	20:55	BA	419413
1,2-Dichlorobenzene	ETO15	50.00	53	150	ND	ND		08/19/16	20:55	BA	419413
Hexachlorobutadiene	ETO15	50.00	93	270	ND	ND		08/19/16	20:55	BA	419413
1,2,4-Trichlorobenzene	ETO15	50.00	110	190	ND	ND		08/19/16	20:55	BA	419413
Naphthalene	ETO15	50.00	64	130	130	24.81		08/19/16	20:55	BA	419413
(S) 4-Bromofluorobenzene	ETO15	50.00	65	135	110 %			08/19/16	20:55	BA	419413



SAMPLE RESULTS

Report prepared for: Divya Bhargava
 Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	SG-3	Lab Sample ID:	1608182-003A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Air
Project Number:	13255.000.000	Certified Clean WO # :	
Date/Time Sampled:	08/19/16 / 12:20	Received PSI :	13.2
Canister/Tube ID:	6321	Corrected PSI :	
Collection Volume (L):			
SDG:			

Prep Method: TO15-GRO	Prep Batch Date/Time: 8/19/16	12:01:00AM
Prep Batch ID: 1841	Prep Analyst:	BALI

Parameters:	Analysis Method	DF	MDL ug/m3	PQL ug/m3	Results ug/m3	Results ppbv	Q	Analyzed	Time	By	Analytical Batch
TPH-Gasoline	TO-15	50.00	2000	8800	245000	69,602.27	x	08/19/16	20:55	BA	419423

NOTE: x-not a match to Gas reference std but within C5-C12 quantitation range (possibly aged gasoline)



MB Summary Report

Work Order:	1608182	Prep Method:	TO15-P	Prep Date:	08/19/16	Prep Batch:	1833
Matrix:	Air	Analytical Method:	ETO15	Analyzed Date:	8/19/2016	Analytical Batch:	419413
Units:	ppbv						

Parameters	MDL	PQL	Method Blank Conc.	Lab Qualifier	
Dichlorodifluoromethane	0.32	0.50	ND		
1,1-Difluoroethane	0.13	5.0	ND		
1,2-Dichlorotetrafluoroethane	4.0	8.0	ND		
Chloromethane	0.99	2.0	ND		
Vinyl Chloride	0.088	0.50	ND		
1,3-Butadiene	0.15	0.50	ND		
Bromomethane	0.17	0.50	ND		
Chloroethane	0.31	0.50	ND		
Trichlorofluoromethane	0.099	0.50	ND		
1,1-Dichloroethene	0.21	0.50	ND		
Freon 113	0.13	0.50	ND		
Carbon Disulfide	0.12	0.50	ND		
2-Propanol (Isopropyl Alcohol)	0.52	5.0	ND		
Methylene Chloride	0.20	0.50	ND		
Acetone	0.17	5.0	0.64	J	
trans-1,2-Dichloroethene	0.12	0.50	ND		
Hexane	0.13	0.50	ND		
MTBE	0.12	0.50	ND		
tert-Butanol	0.20	0.50	ND		
Diisopropyl ether (DIPE)	0.18	0.50	ND		
1,1-Dichloroethane	0.13	0.50	ND		
ETBE	0.078	0.50	ND		
cis-1,2-Dichloroethene	0.21	0.50	ND		
Chloroform	0.20	0.50	ND		
Vinyl Acetate	0.22	0.50	ND		
Carbon Tetrachloride	0.18	0.50	ND		
1,1,1-Trichloroethane	0.15	0.50	ND		
2-Butanone (MEK)	0.13	0.50	ND		
Ethyl Acetate	0.13	0.50	ND		
Tetrahydrofuran	0.15	0.50	ND		
Benzene	0.14	0.50	ND		
TAME	0.16	0.50	ND		
1,2-Dichloroethane (EDC)	0.10	0.50	ND		
Trichloroethylene	0.15	0.50	ND		
1,2-Dichloropropane	0.17	0.50	ND		
Bromodichloromethane	0.11	0.50	ND		
1,4-Dioxane	0.50	1.0	ND		
trans-1,3-Dichloropropene	0.23	0.50	ND		
Toluene	0.20	0.50	ND		
4-Methyl-2-Pentanone (MIBK)	0.18	0.50	ND		
cis-1,3-Dichloropropene	0.093	0.50	ND		



MB Summary Report

Work Order:	1608182	Prep Method:	TO15-P	Prep Date:	08/19/16	Prep Batch:	1833
Matrix:	Air	Analytical Method:	ETO15	Analyzed Date:	8/19/2016	Analytical Batch:	419413
Units:	ppbv						

Parameters	MDL	PQL	Method Blank Conc.	Lab Qualifier
Tetrachloroethylene	0.22	0.50	ND	
1,1,2-Trichloroethane	0.11	0.50	ND	
Dibromochloromethane	0.13	0.50	ND	
1,2-Dibromoethane (EDB)	0.096	0.50	ND	
2-Hexanone	0.16	0.50	ND	
Ethyl Benzene	0.15	0.50	ND	
Chlorobenzene	0.13	0.50	ND	
1,1,1,2-Tetrachloroethane	0.12	0.50	ND	
m,p-Xylene	0.23	0.50	ND	
o-Xylene	0.070	0.50	ND	
Styrene	0.11	0.50	ND	
Bromoform	0.13	0.50	ND	
1,1,2,2-Tetrachloroethane	0.12	0.50	ND	
4-Ethyl Toluene	0.11	0.50	ND	
1,3,5-Trimethylbenzene	0.061	0.50	ND	
1,2,4-Trimethylbenzene	0.12	0.50	ND	
1,4-Dichlorobenzene	0.12	0.50	ND	
1,3-Dichlorobenzene	0.22	0.50	ND	
1,2-Dichlorobenzene	0.18	0.50	ND	
Hexachlorobutadiene	0.17	0.50	ND	
1,2,4-Trichlorobenzene	0.29	0.50	ND	
Naphthalene	0.24	0.50	ND	
(S) 4-Bromofluorobenzene			97	

Work Order:	1608182	Prep Method:	TO15-GRO	Prep Date:	08/19/16	Prep Batch:	1841
Matrix:	Air	Analytical Method:	ETO15	Analyzed Date:	8/19/2016	Analytical Batch:	419423
Units:	ppbv						

Parameters	MDL	PQL	Method Blank Conc.	Lab Qualifier
TPH-Gasoline	11	50	ND	



LCS/LCSD Summary Report

Raw values are used in quality control assessment.

Work Order:	1608182	Prep Method:	TO15-P	Prep Date:	08/19/16	Prep Batch:	1833
Matrix:	Air	Analytical Method:	ETO15	Analyzed Date:	8/19/2016	Analytical Batch:	419413
Units:	ppbv						

Parameters	MDL	PQL	Method Blank Conc.	Spike Conc.	LCS % Recovery	LCSD % Recovery	LCS/LCSD % RPD	% Recovery Limits	% RPD Limits	Lab Qualifier
1,1-Dichloroethene	0.21	0.50	ND	8.00	101	103	1.84	65 - 135	30	
Benzene	0.14	0.50	ND	8.00	92.8	91.8	200	65 - 135	30	
Trichloroethylene	0.15	0.50	ND	8.00	93.3	95.0	200	65 - 135	30	
Toluene	0.20	0.50	ND	8.00	88.6	88.3	200	65 - 135	30	
Chlorobenzene	0.13	0.50	ND	8.00	87.4	88.4	200	65 - 135	30	
(S) 4-Bromofluorobenzene				20.0	98.9	97.8		65 - 135		

Work Order:	1608182	Prep Method:	TO15-GRO	Prep Date:	08/19/16	Prep Batch:	1841
Matrix:	Air	Analytical Method:	ETO15	Analyzed Date:	8/19/2016	Analytical Batch:	419423
Units:	ppbv						

Parameters	MDL	PQL	Method Blank Conc.	Spike Conc.	LCS % Recovery	LCSD % Recovery	LCS/LCSD % RPD	% Recovery Limits	% RPD Limits	Lab Qualifier
TPH-Gasoline	11	50	ND	504	91.8	98.4	7.10	65 - 135	30	



Laboratory Qualifiers and Definitions

DEFINITIONS:

Accuracy/Bias (% Recovery) - The closeness of agreement between an observed value and an accepted reference value.
Blank (Method/Preparation Blank) -MB/PB - An analyte-free matrix to which all reagents are added in the same volumes/proportions as used in sample processing. The method blank is used to document contamination resulting from the analytical process.
Duplicate - a field sample and/or laboratory QC sample prepared in duplicate following all of the same processes and procedures used on the original sample (sample duplicate, LCSD, MSD)
Laboratory Control Sample (LCS ad LCSD) - A known matrix spiked with compounds representative of the target analyte(s). This is used to document laboratory performance.
Matrix - the component or substrate that contains the analyte of interest (e.g., - groundwater, sediment, soil, waste water, etc)
Matrix Spike (MS/MSD) - Client sample spiked with identical concentrations of target analyte (s). The spiking occurs prior to the sample preparation and analysis. They are used to document the precision and bias of a method in a given sample matrix.
Method Detection Limit (MDL) - the minimum concentration of a substance that can be measured and reported with a 99% confidence that the analyte concentration is greater than zero
Practical Quantitation Limit/Reporting Limit/Limit of Quantitation (PQL/RL/LOQ) - a laboratory determined value at 2 to 5 times above the MDL that can be reproduced in a manner that results in a 99% confidence level that the result is both accurate and precise. PQLs/RLs/LODs reflect all preparation factors and/or dilution factors that have been applied to the sample during the preparation and/or analytical processes.
Precision (%RPD) - The agreement among a set of replicate/duplicate measurements without regard to known value of the replicates
Surrogate (S) or (Surr) - An organic compound which is similar to the target analyte(s) in chemical composition and behavior in the analytical process, but which is not normally found in environmental samples. Surrogates are used in most organic analysis to demonstrate matrix compatibility with the chosen method of analysis
Tentatively Identified Compound (TIC) - A compound not contained within the analytical calibration standards but present in the GCMS library of defined compounds. When the library is searched for an unknown compound, it can frequently give a tentative identification to the compound based on retention time and primary and secondary ion match. TICs are reported as estimates and are candidates for further investigation.
Units: the unit of measure used to express the reported result - mg/L and mg/Kg (equivalent to PPM - parts per million in liquid and solid), ug/L and ug/Kg (equivalent to PPB - parts per billion in liquid and solid), ug/m3 , mg/m3 , ppbv and ppmv (all units of measure for reporting concentrations in air), % (equivalent to 10000 ppm or 1,000,000 ppb), ug/Wipe (concentration found on the surface of a single Wipe usually taken over a 100cm ² surface)

LABORATORY QUALIFIERS:

<p>B - Indicates when the analyte is found in the associated method or preparation blank</p> <p>D - Surrogate is not recoverable due to the necessary dilution of the sample</p> <p>E - Indicates the reportable value is outside of the calibration range of the instrument but within the linear range of the instrument (unless otherwise noted) Values reported with an E qualifier should be considered as estimated.</p> <p>H - Indicates that the recommended holding time for the analyte or compound has been exceeded</p> <p>J - Indicates a value between the method MDL and PQL and that the reported concentration should be considered as estimated rather the quantitative</p> <p>NA - Not Analyzed</p> <p>N/A - Not Applicable</p> <p>ND - Not Detected at a concentration greater than the PQL/RL or, if reported to the MDL, at greater than the MDL.</p> <p>NR - Not recoverable - a matrix spike concentration is not recoverable due to a concentration within the original sample that is greater than four times the spike concentration added</p> <p>R - The % RPD between a duplicate set of samples is outside of the absolute values established by laboratory control charts</p> <p>S - Spike recovery is outside of established method and/or laboratory control limits. Further explanation of the use of this qualifier should be included within a case narrative</p> <p>X -Used to indicate that a value based on pattern identification is within the pattern range but not typical of the pattern found in standards. Further explanation may or may not be provided within the sample footnote and/or the case narrative.</p>



Sample Receipt Checklist

Client Name: Engeo (San Ramon)

Date and Time Received: 8/19/2016 3:20:00PM

Project Name: 20957 Baker Rd

Received By: Lorna Imbat

Work Order No.: 1608182

Physically Logged By: Lorna Imbat

Checklist Completed By:

Carrier Name: Client Drop Off

Chain of Custody (COC) Information

Chain of custody present? Yes
Chain of custody signed when relinquished and received? Yes
Chain of custody agrees with sample labels? Yes
Custody seals intact on sample bottles? Not Present

Sample Receipt Information

Custody seals intact on shipping container/cooler? Not Present
Shipping Container/Cooler In Good Condition? Yes
Samples in proper container/bottle? Yes
Samples containers intact? Yes
Sufficient sample volume for indicated test? Yes

Sample Preservation and Hold Time (HT) Information

All samples received within holding time? Yes
Container/Temp Blank temperature in compliance? Temperature: °C
Water-VOA vials have zero headspace?
Water-pH acceptable upon receipt? N/A
pH Checked by: n/a pH Adjusted by: n/a

Comments:



Login Summary Report

Client ID: TL5123 Engeo (San Ramon)
Project Name: 20957 Baker Rd
Project # : 13255.000.000
Report Due Date: 8/22/2016

QC Level: II
TAT Requested: Next Day
Date Received: 8/19/2016
Time Received: 3:20 pm

Comments:

Work Order # : 1608182

<u>WO Sample ID</u>	<u>Client Sample ID</u>	<u>Collection Date/Time</u>	<u>Matrix</u>	<u>Scheduled Disposal</u>	<u>Sample On Hold</u>	<u>Test On Hold</u>	<u>Requested Tests</u>	<u>Subbed</u>
1608182-001A	SG-1	08/19/16 13:00	Air				VOC_A_TO15GRO VOC_A_TO15	
1608182-002A	SG-2	08/19/16 11:30	Air				VOC_A_TO15GRO VOC_A_TO15	
1608182-003A	SG-3	08/19/16 12:20	Air				VOC_A_TO15GRO VOC_A_TO15	



483 Sinclair Frontage Road
 Milpitas, CA 95035
 Phone: 408.263.5258
 FAX: 408.263.8293
 www.torrentlab.com

CHAIN OF CUSTODY

LAB WORK ORDER NO
1608182

• NOTE: SHADED AREAS ARE FOR TORRENT LAB USE ONLY •

Company Name: ENGeo, INC	<input checked="" type="checkbox"/> Env. <input type="checkbox"/> DOD <input type="checkbox"/> Food <input type="checkbox"/> Special	Project Name: 20957 Baker Rd
Address: 2010 Crow Canyon Place, Suite 250	Project # 13255.000.000	
City: San Ramon State: CA Zip Code: 94583	Comments: Please hold 12-18" interval samples pending other results	
Telephone: Cell:	Email: dbhargava@engco.com	
REPORT TO: Divya Bhargava	SAMPLER: Lauren Gordon	P.O. # QUOTE #

TURNAROUND TIME:

10 Work Days 4 Work Days 1 Work Day

7 Work Days 3 Work Days Noon - Nxt Day

5 Work Days 2 Work Days 2-8 Hours

SAMPLE TYPE:

Storm Water Air

Waste Water Wipe

Ground Water Other

Soil

REPORT FORMAT:

Excel/ EDD

EDF

QC Level III

QC Level IV

VOCs + TPAS (FD-15)

PESTICIDES (8081)

LEAD + ARSENIC (6010)

ANALYSIS REQUESTED

LAB ID	CANISTER I.D.	CLIENT'S SAMPLE I.D.	DATE / TIME SAMPLED	MATRIX	# OF CONT	CONT TYPE	PRES.	VOCs + TPAS (FD-15)	PESTICIDES (8081)	LEAD + ARSENIC (6010)	REMARKS
		S-1 @ 3-9"	08/19/16 0910	Soil	1	6" Sleeve	10E		X	X	
		S-1 @ 12-18"	0915						X	X	Please hold pending shallow results
		S-2 @ 3-9"	0920						X	X	
		S-2 @ 12-18"	0925						X	X	Please hold pending shallow results
		S-3 @ 3-9"	0930						X	X	
		S-3 @ 12-18"	0935						X	X	please hold pending shallow results
		S-4 @ 3-9"	0940						X	X	
		S-4 @ 12-18"	0945						X	X	Please hold pending shallow results
001A	SG-1		1300	Soil (GPS)	1	1L Canister	NA	X			RUSH 1 DAY A 7464 6116 6321
002A	SG-2		1130					X			
003A	SG-3		1220					X			

1	Relinquished By: <u>Lauren Gordon</u>	Print: <u>Lauren Gordon</u>	Date: <u>08/19/16</u>	Time: <u>1520</u>	Received By: <u>Kathie Evans</u>	Print: <u>Kathie Evans</u>	Date: <u>8-19-16</u>	Time: <u>15:20</u>
2	Relinquished By:	Print:	Date:	Time:	Received By:	Print:	Date:	Time:

Were Samples Received in Good Condition? Yes NO Samples on Ice? Yes NO Method of Shipment D/Off Sample seals intact? Yes NO N/A

NOTE: Samples are discarded by the laboratory 30 days from date of receipt unless other arrangements are made. Temp. Gun # #1 Temp 7 °C Page of

Log In By: Date: Labeled By: Date: Log In Reviewed By: Date: Rev 3.



Engeo (San Ramon)
2010 Crow Canyon Place, #250
San Ramon, California 94583
Tel: (925) 866-9000
Fax: (925) 866-0199
RE: 20957 Baker Rd

Work Order No.: 1608183

Dear Divya Bhargava:

Torrent Laboratory, Inc. received 8 sample(s) on August 19, 2016 for the analyses presented in the following Report.

As requested on the Chain of Custody, four samples were placed on hold.

All data for associated QC met EPA or laboratory specification(s) except where noted in the case narrative.

Torrent Laboratory, Inc. is certified by the State of California, ELAP #1991. If you have any questions regarding these test results, please feel free to contact the Project Management Team at (408)263-5258; ext 204.

A handwritten signature in blue ink, appearing to read "Patti L Sandrock", is written over a light blue horizontal line.

Patti L Sandrock
QA Officer

August 22, 2016

Date



Date: 8/22/2016

Client: Engeo (San Ramon)

Project: 20957 Baker Rd

Work Order: 1608183

CASE NARRATIVE

No issues encountered with the receiving, preparation, analysis or reporting of the results associated with this work order.

Unless otherwise indicated in the following narrative, no results have been method and/or field blank corrected.

Reported results relate only to the items/samples tested by the laboratory.

This report shall not be reproduced, except in full, without the written approval of Torrent Analytical, Inc.



Sample Result Summary

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date Received: 08/19/16

Date Reported: 08/22/16

S-1 @ 3-9" 1608183-001

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results</u>	<u>Unit</u>
Arsenic	SW6010B	1	0.15	1.3	13.7	mg/Kg
Lead	SW6010B	1	0.12	3.0	7.41	mg/Kg

S-2 @ 3-9" 1608183-003

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results</u>	<u>Unit</u>
Arsenic	SW6010B	1	0.15	1.3	27.3	mg/Kg
Lead	SW6010B	1	0.12	3.0	6.49	mg/Kg

S-3 @ 3-9" 1608183-005

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results</u>	<u>Unit</u>
Arsenic	SW6010B	1	0.15	1.3	17.9	mg/Kg
Lead	SW6010B	1	0.12	3.0	14.1	mg/Kg

S-4 @ 3-9" 1608183-007

<u>Parameters:</u>	<u>Analysis Method</u>	<u>DF</u>	<u>MDL</u>	<u>PQL</u>	<u>Results</u>	<u>Unit</u>
Arsenic	SW6010B	1	0.15	1.3	26.5	mg/Kg
Lead	SW6010B	1	0.12	3.0	33.2	mg/Kg



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-1 @ 3-9"	Lab Sample ID:	1608183-001A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:10		
SDG:			

Prep Method: 3050B	Prep Batch Date/Time: 8/19/16 6:45:00PM
Prep Batch ID: 1820	Prep Analyst: PPATEL

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
Arsenic	SW6010B	1	0.15	1.3	13.7		mg/Kg	08/20/16	12:18	ERR	419401
Lead	SW6010B	1	0.12	3.0	7.41		mg/Kg	08/20/16	12:18	ERR	419401

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16 5:28:00PM
Prep Batch ID: 1816	Prep Analyst: SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

alpha-BHC	SW8081A	10	1.3	20	ND		ug/Kg	08/20/16	3:42	LA	419404
gamma-BHC (Lindane)	SW8081A	10	1.6	20	ND		ug/Kg	08/20/16	3:42	LA	419404
beta-BHC	SW8081A	10	3.2	20	ND		ug/Kg	08/20/16	3:42	LA	419404
delta-BHC	SW8081A	10	1.6	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Heptachlor	SW8081A	10	1.1	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Aldrin	SW8081A	10	2.0	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Heptachlor Epoxide	SW8081A	10	0.78	20	ND		ug/Kg	08/20/16	3:42	LA	419404
gamma-Chlordane	SW8081A	10	1.6	20	ND		ug/Kg	08/20/16	3:42	LA	419404
alpha-Chlordane	SW8081A	10	1.7	20	ND		ug/Kg	08/20/16	3:42	LA	419404
4,4-DDE	SW8081A	10	1.9	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Endosulfan I	SW8081A	10	1.8	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Dieldrin	SW8081A	10	1.5	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Endrin	SW8081A	10	1.9	20	ND		ug/Kg	08/20/16	3:42	LA	419404
4,4-DDD	SW8081A	10	5.7	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Endosulfan II	SW8081A	10	5.8	20	ND		ug/Kg	08/20/16	3:42	LA	419404
4,4-DDT	SW8081A	10	1.3	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Endrin Aldehyde	SW8081A	10	1.5	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Methoxychlor	SW8081A	10	2.0	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Endosulfan Sulfate	SW8081A	10	1.2	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Endrin Ketone	SW8081A	10	0.94	20	ND		ug/Kg	08/20/16	3:42	LA	419404
Chlordane	SW8081A	10	21	200	ND		ug/Kg	08/20/16	3:42	LA	419404
Toxaphene	SW8081A	10	85	500	ND		ug/Kg	08/20/16	3:42	LA	419404

Acceptance Limits



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-1 @ 3-9"	Lab Sample ID:	1608183-001A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:10		
SDG:			

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16 5:28:00PM
Prep Batch ID: 1816	Prep Analyst: SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

TCMX (S)	SW8081A	70 - 125	89.0	ug/Kg	08/20/16	3:42	LA	419404
DCBP (S)	SW8081A	30 - 135	115	ug/Kg	08/20/16	3:42	LA	419404

NOTE: Sample diluted due to nature of the matrix (dark, viscous extract)



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-2 @ 3-9"	Lab Sample ID:	1608183-003A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:20		
SDG:			

Prep Method: 3050B	Prep Batch Date/Time: 8/19/16 6:45:00PM
Prep Batch ID: 1820	Prep Analyst: PPATEL

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
Arsenic	SW6010B	1	0.15	1.3	27.3		mg/Kg	08/20/16	12:21	ERR	419401
Lead	SW6010B	1	0.12	3.0	6.49		mg/Kg	08/20/16	12:21	ERR	419401

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16 5:28:00PM
Prep Batch ID: 1816	Prep Analyst: SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

alpha-BHC	SW8081A	4	0.51	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
gamma-BHC (Lindane)	SW8081A	4	0.64	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
beta-BHC	SW8081A	4	1.3	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
delta-BHC	SW8081A	4	0.62	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Heptachlor	SW8081A	4	0.42	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Aldrin	SW8081A	4	0.78	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Heptachlor Epoxide	SW8081A	4	0.31	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
gamma-Chlordane	SW8081A	4	0.65	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
alpha-Chlordane	SW8081A	4	0.69	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
4,4-DDE	SW8081A	4	0.78	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Endosulfan I	SW8081A	4	0.73	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Dieldrin	SW8081A	4	0.59	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Endrin	SW8081A	4	0.75	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
4,4-DDD	SW8081A	4	2.3	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Endosulfan II	SW8081A	4	2.3	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
4,4-DDT	SW8081A	4	0.52	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Endrin Aldehyde	SW8081A	4	0.60	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Methoxychlor	SW8081A	4	0.80	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Endosulfan Sulfate	SW8081A	4	0.47	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Endrin Ketone	SW8081A	4	0.38	8.0	ND		ug/Kg	08/20/16	3:55	LA	419404
Chlordane	SW8081A	4	8.4	80	ND		ug/Kg	08/20/16	3:55	LA	419404
Toxaphene	SW8081A	4	34	200	ND		ug/Kg	08/20/16	3:55	LA	419404

Acceptance Limits



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-2 @ 3-9"	Lab Sample ID:	1608183-003A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:20		
SDG:			

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16 5:28:00PM
Prep Batch ID: 1816	Prep Analyst: SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

TCMX (S)	SW8081A	70 - 125			85.8		ug/Kg	08/20/16	3:55	LA	419404
DCBP (S)	SW8081A	30 - 135			104		ug/Kg	08/20/16	3:55	LA	419404

NOTE: Sample diluted due to nature of the matrix (dark, viscous extract)



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-3 @ 3-9"	Lab Sample ID:	1608183-005A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:30		
SDG:			

Prep Method: 3050B	Prep Batch Date/Time: 8/19/16	6:45:00PM
Prep Batch ID: 1820	Prep Analyst:	PPATEL

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
Arsenic	SW6010B	1	0.15	1.3	17.9		mg/Kg	08/20/16	12:23	ERR	419401
Lead	SW6010B	1	0.12	3.0	14.1		mg/Kg	08/20/16	12:23	ERR	419401

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16	5:28:00PM
Prep Batch ID: 1816	Prep Analyst:	SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

alpha-BHC	SW8081A	4	0.51	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
gamma-BHC (Lindane)	SW8081A	4	0.64	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
beta-BHC	SW8081A	4	1.3	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
delta-BHC	SW8081A	4	0.62	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Heptachlor	SW8081A	4	0.42	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Aldrin	SW8081A	4	0.78	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Heptachlor Epoxide	SW8081A	4	0.31	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
gamma-Chlordane	SW8081A	4	0.65	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
alpha-Chlordane	SW8081A	4	0.69	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
4,4-DDE	SW8081A	4	0.78	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Endosulfan I	SW8081A	4	0.73	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Dieldrin	SW8081A	4	0.59	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Endrin	SW8081A	4	0.75	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
4,4-DDD	SW8081A	4	2.3	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Endosulfan II	SW8081A	4	2.3	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
4,4-DDT	SW8081A	4	0.52	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Endrin Aldehyde	SW8081A	4	0.60	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Methoxychlor	SW8081A	4	0.80	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Endosulfan Sulfate	SW8081A	4	0.47	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Endrin Ketone	SW8081A	4	0.38	8.0	ND		ug/Kg	08/20/16	4:09	LA	419404
Chlordane	SW8081A	4	8.4	80	ND		ug/Kg	08/20/16	4:09	LA	419404
Toxaphene	SW8081A	4	34	200	ND		ug/Kg	08/20/16	4:09	LA	419404

Acceptance Limits



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-3 @ 3-9"	Lab Sample ID:	1608183-005A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:30		
SDG:			

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16 5:28:00PM
Prep Batch ID: 1816	Prep Analyst: SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

TCMX (S)	SW8081A	70 - 125			87.6		ug/Kg	08/20/16	4:09	LA	419404
DCBP (S)	SW8081A	30 - 135			105		ug/Kg	08/20/16	4:09	LA	419404

NOTE: Sample diluted due to nature of the matrix (dark, viscous extract)



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-4 @ 3-9"	Lab Sample ID:	1608183-007A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:40		
SDG:			

Prep Method: 3050B	Prep Batch Date/Time: 8/19/16	6:45:00PM
Prep Batch ID: 1820	Prep Analyst:	PPATEL

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
Arsenic	SW6010B	1	0.15	1.3	26.5		mg/Kg	08/20/16	12:26	ERR	419401
Lead	SW6010B	1	0.12	3.0	33.2		mg/Kg	08/20/16	12:26	ERR	419401

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16	5:28:00PM
Prep Batch ID: 1816	Prep Analyst:	SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

alpha-BHC	SW8081A	4	0.51	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
gamma-BHC (Lindane)	SW8081A	4	0.64	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
beta-BHC	SW8081A	4	1.3	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
delta-BHC	SW8081A	4	0.62	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Heptachlor	SW8081A	4	0.42	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Aldrin	SW8081A	4	0.78	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Heptachlor Epoxide	SW8081A	4	0.31	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
gamma-Chlordane	SW8081A	4	0.65	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
alpha-Chlordane	SW8081A	4	0.69	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
4,4-DDE	SW8081A	4	0.78	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Endosulfan I	SW8081A	4	0.73	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Dieldrin	SW8081A	4	0.59	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Endrin	SW8081A	4	0.75	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
4,4-DDD	SW8081A	4	2.3	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Endosulfan II	SW8081A	4	2.3	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
4,4-DDT	SW8081A	4	0.52	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Endrin Aldehyde	SW8081A	4	0.60	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Methoxychlor	SW8081A	4	0.80	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Endosulfan Sulfate	SW8081A	4	0.47	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Endrin Ketone	SW8081A	4	0.38	8.0	ND		ug/Kg	08/20/16	4:23	LA	419404
Chlordane	SW8081A	4	8.4	80	ND		ug/Kg	08/20/16	4:23	LA	419404
Toxaphene	SW8081A	4	34	200	ND		ug/Kg	08/20/16	4:23	LA	419404

Acceptance Limits



SAMPLE RESULTS

Report prepared for: Divya Bhargava
Engeo (San Ramon)

Date/Time Received: 08/19/16, 3:20 pm
Date Reported: 08/22/16

Client Sample ID:	S-4 @ 3-9"	Lab Sample ID:	1608183-007A
Project Name/Location:	20957 Baker Rd	Sample Matrix:	Soil
Project Number:	13255.000.000		
Date/Time Sampled:	08/19/16 / 9:40		
SDG:			

Prep Method: 3546_OCP	Prep Batch Date/Time: 8/19/16 5:28:00PM
Prep Batch ID: 1816	Prep Analyst: SNARASIMHAN

Parameters:	Analysis Method	DF	MDL	PQL	Results	Q	Units	Analyzed	Time	By	Analytical Batch
-------------	-----------------	----	-----	-----	---------	---	-------	----------	------	----	------------------

The results shown below are reported using their MDL.

TCMX (S)	SW8081A	70 - 125	81.8	ug/Kg	08/20/16	4:23	LA	419404
DCBP (S)	SW8081A	30 - 135	95.1	ug/Kg	08/20/16	4:23	LA	419404

NOTE: Sample diluted due to nature of the matrix (dark, viscous extract)



MB Summary Report

Work Order:	1608183	Prep Method:	3546_OCP	Prep Date:	08/19/16	Prep Batch:	1816
Matrix:	Soil	Analytical Method:	SW8081A	Analyzed Date:	8/20/2016	Analytical Batch:	419404
Units:	ug/Kg						

Parameters	MDL	PQL	Method Blank Conc.	Lab Qualifier
alpha-BHC	0.13	2.0	ND	
gamma-BHC (Lindane)	0.16	2.0	ND	
beta-BHC	0.32	2.0	ND	
delta-BHC	0.16	2.0	ND	
Heptachlor	0.11	2.0	ND	
Aldrin	0.20	2.0	ND	
Heptachlor Epoxide	0.078	2.0	ND	
gamma-Chlordane	0.16	2.0	ND	
alpha-Chlordane	0.17	2.0	ND	
4,4-DDE	0.19	2.0	ND	
Endosulfan I	0.18	2.0	ND	
Dieldrin	0.15	2.0	ND	
Endrin	0.19	2.0	ND	
4,4-DDD	0.57	2.0	ND	
Endosulfan II	0.58	2.0	ND	
4,4-DDT	0.13	2.0	ND	
Endrin Aldehyde	0.15	2.0	ND	
Methoxychlor	0.20	2.0	ND	
Endosulfan Sulfate	0.12	2.0	ND	
Endrin Ketone	0.094	2.0	ND	
Chlordane	2.1	20	ND	
Toxaphene	8.5	50	ND	
TCMX (S)			88.1	
DCBP (S)			98.5	

Work Order:	1608183	Prep Method:	3050B	Prep Date:	08/19/16	Prep Batch:	1820
Matrix:	Soil	Analytical Method:	SW6010B	Analyzed Date:	8/20/2016	Analytical Batch:	419401
Units:	mg/Kg						

Parameters	MDL	PQL	Method Blank Conc.	Lab Qualifier
Arsenic	0.15	5.00	0.98	
Lead	0.10	5.00	ND	



LCS/LCSD Summary Report

Raw values are used in quality control assessment.

Work Order:	1608183	Prep Method:	3546_OCP	Prep Date:	08/19/16	Prep Batch:	1816
Matrix:	Soil	Analytical Method:	SW8081A	Analyzed Date:	8/20/2016	Analytical Batch:	419404
Units:	ug/Kg						

Parameters	MDL	PQL	Method Blank Conc.	Spike Conc.	LCS % Recovery	LCSD % Recovery	LCS/LCSD % RPD	% Recovery Limits	% RPD Limits	Lab Qualifier
gamma-BHC (Lindane)	0.16	2.0	ND	40	86.6	89.9	3.97	25 - 135	30	
Heptachlor	0.11	2.0	ND	40	84.9	87.8	3.18	40 - 130	30	
Aldrin	0.20	2.0	ND	40	85.5	86.0	0.583	25 - 140	30	
Dieldrin	0.15	2.0	ND	40	87.0	88.7	1.99	60 - 130	30	
Heptachlor	0.19	2.0	ND	40	83.8	87.2	4.09	55 - 135	30	
4,4-DDT	0.13	2.0	ND	40	101	104	1.95	45 - 140	30	
TCMX (S)				100	81.5	85.0		70 - 125		
DCBP (S)				100	97.8	100		30 - 135		

Work Order:	1608183	Prep Method:	3050B	Prep Date:	08/19/16	Prep Batch:	1820
Matrix:	Soil	Analytical Method:	SW6010B	Analyzed Date:	8/20/2016	Analytical Batch:	419401
Units:	mg/Kg						

Parameters	MDL	PQL	Method Blank Conc.	Spike Conc.	LCS % Recovery	LCSD % Recovery	LCS/LCSD % RPD	% Recovery Limits	% RPD Limits	Lab Qualifier
Arsenic	0.15	5.00	0.98	50	110	117	6.15	80 - 120	30	
Lead	0.10	5.00	ND	50	98.2	101	2.81	80 - 120	30	



MS/MSD Summary Report

Raw values are used in quality control assessment.

Work Order:	1608183	Prep Method:	3546_OCP	Prep Date:	08/19/16	Prep Batch:	1816
Matrix:	Soil	Analytical Method:	SW8081A	Analyzed Date:		Analytical Batch:	419404
Spiked Sample:	1608183-007A						
Units:	ug/Kg						

Parameters	MDL	PQL	Sample Conc.	Spike Conc.	MS % Recovery	MSD % Recovery	MS/MSD % RPD	% Recovery Limits	% RPD Limits	Lab Qualifier
gamma-BHC (Lindane)	0.636	8.00	ND	40	89.4	90.3	1.00	25 - 135	30	
Heptachlor	0.420	8.00	ND	40	85.7	85.2	0.585	40 - 130	30	
Aldrin	0.780	8.00	ND	40	89.4	91.2	1.99	25 - 140	30	
Dieldrin	0.592	8.00	ND	40	89.7	90.2	0.550	60 - 130	30	
Endrin	0.752	8.00	ND	40	74.5	74.4	0.134	55 - 135	30	
4,4-DDT	0.516	8.00	ND	40	121	123	1.64	45 - 140	30	
TCMX (S)				100	84.0	85.2		70 - 125		
DCBP (S)				100	104	107		30 - 135		



Laboratory Qualifiers and Definitions

DEFINITIONS:

Accuracy/Bias (% Recovery) - The closeness of agreement between an observed value and an accepted reference value.
Blank (Method/Preparation Blank) -MB/PB - An analyte-free matrix to which all reagents are added in the same volumes/proportions as used in sample processing. The method blank is used to document contamination resulting from the analytical process.
Duplicate - a field sample and/or laboratory QC sample prepared in duplicate following all of the same processes and procedures used on the original sample (sample duplicate, LCSD, MSD)
Laboratory Control Sample (LCS ad LCSD) - A known matrix spiked with compounds representative of the target analyte(s). This is used to document laboratory performance.
Matrix - the component or substrate that contains the analyte of interest (e.g., - groundwater, sediment, soil, waste water, etc)
Matrix Spike (MS/MSD) - Client sample spiked with identical concentrations of target analyte (s). The spiking occurs prior to the sample preparation and analysis. They are used to document the precision and bias of a method in a given sample matrix.
Method Detection Limit (MDL) - the minimum concentration of a substance that can be measured and reported with a 99% confidence that the analyte concentration is greater than zero
Practical Quantitation Limit/Reporting Limit/Limit of Quantitation (PQL/RL/LOQ) - a laboratory determined value at 2 to 5 times above the MDL that can be reproduced in a manner that results in a 99% confidence level that the result is both accurate and precise. PQLs/RLs/LODs reflect all preparation factors and/or dilution factors that have been applied to the sample during the preparation and/or analytical processes.
Precision (%RPD) - The agreement among a set of replicate/duplicate measurements without regard to known value of the replicates
Surrogate (S) or (Surr) - An organic compound which is similar to the target analyte(s) in chemical composition and behavior in the analytical process, but which is not normally found in environmental samples. Surrogates are used in most organic analysis to demonstrate matrix compatibility with the chosen method of analysis
Tentatively Identified Compound (TIC) - A compound not contained within the analytical calibration standards but present in the GCMS library of defined compounds. When the library is searched for an unknown compound, it can frequently give a tentative identification to the compound based on retention time and primary and secondary ion match. TICs are reported as estimates and are candidates for further investigation.
Units: the unit of measure used to express the reported result - mg/L and mg/Kg (equivalent to PPM - parts per million in liquid and solid), ug/L and ug/Kg (equivalent to PPB - parts per billion in liquid and solid), ug/m3 , mg/m3 , ppbv and ppmv (all units of measure for reporting concentrations in air), % (equivalent to 10000 ppm or 1,000,000 ppb), ug/Wipe (concentration found on the surface of a single Wipe usually taken over a 100cm ² surface)

LABORATORY QUALIFIERS:

<p>B - Indicates when the analyte is found in the associated method or preparation blank</p> <p>D - Surrogate is not recoverable due to the necessary dilution of the sample</p> <p>E - Indicates the reportable value is outside of the calibration range of the instrument but within the linear range of the instrument (unless otherwise noted) Values reported with an E qualifier should be considered as estimated.</p> <p>H - Indicates that the recommended holding time for the analyte or compound has been exceeded</p> <p>J - Indicates a value between the method MDL and PQL and that the reported concentration should be considered as estimated rather the quantitative</p> <p>NA - Not Analyzed</p> <p>N/A - Not Applicable</p> <p>ND - Not Detected at a concentration greater than the PQL/RL or, if reported to the MDL, at greater than the MDL.</p> <p>NR - Not recoverable - a matrix spike concentration is not recoverable due to a concentration within the original sample that is greater than four times the spike concentration added</p> <p>R - The % RPD between a duplicate set of samples is outside of the absolute values established by laboratory control charts</p> <p>S - Spike recovery is outside of established method and/or laboratory control limits. Further explanation of the use of this qualifier should be included within a case narrative</p> <p>X -Used to indicate that a value based on pattern identification is within the pattern range but not typical of the pattern found in standards. Further explanation may or may not be provided within the sample footnote and/or the case narrative.</p>



Sample Receipt Checklist

Client Name: Engeo (San Ramon)

Date and Time Received: 8/19/2016 3:20:00PM

Project Name: 20957 Baker Rd

Received By: ke

Work Order No.: 1608183

Physically Logged By: Lorna Imbat

Checklist Completed By:

Carrier Name: Client Drop Off

Chain of Custody (COC) Information

Chain of custody present? Yes
Chain of custody signed when relinquished and received? Yes
Chain of custody agrees with sample labels? Yes
Custody seals intact on sample bottles? Not Present

Sample Receipt Information

Custody seals intact on shipping container/cooler? Not Present
Shipping Container/Cooler In Good Condition? Yes
Samples in proper container/bottle? Yes
Samples containers intact? Yes
Sufficient sample volume for indicated test? Yes

Sample Preservation and Hold Time (HT) Information

All samples received within holding time? Yes
Container/Temp Blank temperature in compliance? Temperature: °C
Water-VOA vials have zero headspace?
Water-pH acceptable upon receipt? N/A
pH Checked by: n/a pH Adjusted by: n/a

Comments:



Login Summary Report

Client ID: TL5123 Engeo (San Ramon)
Project Name: 20957 Baker Rd
Project # : 13255.000.000
Report Due Date: 8/22/2016

QC Level: II
TAT Requested: Next Day
Date Received: 8/19/2016
Time Received: 3:20 pm

Comments:

Work Order # : 1608183

<u>WO Sample ID</u>	<u>Client Sample ID</u>	<u>Collection Date/Time</u>	<u>Matrix</u>	<u>Scheduled Disposal</u>	<u>Sample On Hold</u>	<u>Test On Hold</u>	<u>Requested Tests</u>	<u>Subbed</u>
1608183-001A	S-1 @ 3-9"	08/19/16 9:10	Soil	02/15/17			Pest_S_8081OCP Met_S_AsPb	
1608183-002A	S-1 @ 12-18"	08/19/16 9:15	Soil	02/15/17	On-Hold		Hold Samples	
1608183-003A	S-2 @ 3-9"	08/19/16 9:20	Soil	02/15/17			Met_S_AsPb Pest_S_8081OCP	
1608183-004A	S-2 @ 12-18"	08/19/16 9:25	Soil	02/15/17	On-Hold		Hold Samples	
1608183-005A	S-3 @ 3-9"	08/19/16 9:30	Soil	02/15/17			Pest_S_8081OCP Met_S_AsPb	
1608183-006A	S-3 @ 12-18"	08/19/16 9:35	Soil	02/15/17	On-Hold		Hold Samples	
1608183-007A	S-4 @ 3-9"	08/19/16 9:40	Soil	02/15/17			Pest_S_8081OCP Met_S_AsPb	
1608183-008A	S-4 @ 12-18"	08/19/16 9:45	Soil	02/15/17	On-Hold		Hold Samples	



Milpitas, CA 95035
 Phone: 408.263.5258
 FAX: 408.263.8293
 www.torrentlab.com

CHAIN OF CUSTODY

* NOTE: SHADED AREAS ARE FOR TORRENT LAB USE ONLY *

LAB WORK ORDER NO
1608183

Company Name: <u>ENGEO, INC</u>	<input checked="" type="checkbox"/> Env. <input type="checkbox"/> DOD <input type="checkbox"/> Food <input type="checkbox"/> Special	Project Name: <u>20957 Baker Rd</u>
Address: <u>2010 Crow Canyon Place, Suite 200</u>	Project # <u>13255.000.000</u>	
City: <u>San Ramon</u> State: <u>CA</u> Zip Code: <u>94583</u>	Comments: <u>Please hold 12-18" interval samples pending other results</u>	
Telephone: _____ Cell: _____	Email: <u>dbhangava@engeo.com</u>	
REPORT TO: <u>Divya Bhargava</u> SAMPLER: <u>Lauren Gordon</u>	P.O. # _____	QUOTE # _____

TURNAROUND TIME:	SAMPLE TYPE:	REPORT FORMAT:	ANALYSIS REQUESTED
<input type="checkbox"/> 10 Work Days <input type="checkbox"/> 4 Work Days <input checked="" type="checkbox"/> 1 Work Day <input type="checkbox"/> 7 Work Days <input type="checkbox"/> 3 Work Days <input type="checkbox"/> Noon - Nxt Day <input type="checkbox"/> 5 Work Days <input type="checkbox"/> 2 Work Days <input type="checkbox"/> 2-8 Hours	<input type="checkbox"/> Storm Water <input type="checkbox"/> Air <input type="checkbox"/> Waste Water <input type="checkbox"/> Wipe <input type="checkbox"/> Ground Water <input type="checkbox"/> Other <input checked="" type="checkbox"/> Soil	<input type="checkbox"/> Excel/ EDD <input type="checkbox"/> EDF <input type="checkbox"/> QC Level III <input type="checkbox"/> QC Level IV	

VOCs + THMs (10-15)
 PESTICIDES (8081)
 LEAD + ARSENIC (6010)

LAB ID	CANISTER I.D.	CLIENT'S SAMPLE I.D.	DATE / TIME SAMPLED	MATRIX	# OF CONT	CONT TYPE	PRES.	VOCs + THMs (10-15)	PESTICIDES (8081)	LEAD + ARSENIC (6010)	REMARKS
-001A		S-1 @ 3-9"	08/19/16 0910	Soil	1	6" sleeve	ICE		X	X	
-002A		S-1 @ 12-18"	0915						X	X	Please hold pending shallow results
-003A		S-2 @ 3-9"	0920						X	X	
-004A		S-2 @ 12-18"	0925						X	X	Please hold pending shallow results
-005A		S-3 @ 3-9"	0930						X	X	
-006A		S-3 @ 12-18"	0935						X	X	please hold pending shallow results
-007A		S-4 @ 3-9"	0940						X	X	
-008A		S-4 @ 12-18"	0945						X	X	Please hold pending shallow results
		SG-1	1300	Soil GAS	1	1L Canister	NA	X			RUSH 1 DAY
		SG-2	1130					X			
		SG-3	1220					X			

1 Relinquished By: <u>Lauren Gordon</u> Print: _____ Date: <u>08/19/16</u> Time: <u>1520</u>	Received By: <u>Kathie Evans</u> Print: <u>Kathie Evans</u> Date: <u>8-19-16</u> Time: <u>15:20</u>
2 Relinquished By: _____ Print: _____ Date: _____ Time: _____	Received By: _____ Print: _____ Date: _____ Time: _____

Were Samples Received in Good Condition? Yes NO Samples on Ice? Yes NO Method of Shipment Dloff Sample seals intact? Yes NO N/A

NOTE: Samples are discarded by the laboratory 30 days from date of receipt unless other arrangements are made. Temp. Gun # #1 Temp 7 °C Page _____ of _____

Log In By: _____ Date: _____ Labeled By: _____ Date: _____ Log In Reviewed By: _____ Date: _____