

RECEIVED

By dehloptoxic at 9:06 am, Nov 07, 2006



76 Broadway
Sacramento, California 95818

October 31, 2006

Mr. Don Hwang
Alameda County Health Agency
1131 Harbor Bay Parkway
Alameda, California 94502

Re: **Report Transmittal
Quarterly Report
Third Quarter – 2006
76 Service Station #6129
3420 35th Avenue
Oakland, CA**

Dear Mr. Hwang:

I declare under penalty of perjury that to the best of my knowledge the information and/or recommendations contained in the attached report is/are true and correct.

If you have any questions or need additional information, please contact

Shelby S. Lathrop (Contractor)
ConocoPhillips
Risk Management & Remediation
76 Broadway
Sacramento, CA 95818
Phone: 916-558-7609
Fax: 916-558-7639

Sincerely,

A handwritten signature in black ink that reads "Thomas H. Kosel". The signature is written in a cursive, flowing style.

Thomas Kosel
Risk Management & Remediation

Attachment

November 3, 2006

Mr. Donald Hwang
Alameda County Health Agency
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502

Re: Quarterly Summary Report – Third Quarter 2006
Delta Project Number: C106129031



Dear Mr. Hwang:

On behalf of ConocoPhillips (COP), Delta Consultants (Delta) is forwarding the quarterly summary report for the following location:

Service Station

76 Service Station No. 6129

Location

3420 35th Avenue
Oakland, California


Sincerely,
Delta Consultants

Handwritten signature of Ben Wright in black ink.

Ben Wright
Staff Geologist

Handwritten signature of Daniel J. Davis in black ink.

Daniel J. Davis, R.G.
Senior Project Manager



Forward: TRC - Quarterly Monitoring Report

cc: Ms. Shelby Lathrop, ConocoPhillips (electronic copy)

QUARTERLY SUMMARY REPORT
Third Quarter 2006
76 Service Station No. 6129
3420 35th Avenue
Oakland, California

PREVIOUS ASSESSMENT

According to Kaprealian Engineering, Inc. (KEI), in 1989 two 10,000-gallon gasoline underground storage tanks (USTs) and one 550-gallon waste oil UST were removed from the site. Analytical results of soil samples collected beneath the former gasoline USTs, used-oil UST and product piping indicated that low concentrations of petroleum hydrocarbons were present in each of the sampling areas. Three groundwater monitoring wells (MW-1 through MW-3) were installed in 1989 to depths of approximately 44 feet below ground surface (bgs).

In 1990, four soil borings (EB1 through EB4) were drilled at the site in the vicinity of MW-3 in an attempt to define the hydrocarbon impact to soil. Based on the results of the soil sampling, approximately 230 cubic yards of soil were excavated from an area between the dispenser islands and around well MW-3 in 1991. Excavation was performed so as to not destroy well MW-3. Analytical results from confirmation soil samples indicated that the majority of the impacted soil had been removed.

On November 12 and 13, 2003, as part of a due diligence investigation, four soil borings (SB-1 and SB-3 through SB-5) were drilled to total depths of approximately 31.5 to 36.5 feet bgs. Proposed boring SB-2 was unable to be drilled due to the presence of subsurface utilities and/or structures. Groundwater was encountered in the borings at a depth of approximately 35 feet bgs. Methyl tertiary butyl ether (MTBE) was reported at concentrations varying from 0.37 to 0.41 milligrams per kilogram (mg/kg) in the soil samples collected between 26 and 31 feet bgs. All other constituents were reported below the laboratory reporting limit for the soil samples analyzed. The three existing groundwater wells were sampled on November 13, 2003. Analytical results indicated the presence of MTBE at concentrations between 240 and 3,700 micrograms per liter ($\mu\text{g/l}$), with the most elevated concentrations occurring in wells MW-2 (2,100 $\mu\text{g/l}$) and MW-3 (3,700 $\mu\text{g/l}$).

SENSITIVE RECEPTORS

A 1,000-foot radius well search was completed as requested on September 28, 2004 by the Alameda County Public Works Agency (ACPWA). The results showed a six-inch diameter irrigation well located at 3397 Arkansas Street, approximately 800 feet west-northwest of the site. The well was drilled in August 1977 to total depth 62 feet bgs with depth to water reported at 18 feet bgs. Alameda County Health Care Services update of July 30, 1984 reported the well owner as Arthur Smith.

MONITORING AND SAMPLING

Groundwater monitoring and sampling activities were conducted at the site from January 1990 through May 1991. Sampling activities were re-initiated during the third quarter 2004. The monitoring well network is scheduled to be sampled on a quarterly basis.

During the most recent groundwater monitoring event, conducted on September 15, 2006, depth to groundwater ranged from 25.76 feet (MW-3) to 29.17 feet (MW-2) below top of casing (TOC). The groundwater flow direction was southwest at a gradient of 0.02 foot per foot (ft/ft), consistent with historic events. Historic groundwater flow directions presented as a rose diagram is included as Attachment A.

During the September 2006 groundwater sampling event, maximum detectable hydrocarbon concentrations were as follows: total petroleum hydrocarbons with gasoline distinction (TPH-G) (ND<1,200 µg/l in MW-3), benzene (ND<12 µg/l in MW-3), and MTBE (1,200 µg/l in MW-3).

REMEDIATION STATUS

Remediation is not currently being conducted at the site.

CHARACTERIZATION STATUS

Hydrocarbon concentrations in the soil and groundwater have not been completely delineated. MTBE in soil and groundwater are above environmental screening levels (ESLs). ESLs are considered to be conservative and to not pose a significant long term threat to human health and the environment.

Additional assessment activity has been approved to delineate both the vertical and horizontal extent (up-gradient and down-gradient) of the MTBE contamination.

RECENT CORRESPONDENCE

No recent correspondence was documented during this reporting period.

THIS QUARTER ACTIVITIES (Third Quarter 2006)

1. TRC conducted the quarterly monitoring and sampling event at the site.
2. Delta initiated assessment activities by completing six CPT borings at the site. Direct push methods were planned to complete the assessment but site conditions precluded successful use of this technology.

WASTE DISPOSAL SUMMARY

In 1991, based on the analytical results of soil samples from borings EB1 through EB4, approximately 230 cubic yards of soil were excavated from the area between the dispensers and the pump islands in the area around MW-3.

Thirteen (13) drums of nonhaz soil and water produced during recent field activities were transported offsite for disposal on 10/19/06.

NEXT QUARTER ACTIVITIES (Fourth Quarter 2006)

1. TRC will conduct the quarterly groundwater monitoring and sampling event at the site.


2. Delta will complete the ongoing assessment to delineate petroleum hydrocarbons in soil and groundwater at the site.

CONSULTANT: Delta Consultants

Attachment A – Historic Groundwater Flow Directions

Attachment A
Historic Groundwater Flow Directions

Historic Groundwater Flow Directions
ConocoPhillips Site No. 6129
3420 35th Avenue
Oakland, California




■ Groundwater Flow Direction

Legend
Concentric circles represent
quarterly monitoring events
First Quarter 1990 through Third
Quarter 2006
15 data points shown



October 11, 2006

ConocoPhillips Company
76 Broadway
Sacramento, CA 94563



ATTN: MR. THOMAS KOSEL

SITE: 76 STATION 6129
3420 35TH AVENUE
OAKLAND, CALIFORNIA

RE: QUARTERLY MONITORING REPORT
JULY THROUGH SEPTEMBER 2006

Dear Mr. Kosel:

Please find enclosed our Quarterly Monitoring Report for 76 Station 6129, located at 3420 35th Avenue, Oakland, California. If you have any questions regarding this report, please call us at (949) 753-0101.

Sincerely,

TRC

Anju Farfan
QMS Operations Manager

CC: Mr. Daniel Davis, Delta Environmental Consultants, Inc. (2 copies)

Enclosures:
20-0400/6129R011.QMS






**QUARTERLY MONITORING REPORT
JULY THROUGH SEPTEMBER 2006**

76 STATION 6129
3420 35th Avenue
Oakland, California

Prepared For:

Mr. Thomas Kosel
CONOCOPHILLIPS COMPANY
76 Broadway
Sacramento, CA 94563

By:

Senior Project Geologist, Irvine Operations
October 9, 2006



LIST OF ATTACHMENTS

Summary Sheet	Summary of Gauging and Sampling Activities
Tables	Table Key Contents of Tables Table 1: Current Fluid Levels and Selected Analytical Results Table 1a: Additional Current Analytical Results Table 2: Historic Fluid Levels and Selected Analytical Results Table 2a: Additional Historic Analytical Results
Figures	Figure 1: Vicinity Map Figure 2: Groundwater Elevation Contour Map Figure 3: Dissolved-Phase TPH-G (GC/MS) Concentration Map Figure 4: Dissolved-Phase Benzene Concentration Map Figure 5: Dissolved-Phase MTBE Concentration Map
Graphs	Groundwater Elevations vs. Time Benzene Concentrations vs. Time MTBE 8260B Concentrations vs. Time
Field Activities	General Field Procedures Field Monitoring Data Sheet – 9/15/06 Groundwater Sampling Field Notes – 9/15/06
Laboratory Reports	Official Laboratory Reports Quality Control Reports Chain of Custody Records
Statements	Purge Water Disposal Limitations

Summary of Gauging and Sampling Activities
July 2006 through September 2006
76 Station 6129
3420 35th Ave.
Oakland, CA

Project Coordinator: **Thomas Kosel**
Telephone: **916-558-7666**

Water Sampling Contractor: **TRC**
Compiled by: **Daniel Lee**

Date(s) of Gauging/Sampling Event: **09/15/06**

Sample Points

Groundwater wells: **3** onsite, **0** offsite Wells gauged: **3** Wells sampled: **3**
Purging method: **Submersible pump**
Purge water disposal: **Onyx/Rodeo Unit 100**
Other Sample Points: **0** Type: **n/a**

Liquid Phase Hydrocarbons (LPH)

Wells with LPH: **0** Maximum thickness (feet): **n/a**
LPH removal frequency: **n/a** Method: **n/a**
Treatment or disposal of water/LPH: **n/a**

Hydrogeologic Parameters

Depth to groundwater (below TOC): Minimum: **28.73 feet** Maximum: **29.17 feet**
Average groundwater elevation (relative to available local datum): **72.55 feet**
Average change in groundwater elevation since previous event: **-2.99 feet**
Interpreted groundwater gradient and flow direction:
 Current event: **0.02 ft/ft, southwest**
 Previous event: **0.02 ft/ft, southwest (06/08/06)**

Selected Laboratory Results

Wells with detected **Benzene**: **0** Wells above MCL (1.0 µg/l): **n/a**
 Maximum reported benzene concentration: **n/a**
Wells with **TPH-G by GC/MS** **0**
Wells with **MTBE** **3** Maximum: **1,200 µg/l (MW-3)**

Notes:

TABLES

TABLE KEY

STANDARD ABBREVIATIONS

--	=	not analyzed, measured, or collected
LPH	=	liquid-phase hydrocarbons
Trace	=	less than 0.01 foot of LPH in well
ug/l	=	micrograms per liter (approx. equivalent to parts per billion, ppb)
mg/l	=	milligrams per liter (approx. equivalent to parts per million, ppm)
ND<	=	not detected at or above laboratory detection limit
TOC	=	top of casing (surveyed reference elevation)

ANALYTES

BTEX	=	benzene, toluene, ethylbenzene, and (total) xylenes
DIPE	=	di-isopropyl ether
ETBE	=	ethyl tertiary butyl ether
MTBE	=	methyl tertiary butyl ether
PCB	=	polychlorinated biphenyls
PCE	=	tetrachloroethene
TBA	=	tertiary butyl alcohol
TCA	=	trichloroethane
TCE	=	trichloroethene
TPH-G	=	total petroleum hydrocarbons with gasoline distinction
TPH-G (GC/MS)	=	total petroleum hydrocarbons with gasoline distinction utilizing EPA Method 8260B
TPH-D	=	total petroleum hydrocarbons with diesel distinction
TRPH	=	total recoverable petroleum hydrocarbons
TAME	=	tertiary amyl methyl ether
1,1-DCA	=	1,1-dichloroethane
1,2-DCA	=	1,2-dichloroethane (same as EDC, ethylene dichloride)
1,1-DCE	=	1,1-dichloroethene
1,2-DCE	=	1,2-dichloroethene (cis- and trans-)

NOTES

1. Elevations are in feet above mean sea level. Depths are in feet below surveyed top-of-casing.
2. Groundwater elevations for wells with LPH are calculated as: $\text{Surface Elevation} - \text{Measured Depth to Water} + (\text{Dp} \times \text{LPH Thickness})$, where Dp is the density of the LPH, if known. A value of 0.75 is used for gasoline and when the density is not known. A value of 0.83 is used for diesel.
3. Wells with LPH are generally not sampled for laboratory analysis (see General Field Procedures).
4. Comments shown on tables are general. Additional explanations may be included in field notes and laboratory reports, both of which are included as part of this report.
5. A "J" flag indicates that a reported analytical result is an estimated concentration value between the method detection limit (MDL) and the practical quantification limit (PQL) specified by the laboratory.
6. Other laboratory flags (qualifiers) may have been reported. See the official laboratory report (attached) for a complete list of laboratory flags.
7. Concentration graphs based on tables (presented following Figures) show non-detect results prior to the Second Quarter 2000 plotted at fixed values for graphical display. Non-detect results reported since that time are plotted at reporting limits stated in the official laboratory report.
8. Groundwater vs. Time graphs may be corrected for apparent level changes due to re-survey.

REFERENCE

TRC began groundwater monitoring and sampling 76 Station 6129 in August 2004.

Contents of Tables

Site: 76 Station 6129

Current Event

Table 1	Well/ Date	Depth to Water	LPH Thickness	Ground- water Elevation	Change in Elevation	TPH-G (8015M)	TPH-G (GC/MS)	Benzene	Toluene	Ethyl- benzene	Total Xylenes	MTBE (8260B)	Comments
Table 1a	Well/ Date	TBA	Ethanol (8260B)	Ethylene- dibromide (EDB)	1,2-DCA (EDC)	DIPE	ETBE	TAME					

Historic Data

Table 2	Well/ Date	Depth to Water	LPH Thickness	Ground- water Elevation	Change in Elevation	TPH-G (8015M)	TPH-G (GC/MS)	Benzene	Toluene	Ethyl- benzene	Total Xylenes	MTBE (8260B)	Comments
Table 2a	Well/ Date	TBA	Ethanol (8260B)	Ethylene- dibromide (EDB)	1,2-DCA (EDC)	DIPE	ETBE	TAME					

Table 1
CURRENT FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
September 15, 2006
76 Station 6129

Date Sampled	TOC Elevation	Depth to Water	LPH Thickness	Ground-water Elevation	Change in Elevation	TPH-G (8015M)	TPH-G (GC/MS)	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE (8260B)	Comments
	(feet)	(feet)	(feet)	(feet)	(feet)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	
MW-1													
09/15/06	102.24	28.86	0.00	73.38	-2.79	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	1.4	
MW-2													
09/15/06	102.16	29.17	0.00	72.99	-3.41	--	ND<500	ND<5.0	ND<5.0	ND<5.0	ND<5.0	570	
MW-3													
09/15/06	100.00	28.73	0.00	71.27	-2.76	--	ND<1200	ND<12	ND<12	ND<12	ND<12	1200	

Table 1 a
ADDITIONAL CURRENT ANALYTICAL RESULTS
76 Station 6129

Date Sampled	TBA	Ethanol (8260B)	Ethylene- dibromide (EDB)	1,2-DCA (EDC)	DIPE	ETBE	TAME
	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)
MW-1							
09/15/06	ND<10	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
MW-2							
09/15/06	ND<100	ND<2500	ND<5.0	ND<5.0	17	ND<5.0	ND<5.0
MW-3							
09/15/06	ND<250	ND<6200	ND<12	ND<12	ND<12	ND<12	ND<12

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
January 1990 Through September 2006
76 Station 6129

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethylbenzene (µg/l)	Total Xylenes (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-1													
01/05/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
05/11/90	--	--	--	--	--	ND	--	ND	7.1	ND	ND	--	
08/09/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
11/14/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
02/12/91	--	--	--	--	--	ND	--	0.32	ND	ND	ND	--	
05/09/91	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
11/13/03	--	--	--	--	--	--	180	ND<1.0	ND<1.0	ND<1.0	ND<2.0	240	
08/27/04	102.24	30.65	0.00	71.59	--	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	ND<0.50	
11/23/04	102.24	29.35	0.00	72.89	1.30	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	ND<0.50	
02/09/05	102.24	26.89	0.00	75.35	2.46	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	9.3	
05/17/05	102.24	26.56	0.00	75.68	0.33	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	1.9	
07/27/05	102.24	27.33	0.00	74.91	-0.77	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	ND<0.50	
12/06/05	102.24	29.59	0.00	72.65	-2.26	--	ND<50	ND<0.50	0.93	ND<0.50	1.8	ND<0.50	
02/21/06	102.24	28.27	0.00	73.97	1.32	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	2.6	
06/08/06	102.24	26.07	0.00	76.17	2.20	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	11	
09/15/06	102.24	28.86	0.00	73.38	-2.79	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	1.4	
MW-2													
01/05/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
05/11/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
08/09/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
11/14/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
02/12/91	--	--	--	--	--	ND	--	ND	0.42	ND	0.51	--	
05/09/91	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
January 1990 Through September 2006
76 Station 6129

Date Sampled	TOC Elevation (feet)	Depth to Water (feet)	LPH Thickness (feet)	Ground-water Elevation (feet)	Change in Elevation (feet)	TPH-G (8015M) (µg/l)	TPH-G (GC/MS) (µg/l)	Benzene (µg/l)	Toluene (µg/l)	Ethyl-benzene (µg/l)	Total Xylenes (µg/l)	MTBE (8260B) (µg/l)	Comments
MW-2 continued													
11/13/03	--	--	--	--	--	--	ND<2000	ND<20	ND<20	ND<20	ND<40	2100	
08/27/04	102.16	30.28	0.00	71.88	--	--	950	ND<5.0	ND<5.0	ND<5.0	ND<10	1400	
11/23/04	102.16	28.75	0.00	73.41	1.53	--	53	ND<0.50	ND<0.50	ND<0.50	ND<1.0	4.2	
02/09/05	102.16	26.08	0.00	76.08	2.67	--	ND<500	ND<0.50	ND<0.50	ND<0.50	ND<1.0	400	
05/17/05	102.16	24.53	0.00	77.63	1.55	--	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<1.0	330	
07/27/05	102.16	27.51	0.00	74.65	-2.98	--	ND<500	ND<5.0	ND<5.0	ND<5.0	ND<10	580	
12/06/05	102.16	29.13	0.00	73.03	-1.62	--	340	ND<0.50	ND<0.50	ND<0.50	ND<1.0	780	
02/21/06	102.16	29.23	0.00	72.93	-0.10	--	190	ND<0.50	ND<0.50	ND<0.50	ND<1.0	340	
06/08/06	102.16	25.76	0.00	76.40	3.47	--	ND<500	ND<5.0	ND<5.0	ND<5.0	ND<10	440	
09/15/06	102.16	29.17	0.00	72.99	-3.41	--	ND<500	ND<5.0	ND<5.0	ND<5.0	ND<5.0	570	
MW-3													
01/05/90	--	--	0.00	--	--	ND	--	ND	ND	ND	ND	--	
05/11/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
08/09/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
11/14/90	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
02/12/91	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
05/09/91	--	--	--	--	--	ND	--	ND	ND	ND	ND	--	
11/13/03	--	--	--	--	--	--	2600	ND<20	ND<20	ND<20	ND<40	3700	
08/27/04	100.00	29.61	0.00	70.39	--	--	1700	ND<10	ND<10	ND<10	ND<20	2600	
11/23/04	100.00	28.48	0.00	71.52	1.13	--	1500	ND<10	ND<10	ND<10	ND<20	1800	
02/09/05	100.00	26.45	0.00	73.55	2.03	--	ND<1000	ND<0.50	ND<0.50	ND<0.50	ND<1.0	2100	
05/17/05	100.00	25.61	0.00	74.39	0.84	--	ND<1000	ND<0.50	ND<0.50	ND<0.50	ND<1.0	1200	
07/27/05	100.00	27.35	0.00	72.65	-1.74	--	ND<1000	ND<10	ND<10	ND<10	ND<20	1400	
12/06/05	100.00	28.78	0.00	71.22	-1.43	--	430	ND<0.50	1.6	ND<0.50	3.6	1800	

Table 2
HISTORIC FLUID LEVELS AND SELECTED ANALYTICAL RESULTS
January 1990 Through September 2006
76 Station 6129

Date Sampled	TOC Elevation	Depth to Water	LPH Thickness	Ground- water Elevation	Change in Elevation	TPH-G (8015M)	TPH-G (GC/MS)	Benzene	Toluene	Ethyl- benzene	Total Xylenes	MTBE (8260B)	Comments
(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	
MW-3 continued													
02/21/06	100.00	28.91	0.00	71.09	-0.13	--	420	ND<0.50	ND<0.50	ND<0.50	ND<1.0	1100	
06/08/06	100.00	25.97	0.00	74.03	2.94	--	ND<1200	ND<12	ND<12	ND<12	ND<25	1000	
09/15/06	100.00	28.73	0.00	71.27	-2.76	--	ND<1200	ND<12	ND<12	ND<12	ND<12	1200	

Table 2 a
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6129


Date Sampled	TBA	Ethanol (8260B)	Ethylene-dibromide (EDB)	1,2-DCA (EDC)	DIPE	ETBE	TAME
	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)
MW-1							
11/13/03	ND<200	ND<1000	ND<4.0	ND<4.0	ND<4.0	ND<4.0	ND<4.0
08/27/04	ND<5.0	ND<50	ND<0.50	ND<0.50	ND<1.0	ND<0.50	ND<0.50
11/23/04	ND<5.0	ND<50	ND<0.50	ND<0.50	ND<1.0	ND<0.50	ND<0.50
02/09/05	ND<5.0	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
05/17/05	ND<5.0	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
07/27/05	ND<5.0	ND<50	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
12/06/05	ND<10	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
02/21/06	ND<10	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
06/08/06	ND<10	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
09/15/06	ND<10	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
MW-2							
11/13/03	ND<4000	ND<20000	ND<80	ND<80	ND<80	ND<80	ND<80
08/27/04	ND<50	ND<500	ND<5.0	ND<5.0	24	ND<5.0	ND<5.0
11/23/04	ND<5.0	ND<50	ND<0.50	ND<0.50	18	ND<0.50	ND<0.50
02/09/05	ND<50	ND<500	ND<5.0	ND<5.0	19	ND<5.0	ND<5.0
05/17/05	ND<5.0	ND<50	ND<0.50	ND<0.50	12	ND<0.50	ND<0.50
07/27/05	140	ND<500	ND<5.0	ND<5.0	16	ND<5.0	ND<5.0
12/06/05	61	ND<250	ND<0.50	ND<0.50	15	ND<0.50	ND<0.50
02/21/06	ND<10	ND<250	ND<0.50	ND<0.50	18	ND<0.50	ND<0.50
06/08/06	ND<100	ND<2500	ND<5.0	ND<5.0	14	ND<5.0	ND<5.0
09/15/06	ND<100	ND<2500	ND<5.0	ND<5.0	17	ND<5.0	ND<5.0
MW-3							
11/13/03	ND<4000	ND<20000	ND<80	ND<80	ND<80	ND<80	ND<80
08/27/04	ND<100	ND<1000	ND<10	ND<10	ND<20	ND<10	ND<10
11/23/04	ND<100	ND<1000	ND<10	ND<10	ND<20	ND<10	ND<10

Table 2 a
ADDITIONAL HISTORIC ANALYTICAL RESULTS
76 Station 6129

Date Sampled	TBA	Ethanol (8260B)	Ethylene- dibromide (EDB)	1,2-DCA (EDC)	DIPE	ETBE	TAME
	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)	(µg/l)
MW-3 continued							
02/09/05	130	ND<1000	ND<10	ND<10	ND<10	ND<10	ND<10
05/17/05	ND<100	ND<1000	ND<10	ND<10	ND<10	ND<10	ND<10
07/27/05	360	ND<1000	ND<10	ND<10	ND<10	ND<10	ND<10
12/06/05	160	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	ND<0.50
02/21/06	88	ND<250	ND<0.50	ND<0.50	ND<0.50	ND<0.50	0.58
06/08/06	ND<250	ND<6200	ND<12	ND<12	ND<12	ND<12	ND<12
09/15/06	ND<250	ND<6200	ND<12	ND<12	ND<12	ND<12	ND<12

FIGURES

PS = 1:1 L:\VICINITY MAP S\6129vm.dwg Oct 05, 2006 - 11:09am lwinters



SCALE 1:24,000

SOURCE:

United States Geological Survey
7.5 Minute Topographic Map:
Oakland East Quadrangle




VICINITY MAP

76 Station 6129
3420 35th Avenue
Oakland, California

TRC

FIGURE 1

PS=1:1 6129-003 L:\Graphics\Projects\Number\20-xxxx\20-0400(Unocad)\MS\20-0400(Unocad)\x-6000\6129+16129_QMS.dwg Oct 09, 2006 - 9:03am Winters



LEGEND

- MW-3 ⊕ Monitoring Well with Groundwater Elevation (feet)
- 73.30 — Groundwater Elevation Contour
- ➔ General Direction of Groundwater Flow

NOTES:
 Contour lines are interpretive and based on fluid levels measured in monitoring wells. Elevations are in feet above mean sea level. UST = underground storage tank.



**GROUNDWATER ELEVATION
 CONTOUR MAP
 September 15, 2006**

76 Station 6129
 3420 35th Avenue
 Oakland, California



FIGURE 2

PS=1:1 6129-003 L:\Graphics\Projects\Number\20-xxxx\20-0400(Unocid\MS)\x-6000\6129+ \6129_GMS.dwg Oct 09, 2006 - 9:04am lwinters



LEGEND

MW-3 ⊕ Monitoring Well with
Dissolved-Phase TPH-G
(GC/MS) Concentration (µg/l)

NOTES:

TPH-G (GC/MS) = total petroleum hydrocarbons with gasoline distinction utilizing EPA Method 8260B.
µg/l = micrograms per liter. ND = not detected at limit indicated on official laboratory report.
UST = underground storage tank.



**DISSOLVED-PHASE
TPH-G (GC/MS)
CONCENTRATION MAP
September 15, 2006**

76 Station 6129
3420 35th Avenue
Oakland, California



FIGURE 3

PS=1:1 6129-003 L:\Graphics\Projects\Number\20-xxx\20-0400(UnocalQMS)\x-6000(UnocalQMS)\6129-QMS.dwg Oct 08, 2006 - 9:03am Iwinters



LEGEND

MW-3 ⊕ Monitoring Well with Dissolved-Phase Benzene Concentration (µg/l)

NOTES:
 µg/l = micrograms per liter. ND = not detected at limit indicated on official laboratory report.
 UST = underground storage tank.


DISSOLVED-PHASE BENZENE CONCENTRATION MAP
 June 8, 2006

76 Station 6129
 3420 35th Avenue
 Oakland, California



FIGURE 4

PS=1:1 6129-003 L:\Graphics\Projects\Number\20-xxxx\20-0400(Unocad)MS\6-6000\6129+ \6129-QMS.dwg Oct 09, 2006 - 9:05am iwhiters



LEGEND

MW-3 ⊕ Monitoring Well with Dissolved-Phase MTBE Concentration (µg/l)

—1,000— Dissolved-Phase MTBE Contour (µg/l)

NOTES:

Contour lines are interpretive and based on laboratory analysis results of groundwater samples. MTBE = methyl tertiary butyl ether. µg/l = micrograms per liter. UST = underground storage tank. Results obtained using EPA Method 8260B.

**DISSOLVED-PHASE MTBE
CONCENTRATION MAP
September 15, 2006**

76 Station 6129
3420 35th Avenue
Oakland, California





FIGURE 5




GRAPHS

Groundwater Elevations vs. Time
76 Station 6129






Elevations may have been corrected for apparent changes due to resurvey

Benzene Concentrations vs Time
76 Station 6129



MTBE 8260B Concentrations vs Time 76 Station 6129



GENERAL FIELD PROCEDURES

Groundwater Monitoring and Sampling Assignments

For each site, TRC technicians are provided with a Technical Service Request (TSR) that specifies activities required to complete the groundwater monitoring and sampling assignment for the site. TSRs are based on client directives, instructions from the primary environmental consultant for the site, regulatory requirements, and TRC's previous experience with the site.

Fluid Level Measurements

Initial site activities include determination of well locations based on a site map provided with the TSR. Well boxes are opened and caps are removed. Indications of well or well box damage or of pressure buildup in the well are noted.

Fluid levels in each well are measured using a coated cloth tape equipped with an electronic interface probe, which distinguishes between liquid phase hydrocarbon (LPH) and water. The depth to LPH (if it is present), to water, and to the bottom of the well are measured from the top of the well casing (surveyors mark or notch if present) to the nearest 0.01 foot. Unless otherwise instructed, a well with less than 0.67 foot between the measured top of water and the measured bottom of the well casing is considered dry, and is not sampled. If the well contains 0.67 foot or more of water, an attempt is made to bail and/or sample as specified on the TSR.

Wells that are found to contain LPH are not purged or sampled. Instead, one casing volume of fluid is bailed from the well and the well is re-sealed. Bailed fluids are placed in a container separate from normal purge water, and properly disposed.

Purging and Groundwater Parameter Measurement

TSR instructions may specify that a well not be purged (no-purge sampling), be purged using low-flow methods, or be purged using conventional pump and/or bail methods. Conventional purging generally consists of pumping or bailing until a minimum of three casing volumes of water have been removed or until the well has been pumped dry. Pumping is generally accomplished using submersible electric or pneumatic diaphragm pumps.

During conventional purging, three groundwater parameters (temperature, pH, and conductivity) are measured after removal of each casing volume. Stabilization of these parameters, to within 10 percent, confirm that sufficient purging has been completed. In some cases, the TSR indicates that other parameters are also to be measured during purging. TRC commonly measures dissolved oxygen (DO), oxidation-reduction potential (ORP), and/or turbidity. Instruments used for groundwater parameter measurements are calibrated daily according to manufacturer's instructions.

Low-flow purging utilizes a bladder or peristaltic pump to remove water from the well at a low rate. Groundwater parameters specified by the TSR are measured continuously until they become stable in general accordance with EPA guidelines.

Purge water is generally collected in labeled drums for disposal. Drums may be left on site for disposal by others, or transported to a collection location for eventual transfer to a licensed treatment or recycling facility. In some cases, purge water may be collected directly from the site by a licensed vacuum truck company, or may be treated on site by an active remediation system, if so directed.

Groundwater Sample Collection

After wells are purged, or not purged, according to TSR instructions, samples are collected for laboratory analysis. For wells that have been purged using conventional pump or bail methods, sampling is conducted after the well has recovered to 80 percent of its original volume or after two hours if the well does not recover to at least 80 percent. If there is insufficient recharge of water in the well after two hours, the well is not sampled.

Samples are collected by lowering a new, disposable, ½-inch to 4-inch polyethylene bottom-fill bailer to just below the water level in the well. The bailer is retrieved and the water sample is carefully transferred to containers specified for the laboratory analytical methods indicated by the TSR. Particular care is given to containers for volatile organic analysis (VOAs) which require filling to zero headspace and fitting with Teflon-sealed caps.

After filling, all containers are labeled with project number (or site number), well designation, sample date, sample time, and the sampler's initials, and placed in an insulated chest with ice. Samples remain chilled prior to and during transport to a state-certified laboratory for analysis. Sample container descriptions and requested analyses are entered onto a chain-of-custody form in order to provide instructions to the laboratory. The chain-of-custody form accompanies the samples during transportation to provide a continuous record of possession from the field to the laboratory. If a freight or overnight carrier transports the samples, the carrier is noted on the form.

For wells that have been purged using low-flow methods, sample containers are filled from the effluent stream of the bladder or peristaltic pump. In some cases, if so specified by the TSR, samples are taken from the sample ports of actively pumping remediation wells.

Sequence of Gauging, Purging and Sampling

The sequence in which monitoring activities are conducted are specified on the TSR. In general, wells are gauged beginning with the least affected well and ending with the well that has the highest concentration based on previous analytic results. After all gauging for the site is completed, wells are purged and/or sampled from the least-affected to the most-affected well.

Decontamination

In order to reduce the possibility of cross contamination between wells, strict isolation and decontamination procedures are observed. Portable pumps are not used in wells with LPH. Technicians wear nitrile gloves during all gauging, purging and sampling activities. Gloves are changed between wells and more often if warranted. Any equipment that could come in contact with fluids are either dedicated to a particular wells, decontaminated prior to each use, or discarded after a single use. Decontamination consists of washing in a solution of Liqui-nox and water and rinsing twice. The final rinse is in deionized water.

Exceptions

Additional tasks or non-standard procedures, if any, that may be requested or required for a particular site, and noted on the site TSR, are documented in field notes on the following pages.

GROUNDWATER SAMPLING FIELD NOTES

Technician: Chris

Site: 6129

Project No.: 41060001

Date: 9-15-06

Well No. MW-1

Purge Method: SUB

Depth to Water (feet): 28.86

Depth to Product (feet): Ø

Total Depth (feet) 43.45

LPH & Water Recovered (gallons): Ø

Water Column (feet): 14.59

Casing Diameter (Inches): 2"

80% Recharge Depth(feet): 31.77

1 Well Volume (gallons): 2

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, C)	pH	D.O.	ORP	Turbidity
1036			2	629	16.1	7.33			
			4	777	18.2	6.96			
	1040		6	775	19.1	6.83			
Static at Time Sampled			Total Gallons Purged			Sample Time			
31.73			6			1050			
Comments:									

Well No. MW-2

Purge Method: SUB

Depth to Water (feet): 29.17

Depth to Product (feet): Ø

Total Depth (feet) 43.58

LPH & Water Recovered (gallons): Ø

Water Column (feet): 14.41

Casing Diameter (Inches): 2"

80% Recharge Depth(feet): 32.05

1 Well Volume (gallons): 2

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (µS/cm)	Temperature (F, C)	pH	D.O.	ORP	Turbidity
1058			2	811	18.6	6.88			
			4	979	18.5	6.69			
	1104		6	852	18.7	6.58			
Static at Time Sampled			Total Gallons Purged			Sample Time			
31.82			6			1109			
Comments:									

GROUNDWATER SAMPLING FIELD NOTES

Technician: Chris

Site: 6129

Project No.: 41060001

Date: 9-15-06

Well No. MW-3

Purge Method: SVB

Depth to Water (feet): 28.73

Depth to Product (feet): 0

Total Depth (feet): 42.61

LPH & Water Recovered (gallons): 0

Water Column (feet): 13.88

Casing Diameter (Inches): 2"

80% Recharge Depth(feet): 31.50

1 Well Volume (gallons): 2

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (uS/cm)	Temperature (F, C)	pH	D.O.	ORP	Turbidity
1120			2	734	18.0	6.85			
	1126		6	658	19.0	6.90			
				612	19.2	7.01			
Static at Time Sampled			Total Gallons Purged		Sample Time				
31.48			6		1138				
Comments:									

Well No. _____

Purge Method: _____

Depth to Water (feet): _____

Depth to Product (feet): _____

Total Depth (feet): _____

LPH & Water Recovered (gallons): _____

Water Column (feet): _____

Casing Diameter (Inches): _____

80% Recharge Depth(feet): _____

1 Well Volume (gallons): _____

Time Start	Time Stop	Depth to Water (feet)	Volume Purged (gallons)	Conductivity (uS/cm)	Temperature (F, C)	pH	D.O.	ORP	Turbidity
Static at Time Sampled			Total Gallons Purged		Sample Time				
Comments:									

Date of Report: 09/29/2006

Anju Farfan

TRC Alton Geoscience


21 Technology Drive
Irvine, CA 92618-2302

RE: 6129

BC Lab Number: 0609643

Enclosed are the results of analyses for samples received by the laboratory on 09/18/06 20:35. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Contact Person: Vanessa Hooker

Client Service Rep



Authorized Signature

TRC Alton Geoscience
 21 Technology Drive
 Irvine CA, 92618-2302

Project: 6129
 Project Number: [none]
 Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Information
------------	---------------------------

0609643-01	COC Number: --- Project Number: 6129 Sampling Location: MW-1 Sampling Point: MW-1 Sampled By: Chris M. of TRCI	Receive Date: 09/18/06 20:35 Sampling Date: 09/15/06 10:50 Sample Depth: --- Sample Matrix: Water	Delivery Work Order: Global ID: T060010465 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	---	--	--

0609643-02	COC Number: --- Project Number: 6129 Sampling Location: MW-2 Sampling Point: MW-2 Sampled By: Chris M. of TRCI	Receive Date: 09/18/06 20:35 Sampling Date: 09/15/06 11:09 Sample Depth: --- Sample Matrix: Water	Delivery Work Order: Global ID: T060010465 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	---	--	--

0609643-03	COC Number: --- Project Number: 6129 Sampling Location: MW-3 Sampling Point: MW-3 Sampled By: Chris M. of TRCI	Receive Date: 09/18/06 20:35 Sampling Date: 09/15/06 11:38 Sample Depth: --- Sample Matrix: Water	Delivery Work Order: Global ID: T060010465 Matrix: W Sample QC Type (SACode): CS Cooler ID:
-------------------	---	--	--

TRC Alton Geoscience
21 Technology Drive
Irvine CA, 92618-2302

Project: 6129
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 0609643-01 **Client Sample Name:** 6129, MW-1, MW-1, 9/15/2006 10:50:00AM, Chris M.

Constituent	Result	Units	PQL	MDL	Method	Prep Date	Run Date/Time	Analyst	Instru-ment ID	Dilution	QC Batch ID	MB Bias	Lab Quals
Benzene	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
1,2-Dibromoethane	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248		
1,2-Dichloroethane	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248		
Ethylbenzene	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
Methyl t-butyl ether	1.4	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
Toluene	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
Total Xylenes	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
t-Amyl Methyl ether	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
t-Butyl alcohol	ND	ug/L	10		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
Diisopropyl ether	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
Ethanol	ND	ug/L	250		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	V11
Ethyl t-butyl ether	ND	ug/L	0.50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
Total Purgeable Petroleum Hydrocarbons	ND	ug/L	50		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248	ND	
1,2-Dichloroethane-d4 (Surrogate)	110	%	76 - 114 (LCL - UCL)		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248		
Toluene-d8 (Surrogate)	101	%	88 - 110 (LCL - UCL)		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248		
4-Bromofluorobenzene (Surrogate)	97.0	%	86 - 115 (LCL - UCL)		EPA-8260	09/27/06	09/28/06 00:09	SDU	MS-V10	1	BPI1248		

TRC Alton Geoscience
 21 Technology Drive
 Irvine CA, 92618-2302

 Project: 6129
 Project Number: [none]
 Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 0609643-02		Client Sample Name: 6129, MW-2, MW-2, 9/15/2006 11:09:00AM, Chris M.												
Constituent	Result	Units	PQL	MDL	Method	Prep Date	Run Date/Time	Analyst	Instru-ment ID	Dilution	QC Batch ID	MB Bias	Lab Quals	
Benzene	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
1,2-Dibromoethane	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248		A01	
1,2-Dichloroethane	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248		A01	
Ethylbenzene	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
Methyl t-butyl ether	570	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
Toluene	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
Total Xylenes	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
t-Amyl Methyl ether	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
t-Butyl alcohol	ND	ug/L	100		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
Diisopropyl ether	17	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
Ethanol	ND	ug/L	2500		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	V11, A01	
Ethyl t-butyl ether	ND	ug/L	5.0		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01	
Total Purgeable Petroleum Hydrocarbons	ND	ug/L	500		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248	ND	A01, J, A53	
1,2-Dichloroethane-d4 (Surrogate)	109	%	76 - 114 (LCL - UCL)		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248			
Toluene-d8 (Surrogate)	98.8	%	88 - 110 (LCL - UCL)		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248			
4-Bromofluorobenzene (Surrogate)	99.2	%	86 - 115 (LCL - UCL)		EPA-8260	09/27/06	09/27/06 18:36	SDU	MS-V10	10	BPI1248			

TRC Alton Geoscience
21 Technology Drive
Irvine CA, 92618-2302

Project: 6129
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

BCL Sample ID: 0609643-03 **Client Sample Name:** 6129, MW-3, MW-3, 9/15/2006 11:38:00AM, Chris M.

Constituent	Result	Units	PQL	MDL	Method	Prep	Run	Analyst	Instru- ment ID	Dilution	QC	MB	Lab
						Date	Date/Time				Batch ID	Bias	Quals
Benzene	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
1,2-Dibromoethane	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
1,2-Dichloroethane	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Ethylbenzene	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Methyl t-butyl ether	1200	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Toluene	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Total Xylenes	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
t-Amyl Methyl ether	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
t-Butyl alcohol	ND	ug/L	250		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Diisopropyl ether	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Ethanol	ND	ug/L	6200		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01, V11
Ethyl t-butyl ether	ND	ug/L	12		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01
Total Purgeable Petroleum Hydrocarbons	ND	ug/L	1200		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334	ND	A01, A53
1,2-Dichloroethane-d4 (Surrogate)	108	%	76 - 114 (LCL - UCL)		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334		
Toluene-d8 (Surrogate)	100	%	88 - 110 (LCL - UCL)		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334		
4-Bromofluorobenzene (Surrogate)	98.8	%	86 - 115 (LCL - UCL)		EPA-8260	09/27/06	09/27/06 18:12	SDU	MS-V10	25	BPI1334		

TRC Alton Geoscience
21 Technology Drive
Irvine CA, 92618-2302

Project: 6129
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Precision & Accuracy

Constituent	Batch ID	QC Sample Type	Source Sample ID	Source Result	Result	Spike Added	Units	RPD	Control Limits		
									Percent Recovery	RPD	Percent Recovery Lab Quas
Benzene	BPI1248	Matrix Spike	0609601-01	ND	24.100	25.000	ug/L		96.4		70 - 130
		Matrix Spike Duplicate	0609601-01	ND	27.120	25.000	ug/L	11.4	108	20	70 - 130
Toluene	BPI1248	Matrix Spike	0609601-01	ND	22.330	25.000	ug/L		89.3		70 - 130
		Matrix Spike Duplicate	0609601-01	ND	25.160	25.000	ug/L	12.3	101	20	70 - 130
1,2-Dichloroethane-d4 (Surrogate)	BPI1248	Matrix Spike	0609601-01	ND	10.160	10.000	ug/L		102		76 - 114
		Matrix Spike Duplicate	0609601-01	ND	10.580	10.000	ug/L		106		76 - 114
Toluene-d8 (Surrogate)	BPI1248	Matrix Spike	0609601-01	ND	9.9700	10.000	ug/L		99.7		88 - 110
		Matrix Spike Duplicate	0609601-01	ND	10.080	10.000	ug/L		101		88 - 110
4-Bromofluorobenzene (Surrogate)	BPI1248	Matrix Spike	0609601-01	ND	9.9600	10.000	ug/L		99.6		86 - 115
		Matrix Spike Duplicate	0609601-01	ND	10.110	10.000	ug/L		101		86 - 115
Benzene	BPI1334	Matrix Spike	0609600-01	0.22000	28.020	25.000	ug/L		111		70 - 130
		Matrix Spike Duplicate	0609600-01	0.22000	27.050	25.000	ug/L	3.67	107	20	70 - 130
Toluene	BPI1334	Matrix Spike	0609600-01	ND	25.460	25.000	ug/L		102		70 - 130
		Matrix Spike Duplicate	0609600-01	ND	24.160	25.000	ug/L	5.44	96.6	20	70 - 130
1,2-Dichloroethane-d4 (Surrogate)	BPI1334	Matrix Spike	0609600-01	ND	10.890	10.000	ug/L		109		76 - 114
		Matrix Spike Duplicate	0609600-01	ND	10.900	10.000	ug/L		109		76 - 114
Toluene-d8 (Surrogate)	BPI1334	Matrix Spike	0609600-01	ND	10.070	10.000	ug/L		101		88 - 110
		Matrix Spike Duplicate	0609600-01	ND	10.170	10.000	ug/L		102		88 - 110
4-Bromofluorobenzene (Surrogate)	BPI1334	Matrix Spike	0609600-01	ND	10.000	10.000	ug/L		100		86 - 115
		Matrix Spike Duplicate	0609600-01	ND	9.7700	10.000	ug/L		97.7		86 - 115

TRC Alton Geoscience
 21 Technology Drive
 Irvine CA, 92618-2302

Project: 6129
 Project Number: [none]
 Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Laboratory Control Sample

Constituent	Batch ID	QC Sample ID	QC Type	Result	Spike Level	PQL	Units	Control Limits		Lab Quals
								Percent Recovery	RPD	
Benzene	BPI1248	BPI1248-BS1	LCS	24.590	25.000	0.50	ug/L	98.4	70 - 130	
Toluene	BPI1248	BPI1248-BS1	LCS	22.050	25.000	0.50	ug/L	88.2	70 - 130	
1,2-Dichloroethane-d4 (Surrogate)	BPI1248	BPI1248-BS1	LCS	10.650	10.000		ug/L	106	76 - 114	
Toluene-d8 (Surrogate)	BPI1248	BPI1248-BS1	LCS	9.8800	10.000		ug/L	98.8	88 - 110	
4-Bromofluorobenzene (Surrogate)	BPI1248	BPI1248-BS1	LCS	10.200	10.000		ug/L	102	86 - 115	
Benzene	BPI1334	BPI1334-BS1	LCS	27.590	25.000	0.50	ug/L	110	70 - 130	
Toluene	BPI1334	BPI1334-BS1	LCS	25.110	25.000	0.50	ug/L	100	70 - 130	
1,2-Dichloroethane-d4 (Surrogate)	BPI1334	BPI1334-BS1	LCS	10.770	10.000		ug/L	108	76 - 114	
Toluene-d8 (Surrogate)	BPI1334	BPI1334-BS1	LCS	10.080	10.000		ug/L	101	88 - 110	
4-Bromofluorobenzene (Surrogate)	BPI1334	BPI1334-BS1	LCS	10.140	10.000		ug/L	101	86 - 115	

TRC Alton Geoscience
 21 Technology Drive
 Irvine CA, 92618-2302

 Project: 6129
 Project Number: [none]
 Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Method Blank Analysis

Constituent	Batch ID	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
Benzene	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.13	
Ethylbenzene	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.14	
Methyl t-butyl ether	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.15	
Toluene	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.15	
Total Xylenes	BPI1248	BPI1248-BLK1	ND	ug/L	1.0	0.40	
t-Amyl Methyl ether	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.31	
t-Butyl alcohol	BPI1248	BPI1248-BLK1	ND	ug/L	10	10	
Diisopropyl ether	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.23	
Ethanol	BPI1248	BPI1248-BLK1	ND	ug/L	1000	110	
Ethyl t-butyl ether	BPI1248	BPI1248-BLK1	ND	ug/L	0.50	0.27	
Total Purgeable Petroleum Hydrocarbons	BPI1248	BPI1248-BLK1	ND	ug/L	50	23	
1,2-Dichloroethane-d4 (Surrogate)	BPI1248	BPI1248-BLK1	107	%	76 - 114 (LCL - UCL)		
Toluene-d8 (Surrogate)	BPI1248	BPI1248-BLK1	99.0	%	88 - 110 (LCL - UCL)		
4-Bromofluorobenzene (Surrogate)	BPI1248	BPI1248-BLK1	101	%	86 - 115 (LCL - UCL)		
Benzene	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.14	
1,2-Dibromoethane	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.22	
1,2-Dichloroethane	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.15	
Ethylbenzene	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.094	
Methyl t-butyl ether	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.13	
Toluene	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.12	
Total Xylenes	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.31	
t-Amyl Methyl ether	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.34	
t-Butyl alcohol	BPI1334	BPI1334-BLK1	ND	ug/L	10	9.3	
Diisopropyl ether	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.34	
Ethanol	BPI1334	BPI1334-BLK1	ND	ug/L	250	85	

TRC Alton Geoscience
 21 Technology Drive
 Irvine CA, 92618-2302

Project: 6129
 Project Number: [none]
 Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Volatile Organic Analysis (EPA Method 8260)

Quality Control Report - Method Blank Analysis

Constituent	Batch ID	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
Ethyl t-butyl ether	BPI1334	BPI1334-BLK1	ND	ug/L	0.50	0.32	
Total Purgeable Petroleum Hydrocarbons	BPI1334	BPI1334-BLK1	ND	ug/L	50	16	
1,2-Dichloroethane-d4 (Surrogate)	BPI1334	BPI1334-BLK1	104	%	76 - 114 (LCL - UCL)		
Toluene-d8 (Surrogate)	BPI1334	BPI1334-BLK1	98.0	%	88 - 110 (LCL - UCL)		
4-Bromofluorobenzene (Surrogate)	BPI1334	BPI1334-BLK1	102	%	86 - 115 (LCL - UCL)		

TRC Alton Geoscience
21 Technology Drive
Irvine CA, 92618-2302

Project: 6129
Project Number: [none]
Project Manager: Anju Farfan

Reported: 09/29/06 09:14

Notes and Definitions

- V11 The Continuing Calibration Verification (CCV) recovery is not within established control limits.
- J Estimated value
- A53 Chromatogram not typical of gasoline.
- A01 PQL's and MDL's are raised due to sample dilution.
- ND Analyte NOT DETECTED at or above the reporting limit
- dry Sample results reported on a dry weight basis
- RPD Relative Percent Difference

Submission #: 08-09642

Project Code:

TB Batch #

SHIPPING INFORMATION

Federal Express UPS Hand Delivery BC Lab Field Service Other (Specify)

SHIPPING CONTAINER

Ice Chest None Box Other (Specify)

Refrigerant: Ice Blue Ice None Other Comments:

Custody Seals: Ice Chest Containers None Comments: Intact? Yes No Intact? Yes No

All samples received? Yes No All samples containers intact? Yes No Description(s) match COC? Yes No

COC Received YES NO

Ice Chest ID: 814
Temperature: 3.9 °C
Thermometer ID: 98

Emissivity: 0.98
Container: 250

Date/Time: 9/18/6
Analyst Init: JMR

SAMPLE CONTAINERS	SAMPLE NUMBERS									
	1	2	3	4	5	6	7	8	9	10
QT GENERAL MINERAL/ GENERAL PHYSICAL										
PT PE UNPRESERVED										
QT INORGANIC CHEMICAL METALS										
PT INORGANIC CHEMICAL METALS										
PT CYANIDE										
PT NITROGEN FORMS										
PT TOTAL SULFIDE										
2oz. NITRATE / NITRITE										
100ml TOTAL ORGANIC CARBON										
QT TOX										
PT CHEMICAL OXYGEN DEMAND										
PTA PHENOLICS										
40ml VOA VIAL TRAVEL BLANK	A.3.	A.3.	A.3.							
40ml VOA VIAL										
QT EPA 413.1, 413.2, 418.1										
PT ODOR										
RADIOLOGICAL										
BACTERIOLOGICAL										
40 ml VOA VIAL- 504										
QT EPA 508/608/8080										
QT EPA 515.1/8150										
QT EPA 525										
QT EPA 525 TRAVEL BLANK										
100ml EPA 547										
100ml EPA 531.1										
QT EPA 548										
QT EPA 549										
QT EPA 632										
QT EPA 8015M										
QT QA/QC										
QT AMBER										
8 OZ. JAR										
32 OZ. JAR										
SOIL SLEEVE										
PCB VIAL										
PLASTIC BAG										
FERROUS IRON										
ENCORE										

Comments: Sample Numbering Completed By: JMR Date/Time: 9/19/6 0030

BC LABORATORIES, INC.

4100 Atlas Court □ Bakersfield, CA 93308
(661) 327-4911 □ FAX (661) 327-1918

CHAIN OF CUSTODY

Analysis Requested

#06-09643

Circle one: Phillips 66 / Unocal		Consultant Firm: TRC		MATRIX (GW) Ground-water (S) Soil (WW) Waste-water (SL) Sludge	BTEX/MTBE by 8021B, Gas by 8015	TPH GAS by 8015M	TPH DIESEL by 8015	8260 full list w/ MTBE & oxygenates	BTEX/MTBE/OXYS BY 8260B	ETHANOL by 8260B	TPH-g by GC/MS	EDB/EDC by 8260B	Turnaround Time Requested
Address: .3420 35 th Ave		21 Technology Drive Irvine, CA 92618-2302 Attn: Anju Farfan											
City: Oakland		4-digit site#: 6129											
State: CA Zip:		Project #: 41060001/FA20											
COP Manager: Thomas Kosel		Sampler Name: <i>Chris</i>											
Lab#	Sample Description	Field Point Name	Date & Time Sampled										
		MW-1 -1	09-15-06 1050	GW					X	X	X	X	STD
		MW-2 -2	↓ 1109	GW					X	X	X	X	STD
		MW-3 -3	↓ 1138	GW					X	X	X	X	STD

CHK BY	DISTRIBUTION
<i>[Signature]</i>	<i>[Signature]</i>
	SUB-OUT <input type="checkbox"/>

Comments: Global ID: T060010465	Relinquished by: <i>Chris M...</i>	Received by: Refrigerator	Date & Time: 09-15-06 11230
	Relinquished by (Signature): <i>[Signature]</i>	Received by: <i>[Signature]</i>	Date & Time: 9/15/06 1440
	Relinquished by (Signature): <i>Ross Dickey 9/18/06</i>	Received by: <i>[Signature]</i>	Date & Time: 9/18/06 1755

(A) = ANALYSIS (C) = CONTAINER (P) = PRESERVATIVE
Ret: [Signature] 9/18/06 2035 *[Signature]* *11/18/06 2035*

STATEMENTS

Purge Water Disposal

Non-hazardous groundwater produced during purging and sampling of monitoring was accumulated at TRC's groundwater monitoring facility at Concord, California, for transportation by Onyx Transportation, Inc., to the ConocoPhillips Refinery at Rodeo, California. Disposal at the Rodeo facility was authorized by ConocoPhillips in accordance with "ESD Standard Operating Procedures – Water Quality and Compliance", as revised on February 7, 2003. Documentation of compliance with ConocoPhillips requirements is provided by an ESD Form R-149, which is on file at TRC's Concord Office. Purge water containing a significant amount of liquid-phase hydrocarbons was accumulated separately in drums for transportation and disposal by Filter Recycling, Inc.

Limitations

The fluid level monitoring and groundwater sampling activities summarized in this report have been performed under the responsible charge of a California Registered Geologist or Registered Civil Engineer and have been conducted in accordance with current practice and the standard of care exercised by geologists and engineers performing similar tasks in this area. No warranty, express or implied, is made regarding the conclusions and professional opinions presented in this report. The conclusions are based solely upon an analysis of the observed conditions. If actual conditions differ from those described in this report, our office should be notified.