

### JUN 2 0 2002



June 18, 2002

3164 Gold Camp Drive Suite 200 Rancho Cordova, CA 95670-6021 U S A 916/638-2085 FAX: 916/638-8385

JUN 2 @ ZOOZ

Mr. Paul Supple Atlantic Richfield Company P.O. Box 6549 Moraga, CA 94570

Subject: Quarterly Groundwater Monitoring Report, First Quarter 2002

ARCO Service Station No. 4931

Oakland, California Project No. D000-313

Dear Mr. Supple:

Delta Environmental Consultants, Inc. is submitting the attached report that presents the results of the first quarter 2002 groundwater monitoring program at ARCO Service Station No. 4931, located at 731 West MacArthur Boulevard, Oakland, California. The monitoring program complies with the Alameda County Health Care Services Agency requirements regarding underground tank investigations.

The interpretations contained in this report represent our professional opinions and are based, in part, on information supplied by the client. These opinions are based on currently available information and are arrived at in accordance with currently accepted hydrogeological and engineering practices at this time and location. Other than this, no warranty is implied or intended.

If you have any questions concerning this project, please contact Steven W. Meeks at (916) 536-2613.

Sincerely,

DELTA ENVIRONMENTAL CONSULTANTS, INC.

Steven W. Meeks, P.E

Project Manager

California Registered Civil Engineer No. C057461

TLA (Lrp007.313.doc) Enclosures

cc: Ms. Susan Hugo – Alameda County Health Care Services Agency

Mr. Chuck Headlee - California Regional Water Quality Control Board, San Francisco Bay Region

JUN 2 0 2002

Date: June 18, 2002

#### ARCO QUARTERLY GROUNDWATER MONITORING REPORT

Station No.: 4931 Address: 731 West MacArthur Boulevard, Oakland, CA

ARCO Environmental Engineer/Phone No.: Paul Supple 925-299-8891

Consulting Co./Contact Person Delta Environmental Consultants, Inc.

Steven W. Meeks, P.E.

Consultant Project No.: D000-313

Primary Agency/Regulatory ID No. Alameda County Health Care Services Agency

#### **WORK PERFORMED THIS QUARTER**

1. Performed quarterly groundwater monitoring for the first quarter 2002.

2. Prepared quarterly groundwater monitoring for the fourth quarter 2001.

#### WORK PROPOSED FOR NEXT QUARTER

1. Prepare and submit quarterly groundwater monitoring report for first quarter 2002.

2. Perform quarterly groundwater monitoring and sampling for second quarter 2002.

3. Site will be transferred to new consultant (URS) during second guarter 2002.

#### **QUARTERLY MONITORING:**

Current Phase of Project	Monitoring/Remediation
Frequency of Groundwater Sampling:	Annual (2 <sup>nd</sup> Quarter): A-7, A-13
, ,	Semi-Annual (2 <sup>nd</sup> /4 <sup>th</sup> Quarter): A-3, A-5, A-11, A-12
	Quarterly: A-2, A-4, A-6, A-8, A-9
Frequency of Groundwater Monitoring:	Quarterly
Is Free Product (FP) Present On-Site:	No
FP Recovered this Quarter:	N/A
Cumulative FP Recovered to Date:	Unknown
Bulk Soil Removed This Quarter:	None
Bulk Soil Removed to Date:	Unknown
Current Remediation Techniques:	Intrinsic Bioremediation Enhancement using ORC
Approximate Depth to Groundwater:	6.04 feet
Groundwater Gradient:	0.047 ft/ft West
Cumulative TPHg/Benzene Removed:	0.45/0.06 gallons

#### **DISCUSSION:**

- Bioremediation enhancement is ongoing using oxygen release compound (ORC) in wells A-4, A-8, A-9 and AR-1.
- Benzene was detected at 1,400 micrograms per liter (μg/L) in a sample collected from monitoring well A-8.
- Total petroleum hydrocarbons as gasoline were detected at 6,600 μg/L in a sample collected from monitoring well A-8.
- Methyl tertiary butyl ether was detected in samples collected from monitoring wells A-4 and A-8 at 1,400 μg/L and 2,700 μg/L, respectively.

#### ATTACHMENTS:

- Table 1 Groundwater Elevation and Analytical Data
- Table 2 Groundwater Flow Direction and Gradient
- Figure 1 Groundwater Analytical Summary Map
- Figure 2 Groundwater Elevation Contour Map
- Appendix A Sampling and Analysis Procedures
- Appendix B Historical Data Tables (IT Corporation)
- Appendix C Certified Analytical Reports with Chain-of-Custody Documentation
- Appendix D Remedial System Performance Summary
- Appendix E Field Sample Data

TABLE 1
GROUNDWATER ANALYTICAL DATA

Well Number	Date Sampled	Top of Riser Elevation (ft)	Depth to Groundwater (ft)	Groundwater Elevation (ft)	Benzene (µg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (μg/L)	TPH as Gasoline (μg/L)	MTBE (µg/L)
A-2	06/21/00	55.48	6.85	48.63	<0.5	<0.5	<0.5	<1.0	<50	<3.0
	09/20/00		10.45	45.03	< 0.5	< 0.5	<0.5	<0.5	<50	<2.5
	12/26/00		6.27	49.21	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	03/20/01		4.57	50.91	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	06/12/01		9.27	46.21	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	09/23/01		10.75	44.73	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	12/31/01		4.13	51.35	< 0.5	< 0.5	1	3.2	<50	<2.5
	03/21/02		3.26	52.22	<0.5	<0.5	<0.5	<0.5	<50	<2.5
A-3	06/21/00	54.66	9.48	45.18	<0.5	<0.5	<0.5	<1.0	<50	46
	09/20/00		10.24	44.42	< 0.5	< 0.5	<0.5	<0.5	<50	89.6
	12/26/00		9.58	45.08	< 0.5	< 0.5	< 0.5	< 0.5	< 50	7.11
	03/20/01		6.34	48.32	NS	NS	NS	NS	NS	NS
	06/12/01		9.76	44.90	< 0.5	< 0.5	< 0.5	<0.5	< 50	86
	09/23/01		10.55	44.11	NS	NS	NS	NS	NS	NS
	12/31/01		3.70	50.96	< 0.5	< 0.5	< 0.5	1	<50	60
	03/21/02		5.75	48.91	NS	NS	NS	NS	NS	NS
A-4	06/21/00	54.73	9.49	45.24	110	2.1	11	5.9	2,100	2,000
	09/20/00		10.33	44.40	127	<5.0	9.07	7.42	1,540	1,940
	12/26/00		9.34	45.39	42.7	<5.0	11	10.9	1,550	1,210
	03/20/01		7.56	47.17	40.9	<5.0	15.5	14.6	913	<25
	06/12/01		9.83	44.90	230	<20	21	<20	2,000	4,700
	09/23/01		10.54	44.19	35	<10	<10	<10	1,600	3,000
	12/31/01		5.42	49.31	<5.0	<5.0	<5.0	<5.0	<500	880
	03/21/02		6.18	48.55	<50	<50	<50	<50	<5,000	1,400
									-	

TABLE 1
GROUNDWATER ANALYTICAL DATA

Well Number	Date Sampled	Top of Riser Elevation (ft)	Depth to Groundwater (ft)	Groundwater Elevation (ft)	Benzene (µg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (μg/L)	TPH as Gasoline (μg/L)	MTBE (μg/L)
A-5	06/21/00	54.17	9.29	44.88	<0.5	<0.5	<0.5	<1.0	980	2,000
	09/20/00		10.23	43.94	NS	NS	NS	NS	NS	NS
	12/26/00		9.65	44.52	<0.5	<0.5	<0.5	<0.5	525	1,200
	03/20/01		8.05	46.12	NS	NS	NS	NS	NS	NS
	06/12/01		9.81	44.36	<5.0	<5.0	<5.0	<5.0	830	3,200
	09/23/01		10.42	43.75	NS	NS	NS	NS	NS	NS
	12/31/01		6.03	48.14	<0.5	<0.5	<0.5	<0.5	320	60
	03/21/02		6.71	47.46	NS	NS	NS	NS	NS	NS
A-6	06/21/00	55.17	8.67	46.50	<0.5	<0.5	<0.5	<1.0	<50	<3.0
	09/20/00		9.34	45.83	< 0.5	< 0.5	<0.5	< 0.5	<50	<2.5
	12/26/00		8.65	46.52	< 0.5	< 0.5	< 0.5	< 0.5	< 50	<2.5
	03/20/01		6.84	48.33	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	06/12/01		8.93	46.24	< 0.5	< 0.5	< 0.5	< 0.5	< 50	7
	09/23/01		9.74	45.43	< 0.5	< 0.5	< 0.5	< 0.5	< 50	<2.5
	12/31/01		4.81	50.36	< 0.5	< 0.5	< 0.5	<0.5	< 50	3.2
	03/21/02		5.44	49.73	<0.5	<0.5	<0.5	<0.5	<50	<2.5
A-7	06/21/00	54.71	8.58	46.13	<0.5	<0.5	<0.5	<1.0	<50	<3.0
	09/20/00		9.19	45.52	NS	NS	NS	NS	NS	NS
	12/26/00		8.50	46.21	NS	NS	NS	NS	NS	NS
	03/20/01		6.75	47.96	NS	NS	NS	NS	NS	NS
	06/12/01		8.80	45.91	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	09/23/01		9.59	45.12	NS	NS	NS	NS	NS	NS
	12/31/01		4.78	49.93	NS	NS	NS	NS	NS	NS
	03/21/02		5.35	49.36	NS	NS	NS	NS	NS	NS

TABLE 1
GROUNDWATER ANALYTICAL DATA

Well Number	Date Sampled	Top of Riser Elevation (ft)	Depth to Groundwater (ft)	Groundwater Elevation (ft)	Benzene (µg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (µg/L)	TPH as Gasoline (μg/L)	MTBE (μg/L)
A-8	06/21/00	53.77	9.07	44.70	<0.5	<0.5	<0.5	810	810	1,500
	09/20/00		9.72	44.05	2,680	46	439	370	10,800	4,410
	12/26/00		9.20	44.57	1,440	<50	202	106	7,700	2,230
	03/20/01		7.51	46.26	1,280	<50	53.9	<50	<5,000	2,880
	06/12/01		9.53	44.24	1,700	<50	61	54	5,600	2,900
	09/23/01		10.08	43.69	3,500	<50	110	64	10,000	6,500
	12/31/01		4.34	49.43	610	<10	60	24	4,300	520
	03/21/02		6.67	47.10	1400	<50	130	<50	6,600	2,700
A-9	06/21/00	53.04	8.56	44.48	<0.5	<0.5	<0.5	<1.0	<50	5.0
	09/20/00		9.05	43.99	< 0.5	< 0.5	<0.5	<0.5	<50	<2.5
	12/26/00		8.49	44.55	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	03/20/01		6.95	46.09	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	06/12/01		8.67	44.37	< 0.5	< 0.5	< 0.5	<0.5	< 50	4.8
	09/23/01		9.21	43,83	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	12/31/01		4.57	48.47	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	03/21/02		5.60	. 47.44	<0.5	<0.5	<0.5	<0.5	<50	<2.5
A-10	06/21/00	54.26	10.47	43.79	NS	NS	NS	NS	NS	NS
	09/20/00		10.76	43.50	NS	NS	NS	NS	NS	NS
	12/26/00		NM	NC	NS	NS	NS	NS	NS	NS
	03/20/01		NM	NC	NS	NS	NS	N\$	NS	NS
	09/23/01		NM	NC	NS	NS	NS	NS	NS	NS
	12/31/01		NM	NC	NS	NS	NS	NS	NS	NS
	03/21/02		NM	NC	NS	NS	NS	NS	NS	NS

TABLE 1
GROUNDWATER ANALYTICAL DATA

Well Number	Date Sampled	Top of Riser Elevation (ft)	Depth to Groundwater (ft)	Groundwater Elevation (ft)	Benzene (µg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (µg/L)	TPH as Gasoline (μg/L)	MTBE (µg/L)
A-11	06/21/00	53.74	9.54	44.20	<0.5	<0.5	<0.5	<1.0	<50	4.0
	09/20/00		10.62	43.12	NS	NS	NS	NS	NS	NS
	12/26/00		10.03	43.71	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	03/20/01		8.49	45.25	N\$	NS	NS	NS	NS	NS
	06/12/01		10.21	43.53	< 0.5	< 0.5	< 0.5	<0.5	< 50	<2.5
	09/23/01		10.77	42.97	NS	NS	NS	NS	NS	NS
	12/31/01		6.06	47.68	< 0.5	< 0.5	< 0.5	< 0.5	< 50	<2.5
	03/21/02		7.14	46.60	NS	NS	NS	NS	NS	NS
A-12	06/21/00	52.05	9.28	42.77	<0.5	<0.5	<0.5	<1.0	<50	18
	09/20/00		9.55	42.50	NS	NS	NS	NS	NS	NS
	12/26/00		9.05	43.00	< 0.5	< 0.5	< 0.5	<0.5	< 50	17.3
	03/20/01		7.92	44.13	NS	NS	NS	NS	NS	NS
	06/12/01		9.26	42.79	< 0.5	< 0.5	< 0.5	<0.5	< 50	25
	09/23/01		9.68	42.37	NS	NS	NS	NS	NS	NS
	12/31/01		5.74	46.31	< 0.5	< 0.5	< 0.5	<0.5	< 50	9.5
	03/21/02		6.64	45.41	NS	NS	NS	NS	NS	NS
A-13	06/21/00	55.11	NM	NC	NS	NS	NS	NS	NS	NS
	09/20/00		NM	NC	NS	NS	NS	NS	NS	NS
	12/26/00		NM	NC	NS	NS	NS	NS	NS	NS
	03/20/01		NM	NC	NS	NS	NS	NS	NS	NS
	06/12/01		NM	NC	NS	NS	NS	NS	NS	NS
	09/23/01		NM	NC	NS	NS	NS	NS	NS	NS
	12/31/01		NM	NC	NS	NS	NS	NS	NS	NS
	03/21/02		6.70	48.41	NS	NS	NS	NS	NS	NS

TABLE 1
GROUNDWATER ANALYTICAL DATA

Well Number	Date Sampled	Top of Riser Elevation (ft)	Depth to Groundwater (ft)	Groundwater Elevation (ft)	Benzene (µg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (µg/L)	TPH as Gasoline (μg/L)	MTBE (μg/L)
AR-1	06/21/00	54.72	NM	NC	NS	NS	NS	NS	NS	NS
	09/20/00		NM	NC	NS	NS	NS	NS	NS	NS
	12/26/00		9.95	44.77	NS	NS	NS	NS	NS	NS
	03/20/01		8.34	46.38	NS	NS	NS	NS	NS	NS
	06/12/01		10.17	44.55	NS	NS	NS	NS	NS	NS
	09/23/01		10.72	44.00	NS	NS	NS	NS	NS	NS
	12/31/01		5.91	48.81	NS	NS	NS	NS	NS	NS
	03/21/02		7.00	47.72	NS	NS	NS	NS	NS	NS
AR-2	06/21/00	54.77	NM	NC	NS	NS	NS	NS	NS	NS
	09/20/00		NM	NC	NS	NS	NS	NS	NS	NS
	12/26/00		NM	NC	NS	NS	NS	NS	NS	NS
	03/20/01		3.13	51.64	NS	NS	NS	NS	NS	NS
	06/12/01		4.51	50.26	NS	NS	NS	NS	NS	NS
	09/23/01		6.05	48.72	NS	NS	NS	NS	NS	NS
	12/31/01		2.79	51.98	NS	NS	NS	NS	NS	NS
	03/21/02		7.75	47.02	NS	NS	NS	NS	NS	NS

TABLE 1
GROUNDWATER ANALYTICAL DATA

Well Number	Date Sampled	Top of Riser Elevation (ft)	Depth to Groundwater (ft)	Groundwater Elevation (ft)	Benzene (µg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (μg/L)	TPH as Gasoline (µg/L)	MTBE (µg/L)
AR-3	06/21/00	54.19	NM	NC	NS	NS	NS	NS	NS	NS
	09/20/00		NM	NC	NS	NS	NS	NS	NS	NS
	12/26/00		9.70	44.49	NS	NS	NS	NS	NS	NS
	03/20/01		NM	NC	NS	NS	NS	NS	NS	NS
	06/12/01		NM	NC	NS	NS	NS	NS	NS	NS
	09/23/01		10.43	43.76	NS	NS	NS	NS	NS	NS
	12/31/01		5.18	49.01	NS	NS	NS	NS	NS	NS
	03/21/02		6.78	47.41	NS	NS	NS	NS	NS	NS

<sup>&</sup>lt;sup>a</sup> Well appears to have been paved over

μg/L = Micrograms per liter

TPH = Total Petroleum Hydrocarbons

NM = Not measured

MTBE = Methyl tertiary butyl ether analyzed by EPA Method 8021B unless otherwise noted

NC = Not calculated

NS = Not sampled

Note: Please refer to Appendix B for Historical Groundwater Elevation and Analytical Data Tables developed by IT Corporation


### TABLE 2


### FLOW DIRECTION AND GRADIENT

ARCO Service Station No. 4931 731 West Macarthur Boulevard Oakland, California

Date Measured	Average Flow Direction	Average Hydraulic Gradient
06/21/00	West-Southwest	0.031
09/20/00	Southwest	0.013
12/26/00	West	0.028
03/20/01	West	0.046
06/12/01	West	0.014
09/23/01	West	0.012
12/31/01	West	0.024
03/21/02	West	0.047

Note: Please refer to Appendix B for Historical Groundwater Elevation and Analytical Data Tables developed by IT Corporation





NOTE: SITE MAP ADAPTED FROM IT CORPORATION FIGURES SITE DIMENSIONS AND FACILITY LOCATIONS NOT VERIFIED.

### FIGURE 1

GROUND WATER ANALYTICAL SUMMARY FIRST QUARTER 2002 (3/21/02)


ARCO STATION NO. 4931


731 WEST MACARTHUR BOULEVARD

OAKLAND, CALIFORNIA

PROJECT NO. D000-313	DRAWN BY TLA 6/2/02
FILE NO 4931-1	PREPARED BY TLA
REVISION NO. 1	REVIEWED BY







NOTE: SITE MAP ADAPTED FROM IT CORPORATION FIGURES. SITE DIMENSIONS AND FACILITY LOCATIONS NOT VERIFIED.

FIGURE 2

GROUND WATER ELEVATION CONTOUR MAP FIRST QUARTER 2002 (3/21/02)

ARCO STATION NO. 4931

731 WEST MACARTHUR BOULEVARD

OAKLAND, CALIFORNIA

PROJECT NO D000-313	DRAWN BY TLA 6/2/02
FILE NO. 4931-1	PREPARED BY TLA
REVISION NO	REVIEWED BY



### **APPENDIX A**

Sampling and Analysis Procedures

#### FIELD METHODS AND PROCEDURES

#### 1.0 GROUND WATER AND LIQUID-PHASE HYDROCARBON DEPTH ASSESSMENT

A water/liquid-phase hydrocarbon (LPH) interface probe was used to assess the thickness of LPH, if present, and a water level indicator was used to measure ground water depth in monitoring wells that did not contain LPH. Depth to ground water was measured from the top of each monitoring well casing. The tip of the water level indicator was subjectively analyzed for LPH sheen. All measurements and physical observations were recorded in the field.

#### 2.0 SUBJECTIVE ANALYSIS OF GROUND WATER

Prior to purging, a water sample was collected from the monitoring well for subjective analysis. The sample was retrieved by gently lowering a clean, disposable bailer to approximately one-half the bailer length past the air/liquid interface. The bailer was then retrieved and the sample contained within the bailer was examined for LPH and the appearance of a LPH sheen.

#### 3.0 MONITORING WELL PURGING AND SAMPLING

Monitoring wells were purged using a centrifugal pump or disposable bailers until pH, temperature, and conductivity of the purge water had stabilized and a minimum of three to four well volumes of water had been removed. Ground water removed from the wells was stored in 55-gallon barrels at the site. The barrels were labeled with corresponding monitoring well numbers and the date of purging. After purging, ground water levels were allowed to stabilize. A ground water sample was then removed from each of the wells using a dedicated disposable bailer. If the well was purged dry, it was allowed to sufficiently recharge and a sample was collected. Samples were collected in air-tight vials, appropriately labeled, and stored on ice from the time of collection through the time of delivery to the laboratory. A chain-of-custody form was completed to document possession of the samples. Ground water samples were transported to the laboratory and analyzed within the EPA-specified holding times for the requested analyses. Purge water will be collected from the storage barrels in a vacuum truck and transported to an appropriate facility for treatment and/or disposal.

If the depth to groundwater was above the top of screens of the monitoring wells, then the wells were purged. Before sampling occurred, a polyvinyl chloride (PVC) bailer, centrifugal pump, low-flow submersible pump, or Teflon bailer was used to purge standing water in the casing and gravel pack from the monitoring well. Monitoring wells were purged according to the protocol previously stated in the first paragraph of this sub-section. In most monitoring wells, the amount of water purged before sampling was greater than or equal to three casing volumes. Some monitoring wells were expected to be evacuated to dryness after removing fewer than three casing volumes. These low-yield monitoring wells were allowed to recharge for up to 24 hours. Samples were obtained as soon as the monitoring wells recharged to a level sufficient for sample collection. If insufficient water recharged after 24 hours, the monitoring well was recorded as dry for the sampling event.

### APPENDIX B

Historical Data Tables

IT Corporation

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	ТРН	<u> </u>		Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene		Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-2	03/26/96	55.48	5.37	50.11	<50	<0.5	< 0.5	< 0.5	<0.5	NA	NA	NM	
A-2	05/22/96	55.48	5.25	50.23	<50	<0.5	<0.5	< 0.5	< 0.5	NA	NA	NM	
A-2	08/22/96	55.48	10.45	45.03	<50	1.1	1.8	< 0.5	1.3	<2.5	NA	NM	
A-2	12/19/96	55.48	5.53	49.95	<50	<0.5	< 0.5	< 0.5	< 0.5	2.7	NA	NM	
A-2	04/01/97	55.48	8.77	46.71	<50	< 0.5	< 0.5	< 0.5	< 0.5	<2.5	NA	NM	
A-2	05/27/97	55.48	9.87	45.61	<50	< 0.5	< 0.5	< 0.5	< 0.5	4.6	NA	NM	
A-2	08/12/97	55.48	11.11	44.37	<50	< 0.5	< 0.5	< 0.5	< 0.5	5.6	NA	NM	
A-2	11/14/97	55.48	10.63	44.85	<50	0.9	2.8	< 0.5	2.4	27	NA	2.6	
A-2	03/18/98	55.48	3.58	51.90	<50	< 0.5	< 0.5	< 0.5	<0.5	<3	NA	NM	
A-2	05/19/98	55.48	4.82	50.66	<50	< 0.5	< 0.5	< 0.5	< 0.5	<3	NA	1 30	Р
A-2	07/29/98	55.48	8.94	46.54	<50	< 0.5	< 0.5	< 0.5	<0.5	<3	NA	1.2	NP
A-2	10/09/98	55.48	10.82	44.66	<50	< 0.5	< 0.5	< 0.5	<0.5	<3	NA	0.5	NP
A-2	02/19/99	55.48	4.46	51.02	<50	< 0.5	< 0.5	<0.5	< 0.5	<3	NA	3.0	P
A-2	06/02/99	55.48	5.59	49.89	<50	< 0.5	0.6	<0.5	< 0.5	<3	NA	5.35	NP
A-2	08/26/99	55.48	10.67	44.81	<50	< 0.5	< 0.5	< 0.5	<0.5	<3	NA	0.79	NP
A-2	10/26/99	55.48	4.61	50.87	<50	< 0.5	<0.5		<1	<3	NA	2 14	P
A-2	02/25/00	55.48	3.10	52.38	<50	<0.5	< 0.5	<0.5	<1	<3	NA	4.21	NP
A-3	03/26/96	54.66	7.20	47.46	Not Sample	ed: Well S	ampled Se	emiannual	ly				
A-3	05/22/96	54.66	7.70	46.96	<50	1.2	1.9		1.3	NA	NA	NM	
A-3	08/22/96	54.66	10.88	43.78	Not Sample	ed: Well S	ampled Se	emiannual	ly				
A-3	12/19/96	54.66	7.70	46.96	5,900	<25	<25	<25	<25	NA	5,300	NM	
A-3	04/01/97	54.66	9.78	44.88	Not Sample	ed: Well S	ampled Se	emiannual	ly		•		
A-3	05/27/97	54.66	10.55	44,11	2,300	<20	· <20	<20	<20	3,800	NA	NM	
A-3	08/12/97	54.66	11.12	43.54	Not Sample	ed: Well S	ampled Se	emiannual	ly	,			
A-3	11/14/97	54.66	8.24	46.42	<1,000	<10	<10	<10	<10	1,500	NA	3.8	
A-3	03/18/98	54.66	5.05	49.61	Not Sample	ed: Well S	ampled Se	emiannual	ly	•			
A-3	05/19/98	54.66	9.00	45.66	<250	<2.5	<2.5		<2.5	220	NA	4 60	Р
A-3	07/29/98	54.66	9.86	44.80	Not Sample	ed: Well S	ampled Se	emiannual	ly				
A-3	10/09/98	54.66	11.36	43.30	<250	<2.5	·<2.5	<2.5	<2.5	260	NA	1.0	NP
A-3	02/19/99	54.66	6.19	48.47	<50	< 0.5	< 0.5	< 0.5	< 0.5	<3	NA	2 5	NP
A-3	06/02/99	54.66	10.82	43.84	120	<1	<1	<1	<1	160	NA	2.78	NP

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	TPH			Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene	benzene	Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-3	08/26/99	54.66	10.73	43.93	Not Sampl	ed: Well S	ampled Se	emiannual	lv			0.95	
A-3	10/26/99	54.66	6.58	48.08	<50		<0.5	<0.5	., <1	32	NA	2.06	NP
A-3	02/25/00	54.66	5.41	49.25	Not Sampl					J <b>.</b>		2.00	111
-									-,				
A-4	03/26/96	54.73	7.95	46.78	8,900	1,200	21	200	220	NA	NA	NM	
∥ A-4	05/22/96	54.73	8.35	46.38	5,300	700	<10	170	130	NA	NA	NM	
A-4	08/22/96	54.73	11.03	43.70	3,000	480	<5.0	75	26	150	NA	NM	
A-4	12/19/96	54.73	8.67	46.06	<2,000	<20	<20	<20	<20	NA	15,000	NM	
A-4	04/01/97	54.73	11.95	42.78	8,900	1,700	22	310	260	6,900	NA	NM	
A-4	05/27/97	54.73	10.80	43.93	7,100	960	<20	150	74	7,900	NA	NM	
A-4	08/12/97	54.73	11.38	43.35	4,300	670	12	51	27	2,800	NA	NM	
A-4	11/14/97	54.73	7.74	46.99	<20,000	300	500	<200	< 200	27,000	NA	2.2	
A-4	03/18/98	54.73	6.80	47.93	4,700	600	<20	99	94	1,200	NA	1.0	
A-4	05/19/98	54.73	9.06	45.67	<2000	<20	<20	<20	720	2,000	NA	1.28	P
∥ A-4	07/29/98	54.73	10.05	44.68	8,400	1,300	<20	290	130	1,800	NA	0.7	NP
A-4	10/09/98	54.73	11.20	43.53	3,500	400	<20	54	<20	1,700	NA	1.0	NP
A-4	02/19/99	54.73	6.85	47.88	<1,000	<10	<10	<10	12	650	NA	0.1	NP .
A-4	06/02/99	54.73	11.00	43.73	6,100	760	16	260	89	2,300	NA	1 12	NP
A-4	08/26/99	54.73	10.80	43.93	1,100	68	5	8	4	1,400	NA	1 15	NP
A-4	10/26/99	54.73	10.11	44.62	1,500	39	2.3	9.0	5	1,700	NA	10.12	NP
A-4	02/25/00	54.73	5.90	48.83	870	53	1.1	4.6	20	600	NA	1.72	NP
1	03/26/96	54.17	7.00	4634	N. G. I	. 1 337 11 6							
A-5		54.17	7.93	46.24	Not Sample				-				
A-5	05/22/96	54.17	8.20	45.97	<50		< 0.5	<0.5	<0.5	NA	NA	NM	
A-5	08/22/96	54.17	10.70	43.47	Not Sample								
A-5	12/19/96	54.17	8.39	45.78	9,900		330	230	700	NA	24	NM	
A-5	04/01/97	54.17	10.83	43.34	Not Sample								
A-5	05/27/97	54.17	10.65	43.52	100		<0.5	<0.5	<0.5	120	NA	NM	
A-5	08/12/97	54.17	11.05	43.12	Not Sample								
A-5	11/14/97	54.17	10.51	43.66	<50		<0.5	<0.5	<0.5	41	NA	4.8	
A-5	03/18/98	54.17	8.10	46.07	Not Sample					710	31.	0.40	ъ
A-5	05/19/98	54,17	9.31	44.86	590	<5	<5	<5	<5	710	NA.	2 48	P

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	ТРН			Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene		benzene	Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-5	07/29/98	54.17	9.89	44.28	Not Sampl	ed: Well S	ampled Se	emiannual	lv				
A-5	10/09/98	54.17	11.02	43.15	690		•		<b>&lt;</b> 5	710	NA	1.0	NP
A-5	02/19/99	54.17	6.82	47.35	<2,000	<20	<20	<20	<20	2,300	NA		NP
A-5	06/02/99	54.17	10.82	43.35	1,500	< 0.5	2.3	< 0.5	< 0.5	2,400	NA	2.81	NP
A-5	08/26/99	54.17	10.65	43.52	Not Sampl	ed: Well S	ampled Se	emiannual	ly	•		0.49	
A-5	10/26/99	54.17	10.35	43.82	380		< 0.5	< 0.5	<1	440	NA	1,55	NP
A-5	02/25/00	54.17	6.89	47.28	Not Sampl	ed: Well S	ampled Se	emiannual	ly				
	00400												
A-6	03/26/96	55.17	7.15	48.02	52		<0.5	1.1	2.0	NA	NA		
A-6	05/22/96	55.17	7.35	47.82	<50		<0.5	0.88	1.7	NA	NA		
A-6	08/22/96	55.17	10.12	45.05	<50		<0.5	<0.5	<0.5	<2.5	NA	NM	
A-6	12/19/96	55.17	7.43	47.74	<50		< 0.5	0.78	1.5	<2.5	NA	NM	
A-6	04/01/97	55.17	9.97	45.20	<50		<0.5	1.9	3.2	<2.5	NA	NM	
A-6	05/27/97	55.17	9.66	45.51	<50		<0.5	<0.5	<0.5	<2.5	NA	NM	
A-6	08/12/97	55.17	10.43	44.74	<50		< 0.5	< 0.5	< 0.5	<2.5	NA	NM	
A-6	11/14/97	55.17	9.76	45.41	<50		<0.5	<0.5	< 0.5	<3	NA	<1.0	
A-6	03/18/98	55.17	7.00	48.17	<50		0.5	2.3	2.6	<3	NA	3.0	
A-6	05/19/98	55.17	8.27	46.90	<50		< 0.5	1.3	4.7	<3	NA	2.16	P
A-6	07/29/98	55.17	8.96	46.21	<50		< 0.5	< 0.5	< 0.5	<3	NA	0.8	NP
A-6	10/09/98	55.17	10.23	44.94	<50		<0.5	< 0.5	<0.5	<3	NA	1.0	NP
A-6	02/19/99	55.17	5.79	49.38	<50		< 0.5	< 0.5	< 0.5	5	NA	0 4	NP
A-6	06/02/99	55,17	9.71	45.46	<50		<0.5	< 0.5	< 0.5	<3	NA	2.00	NP
A-6	08/26/99	55,17	9.79	45 38	<50		<0.5	< 0.5	0.7	<3	NA	0.66	NP
A-6	10/26/99	55.17	9.70	45.47	<50	< 0.5	< 0.5	< 0.5	<1	<3	NA	1.66	NP
A-6	02/25/00	55.17	5.68	49.49	<50	< 0.5	< 0.5	< 0.5	<1	<3	NA	1.22	NP
A-7	03/26/96	54.71	6.90	47.81	Not Sample				-				
A-7	05/22/96	54.71	8.27	46.44	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	NM	
A-7	08/22/96	54.71	9.80	44.91	Not Sample		-		ly				
A-7	12/19/96	54.71	7.19	47.52	Not Sample								
A-7	04/01/97	54.71	9.63	45.08	Not Sample								
A-7	05/27/97	<u>54</u> 71	9.34	45.37	<u>&lt;5</u> 0	<0.5	<0.5	<0.5	<0 5	<2.5	NA	NM	

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	ТРН			Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene	benzene	Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-7	08/12/97	54.71	10.10	44.61	Not Sampl	ed: Well S	ampled A	nnually					
A-7	11/14/97	54.71	9.35	45.36	Not Sampl		•	•					
A-7	03/18/98	54.71	6.75	47.96	Not Sampl								
A-7	05/19/98	54.71	8.85	45.86	<50		<0.5		< 0.5	<3	NA	1.82	P
A-7	07/29/98	54.71	8.84	45.87	Not Sampl	ed: Well S	ampled A	nnually					
A-7	10/09/98	54.71	10.05	44.66	Not Sampl								
A-7	02/19/99	54.71	5.57	49.14	<50	< 0.5	<0.5	< 0.5	< 0.5	<3	NA	4.7	NP
A-7	06/02/99	54,71	9.56	45.15	<50	< 0.5	< 0.5	< 0.5	< 0.5	<3	NA	2.17	NP
A-7	08/26/99	54.71	9.66	45.05	Not Sampl	ed: Well S	Sampled A	nnually				0.49	
A-7	10/26/99	54.71	9.54	45.17	Not Sampl	ed: Well S	ampled A	nnually				1.26	
A-7	02/25/00	54.71	5.60	49.11	Not Sampl	ed: Well S	sampled A	nnually					
A-8	03/26/96	53,77	7.10	46.67	48,000	2,600	<100	650	1,100	NA	NA	NM	
A-8	05/22/96	53.77	7.20	46.57	14,000	,			190	NA	NA	NM	
A-8	08/22/96	53.77	11.57	42.20	8,000				96	4,300	NA	NM	
A-8	12/19/96	53.77	8.04	45.73	12,000	,			230	<500	NA	NM	
A-8	04/01/97	53.77	9.98	43.79	Not Sampl								
A-8	05/27/97	53.77	11.45	42,32	11,000				210	2,300	NA	NM	
A-8	08/12/97	<i>5</i> 3.77	11.59	42.18	Not Sampl			emiannual		•			
A-8	11/14/97	53.77	9.85	43.92	26,000					4,100	NA	2.2	
A-8	03/18/98	53.77	7.80	45.97	Not Sampl			emiannual	ly	·			
A-8	05/19/98	53.77	8.78	44.99	88,000					6,700	NA	1.36	P
A-8	07/29/98	53.77	9.59	44.18	46,000	4,900	160	620	580	13,000	NA	0.5	NP
A-8	10/09/98	53.77	11.23	42.54	130,000	3,700	110	500	770	7,300	NA	1.0	NP
A-8	02/19/99	53.77	6.51	47.26	<1,000			<10	<10	840	NA	0.2	NP
A-8	06/02/99	53.77	10.68	43.09	8,500	1,300	32	180	110	6,700	NA	1.31	NP
A-8	08/26/99	53.77	10.43	43.34	6,200			64	60	3,700	NA	0.69	
A-8	10/26/99	53.77	10.23	43.54	15,000	2,800			360	480	NA	0.62	NP
A-8	02/25/00	53.77	5.93	47.84	2,600	330	6.6	18	26	1,100	NA	1.43	NP
A-9	03/26/96	53.04	7.05	45.99	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	NM	
A-9	05/22/96	53.04	7.20	45.84	<50				<0.5	NA	NA	NM	

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	ТРН	·		Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene	benzene	Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-9	08/22/96	53.04	9.68	43.36	<50	<0.5	<0.5	<0.5	<0.5	8.5	NA	NM	
A-9	12/19/96	53.04	7.43	45.61	<50		<0.5	<0.5	<0.5	2.6	NA	NM	
A-9	04/01/97	53.04	9.95	43.09	Not Sample							2 ****	
A-9	05/27/97	53.04	9.56	43.48	<50	2.3	<0.5	<0.5	<0.5	45	NA	NM	
A-9	08/12/97	53.04	10.15	42.89	Not Sampl			emiannual					
A-9	11/14/97	53.04	8.64	44.40	<200	<2.0	<2.0	<2.0	<2.0	190	NA	9.6	
A-9	03/18/98	53.04	6.45	46.59	Not Sample	ed: Well S	ampled Se	miannual					
A-9	05/19/98	53.04	8.35	44.69	<50	<0.5	<0.5	< 0.5	< 0.5	7	NA	1.27	P
A-9	07/29/98	53.04	8.74	44.30	<50	< 0.5	< 0.5	< 0.5	< 0.5	<3	NA	0.99	NP
A-9	10/09/98	53.04	10.05	42.99	<50	< 0.5	< 0.5	< 0.5	< 0.5	<3	NA	1.0	NP
A-9	02/19/99	53.04	6.91	46.13	<50	<0.5	< 0.5	< 0.5	< 0.5	<3	NA	2.0	NP
A-9	06/02/99	53.04	9.72	43.32	<50	<0.5	< 0.5	< 0.5	< 0.5	16	NA	2.32	NP
A-9	08/26/99	53.04	9.48	43.56	<50	<0.5	<0.5	< 0.5	< 0.5	<3	NA	0.71	NP
A-9	10/26/99	53.04	9.17	43.87	1,500	6.2	0.7	78	11	91	NA	2.15	NP
A-9	02/25/00	53.04	5.84	47.20	<50	<0.5	< 0.5	< 0.5	<1	<3	NA	1.55	NP
A-10	03/26/96	54.26	8.28	45.98	Not Sample	ed: Well R	emoved fi	rom Samp	ling Progra	am			
A-10	05/22/96	54.26	8.60	45.66	Not Sample								
A-10	08/22/96	54.26	10.98	43.28	Not Sample								
A-10	12/19/96	54 26	8.80	45.46	Not Sample								
A-10	04/01/97	54.26	11.15	43.11	Not Sample								
A-10	05/27/97	54.26	10.90	43.36	Not Sample								
A-10	08/12/97	54.26	11.30	42.96	Not Sample								
A-10	11/14/97	54.26	10.80	43.46	Not Sample								
A-10	03/18/98												
A-11	03/26/96	53.74	8.10	45.64	Not Sample	ed. Well S	amnled Sa	miannyali	١,,				
A-11	05/22/96	53.74	8.25	45.49	<50	o. wen s	20.5 × ampied	31112111112111   0.5	<0.5	NA	NA	NM	
A-11	08/22/96	53.74	10.58	43.16	Not Sample					NA	INA	INIVI	
A-11	12/19/96	53.74	8.37	45.37	<50	50. WEN 5	20.5 <	711121111112211 0.5>	<0.5	<2.5	NA	NM	
A-11	04/01/97	53.74	10.95	42.79	Not Sample					~2.3	INA	INIVI	
A-11	05/27/97	53 74	10.60	43.14	<50	<0.5	20.5	40.5	<0.5	3.1	NA	NM	

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	TPH			Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene	benzene	Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-11	08/12/97	53.74	11.07	42.67	Not Sample	ed: Well S	ampled Se	miannuall	iv.				
A-11	11/14/97	53.74	10.58	43.16	<50		40.5	<0.5	<0.5	<3	NA	1.6	
A-11	03/18/98	53.74	8.14	45.60	Not Sample					-,	1121	1.0	
A-11	05/19/98	53.74	9.40	44.34	<50		<0.5	<0.5	<0.5	<3	NA	1.13	P
A-11	07/29/98	53.74	10.32	43.42	Not Sample					-			•
A-11	10/09/98	53.74	10.91	42.83	<50		<0.5	<0.5	<0.5	<3	NA	2.0	NP
A-11	02/19/99	53.74	6.77	46.97	<50		< 0.5	< 0.5	< 0.5	<3	NA	1.8	NP
A-11	06/02/99	53.74	10.95	42.79	<50	< 0.5	< 0.5	< 0.5	< 0.5	6	NA	1.38	NP
A-11	08/26/99	53.74	11.05	42.69	Not Sample	ed: Well S	ampled Se	emiannuall				0.49	
A-11	10/26/99	53.74	10.81	42.93	<50		<0.5	< 0.5	~ <1	4	NA	1.27	NP
A-11	02/25/00	53.74	6.70	47 04	Not Sample	ed: Well S	ampled Se	miannuall	y				
A-12	03/26/96	52.05	7.83	44.22	Not Sample	ed: Well S	ampled Se	emiannuall	ly				
A-12	05/22/96	52.05	7.80	44.25	<50		<0.5	<0.5	< 0.5	NA	NA	NM	
A-12	08/22/96	52.05	9.97	42.08	Not Sample			emiannuall	y				
A-12	12/19/96	52.05	8.18	43.87	85		< 0.5	< 0.5	< 0.5	170	NA	NM	
A-12	04/01/97	52.05	10 30	41.75	Not Sample								
A-12	05/27/97	52.05	10.05	42.00	50		<0.5	< 0.5	< 0.5	96	NA	NM	
A-12	08/12/97	52.05	10.46	41.59	Not Sample				•				
A-12	11/14/97	52.05	9.70	42.35	<50		<0.5	<0.5	< 0.5	75	NA	7.0	
A-12	03/18/98	52.05	8.15	43.90	Not Sample								
A-12	05/19/98	52.05	9 15	42.90	<50		<0.5	<0.5	< 0.5	29	NA	1.47	P
A-12	07/29/98	52.05	9.38	42.67	Not Sample								
A-12	10/09/98	52 05	10.21	41.84	<50		<0.5	<0.5	<0.5	7	NA	2.0	NP
A-12	02/19/99	52.05	6.96	45.09	<50		< 0.5	< 0.5	< 0.5	<3	NA	5.2	NP
A-12	06/02/99	52.05	10.25	41.80	<50	0.0	<0.5	<0.5	< 0.5	7	NA	1.38	NP
A-12	08/26/99	52.05	9.91	42 14	Not Sample							0.51	
A-12	10/26/99	52.05	9.73	42.32	<50	***	<0.5	<0.5	<1	12	NA	1.09	NP
A-12	02/25/00	52.05	6.97	45.08	Not Sample	ed: Well S	ampled Se	miannuall	y				
A-13	03/26/96	55.11					Well	Inaccessib	le				
A-13	05/22/96	55.11											

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	TPH			Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene	benzene	Xylenes	8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
A-13	08/22/96	55.11					Well	Inaccessil	nle				
A-13	12/19/96	55.11											
A-13	04/01/97	55.11											
A-13	05/27/97	55.11											
A-13	08/12/97	55.11					Well	Inaccessil	ble				
A-13	11/14/97	55.11											
A-13	03/18/98	55.11					Well	Inaccessil	ble				
A-13	05/19/98	55.11											
A-13	07/29/98	55.11		*******			Well	Inaccessil	ble				
A-13	10/09/98	55.11					Well	Inaccessil	ble				
A-13	02/19/99	55.11					Well	Inaccessil	ble				
A-13	06/02/99	55.11		***********			Well	Inaccessil	ole				
A-13	08/26/99	55.11			************		Well	Inaccessil	ble				
A-13	10/26/99	55.11		********	**********		Well	Inaccessil	ble				
A-13	02/25/00	55.11					Well	Inaccessil	ole				
1													
AR-1	03/26/96	54.72	8.13	46.59	6,200	110	64	38	520	NA	NA	NM	
AR-1	05/22/96	54.72	8.57	46.15	NS	NS	NS	NS	NS	NS	NS	NM	
AR-1	08/22/96	54.72	10.97	43.75	5,600	100	28	29	310	960	NA	NM	
AR-I	12/19/96	54.72	8.93	45.79	Not Sample	d: Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	04/01/97	54.72	11.78	42.94	Not Sample	d Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	05/27/97	54.72	10.76	43.96	Not Sample	d: Well F	Removed f	rom Samp	ling Progr	am			
AR-1	08/12/97	54.72	11.40	43.32	Not Sample	d: Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	11/14/97	54.72	10.80	43.92	Not Sample	d: Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	03/18/98	54.72	NM	NM	Not Sample	d: Well F	Removed fi	rom Samp	ling Progr	am			
AR-I	05/19/98	54.72	NM	NM	Not Sample								
AR-1	07/29/98	54,72	10,17	44.55	Not Sample	d: Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	10/09/98	54.72	11.25	43.47	Not Sample	:d: Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	02/19/99	54.72	7.02	47.70	Not Sample	d Well F	Removed fi	rom Samp	ling Progr	am			
AR-1	06/02/99	54.72	11.00	43.72	Not Sample	d: Well F	temoved fi	rom Samp	ling Progr	am			
AR-1	08/26/99	54.72	10.96	43.76	Not Sample							0.39	
AR-I	10/26/99	54.72	10,68	44 04	Not Sample	d: Well F	lemoved fi	rom Samp	ling Progr	am		1.39	

Table 1
Groundwater Elevation and Analytical Data
Total Purgeable Petroleum Hydrocarbons
(TPPH as Gasoline, BTEX Compounds, and MTBE)

	Date	Well	Depth to	Groundwater	TPH			Ethyl-	Total	MTBE	MTBE	Dissolved	Purged/
Well	Gauged/	Elevation	Water	Elevation	Gasoline	Benzene	Toluene			8021B*	8260	Oxygen	Not Purged
Number	Sampled	(feet, MSL)	(feet, TOB)	(feet, MSL)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppm)	(P/NP)
AR-1	02/25/00	54.72										(# F 2)	(2.0.0)
AK-1	02/23/00	54.72	7.15	47.57	Not Sample	ea: Well K	emoved in	rom Samp	ling Progr	am			
AR-2	03/26/96	54.77	4.93	49.84	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	NM	
AR-2	05/22/96	54,77	5.65	49.12	NS	NS	NS	NS	NS	NS	NS	NM	
AR-2	08/22/96	54.77	7.27	47.50	<50	< 0.5	< 0.5	<0.5	< 0.5	200	NA	NM	
AR-2	12/19/96	54.77	7.78	46.99	Not Sample								
AR-2	04/01/97	54.77	6.80	47.97	Not Sample								
AR-2	05/27/97	54.77	6.32	48.45	Not Sample								
AR-2	08/12/97	54.77	7.43	47.34	Not Sample								
AR-2	11/14/97	54.77	8.95	45.82	Not Sample								
AR-2	03/18/98	54.77	NM	NM	Not Sample								
AR-2	05/19/98	54.77	NM	NM	Not Sample	ed: Well R	emoved fi	rom Samp	ling Progr	am			
AR-2	07/29/98	54.77	4.47	50.30	Not Sample								
AR-2	10/09/98	54.77	6.90	47.87	Not Sample								
AR-2	02/19/99	54.77	3.80	50.97	Not Sample	ed: Well R	emoved fi	rom Samp	ling Progr	am			
AR-2	06/02/99	54.77	4.61	50.16	Not Sample	ed: Well R	emoved fi	rom Samp	ling Progra	am			
AR-2	08/26/99	54.77	5.22	49.55	Not Sample							0.44	
AR-2	10/26/99	54.77	3.20	51.57	Not Sample	ed: Well R	lemoved fr	rom Samp	ling Progr	am		1.79	
AR-2	02/25/00	54.77	2.33	52.44	Not Sample	ed: Well R	emoved fi	rom Samp	ling Progr	am			
AR-3	03/26/96	54.19	7.95	46.24	<50	<0.5	<0.5	<0.5	<0.5	NA	NA	NM	
AR-3	05/22/96	54.19	8.30	45.89	NS	NS	NS	NS	NS	NS	NS	NM	
AR-3	08/22/96	54.19	10.84	43.35	Not Sample							1111	
AR-3	12/19/96	54.19	8.56	45.63	Not Sample								
AR-3	04/01/97	54.19	11.24	42.95	Not Sample	ed: Well R	emoved fr	om Samp	ling Progra	am			
AR-3	05/27/97	54.19	10.67	43.52	Not Sample								
AR-3	08/12/97	54.19	11.10	43.09	Not Sample								
AR-3	11/14/97	54.19	10.60	43.59	Not Sample								
AR-3	03/18/98	54.19	NM	NM	Not Sample								
AR-3	05/19/98	54.19	NM	NM	Not Sample								
AR-3	07/29/98	54.19	9.95	44.24	Not Sample								
AR-3	10/09/98	<u>5</u> 4.19	11.20	42.99	Not Sample								

# Table 1 Groundwater Elevation and Analytical Data Total Purgeable Petroleum Hydrocarbons (TPPH as Gasoline, BTEX Compounds, and MTBE)

### ARCO Service Station 4931 731 West MacArthur Boulevard, Oakland, California

Well Number	Date Gauged/ Sampled	Well Elevation (feet, MSL)	Depth to Water (feet, TOB)	Groundwater Elevation (feet, MSL)	TPH Gasoline (ppb)	Benzene (ppb)	Toluene (ppb)	Ethyl- benzene (ppb)	Total Xylenes (ppb)	MTBE 8021B* (ppb)	MTBE 8260 (ppb)	Dissolved Oxygen (ppm)	Purged/ Not Purged (P/NP)
AR-3 AR-3 AR-3 AR-3 AR-3	02/19/99 06/02/99 08/26/99 10/26/99 02/25/00	54.19 54.19 54.19 54.19		47.21 43.39 43.50 NM 46.98	Not Sampl Not Sampl Not Sampl Not Sampl Not Sampl	led: Well R led: Well R led: Well R	emoved fi emoved fi emoved fi	rom Samp rom Samp rom Samp	ling Progr ling Progr ling Progr	am am am		0.40	

TPH = Total petroleum hydrocarbons by modified EPA method 8015

BTEX = Benzene, toluene, ethylbenzene, total xylenes by EPA method 8021B. (EPA method 8020 prior to 10/26/99).

MTBE = Methyl tert-butyl ether

= EPA method 8020 prior to 10/26/99

MSL = Mean sea level TOB = Top of box ppb = Parts per billion

ppm = Parts per million < Less than laboratory detection limit stated to the right

NA = Not analyzed NM = Not measured NS = Not sampled

# Table 2 Groundwater Flow Direction and Gradient

Date	Average	Average
Measured	Flow Direction	Hydraulic Gradient
03/26/96	Southwest	0.03
05/22/96	Southwest	0.04
08/22/96	Southwest	0.02
12/19/96	Southwest	0.03
04/01/97	Southwest	0.03
05/27/97	Southwest	0.04
08/12/97	Southwest	0.02
11/14/97	Southwest	0.02
03/18/98	West	0.03
05/19/98	West-Southwest	0.02
07/29/98	West-Southwest	0.02
10/09/98	Southwest	0.007
02/19/99	Southwest	0.04
06/02/99	West	0.04
08/26/99	West-Southwest	0.02
10/26/99	West-Northwest	0.13
02/25/00	West-Southwest	0.05
	<u> </u>	

### **APPPENDIX C**

Certified Analytical Reports And Chain-of-Custody Documentation



8 April, 2002

Steven Meeks
Delta Environmental Consultants (Rancho Cordova)
3164 Gold Camp Drive Ste. 200
Rancho Cordova, CA 95670

RE: ARCO 4931, Oakland, CA Sequoia Report: S203429

Enclosed are the results of analyses for samples received by the laboratory on 03/26/02 09:40. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Ron Chew

Client Services Representative

Lito Diaz

**Laboratory Director** 

CA ELAP Certificate #1624



819 Striker Avenue, Suite 8 Sacramento, CA 95834 (916) 921-9600 FAX (916) 921-0100 www.sequoialabs.com

Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project ARCO 4931, Oakland, CA

Project Number. 4931, Oakland, CA Project Manager: Steven Meeks Reported: 04/08/02 15:09

#### ANALYTICAL REPORT FOR SAMPLES

Sample 1D	Laboratory ID	Matrix	Date Sampled	Date Received
A-2	\$203429-01	Water	03/21/02 13:20	03/26/02 09:40
A-4	\$203429-02	Water	03/21/02 13:25	03/26/02 09:40
A-6	\$203429-03	Water	03/21/02 12:15	03/26/02 09:40
A-8	\$203429-04	Water	03/21/02 12:45	03/26/02 09:40
A-9	\$203429-05	Water	03/21/02 12.52	03/26/02 09 40
тв	\$203429-06	Water	03/21/02 06:00	03/26/02 09:40

Sequoia Analytical - Sacramento

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: ARCO 4931, Oakland, CA

Project Number. 4931, Oakland, CA Project Manager Steven Meeks Reported: 04/08/02 15:09

### Total Purgeable Hydrocarbon, BTEX and MTBE by DHS LUFT

### Sequoia Analytical - Sacramento

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
A-2 (S203429-01) Water	Sampled: 03/21/02 13:20	Received: 03/2	6/02 09 <u>:</u>	40					
Purgeable Hydrocarbons	ND	50	ug/l	1	2040050	04/02/02	04/02/02	DHS LUFT	
Benzene	ND	0.50	н	n	n	II	11	Ħ	
Toluene	ND	0.50	n	n	IJ	n	15	Ħ	
Ethylbenzene	ND	0.50	D	U	u	n	В	**	
Xylenes (total)	ND	0.50	n	n	II	IF	n	n	
Methyl tert-butyl ether	ND	2.5		п	IJ	n .		Ħ	
Surrogate: a,a,a-Trifluorote	oluene	102 %	60-	-140	и	n	"	"	
A-4 (S203429-02) Water	Sampled: 03/21/02 13:25	Received: 03/2	6/02 09:4	40			· ·· ··		
Purgeable Hydrocarbons	ND	5000	ug/l	100	2040087	04/03/02	04/03/02	DHS LUFT	
Benzene	ND	50	17	II .	79	**	II .	D	
Toluene	ND	50	**	**	11	**	н	"	
Ethylbenzene	ND	50	19	79	n	n	11	u	
Xylenes (total)	ND	50	n	и	n	n	ri .	u	
Methyl tert-butyl ether	1400	250	1)	11	11		*1	n .	
Surrogate: a.a.a-Trifluorote	oluene	110 %	60-	-140	u	н	"	ıt	
A-6 (S203429-03) Water	Sampled: 03/21/02 12:15	Received: 03/2	6/02 <u>09:</u> 4	40	.,				
Purgeable Hydrocarbons	ND	50	ug/l	1	2040050	04/02/02	04/02/02	DHS LUFT	
Benzene	ND	0.50	"	n	n	n	<b>»</b>	н	
Toluene	ND	0.50	n	U	Ħ	п	D	p	
Ethylbenzene	ND	0.50	II .	II .	0	II .	n	н	
Xylenes (total)	ND	0.50	II	u	n	Ħ	ρ	"	
Methyl tert-butyl ether	ND	2.5	u		11	n .	11		
Surrogate: a,a,a-Trifluorote	oluene	108 %	60-	-140	n.	"	"	"	



3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: ARCO 4931, Oakland, CA

Project Number: 4931, Oakland, CA Project Manager: Steven Meeks Reported: 04/08/02 15:09

# Total Purgeable Hydrocarbon, BTEX and MTBE by DHS LUFT Sequoia Analytical - Sacramento

Reporting Method Result Limit Units Dilution Batch Prepared Analyzed Notes Analyte A-8 (S203429-04) Water Sampled: 03/21/02 12:45 Received: 03/26/02 09:40 04/02/02 **DHS LUFT** HC-12 04/02/02 Purgeable Hydrocarbons 6600 5000 ug/l 100 2040050 1400 50 Benzene ND 50 Toluenc Ethylbenzene 130 50 ND 50 Xylenes (total) 2700 Methyl tert-butyl ether 250 Surrogate: a.a.a-Trifluorotoluene 99.1 % 60-140 A-9 (S203429-05) Water Sampled: 03/21/02 12:52 Received: 03/26/02 09:40 **DHS LUFT** Purgeable Hydrocarbons ND 50 ug/l 1 2040050 04/02/02 04/02/02 ND 0.50 Benzene ND 0.50 Toluene Ethylbenzene ND 0.50 Xylenes (total) ND 0.50 ND 2.5 Methyl tert-butyl ether Surrogate: a,a,a-Trifluorotoluene 100 % 60-140 TB (\$203429-06) Water Sampled: 03/21/02 06:00 Received: 03/26/02 09:40 Purgeable Hydrocarbons ND 50 1 2040050 04/02/02 04/02/02 DHS LUFT ug/l ND Benzene 0.50 ND 0.50 Toluene Ethylbenzene ND 0.50 ND 0.50 Xylenes (total) ND 2.5 Methyl tert-butyl ether

60-140

98.4 %

Surrogate: a,a,a-Trifluorotoluene



3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project. ARCO 4931, Oakland, CA

Project Number: 4931, Oakland, CA Project Manager: Steven Meeks Reported: 04/08/02 15:09

# Total Purgeable Hydrocarbon, BTEX and MTBE by DHS LUFT - Quality Control Sequoia Analytical - Sacramento

l		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 2040050 - EPA 5030B (P/T)										
Blank (2040050-BLK1)				Prepared	& Analyz	ed: 04/02/	02			
Purgeable Hydrocarbons	ND	50	ug/l	·						
Benzene	ND	0.50	II .							
Toluene	ND	0.50	п							
Ethylbenzene	ND	0.50	"							
Xylenes (total)	ND	0.50	**							
Methyl tert-butyl ether	ND	2.5	u							
Surrogate: a,a,a-Trifluorotoluene	10.0		"	10.0		100	60-140			
LCS (2040050-BS1)				Prepared	& Analyze	ed: 04/02/	02			
Benzene	7.77	0.50	ug/l	10.0		77.7	70-130			
Toluene .	9.36	0.50	u	10 0		93.6	70-130			
Ethylbenzene	102	0.50	U	10.0		102	70-130			
Kylenes (total)	32.0	0.50	17	30.0		107	70-130			
Methyl tert-butyl ether	8.26	2.5	+1	10.0		82.6	70-130			
Surrogate: a,a,a-Trifluorotoluene	10.7		ıı	10.0		107	60-140			
Matrix Spike (2040050-MS1)	Sou	rce: S20343	4-08	Prepared a	& Analyze	ed: 04/02/	02			
Benzene	7 65	0 50	ug/l	10.0	ND	76 5	60-140		,	
<b>Coluene</b>	9.37	0.50	tı	10.0	ND	93.7	60-140			
Ethylbenzene	10.3	0 50		10.0	ND	103	60-140			
Kylenes (total)	31.9	0 50	19	30.0	ND	106	60-140			
Methyl tert-butyl ether	14.4	2.5	п	10.0	5.4	90.0	60-140			
Surrogate: a,a,a-Trifluorotoluene	9.94		"	10 0		99.4	60-140			
Matrix Spike Dup (2040050-MSD1)	Sou	rce: S20343	4-08	Prepared &	& Analyze	d: 04/02/	02			
Benzene	8.20	0.50	ug/l	10.0	ND	82.0	60-140	6.94	25	
oluene	10.0	0.50	n	10.0	ND	100	60-140	6.50	25	
ithylbenzene	11.1	0.50	п	10.0	ND	111	60-140	7.48	25	
(ylenes (total)	34.2	0.50	n	30.0	ND	114	60-140	6.96	25	
dethyl tert-butyl ether	15.4	2.5	ч	10.0	5.4	100	60-140	6.71	25	
Surrogate: a,a,a-Trifluorotoluene	10.7		"	10.0		107	60-140			



3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project ARCO 4931, Oakland, CA

Project Number: 4931, Oakland, CA Project Manager: Steven Meeks Reported: 04/08/02 15:09

# Total Purgeable Hydrocarbon, BTEX and MTBE by DHS LUFT - Quality Control Sequoia Analytical - Sacramento

}		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 2040087 - EPA 5030B (P/T)				<del> </del>						
Blank (2040087-BLK1)	. <u> </u>			Prepared	& Analyze	d: 04/03/	02			
Purgeable Hydrocarbons	ND	50	ug/l							
Benzene	ND	0 50	Ħ							
Toluene	ND	0.50	,,							
Ethylbenzene	ND	0.50	n							
Xylenes (total)	ND	0.50	tt							
Methyl tert-butyl ether	ND	2.5	11							
lurrogate: a,a,a-Trifluorotoluene	11.4		Ħ	10.0		114	60-140			
.CS (2040087-BS1)				Prepared	& Analyze	d: 04/03/	02			
Benzene	8.68	0.50	ug/l	10.0		86.8	70-130			
Foluene	9.05	0.50		10.0		90 5	70-130			
Ethylbenzene	10.3	0.50	Ħ	0.01		103	70-130			
Xylenes (total)	30.5	0.50	n	30.0		102	70-130			
Methyl tert-butyl ether	10.3	2.5	"	10.0		103	70-130			
Surrogate: a,a,a-Trifluorotoluene	11.0		"	10 0		110	60-140			
Matrix Spike (2040087-MS1)	Sour	rce: S20345	6-01	Prepared	& Analyze	d: 04/03/	02			
Benzene	9.42	0.50	ug/l	10 0	0.70	87 2	60-140			
Toluene	10.5	0.50	19	10 0	1.5	90 0	60-140			
Ethylbenzene	10.7	0.50	II .	10.0	ND	104	60-140			
(ylenes (total)	35.4	0.50	**	30.0	4.8	102	60-140			
Methyl tert-butyl ether	11.8	2.5	11	10.0	ND	96.0	60-140			
Survogate. a,a,a-Trifluorotoluene	11.4		"	10.0		114	60-140			
Matrix Spike Dup (2040087-MSD1)	Sour	rce: S20345	6-01	Prepared	& Analyze	d: 04/03/	02		<u>, ,</u>	
Benzene	9.57	0.50	ug/l	10.0	0.70	88.7	60-140	1.58	25	
Toluene	10.6	0.50	н	10.0	1.5	910	60-140	0.948	25	
Ethylbenzene	10.9	0.50	**	10.0	ND	106	60-140	1.85	25	
(ylenes (total)	35.8	0 50	n	30.0	4.8	103	60-140	1.12	25	
Methyl tert-butyl ether	11.6	2 5	u	10.0	ND	94.0	60-140	1.71	25	
Surrogate: a,a,a-Trifluorotoluene	10.7		"	10 0		107	60-140			



819 Striker Avenue, Suite 8 Sacramento, CA 95834 (916) 921-9600 FAX (916) 921-0100 www.sequoialabs.com

Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project ARCO 4931, Oakland, CA

Project Number 4931, Oakland, CA

Project Manager. Steven Meeks

Reported: 04/08/02 15:09

#### Notes and Definitions

HC-12 Hydrocarbon pattern is present in the requested fuel quantitation range but does not resemble the pattern of the requested fuel.

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

ARCO								Work A	uthoriza	lon !	Vo.										_	C	hain of Custody
ARCO Fecting No. 4931 City Oak Land ARCO engineer Paul Supple Telephone no. (ARCO)										Project Manager STONEN AMERKS											Laboratory name		
ARCO Facility No. 4931 City (Facility) Oak Law ARCO engineer Paul Supple Tele (ARCO COMPANY DETRE						Telepho	Telephone no.				Project Manager STEVEN IMERKS  [Consultant) STEVEN IMERKS  Telephono no. (Consultant) 638-8385									5	Sequola Contract number		
Company name (Consultant) D-17a							Address (Consul	tani) Ra	With Cordova												Colgradi Mulhes		
	-			Matrix		Prései	walion	noûe			23 CS /	5.0	tı	36		SZIE	Semi VGAC	710 <b>/7</b> .200					Method of shipment
Sample I.D.	Lats no.	Container no.	Ioa	Water	Other	lca	Acid	Sampling data	Sompling time	STEX SOC/EPA 8021	STEVTPH AT	PH Modified 80	11 and Grease 119.1 □ <13.2	TPH EPA 478.11SN/S03E	ITEX + 14TBE PA 8260	17EX + Landerd Chygos PA 8250	CLP Astals YOAC	WANGER BARB	Lead Dia/OHS CJ Send EPA 7/20/7/21 CJ				Special detection
				X		X	X		13;20		X		0 4	- 2		Œ.					<u></u>		
A-7 4-4						Ì			13:25	<del>                                     </del>	<u> </u>					- J.W.	<u></u>	.Δ.ι -	Ş	}			
A-6 A-8 A-9 IB	<del>-</del>	j j							12:15										03				Special QA/QC
A-8									12:45										O				
1-9									12:52										05				]
IB_				<u> </u>		<u> </u>	<u> </u>	<u> </u>	600		7								0/2	2			Remerks
																					<b>-</b> _		<u> </u> 
			i 			<u> </u>	<u> </u>					-											
							<u> </u>			-													Type or Work  Dispenser Work
		<u> </u>			<del>                                     </del>	<u> </u>							<u> </u>									_	Une Job     Routine Sampling     Site Acquisitions
										<del>-</del>		<del> </del>						i					CI She Assessment CI UST Removal
																						<del>                                     </del>	☐ USTReplacement ☐ Other
	ļ					<b> </b>		<del></del>															Lab number
																							Tunaround lime
																							Priority Rush 1 808 iness Day
Condition of sample:							Temperature received:										Rush						
Relinquishe	nsa yoʻb	The state of the s	19xx	2	-	1	Date 2-7/4	/\	990	Peger	VEO BY	O LC	a	Cont	eOS	٨٨٨		ड्य	Vals	רית	<u>راً،</u>	D_	2 Business Days 🔲
Relinquished by earnple  Relinquished by  Relinquished by  Oatc							Timo								., 1		Expedited 5 Business Days []						
Relinquished by				Data Time				Received by laboratory Date Time											Standard 10 Business Days · 🎉				

### APPENDIX D

Remedial System Performance Summary

#### **ARCO STATION NO. 4931**

731 West MacArthur Boulevard Oakland, California

#### REMEDIAL SYSTEM PERFORMANCE SUMMARY

#### **GWE System**

Groundwater extraction (GWE) was conducted intermittently between November 10, 1992 and July 5, 1995. The TWE system was comprised of electric GWE pumps in monitoring wells A-9, AR-1, AR-2, AR-3 and in three 1,500-pound granular activated carbon vessels arranged in series. The GWE system was permitted by East Bay Municipal Utility District Permit Account Number 502-62131. Based on Alameda County Health Care Services Agency authorization that GWE at the site was no longer required, the permit was relinquished during the second quarter 1996. Overall, 4.6 million gallons of groundwater were extracted and less than 0.06 gallon of benzene removed. Refer to the IT Corporation Second Quarter 1997 Groundwater Monitoring Report for historical GWE system performance and analytical data.

#### Intrinsic Bioremediation Evaluation

At the request of ARCO, intrinsic bioremediation indicator parameters (bioparameters) were monitored during the first quarter 1996 groundwater monitoring event. Groundwater samples from monitoring wells A-4, A-8 and A-12 were analyzed for biological oxygen demand (BOD), carbon dioxide (CO<sub>2</sub>), chemical oxygen demand (DOD), methane, nitrate, sulfate, dissolved oxygen (DO) and ferrous iron. Monitoring wells A-4 and A-8 are located within the plume. Monitoring well A-12 is located outside the plume. Based on analysis of the collected data, intrinsic bioremediation was occurring at the site. Refer to the IT Corporation First Quarter 1997 Groundwater Monitoring Report for details.

Oxygen release compound (ORC) is currently being used in monitoring wells A-4, A-9 and AR-1 to enhance biodegradation of dissolved oxygen. ORC was scheduled for replacement during the second quarter 2002.

### **APPENDIX E**

Field Sample Data



3164 Gold Rancho Co Direct: (916) Fax: (916) 638-8385

Camp Drive, Suite 200	Arco Site Address: 731 Wes
rdova, California 95670	Oaki
) 638-2085	<u></u>

Arco 4931 st MacArthur Blvd Arco Site Number. and, California Delta Project No.: D000-313 Arco Project Manager: Paul Supple Delta Project PM: Steve Meeks Site Sampled By: Doulos 03/21/02 Date Sampled:

Site Contact & Phone Number.

		Water Le	evel Data	1		Purge Volume Calculations						Sam	pling Ar	Sample Record				
Well ID	Time	Depth to Water (feet)	Top of Screen Interval (feet)	Total Depth of Well (feet)	Check if Purge Not Required	Casing Water Column (A)	Well Diameter (inches)	Multiplier Value (B)	Three Casing Volumes (gallons)	Actual Water Purged (gallons)	BTEX (8020) VOA	TPH-g (8015M) VOA	MTBE (8020) VOA	Other	Dissolved Oxygen (mg/L)	Sample Freqency (A, S, Q)	Sample	Sample Time
A-2	11:20	3.26	5.0	19.0		15.74	4 inch	2.0	31.5	31.4	[7]	V	v		0.89	Q/2,5,8,11	A-2	13:20
A-3	11:43	5.75	5.0	19.3		13.55	4 inch	2.0	27.1	N/A					NM	S/5,11		
A-4	11:29	6.18	5.0	19.6	Ø	13.42	4 inch	2.0	26.8	NP	[5]	V	[7]		0.95	Q/2,5,8,11	A-4	13:25
A-5	11:37	6.71	3.0	24.0		17.29	3 inch	1.1	19.0	N/A					NM	S/5,11		
A-6	11:23	5.44	2.0	25.0	Ø	19.56	3 inch	1.1	21.5	ΝP	5	[2]	7		1.10	Q/2,5,8,11	A-6	12:15
A-7	11:26	5.35	3.0	22.6		17.25	3 inch	1.1	19.0	N/A					NM	A/5		
A-8	11:58	6.67	2.0	20.0		13.33	3 inch	1.1	14.7	14.6	7	Image: section of the	[7]		1.02	Q/2,5,8,11	A-8	12:45
A-9	12:05	5.60	5.0	38.0	V	32.40	6 inch	4.4	142.6	NP	V	V	V		1.05	Q/2,5,8,11	A-9	12:52
A-11	11:54	7.14	5.0	28.0		20.86	3 inch	1.1	22.9	N/A					NM	S/5,11		
A-12	11:48	6.64	5.0	30.0		23.36	3 inch	1.1	25.7	N/A					NM	S/5,11		
A-13	11:50	6.70	10.0	29.5		N/A	3 inch	1.1	N/A	N/A					NM	A/5		
AR-1	11:33	7.00	10.0	31.5		24.50	6 inch	4.4	107.8	N/A					NM	NS		
AR-2	11:40	7.75	10.0	27.5		19.75	6 inch	4.4	86.9	N/A					NM	NS		
AR-3	11:44	6.78	10.0	27.0		N/A	6 inch	4.4	N/A	N/A					NM	NS		
						·				_								Ĺ
															Ĺ			
	····																	
									<u>-</u>									
							<u></u>								Semi-Annual			<u> </u>

(A)-Casing Water Column: Depth to Bottom - Depth to Water (B)-Multiplier Values: (2" Well: 0.5) (4" Well: 2.0) (6" Well: 4.4)

Sampling Sequence:

Annual: A-7, A-13; Semi-Annual: A-3, A-5, A-11, A-12;

Quarterly: A-6, A-8, A-9, A-2, A-4,

List depth of Sample on C O.C. [I.e. MW-1(30)] Make Sure to Note on C O C. "Provide Lowest Reporting Limit Available." Sampling Notes:

Original Copies of Field Sampling Sheets are Located in Project File

If the water level is below the top of the screen, take a grab sample and check box for NO PURGE (NP). If the water level is above the screen, purge as normal



Site Contact & Phone Number:

3164 Gold Camp Drive, Suite 200 Rancho Cordova, California 95670 Direct: (916) 638-2085 Fax: (916) 638-8385

Arco Site Address:	731	West MacArthur I	3Ivd

Arco Site Number: Arco 4931

Paul Supple Arco Project Manager:

Oakland, California

Delta Project No.: Delta Project PM: Steve Meeks

D000-313

Site Sampled By: **Doulos** 

3/21/02 Date Sampled:

Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons
A-2	13:00	19.2	7.90	591	10	A-9	No P	urge Req	uired					i i			
	13:03	21.5	7.13	291	20												
	13:05	23.7	6.91	504	32												
<u> </u>													170				
Well ID	Time		pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F		Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons
A-3	Not San	pled				A-11		NOT SAI	MPLED			,					
Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp Cond.	Gallons
A-4			ge Requir			A-12	<u> </u>		MPLED								
<u></u>						<u></u>											
Well ID	Time		pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp Cond.	Gallons
A-5	Not Sampled					A-13	Not Sam	pled									
								ļ						ļ			
	ļ		<del> </del>				ļ	<u> </u>						<del> </del>			
Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp Cond	Gallons
A-6	<u> </u>		ge Requir			AR-1	Not Sam	1		<u></u>				<u> </u>			
	1 1					, , ,		1					<del></del>				
		0=															
Well ID	Time		pH Units	Sp Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond	Gallons
A-7	Not Sam	pled				AR-2	Not Sam	pled									
									<del></del>					<b> </b>			
	<del> </del>			-			ļ							<del>                                     </del>			
Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp °F	pH Units	Sp. Cond.	Gallons	Well ID	Time	Temp ⁰F	pH Units	Sp. Cond.	Gallons
A-8	12:15	20.5	7.4	1,373		AR-3	Not Sam	pled									
	12:14	23.0	7.09	722													
	12:20	24.3	7.20	662			<u> </u>										
L	i		ļ <u>.</u>			l	l	L		l[		l (		<u> </u>	l	l (	ſ

Notes: NP = NO PURGE

Original Copies of Field Sampling Sheets are Located in Project File