

Heilshorn Environmental Engineering

June 25, 1999

Ms. Medula Logan, Risk Assessor Alameda County Environmental Health Services Environmental Protection 1131 Harbor Way parkway, Suite 250 Alameda CA 94502-677 5x10 3030

ag NW 28 PH 3: 37

SUBJECT:

Addendum To Risk Based Corrective Action Assessment For Soil

REGARDING:

Beck Roofing Company, 21123 Meekland Avenue, Hayward, CA

Dear Ms. Logan:

This addendum was developed per your verbal request. You requested additional analyses and data to complete your review of potential health risks presented by residual benzene and MTBE contamination at the Beck Roofing site. The request included:

- Compare the arithmetic average soil and groundwater data values for MTBE and benzene to the Tier 1 RBSL.
- Evaluate the data at the 1 x 10-5 excess risk level rather than 10-4 or 10-6
- Provide data for boring SB20, the boring closest to the buildings

Addendum tables 1-3 provide the average values and comparisons. MTBE data were not developed for the soil samples since samples were collected before MTBE was a constituent of regulatory concern.

The groundwater data meet the Tier 1 risk based screening levels (RBSL). The soil data do not meet the RBSL for the 25 and 30-foot deep samples The average values meet the Tier I RBSLs if they are recalculated eliminating one data location, Boring SB21. (See Table 3). The extent of contamination was estimated using SB21 for the source data since this point appears to cause the average data values to exceed the RBSL.

Ms. Logan stated that Alameda County does not permit inclusion of biodegradation factors in degradation calculations. The calculations were redone using field data for points adjacent to SB21, the contamination source location, in the down and cross gradient directions. Soil data for SB21 and MW3 were used to determine the down gradient extent of contamination. Soil data for

SB21 and MW 1 were used to calculate the cross gradient extent of contamination. A simple linear graphical solution was used to determine the distance from the source of contamination, SB21, to a zero concentration level. The resulting graphs show the down gradient extent of contamination at 51.5 feet from SB 21, and a lateral extent of contamination at 49 feet from SB21. The office building is 60 feet away from SB21 in the cross gradient direction and about 50 feet in a direction diagonally between down and cross gradient.

The plume of benzene does not reach or extend under the office or warehouse building, based on the graphical solutions using 1991 and 1994 soil data for 25 and 30 feet bgs. Therefore, the soil to indoor air pathway is expected to be incomplete and not present a significant health risk at Beck Roofing.

Ms. Logan requested SB20 data, since this boring is closest to the buildings. The available data, 25 to 35 feet bgs, show nondetectable levels of benzene.

During subsequent telephone conversations Ms. Logan suggested that the wells which have shown nondetectable levels of benzene and MTBE (MW-1, -2 and -4) could be closed. She stated that MW3 should be monitored for two additional quarters then could be closed if the data meet Tier 1 RBSL values.

HE2 will monitor and sample MW3 during July, with permission of Beck Roofing. Alameda County, the Regional Water Quality Control Board (RWQCB) and the Department of Water Resources will be notified or provided with the required forms and reports for the well closures. The wells will not be closed until Beck Roofing receives written approval to proceed from Alameda County and/or the RQWCB.

Please contact me if you have any additional questions or concerns regarding this site. We look forward to your letter.

Sincerely,

Heilshorn Environmental Engineering

Elyse D. Heilshorn, P.E.

Ed Heilshim

Consulting Engineer

cc: Mr. Amir Gholami, Alameda County



ADDENDUM TABLES COMPARISON OF AVERAGED DATA VALUES TO RBSL

Table 1 GROUNDWATER DATA 11/96-1/99

Well	Well Avg MTBE μg/L		Average Benzene, µg/L	Avg Benzene Conc. meets Tier 1 RBSL?	
Tier i MTBE RBSL 10-5, µg/L		27,000			
Tier Benzehe RBSL-10-5; µg/L				739	
MW-1	ND	Yes	1.05	Yes	
MW-2	ND	Yes	3.025	Yes	
MW-3	ND	Yes	111.125	Yes	
MW-4	ND	Yes	0.65	Yes	

Notes:

MTBE RBSL provided by Medula Logan. Value calculated for another Alameda County site. Benzene RBSL value for commercial setting, groundwater to indoor air pathway.


Table 2 SOIL DATA INCLUDING SB-21 (TANK PIT) DATA

Sample Depth Ft,bgs	Average Benzene	Soil to Outdoor Air	Avg Conc. meets Outdoor Air	Soil to Indoor Air Pathway	Avg Conc. meets Indoor	
	Conc. mg/kg	Pathway	RBSL?		Air RBSL?	
Tier 1 RBSL 10-5 Commercial Benzene, mg/kg	1 kg	4.57		0.169		
20	0.063		Yes		Yes	
25	0.33		Yes		No	
30	1.51		Yes		No Sing	


Table 3 SOIL DATA EXCLUDING SB-21 (TANK PIT) DATA

Sample Depth Ft,bgs	Average Benzene Conc. mg/kg	Soil to Outdoor Air Pathway	Avg Conc. meets Outdoor Air RBSL?	Soil to Indoor Air Pathway	Avg Conc. meets Indoor Air RBSL?
Tier 1 RBSL 10-5 Commercial Benzene, mg/kg		4.57		0.169	
20	0.063		Yes		Yes
25	0.090		Yes	, , , , , , , , , , , , , , , , , , , ,	Yes
30	0.081		Yes		Yes

Benzene Downgradient Extent in Soil



Benzene Cross Gradient Extent in Soil



Heilshorn Environmental Engineering



June 25, 1999

Ms. Medula Logan, Risk Assessor Alameda County Environmental Health Services Environmental Protection 1131 Harbor Way parkway, Suite 250 Alameda CA 94502-677



SUBJECT:

Addendum To Risk Based Corrective Action Assessment For Soil

REGARDING:

Beck Roofing Company, 21123 Meekland Avenue, Hayward, CA

Dear Ms. Logan:

This addendum was developed per your verbal request. You requested additional analyses and data to complete your review of potential health risks presented by residual benzene and MTBE contamination at the Beck Roofing site. The request included:

- Compare the arithmetic average soil and groundwater data values for MTBE and benzene to the Tier 1 RBSL.
- Evaluate the data at the 1 x 10-5 excess risk level rather than 10-4 or 10-6
- Provide data for boring SB20, the boring closest to the buildings

Addendum tables 1-3 provide the average values and comparisons. MTBE data were not developed for the soil samples since samples were collected before MTBE was a constituent of regulatory concern.

The groundwater data meet the Tier 1 risk based screening levels (RBSL). The soil data do not meet the RBSL for the 25 and 30-foot deep samples The average values meet the Tier I RBSLs if they are recalculated eliminating one data location, Boring SB21. (See Table 3). The extent of contamination was estimated using SB21 for the source data since this point appears to cause the average data values to exceed the RBSL.

Ms. Logan stated that Alameda County does not permit inclusion of biodegradation factors in degradation calculations. The calculations were redone using field data for points adjacent to SB21, the contamination source location, in the down and cross gradient directions. Soil data for SB21 and MW3 were used to determine the down gradient extent of contamination. Soil data for

SB21 and MW 1 were used to calculate the cross gradient extent of contamination. A simple linear graphical solution was used to determine the distance from the source of contamination, SB21, to a zero concentration level. The resulting graphs show the down gradient extent of contamination at 51.5 feet from SB 21, and a lateral extent of contamination at 49 feet from SB21. The office building is 60 feet away from SB21 in the cross gradient direction and about 50 feet in a direction diagonally between down and cross gradient.

The plume of benzene does not reach or extend under the office or warehouse building, based on the graphical solutions using 1991 and 1994 soil data for 25 and 30 feet bgs. Therefore, the soil to indoor air pathway is expected to be incomplete and not present a significant health risk at Beck Roofing.

Ms. Logan requested SB20 data, since this boring is closest to the buildings. The available data, 25 to 35 feet bgs, show nondetectable levels of benzene.

During subsequent telephone conversations Ms. Logan suggested that the wells which have shown nondetectable levels of benzene and MTBE (MW-1, -2 and -4) could be closed. She stated that MW3 should be monitored for two additional quarters then could be closed if the data meet Tier 1 RBSL values.

HE2 will monitor and sample MW3 during July, with permission of Beck Roofing. Alameda County, the Regional Water Quality Control Board (RWQCB) and the Department of Water Resources will be notified or provided with the required forms and reports for the well closures. The wells will not be closed until Beck Roofing receives written approval to proceed from Alameda County and/or the RQWCB.

Please contact me if you have any additional questions or concerns regarding this site. We look forward to your letter.

Sincerely,

Heilshorn Environmental Engineering

Elyse D. Heilshorn, P.E.

Consulting Engineer

cc: Mr. Amir Gholami, Alameda County



ADDENDUM TABLES COMPARISON OF AVERAGED DATA VALUES TO RBSL

Table 1 GROUNDWATER DATA 11/96-1/99

Well	Avg MTBE μg/L	Avg MTBE Conc. meets Tier 1 RBSL?	Average Benzene, µg/L	Avg Benzene Conc. meets Tier 1 RBSL?	
Tier 1 MTBE RBSL 10-5, μg/L		27,000			
Tier 1 Benzene RBSL 10-5, µg/L				739	
MW-1	ND	Yes	1.05	Yes	
MW-2	ND	Yes	3.025	Yes	
MW-3	ND	Yes	111.125	Yes	
MW-4	ND	Yes	0.65	Yes	

Notes:

MTBE RBSL provided by Medula Logan. Value calculated for another Alameda County site. Benzene RBSL value for commercial setting, groundwater to indoor air pathway.


Table 2 SOIL DATA INCLUDING SB-21 (TANK PIT) DATA

Sample Depth Ft,bgs	Average Benzene Conc. mg/kg	Soil to Outdoor Air Pathway	Avg Conc. meets Outdoor Air RBSL?	Soil to Indoor Air Pathway	Avg Conc. meets Indoor Air RBSL?
Tier I RBSL 10-5 Commercial Benzene, mg/kg		4.57		0.169	
20	0.063		Yes		Yes
25	0.33		Yes		No
30	1.51		Yes		No

Table 3 SOIL DATA EXCLUDING SB-21 (TANK PIT) DATA

Sample Depth Ft,bgs	Average Benzene Conc. mg/kg	Soil to Outdoor Air Pathway	Avg Conc. meets Outdoor Air RBSL?	Soil to Indoor Air Pathway	Avg Conc. meets Indoor Air RBSL?
Tier I RBSL 10-5 Commercial Benzene, mg/kg		4.57		0.169	
20	0.063		Yes		Yes
25	0.090		Yes		Yes
30	0.081		Yes		Yes

Benzene Downgradient Extent in Soil



Benzene Cross Gradient Extent in Soil

