A Report Prepared For:

Pacific Electric Motor Company 1009 66th Avenue Oakland, California 94601

Attention: Mr. Rand Perry

Alameda County

Environmental Health

SECOND QUARTER 2003
GROUNDWATER MONITORING REPORT
PACIFIC ELECTRIC MOTOR COMPANY
1009 66TH AVENUE
OAKLAND, CALIFORNIA

JULY 31, 2003

By:

Keary Knickerbocker

Project Environmental Scientist

William W. Mast, R.G.

Associate Engineer

No. 5647

618.001.02.005

TABLE OF CONTENTS

LIST OF TABLE	ES	iii
LIST OF ILLUS	TRATIONS	iii
1.0 INTRODUC	CTION	1
2.0 BACKGRO	UND INFORMATION	1
3.0 WATER-LE	EVEL AND DISSOLVED OXYGEN MEASUREMENTS	3
4.0 GROUNDW	VATER SAMPLING	3
5.1 Water-Le	ON OF MONITORING RESULTSvel and Dissolved Oxygen Measurements	4
6.0 REFERENC	CES	5
TABLES		
ILLUSTRATION	NS 2V	
APPENDICES	A – GROUNDWATER SAMPLING REPORT	
	B - LABORATORY REPORT AND CHAIN-OF-CUSTODY RECORDS	3
DISTRIBUTION		

LIST OF TABLES

Table 1	Monitoring Well Completion Details
Table 2	Water-Level Elevation Data
Table 3	Summary of Analytical Results for Groundwater Samples

LIST OF ILLUSTRATIONS

Plate 1	Site Location	Man
---------	---------------	-----

Plate 2 Site Plan and Monitoring Well Location and Water-Level Elevation Map

1.0 INTRODUCTION

This report presents the results of quarterly groundwater monitoring performed by PES Environmental, Inc. (PES) during the second quarter of 2003 at Pacific Electric Motor Company (PEM) in Oakland, California (Plate 1). The monitoring is being performed to fulfill post-remediation groundwater monitoring requirements of the Alameda County Health Care Services, Environmental Health Services (ACEHS), as described in a letter dated August 9, 2002.

The purpose of groundwater monitoring is to assess the presence and trend of petroleum hydrocarbons previously observed in onsite groundwater monitoring wells, and evaluate the success of recent remedial action conducted at the site.

Per the ACEHS' letter, the groundwater monitoring program consists of measuring the depth to groundwater in four monitoring wells (wells MW-1, MW-2, MW-3, MW-4), and one unused extraction well (EW-1), and purging and sampling the monitoring wells on a quarterly basis for four consecutive quarters, at which time the monitoring program will be reevaluated. The second quarter 2003 monitoring event marks the third of the four consecutive monitoring events to be performed at the site.

2.0 BACKGROUND INFORMATION

The site is located in a residential and light industrial area in Oakland, California and is not currently occupied. Most recently the site housed repair operations for large electric motors. PEM formerly operated a 2,000-gallon steel gasoline underground storage tank (UST) on the east side of the warehouse building (Plate 2). The tank was reportedly installed in approximately 1975 (ENVIRON, 1997). In February 1995, the UST was removed by W.A. Craig, Inc. (WAC). Observations at the time of removal indicated that the tank was in good condition and no holes were evident. However, free-phase gasoline product was observed on the water surface in the tank excavation. Soil samples collected from the UST excavation and associated piping trenches detected total petroleum hydrocarbons as gasoline (TPHg) at concentrations up to 10,000 milligrams per kilogram.

In April 1995, WAC performed a soil investigation consisting of the drilling and sampling of nine soil borings to delineate the lateral and vertical extent of the petroleum hydrocarbons in soil. On the basis of the results of the soil investigation, WAC prepared and implemented a remediation program to remove soil affected by petroleum hydrocarbons. Approximately 1,500 cubic yards of soil were excavated and stockpiled onsite, and 116,000 gallons of petroleum hydrocarbon-affected water were pumped from the excavation and disposed. A dewatering sump installed by WAC during soil excavation was later converted to groundwater monitoring well WAC-1 (Plate 2). Because of its uncertain construction, ACEHS stated that no monitoring of Well WAC-1 is required (ACEHS, 1997). WAC summarized the results of their remediation program in a report entitled Excavation and Sampling Report, Pacific

1

Electric Motor Co., 1009 66th Avenue, Oakland, California, dated May 12, 1997 (WAC, 1997).

ENVIRON, Inc. (ENVIRON) installed and sampled three shallow monitoring wells (MW-1, MW-2, MW-3) in June 1997 to evaluate groundwater conditions in the vicinity of the former UST. Well completion details are summarized in Table 1. The well installation program and associated soil and groundwater sampling program was summarized in the ENVIRON report Soil and Ground Water Investigation, Summary Report, Pacific Electric Motor Co., 1009-66th Avenue, Oakland, California, dated July 17, 1997 (ENVIRON, 1997). ENVIRON concluded that the remediation performed had successfully removed the source of the petroleum hydrocarbons (i.e., the former UST), and that residual concentrations of petroleum hydrocarbons in soil and groundwater were present only in the immediate vicinity of the former UST.

In September 1998 PES conducted additional soil and groundwater sampling in the vicinity of the former UST, as requested by the ACEHS in a May 13, 1998 letter to PEM (ACEHS, 1998a). Two soil borings were drilled within the backfill of the former UST excavation, and one monitoring well was installed downgradient of the former UST. Petroleum hydrocarbons were generally not detected in the excavation backfill, although groundwater samples collected from both soil borings indicated the presence of methyl tert-butyl ether (MTBE), a gasoline additive. Elevated petroleum hydrocarbons were found in soil and groundwater downgradient of the UST excavation during installation and groundwater sampling of monitoring well MW-4. On the basis of the elevated concentrations of petroleum hydrocarbons, PES recommended performing periodic groundwater monitoring. The additional investigation was summarized in the PES report Results of Additional Soil and Groundwater Investigation, 1009 66th Avenue, Oakland, California, dated November 11, 1998 (PES, 1998a).

Groundwater monitoring has been conducted at the site since the installation of monitoring wells MW-1, MW-2, and MW-3 in June 1997. Monitoring well MW-4 was incorporated into the monitoring program upon installation in September 1998. Historical and current water-level elevation data is presented in Table 2. Historical and current analytical results of groundwater monitoring events are presented in Table 3.

Additional site remediation activities were conducted by Decon Environmental Services (Decon) in 2002. The remediation activities included soil excavation from an area located to the south/southwest of the original excavation discussed above and the injection of Oxygen Release Compound (ORC) at 25 locations in the vicinity of monitoring well MW-4 and around the northern portion of the additional excavation area. The areas of excavation and ORC injection are shown on Plate 2. To dewater the excavation, Decon constructed an extraction well (EW-1) in the northern portion of the excavation area following backfilling activities.

2

3.0 WATER-LEVEL AND DISSOLVED OXYGEN MEASUREMENTS

Water levels in the five onsite wells were measured by Blaine Tech Services, Inc. (Blaine Tech) of San Jose, California, prior to sampling on May 16, 2003. Depth-to-water in the wells was measured from the top-of-casing (TOC) reference benchmark to a precision of 0.01-feet using an electronic water-level indicator. Depth-to-water measurements were converted to water-level elevations by subtracting the depth to water from the surveyed TOC elevation. Well construction details and TOC elevations are compiled in Table 1. Measurable free product was not observed in any of the monitoring wells, however, a sheen was present on the water removed from monitoring well MW-1.

Following completion of water-level measurements, Blaine Tech collected dissolved oxygen (DO) readings from each well. DO measurements were collected using a handheld meter. A probe was lowered into the screened interval of the well and gently raised and lowered until the DO readings stabilized.

To prevent cross-contamination between wells, the portions of the water-level indicator and DO meter that were submerged in the wells were cleaned between well measurements using a phosphate-free detergent/deionized water solution and double rinsed with deionized water.

4.0 GROUNDWATER SAMPLING

On May 16, 2003, Blaine Tech collected groundwater samples from Wells MW-1, MW-2, MW-3, MW-4, and EW-1. Groundwater samples were collected from each well after removing approximately three well volumes of water with disposable bailers. Because of the large volume of water required for adequate purging, EW-1 was purged using a submersible electric pump. The pump and associated tubing was cleaned prior to and following the completion of well purging using a phosphate-free detergent/deionized water solution and double rinsed with deionized water. During well purging, the discharged water was monitored for pH, temperature, electrical conductivity, and turbidity.

Following purging, samples were collected from the wells using disposable polyethylene bailers and transferred to the appropriate laboratory sample containers. The sample containers were filled slowly to minimize sample volatilization and to ensure that the sample was free of air bubbles. The samples were labeled to designate sample number, time and date collected, and analysis required. The samples were immediately placed in a chilled, thermally-insulated cooler. Sampling procedures are documented in the groundwater sampling report prepared by Blaine Tech, included as Appendix A.

Groundwater samples were transported under chain-of-custody protocol to Severn Trent Laboratories, Inc. (STL), a state-certified laboratory in Pleasanton, California. STL analyzed samples for:

61800102R011.doc 3

- Total petroleum hydrocarbons quantified as gasoline (TPHg) using U.S. Environmental Protection Agency (EPA) Test Method 8015-Modified
- Benzene, toluene, ethyl-benzene, and total xylenes (BTEX) using U.S. EPA Test Method 8021B or U.S. EPA Test Method 8260B; and
- Tert-butyl alcohol (TBA), methyl tert-butyl ether (MTBE), di-isopropyl ether (DIPE), ethyl tert-butyl ether (ETBE), tert-amyl methyl ether (TAME), ethylene dichloride (EDC [also known as 1,2-dichloroethane]), and ethylene dibromide (EDB) using U.S. EPA Test Method 8260B.

Analytical data from the second quarter 2003 monitoring event will be submitted electronically to the SWRCB Geotracker database along with the well location data. The laboratory reports and chain-of-custody records are included in Appendix B.

5.0 DISCUSSION OF MONITORING RESULTS

This section summarizes the field measurements (water-level and DO) and groundwater analytical results from the May 2003 sampling event.

5.1 Water-Level and Dissolved Oxygen Measurements

Depth-to-water measurements taken on May 16, 2003 ranged from 2.73 feet (EW-1) to 3.87 feet (MW-4) below TOC. Calculated groundwater elevations ranged from 6.57 feet (MW-3) to 7.53 feet (EW-1) relative to mean sea level (MSL). Historical and current depth-to-water measurements and water-level elevations are presented in Table 2.

Groundwater-level elevations are presented on Plate 2. A definitive groundwater flow direction could not be extrapolated from the groundwater-level elevations observed on May 16, 2003. It should be noted, however, that the area in the center of the groundwater monitoring zone has been highly disturbed during remediation activities (Section 2.0). Consequently, any number of factors including the excavation of soil and subsequent backfilling of the remediation area and the injection of ORC could be influencing groundwater elevations in the vicinity of the monitoring wells.

DO measurements collected on May 16, 2003 ranged from 0.2 milligrams per liter (mg/L), in monitoring well MW-1, to 2.7 mg/L in well MW-2. DO measurements are presented in Blain Tech's groundwater sampling report (Appendix B) and in Table 3.

4

61800102R011.doc

5.2 Groundwater Chemistry

A summary of current laboratory chemical results for petroleum hydrocarbons is presented in Table 3. Copies of the laboratory report and chain-of-custody documentation are provided in Appendix B.

During the current monitoring period, at monitoring wells MW-2 and MW-3, only MTBE was detected at concentrations of 16 micrograms per liter (μ g/L) and 2.6 μ g/L, respectively. No other petroleum hydrocarbons were detected in either well at or above the respective laboratory reporting limits.

In the sample collected from monitoring well MW-1, petroleum hydrocarbons were detected at the following concentrations: TPH-g at 5,600 μ g/L; benzene at 22 μ g/L; ethyl-benzene at 240 μ g/L; and total xylenes at 490 μ g/L. No other compounds were detected at or above the respective laboratory reporting limits in the sample collected from well MW-1. Petroleum hydrocarbon concentrations detected in the sample collected from well MW-1 in May 2003 are relatively consistent with concentrations observed during the previous monitoring event conducted in December 2002.

In the sample collected from monitoring well MW-4, petroleum hydrocarbons were detected at the following concentrations: TPHg at 530,000 μ g/L; benzene at 24,000 μ g/L; toluene at 20,000 μ g/L; ethyl-benzene at 12,000 μ g/L; total xylenes at 63,000 μ g/L; and MTBE at 42,000 μ g/L. While concentrations of petroleum hydrocarbon compounds detected during the May 2003 event were generally higher than those observed in December 2002 and February 2003, they are generally consistent with the range of concentrations observed prior to the 2002 remediation activities.

In the sample collected from EW-1, petroleum hydrocarbons were detected at the following concentrations: TPHg at 330 μ g/L; benzene at 12 μ g/L; toluene at 7.6 μ g/L; ethyl-benzene at 4.2 μ g/L; total xylenes at 14 μ g/L; and MTBE at 300 μ g/L. No other compounds were detected at or above the respective laboratory reporting limits in the sample collected from the extraction well. Concentrations detected in well EW-1 during the current sampling event were lower than those observed during the previous quarter.

In general, these data appear to indicate that the petroleum hydrocarbon plume associated with the former UST remains localized and relatively stable.

6.0 REFERENCES

Alameda County Environmental Health Services (ACEHS), 1997. Soil and Groundwater Investigation for Pacific Electric Motor Co., 1009-66th Ave., Oakland, CA 94601. August 19.

61800102R011.doc 5

- ______, 1998a. Evaluation of Residual Health Risks at Pacific Electric Motor Company, 1009 66th Avenue, Oakland, CA 94601. May 13.
 ______, 1998b. Additional Soil and Groundwater Investigation Report, 1009 66th Ave., Oakland, 94601. December 1.
 ENVIRON Corporation, 1997. Soil and Groundwater Investigation, Summary Report, Pacific Electric Motor Co., 1009-66th Avenue, Oakland, California. July 17.
 PES Environmental, Inc. (PES), 1998a. Results of Additional Soil and Groundwater Investigation, 1009 66th Avenue, Oakland, California. November 11.
 ______, 1998b. Proposal, Quarterly Groundwater Sampling, Pacific Electric Motor Company, Oakland, California. December 11.
- W. A. Craig, Inc. (WAC), 1997. Excavation and Sampling Report, Pacific Electric Motor Co., 1009 66th Avenue, Oakland, California. May 12. (Partial)

Table 1
Monitoring Well Completion Details
Groundwater Monitoring Report
Pacific Electric Motor Company
1009 66th Avenue, Oakland, California

Well	Date	Installed	Top of Casing Elevation	Boring Diameter	Casing Diameter	Total Depth Boring	Total Depth of Casing		d Interval feet bgs)
Number	Installed	Ву	(feet MSL)	(inches)	(inches)	(feet bgs)	(feet bgs)	Тор	Bottom
MW-1	6/10/1997	ENVIRON	10.87	8	2	26.5	25.5	5	25
MW-2	6/10/1997	ENVIRON	10.02	8	2	25.5	25.5	5	25
MW-3	6/10/1997	ENVIRON	10.12	8	2	25.5	25.5	5	25
MW-4	9/14/1998	PES	10.50	8	2	25.0	25.0	15	25
EW-1*	NP	Decon	10.26	NP	7	NP	8.77	NP	NP

Notes:

bgs = Below ground surface

NP = Information not provided to PES

^{* =} Well completion information derived from December 2002 sampling event field notes

Table 2
Water-Level Elevation Data
Groundwater Monitoring Report
Pacific Electric Motor Company
1009 66th Avenue, Oakland, California

Well	Date	Measured	Top of Casing Elevation	Depth to Water	Water-level Elevation
Number	Measured	Ву	(feet ¹ /feet MSL ²)	(feet BTOC)	(feet ¹ /feet MSL ²)
MW-1	6/19/1997	ENVIRON	100.67	5.87	94.80
10.00	7/1/1997	ENVIRON	100.67	5.88	94.79
	9/29/1997	PES	100.67	6.45	94.22
	12/16/1997	PES	100.67	3.42	97.25
	3/10/1998	PES	100.67	3.06	97.61
	10/1/1998	PES	100.67	6.36	94.31
	1/19/1999	PES	100.67	5.33	95.34
	4/15/1999	PES	100.67	3.23	97.44
	5/6/1999	PES	100.67	4.36	96.31
	7/30/1999	PES	100.67	4.30 5.49	95.18
		PES			
	11/15/1999	PES	100.67	6.30	94.37
	3/24/2000		100.67	3.47	97.20
	5/18/2000	PES	100.67	4.34	96.33
	7/26/2000	PES	100.67	5.28	95.39
	10/30/2000	PES	100.67	5.68	94.99
	11/14/2000	PES	100.67	5.53	95.14
	7/24/2001	PES	100.67	5.52	95.15
	11/28/2001	PES	100.67	5.31	95.36
	2/18/2002	PES	100.67	3.69	96.98
	12/11/2002	PES	10.87	5.71	5.16
	2/26/2003	PES	10.87	3.90	6.97
	5/16/2003	PES	10.87	3.61	7.26
MW-2	6/19/1997	ENVIRON	99.85	5.30	94.55
	7/1/1997	ENVIRON	99.85	5.37	94.48
	9/29/1997	PES	99.85	6.05	93.80
	12/16/1997	PES	99.85	3.81	96.04
	3/10/1998	PES	99.85	2.89	96.96
	10/1/1998	PES	99.85	5.83	94.02
	1/19/1999	PES	99.85	5.26	94.59
	4/15/1999	PES	99.85	3.19	96.66
	5/6/1999	PES	99.85	3.91	95.94
	7/30/1999	PES	99.85	4.79	95.9 4 95.06
	11/15/1999	PES			
	3/24/2000	PES	99.85	5.92 3.55	93.93
	5/18/2000 5/18/2000	PES	99.85	3.55 4.04	96.30 05.81
	7/26/2000	PES	99.85		95.81 05.00
		. — –	99.85	4.85	95.00
	10/30/2000	PES	99.85	5.31	94.54
	11/14/2000	PES	99.85	5.14	94.71
	7/24/2001	PES	99.85	5.12	94.73
	11/28/2001	PES	99.85	5.15	94.70
	2/18/2002	PES	99.85	3.73	96.12
	12/11/2002	PES	10.02	5.30	4.72
	2/26/2003 5/16/2003	PES PES	10.02 10.02	3.55 3.37	6.47 6.65
	3/ TU/ZUU3	rea	10.02	3.37	0.00
MW-3	6/19/1997	ENVIRON	99.93	5.50	94.43
	7/1/1997	ENVIRON	99.93	5.52	94.41
	9/29/1997	PES	99.93	6.16	93.77
	12/16/1997	PES	99.93	5.52	94.41
	3/10/1998	PES	99.93	3.11	96.82
	10/1/1998	PES	99.93	5.96	93.97
	1/19/1999	PES	99.93	5.45	94.48
			00.00	0,-10	Q-1.1Q

Table 2
Water-Level Elevation Data
Groundwater Monitoring Report
Pacific Electric Motor Company
1009 66th Avenue, Oakland, California

Well	Date	Measured	Top of Casing Elevation	Depth to Water	Water-level Elevation
Number	Measured	By	(feet ¹ /feet MSL ²)	(feet BTOC)	(feet ¹ /feet MSL
MW-3	5/6/1999	PES	99.93	4.12	95.81
cont.	7/30/1999	PES	99.93	5.14	94.79
00111.	11/15/1999	PES	99.93	6.35	93.58
	3/24/2000	PES	99.93	3.29	96.64
	5/18/2000	PES	99.93	4.16	95.77
	7/26/2000	PES	99.93	5.14	94.79
	10/30/2000	PES	99.93	5.43	94.50
	11/14/2000	PES	99.93	5.25	94.68
	7/24/2001	PES	99.93	5.29	94.64
	11/28/2001	PES	99.93	4.92	95.01
	2/18/2002	PES	99.93	3.88	96.05
	12/11/2002	PES	10.12	5.37	4.75
	2/26/2003	PES	10.12	3.71	6.41
	5/16/2003	PES	10.12	3.55	6.57
	0.10.2000	. 20	10.12	5.55	0.07
MW-4	10/1/1998	PES	100.32	6.32	94.00
	1/19/1999	PES	100.32	5.59	94.73
	4/15/1999	PES	100.32	7.71#	92.61 #
	5/6/1999	PES	100.32	4.50	95.82
	7/30/1999	PES	100.32	5.18	95.14
	11/15/1999	PES	100.32	6.27	94.05
	3/24/2000	PES	100.32	3.59	96.73
	5/18/2000	PES	100.32	4.40	95.92
	7/26/2000	PES	100.32	5.65	94.67
	10/30/2000	PES	100.32	5.89	94.43
	11/14/2000	PES	100.32	5.61	94.71
	7/24/2001	PES	100.32	5.34	94.98
	11/28/2001	PES	100.32	5.67	94.65
	2/18/2002	PES	100.32	4.21	96.11
	12/11/2002	PES	10.50	5.77	4.73
	2/26/2003	PES	10.50	4.00	6.50
	5/16/2003	PES	10.50	3.87	6.63
EW-1	12/11/2002	PES	10.26	5.00	5.26
	2/26/2003	PES	10.26	3.10	7.16
	5/16/2003	PES	10.26	2.73	7.53

Notes:

BTOC = Below top of casing

^{1 =} Top of casing elevations referenced to site datum established by ENVIRON (1997), used through February 2002

² = Top of casing elevations resurveyed by Cross Land Surveying, Inc. on January 16, 2003; referenced to NGVD 1929 MSL = Mean sea level

^{# =} Anomalous data, not used for water-level elevation contouring

Table 3
Summary of Analytical Results for Groundwater Samples
Groundwater Monitoring Report
Pacific Electric Motor Company
1009 66th Avenue, Oakland, California

			Dissolved	· - ·-		 	Ethyl-		LITTE		 	г	,			
Well	Date	Sampled	Oxygen	TPH-g	Benzene	Toluene	1 1	Vida	MTBE	MTBE			1	ŀ	1	
Number	Sampled	Ву	(mg/L)	(µg/L)	(µg/L)	(µg/L)	benzene	Xylenes	EPA 8020	EPA 8260	TBA	DIPE	ETBE	TAME	EDC	EDB
MW-1							(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MAA-1	6/19/1997	ENVIRON	na	18,000	3,300	200	1,100	4,900	<250							
	9/29/1997	PES	na	29,000	4,800	<25	2,000	3,500	<250		1		_		l	l
	12/16/1997	PES	na j	<50	1.3	<0.5	0.6	0.7	<5					J		l
	3/10/1998	PES	na i	190	2.0	<0.5	5.7	1.7	<5]						
	1/19/1999	PES	na	1,000	40	<0.5	18	68	8.3	6.9		_				l <u>-</u>
1	4/15/1999	PES	na	<50	0.92	0.9	0.7	0.87	<5.0	-		_			j	
l	7/30/1999	PES	na i	1,400	60	<0.5	63	120	13	<5.0			1			
	11/15/1999	PES	na	3,600	120	<0.5	150	620	<5.0							
	3/24/2000	PES	na	< 5 0	<0.5	<0.5	<0.5	<0.5	<5.0							-
	5/18/2000	PES	па	1,300	10	1.2	38	130	8,6	<5.0		l <u></u>	l _			<u> </u>
	7/26/2000	PES	na	6,400	100	7.4	260	680	<5.0				l			-
	10/30/2000	PES	na	6,000	130	14	330	950	<100							<u> </u>
	7/24/2001	PE\$	na i	1,200	13	<0.5	70	39	13				_	<u>"</u>	ľ	
İ	11/28/2001	PES	na I	1,800	27	0.93	72	160	<5.0							-
	2/18/2002	PES	na	2,400	18	<2.5	89	200	<25			_		-		
	12/11/2002	PES	0.7	8,400	83	9.2	320	640		<0.50	<5.0	<1.0	<0.50	<0.50	<0.50	
	2/26/2003	PES	2.2*	8,300	12	<10	240	720	1	<10	<100	<20	<10	<10		<0.50
ļ	5/16/2003	₽ES	0.2	5,600	22	<5.0	240	490		<5.0	<50	<10	<5.0	l	<10	<10
			[~10	\ \0.0	<5.0	<5,0	<5.0
MW-2	6/19/1997	ENVIRON	na	<50	<0.5	<0.5	<0,5	<0.5	<5.0	••						
	9/29/1997	PES	na	<50	<0.5	<0.5	<0.5	<0,5	<5				_			
	12/16/1997	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5							
	3/10/1998	PES	па	<50	<0.5	<0.5	<0.5	<0.5	<5.0				_			
	1/19/1999	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0	<5.0		-	-			-
	4/15/1999	PES	na	<50	0.75	0.64	<0.5	0.74	<5.0 <5.0	~5.0						
	7/30/1999	PES	na I	<50	<0.5	<0.5	<0.5	<0.5	<5.0		-				**	
	11/15/1999	PES	na i	<50	<0.5	<0.5	<0.5	<0.5	<5.0 <5.0		_		1			-
	3/24/2000	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0 <5.0			_				
	5/18/2000	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0			'			-	
	7/26/2000	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0		 			-		_
ŀ	10/30/2000	PES	na 1	<50	<0.5	<0.5	<0.5	<0.5	<5.0						_	
	7/24/2001	PES	na	<50	<0.5	<0.5	<0.5	<0.5	7.6							
1	11/28/2001	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0		* **				- :	
1	2/18/2002	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0							
	12/11/2002	PES	1.4	<50	<0.50	<0.50	<0.50	<1.0							_	
1	2/26/2003	PES	0.8	<50	<0.50	<0.50	<0.50	<1.0		5.8	<5.0	<1.0	<0.50	<0.50	<0.50	<0.50
ļ	5/16/2003	PES	2.7	<50	<0.50	<0.50	<0.50	<1.0		10	<5.0	<1.0	<0.50	<0.50	<0.50	<0.50
					-0.00	-0.50	~0.50	~1.0		16	<5.0	<1.0	<0.50	<0.50	<0.50	<0.50
MW-3	6/19/1997	ENVIRON	na	<50	<0.5	<0.5	<0.5	<0.5	4E 0							
	9/29/1997	PES	na	<50	<0.5	<0.5	<0.5		<5.0		-					
	12/16/1997	PES	па	<50	<0.5	<0.5 <0.5		<0.5	<5 -5		-		-			
	3/10/1998	PES	na	<50	<0.5		<0.5	<0.5	<5			-				
	1/19/1999	PES	na	<50	0.78	<0.5	<0.5	<0.5	<5.0							
	4/15/1999	PES	na	<50 <50		<0.5	<0.5	<0.5	8.7	<5.0	-					_
	7/30/1999	PES	na	<50 <50	5.4	3.9	1.7	5.6	23	25		- ,				
	11/15/1999	PES	na	<50 <50	<0.5	<0.5	<0.5	<0.5	<5.0							
	3/24/2000	PES	na	<50 <50	<0.5	<0.5	<0.5	<0.5	<5.0		-		••			-
	~ E 4/E000	1 20		<u> </u>	<0.5	<0.5	<0.5	<0.5	<5.0		••			_		

Table 3
Summary of Analytical Results for Groundwater Samples
Groundwater Monitoring Report
Pacific Electric Motor Company
1009 66th Avenue, Oakland, California

Well Number	Date Sampled	Sampled By	Dissolved Oxygen (mg/L)	TPH-g (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl- benzene (µg/L)	Xylenes {µg/L}	MTBE EPA 8020 (µg/L)	МТВЕ ЕРА \$260 (µg/L)	TBA (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TAME (µg/L)	EDC (µg/L)	EDB
мw-з	5/18/2000	PES	na	<50	<0,5	<0.5	<0.5	<0.5	<5.0							(µg/L)
cont.	7/26/2000	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0 <5.0	-		-			_	
	10/30/2000	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0 <5.0		••	-				
	7/24/2001	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0 <5.0				-			
	11/28/2001	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0							
1	2/18/2002	PES	na	<50	<0.5	<0.5	<0.5	<0.5	<5.0 <5.0		-				!	
	12/11/2002	PES	1.9	<50	<0.50	<0.50	<0.50	<1.0	~5.0	- 0.78	<5.0					
	2/26/2003	PES	1.9	<50	<0.50	<0.50	<0.50	<1.0		<0.50		<1.0	<0.50	<0.50	<0.50	<0.50
ł	5/16/2003	PES	1.9	<50	<0.50	<0.50	<0.50	<1.0		2.6	<5.0	<1.0	<0.50	<0.50	<0.50	<0.50
					10.00	-0,00	10,50	~1.0		2.5	<5.0	<1.0	<0.50	<0.50	<0.50	<0.50
MW-4	9/15/1998	PES	na	170,000	26,000	32,000	2,900	18,000	26,000							
1	1/19/1999	PES	na	2,600	1,700	3.8	25	29	13,000	16,000					-	**
1	4/15/1999	PES	na	210.000	28,000	15,000	3,700	19,000	52,000	67,000					-	_
	7/30/1999	PES .	na	91,000	16,000	7.500	2,300	8,500	68,000	67,000	-		-		-	_
	11/15/1999	PES	na :	63,000	8,500	2,400	1,400	4.000	57,000	58,000					-	**
	3/24/2000	PES	na l	95,000	16,000	13,000	2,500	12,000	44,000	20,000	-			-	**	-
	5/18/2000	PES	na Ì	91,000	15,000	10,000	2,200	9.600	64,000	77,000		-			_	
	7/26/2000	PES	na	130,000	11.000	6,400	1,700	6,500	80,000	77,000					-	
	10/30/2000	PES	na	59,000	6,700	2,200	750	3,100	68,000	68.000**				-		
	7/24/2001	PES	na	180,000	25,000	23,000	3,500	20,000	44,000	44.000**		-		-	- !	
	11/28/2001	PES	na	67,000	8,100	3,300	1,400	5,600	57,000	57.000**		-	-			
	2/18/2002	PES	na	98,000	20,000	12,000	2,300	15.000	47,000	47,000**					••	
	12/11/2002	PES	0.8	200,000	340	<50	590	1,000	**	17,000	3,600	<100	 <50	 <50		
	2/26/2003	PES	0.1	63,000	8,100	4,400	1,900	B.200		30,000	<1,300	<250	<130	<130	<50 <130	<50
	5/16/2003	PES	0.4	530,000	24,000	20,000	12,000	63,000		42,000	<2,500	<500	<250	<250	<130 <250	<130 <250
EW-1	12/11/2002	PES	2.4	6,600	530	<50	87	<100		2.600	1,600	<100	<50	<50	<50	-to
	2/26/2003	PES	0.1	4,000	170	20	41	53		5,000	130	<25	<50 <13	<13		<50
	5/16/2003	PE\$	0.5	330	12	7.6	4.2	14	:	300	<25	<5.0	<2.5	<13 <2.5	<13 <2.5	<13 <2.5

Notes:

TPH-g = Total petroleum hydrocarbons quantified as gasoline (EPA 8015M)

MTBE = Methyl tert-butyl ether (EPA 8020; detected concentrations were confirmed by EPA 8260)

TBA = terl-butyl alchohol

DIPE = di-isopropyl ether

ETBE = ethyl tert-butyl ether

TAME = tert-amyl methyl ether

EDC = ethylene dichloride (also known as 1,2-dichloroethane)

EDB = ethylene dibromide

mg/L = milligrams per liter

μg/L = micrograms per liter


na = not analyzed

* = Dissolved oxygen measurement collected following purging

** = MTBE results confirmed but not requantified by EPA Method 8260

<50 = Not detected at or above the indicated laboratory reporting limit

-- # Not analyzed





PES Environmental, Inc. Engineering & Environmental Services Site Location Map
Second Quarter 2003 Groundwater
Monitoring Report
Pacific Electric Motor Company
1009 66th Avenue, Oakland, California


PLATE

618.001.02.005

JOB NUMBER

61800101004_V1.CDR DRAWING NUMBER WWM REVIEWED BY 7/03

DATE



PES Environmental, Inc.
Engineering & Environmental Services

Site Plan and Well Location Map and Water-level Elevation Map Second Quarter 2003 Groundwater Monitoring Report Pacific Electric Motor Company 1009 66th Avenue Oakland, California

2

618.001.02.005

61800102004_2Q-2003.cdr

WWM

JOB NUMBER DRAWING NUMBER

REVIEWED BY

7/03

APPENDIX A

GROUNDWATER SAMPLING REPORT

Page of !

WELLHEAD INSPECTION CHECKLIST

lient	PEUC			Date	5/1		· · · · - · · · · · · · · · · · · · · ·
ite Address	1009 664	4 Aus, O	AKLAND				
ob Number	030516-B	Al	Tech	nician	BRIAN	Accorn	
Well ID	Well Inspected - No Corrective Action Required	From Comp	ibox Cap onents aned Replaced	Lock Replaced	Other Action Taken (explain below)	Well Not Inspected (explain below)	Repair Order Submitted
MW-1							
MW-2					0		
MW3				ļ			
MW-4 EW-1							ļ
2W-1					(a)		
NOTES:	Chissing one	1 11 1 15 1	2 0 1.1		(a) A	. n 1 . h	nlap-n
NOTES.	Missing one	-belt - belt 1	<u>vie in lid</u>	dancie	a - W	al has I	S + 1
	· · · · · · · · · · · · · · · · · · ·				·		

WELL GAUGING DATA

Project # _	030516-BAI	Date 5/16/63	Client	PES ENVIRONMENTAL
Site	1009 66th 1	HE DAKLAND		

			1						
-	337.11	,	[Thickness	Volume of]
	Well		Depth to	of	Immiscibles			Survey	
377 11 110	Size	Sheen /	Immiscible			Depth to water			
Well ID	(in.)	Odor	Liquia (ft.)	Liquid (ft.)	(ml)	(ft.)	bottom (ft.)	or TOC	
MW-1.	2					3.61	24.78	Toc	A CONTRACTOR OF THE CONTRACTOR
MW-2	2					3.37	24.76	(
mw-3	ス					3.55	24.63		
mury	ュ					3.87	24.57		
€w-1	8					2.73	もって	7	
								erman parameter and parameter	

			1	<u> </u>					· · · · · · · · · · · · · · · · · · ·
:						1	en e		
						-			
<u> </u>		and the state of t							.
						THE PROPERTY OF THE PROPERTY O			
-									THE CONTRACT OF THE CONTRACT O
					<u> </u>		·		
	-								
				Transmission of the Control of the C			The Principle (1).	as byging i Lillandiii	

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (408) 573-0555

WELL MONITORING DATA SHEET

		* * * * * * * * * * * * * * * * * * * *	EEE WONE	OKING DATA	\ OHEET	
Project #	: 0305	16-BA1		Client: Res	ENVIRONME	artial.
Sampler:		ALLORA		Start Date: 5	5/16/03	
Well I.D	: MW-/			Well Diameter	: ② 3 4	6 8
Total We	ell Depth:	24.78		Depth to Water	r: 3.61	
Before:		After:		Before:		After:
Depth to	Free Produc	ct:	<u>.</u>	Thickness of F	ree Product (fe	et):
Referenc	ed to:	PVC	Grade	D.O. Meter (if	req'd):	YŚI HACH
Purge Meth	od: Bailer Disposable Bai Middleburg Electric Subme		Waterra Peristaltic Extraction Pump Other	Sampling Method: Other:	Disposable Bailer Extraction Port Dedicated Tubing	<u>Diameter Multiplier</u> 0.65
3.5 Gals.	(Gals.) X	_3	= 10.5	2" 3"	0.16 6" 0.37 Othe	1.47 r radius² * 0.163
Time	Temp.	рН	Conductivity (mS or (MS))	Turbidity (NTU)	Gals. Removed	Observations
1117	626	סינ	345	ור	3.5	mild slight clear, odor, steen od cloudly, brown, sli
1123	63.1	م،ما	2-80	210	7.0	cloudy, brown, 31:
(128	64.0	6.5	283	496	10.5	<i>"</i>
Did well	dewater?	Yes	No	Gallons actuall	y evacuated:	10.5
Sampling	Time:	130		Sampling Date	5/16/03	
Sample I.	D.: _Mu	۱-د	"	Laboratory: 5-	<u> </u>	
Analyzed	for: PH-G	BTEX	мтве т рн-D	Other: TAME, DI	PE, ETBE, TRA.ET	08, yedc all by 8760
Equipmen	nt Blank I.D),:	@ Time	Duplicate I.D.:		
Analyzed	for: TPH-G	BTEX N	мтве трн-d	Other:		
D.O. (if r	eq'd): 🍗	un Hole	Pre-purge.	ن.ک ^{mg} /د	Post-purge:	mg/L
ORP (if re			Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services. Inc. 1680 Rogers Ave., San Jose, CA 95112 (408) 572 0555

WELL MONITORING DATA SHEET

Project #	03051	6-BA1		Client: PE	S ENVIRONME	NTAL
Sampler:	BRIANA	Leon		Start Date:	5/16/03	
Well I.D.	<u> </u>			Well Diameter	: 2 3 4	6 8
Total We	ll Depth:	24.76		Depth to Wate	r: 3.37	
Before:		After:		Before:		After:
Depth to	Free Produc			Thickness of F	ree Product (fe	et):
Reference	ed to:	(PVC)	Grade	D.O. Meter (if	req'd):	YSI HACH
Purge Metho	od: Bailer Disposable Bai Middleburg Electric Subme		Waterra Peristaltic Extraction Pump Other	Sampling Method: Other:	Disposable Bailer Extraction Port Dedicated Tubing	Diameter Multiplier
3.5	_(Gals.) X	3	= 10.5	2"	0.16 6"	0.65 1.47
Gals.			T	3"	0.37 Othe	er radius ² * 0.163
Time	Temp. (°F or °C)	pН	Conductivity (mS or as)	Turbidity (NTU)	Gals. Removed	Observations
0937	<u>હ્</u> ય.૧	6.5	1,185	590	3.5	doudy brown
৩ 9५५	64.1	6.8	1,183	>1,000	7.0	"
0949	63.7	6.8	1,129	סטם, וד	10.5	• • • • • • • • • • • • • • • • • • • •
Did well o	lewater?	Yes (No.	Gallons actuall	v evacuated.	10.5
Sampling	T.'			Sampling Date		10.5
Sample I.I		350 2		Laboratory:	5/6/03 STL	
	for: TPH-G	BTEX N	итве) трн-d			108, + EDC all by 8760
<u> </u>	t Blank I.D		<u> </u>	·		
Analyzed				Duplicate I.D.: Other:	<u> </u>	
	 		re-purge:	an mg/L	Post-purge:	mg/L
ORP (if re			Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Roners Ave. San Jose CA 05442 (400) 572 0555

WELL MONITORING DATA SHE	RE	SH	A	T	A	D	\mathbf{G}	IN	R	\mathbf{C}	П)N	AC	1	LL	V.	١
--------------------------	----	----	---	---	---	---	--------------	----	---	--------------	---	----	----	---	----	----	---

		YY	RLL MOMI	ORING DATA	ASHLET			
Project #	: 03051	6-BA1	<u>-</u>	Client: PES	Environme	NTAL		
Sampler:	BRIAN	ALLORN		!	5/16/03			
Well I.D.	: MW-3			Well Diameter	: ② 3 4	6 8		
Total We	ell Depth:	24.63		Depth to Water: 3.55				
Before:		After:		Before:		After:		
Depth to	Free Produ	ct:		Thickness of F	ree Product (fe	et):		
Referenc	ed to:	PVC	Grade	D.O. Meter (if	req'd):	YSI HACH		
Purge Meth	od: Bailer Disposable Bai Middleburg Electric Subme		Waterra Peristaltic Extraction Pump Other	Sampling Method: Other:	Disposable Bailer Extraction Port Dedicated Tubing	Diameter Multiplier		
3.5 Gals.	_(Gals.) X	3	= 10.5		0.04 4" 0.16 6" 0.37 Othe	0.65 1.47		
Time	Temp. (°F or °C)	pН	Conductivity (mS or uS)	Turbidity (NTU)	Gals. Removed	Observations		
1046	نه اول	6.9	۵,445	338	3.5	cloudy brown		
1053	61.8	6.8	3,094	231	7.6	11		
1058	63.2	6.7	4.065	188	10.5	11		
					-			
Did well o	dewater?	Yes (No	Gallons actuall	y evacuated:	10.5		
Sampling	Time:	100		Sampling Date:	5/16/03			
Sample I.	D.: ռւա	-3		Laboratory:	51L			
Analyzed	for: (TPH-G	BTEX M	тве трн-d	Other: TAME, DI	PE, ETBE, TBA, E	DB+ EDC all by 8240		
Equipmen	t Blank I.D	•	@ Time	Duplicate I.D.:				
Analyzed	for: трн-G	BTEX M	ITBE TPH-D	Other:				
D.O. (if re	eq'd): D	wn-Hole	Pre-purge:) , 9 ^{mg} /L	Post-purge:	mg/L		
ORP (if re	eq'd):		Pre-purge:	mV	Post-purge:	mV		

Blaine Tech Services. Inc. 1680 Roders Ave., San Jose CA 05442 (ADD) 572 0555

WELL MO	DNITORING	DATA	SHEET

Project #	: 63051	6-BA1	·····	Client: PES	ENVIRONME	WTAL
Sampler	BRIANI	ALCORN		Start Date:		
Well I.D	.: MW-4			Well Diameter	: ② 3 4	6 8
Total W	ell Depth: ¿	2457		Depth to Wate	r: 3.87	
Before:		After:		Before:		After:
Depth to	Free Produ	ct:		Thickness of F	ree Product (fe	et):
Referenc	ed to:	PVC) Grade	D.O. Meter (if	req'd):	YSI HACH
Purge Meth	nod: Bailer Disposable Bai Middleburg Electric Subme		Waterra Peristaltic Extraction Pump Other	Sampling Method: Other:	Disposable Bailer Extraction Port Dedicated Tubing	Diameter Multiplier
3.5	(Gals.) X	3	= 10.5	1" 2"	0.04 4" 0.16 6"	0.65 1.47
Gals.				3"	0.37 Othe	radius² * 0.163
Time	Temp.	pН	Conductivity (mS or (μS)	Turbidity (NTU)	Gals. Removed	Observations
1613	67.6	7.1	2,372	319	3.5	cloudy gray, ada
1019	۵،۲ی	ه.ما	3,172	349	7.0	17
1029	66.7	6.6	3,432	732	10.5	"
Did well	dewater?	Yes (No	Gallons actuall	y evacuated:	10.5
Sampling	Time: (6	30		Sampling Date:	5/16/03	
Sample I.	D.: Mu	٧-٢	<u>-</u>		STL	
Analyzed	for: (TPH-G	BTEX M	тве трн-d	-	-	DB+EDC all by
Equipmen	nt Blank I.D	.:	@ Time	Duplicate I.D.:		1000
Analyzed	for: TPH-G	BTEX M	TBE TPH-D	Other:		
O.O. (if re	eq'd): Do	un Hole	Pre-purge:	0.4 mg/L	Post-purge:	mg/L
ORP (if re			Pre-purge:	mV	Post-purge:	mV
Zlaina T	ach Sarvic	es inc	1680 Rogers	Ava Far la	00 05440	

WELL MONITORING DATA SHEET

Project #	: 0305	16-BA)		Client: PE	s Environm	ENTAL			
Sampler:	BRIAN	s Alloen	٠	Start Date:					
Wel I.D.	: Ew-1			Well Diameter	: 2 3 4	6 8			
Total We	ll Depth:	8.74		Depth to Water	r: 2.73				
Before:		After:		Before:		After:			
Depth to	Free Produc	et:		Thickness of F	ree Product (fe	et):			
Reference	ed to:	PVC) Grade	D.O. Meter (if req'd): YSI HACH					
Purge Metho	Bailer Disposable Bai Middleburg Electric Subme	rsible	Waterra Peristaltic Extraction Pump Other	Sampling Method: Other:	Disposable Bailer Extraction Port Dedicated Tubing	Diameter Multiplier 0.65			
	_(Gals.) X	3	= 48.0	2" 3"	0.16 6" 0.37 Othe	1.47			
Time	Temp. (°F or °C)	рН	Conductivity (mS of µS)	Turbidity (NTU)	Gals. Removed	Observations			
1151	70.0	9.2	1,267	496	16.0	cloudy, yellow, due			
1154	70.5	10.6	1,222	8	32.0	clear, yellow, ado			
1157	70.3	10.6	1,1106	12	48.0	.,			
Did well o	dewater?	Yes (No	Gallons actuall	y evacuated:	48			
Sampling	Time: (;	200		Sampling Date:	5/16/03				
Sample I.I	D.: Ew	-1		Laboratory:	STL				
Analyzed	for: 74H-G	BTEX M	итве) трн-d	Other:					
Equipmen	t Blank I.D	•	@ Time	Duplicate I.D.:					
Analyzed	for: TPH-G	BTEX M	ITBE TPH-D	Other:					
D.O. (if re	q'd): D	own Ho	Pre-purge:	0.5 mg/L	Post-purge:	mg/L			
ORP (if re	q'd):	·	Pre-purge:	mV	Post-purge:	mV			

Blaine Tech Services. Inc. 1680 Rogers Ave., San Jose CA 05442 (Ang.) 572 DEEE

APPENDIX B

LABORATORY REPORT
AND
CHAIN-OF-CUSTODY RECORDS



PES

May 23, 2003

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Attn.:

Will Mast

Project#: 618.001.02.005

Project:

Pacific Electric Motor

Site:

1099 66th Ave., Oakland, CA

Dear Mr. Mast,

Attached is our report for your samples received on 05/16/2003 18:22

This report has been reviewed and approved for release. Reproduction of this report is permitted only in its entirety.

Please note that any unused portion of the samples will be discarded after 06/30/2003 unless you have requested otherwise.

We appreciate the opportunity to be of service to you. If you have any questions, please call me at (925) 484-1919.

You can also contact me via email. My email address is: asalimpour@stl-inc.com

Sincerely,

Afsaneh Salimpour

Project Manager

Abanch. Salinger



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Samples Reported

Sample Name	Date Sampled	Matrix	Lab#
MW-1	05/16/2003 11:30	Water	1
MW-2	05/16/2003 09:50	Water	2
MW-3	05/16/2003 11:00	Water	3
MW-4	05/16/2003 10:30	Water	4
EW-1	05/16/2003 12:00	Water	5



Gas/BTEXFuel Oxygenates by 8260B

PE\$

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Prep(s):

5030B

Test(s):

8260FAB

Sample ID: MW-1

Lab ID:

2003-05-0508 - 1

Sampled: 05/16/2003 11:30

Extracted:

5/23/2003 11:16

Matrix:

Water

QC Batch#: 2003/05/23-01.64

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	5600	500	ug/L	10.00	05/23/2003 11:16	
Benzene	22	5.0	ug/L	10.00	05/23/2003 11:16	
Toluene	ND	5.0	ug/L	10.00	05/23/2003 11:16	
Ethylbenzene	240	5.0	ug/L	10.00	05/23/2003 11:16	
Total xylenes	490	10	ug/L	10.00	05/23/2003 11:16	
tert-Butyl alcohol (TBA)	ND	50	ug/L	10.00	05/23/2003 11:16	
Methyl tert-butyl ether (MTBE)	ND	5.0	ug/L	10.00	05/23/2003 11:16	
Di-isopropyl Ether (DIPE)	ND	10	ug/L	10.00	05/23/2003 11:16	
Ethyl tert-butyl ether (ETBE)	ND	5.0	ug/L	10.00	05/23/2003 11:16	
tert-Amyl methyl ether (TAME)	ND	5.0	ug/L	10.00	05/23/2003 11:16	
1,2-DCA	ND	5.0	ug/L	10.00	05/23/2003 11:16	
EDB	ND	5.0	ug/L	10.00	05/23/2003 11:16	
Ethanol	ND	250	ug/L	10.00	05/23/2003 11:16	
Surrogates(s)						
1,2-Dichloroethane-d4	100.5	76-114	%	10.00	05/23/2003 11:16	
Toluene-d8	98.0	88-110	%	10.00	05/23/2003 11:16	



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Prep(s):

5030B

Test(s):

8260FAB

Sample ID: MW-2

Lab ID:

2003-05-0508 - 2

Sampled: 05/16/2003 09:50 Matrix:

Water

Extracted:

5/23/2003 11:38 QC Batch#: 2003/05/23-01.64

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	ND	50	ug/L	1.00	05/23/2003 11:38	
Benzene	ND	0.50	ug/L	1.00	05/23/2003 11:38	
Toluene	ND	0.50	ug/L	1.00	05/23/2003 11:38	
Ethylbenzene	ND	0.50	ug/L	1.00	05/23/2003 11:38	
Total xylenes	ND	1.0	ug/L	1.00	05/23/2003 11:38	
tert-Butyl alcohol (TBA)	ND	5.0	ug/L	1.00	05/23/2003 11:38	
Methyl tert-butyl ether (MTBE)	16	0.50	ug/L	1.00	05/23/2003 11:38	
Di-isopropyl Ether (DIPE)	ND	1.0	ug/L	1.00	05/23/2003 11:38	
Ethyl tert-butyl ether (ETBE)	ND	0.50	ug/L	1.00	05/23/2003 11:38	
tert-Amyl methyl ether (TAME)	ND	0.50	ug/L	1.00	05/23/2003 11:38	
1,2-DCA	ND	0.50	ug/L	1.00	05/23/2003 11:38	
EDB	ND	0.50	ug/L	1.00	05/23/2003 11:38	
Ethanol	ND	25	ug/L	1.00	05/23/2003 11:38	
Surrogates(s)						
1,2-Dichloroethane-d4	104.1	76-114	%	1.00	05/23/2003 11:38	
Toluene-d8	99.2	88-110	%	1.00	05/23/2003 11:38	



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Prep(s): 50

5030B

Test(s):

8260FAB

Sample ID: MW-3

Lab ID:

2003-05-0508 - 3

Sampled: 05/16/2003 11:00

Extracted:


5/23/2003 02:53

Matrix:

Water

QC Batch#: 2003/05/22-2c.65

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	ND	50	ug/L	1.00	05/23/2003 02:53	
Benzene	ND	0.50	ug/L	1.00	05/23/2003 02:53	
Toluene	ND	0.50	ug/L	1.00	05/23/2003 02:53	
Ethylbenzene	ND	0.50	ug/L	1.00	05/23/2003 02:53	
Total xylenes	ND	1.0	ug/L	1.00	05/23/2003 02:53	
tert-Butyl alcohol (TBA)	ND	5.0	ug/L	1.00	05/23/2003 02:53	
Methyl tert-butyl ether (MTBE)	2.6	0.50	ug/L	1.00	05/23/2003 02:53	
Di-isopropyl Ether (DIPE)	ND	1.0	ug/L	1.00	05/23/2003 02:53	
Ethyl tert-butyl ether (ETBE)	ND	0.50	ug/L	1.00	05/23/2003 02:53	
tert-Amyl methyl ether (TAME)	ND	0.50	ug/L	1.00	05/23/2003 02:53	
1,2-DCA	ND	0.50	ug/L	1.00	05/23/2003 02:53	
EDB	ND	0.50	ug/L	1.00	05/23/2003 02:53	
Ethanol	ND	25	ug/L	1.00	05/23/2003 02:53	
Surrogates(s)	ł					
1,2-Dichloroethane-d4	112.0	76-114	%	1.00	05/23/2003 02:53	
Toluene-d8	100.3	88-110	%	1.00	05/23/2003 02:53	





Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Prep(s):

5030B

Test(s):

8260FAB

Sample ID: MW-4

Lab ID:

2003-05-0508 - 4

Sampled: 05/16/2003 10:30 Matrix:


Water

Extracted:

5/23/2003 12:00

QC Batch#: 2003/05/23-01.64

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	530000	25000	ug/L	500.00	05/23/2003 12:00	
Benzene	24000	250	ug/L	500.00	05/23/2003 12:00	
Toluene	20000	250	ug/L	500.00	05/23/2003 12:00	
Ethylbenzene	12000	250	ug/L	500.00	05/23/2003 12:00	
Total xylenes	63000	500	ug/L	500.00	05/23/2003 12:00	
tert-Butyl alcohol (TBA)	ND	2500	ug/L	500.00	05/23/2003 12:00	
Methyl tert-butyl ether (MTBE)	42000	250	ug/L	500.00	05/23/2003 12:00	
Di-isopropyl Ether (DIPE)	ND	500	ug/L	500.00	05/23/2003 12:00	
Ethyl tert-butyl ether (ETBE)	ND	250	ug/L	500.00	05/23/2003 12:00	
tert-Amyl methyl ether (TAME)	ND	250	ug/L	500.00	05/23/2003 12:00	
1.2-DCA	ND	250	ug/L	500.00	05/23/2003 12:00	
EDB	ND	250	ug/L	500.00	05/23/2003 12:00	
Ethanol	ND	13000	ug/L	500.00	05/23/2003 12:00	
Surrogates(s)						
1,2-Dichloroethane-d4	100.0	76-114	%	1.00	05/23/2003 12:00	
Toluene-d8	98.8	88-110	%	1.00	05/23/2003 12:00	





Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Prep(s):

5030B

Test(s):

8260FAB

Sample ID: EW-1

Lab ID:

2003-05-0508 - 5

Sampled: 05/16/2003 12:00

Extracted:

5/23/2003 12:23

Matrix:

Water

QC Batch#: 2003/05/23-01.64

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	330	250	ug/L	5.00	05/23/2003 12:23	
Benzene	12	2.5	ug/L	5.00	05/23/2003 12:23	
Toluene	7.6	2.5	ug/L	5.00	05/23/2003 12:23	
Ethylbenzene	4.2	2.5	ug/L	5.00	05/23/2003 12:23	
Total xylenes	14	5.0	ug/L	5.00	05/23/2003 12:23	
tert-Butyl alcohol (TBA)	ND	25	ug/L	5.00	05/23/2003 12:23	
Methyl tert-butyl ether (MTBE)	300	2.5	ug/L	5.00	05/23/2003 12:23	
Di-isopropyl Ether (DIPE)	ND	5.0	ug/L	5.00	05/23/2003 12:23	
Ethyl tert-butyl ether (ETBE)	ND	2.5	ug/L	5.00	05/23/2003 12:23	
tert-Amyl methyl ether (TAME)	ND	2.5	ug/L	5.00	05/23/2003 12:23	
1,2-DCA	ND	2.5	ug/L	5.00	05/23/2003 12:23	
EDB	ND	2.5	ug/L	5.00	05/23/2003 12:23	
Ethanol	ND	130	ug/L	5.00	05/23/2003 12:23	
Surrogates(s)					1	
1,2-Dichloroethane-d4	103.7	76-114	%	1.00	05/23/2003 12:23	
Toluene-d8	97.7	88-110	%	1.00	05/23/2003 12:23	



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Batch QC Report

Prep(s): 5030B Method Blank

MB: 2003/05/22-2c.65-056

Water

Test(s): 8260FAB QC Batch # 2003/05/22-2c.65

Date Extracted: 05/22/2003 20:59

Compound	Conc.	RL	Unit	Analyzed	Flag
Gasoline	ND	50	ug/L	05/22/2003 20:59	
Benzene	ND	0.5	ug/L	05/22/2003 20:59	
Toluene	ND	0.5	ug/L	05/22/2003 20:59	
Ethylbenzene	ND	0.5	ug/L	05/22/2003 20:59	
Total xylenes	ND	1.0	ug/L	05/22/2003 20:59	
tert-Butyl alcohol (TBA)	ND	5.0	ug/L	05/22/2003 20:59	
Methyl tert-butyl ether (MTBE)	ND	0.5	ug/L	05/22/2003 20:59	
Di-isopropyl Ether (DIPE)	ND	1.0	ug/L	05/22/2003 20:59	
Ethyl tert-butyl ether (ETBE)	ND	0.5	ug/L	05/22/2003 20:59	
tert-Amyl methyl ether (TAME)	ND	0.5	ug/L	05/22/2003 20:59	
1.2-DCA	ND	0.5	ug/L	05/22/2003 20:59	
EDB	ND	0.5	ug/L	05/22/2003 20:59	
Ethanol	ND	25	ug/L	05/22/2003 20:59	
Surrogates(s)					
1,2-Dichloroethane-d4	106.4	76-114	%	05/22/2003 20:59	
Toluene-d8	100.2	88-110	%	05/22/2003 20:59	



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Batch QC Report

Prep(s): 5030B Method Blank

MB: 2003/05/23-01.64-003

Test(s): 8260FAB
Water QC Batch # 2003/05/23-01.64

Date Extracted: 05/23/2003 10:01

Compound	Conc.	RL	Unit	Analyzed	Flag
Gasoline	ND	50	ug/L	05/23/2003 10:01	•
Benzene	ND	0.5	ug/L	05/23/2003 10:01	
Toluene	ND	0.5	ug/L	05/23/2003 10:01	
Ethylbenzene	ND	0.5	ug/L	05/23/2003 10:01	
Total xylenes	ND	1.0	ug/L	05/23/2003 10:01	
tert-Butyl alcohol (TBA)	ND	5.0	ug/L	05/23/2003 10:01	
Methyl tert-butyl ether (MTBE)	ND	0.5	ug/L	05/23/2003 10:01	
Di-isopropyl Ether (DIPE)	ND	1.0	ug/L	05/23/2003 10:01	
Ethyl tert-butyl ether (ETBE)	ND	0.5	ug/L	05/23/2003 10:01	
tert-Amyl methyl ether (TAME)	ND	0.5	ug/L	05/23/2003 10:01	
1.2-DCA	ND	0.5	ug/L	05/23/2003 10:01	
EDB	ND	0.5	ug/L	05/23/2003 10:01	
Ethanol	ND	25	ug/L	05/23/2003 10:01	
Surrogates(s)					
1,2-Dichloroethane-d4	98.8	76-114	%	05/23/2003 10:01	
Toluene-d8	97.4	88-110	%	05/23/2003 10:01	



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Batch QC Report

Prep(s): 5030B

Test(s): 8260FAB

Laboratory Control Spike

Water

QC Batch # 2003/05/22-2c.65

LCS 2003/05/22-2c.65-055 LCSD 2003/05/22-2c.65-002 Extracted: 05/22/2003 Extracted: 05/22/2003 Analyzed: 05/22/2003 20:14 Analyzed: 05/22/2003 20:37

Conc.	ug/L			overy	RPD	Ctrl.Lin	nits %	Flags	
LCS	LCSD			LCS LCSD		Rec	RPD	LCS	LCSD
25.5	24.7	25	102.0	98.8	3.2	69-129	20]
		1							
34.7	34.3	25	130.0	137.2	0.5	00-100	~		
513 502	495 488	500 500	102.6	99.0 97.6		76-114 88-110			
	25.5 24.8 34.7	LCS LCSD 25.5 24.7 24.8 23.7 34.7 34.3 513 495	LCS LCSD 25.5 24.7 25 24.8 23.7 25 34.7 34.3 25 513 495 500	LCS LCSD LCS 25.5 24.7 25 102.0 24.8 23.7 25 99.2 34.7 34.3 25 138.8 513 495 500 102.6	LCS LCSD LCS LCSD 25.5 24.7 25 102.0 98.8 24.8 23.7 25 99.2 94.8 34.7 34.3 25 138.8 137.2 513 495 500 102.6 99.0	LCS LCSD LCS LCSD % 25.5 24.7 25 102.0 98.8 3.2 24.8 23.7 25 99.2 94.8 4.5 34.7 34.3 25 138.8 137.2 0.9 513 495 500 102.6 99.0 99.0	LCS LCSD LCS LCSD % Rec. 25.5 24.7 25 102.0 98.8 3.2 69-129 24.8 23.7 25 99.2 94.8 4.5 70-130 34.7 34.3 25 138.8 137.2 0.9 65-165 513 495 500 102.6 99.0 76-114	LCS LCSD LCS LCSD % Rec. RPD 25.5 24.7 25 102.0 98.8 3.2 69-129 20 24.8 23.7 25 99.2 94.8 4.5 70-130 20 34.7 34.3 25 138.8 137.2 0.9 65-165 20 513 495 500 102.6 99.0 76-114	LCS LCSD LCS LCSD % Rec. RPD LCS 25.5 24.7 25 102.0 98.8 3.2 69-129 20 24.8 23.7 25 99.2 94.8 4.5 70-130 20 34.7 34.3 25 138.8 137.2 0.9 65-165 20 513 495 500 102.6 99.0 76-114



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Batch QC Report

Prep(s): 5030B

Test(s): 8260FAB

Laboratory Control Spike

2003/05/23-01.64-002

Water

QC Batch # 2003/05/23-01.64

LCS LCSD 2003/05/23-01.64-001 Extracted: 05/23/2003 Extracted: 05/23/2003 Analyzed: 05/23/2003 09:17

Analyzed: 05/23/2003 09:39

Compound	Conc.	ug/L	Exp.Conc.	Recovery		RPD	Ctrl.Limits %		Flags	
Compound	LCS	LCSD		LCS	LCSD	%	Rec.	RPD	LCS	LCSD
Benzene Toluene Methyl tert-butyl ether (MTBE)	25.5 25.0 26.3	23.4 23.8 24.4	25.0 25.0 25.0	102.0 100.0 105.2	93.6 95.2 97.6	8.6 4.9 7.5	69-129 70-130 65-165	20 20 20		<u> </u>
Surrogates(s) 1,2-Dichloroethane-d4 Toluene-d8	515 511	481 508	500 500	103.0 102.2	96.2 101.6		76-114 88-110	0		



Gas/BTEXFuel Oxygenates by 8260B

PES

Attn.: Will Mast

1682 Novato Blvd., Suite 100 Novato, CA 94947-7021

Phone: (415) 899-1600 Fax: (415) 899-1601

Project: 618.001.02.005

Pacific Electric Motor

Received: 05/16/2003 18:22

Site: 1099 66th Ave., Oakland, CA

Batch QC Report

Prep(s): 5030B Test(s): 8260FAB

Matrix Spike (MS/MSD)

Water

QC Batch # 2003/05/22-2c.65

MW-1 >> MS

Lab ID: 2003-05-0358 - 001

MS: 2003/05/22-2c.65-053 Extracted: 05/22/2003

Analyzed:

05/22/2003 22:49

Dilution:

1.00

MSD:

2003/05/22-2c.65-054

Extracted: 05/22/2003

Analyzed:

05/22/2003 23:12

Dilution:

1.00

Compound	Conc.	ug/L		Spk.Level	Recovery			Limit	s %	Flags		
	MS	MSD	Sample	ug/L	MS	MSD	RPD	Rec.	RPD	MS	MSD	
Benzene	26.6	25.8	ND	25	106.4	103.2	3.1	69-129	20			
Toluene	25.4	24.8	ND	25	101.6	99.2	2.4	70-130	20		ŀ	
Methyl tert-butyl ether	36.1	35.7	ND	25	144.4	142.8	1.1	65-165	20			
Surrogate(s)												
1,2-Dichloroethane-d4	522	515		500	104.3	103.0		76-114				
Toluene-d8	499	487		500	99.7	97.5	Ī	88-110				

DIA				1680 ROG				CON	IDUCT	ANALYSIS	TO DE	TECT	LAB	STL San Fra	ancisco 74	328 ohs#
BLA! TECH SER			I JUSE,		A 95112-11 408) 573-77 408) 573-05	71		EDC (8260)					ALL ANALYSES MUST LIMITS SET BY CALIF	MEET SPECIF ORNIA DHS AN	ICATIONS AN	DETECTION
CHAIN OF CUS	STODY	BTS#	P3 3	-516-B	Δ1] _		ED8, EI					LIA OTHER			
CLIENT	PES		<u> </u>	<u> </u>	* 47)	CONTAINERS	:	TBA,					SPECIAL INSTRUCTION		-	7508
SITE	Pacific I	Electric :	Motor			ONTA		DIPE,					Invoice and Repo	ort to + DEC		
	1099 66	th Aven	ue			¥ [(8260)	ETBE					Attn: Will Mast	nt to . TES		
	Oakland,							TAME,					Job # 618.001.02	.005		
			MATRIX MATRIX MOS =S		AINERS	= COMPOSITE	TPH - Gas	BTEX MTBE,							i I	
SAMPLE I.D.	DATE	TIME		TOTAL		O	X		-		-		ADD'L INFORMATION	STATUS	CONDITION	LAB SAMPLE #
\ Mw-1	5/16	1130	3	٥		-	X	×			 			· · · · · · · · · · · · · · · · · · ·		
		2950 5950			· -·	 	X	×				 				
ww-4	-	7030					×	×							<u> </u>	2.00
Ew-1	5	1200	5	5			Х	乂								<u> </u>
						_					<u> </u>	<u> </u>				
				<u> </u>			<u> </u>				_					
	_						_		-		<u> </u>					
SAMPLING COMPLETED	DATE		SAMPLI PERFOR		Break	s A	ا نده د	دد		<u> </u>	1	<u> </u>	RESULTS NEEDED NO LATER THAN	As Contracte	ed with PES	
RELEASED BY	~/	L				DAT			TIME		•	IVED BY	No		DATE \$ //6/	TIME (13) 16/0
		1914	orly			<i>5/</i>	16/0	7	TIME 18	221	KEUL	IVED BY			DATE /	/ TIME
RELEASED BY						DAT			TIME	l		IVED BY	una K.		DATE / 16/02	TIME 1822
SHIPPED VIA						IDAT	E SEN	T	TIME	SENT	COOL	ER#			<u> </u>	
<u> </u>						<u> </u>	·			<u> </u>	1		ا	<u></u>		



STL San Francisco

Sample Receipt Checklist

Submission #:2003- 05	<u>- 0508</u>	,	
Checklist completed by: (initials)	SU Date: 05,19,03		
Courier name: DSTL San Francisc			
Custody seals intact on shipping cor	tainer/sampies	YesN	Not Volume Not
Chain of custody present?			YesNo
Chain of custody signed when reling	uished and received?		YesNo
Chain of custody agrees with sample	labels?		Yes No
Samples in proper container/bottle?			YesNo
Sample containers intact?			Yes No
Sufficient sample volume for indicate	ed test?		Yes No
All samples received within holding t	ime?		Yes No
Container/Temp Blank temperature i	n compliance (4º C ± 2)?	Temp2_O°C	YesNo
Water - VOA vials have zero headsp	ace?	No VOA vials submitted	_Yes No
For any item check-listed "No", p Comments:	rovided detail of discrepancy in co	mment section below:	
Project Management [Ro	uting for instruction of ind	icated discrepancy(ies)]	
Project Manager: (initials)	Date://03		•
Client contacted: ☐ Yes ☐ No			
Summary of discussion:			
Corrective Action (per PM/Client):			

DISTRIBUTION

SECOND QUARTER 2003 GROUNDWATER MONITORING REPORT PACIFIC ELECTRIC MOTOR COMPANY 1009 66TH AVENUE OAKLAND, CALIFORNIA

JULY 31, 2003

COPY NO.

		Copy No.
1 Сору	Pacific Electric Motor Company 137 Fiesta Circle Orinda, California 94563	1
	Attention: Mr. Steve Boyd	
2 Copies	Pacific Electric Motor Company 129 Natalie Drive Moraga, California 94556-2422	2 - 3
	Attention: Mr. Rand Perry	
2 Copies	Alameda County Health Care Service Agency Department of Environmental Health 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502-6577	4 - 5
	Attention: Mr. Barney Chan	
3 Copies	PES Job File	6 - 8
1 Copy	Unbound Original	9