

Ultramar

Ultramar, Inc.
P.O. Box 466
525 W. Third Street
Hanford, CA 93232-0466
(209) 582-0241

Telecopy: 209-585-5685 Credit
209-583-3330 Administrative
209-583-3302 Information Services
209-583-3358 Accounting

September 7, 1999

Ms. Eva Chu
Hazardous Materials Program
Department of Environmental Health
Alameda County Health Care Services
1131 Harbor Bay Parkway, 2nd Floor
Alameda, CA 94502

SUBJECT: BEACON STATION NO. 721, 44 LEWELLING BLVD., SAN LORENZO, CALIFORNIA

Dear Ms. Leach:

Enclosed is a copy of the ***Quarterly Ground Water Monitoring and Remediation System Status Report, Second Quarter 1999*** for the above-referenced Ultramar facility. Also included is a copy of the Quarterly Status Report.

Please call me at (559) 583-3345 if you have any questions regarding this project.

Sincerely,


ULTRAMAR INC.

Terrence A. Fox
Terrence A. Fox
Senior Project Manager
Marketing Environmental Department

Enclosures

cc w/encl: Mr. Steve Morse, San Francisco Bay Region, RWQCB

99 SEP 10 PM:09
ENVIRONMENTAL
PROTECTION AGENCY



A Member of the Ultramar Group of Companies

BEACON
#1 Quality and Service

Ultramar

Ultramar, Inc.
P.O. Box 466
525 W. Third Street
Hanford, CA 93232-0466
(209) 582-0241

Telecopy: 209-585-5685 Credit
209-583-3330 Administrative
209-583-3302 Information Services
209-583-3358 Accounting

ENVIRONMENTAL PROJECT QUARTERLY STATUS REPORT

DATE REPORT SUBMITTED: September 7, 1999
QUARTER ENDING: June 30, 1999

SERVICE STATION NO.: 721
ADDRESS: 44 Lewelling Blvd., San Lorenzo, CA
COUNTY: Alameda

ULTRAMAR CONTACT: Terrence A. Fox **TEL. NO:** 559-583-3345

BACKGROUND:

In April 1987, three underground gasoline storage tanks were excavated and removed. Samples collected from beneath the former tanks indicated that hydrocarbons were present in the soil. In May 1987, three monitoring wells (MW-1 through MW-3) were installed by Conoco. Hydrocarbons were detected in soil and ground-water samples collected from the wells. In December 1988, four additional wells (MW-4 through MW-7) were installed. Dissolved-phase hydrocarbons were detected in the new wells. In September 1989, two additional wells (MW-8 and MW-9) were installed. The site has been on a monitoring program since May 1987.

In July 1990, the site was purchased by Ultramar Inc. from Conoco. The monitoring program has continued. Submitted work plan for additional assessment on March 14, 1991.

In October 1991, drilled two additional offsite wells (MW-10 and MW-11) southwest of the site and one onsite recovery well (RW-1). In November 1991, performed ground-water pump test and vapor extraction test.

In April 1992, Ultramar submitted an Interim Remediation Plan. The plan was approved in June 1992.

In March 1993, installed the subsurface piping for the remediation system. Completed installation of ground-water remediation system in April 1993. Began operation in June 1993.

In April 1993, the ground-water extraction system began operation. In March 1994, the vapor extraction system began operation.



A Member of the Ultramar Group of Companies

BEACON
#1 Quality and Service

Obtained the Permit to Operate for the vapor extraction system on June 8, 1994.

In December 1995, installed an air sparging system.

In January 1997, discontinued to operate the remediation system. Approximately 1,184,392 gallons of ground water have been removed, treated, and discharged. Approximately 103 gallons of hydrocarbons have been removed the vapor extraction system.

In October 1997, drilled confirmation borings. Results indicate soil clean.

In June 1998, the air sparging system was restarted.

SUMMARY OF THIS QUARTER'S ACTIVITIES:

Performed quarterly monitoring on June 24, 1999. Continued to operate the air sparging system.

RESULT OF QUARTERLY MONITORING:

Monitoring data indicates that benzene concentrations were detected in MW-1, MW-3, MW-10, and MW-11.

PROPOSED ACTIVITY OR WORK FOR NEXT QUARTER:

<u>ACTIVITY</u>	<u>ESTIMATED COMPLETION DATE</u>
Continue quarterly ground-water monitoring.	Ongoing
Continue to operate the air sparging system.	
Restart groundwater system.	July 28, 1999



3164 Gold Camp Drive
Suite 200
Rancho Cordova, CA 95670-6021
U.S.A.
916/638-2085
FAX: 916/638-8385

September 1, 1999

Mr. Terrence A. Fox
Ultramar Inc.
525 West Third Street
Hanford, California 93230

- When testing in/ off at 6Wextr.sys.
Also quantify for MTBC.
- decrease sampling frequency : done
in Jan 1999 letter.

Subject: *Quarterly Ground Water Monitoring and Remediation System Status Report*
Second Quarter 1999
Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California
Delta Project No. D093-936

Dear Mr. Fox:

Delta Environmental Consultants, Inc. (Delta) has been authorized by Ultramar Inc. to conduct quarterly ground water monitoring and remedial actions at the subject site. The monitoring is intended to evaluate the distribution of dissolved petroleum hydrocarbon constituents in ground water in the vicinity of the site. The remedial activities are intended to decrease the petroleum hydrocarbon constituents in soil and ground water beneath the site. This report summarizes the results of ground water monitoring activities performed at the site on June 24, 1999. The site location is shown in Figure 1 and site features are illustrated in Figure 2.

Ground water monitoring included measurement of depth to ground water, subjective analyses of water samples to evaluate the presence or absence of free petroleum product or product sheen, and collection of ground water samples for chemical analysis. Methods used to perform these tasks are described in Enclosure A.

Ground Water Table Measurements and Flow Direction

On June 24, 1999, depth to ground water was measured in monitoring wells MW-1 through MW-11, and recovery well RW-1 at depths ranging from 13.35 (MW-7) to 17.50 (MW-11) feet below the top of the well casings. Ground water elevations have decreased an average of 1.06 feet since the previous quarterly event in February 1999. Cumulative ground water elevation measurements at the site are compiled in Table 1. Based on the ground water elevation measurements, the inferred ground water flow direction is generally toward the southwest with a gradient of less than 0.01. A ground water elevation contour map prepared from the current event data is included as Figure 3. Water levels in monitoring wells MW-1, MW-2 and recovery well RW-1 appear to be influenced by air sparging in wells AS-1 through AS-3.

Mr. Terrence A. Fox
Ultramar Inc.
September 1, 1999
Page 2

Ground Water Analytical Results

On June 24, 1999, ground water samples were collected from monitoring wells MW-1 through MW-4, MW-10, MW-11 and recovery well RW-1. The ground water samples were submitted to Kiff Analytical of Davis, California (a California-certified laboratory). The ground water samples were submitted for analysis of benzene, toluene, ethylbenzene, and total xylenes (BTEX), and methyl tertiary butyl ether (MTBE) by EPA Method 8020, and total petroleum hydrocarbons (TPH) as gasoline by EPA Method 8015 Modified. Copies of the sampling information data sheets are included in Enclosure B.

Benzene was not detected at or above the laboratory's reporting limits in ground water samples collected from MW-2, MW-4 and RW-1. Benzene was reported in the samples collected from wells MW-1, MW-3, MW-10 and MW-11 at concentrations ranging from 4.6 micrograms per liter ($\mu\text{g/L}$) in MW-11 to 27 $\mu\text{g/L}$ in both MW-3 and MW-10. The samples collected from MW-1 through MW-4, MW-10, MW-11 and RW-1 were reported to contain concentrations of MTBE ranging from 42 $\mu\text{g/L}$ in RW-1 to 39,000 $\mu\text{g/L}$ in MW-2. Utilizing the June 24, 1999 ground water analytical data, a benzene isoconcentration map was constructed and is included as Figure 4. Cumulative ground water analytical results for TPH as gasoline, BTEX, and MTBE are summarized in Table 1. A copy of the certified laboratory analytical report with chain-of-custody documentation is provided in Enclosure C.

Remediation System Status

The ground water treatment system consists of a submersible pump which pumps water from recovery well RW-1 into a 1,000-gallon influent tank that gravity feeds into a diffused aeration tank (DAT) where hydrocarbons are stripped off the groundwater. Two 200-pound vapor phase granular activated carbon (GAC) columns abate the vapors. The ground water is then pumped through two 200-pound aqueous phase GAC columns and into a 50 gallon LEL tank prior to discharge to the sewer. The ground water treatment system was restarted on June 24, 1999 for a period of three hours. After laboratory analytical results confirmed that the system was in compliance with permit conditions mandated by the Oro Loma Sanitary District (Permit No. 018), the system was restarted again on July 28, 1999. As of July 30, 1999, the ground water treatment system has processed a total of 1,189,342 gallons of ground water to the sewer. The system had processed a total of 4,910 gallons of ground water since the system was restarted on June 24, 1999. Cumulative totals for ground water treated and discharged to the sewer are summarized in Table 2. Cumulative analytical results for the ground water treatment system are summarized in Table 3. Copies of analytical results for the ground water treatment system are included in Enclosure D.

*Is System effective in removing
MTBE?*

The air sparging system injects air into the ground water through air sparging wells AS-1 through AS-3. Locations of the air sparging wells are illustrated on Figure 2. The purpose of the air sparging system is to increase the dissolved oxygen content in the ground water, which enhances the rate of biodegradation in the ground water. The SVE system is not currently operating, but is expected to be restarted sometime during the third quarter 1999.

Mr. Terrence A. Fox
Ultramar Inc.
September 1, 1999
Page 3

Remarks/Signatures

The interpretations contained in this report represent our professional opinions, and are based in part, on information supplied by the client. These opinions are based on currently available information and are arrived at in accordance with currently accepted hydrogeologic and engineering practices at this time and location. Other than this, no warranty is implied or intended.

It is recommended that a copy of this report be forwarded to:

Mr. Steven Ritchie
California Regional Water Quality Control Board
San Francisco Bay Region
1515 Clay Street, Suite 1400
Oakland, California 94612


Ms. Eva Chu
Alameda County
Environmental Health Department
470 27th Street, Room 322
Oakland, California 94612

If you have any questions, please contact Richard Munsch at (916) 638-2164.

Sincerely,

DELTA ENVIRONMENTAL CONSULTANTS, INC.


Trevor L. Atkinson
Project Engineer


Richard D. Munsch
Project Manager


Steven W. Meeks, P.E.
California Registered Civil Engineer No. C057461

TLA (LRP017.936)
Enclosures



TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser	Depth to Water	Ground Water		Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Comments
		Elevation (ft)	(ft)	Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW-1	02/18/92	43.67	16.42	27.25	NS	NS	NS	NS	NS	
	05/14/92		17.28	26.39	NS	NS	NS	NS	NS	
	05/15/92		NM	NC	2,000	47	1,200	400	41,000	NA
	08/27/92		19.48	24.19	NS	NS	NS	NS	NS	
	08/28/92		NM	NC	3,800	54	850	970	110,000	NA
	11/19/92		20.57	23.10	200	<5.0	90	140	3,600	NA
	02/03/93		15.91	27.76	180	22	79	130	3,000	NA
	06/23/93		16.21	27.46	2,400	74	650	510	12,000	NA
	09/22/93		17.85	25.82	3,000	290	1,100	1,200	23,000	NA
	01/24/94		17.91	25.76	2,400	280	1,100	1,700	18,000	NA
	04/07/94		16.94	26.73	4,200	820	1,600	2,100	20,000	NA
	06/07/94		17.20	26.47	1,800	510	1,100	1,600	26,000	NA
	09/28/94		18.73	24.94	1,700	210	970	870	18,000	NA
	12/14/94		17.56	26.11	4,400	2,400	2,300	4,300	31,000	NA
	03/15/95		14.92	28.75	830	310	840	1,200	17,000	NA
	06/13/95		15.38	28.29	1,300	99	1,500	1,100	22,000	NA
	09/28/95		16.75	26.92	580	<25	780	410	8,800	NA
	12/28/95		17.28	26.39	4.9	<1.3	<1.3	290	4,800	74
	01/30/96		NM	NC	17	7.1	20	45	1,500	63
	03/12/96		14.13	29.54	<0.5	<0.5	<0.5	<0.5	110	44
	06/11/96		14.90	28.77	48	0.9	37	26	600	75
	10/02/96		16.31	27.36	16	<0.5	6	0.92	210	11
	01/28/97		12.99	30.68	<0.5	<0.5	<0.5	<0.5	150	160
	05/20/97		15.28	28.39	<2.5	<2.5	<2.5	<2.5	680	640
	08/18/97		16.74	26.93	<2.5	<2.5	<2.5	<2.5	<250	540
	09/29/97		NM	NC	NS	NS	NS	NS	NS	Not measured
	11/05/97		17.45	26.22	2.8	<2.5	<2.5	<2.5	<250	400/390 ^b
	03/31/98		12.47	31.20	260	13	110	150	3,300	7,900
	05/26/98		13.69	29.98	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	120	<10	39	55	7,800	9,300
	08/19/98		14.58	29.09	12	<2.5	6.0 ^c	3.8 ^c	<250 ^c	2,200
	11/17/98		15.39	28.28	8.3	<2.5	9.2	7.6	860	4,200
	02/18/99		13.52	30.15	2.7	<2.5	<2.5	3.9	310	4,200
	06/24/99		15.02	28.65	10	<2.5	12	6.5	860	3,400
										No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation	Depth to Water	Ground Water Elevation		Benzene	Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Comments
		(ft)	(ft)	(ft)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW-2	02/18/92	43.09	16.65	26.44	<0.5	<0.5	1.9	<0.5	1,600	NA	
	05/14/92		16.64	26.45	1.2	1	1.3	<0.5	740	NA	
	08/27/92		16.61	26.28	6.5	1.1	0.6	<0.5	1,400	NA	
	11/19/92		19.91	23.18	<0.5	<0.5	2.7	<0.5	360	NA	
	02/03/93		15.23	27.86	1.2	1.6	4.5	6.4	590	NA	
	06/23/93		15.55	27.54	<0.5	<0.5	0.52	0.5	160	NA	No free product or sheen
	09/22/93		17.22	25.87	<0.5	0.59	1.2	0.59	290	NA	No free product or sheen
	01/24/94		17.20	25.89	<0.5	<0.5	0.68	<0.5	330	NA	
	04/07/94		16.26	26.83	<0.5	<0.5	<0.5	4.4	490	NA	No free product or sheen
	06/07/94		16.46	26.63	<0.5	<0.5	1.5	<0.5	550	NA	No free product or sheen
	09/28/94		18.06	25.03	<0.5	<0.5	<0.5	<0.5	190	NA	No free product or sheen
	12/14/94		16.86	26.23	7.2	0.84	<0.5	<0.5	1,400	NA	No free product or sheen
	03/15/95		14.08	29.01	39	<0.5	0.53	<0.5	730	NA	No free product or sheen
	06/13/95		14.67	28.42	8.3	<0.5	<0.5	<0.5	750 ^a	NA	No free product or sheen
	09/28/95		16.07	27.02	<0.5	<0.5	<0.5	<0.5	670 ^a	NA	No free product or sheen
	12/28/95		16.46	26.63	9.5	<5.0	<5.0	5.2	3,100	4,600	No free product or sheen
	03/12/96		13.11	29.98	<1.3	<1.3	<1.3	<1.3	710	3,200	No free product or sheen
	06/11/96		14.14	28.95	1.6	<1.3	<1.3	<1.3	1,900 ^a	5,100	No free product or sheen
	10/02/96		15.71	27.38	<2.5	<2.5	<2.5	<2.5	2,800	7,900	No free product or sheen
	01/28/97		12.05	31.04	<0.5	<0.5	<0.5	<0.5	130	210	No free product or sheen
	05/20/97		14.65	28.44	120	16	<2.5	4.0	1,400	390	No free product or sheen
	08/18/97		16.00	27.09	<2.5	<2.5	<2.5	<2.5	<250	2,000	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		16.75	26.34	<2.5	<2.5	<2.5	<2.5	<250	2,900/2,900 ^b	No free product or sheen
	03/31/98		11.54	31.55	<0.5	<0.5	<0.5	<0.5	<10,000	85,000	No free product or sheen
	05/26/98		12.78	30.31	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	<500	<500	<500	<500	<50,000	97,000	No free product or sheen
	08/19/98		14.40	28.69	<0.5	<0.5	<0.5	<0.5	210	22,000	No free product or sheen
	11/17/98		15.18	27.91	<0.5	<0.5	<0.5	<0.5	<50	17,000	No free product or sheen
	02/18/99		14.07	29.02	<0.5	<0.5	<0.5	<0.5	<50	13,000	No free product or sheen
	06/24/99		14.70	28.39	<15	<0.5	<0.5	<0.5	180	39,000	No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser	Depth to Water	Ground Water		Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Comments
		Elevation (ft)	(ft)	Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW-3	02/18/92	43.10	16.89	26.21	NS	NS	NS	NS	NS	NS
	05/14/92		16.60	26.50	NS	NS	NS	NS	NS	NS
	05/15/92		NM	NC	6,300	5,900	1,700	6,100	160,000	NA
	08/27/92		18.96	24.14	NS	NS	NS	NS	NS	NS
	08/28/92		NM	NC	2,500	40,000	6,700	44,000	1,300,000	NA
	11/18/92		20.38	23.01	NS	NS	NS	NS	NS	NS
	11/19/92		NM	NC	NS	NS	NS	NS	NS	NS
	02/03/93		15.43	27.67	7,200	11,000	2,900	13,000	82,000	NA
	06/23/93		15.67	27.43	3,200	5,300	2,500	9,100	61,000	NA
	09/22/93		17.20	25.90	12,000	14,000	3,900	18,000	94,000	NA
	01/24/94		17.35	25.75	14,000	17,000	4,200	14,000	110,000	NA
	04/07/94		14.48	28.62	6,500	1,800	1,700	4,100	28,000	NA
	06/07/94		13.37	29.73	6,400	2,300	1,500	3,500	27,000	NA
	09/28/94		18.05	25.05	7,400	4,300	1,500	4,600	40,000	NA
	12/14/94		16.92	26.18	17,000	21,000	3,900	22,000	140,000	NA
	03/15/95		14.22	28.88	4,900	1,900	1,800	7,100	58,000	NA
	06/13/95		14.49	28.61	7,200	2,900	1,200	4,600	44,000	NA
	09/28/95		15.17	27.93	5,600	2,100	1,900	6,900	30,000	NA
	12/28/95		15.45	27.65	32	5.8	18	4,700	16,000	360
	01/30/96		NM	NC	850	800	190	1,700	8,700	430
	03/12/96		11.35	31.75	48	64	5.3	630	2,400	97
	06/11/96		Dry	Dry	NS	NS	NS	NS	NS	Dry
	10/02/96		Dry	Dry	NS	NS	NS	NS	NS	Dry
	01/28/97		Dry	Dry	NS	NS	NS	NS	NS	Dry
	05/20/97		Dry	Dry	NS	NS	NS	NS	NS	Plugged at 14 feet
	07/10/97		NM	NC	<0.50	<0.50	<0.50	4.8	300	40
	08/18/97		16.05	27.05	480	8.4	100	230	3,600	170
	09/29/97		NM	NC	740	8.6	160	240	3500	210
	11/05/97		16.78	26.32	870	15	180	210	4,100	240/210 ^b
	03/31/98		11.55	31.55	1,800	600	410	1,400	12,000	510
										No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser	Depth to Water	Ground Water		Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Comments
		Elevation (ft)	(ft)	Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW-3 (Cont.)	05/26/98	43.10	12.80	30.30	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	1,500	400	280	870	6,500	480
	08/19/98		14.27	28.83	130	11	24	60	1,400	140
	11/17/98		15.11	27.99	48	3.5	9.9	14	510	120
	02/18/99		13.30	29.80	67	28	24	81	690	88
	06/24/99		14.44	28.66	27	21	8.6	32	540	61

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-4	02/18/92	44.66	18.51	26.15	<0.5	<0.5	12	21	5,100	NA	
	05/14/92		18.22	26.44	<0.5	5.6	1.8	2.2	4,600	NA	
	08/27/92		20.47	24.19	NS	NS	NS	NS	NS	NS	
	08/28/92		NM	NC	6.6	1.3	1.6	3.1	1,700	NA	
	11/19/92		21.58	23.08	<0.5	<0.5	<0.5	<0.5	400	NA	
	02/03/93		16.98	27.68	<0.5	<0.5	<0.5	<0.5	1,100	NA	
	06/23/93		17.23	27.43	<0.5	<0.5	<0.5	<0.5	120	NA	
	09/22/93		18.83	25.83	<0.5	<0.5	<0.5	<0.5	110	NA	No free product or sheen
	01/24/94		18.86	25.80	<0.5	<0.5	<0.5	<0.5	260	NA	No free product or sheen
	04/07/94		17.90	26.76	<0.5	<0.5	<0.5	<0.5	430	NA	No free product or sheen
	06/07/94		18.08	26.58	<0.5	<0.5	<0.5	<0.5	150	NA	No free product or sheen
	09/28/94		19.70	24.96	<0.5	<0.5	<0.5	<0.5	75	NA	No free product or sheen
	12/14/94		18.55	26.11	<0.5	<0.5	<0.5	<0.5	160	NA	No free product or sheen
	03/15/95		16.14	28.52	<0.5	<0.5	<0.5	<0.5	500	NA	No free product or sheen
	06/13/95		16.41	28.25	<0.5	<0.5	<0.5	<0.5	210 ^a	NA	No free product or sheen
	09/28/95		17.88	26.78	<0.5	<0.5	<0.5	<0.5	140 ^a	NA	No free product or sheen
	12/28/95		17.81	26.85	<0.5	<0.5	<0.5	<0.5	510 ^a	<5.0	No free product or sheen
	03/12/96		14.77	29.89	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	06/11/96		15.88	28.78	<0.5	<0.5	<0.5	<0.5	50 ^a	<5.0	No free product or sheen
	10/02/96		17.40	27.26	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	01/28/97		14.11	30.55	<0.5	<0.5	<0.5	<0.5	270 ^a	<5.0	No free product or sheen
	05/20/97		16.24	28.42	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/18/97		17.59	27.07	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		18.24	26.42	<0.5	<0.5	<0.5	<0.5	<50	<5.0/<0.5 ^b	No free product or sheen
	03/31/98		13.61	31.05	<0.5	<0.5	<0.5	<0.5	110	<5.0	No free product or sheen
	05/26/98		14.78	29.88	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	<0.5	<0.5	<0.5	<0.5	94	<5.0	No free product or sheen
	08/19/98		16.15	28.51	<0.5 ^c	<0.5 ^c	<0.5 ^c	<0.5 ^c	120 ^c	46 ^c	No free product or sheen
	11/17/98		16.93	27.73	1.3	<0.5	<0.5	<0.5	<50	780	No free product or sheen
	02/18/99		15.30	29.36	8.2	<0.5	<0.5	<0.5	130	240	No free product or sheen
	06/24/99		16.35	28.31	<1.0	<0.5	<0.5	<0.5	<50	2,100	No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-5	02/18/92	43.79	17.37	26.42	<0.5	<0.5	<0.5	<0.5	<50	NA	
	05/14/92		17.29	26.50	<0.5	<0.05	<0.5	<0.5	<50	NA	
	08/27/92		22.18	21.61	<0.5	<0.5	<0.5	<0.5	<50	NA	
	11/19/92		20.68	23.11	<0.5	<0.5	<0.5	<0.5	<50	NA	
	02/03/93		15.91	27.88	3.0	2.7	8.0	9.9	55	NA	
	06/23/93		16.24	27.55	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	09/22/93		17.93	25.86	0.66	1.1	<0.5	0.6	<50	NA	No free product or sheen
	01/24/94		17.82	25.97	<0.5	<0.5	<0.5	<0.5	<50	NA	
	04/07/94		16.91	26.88	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	06/07/94		17.10	26.69	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	09/28/94		18.73	25.06	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	12/14/94		17.53	26.26	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	03/15/95		14.96	28.83	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	06/13/95		15.30	28.49	<0.5	0.52	<0.5	<0.5	<50	NA	No free product or sheen
	09/28/95		16.74	27.05	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	12/28/95		15.10	28.69	<0.5	<0.5	<0.5	<0.5	120	<5.0	No free product or sheen
	03/12/96		13.67	30.12	<0.5	<0.5	<0.5	<0.5	<50	9	No free product or sheen
	06/11/96		14.88	28.91	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	10/02/96		16.42	27.37	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	01/28/97		12.83	30.96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	05/20/97		15.33	28.46	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/18/97		16.69	27.10	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		17.37	26.42	<0.5	<0.5	<0.5	<0.5	<50	<5.0/<0.5 ^b	No free product or sheen
	03/31/98		12.40	31.39	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	05/26/98		13.62	30.17	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/19/98		15.19	28.60	<0.5	<0.5	<0.5	<0.5	<50	7	No free product or sheen
	11/17/98		15.89	27.90	<0.5	<0.5	<0.5	<0.5	<50	6	No free product or sheen
	02/18/99		14.23	29.56	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	06/24/99		15.29	28.50	NS	NS	NS	NS	NS	NS	Not sampled

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-6	02/18/92	42.47	15.87	26.60	4.8	<0.5	<0.5	<0.5	370	NA	
	05/14/92		16.04	26.43	<0.5	<0.5	<0.5	<0.5	120	NA	
	08/27/92		18.17	24.30	1.2	<0.5	<0.5	<0.5	<50	NA	
	11/19/92		19.30	23.17	1.3	<0.5	1	1.1	66	NA	
	02/03/93		14.60	27.87	1.9	2.6	23	12	100	NA	
	06/23/93		15.00	27.47	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	09/22/93		16.66	25.81	2.2	3.8	0.53	2.7	81	NA	No free product or sheen
	01/24/94		16.52	25.95	<0.5	<0.5	<0.5	<0.5	98	NA	
	04/07/94		15.70	26.77	0.71	<0.5	<0.5	<0.5	150	NA	No free product or sheen
	06/07/94		15.88	26.59	<0.5	<0.5	<0.5	<0.5	180	NA	No free product or sheen
	09/28/94		17.51	24.96	<0.5	<0.5	<0.5	<0.5	100	NA	No free product or sheen
	12/14/94		16.27	26.20	<0.5	<0.5	<0.5	<0.5	140	NA	No free product or sheen
	03/15/95		13.52	28.95	<0.5	<0.5	<0.5	<0.5	110	NA	No free product or sheen
	06/13/95		13.96	28.51	<0.5	0.87	<0.5	<0.5	150 ^a	NA	No free product or sheen
	09/28/95		15.61	26.86	0.78	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	12/28/95		15.54	26.93	<0.5	<0.5	<0.5	6.3	410	70	No free product or sheen
	01/30/96		NM	NC	1.0	<0.5	<0.5	11	81	46	Not measured
	03/12/96		11.88	30.59	<0.5	<0.5	<0.5	<0.5	<50	7	No free product or sheen
	06/11/96		13.52	28.95	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	10/02/96		15.10	27.37	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	01/28/97		11.18	31.29	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	05/20/97		14.00	28.47	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/18/97		15.54	26.93	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		16.25	26.22	<0.5	<0.5	<0.5	<0.5	<50	<5.0/2.8 ^b	No free product or sheen
	03/31/98		10.60	31.87	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	05/26/98		12.01	30.46	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/19/98		13.60	28.87	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	11/17/98		14.53	27.94	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	02/18/99		12.39	30.08	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	06/24/99		13.89	28.58	NS	NS	NS	NS	NS	NS	Not sampled

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-7	02/18/92	41.54	15.51	26.03	16	<0.5	10	16	670	NA	
	05/14/92		15.41	26.13	44	<0.5	38	88	1,500	NA	
	08/27/92		17.45	24.09	400	5.8	290	1,400	23,000	NA	
	11/19/92		18.54	23.00	29	<0.5	10	53	330	NA	
	02/03/93		14.10	27.44	200	<0.5	110	480	2,000	NA	
	06/23/93		14.33	27.21	20	<0.5	16	16	280	NA	No free product or sheen
	09/22/93		15.92	25.62	71	2.2	33	210	860	NA	No free product or sheen
	01/24/94		16.07	25.47	61	<1.3	10	160	900	NA	
	04/07/94		15.10	26.44	53	<0.5	7.1	49	630	NA	
	06/07/94		15.16	26.38	55	<0.5	14	24	730	NA	No free product or sheen
	09/28/94		16.82	24.72	21	<0.5	2.3	3.1	300	NA	No free product or sheen
	12/14/94		15.75	25.79	19	<0.5	3.3	32	430	NA	No free product or sheen
	03/15/95		14.00	27.54	0.88	<0.5	<0.5	<0.5	70	NA	No free product or sheen
	06/13/95		13.44	28.10	7.3	0.79	7.6	8.9	190	NA	No free product or sheen
	09/28/95		14.84	26.70	1.5	<0.5	1.2	0.84	60	NA	No free product or sheen
	12/28/95		14.55	26.99	<0.5	<0.5	0.91	0.69	60	10	No free product or sheen
	03/12/96		11.88	29.66	<0.5	<0.5	<0.5	<0.5	<50	11	No free product or sheen
	06/11/96		13.52	28.58	<0.5	<0.5	<0.5	<0.5	79	16	No free product or sheen
	10/02/96		14.50	27.04	<0.5	<0.5	<0.5	<0.5	<50	26	No free product or sheen
	01/28/97		11.08	30.46	<0.5	<0.5	<0.5	<0.5	<50	13	No free product or sheen
	05/20/97		13.46	28.08	<0.5	0.85	<0.5	<0.5	78	40	No free product or sheen
	08/18/97		14.95	26.59	<0.5	<0.5	<0.5	<0.5	<50	18	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		15.43	26.11	<0.5	<0.5	<0.5	<0.5	<50	8.9/8.0 ^b	No free product or sheen
	03/31/98		10.25	31.29	<0.5	<0.5	<0.5	1.3	<5.0	6	No free product or sheen
	05/26/98		11.45	30.09	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	<0.5	<0.5	<0.5	<0.5	<50	10	No free product or sheen
	08/19/98		13.08	28.46	<0.5	<0.5	<0.5	<0.5	<50	27	No free product or sheen
	11/17/98		13.93	27.61	<0.5	<0.5	<0.5	<0.5	<50	30	No free product or sheen
	02/18/99		12.16	29.38	<0.5	<0.5	<0.5	<0.5	51	22	
	06/24/99		13.35	28.19	NS	NS	NS	NS	NS	NS	Not sampled

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-8	02/18/92	42.26	16.57	25.69	<0.5	<0.5	9.5	<0.5	1,200	NA	
	05/14/92		16.24	26.02	<0.5	<0.5	<0.5	<0.5	130	NA	
	08/27/92		18.28	23.98	<0.5	<0.5	<0.5	<0.5	140	NA	
	11/19/92		19.32	22.94	<0.5	<0.5	2.0	<0.5	320	NA	
	02/03/93		14.87	27.39	<0.5	<0.5	<0.5	<0.5	<50	NA	
	06/23/93		15.18	27.08	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	09/22/93		18.79	23.47	<0.5	0.67	<0.5	<0.5	<50	NA	No free product or sheen
	01/24/94		17.06	25.20	<0.5	<0.5	<0.5	<0.5	290	NA	
	04/07/94		15.95	26.31	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	06/07/94		15.10	27.16	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	09/28/94		17.63	24.63	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	12/14/94		16.66	25.60	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	03/15/95		14.30	27.96	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	06/13/95		14.37	27.89	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	09/28/95		15.62	26.64	NS	NS	NS	NS	NS	NA	No free product or sheen
	12/28/95		15.62	26.64	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	03/12/96		12.75	29.51	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	06/11/96		13.94	28.32	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	10/02/96		15.41	26.85	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	01/28/97		12.30	29.96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	05/20/97		14.42	27.84	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/18/97		16.16	26.10	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		16.25	26.01	<0.5	<0.5	<0.5	<0.5	<50	<5.0/<0.5 ^b	No free product or sheen
	03/31/98		11.49	30.77	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	05/26/98		12.60	29.66	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	08/19/98		14.15	28.11	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free Product or sheen
	11/17/98		14.98	27.28	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	02/18/99		13.41	28.85	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	06/24/99		14.35	27.91	NS	NS	NS	NS	NS	NS	Not sampled

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser	Depth to Water	Ground Water		Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Comments
		Elevation (ft)	(ft)	Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW-9	02/18/92	44.94	18.87	26.07	<0.5	<0.5	<0.5	<0.5	<50	NA
	05/14/92		18.55	26.39	<0.5	<0.5	<0.5	<0.5	<50	NA
	08/27/92		20.80	24.14	<0.5	<0.5	<0.5	<0.5	<50	NA
	11/19/92		21.90	23.04	<0.5	<0.5	<0.5	1.3	<50	NA
	02/03/93		17.25	27.69	<0.5	<0.5	<0.5	<0.5	<50	NA
	06/23/93		17.61	27.33	<0.5	<0.5	<0.5	<0.5	<50	NA
	09/22/93		19.18	25.76	<0.5	<0.5	<0.5	<0.5	<50	NA
	01/24/94		19.17	25.77	<0.5	<0.5	<0.5	<0.5	<50	NA
	04/07/94		18.23	26.71	<0.5	<0.5	<0.5	<0.5	<50	NA
	06/07/94		18.40	26.54	<0.5	<0.5	<0.5	<0.5	<50	NA
	09/28/94		20.01	24.93	<0.5	<0.5	<0.5	<0.5	<50	NA
	12/14/94		18.88	26.06	<0.5	<0.5	<0.5	<0.5	<50	NA
	03/15/95		16.24	28.70	<0.5	<0.5	<0.5	<0.5	<50	NA
	06/13/95		16.75	28.19	<0.5	<0.5	<0.5	<0.5	<50	NA
	09/28/95		18.04	26.90	<0.5	<0.5	<0.5	<0.5	<50	NA
	12/28/95		17.87	27.07	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	03/12/96		NM	NC	NS	NS	NS	NS	NS	Not measured
	06/11/96		16.26	28.68	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	10/02/96		17.74	27.20	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	01/28/97		14.51	30.43	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	05/20/97		16.73	28.21	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	08/18/97		NM	NC	NS	NS	NS	NS	NS	Not measured
	09/29/97		NM	NC	NS	NS	NS	NS	NS	Not measured
	11/05/97		18.61	26.33	<0.5	<0.5	<0.5	<0.5	<50	<5.0/<0.5 ^b
	03/31/98		NM	NC	NS	NS	NS	NS	NS	No free product or sheen
	05/26/98		15.28	29.66	NS	NS	NS	NS	NS	Not measured
	05/28/98		NM	NC	NS	NS	NS	NS	NS	No free product or sheen
	08/19/98		16.55	28.39	<0.5	<0.5	<0.5	<0.5	<50	Not measured
	11/17/98		17.32	27.62	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	02/18/99		15.74	29.20	<0.5	<0.5	<0.5	<0.5	<50	No free product or sheen
	06/24/99		16.73	28.21	NS	NS	NS	NS	NS	Not sampled

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-10	02/18/92	42.34	16.63	25.71	110	57	440	53	18,000	NA	
	05/14/92		15.25	27.09	NS	NS	NS	NS	NS	NS	
	05/15/92		NM	NC	24	9.8	97	<0.5	8,500	NA	
	08/27/92		18.35	23.99	NS	NS	NS	NS	NS	NS	
	08/29/92		NM	NC	20	2.8	40	3.5	9,600	NA	
	11/19/92		19.43	22.91	36	21	330	31	5,700	NA	
	02/03/93		15.01	27.33	15	4.6	36	9.6	2,200	NA	
	06/23/93		15.30	27.04	21	24	540	45	8,100	NA	No free product or sheen
	09/22/93		16.90	25.44	22	17	350	16	6,200	NA	No free product or sheen
	01/24/94		NM	NC	NS	NS	NS	NS	NS	NA	Not measured
	04/07/94		15.97	26.37	6.4	2.9	150	4.7	4,000	NA	No free product or sheen
	06/07/94		16.04	26.30	5.6	<2.5	150	5.7	6,700	NA	No free product or sheen
	09/28/94		17.69	24.65	2.2	2.6	110	44	5,700	NA	No free product or sheen
	12/14/94		16.65	25.69	<1.3	<1.3	77	27	3,500	NA	No free product or sheen
	03/15/95		14.08	28.26	<5.0	6.7	150	23	7,200	NA	No free product or sheen
	06/13/95		14.49	27.85	9	48	610	130	8,400	NA	No free product or sheen
	09/28/95		15.81	26.53	22	17	360	24	6,300	NA	No free product or sheen
	12/28/95		15.46	26.88	4.4	5.6	340	11	5,000	37	No free product or sheen
	03/12/96		12.62	29.72	1.4	5.9	41	73	4,500	120	No free product or sheen
	06/11/96		14.40	27.94	<5.0	25	350	81	7,500	<25	No free product or sheen
	10/02/96		15.47	26.87	18	<2.5	<2.5	<2.5	2,600	<25	No free product or sheen
	01/28/97		15.69	26.65	5.9	<2.5	29	19	2,800	<25	No free product or sheen
	05/20/97		14.48	27.86	<20	34	290	74	6,000	<100	No free product or sheen
	08/18/97		15.91	26.43	<20	7.7	94	15	5,900	<50	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		16.32	26.02	1.1	0.86	47	1.6	5,400	<50/2.3 ^b	No free product or sheen
	03/31/98		12.25	30.09	56	180	1,400	3,700	20,000	250	No free product or sheen
	05/26/98		12.97	29.37	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	76	200	1,600	3,900	16,000	190	No free product or sheen
	08/19/98		14.27	28.07	95	160	1,300	1,700	14,000	<100	No free product or sheen
	11/17/98		15.08	27.26	82	64	590	150	7500	290	No free product or sheen
	02/18/99		13.61	28.73	41	16	270	79	4,700	<100	No free product or sheen
	06/24/99		14.50	27.84	27	74	280	160	9,400	300	No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
MW-11	02/18/92	45.00	17.00	28.00	<0.5	<0.5	<0.5	<0.5	2,400	NA	
	05/14/92		19.02	25.98	<0.5	1.9	1.3	0.7	1,600	NA	
	08/27/92		21.13	23.87	15	2	0.6	1.2	2,100	NA	
	11/19/92		17.91	27.09	<0.5	<0.5	<0.5	<0.5	490	NA	
	02/03/92		17.91	27.09	<0.5	<0.5	0.55	<0.5	500	NA	
	06/23/93		18.14	26.86	<0.5	<0.5	<0.5	<0.5	350	NA	No free product or sheen
	09/22/93		19.63	25.37	<0.5	0.65	<0.5	0.71	200	NA	No free product or sheen
	01/24/94		19.79	25.21	<0.5	<0.5	<0.5	<0.5	450	NA	
	04/07/94		18.78	26.22	<0.5	<0.5	<0.5	<0.5	500	NA	No free product or sheen
	06/07/94		18.88	26.12	<0.5	<0.5	<0.5	0.64	560	NA	No free product or sheen
	09/28/94		20.45	24.55	<0.5	<0.5	<0.5	<0.5	600	NA	No free product or sheen
	12/14/94		19.45	25.55	<0.5	<0.5	<0.5	<0.5	340	NA	No free product or sheen
	03/15/95		17.32	27.68	<0.5	<0.5	<0.5	<0.5	340	NA	No free product or sheen
	06/13/95		17.43	27.57	<0.5	<0.5	<0.5	<0.5	210 ^a	NA	No free product or sheen
	09/28/95		18.67	26.33	4.1	0.5	<0.5	<0.5	93	NA	No free product or sheen
	12/28/95		18.31	26.69	<0.5	<0.5	<0.5	<0.5	380 ^a	<5.0	No free product or sheen
	03/12/96		15.89	29.11	<0.5	<0.5	<0.5	<0.5	110	<5.0	No free product or sheen
	06/11/96		16.98	28.02	<0.5	<0.5	<0.5	<0.5	400 ^a	<5.0	No free product or sheen
	10/02/96		18.20	26.80	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	01/28/97		12.53	32.47	<0.5	<0.5	<0.5	<0.5	110 ^a	<5.0	No free product or sheen
	05/20/97		17.36	27.64	<0.5	<0.5	<0.5	<0.5	330	<5.0	No free product or sheen
	08/18/97		18.84	26.16	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	09/29/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	11/05/97		NM	NC	NS	NS	NS	NS	NS	NS	Not measured
	03/31/98		15.39	29.61	<0.5	2.8	12	16	460	<5.0	No free product or sheen
	05/26/98		16.25	28.75	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	14	24	88	75	1,100	24	No free product or sheen
	08/19/98		17.30	27.70	16	9.6	69	17	1,200	6	No free product or sheen
	11/17/98		18.05	26.95	15	4.4	14	<0.5	580	21	No free product or sheen
	02/18/99		16.87	28.13	8.0	<0.5	1.4	<0.5	390	44	No free product or sheen
	06/24/99		17.50	27.50	4.6	<0.5	0.66	<0.5	610	59	No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation (ft)	Depth to Water (ft)	Ground Water Elevation (ft)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	TPH as gasoline (µg/L)	MTBE (µg/L)	Comments
RW-1	05/14/92	43.17	16.88	26.29	NS	NS	NS	NS	NS	NS	
	05/15/92		NM	NC	270	62	29	140	790	NA	
	08/27/92		19.05	24.12	1,300	200	68	810	24,000	NA	
	11/19/92		21.11	22.07	NS	NS	NS	NS	NS	NS	
	02/03/92		15.48	27.69	71	35	22	110	620	NA	
	06/23/93		28.25	14.92	30	33	9.8	35	220	NA	No free product or sheen
	09/22/93		17.83	25.34	800	400	170	910	4,100	NA	No free product or sheen
	01/24/94		24.00	19.17	33	6	6.9	23	190	NA	
	04/07/94		16.05	27.12	110	57	32	260	1,500	NA	No free product or sheen
	06/07/94		16.00	27.17	130	51	45	180	1,700	NA	No free product or sheen
	09/28/94		18.35	24.82	54	9.2	12	29	350	NA	No free product or sheen
	12/14/94		19.50	23.67	6.8	2.1	1.2	3.4	79	NA	No free product or sheen
	03/15/95		17.00	26.17	NS	NS	NS	NS	NS	NS	No free product or sheen
	04/10/95		NM	NC	54	11	11	69	410	NA	Not measured
	06/13/95		14.95	28.22	1,600	780	340	1,400	8,200	NA	No free product or sheen
	09/28/95		27.63	15.54	<0.5	<0.5	<0.5	<0.5	<50	NA	No free product or sheen
	12/28/95		14.54	28.63	<0.5	<0.5	<0.5	<0.5	<50	<5.0	No free product or sheen
	03/12/96		11.02	32.15	<0.5	<0.5	<0.5	<0.5	86	110	No free product or sheen
	06/11/96		14.52	28.65	38	11	4.7	50	230	68	No free product or sheen
	10/02/96		15.53	27.64	68	29	14	75	360	47	No free product or sheen
	01/28/97		12.59	30.58	0.77	<0.5	<0.5	<0.5	<50	9	No free product or sheen
	05/20/97		14.85	28.32	<0.5	<0.5	<0.5	<0.5	<50	32	No free product or sheen
	08/18/97		16.19	26.98	25	<0.5	<0.5	3.6	220	170	No free product or sheen
	09/29/97		NM	NC	240	2.8	51	55	900	230	Not measured
	11/05/97		16.95	26.22	340	3.2	59	78	1,300	240/220 ^b	No free product or sheen
	03/31/98		11.85	31.32	450	130	200	940	4,100	4,100	No free product or sheen

TABLE 1
GROUND WATER MONITORING DATA

Beacon Station No. 721
44 Lewelling Boulevard
San Lorenzo, California

Monitoring Well	Date	Top of Riser Elevation	Depth to Water	Ground Water Elevation	Benzene	Toluene	Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Comments
		(ft)	(ft)	(ft)	($\mu\text{g}/\text{L}$)						
RW-1 (cont)	05/26/98	43.17	13.13	30.04	NS	NS	NS	NS	NS	NS	No free product or sheen
	05/28/98		NM	NC	830	210	170	720	17,000	14,000	No free product or sheen
	08/19/98		14.70	28.47	20	<2.5	7.1	15	540	2,100	No free product or sheen
	11/17/98		15.54	27.63	7.8	<2.5	5.6	<2.5	630	730	No free product or sheen
	02/18/99		13.75	29.42	6.7	1.6	3.2	15	180	100	No free product or sheen
	06/24/99		14.96	28.21	<0.5	<0.5	<0.5	<0.5	<50	42	No free product or sheen

^a Product is not typical gasoline.

^b MTBE by EPA Method 8020/EPA Method 8260.

^c Constituents by EPA Method 8260.

Top of Riser Elevations = Elevations surveyed by Aegis Environmental and are assumed relative to mean sea level.

TPH = Total petroleum hydrocarbons.

MTBE = Methyl tertiary butyl ether.

$\mu\text{g}/\text{L}$ = Micrograms per liter.

NS = Not sampled.

NM = Not measured.

NC = Not calculated.

NA = Not analyzed.

Note: Aegis Environmental, Inc. collected data prior to June 23, 1993.

TABLE 2
VOLUME OF GROUND WATER TREATED

Beacon Station No. 721
 44 Lewelling Boulevard
 San Lorenzo, California

Date	Totalizer Reading (gallons)	Change in Totalizer Reading (gallons)	Total Discharge (gallons)	Average Flow Rate (gallons per Minute)
06/21/93	2,120	NA	2,120	NA
07/14/93	117,367	115,247	117,367	3.48
08/14/93	210,470	93,103	210,470	2.09
09/22/93	255,241	44,771	255,241	0.80
01/24/94	399,520	144,279	399,520	0.81
03/31/94	460,075	60,555	460,075	0.64
06/21/94	597,663	137,588	597,663	1.17
09/28/94	662,894	65,231	662,894	0.46
12/14/94	723,160	60,266	723,160	0.54
03/15/95	902,621	179,461	902,621	1.37
06/30/95	929,056	26,435	929,056	0.17
09/26/95	1,018,150	89,094	1,018,150	0.70
12/06/95	1,053,866	35,716	1,053,866	0.35
01/30/96	1,067,852	13,986	1,067,852	0.18
01/30/96 ^a	0	NA	1,067,852	NA
03/19/96	8,900	8,900	1,076,752	0.13
06/27/96	107,780	98,880	1,175,632	0.69
09/18/96	108,910	1,130	1,176,762	0.01
10/22/96	116,540	7,630	1,184,392	0.16
06/24/99	116,580	40	1,184,432	0.00
07/26/99	117,170	590	1,185,022	0.01
07/27/99	120,840	3,670	1,188,692	2.55
07/28/99	121,030	190	1,188,882	0.13
07/29/99	121,270	240	1,189,122	0.17
07/30/99	121,490	220	1,189,342	0.15

^a Flow totalizer replaced on January 30, 1996

TABLE 3
CUMMULATIVE GROUND WATER SYSTEM ANALYTICAL RESULTS

Beacon Station No. 721
 44 Lewelling Boulevard
 San Lorenzo, California

Sample ID	Date	Benzene	Toluene	Ethyl-	Total	TPH as	Priority Pollutant	Phenols & Cyanide	pH
		(µg/L)	(µg/L)	benzene	Xylenes	gasoline			
Effluent	05/28/93	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	10/01/93	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	01/24/94	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	04/07/94	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	05/18/94	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	12/14/94	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Mid-Carbon	12/14/94	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	12/14/94	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	03/22/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Mid-Carbon	03/22/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	03/22/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	04/10/95	3.9	0.57	0.65	5.5	<50	NA	NA	NA
Mid-Carbon	04/10/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	04/10/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	07/28/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	08/10/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Mid-Carbon	08/10/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	08/10/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	09/14/95	<0.5	<0.5	<0.5	<0.5	490 ^a	NA	NA	NA
Mid-Carbon	09/14/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	09/14/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	12/06/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Mid-Carbon	12/06/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	12/06/95	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	01/30/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA
Mid-Carbon	01/30/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA
Effluent	01/30/96	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Influent	02/27/96	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Mid-Carbon	02/27/96	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA
Effluent	02/27/96	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA

TABLE 3
CUMMULATIVE GROUND WATER SYSTEM ANALYTICAL RESULTS

Beacon Station No. 721
 44 Lewelling Boulevard
 San Lorenzo, California

Sample ID	Date	Benzene	Toluene	Ethyl-benzene	Total Xylenes	TPH as gasoline	MTBE	Priority Pollutant	Phenols & Cyanide	pH
		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	Metals (µg/L)	(µg/L)	(µg/L)
Influent	03/12/96	<0.5	<0.5	<0.5	<0.5	<50	5.3	NA	NA	NA
Mid-Carbon	03/12/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Effluent	03/12/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Influent	04/16/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Mid-Carbon	04/16/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Effluent	04/16/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Influent	05/07/96	<0.5	<0.5	<0.5	<0.5	<50	7.9	NA	NA	NA
Mid-Carbon	05/07/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Effluent	05/07/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Influent	06/11/96	2.4	0.57	5.9	2.8	190	610	NA	NA	NA
Mid-Carbon	06/11/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Effluent	06/11/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Influent	09/18/96	<0.5	<0.5	<0.5	<0.5	<50	11	NA	NA	NA
Mid-Carbon	09/18/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Effluent	09/18/96	<0.5	<0.5	<0.5	<0.5	<50	<5.0	NA	NA	NA
Influent	06/24/99	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA	NA
DAT Effluent	06/24/99	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA	NA
Mid-Carbon	06/24/99	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA	NA
Effluent	06/24/99	<0.5	<0.5	<0.5	<0.5	<50	NA	0.0037 ^a	ND	8.9
Influent	07/26/99	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA	NA
Influent	07/27/99	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA	NA
Influent	07/28/99	<0.5	<0.5	<0.5	<0.5	<50	NA	NA	NA	NA

^a Not typical gasoline.

^b Arsenic

Priority Pollutant Metals = Arsenic, cadmium, copper, lead, mercury, nickel, selenium, silver, total chromium & zinc.

TPH = Total petroleum hydrocarbons

MTBE = Methyl tertiary butyl ether.

mg/L = Micrograms per liter.

NA = Not analyzed.

ND = Not detected

Note: The ground water treatment system using an air stripper was shut down in October 1996, and was restarted with a Diffused Aeration Tank on June 24, 1999.




FIGURE 1
SITE LOCATION MAP
BEACON STATION NO. 721
44 LEWELLING BOULEVARD
SAN LORENZO, CA.

PROJECT NO. 40-93-936	DRAWN BY I.H. 11/2/82
FILE NO. _____	PREPARED BY TMG
REVISION NO. 1	REVIEWED BY J.W. 4/17/83


Delta Environmental Consultants, Inc.



0 2000 FT
SCALE 1 : 24,000

LEWELLING BOULEVARD

VIA GRANADA



North

LEGEND:

- RW-1 RECOVERY WELL LOCATION
- MW-1 MONITORING WELL LOCATION
- AS-1 AIR SPARGING WELL LOCATION

NOTE:

BASE MAP ADAPTED FROM RESNA FIGURE DATED 1/9/92
SITE DIMENSIONS AND FACILITY LOCATIONS NOT VERIFIED



FIGURE 2
SITE VICINITY MAP

BEACON STATION NO. 721
44 LEWELLING BOULEVARD
SAN LORENZO, CA.

PROJECT NO. DD93-938	DRAWN BY I.H. 10/12/95
FILE NO. 83-938-1	PREPARED BY JWS
REVISION NO. 3	REVIEWED BY <i>[Signature]</i>

LEWELLING BOULEVARD




FIGURE 3
GROUND WATER ELEVATION CONTOUR MAP
6/24/99
BEACON STATION NO. 721
44 LEWELLING BOULEVARD
SAN LORENZO, CA.

PROJECT NO. D083-936	DRAWN BY TLA 8/2/99
FILE NO. 93-936-1	PREPARED BY TLA
REVISION NO. 1	REVIEWED BY <i>Sean</i>



QUALITY ASSURANCE PLAN

This section describes the field and analytical procedures to be followed throughout the investigation.

General Sample Collection and Handling Procedures

Proper collection and handling are essential to ensure the quality of a sample. Each sample is collected in a suitable container, preserved correctly for the intended analysis, and stored prior to analysis for no longer than the maximum allowable holding time. Details on the procedures for collection and handling of samples used on this project can be found in this section.

Water Sample Collection for Volatile Organic Analyses

For volatile organic analyses (VOA), the water sample is decanted into each VOA vial in such a manner that there is no meniscus at the top of the vial. A cap is quickly secured to the top of the vial. The vial is inverted and gently tapped to see if air bubbles are present. If none are present, the vial is labeled and refrigerated according to soil and water sample labeling and preservation.

Water Sample Labeling and Preservation

Label information includes a unique sample identification number, job identification number, date, and time. After labeling, all soil and water samples are placed in a Ziploc® type bag and placed in an ice chest cooled to approximately 4° Celsius. Upon arriving at Delta's office, the samples are transferred to a locked refrigerator cooled to approximately 4° Celsius. Chemical preservation is controlled by the required analysis and is noted on the chain of custody form.

Upon recovery, the sample container is sealed to minimize the potential of volatilization and cross-contamination prior to chemical analysis. Soil sampling tubes are typically closed at each end with Teflon® sheeting and plastic caps. The sample is then placed in a Ziploc® type bag and sealed. The sample is labeled and refrigerated at approximately 4° Celsius for delivery, under strict chain-of-custody, to the analytical laboratory.

Sample Identification and Chain-of-Custody Procedures

Sample identification and chain-of-custody procedures document sample possession from the time of collection to ultimate disposal. Each sample container submitted for analysis has a label affixed to identify the job number, sampler, date and time of sample collection, and a sample number unique to that sample. This information, in addition to a description of the sample, field measurements made, sampling

methodology, names of on-site personnel, and any other pertinent field observations, is recorded on the borehole log or in the field records. A California-certified laboratory analyzes samples.

A chain-of-custody form is used to record possession of the sample from time of collection to its arrival at the laboratory. When the samples are shipped, the person in custody of them relinquishes the samples by signing the chain-of-custody form and noting the time. The sample-control officer at the laboratory verifies sample integrity and confirms that the samples are collected in the proper containers, preserved correctly, and contain adequate volumes for analysis.

If these conditions are met, each sample is assigned a unique log number for identification throughout analysis and reporting. The log number is recorded on the chain-of-custody form and in the legally required logbook, maintained by the laboratory, in the laboratory. The sample description, date received, client's name, and other relevant information is also recorded.

Delta Environmental Consultants, Inc.
SITE SAMPLING / VISIT CHECKLIST

SITE NAME:	BEACON STATION NO. 721	PROJECT NUMBER:	D093-936
ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)	TIME ARRIVED AT SITE:	0500
DATE:	6-24-99	TIME DEPARTED FROM SITE:	1200

WELLS SAMPLED:	MW-1, 2, 3, 4*, 7**, 10, 11* & RW-1
SAMPLING ORDER:	1, 3, 2, 4, 11, 10 RW-1
SAMPLING PARAMETERS:	BTEX, TPHg & MTBE (4 X 40 mL VOA) : EPA METHOD 8020
SAMPLING NOTES:	* SAMPLE MW-4 & MW-11 SEMIANNUALLY (2ND & 4TH QUARTERS ONLY)
SAMPLING NOTES:	** SAMPLE MW-7 ANNUALLY (4TH QUARTER ONLY)

WATER LEVEL DATA SHEETS ATTACHED:	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>
FIELD SAMPLING DATA SHEETS ATTACHED:	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>
** NUMBER OF SAMPLING SHEETS:	7	
TEMPORARY STORAGE OF WASTE ON SITE:	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>
CHAIN OF CUSTODY COPIES ATTACHED:	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>
DATE & TIME SAMPLES SHIPPED:	6/24/99 1353	
CARRIER SAMPLES WERE SHIPPED BY:	Delta	

ANY PROBLEMS / COMMENTS:	<p>116580 Total 12.00</p>  <p>Delta Environmental Consultants, Inc.</p>	
--------------------------	---	--



Delta Environmental Consultants, Inc.

GROUND WATER LEVEL DATA

SITE NAME:	BEACON STATION NO. 721	PROJECT NUMBER:	D093-936
ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)	RECORDED BY:	Marty O'HILL
DATE:	6-24-99	MEASURING DEVICE:	SLOPE INDICATOR



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID:	MW-1	SITE NAME:	BEACON STATION NO. 721
DEPTH OF WELL (FT):	31.20	DELTA JOB NUMBER:	D093-936
DEPTH TO GROUND WATER (FT):	15.02	ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT):	16.18	DATE/ SAMPLER INITIALS:	6-24-99 MAF

CASING DIAMETER (INCHES): 2 4 6 8 10 12

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH	16.18	X 0.5 =	8
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F) C	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/ COMMENTS
	21.0	7.4	851	8	
	22.1	7.6	823	4	
	24.3	7.4	868	8	

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

DATE SAMPLED:	6-24-99	TIME:	0650	COMMENTS:
---------------	---------	-------	------	-----------

SAMPLE ID	CONTAINER TYPES	ANALYSIS	COMMENTS
MW-1	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID:	MW-2	SITE NAME:	BEACON STATION NO. 721
DEPTH OF WELL (FT):	33.30	DELTA JOB NUMBER:	D093-936
DEPTH TO GROUND WATER (FT):	14.70	ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT):	18.6	DATE/ SAMPLER INITIALS:	6-24-99 CHM

CASING DIAMETER (INCHES): 2 4 6 8 10 12

(CIRCLE ONE)

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH	18.6	X 0.5 =	9
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F)	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/ COMMENTS
23.5	7.5	7.62	8		
22.9	8.0	7.61	4		
23.1	7.7	7.59	9		

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

DATE SAMPLED:	6-24-99	TIME:	0721	COMMENTS:
---------------	---------	-------	------	-----------

SAMPLE ID	CONTAINER TYPES	ANALYSIS	COMMENTS
MW-2	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID:	MW-3	SITE NAME:	BEACON STATION NO. 721
DEPTH OF WELL (FT):	29.30	DELTA JOB NUMBER:	D093-936
DEPTH TO GROUND WATER (FT):	14.44	ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT):	14.86	DATE/ SAMPLER INITIALS:	6-24-99 CAG

CASING DIAMETER (INCHES): 2 4 6 8 10 12

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH	14.86	X 0.5 =	8
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F)	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/COMMENTS
	22.8	7.6	872	8	
	22.7	7.8	774	4	
	23.5	7.6	793	6	

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

DATE SAMPLED:	6-24-99	TIME:	0703	COMMENTS:
---------------	---------	-------	------	-----------

SAMPLE ID	CONTAINER TYPES	ANALYSIS	COMMENTS
MW-3	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID: MW-4 (2 ND & 4 TH Quarters)	SITE NAME: BEACON STATION NO. 721
DEPTH OF WELL (FT): 24.60	DELTA JOB NUMBER: D093-936
DEPTH TO GROUND WATER (FT): 16.35	ADDRESS: 44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT): 8.25	DATE/ SAMPLER INITIALS: 6-24-99 CMM

CASING DIAMETER (INCHES): 2 4 6 8 10 12

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH	8.25	X 0.5 =	4
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F)	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/ COMMENTS
	23.1	7.3	771	8	
	22.9	7.3	972	4	

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

DATE SAMPLED:	6-24-99	TIME:	0734	COMMENTS:
---------------	---------	-------	------	-----------

SAMPLE ID	CONTAINER TYPES	ANALYSES	COMMENTS
MW-4	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID:	MW-10	SITE NAME:	BEACON STATION NO. 721
DEPTH OF WELL (FT):	29.50	DELTA JOB NUMBER:	D093-936
DEPTH TO GROUND WATER (FT):	14.50	ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT):	15	DATE/ SAMPLER INITIALS:	6-24-99 CR

CASING DIAMETER (INCHES): 2 4 6 8 10 12

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH	15	X 0.5 =	7
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F)	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/COMMENTS
	19.4	7.0	861	8	
	20.6	6.9	863	3	
	20.2	6.9	852	7	

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

DATE SAMPLED:	6-24-99	TIME:	0801	COMMENTS:
---------------	---------	-------	------	-----------

SAMPLE ID	CONTAINER TYPES	ANALYSIS	COMMENTS
MW-10	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID: MW-11 (2 nd & 4 th Quarters)	SITE NAME: BEACON STATION NO. 721
DEPTH OF WELL (FT): 29.50	DELTA JOB NUMBER: D093-936
DEPTH TO GROUND WATER (FT): 17.50	ADDRESS: 44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT): 17	DATE/ SAMPLER INITIALS: 6-24-99 CH

CASING DIAMETER (INCHES): 2 4 6 8 10 12

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH	17	X 0.5 =	6
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F)	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/COMMENTS
	22.7	6.9	1034	8	
	20.7	6.9	826	3	
	19.9	6.9	810	6	

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

DATE SAMPLED:	6-24-99	TIME:	0755	COMMENTS:	
---------------	---------	-------	------	-----------	--

SAMPLE ID:	CONTAINER TYPES	ANALYSIS	COMMENTS
MW-11	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Delta Environmental Consultants, Inc.

FIELD RECORD OF WATER SAMPLING

SAMPLE ID:	RW-1	SITE NAME:	BEACON STATION NO. 721
DEPTH OF WELL (FT):	29.50	DELTA JOB NUMBER:	D093-936
DEPTH TO GROUND WATER (FT):		ADDRESS:	44 LEWELLING BLVD (SAN LORENZO, CA)
CASING WATER LEVEL (FT):		DATE/ SAMPLER INITIALS:	6-24-99 CWA

CASING DIAMETER (INCHES): 2 4 6 8 10 12

PURGING PRIOR TO SAMPLING

CHECK BOX IF PURGING NOT REQUIRED

PURGING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: _____

PURGE VOLUME CALCULATIONS:

CASING DIAMETER	CASING WATER LEVEL (DEPTH OF WELL - DEPTH TO GW)	MULTIPLY BY	THREE CASING VOLUMES (GALLONS)
2 INCH		X 0.5 =	
4 INCH		X 2.0 =	
6 INCH		X 4.4 =	

DATE PURGED:		START TIME:		END TIME:	
--------------	--	-------------	--	-----------	--

TIME	TEMP (°F)	pH UNITS	SPEC COND.	GALLONS REMOVED	SAMPLE APPEARANCE/ COMMENTS

RECORD OF SAMPLING

CHECK BOX IF SAMPLES NOT COLLECTED

SAMPLING METHOD (CHECK ONE):

CENTRIFUGAL PUMP SUBMERSIBLE PUMP BAILER OTHER: *Pow 4*

DATE SAMPLED:	6-24-99	TIME:	0919	COMMENTS:	<i>Pow 4</i>
---------------	---------	-------	------	-----------	--------------

SAMPLE ID	CONTAINER TYPES	ANALYSIS	COMMENTS
RW-1	4 X 40mL VOA	BTEX, TPHg, MTBE	EPA METHOD 8020



Ultramar Inc.
CHAIN OF CUSTODY REPORT

BEACON

Beacon Station No. 721	Sampler (Print Name) Chris Hill Marty Wagner	ANALYSES	Date 6-24-99	Form No. of	
Project No. D093-936	Sampler (Signature) Chris Hill	BTEX TPH (gasoline) TPH (diesel)	Kill Lab		
Project Location SAN LORENZO	Affiliation Dr. 1/6	MTBE	Standard TAT		
Sample No./Identification	Date	Time	Lab No.	No. of Containers	REMARKS
MW 1	6-24-99	0650		X	
MW 2		0721		X	4
MW 3		0703		X	4
MW 4		0734		X	4
MW 10		0801		X	4
MW 11		0755		X	4
RW-1	6-24-99	0919		X	4
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)	Date	Time
<i>Chris Hill Dr. 1/6</i>	6-24-99	1353	<i>Marty Wagner</i>	6-24-99	1353
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)	Date	Time
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)	Date	Time
Report To: Richard Marsh Dr. 1/6			Bill to: ULTRAMAR INC. 525 West Third Street Hanford, CA 93230 Attention: <i>Terry Fox</i>		

WHITE: Return to Client with Report

YELLOW: Laboratory Copy

PINK: Originator Copy

ENCLOSURE C

Ground Water Sample Laboratory Report



Report Number : 14400

Date : 07/14/99

Richard Munsch
Delta Environmental Consultants, Inc.
3164 Gold Camp Drive, Suite 200
Rancho Cordova, CA 95670

Subject : 7 Water Samples
Project Name : Beacon 721
Project Number : D093-936

Dear Mr. Munsch,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink that reads "Joel Kiff". The signature is fluid and cursive, with "Joel" on the top line and "Kiff" on the bottom line. To the left of the signature, the name "Joel Kiff" is printed in a smaller, sans-serif font.



Report Number : 14400

Date : 07/14/99

Subject : 7 Water Samples
Project Name : Beacon 721
Project Number : D093-936

Case Narrative

The quantitation of TPH as Gasoline does not include the compound Methyl-t-butyl ether for the following samples:

MW1
MW2
MW4
RW-1

Approved By: 
Joel Kiff



Report Number : 14400

Date : 07/14/99

Project Name : Beacon 721

Project Number : D093-936

Sample : MW 1

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	10	2.5	ug/L	EPA 8020	06/27/99
Toluene	< 2.5	2.5	ug/L	EPA 8020	06/27/99
Ethylbenzene	12	2.5	ug/L	EPA 8020	06/27/99
Total Xylenes	6.5	2.5	ug/L	EPA 8020	06/27/99
Methyl-t-butyl ether	3400	250	ug/L	EPA 8020	06/27/99
TPH as Gasoline	860	250	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	105		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	105		% Recovery	M EPA 8015	06/27/99

Sample : MW 2

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 15	15	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Methyl-t-butyl ether	39000	2500	ug/L	EPA 8020	06/30/99
TPH as Gasoline	180	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	83.1		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	128		% Recovery	M EPA 8015	06/27/99

Approved By: Joel Kiff



Report Number : 14400

Date : 07/14/99

Project Name : Beacon 721

Project Number : D093-936

Sample : MW 3

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	27	0.50	ug/L	EPA 8020	06/26/99
Toluene	21	0.50	ug/L	EPA 8020	06/26/99
Ethylbenzene	8.6	0.50	ug/L	EPA 8020	06/26/99
Total Xylenes	32	0.50	ug/L	EPA 8020	06/26/99
Methyl-t-butyl ether	61	5.0	ug/L	EPA 8020	06/26/99
TPH as Gasoline	540	50	ug/L	M EPA 8015	06/26/99
aaa-Trifluorotoluene (8020 Surrogate)	86.6		% Recovery	EPA 8020	06/26/99
aaa-Trifluorotoluene (Gasoline Surrogate)	113		% Recovery	M EPA 8015	06/26/99

Sample : MW 4

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 1.0	1.0	ug/L	EPA 8020	06/26/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/26/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/26/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/26/99
Methyl-t-butyl ether	2100	50	ug/L	EPA 8020	06/27/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	06/26/99
aaa-Trifluorotoluene (8020 Surrogate)	104		% Recovery	EPA 8020	06/26/99
aaa-Trifluorotoluene (Gasoline Surrogate)	107		% Recovery	M EPA 8015	06/26/99

Approved By: Joel Kiff



Report Number : 14400

Date : 07/14/99

Project Name : Beacon 721

Project Number : D093-936

Sample : MW 10

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	27	10	ug/L	EPA 8020	06/27/99
Toluene	74	10	ug/L	EPA 8020	06/27/99
Ethylbenzene	280	10	ug/L	EPA 8020	06/27/99
Total Xylenes	160	10	ug/L	EPA 8020	06/27/99
Methyl-t-butyl ether	300	100	ug/L	EPA 8020	06/27/99
TPH as Gasoline	9400	1000	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	105		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	110		% Recovery	M EPA 8015	06/27/99

Sample : MW 11

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	4.6	0.50	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	0.66	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Methyl-t-butyl ether	59	5.0	ug/L	EPA 8020	06/27/99
TPH as Gasoline	610	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	99.5		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	113		% Recovery	M EPA 8015	06/27/99

Approved By: Joel Kiff



Report Number : 14400

Date : 07/14/99

Project Name : Beacon 721

Project Number : D093-936

Sample : RW-1

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Methyl-t-butyl ether	42	5.0	ug/L	EPA 8020	06/27/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	103		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	101		% Recovery	M EPA 8015	06/27/99

Approved By: Joel Kiff



Ultramar Inc.
CHAIN OF CUSTODY REPORT

14400

BEACON

Beacon Station No. 721	Sampler (Print Name) Chris Hill	Analyses	Date 6-24-99	Form No. 1 of 1						
Project No. DUG3-936	Sampler (Signature)		Kift LAB							
Project Location SPN Lorenzo	Affiliation De/1k		Standard TAT							
Sample No./Identification	Date 6-24-99	Time 0650	Lab No.	BTEX	TPH (gasoline)	TPH (diesel)	MTBE	8222	No. of Containers	REMARKS
MW 1				X	X				4	-01
MW 2		0721		X	X				4	-02
MW 3		0703		X	X				4	-03
MW 4		0734		X	X				4	-04
MW 10		0801		X	X				4	-05
MW 11		0755		X	X				4	-06
Rw-1	6-24-99	0919		X	X				4	-07
Relinquished by: (Signature/Affiliation)	Date 6-24-99	Time 1353	Received by: (Signature/Affiliation)						Date 0624-99	Time 1353
Chris Hill De/1k			Maynard Elkins							
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)						Date	Time
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)						Date	Time
Report To: Richard Munsch De/1k	Bill to:	ULTRAMAR INC. 525 West Third Street Hanford, CA 93230 Attention: Zony Fox								

WHITE: Return to Client with Report

YELLOW: Laboratory Copy

PINK: Originator Copy

32-6003 1/00

ENCLOSURE D

Ground Water Treatment System Analytical Results



Report Number : 14401

Date : 07/12/99

Richard Munsch
Delta Environmental Consultants, Inc.
3164 Gold Camp Drive, Suite 200
Rancho Cordova, CA 95670

Subject : 4 Water Samples
Project Name : Beacon 721
Project Number : D093-936

Dear Mr. Munsch,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink, appearing to read "Joel Kiff".

Joel Kiff



Report Number : 14401

Date : 07/12/99

Project Name : Beacon 721

Project Number : D093-936

Sample : Effluent

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	103		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	100		% Recovery	M EPA 8015	06/27/99

Sample : MID

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	101		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	100		% Recovery	M EPA 8015	06/27/99

Approved By: Joel Kiff



Report Number : 14401

Date : 07/12/99

Project Name : Beacon 721

Project Number : D093-936

Sample : DAT Effluent

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	103		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	100		% Recovery	M EPA 8015	06/27/99

Sample : Influent

Matrix : Water

Sample Date : 06/24/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	06/27/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	06/27/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	06/27/99
aaa-Trifluorotoluene (8020 Surrogate)	99.1		% Recovery	EPA 8020	06/27/99
aaa-Trifluorotoluene (Gasoline Surrogate)	103		% Recovery	M EPA 8015	06/27/99

Approved By: Joel Kiff



alpha

Alpha Analytical Laboratories Inc.

860 Waugh Lane, H-1, Ukiah, California 95482

e-mail: clientservices@alpha-labs.com • Phone: (707) 468-0401 • Fax: (707) 468-5267

CHEMICAL EXAMINATION REPORT

Page 1 of 2

Kiff Analytical
720 Olive Drive Suite D
Davis, CA 95616
Attn: Joel Kiff

Date Printed
07/02/99

Order Number	Receipt Date/Time	Client	Client P.O.	Send Via
A99062507	06/25/99 10:40AM	KIFFLAB	14401	MAIL

	METHOD	EXTRACTED	TEST DATE	RESULT	UNITS	PQL
--	--------	-----------	-----------	--------	-------	-----

Order A99062507 consisted of 1 Samples and 5 Tests.

Sample 1 Effluent

Sample Type: Aqueous Sampled By: Sampled: 06/24/99

Lead	200.9	06/29/99	ND	mg/L	.005
pH	150.1	06/25/99	8.9	pH	-
Total Cyanide	335.2	06/29/99	ND	mg/L	.02
Total Phenol	420.1	06/28/99	ND	mg/L	.10

PQL = Practical Quantitation Limit ND - None Detected

Bruce L. Gove
Laboratory Director

Bruce L. Gove
Date Printed: 07/02/99



alpha

Alpha Analytical Laboratories Inc.

e-mail: clientservices@alpha-labs.com • Phone: (707) 468-0401 • Fax: (707) 468-5267

860 Waugh Lane, H-1, Ukiah, California 95482

Order Number: A99062507

July 02, 1999

Page 2 of 2

Sample Notes:

Bruce L. Gove
Laboratory Director Date Printed: 07/02/99

Bruce L. Gove

14401

KIFF ANALYTICAL SUBCONTRACT FORM

Please mail results to :

Please fax to :

JOEL KIFF
KIFF ANALYTICAL

530-297-4803

720 OLIVE DRIVE, SUITE D
DAVIS, CA 95616Subcontract Lab: Alpha Analytical
860 Waugh Lane, H-1
Ukiah, CA 95482

707-468-0401

PROJECT NAME : Beacon 721

Account No. : KIFFLAB

PROJECT NUMBER: D093-936

Sample	Matrix	Sampled	Tests	Due	Container
Effluent	WA	06/24/99	Lead by GFAA	X	07/01/99
Effluent	WA	06/24/99	pH		07/01/99
Effluent	WA	06/24/99	Cyanide		07/01/99
Effluent	WA	06/24/99	Tot. Rec. Phenols (EPA 420.1)		07/01/99

more metals to be added later.

Relinquished by : May ArbitDate/Time: 06/24/99 / 1728 Received by: _____

Relinquished by : _____

Date/Time: 6/25/99 10:40 Received by: Sandi Simmonds

Relinquished by : _____

Date/Time: _____ Received by: _____



Ultramar Inc.
CHAIN OF CUSTODY REPORT

14401

BEACON

Beacon Station No. 721	Sampler (Print Name) Martin Morgan			ANALYSES					Date 6/24/99	Form No. 1 of 1	
Project No. D093-936	Sampler (Signature) <i>M. Morgan</i>			BTEX TPH (gasoline) TPH (diesel) Metals - Bench Sheet Phenols Cyanide pH	No. of Containers	Kiff Lab 5302974800 (5 DAY) JAT					
Project Location San Lorenzo, CA	Affiliation Delta Env Cons.										
Sample No./Identification effluent	Date 6/24/99	Time 1115	Lab No. -01	XX	XXXX					No. of Containers 6	
Mid	6/24/99	1100	-02	XX						2	
DAT effluent	6/24/99	1016	-03	XX						2	
influent	6/24/99	1010	-04	XX						2	
Relinquished by: (Signature/Affiliation) <i>M. Morgan</i> / Delta	Date 6/24/99	Time 1353	Received by: (Signature/Affiliation) <i>Margaret Edwards</i>							Date 6/24/99	Time 1353
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)							Date	Time
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)							Date	Time
Report To: Richard Munsch 916 638-2085				Bill to: ULTRAMAR INC. 525 West Third Street Hanford, CA 93230 Attention: Terry Fox							



Report Number : 14657

Date : 08/04/99

Richard Munsch
Delta Environmental Consultants, Inc.
3164 Gold Camp Drive, Suite 200
Rancho Cordova, CA 95670

Subject : 1 Water Sample
Project Name : Beacon 721
Project Number : D093-936

Dear Mr. Munsch,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink, appearing to read "Joel Kiff".

Joel Kiff



Report Number : 14657

Date : 08/04/99

Project Name : Beacon 721

Project Number : D093-936

Sample : DAT influent

Matrix : Water

Sample Date : 07/26/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	07/30/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	07/30/99
aaa-Trifluorotoluene (8020 Surrogate)	101		% Recovery	EPA 8020	07/30/99
aaa-Trifluorotoluene (Gasoline Surrogate)	93.5		% Recovery	M EPA 8015	07/30/99

Approved By: Joel Kiff



Ultramar Inc.
CHAIN OF CUSTODY REPORT

BEACON
PAM 672579

14657

Beacon Station No. 721	Sampler (Print Name) Martin Morgan			ANALYSES			Date 7/26/99	Form No. / of /		
Project No. D093-936	Sampler (Signature) 							Kiff Lab (530) 297-4800		
Project Location San Lorenzo, CA	Affiliation Delta Env. Cons.						No. of Containers 2	Standard TAT		
Sample No./Identification DAT Influent	Date 7/26/99	Time 0702	Lab No.	BTEX XX	TPH (gasoline)	TPH (diesel)		REMARKS -C		
Relinquished by: (Signature/Affiliation) 			Date 7/26/99	Time 1126	Received by: (Signature/Affiliation)			Date 7/26/99	Time 1126	
Relinquished by: (Signature/Affiliation)			Date	Time	Received by: (Signature/Affiliation)			Date	Time	
Relinquished by: (Signature/Affiliation)			Date	Time	Received by: (Signature/Affiliation)			Date 07/28/99	Time 1126	
Report To: Richard Munsch 916 638 2085			Bill to: ULTRAMAR INC. 525 West Third Street Hanford, CA 93230 Attention: Jerry Fox							

WHITE: Return to Client with Report

YELLOW: Laboratory Copy

PINK: Originator Copy



Report Number : 14658

Date : 08/04/99

Richard Munsch
Delta Environmental Consultants, Inc.
3164 Gold Camp Drive, Suite 200
Rancho Cordova, CA 95670

Subject : 1 Water Sample
Project Name : Beacon 721
Project Number : D093-936

Dear Mr. Munsch,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink, appearing to read "Joel Kiff".

Joel Kiff



Report Number : 14658

Date : 08/04/99

Project Name : Beacon 721

Project Number : D093-936

Sample : DAT influent

Matrix : Water

Sample Date : 07/27/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	07/30/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	07/30/99
aaa-Trifluorotoluene (8020 Surrogate)	101		% Recovery	EPA 8020	07/30/99
aaa-Trifluorotoluene (Gasoline Surrogate)	95.6		% Recovery	M EPA 8015	07/30/99

Approved By: Joel Kiff



Ultramar Inc.
CHAIN OF CUSTODY REPORT

BEACON

14658

Beacon Station No. 721	Sampler (Print Name) Martin Morgan	ANALYSES			Date 7/27/99	Form No. / of 1
Project No. D093-936	Sampler (Signature) 	BTEX	TPH (gasoline)	TPH (diesel)	Kiff Lab (530) 292-4800	
Project Location San Lorenzo, CA	Affiliation Delta Env. Cons.					Standard TAT
Sample No./Identification DAT Influent	Date 7/27/99	Time 0513	Lab No.		No. of Containers 2	REMARKS -0'
Relinquished by: (Signature/Affiliation) 	Date 7/28/99	Time 1126	Received by: (Signature/Affiliation)		Date 7/28/99	Time 1126
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)		Date	Time
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)		Date 7/28/99	Time 1126
Report To: Richard Munsch 916 638 2085	Bill to:	ULTRAMAR INC. 525 West Third Street Hanford, CA 93230 Attention: Jerry Fox				

WHITE: Return to Client with Report

YELLOW: Laboratory Copy

PINK: Originator Copy



Report Number : 14659

Date : 08/04/99

Richard Munsch
Delta Environmental Consultants, Inc.
3164 Gold Camp Drive, Suite 200
Rancho Cordova, CA 95670

Subject : 1 Water Sample
Project Name : Beacon 721
Project Number : D093-936

Dear Mr. Munsch,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink, appearing to read "Joel Kiff".

Joel Kiff



Report Number : 14659

Date : 08/04/99

Project Name : Beacon 721

Project Number : D093-936

Sample : DAT influent

Matrix : Water

Sample Date : 07/28/99

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Toluene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8020	07/30/99
Total Xylenes	< 0.50	0.50	ug/L	EPA 8020	07/30/99
TPH as Gasoline	< 50	50	ug/L	M EPA 8015	07/30/99
aaa-Trifluorotoluene (8020 Surrogate)	101		% Recovery	EPA 8020	07/30/99
aaa-Trifluorotoluene (Gasoline Surrogate)	95.2		% Recovery	M EPA 8015	07/30/99

Approved By: Joel Kiff



Ultramar Inc.
CHAIN OF CUSTODY REPORT

BEACON

14659

Beacon Station No. 721	Sampler (Print Name) Martin Morgan			ANALYSES			Date 7/28/99	Form No. 1 of 1
Project No. DD93-936	Sampler (Signature) 						K. H. Lab 5302974800	
Project Location San Lorenzo, CA	Affiliation Delta Env Cons						Standard TAT	
Sample No./Identification DAT influent	Date 7/28/99	Time 0506	Lab No.	BTEX	TPH (gasoline)	TPH (diesel)	REMARKS -01	
				X	X			
Relinquished by: (Signature/Affiliation) 	Date 7/28/99	Time 1126	Received by: (Signature/Affiliation)				Date	Time
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)				Date	Time
Relinquished by: (Signature/Affiliation)	Date	Time	Received by: (Signature/Affiliation)				Date 7/29/99	Time 1126
Report To: Richard Munsch 916 638 2085	Bill to: ULTRAMAR INC. 525 West Third Street Hanford, CA 93230 Attention:							