

PROTECTION

98 DEC 18 PM 3: 47

Environmental & Water Resources Engineering Groundwater Consultants

December 7, 1998

CERTIFICATION OF WELL DESTRUCTION

ADOBE PLAZA

3098 Castro Valley Boulevard Castro Valley, California

Introduction

The site is the Adobe Plaza shopping center at 3098 Castro Valley Boulevard in Castro Valley, California. The location of the site is shown in Figure 1.

On July 27, 1988, two 10,000-gallon Gasoline underground storage tanks were removed from the site. The excavated soil was aerated on-site and used as backfill once laboratory analysis of the soil samples collected from the aerated soil revealed non-detectable levels of petroleum hydrocarbon constituents. Due to the possibility of impact to groundwater, three shallow groundwater monitoring wells were installed on the site on August 11, 1989. Five quarterly and three semi-annual groundwater sampling events were subsequently conducted. Based upon the non-detectable levels of petroleum hydrocarbons in the groundwater, the Leaking Underground Fuel Tank case at this site has been classified as "closed" by the Environmental Protection Department of the Alameda County Health Care Services Agency.




FIGURE 1. Site Location Map.

Permitting


Prior to conducting the well destruction activities at the site, a Well Destruction Permit was obtained from the Water Resources Department of the Alameda County Public Works Agency (Permit No. 98WR501). A copy of the permit is provided in Attachment A.

Monitoring Well Destruction

On December 3, 1998, shallow groundwater monitoring wells MW-1, MW-2, and MW-3 were destroyed. The locations of the destroyed monitoring wells are shown in Figure 2.

The work was conducted by West Hazmat Drilling Corporation of Newark, California, under the supervision of Hageman-Aguiar, Inc. Prior to the well destruction, the total depth of each well below ground surface was sounded:

WELL	TOTAL DEPTH (FEET)
MW-1	23
MW-2	20
MW-3	23



CASTRO VALLEY BLVD

FIGURE 2.
Site Map.

Each well was tremmie grouted to displace the water in the well. Monitoring well MW-1 was destroyed by pressure grouting with approximately 20 p.s.i. of pressure with "neat" Portland cement. Monitoring wells MW-2 and MW-3 were destroyed by pressure-grouting with 25 p.s.i. of pressure for 5 minutes with "neat" Portland cement. Upon completion of the pressure-grouting, the well box at each location was removed. The destroyed wells were then covered with landscaping materials.

Copies of the completed DWR 188 Forms are provided in Attachment B.

CERTIFICATION OF WELL DESTRUCTION

ADOBE PLAZA

3098 Castro Valley Boulevard, Castro Valley, CA

December 7, 1998

No. C.34202

REPORTESSIONAL CONTROL OF CALIFORNIA SERVICE STATE OF CALIFORNIA SERVICE SERVICE STATE OF CALIFORNIA SERVICE SERV

Gary Aguiar

RCE 34262

Reneé L. Athey

Staff Engineer

ATTACHMENT A

Well Destruction Permit



ALAMEDA COUNTY PUBLIC WORKS AGENCY

Water resources section 961 Turner Court, Sutte 306, Hayward, Ca 94545-2651 TAK (310) 678-5263 PHONE (510) 670-8875 ANDREAS GODFREY

FOR OFFICE USE FOR APPLICANT TO COMPLETE 98WR501 PERMIT NUMBER WELL NUMBER APN_ R. Accuracy # n CCB

	Permit Conditions
	Circled Permit Requirements Apply
(ERAL 1. A permit application should be submitted so as to arrive at the ACPWA office five days prior to proposed starting date. 2. Submit to ACPWA within 60 days after completion of permitted work the original Department of Water Resources Water Well Dellicis Report or equivalent in well projects, or drilling logs and location shotch for approved date. 3. Permit is void if project not begun within 90 days of approved date. 12. REPPLY WELLS 1. Minimum surface seal thickness is two inches of sement grout placed by tramis. 2. Minimum scal depth is 50 feet for municipal and
c can	industrial wells or 30 feet for connecte and irrigation wells unless a lesser depth is specially approved.
INCL	Liding Piezometers
	1. Minimum surface seal thickness is two holes of coment grads placed by tremis.
	a beingmouse cast denth for monitoring wells is the

- - maximum depth practicable or 20 fact.
- D. GEOTECHNICAL

Backfill bore hote with compacted cuttings or heavy bentonic and upper two feet with compacted material. in arcas of known or suspected contemination, tremied coment grout shall be used in place of compacted ourdage.

- E. CATRODIC Fill hole above anode zone with concrete placed by wante. F. WELL DESTRUCTION Zes stucked.
- G. SPECIAL CONDITIONS

APPROVED	_DATE_ 11/24/98
APPROVED	_DATE

(510) 670-5248 ALVIN KAN DRILLING PERMIT APPLICATION ATION OF PROJECT 3098 California Coordinates Source CON ATN Name Cliffon Sherwood Adding PD Box Phone city Castle APPLICANT
Name Hagaman - Aguiar, Inc. Bary Aguiar
Name Hagaman - Aguiar, Inc. Bary Aguiar
Address 11100 Son Faho Ap., Str 2004 Phone (5/6)/620-087 APPLICANT Name Hagoman-Aquiac TYPE OF PROJECT Georechnical Investigation Wall Construction Cathodic Prometion П General. Q Contamination • Wear Supply Well Destruction 3 ٥ Monitoring PROPOSED WATER SUPPLY WELL USE Replucement Damestic O New Domestic D J Municipal Q Imgation ۵ Other Industrial 0 DELLING METHOD: D Air ROUTY Auter Mud Romry 'n Destray the wells by Pressure Gronting. Cable 0 Other ø DRILLBA'S LICENSE NO 554979 Well projects Dell Hote Diameter Maximum Dopth 50 Casing Diameter Humber 3 Surface Seal Depth GEOTECHNICAL PROJECTS Meximum Number of Borings Depih ... Hole Diameter __

I hereby agree to comply with all requirements of this permit and Alameda County Orginance No. 75-64,

ESTIMATED STARTING DATE ESTIMATED COMPLETION DATE

m DATE 11/17/98 APPLICANT'S SIGNATURE

12-03-98



ALAMEDA COUNTY PUBLIC WORKS AGENCY

WATER RESOURCES SECTION

951 TURNER COURT, SUITE 300, HAYWARD, CA 94545-2651

PHONE (510) 670-5575 ANDREAS GODFREY FAX (510) 670-5262

(510) 670-5248 ALVIN KAN

WATER RESOURCES SECTION
GROUNDWATER PROTECTION ORDINANCE
For Pressure Grouting of Monitoring Well

3098 CASTRO VALLEY BLVD CASTRO VALLEY PERMIT NO. 98WR501

Destruction Requirements:

- 1. Clean out all bridged or poorly compacted materials to the bottom of the well.
- 2. Pressure grout the casing to 2 feet below finished grade or original ground, whichever is the lower elevation.
- 3. Remove casing, seal and gravel pack to 2 feet below finished grade or original ground, whichever is the lower elevation.
- 4. After the seal has set, backfill the remaining hole with compacted material.

CONFIDENTIAL

STATE OF CALIFORNIA DWR WELL COMPLETION REPORT (WELL LOGS)

REMOVED

CONFIDENTIAL

STATE OF CALIFORNIA DWR WELL COMPLETION REPORT (WELL LOGS)

REMOVED

CONFIDENTIAL

STATE OF CALIFORNIA DWR WELL COMPLETION REPORT (WELL LOGS)

REMOVED