



**RECEIVED**

By Alameda County Environmental Health 11:59 am, Nov 16, 2017

November 14, 2017

Alameda County Environmental Health Services  
Environmental Protection  
1131 Harbor Bay Parkway, Suite 250  
Alameda, California 94502-6577  
Attn: Anne Jurek

**RE: Groundwater Monitoring Results, Second Semi-Annual 2017 Monitoring Period,  
Cargill Salt – Alameda Facility, Alameda, California,  
SLIC Case No. RO0002480**

Dear Ms. Jurek,

The attached report presents the groundwater monitoring results for the second semi-annual 2017 monitoring period for the Cargill Salt Alameda facility. The report presents the results of groundwater monitoring data collected during August 2017. Groundwater levels in the site monitoring wells were measured, groundwater samples were collected and analyzed, and the groundwater flow direction and gradient were determined.


The tetrachloroethene (PCE) concentrations reported for monitoring wells at the site continue to indicate that the phytoremediation project implemented in June 2005 has significantly reduced the average seasonal concentration of PCE at the site.

I declare, under penalty of perjury, that the information and/or recommendations contained in the attached report are true and correct to the best of my knowledge.

Should you have any questions concerning the report, please don't hesitate to call me at (510) 790-8182.

Sincerely,

Sean Riley  
Environmental Manager



C R A W F O R D  
C O N S U L T I N G  
I N C .

**Groundwater Monitoring Results  
Second Semi-Annual 2017 Monitoring Period**

**Cargill Salt – Alameda Facility  
Alameda, California**

*Prepared for:*  
**Cargill Salt  
7220 Central Avenue  
Newark, California 94560**

*Prepared by:*  
**Crawford Consulting, Inc.  
4 North Second Street, Suite 650  
San Jose, CA 95113**

**Project No. CS1605  
November 14, 2017**

# **Contents**

1	Introduction .....	1
1.1	Reporting Period Activities .....	1
1.2	Background Information .....	2
1.2.1	Site Description.....	2
1.2.2	Summary of Investigative and Remedial Activities.....	2
1.2.3	Source of VOC Impact.....	3
2	Groundwater Flow Analysis .....	4
2.1	Water-Level Measurement .....	4
2.2	Groundwater Flow Direction and Gradient.....	5
2.3	Groundwater Velocity .....	5
3	Groundwater Sampling and Analysis .....	6
3.1	Sample Collection and Analysis.....	6
3.2	Analytical Results.....	6
3.2.1	Quality Control .....	6
3.2.2	Groundwater Results.....	8
3.3	Discussion .....	9
4	Phytoremediation Project Status .....	10

Professional Certification

References

Limitations

## **Tables**

- Table 1. Groundwater Level Data
- Table 2. Relative Percent Difference Based on Duplicate Samples
- Table 3a. Summary of Groundwater Monitoring Well Data - Third Quarter 2017
- Table 3b. Historical Summary of Groundwater Monitoring Well Data

## **Illustrations**

- Figure 1. Site Location
- Figure 2. Groundwater Monitoring Well Locations
- Figure 3. Graphical Summary of Groundwater Elevations
- Figure 4. Groundwater Elevation Contours – August 2017
- Figure 5. VOC Concentrations in Groundwater – August 2017
- Figure 6. Graphical Summary of PCE Concentrations
- Figure 7. PCE Concentrations vs. Groundwater Elevation

## **Appendices**

- Appendix A. Field Data Sheets
- Appendix B. Groundwater Velocity Calculations
- Appendix C. Certified Analytical Reports and Chain-of-Custody Documentation

# 1 Introduction

Crawford Consulting, Inc. (Crawford) has prepared this report on behalf of Cargill Salt for the Cargill Salt Dispensing Systems Division facility (hereafter, the Site) in Alameda, California.

Results of groundwater transect sampling and the initial sampling of three groundwater monitoring wells installed in November 1999 were presented in the January 31, 2000 report, *Groundwater Characterization and Monitoring Well Installation, Cargill Salt – Alameda Facility, Alameda, California* (Crawford Consulting, Inc. and Conor Pacific/EFW). The purpose of the groundwater transect sampling and the monitoring well installation and sampling was to help characterize and monitor the occurrence of volatile organic compounds (VOCs), primarily tetrachloroethene (PCE) and its breakdown product, trichloroethene (TCE), previously detected in groundwater at the Site.

One of the recommendations in the report was to confirm the groundwater analytical results of the newly installed monitoring wells (wells MW-1, MW-2, and MW-3) and the groundwater flow direction and gradient via quarterly monitoring. Cargill Salt began groundwater monitoring on a quarterly basis after the initial groundwater monitoring well sampling event in November 1999. For 2000 through 2005, reporting was performed on an annual basis. Cargill Salt began reporting on a semi-annual basis in 2006.

Cargill Salt conducted additional characterization activities in November and December 2001 to evaluate the off-site extent of VOCs in the soil and groundwater. Soil and groundwater samples were collected and analyzed from a neighboring residential property and along Clement Avenue, slug tests were performed in the three existing monitoring wells, and a groundwater monitoring well (MW-4) was installed in Clement Avenue.

A phytoremediation project was implemented at the Site in June 2005. Based on reductions in PCE concentrations in groundwater since 2006, Alameda County Environmental Health suggested in a September 30, 2009 letter that Cargill Salt reduce the groundwater monitoring frequency from quarterly to semi-annually. The second half of 2009 was the first semi-annual monitoring period under the reduced monitoring frequency. Groundwater sampling and analysis are now performed during the first and third quarters.

## 1.1 Reporting Period Activities

This report presents the results of groundwater monitoring data collected for the second semi-annual 2017 monitoring event. Groundwater levels in the site monitoring wells were measured, groundwater samples were collected and analyzed, and the groundwater flow direction and gradient were determined.

The monitoring event for the second semi-annual 2017 monitoring period was conducted on August 2, 2017. Supervision of the monitoring event was conducted for Cargill Salt by Crawford. Groundwater level measurements and collection of groundwater samples were conducted by Field Solutions, Inc. The groundwater samples were analyzed by TestAmerica Laboratories, Inc., a state-certified laboratory in Pleasanton, California.

## **1.2 Background Information**

A description of the Site and a summary of the development of characterization and monitoring programs for the Site are presented in this section. The information presented in this section is for historical reference and does not include reporting of monitoring data for the monitoring period of this semi-annual report.

### **1.2.1 Site Description**

Alameda is an island on the east side of San Francisco Bay, separated from Oakland by a tidal canal (Figure 1). The Cargill Salt Dispensing Systems Division facility is located on a rectangular lot in an industrial and residential neighborhood. The facility building occupies approximately one-third of the Site and is separated from the vacant, unpaved side of the lot by an asphalt driveway (Figure 2). The Site is bordered by a sheet-metal shop and a residential lot to the northwest, an apartment complex to the southwest, and a residential lot to the southeast.

From 1951 to 1978, the Alameda facility produced salt-dispensing units, which required casting and milling aluminum parts.

Constituents of concern associated with site operations have included casting sands with elevated concentrations of metals, and solvents, machine oils, and grease used in casting and milling operations. As discussed below, previous investigations and remedial activities have investigated and remediated metals and solvents (VOCs) in vadose-zone soil.

### **1.2.2 Summary of Investigative and Remedial Activities**

Cargill Salt initiated site investigative activities in 1993 to determine if facility operations had impacted site soils. Cargill Salt submitted the results of the soil sampling investigation to the Alameda County Environmental Health Services (ACEHS) in October 1993 along with a workplan for excavation and disposal of impacted soils and assessment of potential impact to groundwater (Groundworks Environmental, Inc. [Groundworks], 1993).

After approval of the workplan by ACEHS, Cargill Salt conducted several phases of soil remediation and groundwater characterization. Surficial soils impacted by metals were excavated for disposal off site. Vadose-zone soils with the highest degree of impact by VOCs were also excavated for off-site disposal (see “Soil excavation area” on Figure 2).

The results of these activities were submitted to the ACEHS in a report, *Soil and Groundwater Investigations and Remedial Activities, July 1993 – September 1994, Cargill Salt – Alameda Facility, Alameda, California* (Groundworks, 1995). Recommendations for additional work to further delineate the lateral and vertical extent of VOCs in groundwater beneath the Site were presented in the report.

A workplan for the additional delineation of VOCs in groundwater, *Workplan for Groundwater Characterization and Monitoring Well Installation, 2016 Clement Avenue, Alameda, California* (CCI), was submitted to the ACEHS in July 1999.

After approval of the workplan by the ACEHS, Cargill Salt conducted groundwater sampling and well installation activities during August and November of 1999. The results of these activities were submitted to the ACEHS in a report, *Groundwater Characterization and Monitoring Well Installation, Cargill Salt – Alameda Facility, Alameda, California* (Crawford Consulting, Inc. and

Conor Pacific/EFW, dated January 31, 2000). After the initial groundwater monitoring well sampling event in November 1999, Cargill Salt began groundwater monitoring on a quarterly basis.

A work plan for remedial investigation activities, *Workplan for Off-Site Characterization, Cargill Salt – Alameda Facility, Alameda, California* (Conor Pacific/EFW), was submitted to the ACEHS in June 2001. After approval of the workplan by the ACEHS, Cargill Salt conducted characterization activities in November and December 2001 to evaluate off-site extent of VOCs in the soil and groundwater. Soil and groundwater samples were collected and analyzed from a neighboring residential property and along Clement Avenue, slug tests were performed in the three existing monitoring wells, and a groundwater monitoring well (MW-4) was installed in Clement Avenue. The results of these activities were submitted to the ACEHS in the August 21, 2002 submittal *Off-Site Groundwater Characterization, Cargill Salt – Alameda Facility, Alameda, California*, prepared by Conor Pacific/EFW.

A phytoremediation project was implemented at the Site in June 2005. The project involved planting 96 bare-root hybrid poplar trees in a grid of 24 rows. The rows are generally 6 feet apart with trees on 7-foot centers on each row. Selection of the phytoremediation approach and implementation of the project were described in the October 20, 2006 report, *Groundwater Monitoring Results, First through Fourth Quarter 2005, Cargill Salt – Alameda Facility, Alameda, California* prepared by Crawford Consulting, Inc. In April 2008, seven additional saplings were planted in the rear of the property near monitoring well MW-2.

The Site groundwater monitoring wells were re-surveyed in September 2006 by CSS Environmental Services in order to provide Geotracker-compliant survey data. Results of the casing elevation survey indicate that each well is approximately 6.4 feet higher than the previous survey conducted in 1999. This difference is due to the use of different datum for the 2006 and 1999 surveys. The casing elevations from the September 2006 survey are shown on Table 1.

### **1.2.3 Source of VOC Impact**

As discussed in the 1995 report, the occurrence of VOCs in soils and groundwater at the Site appears to be the result of a discharge or spill to surficial soils at a location near the rear property line at the southwestern corner of the property. The area with the highest degree of chemical impact was delineated prior to excavation and was then excavated using a backhoe and transported off-site for appropriate disposal. It is possible that the VOCs detected in soils and groundwater at this location were associated with waste products from facility operations. The VOCs may be associated with solvents previously used for degreasing operations at the facility, although there are no records indicating use of PCE. Site records indicate that the solvents used for degreasing operations were not PCE-based solvents.

It is also possible that the VOCs and oil and grease are associated with waste products discarded from neighboring properties. There is an apartment complex next to the rear property line of the facility, and the laundry room for this complex is in the utility shed immediately adjacent to the rear property line. This laundry room is only 4 feet away from the area of highest impact to soil. If PCE associated with laundry cleaning products were spilled in this laundry room, it is possible that it could have drained onto the Cargill Salt property.

## **2 Groundwater Flow Analysis**

Groundwater levels were measured and a groundwater contour map was prepared for the second semi-annual 2017 monitoring event.

### **2.1 Water-Level Measurement**

Water levels in four of the groundwater monitoring wells (MW-1, MW-2, MW-3 and MW-4) were measured on August 2, 2017, before any of the groundwater monitoring wells were purged for sampling for the semi-annual monitoring event. The groundwater monitoring well locations are shown on Figure 2. The water levels were measured with an electric sounder. The depth to water at each well was recorded on a *Water Level Field Data* sheet (see Appendix A).

The water-level data through the third quarter of 2017 are shown on Table 1. The data in Table 1 include the date and time of measurement, the well casing elevation, the measured depth to groundwater, the groundwater elevation, and the change in elevation from the previous measurement. A plot of historical groundwater elevations is shown in Figure 3.

As reviewed in previous semi-annual monitoring reports, groundwater levels in the on-site monitoring wells (MW-1, MW-2, and MW-3) and off-site well (MW-4) showed a different pattern in the first and third quarters of 2011 than the general seasonal pattern for the previous nine years (see Figure 3). Groundwater levels in all four wells generally exhibit similar seasonal fluctuations, and the first quarter groundwater elevations have typically exhibited effects of winter-season recharge. However, the groundwater elevations recorded in March 2011 for the three most downgradient wells showed a decline rather than the typical seasonal rise. The levels measured for those three wells in March 2011 were the lowest recorded to date. That trend continued in 2011, with the September 2011 groundwater elevations recorded for all four wells being the lowest recorded to date for each of the wells.

An overall downward trend had continued from 2011 through the third quarter 2014 measurement event. Seasonal recharge was still apparent but the average groundwater elevation had been declining. The change in the groundwater elevations noted for March 2011 through 2014 may have been related to nearby East Bay Municipal Utility District (EBMUD) sewer pipeline repair and replacement operations as well as to dewatering operations that were conducted at a nearby facility demolition project.

The overall downward trend noted through the third quarter 2014 measurement event has reversed and groundwater levels have recovered to levels similar to those recorded before 2011 (see Figure 3). The water levels recorded for the second semi-annual 2017 monitoring period (in August 2017) exhibited a typical seasonal decline, and were 0.9 to 3.7 feet lower than the elevations measured for the first semi-annual 2017 monitoring period (in February 2017).

## **2.2 Groundwater Flow Direction and Gradient**

A groundwater contour map based on the August 2017 water-level data is shown on Figure 4.

The groundwater flow pattern determined for the August 2017 measurement event was generally similar to patterns previously determined for the site. The flow direction determined for the site area was to the north-northeast. The horizontal hydraulic gradient measured for the site for the August 2017 measurement event was 0.011, similar to gradients previously determined.

## **2.3 Groundwater Velocity**

Average linear groundwater flow velocities (V) were calculated using a form of Darcy's Law,

$$V = K i / n,$$

where "K" is the hydraulic conductivity, "i" is the horizontal hydraulic gradient, and "n" is the effective porosity. The groundwater velocity calculations for the third quarter of 2017 groundwater data are presented in Appendix B.

Using hydraulic conductivity and porosity values determined for saturated native materials at the Site [based on slug tests and laboratory soil testing, respectively (Conor Pacific/EFW, 2002)], and the horizontal hydraulic gradients determined from the third quarter 2017 groundwater contour map, the groundwater flow velocity beneath the Site is calculated to be approximately 1 foot per year (ft/yr) for the third quarter 2017 measurements. The groundwater velocities measured for the Site have historically been in the range of 0.1 to 2 ft/yr.

## **3 Groundwater Sampling and Analysis**

This section summarizes the sample collection and analytical methods, presents an evaluation of quality control data, and summarizes the results of the sampling events.

### **3.1 Sample Collection and Analysis**

Groundwater samples were collected August 2, 2017 from groundwater monitoring wells MW-1, MW-2, MW-3, and MW-4.

Dedicated tubing was installed in wells MW-1, MW-2, and MW-3 prior to the first quarter 2000 sampling event and on December 17, 2001 in well MW-4 to facilitate sampling with a peristaltic pump. Dedicated fluorinated ethylene propylene resin (FEP)-lined polyethylene tubing was installed in each monitoring well. The tubing intake was placed about one foot above the well bottom in each of the wells. Viton® dedicated check valves were installed on the tubing intakes to prevent back-flow of water into the well. A short length of dedicated Viton® tubing was installed at the well head for use in a peristaltic pump head. Prior to sample collection for each quarterly monitoring event, the wells were purged using a peristaltic pump. Field parameters (pH, electrical conductivity, temperature, and turbidity) were measured in purged groundwater from each well prior to sampling; these data are recorded on the Sample Collection Field Data sheets presented in Appendix A. After purging, groundwater samples were collected using the peristaltic pump and the dedicated Viton® pump head discharge tubing.

The groundwater samples were analyzed for VOCs using U.S. Environmental Protection Agency (USEPA) Method 8260. Results for all Method 8010 analytes were reported. The groundwater samples for the second semi-annual 2017 event were delivered with appropriate chain-of-custody documentation to TestAmerica Laboratories, Inc., a state-certified laboratory in Pleasanton, California, for chemical analysis.

### **3.2 Analytical Results**

The results of field and laboratory quality control measures and the results of the groundwater monitoring well samples are reviewed in this section. The certified analytical reports and chain-of-custody documentation are presented in Appendix C.

#### **3.2.1 Quality Control**

Quality control (QC) samples were analyzed as part of the sampling and analysis program to evaluate the precision and accuracy of the reported groundwater chemistry data. QC samples included both field and laboratory samples. Descriptions of the purpose of specific field and laboratory QC samples used during the sampling and analysis program and an evaluation of field and laboratory QC results are presented below.

### Field Quality Control Samples

A field duplicate was used during the second semi-annual 2017 sampling event for the Site. A field duplicate is used to assess sampling and analytical precision. The duplicate is collected at a selected well (MW-2) and then submitted "blind" to the laboratory for analysis with the same batch as the regular sample for the selected well. An estimate of precision is obtained by calculating the relative percent difference (RPD) between the regular sample and the duplicate sample using the following formula:

$$RPD = \frac{[x - y] 100}{0.5 (x + y)}$$

where:  $[x - y]$  = the absolute value of the difference in concentration between the regular sample (x) and the duplicate sample (y).

### Laboratory Quality Control Samples

The following types of laboratory QC samples were used during the second semi-annual 2017 analytical program for the Site:

- surrogate spikes
- matrix spikes/duplicate matrix spikes

A surrogate spike is a check standard added to a sample in a known amount prior to analysis. Surrogate spikes consist of analytes not normally found in environmental samples and not targeted by the analytical procedure. Surrogate spikes provide information on recovery efficiency by comparing the percent recovery of specific surrogate analyses to statistically derived acceptance limits developed by the USEPA or the laboratory (provided such laboratory-specific limits are stricter than those developed by the USEPA). If the recoveries fall within the acceptance limits for the analytes, the analysis exhibits acceptable recovery efficiency. Recoveries that fall outside the acceptance limits indicate a potential problem with the recovery efficiency of analytes, which in turn indicates a potential bias with respect to the reported concentration of the environmental samples analyzed in the same batch.

Matrix spikes and duplicate matrix spikes are analyzed by the laboratory for the purpose of providing a quantitative measure of accuracy and precision, and to document the effect that the sample matrix has on the analysis. A selected sample is spiked in duplicate with known concentrations of analytes. The recoveries of the spiked analytes are compared to statistically derived acceptance limits developed by the USEPA or the laboratory (provided such laboratory-specific limits are stricter than those developed by the USEPA). If the recoveries fall within the acceptance limits for the analytes, the analysis has no statistically significant bias (i.e., the analysis is accurate). Recoveries that fall outside of the acceptance limits have a positive or negative bias, depending on whether the recovery is greater or less than the upper or lower acceptance limit, respectively. Analyses where analyte recoveries fall outside the acceptance limits should be regarded as estimates only.

Precision for matrix spikes is measured by calculating the relative percent differences (RPDs) between the measured concentration of analytes in the matrix and the duplicate matrix spike. The following equation is used for matrix spikes:

$$RPD = \frac{[MS - MSD]}{0.5(MS + MSD)} \times 100$$

where: [ MS - MSD ] = the absolute value of the difference in concentration between the matrix spike (MS) and the matrix spike duplicate (MSD)

### Third Quarter 2017 Field QC Results

One field duplicate (DUP-1) was analyzed as part of the third quarter 2017 sampling event at the Site. The duplicate sample was collected at groundwater monitoring well MW-2 and was analyzed for halogenated VOCs using USEPA Method 8260B (8010 list). Table 2 summarizes the calculated RPDs for MW-2 and MW-2 duplicate (DUP-1). The three parameters [cis-1,2-dichloroethene (cis-1,2-DCE), trichloroethene (TCE), and tetrachloroethene (PCE)] for which the RPDs could be calculated (see Table 2), exhibited a low RPD value (i.e., less than 5%) indicative of good precision for PCE and TCE, and a medium RPD value (more than 5% but less than 10%) indicative of fair precision for cis-1,2-DCE.

### Second Semi-Annual 2017 Laboratory QC Results

A review of the second semi-annual 2017 field data sheets and laboratory reports (presented in Appendices A and C, respectively) indicates that all analyses were performed within USEPA or California Department of Health Services (DHS) recommended maximum sample holding times.

QC data on surrogate spike recoveries and matrix spike recoveries are presented in the laboratory reports. These data indicate: (1) no surrogate spike recoveries were outside of the laboratory's acceptance limits; (2) RPD values for the matrix spikes and duplicate matrix spikes indicate a high overall degree of analytical precision.

No matrix spike or duplicate matrix spike recoveries were outside of the laboratory's control limits.

The laboratory QC data indicate that the results reported herein are of adequate quality for evaluation of site groundwater conditions.

### **3.2.2 Groundwater Results**

The results for the second semi-annual 2017 monitoring event are shown on Table 3a and Figure 5. The results of historical VOC analyses for 2000 through September 2017 are summarized in Table 3b, which also shows the VOC results for the initial sampling event for monitoring wells MW-1, MW-2, and MW-3 in November 1999. Historical PCE results for all four wells are plotted on Figure 6.

Consistent with previous monitoring events, PCE and its breakdown products TCE, cis-1,2-DCE, and 1,1-dichloroethene (DCE) were detected in Site groundwater samples from the second semi-annual 2017 monitoring event.

For the second semi-annual 2017 event, the concentrations of PCE detected were:

- 48 micrograms per liter ( $\mu\text{g}/\text{L}$ ) in monitoring well MW-1
- 340  $\mu\text{g}/\text{L}$  in MW-2
- not detected in MW-3 and MW-4

Other VOCs detected included the following:

- TCE was detected at 18 µg/L in monitoring well MW-1, but was not detected in MW-2, MW-3 or MW-4.
- DCE was detected at 4.7 µg/L in monitoring well MW-3, but was not detected in monitoring wells MW-1, MW-2 or MW-4.
- Cis-1,2-DCE was detected at 13 µg/L in monitoring well in MW-1 and 32 µg/L in MW-2, but was not detected in monitoring wells MW-3 or MW-4.

### 3.3 Discussion

Variations in VOC concentrations at monitoring well MW-2, the well with historically the highest reported PCE concentrations at the site, generally correlate with variations in groundwater elevations at the Site. An increase in VOC concentrations generally follows a rise in groundwater elevations, and a decrease in VOC concentration generally follows a fall in groundwater levels (see Figure 7). The variations in VOC concentrations sometimes lag one quarter behind the variations in groundwater elevation.

The results for VOC concentrations reported for the second semi-annual 2017 monitoring event are generally similar to the results reported since the second quarter of 2009 (see Figure 6 and Table 3b), with the following exceptions:

- The concentration of cis-1,2-DCE reported for well MW-1 for the second semi-annual 2017 monitoring event (13 µg/L) was the highest concentration recorded to date for the well.
- The concentration of DCE reported for well MW-3 for the second semi-annual 2017 monitoring event (4.7 µg/L) is significantly lower than the concentrations reported for the well for all the monitoring events from March 2011 through September 2016.

The higher DCE concentrations noted for well MW-3 from March 2011 through September 2016 may be related to the downward trend in groundwater elevations noted for the site through the third quarter of 2014. As discussed in Section 2.1, the downward groundwater elevation trend measured from March 2011 through September 2014 may have been related to nearby EBMUD sewer pipeline repair and replacement operations as well as to dewatering operations that were conducted at a nearby facility demolition project.

As described in previous monitoring reports, the average seasonal concentration of PCE reported for groundwater monitoring well MW-2 has been lower since the second quarter of 2006 (June 2006 event) compared to results reported since monitoring began in 1999 (see Figure 6). The PCE concentrations reported for MW-2 since June 2006 are an indication that the phytoremediation project implemented in June 2005 has significantly reduced the average seasonal concentration of PCE at the site.

## 4 Phytoremediation Project Status

A phytoremediation project was implemented at the Site in June 2005. The project involved planting 96 bare-root hybrid poplar trees in a grid on the unpaved portion of the site. Selection of the phytoremediation approach and implementation of the project were described in the report, *Groundwater Monitoring Results, First through Fourth Quarter 2005, Cargill Salt – Alameda Facility, Alameda, California* (Crawford Consulting, Inc., October 20, 2006).

The trees were 4-ft-tall, bare-root poles with no foliage when planted in June 2005. During the first two years of growth, the trees developed foliage and most grew 3 to 10 additional feet in height. Photos comparing the appearance of the trees just after planting in 2005 with photos taken in subsequent years are shown below and on the following pages. After three years, most of the trees had grown to heights of 10 to 25 feet. After five years, most of the trees had grown to heights of 25 to 35 feet. The current height of most of the trees is estimated to range from 35 to 50 feet. In April 2008, seven additional saplings were planted in the rear of the property near monitoring well MW-2. There are currently 101 hybrid poplars at the site (two trees were removed to alleviate overcrowding).

As discussed in Section 3.3 and shown on Figure 6, the PCE concentrations reported for monitoring well MW-2 since June 2006 are an indication that the phytoremediation project has been effective at significantly reducing the average seasonal VOC concentration in groundwater at the site.



Bare-root trees planted in June 2005 - View towards rear of property



June 2007 - View from driveway towards rear of property



September 2009 - View from street towards driveway and rear of property



November 2010 – View from street towards driveway and rear of property  
(compare tree height to photo on previous page)



May 2011 – Same view as above



May 9, 2013 – Same view as previous picture.



September 17, 2015 – Similar view as previous picture.



May 11, 2016 – Similar view as previous picture.



May 11, 2016 – View of the trees from further down the street.



June 2007 - View of front planting strip at Clement Avenue



September 2009 - View of front planting strip at Clement Avenue.  
(Note relative height of gate vs. trees in the pictures above and on next page)



November 2010 – Trees dropping foliage. Also, branches on bottom 6 feet of trunks have been cleared for site visibility.



May 11, 2011 – Same view as above




May 9, 2013 – Same view as previous picture.



May 11, 2016 – Similar view as above.




May 9, 2013 – View from back of property towards the street.



May 11, 2016 – Similar view as above.



September 17, 2015 – View from back of property towards the street.



September 17, 2015 – Panoramic view of property from back of property towards the street.

## Professional Certification

**Groundwater Monitoring Results  
Second Semi-Annual 2017 Monitoring Period  
Cargill Salt – Alameda Facility  
Alameda, California**

This report has been prepared by CRAWFORD CONSULTING, INC. with the professional certification of the California professional geologist whose signature appears below.



Dana C. Johnston  
Project Manager



Mark C. Wheeler  
Principal Geologist  
P.G. 4563

## References

- Alameda County Environmental Health Services, 1999. Letter to Cargill Salt: Groundwater Monitoring Well Installation at 2016 Clement Avenue, Alameda, CA, May 7, 1999.
- Conor Pacific/EFW, 2001. Workplan for Off-Site Characterization, Cargill Salt Alameda Facility, June 18, 2001.
- \_\_\_\_\_, 2002. Off-Site Groundwater Characterization, Cargill Salt – Alameda Facility, Alameda, California, August 21, 2002.
- Crawford Consulting, Inc., 1999. Workplan for Groundwater Characterization and Monitoring Well Installation, 2016 Clement Avenue, Alameda, California, July 7, 1999.
- \_\_\_\_\_, 2001. Groundwater Monitoring Results, First through Fourth Quarter 2000, Cargill Salt – Alameda Facility, Alameda, California, April 11, 2001.
- \_\_\_\_\_, 2002. Groundwater Monitoring Results, First through Fourth Quarter 2001, Cargill Salt – Alameda Facility, Alameda, California, August 14, 2002.
- \_\_\_\_\_, 2003. Groundwater Monitoring Results, First through Fourth Quarter 2002, Cargill Salt – Alameda Facility, Alameda, California, August 13, 2003.
- \_\_\_\_\_, 2004. Groundwater Monitoring Results, First through Fourth Quarter 2003, Cargill Salt – Alameda Facility, Alameda, California, February 27, 2004.
- \_\_\_\_\_, 2005. Groundwater Monitoring Results, First through Fourth Quarter 2004, Cargill Salt – Alameda Facility, Alameda, California, November 7, 2005.
- \_\_\_\_\_, 2006. Groundwater Monitoring Results, First through Fourth Quarter 2005, Cargill Salt – Alameda Facility, Alameda, California, October 20, 2006.
- \_\_\_\_\_, 2006. Groundwater Monitoring Results, First Semi-Annual 2006 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 8, 2006.
- \_\_\_\_\_, 2007. Groundwater Monitoring Results, Second Semi-Annual 2006 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, February 28, 2007
- \_\_\_\_\_, 2007. Groundwater Monitoring Results, First Semi-Annual 2007 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, September 28, 2007.
- \_\_\_\_\_, 2007. Groundwater Monitoring Results, Second Semi-Annual 2007 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, February 28, 2008
- \_\_\_\_\_, 2008. Groundwater Monitoring Results, First Semi-Annual 2008 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, December 22, 2008.
- \_\_\_\_\_, 2008. Groundwater Monitoring Results, Second Semi-Annual 2008 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, March 2, 2009
- \_\_\_\_\_, 2009. Groundwater Monitoring Results, First Semi-Annual 2009 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, September 30, 2009.
- \_\_\_\_\_, 2009. Groundwater Monitoring Results, Second Semi-Annual 2009 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 11, 2009
- \_\_\_\_\_, 2010. Groundwater Monitoring Results, First Semi-Annual 2010 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 12, 2010.
- \_\_\_\_\_, 2010. Groundwater Monitoring Results, Second Semi-Annual 2010 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 12, 2010.

## References (continued)

- \_\_\_\_\_, 2011. Groundwater Monitoring Results, First Semi-Annual 2011 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 11, 2011.
- \_\_\_\_\_, 2011. Groundwater Monitoring Results, Second Semi-Annual 2011 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 14, 2011.
- \_\_\_\_\_, 2012. Groundwater Monitoring Results, First Semi-Annual 2012 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 14, 2012.
- \_\_\_\_\_, 2012. Groundwater Monitoring Results, Second Semi-Annual 2012 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 13, 2012.
- \_\_\_\_\_, 2013. Groundwater Monitoring Results, First Semi-Annual 2013 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 14, 2013.
- \_\_\_\_\_, 2013. Groundwater Monitoring Results, Second Semi-Annual 2013 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 13, 2013, Revised November 20, 2013.
- \_\_\_\_\_, 2014. Groundwater Monitoring Results, First Semi-Annual 2014 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 12, 2014.
- \_\_\_\_\_, 2014. Groundwater Monitoring Results, Second Semi-Annual 2014 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 12, 2014.
- \_\_\_\_\_, 2015. Groundwater Monitoring Results, First Semi-Annual 2015 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 12, 2015.
- \_\_\_\_\_, 2015. Groundwater Monitoring Results, Second Semi-Annual 2015 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, November 12, 2015.
- \_\_\_\_\_, 2016. Groundwater Monitoring Results, First Semi-Annual 2016 Monitoring Period, Cargill Salt – Alameda Facility, Alameda, California, May 13, 2016.
- Crawford Consulting, Inc. and Conor Pacific/EFW, 2000. Groundwater Characterization and Monitoring Well Installation, Cargill Salt – Alameda Facility, Alameda, California, January 31, 2000.
- Groundworks Environmental, Inc. (Groundworks), 1993. Results of Soil Sampling and Workplan for Remedial Activities, Alameda facility, October 19, 1993.
- \_\_\_\_\_, 1995. Soil and Groundwater Investigations and Remedial Activities, July 1993 – September 1994, Cargill Salt – Alameda Facility, Alameda, California, July 31, 1995.
- Hickenbottom, K. S., and Muir, K.S., 1988. Geohydrology and Groundwater-Quality Overview of the East Bay Plain Area, Alameda County, California, 205 (j) Report, prepared for the California Regional Water Quality Control Board, San Francisco Bay Region, by the Alameda County Flood Control and Water Conservation District, June 1988.

## **Limitations**

This report and the evaluations presented herein have been prepared in accordance with generally accepted professional standards and are based solely on the scope of work and services described herein. This report has been prepared solely for the use of Cargill Salt for the purposes noted herein. Any use of this report, in whole or in part, by a third party for other than the purposes noted herein is at such party's sole risk.

Table 1. Groundwater Level Data

Well/ Piezometer	Date	Time	Casing Elevation (feet, MSL)	Depth to Water (feet)	Water Elevation (feet, MSL)	Elev. Change from Last Measurement (feet)
MW-1	11/16/1999	09:56	13.16	3.75	9.41	NA
MW-1	3/30/2000	10:09	13.16	2.81	10.35	0.94
MW-1	5/16/2000	09:43	13.16	3.32	9.84	-0.51
MW-1	7/28/2000	09:11	13.16	3.58	9.58	-0.26
MW-1	11/30/2000	08:36	13.16	3.52	9.64	0.06
MW-1	3/26/2001	08:47	13.16	3.15	10.01	0.37
MW-1	6/25/2001	10:19	13.16	3.53	9.63	-0.38
MW-1	9/28/2001	09:32	13.16	3.96	9.20	-0.43
MW-1	12/17/2001	10:47	13.16	3.23	9.93	0.73
MW-1	3/21/2002	07:28	13.16	2.89	10.27	0.34
MW-1	6/6/2002	08:03	13.16	3.50	9.66	-0.61
MW-1	9/20/2002	08:30	13.16	3.86	9.30	-0.36
MW-1	12/19/2002	08:38	13.16	3.13	10.03	0.73
MW-1	3/4/2003	10:31	13.16	3.08	10.08	0.05
MW-1	6/9/2003	08:32	13.16	3.29	9.87	-0.21
MW-1	9/8/2003	10:02	13.16	3.79	9.37	-0.50
MW-1	12/1/2003	10:16	13.16	3.78	9.38	0.01
MW-1	3/4/2004	09:31	13.16	2.88	10.28	0.90
MW-1	6/2/2004	08:42	13.16	3.45	9.71	-0.57
MW-1	9/14/2004	08:01	13.16	3.87	9.29	-0.42
MW-1	12/8/2004	07:44	13.16	3.23	9.93	0.64
MW-1	3/3/2005	08:07	13.16	2.01	11.15	1.22
MW-1	6/10/2005	07:05	13.16	2.90	10.26	-0.89
MW-1	9/16/2005	08:00	13.16	3.62	9.54	-0.72
MW-1	12/6/2005	08:00	13.16	3.28	9.88	0.34
MW-1	3/10/2006	07:40	13.16	2.28	10.88	1.00
MW-1	6/9/2006	09:45	13.16	3.09	10.07	-0.81
MW-1	9/11/2006	10:24	13.16	3.70	9.46	-0.61
MW-1	12/15/2006	07:34	13.16	2.94	10.22	0.76
MW-1	3/6/2007	09:18	13.16	2.87	10.29	0.07
MW-1	6/15/2007	07:29	13.16	3.30	9.86	-0.43
MW-1	9/11/2007	08:05	13.16	3.85	9.31	-0.55
MW-1	12/4/2007	08:53	13.16	3.58	9.58	0.27
MW-1	3/20/2008	08:13	13.16	3.00	10.16	0.58
MW-1	6/18/2008	08:22	13.16	3.73	9.43	-0.73
MW-1	9/3/2008	08:06	13.16	3.93	9.23	-0.20
MW-1	12/4/2008	08:12	13.16	3.71	9.45	0.22
MW-1	3/5/2009	09:18	13.16	1.83	11.33	1.88
MW-1	6/11/2009	08:40	13.16	3.52	9.64	-1.69
MW-1	9/3/2009	07:57	13.16	3.98	9.18	-0.46
MW-1	3/2/2010	08:10	13.16	2.37	10.79	1.61
MW-1	9/3/2010	07:01	13.16	3.80	9.36	-1.43
MW-1	3/17/2011	08:04	13.16	4.44	8.72	-0.64
MW-1	9/23/2011	07:25	13.16	6.43	6.73	-1.99
MW-1	3/22/2012	07:47	13.16	4.47	8.69	1.96
MW-1	9/17/2012	08:14	13.16	6.66	6.50	-2.19
MW-1	3/6/2013	07:21	13.16	4.98	8.18	1.68
MW-1	9/4/2013	07:46	13.16	6.89	6.27	-1.91
MW-1	3/12/2014	07:45	13.16	5.18	7.98	1.71

Table 1. Groundwater Level Data

Well/ Piezometer	Date	Time	Casing Elevation (feet, MSL)	Depth to Water (feet)	Water Elevation (feet, MSL)	Elev. Change from Last Measurement (feet)
MW-1	9/26/2014	08:00	13.16	7.35	5.81	-2.17
MW-1	3/3/2015	07:50	13.16	3.95	9.21	3.40
MW-1	9/2/2015	08:21	13.16	6.87	6.29	-2.92
MW-1	2/2/2016	08:54	13.16	4.57	8.59	2.30
MW-1	9/29/2016	09:39	13.16	6.14	7.02	-1.57
MW-1	2/3/2017	08:13	13.16	0.76	12.40	5.38
MW-1	8/2/2017	07:42	13.16	3.77	9.39	-3.01
MW-2	11/16/1999	11:15	16.22	5.22	11.00	NA
MW-2	3/30/2000	10:05	16.22	2.80	13.42	2.42
MW-2	5/16/2000	09:35	16.22	4.13	12.09	-1.33
MW-2	7/28/2000	09:17	16.22	4.85	11.37	-0.72
MW-2	11/30/2000	08:32	16.22	4.75	11.47	0.10
MW-2	3/26/2001	08:40	16.22	3.28	12.94	1.47
MW-2	6/25/2001	12:12	16.22	4.75	11.47	-1.47
MW-2	9/28/2001	12:20	16.22	5.41	10.81	-0.66
MW-2	12/17/2001	10:44	16.22	4.07	12.15	1.34
MW-2	3/28/2002	09:37	16.22	3.40	12.82	0.67
MW-2	6/6/2002	08:11	16.22	4.70	11.52	-1.30
MW-2	9/20/2002	08:34	16.22	5.28	10.94	-0.58
MW-2	12/19/2002	08:45	16.22	3.37	12.85	1.91
MW-2	3/4/2003	10:26	16.22	3.11	13.11	0.26
MW-2	6/9/2003	08:31	16.22	4.16	12.06	-1.05
MW-2	9/8/2003	10:08	16.22	5.26	10.96	-1.10
MW-2	12/1/2003	10:20	16.22	5.05	11.17	0.21
MW-2	3/4/2004	09:34	16.22	2.86	13.36	2.19
MW-2	6/2/2004	08:53	16.22	4.47	11.75	-1.61
MW-2	9/14/2004	07:59	16.22	5.26	10.96	-0.79
MW-2	12/8/2004	08:00	16.22	4.20	12.02	1.06
MW-2	3/3/2005	08:04	16.22	1.90	14.32	2.30
MW-2	6/10/2005	07:09	16.22	3.74	12.48	-1.84
MW-2	9/16/2005	08:08	16.22	4.92	11.30	-1.18
MW-2	12/6/2005	10:58	16.22	4.39	11.83	0.53
MW-2	3/10/2006	07:47	16.22	2.13	14.09	2.26
MW-2	6/9/2006	10:03	16.22	3.75	12.47	-1.62
MW-2	9/11/2006	10:22	16.22	4.94	11.28	-1.19
MW-2	12/15/2006	07:32	16.22	4.08	12.14	0.86
MW-2	3/6/2007	09:13	16.22	3.27	12.95	0.81
MW-2	6/15/2007	07:31	16.22	4.57	11.65	-1.30
MW-2	9/11/2007	08:07	16.22	5.60	10.62	-1.03
MW-2	12/4/2007	08:47	16.22	4.99	11.23	0.61
MW-2	3/20/2008	08:17	16.22	3.48	12.74	1.51
MW-2	6/18/2008	08:27	16.22	4.93	11.29	-1.45
MW-2	9/3/2008	08:08	16.22	5.58	10.64	-0.65
MW-2	12/4/2008	08:14	16.22	5.07	11.15	0.51
MW-2	3/5/2009	11:10	16.22	2.30	13.92	2.77
MW-2	6/11/2009	08:41	16.22	4.44	11.78	-2.14
MW-2	9/3/2009	08:01	16.22	5.55	10.67	-1.11
MW-2	3/2/2010	08:12	16.22	2.88	13.34	2.67
MW-2	9/3/2010	07:04	16.22	5.18	11.04	-2.30

Table 1. Groundwater Level Data

Well/ Piezometer	Date	Time	Casing Elevation (feet, MSL)	Depth to Water (feet)	Water Elevation (feet, MSL)	Elev. Change from Last Measurement (feet)
MW-2	3/17/2011	08:08	16.22	3.14	13.08	2.04
MW-2	9/23/2011	07:27	16.22	6.13	10.09	-2.99
MW-2	3/22/2012	07:42	16.22	4.24	11.98	1.89
MW-2	9/17/2012	08:18	16.22	6.77	9.45	-2.53
MW-2	3/6/2013	07:24	16.22	4.15	12.07	2.62
MW-2	9/4/2013	07:40	16.22	NA	NA	NA
MW-2	3/12/2014	07:47	16.22	5.12	11.10	NA
MW-2	9/26/2014	08:08	16.22	7.65	8.57	-2.53
MW-2	3/3/2015	07:52	16.22	3.80	12.42	3.85
MW-2	9/2/2015	08:27	16.22	6.63	9.59	-2.83
MW-2	2/2/2016	08:57	16.22	4.10	12.12	2.53
MW-2	9/29/2016	09:35	16.22	6.73	9.49	-2.63
MW-2	2/3/2017	08:15	16.22	1.90	14.32	4.83
MW-2	8/2/2017	07:45	16.22	5.55	10.67	-3.65
MW-3	11/16/1999	15:43	13.34	4.34	9.00	NA
MW-3	3/30/2000	10:01	13.34	2.77	10.57	1.57
MW-3	5/16/2000	09:46	13.34	3.44	9.90	-0.67
MW-3	7/28/2000	09:05	13.34	3.72	9.62	-0.28
MW-3	11/30/2000	08:34	13.34	3.73	9.61	-0.01
MW-3	3/26/2001	08:54	13.34	3.51	9.83	0.22
MW-3	6/25/2001	10:21	13.34	3.65	9.69	-0.14
MW-3	9/28/2001	09:30	13.34	3.96	9.38	-0.31
MW-3	12/17/2001	10:38	13.34	3.28	10.06	0.68
MW-3	3/21/2002	07:28	13.34	3.10	10.24	0.18
MW-3	6/6/2002	08:07	13.34	3.63	9.71	-0.53
MW-3	9/20/2002	08:25	13.34	3.82	9.52	-0.19
MW-3	12/19/2002	08:42	13.34	3.10	10.24	0.72
MW-3	3/4/2003	10:36	13.34	3.29	10.05	-0.19
MW-3	6/9/2003	08:28	13.34	3.41	9.93	-0.12
MW-3	9/8/2003	10:00	13.34	3.85	9.49	-0.44
MW-3	12/1/2003	10:30	13.34	3.90	9.44	-0.05
MW-3	3/4/2004	09:22	13.34	3.11	10.23	0.79
MW-3	6/2/2004	08:46	13.34	3.53	9.81	-0.42
MW-3	9/14/2004	08:05	13.34	4.07	9.27	-0.54
MW-3	12/8/2004	07:40	13.34	3.73	9.61	0.34
MW-3	3/3/2005	07:53	13.34	2.36	10.98	1.37
MW-3	6/10/2005	07:14	13.34	3.15	10.19	-0.79
MW-3	9/16/2005	08:04	13.34	3.90	9.44	-0.75
MW-3	12/6/2005	08:04	13.34	3.35	9.99	0.55
MW-3	3/10/2006	07:43	13.34	2.89	10.45	0.46
MW-3	6/9/2006	09:33	13.34	3.26	10.08	-0.37
MW-3	9/11/2006	10:19	13.34	3.70	9.64	-0.44
MW-3	12/15/2006	07:37	13.34	3.10	10.24	0.60
MW-3	3/6/2007	09:16	13.34	3.04	10.30	0.06
MW-3	6/15/2007	07:27	13.34	3.60	9.74	-0.56
MW-3	9/11/2007	08:03	13.34	3.87	9.47	-0.27
MW-3	12/4/2007	08:50	13.34	3.62	9.72	0.25
MW-3	3/20/2008	08:15	13.34	3.13	10.21	0.49
MW-3	6/18/2008	08:24	13.34	3.90	9.44	-0.77

Table 1. Groundwater Level Data

Well/ Piezometer	Date	Time	Casing Elevation (feet, MSL)	Depth to Water (feet)	Water Elevation (feet, MSL)	Elev. Change from Last Measurement (feet)
MW-3	9/3/2008	08:02	13.34	3.92	9.42	-0.02
MW-3	12/4/2008	08:10	13.34	3.59	9.75	0.33
MW-3	3/5/2009	09:23	13.34	2.79	10.55	0.80
MW-3	6/11/2009	08:38	13.34	3.14	10.20	-0.35
MW-3	9/3/2009	07:55	13.34	4.31	9.03	-1.17
MW-3	3/2/2010	08:09	13.34	2.94	10.40	1.37
MW-3	9/3/2010	07:07	13.34	3.75	9.59	-0.81
MW-3	3/17/2011	07:59	13.34	4.88	8.46	-1.13
MW-3	9/23/2011	07:23	13.34	6.33	7.01	-1.45
MW-3	3/22/2012	07:45	13.34	5.05	8.29	1.28
MW-3	9/17/2012	08:10	13.34	6.54	6.80	-1.49
MW-3	3/6/2013	07:12	13.34	5.22	8.12	1.32
MW-3	9/4/2013	07:48	13.34	6.58	6.76	-1.36
MW-3	3/12/2014	07:49	13.34	5.33	8.01	1.25
MW-3	9/26/2014	07:50	13.34	NA	NA	NA
MW-3	3/3/2015	07:48	13.34	4.90	8.44	NA
MW-3	9/2/2015	08:18	13.34	7.29	6.05	-2.39
MW-3	2/2/2016	08:52	13.34	4.90	8.44	2.39
MW-3	9/29/2016	09:37	13.34	6.02	7.32	-1.12
MW-3	2/3/2017	08:11	13.34	1.43	11.91	4.59
MW-3	8/2/2017	07:40	13.34	3.62	9.72	-2.19
MW-4	12/17/2001	10:40	12.43	2.55	9.88	NA
MW-4	3/28/2002	08:05	12.43	3.06	9.37	-0.51
MW-4	6/6/2002	07:57	12.43	2.85	9.58	0.21
MW-4	9/20/2002	08:28	12.43	3.21	9.22	-0.36
MW-4	12/19/2002	08:53	12.43	3.70	8.73	-0.49
MW-4	3/4/2003	10:34	12.43	3.14	9.29	0.56
MW-4	6/9/2003	08:29	12.43	2.82	9.61	0.32
MW-4	9/8/2003	10:04	12.43	3.43	9.00	-0.61
MW-4	12/1/2003	10:14	12.43	3.12	9.31	0.31
MW-4	3/4/2004	09:27	12.43	2.81	9.62	0.31
MW-4	6/2/2004	08:44	12.43	3.34	9.09	-0.53
MW-4	9/14/2004	08:03	12.43	3.51	8.92	-0.17
MW-4	12/8/2004	07:36	12.43	3.10	9.33	0.41
MW-4	3/3/2005	07:44	12.43	2.48	9.95	0.62
MW-4	6/10/2005	07:02	12.43	2.47	9.96	0.01
MW-4	9/16/2005	08:12	12.43	3.23	9.20	-0.76
MW-4	12/6/2005	07:50	12.43	3.17	9.26	0.06
MW-4	3/10/2006	07:37	12.43	3.77	8.66	-0.60
MW-4	6/9/2006	07:30	12.43	2.49	9.94	1.28
MW-4	9/11/2006	10:17	12.43	3.19	9.24	-0.70
MW-4	12/21/2006	NR	12.43	2.90	9.53	0.29
MW-4	3/6/2007	09:20	12.43	2.54	9.89	0.36
MW-4	6/15/2007	07:33	12.43	3.03	9.40	-0.49
MW-4	9/11/2007	08:11	12.43	3.27	9.16	-0.24
MW-4	12/4/2007	08:55	12.43	3.25	9.18	0.02
MW-4	3/20/2008	08:20	12.43	2.65	9.78	0.60
MW-4	6/18/2008	08:31	12.43	3.35	9.08	-0.70
MW-4	9/3/2008	07:58	12.43	3.28	9.15	0.07

Table 1. Groundwater Level Data

Well/ Piezometer	Date	Time	Casing Elevation (feet, MSL)	Depth to Water (feet)	Water Elevation (feet, MSL)	Elev. Change from Last Measurement (feet)
MW-4	12/4/2008	08:17	12.43	3.12	9.31	0.16
MW-4	3/5/2009	09:27	12.43	2.16	10.27	0.96
MW-4	6/11/2009	08:43	12.43	2.84	9.59	-0.68
MW-4	9/3/2009	08:04	12.43	3.49	8.94	-0.65
MW-4	3/2/2010	08:14	12.43	2.32	10.11	1.17
MW-4	9/3/2010	07:10	12.43	3.10	9.33	-0.78
MW-4	3/17/2011	07:55	12.43	4.52	7.91	-1.42
MW-4	9/23/2011	07:21	12.43	5.38	7.05	-0.86
MW-4	3/22/2012	07:50	12.43	4.58	7.85	0.80
MW-4	9/17/2012	08:21	12.43	5.45	6.98	-0.87
MW-4	3/6/2013	07:27	12.43	4.65	7.78	0.80
MW-4	9/4/2013	07:58	12.43	5.47	6.96	-0.82
MW-4	3/12/2014	07:52	12.43	9.25	3.18	-3.78
MW-4	9/26/2014	08:14	12.43	5.57	6.86	3.68
MW-4	3/3/2015	07:55	12.43	4.40	8.03	1.17
MW-4	9/2/2015	08:10	12.43	5.56	6.87	-1.16
MW-4	2/2/2016	09:00	12.43	4.05	8.38	1.51
MW-4	9/29/2016	09:41	12.43	4.67	7.76	-0.62
MW-4	2/3/2017	08:18	12.43	2.04	10.39	2.63
MW-4	8/2/2017	07:47	12.43	2.93	9.50	-0.89

**Key:**

NA = Not available

feet, MSL = feet, relative to Mean Sea Level

Casing elevations for all wells were resurveyed on September 6, 2006 by CSS Environmental Services for Geotracker compliance.

**Table 2.**  
Relative Percent Difference Based on Duplicate Samples

Third Quarter 2017			
Analysis	Well MW-2 Results	Duplicate (DUP-1) Results	RPD <sup>1</sup> (%)
<b>Volatile Organic Compounds (µg/L)</b>			
Cis-1,2-Dichloroethene	32	34	6.1
Trichloroethene (TCE)	26	27	3.8
Tetrachloroethene (PCE)	340	340	0
<sup>1</sup> RPD = relative percent difference Results measured in micrograms per liter (µg/L) All other 8010 list analytes not detected (by 8260).			

Table 3a. Summary of Groundwater Monitoring Well Data - Third Quarter 2017

Well No. Field Date	<b>MW-1</b> 8/2/2017	<b>MW-2</b> 8/2/2017	<b>MW-3</b> 8/2/2017	<b>MW-4</b> 8/2/2017	MCL <sup>1</sup>
DCE <sup>2</sup>	<0.5	<0.5	<b>4.7</b>	<0.5	6
DCA <sup>3</sup>	<0.5	<0.5	<0.5	<0.5	5
cis-1,2-DCE <sup>4</sup>	<b>13</b>	<b>32</b>	<0.5	<0.5	6
TCA <sup>5</sup>	<0.5	<0.5	<0.5	<0.5	200
TCE <sup>6</sup>	<b>18</b>	<0.5	<0.5	<0.5	5
PCE <sup>7</sup>	<b>48</b>	<b>340</b>	<0.5	<0.5	5
Other analytes <sup>8</sup>	nd <sup>9</sup>	nd	nd	nd	nd

Notes:

Results measured in micrograms per liter ( $\mu\text{g/L}$ )

<sup>1</sup> MCL = California Primary Drinking Water Standard - Maximum Contaminant Level

<sup>2</sup> DCE = 1,1-Dichloroethene

<sup>3</sup> DCA = 1,1-Dichloroethane

<sup>4</sup> cis-1,2-DCE = cis-1,2-Dichloroethene

<sup>5</sup> TCA = 1,1,1-Trichloroethane

<sup>6</sup> TCE = Trichloroethene

<sup>7</sup> PCE = Tetrachloroethene

<sup>8</sup> All other 8010 list analytes

<sup>9</sup> nd = not detected above laboratory reporting limit

Table 3b. Historical Summary of Groundwater Monitoring Well Data

Results measured in micrograms per liter ( $\mu\text{g/L}$ )

## Notes:

<sup>1</sup> MCL = California Primary Drinking Water Standard - Maximum Contaminant Level  
(in micrograms per liter [ $\mu\text{g}/\text{L}$ ])

<sup>2</sup> DCE = 1,1-Dichloroethene

<sup>3</sup> CFC 113 = Trichlorotrifluoroethane (1,1,2-Trichloro-1,2,2-trifluoroethane)

<sup>4</sup> na = not analyzed

<sup>5</sup> ne = not established or none applic.

<sup>6</sup> DCA ≡ 1,1-Dichloroethane

<sup>7</sup> cis-1,2-DCE = cis-1,2-Dichloroethane

<sup>8</sup> TCA = 1,1,1-Trichloroethane

<sup>9</sup> TCE = Trichloroethene

<sup>10</sup> PCE = Tetrachloroethylene

<sup>11</sup> All thio-8010 literature.

### All other 8010 list analytes

\* Chl = *Chlorotrichum*

<sup>†</sup> Chloroform detected in equip.

Table 3b. Historical Summary of Groundwater Monitoring Well Data

Well No.	MW-1																							MCL <sup>1</sup>					
	Field Date	3/6/07	6/15/07	9/11/07	12/4/07	3/20/08	6/18/08	9/3/08	12/4/08	3/5/09	6/11/09	9/3/09	3/2/10	9/3/10	3/17/11	9/23/11	3/22/12	9/17/12	3/6/13	9/4/13	3/12/14	9/26/14	3/3/15	9/2/15	2/2/16	9/29/16	2/3/17	8/2/17	
DCE <sup>2</sup>		<2.0	<b>3.0</b>	<5.0	<5.0	<2.0	<5.0	<5.0	<5.0	<0.5	<2.5	<10	<5.0	<5.0	<b>6.1</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<b>0.56</b>	<0.5	<0.5	<0.5	<0.5	6	
CFC 113 <sup>3</sup>		<2.0	<2.0	<5.0	<5.0	<2.0	<5.0	<5.0	<5.0	<0.5	<2.5	<10	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<2.0	<0.5	<0.5	<0.5	<0.5	<0.5	ne <sup>5</sup>	
DCA <sup>6</sup>		<2.0	<2.0	<5.0	<5.0	<2.0	<5.0	<5.0	<5.0	<0.5	<2.5	<10	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
Chloroform		<4.0	<4.0	<10	<10	<4.0	<10	<10	<10	<b>1.9</b>	<5.0	<20	<10	<10	<10	<10	<10	<10	<10	<10	<10	<0.5	<1.0	<1.0	<1.0	<1.0	<1.0	ne	
cis-1,2-DCE <sup>7</sup>		<2.0	<2.0	<5.0	<5.0	<2.0	<5.0	<5.0	<5.0	<b>0.62</b>	<2.5	<10	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<b>6.6</b>	<0.5	<b>1.8</b>	<0.5	<b>8.0</b>	<b>13</b>	6
TCA <sup>8</sup>		<2.0	<2.0	<5.0	<5.0	<2.0	<5.0	<5.0	<5.0	<0.5	<2.5	<10	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	200	
TCE <sup>9</sup>		<b>17</b>	<b>38</b>	<b>51</b>	<b>29</b>	<b>18</b>	<b>42</b>	<b>65</b>	<b>42</b>	<b>6.5</b>	<b>40</b>	<b>68</b>	<b>27</b>	<b>57</b>	<b>36</b>	<b>89</b>	<b>40</b>	<b>37</b>	<b>60</b>	<b>19</b>	<b>100</b>	<b>8.6</b>	<b>38</b>	<b>7.6</b>	<b>27</b>	<b>6.9</b>	<b>18</b>	<b>18</b>	5
PCE <sup>10</sup>		<b>170</b>	<b>310</b>	<b>430</b>	<b>330</b>	<b>170</b>	<b>390</b>	<b>620</b>	<b>320</b>	<b>68</b>	<b>300</b>	<b>640</b>	<b>170</b>	<b>420</b>	<b>330</b>	<b>850</b>	<b>350</b>	<b>380</b>	<b>390</b>	<b>190</b>	<b>180</b>	<b>78</b>	<b>130</b>	<b>58</b>	<b>58</b>	<b>48</b>	<b>5.4</b>	<b>48</b>	5
Other analytes <sup>11</sup>		nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	--									

Well No.	MW-2																								MCL <sup>1</sup>				
	Field Date	3/6/07	6/15/07	9/11/07	12/4/07	3/20/08	6/18/08	9/3/08	12/4/08	3/5/09	6/11/09	9/3/09	3/2/10	9/3/10	3/17/11	9/23/11	3/22/12	9/17/12	3/6/13	9/4/13	3/12/14	9/26/14	3/3/15	9/2/15	2/2/16	9/29/16	2/3/17	8/2/17	
DCE <sup>2</sup>		<20	<20	<20	<20	<20	<20	<20	<20	<20	<25	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	na	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<2.5	<0.5	6	
CFC 113 <sup>3</sup>		<20	<20	<20	<20	<20	<20	<20	<20	<20	<25	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	na	<0.5	<2.0	<0.5	<0.5	<0.5	<0.5	<0.5	<10	<0.5	ne <sup>5</sup>
DCA <sup>6</sup>		<20	<20	<20	<20	<20	<20	<20	<20	<20	<25	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	na	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
Chloroform		<40	<40	<40	<40	<40	<40	<40	<40	<40	<40	<50	<10	<10	<10	<1.0	<1.0	<1.0	<1.0	na	<1.0	<0.5	<1.0	<1.0	<1.0	<1.0	<2.5	<1.0	ne
cis-1,2-DCE <sup>7</sup>		<20	<20	<20	<20	<20	<20	<20	<20	<20	<25	<5.0	<b>8.0</b>	<b>6.2</b>	<b>13</b>	<b>1.3</b>	<b>3.8</b>	<0.5	<b>32</b>	na	<b>3.2</b>	<b>0.72</b>	<b>100</b>	<b>9.2</b>	<b>16</b>	<b>2.4</b>	<b>47</b>	<b>32</b>	6
TCA <sup>8</sup>		<20	<20	<20	<20	<20	<20	<20	<20	<20	<25	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	na	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	200	
TCE <sup>9</sup>		<20	<b>22</b>	<b>31</b>	<20	<20	<b>21</b>	<20	<20	<20	<25	<5.0	<b>9.5</b>	<5.0	<b>6.3</b>	<b>0.93</b>	<b>2.3</b>	<0.5	<b>3.3</b>	na	<0.5	<0.5	<b>10</b>	<b>11</b>	<b>24</b>	<b>6.0</b>	<b>31</b>	<b>26</b>	5
PCE <sup>10</sup>		<b>1,600</b>	<b>2,400</b>	<b>1,700</b>	<b>1,100</b>	<b>2,900</b>	<b>1,700</b>	<b>1,600</b>	<b>2,000</b>	<b>2,300</b>	<b>1,500</b>	<b>410</b>	<b>860</b>	<b>180</b>	<b>530</b>	<b>40</b>	<b>120</b>	<b>18</b>	<b>220</b>	na	<b>5.4</b>	<b>11</b>	<b>600</b>	<b>20</b>	<b>25</b>	<b>39</b>	<b>600</b>	<b>340</b>	5
Other analytes <sup>11</sup>		nd	nd	nd	nd	nd	nd	nd	nd	nd	na	nd	nd	nd	nd	nd	nd	nd	--										

## Notes:

<sup>1</sup> MCL = California Primary Drinking Water Standard - Maximum Contaminant Level  
(in micrograms per liter [µg/L])

<sup>2</sup> DCE = 1,1-Dichloroethene

<sup>3</sup> CFC 113 = Trichlorotr

Table 3b. Historical Summary of Groundwater Monitoring Well Data

Results measured in micrograms per liter ( $\mu\text{g/L}$ )

Well No.	MW-3																											
Field Date	11/16/99	3/30/00	5/16/00	7/28/00	11/30/00	3/26/01	6/25/01	9/28/01	12/17/01	3/21/02	6/6/02	9/20/02	12/19/02	3/4/03	6/9/03	9/8/03	12/1/03	3/4/04	6/2/04	9/14/04	12/8/04	3/3/05	6/10/05	9/16/05	12/6/05	3/10/06	6/9/06	MCL <sup>1</sup>
DCE <sup>2</sup>	<0.500	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>0.51</b>	<0.5	<b>0.81</b>	<0.5	<0.5	<b>0.68</b>	<b>2.4</b>	<b>1.5</b>	<b>1.1</b>	<b>0.86</b>	<b>4.3</b>	6		
CFC 113 <sup>3</sup>	na	<0.5	<0.5	<0.5	<1.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	ne <sup>5</sup>		
DCA <sup>6</sup>	<0.500	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>0.50</b>	5	
Chloroform	<0.500	<0.5	<0.5	<0.5	<1.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	ne	
cis-1,2-DCE <sup>7</sup>	<0.500	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	6	
TCA <sup>8</sup>	<0.500	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>1.0</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	200	
TCE <sup>9</sup>	<0.500	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5		
PCE <sup>10</sup>	<0.500	<0.5	<0.5	<b>0.8</b>	<0.5	<0.5	<0.5	<b>0.81</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>0.90</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
Other analytes <sup>11</sup>	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	--		

Well No.	MW-4																											
Field Date	12/17/01	3/28/02	6/6/02	9/20/02	12/19/02	3/4/03	6/9/03	9/8/03	12/1/03	3/4/04	6/2/04	9/14/04	12/8/04	3/3/05	6/10/05	9/16/05	12/6/05	3/10/06	6/9/06	9/11/06	12/21/06	3/6/07	6/15/07	9/11/07	12/4/07	3/20/08	6/18/08	MCL <sup>1</sup>
DCE <sup>2</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	6		
CFC 113 <sup>3</sup>	<2.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	ne <sup>5</sup>		
DCA <sup>6</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5		
Chloroform	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	ne		
cis-1,2-DCE <sup>7</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	6		
TCA <sup>8</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	200		
TCE <sup>9</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5		
PCE <sup>10</sup>	<b>2.6</b>	<b>2.8</b>	<b>2.0</b>	<b>2.5</b>	<b>1.1</b>	<b>2.1</b>	<b>1.6</b>	<b>1.6</b>	<b>1.7</b>	<b>1.4</b>	<b>1.3</b>	<b>1.2</b>	<b>0.93</b>	<b>0.98</b>	<b>0.8</b>	<b>1.1</b>	<b>0.79</b>	<b>0.64</b>	<b>0.70</b>	<b>0.63</b>	<b>0.70</b>	<b>0.75</b>	<b>0.86</b>	<b>0.92</b>	<b>0.91</b>	<b>0.86</b>	5	
Other analytes <sup>11</sup>	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	--														

## Notes:

<sup>1</sup> MCL = California Primary Drinking Water Standard - Maximum Contaminant Level  
(in micrograms per liter [ $\mu\text{g/L}$ ])<sup>2</sup> DCE = 1,1-Dichloroethene<sup>3</sup> CFC 113 = Trichlorotrifluoroethane (1,1,2-Trichloro-1,2,2-trifluoroethane)<sup>4</sup> na = not analyzed<sup>5</sup> ne = not established or none applicable<sup>6</sup> DCA = 1,1-Dichloroethane<sup>7</sup> cis-1,2-DCE = cis-1,2-Dichloroethene

Table 3b. Historical Summary of Groundwater Monitoring Well Data

Well No.	MW-3																													
Field Date	9/11/06	12/15/06	3/6/07	6/15/07	9/11/07	12/4/07	3/20/08	6/18/08	9/3/08	12/4/08	3/5/09	6/11/09	9/3/09	3/2/10	9/3/10	3/17/11	9/23/11	3/22/12	9/17/12	3/6/13	9/4/13	3/12/14	9/26/14	3/3/15	9/2/15	2/2/16	9/29/16	2/3/17	8/2/17	MCL <sup>1</sup>
DCE <sup>2</sup>	<b>2.8</b>	<b>1.6</b>	<b>1.5</b>	<b>2.4</b>	<b>1.4</b>	<b>1.1</b>	<b>1.0</b>	<b>1.4</b>	<b>0.79</b>	<b>0.59</b>	<0.5	<b>0.95</b>	<b>0.51</b>	<0.5	<b>0.64</b>	<b>13</b>	<b>34</b>	<b>45</b>	<b>53</b>	<b>50</b>	<b>43</b>	<b>61</b>	<b>53</b>	<b>45</b>	<b>30</b>	<b>33</b>	<b>29</b>	<0.5	<b>4.7</b>	6
CFC 113 <sup>3</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>0.90</b>	<b>1.4</b>	<b>1.4</b>	<b>1.7</b>	<b>2.2</b>	<b>1.5</b>	<b>2.5</b>	<b>1.8</b>	<b>2.1</b>	<b>1.8</b>	<b>1.3</b>	<b>1.8</b>	<0.5	<0.5	ne <sup>5</sup>
DCA <sup>6</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>0.90</b>	<b>1.4</b>	<b>1.4</b>	<b>1.7</b>	<b>2.2</b>	<b>1.5</b>	<b>2.5</b>	<b>1.8</b>	<b>2.1</b>	<b>1.8</b>	<b>1.3</b>	<b>1.8</b>	<0.5	<0.5	5
Chloroform	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	ne	
cis-1,2-DCE <sup>7</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	6	
TCA <sup>8</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>1.3</b>	<b>1.5</b>	<b>1.5</b>	<b>1.2</b>	<b>1.1</b>	<b>2.5</b>	<b>0.87</b>	<b>0.75</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	200
TCE <sup>9</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
PCE <sup>10</sup>	<0.5	<b>0.56</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<b>1.2</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<b>0.79</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5
Other analytes <sup>11</sup>	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	--		

Well No.	MW-4																									
Field Date	9/3/08	12/4/08	3/5/09	6/11/09	9/3/09	3/2/10	9/3/10	3/17/11	9/23/11	3/22/12	9/17/12	3/6/13	9/4/13	3/12/14	9/26/14	3/3/15	9/2/15	2/2/16	9/29/16	2/3/17	8/2/17	MCL <sup>1</sup>				
DCE <sup>2</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	6	
CFC 113 <sup>3</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	ne <sup>5</sup>	
DCA <sup>6</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
Chloroform	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	ne	
cis-1,2-DCE <sup>7</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	6
TCA <sup>8</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	200
TCE <sup>9</sup>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
PCE <sup>10</sup>	<b>0.84</b>	<b>0.65</b>	<b>0.62</b>	<b>0.70</b>	<b>0.79</b>	<b>0.78</b>	<b>0.64</b>	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	5	
Other analytes <sup>11</sup>	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	--							

## Notes:

<sup>1</sup> MCL = California Primary Drinking Water Standard - Maximum Contaminant Level  
(in micrograms per liter [µg/L])

<sup>2</sup> DCE = 1,1-Dichloroethene



<sup>3</sup> CFC 113 = Trichlorotrifluoroethane (1,1,2-Trichloro-1,2,2-trifluoroethane)

<sup>4</sup> na = not analyzed


<sup>5</sup> ne = not established or none applicable

<sup>6</sup> DCA = 1,1-Dichloroethane

<sup>7</sup> cis



Project No. CS1605  
Cargill Salt Dispensing Systems Division  
2016 Clement Avenue, Alameda, California  
**Figure 1. Site Location**




**MW-4**

Curb line (Typ.)



*Clement Avenue*



#### EXPLANATION

- Groundwater monitoring well
- \* Excavated in February 1994

0 40 Feet  
Approximate Scale

Base map from Conor Pacific/EFW, Off-Site  
Groundwater Characterization, August 21, 2002.


1605fig215Q3.dsf 11/2/16




**CRAWFORD  
CONSULTING  
INC.**

Project No. CS1605  
Cargill Salt Dispensing Systems Division  
2016 Clement Avenue, Alameda, California  
**Figure 2. Groundwater Monitoring Well Locations**

**Figure 3. Graphical Summary of Groundwater Elevations**






1605fig417Q3.dsf 11/8/17



C R A W F O R D  
C O N S U L T I N G  
I N C .


Project No. CS1605  
Cargill Salt Dispensing Systems Division  
2016 Clement Avenue, Alameda, California

**Figure 4. Groundwater Elevation Contours - August 2017**




1605fig517Q3.dsf 11/8/17

**Figure 6. Graphical Summary of PCE Concentrations**



**Figure 7. PCE Concentrations vs. Groundwater Elevation**



**Appendix A**

**Field Data Sheets**

## WATER LEVEL FIELD DATA

Cargill Salt  
 Alameda Facility  
 Alameda, California  
 Project No. CS1605

Well ID	Date	Time	Depth to Water (1st Msmt.) (feet)	Depth to Water (2nd Msmt.) (feet)	Comments
MW-1	8/21/17	0742	3.77	3.77	missing bolts on lid.
MW-2	8/21/17	0745	5.55	5.55	missing bolts on lid
MW-3	8/21/17	0740	3.42	3.42	missing bolts on lid.
MW-4	8/21/17	0747	2.93	2.93	wul box needs to be replaced

### Data Collection

Field measurements by:  
 Print: Manuel Gallegos  
 Signature: M. Gallegos  
 Date: 8-2-17

Reviewed by:  
 Print: JIM BUTERA  
 Signature: J. Butera  
 Date: 8/7/17

# SAMPLE COLLECTION FIELD DATA

Page 1 of 1

Project No.: CS1605  
 Project Name: Alameda Facility  
 Location: Alameda, CA  
 Client: Cargill Salt

Well ID: MW-1  
 Sample ID: MW-1  
 Start Date: 8-2-17  
 Finish Date: 8-2-17

## WELL INFORMATION

Casing diameter (in.): 1.0 Depth to water (ft): 3.75 Well depth (ft): 18.3  
 One casing volume (gal.): 0.59 Calculated purge volume (gal.) ( $3 \times$  casing volume): 1.78  
 $\text{One casing volume} = \pi \times [\text{casing radius (in.)} \times 1 \text{ ft}/12 \text{ in.}]^2 \times [\text{well depth (ft)} - \text{depth to water (ft)}] \times 7.48 \text{ gal}/\text{ft}^3$   
 $\text{Gallons per linear ft for casing diameter of: } 1'' = 0.041 \quad 2'' = 0.16 \quad 4'' = 0.65 \quad 5'' = 1.0 \quad 6'' = 1.5 \quad 8'' = 2.6$   
 Floating product thickness (ft): NP Method for checking: Interface probe  Clear bailer

## WELL PURGING (3.785 liters per 1 gallon)

Date purged: 8-2-17 Start time: 0845 End time: 0917  
 Purging equipment: Submersible pump  Bladder pump  Peristaltic pump   
 PVC bailer  Teflon bailer  Other   
 Purge rate (lpm): 0.2 Well yield (H/L): High  
 Purge water disposal: Drum on site

Time (2400 hr)	Cumulative Vol. Purged (Liters)	pH (units)	EC (mS/cm)	T (°C)	Color (Visual)	Turbidity (NTU)
<u>0855</u>	<u>2.2</u>	<u>6.77</u>	<u>588</u>	<u>18.4</u>	<u>clear</u>	<u>5.3</u>
<u>0904</u>	<u>4.4</u>	<u>6.76</u>	<u>634</u>	<u>18.7</u>	<u>clear</u>	<u>2.5</u>
<u>0917</u>	<u>6.4</u>	<u>6.77</u>	<u>698</u>	<u>18.4</u>	<u>clear</u>	<u>2.0</u>

Total Purged (Liters): 6.4

## WELL SAMPLING

Date sampled: 8-2-17 Start time: 0918 End time: 0920  
 Depth to water (ft) before sampling: 10.90  
 Sampling equipment: Peristaltic pump  Bladder pump  Teflon bailer   
 PVC bailer  Other

Weather conditions: clear sunny Ambient temperature (° F): 61  
 Well condition/Remarks: well box missing bolts

All samples taken

Meter calibration: EC Sea-Me-4 pH \_\_\_\_\_  
 Temperature 25 Turbidity \_\_\_\_\_

Purged and sampled by (print): Manuel Gallegos

Signature: Manuel Gallegos

Reviewed by: B

## SAMPLE COLLECTION FIELD DATA

Page \_\_\_\_\_ of \_\_\_\_\_

Project No.: CS1605  
Project Name: Alameda Facility  
Location: Alameda, CA  
Client: Cargill Salt

Well ID: MW-2  
Sample ID: MW-2  
Start Date: 8-217  
Finish Date: 8-217

## WELL INFORMATION

Casing diameter (in.): 1.0 Depth to water (ft): 5.67 Well depth (ft): 17.5  
 One casing volume (gal.): 0.48 Calculated purge volume (gal.) ( $3 \times$  casing volume): 1.45  
 $\text{One casing volume} = \pi x [\text{casing radius (in.)} x 1 \text{ ft}/12 \text{ in.}]^2 x [\text{well depth (ft)} - \text{depth to water (ft)}] x 7.48 \text{ gal/ft}^3$   
 Gallons per linear ft for casing diameter of:  $1'' = 0.041$     $2'' = 0.16$     $4'' = 0.65$     $5'' = 1.0$     $6'' = 1.5$     $8'' = 2.6$   
 Floating product thickness (ft): NP Method for checking: Interface probe  Clear bailer

#### **WELL PURGING (3.785 liters per 1 gallon)**

Date purged: 8-2-17 Start time: 1045 End time: 1114  
Purging equipment: Submersible pump \_\_\_\_\_ Bladder pump \_\_\_\_\_ Peristaltic pump   
PVC bailer \_\_\_\_\_ Teflon bailer \_\_\_\_\_ Other \_\_\_\_\_  
Purge rate (lpm): 0.17 Well yield (H/L): High  
Purge water disposal: Drum on Sit

Time (2400 hr)	Cumulative Vol. Purged (Liters)	pH (units)	EC (mS/cm)	T (° C)	Color (Visual)	Turbidity (NTU)
1056	1.8	6.85	594	19.2	clear	2.1
1105	3.6	6.50	599	18.8	clear	1.7
1114	5.4	6.50	594	18.8	clear	0.9

Total Purged (Liters):

Date sampled: 8-2-17 Start time: 1117 End time: 1122  
Depth to water (ft) before sampling: NR  
Sampling equipment: Peristaltic pump  Bladder pump \_\_\_\_\_ Teflon bailer \_\_\_\_\_  
PVC bailer  Other

Weather conditions: Sunny, clear Ambient temperature (° F): 66  
Well condition/Remarks: missing bolts on lid

All samples taken  
Unash to get sonder past roots for liquid level @ sample  
a DUR-1

Meter calibration: EC See pH Temperature Turbidity

Purged and sampled by (print): M. Gallagher

Signature: 

Reviewed by: 

# SAMPLE COLLECTION FIELD DATA

Page 1 of 1

Project No.: CS1605  
 Project Name: Alameda Facility  
 Location: Alameda, CA  
 Client: Cargill Salt

Well ID: MW-3  
 Sample ID: MW-3  
 Start Date: 8-2-17  
 Finish Date: 8-2-17

## WELL INFORMATION

Casing diameter (in.): 1.0 Depth to water (ft): 3.59 Well depth (ft): 17.4  
 One casing volume (gal.): 0.57 Calculated purge volume (gal.) ( $3 \times$  casing volume): 1.72  
 $\text{One casing volume} = \pi \times [\text{casing radius (in.)} \times 1 \text{ ft}/12 \text{ in.}]^2 \times [\text{well depth (ft)} - \text{depth to water (ft)}] \times 7.48 \text{ gal/ft}^3$   
 Gallons per linear ft for casing diameter of: 1" = 0.041 2" = 0.16 4" = 0.65 5" = 1.0 6" = 1.5 8" = 2.6  
 Floating product thickness (ft): N/D Method for checking: Interface probe  Clear bailer

## WELL PURGING (3.785 liters per 1 gallon)

Date purged:	<u>8-2-17</u>	Start time:	<u>0932</u>	End time:	<u>1024</u>	
Purging equipment:	Submersible pump	Bladder pump	Peristaltic pump <input checked="" type="checkbox"/>			
Purge rate (lpm):	<u>0.11</u>	Teflon bailed	Other			
Purge water disposal:	<u>Drum on site</u>					
Time (2400 hr)	Cumulative Vol. Purged (Liters)	pH (units)	EC (mS/cm)	T (°C)	Color (Visual)	Turbidity (NTU)
<u>0943</u>	<u>2.1</u>	<u>6.99</u>	<u>535</u>	<u>20.3</u>	<u>Clear</u>	<u>19.4</u>
<u>0954</u>	<u>4.2</u>	<u>7.10</u>	<u>613</u>	<u>19.8</u>	<u>Tan</u>	<u>424.5</u>
<u>1024</u>	<u>6.3</u>	<u>7.18</u>	<u>610</u>	<u>20.3</u>	<u>Clear</u>	<u>9.4</u>
Total Purged (Liters): <u>6.3</u>						

## WELL SAMPLING

Date sampled:	<u>8-2-17</u>	Start time:	<u>1027</u>	End time:	<u>1031</u>
Sampling equipment:	Peristaltic pump <input checked="" type="checkbox"/>	Bladder pump	Teflon bailed		
Well condition/Remarks:	Depth to water (ft) before sampling: <u>NK</u>				
Meter calibration:	EC	<u>See MW-4</u>			
Temperature					
Turbidity					

Weather conditions: Sunny, clear Ambient temperature (° F): 65  
 Well condition/Remarks: missing bolts on lid.  
\* Sand entering during purging from roots in well.  
All samples taken

Meter calibration: EC See MW-4  
 Temperature  Turbidity

Purged and sampled by (print): Manuel Gallegos

Signature: Manuel Gallegos

Reviewed by: JB

# SAMPLE COLLECTION FIELD DATA

Page 1 of 1

Project No.: CS1605  
 Project Name: Alameda Facility  
 Location: Alameda, CA  
 Client: Cargill Salt

Well ID: MW-4  
 Sample ID: MW-4  
 Start Date: 8-2-17  
 Finish Date: 8-2-17

## WELL INFORMATION

Casing diameter (in.): 1.0 Depth to water (ft): 2.92 Well depth (ft): 19.0  
 One casing volume (gal.): 0.65 Calculated purge volume (gal.) ( $3 \times$  casing volume): 1.97  
 $\text{One casing volume} = \pi \times [\text{casing radius (in.)} \times 1 \text{ ft}/12 \text{ in.}]^2 \times [\text{well depth (ft)} - \text{depth to water (ft)}] \times 7.48 \text{ gal/ft}^3$   
 $\text{Gallons per linear ft for casing diameter of: } 1'' = 0.041 \quad 2'' = 0.16 \quad 4'' = 0.65 \quad 5'' = 1.0 \quad 6'' = 1.5 \quad 8'' = 2.6$   
 Floating product thickness (ft): ND Method for checking: Interface probe  Clear bailer

## WELL PURGING (3.785 liters per 1 gallon)

Date purged: 8-2-17 Start time: 0749 End time: 0825  
 Purging equipment: Submersible pump  Bladder pump  Peristaltic pump   
 PVC bailer  Teflon bailer  Other   
 Purge rate (lpm): 0.2 Well yield (H/L): High  
 Purge water disposal: Drum on site

Time (2400 hr)	Cumulative Vol. Purged (Liters)	pH (units)	EC (mS/cm)	T (°C)	Color (Visual)	Turbidity (NTU)
<u>0801</u>	<u>2.4</u>	<u>6.75</u>	<u>395</u>	<u>20.7</u>	<u>Clear</u>	<u>4.0</u>
<u>0813</u>	<u>4.8</u>	<u>6.92</u>	<u>520</u>	<u>20.4</u>	<u>Clear</u>	<u>2.9</u>
<u>0825</u>	<u>7.2</u>	<u>6.95</u>	<u>547</u>	<u>20.7</u>	<u>Clear</u>	<u>2.4</u>

Total Purged (Liters): 7.2

## WELL SAMPLING

Date sampled: 8-2-17 Start time: 0826 End time: 0828  
 Sampling equipment: Peristaltic pump  Bladder pump  Teflon bailer   
 PVC bailer  Other

Weather conditions: Clear Ambient temperature (° F): 61

Well condition/Remarks: Well box needs to be replaced lid crushed

All samples taken

Meter calibration: EC 15,100 - 15,000 pH 6.96-7.00/9.91-10.00/3.81-4.00  
 Temperature 28.9 Turbidity 10.11-16.00

Purged and sampled by (print): Manat Cullagos

Signature: 

Reviewed by:



**Appendix B**

**Groundwater Velocity Calculations**

## APPENDIX B

### GROUNDWATER VELOCITY CALCULATIONS

FOR CARGILL ALAMEDA SITE

#### GROUNDWATER VELOCITY FORMULA

$$V = K i / n \quad \text{where:}$$

$V$  = average linear groundwater velocity       $i$  = hydraulic gradient  
 $K$  = hydraulic conductivity       $n$  = effective porosity

#### PARAMETERS

Range of hydraulic conductivity values ( $K$ ) from slug tests:

Material	Well	$K$ (cm/sec)
Silty sand (SM) and Clayey sand (SC)	MW-1	0.00002
Silty sand (SM) and Clayey sand (SC)	MW-2	0.00002
Silty sand (SM) and Clayey sand (SC)	MW-3	0.000003

Highest measured  $K$  = 0.00002

Porosity ( $n$ ) = 33% (from laboratory analysis of boring B21 soil sample)

Hydraulic gradient ( $i$ ) calculated from groundwater contours:

8/2/2017                    0.011

#### UNIT CONVERSIONS

1 day = 86,400 sec	1 cm/sec = 2,834.65 ft/day
1 foot = 30.48 cm	1 cm/sec = 1,034,645.67 ft/yr

#### CALCULATED VELOCITIES

Measurement Event	Flow Direction	$K$ (cm/sec)	$i$ (ft/ft)	$n$	$V$ (ft/yr)
8/2/2017	NE	0.00002	0.011	0.33	1

Calculations and assumptions prepared by:

*Mark C. Wheeler*

Date: 11/9/2017

## **Appendix C**

### **Certified Analytical Reports and Chain-of-Custody Documentation**

# TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING



## ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Pleasanton

1220 Quarry Lane

Pleasanton, CA 94566

Tel: (925)484-1919

TestAmerica Job ID: 720-81020-1

Client Project/Site: Alameda Facility CS 1605

For:

Crawford Consulting Inc

4 North First Street Suite 650

San Jose, California 95113-1326

Attn: Ms. Dana Johnston

Authorized for release by:

8/7/2017 4:01:15 PM

Paloma Duong, Project Manager I

(925)484-1919

[paloma.duong@testamericainc.com](mailto:paloma.duong@testamericainc.com)

### LINKS

Review your project  
results through

**TotalAccess**

Have a Question?

Ask  
The  
Expert

Visit us at:

[www.testamericainc.com](http://www.testamericainc.com)

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

# Table of Contents

Cover Page .....	1
Table of Contents .....	2
Definitions/Glossary .....	3
Case Narrative .....	4
Detection Summary .....	5
Client Sample Results .....	6
QC Sample Results .....	12
QC Association Summary .....	22
Lab Chronicle .....	23
Certification Summary .....	24
Method Summary .....	25
Sample Summary .....	26
Chain of Custody .....	27
Receipt Checklists .....	28

# Definitions/Glossary

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Qualifiers

### GC/MS VOA

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
E	Result exceeded calibration range.

## Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
□	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

# Case Narrative

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Job ID: 720-81020-1**

**Laboratory: TestAmerica Pleasanton**

## Narrative

### Job Narrative 720-81020-1

## Comments

No additional comments.

## Receipt

The samples were received on 8/2/2017 12:45 PM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 4.3° C.

## GC/MS VOA

Method 8260B: Due to the high concentration of Tetrachloroethene, the matrix spike / matrix spike duplicate (MS/MSD) for analytical batch 720-227775 could not be evaluated for accuracy and precision. The associated laboratory control sample (LCS) met acceptance criteria.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

## Detection Summary

Client: Crawford Consulting Inc  
 Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

### Client Sample ID: MW-1

### Lab Sample ID: 720-81020-1

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
cis-1,2-Dichloroethene	13		0.50		ug/L	1		8260B	Total/NA
Trichloroethene	18		0.50		ug/L	1		8260B	Total/NA
Tetrachloroethene	48		0.50		ug/L	1		8260B	Total/NA

### Client Sample ID: MW-2

### Lab Sample ID: 720-81020-2

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
cis-1,2-Dichloroethene	32		0.50		ug/L	1		8260B	Total/NA
Trichloroethene	26		0.50		ug/L	1		8260B	Total/NA
Tetrachloroethene	340		5.0		ug/L	10		8260B	Total/NA

### Client Sample ID: MW-3

### Lab Sample ID: 720-81020-3

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
1,1-Dichloroethene	4.7		0.50		ug/L	1		8260B	Total/NA

### Client Sample ID: MW-4

### Lab Sample ID: 720-81020-4

No Detections.

### Client Sample ID: DUP-1

### Lab Sample ID: 720-81020-5

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
cis-1,2-Dichloroethene	34		0.50		ug/L	1		8260B	Total/NA
Trichloroethene	27		0.50		ug/L	1		8260B	Total/NA
Tetrachloroethene	340		5.0		ug/L	10		8260B	Total/NA

### Client Sample ID: TB-1

### Lab Sample ID: 720-81020-6

No Detections.

This Detection Summary does not include radiochemical test results.

TestAmerica Pleasanton

# Client Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Client Sample ID: MW-1**

Date Collected: 08/02/17 09:18

Date Received: 08/02/17 12:45

**Lab Sample ID: 720-81020-1**

Matrix: Water

**Method: 8260B - Volatile Organic Compounds (GC/MS)**

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1-Dichloroethene	ND		0.50		ug/L			08/04/17 01:55	1
1,1-Dichloroethane	ND		0.50		ug/L			08/04/17 01:55	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/04/17 01:55	1
Vinyl chloride	ND		0.50		ug/L			08/04/17 01:55	1
Chloroethane	ND		1.0		ug/L			08/04/17 01:55	1
Trichlorofluoromethane	ND		1.0		ug/L			08/04/17 01:55	1
Methylene Chloride	ND		5.0		ug/L			08/04/17 01:55	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/04/17 01:55	1
<b>cis-1,2-Dichloroethene</b>	<b>13</b>		0.50		ug/L			08/04/17 01:55	1
Chloroform	ND		1.0		ug/L			08/04/17 01:55	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/04/17 01:55	1
Carbon tetrachloride	ND		0.50		ug/L			08/04/17 01:55	1
1,2-Dichloroethane	ND		0.50		ug/L			08/04/17 01:55	1
<b>Trichloroethene</b>	<b>18</b>		0.50		ug/L			08/04/17 01:55	1
1,2-Dichloropropane	ND		0.50		ug/L			08/04/17 01:55	1
Dichlorobromomethane	ND		0.50		ug/L			08/04/17 01:55	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/04/17 01:55	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/04/17 01:55	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/04/17 01:55	1
<b>Tetrachloroethene</b>	<b>48</b>		0.50		ug/L			08/04/17 01:55	1
Chlorodibromomethane	ND		0.50		ug/L			08/04/17 01:55	1
Chlorobenzene	ND		0.50		ug/L			08/04/17 01:55	1
Bromoform	ND		1.0		ug/L			08/04/17 01:55	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/04/17 01:55	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/04/17 01:55	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/04/17 01:55	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/04/17 01:55	1
Chloromethane	ND		1.0		ug/L			08/04/17 01:55	1
Bromomethane	ND		1.0		ug/L			08/04/17 01:55	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/04/17 01:55	1
EDB	ND		0.50		ug/L			08/04/17 01:55	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/04/17 01:55	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	96		70 - 130		08/04/17 01:55	1
4-Bromofluorobenzene	92		67 - 130		08/04/17 01:55	1
1,2-Dichloroethane-d4 (Surr)	99		72 - 130		08/04/17 01:55	1

# Client Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Client Sample ID: MW-2**

Date Collected: 08/02/17 11:17

Date Received: 08/02/17 12:45

**Lab Sample ID: 720-81020-2**

Matrix: Water

**Method: 8260B - Volatile Organic Compounds (GC/MS)**

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1-Dichloroethene	ND		0.50		ug/L			08/03/17 22:42	1
1,1-Dichloroethane	ND		0.50		ug/L			08/03/17 22:42	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/03/17 22:42	1
Vinyl chloride	ND		0.50		ug/L			08/03/17 22:42	1
Chloroethane	ND		1.0		ug/L			08/03/17 22:42	1
Trichlorofluoromethane	ND		1.0		ug/L			08/03/17 22:42	1
Methylene Chloride	ND		5.0		ug/L			08/03/17 22:42	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 22:42	1
<b>cis-1,2-Dichloroethene</b>	<b>32</b>		0.50		ug/L			08/03/17 22:42	1
Chloroform	ND		1.0		ug/L			08/03/17 22:42	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/03/17 22:42	1
Carbon tetrachloride	ND		0.50		ug/L			08/03/17 22:42	1
1,2-Dichloroethane	ND		0.50		ug/L			08/03/17 22:42	1
<b>Trichloroethene</b>	<b>26</b>		0.50		ug/L			08/03/17 22:42	1
1,2-Dichloropropane	ND		0.50		ug/L			08/03/17 22:42	1
Dichlorobromomethane	ND		0.50		ug/L			08/03/17 22:42	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 22:42	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 22:42	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/03/17 22:42	1
<b>Tetrachloroethene</b>	<b>340</b>		5.0		ug/L			08/04/17 15:52	10
Chlorodibromomethane	ND		0.50		ug/L			08/03/17 22:42	1
Chlorobenzene	ND		0.50		ug/L			08/03/17 22:42	1
Bromoform	ND		1.0		ug/L			08/03/17 22:42	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/03/17 22:42	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/03/17 22:42	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/03/17 22:42	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/03/17 22:42	1
Chloromethane	ND		1.0		ug/L			08/03/17 22:42	1
Bromomethane	ND		1.0		ug/L			08/03/17 22:42	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/03/17 22:42	1
EDB	ND		0.50		ug/L			08/03/17 22:42	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/03/17 22:42	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	100		70 - 130		08/03/17 22:42	1
Toluene-d8 (Surr)	97		70 - 130		08/04/17 15:52	10
4-Bromofluorobenzene	97		67 - 130		08/03/17 22:42	1
4-Bromofluorobenzene	100		67 - 130		08/04/17 15:52	10
1,2-Dichloroethane-d4 (Surr)	101		72 - 130		08/03/17 22:42	1
1,2-Dichloroethane-d4 (Surr)	101		72 - 130		08/04/17 15:52	10

TestAmerica Pleasanton

# Client Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Client Sample ID: MW-3**

Date Collected: 08/02/17 10:27

Date Received: 08/02/17 12:45

**Lab Sample ID: 720-81020-3**

Matrix: Water

**Method: 8260B - Volatile Organic Compounds (GC/MS)**

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
<b>1,1-Dichloroethene</b>	<b>4.7</b>		0.50		ug/L			08/03/17 23:12	1
1,1-Dichloroethane	ND		0.50		ug/L			08/03/17 23:12	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/03/17 23:12	1
Vinyl chloride	ND		0.50		ug/L			08/03/17 23:12	1
Chloroethane	ND		1.0		ug/L			08/03/17 23:12	1
Trichlorofluoromethane	ND		1.0		ug/L			08/03/17 23:12	1
Methylene Chloride	ND		5.0		ug/L			08/03/17 23:12	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 23:12	1
cis-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 23:12	1
Chloroform	ND		1.0		ug/L			08/03/17 23:12	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/03/17 23:12	1
Carbon tetrachloride	ND		0.50		ug/L			08/03/17 23:12	1
1,2-Dichloroethane	ND		0.50		ug/L			08/03/17 23:12	1
Trichloroethene	ND		0.50		ug/L			08/03/17 23:12	1
1,2-Dichloropropane	ND		0.50		ug/L			08/03/17 23:12	1
Dichlorobromomethane	ND		0.50		ug/L			08/03/17 23:12	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 23:12	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 23:12	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/03/17 23:12	1
Tetrachloroethene	ND		0.50		ug/L			08/03/17 23:12	1
Chlorodibromomethane	ND		0.50		ug/L			08/03/17 23:12	1
Chlorobenzene	ND		0.50		ug/L			08/03/17 23:12	1
Bromoform	ND		1.0		ug/L			08/03/17 23:12	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/03/17 23:12	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/03/17 23:12	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/03/17 23:12	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/03/17 23:12	1
Chloromethane	ND		1.0		ug/L			08/03/17 23:12	1
Bromomethane	ND		1.0		ug/L			08/03/17 23:12	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/03/17 23:12	1
EDB	ND		0.50		ug/L			08/03/17 23:12	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/03/17 23:12	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	99		70 - 130		08/03/17 23:12	1
4-Bromofluorobenzene	98		67 - 130		08/03/17 23:12	1
1,2-Dichloroethane-d4 (Surr)	101		72 - 130		08/03/17 23:12	1

# Client Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Client Sample ID: MW-4**

Date Collected: 08/02/17 08:26

Date Received: 08/02/17 12:45

**Lab Sample ID: 720-81020-4**

Matrix: Water

**Method: 8260B - Volatile Organic Compounds (GC/MS)**

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1-Dichloroethene	ND		0.50		ug/L			08/03/17 23:42	1
1,1-Dichloroethane	ND		0.50		ug/L			08/03/17 23:42	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/03/17 23:42	1
Vinyl chloride	ND		0.50		ug/L			08/03/17 23:42	1
Chloroethane	ND		1.0		ug/L			08/03/17 23:42	1
Trichlorofluoromethane	ND		1.0		ug/L			08/03/17 23:42	1
Methylene Chloride	ND		5.0		ug/L			08/03/17 23:42	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 23:42	1
cis-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 23:42	1
Chloroform	ND		1.0		ug/L			08/03/17 23:42	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/03/17 23:42	1
Carbon tetrachloride	ND		0.50		ug/L			08/03/17 23:42	1
1,2-Dichloroethane	ND		0.50		ug/L			08/03/17 23:42	1
Trichloroethene	ND		0.50		ug/L			08/03/17 23:42	1
1,2-Dichloropropane	ND		0.50		ug/L			08/03/17 23:42	1
Dichlorobromomethane	ND		0.50		ug/L			08/03/17 23:42	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 23:42	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 23:42	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/03/17 23:42	1
Tetrachloroethene	ND		0.50		ug/L			08/03/17 23:42	1
Chlorodibromomethane	ND		0.50		ug/L			08/03/17 23:42	1
Chlorobenzene	ND		0.50		ug/L			08/03/17 23:42	1
Bromoform	ND		1.0		ug/L			08/03/17 23:42	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/03/17 23:42	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/03/17 23:42	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/03/17 23:42	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/03/17 23:42	1
Chloromethane	ND		1.0		ug/L			08/03/17 23:42	1
Bromomethane	ND		1.0		ug/L			08/03/17 23:42	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/03/17 23:42	1
EDB	ND		0.50		ug/L			08/03/17 23:42	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/03/17 23:42	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	99		70 - 130		08/03/17 23:42	1
4-Bromofluorobenzene	96		67 - 130		08/03/17 23:42	1
1,2-Dichloroethane-d4 (Surr)	98		72 - 130		08/03/17 23:42	1

# Client Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Client Sample ID: DUP-1**

Date Collected: 08/02/17 00:00

Date Received: 08/02/17 12:45

**Lab Sample ID: 720-81020-5**

Matrix: Water

**Method: 8260B - Volatile Organic Compounds (GC/MS)**

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1-Dichloroethene	ND		0.50		ug/L			08/04/17 00:12	1
1,1-Dichloroethane	ND		0.50		ug/L			08/04/17 00:12	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/04/17 00:12	1
Vinyl chloride	ND		0.50		ug/L			08/04/17 00:12	1
Chloroethane	ND		1.0		ug/L			08/04/17 00:12	1
Trichlorofluoromethane	ND		1.0		ug/L			08/04/17 00:12	1
Methylene Chloride	ND		5.0		ug/L			08/04/17 00:12	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/04/17 00:12	1
<b>cis-1,2-Dichloroethene</b>	<b>34</b>		0.50		ug/L			08/04/17 00:12	1
Chloroform	ND		1.0		ug/L			08/04/17 00:12	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/04/17 00:12	1
Carbon tetrachloride	ND		0.50		ug/L			08/04/17 00:12	1
1,2-Dichloroethane	ND		0.50		ug/L			08/04/17 00:12	1
<b>Trichloroethene</b>	<b>27</b>		0.50		ug/L			08/04/17 00:12	1
1,2-Dichloropropane	ND		0.50		ug/L			08/04/17 00:12	1
Dichlorobromomethane	ND		0.50		ug/L			08/04/17 00:12	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/04/17 00:12	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/04/17 00:12	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/04/17 00:12	1
<b>Tetrachloroethene</b>	<b>340</b>		5.0		ug/L			08/04/17 16:48	10
Chlorodibromomethane	ND		0.50		ug/L			08/04/17 00:12	1
Chlorobenzene	ND		0.50		ug/L			08/04/17 00:12	1
Bromoform	ND		1.0		ug/L			08/04/17 00:12	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/04/17 00:12	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/04/17 00:12	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/04/17 00:12	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/04/17 00:12	1
Chloromethane	ND		1.0		ug/L			08/04/17 00:12	1
Bromomethane	ND		1.0		ug/L			08/04/17 00:12	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/04/17 00:12	1
EDB	ND		0.50		ug/L			08/04/17 00:12	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/04/17 00:12	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	98		70 - 130		08/04/17 00:12	1
Toluene-d8 (Surr)	95		70 - 130		08/04/17 16:48	10
4-Bromofluorobenzene	96		67 - 130		08/04/17 00:12	1
4-Bromofluorobenzene	95		67 - 130		08/04/17 16:48	10
1,2-Dichloroethane-d4 (Surr)	100		72 - 130		08/04/17 00:12	1
1,2-Dichloroethane-d4 (Surr)	89		72 - 130		08/04/17 16:48	10

TestAmerica Pleasanton

# Client Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

**Client Sample ID: TB-1**

**Date Collected: 08/02/17 00:00**

**Date Received: 08/02/17 12:45**

**Lab Sample ID: 720-81020-6**

**Matrix: Water**

**Method: 8260B - Volatile Organic Compounds (GC/MS)**

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1-Dichloroethene	ND		0.50		ug/L			08/04/17 00:42	1
1,1-Dichloroethane	ND		0.50		ug/L			08/04/17 00:42	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/04/17 00:42	1
Vinyl chloride	ND		0.50		ug/L			08/04/17 00:42	1
Chloroethane	ND		1.0		ug/L			08/04/17 00:42	1
Trichlorofluoromethane	ND		1.0		ug/L			08/04/17 00:42	1
Methylene Chloride	ND		5.0		ug/L			08/04/17 00:42	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/04/17 00:42	1
cis-1,2-Dichloroethene	ND		0.50		ug/L			08/04/17 00:42	1
Chloroform	ND		1.0		ug/L			08/04/17 00:42	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/04/17 00:42	1
Carbon tetrachloride	ND		0.50		ug/L			08/04/17 00:42	1
1,2-Dichloroethane	ND		0.50		ug/L			08/04/17 00:42	1
Trichloroethene	ND		0.50		ug/L			08/04/17 00:42	1
1,2-Dichloropropane	ND		0.50		ug/L			08/04/17 00:42	1
Dichlorobromomethane	ND		0.50		ug/L			08/04/17 00:42	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/04/17 00:42	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/04/17 00:42	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/04/17 00:42	1
Tetrachloroethene	ND		0.50		ug/L			08/04/17 00:42	1
Chlorodibromomethane	ND		0.50		ug/L			08/04/17 00:42	1
Chlorobenzene	ND		0.50		ug/L			08/04/17 00:42	1
Bromoform	ND		1.0		ug/L			08/04/17 00:42	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/04/17 00:42	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/04/17 00:42	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/04/17 00:42	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/04/17 00:42	1
Chloromethane	ND		1.0		ug/L			08/04/17 00:42	1
Bromomethane	ND		1.0		ug/L			08/04/17 00:42	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/04/17 00:42	1
EDB	ND		0.50		ug/L			08/04/17 00:42	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/04/17 00:42	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	98		70 - 130		08/04/17 00:42	1
4-Bromofluorobenzene	96		67 - 130		08/04/17 00:42	1
1,2-Dichloroethane-d4 (Surr)	99		72 - 130		08/04/17 00:42	1

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS)

**Lab Sample ID:** MB 720-227775/4

**Matrix:** Water

**Analysis Batch:** 227775

**Client Sample ID:** Method Blank  
**Prep Type:** Total/NA

Analyte	MB	MB	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
1,1-Dichloroethene	ND		0.50		ug/L			08/03/17 19:42	1
1,1-Dichloroethane	ND		0.50		ug/L			08/03/17 19:42	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/03/17 19:42	1
Vinyl chloride	ND		0.50		ug/L			08/03/17 19:42	1
Chloroethane	ND		1.0		ug/L			08/03/17 19:42	1
Trichlorofluoromethane	ND		1.0		ug/L			08/03/17 19:42	1
Methylene Chloride	ND		5.0		ug/L			08/03/17 19:42	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 19:42	1
cis-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 19:42	1
Chloroform	ND		1.0		ug/L			08/03/17 19:42	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/03/17 19:42	1
Carbon tetrachloride	ND		0.50		ug/L			08/03/17 19:42	1
1,2-Dichloroethane	ND		0.50		ug/L			08/03/17 19:42	1
Trichloroethene	ND		0.50		ug/L			08/03/17 19:42	1
1,2-Dichloropropane	ND		0.50		ug/L			08/03/17 19:42	1
Dichlorobromomethane	ND		0.50		ug/L			08/03/17 19:42	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 19:42	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 19:42	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/03/17 19:42	1
Tetrachloroethene	ND		0.50		ug/L			08/03/17 19:42	1
Chlorodibromomethane	ND		0.50		ug/L			08/03/17 19:42	1
Chlorobenzene	ND		0.50		ug/L			08/03/17 19:42	1
Bromoform	ND		1.0		ug/L			08/03/17 19:42	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/03/17 19:42	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/03/17 19:42	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/03/17 19:42	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/03/17 19:42	1
Chloromethane	ND		1.0		ug/L			08/03/17 19:42	1
Bromomethane	ND		1.0		ug/L			08/03/17 19:42	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/03/17 19:42	1
EDB	ND		0.50		ug/L			08/03/17 19:42	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/03/17 19:42	1

Surrogate	MB	MB	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
	Result	Qualifier						
Toluene-d8 (Surr)	100		70 - 130				08/03/17 19:42	1
4-Bromofluorobenzene	99		67 - 130				08/03/17 19:42	1
1,2-Dichloroethane-d4 (Surr)	101		72 - 130				08/03/17 19:42	1

**Lab Sample ID:** LCS 720-227775/5

**Matrix:** Water

**Analysis Batch:** 227775

**Client Sample ID:** Lab Control Sample  
**Prep Type:** Total/NA

Analyte	Spike	LCS	LCS	Unit	D	%Rec	Limits
	Added	Result	Qualifier				
1,1-Dichloroethene	25.0	23.9		ug/L		96	64 - 128
1,1-Dichloroethane	25.0	25.6		ug/L		102	70 - 130
Dichlorodifluoromethane	25.0	23.1		ug/L		92	32 - 158
Vinyl chloride	25.0	24.6		ug/L		99	54 - 135
Chloroethane	25.0	24.0		ug/L		96	62 - 138

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: LCS 720-227775/5**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: Lab Control Sample**  
**Prep Type: Total/NA**

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec.	Limits
Trichlorofluoromethane	25.0	24.4		ug/L		98	66 - 132	
Methylene Chloride	25.0	26.6		ug/L		106	70 - 147	
trans-1,2-Dichloroethene	25.0	25.6		ug/L		102	68 - 130	
cis-1,2-Dichloroethene	25.0	25.5		ug/L		102	70 - 130	
Chloroform	25.0	25.7		ug/L		103	70 - 130	
1,1,1-Trichloroethane	25.0	25.4		ug/L		102	70 - 130	
Carbon tetrachloride	25.0	25.3		ug/L		101	70 - 146	
1,2-Dichloroethane	25.0	24.5		ug/L		98	61 - 132	
Trichloroethene	25.0	25.7		ug/L		103	70 - 130	
1,2-Dichloropropane	25.0	26.0		ug/L		104	70 - 130	
Dichlorobromomethane	25.0	26.6		ug/L		106	70 - 130	
trans-1,3-Dichloropropene	25.0	26.3		ug/L		105	70 - 140	
cis-1,3-Dichloropropene	25.0	26.6		ug/L		107	70 - 130	
1,1,2-Trichloroethane	25.0	26.0		ug/L		104	70 - 130	
Tetrachloroethene	25.0	25.6		ug/L		103	70 - 130	
Chlorodibromomethane	25.0	26.0		ug/L		104	70 - 145	
Chlorobenzene	25.0	26.4		ug/L		106	70 - 130	
Bromoform	25.0	25.1		ug/L		101	68 - 136	
1,1,2,2-Tetrachloroethane	25.0	24.6		ug/L		98	70 - 130	
1,3-Dichlorobenzene	25.0	25.5		ug/L		102	70 - 130	
1,4-Dichlorobenzene	25.0	25.9		ug/L		104	70 - 130	
1,2-Dichlorobenzene	25.0	25.5		ug/L		102	70 - 130	
Chloromethane	25.0	22.8		ug/L		91	52 - 175	
Bromomethane	25.0	25.0		ug/L		100	43 - 151	
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	25.5		ug/L		102	42 - 162	
EDB	25.0	25.3		ug/L		101	70 - 130	
1,2,4-Trichlorobenzene	25.0	26.3		ug/L		105	70 - 130	

**LCS LCS**

Surrogate	%Recovery	Qualifier	Limits
Toluene-d8 (Surr)	102		70 - 130
4-Bromofluorobenzene	101		67 - 130
1,2-Dichloroethane-d4 (Surr)	96		72 - 130

**Lab Sample ID: LCSD 720-227775/6**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: Lab Control Sample Dup**  
**Prep Type: Total/NA**

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec.	RPD	RPD Limit
1,1-Dichloroethene	25.0	24.3		ug/L		97	64 - 128	2	20
1,1-Dichloroethane	25.0	25.7		ug/L		103	70 - 130	1	20
Dichlorodifluoromethane	25.0	22.6		ug/L		90	32 - 158	2	20
Vinyl chloride	25.0	24.8		ug/L		99	54 - 135	1	20
Chloroethane	25.0	24.4		ug/L		98	62 - 138	2	20
Trichlorofluoromethane	25.0	24.0		ug/L		96	66 - 132	2	20
Methylene Chloride	25.0	26.8		ug/L		107	70 - 147	1	20
trans-1,2-Dichloroethene	25.0	25.9		ug/L		104	68 - 130	1	20
cis-1,2-Dichloroethene	25.0	25.5		ug/L		102	70 - 130	0	20

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: LCSD 720-227775/6**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: Lab Control Sample Dup**  
**Prep Type: Total/NA**

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	Limits	RPD	RPD Limit
Chloroform	25.0	25.9		ug/L		104	70 - 130	1	20
1,1,1-Trichloroethane	25.0	26.1		ug/L		105	70 - 130	3	20
Carbon tetrachloride	25.0	25.5		ug/L		102	70 - 146	1	20
1,2-Dichloroethane	25.0	24.5		ug/L		98	61 - 132	0	20
Trichloroethylene	25.0	25.8		ug/L		103	70 - 130	0	20
1,2-Dichloropropane	25.0	26.0		ug/L		104	70 - 130	0	20
Dichlorobromomethane	25.0	26.7		ug/L		107	70 - 130	0	20
trans-1,3-Dichloropropene	25.0	26.6		ug/L		106	70 - 140	1	20
cis-1,3-Dichloropropene	25.0	27.1		ug/L		108	70 - 130	2	20
1,1,2-Trichloroethane	25.0	26.1		ug/L		104	70 - 130	0	20
Tetrachloroethylene	25.0	25.7		ug/L		103	70 - 130	0	20
Chlorodibromomethane	25.0	26.1		ug/L		104	70 - 145	0	20
Chlorobenzene	25.0	26.4		ug/L		106	70 - 130	0	20
Bromoform	25.0	25.2		ug/L		101	68 - 136	0	20
1,1,2,2-Tetrachloroethane	25.0	24.9		ug/L		99	70 - 130	1	20
1,3-Dichlorobenzene	25.0	25.7		ug/L		103	70 - 130	1	20
1,4-Dichlorobenzene	25.0	25.9		ug/L		104	70 - 130	0	20
1,2-Dichlorobenzene	25.0	25.6		ug/L		102	70 - 130	0	20
Chloromethane	25.0	22.8		ug/L		91	52 - 175	0	20
Bromomethane	25.0	25.2		ug/L		101	43 - 151	1	20
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	25.7		ug/L		103	42 - 162	1	20
EDB	25.0	25.5		ug/L		102	70 - 130	1	20
1,2,4-Trichlorobenzene	25.0	26.3		ug/L		105	70 - 130	0	20

**LCSD LCSD**

**%Recovery Qualifier Limits**

Toluene-d8 (Surr)	101		70 - 130
4-Bromofluorobenzene	101		67 - 130
1,2-Dichloroethane-d4 (Surr)	97		72 - 130

**Lab Sample ID: 720-81020-2 MS**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: MW-2**

**Prep Type: Total/NA**

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	Limits
1,1-Dichloroethene	ND		25.0	23.6		ug/L		94	60 - 140
1,1-Dichloroethane	ND		25.0	25.6		ug/L		102	60 - 140
Dichlorodifluoromethane	ND		25.0	23.2		ug/L		93	38 - 140
Vinyl chloride	ND		25.0	25.4		ug/L		102	58 - 140
Chloroethane	ND		25.0	24.7		ug/L		99	51 - 140
Trichlorofluoromethane	ND		25.0	25.1		ug/L		100	60 - 140
Methylene Chloride	ND		25.0	25.6		ug/L		102	40 - 140
trans-1,2-Dichloroethene	ND		25.0	25.4		ug/L		102	60 - 140
cis-1,2-Dichloroethene	32		25.0	57.2		ug/L		100	60 - 140
Chloroform	ND		25.0	26.1		ug/L		104	60 - 140
1,1,1-Trichloroethane	ND		25.0	26.0		ug/L		104	60 - 140
Carbon tetrachloride	ND		25.0	25.7		ug/L		103	60 - 140
1,2-Dichloroethane	ND		25.0	24.9		ug/L		100	60 - 140

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: 720-81020-2 MS**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: MW-2**

**Prep Type: Total/NA**

Analyte	Sample	Sample	Spike	MS	MS	Unit	D	%Rec	%Rec.
	Result	Qualifier	Added	Result	Qualifier				
Trichloroethene	26		25.0	51.2		ug/L		100	60 - 140
1,2-Dichloropropane	ND		25.0	26.5		ug/L		106	60 - 140
Dichlorobromomethane	ND		25.0	27.1		ug/L		108	60 - 140
trans-1,3-Dichloropropene	ND		25.0	25.9		ug/L		104	60 - 140
cis-1,3-Dichloropropene	ND		25.0	26.4		ug/L		105	60 - 140
1,1,2-Trichloroethane	ND		25.0	26.7		ug/L		107	60 - 140
Tetrachloroethene	320	E	25.0	340	E 4	ug/L		62	60 - 140
Chlorodibromomethane	ND		25.0	26.8		ug/L		107	60 - 140
Chlorobenzene	ND		25.0	26.3		ug/L		105	60 - 140
Bromoform	ND		25.0	25.8		ug/L		103	56 - 140
1,1,2,2-Tetrachloroethane	ND		25.0	26.3		ug/L		105	60 - 140
1,3-Dichlorobenzene	ND		25.0	25.6		ug/L		102	60 - 140
1,4-Dichlorobenzene	ND		25.0	25.8		ug/L		103	60 - 140
1,2-Dichlorobenzene	ND		25.0	26.3		ug/L		105	60 - 140
Chloromethane	ND		25.0	23.3		ug/L		93	52 - 140
Bromomethane	ND		25.0	24.7		ug/L		99	23 - 140
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		25.0	25.0		ug/L		100	60 - 140
EDB	ND		25.0	26.1		ug/L		104	60 - 140
1,2,4-Trichlorobenzene	ND		25.0	24.7		ug/L		99	60 - 140
<hr/>									
Surrogate	MS	MS	Limits	%Recovery	Qualifier				
	%Recovery	Qualifier							
Toluene-d8 (Surr)	100		70 - 130						
4-Bromofluorobenzene	100		67 - 130						
1,2-Dichloroethane-d4 (Surr)	98		72 - 130						

**Lab Sample ID: 720-81020-2 MSD**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: MW-2**  
**Prep Type: Total/NA**

Analyte	Sample	Sample	Spike	MSD	MSD	Unit	D	%Rec	%Rec.
	Result	Qualifier	Added	Result	Qualifier				
1,1-Dichloroethene	ND		25.0	23.7		ug/L		94	60 - 140
1,1-Dichloroethane	ND		25.0	25.8		ug/L		103	60 - 140
Dichlorodifluoromethane	ND		25.0	22.0		ug/L		88	38 - 140
Vinyl chloride	ND		25.0	24.8		ug/L		99	58 - 140
Chloroethane	ND		25.0	23.8		ug/L		95	51 - 140
Trichlorofluoromethane	ND		25.0	23.5		ug/L		94	60 - 140
Methylene Chloride	ND		25.0	25.9		ug/L		104	40 - 140
trans-1,2-Dichloroethene	ND		25.0	25.5		ug/L		102	60 - 140
cis-1,2-Dichloroethene	32		25.0	56.2		ug/L		96	60 - 140
Chloroform	ND		25.0	26.2		ug/L		105	60 - 140
1,1,1-Trichloroethane	ND		25.0	25.5		ug/L		102	60 - 140
Carbon tetrachloride	ND		25.0	25.6		ug/L		102	60 - 140
1,2-Dichloroethane	ND		25.0	25.4		ug/L		102	60 - 140
Trichloroethene	26		25.0	50.1		ug/L		95	60 - 140
1,2-Dichloropropane	ND		25.0	26.6		ug/L		106	60 - 140
Dichlorobromomethane	ND		25.0	27.4		ug/L		110	60 - 140
trans-1,3-Dichloropropene	ND		25.0	26.4		ug/L		106	60 - 140

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: 720-81020-2 MSD**

**Matrix: Water**

**Analysis Batch: 227775**

**Client Sample ID: MW-2**  
**Prep Type: Total/NA**

Analyte	Sample	Sample	Spike	MSD	MSD	Unit	D	%Rec	Limits	RPD	RPD Limit
	Result	Qualifier	Added	Result	Qualifier						
cis-1,3-Dichloropropene	ND		25.0	26.5		ug/L		106	60 - 140	1	20
1,1,2-Trichloroethane	ND		25.0	27.1		ug/L		109	60 - 140	2	20
Tetrachloroethene	320	E	25.0	324	E 4	ug/L		-2	60 - 140	5	20
Chlorodibromomethane	ND		25.0	27.2		ug/L		109	60 - 140	1	20
Chlorobenzene	ND		25.0	26.3		ug/L		105	60 - 140	0	20
Bromoform	ND		25.0	26.5		ug/L		106	56 - 140	3	20
1,1,2,2-Tetrachloroethane	ND		25.0	27.2		ug/L		109	60 - 140	3	20
1,3-Dichlorobenzene	ND		25.0	25.5		ug/L		102	60 - 140	0	20
1,4-Dichlorobenzene	ND		25.0	25.8		ug/L		103	60 - 140	0	20
1,2-Dichlorobenzene	ND		25.0	26.5		ug/L		106	60 - 140	1	20
Chloromethane	ND		25.0	22.7		ug/L		91	52 - 140	3	20
Bromomethane	ND		25.0	23.6		ug/L		95	23 - 140	4	20
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		25.0	25.0		ug/L		100	60 - 140	0	20
EDB	ND		25.0	26.7		ug/L		107	60 - 140	2	20
1,2,4-Trichlorobenzene	ND		25.0	24.6		ug/L		98	60 - 140	1	20
<b>Surrogate</b>		<b>MSD</b>	<b>MSD</b>	<b>%Recovery</b>		<b>Qualifier</b>	<b>Limits</b>				
Toluene-d8 (Surr)	100			70 - 130							
4-Bromofluorobenzene	99			67 - 130							
1,2-Dichloroethane-d4 (Surr)	98			72 - 130							

**Lab Sample ID: MB 720-227817/4**

**Matrix: Water**

**Analysis Batch: 227817**

**Client Sample ID: Method Blank**  
**Prep Type: Total/NA**

Analyte	MB	MB	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
1,1-Dichloroethene	ND		0.50		ug/L			08/03/17 20:14	1
1,1-Dichloroethane	ND		0.50		ug/L			08/03/17 20:14	1
Dichlorodifluoromethane	ND		0.50		ug/L			08/03/17 20:14	1
Vinyl chloride	ND		0.50		ug/L			08/03/17 20:14	1
Chloroethane	ND		1.0		ug/L			08/03/17 20:14	1
Trichlorofluoromethane	ND		1.0		ug/L			08/03/17 20:14	1
Methylene Chloride	ND		5.0		ug/L			08/03/17 20:14	1
trans-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 20:14	1
cis-1,2-Dichloroethene	ND		0.50		ug/L			08/03/17 20:14	1
Chloroform	ND		1.0		ug/L			08/03/17 20:14	1
1,1,1-Trichloroethane	ND		0.50		ug/L			08/03/17 20:14	1
Carbon tetrachloride	ND		0.50		ug/L			08/03/17 20:14	1
1,2-Dichloroethane	ND		0.50		ug/L			08/03/17 20:14	1
Trichloroethene	ND		0.50		ug/L			08/03/17 20:14	1
1,2-Dichloropropane	ND		0.50		ug/L			08/03/17 20:14	1
Dichlorobromomethane	ND		0.50		ug/L			08/03/17 20:14	1
trans-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 20:14	1
cis-1,3-Dichloropropene	ND		0.50		ug/L			08/03/17 20:14	1
1,1,2-Trichloroethane	ND		0.50		ug/L			08/03/17 20:14	1
Tetrachloroethene	ND		0.50		ug/L			08/03/17 20:14	1
Chlorodibromomethane	ND		0.50		ug/L			08/03/17 20:14	1

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: MB 720-227817/4**

**Matrix: Water**

**Analysis Batch: 227817**

**Client Sample ID: Method Blank**  
**Prep Type: Total/NA**

Analyte	MB		RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
Chlorobenzene	ND		0.50		ug/L			08/03/17 20:14	1
Bromoform	ND		1.0		ug/L			08/03/17 20:14	1
1,1,2,2-Tetrachloroethane	ND		0.50		ug/L			08/03/17 20:14	1
1,3-Dichlorobenzene	ND		0.50		ug/L			08/03/17 20:14	1
1,4-Dichlorobenzene	ND		0.50		ug/L			08/03/17 20:14	1
1,2-Dichlorobenzene	ND		0.50		ug/L			08/03/17 20:14	1
Chloromethane	ND		1.0		ug/L			08/03/17 20:14	1
Bromomethane	ND		1.0		ug/L			08/03/17 20:14	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50		ug/L			08/03/17 20:14	1
EDB	ND		0.50		ug/L			08/03/17 20:14	1
1,2,4-Trichlorobenzene	ND		1.0		ug/L			08/03/17 20:14	1
Surrogate	MB		Limits				Prepared	Analyzed	Dil Fac
	%Recovery	Qualifier							
Toluene-d8 (Surr)	97		70 - 130					08/03/17 20:14	1
4-Bromofluorobenzene	95		67 - 130					08/03/17 20:14	1
1,2-Dichloroethane-d4 (Surr)	96		72 - 130					08/03/17 20:14	1

**Lab Sample ID: LCS 720-227817/5**

**Matrix: Water**

**Analysis Batch: 227817**

**Client Sample ID: Lab Control Sample**  
**Prep Type: Total/NA**

Analyte	Spike Added	LCS		Unit	D	%Rec	%Rec.	Limits
		Result	Qualifier					
1,1-Dichloroethene	25.0	24.0		ug/L		96	64 - 128	
1,1-Dichloroethane	25.0	26.3		ug/L		105	70 - 130	
Dichlorodifluoromethane	25.0	23.5		ug/L		94	32 - 158	
Vinyl chloride	25.0	27.4		ug/L		110	54 - 135	
Chloroethane	25.0	27.8		ug/L		111	62 - 138	
Trichlorofluoromethane	25.0	25.5		ug/L		102	66 - 132	
Methylene Chloride	25.0	26.4		ug/L		106	70 - 147	
trans-1,2-Dichloroethene	25.0	26.4		ug/L		106	68 - 130	
cis-1,2-Dichloroethene	25.0	25.6		ug/L		102	70 - 130	
Chloroform	25.0	26.3		ug/L		105	70 - 130	
1,1,1-Trichloroethane	25.0	25.7		ug/L		103	70 - 130	
Carbon tetrachloride	25.0	26.3		ug/L		105	70 - 146	
1,2-Dichloroethane	25.0	25.4		ug/L		102	61 - 132	
Trichloroethene	25.0	26.3		ug/L		105	70 - 130	
1,2-Dichloropropane	25.0	27.0		ug/L		108	70 - 130	
Dichlorobromomethane	25.0	27.6		ug/L		110	70 - 130	
trans-1,3-Dichloropropene	25.0	24.9		ug/L		100	70 - 140	
cis-1,3-Dichloropropene	25.0	26.0		ug/L		104	70 - 130	
1,1,2-Trichloroethane	25.0	27.4		ug/L		110	70 - 130	
Tetrachloroethene	25.0	26.8		ug/L		107	70 - 130	
Chlorodibromomethane	25.0	25.1		ug/L		100	70 - 145	
Chlorobenzene	25.0	26.9		ug/L		108	70 - 130	
Bromoform	25.0	24.4		ug/L		98	68 - 136	
1,1,2,2-Tetrachloroethane	25.0	25.9		ug/L		104	70 - 130	
1,3-Dichlorobenzene	25.0	27.3		ug/L		109	70 - 130	
1,4-Dichlorobenzene	25.0	27.2		ug/L		109	70 - 130	

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: LCS 720-227817/5**

**Matrix: Water**

**Analysis Batch: 227817**

**Client Sample ID: Lab Control Sample**  
**Prep Type: Total/NA**

Analyte	Spike	LCS	LCS	Unit	D	%Rec	%Rec.
	Added	Result	Qualifier				
1,2-Dichlorobenzene	25.0	27.5		ug/L		110	70 - 130
Chloromethane	25.0	26.9		ug/L		107	52 - 175
Bromomethane	25.0	26.1		ug/L		104	43 - 151
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	25.9		ug/L		104	42 - 162
ne							
EDB	25.0	25.3		ug/L		101	70 - 130
1,2,4-Trichlorobenzene	25.0	28.7		ug/L		115	70 - 130
<hr/>							
Surrogate	LCS	LCS	Limits	Unit	D	%Rec	RPD
	%Recovery	Qualifier					
Toluene-d8 (Surr)	100		70 - 130				
4-Bromofluorobenzene	100		67 - 130				
1,2-Dichloroethane-d4 (Surr)	92		72 - 130				

**Lab Sample ID: LCSD 720-227817/6**

**Matrix: Water**

**Analysis Batch: 227817**

**Client Sample ID: Lab Control Sample Dup**  
**Prep Type: Total/NA**

Analyte	Spike	LCSD	LCSD	Unit	D	%Rec	%Rec.	RPD	RPD Limit
	Added	Result	Qualifier						
1,1-Dichloroethene	25.0	23.5		ug/L		94	64 - 128	2	20
1,1-Dichloroethane	25.0	26.4		ug/L		106	70 - 130	0	20
Dichlorodifluoromethane	25.0	23.2		ug/L		93	32 - 158	1	20
Vinyl chloride	25.0	28.2		ug/L		113	54 - 135	3	20
Chloroethane	25.0	27.9		ug/L		112	62 - 138	0	20
Trichlorofluoromethane	25.0	25.3		ug/L		101	66 - 132	1	20
Methylene Chloride	25.0	26.1		ug/L		104	70 - 147	1	20
trans-1,2-Dichloroethene	25.0	26.6		ug/L		106	68 - 130	0	20
cis-1,2-Dichloroethene	25.0	25.9		ug/L		103	70 - 130	1	20
Chloroform	25.0	26.0		ug/L		104	70 - 130	1	20
1,1,1-Trichloroethane	25.0	25.6		ug/L		103	70 - 130	0	20
Carbon tetrachloride	25.0	26.6		ug/L		106	70 - 146	1	20
1,2-Dichloroethane	25.0	25.1		ug/L		100	61 - 132	1	20
Trichloroethene	25.0	26.8		ug/L		107	70 - 130	2	20
1,2-Dichloropropane	25.0	27.3		ug/L		109	70 - 130	1	20
Dichlorobromomethane	25.0	27.7		ug/L		111	70 - 130	0	20
trans-1,3-Dichloropropene	25.0	24.9		ug/L		100	70 - 140	0	20
cis-1,3-Dichloropropene	25.0	25.8		ug/L		103	70 - 130	1	20
1,1,2-Trichloroethane	25.0	27.2		ug/L		109	70 - 130	1	20
Tetrachloroethene	25.0	26.8		ug/L		107	70 - 130	0	20
Chlorodibromomethane	25.0	25.0		ug/L		100	70 - 145	0	20
Chlorobenzene	25.0	26.8		ug/L		107	70 - 130	0	20
Bromoform	25.0	23.9		ug/L		96	68 - 136	2	20
1,1,2,2-Tetrachloroethane	25.0	24.9		ug/L		100	70 - 130	4	20
1,3-Dichlorobenzene	25.0	27.4		ug/L		110	70 - 130	1	20
1,4-Dichlorobenzene	25.0	27.3		ug/L		109	70 - 130	0	20
1,2-Dichlorobenzene	25.0	27.4		ug/L		110	70 - 130	0	20
Chloromethane	25.0	27.8		ug/L		111	52 - 175	4	20
Bromomethane	25.0	26.4		ug/L		106	43 - 151	1	20

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: LCSD 720-227817/6**

**Matrix: Water**

**Analysis Batch: 227817**

**Client Sample ID: Lab Control Sample Dup**  
**Prep Type: Total/NA**

Analyte	Spike Added	LCSD		Unit	D	%Rec.		RPD	Limit
		Result	Qualifier			%Rec	Limits		
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	26.0	ug/L		104	42 - 162	0	20	
EDB	25.0	25.0	ug/L		100	70 - 130	1	20	
1,2,4-Trichlorobenzene	25.0	28.5	ug/L		114	70 - 130	1	20	

**LCSD**

**LCSD**

Surrogate	%Recovery	LCSD	LCSD	Limits
		Qualifier		
Toluene-d8 (Surr)	100			70 - 130
4-Bromofluorobenzene	98			67 - 130
1,2-Dichloroethane-d4 (Surr)	94			72 - 130

**Lab Sample ID: MB 720-227840/4**

**Matrix: Water**

**Analysis Batch: 227840**

**Client Sample ID: Method Blank**  
**Prep Type: Total/NA**

Analyte	MB	MB	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
1,1-Dichloroethene	ND		0.50	ug/L				08/04/17 10:47	1
1,1-Dichloroethane	ND		0.50	ug/L				08/04/17 10:47	1
Dichlorodifluoromethane	ND		0.50	ug/L				08/04/17 10:47	1
Vinyl chloride	ND		0.50	ug/L				08/04/17 10:47	1
Chloroethane	ND		1.0	ug/L				08/04/17 10:47	1
Trichlorofluoromethane	ND		1.0	ug/L				08/04/17 10:47	1
Methylene Chloride	ND		5.0	ug/L				08/04/17 10:47	1
trans-1,2-Dichloroethene	ND		0.50	ug/L				08/04/17 10:47	1
cis-1,2-Dichloroethene	ND		0.50	ug/L				08/04/17 10:47	1
Chloroform	ND		1.0	ug/L				08/04/17 10:47	1
1,1,1-Trichloroethane	ND		0.50	ug/L				08/04/17 10:47	1
Carbon tetrachloride	ND		0.50	ug/L				08/04/17 10:47	1
1,2-Dichloroethane	ND		0.50	ug/L				08/04/17 10:47	1
Trichloroethene	ND		0.50	ug/L				08/04/17 10:47	1
1,2-Dichloropropane	ND		0.50	ug/L				08/04/17 10:47	1
Dichlorobromomethane	ND		0.50	ug/L				08/04/17 10:47	1
trans-1,3-Dichloropropene	ND		0.50	ug/L				08/04/17 10:47	1
cis-1,3-Dichloropropene	ND		0.50	ug/L				08/04/17 10:47	1
1,1,2-Trichloroethane	ND		0.50	ug/L				08/04/17 10:47	1
Tetrachloroethene	ND		0.50	ug/L				08/04/17 10:47	1
Chlorodibromomethane	ND		0.50	ug/L				08/04/17 10:47	1
Chlorobenzene	ND		0.50	ug/L				08/04/17 10:47	1
Bromoform	ND		1.0	ug/L				08/04/17 10:47	1
1,1,2,2-Tetrachloroethane	ND		0.50	ug/L				08/04/17 10:47	1
1,3-Dichlorobenzene	ND		0.50	ug/L				08/04/17 10:47	1
1,4-Dichlorobenzene	ND		0.50	ug/L				08/04/17 10:47	1
1,2-Dichlorobenzene	ND		0.50	ug/L				08/04/17 10:47	1
Chloromethane	ND		1.0	ug/L				08/04/17 10:47	1
Bromomethane	ND		1.0	ug/L				08/04/17 10:47	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		0.50	ug/L				08/04/17 10:47	1
EDB	ND		0.50	ug/L				08/04/17 10:47	1
1,2,4-Trichlorobenzene	ND		1.0	ug/L				08/04/17 10:47	1

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: MB 720-227840/4**

**Matrix: Water**

**Analysis Batch: 227840**

**Client Sample ID: Method Blank**  
**Prep Type: Total/NA**

Surrogate	MB	MB	%Recovery	Qualifier	Limits
Toluene-d8 (Surr)		98			70 - 130
4-Bromofluorobenzene		98			67 - 130
1,2-Dichloroethane-d4 (Surr)		97			72 - 130

**Prepared**      **Analyzed**      **Dil Fac**

**Lab Sample ID: LCS 720-227840/5**

**Matrix: Water**

**Analysis Batch: 227840**

**Client Sample ID: Lab Control Sample**  
**Prep Type: Total/NA**

Analyte	Spike	LCS	LCS	Unit	D	%Rec	%Rec.	Limits
	Added	Result	Qualifier					
1,1-Dichloroethene	25.0	24.4		ug/L		98	64 - 128	
1,1-Dichloroethane	25.0	27.4		ug/L		110	70 - 130	
Dichlorodifluoromethane	25.0	23.4		ug/L		94	32 - 158	
Vinyl chloride	25.0	25.9		ug/L		104	54 - 135	
Chloroethane	25.0	26.4		ug/L		105	62 - 138	
Trichlorofluoromethane	25.0	25.7		ug/L		103	66 - 132	
Methylene Chloride	25.0	25.9		ug/L		104	70 - 147	
trans-1,2-Dichloroethene	25.0	25.9		ug/L		104	68 - 130	
cis-1,2-Dichloroethene	25.0	27.3		ug/L		109	70 - 130	
Chloroform	25.0	26.0		ug/L		104	70 - 130	
1,1,1-Trichloroethane	25.0	27.4		ug/L		109	70 - 130	
Carbon tetrachloride	25.0	26.8		ug/L		107	70 - 146	
1,2-Dichloroethane	25.0	26.0		ug/L		104	61 - 132	
Trichloroethene	25.0	25.4		ug/L		101	70 - 130	
1,2-Dichloropropane	25.0	27.9		ug/L		112	70 - 130	
Dichlorobromomethane	25.0	27.0		ug/L		108	70 - 130	
trans-1,3-Dichloropropene	25.0	26.2		ug/L		105	70 - 140	
cis-1,3-Dichloropropene	25.0	26.9		ug/L		108	70 - 130	
1,1,2-Trichloroethane	25.0	26.9		ug/L		107	70 - 130	
Tetrachloroethene	25.0	25.0		ug/L		100	70 - 130	
Chlorodibromomethane	25.0	25.3		ug/L		101	70 - 145	
Chlorobenzene	25.0	25.8		ug/L		103	70 - 130	
Bromoform	25.0	25.3		ug/L		101	68 - 136	
1,1,2,2-Tetrachloroethane	25.0	28.3		ug/L		113	70 - 130	
1,3-Dichlorobenzene	25.0	26.1		ug/L		105	70 - 130	
1,4-Dichlorobenzene	25.0	26.3		ug/L		105	70 - 130	
1,2-Dichlorobenzene	25.0	26.4		ug/L		106	70 - 130	
Chloromethane	25.0	26.7		ug/L		107	52 - 175	
Bromomethane	25.0	25.5		ug/L		102	43 - 151	
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	25.0		ug/L		100	42 - 162	
EDB		25.0	25.7	ug/L		103	70 - 130	
1,2,4-Trichlorobenzene		25.0	25.2	ug/L		101	70 - 130	

Surrogate	LCS	LCS	%Recovery	Qualifier	Limits
Toluene-d8 (Surr)		99			70 - 130
4-Bromofluorobenzene		97			67 - 130
1,2-Dichloroethane-d4 (Surr)		96			72 - 130

TestAmerica Pleasanton

# QC Sample Results

Client: Crawford Consulting Inc  
 Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

**Lab Sample ID: LCSD 720-227840/6**

**Matrix: Water**

**Analysis Batch: 227840**

**Client Sample ID: Lab Control Sample Dup**  
**Prep Type: Total/NA**

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
1,1-Dichloroethene	25.0	24.4		ug/L	97	64 - 128	0	20	
1,1-Dichloroethane	25.0	27.2		ug/L	109	70 - 130	1	20	
Dichlorodifluoromethane	25.0	22.6		ug/L	90	32 - 158	3	20	
Vinyl chloride	25.0	25.3		ug/L	101	54 - 135	2	20	
Chloroethane	25.0	26.2		ug/L	105	62 - 138	1	20	
Trichlorofluoromethane	25.0	25.5		ug/L	102	66 - 132	1	20	
Methylene Chloride	25.0	26.4		ug/L	106	70 - 147	2	20	
trans-1,2-Dichloroethene	25.0	25.7		ug/L	103	68 - 130	1	20	
cis-1,2-Dichloroethene	25.0	27.2		ug/L	109	70 - 130	0	20	
Chloroform	25.0	26.0		ug/L	104	70 - 130	0	20	
1,1,1-Trichloroethane	25.0	27.0		ug/L	108	70 - 130	1	20	
Carbon tetrachloride	25.0	26.6		ug/L	106	70 - 146	1	20	
1,2-Dichloroethane	25.0	26.6		ug/L	106	61 - 132	2	20	
Trichloroethene	25.0	25.2		ug/L	101	70 - 130	1	20	
1,2-Dichloropropane	25.0	28.1		ug/L	113	70 - 130	1	20	
Dichlorobromomethane	25.0	27.3		ug/L	109	70 - 130	1	20	
trans-1,3-Dichloropropene	25.0	27.3		ug/L	109	70 - 140	4	20	
cis-1,3-Dichloropropene	25.0	27.5		ug/L	110	70 - 130	2	20	
1,1,2-Trichloroethane	25.0	28.4		ug/L	114	70 - 130	6	20	
Tetrachloroethene	25.0	24.9		ug/L	99	70 - 130	0	20	
Chlorodibromomethane	25.0	26.5		ug/L	106	70 - 145	5	20	
Chlorobenzene	25.0	25.7		ug/L	103	70 - 130	0	20	
Bromoform	25.0	27.2		ug/L	109	68 - 136	7	20	
1,1,2,2-Tetrachloroethane	25.0	30.4		ug/L	122	70 - 130	7	20	
1,3-Dichlorobenzene	25.0	26.1		ug/L	104	70 - 130	0	20	
1,4-Dichlorobenzene	25.0	26.3		ug/L	105	70 - 130	0	20	
1,2-Dichlorobenzene	25.0	26.6		ug/L	106	70 - 130	1	20	
Chloromethane	25.0	26.4		ug/L	106	52 - 175	1	20	
Bromomethane	25.0	25.4		ug/L	101	43 - 151	1	20	
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	25.0		ug/L	100	42 - 162	0	20	
EDB	25.0	27.3		ug/L	109	70 - 130	6	20	
1,2,4-Trichlorobenzene	25.0	25.8		ug/L	103	70 - 130	2	20	

Surrogate	LCSD %Recovery	LCSD Qualifier	Limits
Toluene-d8 (Surr)	99		70 - 130
4-Bromofluorobenzene	99		67 - 130
1,2-Dichloroethane-d4 (Surr)	100		72 - 130

TestAmerica Pleasanton

# QC Association Summary

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## GC/MS VOA

### Analysis Batch: 227775

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
720-81020-2	MW-2	Total/NA	Water	8260B	
720-81020-3	MW-3	Total/NA	Water	8260B	
720-81020-4	MW-4	Total/NA	Water	8260B	
720-81020-5	DUP-1	Total/NA	Water	8260B	
720-81020-6	TB-1	Total/NA	Water	8260B	
MB 720-227775/4	Method Blank	Total/NA	Water	8260B	
LCS 720-227775/5	Lab Control Sample	Total/NA	Water	8260B	
LCSD 720-227775/6	Lab Control Sample Dup	Total/NA	Water	8260B	
720-81020-2 MS	MW-2	Total/NA	Water	8260B	
720-81020-2 MSD	MW-2	Total/NA	Water	8260B	

### Analysis Batch: 227817

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
720-81020-1	MW-1	Total/NA	Water	8260B	
MB 720-227817/4	Method Blank	Total/NA	Water	8260B	
LCS 720-227817/5	Lab Control Sample	Total/NA	Water	8260B	
LCSD 720-227817/6	Lab Control Sample Dup	Total/NA	Water	8260B	

### Analysis Batch: 227840

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
720-81020-2	MW-2	Total/NA	Water	8260B	
720-81020-5	DUP-1	Total/NA	Water	8260B	
MB 720-227840/4	Method Blank	Total/NA	Water	8260B	
LCS 720-227840/5	Lab Control Sample	Total/NA	Water	8260B	
LCSD 720-227840/6	Lab Control Sample Dup	Total/NA	Water	8260B	

# Lab Chronicle

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## **Client Sample ID: MW-1**

**Date Collected:** 08/02/17 09:18  
**Date Received:** 08/02/17 12:45

## **Lab Sample ID: 720-81020-1**

**Matrix:** Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260B		1	227817	08/04/17 01:55	BAJ	TAL PLS

## **Client Sample ID: MW-2**

**Date Collected:** 08/02/17 11:17  
**Date Received:** 08/02/17 12:45

## **Lab Sample ID: 720-81020-2**

**Matrix:** Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260B		1	227775	08/03/17 22:42	BAJ	TAL PLS
Total/NA	Analysis	8260B		10	227840	08/04/17 15:52	A1C	TAL PLS

## **Client Sample ID: MW-3**

**Date Collected:** 08/02/17 10:27  
**Date Received:** 08/02/17 12:45

## **Lab Sample ID: 720-81020-3**

**Matrix:** Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260B		1	227775	08/03/17 23:12	BAJ	TAL PLS

## **Client Sample ID: MW-4**

**Date Collected:** 08/02/17 08:26  
**Date Received:** 08/02/17 12:45

## **Lab Sample ID: 720-81020-4**

**Matrix:** Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260B		1	227775	08/03/17 23:42	BAJ	TAL PLS

## **Client Sample ID: DUP-1**

**Date Collected:** 08/02/17 00:00  
**Date Received:** 08/02/17 12:45

## **Lab Sample ID: 720-81020-5**

**Matrix:** Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260B		1	227775	08/04/17 00:12	BAJ	TAL PLS
Total/NA	Analysis	8260B		10	227840	08/04/17 16:48	A1C	TAL PLS

## **Client Sample ID: TB-1**

**Date Collected:** 08/02/17 00:00  
**Date Received:** 08/02/17 12:45

## **Lab Sample ID: 720-81020-6**

**Matrix:** Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260B		1	227775	08/04/17 00:42	BAJ	TAL PLS

### Laboratory References:

TAL PLS = TestAmerica Pleasanton, 1220 Quarry Lane, Pleasanton, CA 94566, TEL (925)484-1919

TestAmerica Pleasanton

# Accreditation/Certification Summary

Client: Crawford Consulting Inc

Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

## Laboratory: TestAmerica Pleasanton

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	EPA Region	Identification Number	Expiration Date
California	State Program	9	2496	01-31-18
Analysis Method	Prep Method	Matrix	Analyte	

1

2

3

4

5

6

7

8

9

10

11

12

13

14

TestAmerica Pleasanton

## Method Summary

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

Method	Method Description	Protocol	Laboratory
8260B	Volatile Organic Compounds (GC/MS)	SW846	TAL PLS

**Protocol References:**

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

**Laboratory References:**

TAL PLS = TestAmerica Pleasanton, 1220 Quarry Lane, Pleasanton, CA 94566, TEL (925)484-1919

1

2

3

4

5

6

7

8

9

10

11

12

13

14

## Sample Summary

Client: Crawford Consulting Inc  
Project/Site: Alameda Facility CS 1605

TestAmerica Job ID: 720-81020-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
720-81020-1	MW-1	Water	08/02/17 09:18	08/02/17 12:45
720-81020-2	MW-2	Water	08/02/17 11:17	08/02/17 12:45
720-81020-3	MW-3	Water	08/02/17 10:27	08/02/17 12:45
720-81020-4	MW-4	Water	08/02/17 08:26	08/02/17 12:45
720-81020-5	DUP-1	Water	08/02/17 00:00	08/02/17 12:45
720-81020-6	TB-1	Water	08/02/17 00:00	08/02/17 12:45

1

2

3

4

5

6

7

8

9

10

11

12

13

14

TestAmerica Pleasanton

1 2 3 4 5 6 7 8 9 10 11 12 13 14

**Test America**1220 Quarry Lane, Pleasanton, CA 94566  
(925) 484-1919 FAX (925) 484-1096

Service Request:

Date

8/7/2017

**CHAIN OF CUSTODY / LABORATORY ANALYSIS REQUEST FORM**

177415

**Project Name:** Alameda Facility  
**Project Number:** CS1605  
**Project Manager:** Dana Johnston  
**Company/Address:** Crawford Consulting, Inc  
 4 North Second St, Suite 650  
 San Jose, CA 95113  
**Phone** (408) 287-9934

**Sampler's Signature***Dana*

REMARKS

					Number of Containers	Analysis Requested	Date
Sample I.D.	Date	Time	LAB I.D.	Sample Matrix			
MW-1	8/2/12	0915		water	3		
MW-2	8/2/12	1117		water	3	X	
MW-3	8/2/12	1022		water	3	X	
MW-4	8/2/12	0824		water	3	X	
DUP-1	8-2-12	—		water	3	X	
TB-1	8-2-12	—		water	3	X	



720-81020 Chain of Custody

Page 27 of 28

Relinquished By	Received By	TURNAROUND REQUIREMENTS	REPORT REQUIREMENTS	INVOICE INFORMATION	SAMPLE RECEIPT
<i>Dana Johnston</i>	<i>Jeanne Waller</i>	<input checked="" type="checkbox"/> 24 hr <input type="checkbox"/> 48 hr <input type="checkbox"/> 5 day <input checked="" type="checkbox"/> Standard (5 working days) <input checked="" type="checkbox"/> Provide Verbal Preliminary Results <input checked="" type="checkbox"/> Provide pdf Results <input checked="" type="checkbox"/> Due Date: _____	<input checked="" type="checkbox"/> I Routine Report <input checked="" type="checkbox"/> II Report includes Dup MS <input checked="" type="checkbox"/> ASRD, as required, may be charged as samples <input checked="" type="checkbox"/> III Data Validation Report (includes All Raw Data) <input checked="" type="checkbox"/> RNOCB (INDs, PQLs, TRACHe)	PO # _____ Shipping VIA _____ Shipping # _____ Bill to _____ Condition _____ _____ _____	
<i>F. S. T</i>	<i>Jeanne Waller</i>				
Firm: 8-2-12 - 1245	Firm: <i>Jeanne Waller</i>				
Date/Time	Date/Time: 8-2-12 1245				
Relinquished By	Received By				
Signature	Signature				
Printed Name	Printed Name				
Firm	Firm				
Date/Time	Date/Time				
Signature	Signature				
Printed Name	Printed Name				
Firm	Firm				
Date/Time	Date/Time				

**Special Instructions/Comments:**

Please report MRLs only

Please pdf results to Dana Johnston at dana@crawfordconsulting.com

Please provide EDF for Geotracker Global ID is SL060017751

43°

## Login Sample Receipt Checklist

Client: Crawford Consulting Inc

Job Number: 720-81020-1

**Login Number:** 81020

**List Source:** TestAmerica Pleasanton

**List Number:** 1

**Creator:** Thibodeaux, Summer J

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	N/A	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

