

Westinghouse Electric Corporation 11 Stanwix Street Pittsburgh Pennsylvania 15222-1384

May 1, 1996

Mr. Sumadhu Arigala

California Regional Water Quality Control Board
2101 Webster Street, Suite 500

Oakland, CA 94612

Re: Groundwater Sampling Results

Westinghouse Emeryville Site, Emeryville, CA

Dear Mr Arigala:

As we discussed in our recent meeting, Westinghouse Electric Corporation requested their contractor, EMCON, Inc., to install a temporary groundwater monitoring well at the southwest corner of the Westinghouse property in Emeryville, CA. The well was installed and the groundwater sampled and analyzed as described in the attached report from EMCON. No PCBs were detected in the groundwater sample above the reporting limit of 0.1 micrograms per liter (0.1 ug/L). Based on this analysis, Westinghouse has requested that EMCON abandon the well according to the Board's protocol.

Westinghouse believes this resolves the last outstanding issue with respect to the risk assessment for the Emeryville site.

If you have any questions, please feel free to call me at (412) 642-5851 at your convenience.

Sincerely,

Gordon T. Taylor Principal Engineer

Environmental Remediation
Law and Environmental Affairs

Attachment



April 18, 1996 Project 20F88-001.019

Mr. Gordon Taylor Westinghouse Electric Corporation Gateway Center Pittsburgh, Pennsylvania 15222

Re: Well installation report, Emeryville, California

Dear Mr. Taylor:

This report documents the installation and sampling of one groundwater monitoring well at the Westinghouse Electric Corporation (WEC) property in Emeryville, California (Figure 1). The installation and sampling of the new well was requested by WEC to evaluate analyte concentrations detected in a grab groundwater sample obtained from Hydropunch[®] boring TP-6, conducted in July 1995. The field work was conducted in April 1996 in a manner consistent with the proposal approved by WEC dated March 19, 1996.

SUMMARY OF FIELD ACTIVITIES

Before drilling, the site health and safety plan was reviewed to ensure safe work practices at the site. Additionally, a well installation permit was obtained from the Alameda County Flood Control and Water Conservation District (Zone 7).

Drilling and Well Installation

On April 2, 1996, EMCON drilled boring S-9 adjacent to former Hydropunch boring TP-6 in the southwest portion of the property (Figure 2). The boring was drilled to a depth of 20 feet below the ground surface (BGS) using 8-inch-diameter augers. The boring was sampled for lithologic description and field head-space readings at approximate 5-foot depth intervals using a modified California split-spoon sampler. Upon completion of soil sampling, the boring was completed as a temporary groundwater monitoring well by installing 2-inch-diameter polyvinyl chloride (PVC) well screen and casing. A locking cap was provided for the well casing; however, as requested by WEC, a permanent vault box was not installed. Based on the information in this report, this well will be removed and the borehole backfilled to the surface with grout.



A description of the exploratory boring and well installation procedures was previously presented in EMCON's *Well Installation Report* dated September 28, 1995. Similar procedures were used for the installation of well S-9. The exploratory boring log and well construction detail are included in Appendix A.

Well Development and Sampling

On April 5, 1996, well S-9 was developed using a surge block and centrifugal pump. As water was removed from the well, its turbidity, temperature, color, pH, and electrical conductivity were recorded. The well was pumped until the water removed was relatively nonturbid, silt- and sand-free, and had a stable pH.

On April 9, 1996, the water level in well S-9 was gauged. The well was then micropurged and sampled. The well was micro-purged by lowering a Teflon® tube into the well to a depth at the approximate midpoint of the screened interval (about 15 feet BGS). The Teflon tubing was hooked up to a peristaltic pump that was connected to a flow-thru cell. The pumping rate was approximately 100 milliliters per minute. The flow-thru cell was monitored by a YSI in-line analyzer for pH, temperature, conductivity, and oxidation-reduction potential (ORP). Separate turbidity and oxygen meters were also used. The monitoring parameters were consistent after approximately 20 minutes of micro-purging (one gallon of water), and a sample was obtained by pumping groundwater into 40 milliliter vials from Teflon tubing on the discharge end of the pump. Well development and water sampling field data sheets are presented in Appendix B.

Disposal of Materials

Drill cuttings, and decontamination, well development, and purging water generated during site activities were placed in 55-gallon drums and temporarily stored on site. The water will be disposed of at an appropriate facility with the purge water generated during the semiannual groundwater monitoring events. EMCON will base soil disposal options on the soil analytical results from Hydropunch boring TP-6, located adjacent to S-9.

LABORATORY ANALYSES

The groundwater sample was analyzed for PCBs by U.S. Environmental Protection Agency (USEPA) method 8080. The sample was analyzed on a 48-hour turnaround. Copies of the laboratory report and chain-of-custody documentation are presented in Appendix C.

FINDINGS

Soil conditions consisted of clayey silt, silt, and silty sand similar to the other borings drilled on site. No PCBs were detected above the method reporting limit of 0.1 micrograms per liter in the groundwater sample from S-9 as shown on the laboratory reports in Appendix C.

If you have questions regarding this letter report, please call us.

Sincerely.

EMCON

Peter T. Christianson Project Geologist Mark Smolley, RG
Project Supervisor

Attachments: Limitations


Figure 1 - Site Location Figure 2 - Site Plan

Appendix A - Exploratory Boring Log and Well Completion Detail Appendix B - Well Development and Water Sampling Field Data Sheets Appendix C - Laboratory Report and Chain-of-Custody Documentation

LIMITATIONS

The services described in this report were performed consistent with generally accepted professional consulting principles and practices. No other warranty, express or implied, is made. These services were performed consistent with our agreement with our client. This report is solely for the use and information of our client unless otherwise noted. Any reliance on this report by a third party is at such party's sole risk.

Opinions and recommendations contained in this report apply to conditions existing when services were performed and are intended only for the client, purposes, locations, time frames, and project parameters indicated. We are not responsible for the impacts of any changes in environmental standards, practices, or regulations subsequent to performance of services. We do not warrant the accuracy of information supplied by others, nor the use of segregated portions of this report.





WESTINGHOUSE ELECTRIC CORPORATION
WELL INSTALLATION REPORT
EMERYVILLE, CALIFORNIA

SITE LOCATION

FIGURE

1

PROJECT NO.
F88-01.19

PELADEAU

■ B3

STREET

■ B2

■ B1

TP-2

- PROPERTY LINE

B13 (5)

B14

ALLEY

TP-1 FORMER UNDERGROUND STORAGE TANK

SITÉ ACCESS GATE

B12

B8


B10

APPENDIX A EXPLORATORY BORING LOG AND WELL COMPLETION DETAIL



EXPLANATION OF SYMBOLS ON EXPLORATORY BORING LOGS

Well Details Column



Sample Column

BAG/BULK SAMPLES

FIVE-FOOT SPLIT BARREL SAMPLER (CONTINUOUS SAMPLER)

MODIFIED CALIFORNIA SPLIT SPOON

OTHER SAMPLERS (SEE REMARKS FOR TYPE AND SIZE)

PITCHER BARREL

ROCK CORE (SEE REMARKS FOR TYPE AND SIZE)


SHELBY TUBE SAMPLER

STANDARD PENETRATION TEST SPLIT SPOON SAMPLER (2" OD)

MAJOR DIVISIONS		SYMBOLS	TYPICAL SOIL DESCRIPTIONS
S eve size)	GRAVELS (More than 1/2 of coarse fraction) no. 4 sieve size)	GW	Well graded gravels or gravel—sand mixtures, little or no fines
		GP	Poorly graded gravels or gravel-sand mixtures, little or no fines
SOIL 00 si		GM 20	Silty graveis, gravel-sand-silt mixtures
Soil) no 2		GC S	Clayey gravels, gravel-sand-clay mixtures
0		SW	Well graded sands or gravelly sands, little or no fines
COARSE (More than 1/2	SANDS (More than 1/2 of coarse fraction (no. 4 sieve size)	SP	Poorly graded sands or gravelly sands, little or no fines
		SM	Silty sands, sand-silt mixtures
		sc	Clayey sands, sand-clay mixtures
re size)	SILTS & CLAYS	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity
SOILS 200 sieve		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silly clays, lean clays
		OL	Organic silts and organic silty clays of low plasticity
	SILTS & CLAYS	мн	inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
FINE than 1/2	<u>LL > 50</u>	сн	Inorganic clays of high plasticity, fat clays
(More		он	Organic clays of medium to high plasticity, organic silty clays, organic silts
н	IGHLY ORGANIC SOILS	₽ŧ	Peat and other highly organic soils

CLASSIFICATION CHART (Unified Soil Classification System)

CLASSIFICATION	RANGE OF GI	RAIN SIZES	
	U.S. Standard Sieve Size	Grain Size in Millimeters	
BOULDERS	Above 12"	Above 305	
COBBLES	12" to 3"	305 to 76.2	
GRAVEL coarse fine	3" to No. 4 3" to 3/4" 3/4" to No. 4	76.2 to 4.76 76.2 to 19.1 19.1 to 4.76	
SAND coarse medium fine	No 4 to No. 200 No 4 to No 10 No 10 to No. 40 No. 40 to No. 200	476 to 0.074 476 to 2.00 2.00 to 0.420 0.420 to 0.074	
SILT & CLAY	Below No. 200	Below 0074	



PLASTICITY CHART

GRAIN SIZE CHART

METHOD OF SOIL CLASSIFICATION



LOG OF EXPLORATORY BORING

PROJECT NUMBER: 20F88-001.019

BORING NO .: S-9

PROJECT NAME: Westinghouse

PAGE: 1 of 1

BY: T. Gyrion

DATE: 4/02/98

SURFACE ELEVATION: NA ft.

RECOVERY (ft/ft)	PID (ppm)	TION	GROUND DEPTH WATER IN LEVELS FEET S	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
		I		•••	CONCRETE.	
1.0/1.0	0	18			SILTY SAND (SM), reddish brown (5YR, 4/3); 45% low plasticity fines; 55% fine to medium sand, (5:1); abundant iron oxide staining; medium dense; wet.	
1.0/1.0	0	15	10-		@9.0': dark greenish gray (5BG, 4/1); 35% low-plasticity fines; 50% fine to coarse sand, (5:1:2); 15% fine to coarse gravel, (1:2), angular clasts; medium dense; wet. @9.5': dark brown (7.5YR, 4/4); 20% low-plasticity fines; 80% fine to medium sand, (2:1), poorly sorted; medium dense; wet.	
1.0/1.0	0	17	- 15-		CLAYEY SILT (MH), light yelllowish brown (10YR, 6/4); 100% medium- to high-plasticity fines; trace fine sand; very stiff; moist.	
1.0/1.0	0	17	20		@20.0': light yellowish brown (10YR, 6/4); 90% medium— to high— plasticity fines; 10% fine to medium sand, (1:1), well rounded; medium dense; moist to wet. BORING TERMINATED AT 20.0 FEET.	



REMARKS

Boring drilled with 8-inch-diameter hollow-stem auger drilling equipment. Boring sampled using modified California split-spoon samplers. Boring completed as a 2-inch-diameter PVC monitoring well. Well construction information is presented in Well Details and shown graphically on this log. See explanation sheet for definition of symbols used in Well Detail and sample columns on this log.

WELL DETAILS

PROJECT NUMBER 20F88-001.019


PROJECT NAME Westinghouse TOP OF CASING ELEV. NA

LOCATION Emeryville, CA GROUND SURFACE ELEV. NA

WELL PERMIT NO. 96244

DATUM FT - MSL

INSTALLATION DATE 4/2/96



EXPLORATORY BORING

WELL CONSTRUCTION

20.5 ft. c. Total casing length Schedule 40 PVC Material 2.0 in. d. Diameter 9.4 ft. e. Depth to top perforations 9.2 ft. f. Perforated length 18.6 ft. Perforated interval from _____9.4_ to Machine-slotted_ Perforation type Perforation size __0.010 in. na ft. g. Surface seal Material 6.5 ft. h. Backfill Cement Material 1.0 ft. i. Seal Bentonite Material 11.5 ft. j. Gravel pack 20.0 ft. 8.5 to Gravel pack interval from ____ #2/16 sand Material na ft. k. Bottom seal/fill Material na Casing stickup

m. Protective casing diameter

in.

Well Constructed by THG

APPENDIX B

WELL DEVELOPMENT AND WATER SAMPLING FIELD DATA SHEETS



FIELD REPORT FIELD SERVICES GROUP

ASSOCIATES
CLIENT NAME: WEC-EMERYNIUR NAME: M. POSS LOCATION: EMERYNIUR (A
SERVICES RENDERED
GROUND WATER WELLS: Sampling Development Maintenance/Repair Water-Level Survey
SOIL SAMPLING:
OTHER: MICYO- PUCGING
REMARKS: Well S-9 was murgarized by using a peristalitic pump at a 2 rate of 100 ml fain. Tetlow training was 10 merced 215' down into the middle of the screen interval. The tetlow training was hopeed up to the peristablic pump, which was them connected to a flow thru cell. The flow thru cell was being monitared by a incline. Analyzer 1857 3500) for ph. Temp, (and. + ORP. Seperate Oxygen and NTU meters where used. Silicon training was used to inside peristablic promp to draw water thru it and to connect to flow tubing to poristablic pump. When peristablic promp to draw water thru it and to connect to flow tubing to poristablic pump. When peristablic pump for minutes a 1 gallow of water was periged sensitable surpressions.
SIGNATURE: Multi Prom

	WEL	L DEV	ELOPMI	ENI FI	ELD DATA	SHEET		
Project Number: 2018-001.0/9 Performed By: M. ROSS								
Client: WEC - EMERYVILLE Date: 4-5-96								
Location: EMERYUILLE, CA Well ID: 5-9								
g Diamete	er: 🖊 2 ind	ch 3	inch	4 inch			ther	
to Water	(feet): St	tart 6	44	<u>~</u>			3	
otal Dept	h (feet): St	art	9,4		End 19.8			
One Casing Volume at Start (gal): 2.11 Total Volume Purged (gal): 80.0								
			DEVELOR					
Centrifuga	l Pump	Baile				k (Swah)		
			. (10)		Other			
			FIELD	INSTRUM	<u>IENTS</u>			
H, EC, Te	mp. Meter	NTU	Meter _	_ Imhoff	ConeCo	lorimeter Oth	er	
water Di	sposai Metho	oa:	r	r				
Time		Temp.	E.C.	pН	Turbidity Visual NTU	Color Visual Cobalt	Odor	Settleable
		(° F)		(Stnd)	Moderate 0 - 200 or	Cloudy 0 to 500	22.000 2000 2000 au	Solids (%)
	10 /	. ,			Trace	Brown		120 2
1110	10,0	68.4	975	7.80		7 500	NOME	53%
1120	20.0	1.79	921	721	Heavy	BRN		~/
						7500		
1/32	30.0	68.8	816	7.30	7 1000	13PL 7 500	NONE	Dolo
1144	40.0	68.8	870	741	HDAUY	BRN 500	NOME	20%
	-							100
11>1	70,0	68.7		1,35	> /100	>500	NOVE	1910
1200	60,0	67.8	834	6.89	7/000	BRN >500	North	15%
1213	70,0	65.6	<i>336</i>	6.86	Heavy	BRN 7500	NONE	4%
1221	80.D	65.9	847	6.87	Hay	BON -	Nove	4%
	. /-00	10	***************************************	A-drop-trans-trans-trans-			347	6
REMARKS:								
	24 /							
SIGNATURE: Mitto Recent REVIEWED BY: KR Page 2 of 2								
	Clie Loc g Diamete to Water Total Depti Casing Vol Centrifuga Submersib H, EC, Te Water Dia Time 0	Project Number Client: Lacation: Stands of the Water (feet): Stands of the Water Disposal Method Submersible Pump OH, EC, Temp. Meter Water Disposal Method Cumulative Discharge (gal) IIIO /0,0 IIIO /0,0 IIIO /0,0 IIIIO /0,0 IIIIO /0,0 IIIIO /0,0 IIIIO /0,0 IIIIO /0,0 IIIIIO /0,0 IIIIO /0,0	Project Number: 20f88 Client: 1 SEC - EMER Location: EMERYU, U.S. g Diameter: 2 inch	Project Number: 20138 - 001.01 Client: LJEC - EMERYULUE Location: Generyulue John John John John John John John John	Project Number: 2018 - 001.019 Client: LSEC - EMERYULLE Location: EMERYULLE Location: EMERYULLE Location: Start	Project Number: 2078 - 001 . 0/9 Client: LJEC - EMERYULUE Location: EMERYULUE, LA g Diameter: 2 inch 3 inch 4 inch 6. 6. 63 Total Depth (feet): Start 19.4 Casing Volume at Start (gal): 2.11 DEVELOPMENT METHOD Centrifugal Pump Bailer (Teflon ®) Surge Bloc Submersible Pump Bailer (PVC) Time Cumulative Temp. 226° C (°F) (µmho/cm) (Stnd) (Phany) Scale 19. Water Disposal Method: Time Cumulative Temp. 226° C (°F) (µmho/cm) (Stnd) (Phany) Scale 19. If I/O 10,0 (31,4 9 75 7.80 Phany) 10,00 I// 20,0 (37,9 9 21 7.24 Phany) 10,00 I// 32 30.0 (38.8 876 7.30 Phany) 10,00 I// 49 40.0 (38.8 870 7.41 Phany) 10,00 I// 49 40.0 (38.8 870 7.41 Phany) 10,00 I// 50,0 (37,9 852 7.35 Phany) 10,00 I// 31 70.0 (58.6 836 6.86 Phany) 10,00 I// 32 80.0 (58.9 847 6.87 Phany) 10,00 I// 33 70.0 (58.6 836 6.86 Phany) 10,000 I// 34 70.0 (58.6 836 6.86 Phany) 10,000 I// 30 80.0 (58.9 847 6.87 Phany) 10,000 I// 31 70.0 (58.6 836 6.86 Phany) 10,000 I// 32 80.0 (58.9 847 6.87 Phany) 10,000 I// 33 70.0 (58.6 836 6.86 Phany) 10,000 I// 34 70.0 (58.6 836 6.86 Phany) 10,000 I// 35 70.0 (58.6 836 6.86 Phany) 10,000 I// 35 70.0 (58.6 836 6.86 Phany) 10,000 I// 35 70.0 (58.6 836 Phany) 10,000 I// 36 70.0 (58.6 836 Phany) 10,000 I// 37 80.0 (58.9 847) (68.7 Phany) 10,000 I// 38 70.0 (58.6 836 Phany) 10,000 I// 38 70.0 (58.6 84 Phany) 10,000 I// 38 70.0 (58.6 84 Phany) 10,000 I// 38 70.0 (58.6 84 Phany) 10,000 I/	Client:	Project Number: 2018 8 - 001.0/9 Client: Lactor - Conceyout Le Location: Exmery Lite Lacation:

Rev. 1, 4/90

WEC Sampling Operation and Maintenance Field Report

CALIBAR		o por action	and Mai		ieid Nepoi	L
COND -7		will	STart) ->	6.53	C.r.	10-12-00
nh -> 6.9	6/7.00	nil (END) ->	6,59	211-	HRT -> 1328
	0/10.00	.,,,,	12.415	UI J	5	T 100
	14.00	DODIH	of Birge	-> 15 fT	surp	ling Time -> 140
emp -		- Sqr.	0.70	7 13 17		
1						
	Tana	C00	ala	ORP		
lime	Temp	COND	ph	(mv)	OX YGEN	NTU
339	18.2	910	Le.74	129	.18	29.0
341	18,0	1130	6.56	093	014	27.9
143	17.9	1070	6.50	093	.16	27. 2
343 345	17.9	1190	6.47	084	.14	23,0
347	17.8	1220	6.54	084	.15	23.7
349	17.8	1220	6.42	083	.16	23.5
351	17,8	1180	6.40	081	.18	23.4
353	17.8	1200	6.38	076	.17	22.5
53	17.7	1/90	6-36	070	-16	19.5
357	17.7	1220	6.34	066	.16	19.5
59	17,6	1230	6.33	064	.17	18.7
-						
					•	
1						
1						
			Ex.			

Name M. Rots

Project Name WEC- EMERYULL

Project Number 20 F 88 - 001.019

APPENDIX C LABORATORY REPORT AND CHAIN-OF-CUSTODY DOCUMENTATION



April 15, 1996

Service Request No: S9600580

Mr. Terry Gyrion EMCON 1921 Ringwood Avenue San Jose, CA 95131

Re: Westinghouse-Emeryville/Project No. 208F88-001.019

Dear Mr. Terry Gyrion:

The following pages contain analytical results for sample(s) received by the laboratory on April 9, 1996. Results of sample analyses are followed by Appendix A which contains sample custody documentation and quality assurance deliverables requested for this project. The work requested has been assigned the Service Request No. Listed above -- to help expedite our service please refer to this number when contacting the laboratory.

Analytical results were produced by procedures consistent with Columbia Analytical Services' (CAS) Quality Assurance Manual (with any deviations noted). Signature of this CAS Analytical Report below confirms that pages 2 through 5, following, have been thoroughly reviewed and approved for release in accord with CAS Standard Operating Procedure ADM-DatRev3.

Please feel welcome to contact me should you have questions or further needs.

Sincerely,

Steven L. Green Project Chemist

SLG/cvr

COLUMBIA ANALYTICAL SERVICES, Inc.

Acronyms

A2LA American Association for Laboratory Accreditation

ASTM American Society for Testing and Materials

BOD Biochemical Oxygen Demand

BTEX Benzene, Toluene, Ethylbenzene, Xylenes

CAM California Assessment Metals
CARB California Air Resources Board

CAS Number Chemical Abstract Service registry Number

CFC Chlorofluorocarbon
CFU Colony-Forming Unit
COD Chemical Oxygen Demand

DEC Department of Environmental Conservation
DEQ Department of Environmental Quality
DHS Department of Health Services
DLCS Duplicate Laboratory Control Sample

DMS Duplicate Matrix Spike
DOE Department of Ecology
DOH Department of Health

EPA U. S. Environmental Protection Agency

ELAP Environmental Laboratory Accreditation Program

GC Gas Chromatography

GC/MS Gas Chromatography/Mass Spectrometry

IC Ion Chromatography

ICB Initial Calibration Blank sample

ICP Inductively Coupled Plasma atomic emission spectrometry

ICV Initial Calibration Verification sample

J Estimated concentration. The value is less than the MRL, but greater than or equal to

the MDL. If the value is equal to the MRL, the result is actually <MRL before rounding.

LUFT Laboratory Control Sample
Leaking Underground Fuel Tank

M Modified

MBAS Methylene Blue Active Substances

MCL Maximum Contaminant Level. The highest permissible concentration of a

substance allowed in drinking water as established by the U. S. EPA.

MDL Method Detection Limit
MPN Most Probable Number
MRL Method Reporting Limit

MS Matrix Spike

MTBE Methyl tert-Butyl Ether

NA Not Applicable
NAN Not Analyzed
NC Not Calculated

NCASI National Council of the paper industry for Air and Stream Improvement
ND Not Detected at or above the method reporting/detection limit (MRL/MDL)

NIOSH National Institute for Occupational Safety and Health

NTU Nephelometric Turbidity Units

ppb Parts Per Billion ppm Parts Per Million

PQL Practical Quantitation Limit
QA/QC Quality Assurance/Quality Control
RCRA Resource Conservation and Recovery Act

RPD Relative Percent Difference SIM Selected Ion Monitoring

SM Standard Methods for the Examination of Water and Wastewater, 18th Ed., 1992

STLC Solubility Threshold Limit Concentration

SW Test Methods for Evaluating Solid Waste, Physical/Chemical Methods, SW-846,

3rd Ed., 1986 and as amended by Updates I, II, IIA, and IIB.

TCLP Toxicity Characteristic Leaching Procedure

TDS Total Dissolved Solids

TPH Total Petroleum Hydrocarbons

tr Trace level. The concentration of an analyte that is less than the PQL but greater than or equal

to the MDL. If the value is equal to the PQL, the result is actually <PQL before rounding.

TRPH Total Recoverable Petroleum Hydrocarbons

TSS Total Suspended Solids

TTLC Total Threshold Limit Concentration

VOA Volatile Organic Analyte(s) ACRONLST,DOC 7/14/95

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client:

EMCON

Project:

Sample Matrix: Water

Westinghouse-Emeryville/#20F88-001.019

Service Request: L9602068 Date Collected: 4/9/96

Date Received: 4/9/96

Date Extracted: 4/10/96

Polychlorinated Biphenyls (PCBs) EPA Methods 3510/8080 Units: ug/L (ppb)

	Sample Name: Lab Code: Date Analyzed:	S-9 L9602068-001 4/11/96	Method Blank L9602068-MB 4/11/96
Analyte	MRL		
Aroclor 1016	0.1	ND	ND
Aroclor 1221	0.1	ND	ND
Aroclor 1232	0.1	ND	ND
Aroclor 1242	0.1	ND	ND
Aroclor 1248	0.1	ND	ND
Aroclor 1254	0.1	ND	ND
Aroclor 1260	0.1	ND	ND

APPENDIX A

COLUMBIA ANALYTICAL SERVICES, INC.

QA/QC Report

Client:

EMCON

Project:

Westinghouse-Emeryville/#20F88-001.019

Sample Matrix: Water

Service Request: L9602068

Date Collected: NA

Date Received: NA

Date Extracted: NA

Date Analyzed: NA

Surrogate Recovery Summary Polychlorinated Biphenyls (PCBs) EPA Methods 3510/8080

Sample Name	Lab Code	Percent Recovery Tetrachloro- <i>m</i> -xylene
S-9	L9602068-001	54
Method Blank	L9602068-MB	66

CAS Acceptance Limits: 45-140

Services (960206 8 1280 • FAX (408) 437-9358 Analytical Services

CHAIN OF CUSTODY/LABORATORY ANALYSIS REPORT FORM SERVICE REQUEST NO 9/6/00/5/3/0

II. Report (induces DUP.MAS. MSD, as required, may be charged as samples) REPORT REQUIREMENTS III. Data Yafdabon Report (includes All Raw Data) REMARKS (NDLs:POLSTRACE*) I. Roubine Report Provide Verbal Preliminary Results TURNAROUND BEQUIREMENTS 24 h / 48 hr. 35 day Provide FAX prelimipary Results H-SO-11-50-11-50-1 Standard (10-15 working days) ANALYSIS REQUESTED Requested Report Date ≥ atterna Hasupa Signature inc Hayangaa 오 Printed Name CP RECEIVED BY: 모 93/0//hmy N. 오 모 끞 550 ₽ N RELINGUISHED BY PRESERVATIVE ИЛМВЕЙ ОР СОИТАІИЕНЗ PROJECT NAMEWESTINGHOUSE - EMERY & LE 20 F88-00101) SAMPLE RECEIVED BY: PHONE LD GB FAX 19.9.96 **Date/Time** 50% COMPANY/ADDRESS EMCON LINGWOOD 1-9.16 DATE 550 PROJECT MGR. 67/2/01 RELINQUISHED BY: SAMPLERS SIGNATURE SAMPLE 0 0 Date:Time t in

1	
362515	; PINK - retained by originator
	del -
2026	; YELLOW · lab;
EDEK 9.	DISTRIBUTION: WHITE - return to originator;
سلخا	DISTRIBUTION:

400-5

Zn

>

S

S Ag

¥

ž

å

Z

₽ B

Fe

ပ္ပ

S

ర

Ca

8

Ba

Sb Pb As As

Metals:

Printed Name

Printed Name

Signature

Signature

Dale/Time

DateTime

FIFTE

SPECIAL INSTRUCTIONS/COMMENTS: Gircle which metals are to be analyzed:

RECEIVED BY:

RELINGUISHED BY: