
ţ



111




Results of a Soil and Ground-Water Investigation in the Vicinity of the Former Underground Storage Tanks at the Beach Street Area at the Yerba Buena/East Baybridge Project Site, Oakland, California

> April 8, 1996 LF 1649.95-25

Prepared for Catellus Development 201 Mission Street, Second Floor San Francisco, California 94121







April 8, 1996 LF 1649.95-025

Ms. Susan Hugo Alameda County Health Care Services Agency 80 Swan Way, Suite 200 Oakland, California 94621

Subject:

Results of a Soil and Ground-Water Investigation in the Vicinity of the Former Underground Storage Tanks at the Beach Street Area, Yerba Buena/East Baybridge Project Site, Oakland, California

Troject Site, Summa

Dear Ms. Hugo:

The enclosed report presents the results of soil and ground-water investigation conducted west of two fuel underground storage tanks formerly located in the northwest portion of the Yerba Buena/East Baybridge project site in Oakland, California.

The scope of the investigation was conducted in accordance with the document entitled, "Work Plan to Install One Monitoring Well and Two Soil Borings in the Beach Street Area Yerba Buena/East Baybridge Project Site, Oakland, California" dated March 31, 1994. This work was performed in response to a request by the Alameda County Health Care Services Agency in a letter dated February 22, 1994 to Ms. Kimberly Brandt of Catellus Development Corporation, the property owners.

If you have any questions, please contact Ron Goloubow.

Sincerely,

Ron E. Goloubow

Senior Project Geologist

Enclosure

cc: Mr. James Adams, Catellus Development

CONTENTS

CERTIFICATION	iii
.0 INTRODUCTION	1
2.0 BACKGROUND	1
3.0 OBJECTIVE	2
3.0 SCOPE OF WORK	2
5.0 FIELD INVESTIGATION	2
5.1 Soil Borings	2
5.2 Soil and Grab Ground-Water Sampling	2
5.3 Monitoring Well Installation, Development, Purging, and Sampling	3
5.4 Monitoring Well Location and Elevation Survey	3
5.5 Ground-Water Occurrence and Flow Direction	
5.0 ANALYTICAL RESULTS	4
6.1 Soil Samples	4
6.2 Ground-Water Samples	4
O CONCLUSIONS AND RECOMMENDATIONS	5

TABLES

1 Analytical Results for Soil and Ground-Water Samples Collected Near Former UST Location, Beach Street Area, East Baybridge Center

FIGURES

- 1 Site Location Map
- 2 Site Plan Showing Ground-Water Elevations in Shallow Wells, December 19, 1995, and Locations of New Soil Borings EB-1 and EB-2 and Monitoring Well MW-12R

APPENDICES

- A Well Construction and Lithology Logs
- B Water-Quality Sampling Information
- C Analytical Reports for Soil and Ground-Water Samples

Page ii 1649SGWI RPT:ADM

CERTIFICATION

All hydrogeologic and geologic information, conclusions, and recommendations in this document have been prepared under the supervision of and reviewed by a Levine-Fricke California Registered Geologist.

Donald T. Bradshaw

Principal Hydrogeologist

California Registered Geologist (5300)

Page iii

1.0 INTRODUCTION

This report describes the results of soil and ground-water samples collected west and downgradient from two fuel underground storage tanks (USTs) formerly located in the northwest portion (Beach Street area) of the Yerba Buena/East Bay Bridge Project Site ("the Site") in Oakland, California (Figures 1 and 2). The samples were collected during the installation of one ground-water monitoring well (MW-12R) and two soil borings (EB-1 and EB-2). Levine Fricke performed this work in response to a request by the Alameda County Health Care Services Agency (ACHA) in letter dated February 22, 1994 to Catellus Development Corporation, the property owners and in accordance with the "Work Plan to Install One Monitoring Well and Two Soil Borings in the Beach Street Area Yerba Buena/East Baybridge Project Site, Oakland, California" dated March 31, 1994. The work plan was approved by the ACHA in a letter to Catellus dated June 10, 1994.

2.0 BACKGROUND

During excavation of petroleum-affected soil identified during previous investigations conducted by Levine Fricke, two 12,000-gallon fuel USTs were encountered in the northwestern portion of the Site (Figure 2). The USTs were removed and disposed of by a licensed hazardous waste transportation company under a hazardous waste manifest in August 1993. Inspection of the USTs after removal indicated several holes at the bottom and top of each UST.

Approximately 6,000 cubic yards (cy) of petroleum-affected soil were removed from the UST excavation and in the vicinity of the USTs. Soil samples collected from the final excavation bottom and sidewalls indicated that concentrations of petroleum hydrocarbons were reduced to cleanup goals for the Site, with the exception of approximately 90 cy of soil along the western property boundary. This material was left in place because of geotechnical considerations concerning stability of the excavation sidewalls adjacent to Beach Street and the sidewalk.

The area of on-site affected soil is located at a depth of 7.5 to 15 feet below ground surface (bgs), and extends from the western property line approximately 5.5 feet east. The excavation was backfilled in October 1993. A report describing UST removal and soil remediation activities was prepared by Levine-Fricke and submitted to the ACHA and Regional Water Quality Control Board (RWQCB) for review (Levine-Fricke 1993). In that report, Levine-Fricke recommended that one well be installed downgradient (west) from the former USTs to assess the potential effect of petroleum hydrocarbons on shallow ground-water quality. It was proposed that ground-water samples be collected from the monitoring well for analysis of petroleum hydrocarbons on a quarterly basis for at least one year. In addition, in response to the ACHA request, it was proposed that two soil borings (EB-1 and EB-2) be drilled west of the former USTs

Page 1

to assess the possible lateral extent of petroleum-affected soil in the vicinity of the USTs.

3.0 OBJECTIVE

The objective of the work was to assess the extent of petroleum-affected soil and shallow ground water downgradient from the former USTs. To meet this objective, soil and ground-water samples were collected and submitted for analysis from soil borings EB-1 and EB-2 and ground-water monitoring well MW-12R.

4.0 SCOPE OF WORK

In order to meet the objective of this investigation, the following scope of work was implemented:

- drilling of two soil borings and the installation of one shallow ground-water monitoring well
- analysis of soil and ground-water samples
- preparation of this summary report

5.0 FIELD INVESTIGATION

Soil boring, soil sampling, well installation, and ground-water sampling conducted during this investigation are presented in this section. Before conducting the field work, an excavation permit was obtained from the City of Oakland Public Works Department, and a drilling permit was obtained from the Alameda County Flood Control District, Zone 7. Lithology logs and well completion details are included in Appendix A. Drilling and sampling equipment were steam cleaned before the start of work and also after completion of each boring to reduce the potential for cross contamination.

5.1 Soil Borings

On December 14 and 18, 1995, Levine Fricke retained Gregg Drilling Company ("Gregg") to drill two soil borings using a truck-mounted drill rig equipped with hollow-stem augers at the locations shown on Figure 2. Each boring was drilled to approximately 9 feet bgs and were backfilled to grade with Portland-cement grout.

5.2 Soil and Grab Ground-Water Sampling

Soil samples were collected on a continuous basis using a split-spoon sampler, lined with brass tubes from approximately 4 feet bgs to the total depth of each boring. A

Page 2

photoionization detector (PID) was used in the field to screen soil samples for the presence of volatile organic compounds (VOCs). Results of the PID screening were recorded on the boring logs and are presented in Appendix A.

One soil sample was submitted for chemical analysis from borings EB-1 and MW-12R. Three soil samples were submitted for chemical analysis from boring EB-2. Sample depths ranged from 6.5 to 11.5 feet bgs. Samples were stored in a cooled ice chest and transported under chain-of-custody procedures to American Environmental Network (AEN), a state-certified analytical laboratory located in Pleasant Hill, California.

Two grab ground-water samples (one from each soil boring) were collected and analyzed. Grab ground-water samples were obtained by drilling each soil boring until ground water was observed at a depth of 5 to 8 feet bgs in each soil boring. A disposable Teflon bailer was then lowered into the borehole and used to obtain the ground-water sample. Ground-water samples were stored in a cooled ice chest and transported under chain-of-custody procedures to AEN.

5.3 Monitoring Well Installation, Development, Purging, and Sampling

On December 14, 1995, shallow ground-water monitoring well MW-12R was completed using Schedule 40, 2-inch diameter to a depth of 15.5 feet bgs. Factory-slotted 0.02-inch screen was installed from 15.5 to 5.5 feet bgs in MW-12R. A sand pack of No. 3 Monterey sand was installed adjacent to the screened interval from the well bottom to approximately six inches above the top of the screened interval. A seal of bentonite pellets, one foot thick, was placed over the top of the sand pack. The remaining annular space was backfilled with a Portland-type cement to grade surface. The well was finished with flush-mounted monument and a locking waterproof cap.

Approximately two weeks after well installation, MW-12R was developed using a centrifugal pump to remove water and fine sediments inside the well casing. Development continued until field characteristics (i.e., pH, temperature, and turbidity) stabilized and water was relatively free of suspended sediments. Following development a ground-water sample was collected from well MW-12R using a Teflon bailer.

Well development and ground-water sampling data were recorded by Levine Fricke field personnel. These data are presented in Appendix B.

5.4 Monitoring Well Location and Elevation Survey

Kier and Wright, a licensed surveyor, surveyed the top of casing elevation of monitoring well MW-12R on December 21, 1995. An elevation of 10.42 feet above mean sea level was measured for the top of casing at well MW-12R.

1649SGWLRPT.ADM

5.5 Ground-Water Occurrence and Flow Direction

On December 19, 1995 ground-water elevations of monitoring and extraction wells at the East Baybridge Center were measured by Levine-Fricke personnel. Depth to water at well MW-12R was measured at 10.69 feet below the top of casing. A ground-water contour map was prepared using ground-water elevation data collected on December 19, 1995 (Figure 2). This ground-water elevation contour map indicates that in the Beach Street Area ground-water flow direction is to the west. Saturated sediments at boring EB-1 were observed at 8 feet bgs and between 5 and 8 feet bgs at boring EB-2.

6.0 ANALYTICAL RESULTS

Analytical results for the soil and ground-water samples collected during this investigation are presented in this section. A total of five soil samples was analyzed for total petroleum hydrocarbons as gasoline (TPHg), using EPA Modified Method 8015, TPH as diesel and oil (TPHd and TPHo) using EPA Method 3510, and benzene, toluene, ethylbenzene, and total xylenes (BTEX) using EPA Method 8020. Grab ground-water samples from soil borings EB-1 and EB-2 and a ground-water sample from MW12R were also analyzed for TPHg, BTEX, TPHd, and TPHo using EPA Methods 8015/8020 and 3510, respectively. Analytical results for the soil and ground-water samples are summarized on Table 1.

6.1 Soil Samples

TPHo was detected each soil sample (Table 1). Concentrations of TPHo ranged from 7 parts per million (ppm) in well MW-12R at a depth of 11.5 feet bgs to 3,400 ppm in soil boring EB-1 at a depth of 7 feet bgs. TPHd was detected in soil samples from EB-1 and EB-2 at concentrations ranging from 40 to 1,900 ppm. Three samples from soil boring EB-2 contained detectable concentrations of TPHg ranging from 7.5 ppm at 6.5 feet bgs to 20 ppm at 8 feet bgs. BTEX was not present above detection limits for any of the soil samples.

6.2 Ground-Water Samples

TPHd was detected in the four ground-water samples collected during this investigation (Table 1).

- TPHd was detected in EB-1, EB-2, and MW-12R at concentrations of 0.2 to 3.8 ppm.
- TPHg was detected in samples collected from borings EB-1 and EB-2 at 0.1 and 0.52 ppm, respectively. TPHg was not present above analytical detection limits in the sample collected from well MW-12R.

Page 4

- TPHo was detected in the sample collected from boring EB-2 at 3.4 ppm. TPHo was not present above analytical detection limits in the samples collected from well MW-12R or boring EB-1.
- Low concentrations (near detection limits) of benzene (0.0005 ppm) and toluene (0.0006 ppm) were detected in sample EB-1. BTEX were not present above detection limits in samples collected from boring EB-2 or well MW-12R. Certified analytical reports are included in Appendix C.

7.0 CONCLUSIONS AND RECOMMENDATIONS

Results of this investigation indicated that petroleum hydrocarbons have affected the soil and ground-water west and downgradient from the former USTs. Since 6,000 cy of affected soil were removed near the source of the former USTs, Levine Fricke does not recommend any additional remediation in the vicinity of the former USTs. Given the relatively low concentrations of TPHd (up to 3.8 ppm) detected in the ground-water samples collected during this investigation, no additional investigation is warranted at this Site.

It is recommended that well MW-12R be incorporated into the quarterly monitoring program for the East Baybridge Center Development for one year. In addition to water levels measured at this well, samples collected from this well will be analyzed for TPHd, TPHg, and BTEX. Results will be included in the quarterly monitoring report which is submitted to the RWQCB and ACHA. After one year of monitoring, groundwater quality data collected from well MW-12R will be evaluated to determine if further monitoring is warranted at well MW-12R.

1649SGWLRPT:ADM Page 5

Table 1

Analytical Results for Soil and Ground-Water Samples Collected Near Former UST Location,
Beach Street Area, East Baybridge Center, Oakland, California

(Concentrations expressed in parts per million [mg/l])

(ft bgs) Sampled Type Lab TPHg TPHd TPHo Benzene Toluene MW-12R (11.5) 14-Dec-95 Soil AEN < 0.2 < 1 7 < 0.005 < 0.005 EB-1 (7) 18-Dec-95 Soil AEN < 0.2 70 3,400 < 0.005 < 0.005 EB-2 (6.5) 18-Dec-95 Soil AEN 7.5 40 200 < 0.010 < 0.010 EB-2 (8) 18-Dec-95 Soil AEN 20 840 1,100 < 0.020 < 0.020 EB-2 (9.5) 18-Dec-95 Soil AEN 19 1,900 2,400 < 0.020 < 0.020 EB-1GGW 18-Dec-95 Water AEN 0.1 0.5 < 0.2 0.0005 0.0006		Total
EB-1 (7) 18-Dec-95 Soil AEN <0.2 70 3,400 <0.005 <0.005 EB-2 (6.5) 18-Dec-95 Soil AEN 7.5 40 200 <0.010 <0.010 EB-2 (8) 18-Dec-95 Soil AEN 20 840 1,100 <0.020 <0.020 EB-2 (9.5) 18-Dec-95 Soil AEN 19 1,900 2,400 <0.020 <0.020	Ethylbenzene	Xylenes
EB-2 (6.5) 18-Dec-95 Soil AEN 7.5 40 200 <0.010 <0.010 EB-2 (8) 18-Dec-95 Soil AEN 20 840 1,100 <0.020 <0.020 EB-2 (9.5) 18-Dec-95 Soil AEN 19 1,900 2,400 <0.020 <0.020	< 0.005	< 0.005
EB-2 (8) 18-Dec-95 Soil AEN 20 840 1,100 <0.020 <0.020 EB-2 (9.5) 18-Dec-95 Soil AEN 19 1,900 2,400 <0.020 <0.020	< 0.005	< 0.005
EB-2 (9.5) 18-Dec-95 Soil AEN 19 1,900 2,400 <0.020 <0.020	< 0.010	< 0.030
	< 0.020	< 0.060
EB-1GGW 18-Dec-95 Water AEN 0.1 0.5 <0.2 0.0005 0.0006	< 0.020	< 0.060
	< 0.0005	< 0.002
EB-2GGW 18-Dec-95 Water AEN 0.52 3.8 3.4 < 0.0005 < 0.0005	< 0.0005	< 0.002
MW-12R 27-Dec-95 Water AEN NA 0.2 <0.2 NA NA	NA	NA
MW-12R 26-Feb-96 Water AEN <0.05 0.36 <0.2 <0.0005 <0.0005	< 0.0005	< 0.0005

Data entered by PCA 29-Mar-96. Proofed by REG.

Notes:

TPHg - total petroleum hydrocarbons as gasoline

TPHd - total petroleum hydrocarbons as diesel

TPHo - total petroleum hydrocarbons as oil

NA - not analyzed

ft bgs = feet below ground surface

GGW = grab ground water




Figure 1: SITE LOCATION MAP

Project No. 1649.16

LEVINE-FRICKE
ENGINEERS, HYDROGEOLOGISTS & APPLIED SCIENTISTS

0 150 300 FEZT


EXPLANATION

- MONITORING WELL LOCATION
- A EXTRACTION WELL
- X ABANDONED GROUND WATER MONITORING WELL
- SOIL BORING LOCATION
- _____ APPROXIMATE AREA OF VOC~AFFECTED GROUND WATER

----- APPROXIMATE PROPERTY LINE

8 57 GROUND-WATER ELEVATION

12 GROUND-WATER ELEVATION CONTOUR (FEET, MSL)



├	,	r					
	REVISION	DES GN	NWAFC	CHECKED	DATE		
1		i			i	SCALE .	
I		!				DESIGN	
1		Ì				DESTON	
\vdash						DRAWN	
	1	1 .			<u> </u>	DICALOR	
i		i		į		CHECKED	
1		 	.				





YERBA	BUENA/EAST	BAYBRIDGE	DEVELOPMENT
		Figure 2	

Figure 2							
SITE PLAN SHOWING GROUND-WATER ELEVATIONS							
IN SHALLOW WELLS, DECEMBER 19, 1995, AND							
LOCATIONS OF NEW SOIL BORINGS EB-1 AND							
EB-2 AND MONNORING WELL MW-12R							


roject No 1649

Date JAN. 96

Sheet

APPENDIX A

WELL CONSTRUCTION AND LITHOLOGY LOGS








Figure A1: WELL CONSTRUCTION AND LITHOLOGY FOR WELL MW-12R








Figure A2: LITHOLOGY AND SAMPLE DATA FOR SOIL BORING EB-1 AND EB-2

APPENDIX B

WATER-QUALITY SAMPLING INFORMATION

WATER-QUALITY SAMPLING INFORMATION

Date: 12/27/95
Sample No.: MW 1722
☐ FB: 117' e
DUP:
A 25 C . 2 A
Consult Mar
/ 8.55
10.94
7.61
.16
4566
761
12176
7.61 18.55
7.61 18.55
6088 12.46
12 46
80% DTW_12.46
nrbidity Remarks
STALT
TURBO; BLOTEMESOFSNE
TURBIN BLOTENES
TURBIA
TUBNO OFF
ON
TUPBID
——————————————————————————————————————
7. 4213
TURBID/OFF TURBID TURBID TURBID ON/OFF TURBIN
TURBIO
1 2 11 / 2 2 2 2 2 2
SA OFF TURISIO
SM-PLE (11:45 ON UNSELS
SHOWED BLOTCHED OF

TIANTER VOILINFR

APPENDIX C

ANALYTICAL REPORTS FOR SOIL AND GROUND-WATER SAMPLES

American Environmental Network

Certificate of Analysis

DOHS Certification: 1172

AIHA Accreditation: 11134

PAGE 1

LEVINE-FRICKE 1900 POWELL ST. 12TH FL. EMERYVILLE, CA 94608

ATTN: LARRY LAPUYADE CLIENT PROJ. ID: 1649.25

CLIENT PROJ. NAME: EAST BAY BRIDG

C.O.C. NUMBER: 19222

REPORT DATE: 01/12/96

DATE(S) SAMPLED: 12/18/95

DATE RECEIVED: 12/18/95

AEN WORK ORDER: 9512236

PROJECT SUMMARY:

On December 18, 1995, this laboratory received 6 (2 water & 4 soil) sample(s).

Client requested sample(s) be analyzed for organic parameters. Results of analysis are summarized on the following page(s). Please see quality control report for a summary of QC data pertaining to this project.

Samples will be stored for $30~{\rm days}$ after completion of analysis, then disposed of in accordance with State and Federal regulations. Samples may be archived by prior arrangement.

If you have any questions, please contact Client Services at (510) 930-9090.

Larry Klein

Laboratory Director

LEVINE-FRICKE

SAMPLE ID: EB-1GGW AEN LAB NO: 9512236-01 AEN WORK ORDER: 9512236 CLIENT PROJ. ID: 1649.25 DATE SAMPLED: 12/18/95 DATE RECEIVED: 12/18/95 REPORT DATE: 01/12/96

ANALYTE	METHOD/ CAS#	RESULT	REPORTING LIMIT	UNITS	DATE ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes, Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	0.5 * 0.6 * ND ND 0.1 *	0.5 0.5	ug/L ug/L ug/L ug/L mg/L	12/26/95 12/26/95 12/26/95 12/26/95 12/26/95
#Extraction for TPH	EPA 3510	-		Extrn Date	12/29/95
TPH as Diesel	GC-FID	0.5 *	0.05	mg/L	12/30/95
TPH as Oil	GC-FID	ND	0.2	mg/L	12/30/95

ND = Not detected at or above the reporting limit
* = Value at or above reporting limit

LEVINE-FRICKE

SAMPLE ID: EB-2GGW AEN LAB NO: 9512236-02 AEN WORK ORDER: 9512236 CLIENT PROJ. ID: 1649.25 DATE SAMPLED: 12/18/95 DATE RECEIVED: 12/18/95 REPORT DATE: 01/12/96

ANALYTE -	METHOD/ CAS#	RESULT	REPORTIN LIMIT	G UNITS	DATE ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes, Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	ND . ND ND ND ND 0.52 *	0.5 0.5 2	ug/L ug/L ug/L ug/L mg/L	12/26/95 12/26/95 12/26/95 12/26/95 12/26/95
#Extraction for TPH	EPA 3510	-		Extrn Date	12/29/95
TPH as Diesel	GC-FID	3.8 *	0.05	mg/L	12/30/95
TPH as Oil	GC-FID	3.4 *	0.2	mg/L	12/30/95

ND = Not detected at or above the reporting limit
* = Value at or above reporting limit

LEVINE-FRICKE

SAMPLE ID: EB-2-6.5 AEN LAB NO: 9512236-03 AEN WORK ORDER: 9512236 CLIENT PROJ. ID: 1649.25

DATE SAMPLED: 12/18/95 DATE RECEIVED: 12/18/95 **REPORT DATE:** 01/12/96

ANALYTE	METHOD/ CAS#	RESULT	REPORTIN LIMIT	G UNITS	DATE S ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes, Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	ND ND ND ND 7.5	10 10 30	ug/kg ug/kg ug/kg ug/kg mg/kg	12/19/95 12/19/95 12/19/95 12/19/95 12/19/95
#Extraction for TPH	EPA 3550	-		Extrn Da	te 12/31/95
TPH as Diesel	GC-FID	40 %	* 5	mg/kg	01/02/96
TPH as 0il	GC-FID	200 *	30	mg/kg	01/02/96

RLs elevated for gas/BTEX and diesel due to high levels of target compounds. Sample run at dilution.

LEVINE-FRICKE

SAMPLE ID: EB-2-8 AEN LAB NO: 9512236-04 AEN WORK ORDER: 9512236 CLIENT PROJ. ID: 1649.25

DATE SAMPLED: 12/18/95 DATE RECEIVED: 12/18/95 REPORT DATE: 01/12/96

ANALYTE .	METHOD/ CAS#	RESULT	REPORTING LIMIT	G UNITS	DATE ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes, Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	ND ND ND ND 20 *	20 20 60	ug/kg ug/kg ug/kg ug/kg mg/kg	12/19/95 12/19/95 12/19/95 12/19/95 12/19/95
#Extraction for TPH	EPA 3550	-		Extrn Da	te 12/31/95
TPH as Diesel	GC-FID	840 *	10	mg/kg	01/02/96
TPH as Oil	GC-FID	1,100 *	50	mg/kg	01/02/96

RLs elevated for gas/BTEX and diesel due to high levels of target compounds. Sample run at dilution.

LEVINE-FRICKE

SAMPLE ID: EB-2-9.5 AEN LAB NO: 9512236-05 AEN WORK ORDER: 9512236 CLIENT PROJ. ID: 1649.25 DATE SAMPLED: 12/18/95 DATE RECEIVED: 12/18/95 REPORT DATE: 01/12/96

ANALYTE	METHOD/ CAS#	RESULT	REPORTING LIMIT	UNITS	DATE ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes, Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	ND ND ND ND 19 *	20 t 20 t 60 t	ıg/kg ıg/kg ıg/kg ıg/kg ıg/kg	12/19/95 12/19/95 12/19/95 12/19/95 12/19/95
#Extraction for TPH	EPA 3550	-	Ε	xtrn Date	12/31/95
TPH as Diesel	GC-FID	1,900 *	10 m	ıg/kg	01/02/96
TPH as 0il	GC-FID	2,400 *	50 m	ıg/kg	01/02/96

RLs elevated for gas/BTEX and diesel due to high levels of target compounds. Sample run at dilution.

LEVINE-FRICKE

SAMPLE ID: EB-1-7 AEN LAB NO: 9512236-06 AEN WORK ORDER: 9512236 CLIENT PROJ. ID: 1649.25 DATE SAMPLED: 12/18/95 DATE RECEIVED: 12/18/95 REPORT DATE: 01/12/96

ANALYTE	METHOD/ CAS#	RESULT	REPORTING LIMIT	G UNITS	DATE ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes. Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	ND ND ND ND ND	5 5 5	ug/kg ug/kg ug/kg ug/kg mg/kg	12/20/95 12/20/95 12/20/95 12/20/95 12/20/95
#Extraction for TPH	EPA 3550	-		Extrn Dat	e 12/31/95
TPH as Diesel	GC-FID	70 *	50	mg/kg	01/04/96
TPH as Oil	GC-FID	3,400 *	300	mg/kg	01/04/96

RL elevated for diesel due to high levels of target compounds. Sample run at dilution.

AEN (CALIFORNIA) QUALITY CONTROL REPORT

AEN JOB NUMBER: 9512236

CLIENT PROJECT ID: 1649.25

Quality Control Summary

All laboratory quality control parameters were found to be within established limits.

<u>Definitions</u>

Laboratory Control Sample (LCS)/Method Spike(s): Control samples of known composition. LCS and Method Spike data are used to validate batch analytical results.

Matrix Spike(s): Aliquot of a sample (aqueous or solid) with added quantities of specific compounds and subjected to the entire analytical procedure. Matrix spike and matrix spike duplicate QC data are advisory.

Method Blank: An analytical control consisting of all reagents, internal standards, and surrogate standards carried through the entire analytical process. Used to monitor laboratory background and reagent contamination.

Not Detected (ND): Not detected at or above the reporting limit.

Relative Percent Difference (RPD): An indication of method precision based on duplicate analysis.

Reporting Limit (RL): The lowest concentration routinely determined during laboratory operations. The RL is generally 1 to 10 times the Method Detection Limit (MDL). Reporting limits are matrix, method, and analyte dependent and take into account any dilutions performed as part of the analysis.

Surrogates: Organic compounds which are similar to analytes of interest in chemical behavior, but are not found in environmental samples. Surrogates are added to all blanks, calibration and check standards, samples, and spiked samples. Surrogate recovery is monitored as an indication of acceptable sample preparation and instrumental performance.

- D: Surrogates diluted out.
- #: Indicates result outside of established laboratory QC limits.

QUALITY CONTROL DATA

METHOD: EPA 3510 GCFID

AEN JOB NO: 9512236 AEN LAB NO: 1229-BLANK DATE EXTRACTED: 12/29/95
DATE ANALYZED: 12/30/95
INSTRUMENT: C

MATRIX: WATER

Method Blank

Analyte	Result (mg/L)	Reporting Limit (mg/L)
Diesel	ND	0.05
Oil	ND	0.2

QUALITY CONTROL DATA

METHOD: EPA 3510 GCFID

AEN JOB NO: 9512236 DATE EXTRACTED: 12/29/95 INSTRUMENT: C

MATRIX: WATER

Surrogate Standard Recovery Summary

Date Analyzed	Client Id.	Lab Id.	Percent Recovery n-Pentacosane
12/30/95 12/30/95	EB-1GGW EB-2GGW	01 02	101 107
QC Limits:			59-118

DATE EXTRACTED: 12/31/95 DATE ANALYZED: 01/02/96 DI WATER

SAMPLE SPIKED: INSTRUMENT: C

Method Spike Recovery Summary

	Spike	Avonago		QC Limit	ts
Analyte	Added (mg/L)	Average Percent Recovery	RPD	Percent Recovery	RPD
Diesel	2.03	72	1	58-107	15

QUALITY CONTROL DATA

METHOD: EPA 3550 GCFID

AEN JOB NO: 9512236 AEN LAB NO: 1231-BLANK DATE EXTRACTED: 12/31/95 DATE ANALYZED: 01/02/96

INSTRUMENT: A MATRIX: SOIL

Method Blank

Analyte	Result (mg/kg)	Reporting Limit (mg/kg)
Diesel	ND	1
Oil	ND	5

QUALITY CONTROL DATA

METHOD: EPA 3550 GCFID

AEN. JOB NO: 9512236 DATE EXTRACTED: 12/31/95 INSTRUMENT: A

MATRIX: SOIL

Surrogate Standard Recovery Summary

Date Analyzed	Client Id.	Lab Id.	Percent Recovery n-Pentacosane
01/02/96 01/02/96 01/02/96 01/04/96	EB-2-6.5 EB-2-8 EB-2-9.5 EB-1-7	03 04 05 06	92 87 94 D
QC Limits:			45-110

D: Surrogates diluted out.

DATE EXTRACTED: 12/28/95 DATE ANALYZED: 12/28/95 SAMPLE SPIKED: INSTRUMENT: A 9512292-37

Matrix Spike Recovery Summary

	Sniko	Λυορραο		QC Lir	mits
Analyte	Spike Added (mg/kg)	Average Percent Recovery	RPD	Percent Recovery	RPD
Diesel	41.2	74	2	44-108	13

QUALITY CONTROL DATA

METHOD: EPA 8020, 5030 GCFID

AEN JOB NO: 9512236 AEN LAB NO: 1226-BLANK DATE ANALYZED: 12/26/95 INSTRUMENT: F

MATRIX: WATER

Method Blank

	CAS #	Result (ug/L)	Reporting Limit (ug/L)
Benzene	71-43-2	ND	0.5
Toluene	108-88-3	ND	0.5
Ethylbenzene Xylenes, Total	100-41-4 1330-20-7	ND ND	0.5
HCs as Gasoline	1000 20-7	ND mg/L	0.05 mg/L

QUALITY CONTROL DATA

METHOD: EPA 8020, 5030 GCFID

AEN JOB NO: 9512236

INSTRUMENT: MATRIX: WATER

Surrogate Standard Recovery Summary

Date Analyzed	Client Id.	Lab Id.	Percent Recovery Fluorobenzene
12/26/95 12/26/95	EB-1GGW EB-2GGW	01 02	92 93
QC Limits:			70-130

DATE ANALYZED: 12/26/95 SAMPLE SPIKED: LCS INSTRUMENT F

Laboratory Control Sample Recovery

	C			QC Limi	ts
Analyte	Spike Added (ug/L)	Average Percent Recovery	RPD	Percent Recovery	RPD
Benzene Toluene Hydrocarbons	17.9 53.9	80 87	13 10	60-120 60-120	20 20
as Gasoline	500	98	5	60-120	20

QUALITY CONTROL DATA

METHOD: EPA 8020, 5030 GCFID

AEN JOB NO: 9512236 AEN LAB NO: 1219-BLANK DATE ANALYZED: 12/19/95

INSTRUMENT: E MATRIX: SOIL

Method Blank

Analyte	CAS #	Result (ug/kg)	Reporting Limit (ug/kg)
Benzene Toluene Ethylbenzene Xylenes, Total HCs as Gasoline	71-43-2 108-88-3 100-41-4 1330-20-7	ND ND ND ND ND mg/kg	5 5 5 5 0.2 mg/kg

AEN LAB NO: 1220-BLANK DATE ANALYZED: 12/20/95

INSTRUMENT: E

Method Blank

Analyte	CAS #	Result (ug/kg)	Reporting Limit (ug/kg)
Benzene Toluene Ethylbenzene Xylenes, Total HCs as Gasoline	71-43-2 108-88-3 100-41-4 1330-20-7	ND ND ND ND ND mg/kg	5 5 5 5 0.2 mg/kg

QUALITY CONTROL DATA

METHOD: EPA 8020, 5030 GCFID

AEN JOB NO: 9512236

INSTRUMENT: E MATRIX: SOIL

Surrogate Standard Recovery Summary

Date Analyzed	Client Id.	Lab Id.	Percent Recovery Fluorobenzene
12/19/95 12/19/95 12/19/95 12/20/95	EB-2-6.5 EB-2-8 EB-2-9.5 EB-1-7	03 04 05 06	107 106 105 116
QC Limits:			70-130

DATE ANALYZED: 12/18/95 SAMPLE SPIKED: 9512080-14

INSTRUMENT · E

Matrix Spike Recovery Summary

	Sniko	Avonage		QC Limi	ts
Analyte	Spike Added (ug/kg)	Average Percent Recovery	RPD	Percent Recovery	RPD
Benzene Toluene Hydrocarbons	36.1 103	99 97	16 11	79-113 84-110	26 20
as Gasoline	1000	101	13	60-126	20

CHAIN OF CUSTODY / ANALYSES REQUEST FORM

05177210

Project No					- · · ·										$\frac{-}{-}$	U U U U	عي در
1	L	549	25		Field	Logb	ook	No.	:		[C	ate:	2-18-95	Serial			
Project Na	me: E	A37 (BAY BRID	- - - - - - - - - - - - - - - - - - -	Projec	ct Lo	catio	n:			مرس	Sal	Plan B	\ \	0	1922	22
Sampler (Si	gnature)	: Ja	u James	mode	·				25 69	NAY	SES			Samp	lerc.		
	1	S	AMPLES (/ 5		9/	7	/	//	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	L	Q L		
SAMPLE NO.	DATE	TIME	LAB SAMPLE NO.	NO. OF CON- TAINERS	SAMPLE TYPE	18		3) 4	90°	//		/ 🔾	2-18-95 rland	-		ARKS	<u> </u>
EB-166W	12-18	1330	DIA-E	5_	GHOM	X	X	χ	入				Re	SUVIS	$\overline{\pi}$	1	
EB-266W		1230	DZA-E	_5	1		1	7	12					rry			\ <u></u>
EB-2-6.5			03A		Solu		-1		17	ľ			1			OTM	77_
EB-2-8			DAA.						18	•			ANAL			~ 0 =	
EB-2-9,5			05A*						1				1740	A50L, LUG	177	ש פיי	12X
EB-1-7	V	-	06A	V	V	V	V	V	1				ماده	a mon	F (3)	FOA (3015/ 802
					,								TOMA	` 0 /			
													1 Prod	esel/TI	PHON	¿moron	- 04
	7.0												USINI	9 EIAI	1. 8 P1	400	
	<u> </u>												32110	y Carr	NACA B	ADOX -	220
	- ;												NOR	mer:	TUZ	NAR	MIN
			•						ļ				T	me.			<u> </u>
									ļ								
									ļ						-		
															_		
RELINQUISHED E	× /1												1				
(Signature) ($\supset I_{L}$	i/)	Sangale ()	DATE	5 TH	1E 54	% R	RECEIVE	D BY:	Med		1/2/1	(6)	D	ATE L	ŢĮME
RELINQUISHED B (Signature)	Y: 12 C	1) I	5-10 m100	7	DATE 12/18/2			R	RECEIVE	D BY:)	well	CMI	Mr.		2 <u>//8/ゲナ</u> ATE	IME 16:05 TIME
RELINQUISHED B (Signature)		2.	1 - 12 4 2		DATE	TIN	IE	R	Signat ECEIVE Signat	D BY:			WSU	leice	- 17	2 1865 ATE	TIME
METHOD OF SHIP	MENT:	Ceru	vila		DATE	TIN	1E		AB COM								
Sample Collector: LEVINE-FRICKE				Analytical Laboratory:													
			1900 Powell Stre	et, 12th F							-4201	a cor y	•				
			Emeryville, Cali (510) 652-4500		800							٧.	AEN				
hipping Copy (ipping Copy (White) Lab Copy (Cases) 5:3, Co. (V.33)									,~, ,	<u>•</u>						

American Environmental Network

Certificate of Analysis

DORS Certification, 1172

AIHA Accreditation: 11134

PAGE 1

LEVINE-FRICKE 1900 POWELL ST. 12TH FL. EMERYVILLE, CA 94608

ATTN: LARRY LAPUYADE

CLIENT PROJ. ID: 1649.25 CLIENT PROJ. NAME: EAST BAY BRIDG

C.O.C. NUMBER: 19221

REPORT DATE: 12/28/95

DATE(S) SAMPLED: 12/14/95

DATE RECEIVED: 12/15/95

AEN WORK ORDER: 9512214

PROJECT SUMMARY:

On December 15, 1995, this laboratory received 1 soil sample(s).

Client requested sample(s) be analyzed for organic parameters. Results of analysis are summarized on the following page(s). Please see quality control report for a summary of QC data pertaining to this project.

Samples will be stored for 30 days after completion of analysis, then disposed of in accordance with State and Federal regulations. Samples may be archived by prior arrangement.

If you have any questions, please contact Client Services at (510) 930-9090.

Laboratory Director

All the second of the second of

LEVINE-FRICKE

SAMPLE ID: MW-12R-11.5 AEN LAB NO: 9512214-01 AEN WORK ORDER: 9512214 CLIENT PROJ. ID: 1649.25

DATE SAMPLED: 12/14/95 DATE RECEIVED: 12/15/95 REPORT DATE: 12/28/95

ANALYTE -	METHOD/ CAS#	RESULT	REPORTING LIMIT UNITS	DATE ANALYZED
BTEX & Gasoline HCs Benzene Toluene Ethylbenzene Xylenes, Total Purgeable HCs as Gasoline	EPA 8020 71-43-2 108-88-3 100-41-4 1330-20-7 5030/GCFID	ND ND ND ND ND	5 ug/kg 5 ug/kg 5 ug/kg 5 ug/kg 0.2 mg/kg	12/18/95 12/18/95 12/18/95 12/18/95 12/18/95
#Extraction for TPH	EPA 3550	-	Extrn Date	12/20/95
TPH as Diesel	GC-FID	ND	1 mg/kg	12/20/95
TPH as 0il	GC-FID	7 *	5 mg/kg	12/20/95

AEN (CALIFORNIA) QUALITY CONTROL REPORT

AEN JOB NUMBER: 9512214

CLIENT PROJECT ID: 1649.25

Quality Control Summary

All laboratory quality control parameters were found to be within established limits.

<u>Definitions</u>

Laboratory Control Sample (LCS)/Method Spike(s): Control samples of known composition. LCS and Method Spike data are used to validate batch analytical results.

Matrix Spike(s): Aliquot of a sample (aqueous or solid) with added quantities of specific compounds and subjected to the entire analytical procedure. Matrix spike and matrix spike duplicate QC data are advisory.

Method Blank: An analytical control consisting of all reagents, internal standards, and surrogate standards carried through the entire analytical process. Used to monitor laboratory background and reagent contamination.

Not Detected (ND): Not detected at or above the reporting limit.

Relative Percent Difference (RPD): An indication of method precision based on duplicate analysis.

Reporting Limit (RL): The lowest concentration routinely determined during laboratory operations. The RL is generally 1 to 10 times the Method Detection Limit (MDL). Reporting limits are matrix, method, and analyte dependent and take into account any dilutions performed as part of the analysis.

Surrogates: Organic compounds which are similar to analytes of interest in chemical behavior, but are not found in environmental samples. Surrogates are added to all blanks, calibration and check standards, samples, and spiked samples. Surrogate recovery is monitored as an indication of acceptable sample preparation and instrumental performance.

- D: Surrogates diluted out.
- #: Indicates result outside of established laboratory QC limits.

QUALITY CONTROL DATA

METHOD: EPA 3550 GCFID

AEN JOB NO: 9512214
AEN LAB NO: 1220-BLANK
DATE EXTRACTED: 12/20/95
DATE ANALYZED: 12/20/95
INSTRUMENT: A

MATRIX: SOIL

Method Blank

Analyte	Result (mg/kg)	Reporting Limit (mg/kg)		
Diesel	ND	1		
Oil	ND	5		

QUALITY CONTROL DATA

METHOD: EPA 3550 GCFID

AEN JOB NO: 9512214 DATE EXTRACTED: 12/20/95 INSTRUMENT: A MATRIX: SOIL

Surrogate Standard Recovery Summary

Date Analyzed	Client Id.	Lab Id.	Percent Recovery n-Pentacosane
12/20/95	MW-12R-11.5	01	88
QC Limits:			45-110

DATE EXTRACTED: 12/15/95 DATE ANALYZED: 12/17/95 SAMPLE SPIKED: 9512115-01

INSTRUMENT: A

Matrix Spike Recovery Summary

	Snika	Augusta		QC Lir	mits
Analyte	Spike Added (mg/kg)	Average Percent Recovery	RPD	Percent Recovery	RPD
Diesel	41.2	82	10	44-108	13

QUALITY CONTROL DATA

METHOD: EPA 8020, 5030 GCFID

AEN JOB NO: 9512214 AEN LAB NO: 1218-BLANK DATE ANALYZED: 12/18/95 INSTRUMENT: E MATRIX: SOIL

Method Blank

Analyte	CAS #	Result (ug/kg)	Reporting Limit (ug/kg)
Benzene	71-43-2	ND	5
Toluene	108-88-3	ND	5
Ethylbenzene	100-41-4	ND	5
Xylenes. Total	1330-20-7	ND	5
Xylenes, Total	1330-20-7	ND	5
HCs as Gasoline		ND mg/kg	0.2

QUALITY CONTROL DATA

METHOD: EPA 8020, 5030 GCFID

AEN JOB NO: 9512214 INSTRUMENT: E MATRIX: SOIL

Surrogate Standard Recovery Summary

Date Analyzed	Client Id.	Lab Id.	Percent Recovery Fluorobenzene
12/18/95	MW-12R-11.5	01	103
QC Limits:			70-130

DATE ANALYZED: 12/17/95 SAMPLE SPIKED: LCS INSTRUMENT E

Laboratory Control Sample Recovery

	Spike	Average		QC Lim	nts
Analyte	Added (ug/kg)	Percent Recovery	RPD	Percent Recovery	RPD
Benzene Toluene	36.1 103	95 98	6 7	60-120 60-120	20 20
Hydrocarbons as Gasoline	1000	113	7	60-120	20

CHAIN OF CUSTODY / ANALYSES REQUEST FORM

Project No.: \ Field Logbook No.: Date: 12-15-98 Serial No.: Project Location: OAK (AM) Νō 19221 Project Name: Sampler (Signature) **ANALYSES** Samplers: HOLD NO. OF LAB SAMPLE SAMPLE SAMPLE NO. DATE TIME CON-REMARKS TYPE TAINERS MW-122-11512-14 -Siù No luse Turnamin RELINQUISHED BY: DATE 12-15-9 TIME 7-30 RECEIVED BY: Mixture (Signature) (Signature) / RELINQUISHED BY: DATE RECEIVED BY: (Signature) (Signature) RELINQUISHED BY: ŤIME RECEIVED BY: (Signature) (Signature) METHOD OF SHIPMENT: DATE TIME LAB COMMENTS: JOUNIL Sample Collector: LEVINE-FRICKE Analytical Laboratory: 1900 Powell Street, 12th Floor Emeryville, California 94608 (510) 652-4500

9512214

LEVINE-FRICKE

SAMPLE ID: MW-12R AEN LAB NO: 9512385-02 AEN WORK ORDER: 9512385 CLIENT PROJ. ID: 1649.95.02

DATE SAMPLED: 12/27/95 DATE RECEIVED: 12/28/95 REPORT DATE: 01/16/96

ANALYTE	METHOD/ CAS#	RESULT	REPORTING LIMIT	G UNITS	DATE ANALYZED
#Extraction for TPH	EPA 3510	-		Extrn Date	01/05/96
TPH as Diesel	GC-FID	0.2 *	0.05	mg/L	01/09/96
TPH as Oil	GC-FID	ND	0.2	mg/L	01/09/96
EPA 8010 - Water matrix Bromodichloromethane Bromoform Bromomethane Carbon Tetrachloride Chlorobenzene Chloroethane 2-Chloroethyl Vinyl Ether Chloroform Chloromethane Dibromochloromethane 1,2-Dichlorobenzene 1,3-Dichlorobenzene 1,4-Dichlorobenzene Dichlorodifluoromethane 1,1-Dichloroethane 1,1-Dichloroethane 1,1-Dichloroethene cis-1,2-Dichloroethene trans-1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene trans-1,3-Dichloropropene Methylene Chloride 1,1,2-Tetrachloroethane Tetrachloroethene 1,1,1-Trichloroethane 1,1,2-Trichloroethane Trichlorofluoromethane	FPA 8010 75-27-4 75-25-2 74-83-9 56-23-5 108-90-7 75-00-3 110-75-8 67-66-3 74-87-3 124-48-1 95-50-1 541-73-1 106-46-7 75-71-8 75-71-8 75-34-3 107-06-2 75-35-4 156-59-2 156-60-5 78-87-5 10061-01-5 10061-02-6 75-09-2 79-34-5 127-18-4 71-55-6 79-00-5 79-01-6 75-69-4 75-613-1 75-01-4	ND N	0.5255255255555555555555555555555555555	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	01/09/96 01/09/96

ND = Not detected at or above the reporting limit
* = Value at or above reporting limit