Stacie H. Frerichs
Team Lead
Marketing Business Unit

Chevron Environmental Management Company
6001 Bollinger Canyon Road
San Ramon, CA 94583
Tel (925) 842-9655
Fax (925) 842-8370

May 12, 2010
(date)

Alameda County Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502-6577

Re: Chevron Facility #_9-1583_____

Address: 5509 Martin Luther King Jr. Way, Oakland, California_____

I have reviewed the attached report titled *Work Plan for Additional Investigation*_____ and dated May 12, 2010.

I agree with the conclusions and recommendations presented in the referenced report. The information in this report is accurate to the best of my knowledge and all local Agency/Regional Board guidelines have been followed. This report was prepared by Conestoga-Rovers & Associates, upon whose assistance and advice I have relied.

This letter is submitted pursuant to the requirements of California Water Code Section 13267(b)(1) and the regulating implementation entitled Appendix A pertaining thereto.

I declare under penalty of perjury that the foregoing is true and correct.

Sincerely,

SH Frerichs

Stacie H. Frerichs
Project Manager

Enclosure: Report

CONESTOGA-ROVERS
& ASSOCIATES

10969 Trade Center Drive, Suite 106, Rancho Cordova, CA 95670
Telephone: 916-889-8900 Facsimile: 916-889-8999
www.CRAworld.com

May 12, 2010

Reference No. 611960

Mr. Mark Detterman, P.G., C.E.G.
Alameda County Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502-6577

Re: Work Plan for Additional Investigation
Former Chevron Service Station No. 9-1583
5509 Martin Luther King Jr. Way
Oakland, California
LOP Case RO0000002

Dear Mr. Detterman:

Conestoga-Rovers & Associates (CRA) has prepared this *Work Plan for Additional Investigation* (work plan) on behalf of Chevron Environmental Management Company (Chevron) for the site referenced above. CRA previously submitted to Alameda County Environmental Health (ACEH) the November 21, 2008 *Soil Vapor Assessment Report* (report), which presented the results of the installation and sampling of five soil vapor wells (VP-1 through VP-5) at the site to evaluate potential vapor intrusion concerns. Elevated concentrations of total petroleum hydrocarbons as gasoline (TPHg) were detected in three of the wells; however, significant concentrations of 2,2,4-Trimethylpentane (iso-octane) were also detected in two of these wells, indicating that at least a portion of the detected TPHg was due to a recent release or vapor leak(s) from existing underground storage tank (UST) equipment.

In order to confirm the previous results and to further evaluate soil vapor quality at the site, CRA plans to re-sample wells VP-1 through VP-5. In the report, updating the site conceptual model (SCM) was recommended. However, based on recent well survey data, incorrect well elevations have historically been used resulting in an incorrect calculated groundwater flow direction (southeast). The new calculated flow direction is to the northwest towards San Francisco Bay. Based on the updated flow direction, the downgradient extent of impacted groundwater has not been adequately evaluated. Therefore, CRA proposes to drill one downgradient exploratory boring to evaluate this data gap. Presented in the following sections are the site description and background and the proposed scope of work. We have also proposed some changes to the site groundwater monitoring program based on the recent results.

SITE DESCRIPTION AND BACKGROUND

The site is located on the northwest corner of the intersection of Martin Luther King Jr. Way (formerly Grove Street) and 55th Street in Oakland, California (Figure 1), and is currently occupied by a Super Stop gas station. Current station facilities include three 10,000-gallon USTs containing gasoline and diesel, four dispenser islands, and a station building. The site was occupied by a Chevron service station from approximately 1968, when Chevron first leased the property, through 1998. Former station facilities included the station building, four dispenser islands, three 10,000-gallon gasoline USTs, a 1,000-gallon used-oil UST, three hydraulic hoists, and an oil-water clarifier. The four USTs reportedly were installed in 1984; no information regarding previous USTs is known. The used-oil UST was removed in 1995 and the hydraulic hoists and clarifier were removed in 1998. Chevron sold the station facilities in 1998. The station was de-branded in 2003, and has since been occupied by a Super Stop station. The USTs appear to have been reconfigured as currently three grades of gasoline and diesel are dispensed at the site. Locations of former and current site features are shown on Figure 2.

Land use in the vicinity of the site is mixed commercial and residential. The site is bounded by Martin Luther King, Jr. Way to the east-northeast, 55th Street to the south-southeast, a single-family residential property to the west-southwest, and single- and multi-family residential properties to the north and northwest. A 76 service station is present on the southwest corner of the intersection of Martin Luther King Jr. Way and 55th Street. This facility is also an open fuel release case (former BP service station #11127 at 5425 Martin Luther King, Jr. Way); however, case closure has been requested and it appears no environmental work is currently being performed.

Environmental work has been performed at the subject site since 1983. Previous work included drilling five borings (B-1 through B-5), installation of monitoring wells MW-1 through MW-8 both on- and offsite; and collection of confirmation soil samples during UST system removal/upgrade work. Groundwater monitoring has been performed since 1990. Remedial activities at the site included over-excavation of impacted soil during product piping upgrade work in 1989 (approximately 25 cubic yards) and the used-oil UST removal in 1995 (approximately 80 cubic yards); and light non-aqueous phase liquid (LNAPL) removal from well MW-3 in 1992. A summary of the environmental work performed at the site is included as Attachment A.

In late-2008, CRA installed and sampled soil vapor wells VP-1 through VP-5. TPHg was detected in samples VP-1 through VP-5 at concentrations of 550 micrograms per cubic meter ($\mu g/m^3$), 330,000 $\mu g/m^3$, 540 $\mu g/m^3$, 38,000 $\mu g/m^3$, and 46,000 $\mu g/m^3$, respectively. TPH as diesel (TPHd) was detected in samples VP-2 (6,900 $\mu g/m^3$) and VP-4 (920 $\mu g/m^3$); however, the laboratory reported that the TPH pattern in the samples did not resemble that of diesel fuel.

Iso-octane was detected in samples VP-2 (17,000 µg/m³) and VP-4 (5,400 µg/m³); the presence of iso-octane in the soil vapor samples suggested that at least a portion of the TPHg in soil vapor was due to a recent release or leak(s) from existing UST system equipment. Iso-octane is a significant constituent of California Reformulated Gasoline (CaRFG) Phase 3, which has been used in California since 2004 after the elimination of methyl tertiary butyl ether (MTBE) and CaRFG Phase 2. To confirm these results and further evaluate soil vapor quality at the site, CRA plans to re-sample the vapor wells.

The site wells were re-surveyed in November 2009 due to some discrepancy regarding the historical groundwater flow direction. The survey confirmed that when wells MW-7 and MW-8 were installed in the northwest portion of the site in 1994, only these two wells were surveyed and a different datum (several feet higher than the datum used for the previous wells) was used. Therefore, the top of casing (TOC) elevations for wells MW-7 and MW-8 were mistakenly indicated as several feet higher than the remaining wells, resulting in a general calculated groundwater flow direction to the southeast, whereas the flow direction would be expected to be to the northwest toward San Francisco Bay. Based on the corrected flow direction (northwest), the downgradient extent of impacted groundwater has not been adequately evaluated and additional investigation appears warranted. An updated rose diagram showing the historical groundwater flow direction is presented on Figure 2.

SOIL VAPOR WELL RE-SAMPLING

In order to confirm the previous results and to further evaluate potential soil vapor risk at the site, CRA will re-sample wells VP-1 through VP-5. Soil vapor samples will be collected from the wells in 1-liter SUMMA™ canisters for laboratory analysis in general accordance with the Department of Toxic Substances Control (DTSC) *Advisory-Active Soil Gas Investigations* guidance document dated January 28, 2003. CRA's standard field procedures for soil vapor sampling are included as Attachment B. A generalized schematic of the soil vapor sampling apparatus is presented on Figure B of Attachment B.

In accordance with the DTSC guidance, a field duplicate sample will also be collected and leak testing will be performed during sampling. Helium will be used as a leak check compound to evaluate if significant ambient air is entering the SUMMA™ canisters during sampling. To perform the leak testing, a plastic shroud will be placed over the sampling apparatus and well, and filled with helium during sample collection. The helium concentration within the shroud will be monitored using a helium detector for comparison with the sample results. Additionally, the samples will be analyzed for oxygen (O_2), carbon dioxide (CO_2), and methane (CH_4) to further evaluate the data quality.

The soil vapor samples will be kept at ambient temperature and submitted under chain-of-custody to Air Toxics Ltd. in Folsom, California for analysis. The samples will be analyzed for the following constituents:

- TPHg by EPA Method TO-3
- Benzene, toluene, ethylbenzene, and xylenes (BTEX), MTBE, and 2,2,4-trimethylpentane by EPA Method TO-15
- Helium, O_2, CO_2, and CH_4 by ASTM D-1946

ADDITIONAL EXPLORATORY BORING

To further evaluate the extent of impacted groundwater, CRA proposes to drill one exploratory boring downgradient of the site. The proposed boring location is shown on Figure 2. The details of the proposed investigation are presented below.

Permits and Access Agreements

CRA will obtain all necessary permits and access agreements for the proposed boring prior to beginning field operations. A minimum of 72 hours written notification will be given to ACEH before initiation of drilling activities.

Site Health and Safety Plan

CRA will prepare a site-specific health and safety plan (HASP) to inform site workers of known hazards and to provide health and safety guidance. The plan will be reviewed and signed by all site workers and visitors and will be kept onsite during field activities.

Underground Utility Location

At least 48 hours prior to the start of drilling activities, CRA will notify Underground Service Alert to clear the proposed boring location with local public utility companies. Additionally, the upper 5 feet of the boring will be cleared for utilities using a hand auger in accordance with CRA safety protocols.

Drilling

Below approximately 5 fbg, the boring will be advanced using a truck-mounted drill rig with direct-push equipment to approximately 15 to 20 fbg. Groundwater is anticipated to be

encountered at approximately 10 to 20 fbg. The final location and depth of the boring will be based on field conditions.

Soil Sampling and Laboratory Analysis

Soil samples will be continuously collected the entire length of the boring for logging and observation purposes. The soil encountered in the boring will be logged in accordance with American Society for Testing and Materials (ASTM) D-2488 protocols. Soil samples from the boring will be screened in the field for volatile organic vapors using a photo-ionization detector (PID). Samples that return PID readings of 100 parts per million by volume (ppmv) or greater, or those in which evidence of contamination is observed, may be retained for laboratory analysis.

Soil samples retained for laboratory analysis will be collected in acetate, brass, or stainless steel liners, capped using Teflon tape and plastic end caps, labeled, placed in an ice-chilled cooler, and transported under chain of custody to Lancaster Laboratories, Inc. (Lancaster) in Lancaster, Pennsylvania, for analysis. CRA's standard field procedures for direct-push borings including soil sampling are included in Attachment B. The soil samples will be analyzed for the following constituents:

- TPHg by EPA Method 8015M
- BTEX and MTBE by EPA Method 8260B

Groundwater Sampling and Laboratory Analysis

If encountered, a grab-groundwater sample will be collected from the boring and analyzed for the same constituents as the soil samples with the addition of TPH as motor oil (TPHmo). CRA's standard field procedures for groundwater sampling are included in Attachment B.

Soil and Water Disposal

Soil cuttings and decontamination rinsate generated during field activities will be temporarily stored onsite in 55-gallon steel drums and sampled for disposal purposes. Once profiled, the drums will be transported to a Chevron-approved facility for disposal.

REPORTING

After receipt of the analytical results, CRA will prepare an investigation report that includes the following:

- A description of field activities
- A figure illustrating the boring location
- A copy of the boring log
- Tabulated soil, groundwater, and soil vapor analytical results
- Analytical reports and chain-of-custody forms
- Conclusions and recommendations

PROPOSED GROUNDWATER MONITORING PROGRAM CHANGES

Based on our review of the groundwater monitoring results, some changes to the sampling frequency and/or the analytical suite appear warranted, as discussed further below.

Wells MW-1 and MW-3 have been sampled since 1990 and historically contained elevated concentrations of TPHg, BTEX, and MTBE. However, concentrations in these wells have significantly decreased and only low concentrations of MTBE remain. TPHg and BTEX generally have not been detected in these wells since at least 2003. These wells are in close proximity to each other (approximately 25 feet) and the USTs, and contain similar concentrations of MTBE. Therefore, as they are providing similar data, we propose to discontinue sampling well MW-1; gauging will continue to evaluate the groundwater flow direction. With regards to well MW-3, we propose to eliminate TPHg and BTEX from the analytical suite.

Similarly, crossgradient well MW-4 has been sampled since 1990 and generally has not contained TPHg and BTEX with the exception of low concentrations during a few events; MTBE has never been detected. Therefore, we propose to also discontinue sampling this well (gauging will continue).

Well MW-5 located in 55th Street has been sampled since 1990, and generally has not contained TPHg and BTEX with the exception of low concentrations during a few events; MTBE has never been detected. Well MW-6 has also been sampled since 1990 and generally has not contained TPHg and BTEX with the exception of low concentrations during a few events. MTBE was consistently detected in well MW-6, but concentrations have decreased and it was not detected during the most recent event (January 2010). Additionally, based on the corrected groundwater

flow direction, these wells are located upgradient of the site. Therefore, we propose to discontinue sampling wells MW-5 and MW-6 (gauging will continue).

TPHg and BTEX generally have not been detected in well MW-7 since the mid-1990s. Therefore, we propose to eliminate TPHg and BTEX from the analytical suite for well MW-7. Similarly, BTEX have not been detected in well MW-8 since 2003; therefore, we propose to eliminate BTEX from the analytical suite for this well.

In summary, the proposed changes are as follows:

- Discontinue sampling of wells MW-1, MW-4, MW-5, and MW-6
- Eliminate analysis for TPHg and BTEX in wells MW-3 and MW-7
- Eliminate analysis for BTEX in well MW-8

A copy of the first semi-annual 2010 groundwater monitoring report is included as Attachment C.

CONESTOGA-ROVERS
& ASSOCIATES

May 12, 2010 Reference No. 611960

SCHEDULE AND CLOSING

Please let us know if ACEH concurs with the proposed work and modifications to the groundwater monitoring program. CRA will perform this investigation upon receiving written approval from ACEH, or if at least 60 days have passed since submittal of this work plan.

We will submit our investigation report approximately six weeks after completion of field activities. If a response to the proposed groundwater monitoring changes is not received, we will assume concurrence and will implement the modifications beginning with the next scheduled event in third quarter 2010.

We appreciate your assistance on this project and look forward to your reply. Please contact Mr. James Kiernan at (916) 889-8917 if you have any questions or require additional information.

Sincerely,

CONESTOGA-ROVERS & ASSOCIATES

James P. Kiernan, P.E. #C68498

REGISTERED PROFESSIONAL ENGINEER
JAMES P. KIERNAN
No. 68498
Exp. 9/30/11
CIVIL
STATE OF CALIFORNIA
5/12/10

JK/jt/7
Encl.

Figure 1	Vicinity Map
Figure 2	Site Plan
Attachment A	Summary of Previous Environmental Work
Attachment B	Standard Field Procedures
Attachment C	First Semi-Annual 2010 Groundwater Monitoring Report

cc: Ms. Stacie Frerichs, Chevron (*electronic*)
Mr. Ben Shimek, Petroleum Sales, Inc.

FIGURES



SOURCE: TOPO! MAPS.

figure 1

VICINITY MAP
FORMER CHEVRON SERVICE STATION 9-1583
5509 MARTIN LUTHER KING JR. WAY
Oakland, California

611960-199(006)GN-WA001 FEB 12/2010

56th STREET

0 20 40ft

RESIDENTIAL

VP-3 MW-7 PLANTER MW-4

VP-4

FORMER USED OIL TANK

WN-10.5

WW-10.5 B-5 WE-11

WS-10.5

H1/CL-7.5

MW-8

VP-5

H2-8

FORMER HOISTS

VP-2

DISP 1/2 (3.5') F A B DISP 5/6 (3.5')

H3-6

EXISTING STATION BUILDING

VP-1

D

C B-4

E

DISP 3/4 (3.5') PLANTER

DISPENSER ISLANDS DISP 7/8 (3.5')

MW-3 B-1

USTS

MW-2

MW-1 B-2

B-3

MARTIN LUTHER KING JR. WAY

OVERHEAD ELECTRICAL AND TELEPHONE LINES

55th STREET

MW-6 MW-5

APARTMENT BUILDING

USTS

DISPENSER ISLANDS

76 STATION BUILDING

LEGEND

PROPOSED BORING LOCATION

VP-1 VAPOR WELL LOCATION

MW-1 MONITORING WELL LOCATION

B-1 HAND AUGER BORING LOCATION

A SOIL SAMPLE LOCATION

ELECTRICAL LINE (OVERHEAD WHERE LABLED)

STORM DRAIN

WATER LINE

APPROXIMATE EXTENT OF EXCAVATION



HISTORICAL GROUNDWATER FLOW DIRECTION

figure 2

SITE PLAN
FORMER CHEVRON SERVICE STATION 9-1583
5509 MARTIN LUTHER KING JR. WAY
Oakland, California

611960-299(007)GN-WA001 MAY 11/2010

ATTACHMENT A

SUMMARY OF PREVIOUS ENVIRONMENTAL WORK

SUMMARY OF PREVIOUS ENVIRONMENTAL WORK

1983 Well Installations: In December 1983, Gettler-Ryan, Inc. (G-R) installed three on-site monitoring wells (MW-1 through MW-3). The wells were installed to a depth of 20 feet below grade (fbg). Groundwater was encountered at depths ranging from 16 to 18 fbg in the well borings. No soil samples were collected for laboratory analysis from the well borings. This investigation was documented in a letter from G-R to Chevron dated January 5, 1984.

1989 Product Piping Upgrade Sampling: In December 1989, Geotest collected six soil samples (A through F) at depths ranging from 2 to 4.5 fbg from the piping trenches in the vicinity of the dispenser islands during piping upgrade work. The samples were analyzed for total petroleum hydrocarbons as gasoline (TPHg) and benzene, toluene, ethylbenzene, and xylenes (BTEX). TPHg was only detected in sample B (1,700 milligrams per kilogram [mg/kg]), collected at a depth of 3 fbg adjacent to the northeast dispenser island. BTEX were also only detected in this sample (0.14 mg/kg, 9.7 mg/kg, 14 mg/kg, and 180 mg/kg, respectively). Limited over-excavation of impacted soil (approximately 25 cubic yards) reportedly was performed in the area of sample B. An additional soil sample (SS-1) was collected by EA Engineering, Science, and Technology, Inc. from the bottom of the excavation and analyzed for TPHg and BTEX. The depth at which this sample was collected is unknown; however, the sample reportedly was collected just above groundwater. TPHg was detected in the sample at 670 mg/kg and BTEX were detected at 0.7 mg/kg, 1.2 mg/kg, 0.96 mg/kg, and 1.5 mg/kg, respectively. A report documenting the details of this work was not available. However, the additional analytical data was provided to ACEH in a letter from Chevron dated July 30, 1993.

1990 Well Redevelopment and Sampling: In March 1990, Geraghty & Miller, Inc. (G&M) redeveloped and sampled wells MW-1 through MW-3. The groundwater samples collected from wells MW-1 through MW-3 contained TPHg at concentrations of 50,000 micrograms per liter (µg/L), 800 µg/L, and 47,000 µg/L, respectively; benzene was also detected at 3,000 µg/L, 400 µg/L, and 1,000 µg/L, respectively. Concentrations of toluene (up to 9,900 µg/L), ethylbenzene (up to 1,900 µg/L), and xylenes (up to 18,000 µg/L) were also detected in all three wells. Details of the investigation were presented in G&M's *Results of Groundwater Sampling Activities* letter report, dated April 2, 1990.

1990 Well Installations: In October 1990, G&M installed monitoring wells MW-4 through MW-6 to further evaluate the extent of petroleum hydrocarbons in groundwater. Well MW-4 was installed in the northeast corner of the site, and wells MW-5 and MW-6 were installed on the south side of 55th Street. A total of six soil

samples were collected from the well borings at depths ranging from 10.5 to 20.5 fbg and analyzed for TPHg. TPHg was only detected in the samples collected at 10.5 fbg from borings MW-5 (190 mg/kg) and MW-6 (11 mg/kg). Details of the investigation were presented in G&M's *Site Assessment Report*, dated December 15, 1990.

1992 LNAPL Removal: During the October 1992 monitoring event, LNAPL (approximately 0.24 feet) was observed in well MW-3. LNAPL had previously not been observed in any of the site wells. The tanks and product lines reportedly tested tight in September 1992 and a 90-day inventory audit did not indicate any loss of product in the tanks. A weekly bailing program to remove the LNAPL was initiated in November 1992 by Groundwater Technology, Inc. (GTI). Approximately 270 milliliters (mL) of LNAPL were removed from well MW-3 in November and December 1992. The bailing was discontinued when only a sheen was observed in the well. Approximately 0.01 feet of LNAPL was observed in well MW-3 during the April and August 2003 monitoring events, but was not observed thereafter.

1994 Well Installations: In February 1994, GTI installed monitoring wells MW-7 and MW-8 to evaluate groundwater quality near the used-oil UST. Four soil samples were collected from the well borings at depths ranging from 5 to 15 fbg and analyzed for TPHg and BTEX; which were not detected in any of the samples. The initial groundwater samples collected from wells MW-7 and MW-8 contained TPHg at 1,200 µg/L and 28,000 µg/L, respectively; benzene was also detected at 440 µg/L and 2,900 µg/L, respectively. Concentrations of toluene (up to 1,300 µg/L), ethylbenzene (up to 1,200 µg/L), and xylenes (up to 6,800 µg/L) were also detected in the two wells. The groundwater samples were also analyzed for TPH as diesel (TPHd) and motor oil (TPHmo); TPHd was not detected and the sample collected from well MW-7 contained TPHmo at 4,100 µg/L. Details of the investigation were presented in GTI's *Additional Soil and Groundwater Assessment Report*, dated April 8, 1994.

1995 Used-Oil Tank Removal and Over-Excavation: In April 1995, the 1,000-gallon used-oil UST was removed from the northwest corner of the site. Touchstone Developments (TD) collected four soil samples from the base of the excavation at depths of 10.5 or 11 fbg. The four samples were analyzed for total recoverable petroleum hydrocarbons (TRPH). Two of the samples were additionally analyzed for TPHg, TPHd, BTEX, volatile organic compounds (VOCs), semi-VOCs, and the metals cadmium, chromium, lead, nickel, and zinc. TRPH was detected in all four of the samples at concentrations ranging from 76 to 2,700 mg/kg. TPHg, BTEX, VOCs, semi-VOCs, and lead were not detected in the two samples analyzed. TPHd was only detected in one of the samples analyzed (75 mg/kg). The metals cadmium (up to 0.60 mg/kg), chromium (up to 46 mg/kg), nickel (up to 61 mg/kg), and zinc (up to 72 mg/kg) were detected in

the two samples analyzed. The excavation was subsequently deepened to 12.5 fbg. Groundwater was encountered in the excavation at approximately 12 fbg. Approximately 80 cubic yards of impacted soil was removed and disposed offsite during the work. Details of the work were presented in TD's *Used Oil Tank Removal Report*, dated June 12, 1995.

1998 Hydraulic Hoist and Clarifier Removal and Excavation: In November 1998, the three hydraulic hoists and the oil-water clarifier were removed from the site. TD collected one soil sample beneath each of the hoists at a depth of 7.5 or 8 fbg. The sample collected beneath the hoist with clarifier was analyzed for TPHg, TPHd, TPH as hydraulic fluid (TPHhf), TRPH, VOCs, semi-VOCs, and the metals cadmium, chromium, lead, nickel, and zinc; only chromium, nickel, and zinc were detected in the sample (32.1 mg/kg, 40.8 mg/kg, and 44 mg/kg, respectively). The remaining two samples were only analyzed for TPHhf, which was not detected. Details of the work were presented in TD's *Hoist/Clarifier Removal and Sampling Report*, dated January 19, 1999.

1998 Dispenser Upgrade Soil Sampling: In December 1998, Geo-Logic collected a soil sample at approximately 3.5 fbg beneath each of the four dispensers during upgrade work. The four samples were analyzed for TPHg, BTEX, and methyl tertiary butyl ether (MTBE), which were not detected in any of the samples. This work was documented in Geo-logic's *Report of Soil Sampling Below Fuel Dispensers* dated December 7, 1998.

2002 Sensitive Receptor Survey: In April 2002, Delta Environmental Consultants, Inc. (Delta) conducted a sensitive receptor survey for the site vicinity. It was determined that drinking water for the site area was supplied by the Alameda County Water District (ACWD) from three sources: treated surface water from the Sacramento/San Joaquin Delta and/or Lake Del Valle, purchased San Francisco water from Hetch Hetchy Reservoir or Calaveras or San Antonio Reservoirs, or blended water consisting of purchased San Francisco water and local groundwater. The groundwater supply came from the Niles Cone Groundwater Basin. No municipal wells were identified within 2,000 feet of the site. A search of Department of Water Resources (DWR) files was performed to evaluate the presence of domestic, municipal, or irrigation supply wells within 2,000 feet of the site. One industrial well and one cathodic protection well were identified approximately 1,200 feet northwest and 1,800 feet southeast of the site, respectively. Utilities identified adjacent to the site included storm drains, sanitary sewer, television cable, and water lines buried at depths of 4 to 22 fbg. Based on conversations with Alameda County Public Works Agency, the water-bearing materials beneath the site had not been classified as a potential drinking water source. No surface water bodies were located within a one-mile radius of the site. The nearest surface water body identified was Glen Echo Creek, located approximately 7,400 feet southeast

of the site. Details were presented in Delta's *Sensitive Receptor Survey*, dated August 1, 2002.

2007 Subsurface Investigation: : In January 2007, Cambria advanced five hand-auger exploratory borings (B-1 through B-5) to further evaluate hydrocarbon impacts to soil and groundwater. Borings B-1 through B-3 were located near the existing USTs, boring B-4 was located to the east of the dispenser islands, and boring B-5 was located in the former used-oil UST excavation. Borings B-1 through B-4 were advanced to depths of 11 to 13 fbg; drilling refusal was encountered in boring B-5 at 5.5 fbg. A total of 14 soil samples were collected at various depths from the borings and analyzed for TPHg, BTEX, fuel oxygenates (methyl tertiary butyl ether [MTBE], ethyl tertiary butyl ether [ETBE], tertiary amyl methyl ether [TAME], di-isopropyl ether [DIPE], and tertiary butyl alcohol [TBA]), 1,2-dichloroethane (1,2-DCA), and ethylene dibromide (EDB). The analytes generally were not detected in the samples with the exception of toluene at 0.001 mg/kg in the sample collected at 3 fbg from boring B-1, and MTBE at 0.0006 mg/kg in the sample collected at 9 fbg from boring B-1. Grab-groundwater samples were collected from borings B-1 through B-4 and analyzed for the same constituents as the soil samples. TPHg was only detected in the groundwater samples collected from borings B-1 (2,600 µg/L) and B-2 (4,500 µg/L). The remaining constituents generally were not detected in the groundwater samples with the exception of ethylbenzene (0.9 µg/L) and MTBE (2 µg/L) in the sample collected from boring B-1, and MTBE (5 µg/L) in the sample collected from boring B-2. Details of the investigation were presented in Cambria's *Subsurface Investigation Report*, dated February 28, 2007.

2008 Soil Vapor Survey: In August 2008, CRA installed five soil vapor wells (VP-1 through VP-5) to 6 fbg at the site. The wells were screened from approximately 5 to 5.5 fbg. A soil sample was collected from each well boring at approximately 3 fbg and analyzed for TPHg, BTEX, MTBE, TBA, 1,2-DCA, and EDB; which were not detected in any of the soil samples. The wells were sampled in September 2008; the soil vapor samples were analyzed for TPHg, TPHd, BTEX, MTBE, TBA, 1,2-DCA, EDB, ethanol, and iso-octane (2,2,4-trimethylpentane). The samples were additionally analyzed for helium (leak check compound), oxygen, and carbon dioxide. TPHg was detected in samples VP-1 through VP-5 at concentrations of 550 micrograms per cubic meter (µg/m^3), 330,000 µg/m^3, 540 µg/m^3, 38,000 µg/m^3, and 46,000 µg/m^3, respectively. TPHd was only detected in samples VP-2 (6,900 µg/m^3) and VP-4 (920 µg/m^3); however, the laboratory reported that the TPH pattern in the samples did not resemble that of diesel fuel. Iso-octane was only detected in samples VP-2 (17,000 µg/m^3) and VP-4 (5,400 µg/m^3); BTEX, MTBE, TBA, 1,2-DCA, EDB, and ethanol were not detected in any of the samples.

ATTACHMENT B

STANDARD FIELD PROCEDURES

Conestoga-Rovers & Associates

STANDARD FIELD PROCEDURES FOR SOIL VAPOR PROBE INSTALLATION AND SAMPLING

VAPOR POINT METHODS

This document describes Conestoga-Rovers & Associates' standard field methods for soil vapor sampling. These procedures are designed to comply with Federal, State and local regulatory guidelines. Specific field procedures are summarized below.

Objectives

Soil vapor samples are collected and analyzed to assess whether vapor-phase subsurface contaminants pose a threat to human health or the environment.

Shallow Soil Vapor Point Installation

The shallow soil vapor point method for soil vapor sampling utilizes a hand auger or drill rig to advance a boring for the installation of a soil vapor sampling point. Once the boring is hand augered to the final depth, a probe, connected with Swagelok fittings to nylon or Teflon tubing of ¼-inch outer-diameter, is placed within 12-inches of number 2/16 filter sand (Figure A). A 12-inch layer of dry granular bentonite is placed on top of the filter pack. Pre-hydrated granular bentonite is then poured to fill the borehole. The tube is coiled and placed within a wellbox finished flush to the surface. Soil vapor samples will be collected no sooner than 48 hours after installation of the soil vapor points to allow adequate time for representative soil vapors to accumulate. Soil vapor sample collection will not be scheduled until after a minimum of three consecutive precipitation-free days and irrigation onsite has ceased. Figure B shows the soil vapor sampling apparatus. A measured volume of air will be purged from the tubing using a different Summa purge canister. Immediately after purging, soil vapor samples will be collected using the appropriate size Summa canister with attached flow regulator and sediment filter. The soil vapor points will be preserved until they are no longer needed for risk evaluation purposes. At that time, they will be destroyed by extracting the tubing, hand augering to remove the sand and bentonite, and backfilling the boring with neat cement. The boring will be patched with asphalt or concrete, as appropriate.

Sampling of Soil Vapor Points

Samples will be collected using a SUMMA™ canister connected to sampling tubing at each vapor point. Prior to collecting soil vapor samples, the initial vacuum of the canisters is measured and recorded on the chain-of-custody. The vacuum of the SUMMA™ canister is used to draw the soil vapor through the flow controller until a negative pressure of approximately 5-inches of Hg is observed on the vacuum gauge and recorded on

the chain-of-custody. The flow controllers should be set to 100-200 ml/minute. Field duplicates should be collected for every day of sampling and/or for every 10 samples collected.

Prior to sample collection, stagnant air in the sampling apparatus should be removed by purging approximately 3 purge volumes. The purge volume is defined as the amount of air within the probe and tubing.

In accordance with the DTSC Advisory-Active Soil Gas Investigations guidance document, dated January 28, 2003, leak testing needs to be performed during sampling. Helium is recommended, although shaving cream is acceptable.

Vapor Sample Storage, Handling, and Transport

Samples are stored and transported under chain-of-custody to a state-certified analytic laboratory. Samples should never be cooled due to the possibility of condensation within the canister.



Schematic Not to Scale

figure B

SOIL VAPOR SAMPLING APPARATUS DIAGRAM

Conestoga-Rovers & Associates

STANDARD FIELD PROCEDURES FOR SOIL BORING AND MONITORING WELL INSTALLATION

This document presents standard field methods for drilling and sampling soil borings and installing, developing and sampling groundwater monitoring wells. These procedures are designed to comply with Federal, State and local regulatory guidelines. Specific field procedures are summarized below.

SOIL BORINGS

Objectives

Soil samples are collected to characterize subsurface lithology, assess whether the soils exhibit obvious hydrocarbon or other compound vapor or staining, and to collect samples for analysis at a State-certified laboratory. All borings are logged using the Unified Soil Classification System by a trained geologist working under the supervision of a California Professional Geologist (PG).

Soil Boring and Sampling

Soil borings are typically drilled using hollow-stem augers or direct-push technologies such as the Geoprobe®. Soil samples are collected at least every five ft to characterize the subsurface sediments and for possible chemical analysis. Additional soil samples are collected near the water table and at lithologic changes. Samples are collected using lined split-barrel or equivalent samplers driven into undisturbed sediments at the bottom of the borehole.

Drilling and sampling equipment is steam-cleaned prior to drilling and between borings to prevent cross-contamination. Sampling equipment is washed between samples with trisodium phosphate or an equivalent EPA-approved detergent.

Sample Analysis

Sampling tubes chosen for analysis are trimmed of excess soil and capped with Teflon tape and plastic end caps. Soil samples are labeled and stored at or below 4^{o} C on either crushed or dry ice, depending upon local regulations. Samples are transported under chain-of-custody to a State-certified analytic laboratory.

Field Screening

One of the remaining tubes is partially emptied leaving about one-third of the soil in the tube. The tube is capped with plastic end caps and set aside to allow hydrocarbons to volatilize from the soil. After ten to fifteen minutes, a portable volatile vapor analyzer measures volatile hydrocarbon vapor concentrations in the tube headspace, extracting the vapor through a slit in the cap. Volatile vapor analyzer measurements are used along with the field observations, odors, stratigraphy and groundwater depth to select soil samples for analysis.

Water Sampling

Water samples, if they are collected from the boring, are either collected using a driven Hydropunch® type sampler or are collected from the open borehole using bailers. The groundwater samples are decanted into the appropriate containers supplied by the analytic laboratory. Samples are labeled, placed in protective foam sleeves, stored on crushed ice at or below 4°C, and transported under chain-of-custody to the laboratory. Laboratory-supplied trip blanks accompany the samples and are analyzed to check for cross-contamination. An equipment blank may be analyzed if non-dedicated sampling equipment is used.

Grouting

If the borings are not completed as wells, the borings are filled to the ground surface with cement grout poured or pumped through a tremie pipe.

MONITORING WELL INSTALLATION, DEVELOPMENT AND SAMPLING

Well Construction and Surveying

Groundwater monitoring wells are installed to monitor groundwater quality and determine the groundwater elevation, flow direction and gradient. Well depths and screen lengths are based on groundwater depth, occurrence of hydrocarbons or other compounds in the borehole, stratigraphy and State and local regulatory guidelines. Well screens typically extend 10 to 15 feet below and 5 feet above the static water level at the time of drilling. However, the well screen will generally not extend into or through a clay layer that is at least three feet thick.

Well casing and screen are flush-threaded, Schedule 40 PVC. Screen slot size varies according to the sediments screened, but slots are generally 0.010 or 0.020 inches wide. A rinsed and graded sand occupies the annular space between the boring and the well screen to about one to two feet above the well screen. A two feet thick hydrated bentonite seal separates the sand from the overlying sanitary surface seal composed of Portland type I, II cement.

Well-heads are secured by locking well-caps inside traffic-rated vaults finished flush with the ground surface. A stovepipe may be installed between the well-head and the vault cap for additional security.

The well top-of-casing elevation is surveyed with respect to mean sea level and the well is surveyed for horizontal location with respect to an onsite or nearby offsite landmark.

Well Development

Wells are generally developed using a combination of groundwater surging and extraction. Surging agitates the groundwater and dislodges fine sediments from the sand pack. After about ten minutes of surging, groundwater is extracted from the well using bailing, pumping and/or reverse air-lifting through an eductor pipe to remove the sediments from the well. Surging and extraction continue until at least ten well-casing volumes of groundwater are extracted and the sediment volume in the groundwater is negligible. This process usually occurs prior to installing the sanitary surface seal to ensure sand pack stabilization. If development occurs after surface seal installation, then development occurs 24 to 72 hours after seal installation to ensure that the Portland cement has set up correctly.

All equipment is steam-cleaned prior to use and air used for air-lifting is filtered to prevent oil entrained in the compressed air from entering the well. Wells that are developed using air-lift evacuation are not sampled until at least 24 hours after they are developed.

Groundwater Sampling

Depending on local regulatory guidelines, three to four well-casing volumes of groundwater are purged prior to sampling. Purging continues until groundwater pH, conductivity, and temperature have stabilized. Groundwater samples are collected using bailers or pumps and are decanted into the appropriate containers supplied by the analytic laboratory. Samples are labeled, placed in protective foam sleeves, stored on crushed ice at or below 4°C, and transported under chain-of-custody to the laboratory. Laboratory-supplied trip blanks accompany the samples and are analyzed to check for cross-contamination. An equipment blank may be analyzed if non-dedicated sampling equipment is used.

Waste Handling and Disposal

Soil cuttings from drilling activities are usually stockpiled onsite and covered by plastic sheeting. At least three individual soil samples are collected from the stockpiles and composited at the analytic laboratory. The composite sample is analyzed for the same constituents analyzed in the borehole samples in addition to any analytes required by the receiving disposal facility. Soil cuttings are transported by licensed waste haulers and disposed in secure, licensed facilities based on the composite analytic results.

Groundwater removed during development and sampling is typically stored onsite in sealed 55-gallon drums. Each drum is labeled with the drum number, date of generation, suspected contents, generator identification and consultant contact. Upon receipt of analytic results, the water is either pumped out using a vacuum truck for transport to a licensed waste treatment/disposal facility or the individual drums are picked up and transported to the waste facility where the drum contents are removed and appropriately disposed.

ATTACHMENT C

FIRST SEMI-ANNUAL 2010 GROUNDWATER MONITORING REPORT

GETTLER-RYAN INC.

TRANSMITTAL

February 4, 2010
G-R #386506

TO: Mr. James Kiernan
Conestoga-Rovers & Associates
10969 Trade Center Drive, Suite 107
Rancho Cordova, CA 95670

FROM: Deanna L. Harding
Project Coordinator
Gettler-Ryan Inc.
6747 Sierra Court, Suite J
Dublin, California 94568

RE: Former Chevron Service Station
#9-1583 (MTI)
5509 Martin Luther King Way
Oakland, California
RO 0000002

WE HAVE ENCLOSED THE FOLLOWING:

COPIES	DATED	DESCRIPTION
2	January 28, 2010	Groundwater Monitoring and Sampling Report **First Semi-Annual Event of January 12, 2010**

COMMENTS:

Pursuant to your request, we are providing you with copies of the above referenced report for **your use and distribution to the following:**

Ms. Stacie H. Frerichs, Chevron EMC, 6111 Bollinger Canyon Road, Room 3596, San Ramon, CA 94583

Please provide any comments/changes and propose any groundwater monitoring modifications for the next event prior to ***February 18, 2009,*** at which time this final report will be distributed to the following:

cc: Mr. Mark Detterman, Alameda County Health Care Services, Dept. of Environmental Health, 1131 Harbor Bay Parkway, Suite 250, Alameda, CA 94502-6577
(No Hard Copy-UPLOAD TO ALAMEDA CO.)
Mr. Ben Shimek, (Owner), 31 Industrial Way, Greenbrae, CA 94904

Enclosures

trans/9-1583-SHF

WELL CONDITION STATUS SHEET

Client/Facility #: Chevron #9-1583
Site Address: 5509 Martin Luther King Way
City: Oakland, CA

Job #: 386506
Event Date: 1-12-10
Sampler: Joe

WELL ID	Vault Frame Condition	Gasket/ O-Ring (M)missing	BOLTS (M) Missing (R) Replaced	Bolt Flanges B= Broken S= Stripped R=Retap	APRON Condition C=Cracked B=Broken G=Gone	Grout Seal (Deficient) inches from TOC	Casing (Condition prevents tight cap seal)	REPLACE LOCK Y / N	REPLACE CAP Y / N	WELL VAULT Manufacture/Size/ # of Bolts	Pictures Taken Yes / No
MW-1	O.K	N/A	N/A	N/K	O.K	O.K	O.K	N	N	Christy box	NO
MW-2	↓	N/A	N/A	N/A	↓	↓	↓	↓	↓	"	↓
MW-3		N/A	N/A	N/A						"	
MW-4		O.K	O.K	(1) of (2)						12" Universal/2	
MW-5		N/A	NA	N/A						8" City Monument (no bolts)	
MW-6		N/A	N/A	N/A						"	
MW-7		O.K	O.K	Both S						6" Morrison/2	
MW-8	↓	O.K	O.K	Both S	↓	↓	↓	↓	↓	12" Emco /2	↓

Comments

GETTLER-RYAN INC.

January 28, 2010
G-R Job #386506

Ms. Stacie H. Frerichs
Chevron Environmental Management Company
6111 Bollinger Canyon Road, Room 3596
San Ramon, CA 94583

RE: First Semi-Annual Event of January 12, 2010
Groundwater Monitoring & Sampling Report
Former Chevron Service Station #9-1583
5509 Martin Luther King Way
Oakland, California

Dear Ms. Frerichs:

This report documents the most recent groundwater monitoring and sampling event performed by Gettler-Ryan Inc. (G-R) at the referenced site. All field work was conducted in accordance with G-R Standard Operating Procedure - Groundwater Sampling (attached).

Static groundwater levels were measured and the wells were checked for the presence of separate-phase hydrocarbons. Static water level data, groundwater elevations, and separate-phase hydrocarbon thickness (if any) are presented in the attached Table 1. A Potentiometric Map is included as Figure 1.

Groundwater samples were collected from the monitoring wells and submitted to a state certified laboratory for analyses. The field data sheets for this event are attached. Analytical results are presented in the table(s) listed below. The chain of custody document and laboratory analytical report are also attached. All groundwater and decontamination water generated during sampling activities was removed from the site, per the Standard Operating Procedure

Please call if you have any questions or comments regarding this report. Thank you.

Sincerely,

Deanna L. Harding
Project Coordinator

PROFESSIONAL GEOLOGIST
DOUGLAS J. LEE
No. 6882
STATE OF CALIFORNIA

Douglas J. Lee
Senior Geologist, P.G. No. 6882

Figure 1: Potentiometric Map
Table 1: Groundwater Monitoring Data and Analytical Results
Table 2: Groundwater Analytical Results - Oxygenate Compounds
Attachments: Standard Operating Procedure - Groundwater Sampling
Field Data Sheets
Chain of Custody Document and Laboratory Analytical Reports



Source: Figure modified from drawing provided by RRM engineering contracting firm.

GETTLER - RYAN INC.
6747 Sierra Court, Suite J
Dublin, CA 94568 (925) 551-7555

POTENTIOMETRIC MAP
Former Chevron Service Station #9-1583
5509 Martin Luther King Way
Oakland, California

FIGURE
1

PROJECT NUMBER	REVIEWED BY	DATE	REVISED DATE
386506		January 12, 2010	

FILE NAME: P:\Enviro\Chevron\9-1583\Q10-9-1583.dwg | Layout Tab: Pot1

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-1													
12/22/83	81.97	71.72	10.25	--	--	--	--	--	--	--	--	--	--
12/30/83	81.97	72.80	9.17	--	--	--	--	--	--	--	--	--	--
03/12/90	81.97	71.89	10.08	--	--	--	50,000	3,000	7,300	1,900	18,000	--	--
03/25/90	82.42	71.51	10.46	--	--	--	--	--	--	--	--	--	--
10/18/90	82.42	--	--	--	--	--	--	--	--	--	--	--	--
10/31/90	82.42	--	--	--	--	--	--	--	--	--	--	--	--
11/16/90	82.42	70.84	11.58	--	--	--	--	--	--	--	--	--	--
02/08/91	82.42	72.31	10.11	--	--	--	100,000	4,200	8,400	16,000	2,600	--	--
05/08/91	82.42	71.97	10.45	--	--	--	31,000	200	66	670	2,000	--	--
08/12/91	82.42	71.19	11.23	--	--	--	17,000	81	7.2	270	710	--	--
11/07/91	82.42	71.72	10.70	--	--	--	7,100	24	6.0	130	170	--	--
02/05/92	82.42	72.05	10.37	--	--	--	110,000	8,900	14,000	2,700	12,000	--	--
05/13/92	82.42	71.84	10.58	--	--	--	19,000	450	85	480	870	--	--
07/17/92	82.42	71.37	11.05	--	--	--	8,500	170	<10	360	600	--	--
10/05/92	82.42	71.01	11.41	--	--	--	22,000	4,300	5,100	570	2,900	--	--
11/11/92	82.42	--	--	--	--	--	--	--	--	--	--	--	--
11/17/92	82.42	--	--	--	--	--	--	--	--	--	--	--	--
11/24/92	82.42	--	--	--	--	--	--	--	--	--	--	--	--
12/01/92	82.42	--	--	--	--	--	--	--	--	--	--	--	--
12/29/92	82.42	--	--	--	--	--	--	--	--	--	--	--	--
01/05/93	82.42	--	--	--	--	--	--	--	--	--	--	--	--
01/08/93	82.42	74.31	8.11	--	--	--	14,000,000	12,000	79,000	270,000	1,300,000	--	--
02/02/93	82.42	--	--	--	--	--	--	--	--	--	--	--	--
04/14/93	82.42	72.57	9.85	--	--	--	48,000	670	1,100	1,600	6,300	--	--
08/06/93	82.42	71.59	10.83	--	--	--	44,000	660	990	1,600	6,100	--	--
10/21/93	82.42	71.52	10.90	--	--	--	18,000	270	460	1,300	4,700	--	--
01/05/94	82.42	72.09	10.33	--	--	--	22,000	160	160	630	2,300	--	--
04/08/94	82.42	72.24	10.18	--	--	--	21,000	37	110	570	1,400	--	--
07/06/94	82.42	71.78	10.64	--	--	--	28,000	210	100	540	1,200	--	--
08/04/94	82.42	71.91	10.51	--	--	--	--	--	--	--	--	--	--
10/05/94	82.42	71.51	10.91	--	--	--	120,000	39	22	320	900	--	--
01/18/95	82.42	73.80	8.62	--	--	--	12,000	<20	<20	130	160	--	--
04/07/95	82.42	72.89	9.53	--	--	--	2,500	<2.5	<2.5	71	38	--	--
07/06/95	82.42	72.03	10.39	--	--	--	5,700	<0.5	<0.5	110	110	--	--
10/11/95	82.42	70.54	11.88	--	--	--	2,700	13	<5.0	13	5.7	650	--
01/17/96	82.42	73.14	9.28	--	--	--	4,200	12	<5.0	43	24	300	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-1 (cont)													
04/05/96	82.42	72.82	9.60	--	--	--	1,300	<1.2	<1.2	7.6	2.8	220	--
07/23/96	82.42	72.19	10.23	--	--	--	700	<1.0	<1.0	7.0	4.8	240	--
10/02/96	82.42	71.67	10.75	--	--	--	1,700	<2.5	9.8	10	13	610	--
01/23/97	82.42	74.75	7.67	--	--	--	1,300	21	<10	<10	<10	2,700	--
04/01/97	82.42	72.22	10.20	--	--	--	670	<2.0	<2.0	4.1	3.6	1,200	--
07/09/97	82.42	72.12	10.30	--	--	--	460	<1.0	<1.0	<1.0	<1.0	440	--
10/07/97	82.42	71.73	10.69	--	--	--	1,100	8.5	<2.0	<2.0	2.0	250	--
01/22/98	82.42	74.20	8.22	--	--	--	460	1.4	5.8	<0.5	<0.5	150	--
04/02/98	82.42	72.89	9.53	--	--	--	220	2.5	1.2	<1.0	1.9	260	--
07/02/98	82.42	72.08	10.34	--	--	--	270	<0.5	0.82	<0.5	<0.5	140	--
10/02/98	82.42	71.70	10.72	--	--	--	170	1.3	<0.5	<0.5	<1.5	320	--
01/18/99	82.42	72.87	9.55	--	--	--	416	<2.5	<2.5	<2.5	<2.5	316/295[2]	--
07/22/99	82.42	71.61	10.81	--	--	--	186	<0.5	3.94	1.46	2.37	63.7	--
01/17/00	82.42	72.21	10.21	--	--	--	248	1.6	<0.5	<0.5	<0.5	41.0	--
07/05/00	82.42	72.12	10.30	0.00	--	--	76[3]	<0.50	<0.50	<0.50	0.79	69	--
01/15/01	82.42	73.01	9.41	0.00	--	--	66.6	<0.500	<0.500	<0.500	0.585	22.5	--
07/03/01	82.42	72.13	10.29	0.00	--	--	<50	<0.50	<0.50	<0.50	<0.50	8.8	--
02/28/02	82.42	72.74	9.68	0.00	--	--	58	<0.50	<0.50	<0.50	<1.5	21	--
07/08/02	82.42	72.14	10.28	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	23	--
01/01/03	82.42	74.28	8.14	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	15	--
07/14/03[8]	82.42	72.12	10.30	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	5	--
01/12/04[8]	82.42	73.40	9.02	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	61	--
07/27/04[8]	82.42	72.10	10.32	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	54	--
01/25/05[8]	82.42	74.24	8.18	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	5	--
07/26/05[8]	82.42	72.40	10.02	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	25	--
01/24/06[8]	82.42	74.22	8.20	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	25	--
07/25/06[8]	82.42	72.30	10.12	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	14	--
01/23/07[8]	82.42	72.57	9.85	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	17	--
07/24/07[8]	82.42	70.59	11.83	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	7	--
01/22/08[8]	82.42	73.12	9.30	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	8	--
07/22/08[8]	82.42	71.69	10.73	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/13/09[8]	82.42	72.41	10.01	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	2	--
07/14/09	82.42	71.52	10.90	0.00	SAMPLED ANNUALLY		--	--	--	--	--	--	--
01/12/10[8]	**85.41**	**76.70**	**8.71**	**0.00**	**--**	**--**	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**15**	**--**

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-2													
12/22/83	83.48	72.98	10.50	--	--	--	--	--	--	--	--	--	--
12/30/83	83.48	73.56	9.92	--	--	--	--	--	--	--	--	--	--
03/12/90	83.48	72.46	11.02	--	--	--	800	400	22	18	55	--	--
03/25/90	83.48	72.15	11.33	--	--	--	--	--	--	--	--	--	--
10/18/90	83.48	71.17	12.31	--	--	--	--	--	--	--	--	--	--
10/31/90	83.48	--	--	--	--	--	--	--	--	--	--	--	--
11/16/90	83.48	--	--	--	--	--	--	--	--	--	--	--	--
02/08/91	83.48	72.43	11.05	--	--	--	4,600	820	440	720	210	--	--
05/08/91	83.48	72.12	11.36	--	--	--	<50	5.0	<0.5	<0.5	<0.5	--	--
08/12/91	83.48	71.51	11.97	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/07/91	83.48	71.98	11.50	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/05/92	83.48	72.29	11.19	--	--	--	1,700	390	170	60	200	--	--
05/13/92	83.48	71.99	11.49	--	--	--	74	9.3	<0.5	<0.5	<0.5	--	--
07/17/92	83.48	71.63	11.85	--	--	--	<50	2.0	<0.5	<0.5	<0.5	--	--
10/05/92	83.48	71.48	12.00	--	--	--	3,500	1,200	530	86	220	--	--
11/11/92	83.48	--	--	--	--	--	--	--	--	--	--	--	--
11/17/92	83.48	--	--	--	--	--	--	--	--	--	--	--	--
11/24/92	83.48	--	--	--	--	--	--	--	--	--	--	--	--
12/01/92	83.48	--	--	--	--	--	--	--	--	--	--	--	--
12/29/92	83.48	--	--	--	--	--	--	--	--	--	--	--	--
01/05/93	83.48	--	--	--	--	--	--	--	--	--	--	--	--
01/08/93	83.48	74.65	8.83	--	--	--	390	140	0.8	7.7	26	--	--
02/02/93	83.48	--	--	--	--	--	--	--	--	--	--	--	--
04/14/93	83.48	72.69	10.79	--	--	--	<50	5.0	<0.5	<0.5	<0.5	--	--
08/06/93	83.48	71.77	11.71	--	--	--	<50	1.0	<0.5	<0.5	<0.5	--	--
10/21/93	83.48	71.74	11.74	--	--	--	<50	1.0	<0.5	9.0	<0.5	--	--
01/05/94	83.48	72.30	11.18	--	--	--	<50	0.7	<0.5	<0.5	0.9	--	--
04/08/94	83.48	72.42	11.06	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/94	83.48	71.80	11.68	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/04/94	83.48	72.29	11.19	--	--	--	--	--	--	--	--	--	--
10/05/94	83.48	71.79	11.69	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
01/18/95	83.48	74.26	9.22	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/07/95	83.48	73.62	9.86	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/95	83.48	72.74	10.74	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/11/95	83.48	72.26	11.22	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/17/96	83.48	73.74	9.74	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-2 (cont)													
04/05/96	83.48	73.52	9.96	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/23/96	83.48	72.57	10.91	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/96	83.48	72.41	11.07	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/23/97	83.48	75.18	8.30	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	3.4	--
04/01/97	83.48	72.90	10.58	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/09/97	83.48	72.58	10.90	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/07/97	83.48	72.52	10.96	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/22/98	83.48	74.73	8.75	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/02/98	83.48	73.66	9.82	--	--	--	89	3.0	5.4	4.1	21	<2.5	--
07/02/98	83.48	72.74	10.74	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/98	83.48	72.43	11.05	--	--	--	<50	<0.5	<0.5	<0.5	<1.5	<2.5	--
01/18/99	83.48	73.09	10.39	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
07/22/99	83.48	72.61	10.87	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
01/17/00	83.48	72.89	10.59	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/05/00	83.48	72.84	10.64	0.00	--	--	<50	<0.50	<0.50	<0.50	<0.50	<2.5	--
01/15/01	83.48	73.77	9.71	0.00	--	--	555[6]	<0.500	<0.500	<0.500	<0.500	<2.50	--
07/03/01	83.48	73.02	10.46	0.00	--	--	<50	<0.50	<0.50	<0.50	<0.50	<2.5	--
02/28/02	83.48	73.49	9.99	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
07/08/02	83.48	72.98	10.50	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
01/01/03	83.48	75.33	8.15	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
07/14/03[8]	83.48	72.96	10.52	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/12/04[8]	83.48	74.31	9.17	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/27/04[8]	83.48	72.85	10.63	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/25/05[8]	83.48	74.36	9.12	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/26/05[8]	83.48	73.56	9.92	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/24/06[8]	83.48	74.33	9.15	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/25/06[8]	83.48	73.03	10.45	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/23/07[8]	83.48	73.37	10.11	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/24/07[8]	83.48	72.90	10.58	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/22/08[8]	83.48	73.85	9.63	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/22/08[8]	83.48	73.08	10.40	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	2	--
01/13/09[8]	83.48	73.10	10.38	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/14/09	83.48	72.93	10.55	0.00	SAMPLED ANNUALLY		--	--	--	--	--	--	--
01/12/10[8]	**86.04**	**76.38**	**9.66**	**0.00**	**--**	**--**	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**--**

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-3													
12/22/83	84.36	72.78	11.58	--	--	--	--	--	--	--	--	--	--
12/30/83	84.36	73.19	11.17	--	--	--	--	--	--	--	--	--	--
03/12/90	84.36	72.22	12.14	--	--	--	47,000	1,000	9,900	1,700	9,800	--	--
03/25/90	84.38	71.81	12.55	--	--	--	--	--	--	--	--	--	--
10/18/90	84.38	--	--	--	--	--	--	--	--	--	--	--	--
10/31/90	84.38	--	--	--	--	--	--	--	--	--	--	--	--
11/16/90	84.38	70.76	13.62	--	--	--	--	--	--	--	--	--	--
02/08/91	84.38	72.20	12.18	--	--	--	58,000	4,900	5,200	9,500	2,000	--	--
05/08/91	84.38	71.86	12.52	--	--	--	50,000	2,100	1,400	2,000	9,400	--	--
08/12/91	84.38	71.11	13.27	--	--	--	15,000	1,300	160	920	1,900	--	--
11/07/91	84.38	71.57	12.81	--	--	--	26,000	1,000	310	1,900	5,900	--	--
02/05/92	84.38	71.91	12.47	--	--	--	35,000	2,800	1,300	1,500	4,700	--	--
05/13/92	84.38	71.76	12.62	--	--	--	47,000	1,500	1,200	1,100	4,800	--	--
07/17/92	84.38	71.25	13.13	--	--	--	15,000	120	11	88	140	--	--
10/05/92	84.38	70.95	13.62	0.24	--	--	--	--	--	--	--	--	--
11/11/92	84.38	71.63	12.89	0.17	--	--	--	--	--	--	--	--	--
11/17/92	84.38	71.54	12.89	0.06	--	--	--	--	--	--	--	--	--
11/24/92	84.38	71.56	12.86	0.05	--	--	--	--	--	--	--	--	--
12/01/92	84.38	71.48	12.92	0.03	--	--	--	--	--	--	--	--	--
12/29/92	84.38	73.14	11.24	Sheen	--	--	--	--	--	--	--	--	--
01/05/93	84.38	73.23	11.15	Sheen	--	--	--	--	--	--	--	--	--
01/08/93	84.38	74.28	10.10	--	--	--	250,000	5,000	17,000	5,500	28,000	--	--
02/02/93	84.38	--	--	--	--	--	--	--	--	--	--	--	--
04/14/93	84.38	72.48	11.91	0.01	--	--	--	--	--	--	--	--	--
08/06/93	84.38	71.49	12.90	0.01	--	--	150,000	3,800	6,600	3,700	17,000	--	--
10/21/93	84.38	71.41	12.97	--	--	--	22,000	2,300	1,700	1,400	5,100	--	--
01/05/94	84.38	71.96	12.42	--	--	--	37,000	1,600	1,100	1,300	6,500	--	--
04/08/94	84.38	72.51	11.87	--	--	--	16,000	250	310	500	2,500	--	--
07/06/94	84.38	71.64	12.74	--	--	--	43,000	660	320	1,900	6,400	--	--
08/04/94	84.38	71.71	12.67	--	--	--	--	--	--	--	--	--	--
10/05/94	84.38	71.43	12.95	--	--	--	12,000	280	90	480	370	--	--
01/18/95	84.38	73.72	10.66	--	--	--	20,000	200	230	700	3,500	--	--
04/07/95	84.38	72.84	11.54	--	--	--	22,000	120	120	810	4,400	--	--
07/06/95	84.38	71.99	12.39	--	--	--	15,000	110	<50	630	2,100	--	--
10/11/95	84.38	72.07	12.31	--	--	--	8,600	24	<10	360	560	1,100	--
01/17/96	84.38	73.68	10.70	--	--	--	9,300	<50	<50	230	1,100	2,300	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-3 (cont)													
04/05/96	84.38	73.35	11.03	--	--	--	8,700	16	<10	110	650	990	--
07/23/96	84.38	72.38	12.00	--	--	--	5,400	20	<5.0	190	480	2,300	--
10/02/96	84.38	72.20	12.18	--	--	--	6,200	43	<20	130	140	2,800	--
01/23/97	84.38	75.12	9.26	--	--	--	5,600	<5.0	<5.0	39	160	550	--
04/01/97	84.38	72.75	11.63	--	--	--	6,900	17	<10	150	330	3,900	--
07/09/97	84.38	72.38	12.00	--	--	--	5,300	31	<5.0	100	180	2,300	--
10/07/97	84.38	72.27	12.11	--	--	--	2,400	15	<2.0	30	15	900	--
01/22/98	84.38	74.73	9.65	--	--	--	3,200	2.5	7.9	70	220	660	--
04/02/98	84.38	73.49	10.89	--	--	--	1,300	14	9.7	25	63	430	--
07/02/98	84.38	72.69	11.69	--	--	--	750	6.9	<5.0	18	9.1	370	--
10/02/98	84.38	72.23	12.15	--	--	--	1,400	5.3	0.73	18	6.6	900	--
01/18/99	84.38	74.05	10.33	--	--	--	1,270	<1.0	<1.0	7.95	<1.0	100/99.7[2]	--
07/22/99	84.38	72.08	12.30	--	--	--	2,240	<1.0	<1.0	29.4	13.7	189	--
01/17/00	84.38	72.78	11.60	--	--	--	848	6.72	2.53	5.02	2.49	90	--
07/05/00	84.38	72.67	11.71	0.00	--	--	90[3]	5.3	<0.50	0.70	<0.50	770	--
01/15/01	84.38	73.93	10.45	0.00	--	--	206	<0.500	<0.500	<0.500	1.09	4.04	--
07/03/01	84.38	72.62	11.76	0.00	--	--	<50	0.53	<0.50	<0.50	1.1	20	--
02/28/02	84.38	73.29	11.09	0.00	--	--	170	<1.0	<1.0	<1.0	1.6	45	--
07/08/02	84.38	71.38	13.00	0.00	--	--	430	0.60	<0.50	0.79	<1.5	42	--
01/01/03	84.38	74.89	9.49	0.00	--	--	140	<0.50	<0.50	<0.50	<1.5	6.1	--
07/14/03[8]	84.38	71.36	13.02	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	43	--
01/12/04[8]	84.38	74.00	10.38	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	2	--
07/27/04[8]	84.38	72.60	11.78	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	41	--
01/25/05[8]	84.38	73.96	10.42	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	27	--
07/26/05[8]	84.38	72.17	12.21	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	12	--
01/24/06[8]	84.38	73.99	10.39	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	0.8	--
07/25/06[8]	84.38	72.76	11.62	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	23	--
01/23/07[8]	84.38	73.44	10.94	0.00	--	--	130	<0.5	<0.5	<0.5	<0.5	2	--
07/24/07[8]	84.38	74.10	10.28	0.00	--	--	210	<0.5	<0.5	<0.5	<0.5	20	--
01/22/08[8]	84.38	73.83	10.55	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/22/08[8]	84.38	72.40	11.98	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	7	--
01/13/09[8]	84.38	72.82	11.56	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	10	--
07/14/09	84.38	72.25	12.13	0.00	SAMPLED ANNUALLY		--	--	--	--	--	--	--
01/12/10[8]	**86.80**	**75.93**	**10.87**	**0.00**	**--**	**--**	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**14**	**--**

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-4													
10/18/90	84.25	68.50	15.75	--	--	--	--	--	--	--	--	--	--
10/31/90	84.25	70.35	13.90	--	--	--	<50	<0.5	<0.5	<0.5	1.0	--	--
11/16/90	84.25	70.00	14.25	--	--	--	--	--	--	--	--	--	--
02/08/91	84.25	71.93	12.32	--	--	--	60	17	2.0	12	<0.5	--	--
05/08/91	84.25	72.02	12.23	--	--	--	65	<0.5	<0.5	<0.5	<0.5	--	--
08/12/91	84.25	70.32	13.93	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/07/91	84.25	70.83	13.42	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/05/92	84.25	71.42	12.83	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
05/13/92	84.25	70.97	13.28	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/17/92	84.25	70.27	13.98	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/05/92	84.25	70.02	14.23	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/11/92	84.25	--	--	--	--	--	--	--	--	--	--	--	--
11/17/92	84.25	--	--	--	--	--	--	--	--	--	--	--	--
11/24/92	84.25	--	--	--	--	--	--	--	--	--	--	--	--
12/01/92	84.25	--	--	--	--	--	--	--	--	--	--	--	--
12/29/92	84.25	--	--	--	--	--	--	--	--	--	--	--	--
01/05/93	84.25	--	--	--	--	--	--	--	--	--	--	--	--
01/08/93	84.25	74.09	10.16	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/02/93	84.25	--	--	--	--	--	--	--	--	--	--	--	--
04/14/93	84.25	72.21	12.04	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/06/93	84.25	70.34	13.91	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/21/93	84.25	70.26	13.99	--	--	--	<50	<0.5	<0.5	<0.5	1.0	--	--
01/05/94	84.25	71.30	12.95	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/08/94	84.25	71.31	12.94	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/94	84.25	70.57	13.68	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/04/94	84.25	70.71	13.54	--	--	--	--	--	--	--	--	--	--
10/05/94	84.25	70.65	13.60	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
01/18/95	84.25	74.77	9.48	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/07/95	84.25	72.70	11.55	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/95	84.25	71.25	13.00	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/11/95	84.25	70.27	13.98	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/17/96	84.25	73.17	11.08	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/05/96	84.25	72.65	11.60	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/23/96	84.25	70.86	13.39	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/96	84.25	70.27	13.98	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/23/97	84.25	74.72	9.53	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-4 (cont)													
04/01/97	84.25	71.68	12.57	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/09/97	84.25	70.64	13.61	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/07/97	84.25	70.51	13.74	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/22/98	84.25	74.90	9.35	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/02/98	84.25	73.00	11.25	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/02/98	84.25	71.84	12.41	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/98	84.25	71.00	13.25	--	--	--	<50	<0.5	<0.5	<0.5	<1.5	<2.5	--
01/18/99	84.25	72.65	11.60	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
07/22/99	84.25	70.70	13.55	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
01/17/00	84.25	71.32	12.93	--	--	--	<50	<0.50	<0.50	<0.50	<0.50	<2.5	--
07/05/00	84.25	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/15/01	84.25	72.73	11.52	0.00	--	--	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	--
07/03/01	84.25	71.30	12.95	0.00	--	--	--	--	--	--	--	--	--
02/28/02	84.25	72.54	11.71	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
07/08/02	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/01/03	84.24	INACCESSIBLE - VEHICLE PARKED OVER WELL					--	--	--	--	--	--	--
07/14/03	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/12/04[8]	84.24	73.23	11.01	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/25/05[8]	84.24	73.28	10.96	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/26/05	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/24/06[8]	84.24	73.36	10.88	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/25/06	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/23/07[8]	84.24	71.85	12.39	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/24/07	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/22/08[8]	84.24	72.77	11.47	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/22/08	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/13/09[8]	84.24	71.56	12.68	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/14/09	84.24	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/12/10[8]	**87.29**	**76.14**	**11.15**	0.00	--	--	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	--
MW-5													
10/18/90	81.95	71.17	10.78	--	--	--	--	--	--	--	--	--	--
10/31/90	81.95	71.32	10.63	--	--	--	110	<0.5	<0.5	<0.5	<0.5	--	--
11/16/90	81.95	71.27	10.68	--	--	--	--	--	--	--	--	--	--
02/08/91	81.95	72.78	9.17	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-5 (cont)													
05/08/91	81.95	73.27	8.68	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/12/91	81.95	71.62	10.33	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/07/91	81.95	72.19	9.76	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/05/92	81.95	72.48	9.47	--	--	--	69	<0.5	<0.5	<0.5	<0.5	--	--
05/13/92	81.95	72.25	9.70	--	--	--	74	<0.5	<0.5	<0.5	<0.5	--	--
07/17/92	81.95	71.74	10.21	--	--	--	880	2.6	<1.2	4.6	11	--	--
10/05/92	81.95	71.34	10.61	--	--	--	120	<0.5	<0.5	0.6	4.9	--	--
11/11/92	81.95	--	--	--	--	--	--	--	--	--	--	--	--
11/17/92	81.95	--	--	--	--	--	--	--	--	--	--	--	--
11/24/92	81.95	--	--	--	--	--	--	--	--	--	--	--	--
12/01/92	81.95	--	--	--	--	--	--	--	--	--	--	--	--
12/29/92	81.95	--	--	--	--	--	--	--	--	--	--	--	--
01/05/93	81.95	--	--	--	--	--	--	--	--	--	--	--	--
01/08/93	81.95	74.61	7.34	--	--	--	61	<0.5	<0.5	<0.5	<0.5	--	--
02/02/93	81.95	--	--	--	--	--	--	--	--	--	--	--	--
04/14/93	81.95	--	--	--	--	--	--	--	--	--	--	--	--
08/06/93	81.95	71.99	9.96	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/21/93	81.95	71.89	10.06	--	--	--	<50	<0.5	<0.5	2.0	4.0	--	--
01/05/94	81.95	72.52	9.43	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/08/94	81.95	72.56	9.39	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/94	81.95	72.19	9.76	--	--	--	<50	0.6	<0.5	<0.5	<0.5	--	--
08/04/94	81.95	72.13	9.82	--	--	--	--	--	--	--	--	--	--
10/05/94	81.95	71.89	10.06	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
01/18/95	81.95	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
04/07/95	81.95	73.31	8.64	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/95	81.95	72.52	9.43	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/11/95	81.95	72.12	9.83	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/17/96	81.95	73.63	8.32	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/05/96	81.95	73.23	8.72	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/23/96	81.95	72.25	9.70	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/96	81.95	72.06	9.89	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/23/97	81.95	74.72	7.23	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/01/97	81.95	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
07/09/97	81.95	72.27	9.68	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/07/97	81.95	72.14	9.81	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/22/98	81.95	74.80	7.15	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-5 (cont)													
04/02/98	81.95	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
07/02/98	81.95	72.43	9.52	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/98	81.95	72.14	9.81	--	--	--	<50	<0.5	<0.5	<0.5	<1.5	<2.5	--
01/18/99	81.95	73.11	8.84	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
07/22/99	81.95	72.01	9.94	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
01/17/00	81.95	72.70	9.25	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/05/00	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/15/01	81.95	73.41	8.54	0.00	--	--	423[6]	<0.500	<0.500	<0.500	<0.500	<2.50	--
07/03/01	81.95	72.62	9.33	0.00	--	--	--	--	--	--	--	--	--
02/28/02	81.95	73.24	8.71	0.00	--	--	270	<0.50	<0.50	<0.50	<1.5	<2.5	--
07/08/02	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/01/03	81.95	INACCESSIBLE - VEHICLE PARKED OVER WELL					--	--	--	--	--	--	--
07/14/03	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/12/04[8]	81.95	73.91	8.04	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/25/05[8]	81.95	73.94	8.01	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/26/05	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/24/06[8]	81.95	73.89	8.06	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/25/06	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/23/07	81.95	INACCESSIBLE - VEHICLE PARKED OVER WELL					--	--	--	--	--	--	--
07/24/07	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/22/08[8]	81.95	73.50	8.45	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/22/08	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/13/09[8]	81.95	71.69	10.26	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/14/09	81.95	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/12/10[8]	**84.93**	**76.45**	**8.48**	0.00	--	--	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	--
MW-6													
10/18/90	80.60	70.81	9.79	--	--	--	--	--	--	--	--	--	--
10/31/90	80.60	70.91	9.69	--	--	--	<50	<0.5	<0.5	<0.5	3.0	--	--
11/16/90	80.60	70.86	9.74	--	--	--	--	--	--	--	--	--	--
02/08/91	80.60	--	--	--	--	--	--	--	--	--	--	--	--
05/08/91	80.60	71.06	9.54	--	--	--	56	<0.5	<0.5	<0.5	<0.5	--	--
08/12/91	80.60	71.10	9.50	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/07/91	80.60	71.71	8.89	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/05/92	80.60	72.01	8.59	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-6 (cont)													
05/13/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
07/17/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
10/05/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
11/11/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
11/17/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
11/24/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
12/01/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
12/29/92	80.60	--	--	--	--	--	--	--	--	--	--	--	--
01/05/93	80.60	--	--	--	--	--	--	--	--	--	--	--	--
01/08/93	80.60	--	--	--	--	--	--	--	--	--	--	--	--
02/02/93	80.60	72.89	7.71	--	--	--	<50	2.1	<0.5	<0.5	2.2	--	--
04/14/93	80.60	72.41	8.19	--	--	--	<50	1.0	<0.5	<0.5	<0.5	--	--
08/06/93	80.60	71.52	9.08	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/21/93	80.60	71.46	9.14	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
01/05/94	80.60	72.06	8.54	--	--	--	<50	4.0	<0.5	<0.5	<0.5	--	--
04/08/94	80.60	--	--	--	--	--	--	--	--	--	--	--	--
07/06/94	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
08/04/94	80.60	71.66	8.94	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/05/94	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
01/18/95	80.60	73.50	7.10	--	--	--	<50	0.69	<0.5	<0.5	0.57	--	--
04/07/95	80.60	72.77	7.83	--	--	--	<50	1.8	<0.5	<0.5	<0.5	--	--
07/06/95	80.60	72.03	8.57	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/11/95	80.60	71.54	9.06	--	--	--	<125	<1.2	<1.2	<1.2	<1.2	540	--
01/17/96	80.60	73.20	7.40	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	180	--
04/05/96	80.60	72.70	7.90	--	--	--	<125	1.4	<1.2	<1.2	<1.2	700	--
07/23/96	80.60	71.86	8.74	--	--	--	<500	<5.0	<5.0	<5.0	<5.0	540	--
10/02/96	80.60	71.62	8.98	--	--	--	<100	<1.0	<1.0	<1.0	1.8	910	--
01/23/97	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
04/01/97	80.60	72.22	8.38	--	--	--	<250	<2.5	<2.5	<2.5	<2.5	640	--
07/09/97	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
10/07/97	80.60	71.71	8.89	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	640	--
01/22/98	80.60	73.90	6.70	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	200	--
04/02/98	80.60	72.79	7.81	--	--	--	<250	<2.5	<2.5	<2.5	<2.5	480	--
07/02/98	80.60	71.62	8.98	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	420	--
10/02/98	80.60	71.68	8.92	--	--	--	<50	<0.5	<0.5	<0.5	<1.5	270	--
01/18/99	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-6 (cont)													
07/22/99	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
01/17/00	80.60	INACCESSIBLE		--	--	--	--	--	--	--	--	--	--
07/05/00	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/15/01	80.60	INACCESSIBLE - CAR PARKED OVER WELL					--	--	--	--	--	--	--
07/03/01	80.60	INACCESSIBLE - CAR PARKED OVER WELL					--	--	--	--	--	--	--
02/28/02	80.60	72.70	7.90	0.00	--	--	<50	<0.50	<0.50	<0.50	<1.5	55	--
07/08/02	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/01/03	80.60	INACCESSIBLE - VEHICLE PARKED OVER WELL					--	--	--	--	--	--	--
07/14/03	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/12/04[8]	80.60	73.23	7.37	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	25	--
01/25/05[8]	80.60	73.17	7.43	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	3	--
07/26/05	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/24/06[8]	80.60	73.20	7.40	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/25/06	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/23/07[8]	80.60	72.53	8.07	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	8	--
07/24/07	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/22/08[8]	80.60	73.07	7.53	0.00	--	--	<50	<0.5	<0.5	1	2	4	--
07/22/08	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/13/09[8]	80.60	70.73	9.87	0.00	--	--	<50	<0.5	<0.5	<0.5	<0.5	6	--
07/14/09	80.60	MONITORED/SAMPLED ANNUALLY				--	--	--	--	--	--	--	--
01/12/10[8]	**83.63**	**75.71**	**7.92**	**0.00**	--	--	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	--
MW-7													
03/08/94	86.36	74.99	11.37	--	<10	4,100	1,200	440	31	73	200	--	--
07/06/94	86.36	--	--	--	--	--	--	--	--	--	--	--	--
08/04/94	86.36	73.86	12.50	--	--	--	120	15	<0.5	3.8	1.8	--	--
10/05/94	86.36	73.99	12.37	--	--	--	150	1.2	<0.5	1.2	1.7	--	--
01/18/95	86.36	74.82	11.54	--	--	--	260	11	<1.0	17	6.8	--	--
04/07/95	86.36	75.63	10.73	--	--	--	230	<0.5	<0.5	25	0.93	--	--
07/06/95	86.36	74.36	12.00	--	--	--	320	<1.0	<1.0	<1.0	<1.0	--	6,900
10/11/95	86.36	73.56	12.80	--	--	2,300[1]	<50	<0.5	<0.5	<0.5	<0.5	120	--
01/17/96	86.36	75.90	10.46	--	--	1,700	<50	<0.5	<0.5	<0.5	<0.5	460	--
04/05/96	86.36	76.56	9.80	--	--	590	130	<0.5	<0.5	<0.5	<0.5	120	--
07/23/96	86.36	74.57	11.79	--	--	820	<500	<5.0	<5.0	<5.0	<0.5	1,200	--
10/02/96	86.36	73.10	13.26	--	--	1,500	<100	<1.0	<1.0	<1.0	<1.0	360	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-7 (cont)													
01/23/97	86.36	77.64	8.72	--	--	<500	<100	<1.0	<1.0	<1.0	<1.0	490	--
04/01/97	86.36	75.09	11.27	--	--	1,600	<250	<2.5	<2.5	<2.5	<2.5	1,200	--
07/09/97	86.36	73.92	12.44	--	--	5,700	<250	5.9	<2.5	<2.5	<2.5	1,200	--
10/07/97	86.36	73.44	12.92	--	--	<500	<50	<0.5	<0.5	<0.5	<0.5	240	--
01/22/98	86.36	75.14	11.22	--	--	<500	<50	<0.5	<0.5	<0.5	<0.5	400	--
04/02/98	86.36	75.67	10.69	--	--	<500	56	<0.5	<0.5	<0.5	<0.5	290	--
07/02/98	86.36	75.94	10.42	--	--	<500	<50	<0.5	<0.5	<0.5	<0.5	380	--
10/02/98	86.36	74.14	12.22	--	--	1,700	<50	<0.5	<0.5	<0.5	<1.5	660	--
01/18/99	86.36	75.36	11.00	--	--	543	<100	<1.0	<1.0	<1.0	<1.0	281/296[2]	--
07/22/99	86.36	74.06	12.30	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	155	--
01/17/00	86.36	75.84	10.52	--	256[1]	1,040	<50	<0.5	<0.5	<0.5	<0.5	104	--
07/05/00	86.36	74.23	12.13	0.00	--	1,400[4]	<50	<0.50	<0.50	<0.50	<0.50	110	--
01/15/01	86.36	75.23	11.13	0.00	--	2,700	<50.0	<0.500	<0.500	<0.500	<0.500	84.3	--
07/03/01	86.36	74.47	11.89	0.00	--	760[7]	<50	<0.50	<0.50	<0.50	<0.50	27	--
02/28/02	86.36	75.26	11.10	0.00	--	<1,000	<50	<0.50	<0.50	<0.50	<1.5	66	--
07/08/02	86.36	74.05	12.31	0.00	--	1,400	<50	<0.50	<0.50	<0.50	<1.5	49	--
01/01/03	86.36	76.65	9.71	0.00	--	1,300	<50	<0.50	<0.50	<0.50	<1.5	35	--
07/14/03[8]	86.36	74.01	12.35	0.00	--	130	<50	<0.5	<0.5	<0.5	<0.5	20	--
01/12/04[8]	86.36	75.66	10.70	0.00	--	250	<50	<0.5	<0.5	<0.5	<0.5	27	--
07/27/04[8]	86.36	74.08	12.28	0.00	--	730	<50	<0.5	<0.5	<0.5	<0.5	44	--
01/25/05[8]	86.36	75.56	10.80	0.00	--	980	<50	<0.5	<0.5	<0.5	<0.5	34	--
07/26/05[8]	86.36	73.69	12.67	0.00	--	1,100	<50	<0.5	<0.5	<0.5	<0.5	19	-
01/24/06[8]	86.36	75.60	10.76	0.00	--	230	<50	<0.5	<0.5	<0.5	<0.5	18	--
07/25/06[8]	86.36	74.17	12.19	0.00	--	160	<50	<0.5	<0.5	<0.5	<0.5	19	--
01/23/07[8]	86.36	74.60	11.76	0.00	--	2,100	<50	<0.5	<0.5	<0.5	<0.5	15	--
07/24/07[8]	86.36	73.91	12.45	0.00	--	3,100	<50	<0.5	<0.5	<0.5	<0.5	24	--
01/22/08[8]	86.36	75.36	11.00	0.00	--	4,400	<50	<0.5	<0.5	<0.5	<0.5	12	--
07/22/08[8]	86.36	73.38	12.98	0.00	--	200	<50	<0.5	<0.5	<0.5	<0.5	25	--
01/13/09[8]	86.36	73.85	12.51	0.00	--	1,400	<50	<0.5	<0.5	<0.5	<0.5	7	--
07/14/09[8]	86.36	73.18	13.18	0.00	--	1,000	<50	<0.5	<0.5	<0.5	<0.5	10	--
01/12/10[8]	**86.36**	**75.01**	**11.35**	**0.00**	**--**	**1,500**	**<50**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**5**	**--**

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-8													
03/08/94	85.93	75.06	10.87	--	<10	<100	28,000	2,900	1,300	1,200	6,800	--	--
07/06/94	85.93	--	--	--	--	--	--	--	--	--	--	--	--
08/04/94	85.93	73.77	12.16	--	--	--	22,000	3,000	260	870	4,400	--	--
10/05/94	85.93	72.71	13.22	--	--	--	12,000	1,800	34	4.6	890	--	--
01/18/95	85.93	75.51	10.42	--	--	--	19,000	1,000	65	1,100	3,500	--	--
04/07/95	85.93	75.48	10.45	--	--	--	14,000	310	<25	720	1,700	--	--
07/06/95	85.93	74.30	11.63	--	--	--	19,000	280	<50	1,200	2,600	--	--
10/11/95	85.93	73.51	12.42	--	--	--	6,100	140	5.5	320	280	1,200	--
01/17/96	85.93	75.95	9.98	--	--	<500	12,000	86	<20	590	1,400	1,100	--
04/05/96	85.93	75.60	10.33	--	--	<500	7,500	180	23	410	480	560	--
07/23/96	85.93	74.56	11.37	--	--	<500	3,800	47	<5.0	350	84	1,800	--
10/02/96	85.93	73.90	12.03	--	--	<500	4,400	65	<5.0	140	28	1,500	--
01/23/97	85.93	77.73	8.20	--	--	<500	3,800	36	5.9	140	36	910	--
04/01/97	85.93	75.80	10.13	--	--	<500	6,100	43	<20	380	76	1,800	--
07/09/97	85.93	73.77	12.16	--	--	<500	7,300	48	<25	120	<25	2,400	--
10/07/97	85.93	73.77	12.16	--	--	<500	3,100	<10	<10	67	<10	1,400	--
01/22/98	85.93	75.83	10.10	--	--	<500	1,900	5.5	8.3	120	17	780	--
04/02/98	85.93	75.55	10.38	--	--	<500	2,900	43	19	110	<10	800	--
07/02/98	85.93	74.78	11.15	--	--	<500	5,000	31	<10	120	15	780	--
10/02/98	85.93	74.03	11.90	--	--	1,200[1]	2,200	6.5	<0.5	21	2.6	140	--
01/18/99	85.93	75.12	10.81	--	554	<250	2,870	<5.0	<5.0	9.02	<5.0	476/478[2]	--
07/22/99	85.93	74.38	11.55	--	--	--	2,190	<1.0	<1.0	3.51	1.61	228	--
01/17/00	85.93	75.06	10.87	--	955[1]	<500	1,220	1.3	1.56	1.56	1.87	344	--
07/05/00	85.93	74.55	11.38	0.00	--	260[5]	1,900[3]	15	6.6	<5.0	<5.0	170	--
01/15/01	85.93	75.59	10.34	0.00	--	<250	2,820	<1.00	<1.00	5.13	3.90	110	--
07/03/01	85.93	74.77	11.16	0.00	--	<250	1,900[3]	6.0	<5.0	<5.0	<5.0	46	--
02/28/02	85.93	75.26	10.67	0.00	--	<1,000	1,500	4.6	<2.0	0.80	2.2	56	--
07/08/02	85.93	74.30	11.63	0.00	--	<400	2,500	4.2	0.85	0.68	2.5	46	--
01/01/03	85.93	76.01	9.92	0.00	--	<400	1,300	2.1	0.66	1.1	2.1	45	--
07/14/03[8]	85.93	74.27	11.66	0.00	--	160	1,900	<0.5	<0.5	<0.5	<0.5	58	--
01/12/04[8]	85.93	75.92	10.01	0.00	--	<40	1,400	<0.5	<0.5	<0.5	<0.5	110	--
07/27/04[8]	85.93	74.33	11.60	0.00	--	<40	1,100	<0.5	<0.5	<0.5	<0.5	89	--
01/25/05[8]	85.93	75.96	9.97	0.00	--	130	900	<0.5	<0.5	<0.5	<0.5	52	--
07/26/05[8]	85.93	74.08	11.85	0.00	--	99	580	<0.5	<0.5	<0.5	<0.5	23	--
01/24/06[8]	85.93	76.06	9.87	0.00	--	69	620	<0.5	<0.5	<0.5	<0.5	31	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
MW-8 (cont)													
07/25/06[8]	85.93	74.77	11.16	0.00	--	<40	420	<0.5	<0.5	<0.5	<0.5	20	--
01/23/07[8]	85.93	74.78	11.15	0.00	--	200	710	<0.5	<0.5	<0.5	<0.5	26	--
07/24/07[8]	85.93	74.15	11.78	0.00	--	730	560	<0.5	<0.5	<0.5	<0.5	30	--
01/22/08[8]	85.93	75.59	10.34	0.00	--	500	520	<0.5	<0.5	<0.5	<0.5	27	--
07/22/08[8]	85.93	73.86	12.07	0.00	--	90	330	<0.5	<0.5	<0.5	<0.5	21	--
01/13/09[8]	85.93	74.35	11.58	0.00	--	62	360	<0.5	<0.5	<0.5	<0.5	14	--
07/14/09[8]	85.93	73.68	12.25	0.00	--	90	500	<0.5	<0.5	<0.5	<0.5	10	--
01/12/10[8]	**85.95**	**75.50**	**10.45**	**0.00**	--	**100**	**370**	**<0.5**	**<0.5**	**<0.5**	**<0.5**	**8**	--
TRIP BLANK													
03/12/90	--	--	--	--	--	--	<50	<0.3	<0.3	<0.3	<0.6	--	--
02/08/91	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
05/08/91	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/12/91	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/07/91	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/05/92	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
05/13/92	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/17/92	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/05/92	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
11/11/92	--	--	--	--	--	--	--	--	--	--	--	--	--
11/17/92	--	--	--	--	--	--	--	--	--	--	--	--	--
11/29/92	--	--	--	--	--	--	--	--	--	--	--	--	--
12/01/92	--	--	--	--	--	--	--	--	--	--	--	--	--
12/29/92	--	--	--	--	--	--	--	--	--	--	--	--	--
01/05/93	--	--	--	--	--	--	--	--	--	--	--	--	--
01/08/93	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
02/02/93	--	--	--	--	--	--	--	--	--	--	--	--	--
04/14/93	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/06/93	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/21/93	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
01/05/94	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/08/94	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/94	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
08/04/94	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/05/94	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
TRIP BLANK (cont)													
01/18/95	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/07/95	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
07/06/95	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
10/11/95	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/17/96	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
04/05/96	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/23/96	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/96	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	--	--
01/23/97	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/01/97	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/09/97	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/07/97	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/22/98	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
04/02/98	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
07/02/98	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
10/02/98	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.5	--
01/18/99	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<1.5	<2.5	--
07/05/00	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<2.0	--
01/15/01	--	--	--	--	--	--	<50	<0.50	<0.50	<0.50	<0.50	<2.5	--
07/03/01	--	--	--	--	--	--	<50.0	<0.500	<0.500	<0.500	<0.500	<2.50	--
QA							<50	<0.50	<0.50	<0.50	<0.50	<2.5	--
02/28/02	--	--	--	--	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
07/08/02	--	--	--	--	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
01/01/03	--	--	--	--	--	--	<50	<0.50	<0.50	<0.50	<1.5	<2.5	--
07/14/03[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/12/04[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/27/04[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/25/05[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/26/05[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/24/06[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/25/06[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/23/07[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/24/07[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
01/22/08[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/22/08[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID/ DATE	TOC (ft.)	GWE (msl)	DTW (ft.)	SPHT (ft.)	TPH-DRO (µg/L)	TPH-MO (µg/L)	TPH-GRO (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	X (µg/L)	MTBE (µg/L)	TOG (µg/L)
QA (cont)													
01/13/09[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
07/14/09[8]	--	--	--	--	--	--	<50	<0.5	<0.5	<0.5	<0.5	<0.5	--
DESTROYED													

Table 1

Groundwater Monitoring Data and Analytical Results

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

EXPLANATIONS:

Groundwater monitoring data and laboratory analytical results prior to July 5, 2000, were compiled from reports prepared by Blaine Tech Services, Inc.

TOC = Top of Casing
(ft.) = Feet
GWE = Groundwater Elevation
(msl) = Mean sea level
DTW = Depth to Water
SPHT = Separate Phase Hydrocarbon Thickness
TPH = Total Petroleum Hydrocarbons

DRO = Diesel Range Organics
MO = Motor Oil
GRO = Gasoline Range Organics
B = Benzene
T = Toluene
E = Ethylbenzene
X = Xylenes

MTBE = Methyl Tertiary Butyl Ether
TOG = Total Oil & Grease
(µg/L) = Micrograms per liter
-- = Not Measured/Not Analyzed
QA = Quality Assurance/Trip Blank

* TOC elevations were surveyed on October 27, 2009, by Virgil Chavez Land Surveying. The benchmark for this survey was a cut square on top of easterly curb of Broadway, opposite 5718 Broadway. Benchmark Elevation = 180.06 feet. Vertical Datum is NGVD 29 from GPS observations.

1 Laboratory report indicates an unidentified hydrocarbon.

2 Confirmation run.

3 Laboratory report indicates gasoline C6-C12.

4 Laboratory report indicates motor oil C16-C36.

5 Laboratory report indicates unidentified hydrocarbons C9-C24.

6 Laboratory report indicates hydrocarbon pattern is present in the requested fuel quantitation range but does not resemble the pattern of the requested fuel. The pattern more closely resembles that of a heavier fuel.

7 Laboratory report indicates unidentified hydrocarbons >C16.

8 BTEX and MTBE by EPA Method 8260.

Table 2

Groundwater Analytical Results - Oxygenate Compounds

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID	DATE	ETHANOL (µg/L)	TBA (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TAME (µg/L)
MW-1	07/14/03	<50	--	5	--	--	--
	01/12/04	<50	--	61	--	--	--
	07/27/04	<50	--	54	--	--	--
	01/25/05	<50	--	5	--	--	--
	07/26/05	<50	--	25	--	--	--
	01/24/06	<50	--	25	--	--	--
	07/25/06	<50	--	14	--	--	--
	01/23/07	<50	--	17	--	--	--
	07/24/07	<50	--	7	--	--	--
	01/22/08	<50	--	8	--	--	--
	07/22/08	<50	--	<0.5	--	--	--
	01/13/09	<50	--	2	--	--	--
	01/12/10	--	--	**15**	--	--	--
MW-2	07/14/03	<50	--	<0.5	--	--	--
	01/12/04	<50	--	<0.5	--	--	--
	07/27/04	<50	--	<0.5	--	--	--
	01/25/05	<50	--	<0.5	--	--	--
	07/26/05	<50	--	<0.5	--	--	--
	01/24/06	<50	--	<0.5	--	--	--
	07/25/06	<50	--	<0.5	--	--	--
	01/23/07	<50	--	<0.5	--	--	--
	07/24/07	<50	--	<0.5	--	--	--
	01/22/08	<50	--	<0.5	--	--	--
	07/22/08	<50	--	2	--	--	--
	01/13/09	<50	--	<0.5	--	--	--
	01/12/10	--	--	**<0.5**	--	--	--
MW-3	07/14/03	<50	--	43	--	--	--
	01/12/04	<50	--	2	--	--	--
	07/27/04	<50	--	41	--	--	--
	01/25/05	<50	--	27	--	--	--
	07/26/05	<50	--	12	--	--	--
	01/24/06	<50	--	0.8	--	--	--
	07/25/06	<50	--	23	--	--	--

Table 2

Groundwater Analytical Results - Oxygenate Compounds

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID	DATE	ETHANOL (µg/L)	TBA (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TAME (µg/L)
MW-3 (cont)	01/23/07	<50	--	2	--	--	--
	07/24/07	<50	--	20	--	--	--
	01/22/08	<50	--	<0.5	--	--	--
	07/22/08	<50	--	7	--	--	--
	01/13/09	<50	--	10	--	--	--
	01/12/10	--	--	**14**	--	--	--
MW-4	07/14/03	SAMPLED ANNUALLY		--	--	--	--
	01/12/04	<50	--	<0.5	--	--	--
	01/25/05	<50	--	<0.5	--	--	--
	01/24/06	<50	--	<0.5	--	--	--
	01/23/07	<50	--	<0.5	--	--	--
	01/22/08	<50	--	<0.5	--	--	--
	01/13/09	<50	--	<0.5	--	--	--
	01/12/10	--	--	**<0.5**	--	--	--
MW-5	07/14/03	SAMPLED ANNUALLY		--	--	--	--
	01/12/04	<50	--	<0.5	--	--	--
	01/25/05	<50	--	<0.5	--	--	--
	01/24/06	<50	--	<0.5	--	--	--
	01/23/07	INACCESSIBLE - VEHICLE PARKED OVER WELL			--	--	--
	01/22/08	<50	--	<0.5	--	--	--
	01/13/09	<50	--	<0.5	--	--	--
	01/12/10	--	--	**<0.5**	--	--	--
MW-6	07/14/03	SAMPLED ANNUALLY		--	--	--	--
	01/12/04	<50	--	25	--	--	--
	01/25/05	<50	--	3	--	--	--
	01/24/06	<50	--	<0.5	--	--	--
	01/23/07	<50	--	8	--	--	--
	01/22/08	<50	--	4	--	--	--
	01/13/09	<50	--	6	--	--	--
	01/12/10	--	--	**<0.5**	--	--	--

Table 2

Groundwater Analytical Results - Oxygenate Compounds

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

WELL ID	DATE	ETHANOL (µg/L)	TBA (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TAME (µg/L)
MW-7	07/14/03	<50	--	20	--	--	--
	01/12/04	<50	--	27	--	--	--
	07/27/04	<50	--	44	--	--	--
	01/25/05	<50	--	34	--	--	--
	07/26/05	<50	--	19	--	--	--
	01/24/06	<50	--	18	--	--	--
	07/25/06	<50	--	19	--	--	--
	01/23/07	<50	--	15	--	--	--
	07/24/07	<50	--	24	--	--	--
	01/22/08	<50	--	12	--	--	--
	07/22/08	<50	--	25	--	--	--
	01/13/09	<50	--	7	--	--	--
	07/14/09	--	--	10	--	--	--
	01/12/10	--	--	5	--	--	--
MW-8	07/14/03	<50	--	58	--	--	--
	01/12/04	<50	--	110	--	--	--
	07/27/04	<50	--	89	--	--	--
	01/25/05	<50	--	52	--	--	--
	07/26/05	<50	--	23	--	--	--
	01/24/06	<50	--	31	--	--	--
	07/25/06	<50	--	20	--	--	--
	01/23/07	<50	--	26	--	--	--
	07/24/07	<50	--	30	--	--	--
	01/22/08	<50	--	27	--	--	--
	07/22/08	<50	--	21	--	--	--
	01/13/09	<50	--	14	--	--	--
	07/14/09	--	--	10	--	--	--
	01/12/10	--	--	8	--	--	--

Table 2

Groundwater Analytical Results - Oxygenate Compounds

Former Chevron Service Station #9-1583

5509 Martin Luther King Way

Oakland, California

EXPLANATIONS:

TBA = t-Butyl alcohol
MTBE = Methyl Tertiary Butyl Ether
DIPE = di-Isopropyl ether
ETBE = Ethyl t-butyl ether
TAME = t-Amyl methyl ether
(µg/L) = Micrograms per liter
-- = Not Analyzed

ANALYTICAL METHODS:

EPA Method 8260 for Oxygenate Compounds

STANDARD OPERATING PROCEDURE - GROUNDWATER SAMPLING

Gettler-Ryan Inc. (GR) field personnel adhere to the following procedures for the collection and handling of groundwater samples prior to analysis by the analytical laboratory. All work is performed in accordance with the GR Health & Safety Plan and all client-specific programs. The scope of work and type of analysis to be performed is determined prior to commencing field work.

Prior to sampling, the presence or absence of free-phase hydrocarbons is determined using an interface probe. Product thickness, if present, is measured to the nearest 0.01 foot and is noted in the field notes. In addition, all depth to water level measurements are collected with a static water level indicator and are also recorded in the field notes, prior to purging and sampling any wells.

After water levels are collected and prior to sampling, if purging is to occur, each well is purged a minimum of three well casing volumes of water using pre-cleaned pumps (stack, peristaltic or Grundfos), or disposable bailers. Temperature, pH and electrical conductivity are measured a minimum of three times during the purging (additional parameters such as dissolved oxygen, oxidation reduction potential, turbidity may also be measured, depending on specific scope of work.). Purging continues until these parameters stabilize.

Groundwater samples are collected using disposable bailers. The water samples are transferred from the bailer into appropriate containers. Pre-preserved containers, supplied by analytical laboratories, are used. When pre-preserved containers are not available, the laboratory is instructed to preserve the sample as appropriate. Duplicate samples are collected for the laboratory to use in maintaining quality assurance/quality control standards, as directed by the scope of work. The samples are labeled to include the job number, sample identification, collection date and time, analysis, preservation (if any), and the sample collector's initials. The water samples are placed in a cooler, maintained at 4°C for transport to the laboratory. Once collected in the field, all samples are maintained under chain of custody until delivered to the laboratory.

The chain of custody document includes the job number, type of preservation, if any, analysis requested, sample identification, date and time collected, and the sample collector's name. The chain of custody is signed and dated (including time of transfer) by each person who receives or surrenders the samples, beginning with the field personnel and ending with the laboratory personnel.

A laboratory supplied trip blank accompanies each sampling set. The trip blank is analyzed for some or all of the same compounds as the groundwater samples.

As requested by Chevron Environmental Management Company, the purge water and decontamination water generated during sampling activities is transported by IWM to Chemical Waste Management located in Kettleman Hills, California.

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING
FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 Job Number: 386506
Site Address: 5509 Martin Luther King Way Event Date: 1-12-10 (inclusive)
City: Oakland, CA Sampler: Joe

Well ID MW-1 Date Monitored: 1-12-10
Well Diameter 2 (3) in.
Total Depth 19.71 ft.
Depth to Water 8.71 ft.

Volume Factor (VF)	3/4"= 0.02	1"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= 1.02	6"= 1.50	12"= 5.80

☐ Check if water column is less then 0.50 ft.

11.00 xVF 0.38 = 4.18 x3 case volume = Estimated Purge Volume: 13 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 10.91

Purge Equipment:
Disposable Bailer ____
Stainless Steel Bailer ____
Stack Pump ✓
Suction Pump ____
Grundfos ____
Peristaltic Pump ____
QED Bladder Pump ____
Other: ____

Sampling Equipment:
Disposable Bailer ✓
Pressure Bailer ____
Discrete Bailer ____
Peristaltic Pump ____
QED Bladder Pump ____
Other: ____

Time Started: ____ (2400 hrs)
Time Completed: ____ (2400 hrs)
Depth to Product: ____ ft
Depth to Water: ____ ft
Hydrocarbon Thickness: ____ ft
Visual Confirmation/Description: ____
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: ____ gal
Amt Removed from Well: ____ gal
Water Removed: ____
Product Transferred to: ____

Start Time (purge): 0945 Weather Conditions: showers
Sample Time/Date: 1010 1-12-10 Water Color: clear Odor: (Y) / N faint
Approx. Flow Rate: 2-3 gpm. Sediment Description: ____
Did well de-water? yes If yes, Time: 0951 Volume: 7 gal. DTW @ Sampling: 9.46

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm - µS)	Temperature ((C) F)	D.O. (mg/L)	ORP (mV)
0950	5	6.91	742	18.4		
0951	7					

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-1	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	~~x 1 liter ambers~~	~~YES~~	NP	LANCASTER	TPH-MO (8015)

COMMENTS: ____

Add/Replaced Lock: ____ Add/Replaced Plug: ____ Add/Replaced Bolt: ____

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 Job Number: 386506
Site Address: 5509 Martin Luther King Way Event Date: 1-12-10 (inclusive)
City: Oakland, CA Sampler: JSC

Well ID MW-2 Date Monitored: 1-12-10
Well Diameter 2 in. Volume Factor (VF): 3/4"= 0.02, 1"= 0.04, 2"= 0.17, 3"= 0.38, 4"= 0.66, 5"= 1.02, 6"= 1.50, 12"= 5.80
Total Depth 18.84 ft.
Depth to Water 9.66 ft. ☐ Check if water column is less then 0.50 ft.
9.18 xVF 0.38 = 3.49 x3 case volume = Estimated Purge Volume: 10.5 gal.
Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 11.49

Purge Equipment:		Sampling Equipment:	
Disposable Bailer		Disposable Bailer	✓
Stainless Steel Bailer		Pressure Bailer	
Stack Pump	✓	Discrete Bailer	
Suction Pump		Peristaltic Pump	
Grundfos		QED Bladder Pump	
Peristaltic Pump		Other:	
QED Bladder Pump			
Other:			

Time Started: (2400 hrs)
Time Completed: (2400 hrs)
Depth to Product: ft
Depth to Water: ft
Hydrocarbon Thickness: ft
Visual Confirmation/Description:
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: gal
Amt Removed from Well: gal
Water Removed:
Product Transferred to:

Start Time (purge): 1022 Weather Conditions: showers
Sample Time/Date: 1043/1-12-10 Water Color: clear Odor: Y / (N)
Approx. Flow Rate: 3 gpm. Sediment Description:
Did well de-water? yes If yes, Time: 1027 Volume: 6 gal. DTW @ Sampling: 10.72

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm)	Temperature (C / F)	D.O. (mg/L)	ORP (mV)
1026	4	7.33	916	17.6		
1027	6					

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-2	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	~~x-1 liter ambers~~	~~YES~~	~~NP~~	~~LANCASTER~~	~~TPH-MO (8015)~~

COMMENTS:

Add/Replaced Lock: Add/Replaced Plug: Add/Replaced Bolt:

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 | Job Number: 386506
Site Address: 5509 Martin Luther King Way | Event Date: 1-12-10 (inclusive)
City: Oakland, CA | Sampler: Joe

Well ID: MW-3
Well Diameter: 2(3) in.
Total Depth: 19.45 ft.
Depth to Water: 10.87 ft.
Date Monitored: 1-12-10

Volume Factor (VF)	3/4"= 0.02	1"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= 1.02	6"= 1.50	12"= 5.80

☐ Check if water column is less then 0.50 ft.

8.58 xVF 0.38 = 3.26 x3 case volume = Estimated Purge Volume: 10 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 12.68

Purge Equipment:
- Disposable Bailer: ____
- Stainless Steel Bailer: ____
- Stack Pump: ✓
- Suction Pump: ____
- Grundfos: ____
- Peristaltic Pump: ____
- QED Bladder Pump: ____
- Other: ____

Sampling Equipment:
- Disposable Bailer: ✓
- Pressure Bailer: ____
- Discrete Bailer: ____
- Peristaltic Pump: ____
- QED Bladder Pump: ____
- Other: ____

Time Started: ____ (2400 hrs)
Time Completed: ____ (2400 hrs)
Depth to Product: ____ ft
Depth to Water: ____ ft
Hydrocarbon Thickness: ____ ft
Visual Confirmation/Description: ____
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: ____ gal
Amt Removed from Well: ____ gal
Water Removed: ____
Product Transferred to: ____

Start Time (purge): 1100 | Weather Conditions: cloudy
Sample Time/Date: 1125 11-12-10 | Water Color: clear | Odor: Y / (N)
Approx. Flow Rate: 3-4 gpm. | Sediment Description: ____
Did well de-water? yes | If yes, Time: 1105 | Volume: 4 gal. | DTW @ Sampling: 11.81

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm - (S))	Temperature ((C) / F)	D.O. (mg/L)	ORP (mV)
1105	4	6.84	587	17.5		
~~1100~~	~~4~~					

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-3	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	~~x 1-liter ambers~~	~~YES~~	~~NP~~	LANCASTER	~~TPH-MO (8015)~~

COMMENTS: ____

Add/Replaced Lock: ____ Add/Replaced Plug: ____ Add/Replaced Bolt: ____

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 Job Number: 386506
Site Address: 5509 Martin Luther King Way Event Date: 1-12-10 (inclusive)
City: Oakland, CA Sampler: Joe

Well ID MW-4 Date Monitored: 1-12-10
Well Diameter (2) 3 in.
Total Depth 26.20 ft.
Depth to Water 11.15 ft. ☐ Check if water column is less then 0.50 ft.

Volume Factor (VF)	3/4"= 0.02	1"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= t.02	6"= 1.50	12"= 5.80

15.05 xVF 0.17 = 2.56 x3 case volume = Estimated Purge Volume: 8 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 14.16

Purge Equipment:
Disposable Bailer ✓
Stainless Steel Bailer
Stack Pump
Suction Pump
Grundfos
Peristaltic Pump
QED Bladder Pump
Other:

Sampling Equipment:
Disposable Bailer ✓
Pressure Bailer
Discrete Bailer
Peristaltic Pump
QED Bladder Pump
Other:

Time Started: (2400 hrs)
Time Completed: (2400 hrs)
Depth to Product: ft
Depth to Water: ft
Hydrocarbon Thickness: ft
Visual Confirmation/Description:
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: gal
Amt Removed from Well: gal
Water Removed:
Product Transferred to:

Start Time (purge): 0855 Weather Conditions: showers
Sample Time/Date: 0918 1-12-10 Water Color: clear Odor: Y / N
Approx. Flow Rate: gpm. Sediment Description:
Did well de-water? If yes, Time: Volume: gal. DTW @ Sampling: 12.61

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm µS)	Temperature (C / F)	D.O. (mg/L)	ORP (mV)
0903	3	7.25	1010	18.0		
0908	5	7.30	969	18.2		
0913	8	7.36	972	18.0		

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW- 4	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	~~x 1 liter ambers~~	~~YES~~	~~NP~~	~~LANCASTER~~	~~TPH-MO (8015)~~

COMMENTS:

Add/Replaced Lock: Add/Replaced Plug: Add/Replaced Bolt:

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 | Job Number: 386506
Site Address: 5509 Martin Luther King Way | Event Date: 1-12-10 (inclusive)
City: Oakland, CA | Sampler: JR

Well ID: MW-5 | Date Monitored: 1-12-10
Well Diameter: (2) 3 in.
Total Depth: 19.11 ft.
Depth to Water: 8.48 ft. ☐ Check if water column is less then 0.50 ft.

Volume Factor (VF)	3/4"= 0.02	1"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= 1.02	6"= 1.50	12"= 5.80

10.63 xVF 0.17 = 1.81 x3 case volume = Estimated Purge Volume: 5.5 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 10.60

Purge Equipment:
Disposable Bailer: ✓
Stainless Steel Bailer:
Stack Pump:
Suction Pump:
Grundfos:
Peristaltic Pump:
QED Bladder Pump:
Other:

Sampling Equipment:
Disposable Bailer: ✓
Pressure Bailer:
Discrete Bailer:
Peristaltic Pump:
QED Bladder Pump:
Other:

Time Started: (2400 hrs)
Time Completed: (2400 hrs)
Depth to Product: ft
Depth to Water: ft
Hydrocarbon Thickness: ft
Visual Confirmation/Description:
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: gal
Amt Removed from Well: gal
Water Removed:
Product Transferred to:

Start Time (purge): 0718 | Weather Conditions: Showers
Sample Time/Date: 0805 1-12-10 | Water Color: clear | Odor: Y / (N)
Approx. Flow Rate: ~ gpm. | Sediment Description:
Did well de-water? _____ If yes, Time: _____ Volume: _____ gal. DTW @ Sampling: 9.03

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm - µS)	Temperature (C / F)	D.O. (mg/L)	ORP (mV)
0735	1.5	6.87	857	18.3		
0740	3	7.18	846	18.1		
0745	5.5	7.26	852	18.4		

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-5	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	~~x 1 liter ambers~~	~~YES~~	~~NP~~	~~LANCASTER~~	~~TPH-MO (8015)~~

COMMENTS:

Add/Replaced Lock: _____ Add/Replaced Plug: _____ Add/Replaced Bolt: _____

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING
FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 | Job Number: 386506
Site Address: 5509 Martin Luther King Way | Event Date: 1-12-10 (inclusive)
City: Oakland, CA | Sampler: Joe

Well ID: MW-6 | Date Monitored: 1-12-10
Well Diameter: (2) 3 in.
Total Depth: 19.65 ft.
Depth to Water: 7.92 ft.

Volume Factor (VF)	3/4"= 0.02	1"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= 1.02	6"= 1.50	12"= 5.80

☐ Check if water column is less then 0.50 ft.

11.73 xVF 0.17 = 1.99 x3 case volume = Estimated Purge Volume: 6 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 10.26

Purge Equipment:
- Disposable Bailer: ✓
- Stainless Steel Bailer:
- Stack Pump:
- Suction Pump:
- Grundfos:
- Peristaltic Pump:
- QED Bladder Pump:
- Other:

Sampling Equipment:
- Disposable Bailer: ✓
- Pressure Bailer:
- Discrete Bailer:
- Peristaltic Pump:
- QED Bladder Pump:
- Other:

Time Started: (2400 hrs)
Time Completed: (2400 hrs)
Depth to Product: ft
Depth to Water: ft
Hydrocarbon Thickness: ft
Visual Confirmation/Description:
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: gal
Amt Removed from Well: gal
Water Removed:
Product Transferred to:

Start Time (purge): 0815 | Weather Conditions: Showers
Sample Time/Date: 0842 1-12-10 | Water Color: clear Odor: Y / (N)
Approx. Flow Rate: ~ gpm. | Sediment Description:
Did well de-water? _____ If yes, Time: _____ Volume: _____ gal. DTW @ Sampling: 8.59

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm - µS)	Temperature (C / F)	D.O. (mg/L)	ORP (mV)
0822	2	7.43	954	18.5		
0830	4	7.41	937	18.2		
0837	6	7.48	943	18.3		

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-6	4 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	~~x 1 liter ambers~~	~~YES~~	~~NP~~	~~LANCASTER~~	~~TPH-MO (8015)~~

COMMENTS:

Add/Replaced Lock: _____ Add/Replaced Plug: _____ Add/Replaced Bolt: _____

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 Job Number: 386506
Site Address: 5509 Martin Luther King Way Event Date: 1-12-10 (inclusive)
City: Oakland, CA Sampler: Joe

Well ID MW-7 Date Monitored: 1-12-10
Well Diameter 2/3 in.
Total Depth 19.45 ft.
Depth to Water 11.35 ft.

Volume Factor (VF)	3/4"= 0.02	1"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= 1.02	6"= 1.50	12"= 5.80

☐ Check if water column is less then 0.50 ft.

8.10 xVF 0.17 = 1.38 x3 case volume = Estimated Purge Volume: 4.5 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 12.97

Purge Equipment:
Disposable Bailer ✓
Stainless Steel Bailer
Stack Pump
Suction Pump
Grundfos
Peristaltic Pump
QED Bladder Pump
Other:

Sampling Equipment:
Disposable Bailer ✓
Pressure Bailer
Discrete Bailer
Peristaltic Pump
QED Bladder Pump
Other:

Time Started: (2400 hrs)
Time Completed: (2400 hrs)
Depth to Product: ft
Depth to Water: ft
Hydrocarbon Thickness: ft
Visual Confirmation/Description:
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: gal
Amt Removed from Well: gal
Water Removed:
Product Transferred to:

Start Time (purge): 1135 Weather Conditions: Cloudy
Sample Time/Date: 1200 1/12.10 Water Color: Clear Odor: (Y) / N Moderate
Approx. Flow Rate: ~ gpm. Sediment Description:
Did well de-water? _____ If yes, Time: _____ Volume: _____ gal. DTW @ Sampling: 12.05

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm - mS)	Temperature (C / F)	D.O. (mg/L)	ORP (mV)
1142	1.5	6.70	595	18.6		
1146	3	6.72	610	18.6		
1151	4.5	6.73	616	18.8		

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-7	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	2 x 1 liter ambers	YES	NP	LANCASTER	TPH-MO (8015)

COMMENTS:

Add/Replaced Lock: _____ Add/Replaced Plug: _____ Add/Replaced Bolt: _____

GETTLER-RYAN INC.

WELL MONITORING/SAMPLING FIELD DATA SHEET

Client/Facility#: Chevron #9-1583 | Job Number: 386506
Site Address: 5509 Martin Luther King Way | Event Date: 1-12-10 (inclusive)
City: Oakland, CA | Sampler: Jay

Well ID: MW-8
Well Diameter: 2/3 in.
Total Depth: 17.10 ft.
Depth to Water: 10.45 ft.
Date Monitored: 1-12-10

Volume Factor (VF)	3/4"= 0.02	t"= 0.04	2"= 0.17	3"= 0.38
	4"= 0.66	5"= 1.02	6"= 1.50	12"= 5.80

☐ Check if water column is less then 0.50 ft.

6.65 xVF 0.17 = 1.13 x3 case volume = Estimated Purge Volume: 3.5 gal.

Depth to Water w/ 80% Recharge [(Height of Water Column x 0.20) + DTW]: 11.78

Purge Equipment:		Sampling Equipment:	
Disposable Bailer	✓	Disposable Bailer	✓
Stainless Steel Bailer		Pressure Bailer	
Stack Pump		Discrete Bailer	
Suction Pump		Peristaltic Pump	
Grundfos		QED Bladder Pump	
Peristaltic Pump		Other:	
QED Bladder Pump			
Other:			

Time Started: (2400 hrs)
Time Completed: (2400 hrs)
Depth to Product: ft
Depth to Water: ft
Hydrocarbon Thickness: ft
Visual Confirmation/Description:
Skimmer / Absorbant Sock (circle one)
Amt Removed from Skimmer: gal
Amt Removed from Well: gal
Water Removed:
Product Transferred to:

Start Time (purge): 1210 | Weather Conditions: cloudy
Sample Time/Date: 1235 1-12-10 | Water Color: clear Odor: Y / N strong
Approx. Flow Rate: ~ gpm. | Sediment Description:
Did well de-water? ____ If yes, Time: ____ Volume: ____ gal. DTW @ Sampling: 10.99

Time (2400 hr.)	Volume (gal.)	pH	Conductivity (µmhos/cm -uS)	Temperature (C / F)	D.O. (mg/L)	ORP (mV)
1216	1	6.67	629	17.8		
1220	2.5	6.72	638	18.0		
1226	4	6.76	635	18.1		

LABORATORY INFORMATION

SAMPLE ID	(#) CONTAINER	REFRIG.	PRESERV. TYPE	LABORATORY	ANALYSES
MW-8	6 x voa vial	YES	HCL	LANCASTER	TPH-GRO(8015)/BTEX+MTBE(8260)
	2 x 1 liter ambers	YES	NP	LANCASTER	TPH-MO (8015)

COMMENTS:

Add/Replaced Lock: ____ Add/Replaced Plug: ____ Add/Replaced Bolt: ____

Chevron California Region Analysis Request/Chain of Custody

Lancaster Laboratories

011210-02

For Lancaster Laboratories use only

Acct. #: 12099 Sample #: 5883138-45 Group #: 019497

C#1178557

CRA MTI Project #: 61H-1960

Facility #: SS#9-1583 G-R#386506 Global ID#T0600100348

Site Address: 5509 MARTIN LUTHER KING WAY, OAKLAND, CA

Chevron PM: MTI Lead Consultant: CRAKJ

Consultant/Office: G-R, Inc., 6747 Sierra Court, Suite J, Dublin, CA 94568

Consultant Prj. Mgr.: Deanna L. Harding (deanna@grinc.com)

Consultant Phone #: 925-551-7555 Fax #: 925-551-7899

Sampler: JOE AJEMIAN

Analyses Requested / Preservation Codes: H (BTEX + MTBE 8260 ☒ 8021 ☐), H (TPH 8015 MOD GRO)

Sample Identification	Date Collected	Time Collected	Grab	Composite	Soil	Water (☐ Potable ☐ NPDES)	Oil ☐ Air	Total Number of Containers	BTEX + MTBE 8260 ☒ 8021 ☐	TPH 8015 MOD GRO	TPH 8015 MOD DRO ☐ Silica Gel Cleanup	8260 full scan	Oxygenates	Total Lead Method	Dissolved Lead Method	TPH-MO (8015)				
MW-1	1-12-10	1010	✓			✓		6	✓	✓										
MW-2	↓	1043	↓			↓		6	✓	✓										
MW-3		1125						6	✓	✓										
MW-4		0918						6	✓	✓										
MW-5		0805						6	✓	✓										
MW-6		0842						6	✓	✓										
MW-7		1200						8	✓	✓							✓			
MW-8		1235						8	✓	✓							✓			

Preservative Codes
H = HCl T = Thiosulfate
N = HNO_3 B = NaOH
S = H_2SO_4 O = Other

☐ J value reporting needed
☒ Must meet lowest detection limits possible for 8260 compounds

8021 MTBE Confirmation
☐ Confirm highest hit by 8260
☐ Confirm all hits by 8260
☐ Run ____ oxy's on highest hit
☐ Run ____ oxy's on all hits

Comments / Remarks

Turnaround Time Requested (TAT) (please circle)
STD. TAT (circled) 72 hour 48 hour
24 hour 4 day 5 day

Data Package Options (please circle if required) EDF/EDD
QC Summary Type I - Full
Type VI (Raw Data) ☐ Coelt Deliverable not needed
WIP (RWQCB)
Disk

Relinquished by:	Date	Time	Received by:	Date	Time
[signature]	1-12-10	1335	[signature]	1/12/10	1335
[signature]	1/12/10	1545	FedEx		

Relinquished by Commercial Carrier:
UPS FedEx Other ________ Received by: Date Time

Temperature Upon Receipt 1.0-2.2 C° Custody Seals Intact? Yes No [signature] 1/14/10

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300 4804.01 (north) Rev. 10/12/06
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

916-677-3407

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

January 25, 2010

Project: 91583

Samples arrived at the laboratory on Thursday, January 14, 2010. The PO# for this group is 91583 and the release number is MTI. The group number for this submittal is 1178557.

Client Sample Description	Lancaster Labs (LLI) #
MW-1-W-100112 Grab Water	5883138
MW-2-W-100112 Grab Water	5883139
MW-3-W-100112 Grab Water	5883140
MW-4-W-100112 Grab Water	5883141
MW-5-W-100112 Grab Water	5883142
MW-6-W-100112 Grab Water	5883143
MW-7-W-100112 Grab Water	5883144
MW-8-W-100112 Grab Water	5883145

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC COPY TO Gettler-Ryan, Inc. Attn: Cheryl Hansen

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Questions? Contact your Client Services Representative
Jill M Parker at (717) 656-2300

Respectfully Submitted,

Robin C. Runkle
Senior Specialist

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-1-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-1

LLI Sample # WW 5883138
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 10:10 by JA

Account Number: 12099

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO01

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		ug/l	ug/l	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	15	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		ug/l	ug/l	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	P100181AA	01/18/2010 16:55	Daniel H Heller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	P100181AA	01/18/2010 16:55	Daniel H Heller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 17:21	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 17:21	Marie D John	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-2-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-2

LLI Sample # WW 5883139
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 10:43 by JA

Account Number: 12099

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO02

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		**ug/l**	**ug/l**	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	N.D.	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		**ug/l**	**ug/l**	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	P100181AA	01/18/2010 17:17	Daniel H Heller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	P100181AA	01/18/2010 17:17	Daniel H Heller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 17:48	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 17:48	Marie D John	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-3-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-3

LLI Sample # WW 5883140
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 11:25 by JA

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

MLO03

Account Number: 12099

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		ug/l	ug/l	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	14	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		ug/l	ug/l	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	P100181AA	01/18/2010 17:40	Daniel H Heller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	P100181AA	01/18/2010 17:40	Daniel H Heller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 18:15	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 18:15	Marie D John	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-4-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-4

LLI Sample # WW 5883141
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 09:18 by JA

Account Number: 12099

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO04

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		ug/l	ug/l	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	N.D.	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		ug/l	ug/l	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	F100153AA	01/16/2010 02:15	Kelly E Keller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	F100153AA	01/16/2010 02:15	Kelly E Keller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 18:42	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 18:42	Marie D John	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-5-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-5

LLI Sample # WW 5883142
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 08:05 by JA

Account Number: 12099

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO05

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		**ug/l**	**ug/l**	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	N.D.	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		**ug/l**	**ug/l**	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	P100222AA	01/22/2010 14:09	Anita M Dale	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	P100222AA	01/22/2010 14:09	Anita M Dale	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 19:09	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 19:09	Marie D John	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-6-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-6

LLI Sample # WW 5883143
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 08:42 by JA

Account Number: 12099

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO06

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		ug/l	ug/l	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	N.D.	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		ug/l	ug/l	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	F100153AA	01/16/2010 02:58	Kelly E Keller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	F100153AA	01/16/2010 02:58	Kelly E Keller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 19:36	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 19:36	Marie D John	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-7-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-7

LLI Sample # WW 5883144
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 12:00 by JA

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Account Number: 12099

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO07

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		ug/l	ug/l	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	5	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		ug/l	ug/l	
01728	TPH-GRO N. CA water C6-C12	n.a.	N.D.	50	1
GC Extractable TPH	**SW-846 8015B modified**		ug/l	ug/l	
02500	Total TPH	n.a.	1,500	39	1
02500	TPH Motor Oil C16-C36	n.a.	1,500	39	1

TPH quantitation is based on peak area comparison of the sample pattern to that of a hydrocarbon component mix calibration in a range that includes C8 (n-octane) through C40 (n-tetracontane) normal hydrocarbons.

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	F100153AA	01/16/2010 03:20	Kelly E Keller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	F100153AA	01/16/2010 03:20	Kelly E Keller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 20:03	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 20:03	Marie D John	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	100140016A	01/15/2010 10:25	Olivia I Santiago	1
02500	TPH Fuels by GC (Waters)	SW-846 8015B modified	1	100140016A	01/18/2010 20:17	Heather E Williams	1

Lancaster Laboratories
2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Sample Description: MW-8-W-100112 Grab Water
Facility# 91583 Job# 386506 MTI# 61H-1960 GRD
5509 Martin Luther King-Oa T0600100348 MW-8

LLI Sample # WW 5883145
LLI Group # 1178557
CA

Project Name: 91583

Collected: 01/12/2010 12:35 by JA

Account Number: 12099

Submitted: 01/14/2010 09:20
Reported: 01/25/2010 at 18:07
Discard: 02/25/2010

Chevron c/o CRA
Suite 110
2000 Opportunity Drive
Roseville CA 95678

MLO08

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Method Detection Limit	Dilution Factor
GC/MS Volatiles	**SW-846 8260B**		**ug/l**	**ug/l**	
06054	Benzene	71-43-2	N.D.	0.5	1
06054	Ethylbenzene	100-41-4	N.D.	0.5	1
06054	Methyl Tertiary Butyl Ether	1634-04-4	8	0.5	1
06054	Toluene	108-88-3	N.D.	0.5	1
06054	Xylene (Total)	1330-20-7	N.D.	0.5	1
GC Volatiles	**SW-846 8015B**		**ug/l**	**ug/l**	
01728	TPH-GRO N. CA water C6-C12	n.a.	370	50	1
GC Extractable TPH	**SW-846 8015B modified**		**ug/l**	**ug/l**	
02500	Total TPH	n.a.	100	40	1
02500	TPH Motor Oil C16-C36	n.a.	100	40	1

TPH quantitation is based on peak area comparison of the sample pattern to that of a hydrocarbon component mix calibration in a range that includes C8 (n-octane) through C40 (n-tetracontane) normal hydrocarbons.

General Sample Comments

State of California Lab Certification No. 2501
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01163	GC/MS VOA Water Prep	SW-846 5030B	1	F100153AA	01/16/2010 03:41	Kelly E Keller	1
06054	BTEX+MTBE by 8260B	SW-846 8260B	1	F100153AA	01/16/2010 03:41	Kelly E Keller	1
01146	GC VOA Water Prep	SW-846 5030B	1	10018A94A	01/18/2010 20:30	Marie D John	1
01728	TPH-GRO N. CA water C6-C12	SW-846 8015B	1	10018A94A	01/18/2010 20:30	Marie D John	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	100140016A	01/15/2010 10:25	Olivia I Santiago	1
02500	TPH Fuels by GC (Waters)	SW-846 8015B modified	1	100140016A	01/18/2010 19:53	Heather E Williams	1

Lancaster Laboratories

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Quality Control Summary

Client Name: Chevron c/o CRA
Reported: 01/25/10 at 06:07 PM

Group Number: 1178557

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank MDL	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: F100153AA	Sample number(s): 5883141,5883143-5883145							
Benzene	N.D.	0.5	ug/l	88		79-120		
Ethylbenzene	N.D.	0.5	ug/l	91		79-120		
Methyl Tertiary Butyl Ether	N.D.	0.5	ug/l	89		76-120		
Toluene	N.D.	0.5	ug/l	91		79-120		
Xylene (Total)	N.D.	0.5	ug/l	93		80-120		
Batch number: F100222AA	Sample number(s): 5883142							
Benzene	N.D.	0.5	ug/l	97	93	79-120	4	30
Ethylbenzene	N.D.	0.5	ug/l	98	94	79-120	5	30
Methyl Tertiary Butyl Ether	N.D.	0.5	ug/l	97	100	76-120	2	30
Toluene	N.D.	0.5	ug/l	98	94	79-120	4	30
Xylene (Total)	N.D.	0.5	ug/l	99	95	80-120	4	30
Batch number: P100181AA	Sample number(s): 5883138-5883140							
Benzene	N.D.	0.5	ug/l	96	95	79-120	0	30
Ethylbenzene	N.D.	0.5	ug/l	95	95	79-120	0	30
Methyl Tertiary Butyl Ether	N.D.	0.5	ug/l	103	103	76-120	0	30
Toluene	N.D.	0.5	ug/l	98	98	79-120	0	30
Xylene (Total)	N.D.	0.5	ug/l	97	97	80-120	0	30
Batch number: 10018A94A	Sample number(s): 5883138-5883145							
TPH-GRO N. CA water C6-C12	N.D.	50.	ug/l	118	118	75-135	0	30
Batch number: 100140016A	Sample number(s): 5883144-5883145							
Total TPH	N.D.	40.	ug/l	79	85	60-120	8	20
TPH Motor Oil C16-C36	N.D.	40.	ug/l					

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: F100153AA	Sample number(s): 5883141,5883143-5883145 UNSPK: P882265								
Benzene	-114 (2)	-25 (2)	80-126	12	30				
Ethylbenzene	-30 (2)	36 (2)	71-134	11	30				
Methyl Tertiary Butyl Ether	156*	160*	72-126	1	30				
Toluene	-453 (2)	-206 (2)	80-125	8	30				
Xylene (Total)	-89 (2)	27 (2)	79-125	11	30				

*- Outside of specification
(1) The result for one or both determinations was less than five times the LOQ.
(2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: Chevron c/o CRA
Reported: 01/25/10 at 06:07 PM

Group Number: 1178557

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: F100222AA	Sample number(s): 5883142 UNSPK: P884459								
Benzene	101		80-126						
Ethylbenzene	102		71-134						
Methyl Tertiary Butyl Ether	95		72-126						
Toluene	101		80-125						
Xylene (Total)	101		79-125						
Batch number: P100181AA	Sample number(s): 5883138-5883140 UNSPK: P883099								
Benzene	106		80-126						
Ethylbenzene	105		71-134						
Methyl Tertiary Butyl Ether	106		72-126						
Toluene	107		80-125						
Xylene (Total)	107		79-125						
Batch number: 10018A94A	Sample number(s): 5883138-5883145 UNSPK: P883132								
TPH-GRO N. CA water C6-C12	104		63-154						

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX+MTBE by 8260B
Batch number: F100153AA

	Dibromofluoromethane	1,2-Dichloroethane-d4	Toluene-d8	4-Bromofluorobenzene
5883141	91	91	92	105
5883143	94	92	89	102
5883144	88	89	87	99
5883145	89	90	89	103
Blank	93	92	90	103
LCS	90	90	90	103
MS	92	93	89	101
MSD	94	93	91	103
Limits:	80-116	77-113	80-113	78-113

Analysis Name: BTEX+MTBE by 8260B
Batch number: F100222AA

	Dibromofluoromethane	1,2-Dichloroethane-d4	Toluene-d8	4-Bromofluorobenzene
5883142	90	90	93	101
Blank	91	91	92	99
LCS	91	88	92	103
LCSD	93	92	92	103
MS	90	88	91	100
Limits:	80-116	77-113	80-113	78-113

*- Outside of specification
(1) The result for one or both determinations was less than five times the LOQ.
(2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: Chevron c/o CRA
Reported: 01/25/10 at 06:07 PM

Group Number: 1178557

Surrogate Quality Control

Analysis Name: BTEX+MTBE by 8260B
Batch number: P100181AA

	Dibromofluoromethane	1,2-Dichloroethane-d4	Toluene-d8	4-Bromofluorobenzene
5883138	91	90	89	87
5883139	91	88	89	86
5883140	91	88	90	88
Blank	91	88	90	87
LCS	91	89	91	89
LCSD	91	91	91	89
MS	91	91	90	87
Limits:	80-116	77-113	80-113	78-113

Analysis Name: TPH-GRO N. CA water C6-C12
Batch number: 10018A94A

	Trifluorotoluene-F
5883138	84
5883139	85
5883140	85
5883141	85
5883142	85
5883143	85
5883144	85
5883145	88
Blank	86
LCS	100
LCSD	98
MS	96
Limits:	63-135

Analysis Name: TPH Fuels by GC (Waters)
Batch number: 100140016A

	Chlorobenzene	Orthoterphenyl
5883144	56	66
5883145	80	86
Blank	72	78
LCS	68	92
LCSD	77	97
Limits:	28-152	52-131

*- Outside of specification
(1) The result for one or both determinations was less than five times the LOQ.
(2) The unspiked result was more than four times the spike added.

Lancaster Laboratories
Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected
TNTC	Too Numerous To Count
IU	International Units
umhos/cm	micromhos/cm
C	degrees Celsius
Cal	(diet) calories
meq	milliequivalents
g	gram(s)
ug	microgram(s)
ml	milliliter(s)
m3	cubic meter(s)
BMQL	Below Minimum Quantitation Level
MPN	Most Probable Number
CP Units	cobalt-chloroplatinate units
NTU	nephelometric turbidity units
F	degrees Fahrenheit
lb.	pound(s)
kg	kilogram(s)
mg	milligram(s)
l	liter(s)
ul	microliter(s)
fib >5 um/ml	fibers greater than 5 microns in length per ml

< less than – The number following the sign is the limit of quantitation, the smallest amount of analyte which can be reliably determined using this specific test.

> greater than

ppm parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.

ppb parts per billion

Dry weight basis Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quatitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*****	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.