## ALTON GEOSCIENCE, INC.

Alamec'a County

September 4, 1990

DEC 1 7 2003

Mr. Peter DeSantis BP Oil Company 2868 Prospect Park Drive, Suite 360 Rancho Cordova, California 95670-6020 Environmental Health
30-081

Subject: Supplemental Site Investigation Report

BP Oil Service Station No. 11132

3201 35th Avenue Oakland, California

Dear Mr. DeSantis:

In accordance with our agreement, Alton Geoscience, Inc. is pleased to submit this report on the supplemental site investigation performed at BP Oil Service Station No. 11132, located at 3201 35th Avenue, Oakland, California.

This report was prepared in response to the concerns of BP Oil Company and the applicable regulatory agencies regarding suspected subsurface contamination at the service station.

A copy of the report should be submitted to the following agencies for their review and approval:

- Mr. Rafat Shahid
   Alameda County Department of Health Services
   80 Swan Way, #200
   Oakland, California 94621
- 2. Mr. Tom Callaghan Regional Water Quality Control Board San Francisco Bay Region 1800 Harrison Street, Room 700 Oakland, California 94612

The scope of work to conduct further investigation and remedial feasibility study will be submitted under separate cover for your review and consideration.

Mr. Peter DeSantis September 4, 1990 Page 2

We would be pleased to discuss the results and findings of this supplemental study. Please call if you have any questions or comments regarding this report.

Sincerely,

ALTON GEOSCIENCE, INC.

Matthew Hopwood Project Manager

Al Sevilla, R.C.E. 26392 Division General Manager

Enclosures

#### **EXECUTIVE SUMMARY**

## Supplemental Site Investigation Report BP Oil Service Station No. 11132 3201 35th Avenue Oakland, California

This report presents the results and findings of a supplemental site investigation performed at BP Oil Service Station No. 11132, located at 3201 35th Avenue, Oakland, California. The investigative work was performed in accordance with the applicable requirements and guidelines of the San Francisco Regional Water Quality Control Board (RWQCB) and the Alameda County Department of Environmental Health (ACDEH). The scope of work included tasks and activities necessary to (1) assess the nature and extent of subsurface contamination onsite and offsite; and (2) develop appropriate courses of action for further investigation and/or remediation, if warranted.

#### PROJECT BACKGROUND

On July 30, 1986, Kaprealian Engineering, Inc. (KEI) was retained by Mobil Oil Corporation to install three 2-inch-diameter monitoring wells at this former Mobil Oil service station. Monitoring and sampling of the wells, performed by KEI, indicated detectable levels of total petroleum hydrocarbons (TPH) in both MW-1 and MW-2 at levels up to 210 parts per million (ppm).

#### SCOPE OF WORK

The scope of the investigative work included the following tasks:

- Conduct a qualitative shallow ground water survey (QSGWS).
- Install five soil borings for conversion into one onsite recovery well and one onsite and three offsite ground water monitoring wells.
- 3. Collect and analyze soil and ground water samples.
- Analyze field data and laboratory results.
- 5. Prepare a report presenting the results, findings, and recommendations of the investigation.

The results of these tasks provide the basis for evaluating the need for further investigation and/or remediation.

## SUMMARY OF FINDINGS AND CONCLUSIONS

The findings and conclusions of this site investigation study are summarized below:

- Soil types encountered at the site during drilling generally consisted of silty clay.
- 2. The average depth to ground water at the site is approximately 20 feet below grade.
- 3. The ground water elevation contour map, developed from the water level and survey data, indicates a southerly ground water flow direction beneath the site, with an average gradient of approximately 0.01 foot per foot.
- 4. TPH-G and BTEX constituents detected in the soil samples from the borings onsite and offsite ranged from nondetectable to 700 ppm of TPH-G and 4.8 ppm of benzene. From the data presented herein, the extent of petroleum hydrocarbon constituents in the soil onsite appears to be limited to the southern portion of the site, south of the pump islands and underground fuel tanks.
- 5. Transmissivity, hydraulic conductivity, and linear velocity of the aquifer (onsite) as determined by the slug testing are 1.71 ft<sup>2</sup>/day, 0.12 ft/day, and 1.0 x 10<sup>-3</sup> ft/day, respectively. These values are representative of soil types with low permeability such as silty clays encountered below the site.
- 6. Soil samples collected from the soil boring for MW-5, located approximately 150 feet from the site, had detectable levels of TPH-G from 10 feet below grade to the capillary fringe. Contamination throughout the soil column indicates the close proximity of a potential contaminant source. A Quikstop store with underground gasoline storage tanks is located approximately 10 feet from MW-5.
- 7. The shallow ground water beneath the site has been impacted by free-floating product (detected in MW-1 and MW-2) and dissolved-phase petroleum hydrocarbon constituents, the extent of which cannot be defined at this time based on presently available data.

- 8. Based on the locations of the monitoring wells and the level of hydrocarbon constituents detected, it appears that the dissolved-phase hydrocarbon contaminant plume has migrated offsite south of the property. This is consistent with the general flow direction of the shallow ground water.
- 9. There are no existing domestic water supply wells in the immediate vicinity or within a 1/2-mile radius of the site (personal communication, City of Oakland Public Works).

#### RECOMMENDATIONS

Based on the results and findings of this site investigation study, Alton Geoscience recommends the following activities:

- 1. Conduct periodic pumping of MW-1, MW-2, and RW-1 to recover free-floating product and control/minimize further contaminant plume migration.
- 2. Install an automated product recovery system to remove free-product as an interim remedial measure.
- Conduct a remedial feasibility study and implement a remedial action plan to comply with applicable laws and regulations.
- 4. Implement a quarterly ground water monitoring and sampling program in accordance with regulatory agency requirements.

Alternative remedial measures that should be evaluated and considered in detail include, but are not limited to, the following:

- Periodic recovery of ground water followed by treatment to reduce hydrocarbon levels, if necessary, and discharge of treated water to the sanitary or storm sewer system.
- 2. Continuous recovery and treatment of ground water for discharge to a sanitary or storm sewer system.



## DRAFT

## SUPPLEMENTAL SITE INVESTIGATION REPORT

BP Oil Service Station No. 11132 3201 35th Avenue Oakland, California

#### SUPPLEMENTAL SITE INVESTIGATION REPORT

## BP Oil Service Station No. 11132 3201 35th Avenue Oakland, California :

September 4, 1990

## Project Number 30-081

This report was based on currently available data and was developed in accordance with current hydrogeologic and engineering practices.

This report was prepared by:

Staff Engineer

Matthew Hopwood

Project Manager

Date

This report was reviewed by:

Al Sevilla

Registered Civil Engineer

No. 26392

Division General Manager

## TABLE OF CONTENTS

		Page
1.0	INTRODUCTION AND BACKGROUND	1
1.1 1.2 1.3 1.4	Purpose and Scope	1 1 2 2
2.0	FIELD METHODS	2
2.1 2.2 2.3 2.4 2.5	Qualitative Shallow Ground Water Survey	2 3 4 4 5
3.0	ANALYTICAL METHODS	5
3.1 3.2 3.3	Qualitative Shallow Ground Water Survey Analysis . Soil Analysis	5 5 5
4.0	AQUIFER ANALYSIS	6
4.1 4.2 4.3 4.4	Rising Head or Slug Test	6 7 7 8
5.0	SITE GEOLOGY AND HYDROGEOLOGY	9
5.1 5.2	Site Geology	9 9
6.0	DISCUSSION OF RESULTS	10
6.1 6.2 6.3 6.4	Qualitative Shallow Ground Water Survey SoilGround Water	10 10 10 11
7 0	ETHDINGS AND CONCLUSIONS	12

## TABLE OF CONTENTS (continued)

#### TABLES

- 1 Survey and Water Level Monitoring Data
- 2 Results of Laboratory Analysis of Soil Samples
- 3 Results of Laboratory Analysis of Ground Water Samples

#### **FIGURES**

- 1 Site Vicinity Map
- 2 Site Plan
- 3 Ground Water Elevation Contour Map
- 4 Total Petroleum Hydrocarbon Isoconcentration Map
- 5 Benzene Isoconcentration Map

#### REFERENCES

## **APPENDICES**

- A Interim Report Qualitative Shallow Ground Water Survey
- B General Field Procedures and Boring Logs
- C Well Development and Water Sampling Procedures and Field Survey Forms
- D Permits
- E Official Laboratory Reports and Chain of Custody Records
- F Aquifer Test Data

#### 1.0 INTRODUCTION AND BACKGROUND

BP Oil Company retained Alton Geoscience, Inc. to conduct a Supplemental Site Investigation Study related to subsurface contamination at Service Station No. 11132, located at 3201 35th Avenue, Oakland, California. The site location is shown in Figure 1, while a site plan is shown in Figure 2.

## 1.1 Purpose and Scope

This supplemental site investigation study was performed to: (1) address the concerns of the San Francisco Bay Regional Water Quality Control Board (RWQCB) and the Alameda County Department of Environmental Health (ACDEH) regarding petroleum hydrocarbon contamination at the site; and (2) determine the nature and extent of hydrocarbon levels in the subsurface soil and ground water.

The scope of the investigative work included the following tasks:

- Conduct a qualitative shallow ground water survey (QSGWS).
- Install five soil borings for conversion into one onsite recovery well and one onsite and three offsite ground water monitoring wells.
- 3. Collect and analyze soil and ground water samples.
- 4. Analyze field data and laboratory results.
- 5. Prepare a report presenting the results, findings, and recommendations of the investigation.

The results of these tasks provide the basis for evaluating the need for further investigation and/or remediation.

## 1.2 Site Description

The site is currently an operating BP Oil service station located on the northeast corner of the intersection of 35th Avenue and Suter Street, Oakland, California. The adjacent properties are primarily residential and commercial developments.

The site is located at an elevation of approximately 160 feet above mean sea level. The location and layout of the underground storage tanks are shown in Figure 2.

## 1.3 Project Background

On July 30, 1986, Kaprealian Engineering, Inc. (KEI) was retained by Mobil Oil Corporation to install three 2-inch-diameter monitoring wells at this former Mobil Oil service station. Monitoring and sampling of the wells, performed by KEI, indicated detectable levels of total petroleum hydrocarbons (TPH) in both MW-1 and MW-2 at levels up to 210 parts per million (ppm).

## 1.4 Regional Geology and Hydrogeology

The topography of the surrounding area is characterized by valleys and gentle slopes. The underlying unit in this region consists of Undivided Quaternary deposits (QU). The QU unit's composition and physical properties vary, but consist predominantly of Temescal Formation, which probably includes covered or unrecognized San Antonio Formation and gravel, sand, and clay (Qg), as well as recent alluvium and colluvium and artificial fill.

The site is located in the 580-square-mile Alameda Bay Plain Ground Water Basin drained by the Guadalupe River and Alameda, Coyote, Redwood, and San Francisquito Creeks. The water-bearing material is comprised of younger and older alluvium. The nearest surface water drainage is San Leandro Creek, approximately 1-1/4 miles to the south, which drains into San Leandro Bay. According to the Alameda County Public Works Department, there are no domestic wells within a 1/2-mile of the site. Municipal or domestic water supply in the area is provided by the East Bay Municipal Utilities District which obtains its water from the Mokelumne River.

## 2.0 FIELD METHODS

The procedures and methods used during field activities were in accordance with applicable regulatory requirements and procedures, outlined in Appendices B and C.

## 2.1 Oualitative Shallow Ground Water Survey

To determine the lateral extent of ground water contamination, a qualitative shallow ground water survey (QSGWS) was initially conducted. The survey is essentially a screening process to assist in determining the most appropriate locations of the additional monitoring wells necessary to define the lateral extent of hydrocarbon levels in the ground water. The procedure is based on the soil boring technique combined with temporary wells for ground water sampling.

On January 26 and February 1, 1990, Alton Geoscience, Inc. supervised the drilling of eight soil borings to various depths, ranging from 25 to 33 feet below grade, depending on subsurface conditions. The borings were advanced 3 to 4 feet beyond the depth at which first ground water was encountered. Following drilling, the borings were converted into temporary wells (TW-1 through TW-10) by inserting clean, 2-inchdiameter, Schedule 40, polyvinyl chloride (PVC) casing with 0.020-inch slots. Prior to sampling, each temporary well was purged of 2 to 3 gallons of ground water. During sampling. ground water was inspected for the presence of free-floating product or sheen. The samples collected were then decanted into sterile volatile organic analysis (VOA) vials for transport to a state-certified laboratory for analysis under chain of custody documentation. During the QSGWS, free-floating product was encountered in one of the temporary wells, TW-2.

An interim report dated May 10, 1990 presents the results of the QSGWS. A copy of the interim report is included as Appendix A.

## 2.2 Soil Borings and Sampling

Based on the results of the QSGWS, the locations of the additional soil borings/monitoring wells were selected. On May 9, 1990, prior to commencement of offsite drilling activities, Ground Water Protection Ordinance Permit 90276 was obtained from the Alameda County Flood Control and Water Conservation District. On May 17, 1990, Street Excavation Permit Nos. 9000935, 9000936, and 90009937 were obtained from the City of Oakland Department of Public Works. Copies of the ground water protection ordinance permit and the street excavation permits are presented in Appendix D.

On May 16, 1990, Alton Geoscience supervised the drilling of two soil borings, which were converted into one 2-inch-diameter ground water monitoring well (MW-4) and one 6-inch-diameter recovery well (RW-1). The borings were drilled using 8-inch-diameter and 10-inch-diameter hollow-stem augers to total depths of approximately 40 feet below grade. During drilling, soil samples were collected from the soil borings at 5-foot intervals below grade until the first ground water was encountered at a depth of approximately 27 feet below grade.

On June 25, 1990, Alton Geoscience supervised the drilling of three offsite soil borings, which were converted into 2-inch-diameter ground water monitoring wells (MW-5, MW-6, and MW-7). The borings were drilled using 8-inch-diameter hollow-stem augers to total depths of approximately 35 feet

below grade. During drilling, soil samples were collected from monitoring well borings at 5-foot intervals until the first ground water was encountered, at a depth of about 26 feet below grade in MW-5 and 28 feet below grade in MW-6 and MW-7.

Drilling activities were performed by West Hazmat Drilling Corporation of Rancho Cordova, California using a truck mounted CME 75 drilling rig. The soil samples were collected using a split-spoon sampler lined with stainless steel tubes. The samples recovered for laboratory analysis were wrapped with aluminum foil, capped with polyurethane caps, labeled, wrapped in cellophane tape, and placed immediately in an iced cooler. A description of drilling procedures and soil sampling protocol and copies of boring logs are presented in Appendix B.

## 2.3 Ground Water Monitoring Well Construction

The soil borings were completed as Ground Water Monitoring Wells MW-4, MW-5, MW-6, and MW-7 and Recovery Well RW-1. The monitoring wells were constructed of clean, 2-inch-diameter, flush-threaded, Schedule 40 PVC, blank casing and 0.020-inch, slotted casing to total depths of 35 to 40 feet below grade. Recovery Well RW-1 was constructed of clean, 6-inch-diameter, flush-threaded, Schedule 40 PVC, blank casing and 0.020-inch, slotted casing to a total depth of approximately 40 feet below grade. Well construction details are shown on the boring logs in Appendix B.

## 2.4 Monitoring Well Development and Sampling

Development and sampling of the monitoring wells were conducted on July 9, 1990. Prior to sampling, the ground water monitoring wells were purged by pumping approximately 10.5 gallons from MW-3, 28 gallons from MW-4, 20 gallons from MW-5, 27 gallons from MW-6, and 23.5 gallons from MW-7. Monitoring Wells MW-1 and MW-2 were not sampled because of the presence of approximately 0.25 and 0.10 foot of free-floating product.

The water samples were decanted from the bailer into clean containers and transported in an iced cooler to a state-certified laboratory for analysis following proper chain of custody procedures. Water sampling field survey forms documenting field observations during well development/purging and sampling are presented in Appendix C.

## 2.5 Ground Water Level Monitoring and Surveying

On July 5, 1990, the monitoring wells were surveyed to the nearest 0.01 foot in reference to City of Oakland benchmark number 2576 with an elevation of 170.467 feet above mean sea level (MSL). The purpose of the survey was to obtain top of casing elevations of the monitoring wells for use in calculating the ground water elevation at each well and determining the ground water flow direction and gradient at the site.

Ground water level monitoring and survey data collected on July 5, 1990 are presented in Table 1. A ground water elevation contour map based on interpretation of the monitoring data is shown in Figure 3.

#### 3.0 ANALYTICAL METHODS

All laboratory analyses of soil and ground water samples were performed by a California state-certified analytical laboratory, using standard test methods of the U.S. Environmental Protection Agency (EPA) and the California Department of Health Services. The laboratory reports and chain of custody records are presented in Appendix E.

## 3.1 Qualitative Shallow Ground Water Sample Analysis

All ground water samples collected from the temporary wells as part of QSGWS were analyzed for TPH-G with BTEX distinction using EPA Methods 5030 and 602. The results of the laboratory analyses of ground water samples are presented in Table 2 of Appendix A.

## 3.2 Soil Analysis

Soil samples from the five borings were analyzed for TPH-G with BTEX distinction using EPA Methods 5030 and 8020. The results of the laboratory analyses of the soil samples are presented in Table 2.

## 3.3 Water Analysis

Ground water samples collected from the monitoring wells were analyzed for TPH-G with BTEX distinction using EPA Methods 5030 and 602. The results of the laboratory analyses of ground water samples are presented in Table 4. TPH-G and benzene isoconcentration maps developed from analytical results of ground water samples are shown in Figure 4 and 5.

## 4.0 AQUIFER TESTING AND ANALYSIS

Analysis of aquifer characteristics to determine the fate and transport of contaminants in ground water involves several stages. The first is the exploratory stage, in which surface and subsurface geological and geophysical techniques are used to define physical characteristics of the water-bearing formation. Next is the evaluation stage to determine the hydrogeologic parameters and characteristics of the aquifer, which are needed to properly design and construct recovery or extraction wells and to control contaminant migration. The last is the confirmation stage, in which the design and operation of the wells are optimized for the management and remediation of ground water. The following sections are based on the work of Bouwer (1979); Cedergren (1977); Freeze et al (1979) and Thompson (1987).

## 4.1 Basis of Analysis

The hydraulic properties of aquifers and soil materials that define the rate of water movement into, through, and out of subsurface material, and the water movement's effect on the pieziometric surfaces of water tables, are hydraulic conductivity (K); storage coefficient (S) (or specific yield for an unconfined aquifer); and transmissivity (T).

Hydraulic conductivity is defined as the rate at which water can move through a porous media (soil) under a unit hydraulic gradient. It is primarily dependent upon the porosity and permeability of the soil and the density and viscosity of the water. However, not all water occupying pore spaces in a saturated aguifer can be readily extracted.

One measure of the water-yielding ability of an aquifer is the storage coefficient, which is defined as the volume of water produced per unit horizontal area by a unit drop in the water table level (unconfined aquifers) or the pieziometric surface (confined aquifers).

Another term used to indicate the water-yielding capacity of an aquifer is transmissivity (T). The transmissivity of an aquifer is the product of the hydraulic conductivity and the saturated thickness (b), or:

T = Kb

where T = Transmissivity in feet<sup>2</sup>/day

K = Hydraulic conductivity in feet/day

b = Approximate aquifer thickness in feet

Of interest in understanding aquifer characteristics is the movement or yielding capabilities of the water-bearing formation. To determine these parameters, values for one or more of the aquifer properties must be obtained. Various techniques have been developed for obtaining values for these properties or parameters. For example, rate-of-rise or rate-of-fall techniques, such as the auger-hole and slug test method, measure the hydraulic conductivity (K) of the soil profile in shallow ground water.

## 4.2 Rate-of-Rise or Rate-of-Fall Techniques

In-situ hydraulic conductivity values can be determined from tests performed in a single well or piezometer. The test is initiated by causing an instantaneous change in the water level in a well through a sudden introduction or removal of a volume of water. The recovery of the water level over time is then observed. The procedure requires the use of a pressure sensitive transducer with the probe placed just off the bottom of the well. Water is then immediately introduced or removed from the well, and pressure readings are recorded over time. When water is removed, the test is called a bail test; when water is added, it is known as a slug test.

Bouwer and Rice (1976) developed a procedure for estimating hydraulic conductivity (K) based on the response of the well to a sudden change in the water table. The hydraulic conductivity can be calculated as follows:

$$K = r \cdot \ln(R/r_w) \cdot \ln(Yo/Y_t) / (2L t)$$

where: R = Effective radial distance over which the head difference is dissipated

rw = Radial distance between well center and undisturbed aquifer

L = Height of perforated section of well through which ground water enters

Yo = Difference in head elevation at time zero

 $Y_t$  = Difference in head elevation at time t

t = Time since Yo

When the observed water elevation data are plotted against time (t) on a semi-logarithmic paper (t on the arithmetic scale), the data points should produce a straight line. The data begin to deviate from the straight line relationship at a small change in water table head. To evaluate 1/t x ln(Yo/Yt) and calculate K, the straight-line portion of the curve should be used. The results of this method are generally considered an appropriate means of estimating the hydraulic conductivity within an order of magnitude.

## 4.3 Field Test Procedures

Alton Geoscience selected the slug test method based on available hydrogeologic data to estimate the hydraulic conductivity (K) of the aquifer, using Monitoring Wells MW-1, and MW-2. Prior to conducting the aquifer test, depth to water was measured in the wells. The slug tests were performed on July 14, 1990, using a 5-gallon bucket (slug) to inject clean distilled water into the well, and a data logger with a pressure sensitive transducer.

The pressure is converted into head (elevation of water above the transducer) as the water instantaneously rises and then flows into the surrounding aquifer. A computer program was used to statistically analyze the field data and determine hydraulic conductivity based on a shape factor coefficient corresponding to the diameter of the well screen and filter pack surrounding the screen.

## 4.4 Analysis of Aguifer Parameters

Graphical results showing the plot of the normalized drawdown (Y/Yo) versus time (t) for each ground water monitoring well are included in Appendix F. The Y/Yo term is obtained by dividing each measured drawdown by the maximum drawdown. Y is the drawdown at time t, and Yo is the maximum drawdown immediately following addition of the "slug" of water.

The hydraulic conductivity (K) values calculated for each well tested are:

Well ID	K. ft/day	
MW-1 MW-2	0.090 0.154	3410'3

The average hydraulic conductivity (K) calculated from the test results is 0.122 foot per day. Assuming an aquifer thickness of 14 feet, the average transmissivity (T) of the aquifer is estimated to be 1.71 ft<sup>2</sup>/day.

Hydraulic conductivity can also be used to calculate the average linear velocity at which a subsurface fluid moves using Darcy's Law. Darcy's Law can be stated as follows:

where: v = Darcy velocity of water

K = Hydraulic conductivity of aquifer material

i = Slope of the water table (gradient)

The result of the calculation yields a value representing the horizontal velocity at which a fluid moves through the pore spaces between specified points within the more permeable zone.

Assuming the average hydraulic conductivity of the aquifer is 0.122 foot/day, and the estimated hydraulic gradient at the site is 0.01 foot/foot, the calculation yields an average linear velocity of  $1.0 \times 10^{-3}$  foot/day. At this rate, a fluid particle would travel 2.74 foot per year.

From review of the boring logs, the subsurface soil is comprised primarily of silty clay. According to the United States Geological Survey Water Supply Paper 2220, (1984), the hydraulic conductivity of silty clay formations typically range from  $10^{-3}$  to 10 feet per day, which is consistent with the slug test data.

#### 5.0 SITE GEOLOGY AND HYDROGEOLOGY

A brief description of the pertinent information on the site geology and hydrogeology is presented below.

## 5.1 Site Geology

The soil borings drilled during this supplemental investigation revealed a consistent stratigraphy beneath the site. Silty clay was the predominant soil type encountered throughout each boring. The soil types encountered during this study were generally consistent with the results of the previous investigation conducted by KEI.

#### 5.2 <u>Site Hydrogeology</u>

The ground water elevations for Monitoring Wells MW-3, MW-4, MW-5, MW-6, MW-7, and RW-1, as measured on July 9, 1990, were used to develop the ground water elevation contour map shown in Figure 3. The data indicates a southerly ground water flow direction, with an average gradient of approximately 0.01 foot per foot. As presented in Table 1, the depth to ground water in MW-1 through MW-7, and RW-1 as measured from

the top of casing on July 9, 1990 ranged from about 17 to 21 feet below grade.

There are no known or reported ground water production wells in use as a domestic or municipal water supply source within the immediate vicinity or a 1/2-mile radius of the site (personal communication, City of Oakland Public Works Department).

## 6.0 DISCUSSION OF RESULTS

The results of the field activities and laboratory analysis of soil and ground water samples collected during this investigation are presented in Tables 2 and 3 and are discussed below.

## 6.1 Qualitative Shallow Ground Water Survey

A total of 10 water samples were collected for analysis during the QSGWS, including water samples from Monitoring Wells MW-2 and MW-3. The samples from MW-1 and TW-2 contained free-floating product and were not analyzed. Chemical analysis of water samples revealed TPH-G levels ranging from nondetectable to 240,000 ppb. A summary of analytical results and the TPH-G and benzene isoconcentration maps based on the QSGWS are presented in Appendix A.

## 6.2 Soil

A total of eighteen soil samples were collected from five borings and analyzed as part of this site investigation study to assess the nature and extent of subsurface soil contamination. The results are discussed below.

- No detectable levels of TPH-G and BTEX constituents were found in the soil samples collected from borings for Monitoring Wells MW-4, MW-6, and MW-7.
- The levels of TPH-G in the soil samples collected from the boring for Recovery Well RW-1 and MW-5 were as high as 50 ppm, and up to 700 ppm, respectively.
- The extent of petroleum hydrocarbon constituents in the soil appears to have migrated offsite (south of the site) and to the zone from 10 feet below grade to the capillary fringe.

#### 6.3 Ground Water

Results of the field survey and laboratory analysis of ground water samples collected from the monitoring wells were used to assess the nature and extent of hydrocarbon constituents in ground water. The results of the laboratory analysis are summarized in Table 4 and discussed below.

- Dissolved-phase TPH-G levels detected in the water samples ranged from nondetectable in Monitoring Wells MW-4, MW-6, and MW-7, to 280 ppb in MW-5. No BTEX constituents were detected in the samples from MW-4, MW-6, and MW-7. However, benzene was detected at levels of 5.3 ppb and 200 ppb in the samples from MW-3 and MW-5, respectively.
- During the sampling event on July 9, 1990, free-floating product was encountered in Monitoring Wells MW-1 and MW-2. The product thickness in MW-1 and MW-2 was 0.25 and 0.10 foot, respectively.
- The sample from Monitoring Well MW-5, the most downgradient offsite monitoring well, had the highest concentrations of TPH-G and BTEX constituents in the soil and ground water samples. It should be noted that MW-5 is located approximately 150 feet from the BP site and immediately adjacent to a Quikstop store with underground gasoline storage tanks.

## 6.4 Hydrogeologic Characteristics

The aquifer analysis and calculations were based on the assumption that the porous media is isotropic and homogeneous. These conditions, however, seldom exist in the natural subsurface environment. The aquifer located beneath the site is neither isotropic nor homogeneous. It exhibits variations in physical properties both vertically and horizontally. Therefore, the hydraulic conductivity determined by the aquifer test data should only be considered accurate within an order of magnitude of actual values at the specific point within the porous media. Based on the calculated hydraulic conductivity of 0.12 foot per day, the actual hydraulic conductivity could range from 0.012 to 1.2 foot per day. This range of hydraulic conductivity values is typical for soils composed of silty clay which is consistent with the soil encountered at the site.

It should be noted that plume migration does not necessarily occur at the same rate as ground water movement. Darcy's Law governing ground water flow does not consider the hydrodynamic processes of adsorption and dispersion that are involved in the transport of contaminants in ground water.

## 7.0 FINDINGS AND CONCLUSIONS

The findings and conclusions of this site investigation study are summarized below:

- Soil types encountered at the site during drilling generally consisted of silty clay.
- 2. The average depth to ground water at the site is approximately 20 feet below grade.
- 3. The ground water elevation contour map, developed from the water level and survey data, indicates a southerly ground water flow direction beneath the site, with an average gradient of approximately 0.01 foot per foot.
- 4. TPH-G and BTEX constituents detected in the soil samples from the borings onsite and offsite ranged from nondetectable to 700 ppm of TPH-G and 4.8 ppm of benzene. From the data presented herein, the extent of petroleum hydrocarbon constituents in the soil onsite appears to be limited to the southern portion of the site, south of the pump islands and underground fuel tanks.
- 5. Transmissivity, hydraulic conductivity, and linear velocity of the aquifer (onsite) as determined by the slug testing are 1.71 ft<sup>2</sup>/day, 0.12 ft/day, and 1.0 x 10<sup>-3</sup> ft/day, respectively. These values are representative of soil types with low permeability such as silty clays encountered below the site.
- 6. Soil samples collected from the soil boring for MW-5, located approximately 150 feet from the site, had detectable levels of TPH-G from 10 feet below grade to the capillary fringe. Contamination throughout the soil column indicates the close proximity of a potential contaminant source. A Quikstop store with underground gasoline storage tanks is located approximately 10 feet from MW-5.

- 7. The shallow ground water beneath the site has been impacted by free-floating product (detected in MW-1 and MW-2) and dissolved-phase petroleum hydrocarbon constituents, the extent of which cannot be defined at this time based on presently available data.
- 8. Based on the locations of the monitoring wells and the level of hydrocarbon constituents detected, it appears that the dissolved-phase hydrocarbon contaminant plume has migrated offsite south of the property. This is consistent with the general flow direction of the shallow ground water.
- 9. There are no existing domestic water supply wells in the immediate vicinity or within a 1/2-mile radius of the site (personal communication, City of Oakland Public Works).




TABLE 1
SURVEY AND WATER LEVEL MONITORING DATA
July 1990

Well Number	Wellhead Elevation (Feet)	Depth to Water (Feet)	Free Product Thickness (Feet)	Ground Water Elevation (Feet)
MW-1	169.75	21.46	0.22	148.13*
MW-2	168.14	20.24	0.10	147.97*
MW-3	167.17	18.96		148.21
MW-4	170.36	21.30		149.06
MW-5	165.14	17.97		147.17
MW-6	165.40	17.20		148.20
MW-7	167.60	19.70		147.90
RW-1	168.01	27.93	1.21	**

## Note:

- \* Elevation adjusted assuming 0.75 specific gravity of free product.
- \*\* Not an accurate elevation due to the presence of over 0.25 foot of free product.

TABLE 2

RESULTS OF
LABORATORY ANALYSIS OF SOIL SAMPLES
June - July 1990

28111

Boring	Sample Depth (ft)	TPH-G (Concen	B trations	T in Parts	E Per Mill	X ion)
			<u>June 199</u>	<u>o</u>		
MW-4 MW-4 MW-4 MW-4 RW-1 RW-1 RW-1	5.0 10.0 15.0 20.0 25.0 5.0 10.0 15.0	ND ND ND ND ND ND 22 41	ND ND ND ND ND ND ND ND	ND ND ND ND ND ND 1.6 18.0	ND ND ND ND ND ND ND 0.58 8.0	ND ND ND ND ND ND ND 2.2 40.0
RW-1	25.0	50	1.4 July 199	3.3 <u>0</u>	1.0	5.4
MW-5 MW-5 MW-5 MW-5 MW-5	5.0 10.0 15.0 20.0 25.0	ND 9.3 14 190 770	ND ND 0.16 1.8 4.8	ND 0.019 0.037 11 44	ND ND 0.29 2.5	ND 0.11 0.42 17 94
MW-6 MW-6 MW-7	15.0 20.0 15.0	ND ND	ND ND ND	ND ND ND	ND ND	ND ND

## Notes:

TPH-G = Total Petroleum Hydrocarbons as Gasoline

B = Benzene T = Toluene

E = Ethylbenzene X = Total Xylenes

ND = Not Detected at Method Detection Limit (refer to Appendix D, Official Laboratory Reports)

TABLE 3 RESULTS OF LABORATORY ANALYSIS OF GROUND WATER SAMPLES July 1990

Monitoring Well	TPH-G (Concer	B atrations	T in Parts	E per Bill:	X ion)
MW-1					#9 Cm
MW-2					
MW-3	140	5.3	4.6	2.0	3.8
MW-4	ND	ND	ND	ND	ND
MW-5	280	200	210	46	290
MW-6	ND	ND	ND	ND	ND
MW-7	ND	ND	ND	ND	ND

## Notes:

TPH-G = Total Petroleum Hydrocarbons as Gasoline


B = Benzene  ${f T}$ = Toluene

E = Ethylbenzene Х = Total Xylenes

= Not Detected at Method Detection Limit ND

(refer to Appendix D, Official Laboratory Reports)
= No sample collected due to the presence of free


floating product



Source: U.S.G.S. Map, East Oakland, California Quadrangle

7.5 minute series. 1959. Photorvised 1980.





# FIGURE 1 SITE VICINITY MAP


B P SERVICE STATION NO. 11132 3201 35TH AVENUE OAKLAND, CALIFORNIA


**PROJECT NO. 30 - 081** 





**ALTON GEOSCIENCE** 

1000 Burnett Ave., Ste 140 Concord, CA 94520











#### REFERENCES

- Bouwer, H., and Rice, R. C., A Slug Test for Determining Hydraulic Conductivity of Unconfined Aguifers with Completely or Partially Penetrating Wells; Water Resources Research, Volume 12, 1976, pp. 423-428.
- Bouwer, H., <u>Groundwater Hydrology</u>; McGraw-Hill, New York, 1979.
- Cedergren, H. R., <u>Seepage</u>, <u>Drainage</u>, and <u>Flownets</u>; John Wiley, 1977.
- Freeze, R. A., and Cherry, J. A., <u>Groundwater</u>; Prentice-Hall, 1979.
- Thompson, D. B., A Microcomputer Program for Interpreting
  Time-Lag Permeability Tests; Ground Water, Vol. 25, 1987,
  pp. 212-218.

## **APPENDIX A**

Interim Report
Qualitative Shallow Ground Water Survey

## ALTON GEOSCIENCE, INC.

May 10, 1990

Mr. William J. Hollis BP Oil Company 2868 Prospect Park Drive, Suite 360 Rancho Cordova, California 95670-6020

30-081

Subject: Interim Report - Preliminary Results of Qualitative Water Survey, Monitoring, and Sampling BP Service Station No. 11132 3201 35th Avenue Oakland, California

Dear Mr. Hollis:

This interim report presents the results of this phase of investigative work completed to date at BP Oil Service Station No. 11132, located at 3201 35th Avenue, Oakland, California. All activities were performed in accordance with the regulations and guidelines of the San Francisco Bay Regional Water Quality Control Board (RWQCB) and the Alameda County Department of Environmental Health (ACDEH).

#### SCOPE OF WORK

The scope of work performed to date by Alton Geoscience includes the following tasks:

- Survey, monitoring, and sampling of three existing onsite monitoring wells.
- Installation, sampling, and destruction of 10 temporary wells for the qualitative water survey.
- Analysis of 13 water samples by a state-certified analytical laboratory.
- Preparation of this letter report.

## SITE DESCRIPTION AND BACKGROUND

The site is currently an operating BP service station at the northern corner of the intersection of 35th Avenue and Suter Street, Oakland, California. The approximate site elevation is 160 feet. Regional surface and ground water flow in the region is to the southwest, towards San Francisco Bay. The nearest surface water drainage is Peralta Creek, about 1/4-mile north of the site.

Mr. William J. Hollis May 10, 1990 Page 2

On July 30, 1986, Kaprealian Engineering, Inc. (KEI) was retained by Mobil Oil Corporation to install three 2-inch-diameter monitoring wells at this former Mobil Oil service station. Monitoring and sampling of the wells, performed by KEI, indicated detectable levels of total petroleum hydrocarbons (TPH) in both MW-1 and MW-2 at levels up to 210 parts per million (ppm).

### FIELD METHODS

The procedures and methods used during field activities were in accordance with regulatory requirements of the RWQCB and ACDEH.

#### Wellhead Survey

On December 12, 1989, the top of casing of the wells was surveyed in reference to an arbitrary datum (MW-1), with an assumed elevation of 160 feet above mean sea level. Depth to water measurements obtained on January 26, 1990 were used to construct the ground water elevation contour map (Figure 2). Wellhead elevations, depth to water measurements, and ground water elevations are presented in Table 1.

#### Oualitative Ground Water Sampling

On January 26 and February 1, 1990, 10 soil borings were completed to various depths, ranging from 25 to 33 feet below grade, at the locations shown in Figure 2. The drilling was completed by West Hazmat Drilling Company of Rancho Cordova, California, using a CME 75 drill rig equipped with 8-inch-diameter, hollow-stem augers.

The borings were advanced 3 to 4 feet beyond the depth at which ground water was encountered. Following drilling, the borings were converted into temporary wells (TW-1 through TW-10) by inserting clean, 2-inch-diameter, Schedule 40, PVC casing with 0.020-inch slots. The ground water level was allowed to stabilize in the wells. Prior to sampling, each temporary well was purged of 2 to 3 gallons of ground water. During purging, ground water was inspected for the presence of free product or sheen, and then decanted into sterile volatile organic analysis (VOA) containers for transport to a state-certified laboratory for analysis under chain of custody documentation.

Mr. William J. Hollis May 10, 1990 Page 3

Following sample collection, the temporary casing was removed from the boring and steam cleaned. Soil borings were then backfilled with grout slurry and capped with asphalt.

On January 26, 1990, ground water samples were collected from the three existing monitoring wells, following RWQCB quidelines and procedures for well purging and sampling.

#### Well Monitoring

On January 26, 1990, Monitoring Wells MW-1, MW-2, and MW-3 were surveyed for depth to water and the presence of sheen or free-floating product. Depth to water and product thickness were measured using an electronic sounder. Approximately 0.1 foot of free product was observed in MW-1.

#### ANALYTICAL METHODS AND RESULTS

Nine of the ground water samples were submitted to a laboratory for analysis. Ground water samples collected from MW-1 and TW-2 were not analyzed due to presence of free product. All laboratory analysis of ground water samples was performed by Superior Analytical, a California state-certified laboratory, using standard test methods of the U.S. EPA and the California Department of Health Services (DHS). Analytical methods used were EPA Method 8015 for total petroleum hydrocarbons as gasoline (TPH) and EPA Method 602 for benzene, toluene, ethylbenzene, and total xylenes (BTEX). Table 2 presents the laboratory results, while the official laboratory report is presented in Attachment A.

#### DISCUSSION OF RESULTS

The sample from Monitoring Well MW-1 contained 0.1 foot of free product, while Temporary Well TW-2 contained 0.05 foot. Samples from the other monitoring and temporary wells contained levels of dissolved TPH as gasoline and hydrocarbon constituents (BTEX) ranging from nondetectable (ND) to 240,000 parts per billion (ppb). It appears that the contaminant plume in the ground water has migrated downgradient towards the southwest and offsite of the property.

Mr. William J. Hollis May 10, 1990 Page 4

#### RECOMMENDATIONS

Based on the results of this qualitative ground water survey, and in accordance with our agreement, we recommend the following:

- 1. Install confirmation/monitoring wells, one upgradient onsite, two crossgradient offsite, and one downgradient offsite.
- Install a large-diameter recovery well and an automatic recovery system (ARS) onsite to control the migration of the plume and remove free product from the ground water.
- 3. Perform aquifer tests to determine the hydrogeologic properties of the aquifer at the site as well as an interim remedial measure.

If you have any questions, please contact either of the undersigned at (415) 682-1582.

Sincerely,

ALTON GEOSCIENCE, INC.

Matthew J. Hopwood Project Geologist

Al Sevilla

Division General Manager

TABLE 1
MONITORING AND SURVEY DATA

Well	Depth to Water (Feet)	Product Thickness (Feet)	TOC Elevation (Feet)	Ground Water Elevation (Feet)
		January 26,	1990	
MW-1	19.48	0.1	160	140.52
MW-2	19.80	'	158.40	138.60
MW-3	20.75		157.42	136.67

TOC = Top of Casing

<sup>\*</sup>A 0.8 conversion factor is used to determine water table depression due to the presence of free-floating product interpreted from Levorson, 1967.

TABLE 2 RESULTS OF ANALYSIS GROUND WATER SAMPLES

January 26, and February 1, 1990 Sampling

Well	TPH (ppb)	Benzene (ppb)	Toluene (ppb)	Ethyl- benzene (ppb)	Total Xylenes (ppb)
MW-1	FP			## DA DA	
MW-2	14,000	580	1,300	460	2,300
MW-3	500	20	30	24	35
TW-1	7,400	230	180	690	1,200
TW-2	FP				
TW-3	22,000	2,400	2,800	530	4,000
TW-4	ND<100	ND <0.3	ND <0.3	ND <0.3	0.7
<b>TW-</b> 5	240,000	1,100	5,100	5,600	28,000
TW-6	20,000	56	910	590	3,700
TW-7	ND<100	ND <0.3	0.4	0.7	4.3
TW-8	ND<100	0.3	0.6	1.1	7.9
TW-9	41,000	2,100	5,700	120	6,900
TW-10	50,000	1,900	7,300	1,400	8,000


ND = Nondetectable

FP = Free Product

ppb = parts per billion
MW = Monitoring Well
TW = Temporary Well

Source: U.S.G.S. Map, East Oakland, California Quadrangle

1959. Photorvised 1980. 7.5 minute series.









FIGURE 1 SITE VICINITY MAP

B P SERVICE STATION NO. 11132 3201 35TH AVENUE OAKLAND, CALIFORNIA

**PROJECT NO. 30 - 081** 









0 10 20 SCALE IN FEET

### LEGEND:

**♦** 

MONITORING WELLS

(140.52')

**GROUND WATER ELEVATION** 

138.00'

GROUND WATER
ELEVATION CONTOUR

-

DIRECTION OF GROUND WATER FLOW

FIGURE 2 GROUND WATER ELEVATION CONTOUR MAP

> B P SERVICE STATION NO. 11132 3201 35TH AVENUE OAKLAND, CALIFORNIA

35TH AVENUE



## ATTACHMENT A

LABORATORY REPORTS AND CHAIN OF CUSTODY FORMS

1385 FAIRFAX St., Ste. D. · SAN FRANCISCO, CA 94124 · PHONE (415) 647-2081

### CERTIFICATE OF ANALYSIS

LABORATORY NO.: 80513 CLIENT: Alton Geoscience CLIENT JOB NO.: 30-081 DATE RECEIVED: 02/02/90 DATE REPORTED: 02/09/90

ANALYSIS FOR BENZENE, TOLUENE, ETHYL BENZENE & XYLENES by EPA SW-846 Methods 5030 and 8020

			Concentration(ug/L)					
LAB #	Sample Identification	Benzene	Toluene	Ethyl Benzene	Xylenes			
1	TW-4	ND<0.3	ND<0.3	ND<0.3	0.7			
2	TW-5	1100	5100	5600	28000			
3	TW-6	56	910	590	3700			
4	TW-7	ND<0.3	0.4	0.7	4.3			
5	TW-8	0.3	0.6	1.1	7.9			
6	TW-9	2100	5700	1200	6900			
7	TW-10	1900	7300	1400	8000			

ug/L - parts per billion (ppb)
ug/kg - parts per billion (ppb)

Method Detection Limit in Soil: 3 ug/kg Method Detection Limit in Water: 0.3 ug/L

### QAQC Summary:

Daily Standard run at 20ug/L: RPD = <15%

MS/MSD Average Recovery = 92 %: Duplicate RPD = <10

Edward R. Morales

Laboratory Manager

## 1385 FAIRFAX St., Ste. D. • SAN FRANCISCO, CA 94124 • PHONE (415) 647-2081

## CERTIFICATE OF ANALYSIS

LABORATORY NO.: 80498 CLIENT: Alton Geoscience CLIENT JOB NO.: 30-081 DATE RECEIVED: 01/29/90 DATE REPORTED: 02/05/90

ANALYSIS FOR BENZENE, TOLUENE, ETHYL BENZENE & XYLENES by EPA SW-846 Methods 5030 and 8020

			ation(ug/	(/L)	
LAB #	Sample Identification	Benzene	Toluene	Ethyl Benzene	Xylenes
1 2 3	MW-2 MW-3 TW-1 TW-3	580 20 230 2400	1300 30 180 2800	460 24 690 530	2300 35 1200 4000

ug/L - parts per billion (ppb) ug/kg - parts per billion (ppb)

Method Detection Limit in Soil: 3 ug/kg Method Detection Limit in Water: 0.3 ug/L

### QAQC Summary:

Daily Standard run at 20ug/L: RPD = <15%

MS/MSD Average Recovery = 96 %: Duplicate RPD = <2%

Edward R. Morales

Laboratory Manager

## 1385 FAIRFAX St., Ste. D. • SAN FRANCISCO, CA 94124 • PHONE (415) 647-2081

CERTIFICATE OF AUALYSI,

LABORATORY NO.: 80498 CLIENT: Alten Geoscience CLIENT JOB NO.: 30-981 DATE RECEIVED: 01/29/90 DATE REPORTED: 02/05/90

ANALYSIS FOR TOTAL PETROLEUM HYDROCARBONS by Modified EPA SW-846 Method 5030 and 8015

LAB	Sample Identification	Concentration (mg/L) Gasoline Range
1	MW-2	14
2	MW-3	9.5
3	TW-1	7.4
4	TW-3	22

mg/L - parts per million (ppm)

Method Detection Limit for Gasoline in Soil: 1 mg/kg Method Detection Limit for Gasoline in Water: 0.1 mg/L

QAQC Summar::

Daily Standard run at 2mg/L: RPD Gasoline = 10% MS/MSD Average Recovery = 95%: Duplicate RPD = 5%

Edward R. Morales

1385 FAIRFAX St., Ste. D. · SAN FRANCISCO, CA 94124 · PHONE (415) 647-2081

CERTIFICATE OF ANALYSIS

LABORATORY NO.: 80513 CLIENT: Alton Geoscience CLIENT JOB NO.: 30-081

DATE RECEIVED: 02/02/90 DATE REPORTED: 02/09/90

ANALYSIS FOR TOTAL PETROLEUM HYDROCARBONS by Modified EPA SW-846 Method 5030 and 8015

LAB #	Sample Identification	Concentration (mg/L) Gasoline Range
4	mt. A	ND<0.1
Ţ	TW-4	240
2	TW-5	
3	TW-6	20
4	TW-7	ND<0.1
5	TW-8	ND<0.1
_	TW-9	41
6	•	
7	TW-10	50

mg/L - parts per million (ppm)

Method Detection Limit for Gasoline in Soil: 0.5 mg/kg Method Detection Limit for Gasoline in Water: 0.1 mg/L

#### QAQC Summary:

Daily Standard run at 2mg/L: RPD Gasoline = 5 MS/MSD Average Recovery = 105%: Duplicate RPD = 2

Edward R. Morales

	ALTON G	EOSCIENCE	CHAIN	of CUS	TODY	DATE: 1/29/90 DUE BY: 2/6/90 LABORATORY: Superior						
	1170 BURNETT A	VE., STE. S 4520, (415) 682-1582		PAGE	l of	1	LA	BORAT	ORY:	<del> 1</del>		
PROJECT	NUMBER (MANA	CED: 30-081 SAM	PLERS SIGNATI	JRE: Willia	<u>ئے</u> گھ. ر	Shipp -		SERE /	ANALYSI		ER ANA	LYSIS
PROJECT	NAME / ADDRES	M. Hopwood S: BP 35th Ave. O	akland				~ (0			Ę X		
REMARK	S OR SPECIAL INS	STRUCTIONS:					ABER			187		1 1
[							NOT			Gas /		
İ							TYPE & NUMBER OF CONTAINERS					
ł							} ხ			t os		
SAMPLE	SAMPLE	LOCATION		SAMPLE	SAMPL GRAB	E TYPE: COMP.				TPH	Ì	
NUMBER	DATE/TIME	DESCRIPTION		MATRIX	GRAB	COMF.	tla 1	1-				
MW-2	1/26/90	MW-2		Wate	<del>                                     </del>	ļ	3×40 ml					_
mw-3		mw-3					3 x 40 ml			X		
		1w-1					3 × 40 ml	1		X		
Tw-1		100-1			H	1	20.00			×		7
toot		TWA									_	$\exists$
Tw-3	<b>V</b>	1W-3			₩	<b></b>	3 x 40 ml		-	X		
					<u> </u>							
					1			1				
						<del> </del>			╂╼═╂═			
		,			<del>- </del>		ļ			<del></del>		
					ļ	<u> </u>		-		_		
						<u> </u>						
		11101	USIVE DATES/1	CHAIN OF		ATURE				INCLUSI	VE DAT	ES/TIMES
SIGNAT	TURE / //	INCL	/90 3:	30 pm	4	110116			<u> </u>			
1. WW	/ / / / / / / / / / / / / / / / / / /	1/	100 to	<del></del>								
2. 11 fs	ranch Sa	100	<u> </u>	n le	3	· ·			<del>-</del> '			

PROJECT REMARK	1170 BURNETT AV CONCORD, CA. 94 NUMBER / MANAC NAME / ADDRESS S OR SPECIAL INS	TRUCTIONS:	PLERS SIGNA	PAGE TURE:	01		LAE	SOIL ANA	LYSIS	WATER		
SAMPLE	he Week	LOCATION/		SAMPLE MATRIX	SAMPL	E TYPE:	TYPE & NUMBER OF CONTAINERS			10H & m/BLEX		
NUMBER	DATE/TIME	DESCRIPTION		Water	1 K	00	3 VOA :	5		X		
76-4 76-5				$\overline{}$						$ \mathcal{X} $		
TW-6				<del></del>						X		
TW-7										x		
TW-8					1/_					K		
TU-9					.   (					ス		
TW-10	4			7	12		2 Vox's			X		
												<u> </u>
												-
SIGNA 1 . S.C. 2. S.C.	SURE Ser yorm		الله الله الله الله الله الله الله الله	CHAIN OF STIMES  2/2		Y ATURE			IN	CLUSIVE	DATES/ 2:	TIMES 25 fr

## APPENDIX B General Field Procedures and Boring Logs

## GENERAL FIELD PROCEDURES

A description of general field procedures conducted during drilling activities is presented below.

## Drilling and Soil Sampling

Soil borings/monitoring wells were drilled utilizing 10-inch-diameter, continuous-flight, hollow-stem augers. To avoid cross-contamination, the augers were steam-cleaned prior to drilling each boring.

Soil samples were obtained for soil description, field, and laboratory analysis. Soil samples collected at 5-foot intervals were retrieved ahead of the lead auger utilizing an 18-inch-long by 2-inch-diameter, split spoon sampler lined with 1.5-inch-diameter, stainless steel sample tube inserts. The sampler and sample tubes were washed with a sodium tripolyphosphate solution and rinsed before each sampling event. The sampler was driven by a 30-inch free fall of a 140-pound hammer. Blow counts were recorded for three successive 6-inch intervals.

Upon retrieval from the sampler, the sample tubes were removed and securely sealed with Teflon sheeting and polyurethane caps. The samples were labeled with sample identification, sample depth, geologist's initials, and date of collection. The soil samples were kept on ice prior to and during transport to a state-certified laboratory.

The soil recovered was described in accordance with the Unified Soil Classification System. For each soil type, field estimates of density/consistency, moisture, color, grading, and soil type were recorded on the boring logs.

## Monitoring Well Installation and Construction Details

Included in this appendix are monitoring well installation and construction details for monitoring wells installed as part of this study.

Monitoring wells were constructed of 4-inch-diameter, flush-threaded, Schedule 40 PVC blank and screened (0.020-inch slot size) casing. The annular space surrounding the screened portion was backfilled with No. 3 Monterey sand (filter pack) to approximately 2 feet above the top of the screened section. A 1-foot-thick bentonite annular seal was placed above the filter pack and the remaining annulus was grouted

with neat cement to the surface. Utility boxes were installed slightly above grade to minimize infiltration of surface waters. Locking, watertight well caps were installed to ensure the integrity of the well.

LC		)FE		SCIENCE, LORATOR				PROJECT NO. 30-081 DATE DRILLED 1/29/90 CLIENT BP OIL COMPANY LOCATION 3201 35TH AVENUE, OAKLAND, CA LOGGED BY M. TAYLOR APPROVED BY	BORING NO.  WELL NO.  MW-4			
FIEL	D ŞK	ETCI	H OF	BORING LOC	ATION	_		EGGGED DT WE TATED IT AT THOSE DT	141244			
	,							DRILLING METHOD HOLLOW-STEM AUGER HOLE DI	AM. 8"			
								SAMPLER TYPE MODIFIED SPLIT SPOON  CASING DATA SEE MONITORING WELL CONSTRUCTION	ON DETAIL			
TOP	TOP OF CASING ELEVATION 170.34							DRILLER WEST HAZMAT	<del></del>			
<u> </u>		Τ	l	Ω.			W	ATER LEVEL 26,87				
BLOWS PER FOOT(IN)	CGLIPPIM	Щ	DEPTH	WELL CONSTRUCTI ORBORING CLOSURE		PROFILE	DA	TE July 9, 1990				
BLOWS P FOOT(N)		SAMPLE	8	LE XSTE	SOEN	Ê.	TII	ME	<u> </u>			
B 11		Š	ļ		===	-		DESCRIPTION				
` `			-0	Christy Box			Α	SPHALT				
			- 2	Portland								
			[	Cement								
		<b>L</b>	-		CL			LTY CLAY; greenish brown; damp, high asticity stiff				
3,4,6	3 0		-6	Bentonite (			Pi	Sicily Stat				
			-8	Pellets								
			<b>-</b>	2" sch.	∭ c∟		S	ILTY CLAY; gravelly, greenish brown with rust				
10,2 35	8,	$\mathbf{H}$	<del>-</del> 10	40 PVC Casing			st	ain residue, dry to damp, low to medium				
	*		12				pl	plasticity, hard				
			<b> </b>									
		<b> </b> _	14		a			ILTY CLAY; gravelly, brown, dry to damp, low to				
10,11 28	7. 0	止	16	2"			m	edium plasticity hard				
	-	1	18	sch. 40 PVC								
			ŀ	.020	a			SILTY CLAY; gravelly, brown rust				
14,2	8, o	十	20	Slot				esidue, dry to damp, low plasticity, hard				
35		+	22				4	naouony, naiv				
			ŀ									
·		Ļ	<u> </u> 24	Sand #3 🔆 Lonestar 🔆	a	-		ILTY CLAY; gravelly, brown, moist				
7,15	·   0	Щ	- 26					nedium plasticity, hard .				
			- 28				Ž	<del>-</del>				
			-									
11, 1	7. O	П	30				c	Oll TV Ot 43/2 come granully haven used readiling placeholis				
25							ð	SILTY CLAY; very gravelly, brown wet, medium plasticity				
	١		+	1 100								
			- 34	'								

ALTON GEOSCIENCE, In LOG OF EXPLORATORY BORING	<u>&amp;</u>		PROJECT NO30-081 DATE DRILLED_1/29/90 CLIENTBP OIL COMPANY LOCATION _3201 _35TH AVENUE, OAKLAND, CA LOGGED BY APPROVED BY	BORING NO. WELL NO. MW-4
TOP OF CASING ELEVATION			DRILLING METHOD HOLLOW-STEM AUGER HOLE DISAMPLER TYPE MODIFIED SPLIT SPOON  CASING DATA SEE MONITORING WELL CONSTRUCTION  DRILLER WEST HAZMAT	,
## BANSOTS  ## BAN	soen CL	PROFILE	MATE IME  DESCRIPTION  SILTY CLAY; gravelly, brown, dry to damp  SILTY CLAY; gravelly, brown, moist, medium plasticity	

	O	FE		SCIENC LORATO		c.		PROJECT NO. 30-081 DATE DRILLED 2/1/90 CLIENT BP OIL COMPANY LOCATION 3201 35TH AVENUE, OAKLAND, CA LOGGED BY M. TAYLOR APPROVED BY	BORING NO.  WELL NO.  MW-5
FIELD	SKE	TCH	OF	BORING LO	OCATIO	ON			
								DRILLING METHOD HOLLOW-STEM AUGER HOLE DI	AM8"
								SAMPLER TYPE MODIFIED SPLIT SPOON CASING DATA SEE MONITORING WELL CONSTRUCTE	N DETAIL
TOP OF CASING ELEVATION 165.14								DRILLER WEST HAZMAT	TO DETAIL
T	· 	1		天		_		WATER LEVEL 24.75	
BLOWS PER FOOT(N)	≨		ᡓ	WELL CONSTRUCTION ORBORING			_	DATE July 9, 1990	
BLOWS P FOOT(N)	CGI (PPM)	룉	E T	, E. S.	<u> </u>	υį	PROFILE	TIME	
頖 쟟	ទ	SAMPLE	_[	E SE	Ę	soen	▎≝┝╴	DESCRIPTION	
			- 0	Christy Bo	X	_	=		
			-				<i>////</i> //	ASPHALT	
13,23, 35	0			Portland Cement Bentonite Pellets	Binnin Beece	CL.		SANDY CLAY; gravelly, brown, damp, low plasticity hard	
11,25, 39	0		- - 10 - - 12 -	2" sch 40 PVC Casing		CL		SILTY CLAY; gravelly, greenish brown, damp, low plasticity, gas odor present hard	
8,11, 21	0		- 14 - - 16 - - 18	2" sch. 40		a		SILTY CLAY; gravelly, greenish brown, moist medium plasticity, gas odor hard	
8,23, 33	0		- - 20 - 22	.020 Slot		СL		SILTY CLAY; sandy and gravel, greenish brown, moist medium plasticity, gas odor hard	
4,7,13	0		- 24 - - 26 - - 28			СL		SILTY CLAY; gravelly, reddish brown, moist to saturated medium plasticity very stiff	
4,5,8	0		- 30 - - 32			СL		SILTY CLAY; with fine sand, tan, damp to medium high pl	asticity, stiff
14,17, 22	0	$\prod$	- - 34	End Cap		CL.		SILTY CLAY; gravelly, reddish brown moist high plasticity	, hard

.

	O E	FE		SCIENC LORATO	-			PROJECT NO. 30-081 DATE DRILLED 2/1/90 CLIENT BP OIL COMPANY LOCATION 3201 35TH AVENUE, OAKLAND, CA	BORING NO. WELL NO.
						/ 35	3	LOGGED BY M. TAYLOR APPROVED BY	MW-6
FIELD	SKE	TCH	- 1 OF	BORING L	OCATION			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	11111
							ŀ	DRILLING METHOD HOLLOW-STEM AUGER HOLE DIA	A4 8*
								SAMPLER TYPE MODIFIED SPLIT SPOON	NW
,								CASING DATA SEE MONITORING WELL CONSTRUCTION	N DETAIL
TOP O	FC	ASIN	IG E	LEVATION	165.38		- 1	DRILLER WEST HAZMAT	
		···········		, ,					
<u>.</u>				<b>.</b>			WA	TER LEVEL 24.75	
BLOWS PER ROOT(N)	cai (PPM)	삘	DE PTH	WELL CONSTRUCT ORBORING	띭	PROFILE	DA	TE July 9, 1990	
BLOWS P FOOT(N)	3	SAMPLE	씸	JE 56	SOON INSQ1	Ě	TIM		
<b>a</b> a.	ၓ	'S						DESCRIPTION	
			-0	Christy Bo	ox			ODUALT	
			۱ ۲	Portland			A;	SPHALT	
			-2	Cement					
			-4	:	G.		Q!	ILTY CLAY; gravelly, redish brown, damp, high	
10,12,	0		-					asticity, very stiff	
15		П	-6	Bentonite Pellets			•	• •	
			-8	011010	開岡				
8,15,			-		∭ (∦ C+			SILTY CLAY; gravelly, reddish brown moist, high	
23	0	П	- 10	2" sch.	MM		p	lasticity, hard	
			- 12	40 PVC					
		ŀ	<b>-</b>	Casing					
5,12,	'		- 14		∭дн			ILTY CLAY; gravelly, brown, moist medium high	
18	0	П	- - 16	2"			pl	lasticity, very stiff	
		H	-	sch. 40					
			- 18	PVC .020			_		
		Щ	- - 20		o-			ILTY CLAY; gravelly, brown, moist to aturated very stiff	
11,15, 15	0		-				0	alurated very Still	
'			- 22						
			- 24	Sand #3				_	
20.00		Щ	- 24	Lonestar			Z		
23-30, 50/4"	0	Ш	- 26				N	O RECOVERY; large cobble or rock obstruction	
		\	- 00				ł		
			- 28 -						
6,13,17	٨	╟╫	- 30					10 0000	
0,13,17		Щ	-				1	NO RECOVERY; same	
			- 32 -				_ d	rilled to 35' w/o sample recovery	
21,29, 35	0		- 34	End Cap	a la	-		ILTY CLAY; gravelly saturated moist, brown, hard	
<u> </u>	Ц			<u> </u>		VIII			<del></del>

ALTON GEOSCIENCE, Inc. LOG OF EXPLORATORY BORING						PROJECT NO. 30-081 DATE DRILLED 2/1/9  CLIENT BP OIL COMPANY  LOCATION 3201 35TH AVENUE, OAKLAND, CA  LOGGED BY M. TAYLOR APPROVED BY  MW-7
FIELD	SKE	TC	l OF	BORING LOCATION		
				· ·		DRILLING METHOD HOLLOW-STEM AUGER HOLE DIAM. 8"
						SAMPLER TYPE MODIFIED SPLIT CASING DATA SEE MONITORING WELL CONSTRUCTION DETAIL
торо	FC	ASII	NG E	LEVATION <u>167.61</u>	_	DRILLER WEST HAZMAT
_				Σ Q		WATER LEVEL 27.29
BLOWS PER FOOT(N)	cai (PPM)	Щ	돈	WELL CONSTRUCTION ORBORING CLOGURE USCS	┃≝┃	DATE JULY 9, 1990
BLOWS R	a) (E	SAMPLE	씸	WELL CONSTE CHBOF CLOGUI	PROFILE	
□ K	ŏ	ŝ		#869 =		DESCRIPTION
			- 0	Christy Box		ASPHALT
14,14,	0		- 2 - 4 - 6	Portland Cement CH Bentonite		SILTY CLAY; brown, damp, high plasticity, very stiff
15 11,27, 39	0		- 8 - - 10 -	2" sch		SILTY CLAY; gravelly, reddish brown damp medium plasticity, hard
15,21, 29	0	I	-	2" sch. 40		SILTY CLAY; gravelly, reddish brown, damp, hard
36,15, 50/5*	0		- 18 - - 20 - - 22	020 Slot CL		SILTY CLAY; gravelly, brown, moist medium plasticity, hard
8,15,21	0	I	- 24 - 26 - 28			SILTY CLAY; gravelly, brown, moist medium plasticity, hard
5,8,12	0		30	a		SILTY CLAY; gravelly, brown, saturated medium plasticity, very stiff
4,7,10	0	I	-34	a a	- 6	SILTY CLAY; tannish brown, moist high plasticity, very stiff

ALTON GEOSCIENCE, Inc. LOG OF EXPLORATORY BORING							<b>3</b>	PROJECT NO. 30-081 DATE DRILLED 1/29/90 CLIENT BP OIL COMPANY LOCATION 3201 35TH AVENUE, OAKLAND, CA LOGGED BY M. TAYLOR APPROVED BY	BORING NO.  WELL NO.  RW-1			
FIELD	SKE	TC	1 OF	BORING LOCA	ATIO	N		LOGGED BY M. TATLON APPROVED BY	/ / / / / / / / / / / / / / / / / / /			
,								DRILLING METHOD HOLLOW-STEM AUGER HOLE DI	AM. 12"			
								SAMPLER TYPE SEE MONITORING WELL CONSTRUCTION	ON DETAIL			
тор с	F C	ASII	NG E	LEVATION _1	68.0	1		DRILLER WEST HAZMAT				
Œ				N.	•		W	ATER LEVEL 27.93				
BLOWG PER Poot(N)	CGI (PPM)	Щ	DEPTH	WELL CONSTRUCT! ORBORING CLOSURE		SCS PROFILE	D	ATE July 9, 1990				
BLOWS P FOOT(N)	GIE	SAMPLE	ద	PL ANST ABOF OSU		36 B	T	ME DESCRIPTION				
	٥	S					ļ	DESCRIPTION				
			0	Christy Box	- 88	700		ASPHALT				
			2	Portland			s	ILTY CLAY; gravels, brown, damp, backfill				
			4	Cement		🕖						
		_	7		<b>S</b>	¤ 🎆	2	ILTY CLAY; gravelly, greenish brown, dry to damp, low pla resent	isticity, odor			
9,19,	0		- 6	Bentonite #	<u>\$</u>							
33			-8	Pellets 5	338 REE							
			١.,					SILTY CLAY; gravelly, greenish brown, dry to damp, medium plasticity, odor present				
16,33,	0		- 10 -	l ∭.			<b>1</b> 0	oor present				
40			- 12	6" sch 40 PVC	-[]		4					
			- - 14	Casing	M.	~ <i>[[]</i>						
15,36,		_	[ '"		<b>"</b>	CL 🥢	8	SILTY CLAY; gravelly, brown, damp, medium odor preser	it			
43	0	$\coprod$	- 16	10 101	×							
"			- 18	sch. 40								
			F	.020		a. 🏻		SILTY CLAY; gravelly, brown, damp, medium plasticity, od	or			
.11,16, 25	0	П	- 20	Slot			ا (	present				
25		┸	- 22									
	Į		21	Sand #3				•				
6,7,	0	-	╁	Lonestar 🔀		a 🛭		ILTY CLAY; sandy gravelly, greenish brown, medium				
16	١	$\mu$	- 26				M.,	lasticity				
			28				Ī	<del>L.</del>				
			<u>ا</u>									
6,13, 17	0	П	30			a 🏽	SI	LTY CLAY; gravelly, sandy (fine) brown, saturated very st	itt			
		Γ	- 32									
			34	.								
<u> </u>		<u></u>					<u> </u>					

ALTON GEOSCIENCE, Inc. LOG OF EXPLORATORY BORING						<u>\</u>	PROJECT NO. 30-081 DATE DRILLED 1/29/90 CLIENT BP OIL COMPANY LOCATION 3201 35TH AVENUE, OAKLAND, CA LOGGED BY M. TAYLOR APPROVED BY	BORING NO.  WELL NO.  RW-1
FIELD	SKE	ТСН	OF E	BORING LOCATION			LOGGED BY MI. TATLON APPROVED BY	LAA.1
. ,							DRILLING METHOD HOLLOW-STEM AUGER HOLE DIA SAMPLER TYPE MODIFIED SPLIT SPOON	4M10"
							CASING DATA SEE MONITORING WELL CONSTRUCTED	N DETAIL
TOP C	OF C	ASIN	G EL	EVATION	•		DRILLER WEST HAZMAT	<del> </del>
55		Ì		Z. O.		W	ATER LEVEL	
BLOWS PER FOOT(R)	PPM	띶	DE PTH	E SIER TO SE	PROFILE	]	ATE	
BLOWS PR FOOT(R)	CGI (PPM)	SAMPLE	22	#ELL CONSTRUCTION ORBØRING CLØSURE USCS	Ě		ME DESCRIPTION	
6, 16, 29	0		36	2" sch. 40 PVC CL			LTY CLAY; gravelly, sandy (fine) brown, saturated, edium high plasticity, hard	
			· 38	.020 Slot		s.	AME	
6, 15, 28			- 40 -	End Cap	<u> </u>	4		
			.	2.10 04				
			-					
			-					
1			_					
			<u> </u>					
			-					
			-					
			-					
			-					
			-					
			-  -					
			-					
			-					
			- -					
			- -					
L								

## **APPENDIX C**

Well Development and Ground Water Sampling and Field Survey Forms

#### WELL DEVELOPMENT AND WATER SAMPLING PROCEDURES

All purging and ground water sampling equipment was cleaned prior to use to minimize cross-contamination between wells. All equipment in contact with ground water was triple-rinsed prior to each sampling event in successive baths consisting of tripolyphosphate solution, tap water, and deionized water. Prior to sampling, the well was developed and purged in accordance with EPA protocol. During purging, pH, temperature, and conductivity were measured periodically until these parameters stabilized, indicating formation water had entered the well casing. The purged water was pumped into 55-gallon D.O.T.-approved drums prior to disposal or recycling at an appropriate waste disposal facility.

Ground water samples were collected by lowering a 4-inch-diameter, bottom-fill, Teflon bailer just below the water level in the well. The samples were carefully transferred from the check-valve-equipped Teflon bailer to zero-headspace 1-liter and 40-milliliter glass containers fitted with Teflon-sealed caps. All samples were inverted to ensure that entrapped air was not present. Each sample was labeled with sample number, well number, sample date, and engineer's/geologist's initials. The samples remained on ice prior to laboratory analysis.

DAIL	Y FIELD REPORT	
100111117	PROJECT NO.: 30 - 08/	DATE: 7.9.70
JOB NAME:	WEATHER: Sunn -1	DAY: / / (0)
LOCATION: 35th Are Dalclard	FOREMAN:	
CONTRACTOR:	INSPECTION TESTING OF	
FIELD TECHNICIAN: Walls + Adlcins,		
SUMMARY OF OPERATIONS:		
		/
9:30-10:50 loade	I truck, started po	apel walk
	1	
11:30 - 12:00 trav	4	
13:00 Hillist St	te.	
take Di	w and Product +1	rickness
1.0 111	issells.	
is close a	of sample MN-4	1,5,637,
Dilibre and	Sample MW-3	
· 6ail 2.10"	bree product from	MW-2
1 ~,25	11 17	MW-1
NO /124 01	induct in RW-1	
measure	locations of well	5
	all wells from E	(1) #2576
Clear Up	s.t.	
Mote: the	ue are 36 baise	ls on site
· incl		<u> </u>
, , , , , , , , , , , , , , , , , , , ,	unload tivele	
1/20 00 1001E	02222	
11:00 go nonte		ALTON CECCCIE
		ALTON GEOSCIE 1170 Burnett Ave., Ste.



ļ

	(+)	4.89	(-)				
STA.	B.S.	H.I.	F.S.	ELEV.	4,89	•	
BANGH	464	10464		170,93			Green
406	499	, !		1	I	17047	HO EL
Beach	4.84	145,34		Jegga 222 i		, , ,	148 29.4.25=148
TP-1	5.37	174.96	5.17	169,59		/	193 CN 4 (2) = 193
mu-7 mu-2	1-3:37	174.75	7,55 6,6]	(167.61)		, .	147,90
WM-F		74.75	7.00 reist	169.75		4	
Ru-L		74.75	6 74	16801	4 -01		148:21
		134.25	4.32	190.35	<del></del>	, 3	198,11
42-5-	!	25.5	4.90	167.85	,	· ·	149.06
_المراكب المراكب	9.66	172,5-1	-5-3-L-:	-1.7.1P			, , , , , ,
1111 6	!	132.5	3 11	165-4	<b>)</b>	~	14717
J2-2-		13-1-1-	72773	167.11			, , ,
		171.86	-2.32	1	•	. /	148,20.
W71:2	L=====================================	172.59	-	(165)			
70.3	17.75	1-728-57-1	4.95	1-16-5-19-1		_	1-17.91
	1-8-18	772.27	-4-64	1752257			
r = z	1-21-5	35.33	2.84	75.36		2	148,00
<u> </u>		75 12	502	1.2.75		K L	, , ,
<b>∆</b> . N - L	!		7 : 4	12.32	; !		
1717-5	!	1	11/15	16812	;		
SIN	1		1.28	167.99			
7.6-5	6.70	_13476d <sup>-</sup>			( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( )		
-7			1-4.35	1-135-27-1	1161		
_13:1:1 <del>Z</del> _	!	1-55-7-5-1	1-3-08	1-26-1-61-1	1		
	1-7/0X	1-1-17-5-1-1	- <del> </del>	احرر-بربر-۱۰			. 1
	!	!!	1-7:0-1	15-4-8-5-1	1		
<u>-</u>	2 3 1	・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・	'Чах	· . ~ . U/ '		^ - ^	Y (-00

## 1170 Burnett Ave., Ste. S Concord, CA 94520

JOB NUMBER 30-081	TECHNICIAN 1996
JOB LOCATION SCHOOL DOCCO.	DATE_719190

JOB LOC	ATION			_ DATE				
PUMPOUT	DATE	OF LAST PU	APOUT:	WEATHER:				
☐ YES ☐ NO		```		TIME:		COMMENTS		
	HOLD	сит	LEVEL			(Notes, conditions, etc.)		
WELL#	DEPTH TO WATER	DEPTH TO PRODUCT	PROD. THICKNESS	TOTAL DEPTH	DEPTH TO PUMP			
11-11-4	21.30			5 /				
15-17	10							
c.n-1	21.46	-	.25	34.10		·		
(N-1	19,99			38.5				
KIL	20,24		.10"	34.47				
MW-S	17.97			30.50				
11.6	= 0			32 9				
3	17. 2			\$ <b>5</b> , <b>5</b> ,				
						,		
				<u> </u>				
				<u> </u>	•			
						:		
				<u> </u>	<u> </u>	<u> </u>		
					<u> </u>			
					<u> </u>			
						*		
		4.			<u> </u>			
	1							

DR 25th Nice Date: 719102
Project   30-081 Site: BP, 35th Ave Date: 7/9/90
Well: MW.   Sampling Team: Watts + ADICINS
Well Development Method: Pomp
Sampling Method: <u>bailer</u>
Describe Equipment Before Sampling This Well: Triple Pinse
Well Development/ Well Sampling Data
Total Well Depth: 34.10 feet Time: Water level Before Pumping: 21.44
Water Casing Diameter Volume Factor to Purge
13.34 feet x 0.16 0.65 $2.13$ $4$ $9.5$
Depth Purging From: feet. Time Purging Begins:
Notes on Initial Discharge:
Time Volume pH Conductivity I Notes
Time Field Parameter Measurement Begins:
Rep #1 Rep #2 Rep #4
Conductivity Temperature (F)
Presample Collection Gallons Purged:
Time Sample Collection Begins:
Time Sample Collection Ends:
Total Gallons Purged:
Comments: FAFE PRODUCT

Project   30-081 Site: RP, 35th Ave Date: 7/9/90
Well: MU.Z Sampling Team: Watts + ADICINS
Well Development Method: Pomp
Sampling Method: <u>bailer</u>
Describe Equipment Before Sampling This Well: Triple Pinse
Well Development/ Well Sampling Data
Total Well Depth: 3 4 40 feet Time: Water level Before Pumping: 20.2 4
Water Casing Diameter Volume  Column 2-inch 4-inch Volume Factor to Purge
feet x 0.16 0.65
Depth Purging From: feet. Time Purging Begins:
Notes on Initial Discharge:
Time Yolume pH Conductivity T Notes
Time Field Parameter Measurement Begins:
Rep #1 Rep #2 Rep #3 Rep #4
Conductivity Temperature (F)
Presample Collection Gallons Purged:
Time Sample Collection Begins:
Time Sample Collection Ends:
Total Gallons Purged:
Comments: FREE FRODUCT

- Al								
Project # 30-081 Site: RP, 35 th Ave Date: 7/9/90								
Well: MWS Sampling Team: Watts + ADICINS								
Well Development Method: Pomp								
Sampling Method: bailer								
Describe Equipment Before Sampling This Well: Triple Pins								
Well Development/ Well Sampling Data								
Total Well Depth: 3/5 feet Time: Water level Before Pumping: 19/96								
Water Casing Diameter Volume Column 2-inch 4-inch Volume Factor to Purge								
155 feet x 0.16 0.65 2.65 1015								
Depth Purging From: feet. Time Purging Begins:								
Notes on Initial Discharge:								
Time Volume pH Conductivity T Notes  4:40 5 851 4.49 5.41 Brown Cloudy								
4.45 7 8.38 3.59								
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$								
Time Field Parameter Measurement Begins:								
Rep #1 Rep #2 Rep #3 Rep #4								
Conductivity Temperature (F)								
Presample Collection Gallons Purged:								
Time Sample Collection Begins:								
Time Sample Collection Ends:								
Total Gallons Purged:								
Comments:								

Project   30-081 Site: RP, 35th AVC Date: 7/9/90
Well: Mile 34 Sampling Team: Watts + ADICINS
Well Development Method: Pomp
Sampling Method: <u>bailer</u>
Describe Equipment Before Sampling This Well: Triple Pinse
Well Development/ Well Sampling Data  2). 30  Water level
Depth: 4.5 feet Time: Before Pumping: 11.10
Column 2-inch 4-inch Volume Factor to Purge
14.10 feet x 0.16 0.65 2.36
Depth Purging From: feet. Time Purging Begins: Notes on Initial Discharge:
Time Volume of Conductivity T Notes  10 7.33 4.32 80.2 hispania
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$
Time Field Parameter Measurement Begins:  Rep #3 Rep #4
PH Conductivity Temperature (F)  Rep 11  Rep 12  Rep 13  Rep 14  Rep 14
Presample Collection Gallons Purged:
Time Sample Collection Begins:
Time Sample Collection Ends:
Total Gallons Purged:
Comments:

Project   30-081	Site: Ri	P. 35-th HV	ン Date:	7-19	190	
Well: <u>MW-5</u>	Sampling	Team: (w) a	Hs + A	DICIN	2	
Well Development						
Sampling Method:		•				
Describe Equipmen						
Well Development/ Well :	Sampling Data					
Total Well Depth: 300 Ofeet	Time:		Water 1 Before E	Level Pumping	1:17,97	
Column 2:	asing Diame -inch 4-in	ich Volume	<u>Faci</u>	or	Volume to Purge	
12,53 feet x 0	.16 0.6	7.0			<u> </u>	•
Depth Purging Fr			e Purging	Begin	s:	
Notes on Initial	Discharge	•				
Time Volume	рН Сол	nductivity	I	Not در کار درد	<u>es</u>	. 2
9:20 12	7.78	4.77	5.50 55.4	15 ro-58		ا ماه
$\frac{\frac{\pi^2}{155^2}}{\frac{15}{15}}$	<u> </u>	472	55,6 55,7	-11	,	
9:32 /7	7.47	4.73	55.9	/•		<b>u.</b>
Time Field Param	neter Measu	rement Begi				
	Rep 11	Rep #2	Reg	<u> </u>	Rep #4	***
pH Conductivity Temperature (F)						
Presample Colle	ction Gallo	ons Purged:			÷.	
Time Sample Col				<del></del>		
Time Sample Col				<del></del> ·	1	
Total Gallons P						
Comments:						-



Project   30-081 Site: RP, 35th AVC Date: 7/9/90
Well: My 6 Sampling Team: Watts + ADICINS
Well Development Method: Pomp
Sampling Method: bailer
Describe Equipment Before Sampling'This Well: Triple Piase
Well Development/ Well Sampling Data
Total Well Depth: 34 feet Time: Before Pumping: 1,20
Water Casing Diameter Volume Column 2-inch 4-inch Volume Factor to Purge
16.80 feet x 0.16 0.65 2.68
Depth Purging From:feet. Time Purging Begins:
Notes on Initial Discharge:
Time Volume pH Conductivity T Notes
4:05 10 867 183 16.3 BRN, TURBID  15 81,22 1.81 59.6 11  20 4.35 2.05 63.10
5:15 25 8.28 7.83 57.6 27 7.50 7.83 57.6 Time Field Parameter Measurement Begins:
Rep 11 Rep 12 Rep 13 Rep 14
PH Conductivity Temperature (F)
Presample*Collection Gallons Purged:
Time Sample Collection Begins:
Time Sample Collection Ends:
Total Gallons Purged:
Comments:

# ALTON GEOSCIENCE, INC. Well Development and Water Sampling Field Survey

Project # 30-081 Site: BP, 35th Ave Date: 7/9/90
Well: MW. 47 Sampling Team: Watts + ADICINS
Well Development Method: Pomp
Sampling Method: bailer
Describe Equipment Before Sampling This Well: Triple Riose
Well Development/ Well Sampling Data
Total Well 34.50  Depth: Feet Time: Before Pumping: 2004.
Water Casing Diameter Volume  Column 2-inch 4-inch Volume Factor to Purge
17.7 feet x 0.16 0.65 2.43 23.6
Depth Purging From: feet. Time Purging Begins:
Notes on Initial Discharge:
Time Volume pH Conductivity T Notes  6:65 $\frac{6.05}{5.05}$ $\frac{7.76}{2.0.33}$ $\frac{6.14}{4.79}$ $\frac{51.2}{50.4}$ $8000000000000000000000000000000000000$
Time Field Parameter Measurement Begins:
Rep #1 Rep #2 Rep #3 Rep #4
Conductivity Temperature (F)
Presample Collection Gallons Purged:
Time Sample Collection Begins:
Time Sample Collection Ends:
Total Gallons Purged:
Comments:

# APPENDIX D Permits



### ALAMEDA COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT

5997 PARKSIDE DRIVE

Pattle A Tay Date 5/3/90

PLEASANTON, CALIFORNIA 94566

(415) 484-2600

### GROUNDWATER PROTECTION ORDINANCE PERMIT APPLICATION

FOR APPLICANT TO COMPLETE	FOR OFFICE USE
1) LOCATION OF PROJECT 3201 3574 ST OAKIAND CA	PERMIT NUMBER 90276  LOCATION NUMBER
2) CLIENT  Name BP OIL; DATICLE Jacob Sen  Address 2868 Prospect Park or Phone 916 631 6918  City Rancho Co-dova Zip 95670-6020	PERMIT CONDITIONS  Circled Permit Requirements Apply
Address 1000 Burnett Ave Phone 415 682 158 L City Concord CA Zip 94520	A. GENERAL  1. A permit application should be submitted so as to arrive at the Zone 7 office five days prior to proposed starting date.  2. Submit to Zone 7 within 60 days after completion
(4) DESCRIPTION OF PROJECT Water Well Construction Seneral Well Destruction Contamination	of permitted work the original Department of Water Resources Water Well Drillers Report or equivalent for well projects, or drilling logs and location sketch for geotechnical projects.  3. Permit is void if project not begun within 90
(5) PROPOSED WATER WELL USE  Domestic Industrial Irrigation  Municipal Monitoring Other	days of approval date.  (B.) WATER WELLS, INCLUDING PIEZOMETERS  1. Minimum surface seal thickness is two inches of cement grout placed by tremie.
(6) PROPOSED CONSTRUCTION Drilling Method: Mud Rotary Air Rotary Auger X Cable Other  DRILLER'S LICENSE NO. C57-554979  WELL PROJECTS Drill Hole Diameter 8 in. Maximum Casing Diameter 4 in. Depth ft. Surface Seal Depth ft. Number 3	<ol> <li>Minimum seal depth is 50 feet for municipal and industrial wells or 20 feet for domestic, irrigation, and monitoring wells unless a lesser depth is specially approved.</li> <li>GEOTECHNICAL. Backfill bore hole with compacted cuttings or heavy bentonite and upper two feet with compacted material. In areas of known or suspected contamination, tremied cement grout shall be used in place of compacted cuttings.</li> <li>CATHODIC. Fill hole above anode zone with concrete placed by tremie.</li> </ol>
GEOTECHNICAL PROJECTS  Number of Borings Maximum  Hole Diameter in. Depth ft.	E. WELL DESTRUCTION. See attached.
(7) ESTIMATED STARTING DATE 5/16 ESTIMATED COMPLETION DATE 5/17	MG M
(8) I hereby agree to comply with all requirements of this permit and Alameda County Ordinance No. 73-68.	Wyman Hong

## OR OTHER WORK AS SPECIFIED

☐ Agent for

Contractor

Owner

BP OIL COMPANY

BP OIL BACILITY \$11132

BETWEEN 35th Ave. AND Siter

2868 PROSPRCT PARK DR., SUITE 360 RANCHO CORDOVA, CA 95670

8201 35th Avenue

(street or address)

(street) (street)

**EXCV** SUBTL 105,00

CITY INSPECTOR'S REPORT

CHECK

LITILITY COMPANY REPORT

BACKFILL

Sa.Ft \_\_\_\_\_

Backfill **Paving** Paving Insp. 105.00

**PAVING** 

	NATURE OF WORK: 1 monitoring well on Suter St.  APPLICANT: Alton Geoscience, Inc.	CONTRACT I hereby aff (commencing Professions
	ADDRESS: 1000 Burnett Ave., Suite 140	UCENSE . 5
	CITY: Concord STATE: CA ZIP 94520	
	PHONE: (415) 682-1582	
	I hereby affirm that I am exempt from the Contractor's License Law for the following reason 'Sec 7031.5, Business and Professions Code: Any city or county which requires a permit to construct, alter, improve, demolish, or repair any structure, prior to its issuance, also requires	Approximate
	the applicant for such permit to file a signed statement that he is licensed pursuant to the pro- visions of the Contractor's License Law Chapter 9 (commencing with Sec. 7000) of Division 3 of the Business and Professions Code, or that he is exempt therefrom and the basis for the	Approximate
	alleged exemption. Any violation of Section 7031.5 by any applicant for a permit subjects the applicant to a civil penalty of not more than \$500):	DATE STREET
œ	L.I.I. as owner of the property, or my employees with wages as their sale compensation, will do the work, and the structure is not intended or offered for sale (Sec. 7044, Business and	<b>/</b> 5
2	Professions Code: The Contractor's License Law does not apply to an owner of property who builds or improves thereon, and who does such work temself or through his own employees.	24-HOU
OWNER/BUILDER	provided that such improvements are not intended or offered for sale. If, however, the building or improvement is sold within one year of completion, the owner-builder will have the burden of proving that he did not build or improve for the purpose of sole).	PHONE
8	I, as owner of the property, am exempt from the sale requirements of the above due to:	Telephone 27 This Permit Vo
Z }	[1] I am improving my principal place of residence or appurtenances thereto, (2) the work will be performed prior to sale, (3) I have resided in the residence for the 12 months prior to completion of the work, and (4) I have not claimed exemption in this subdivision an more than two	THIS FEITHER VO
Ó	structures more than once during any three-year period. (Sec. 7044, Business and Professions Code).	e
	t, as owner of the property, am exclusively contracting with licensed contractors to con-	State law requiring days befo
	struct the project (Sec. 7044, Business and Professions Code: The Contractor's License Law does not apply to an owner of property who builds or improves thereon, and who contracts	valid unless op
	for such projects with a confractor(s) licensed pursuant to the Contractor's License Law).	ground Service
	I applicately under the second	Call Toll Free:
	1-aft 110 - 11/10	
_	Signeriture Dayé	<b></b>
	I hereby affine that I have a certificate of consent to self-insure, or a certificate of Workers' Compensation Insurance, or a certified copy thereof (Sec. 3800, Lab. C.).	This permit is: Municipal Co
ō	PowP89-469257-02 Company Premont Indemnity	This permit is sponsible for or arising out
Ā	Certified copy is hereby furnished.	maintenance.
ž	Certified copy is filed with the city building inspection department.	indemnify, so against any o
COMPENSATION	Signifier . Date	of any bodily tained or ari
	(This section need not be completed if the permit is for one humdred dollars (\$100) or less.)	consequence maintenance.
Ś	Exertify that in the performance of the work for which this permit is issued, I shall not employ any merson in any manner so as to become subject to the Workers' Compensation Laws of California	
· 179-	can person in any manner so as to become subject to the workers. Compensation Laws of Collisionia.  Collisionia  Supplication  Date	
:-		

11039-T 10 APPLICANT, If, after making this Certificate of Exemption, you should become 501, 1 to the Workers' Compensation provisions of the Labor Cade, you must forthwith

( ), with such provisions or this permit shall be deemed revoked.

Ŀ.	. North of 35th Avenue	
_	CONTRACTOR  I hereby affirm that I am licensed under provisions of Chapter 9 (commencing with Section 7000) of Division 3 of the Business and Professions Code, and my license is in full force and effect.	
	MOCIASS 554979 C57 CITY ASSAULTS 5966 18-17-9	
	Approximate Starting Date  Approximate Completion Date  DATE 5/16/90  5/19/90	Supervisor Completion Date
o- on on th	LIMITED OPERATION AREA YESNO	CIT
あずるな事	24-HOUR EMERGENCY PHONE NUMBER	Initials Hours Date
on oi iii	Telephone 273-3668 Forty-eight (48) HOURS BEFORE ACTUAL CONSTRUCTION. This Permit Void 90 Days From Issue.	Concrete Asphalt Sidewalk
ris Em	ATTENTION  State law requires that contractor/owner call Underground Service Alert two working days before excavating to have below-ground utilities located. This permit is not	Size of Cut: Sq. Ft
ri- rw :ts	valid unless applicant has secured an inquiry identification number issued by Under- ground Service Alert.	Paved by Bill No Charges
	Call Toll Free: 800-642-2444	
rs'	This permit issued pursuant to all provisions of Chapter 6, Article 2 of the Oakland Municipal Code.	APPROVED
_	This permit is granted upon the express condition that the permittee shall be re- sponsible for all claims and liabilities arising out of work performed under the permit or arising out of permittee's failure to perform the obligations with respect to street	Engineering Services
	maintenance. The permittee shall, and by acceptance of the permit agrees to defend, indemnify, save and hold harmless the City, its officers and employees, from and against any and all suits, claims or actions brought by any person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sus-	Field Services
;s.)	tained or arising in the construction of the work performed under the permit or in	Traffic Engineering

**Electrical Department** DIRECTOR OF PUBLIC WORKS APPROVED BY

Øм

-Signature

-OCATION: 3201 35th Avenue

BP OIL FACILITY \$11132

#### CITY OF OAKLAND

PERMIT TO EXCAVATE IN STREETS OR OTHER WORK AS SPECIFIED

CCTAVIL

Signature of Contractor Owner or Agent

A Contractor

Owner

☐ Agent for

X9000936

BP OIL COMPANYU 2868 PRPSPECT PARK DR., ... SUITE 360 RANCEO CORDOVA, CA 95670

	(street or address)			
	NATURE OF WORK: 1 monitoring well on Suter st.			
	APPLICANT: Alton Geoscience, Inc.	CC I h		
	ADDRESS: 1000 Burnett Ave., Suite 140	Pri UCE AND		
	CITY: Concord STATE: CA ZIP: 94520			
!	I hereby affirm that I am exempt from the Contractor's License Law for the following reason 'Sec 7031.5, Business and Professions Code: Any city or county which requires a permit to construct, other, improve, demolish, or repair any structure, prior to its issuance, also requires the applicant for such permit to file a signed statement that he is licensed pursuant to the pro-	Ap		
	visions of the Contractor's License Low Chapter 9 (commencing with Sec. 7000) of Division 3 of the Business and Professions Code, or that he is exempt therefrom and the basis for the alleged exemption. Any violation of Section 7031.5 by any applicant for a permit subjects the applicant to a civil penalty of not more than \$500):	LIA DA		
	LLI as owner of the property, or my employees with wages as their sole compensation, will do the work, and the structure is not intended or offered for sole (Sec. 7044, Business and Professions Code: The Contractor's License Law does not apply to an owner of property who builds or improves thereon, and who does such work trimself or through his own employees, provided that such improvements are not intended or offered for sale. If, however, the building or improvement is sold within one year of completion, the owner-builder will have the burden of proving that he did not build or improve for the purpose of sole).			
	It is so owner of the property, am exempt from the sale requirements of the above due to:  (1)) am improving my principal place of residence or appurenances thereto. (2) the work will be performed prior to sale. (3) I have resided in the residence for the 12 months prior to completion of the work, and (4) Thave not claimed exemption in this subdivision on more than two structures more than once during any three-year period. (Sec. 7044, Business and Professions Code)	Tel Thi		
	It, as owner of the property, am exclusively contracting with licensed contractors to construct the project (Sec. 7044, Business and Professions Code: The Contractor's License Law does not apply to an owner of property who builds or improves thereon, and who contracts for such projects with a contractor(s) licensed pursuant to the Contractor's License Law).	ing val gro		
	I am exempt under the second transfer of this imagen	Ca		
	Signature Date			
	thereby affirm that I have a certificate of consent to self-insure, or a certificate of Workers' Compensation Insurance, or a certified copy thereof (Sec. 3800, Lab. C.).	Th		
	Polype9-469257-02 Company Fremont Indemnity	Th sp		
	Certified copy is hereby furnished.	or mo		
	Certified copy is filed with the city building inspection department.	inc		
	Signature Date	of		
	(This section need not be completed if the permit is for one humdred dollars (\$100) or less.)	tai co ma		
	to a standard to the analysis of the court for which this court is because I shall not a make			

Date

11:01(ETO APPLICANT, If, after making this Certificate of Exemption, you should become

set 4 to the Workers' Compensation provisions of the Labor Code, you must forthwith 1 1 years with such provisions or this permit shall be deemed revoked.

LOCATION: _3201_3	(street or address)	(street) (street)	CADI
NATURE OF WORK: 1	monitoring well on Suter st	South of 35th Avenue	
APPLICANT: Alton	Geoscience, Inc.	CONTRACTOR  I hereby affirm that I am licensed under provisions of Chapter 9  (commencing with Section 7000) of Division 3 of the Business and	
ADDRESS: 1000 But	mett Ave., Suite 140	Professions Code, and my license is in full force and effect.  UCHASE 554979 C57 CITY AND CLASS 596620	
CITY: Concord	STATE: CA 710.94520	-	<b>.</b>
I hereby offirm that I am exemp 'Sec 7031.5, Business and Profi- construct, after, improve, demolis the applicant for such permit to I	t from the Contractor's License Law for the following reasor essions Code: Any city or county which requires a permit to sh, or repair any structure, prior to its issuance, also require file a signed statement that he is licensed pursuant to the pro se Law Chapter 9 (commencing with Sec 7000) of Division	Approximate Starting Date DATE 5/16/90 05-17-9 Approximate Completion Date DATE 5/19/90	Supr Com
3 of the Business and Profession alleged exemption. Any violatio the applicant to a civil penalty o	s Code, or that he is exempt therefrom and the basis for the or of Section 7031.5 by any applicant for a permit subject	LIMITED OPERATION AREA YES NO	ļ
do the work, and the structure in Professions Code: The Contractor builds or improves thereon, and provided that such improvements or improvement is sold within an	is not intended or offered for sale (Sec. 7044, Business and it is license law does not apply to an owner of property who who does such work thinself or through his own employees is are not intended or offered for sale If, however, the building e year of completion, the owner-builder will have the building	24-HOUR EMERGENCY PHONE NUMBER 916 678 7276	Initia House Date Cons
1. as owner of the property, (1) I am improving my principal popular formed prior to sale, (3) II	or improve for the purpose of sale).  orn exempt from the sale requirements of the above due to loce of residence or appurtenances thereto. [2] the work will have residence for the 12 months prior to com-	Telephone 273-3668 Forty-eight (48) HOURS BEFORE ACTUAL CONSTRUCTION. This Permit Void 90 Days from Issue.	Aspl Side
structures more than once during Code)  It as owner of the property.	e not claimed exemption in this subdivision on more than two ony three-year period. (Sec. 7044, Business and Professions om exclusively contracting with licensed contractors to con	ALLENTION  State law requires that contractor/owner call Underground Service Alert two work- ing days before excavating to have below-ground utilities located. This permit is not	Size
does not apply to an owner of p	usiness and Professions Code: The Contractor's License Law property who builds or improves thereon, and who contract or(s) licensed pursuant to the Contractor's License Law).	ground Service Alert	Bill N
I am exempt under See	Sept positive pages	Call Toll Free: 800-642-2444	
Signature  Thereby affirm that I have a cer Compensation Insurance, or a ce	Date  tificate of consent to self-insure, or a certificate of Workers ertified copy thereof (Sec. 3800, Lab. C.).	Municipal Code.	<u> </u>
Pol-WP89-469257-0	INORNE	This permit is granted upon the express condition that the permittee shall be re- sponsible for all claims and liabilities arising out of work performed under the permit or arising out of permittee's failure to perform the obligations with respect to street	Engi
Certified copy is hereby furr	nished. he city building inspection department	maintenance. The permittee shall, and by acceptance of the permit agrees to defend, indemnity, save and hold harmless the City, its officers and employees, from and	Field
Signature	Date Date		Con
(This section need not be comple	eted if the permit is for one humdred dollars (\$100) or less		Traf
	of the work for which this permit is issued, I shall not employ s to become subject to the Workers' Compensation Laws o		Elec
Same Paris	Parts.	i i	1.00

	EXCV.	10	3.00
Bair Market	100		
	COMPANY	EPON O	
Supervisor	1150	770H	11:021
Completion Date			
C	ITY INSPEC	TOR'S REPO	ORT
	BACKFILL		VING
Initials			
Hours			
Date			
Concrete			
Aspholt			
Sidewalk			
Size of Cut: Sq.Ft.			<del></del>
]			
Paved by		Туре	
Bill No.		· · · · · · · · · · · · · · · · · · ·	
Charges	Backfill		
	Paving		<del></del>
	Paving Insp.		
APPROVED			
Engineering Services _		Date .	
Field Services		Date .	
Construction		Date .	<del></del>
Traffic Engineering		Date _	
Electrical Department	•	Date .	<del></del>
APPROVED BY DE	-		
		COLO TIONN	-
PER			<del></del>
no 15/17	la.		
1 6 55			<b>О</b> м

A'DRKER'S COMPENSATION

## MANGELS AVE.

BP OIL PACILITY

.OCATION: 201 35th Avenue

(street or address)

### **CITY OF OAKLAND**

PERMIT TO EXCAVATE IN STREETS OR OTHER WORK AS SPECIFIED

BETWEEN35th Ave. AND Sitter
(street) (street)

\$105

X9000937

BP OIL COMPANY

2868 PROSPECT PARK DR. SUITE 360

RANCHO CORDOVA, CA 95670

APPEICANT: 11con Coordinate No. 1 State 140  CITY: Concord State or 12F-9550  PINONE: The sta	NATURE OF WORK: 1 monitoring well on Mangels	Ave.	
ADDRESS: 1000 Busmatt. New State: 440  CITY: Connect STATE: Co. 78: 94500  PHONE: metal on substitution of the State of th			
ADDRESS:	APPIICANT: 11ton Congolonos, Inc	I hereby affirm that I am licensed under provisions of Chapter 9	
STATE	73001 00000007 2100	Professions Code, and my license is in full force and effect.	the second second second second
STATE	ADDRESS: 1000 Premott Imp Guite 140	MOCIASS C57 554979 CTY MISNESS 596620	A COMPANY OF THE STATE OF THE S
PHONE			UTILITY COMPENSITY REPORT O 5.00
Isarchy after Med I can sub-fifting in Chilling To State I can be a fine following a complete on the conference of the complete of the compl		1 1	Supervisor ITEM 1
Approximate is add with me a certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) there was certificate of concern to self-section on the work and (a) the work and	I hereby affirm that I am exempt from the Contractor's Cleanse Law for the following reason	Approximate Starting Date DATE \$/16/90 05-17-	l • ———
Substitute Law Control of the Contrologic Liberts Law Chocker 12 (Commercing with Sec 7000) of Philips 3 of the Business of Philips Law Control of Philips 3 of the Business of Philips Law Control of Philips 3 of the Business of Philips 4 o	construct, other, improve, demolish, or repair any structure, prior to its issuance, also requires	Approximate Completion Date DATE 5/19/90	744. 777. 114027
indeptid assemption. Any violation of Section 703 13 by any opplicant for a permit ablighost the copition to an ordinary better of the opposity or any employees with wages as that sold compensation. But the copition to an owner of the property or any employees with wages as that sold compensation. But the contract of the compensation are in the contract of the con	visions of the Contractor's License Law Chapter 9 (commencing with Sec. 7000) of Division		
The Comment of the process of configuration of the	3 of the Business and Professions Code, or that he is exempt therefrom and the basis for the collected exemption. Any violation of Section 7031.5 by any applicant for a permit subjects	LIMITED OPERATION AREA YES NO	CITY INSPECTOR'S REPORT
Lil to convex of the property, or my employees with varies and the color compression, will be the vertical for a first for the color call (See 2014), blownes and the structure in order seed for a first for the vertical for the v	the applicant to a civil penalty of not more than \$500):		_
Processors Code: the Contended is Lesses and expert from a normal of property that provided that such improvements in a collection or the intended or official for local and improvements in a sold within one year of compeliation, the connection between the property, can extend from the data or many promoted proves or dischors or agreements from the sold and not bad or improve for the property or dischorated or dischorated and provided that such as the first provided that suc	Lit, as owner of the property, or my employees with wages as their sole compensation, will		
Date of experience interest and the control of the	[ Professions Code: The Contractor's License Law does not apply to an owner of property who	24-HOUR EMERGENCY	Hours
af proving that he did not bail or improve for the purpose of solo).  It is a some of the property, an exempt from the sole requirement of the chove due to consider the sole requirement of the chove due to consider the sole (a) throw not do the exemption in this subdivision on more than two technical good to sole, (a) throw noted with the ambients and Professions Code. The Contractor's License Lory between of the property, an exclusively contracting with Econect Contractor's License Lory between of the property, and exclusively contracting with Econect Contractor's License Lory between of the property, and exclusively contracting with Econect Contractor's License Lory between the project (Sec. 7044, Business and Professions Code: The Contractor's License Lory between the project (Sec. 7044, Business and Professions Code: The Contractor's License Lory).  It is a connect of the property, and exclusively contracting with Econect Contractor's License Lory, between the project (Sec. 7044, Business and Professions Code: The Contractor's License Lory).  It is a connect of the property, and exclusively contracting with Econect Contractor's License Lory, between the project (Sec. 7044, Business and Professions Code: The Contractor's License Lory).  It is provided to an owner of property with buside or an owner of property with buside and employment of the property with buside and employment the property with buside and employment the property of the Code of the Contractor's License Lory, between the property of the Code of th	provided that such improvements are not intended or offered for sale. If, however, the building	PHONE NUMBER 916 638 1276	1
This permit is used pursuant to all provisions of Chapter 6, Article 2 of the Oxidand Services 10 or an exercision humans, or a certificate of consent to self-index or conficults of Compensation humans, or a certificate of consent to self-index open the self-index open to self-index open the self-index of the self-index open to self-index open the self-index open to self-index open the self-index open to self-index open the self-index of the self-index open to self-index open the self-index open to self-index open the self-index of the self-index open to self-index open to self-index open the self-index open to self-index open the	or improvement is sold within one year of completion, the owner-builder will have the burden of proving that he did not build ar improve for the ourpose of sole).	• •	1
1) In microwing the process of the present and the process of th	1 1 1	Telephone 273-3668 Forty-eight (48) HOURS BEFORE ACTUAL CONSTRUCTION.	, —
Size of Cut: Sq. Ft   Inches	1 / 1) I can improving our principal place of residence or approving received therein (2) the work will	This remain void 90 Days from issue.	Sidewalk
Stotle low requires that contractor/owner call Underground Service Alert two working days before excurrently owner call Underground Service Alert two working days before excurrently owner call Underground Service Alert two working days before excurrently owner of property who builds or improves thereous and who contracts for such project (Sec. 704.4, Business and Professions Code: The Contractor's License Law index on the Contractor's License Law indicators of the property who builds or improves thereous and who contracts for such project (Sec. 704.4, Business and Professions Code: The Contractor's License Law indicators of License Law indicators of the Contractor's License Law indicators of the Contract	pletion of the work, and (4) I have not claimed exemption in this subdivision on more than two	ATTENITION	Size of Cut: Sq. Ft Inches
Signature   Compensation Insurance, or a certificate or consent to self-index or a certificate copy is hereby furnished.   Certified copy is filled with the city building inspection department.   Signature   Certified copy is hereby furnished.   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the copy is construction of the work performed under the permit or ording out of permittees failure to perform the obligations with respect to street mointenance.   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department.   Signature   Certified copy is filled with the city building inspection department   Signature   Certified copy is filled with the city building inspection department   Signature   Signature   Signature			
Signature   Security   Security   Signature   Security   Security   Signature   Security   Security   Security   Signature   Signature   Security   Signature   Signature   Signature   Signature   Security   Signature   Sig	21, as owner of the property, are exclusively contracting with licensed contractors to con-	ing days before excavating to have below-ground utilities located. This permit is not	Poved byType
or such projects with a contractor's licensed purysont to the Contractor's License Large.  I now exempty ander Seed	{ STUCT THE DIOJECT (Sec. / U.4.4, DUSINESS ONG PIOTESSIONS CODE: THE CONTROCTOR'S LICENSE LOW	valid unless applicant has secured an inquiry identification number issued by Under-	
Signature    Date   Date   Date	for such projects with a contractor(s) licensed pursuant to the Contractor's License Lary).	Good de Are Ver	Charges Backfill
I hereby affirm that I have a certificate of consent to self-insafe, or a certificate of Worker' Compensation Insurance, or a certificate of your threed (Sec. 3800, Lob. C.)  Pole 1989 469257-02 Company Frencht Indemnity Name  Certified copy is hereby furnished.  Certified copy is hereby furnished.  Certified copy is filed with the city building inspection department.  Signulure  Date  City that in the performance of the work for which this permit is issued, I shall not employ easy person in any manner so as to become subject to the Worker' Compensation Laws of Collinguals  Note:  Note:  Oute:  This permit issued pursuant to all provisions of Chapter 6, Article 2 of the Oakland Municipal Code.  This permit is granted upon the express condition that the permittee shall be responsible for all claims and licibilities arising out of work performed under the permit agrees to defend, indemnity, save and hold harmless the City, its officers and employees, from and against any and all suits, claims or actions brought by any person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.  I certify that in the performance of the work for which this permit is issued, I shall not employee any person in any manner so as to become subject to the Workers' Compensation Laws of Collinguals  Note:	om exempt under Sagnature	Coll Toll Free: 800-642-2444	Paving
The permit is sued pursuant to all provisions of Chapter 6, Article 2 of the Oakland Municipal Code.  This permit is granted upon the express condition that the permittee shall be responsible for all claims and liabilities arising out of work performed under the permit or arising out of permittee shall be responsible for all claims and liabilities arising out of work performed under the permit or arising out of permittee's failure to perform the obligations with respect to street maintenance. The permittee shall, and by acceptance of the permit agrees to defend, indemnity, over and hold harmless the City, its officers and employees, from and organist any and all suits, claims or actions brought by any person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.  It certify that in the performance of the work for which this permit is issued, I shall not employees person in any manner so as to become subject to the Workers' Compensation Laws of Country III.  It certify that in the performance of the work for which this permit is issued, I shall not employees from the obligations with respect to street maintenance.  It certify that in the performance of the work for which this permit is issued, I shall not employees from the obligations with respect to street maintenance.  It certify that in the performance of the work for which this permit is issued, I shall not employees from the obligations with respect to street maintenance.  It certify that in the performance of the work for which this permit is issued, I shall not employee the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.  It certify that in the performance of the work for which this permit is issued, I shall not employee the permit or in consequence of permittee's failu			Paving Insp
Company Frescott Indexnity Number 1 Security Street Security Secur		The second control of the control of Change & Audit 2 Chin College	APPROVED
This permit is granted upon the express condition that the permittee shall be responsible for cill cloims and liabilities arising out of work performed under the permit or arising out of permittee's failure to perform the obligations with respect to street maintenance. The permittee shall, and by occeptance of the permit agrees to defend, indemnity, save and hold harmless the City, its officers and employees, from and odinate and all suits, claims or actions brought by any person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.  I certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the Workers' Compensation Laws of Colitoration.  I control to APPLICANT, If, after making this Certificate of Exemption, you should become signature.  This permit is granted upon the express condition that the permittee shall lob information of work performed under the permit agrees to defend, indemnity, save and hold harmless the City, its officers and employees, from and oditions or actions brought by any person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit agrees to defend, indemnity, save and hold harmless the City, its officers and employees, from and oditions or a damage to persons and or person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising out of work performs the obligations with respect to street maintenance.  I certify that in the permittee shall, ond by acceptance of the permittee shall, ond by acceptance of the permittee's failure to perform the obligations with respect to street maintenance.  Fiel	I hereby affirm that I have a certificate of consent to self-inside, or a certificate of Workers'		
Certified copy is hereby furnished.  Certified copy is hereby furnished.  Certified copy is filed with the city building inspection department.  Signature  Date  This section need not be completed if the permit is for one humdred dollars (\$100) or less.  Certified to price the permittee's failure to perform the obligations with respect to street maintenance. The permittee's failure to perform the obligations with respect to street maintenance. The permittee's failure to perform the obligations with respect to street maintenance. The permittee's failure to perform the obligations with respect to street maintenance. The permittee's failure to perform the obligations with respect to street maintenance. The permittee's failure to perform the obligations with respect to street for any person for or on account of any bodilly injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.  Traffic Engineering  Date  Traffic Engineering  Date  Traffic Engineering  Date  PER  PER  PER  PER  PER  PER  PER  PE	1		Engineering Services Date
Certified copy is hereby furnished.  Certified copy is filed with the city building inspection department.  Signature  Date  This section need not be completed if the permit is for one hundred dollars (\$100) or less.)  I certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the Workers' Compensation Laws of Collitarable  Date  Traffic Engineering  Date  Date  Need Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date  Construction  Construction  Date  Traffic Engineering  Date  Field Services  Date	"		
Signulture  Date  ogainst any and all suits, claims or actions brought by any person for or on account of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.  I certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the Workers' Compensation Laws of Colligation  Signulture  Date  Traffic Engineering  Date  Electrical Department  APPROVED BY  Diffection, you should become  Signature of Construction of owner or Agest	I	maintenance. The permittee shall, and by acceptance of the permit agrees to defend,	Field Services Date
of any bodily injuries, disease or illness or damage to persons and/or property sustained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.    Certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the Workers' Compensation Laws of Colligation.    Signature   Date   D		indemnify, save and hold harmless the City, its officers and employees, from and	
This section need not be completed if the permit is for one hundred dollars (\$100) or less tained or arising in the construction of the work performed under the permit or in consequence of permittee's failure to perform the obligations with respect to street maintenance.    Certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the Workers' Compensation Laws of Cultivation    Signiture   Date   Date   Date	Signature Date	of any bodily injuries, disease or illness or damage to persons and/or property sus-	Construction Date
I certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the Workers' Compensation Laws of Collisarilla  Significate  Date    Collisarilla   Date	(T) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1	tained or arising in the construction of the work performed under the permit or in	
Colity person in any manner so as to become subject to the Workers' Compensation Laws of Colity plan  Signature  Date  X  Date  X  Signature of Contractor Owner or Agent  Signature of Contractor Owner or Agent	(this section need not be completed if the permit is for one number dollars (\$100) or less)		Traffic Engineering Date
Califordia  Significate  Date  APPROVED BY  Diffection OF PUBLIC WORKS  PER  140 FILE TO APPLICANT, It, after making this Certificate of Exemption, you should become Signature of Contractor Owner or Agent			
APPROVED BY DIRECTOR OF PUBLIC WORKS  140 FIG. TO APPLICANT, If, after making this Certificate of Exemption, you should become Signature of Contractor Owner or Agent			Electrical Department Date
130 ft. L. I.O. APPLICANI, it, after making this Certificate of Exemption, you should become Signature of Contractor Owner or Agent	The same of the sa	5/ F	APPROVED BY DIRECTOR OF PUBLIC WORKS
130 ft. L. I.O. APPLICANI, it, after making this Certificate of Exemption, you should become Signature of Contractor Owner or Agent		x T_ (election) = storten	
	13/OTBLE TO APPLICANT, If, after making this Certificate of Exemption, you should become	Signature of Contractor Owner or Agent	Irek
in 1 in such provisions or this permit shall be deemed revoked.  □ Agent for □ Contractor □ Owner  □ Owner  □ Owner	solges to the Workers' Compensation provisions of the Labor Code, you must forthwith in a till with such provisions or this permit shall be deemed revoked.	☐ Agent for ☐ Contractor ☐ Owner	Date 5 17 90 OM

#### APPENDIX E

Laboratory Reports and Chain of Custody Records



1961 Concourse Drive, Suite E San Jose, CA 95131 (408) 432-8192 • Fax (408) 432-8198

August 1, 1990

Mr. Matthew Taylor ALTON GEOSCIENCES 1000 Burnett Avenue Suite 140 Concord, CA 94520

Project Number:

30-081

Anametrix Workorder:

9005252

Dear Mr. Taylor:

Enclosed is the reissued Certified Analytical Report (CAR) that you requested. After review of your request, we have determined that a re-issued CAR is in order because of the following reason(s):

At your request, we changed the sample I.D. number from MW 5 to RW 1.

Thank you for your patience. If there is anything more that we can do, please contact me immediately.

Sincerely,

ANAMETRIX, INC.

Sarah R. Schoen, Ph.D. Laboratory Manager

SRS/dm/3505

Enclosure

#### REPORT SUMMARY ANAMETRIX, INC. (408) 432-8192

Anametrix W.O.#: 9005252
Date Received: 05/21/90
Purchase Order#: N/A
Project No.: 30-081 Client : Alton Geoscience
Address : 1000 Burnett Avenue
Suite 140
City : Concord, CA 94520

Attn. : Matt Hopwood	Date Released: 05/30/90
Anametrix   Sample   I.D.   I.D.	Date   Date   Date   Inst   Matrix Sampled  Method  Extract  Analyzed I.D.
RESULTS	
9005252-01 MW 4/5  9005252-02 MW 4/10  9005252-03 MW 4/15  9005252-04 MW 4/20  9005252-05 MW 4/25  9005252-06 RW 1/5  9005252-06 RW 1/10  9005252-08 RW 1/15  9005252-09 RW 1/20  9005252-10 RW 1/25	SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/29/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A       SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHg     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     05/25/90   N/A     SOIL   05/16/90   TPHG     O5/25/90   N/A     SOIL   05/16/90   TPHG     O5/25/90   N/A     SOIL   O5/16/90   TPHG     O5/16/90
QUALITY ASSURANCE (QA)	
9005252-07 RW 1/10	SOIL  05/16/90  SPIKE    05/25/90 N/A

Sample I.D. : 30-081 MW 4/5 Anametrix I.D.: 9005252-01 Analyst : CB
Supervisor : CCG
Date released : 05/30/90
Date ext. TOG : N/A
Date anl. TOG : N/A : SOIL Matrix Date sampled: 05/16/90 Date anl.TPHg: 05/25/90 Date ext.TPHd: N/A Date anl. TPHd: N/A

	Compound Name	Reporting	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005   0.005   0.005   0.005   1	ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-02 Sample I.D. : 30-081 MW 4/10 : 08 Analyst : SOIL Matrix Matrix SOIL
Date sampled: 05/16/90
Date anl.TPHg: 05/25/90
Date ext.TPHd: N/A Supervisor : OPG
Date released : 05/30/90
Date ext. TOG : N/A Date anl. TOG : N/A Date anl. TPHd: N/A

	Compound Name	Reporting	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005   0.005   0.005   0.005   1	ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-03 : 30-081 MW 4/15 Sample I.D.

: SOIL Matrix

Analyst : C/5
Supervisor : C/5
Date released : 05/30/90
Date ext. TOG : N/A
Date anl. TOG : N/A Date sampled: 05/16/90 Date anl.TPHg: 05/25/90 Date ext.TPHd: N/A Date anl. TPHd: N/A

	Compound Name	Reporting	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005 0.005 0.005 0.005 1	ND ND ND ND ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 4/20 Anametrix I.D.: 9005252-04

: SOIL Matrix

Analyst : C/3
Supervisor : D/C/4
Date released : 05/30/90
Date ext. TOG : N/A Date sampled: 05/16/90
Date anl.TPHg: 05/25/90
Date ext.TPHd: N/A
Date anl.TPHd: N/A Date anl. TOG : N/A

CAS #	Compound Name	Reporting Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005 0.005 0.005 0.005 1	ND   ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-05 Sample I.D. : 30-081 MW 4/25

Analyst Analyst : ca Supervisor : DDG : SOIL Matrix

Date sampled: 05/16/90
Date anl.TPHg: 05/25/90
Date ext.TPHd: N/A Date released: 05/30/90
Date ext. TOG: N/A
Date anl. TOG: N/A Date anl. TPHd: N/A

CAS #	Compound Name	Reporting Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005   0.005   0.005   0.005	ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-06 Sample I.D. : 30-081 RW 1/5 Analyst :08 : SOIL Matrix Supervisor : EXC Date released : 05/30/90 Date sampled: 05/16/90
Date anl.TPHg: 05/25/90
Date ext.TPHd: N/A Date ext. TOG : N/A Date anl. TOG : N/A Date anl. TPHd: N/A

CAS #	Compound Name	Reporting Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005   0.005   0.005   0.005   1	ND ND ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-07 Sample I.D. : 30-081 RW 1/10

Analyst :08
Supervisor :006
Date released :05/30/90
Date ext. TOG :N/A : SOIL Matrix Date sampled: 05/16/90

Date anl.TPHg: 05/25/90 Date ext.TPHd: N/A Date anl. TOG : N/A Date anl. TPHd: N/A

	Compound Name	Reporting	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005   0.005   0.005   0.005   1	ND ND ND ND ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-08 Sample I.D. : 30-081 RW 1/15

Analyst :08 : SOIL Matrix Supervisor : Dex

Date sampled: 05/16/90 Date anl.TPHg: 05/29/90 Date ext.TPHd: N/A Date released : 05/30/90
Date ext. TOG : N/A
Date anl. TOG : N/A Date anl. TPHd: N/A

CAS #	Compound Name	Reporting Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.05   0.05   0.05   0.05   1	0.72   1.6   0.58   2.8   22

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9005252-09 Sample I.D. : 30-081 RW 1/20

જ Analyst : SOIL Matrix : 000 Supervisor Date sampled : 05/16/90

Date anl. TPHg: 05/25/90 Date released: 05/30/90

Date ext. TOG : N/A
Date anl. TOG : N/A Date ext. TPHd: N/A Date anl. TPHd: N/A

CAS #	Compound Name	Reporting Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	5 5 5 5 100	ND   18   8.0   40   410

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID

using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 RW 1/25 Anametrix I.D.: 9005252-10

Analyst :%
Supervisor : 000 : SOIL Matrix Date sampled: 05/16/90

Date released : 05/30/90 Date ext. TOG : N/A Date anl. TOG : N/A Date anl.TPHg: 05/25/90 Date ext.TPHd: N/A Date anl. TPHd: N/A

	Compound Name	Reporting	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.5   0.5   0.5   0.5   10	1.4   3.3   1.0   5.4   50

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

### ANAMETRIX INC

Environmental & Analytical Crem stry 1961 Concourse Drive Suite E San Jose, CA 95131 (408) 432-8192 • Fax (408) 432-8198



Stephan Rosen Alton Geoscience 1000 Burnett Avenue Suite 140 Concord, CA 94520 July 12, 1990

Anametrix W.O.#: 9006329 Date Received : 06/26/90 Project No. : 30-081

Dear Mr. Rosen:

Your samples have been received for analysis. The REPORT SUMMARY lists your sample identifications and the analytical methods you requested. The following sections are included in this report: RESULTS and QUALITY ASSURANCE.

NOTE: Amounts reported are net values, i.e. corrected for method blank contamination.

If there is any more that we can do, please give us a call. Thank you for using ANAMETRIX, INC.

Sincerely,

ANAMETRIX, INC.

Sarah Schoen, Ph.D. Laboratory Manager

SRS/1m

#### BTEX MATRIX SPIKE REPORT EPA METHOD 5030 WITH GC/PID ANAMETRIX, INC. (408) 432-8192

Anametrix I.D.: 9005252-07

Sample I.D. : 30-081 RW 1/10
Matrix : SOIL
Date Sampled : 05/16/90
Date Analyzed : 05/25/90 Anametrix I.D.: 9005252-0
Analyst : %
Supervisor : 12%
Date Released : 05/29/90

COMPOUND	SPIKE AMT. (mg/Kg)	MS (mg/Kg)	REC MS	%REC LIMITS
Benzene	0.02	0.016	80%	49-159
Toluene	0.02	0.016	80%	53-156
Ethylbenzene	0.02	0.017	85%	54-151
M+P-Xylenes	0.013	0.011	85%	56-157
O-Xylene	0.0067	0.0054	81%	58-154

## REPORT SUMMARY ANAMETRIX, INC. (408) 432-8192

Client : Alton Geoscience Anametrix W.O.#: 9006329
Address : 1000 Burnett Avenue Suite 140
City : Concord, CA 94520 Purchase Order#: N/A
Project No. : 30-081
Date Released : 07/12/90

Attn. : Stephan Rosen			Date Re	leased :	07/12/90
Anametrix   Sample   I.D.   I.D.	  Matrix	Date Sampled	  Method 	Date  Extract	Date  Inst   Analyzed I.D.
RESULTS					
9006329-01 MW 7/20  9006329-02 MW 7/25  9006329-03 MW 5/5  9006329-04 MW 5/10  9006329-05 MW 5/15  9006329-06 MW 5/20  9006329-07 MW 5/25  9006329-09 MW 6/15  9006329-09 MW 6/15  9006329-10 MW 7/15	SOIL SOIL SOIL SOIL SOIL SOIL SOIL SOIL	06/25/90 06/25/90 06/25/90 06/25/90 06/25/90 06/25/90 06/25/90 06/25/90	TPH		06/30/90   N/A     06/30/90   N/A     06/30/90   N/A     07/06/90   N/A     07/09/90   N/A     07/06/90   N/A     06/30/90   N/A       06/30/90   N/A
QUALITY ASSURANCE (QA)					
9006329-02 MW 7/25	SOIL	06/25/90 	TPH		07/01/90 N/A

Sample I.D. : 30-081 MW 7/20

Anametrix I.D.: 9006329-01

Matrix SOIL
Date sampled: 06/25/90
Date anl.TPHg: 06/30/90

Analyst : CE Supervisor : COG Date released : 07/12/90

CAS #	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene Toluene Ethylbenzene Total Xylenes TPH as Gasoline	0.005   0.005   0.005   0.005   1	ND   ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by

GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 7/25 Anametrix I.D.: 9006329-02

Analyst : AS Supervisor : AG Date released : 07/12/90 Matrix : SOIL Date sampled : 06/25/90

Date an1. TPHg: 06/30/90

	Compound Name	Detection	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005   0.005   0.005   0.005   1	ND ND ND ND ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 5/5

Anametrix I.D.: 9006329-03

Matrix : SOIL
Date sampled : 06/25/90
Date anl.TPHg: 06/30/90

Analyst : As Supervisor : Ay, Date released : 07/12/90

CAS #	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005 0.005 0.005 0.005 1	ND   ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 5/10

Anametrix I.D.: 9006329-04

: SOIL Matrix

Date sampled : 06/25/90

Analyst : 45 Supervisor : 204

Date an1. TPHg: 07/06/90

Date released: 07/12/90

	Compound Name	Detection	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.01 0.01 0.01 0.01 1	ND   0.019   ND   0.11   9.3

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by

GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 5/15

Anametrix I.D.: 9006329-05

Matrix : SOIL

L Analyst

Date sampled: 06/25/90 Supervisor
Date anl.TPHg: 07/09/90 Date released

Analyst : 48
Supervisor : 0004
Date released : 07/12/90

   CAS #	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.01 0.01 0.01 0.01 1	0.16   0.037   0.29   0.42   14

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by

GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9006329-06

Sample I.D. : 30-081 MW 5/20 Matrix : SOIL Date sampled : 06/25/90 Date anl.TPHg: 07/09/90 Analyst : 43
Supervisor : \$\rho\_{0G}\$
Date released : 07/12/90

   CAS #	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.125 0.125 0.125 0.125 2	1.8   11   2.5   17   190

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by

GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Anametrix I.D.: 9006329-07 Sample I.D. : 30-081 MW 5/25

Analyst : 66
Supervisor : 1006
Date released : 07/12/90 : SOIL Matrix Date sampled: 06/25/90 Date anl.TPHg: 07/06/90

   CAS #	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	1.25   1.25   1.25   1.25   25	4.8   44   13   94   770

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 6/15 Anametrix I.D. : 9006329-08

Sample 1.D. : 30-001 PW 0/15

Matrix : SOIL

Pate sampled : 06/25/90

Supervisor : 006

Date sampled: 06/25/90 Supervisor:  $\infty 6$  Date released: 07/12/90

	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene Toluene Ethylbenzene Total Xylenes TPH as Gasoline	0.005 0.005 0.005 0.005 1	ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 6/20 Anametrix I.D.: 9006329-09

Analyst : 3 Supervisor : 006 Matrix : SOIL
Date sampled : 06/25/90
Date anl.TPHg: 06/30/90

Date released: 07/12/90

	Compound Name	Detection	Amount
		Limit	Found
CAS #		(mg/Kg)	(mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005 0.005 0.005 0.005	ND ND ND ND ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

Sample I.D. : 30-081 MW 7/15 Anametrix I.D.: 9006329-10

Analyst : 🗷 Supervisor : 🕬 : SOIL Matrix Date sampled: 06/25/90 Date anl.TPHg: 06/30/90

Date released: 07/12/90

CAS #	Compound Name	Detection Limit (mg/Kg)	Amount   Found   (mg/Kg)
71-43-2  108-88-3  100-41-4  1330-20-7	Benzene   Toluene   Ethylbenzene   Total Xylenes   TPH as Gasoline	0.005 0.005 0.005 0.005	ND   ND   ND   ND   ND

ND - Not detected at or above the practical quantitation limit for the method.

TPHg - Total Petroleum Hydrocarbons as gasoline is determined by GCFID using EPA Method 5030.

BTEX - Benzene, Toluene, Ethylbenzene, and Total Xylenes are determined by modified EPA 8020.

#### BTEX MATRIX SPIKE REPORT EPA METHOD 5030 WITH GC/PID ANAMETRIX, INC. (408) 432-8192

Anametrix I.D.: 9006329-02

Analyst : CB Supervisor : POG

Sample I.D. : 30-081 MW 7/25
Matrix : SOIL
Date Sampled : 06/25/90
Date Analyzed : 07/01/90

Date Released: 07/12/90

COMPOUND	SPIKE AMT. (mg/Kg)	MS (mg/Kg)	REC MS	MSD (mg/Kg)	REC MSD	RPD	%REC LIMITS
Benzene	0.02	0.021	105%	0.024	120%	13%	50-150
Toluene	0.02	0.021	105%	0.023	115%	9%	50-150
Ethylbenzene	0.02	0.02	100%	0.021	105%	5%	50-150
M+P-Xylenes	0.013	0.013	100%	0.014	108%	7%	50-150
O-Xylene	0.0067	0.0064	96%	0.0067	100%	5%	50-150

### SUPERIOR ANALYTICAL LABORATORIES, INC.

825 ARNOLD, STE. 114 • MARTINEZ, CALIFORNIA 94553 • (415) 229-1512

DOHS #319 DOHS #220

CERTIFICATE OF ANALYSIS

LABORATORY NO.: 81159 CLIENT: Alton Geoscience CLIENT JOB NO.: 30-081 DATE RECEIVED: 07/11/90 DATE REPORTED: 07/17/90

ANALYSIS FOR TOTAL PETROLEUM HYDROCARBONS by Modified EPA SW-846 Method 5030 and 8015

LAB #	# Sample Identification  1 MW-3 2 MW-4 3 MW-5	Concentration (mg/L) Gasoline Range
1	MW-3	0.14
2	MW-4	ND<0.05
3		2.8
4	7.77	ND<0.05
5	MW-7	ND<0.05

mg/L - parts per million (ppm)

Method Detection Limit for Gasoline in Water: 0.05 mg/L

#### QAQC Summary:

Daily Standard run at 2mg/L: RPD Gasoline = 9% MS/MSD Average Recovery = 85%: Duplicate RPD = 4%

Richard Srna, Ph.D.

Laboratory Manager

## SUPERIOR ANALYTICAL LABORATORIES, INC.

825 ARNOLD, STE. 114 • MARTINEZ, CALIFORNIA 94553 • (415) 229-1512

**DOHS #319 DOHS #220** 

### CERTIFICATE OF ANALYSIS

LABORATORY NO.: 81159 CLIENT: Alton Geoscience CLIENT JOB NO.: 30-081

DATE RECEIVED: 07/11/90 DATE REPORTED: 07/17/90

ANALYSIS FOR BENZENE, TOLUENE, ETHYL BENZENE & XYLENES by EPA SW-846 Methods 5030 and 8020

			Concentration			
LAB #	Sample Identification	Benzene	Toluene	Ethyl Benzene	Xylenes	
1 2 3 4 5	MW-3 MW-4 MW-5 MW-6 MW-7	5.3 ND<0.3 200 ND<0.3 ND<0.3	4.6 ND<0.3 210 ND<0.3 ND<0.3	2.0 ND<0.3 46 ND<0.3 ND<0.3	3.8 ND<0.3 290 ND<0.3 ND<0.3	

ug/L - parts per billion (ppb)

Method Detection Limit in Water: 0.3 ug/L

QAQC Summary:

Daily Standard run at 20ug/L: RPD = <15%

MS/MSD Average Recovery = 103 %: Duplicate RPD = <3%

Richard Srna, Ph.D.

Laboratory Manager

 	······································
ALTON	GEOSCIENCE
1170 BURNE	TT AVE., STE. S
CONCORD, C	CA. 94520 (415) 682-1582

### CHAIN of CUSTODY RECORD

DATE: 5/16/90 DUEBY: NORMA! ~, ~

f	LABORATORY:	Ana	Me	7

	CONCORD, CA. 94	4520 (415) 682-1582		PAGE						a me Tri	Trix			
PROJECT	NUMBER / MANAG	GER: MATT Holmod SAM	PLERS SIGNA	TURE: M. 7	67/.1			SOIL	ANALYSIS	WATER	ANALYSIS			
		s: 30-081 - 35					ដ	Tex						
REMARKS	OR SPECIAL INS	STRUCTIONS:					TYPE & NUMBER OF CONTAINERS	H-6 ; 87						
SAMPLE NUMBER	SAMPLE DATE/TIME	LOCATION/ DESCRIPTION		SAMPLE MATRIX	SAMPLE GRAB	TYPE: COMP.		10						
MW 4/5	5/16			Soil			BRASS							
mw//o	··			/ 1			!!							
mw 1/s	. "			, ,			۲,							
MW 1/20	11			"			, 1							
MW 1/25	/•			/.			11							
AW 5/5	5/16	> Change To	1/5 8/1/10	/ •			(.							
MN3/10	-> "	- Chinge RW	1/10 MAT. 8/119	/•			(.							
MW 5/15	-> " _	- Change RW!	15 8/1150	//			-							
MW /20	-> //		/20 m. A.T.				/'			-				
MW-5/23	<i>&gt; ''</i>	RW1	25 8/1/90	1		1 '								
										<u> </u>				
SIGNAT	TURE A.	inc 5/2	LUSIVE DATE	CHAIN OF S/TIMES	CUSTODY SIGNA				11	NCLUSIVE I	DATES/TIMES			

SIGNATURE	INCLUSIVE DATESTIMES	SIGNATURE	INCLUSIVE DATES/TIMES
Matt A lay	5/21/90	4	
5 Jahr Merundu	9/24/90 10145	5	
3		É	

ALTON GEO	CHAIN of CUSTODY RECORD				DATE: 6 /26/90 DUI LABORATORY:				Anametrix		
PROJECT NUMBER / MANAGER: 30 - 08/ SAMPLERS SIGNATURE: Matter A. Tay						ANALYSIS			ANALYSIS		
PROJECT NAME / ADDRESS:	BP 0:1 357	AVE Oakland	<b>(</b>		r s	EX					
REMARKS OR SPECIAL INSTRU	JCTIONS:				TYPE & NUMBER OF CONTAINERS	-6+BTEX					
AMPLE SAMPLE	LOCATION/ DESCRIPTION	SAMPLE MATRIX	SAMPLE GRAB	TYPE:	Bruss	HdL					
1W 5 6/25		50:1			(-						
nw 50					<del>                                     </del>			_			
sw 5/15 Nw 5/20			+		-						
1W 3/20					<del>                                     </del>	++					
1w 5/25 6/25		50:1	<del>                                     </del>		1-1-						
			1								
nw 9/15											
nw 1/20						$\dashv +$	-				
						1					
mw 7/5			OUCTORY								
SIGNATURE	INCI 6.1	CHAIN OF USIVE DATES/TIMES		TURE	-		_	INCLU	SIVE DA	ATES/TIME	
Talle Many	alle bis	Car 9:38	5	<u> </u>			<del></del>		· · · · · · · · · · · · · · · · · · ·		

	ALTON GI	EOSCIENCE E, STE 140		IN of CUS	47		RD	DAT	E: 6/	26 / DRY:	10	A	v. jor v.Ame	Tr:)	<u>′</u>
	CONCORD, CA 94	520 (415) 682-1582		71105. 7M STM	117				A	NALY:	SIS		AN	ALYS	IS
ROJECT	NUMBER / MANAG	520 (415) 682-1582  GER: 30 - 08/ SAM  S: 8P 0:1 357	H AVE	Ockland	CA	,	ន		BTEX						
HOJECT	OR SPECIAL INS	STRUCTIONS:				:	VBEI NER								
12,10 11 11 10							D IV		4						
							TYPE & NUMBER OF CONTAINERS		0						
							ໄ≽່ວັ		T.						
		LOCATION		SAMPLE	SAMPLE		-		15	ļ	ŀ				
AMPLE UMBER	SAMPLE DATE/TIME	DESCRIPTION		MATRIX	GRAB	СОМР	Brass		1,		$\dashv$				
14.7	6/25			Soil			Steen		17-					-+	
720	6/25			Soil	/		17.5	•							
1W/25	6/25				\										
İ					<del> </del>		<del> </del>		1						
							-								-
									<u> </u>						
			······································				1								
_					-	<del> </del>	-		+	1					<u> </u>
-															-
										<u> </u>					-
				77					_L_						
					_	1									

	!				
	1.7	CHAIN O INCLUSIVE DATES/TIMES	F CUSTODY SIGNATURE	INC	CLUSIVE DATES/TIMES
SIGNATU	Hew Atank	6/26 8:00 Am	4		
6 (4)	1. Marcala	67690 9:35	5		
3.	W TOTTO DE		6		

4	ALTON GEOSCIENCE 1000 BURNETT AVE., STE. 140 CONCORD, CA 94520 (415) 682-1582
	CONCORD, CA 94520 (415) 682-1582

## CHAIN of CUSTODY RECORD

PAGE

ot

DATE: 7 10190 DUEBY:

LABORATORY:

	CONCORD, CA 94	1520 (415) 682-1582	PAGE	- //	4		А	NALYS	SIS	1A	IALYSI	IS
PROJECT PROJECT	NUMBER / MANA	1520 (415) 682-1582  GER: 30 -081 SAME  S: BP 35-++++++++++++++++++++++++++++++++++++	r, Oakland			ER RS						
REMARKS	OR SPECIAL IN	STRUCTIONS:				TYPE & NUMBER OF CONTAINERS	TPH9/BTEX					
SAMPLE	SAMPLE	LOCATION	SAMPLE MATRIX	SAMPLE GRAB	TYPE: COMP.	<u> </u>	5					
NUMBER	DATE/TIME 7/1/90	DESCRIPTION	water	1		3× 40ml	X					
mw-3	4:30 8	mw-3	Water				$ \dot{\nabla} $					
	7/9/90 1:40t	MW-4					$ \cdot\rangle $			-		
	719190	MW-5										
	7/9/70 5:319	MW-6					X		_		-	· · · · · · · · ·
	7/9/90 7:00 e	mw-7	4	ar .		<u> </u>	X					
					<u> </u>							
										-		
								'	<u> </u>	1	<u></u>	<u> </u>
SIGNA	71105	INC	CHAIN OF	CUSTODY SIGNA					INCL	JSIVE D	ATES/I	TIMES

APPENDIX F
Slug Test Data

### SLUG TEST DATA

MW-1 AUGUST 14, 1990

TIME	DRAWDOWN
(min)	(ft)
0.00 0.18 0.52 0.86 1.02 1.12 1.22 1.32 1.83 1.93 2.04 2.14 2.24 2.35	4.17 4.06 3.83 3.73 3.63 3.52 3.42 3.32 3.22 3.13 3.05 2.97 2.91 2.84 2.69
2.35	2.84
2.95	2.69
2.97	2.68

#### SLUG TEST DATA

MW-2 AUGUST 14, 1990

TIME (min)	DRAWDOWN (ft)
0.00	2.92
0.34	2.79
0.49	2.67
0.56	2.55
0.70	2.44
0.80	2.33
1.31	2.22
1.41	2.12
1.51	2.01
<b>.</b>	1.92
1.62	1.84
1.72	
1.82	1.76
2.43	1.62
2.45	1.61

