Mr. Brian Cobb January 13, 1995 Page 2

Field data collected during the sampling event indicate groundwater elevations have increased relative to last quarter. The groundwater appears to flow from the northeast to the south under varying gradients. Analytical results showed no significant change in constituent concentration when compared to historical data. A summary of the depth-to-water measurements, calculated groundwater elevations, and analytical results are included in Table 1. A groundwater contour map, identifying the primary groundwater flow direction on December 5, 1994 and the analytical results from each sample, is included as Figure 1. Field notes, the chain-of-custody form and the laboratory data sheets are included in Attachment A.

If you have any question regarding the information presented herein, please contact one of us at your earliest convenience.

Sincerely,

**BROWN AND CALDWELL** 

Todd Miller Project Manager

Thomas K. Wheeler

California Registered Geologist No. 3925

mas K. Whelle

TM/TKW:evm Attachments

cc: Mr. John Reeves, Attorney at Law

Ms. Madhulla Logan, Alameda County Department of Environmental Health



3480 Buskirk Avenue Pleasant Hill, CA 94523-4342 P.O. Box 8045 Walnut Creek, CA 94596-1220 (510) 937-9010 FAX (510) 937-9026 ALCO HAZBAT \$3UM19 PN 3:58

January 13, 1995

Mr. Brian Cobb E-Z Serve Management Company 2550 N. Loop West, Suite 600 Houston, Texas 77292-2021

11-1564-04/1

Subject:

Fourth Quarter Groundwater Monitoring Report

Former E-Z Serve Station #100877, 525 West A Street, Hayward, California

Dear Mr. Cobb:

Brown and Caldwell conducted the fourth quarter groundwater monitoring event at E-Z Serve Management Company's Former Station #100877, 525 West A Street, Hayward, California on December 5 and 6, 1994. The work performed at the subject site included collecting depth-to-groundwater measurements from 11 groundwater monitoring wells, purging and sampling 10 wells, and submitting the groundwater samples to SPL Inc. (SPL), an analytical laboratory located in Houston, Texas and certified by the State of California Department of Toxic Substance Control for analysis of hazardous materials. Field work was performed following the procedures outlined in Attachment A.

#### **Summary of Findings**

Depth-to-water measurements were collected using an oil-water interface probe. Free product was identified in Well MW-1A, therefore, this well was not sampled. A petroleum odor was identified in Wells MW-3, MW-6, MW-7, MW-9, and MW-10. A minimum of three well volumes was purged from each of the monitoring wells prior to sampling. Samples were collected from each of the monitoring wells, transferred to the appropriate sampling vials, and submitted to SPL under appropriate chain of custody. In addition, a duplicate sample was collected from Well MW-7 and a field blank was prepared prior to sampling Well MW-7. A trip blank was prepared by SPL and accompanied the samples during shipping. SPL reported receiving the samples at a temperature of 3° Celsius. Samples were analyzed by the laboratory for total petroleum hydrocarbons as gasoline (TPHg), benzene, toluene, ethylbenzene, and xylene isomers, following Environmental Protection Agency Methods 8015 modified and 8020.




Figure 1 Groundwater Surface Elevation Contour and Petroleum Hydrocarbon Constituent Distribution Map for December 5, 1994 Former E-Z Serve Station #100877, 525 West A Street, Hayward, California

Table 1. Summary of Groundwater Elevation Data and Analytical Laboratory Results for Groundwater Samples Collected at Former E-Z Serve Station # 100877

525 West A Street, Hayward, California

		Well	Depth	Product	Groundwater			hods 8015 and		
*** ** **	Date	Elevation	to Water	Thickness	Elevation	<del></del>		entration (μg/		
Well I.D.	Sampled	(feet)	(feet)	(feet)	(feet)	ТРНд	Benzene	Toluene	Ethylbenzene	Xylenes
MW-1	5-Feb-92	99.91	20.82		79.09	46,000	76,000	23,000	2,400	6,500
	11-Sep-92		20.08		79.83	48,000	9,000	1,200	1,800	4,600
	22-D∞-92		19.79		80.12	84,000	22,000	1,600	4,800	17,000
	3-Mar-93		16.23		83.68	54,000	16,000	1,600	1,900	4,300
	23-Jun-93	96.73	16.86		79.87	30,000	18,000	1,100	1,400	3,700
	30-Sep-93		18.04		78.69	33,000	10,000	440	940	1,700
	6-Feb-94		18.15		78.58	64,000	18,000	1,600	4,700	12,000
	2-May-94		17.26		79.47	7,200	2,100	29	490	520
	1-Jul-94		17.60		79.13	13,000	3,700	150	550	12,000
	20-Sep-94		20.59	1	76.14	10,000	3,100			870
	5-Dec-94		17.83		78.90	8,700	3,700	87	520	950
MW-1A	23-Jun-93	97.59	17.80	0.21	80.00	ł	Samp	 le Not Analy:	! i zed	
	30-Sep-93		Not Recorded			_	Wel	l Not Sample	d	
	6-Feb-94		18.89		78.70	8,900	1,700	42	1,000	400
	2-May-94		18.35	0.09	79.33			l Not Sample	d	
	1-Jul-94		18.45		79.14	12,000	1,100	<1	920	1,100
	20-Sep-94		21.72	0.22	75.87		Wel	ll Not Sample	d	
	5-Dec-94		18.87	0.07	78.72	l	Wel	l Not Sample	d 1 I	
MW-2	5-Feb-92	101.45	22.35		79.10	67,000	13,000	4,700	820	1,300
	11-Sep-92		21.67		79.78	57,000	9,000	1,400	1,200	8,400
	22-Dec-92		21.39		80.06	31,000	9,900	350	2,000	4,100
	3-Mar-93		17.75		83.70	17,000	5,100	1,300	720	1,900
	23-Jun-93	98.06	18.42		79.64	60,000	23,000	1,500	4,500	17,000
	30-Sep-93		19.63		78.43	38,000	12,000	780	1,500	6,500
	6-Feb-94		19.61		78.45	34,000	8,900	450	2,000	5,500
	2-May-94		19.84		78.22	18,000	3,800		1,100	3,500
	1-Jul-94		19.18		78.88	18,000	3,700	510	870	2,600
	20-Sep-94		22.17		75.89	19,000	4,500	300	1	4,000
	6-Dec-94		19.37		78.69	22,000	4,700	340	1,400	4,500

Table 1. Summary of Groundwater Elevation Data and Analytical Laboratory Results for Groundwater Samples Collected at Former E-Z Serve Station # 100877

525 West A Street, Hayward, California

	Date	Well Elevation	Depth to Water	Product Thickness	Groundwater Elevation			hods 8015 an entration (μg/		
Well I.D.	Sampled	(feet)	(feet)	(feet)	(feet)	ТРНд	Benzene	Toluene	Ethylbenzene	Xylenes
		(1000)	(1334)	(1000)	(1000)	11116	- DOMESTIC	* Oldene	Ediyiochich	Aylenes
MW-3	5-Feb-92	101.50	21.85		79.65	5,900	1,100	<1	<1	<1
	11-Sep-92		21.13		80.37	9,400	1,200		550	1,100
	22-Dec-92	ļ	20.88		80.62	12,000	2,800		1	1,600
	3-Маг-93		17.29		84.21	11,000	2,200	360	570	900
	23-Jun-93	97.66	17.88		79.78	33,000	12,000	2,700	1,300	3,500
	30-Sep-93		19.18		78.48	4,300	1,100		1 [	670
	6-Feb-94		19.21		78.45	20,000	4,800	430	1,500	2,900
	2-May-94		18.30		79.36	4,200	680	48	310	540
	1-Jul-94		18.63		79.03	4,600	600	63	240	470
	20-Sep-94		21.64		76.02	8,200	2,200	130	670	930
	6-Dec-94		19.15		78.51	4,000	640	34	290	480
MW-4	5-Feb-92	100.50	21.31		79.19	16,000	2,700	410	<1	3,400
	11-Sep-92		20.62		79.88	43,000	7,600		1 1	4,100
	22-Dec-92		20.37		80.13	29,000	8,800		1 1	3,700
	3-Mar-93		16.78		83.72	17,000	5,000		1 1	1,700
	23-Jun-93	97.10	17.45		79.65	5,700	3,000	-		790
	30-Sep-93		18.64		78.46	21,000	7,000		1	2,600
	6-Feb-94		18.59		78.51	24,000	7,200			3,200
	2-May-94		17.81		79.29	10,000	2,200	-		1,200
	1-Jul-94		18.13		78.97	8,200	2,000			930
	20-Sep-94		21.13		75.97	7,200	2,000			1,000
	6-Dec-94		18.36		78.74	9,000	2,300			1,100

Table 1. Summary of Groundwater Elevation Data and Analytical Laboratory Results for Groundwater Samples Collected at Former E-Z Serve Station # 100877

525 West A Street, Hayward, California

	Dete	Well	Depth	Product	Groundwater			ods 8015 an		<del> </del>
377-11 T D	Date	Elevation	to Water	Thickness	Elevation			antration (μg/		
Well I.D.	Sampled	(feet)	(feet)	(feet)	(feet)	TPHg	Benzene	Toluene	Ethylbenzene	Xylenes
MW-5	5-Feb-92	100.48	20.93		79.55	78,000	7,900	5,000	2,900	1,800
	11-Sep-92		20.27		80.21	49,000	4,700	400		4,100
	22-Dec-92		19.99		80.49	34,000	8,600	340	1 1	4,800
	3-Mar-93	i	16.49		83.99	22,000	7,500	640	1 1	3,400
	23-Jun-93	96.73	17.02		79.71	15,000	5,800	120	1 1	2,100
	30-Sep-93		18.25		78.48	25,000	7,600	410	1	4,400
	6-Feb-94		18.26		78.47	23,000	6,000	180		5,900
	2-May-94		17.50		79.23	8,000	1,300	29		770
	1-Jul-94		17.79		78.94	10,000	1,700	97	600	1,400
	20-Sep-94	ľ	20.77		75.96	8,400	1,600	54	650	1,400
duplicate	20-Sep-94					9,300	1,700	56	670	1,600
	5-Dec-94		18.02		78.71	10,000	1,800	< 50	620	1,400
MW-6	5-Feb-92	100.97	21.29		79.68	51,000	5,400	3,500	3,600	10,000
	11-Sep-92	·	20.56		80.41	24,000	2,500	830		2,300
	22-Dec-92	i	20.31		80.66	23,000	5,100	630	2,000	3,100
	3-Mar-93		16.83		84.14	18,000	4,400	820	1,400	2,400
	23-Jun-93	97.09	17.30		79.79	18,000	4,600	850	2,700	3,400
	30-Sep-93		19.05	0.03	78.07	•	Sampl	e Not Analyz	red	
	6-Feb-94		18.55		78.54	20,000	4,600	690	2,100	2,500
	2-May-94		17.74		79.35	5,300	930	54	610	240
	1-Jul-94		18.09		79.00	10,000	1,500	160	850	690
	20-Sep-94		21.05		76.04	11,000	2,000	140	1,200	760
	6-Dec-94		18.33		78.76	8,600	1,300	87	980	610

Table 1. Summary of Groundwater Elevation Data and Analytical Laboratory Results for Groundwater Samples Collected at Former E-Z Serve Station # 100877

525 West A Street, Hayward, California

		Well	Depth	Product	Groundwater		EPA Met	hods 8015 and	d 8020	
	Date	Elevation	to Water	Thickness	Elevation		Conc	entration (μg/		
Well I.D.	Sampled	(feet)	(feet)	(feet)	(feet)	TPHg	Benzene	Toluene	Ethylbenzene	Xylenes
									ļ	
MW-7	23-Jun-93	97.44	17.87		79.57	29,000	4,200	71		5,600
	30-Sep-93		18.94		78.50	30,000	3,200			3,400
	6-Feb-94		19.11	0.06	t			le Not Analyz		
	2-May-94		18.11		79.33	5,700		13		400
	1-Jul-94		18.72		78.72		180			520
	20-Sep-94		21.41		76.03	6,100	540			730
	5-Dec-94		18.66		78.78	,	280			350
duplicate	5-Dec-94				1	3,900	310	< 10	540	540
	1				}					
MW-8	23-Jun-93	97.61	17.64		79.97					67
	30-Sep-93		18.85		78.76				170	720
	6-Feb-94	1	18.91		78.70				1	2
	2-May-94		18.11		79.50		<1			7
	1-Jul-94		18.43		79.18		18	1		37
	20-Sep-94	E .	21.43		76.18			1		<1
	5-Dec-94		18.72		78.89	< 50	<0.5	<0.5	<0.5	<0.5
MW-9	23-Jun-93	95.41	15.94		79.47	45,000	14,000	1,200	2,800	12,000
	30-Sep-93		17.05	3	78.36	86,000	•		1	15,000
	6-Feb-94		17.07	4	78.34	-	-			7,500
	2-May-94		16.24		79.17	· ·		li .		4,700
	1-Jul-94		16.59	1	78.82					1,300
	20-Sep-94		19.61	1	75.80	· ·	-			1,200
	5-Dec-94		16.85	1	78.56			ľ	530	1,600
) (TY) 40	22 7 22	07.11	17.00	<u> </u>	<b>30.50</b>	25 000	222	- 40	2.500	10.000
MW-10	23-Jun-93			1	79.72			i	1 3	12,000
	30-Sep-93	1	18.58	B.	78.53					680
	6-Feb-94	1	18.61	i .	78.50					120
	2-May-94	1	17.83	3	79.28					62
	1-Jul-94		18.17		78.94	•				210
	20-Sep-94		21.15	1	75.96				1 3	560
	5-Dec-94	I	18.43	Ī	78.68	2,700	30	13	260	430

Table 1. Summary of Groundwater Elevation Data and Analytical Laboratory Results for Groundwater Samples Collected at Former E-Z Serve Station # 100877

525 West A Street, Hayward, California

	Date	Well Elevation	Depth to Water	Product Thickness	Groundwater Elevation					
Well I.D.	Sampled	(feet)	(feet)	(feet)	(feet)	TPHg	Benzene	Toluene	Ethylbenzene	Xylenes
QA/QC										
Field Blank	20-Sep-94			İ		< 100	<1	<1	<1	<1
Trip Blank	5-Dec-94		}		1 1	<50	<0.5	< 0.5	<0.5	< 0.5
Field Blank	5-Dec-94					< 50	<0.5	< 0.5	<0.5	< 0.5

# ATTACHMENT A

SAMPLING AND ANALYSIS PLAN FIELD NOTES CHAIN-OF-CUSTODY LABORATORY DATA SHEETS

# EZ-SERVE MANAGEMENT COMPANY QUARTERLY GROUNDWATER MONITORING PROGRAM SAMPLING AND ANALYSIS PLAN

The following sections describe the procedures and protocols followed during this quarterly groundwater monitoring event at the subject site.

#### **Depth-to-Water Measurements**

Prior to sampling the groundwater monitoring wells, the wells were opened to the atmosphere for approximately one-quarter of one hour, to allow the static water level to adjust to the open barometric pressure. The depth-to-groundwater was then be measured, using an oil-water interface probe. The interface probe was lowered slowly until free product or water was encountered. At this point, the mark on the interface probe wire was read to the nearest 0.01 feet at the permanent reference point on the top of the well casing. If free product was encountered the probe was lowered until water was encountered. The difference between the two depths corresponds to the thickness of the free product. The total depth of the well was then measured using the same probe. A second check for free-product on top of the water column was made using a disposable bailer. The disposable bailer was lowered into the water to approximately one-half the bailer length. The bailer was then removed from the well and a check for the presence of free petroleum product or a product sheen was made.

In the event that a dedicated bailer or purge tubing existed in the well, the dedicated equipment was removed prior to sampling, and temporarily stored in a clean, plastic garbage bag.

The depth-to-water and bottom of well measurements, and the presence or absence of free product, was recorded on the field sampling form. In addition, comments regarding the condition of the well and/or containment box were also be noted on the field sampling sheet at this time. Wells observed to contain a product sheen or free product on top of the water column were not be purged or sampled.

#### **Groundwater Monitoring Well Purging**

The depth-to-water and bottom of well measurements were used to calculate the volume of water contained in one well volume. The following values were used to calculate the volume of water contained in the well casing and filter pack surrounding the well.

Well Diameter	Gallons/linear foot
2-inch	0.16
4-inch	0.65
8-inch filter pack	0.78
10-inch filter pack	1.21

The minimum purge volume was calculated to be three times the total well volume. Once the minimum purge volume has been calculated purging was started. Purging was conducted using

either a centrifugal pump connected to a dedicated Wattera pump or a pre-cleaned submersible pump, depending on depth to water and the amount of sediment expected to be contained in the well. Temperature, pH, and specific conductance of the purge water was monitored during the purging process at regular intervals. Purging was ceased when the monitored parameters stabilized (three consecutive readings not varying by more than 10-percent) and a minimum of three well volumes had been purged.

In the event a well dried out during purging, the well was allowed to recover to 80-percent of it's original well volume, or for 24-hours, whichever was less, prior to collecting a groundwater sample.

# **Groundwater Monitoring Well Sampling**

Once the well was successfully purged a groundwater sample was collected using a disposable polyethylene bailer connected to clean nylon or polyethylene cord. The bailer was lowered slowly into the water to avoid agitation of the sample. A portion of the sample was placed in a container and the monitoring parameters were recorded. The remaining portion of the sample was transferred from the bailer to the appropriate, laboratory supplied sampling bottles, using a bottom emptying device. The sampling containers were filled completely, leaving a positive meniscus, so no airspace remained in the vial after sealing.

The sample bottles were labeled with the well identification (i.e. MW-1, MW-2, etc), date and time of the sample collection, the field technicians initials, job number, analyses to be performed, and other relevant information. Samples were immediately placed in an insulated cooler containing crushed ice. The samples were maintained at approximately 3°C until reaching the analytical laboratory.

## **Laboratory Analysis**

Samples were shipped, under appropriate chain-of-custody procedures, to SPL Laboratory in Houston. SPL Laboratory is certified by the State of California for performing the requested analyses. Samples were shipped via Federal Express to minimize the time the samples remained in the cooler. Samples were analyzed for total petroleum hydrocarbons as gasoline (TPHg), and benzene, toluene, ethylbenzene, and xylene isomers (BTEX), following Environmental Protection Agency Methods 5030, 8015 modified, and 8020. Samples were analyzed on a standard two week turn-around time.

#### QA/QC Procedures

<u>Instrument calibration.</u> Equipment used to monitor groundwater parameters was calibrated prior to beginning purging at the site. Monitoring equipment was calibrated following the manufactures instructions using laboratory grade standards.

Equipment Decontamination. Non-disposable and non-dedicated sampling equipment was cleaned prior to use and between uses in each well. Downhole equipment was cleaned by

washing the equipment using a non-phosphate soap solution and rinsing the equipment twice with distilled water.

<u>Duplicate</u>. One duplicate sample was collected from the site from a randomly selected monitoring well. The duplicate sample was collected at the same time as the original sample and was treated in the same manner as the original sample. The duplicate sample was submitted to the laboratory for TPHg and BTEX analysis.

<u>Trip Blank.</u> A trip blank was prepared by the analytical laboratory and accompanied the sample bottles throughout the shipping and sampling events. The trip blank was submitted to the laboratory for TPHg and BTEX analysis.

<u>Field Blank.</u> One field blank was collected in the field by the field technician. The field blank was prepared, prior to sampling, by filling three 40-ml VOAs with distilled water. The field blank was submitted to the laboratory for TPHg and BTEX analysis.



# CAN TO FIND OUT IF DRUMS COSTE FEINHE SHIVELER 510 783-9929 FIELD DATA 22042 VICTORY, HAYNARD

,	CE 1 HAS WHILL							
JOB NAME: FE-EEVE - HAYWARD	CLIENT: EE-SERVE							
LOCATION: GARDENAVE & A'ST. HAYWARD, CA	CONTACT: TODO MILLER							
JOB NO: 1564-64	PHONE: 210-227&							
DATE: 12-45,6-94 SECONDARY:								
PROJ. MGR: TOM WHEELER PHONE:								
FIELD PERSONNEL: MCTIVENNA								
SAFETY OFFICER: MC IN FINA HAS PLAN ONSITE? (FEST)	(NO) WEATHER: OFF/ON RATIO CLE	OUDY, COOL - 54°F						
ph instrument: 151 # 3 500 ser. no:	pH 4.0 = <u>4.0</u> pH 7.0 = <u>7</u>	O pH 10.0 = 10.0						
to a to =	SER. NO: INTERNAL CALIBRA							
OTHER INSTRUMENTATION: CKS CIL/WATER INTERFACE	<u> </u>							
ľ								
1)077 = PICKIUP TRAILER : 2 U-HAULTICONO 2)0012 P.CK UP DRUMS (2 WHSE)	40kb:d;it/L, 111;it/							
18)00 12 PICK UT DRUMS (CHARSET, TIL	~~~							
3) 08 10 - LEAVE FOR SITE 4) 09 26 - ARIZINE LITE 6) 09 40 - ISEGIN TAKING SLULS C) 1055 - 7) 1045 - PLACE TRIP BLANK/100877 T.B. IN SITE NOTES: PROAS & WELLS # 306 HAB I								
6) 0940- BEGIN TAKING 31-31-31-31-31-31-31-31-31-31-31-31-31-3	find the second of the second							
10 10 5 5 - 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	aturation and a sure of the su							
7) 1044- PLACE TRUP BLANK/10087E-T.B. A	7 Gootep I I I I I							
SITE NOTES PRIAS A WELLS # 346 HAB I	BEEU DUMPED OVERS, LAVING	outher sides.						
* TEASH HAS BEEN DIMPED N/W CORDER OF * FENCE NEAR MW-3 HAS BEEN FOLHED OVER * FOUND STOLEN FURSE NEAR MW-6, PHONE	TENCED ID. AKEHI DIBAK 124	7402						
* FOUND STOLEN FURSE NEAT MU-6, PHONE	DEPOPULATION OF THE POPULATION							
E) 1100 - CALIBRATE DH, S.C., TEMP. HETERS. FILT-	4.9, 7=7.0,10=19.0 (3.0); 1020=	1097						
9) 1113 - BEGIN FURGING 19W-BIT : T. T.								
11) 1150 - RECLUS TO EXAMPLE	no full of man of hand to comply the form of the first first open of the first open open open open open open open open							
10) 1132 - SAMPLE MW-8 / 1008+7-MW-8 11) 1150 - BCGIN TUZGING MW-9 12) 1209 - SAMPLE MW-9/100877-MW-9	and a second of the second of							
13) 1210 - ALAINEDA SHEELFE APRIVED TO PEPORT O	ON STOLED PURSE : !							
14) 1230 - BEGIN FURGING MW+10-10-10-10-10	of family by form it has been been former and the							
16) 1505 - COLLECT FIELD BLANK ( MW-F, LAB # 1	OOB77-MW-7FI3							
13 1310 - BEGIN FURGING MN-7		- tour from the tour						
18) 404 - SAMPLE MIN-7/100872-MIN-7, 9-12-UPL	ICATE# MW 712/100577-MW-							
19) 1410 - BEGIN FUZGING MW-1.	The test of the second	the first of the first						
* FIRE DEPT. SHOWED UP, HAD RECEIVED CA		ATER INTO						
SEWERS, WAS UNAWAPE DE WEUS 12 SIT		I me I such so al . sud !						
2) 1505-BEGIN TURGING MU 5								
12 1600 - SAMPLE NIW-5/ 100877-MW-5								
JUES 12/6								
DO730 - LEAVE FOR SITE								
The second secon		man, days days days						
	<del>॓</del> ╸┩┵╅┆╼╿┚╈┧╷╄╬┇╇┰╿┺╹┖┽┣							
Irian In Mason - Il Il	Man to Tame the	SHEET NO.						
1564 04 FE-SERVE HAYNARD - 4 TRLY MONITORING 12-56 1/ JOB NUMBER SUBJECT DATE								

1



JOB NAME: EZ-CERVE - HAYWARD	CLIENT: EZ-SERVE						
LOCATION: GARDEN AVE CA' ST., HAYWARD, CA	CONTACT: TODD MILLER						
JOB NO: 1564-04	PHONE: 210-2278						
DATE: 12-6-94	SECONDARY:						
PROJ. MAR: T. WHEELER	PHONE:						
FIELD PERSONNEL: MCTIVENNA							
SAFETY OFFICER: Mª INENNA HAS PLAN ONSITE? (TES) / (NO) WEATHER: KAINING							
pH INSTRUMENT: Y51 # 3500 SER. NO:	ph 4.0 = 4.0 ph 7.0 = 7.0 ph 10.0 = 10.0						
CONDUCTIVITY INSTRUMENT: YSI # 35cc	SER. NO: INTERNAL CALIBRATION PERFORMED (SSV) (NO)						
OTHER INSTRUMENTATION:							
CONT.							
2) CBCO - STAPE TO PREHICUE TI	francial and a state of colors from the first time of the francial business and the first state of the first						
50090-ARRIVE SITE! TIE TIE							
1) 0900 - BEGIN FORMING MW-2 5) 0945 - SAMPLE MW-2/ 100877-MW-2							
SO955 - KEGIN TURGING: MU+4	and be and find your of from a sense between finding from the first beating flows a distinct and before from a banks a super look y from a single from I found yourse a form a sense of the first flower as						
7) 1030 - SAMPLED MW-4/1008577-MW-4	a before a south grown and I grown a final term of the first term of the south of t						
8) 1040 - BEGIN PORGING MIN 3							
9) 1115 - DAMPUE MW-B/100877-MW-3							
10) 1130 - KEGIN FREING MW-6							
1)1270 - SAUTPUE MW-6/100877-MW-6	and the second s						
	grade of many of further comes of further comes of the co						
	and and an area of the contract of the contrac						
	a denter our change good for our by for denter your it was not and care of						
PEVMSCEPT							
1 4-506-123-1	VATER APPROXILIES GAUS !						
10 mm and the second se	to global a design to the control of the same to be a sure of the control of the grant of the gr						
The second of th	a s find of some of small s grown a story of first small grown a dump or some is first some of first small grown in first some of the story of the s						
A control of the cont	on before and done of the body to be for the first of the control						
	The same of the sa						
I a a distribution of the second of the seco	or a final broad of graft a such to final and final or and final or final of grant final of grant final or fina						
	· • • • • • • • • • • • • • • • • • • •						
- I - I - I - I - I - I	SHEET NO.						
1564-8 04 EZ-SEINE HAYWARD - 1/2 JOB NUMBER SUBJ	FECT MONITOIZING 17694 /2						



BROWN & CALDWELL WELL INFORMATION DATA

JOB NAME: EZ-SERVE, HAYWARD

B&C PERSONNEL: MCTIVENNA

WEATHER: CLOUDY, Cook -54°F

INSTRUMENT: DES/OIL, WATER PROBE

DATE: 12-5-94

JOB #: 1564-04

LOCK TYPE: #2+02

LID TYPE: WHEATON

WELL ID	SWL	ΦT	DIA	TIME	COMMENTS
MW-I	17.83	32.10	4"	1025	
MW-IA	18.80',- 18.87	28A0'	2"	1008	FREE PRODUCT07'
MW-Z	19.37	32.30	4"	1029	, EF GAL DRUM KNOCKED OVER,
MW-3	19.15	32.10'	4"	1013	FUEL ODOR / WATER TRUED
MW-4	18,36	32.11	4"	1035	
MW-5	18.02	32.48	4"	1020	, 59 GAL DRUM KNOCKED OVER,
MW-6	18.33	32.10'	4"	1017	FUTE ODAR WATER SPILLED
MW-7	18.66	30.06	2"	1001	Fuel ODOR
MW-8	18.72	32.15	2"	0954	BOX FULL OF WATER
MW-9	16.85	31.60	2"	0940	FUEL ODOR, WATER IN BOX
MW-10	18.43	31.80	U"	0947	NATER IN BOX/FUEL ODOR
,					_
	-				
	-				
	_	-1		•	

GROUNDWATER SAMPLE COLLECTION RI	ECORD
Project Name: EZ-SERVE Job No.: 1514-04  Location: HAYWARD, CA  Samplers Name: MCIIVENNA  Weather Conditions: CLOUDY, COOL - 52°F	Date: 12-5-94
1. WATER LEVEL DATA: (from TOC)  a. Depth to water (ft) = \frac{18.43^{\cdot}}{31.80^{\cdot}}  b. Total Well Depth = \frac{31.80^{\cdot}}{13.37^{\cdot}} (ba.)  d. Casing Volume = \frac{7.13a}{10^{\cdot}} (c. x [gal/ft casing])  e. Length of filter pack = \frac{10^{\cdot}}{10^{\cdot}}  f. Filter pack volume = \frac{5.464}{7.59a} (e. x [gal/ft filter pack])  g. TOTAL WELL VOLUME = \frac{7.59a}{7.59a} (d. + f.)	TOC Elevation (from LS)  Water Table Elev.  Tape Corr. (TC)  Well Dia.  2-in. casing =0.16 gal/ft 4-in. casing =0.65 gal/ft 6-in. casing =1.47 gal/ft 6.5-in. casing =1.7 gal/ft 8-in. casing =2.60 gal/ft 10-in. casing =4.1 gal/ft 12-in. casing =5.0 gal/ft
b. Required Purge Volume (@ 7.59 gallons per well volume) = 22.79 GAL  c. Field Testing; Equipment Used YS 1 #3500 PH, S.C. TEMP.  d. Pump Rate 24PM  e. Method of GW Disposal 55 GAL DRUM  f. Recovery Rate: Slow (90%>60 min), Medium (90% 30-60 min) Fast (90% <	TIMES TOLO.

Volume Removed (gai)	Time	T <sup>o</sup> c	pН	Spec. Conductivity	Turbidity (NTU's)	Color/ Description  Applied Survey ARAY-(area)	SWL	Pump Placement
B	1234	19,7	6.71	839		COUPT, SICTY, GRAT-GREEN, FUEL COOK		30
16	1232	20.2	6.67	848		SAME		
24	1242	20.0	6.77	842		CLEANER, CLEARER		
.5	1248	18.9	6:74	819		SAMPLED		
			[					

3.	SAMPLE COLLECTION:	Method DISP. BAILER Container 3×40m LVOA Preservation HCL Analysis TPH (GAS) 8015, BTEX 8020
CO	MMENTS, REMARKS	LAB # 100877-MW-10

BROWN AND CALDWELL			
GROUNDWATER SAMPLE COLLECTION REC	CORD		
Project Name: EZ. SERVE Job No.: 1564.C4  Location: HAYWARD, CA  Samplers Name: MCIIVENNA	Date:	2-5-	<u> </u>
1. WATER LEVEL DATA: (from TOC)  a. Depth to water (ft) = 17.25  b. Total Well Depth = 32.10  c. Length of Water Column = 14.27 (b a.)  d. Casing Volume = 4.27 (c. x [gal/ft casing])  e. Length of filter pack = 10	TOC Elevation (from Water Table Elev.) Tape Corr. (TC) Well Dia.  2-in. casing 4-in. casing	×8"	
f. Filter pack volume = 6.826 (e. x [gal/ft filter pack])  g. TOTAL WELL VOLUME = 16.676 (d. + f.)  2. WELL PURGING DATA:  Purge Method	6-in. casing 6.5-in. casing 8-in. casing 10-in. casing 12-in. casing	=======================================	= 1.7 gal/ft = 2.60 gal/ft = 4.1 gal/ft = 5.0 gal/ft
b. Required Purge Volume (@ 10.07 gallons per weil volume) = 48.18 GAL  c. Field Testing; Equipment Used YS 1 #3500 PH, S.C. TEMP. H  d. Pump Rate	fach TURB.		
e. Method of GW Disposal 55 GAL DRUM  f. Recovery Rate: Slow (90% > 60 min), Medium (90% 30-60 min) Fast (90% < 10	) min)		
Volume Spec Turbidity C	Color/ scription	SWL	Pump Placement

Volume Removed (gai)	Time	T⁰c	Нq	Spec. Conductivity	Turbidity (NTU's)	Color/ Description CLEAN, CLEAR	SWL	Pump Placement
17	1420	19.3	6.55	1,082			<u> </u>	20
34	1440	20.4	6.48	1,097		SAME		
50	1450	18.9	6.48	1,063		SAME		
,5	1456	19.0	6.55	1,0.20		CAMPLED	-\ -\	
							- \	
	<u> </u>							
								<u> </u>

3.	SAMPL	E COLLE	CTION:	Method Analysi	DISP. BAILER S_TDH (GAS)	Container	3×40ml BTEX 80	10A I	Preservation .	HCL	
CO	MMENT	S, REMA		-	LAB#10087						<u></u>

					MPLE COLLEC			
ect Name:	FZ-	SERVE	HAYL	USAL	Job No.: 1564	7-04 Date:	12-5-9	4
tion:	HAYN	AKD (	14	<u></u>				
nlers Nam	ie:	MCIIV	ENNA					
ther Cond	itions:	Cu	UDY, Co	OL				
						TOC Elevation (	from I S)	
WATER L	EVEL D	ATA: (fn	om TOC)			Water Table Ele		
. Depth to		=	= 18.8	<u>0'-18.</u> 87'/Free	PRODUCT			
. Total W			= 78			Tape Corr. (TC Well Dia.	7." × 6.5	- IL ,
	_			· 53 (b a.)		weil Dia.	0 1010	
c. Length of Water Column = $\frac{9.53}{1.572}$ (c) d. Casing Volume = $\frac{1.572}{9.53}$ (c) e. Length of filter pack = $\frac{9.53}{9.53}$				570 (c. x [28	d/ft casing])	2-in. casin	or :	=0.16 gal/fi
. Length o			_ 9	.53	<u></u>	4-in. casin	g	=0.65  gal/fi
				139 (e. x [ge		6-in. casin	_	= 1.47  gal/ft
. ritter pa	SECTION 1	OT TRA	= - 6.	654 (d. + f.	)	6.5-in. cas 8-in. casin	_	=1.7 gal/ft =2.60 gal/fi
, IUIAL	, WELL	OLUM	E		,	10-in. casi	_	= 4.1  gal/ft
11777 Y T	N ID CINIC	DATA.				12-in. casi	ng	= 5.0 gal/fi
WELL I	PURGING	DAIA:		N/A				
., Purge M	lethod			-11	aluma) — N	/A		
. Required	d Purge V	olume (@	20 g:	Allons per well vo	olume) =N			
. Field Te	sting; Equ	iipment (	Used	11/0				
i. Pump R	ate		<u></u>	N/A N/A				
e. Method	of GW D	isposal _		N/R		(90% < 10 min)N/A	··········	
	y Rate: Sl	ow (90%	6 > 60  min	), Medium (90%	30-60 min), Fast	(90% < 10 mm)		
f. Recover								T
Volume Removed				Spec.	Turbidity	Color/	SWL	Pump Placemen
Volume	Time	T⁰c	Ηg		Turbidity (NTU's)			
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	Turbidity (NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed		T⁰c	Нg	Spec. Conductivity	(NTU's)	Color/ Description		
Volume Removed (gal)	Time	T°c	pH Wethod	Spec. Conductivity	(NTU's)	Color/ Description  N/A  Prese	SWL	Placemen
Volume Removed (gal)	Time	T°c	pH Wethod	Spec. Conductivity	(NTU's)  Container	Color/ Description  N/A  Prese	SWL	Placemen

BROW	, N. 4	Z D (	C A L	DWEL	<u> </u>			NO	
			GRO	UNDWATER SA	MPLE COLL	ECTION REC	ORD		
Project Name: Location:	1AYWA 1e: <u>M</u> Q	RO, (	LA		Job No.: _	OLA·C4	Date:	12-6-9	1
1. WATER I a. Depth to b. Total W c. Length o d. Casing V e. Length o f. Filter pa g. TOTAL 2. WELL I a. Purge M b. Require c. Field Te d. Pump R e. Method	EVEL D. water (ft) fell Depth of Water C Volume of filter pa uck volume . WELL  PURGING fethod d Purge V esting; Equate of GW D	ATA: (fr	om TOC) =   3   1   8   1   1   1   1   1   1   1   1	7.37' 2.30' 3.13' (b a.)	il/ft filter pack  WATER  blume) = 40 PH, S.C.	ERA 6.06-GAL TEMP., H		×8"	
Volume Removed (gal)	Time 0915	T°c 14.3	рН 6.7-1	Spec. Conductivity	Turbidity (NTU's)	MESTLY CLEA FUEL ODOR	Color/ cription FR, SULHIT EANER, CLEARER	SWL	Pump Placement
32	0932	19.3	6.69	1,134		SANE	Colored Correct		
48	0940	18.7	6.70	1,143		SAMPLE	D		
/ク	1 5 1 1	1 10. T	0.10	1,010	ļ <del></del>	<del> </del>			

						,			
3. SAMP	LE COLLI	ECTION:	Method Analysi	DISP. BAILES TOH/GA	R Containe	13×40ml/0A BTEX8020	Preservat	ion <u>HC</u>	
COMMENT	S, REMA		•	LAB# 1					

3 R O W	7. 4	Z D 1	C A L	DWEL	L		Weil	NO. <u>1-1</u>	V
			GRO	UNDWATER SA	MPLE COLL	ECTION REC	ORD		
Project Name: Ocation: H	EZ-S AYWA	SERV RD, (	IE LA		Job No.: _	76A.CA	Date:	12-6-9	4
Samplers Nam	e: Mc	TIVE	ANN						<u>.</u>
Weather Cond				7					
I. WATER L a. Depth to b. Total We c. Length o	water (ft) ell Depth	)	= <u>1</u> = <u>3</u> = 10	9. 15° 32.10° 2.95° (b a.)			FOC Elevation (fro Water Table Elev. Fape Corr. (TC) Well Dia4		
	of filter pa ck volume	ck e V <b>OLUM</b>	$= \frac{6}{1}$ $E = \frac{1}{1}$	3.4   G (c. x [ga 0' .824 (e. x [ga 5.73g (d. + f.	ni/ft filter pack )		2-in. casing 4-in. casing 6-in. casing 6.5-in. casing 8-in. casing 10-in. casing 12-in. casing	# # #	=0.16 gal/ft =0.65 gal/ft =1.47 gal/ft =1.7 gal/ft =2.60 gal/ft =4.1 gal/ft =5.0 gal/ft
c. Field Te	d Purge V sting; Equate	olume (6 uipment 1 5 GP~	@ <u>15.23</u> g Used <u>Y</u> 1	TRASH allons per weil vo 'S 1 #3500	olume) = 4 0 PH, 5.C.	5.71 GAL	ACH TURB.		
f. Recover	y Rate: Sl	low (90 %	6 > 60 min	), Medium (90%	30-60 min),(	Fast (90% < 10	mix)		
Volume Removed (gai)	Time	T⁰c	рĦ	Spec. Conductivity	Turbidity (NTU's)	C Des	olor/ cription 1004, Fuel Obop	SWL	Pump Placement
16	1050	18.5	6.61	1,009			SFJEL OPOR	<u> </u>	1
32	1100	19.5	6.61	1,014		SAME	1.0000000		
47	1110	18.4	6.66	997		SAMPLE	D		
.5	1115	18.4	שייט	, , ,					

3. SAMPLE COLLECTION: Method DISP. BAILER Container 3 40m LVOA Preservation HCL  Analysis TPH (GAS) 8015, BTEX 8020	
COMMENTS, REMARKS	
LAB# 100877-MW-3	

BROWN AND CALDWELL	Won No.
GROUNDWATER SAMPLE COLLECTION	RECORD
Project Name: EZ.SERVE Job No.: 1564.0  Location: HAYWARD, CA  Samplers Name: MCIIVENNA  Weather Conditions: EARLIER RAIN	4 Date: 17-6-94
1. WATER LEVEL DATA: (from TOC)  a. Depth to water (ft) = \frac{18.36}{32.11}  b. Total Well Depth = \frac{32.11}{13.75} (b a.)  d. Casing Volume = \frac{8.939}{10^4} (c. x [gal/ft casing])  e. Length of filter pack = \frac{10^4}{15.759} (e. x [gal/ft filter pack])  g. TOTAL WELL VOLUME = \frac{15.759}{15.759} (d. + f.)	TOC Elevation (from LS)  Water Table Elev.  Tape Corr. (TC)  Well Dia. 4" × 8"  2-in. casing = 0.16 gal/ft 4-in. casing = 0.65 gal/ft 6-in. casing = 1.47 gal/ft 6.5-in. casing = 1.7 gal/ft 8-in. casing = 2.60 gal/ft 10-in. casing = 4.1 gal/ft 12-in. casing = 5.0 gal/ft
2. WELL PURGING DATA:  a. Purge Method  b. Required Purge Volume (@ 15.75 gallons per weil volume) = 47.27 (c. Field Testing; Equipment Used  d. Pump Rate  1.6 GPM  e. Method of GW Disposal  f. Recovery Rate: Slow (90%>60 min), Medium (90% 30-60 min), Fast (90%)	EA GAL C., HACH TUEB.

Volume Removed (gal)	Time	T°c	pН	Spec. Conductivity	Turbidity (NTU's)	Color/ Description	SWL	Pump Placement
10	1005	19.4	6.76	1,075		MOSTLY CLEAN CLEAK, SUGHT FUEL ODDIC		30'
32	1015	19.1	6.72	1,083		CLEANER, CLEARER		
49	1025	19,3	6.71	1,081		SAME		
,5	1030	18.7	6.79	1,053		SAMPLED		
	İ							

3.	SAMPLE COLLECTION	N: Method DISP. BAILER Container 3 40m LVOA Preservation HCL Analysis TDH (GAS) 8015, BTEX 8020	
C <b>O</b>	MMENTS, REMARKS	LAR# 100877-MW-4	<del></del>
_			

	TER SAMPLE COLLECTION I	the second second second second second second second second second second second second second second second se	
roject Name: EE-SERVE  ocation: HAYWARD, CA  amplers Name: MCIIVENNA  Veather Conditions: CLOUCY, CCOL-52	Job No.: 1564.04	1 Date: 12	-5-94
e. Length of filter pack  f. Filter pack volume  g. TOTAL WELL VOLUME = 16.219	(c. x [gal/ft casing]) (e. x [gal/ft filter pack])	TOC Elevation (from L. Water Table Elev.  Tape Corr. (TC)  Well Dia. 4" × 8  2-in. casing 4-in. casing 6-in. casing 6.5-in. casing 8-in. casing 10-in. casing 12-in. casing	=0.16 gal/f =0.65 gal/f =1.47 gal/f
a. Purge Method  b. Required Purge Volume (@  b.cl gallons per c. Field Testing; Equipment Used  d. Pump Rate  1.74 Pm  e. Method of GW Disposal  f. Recovery Rate: Slow (90% > 60 min), Medium	BUM	HACH TUEB.	

Volume Removed (gai)	Time_	T⁰c	рН	Spec. Conductivity	Turbidity (NTU's)	Color/ Description	SWL	Pump Placement
17	1535	19.7	6.50	1,045		CLEAH, CLEAR, FUEL OLDR		30'
34	1545	19,7	6.53	1,050		SAME		
50	1555	19,9	6,48	1,051		SAME		
.5	1600	18.6	6.51	1,062		SAMPLED		
<del></del>								

IL			<u> </u>					
3.	SAMPL	E COLL	ECTION:	Method Analysi	DISP. BAILER S_TDH (GAS)	Container 3 × 40 m L VOA 8015, BTEX 8020	Preservation	HCL
CO	MMENT	S, REM	ARKS	•	100877-MW-5			
				-KB"	ICCOTT NICO 2			

R K O M V 4 V D C 4 F D M F F F		
GROUNDWATER SAMPLE CO	DLLECTION RECORD	
Project Name: <u>FE.SERVE</u> Job No.:  Location: <u>HAYWARD</u> , <u>CA</u> Samplers Name: <u>MCIIVENNA</u> Weather Conditions: <u>RAINING</u> (RECENT)	1564-C4 Date:	12-6-94
1. WATER LEVEL DATA: (from TOC)  a. Depth to water (ft) =  8.33   b. Total Well Depth =  3.77   c. Length of Water Column =  3.77   d. Casing Volume =  8.95a   e. Length of filter pack =  0   f. Filter pack volume =  6.80a   g. TOTAL WELL VOLUME =  5.77a   2. WELL PURGING DATA:  a. Purge Method    7.77   b. required Purge Volume (@  7.77   gallons per well volume) =    c. Field Testing; Equipment Used                        d. Pump Rate                        e. Method of GW Disposal                      f. Recovery Rate: Slow (90% > 60 min), Medium (90% 30-60 min)	6-in. casing 6.5-in. casing 8-in. casing 10-in. casing 12-in. casing 12-in. casing 12-in. casing	= 0.16 gal/ft = 0.65 gal/ft = 1.47 gal/ft = 1.7 gal/ft = 2.60 gal/ft = 4.1 gal/ft
Volume Removed Spec. Turbidi	ty Color/	Pump SWI Placement

Volume Removed (gal)	Time	T⁰c	pН	Spec. Conductivity	Turbidity (NTU's)	Color/ Description CULAY, CLEAR, FUEL ODOR	SWL	Pump Placement
16	1143	20.9	6.42	1,171		cum, cum, pour		36
32	1158	21.0	6.40	1,124		SAME	<u> </u>	
49	1214	21.1	6.44	1,118		SAMPLED		
.5	1220	19.9	6.49	1,084		SAMPLED		
					<u> </u>		<del> </del>	
					<u> </u>			

3.	SAMPL	E COLLECTION:	Method DISP. BAILER Container 3×40m LVoA Preservation HCL Analysis TPH (GAS) 8015, BTEX 8020	<del></del>
CO	MMENT	S. REMARKS		
			LA13#100877-MW-6	

Weather Conditions:    Carry   Cov	BROWN 4	ND C	AL	DWELI	L		Well I	No
Location: HAVMARD   CA    Samplers Name: MCTIVENNA   Weather Conditions:								
1. WATER LEVEL DATA: (from TOC)  a. Depth to water (ft) = 18 \cdot	Location: HAYWA	1RD, U	A			664.C4	Date: 1	2-5-94
b. Required Purge Volume (@ +10 gallons per well volume) = 11.85 GAL  c. Field Testing; Equipment Used YS 1 # 5500 PH S.C. TEMP. HACH TUBB.  d. Pump Rate .40 GPM  e. Method of GW Disposal 55 GAL DRUM  f. Recovery Rate: Slow (90% > 60 min) Medium (90% 30-60 min) Fast (90% < 10 min)  Volume Removed (gal) Time T°c pH Conductivity (NTU's) Description SWL Placement (gal) Time T°c pH Conductivity (NTU's) Tribidity Description SWL Placement 30's Spect (NTU's) SPECT (NTU's) Tribidity Section 30's Spect (NTU's) SPECT (NTU's) Tribidity Section 30's Spect (NTU's) SPECT (NTU's) SPE	a. Depth to water (f b. Total Well Depth c. Length of Water d. Casing Volume e. Length of filter p f. Filter pack volum g. TOTAL WELL 2. WELL PURGIN	Column  ack ne VOLUME	= 18 = 3 = 11 = 1. = 5 = 7.	0.06   .10' (b a.) .864 (c. x [ga 0' .469 (e. x [ga .86 (d. + f.)	l/ft filter pack	w T v	Vater Table Elev ape Corr. (TC) Vell Dia  2-in. casing 4-in. casing 6-in. casing 6.5-in. casing 8-in. casing 10-in. casing	= 0.16 gal/ft = 0.65 gal/ft = 1.47 gal/ft = 1.7 gal/ft = 2.60 gal/ft = 4.1 gal/ft
Volume Removed (gal) Time T°c pH Conductivity (NTU's) Description SWL Placement (NTU's) HEEN-FROMM, FINE SUCK, 30'	b. Required Purge c. Field Testing; Ed d. Pump Rate	Volume (@ quipment U: .40 GI	<u>f.19</u> gi sed <u>Y</u> P14	allons per well vo	$\frac{1}{1000} \frac{1}{1000} = \frac{1}{1000}$ $\frac{1}{1000} \frac{1}{1000} = \frac{1}{1000}$	TEMP., HA		
	Volume Removed (gal) Time	T°c	рН	Spec. Conductivity		Co Desc U REEU - FILLU	olor/	SWL Pump Placemen

Volume Removed (gal)	Time	T⁰c	Нq	Spec. Conductivity	Turbidity (NTU's)	Color/ Description HELEN-FINE SALFS, SHANDS	SWL	Pump Placement
2	1317	20.4	6.64	1,067				
10	1337	19.2	6.60	1091	<u> </u>	SAME		
24	1357	20.5	6.60	1,131		SAME		
.5	1404	18.2	6.67	1,026		SAMPLED		
							<u> </u>	

3.	SAMPLE COLLECTION: Method DISP. BAILER Container 3×40m LVoA Preservation HCL  Analysis TPH (GAS) 8015, BTEX 8020	
CO	IMENTS, REMARKS  LAB # 100877-MW-7 / COLLECT DUPLICATE # 100877-MW-715  COLLECT FIELD BLANK # 100877-MW-7F13	

J R O W IV A N D C A L D	ATER SAMPLE COLL	ECTION RECORD		
		664.04 Date	. 12-5-	94
Project Name: <u>FZ-SERVE</u> ocation: <u>HAYWARD, CA</u>	Job No.: _17	Date		
Somplers Name: MCIIVENNA				
Weather Conditions: CLOUDY, COOL - 5	54°F			
		TOC Elevation		
1. WATER LEVEL DATA: (from TOC)		Water Table E	lev	,, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
a. Depth to water (ft) = $\frac{18.72}{1}$		Tape Corr. (Te	C)	<del> </del>
b. Total Well Depth = $37.15$		Tape Corr. (To Well Dia	2"×6.5	l
c. Length of Water Column = 13.43	(b a.)		, <u>,</u>	
	(c. x [gal/ft casing])	2-in. casi		=0.16 gal/ft
e. Length of filter pack = 10		4-in. casi	-	=0.65 gal/ft
•, ————————————————————————————————————	(e. x [gal/ft filter pack	6-in. casi	_	= 1.47 gal/ft = 1.7 gal/ft
		6.5-in. casi		= 2.60  gal/ft
g. TOTAL WELL VOLUME = $\frac{7.609}{}$	, (u. 1 1.)	10-in. cas	0	= 4.1 gai/ft
		12-in. ca	<b>-</b>	= 5.0 gal/ft
2. WELL PURGING DATA:	OH PUMP W/L	MATERIAL		
				<del></del>
b. Required Purge Volume (@ 7.6 gallons p	er well volume) = $\frac{7}{2}$	2.82 GAL		
c. Field Testing; Equipment Used YS1	F3500 PH, S.C.,	TEMP. HACH TUE	5	•
d. Pump Rate 1.75 GPm				
e. Method of GW Disposal 55 GAL I	SPUM			
e. Memod of Gw Disposal 75 Grib 1	um (00 % 30-60 min) (1	Past (90% < 10 min)		
f. Recovery Rate: Slow (90% > 60 min), Medi	ші (30 % 30-00 інш) (л			<u> </u>
Volume Removed Sp	pec. Turbidity	Color/	SWL	Pump Placement

Volume Removed (gal)	Time	T⁰c	рН	Spec. Conductivity	Turbidity (NTU's)	Color/ Description BROWD, SILTY, SAUDY	SWL	Pump Placement
ج	1118	26.3	6.57	1,062		'		30
ile	1122	20.7	6.60	1,087		CLEANER, STILL FINE SILTS + SANDS		
24	1120	21.3	6.59	1,100		CLEARING		
.5	1132	19.3	6.64	1,062		SAMPLED	<u> </u>	
		ļ	<u> </u>		<u> </u>			
			ļ		ļ		-	
1		1			1			<u> </u>

3.	SAMPLE COLLECTION:	Method DISP. BAILER Container 3×40m LVOA Preservation HCL Analysis TPH (GAS) 8015, BTEX 8020	
co	MMENTS, REMARKS	LAB# 100877-MW-8	

GROUNDWATER	SAMPLE	COLLECTION	RECORI
COUNTRY A LEK			

GROUNDWATE	R SAMPLE COLLECTION R	ECORD	
	Job No.: 1564.C4	Date:	2-5-94
Location: HAYWARD, CA			
Samplers Name: MCIIVENNA Weather Conditions: CLOUDY, COOL -54°F			
		TOC Elevation (from	n LS)
1. WATER LEVEL DATA: (from TOC)		Water Table Elev.	
a. Depth to water (ft) = $16.85$		<b>~</b> (TC)	
b. Total Well Depth $= 31.60^4$		Well Dia	"×6,5"
c. Length of Water Column = 14.75' (b. d. Casing Volume = 1.369 (c. e. Length of filter pack = 10' = 1.469 (e. g. TOTAL WELL VOLUME = 7.979 (d.	x [gal/ft casing])  x [gal/ft filter pack])  + f.)	2-in. casing 4-in. casing 6-in. casing 6.5-in. casing 8-in. casing 10-in. casing	=0.16 gal/ft =0.65 gal/ft =1.47 gal/ft =1.7 gal/ft =2.60 gal/ft =4.1 gal/ft
1 RA	SH W/WATERRA		
a. Purge Method  b. Required Purge Volume (@ 7.87 gallons per w c. Field Testing; Equipment Used YS 1 # 3 d. Pump Rate 2 GPM e. Method of GW Disposal 55 GAL DE f. Recovery Rate: Slow (90% > 60 min), Medium	well volume) = $\frac{23.46 \text{ CA}}{500 \text{ PH, S.C., TEMP.}}$		
Volume Removed Spec. (gal) Time Toc pH Conducti	Turbidity	Color/ Description AY, HEANY FUEL COOR,	SWL Pump Placement

Volume Removed (gai)	Time	Tºc_	рН	Spec. Conductivity	Turbidity (NTU's)	Color/ Description  GREEN-GRAY, HEAVY FUEL COOR, FINE SICTS, SANDS	SWL	Pump Placement
В	1055	19.9	6,56	1,084		SOME CLEAKING		1
16	1159	70.0	6.54	1,098				1
24	1203	20,5	6.55	1,097		SAME SAMPLED		
.5	1209	18.7	6.60	1,037		SAMPLED		
							<u> </u>	<u> </u>
							<u> </u>	
	<u> </u>							
<u> </u>	<del> </del>						<u> </u>	<u> </u>
	<del> </del>	<del> </del>					<u> </u>	<u> </u>

3. S.	AMPL	E COL	LECTION:	Method Analys	DISP. BAILER is TPH (GAS)	Container 3 × 40 m L VOA 8015, BTEX 8020	Preservation _	HCL
			MARKS		B# 100877			



# SPL, INC.

# REPORT APPROVAL SHEET

WORK ORDER NUMBER: 94-12 - 312

Approved for release by:

Date: 17/13/94

Brent Barron, Project Manager

S. Sample, Laboratory Director



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

PROJECT NO: 1564-04

PROJECT: EZ Serve #100877 MATRIX: LIQUID SITE: Hayward, CA

DATE SAMPLED: 12/05/94 10:45:00 SAMPLED BY: Provided by SPL

DATE RECEIVED: 12/07/94 **SAMPLE ID:** 100877-TB

ANALYTICA	L DATA			
PARAMETER		RESULTS	DETECTION	UNITS
			LIMIT	4-
BENZENE		ND	0.5 P	μg/I
TOLUENE		ND	0.5 P	μg/I
ETHYLBENZENE		ND		μg/I
TOTAL XYLENE		ND	0.5 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBON	S	ND		μg/I
Surrogate	% R	Recovery		
1,4-Difluorobenzene		102		
4-Bromofluorobenzene		86		
METHOD 8020***				
Analyzed by: YN				
Date: 12/11/94				
Petroleum Hydrocarbons - Gasoline		ND	0.1 P	mg/L
Surrogate	% F	Recovery		
1,4-Difluorobenzene		95		
4-Bromofluorobenzene		79		
Modified 8015 - Gasoline				
Analyzed by: YN				
Date: 12/11/94				

ND - Not detected.

(P) - Practical Quantitation Limit

DATE: 01/13/95

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

- Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

PROJECT: EZ Serve #100877 **PROJECT NO: 1564-04** 

MATRIX: LIOUID **SITE:** Hayward, CA **SAMPLED BY:** Brown & Cadwell

DATE SAMPLED: 12/05/94 11:32:00 DATE RECEIVED: 12/07/94 **SAMPLE ID:** 100877-MW-8

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	ND	0.5 P	μg/L
TOLUENE	ND		μg/L
ETHYLBENZENE	ND		μg/L
TOTAL XYLENE	ND	0.5 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	ND		μg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	108		
4-Bromofluorobenzene	115		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	ND	0.05 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	110		
4-Bromofluorobenzene	83		
Modified 8015 - Gasoline			
Analyzed by: YN			
Date: 12/09/94			

ND - Not detected.

(P) - Practical Quantitation Limit

DATE: 01/13/95

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

DATE: 01/13/95

PROJECT: EZ Serve #100877

SITE: Hayward, CA

MATRIX: LIQUID

**PROJECT NO: 1564-04** 

**SAMPLED BY:** Brown & Cadwell

DATE SAMPLED: 12/05/94 12:09:00 DATE RECEIVED: 12/07/94

**SAMPLE ID:** 100877-MW-9

ANALYTICAI	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	2700	10 P	μg/L
TOLUENE	130	10 P	μg/L
ETHYLBENZENE	530	10 P	$\mu$ g/L
TOTAL XYLENE	1600	10 P	$\mu { m g/L}$
TOTAL VOLATILE AROMATIC HYDROCARBONS	4960		$\mu { m g/L}$
Surrogate	% Recovery		
1,4-Difluorobenzene	129		
4-Bromofluorobenzene	117		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	10	1.0 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	136 «		
4-Bromofluorobenzene	88		
Modified SOIE - Casalina		,	

Modified 8015 - Gasoline

Analyzed by: YN

Date: 12/09/94

(P) - Practical Quantitation Limit « - Recovery beyond control limits.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed.

\*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

DATE: 01/13/95

PROJECT: EZ Serve #100877

**SITE:** Hayward, CA

Analyzed by: YN

Date: 12/10/94

PROJECT NO: 1564-04
MATRIX: LIOUID

SAMPLED BY: Brown & Cadwell

DATE SAMPLED: 12/05/94 12:48:00 DATE RECEIVED: 12/07/94

**SAMPLE ID:** 100877-MW-10 **DATE RECEIVED:** 12/07/94

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION LIMIT	UNITS
BENZENE	30	1 P	$\mu { m g/L}$
TOLUENE	13	1 P	μg/L
ETHYLBENZENE	260	1 P	$\mu {f g}/{f L}$
TOTAL XYLENE	430	1 P	$\mu { m g/L}$
TOTAL VOLATILE AROMATIC HYDROCARBONS	733		$\mu$ g/L
Surrogate	% Recovery		
1,4-Difluorobenzene	130		
4-Bromofluorobenzene	146 «		
METHOD 8020***			
Analyzed by: YN			
Date: 12/10/94			
Petroleum Hydrocarbons - Gasoline	2.7	0.1 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	211 «		
4-Bromofluorobenzene	151 «		
Modified 8015 - Gasoline			

(P) - Practical Quantitation Limit « - Recovery beyond control limits.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA

\*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed.

\*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance.

SPL California License # 1903

SPL, Inc., - Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

**PROJECT NO: 1564-04** 

PROJECT: EZ Serve #100877

MATRIX: LIQUID

**SITE:** Hayward, CA **SAMPLED BY:** Brown & Cadwell

DATE SAMPLED: 12/05/94 13:05:00 DATE RECEIVED: 12/07/94

DATE: 01/13/95

**SAMPLE ID:** 100877-MW-7 FB

ANALYTICAL I	ATA		
PARAMETER	RESULTS	DETECTION	UNITS
	170	LIMIT	/ T
BENZENE	ND	0.5 P	μg/L
TOLUENE	ND		μg/L
ETHYLBENZENE	ND		μg/L
TOTAL XYLENE	ND	0.5 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	ND		μg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	105		
4-Bromofluorobenzene	109		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	ND	0.05 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	108		
4-Bromofluorobenzene	81		
Modified 8015 - Gasoline			
Analyzed by: YN			
Date: 12/09/94			

ND - Not detected.

(P) - Practical Quantitation Limit

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed.

\*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

PROJECT NO: 1564-04

PROJECT: EZ Serve #100877
SITE: Hayward, CA

MATRIX: LIQUID

SAMPLED BY: Brown & Cadwell

DATE SAMPLED: 12/05/94 14:04:00

DATE: 01/13/95

**SAMPLE ID:** 100877-MW-7

DATE RECEIVED: 12/07/94

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	280	10 P	μg/L
TOLUENE	ND	10 P	μg/L
ETHYLBENZENE	430	10 P	μg/L
TOTAL XYLENE	350	10 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	1060		μg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	110		
4-Bromofluorobenzene	122		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	3.7	1.0 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	122		
4-Bromofluorobenzene	95		
Modified 8015 - Gasoline			
Analyzed by: YN			
Date: 12/09/94			
,,			

<sup>(</sup>P) - Practical Quantitation Limit ND - Not detected.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance.

SPL California License # 1903

SPL, Inc., - Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

DATE: 01/13/95

PROJECT: EZ Serve #100877

SITE: Hayward, CA

PROJECT NO: 1564-04
MATRIX: LIQUID

**SAMPLED BY:** Brown & Cadwell

DATE SAMPLED: 12/05/94 14:04:00

**SAMPLE ID:** 100877-MW-7D **DATE RECEIVED:** 12/07/94

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	310	10 P	$\mu$ g/L
TOLUENE	ND	10 P	μg/L
ETHYLBENZENE	540	10 P	μg/L
TOTAL XYLENE	540	10 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	1390		μg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	108		
4-Bromofluorobenzene	94		
METHOD 8020***			
Analyzed by: YN			
Date: 12/11/94			
Petroleum Hydrocarbons - Gasoline	3.9	1.0 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	89		
4-Bromofluorobenzene	64		
Modified 8015 - Gasoline			
Analyzed by: YN			
Date: 12/11/94			
3,,			

<sup>(</sup>P) - Practical Quantitation Limit ND - Not detected.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance.

SPL California License # 1903

SPL, Inc., - Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

DATE: 01/13/95

PROJECT: EZ Serve #100877

SITE: Hayward, CA

PROJECT NO: 1564-04 MATRIX: LIQUID

**SAMPLED BY:** Brown & Cadwell **SAMPLE ID: 100877-MW-1D** 

DATE SAMPLED: 12/05/94 14:56:00

DATE RECEIVED: 12/07/94

ANALYTICA	L DATA		
PARAMETER	RESULTS	DETECTION LIMIT	UNITS
BENZENE	3700	50 P	μg/I
TOLUENE	87	50 P	μg/I
ETHYLBENZENE	520	50 P	μg/L
TOTAL XYLENE	950	50 P	$\mu$ g/L
TOTAL VOLATILE AROMATIC HYDROCARBON	S 5257		μg/I
Surrogate	% Recovery		
1,4-Difluorobenzene	$11\overline{2}$		
4-Bromofluorobenzene	111		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	8.7	1.0 P	mg/I
Surrogate	% Recovery		
1,4-Difluorobenzene	97		
4-Bromofluorobenzene	66		
Modified 8015 - Gasoline			
Analyzed by: YN			
Date: 12/11/94			

#### (P) - Practical Quantitation Limit

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

- Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

**PROJECT NO: 1564-04** 

PROJECT: EZ Serve #100877 **SITE:** Hayward, CA

MATRIX: LIOUID

**SAMPLED BY:** Brown & Cadwell

Date: 12/09/94

DATE SAMPLED: 12/05/94 16:00:00

DATE: 01/13/95

**SAMPLE ID: 100877-MW-5D** 

DATE RECEIVED: 12/07/94

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION LIMIT	UNITS
BENZENE	1800	50 P	μg/L
TOLUENE	ND	50 P	μg/L
ETHYLBENZENE	620	50 P	μg/L
TOTAL XYLENE	1400	50 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	3820		$\mu { m g/L}$
Surrogate	% Recovery		
1,4-Difluorobenzene	109		
4-Bromofluorobenzene	110		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	10	5.0 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	115		
4-Bromofluorobenzene	82		
Modified 8015 - Gasoline			
Analyzed by: YN			

(P) - Practical Quantitation Limit ND - Not detected.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed.

\*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

- Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

PROJECT NO: 1564-04

DATE: 01/13/95

PROJECT: EZ Serve #100877 MATRIX: LIOUID SITE: Hayward, CA

DATE SAMPLED: 12/06/94 09:45:00 **SAMPLED BY:** Brown & Cadwell

**SAMPLE ID:** 100877-MW-2 DATE RECEIVED: 12/07/94

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	4700	5 P	μg/L
TOLUENE	340	5 P	μg/L
ETHYLBENZENE	1400	5 P	μg/L
TOTAL XYLENE	4500	5 P	$\mu { m g}/{ m L}$
TOTAL VOLATILE AROMATIC HYDROCARBONS	10940		$\mu g/L$
Surrogate	% Recovery		
1,4-Difluorobenzene	100		
4-Bromofluorobenzene	142 «		
METHOD 8020***			
Analyzed by: DAO			
Date: 12/08/94			
Petroleum Hydrocarbons - Gasoline	22	0.5 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	189 «		
4-Bromofluorobenzene	124		
Modified 8015 - Gasoline	<del></del>		
Analyzed by: DAO			
mary sea sy. she			

(P) - Practical Quantitation Limit « - Recovery beyond control limits.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance

with EPA guidelines for quality assurance. SPL California License # 1903

Date: 12/08/94

Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

DATE: 01/13/95

PROJECT: EZ Serve #100877

SITE: Hayward, CA

MATRIX: LIQUID

**PROJECT NO: 1564-04** 

**SAMPLED BY:** Brown & Cadwell

Date: 12/09/94

DATE SAMPLED: 12/06/94 10:30:00

DATE RECEIVED: 12/07/94 **SAMPLE ID:** 100877-MW-4

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	2300	5 P	μg/L
TOLUENE	400	5 P	μg/L
ETHYLBENZENE	440	5 P	μg/L
TOTAL XYLENE	1100	5 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	4240		μg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	143 «		
4-Bromofluorobenzene	118		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	9.0	0.5 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	157 «		
4-Bromofluorobenzene	92		
Modified 8015 - Gasoline			
Analyzed by: YN			

(P) - Practical Quantitation Limit « - Recovery beyond control limits.

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed.

\*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

PROJECT NO: 1564-04

DATE: 01/13/95

PROJECT: EZ Serve #100877 MATRIX: LIQUID **SITE:** Hayward, CA

DATE SAMPLED: 12/06/94 11:15:00 **SAMPLED BY:** Brown & Cadwell

DATE RECEIVED: 12/07/94 **SAMPLE ID: 100877-MW-3** 

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	640	25 P	μg/L
TOLUENE	34	25 P	μg/L
ETHYLBENZENE	290	25 P	$\mu$ g/L
TOTAL XYLENE	480	25 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	1444		μg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	112		
4-Bromofluorobenzene	111		
METHOD 8020***			
Analyzed by: YN			
Date: 12/09/94			
Petroleum Hydrocarbons - Gasoline	4.0	2.5 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	115		
4-Bromofluorobenzene	84		
Modified 8015 - Gasoline			
Analyzed by: YN			

#### (P) - Practical Quantitation Limit

Date: 12/09/94

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed. \*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

Project Manager



EZ Serve Inc.

2550 North Loop West, #600

Houston, TX 77292 ATTN: Brian Cobb

DATE: 01/13/95

PROJECT: EZ Serve #100877

**SITE:** Hayward, CA

MATRIX: LIQUID **SAMPLED BY:** Brown & Cadwell

**SAMPLE ID:** 100877-MW-6

DATE SAMPLED: 12/06/94 12:20:00 DATE RECEIVED: 12/07/94

**PROJECT NO: 1564-04** 

ANALYTICAL	DATA		
PARAMETER	RESULTS	DETECTION	UNITS
		LIMIT	
BENZENE	1300	25 P	μg/L
TOLUENE	87	25 P	μg/L
ETHYLBENZENE	980	25 P	$\mu g/L$
TOTAL XYLENE	610	25 P	μg/L
TOTAL VOLATILE AROMATIC HYDROCARBONS	2977		$\mu g/L$
Surrogate	% Recovery		
1,4-Difluorobenzene	96		
4-Bromofluorobenzene	90		
METHOD 8020***			
Analyzed by: YN			
Date: 12/11/94			
Petroleum Hydrocarbons - Gasoline	8.6	2.5 P	mg/L
Surrogate	% Recovery		
1,4-Difluorobenzene	92		
4-Bromofluorobenzene	63		

#### (P) - Practical Quantitation Limit

Date: 12/11/94

Modified 8015 - Gasoline

Analyzed by: YN

Notes: \*Ref: Methods for Chemical Analysis of Water and Wastes, 1983, EPA \*\*Ref: Standard Methods for Examination of Water & Wastewater, 17th ed.

\*\*\*Ref: Test Methods for Evaluating Solid Waste, EPA SW846, 3rd Ed.

QUALITY ASSURANCE: These analyses are performed in accordance with EPA guidelines for quality assurance. SPL California License # 1903

# QUALITY CONTROL DOCUMENTATION



## \* SPL BATCH QUALITY CONTROL REPORT \*\* METHOD 8020

PAGE 1

Matrix: Units: Aqueous µg/L Batch Id: HP\_R941208051500

#### LABORATORY CONTROL SAMPLE

SPIKE	Method	Spike	Blani	k Spike	QC Limits(**)		
COMPOUNDS	Blank Result <2>	Added <3>	Result <1>	Recovery %	(Mandatory) % Recovery Range		
Benzene	ND	50	46	92.0	54 - 126		
Toluene	ND	50	45	90.0	61 - 125		
EthylBenzene	ND	50	43	86.0	57 - 129		
O Xylene	ND	50	44	88.0	32 - 160		
1 & P Xylene	ND	100	91	91.0	32 - 160		

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix	\$pi ke	Matrix Dupli	Spike cate	MS/MSD Relative %		.imits(***) (Advisory)
	<b>&lt;2&gt;</b>	<3>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery Range
Benzene	NO	20	21	105	20	100	4.88	19	61 - 131
Toluene	ND	20	20	100	18	90.0	10.5	18	57 - 127
EthylBenzene	ND	20	19	95.0	18	90.0	5.41	18	55 - 131
0 Xylene	ND	20	18	90.0	17	85.0	5.71	20	40 - 130
M & P Xylene	ND	40	35	87.5	32	80.0	8.96	16	43 - 152

Analyst: DAO

Sequence Date: 12/08/94

SPL ID of sample spiked: 9412220-06A

Sample File ID: R\_\_\_312.TX0

Method Blank File ID:

Blank Spike File ID: R\_\_\_303.TX0
Matrix Spike File ID: R\_\_\_306.TX0

Matrix Spike Duplicate File ID: R\_\_\_309.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit

% Recovery = [( <1> - <2> ) / <3> ] x 100

LCS % Recovery = (<1> / <3>) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data (\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412310-04A 9412310-03A 9412310-01A 9412309-05A 9412309-04A 9412309-03A 9412309-02A 9412309-01A 9412304-03A 9412153-04A 9412152-01A 9412220-04A 9412220-03A 9412220-02A 9412220-01A 9412220-06A 9412219-07A



## \* SPL BATCH QUALITY CONTROL REPORT \*\* METHOD 8020

PAGE 1

Matrix: Units: Aqueous µg/L Batch Id: HP\_R941209021600

#### LABORATORY CONTROL SAMPLE

Method Blank Result <2>	Spike Added <3>	Result Recovery		QC Limits(**) (Mandatory) % Recovery Range		
ND	50	50	100	54 - 126		
ND	50	48	96.0	61 - 125		
ND	50	48	96.0	57 - 129		
ND	50	47	94.0	32 - 160		
ND	100	100	100	32 - 160		
	Blank Result <2> ND ND ND ND	Blank Result	Blank Result	Blank Result   Added   Result   Recovery		

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix	Spike	Matrix Dupli	Spike cate	MS/MSD Relative %		.imits(***) (Advisory)
	<2>	<3>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery Range
Benzene	ND	20	26	130	25	125	3.92	19	61 - 131
Toluene	OM	20	25	125	24	120	4.08	18	57 - 127
EthylBenzene	ND	20	25	125	23	115	8.33	18	55 - 131
O Xylene	ND	20	24	120	23	115	4.26	20	40 - 130
M & P Xylene	ND	40	46	115	43	108	6.28	16	43 - 152

Analyst: DAO

Sequence Date: 12/09/94

SPL ID of sample spiked: 9412310-06A

Sample File ID: R\_\_\_345.TX0

Method Blank File ID:

Blank Spike File ID: R\_\_\_338.TX0
Matrix Spike File ID: R\_\_\_347.TX0

Matrix Spike Duplicate File ID: R 349.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit

% Recovery = [(<1> - <2>) / <3>] x 100

LCS % Recovery = (<1> / <3>) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data

(\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412312-08A 9412312-09A 9412312-12A 9412312-06A 9412221-05A 9412312-03A 9412220-05A 9412220-08A

9412220-07A 9412312-11A 9412312-05A 9412312-02A

9412310-06A 9412310-05A



## \* SPL BATCH QUALITY CONTROL REPORT \*\* METHOD 8020

PAGE 1

Matrix: Units: Aqueous µg/L Batch Id: HP\_R941210233500

#### LABORATORY CONTROL SAMPLE

SPIKE	Method	Spike	Blani	C Spike	QC Limits(**) (Mandatory) % Recovery Range		
COMPOUNDS	Blank Result <2>	Added <3>	Result <1>	Recovery %			
Benzene	ND	50	51	102	54 - 126		
Toluene	ND	50	49	98.0	61 - 125		
EthylBenzene	ND	50	49	98.0	57 - 129		
0 Xylene	ND	50	47	94.0	32 - 160		
M & P Xylene	ND	100	100	100	32 - 160		

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix Spike		Matrix Spike Duplicate				QC Limits(***) (Advisory)		
	<2>	<b>&lt;3&gt;</b>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery	Range	
Benzene	38	20	64	130	57	95.0	31.1 *	19	61 -	131	
Toluen <del>e</del>	21	20	44	115	39	90.0	24.4 *	18	57 -	127	
EthylBenzene	ND	20	22	110	20	100	9.52	18	55 -	131	
0 Xylene	10	20	32	110	26	80.0	31.6 *	20	40 -	130	
M & P Xylene	18	40	61	108	54	90.0	18.2 *	16	43 -	152	

Analyst: YN

Sequence Date: 12/09/94

SPL ID of sample spiked: 9412354-01A

Sample File ID: R\_\_\_394.TXO Method Blank File ID:

Blank Spike File ID: R\_\_377.TX0
Matrix Spike File ID: R\_412.TX0

Matrix Spike Duplicate File ID: R\_\_\_413.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit % Recovery = [( <1> - <2> ) / <3> ] x 100

LCS % Recovery = (<1> / <3>) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data (\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412346-03A 9412346-02A 9412346-04A 9412346-01A 9412352-09A 9412352-05A 9412352-06A 9412352-07A 9412352-08A 9412352-03A 9412352-04A 9412354-01A 9412221-07A 9412221-04A 9412220-11A 9412220-09A 9412219-05A 9412312-04A 9412220-12A



#### SPL BATCH QUALITY CONTROL REPORT \*\* METHOD 8020

PAGE 1

Matrix: Units:

Aqueous μg/L

Batch Id: HP\_S941211184600

#### LABORATORY CONTROL SAMPLE

SPIKE	Hethod	Spike	Blank	Spike	QC Limits(**) (Mandatory) % Recovery Range		
COMPOUNDS	Blank Result <2>	Added <3>	Result <1>	Recovery %			
Benzene	ND	50	49	98.0	54 - 126		
Toluene	ND	50	52	104	61 - 125		
EthylBenzene	ND	50	54	108	57 - 129		
0 Xylene	ND	50	54	108	32 - 160		
4 & P Xylene	ND	100	120	120	32 - 160		
	1 1		1				

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix Spike		Matrix Spike Duplicate		MS/MSD Relative %	QC Limits(***) (Advisory)		
	<2>	<3>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery Range	
Benzene	ND	20	18	90.0	18	90.0	0	19	61 - 131	
Toluene	ND	20	22	110	23	115	4.44	18	57 - 127	
EthylBenzene	ND	20	21	105	22	110	4.65	18	55 - 131	
O Xylene	ND	20	18	90.0	17	85.0	5.71	20	40 - 130	
M & P Xylene	ND	40	42	105	37	92.5	12.7	16	43 - 152	

Analyst: YN

Sequence Date: 12/10/94

SPL ID of sample spiked: 9412353-08A

Sample File ID: SS\_\_052.TX0

Method Blank File ID:

Blank Spike File ID: SS\_\_021.TXO Matrix Spike File ID: SS\_056.TX0

Matrix Spike Duplicate File ID: SS\_\_059.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit

% Recovery = [( <1> - <2> ) / <3> ] x 100

LCS % Recovery = (<1> / <3>) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data

(\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412312-04A 9412312-05A 9412353-08A 9412312-13A 9412312-11A 9412312-09A 9412312-03A 9412353-05A 9412312-07A 9412312-06A 9412312-08A 9412354-04A 9412354-02A 9412354-03A 9412221-01A 9412221-03A 9412221-08A 9412221-06A 9412312-01A 9412221-09A



## \* SPL BATCH QUALITY CONTROL REPORT \*\* Modified 8015 - Gasoline

PAGE 1

Matrix: Units: Aqueous

Batch Id: HP\_R941208063800

#### LABORATORY CONTROL SAMPLE

SPIKE	Method	Spike	Blank	Spike	QC Limits(**)
COMPOUNDS	Blank Result <2>	Added <3>	Result <1>	Recovery %	(Mandatory) % Recovery Range
Petroleum Hydrocarbons	ND	0.90	1.00	111	56 - 139

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix	Spike	Matrix Dupli	Spike cate	MS/MSD Relative %	QC Limits(***) (Advisory)			
	<b>&lt;2&gt;</b>	∢3>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery Range		
Petroleum Hydrocarbons	ND	0.9	0.85	94.4	0.77	85.6	9.78	18	40 - 158		

Analyst: DAO

Sequence Date: 12/08/94

SPL ID of sample spiked: 9412220-01A

Sample File ID: RR\_313.TX0

Method Blank File ID:

Blank Spike File ID: RR\_304.TX0
Matrix Spike File ID: RR 305.TX0

Matrix Spike Duplicate File ID: RR\_\_308.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit
% Recovery = [( <1> - <2> ) / <3> ] x 100
LCS % Recovery = (<1> / <3> ) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data (\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412310-04A 9412310-03A 9412310-01A 9412309-05A 9412309-04A 9412309-03A 9412309-02A 9412309-01A 9412304-03A 9412153-04A 9412152-01A 9412220-01A 9412220-01A 9412220-01A 9412220-01A



## \* SPL BATCH QUALITY CONTROL REPORT \*\* Modified 8015 - Gasoline

PAGE 1

Matrix: Units: Aqueous mg/L Batch Id:

HP\_R941209031100

#### LABORATORY CONTROL SAMPLE

SPIKE	Method	Spike	Blank	Spike	QC Limits(**)
COMPOUNDS	Blank Result <2>	Added <3>	Result <1>	Recovery %	(Mandatory) % Recovery Range
Petroleum Hydrocarbons	ND	0.9	1.0	111	56 - 139

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix	Spike	Matrix Dupli	Spike cate	MS/MSD Relative %	QC Limits(***)(Advisory)			
	<2>	<3>	Result <1>	Recovery <4>	Result	Recovery <5>	Difference	RPD Max.	Recovery Range		
Petroleum Hydrocarbons	0.7	0.9	1.84	127	1.63	103	20.9 *	18	40 - 158		

Analyst: DAO

Sequence Date: 12/09/94

SPL ID of sample spiked: 9412310-05A

Sample File ID: RR 344.TX0

Method Blank File ID:

Blank Spike File ID: RR\_337.TX0
Matrix Spike File ID: RR\_346.TX0

Matrix Spike Duplicate File ID: RR\_350.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit % Recovery = [(<1> - <2>) / <3>] x 100 LCS % Recovery = (<1> / <3>) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data (\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412310-02A 9412312-09A 9412312-12A 9412312-06A 9412221-05A 9412220-05A 9412220-05A 9412220-05A 9412312-05A 9412312-02A 9412310-06A 9412310-05A



PAGE 1

Matrix: Units: Aqueous mg/L Batch Id: HP\_R941210125600

#### LABORATORY CONTROL SAMPLE

S P I K E C O M P O U N D S	Method Blank Result	Spike Added <3>	Blank Result <1>	Spike Recovery	_ QC Limits(**) (Mandatory) % Recovery Range
Petroleum Hydrocarbons	<2>	0.9	1.03	114	56 - 139

#### MATRIX SPIKES

SPIKE COMPOUNDS	Sample Results	Spike Added	Matrix Spike		Matrix Spike Duplicate		MS/MSD Relative %	QC Limits(***) (Advisory)		
	<2>	<3>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery Range	
Petroleum Hydrocarbons	ND	0.9	.57	22.8 *	.80	88.9	118 *	18	40 - 158	

Analyst: YN

Sequence Date: 12/10/94

SPL ID of sample spiked: 9412352-04A

Sample File ID: RR 395.TX0

Method Blank File ID:

Blank Spike File ID: RR\_380.TX0
Matrix Spike File ID: RR\_414.TX0

Matrix Spike Duplicate File ID: RR\_415.TXO

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit % Recovery = [( <1> - <2> ) / <3> ] x 100

LCS % Recovery = (<1> / <3> ) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data (\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412346-03A 9412346-04A 9412346-01A 9412352-09A 9412352-05A 9412352-06A 9412352-07A 9412352-08A 9412352-10A 9412352-03A 9412352-04A 9412352-09A 9412221-04A 9412220-11A 9412220-09A 9412312-04A 9412220-12A



## \* SPL BATCH QUALITY CONTROL REPORT \*\* Modified 8015 - Gasoline

Matrix: Units: Aqueous

Batch Id: HP\_\$941210193900

#### LABORATORY CONTROL SAMPLE

SPIKE	Method	Spike	Blank	Spike	QC Limits(**)
COMPOUNDS	Blank Result <2>	Added <3>	Result <1>	Recovery %	(Mandatory) % Recovery Range
Petroleum Hydrocarbons	ND	0.9	0.90	100	56 - 139

#### MATRIX SPIKES

S P I K E C O M P O U N D S	Sample Results	Spike Added	Matrix	Spike	Matrix Dupli	Spike	MS/MSD Relative %	· · · · · · · · · · · · · · · · · · ·			
	<2>	<3>	Result <1>	Recovery <4>	Result <1>	Recovery <5>	Difference	RPD Max.	Recovery Range		
Petroleum Hydrocarbons	ND	0.9	0.35	38.9 *	0.77	85.6	75.0 *	18	40 - 158		

Analyst: YN

Sequence Date: 12/10/94

SPL ID of sample spiked: 9412312-05A

Sample File ID: S\_\_053.TX0

Method Blank File ID:

Blank Spike File ID: S\_\_\_024.TX0
Matrix Spike File ID: S\_\_\_057.TX0

Matrix Spike Duplicate File ID: S\_\_\_058.TX0

\* = Values Outside QC Range

NC = Not Calculated (Sample exceeds spike by factor of 4 or more)

ND = Not Detected/Below Detection Limit % Recovery = [(<1> - <2>) / <3>] x 100 LCS % Recovery = (<1> / <3>) x 100

Relative Percent Difference = |(<4> - <5>)| / [(<4> + <5>) x 0.5] x 100

(\*\*) = Source: SPL-Houston Historical Data (\*\*\*) = Source: SPL-Houston Historical Data

SAMPLES IN BATCH(SPL ID):

9412312-04A 9412312-05A 9412353-08A 9412312-13A 9412312-11A 9412312-09A 9412312-03A 9412353-05A 9412312-07A 9412312-06A 9412312-08A 9412354-04A 941221-01A 9412221-03A 9412221-08A 9412221-09A

# CHAIN OF CUSTODY AND SAMPLE RECEIPT CHECKLIST

	1		٠,	1
age		of		<u> </u>



Environmental Laboratory 8880 Interchange Drive Houston, Texas 77054 713/660-0901

## **Analysis Request and Chain of Custody Record**

Project No.					ect Name					<del></del> -	Project Location			
1564-0	24 		E	Z-S	FRVE :	# 100	877-				HAYWARD	CA		
Field Sample No./ Identification	Date and Time	Grøb	Comp	Cor	imple ntainer e/Mat'l)	Туг	Sample be (Liquid, udge, Etc.)	1	reser- ative				LABORATORY REMARKS	
100877-T.B.	12-5-94/10	35 X		2×4	fonlyon	LI	QUID	H	1	TPH(445) 5030/8	8015, BTEX 8020			
100877-NW-8	1 1132	2		3×4	omlvan									
100877-MW-9	1209													
100877-MW-10	1248													
10087-7-HW7FB	1300	,												
100877-MW-7	1404												•	
100877-MW-710	140	F						П						
100877-MW-1D	1456													·
100877-MU-5E	1600	,												
		1	1				/							
Sample	rs: (Signature	)		Relinqu	ished by:	7				Date: 12-6-94	Received by:	Date:		Intact
K. F. TA	72/-	_		(Signat	ure)	M				Time: /500	(Signature)	Time:		
KEVIN L.M	CTIVEN	MA.		Relinqu	ished by:					Date:	Received by:	Date:		Intact
	filiation			(Signat	ur <del>e</del> )					Time:	(Signature)	Time:		,
BROWN + CALDWELL Relinquished by: (Signature)						Date:	Received by:	Date:		Intact				
	(dig/,male)									Time:	(Signature)	Time:	L	30
	SAMPLER REMARKS: SHIPPED VIA FED-EX, COOLERS ON ICE & BLOCK ICE					<u> </u>	<u></u>	Reclined by laboratory:	Date://Z	- 2	Laboratory No.			
Seal #						,			-		Data Results to:		<u>-</u> :	
L										<u></u>	<u> </u>			

	.7		7
Page		of	



Environmental Laboratory 8880 Interchange Drive Houston, Texas 77054 713/660-0901

## **Analysis Request and Chain of Custody Record**

Project No.					ent/Project N						Project Location		
156A-0	4			F	Z-SER	1E#	-1008	377			HAYWARD, CA		
Field Sample No./ Identification	Dat and Tim	d	Grab	Comp	Sample Containe (Size/Mat		Type	mple (Liquid, je, Etc.)	Preser- vative		ANALYSIS REQUESTED		LABORATORY REMARKS
100877-MW-Z	ग्यद्यक्ष	045	χ		3×4011	VOA	Liqui	P	HCL	TPH(GAS)5030/	8015, BTEX 8020		
100877-MW-4		1030											
100877-MW-3		115											
100877-MW-6	1	w	4		<i>Y</i>				1		ン		
							71.	,,····································					
									ļ				
							<del></del>						
								***					
	<u> </u>				<u></u> .				/				
Sampler		turje)	_		Relinquished (Signature)	by:	4	W-/-		Date: /2-6-94 Time: /500	Received by: (Signature)	Date:	Intact
KEVIN L. N	(CI)	ENA	JA		Relinquished (Signature)	by:	· · ·	<b>t</b>		Date:	Received by: (Signature)	Date:	Intact
	filiation									Time:		Time:	
BRUNN + C	ALDW	ECL			Relinquished (Signature)	letinquished by.  Signature)  Time:					Received by: (Signature)	Date: Time:	thtack 3°C
SAMPLER REMARKS:								Received to aboratory: (Signature) J. W. W.	Date/2/7 Time: (OQ)	Laboratory No.			
Seal#										Data Results to:			

### SPL HOUSTON ENVIRONMENTAL LABORATORY

## SAMPLE LOGIN CHECKLIST

	SAMPLE LOGIN CHECKLIST		
DAT! LOT	E: 12/7 NO TIME: CLIENT NO CONTRACT NO.		
CLII	ENT SAMPLE NOS		
SPL	SAMPLE NOS . 9/123/2		
<del></del>		<u>YES</u>	<u>NO</u>
1.	Is a Chain-of-Custody form present? Is the COC properly completed? If no, describe what is incomplete:		
2	If no, has the client been contacted about it? (Attach subsequent documentation from client about it and the chief lading with the c	oout the situat:	ion)
3.	Is airbill/packing list/bill of lading with shi	pment?	
4. 5. 6.	Is a USEPA Traffic Report present? Is a USEPA SAS Packing List present? Are custody seals present on the package? If yes, were they intact upon receipt?		
7.	Are all samples tagged or labeled?  Do the sample tags/labels match the COC?  If no, has the client been contacted about it?  (Attach subsequent documentation from client about all the contacted abo	oout the situati	
8.	Do all shipping documents agree?  If no, describe what is in nonconformity:		
9. 10. 11.	Condition/temperature of shipping container: Condition/temperature of sample bottles: Sample Disposal?: SPL disposal		ent
NOTE	S (reference item number if applicable):		
	20.		
ATTE DELI	VERED FOR RESOLUTION: REC'D DA	TE: <u>2/7/9c</u> TE:	7
	DLVED: DA	TE:	