February 16, 2007

Steven Plunkett
Alameda County
Department of Environmental Health
1131 Harbor Bay Park Way
Alameda, CA 94502

DELTA

Subject: Case Number # 3580
Quarterly Groundwater Monitoring Report - Fourth Quarter 2006
Former RPMS (E-Z Serve) Location 100877
525 West A Street, Hayward, California
Delta Project RPMS 100877

Dear Mr. Plunkett:

Delta Consultants (Delta) have been contracted by Restructure Petroleum Marketing Services of California (RPMS) to perform environmental services at the Former E-Z Serve Location 100877 (Figure 1).

The groundwater monitoring data discussed in this report were collected on November 29, 2006. The work was performed in accordance with the field methods and procedures included in Enclosure A.

Groundwater Level Measurements

On November 29, 2006, Delta personnel visited the site to conduct groundwater monitoring activities. The depth to groundwater was measured in ten total monitoring and extraction wells MW-1, MW-1A, MW-3, MW-4, MW-5, MW-6, MW-7, MW-12, MW-14 and EX-1. MW-8, MW-9, MW10, MW-11, and MW-13 have been paved over or could not be located; MW-2 was destroyed in March of 2006.

Groundwater ranged from 13.12 feet to 15.67 feet below top of casing. Groundwater data collected on November 29, 2006 were used to create a groundwater elevation contour map, which is included as Figure 3. The groundwater flows to the west at a gradient of 0.03. Measured depths to groundwater and calculated groundwater elevations are presented in Table 1. Field data sheets for the fourth quarter sampling event are attached in Enclosure B.

Groundwater Sampling and Analytical Results

Groundwater samples were transported, under strict chain-of-custody protocols, to *Kiff Analytical LLC of Davis, California,* for analysis for benzene, toluene, ethyl-benzene, total xylenes (BTEX), total petroleum hydrocarbons (TPHg) in the gasoline range, methyl tert butyl ether (MTBE), diisopropyl ether (DIPE), ethyl tert butyl ether (ETBE), tert-amyl methyl ether (TAME) and tert butyl alcohol (TBA) by EPA Method 8260B.

TPHg was detected in eight monitoring wells (MW-1, MW-1A, MW-3, MW-4, MW-5, MW-6, MW-7, MW-14) and one extraction well (EX-1). Benzene was detected in five monitoring wells (MW-1, MW-1A, MW-3, MW-4, MW-5, and MW-6), and one extraction well (EX-1); and MTBE was detected in four monitoring wells (MW-1, MW-1A, MW-4, MW-5, and MW-6) and one extraction well (EX-1). The highest concentrations of TPHg, benzene and MTBE were in well MW-4 at 4,600 µg/L, 88 µg/L, and 5.5 µg/L, respectively. The analytical data for the November 29, 2006 sampling event are presented in Table 1, Groundwater Analytical Data. Field sampling information sheets are presented in Enclosure B. Laboratory analytical results and chain-of-custody documentation are presented in Enclosure C. Groundwater sample results collected from Quality Tune-Ups, across West A Street to the southwest, are included in Enclosure D.

Future Work

Delta recommends continued quarterly groundwater monitoring and sampling.

Remarks

The recommendations contained in this report represent Delta's professional opinions based upon the currently available information and are arrived at in accordance with currently acceptable professional standards. This report is based upon a specific scope of work requested by the client. The Contract between Delta and its client outlines the scope of work, and only those tasks specifically authorized by that contract or outlined in this report were performed. This report is intended only for the use of Delta's Client and anyone else specifically listed on this report. Delta will not and cannot be liable for unauthorized reliance by any other third party. Other than as contained in this paragraph, Delta makes no express or implied warranty as to the contents of this report.

Furthermore, I declare, under penalty of perjury, that the information and or recommendations contained in the attached document or report is true and correct to the best of my knowledge.

If you have any questions regarding this report please call Dr. G. Cleve Solomon at (626) 355-3040.

Sincerely,

DELTA CONSULTANTS

G. Cleve Solomon
California Registered Geologist No. 5122



Exp 01/31/09

cc: Jack Ceccarelli, RPMS of CA

FIGURES

SOURCE: USGS 7.5 MINUTE TOPOGRAPHIC MAP, HAYWARD QUADRANGLE, 1962

FIGURE 1

SITE LOCATION MAP

FORMER E-Z SERVE NO. 100877
525 WEST A STREET
HAYWARD, CALIFORNIA

PROJECT NO. RPMS-0877	DRAWN BY MC 11/10/04
FILE NO. EZ-100877-F1	PREPARED BY JS
REVISION NO. 1	REVIEWED BY

DELTA



FIGURE 2
SITE MAP

FORMER EZ-SERVE LOCATION NO. 100877
525 WEST A STREET
HAYWARD, CA

PROJECT NO. RPMS-0877	DRAWN BY WNL10/4/06
FILE NO. EZ-100877	PREPARED BY DS
REVISION NO. 1	REVIEWED BY

DELTA



FIGURE 3
GROUNDWATER ELEVATION CONTOUR MAP
8/23/06
FORMER EZ-SERVE LOCATION NO. 100877
525 WEST A STREET
HAYWARD, CA

PROJECT NO. RPMS-0877	DRAWN BY WNL10/4/06
FILE NO. EZ-100877	PREPARED BY DS
REVISION NO. 1	REVIEWED BY

DELTA



FIGURE 4

GROUNDWATER ALALYTICAL DATA MAP
8/23/06

FORMER EZ-SERVE LOCATION NO. 100877
525 WEST A STREET
HAYWARD, CA

PROJECT NO. RPMS-0877	DRAWN BY WNL10/4/06
FILE NO. EZ-100877	PREPARED BY DS
REVISION NO. 1	REVIEWED BY

DELTA

TABLE

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation	Sample	Depth to Water	Depth to Product	Free Product Thickness	Water Table Elevation	TPHg	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	DIPE	ETBE	TBA	TAME
(msl)	Date	(feet)	(feet)	(feet)	(msl)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-1	2/5/1992	20.82	--	--	20.93	46000	7600	2300	2400	6500	--	--	--	--	--
	9/11/1992	20.08	--	--	21.67	48000	9000	1200	1800	4600	--	--	--	--	--
41.75	12/22/1992	19.79	--	--	21.96	84000	22000	1600	4800	17000	--	--	--	--	--
	3/3/1993	16.23	--	--	25.52	54000	16000	1600	1900	4300	--	--	--	--	--
	6/23/1993	16.86	--	--	24.89	30000	18000	1100	1400	3700	--	--	--	--	--
	9/30/1993	18.04	--	--	23.71	33000	10000	440	940	1700	--	--	--	--	--
	2/6/1994	18.15	--	--	23.60	64000	18000	1600	4700	12000	--	--	--	--	--
	5/2/1994	17.26	--	--	24.49	7200	2100	29	490	520	--	--	--	--	--
	7/1/1994	17.60	--	--	24.15	13000	3700	150	550	12000	--	--	--	--	--
	9/20/1994	20.59	--	--	21.16	10000	3100	75	440	870	--	--	--	--	--
	12/5/1994	17.83	--	--	23.92	8700	3700	87	520	950	--	--	--	--	--
	3/10/1995	14.67	--	--	27.08	--	--	--	--	--	--	--	--	--	--
	3/15/1995	14.43	--	--	27.32	290	56	2	12	47	--	--	--	--	--
	9/23/1996	14.92	--	--	26.83	20000	5200	860	700	1100	270	--	--	--	--
	12/4/1996	15.61	--	--	26.14	17000	3100	64	610	1200	280	--	--	--	--
	4/8/1997	13.25	--	--	28.50	2100	430	15	52	85	100	--	--	--	--
	6/30/1997	14.68	--	--	27.07	10000	2100	<	<	320	<	--	--	--	--
	11/25/1997	15.99	--	--	25.76	16000	2100	23	76	240	<	--	--	--	--
	6/1/1998	9.98	--	--	31.77	19000	6100	430	1100	2300	420	--	--	--	--
	6/14/2001	15.05	--	--	26.70	6000	380	8.4	260	180	<25	--	--	--	--
	11/7/2001	16.31	--	--	25.44	12000	1000	30	1000	740	11	<5.0	<5.0	<50	<5.0
	1/30/2002	14.15	--	--	27.60	8800	690	16	480	270	14	<5.0	<5.0	<50	<5.0
	5/29/2002	14.55	--	--	27.20	6400	330	13	250	260	12	2.5	<2.0	<20	<2.0
	8/14/2002	15.56	--	--	26.19	5500	470	14	360	160	10	<10	<10	<100	<10
	11/15/2002	16.10	--	--	25.65	10000	440	16	310	150	15	<10	<10	<100	<10
	10/25/2004	15.99	--	--	25.76	4300	260	3.3	150	32	14	<0.90	<0.90	5.8	<0.90
	12/23/2004	15.64	--	--	26.11	11000	860	6.1	880	280	16	<0.90	<0.90	11	<0.90
	2/25/2005	12.79	--	--	28.96	11000	710	6.7	720	330	24	<1.5	<1.5	11	<1.5
	5/19/2005	12.27	--	--	29.48	7500	610	12	370	140	20	<1.5	<1.5	11	<1.5
	9/15/2005	14.30	--	--	27.45	6100	300	3.5	280	71	12	<0.90	<0.90	7.8	<0.90
	3/20/2006	11.44	--	--	30.31	6400	290	3.2	330	61	8.8	<0.90	<0.90	6	<0.90
	5/25/2006	11.05	--	--	30.70	4200	300	6.4	100	40	11	<0.90	<0.90	6.7	<0.90
	8/23/2006	**12.75**	**--**	**--**	**29.00**	**3400**	**140**	**1.9**	**92**	**9.2**	**4.2**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation	Sample	Depth to Water	Depth to Product	Free Product Thickness	Water Table Elevation	TPHg	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	DIPE	ETBE	TBA	TAME
(msl)	Date	(feet)	(feet)	(feet)	(msl)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-1A	6/23/1993	17.80	17.59	0.21	25.75	--	--	--	--	--	--	--	--	--	--
43.40	9/30/1993	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	2/6/1994	18.89	--	--	24.51	8900	1700	42	1000	400	--	--	--	--	--
	5/2/1994	18.35	0.09	0.09	38.40	--	--	--	--	--	--	--	--	--	--
	7/1/1994	18.45	--	--	24.95	12000	1100	<1	920	1100	--	--	--	--	--
	9/20/1994	21.72	21.50	0.22	21.84	--	--	--	--	--	--	--	--	--	--
	12/5/1994	18.87	18.80	0.07	24.58	--	--	--	--	--	--	--	--	--	--
	3/10/1995	15.83	--	--	27.57	--	--	--	--	--	--	--	--	--	--
	3/15/1995	15.55	15.50	0.05	27.89	--	--	--	--	--	--	--	--	--	--
	9/23/1996	16.00	15.99	0.01	27.41	--	--	--	--	--	--	--	--	--	--
	12/4/1996	16.55	--	--	26.85	52000	420	140	1000	3500	130	--	--	--	--
	4/8/1997	14.15	SHEEN	SHEEN	29.25	--	--	--	--	--	--	--	--	--	--
	6/30/1997	15.57	--	--	27.83	17000	180	<	140	1100	<	--	--	--	--
	11/25/1997	16.91	--	--	26.49	19000	110	37	290	910	<	--	--	--	--
	6/1/1998	10.78	--	--	32.62	18000	200	17	230	820	91	--	--	--	--
	6/14/2001	15.93	15.92	0.01	27.48	27000	29	<5.0	620	520	<50	--	--	--	--
	11/7/2001	17.32	--	--	26.08	21000	51	<5.0	700	510	<5.0	<5.0	<5.0	<50	<5.0
	1/30/2002	15.05	--	--	28.35	24000	22	<5.0	390	330	<5.0	<5.0	<5.0	<50	<5.0
	5/29/2002	15.49	--	--	27.91	12000	32	<5.0	550	270	<5.0	<5.0	<5.0	<50	<5.0
	8/14/2002	16.50	--	--	26.90	14000	22	<2.0	510	240	<2.0	<2.0	<2.0	<20	<2.0
	11/15/2002	17.04	--	--	26.36	17000	59	2.4	630	250	<2.0	<2.0	<2.0	<20	<2.0
	10/25/2004	16.90	--	--	26.50	2200	1.3	<0.50	58	3.7	<0.50	<0.50	<0.50	<5.0	<0.50
	12/23/2004	16.60	--	--	26.80	3100	2.2	<0.50	96	5.4	<0.50	<0.50	<0.50	<5.0	<0.50
	2/25/2005	13.75	--	--	29.65	7300	4.7	1.1	140	24	<0.50	<0.50	<0.50	<5.0	<0.50
	5/19/2005	13.12	--	--	30.28	13000	3.1	1.7	190	50	<1.5	<1.5	<1.5	<7.0	<1.5
	9/15/2005	15.16	--	--	28.24	4000	0.84	<0.50	52	2.5	<0.50	<0.50	<0.50	<5.0	<0.50
	11/10/2005	15.78	--	--	27.62	12000	<2.0	0.76	130	3.6	<0.50	<0.50	<0.50	<5.0	<0.50
	3/20/2006	12.64	--	--	30.76	3300	1.1	<0.50	17	1	<0.50	<0.50	<0.50	<5.0	<0.50
	5/25/2006	11.85	--	--	31.55	1600	0.79	<0.50	22	0.94	<0.50	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**13.55**	**--**	**--**	**29.85**	**4700**	**1.6**	**1.1**	**84**	**1.8**	**<0.50**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation	Sample	Depth to Water	Depth to Product	Free Product Thickness	Water Table Elevation	TPHg	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	DIPE	ETBE	TBA	TAME
(msl)	Date	(feet)	(feet)	(feet)	(msl)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-2	2/5/1992	22.35	--	0.00	20.91	67000	13000	4700	820	1300	--	--	--	--	--
	9/11/1992	21.67	--	0.00	21.59	57000	9000	1400	1200	8400	--	--	--	--	--
43.26	12/22/1992	21.39	--	0.00	21.87	31000	9900	350	2000	4100	--	--	--	--	--
	3/3/1993	17.75	--	0.00	25.51	17000	5100	1300	720	1900	--	--	--	--	--
	6/23/1993	18.42	--	0.00	24.84	60000	23000	1500	4500	17000	--	--	--	--	--
	9/30/1993	19.63	--	0.00	23.63	38000	12000	780	1500	6500	--	--	--	--	--
	2/6/1994	19.61	--	0.00	23.65	34000	8900	450	2000	5500	--	--	--	--	--
	5/2/1994	19.84	--	0.00	23.42	18000	3800	260	1100	3500	--	--	--	--	--
	7/1/1994	19.18	--	0.00	24.08	18000	3700	510	870	2600	--	--	--	--	--
	9/20/1994	22.17	--	0.00	21.09	19000	4500	300	1200	4000	--	--	--	--	--
	12/6/1994	19.37	--	0.00	23.89	22000	4700	340	1400	4500	--	--	--	--	--
	3/10/1995	16.33	--	0.00	26.93	--	--	--	--	--	--	--	--	--	--
	3/15/1995	16.89	--	0.00	26.37	29000	5600	350	1900	6300	--	--	--	--	--
	9/23/1996	16.61	--	0.00	26.65	29000	3700	150	1000	4300	860	--	--	--	--
	12/4/1996	17.19	--	0.00	26.07	31000	3800	140	2000	5100	690	--	--	--	--
	4/8/1997	14.86	--	0.00	28.40	20000	2500	80	1300	3400	880	--	--	--	--
	6/30/1997	16.28	--	0.00	26.98	41000	2700	130	1200	4000	890	--	--	--	--
	11/25/1997	17.56	--	0.00	25.70	51000	2900	140	1800	7000	1200	--	--	--	--
	6/1/1998	11.58	--	0.00	31.68	33000	2700	130	1800	5700	610	--	--	--	--
	6/14/2001	16.63	--	0.00	26.63	18000	860	14	1100	2200	<100	--	--	--	--
	11/7/2001	17.85	--	0.00	25.41	20000	880	20	1100	2600	21	<5.0	<5.0	<50	<5.0
	1/30/2002	15.65	--	0.00	27.61	19000	880	19	1100	2400	56	<5.0	<5.0	<50	<5.0
	5/29/2002	16.12	--	0.00	27.14	8100	390	16	560	1400	32	<5.0	<5.0	<50	<5.0
	8/14/2002	17.20	--	0.00	26.06	19000	820	21	1200	2600	29	<20	<20	<200	<20
	11/15/2002	17.63	--	0.00	25.63	34000	910	31	1000	1400	39	<20	<20	<200	<20
	10/25/2004	17.53	--	0.00	25.73	9300	280	3.8	500	980	8.2	<2.0	<2.0	<9.0	<2.0
	12/23/2004	17.15	--	0.00	26.11	10000	310	3.9	470	840	9.5	<2.0	<2.0	<9.0	<2.0
	2/25/2005	14.30	--	0.00	28.96	15000	320	4.8	860	1600	7.7	<2.0	<2.0	<9.0	<2.0
	5/19/2005	13.81	--	0.00	29.45	15000	300	3.6	770	1200	9.2	<2.5	<2.5	<15	<2.5
	9/15/2005	inaccessible due to temporary habitat					--	--	--	--	--	--	--	--	--
	11/10/2005	16.39	--	0.00	26.87	14000	230	2.6	530	1000	6.2	<2.5	<2.5	<15	<2.5
	3/20/2006	13.00	--	0.00	30.26	8700	170	<1.5	360	530	3.8	<1.5	<1.5	<7.0	<1.5
	5/25/2006	Destroyed on March 2, 2006			--	--	--	--	--	--	--	--	--	--	--

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation	Sample	Depth to Water	Depth to Product	Free Product Thickness	Water Table Elevation	TPHg	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	DIPE	ETBE	TBA	TAME
(msl)	Date	(feet)	(feet)	(feet)	(msl)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-3	2/5/1992	21.85	--	--	22.04	16000	2700	410	<1	3400	--	--	--	--	--
	9/11/1992	21.13	--	--	22.76	43000	7600	1600	1400	4100	--	--	--	--	--
43.89	12/22/1992	20.88	--	--	23.01	29000	8800	1200	1500	3700	--	--	--	--	--
	3/3/1993	17.29	--	--	26.60	17000	5000	1500	680	1700	--	--	--	--	--
	6/23/1993	17.88	--	--	26.01	5700	3000	120	560	790	--	--	--	--	--
	9/30/1993	19.18	--	--	24.71	21000	7000	2100	970	2600	--	--	--	--	--
	2/6/1994	19.21	--	--	24.68	24000	7200	1600	990	3200	--	--	--	--	--
	5/2/1994	18.30	--	--	25.59	10000	2200	440	470	1200	--	--	--	--	--
	7/1/1994	18.63	--	--	25.26	8200	2000	370	350	930	--	--	--	--	--
	9/20/1994	21.64	--	--	22.25	7200	2000	360	380	1000	--	--	--	--	--
	12/6/1994	19.15	--	--	24.74	9000	2300	400	440	1100	--	--	--	--	--
	3/10/1995	16.33	--	--	27.56	--	--	--	--	--	--	--	--	--	--
	3/15/1995	16.89	--	--	27.00	4300	980	47	370	780	--	--	--	--	--
	9/23/1996	16.11	--	--	27.78	10000	950	20	700	780	80	--	--	--	--
	12/4/1996	16.63	--	--	27.26	13000	1100	25	1000	1100	67	--	--	--	--
	4/8/1997	14.25	--	--	29.64	3800	210	4.6	270	280	56	--	--	--	--
	6/30/1997	15.70	--	--	28.19	3500	280	<	32	180	<	--	--	--	--
	11/25/1997	16.99	--	--	26.90	6800	230	<	370	290	130	--	--	--	--
	6/1/1998	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	6/14/2001	16.02	--	--	27.87	2100	9	<0.5	78	43	<5.0	--	--	--	--
	11/7/2001	17.33	--	--	26.56	7700	75	<5.0	410	150	<5.0	<5.0	<5.0	<50	<5.0
	1/30/2002	15.10	--	--	28.79	3600	27	<5.0	120	34	<5.0	<5.0	<5.0	<50	<5.0
	5/29/2002	15.63	--	--	28.26	2000	18	<5.0	53	13	<5.0	<5.0	<5.0	<50	<5.0
	8/14/2002	16.63	--	--	27.26	2400	19	<0.5	50	6.5	<0.5	<0.5	<0.5	<5.0	<0.5
	11/15/2002	17.10	--	--	26.79	4300	7.5	<0.5	22	1.1	0.5	<0.5	<0.5	<5.0	<0.5
	10/25/2004	17.01	--	--	26.88	460	0.6	<0.50	9.6	1.7	<0.50	<0.50	<0.50	<5.0	<0.50
	12/20/2004	16.64	--	--	27.25	5400	9	<0.50	280	74	<0.50	<0.50	<0.50	<5.0	<0.50
	2/25/2005	Could not locate, VEAS-2 sampled instead					--	--	--	--	--	--	--	--	--
	5/19/2005	Could not locate, VEAS-2 sampled instead					--	--	--	--	--	--	--	--	--
	9/15/2005	couldn't locate		--	--	--	--	--	--	--	--	--	--	--	--
	11/10/2005	couldn't locate		--	--	--	--	--	--	--	--	--	--	--	--
	3/20/2006	12.44	--	--	31.45	800	0.76	<0.50	19	3.7	<0.50	<0.50	<0.50	<5.0	<0.50
	5/25/2006	12.05	--	--	31.84	500	0.59	<0.50	3.8	0.96	<0.50	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**13.75**	**--**	**--**	**30.14**	**550**	**<0.50**	**<0.50**	**2.2**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation (msl)	Sample Date	Depth to Water (feet)	Depth to Product (feet)	Free Product Thickness (feet)	Water Table Elevation (msl)	TPHg (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TBA (µg/L)	TAME (µg/L)
MW-4	2/5/1992	21.31	--	--	21.45	16000	2700	410	<1	3400	--	--	--	--	--
	9/11/1992	20.62	--	--	22.14	43000	7600	1600	1400	4100	--	--	--	--	--
42.76	12/22/1992	20.37	--	--	22.39	29000	8800	1200	1500	3700	--	--	--	--	--
	3/3/1993	16.78	--	--	25.98	17000	5000	1500	680	1700	--	--	--	--	--
	6/23/1993	17.45	--	--	25.31	5700	3000	120	560	790	--	--	--	--	--
	9/30/1993	18.64	--	--	24.12	21000	7000	2100	970	2600	--	--	--	--	--
	2/6/1994	18.59	--	--	24.17	24000	7200	1600	990	3200	--	--	--	--	--
	5/2/1994	17.81	--	--	24.95	10000	2200	440	470	1200	--	--	--	--	--
	7/1/1994	18.13	--	--	24.63	8200	2000	370	350	930	--	--	--	--	--
	9/20/1994	21.13	--	--	21.63	7200	2000	360	380	1000	--	--	--	--	--
	12/6/1994	18.36	--	--	24.40	9000	2300	400	440	1100	--	--	--	--	--
	3/10/1995	15.25	--	--	27.51	--	--	--	--	--	--	--	--	--	--
	3/15/1995	14.89	--	--	27.87	15000	4400	600	770	2660	--	--	--	--	--
	9/23/1996	15.56	--	--	27.20	32000	7400	540	1500	2800	2100	--	--	--	--
	12/4/1996	16.11	--	--	26.65	23000	7800	140	1200	1200	1900	--	--	--	--
	4/8/1997	13.73	--	--	29.03	16000	3900	680	850	2300	980	--	--	--	--
	6/30/1997	15.19	--	--	27.57	63000	7000	430	1400	4400	1700	--	--	--	--
	11/25/1997	16.49	--	--	26.27	30000	4300	61	810	1500	880	--	--	--	--
	6/1/1998	10.42	--	--	32.34	33000	5700	710	1700	2900	720	--	--	--	--
	6/14/2001	15.55	--	--	27.21	9500	690	45	560	600	<50	--	--	--	--
	11/7/2001	16.81	--	--	25.95	6000	710	20	630	190	27	<5.0	<5.0	<50	<5.0
	1/30/2002	14.60	--	--	28.16	4800	830	16	600	61	42	<5.0	<5.0	<50	<5.0
	5/29/2002	15.14	--	--	27.62	5300	720	57	600	200	35	<20	<20	<200	<20
	8/14/2002	16.07	--	--	26.69	5000	640	15	550	35	28	<2.0	<2.0	<20	<2.0
	11/15/2002	16.61	--	--	26.15	3700	330	10	260	200	20	<2.0	<2.0	<20	<2.0
	10/25/2004	16.50	--	--	26.26	4000	180	15	200	190	4.1	<0.50	<0.50	<5.0	<0.50
	12/23/2004	16.20	--	--	26.56	7400	280	24	340	340	7.9	<0.90	<0.90	<5.0	<0.90
	2/25/2005	13.30	--	--	29.46	4200	160	15	280	420	6.2	<0.90	<0.90	<5.0	<0.90
	5/19/2005	12.74	--	--	30.02	15000	480	76	1100	1600	14	<4.0	<4.0	<20	<4.0
	9/15/2005	14.80	--	--	27.96	5400	220	22	250	430	10	<0.90	<0.90	5.4	<0.90
	11/10/2006	15.45	--	--	27.31	8000	320	37	530	670	9.3	<0.50	<0.50	<5.0	<0.50
	3/20/2006	11.93	--	--	30.83	3900	91	26	5.8	360	5.7	<0.50	<0.50	<5.0	<0.50
	5/25/2006	11.49	--	--	31.27	8300	300	77	570	730	5.4	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**13.23**	**--**	**--**	**29.53**	**9400**	**240**	**79**	**490**	**860**	**6.1**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation	Sample	Depth to Water	Depth to Product	Free Product Thickness	Water Table Elevation	TPHg	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	DIPE	ETBE	TBA	TAME
(msl)	Date	(feet)	(feet)	(feet)	(msl)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-5	2/5/1992	20.93	--	--	21.17	78000	7900	5000	2900	1800	--	--	--	--	--
42.10	9/11/1992	20.27	--	--	21.83	49000	4700	400	1400	4100	--	--	--	--	--
	12/22/1992	19.99	--	--	22.11	34000	8600	340	2200	4800	--	--	--	--	--
	3/3/1993	16.49	--	--	25.61	22000	7500	640	1300	3400	--	--	--	--	--
	6/23/1993	17.02	--	--	25.08	15000	5800	120	1100	2100	--	--	--	--	--
	9/30/1993	18.25	--	--	23.85	25000	7600	410	1000	4400	--	--	--	--	--
	2/6/1994	18.26	--	--	23.84	23000	6000	180	2000	5900	--	--	--	--	--
	5/2/1994	17.50	--	--	24.60	8000	1300	29	440	770	--	--	--	--	--
	7/1/1994	17.79	--	--	24.31	10000	1700	97	600	1400	--	--	--	--	--
	9/20/1994	20.77	--	--	21.33	8400	1600	54	650	1400	--	--	--	--	--
	12/5/1994	18.02	--	--	24.08	10000	1800	<50	620	1400	--	--	--	--	--
	3/10/1995	14.93	--	--	27.17	--	--	--	--	--	--	--	--	--	--
	3/15/1995	14.70	--	--	27.40	5300	1100	11	180	320	--	--	--	--	--
	9/23/1996	15.19	--	--	26.91	9800	1800	11	470	510	100	--	--	--	--
	12/4/1996	15.78	--	--	26.32	10000	2200	9	550	430	70	--	--	--	--
	4/8/1997	13.39	--	--	28.71	11000	1300	15	450	720	180	--	--	--	--
	6/30/1997	14.83	--	--	-14.83	3800	500	<	75	84	<	--	--	--	--
	11/25/1997	16.14	--	--	-16.14	8200	1300	14	310	220	<	--	--	--	--
	6/1/1998	10.10	--	--	-10.10	3600	290	12	52	52	81	--	--	--	--
	6/14/2001	15.19	--	--	-15.19	5100	44	0.71	110	23	<5.0	--	--	--	--
	11/7/2001	16.47	--	--	-16.47	7600	220	<5.0	550	30	<5.0	<5.0	<5.0	<50	<5.0
	1/30/2002	14.27	--	--	-14.27	6200	180	<20	310	130	<20	<20	<20	<200	<20
	5/29/2002	14.73	--	--	-14.73	3900	66	0.8	110	7.4	0.9	2	<0.5	<5.0	<0.5
	8/14/2002	15.73	--	--	-15.73	4300	80	0.9	150	12	1.1	<0.5	<0.5	<5.0	<0.5
	11/15/2002	16.27	--	--	-16.27	7000	99	<5.0	250	500	<5.0	<5.0	<5.0	<50	<5.0
	10/25/2004	16.15	--	--	-16.15	4800	27	0.5	50	3.7	0.79	<0.50	<0.50	<5.0	<0.50
	12/23/2004	15.88	--	--	-15.88	6300	55	<0.90	140	5.6	<0.90	<0.90	<0.90	<5.0	<0.90
	2/25/2005	12.97	--	--	-12.97	4700	44	0.59	110	4.8	0.85	<0.50	<0.50	<5.0	<0.50
	5/19/2005	12.48	--	--	-12.48	3800	32	0.61	66	4.4	1	<0.50	<0.50	<5.0	<0.50
	9/15/2005	15.47	--	--	26.63	4500	22	0.65	78	4	0.95	<0.50	<0.50	<5.0	<0.50
	11/10/2005	15.03	--	--	27.07	4000	19	0.52	77	4.3	0.8	<0.50	<0.50	<5.0	<0.50
	3/20/2006	11.79	--	--	30.31	4000	9.5	<0.50	4.9	4.0	1.5	<0.50	<0.50	<5.0	<0.50
	5/25/2006	11.15	--	--	30.95	3400	12	<0.50	46	3.8	1.6	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**12.88**	**--**	**--**	**29.22**	**4000**	**5.6**	**0.75**	**42**	**3.6**	**1.3**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation	Sample	Depth to Water	Depth to Product	Free Product Thickness	Water Table Elevation	TPHg	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE	DIPE	ETBE	TBA	TAME
(msl)	Date	(feet)	(feet)	(feet)	(msl)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-6	2/5/1992	21.29	--	--	21.04	51000	5400	3500	3600	10000	--	--	--	--	--
	9/11/1992	20.56	--	--	21.77	24000	2500	830	1400	2300	--	--	--	--	--
42.33	12/22/1992	20.31	--	--	22.02	23000	5100	630	2000	3100	--	--	--	--	--
	3/3/1993	16.83	--	--	25.50	18000	4400	820	1400	2400	--	--	--	--	--
	6/23/1993	17.30	--	--	25.03	18000	4600	850	2700	3400	--	--	--	--	--
	9/30/1993	19.05	--	--	23.28	--	--	--	--	--	--	--	--	--	--
	2/6/1994	18.55	--	--	23.78	20000	4600	690	2100	2500	--	--	--	--	--
	5/2/1994	17.74	--	--	24.59	5300	930	54	610	240	--	--	--	--	--
	7/1/1994	18.09	--	--	24.24	10000	1500	160	850	690	--	--	--	--	--
	9/20/1994	21.05	--	--	21.28	11000	2000	140	1200	760	--	--	--	--	--
	12/6/1994	18.33	--	--	24.00	8600	1300	87	980	610	--	--	--	--	--
	3/10/1995	15.35	--	--	26.98	--	--	--	--	--	--	--	--	--	--
	3/15/1995	14.91	--	--	27.42	9800	1600	110	1000	1000	--	--	--	--	--
	9/23/1996	15.50	--	--	26.83	12000	520	55	930	350	51	--	--	--	--
	12/4/1996	16.06	--	--	26.27	11000	390	25	680	170	130	--	--	--	--
	4/8/1997	13.64	--	--	28.69	17000	700	92	1400	900	2700	--	--	--	--
	6/30/1997	15.08	--	--	27.25	11000	270	37	590	450	<	--	--	--	--
	11/25/1997	16.40	--	--	25.93	9100	130	26	500	150	310	--	--	--	--
	6/1/1998	10.31	--	--	32.02	14000	190	50	680	400	160	--	--	--	--
	6/14/2001	15.46	--	--	26.87	6400	29	6.3	200	55	<20	--	--	--	--
	11/7/2001	16.71	--	--	25.62	7200	34	8.7	180	31	<5.0	<5.0	<5.0	<50	<5.0
	1/30/2002	14.60	--	--	27.73	6600	32	7.2	130	28	<5.0	<5.0	<5.0	<50	<5.0
	5/29/2002	14.99	--	--	27.34	5200	26	7	150	27	<5.0	<5.0	<5.0	<50	<5.0
	8/14/2002	16.03	--	--	26.30	5300	24	6.6	120	22	<2.0	<2.0	<2.0	<20	<2.0
	11/15/2002	16.53	--	--	25.80	5000	19	4.7	70	38	<0.5	<0.5	<0.5	<5.0	<0.5
	10/25/2004	16.43	--	--	25.90	3600	9.8	2.1	83	16	2.3	<0.50	<0.50	<5.0	<0.50
	12/23/2004	16.12	--	--	26.21	2100	8.2	1.3	10	2.4	1.5	<0.50	<0.50	<5.0	<0.50
	2/25/2005	13.13	--	--	29.20	2500	6.6	1.4	29	5.2	0.74	<0.50	<0.50	<5.0	<0.50
	5/19/2005	12.61	--	--	29.72	3800	7.5	2.2	54	12	3.1	<0.50	<0.50	<5.0	<0.50
	9/15/2005	14.69	--	--	27.64	1900	2.9	0.88	12	2.7	0.94	<0.50	<0.50	<5.0	<0.50
	11/10/2005	15.30	--	--	27.03	1700	2.1	0.6	5.4	1.7	0.81	<0.50	<0.50	<5.0	<0.50
	3/20/2006	11.88	--	--	30.45	2300	3.6	1.0	12	3.9	1.1	<0.50	<0.50	<5.0	<0.50
	5/25/2006	11.38	--	--	30.95	2400	5	1.8	31	14	3	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**13.10**	**--**	**--**	**29.23**	**2300**	**2.3**	**0.84**	**7.8**	**4.2**	**1.7**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation (msl)	Sample Date	Depth to Water (feet)	Depth to Product (feet)	Free Product Thickness (feet)	Water Table Elevation (msl)	TPHg (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TBA (µg/L)	TAME (µg/L)
MW-7	6/23/1993	17.87	--	--	24.83	29000	4200	71	4400	5600	--	--	--	--	--
42.70	9/30/1993	18.94	--	--	23.76	30000	3200	71	2800	3400	--	--	--	--	--
	2/6/1994	19.11	19.05	0.06	23.63	--	--	--	--	--	--	--	--	--	--
	5/2/1994	18.11	--	--	24.59	5700	630	13	660	400	--	--	--	--	--
	7/1/1994	18.72	--	--	23.98	3100	180	99	160	520	--	--	--	--	--
	9/20/1994	21.41	--	--	21.29	6100	540	6	750	730	--	--	--	--	--
	12/5/1994	18.66	--	--	24.04	3700	280	<10	430	350	--	--	--	--	--
	3/10/1995	15.72	--	--	26.98	3900	310	<10	540	540	--	--	--	--	--
	3/14/1995	15.23	--	--	27.47	1900	290	4	26	296	--	--	--	--	--
	9/23/1996	15.94	--	--	26.76	6300	76	<	420	270	15	--	--	--	--
	12/4/1996	16.43	--	--	26.27	7800	67	<	600	350	22	--	--	--	--
	4/8/1997	14.10	--	--	28.60	5600	42	<	240	96	<	--	--	--	--
	6/30/1997	15.51	--	--	27.19	5500	<	79	<	44	280	--	--	--	--
	11/25/1997	16.80	--	--	25.90	2400	23	5.4	<	54	120	--	--	--	--
	6/1/1998	10.31	--	--	32.39	14000	190	50	680	400	160	--	--	--	--
	6/14/2001	15.46	--	--	27.24	6400	29	6	200	55	<20	--	--	--	--
	11/7/2001	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	1/30/2002	14.97	--	--	27.73	6200	1.5	<0.5	96	4.6	<0.5	<5.0	<5.0	<50	<5.0
	5/29/2002	15.49	--	--	27.21	1600	1	<0.5	3.4	1.9	<0.5	<0.5	<0.5	<5.0	<0.5
	8/14/2002	16.44	--	--	26.26	4100	1.3	<0.5	74	1.3	<0.5	<0.5	<0.5	<5.0	<0.5
	11/15/2002	16.91	--	--	25.79	1000	0.6	<0.5	<0.5	0.6	<0.5	<0.5	<0.5	<5.0	<0.5
	10/25/2004	Could not locate well													
	5/19/2005	13.06	--	--	29.64	660	<0.50	<0.50	1.8	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	9/15/2005	Could not locate well			--	--	--	--	--	--	--	--	--	--	--
	11/10/2005	15.78	--	--	26.92	340	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	3/20/2006	Could not locate well													
	5/25/2006	Well was blocked by debris													
	8/23/2006	**13.60**	**--**	**--**	**29.10**	**380**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation (msl)	Sample Date	Depth to Water (feet)	Depth to Product (feet)	Free Product Thickness (feet)	Water Table Elevation (msl)	TPHg (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TBA (µg/L)	TAME (µg/L)
MW-8	6/23/1993	17.64	--	--	79.97	350	43	9	35	67	--	--	--	--	--
	9/30/1993	18.85	--	--	78.76	2700	190	340	170	720	--	--	--	--	--
97.61	2/6/1994	18.91	--	--	78.70	<100	<1	1	1	2	--	--	--	--	--
	5/2/1994	18.11	--	--	79.50	<100	<1	3	<1	7	--	--	--	--	--
	7/1/1994	18.43	--	--	79.18	300	18	48	19	37	--	--	--	--	--
	9/20/1994	21.43	--	--	76.18	<100	<1	<1	<1	<1	--	--	--	--	--
	12/5/1994	18.72	--	--	78.89	<50	<0.5	<0.5	<0.5	<0.5	--	--	--	--	--
	3/10/1995	18.69	--	--	78.92	--	--	--	--	--	--	--	--	--	--
	3/14/1995	14.83	--	--	82.78	<50	<0.5	<0.5	<0.5	1	--	--	--	--	--
	9/23/1996	15.83	--	--	81.78	<	<	<	<	<	<	<	<	<	<
	Not Sampled, well inaccessible since 4th Quarter, 1996.														
MW-9	6/23/1993	15.94	--	--	79.47	45000	14000	1200	2800	12000	--	--	--	--	--
	9/30/1993	17.05	--	--	78.36	86000	22000	1100	3300	15000	--	--	--	--	--
95.41	2/6/1994	17.07	--	--	78.34	43000	10000	460	2100	7500	--	--	--	--	--
	5/2/1994	16.24	--	--	79.17	17000	5400	270	1300	4700	--	--	--	--	--
	7/1/1994	16.59	--	--	78.82	10000	2100	120	450	1300	--	--	--	--	--
	9/20/1994	19.61	--	--	75.80	7500	2200	97	400	1200	--	--	--	--	--
	12/5/1994	16.85	--	--	78.56	10000	2700	130	530	1600	--	--	--	--	--
	3/10/1995	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	3/14/1995	14.18	--	--	81.23	18000	5900	270	1200	3680	--	--	--	--	--
	Not Sampled, well inaccessible since 1st Quarter, 1995.														
MW-10	6/23/1993	17.39	--	--	79.72	35000	980	640	3500	12000	--	--	--	--	--
	9/30/1993	18.58	--	--	78.53	4000	230	12	100	680	--	--	--	--	--
97.11	2/6/1994	18.61	--	--	78.50	2000	69	12	220	120	--	--	--	--	--
	5/2/1994	17.83	--	--	79.28	710	16	6	85	62	--	--	--	--	--
	7/1/1994	18.17	--	--	78.94	2000	52	43	120	210	--	--	--	--	--
	9/20/1994	21.15	--	--	75.96	2800	34	16	270	560	--	--	--	--	--
	12/5/1994	18.43	--	--	78.68	2700	30	13	260	430	--	--	--	--	--
	3/10/1995	15.37	--	--	81.74	--	--	--	--	--	--	--	--	--	--
	3/14/1995	15.93	--	--	81.18	1400	18	6	200	239	--	--	--	--	--
	9/23/1996	15.59	--	--	81.52	3800	4	2.9	220	170	397	--	--	--	--
	12/4/1996	16.15	--	--	80.96	4600	1.6	7.7	260	150	20	--	--	--	--
	Not Sampled, well inaccessible since 4th Quarter, 1996.														

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation (msl)	Sample Date	Depth to Water (feet)	Depth to Product (feet)	Free Product Thickness (feet)	Water Table Elevation (msl)	TPHg (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TBA (µg/L)	TAME (µg/L)
MW-11	2/10/1995	11.80	--	--	80.88	7000	140	22	600	1000	--	--	--	--	--
	3/10/1995	11.58	--	--	81.10	--	--	--	--	--	--	--	--	--	--
92.68	3/14/1995	13.96	--	--	78.72	6000	200	17	750	1276	--	--	--	--	--
	9/23/1996	12.29	--	--	80.39	27000	55	81	300	3500	40	--	--	--	--
	12/4/1996	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	4/8/1997	10.51	--	--	82.17	24000	280	130	3000	3700	<	--	--	--	--
	Not Sampled, well inaccessible since 2nd Quarter, 1997.														
MW-12	2/10/1995	16.30	--	--	26.95	<50	<0.5	<0.5	<0.5	<0.5	--	--	--	--	--
	3/10/1995	16.37	--	--	26.88	--	--	--	--	--	--	--	--	--	--
43.25	3/14/1995	15.69	--	--	27.56	<50	<0.5	<0.5	<0.5	0.9	--	--	--	--	--
	9/23/1996	16.67	--	--	26.58	<	<	1.6	<	<	<	--	--	--	--
	12/4/1996	17.16	--	--	26.09	<	3.2	<	1.9	3.4	<	--	--	--	--
	4/8/1997	14.88	--	--	28.37	<	<	<	<	<	<	--	--	--	--
	6/30/1997	16.33	--	--	26.92	--	--	--	--	--	--	--	--	--	--
	11/25/1997	17.61	--	--	25.64	--	--	--	--	--	--	--	--	--	--
	6/1/1998	11.58	--	--	31.67	--	--	--	--	--	--	--	--	--	--
	6/14/2001	16.62	--	--	26.63	<50	<0.50	<0.50	<0.50	<0.50	<5.0	--	--	--	--
	11/7/2001	17.91	--	--	25.34	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	1/30/2002	15.60	--	--	27.65	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	5/29/2002	16.24	--	--	27.01	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	8/14/2002	17.20	--	--	26.05	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	11/15/2002	17.62	--	--	25.63	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	10/25/2004	well not sampled, cars parked on well													
	2/25/2005	14.72	--	--	28.53	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	5/19/2005	13.80	--	--	29.45	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	9/15/2005	15.94	--	--	27.31	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	11/10/2005	16.51	--	--	26.74	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	3/20/2006	13.04	--	--	30.21	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	5/25/2006	12.65	--	--	30.60	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**14.44**	**--**	**--**	**28.81**	**<50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation (msl)	Sample Date	Depth to Water (feet)	Depth to Product (feet)	Free Product Thickness (feet)	Water Table Elevation (msl)	TPHg (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TBA (µg/L)	TAME (µg/L)
MW-13	2/10/1995	14.45	--	--	26.52	<50	<0.5	<0.5	<0.5	<0.5	--	--	--	--	--
	3/10/1995	14.30	--	--	26.67	--	--	--	--	--	--	--	--	--	--
40.97	3/14/1995	15.81	--	--	25.16	<50	<0.5	<0.5	<0.5	1	--	--	--	--	--
	9/23/1996	14.60	--	--	26.37	<	<	0.8	1	<	<	--	--	--	--
	12/4/1996	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	4/8/1997	12.75	--	--	28.22	<	<	<	<	<	<	--	--	--	--
	6/30/1997	14.13	--	--	26.84	--	--	--	--	--	--	--	--	--	--
	11/25/1997	15.48	--	--	25.49	--	--	--	--	--	--	--	--	--	--
	6/1/1998	9.58	--	--	31.39	--	--	--	--	--	--	--	--	--	--
	6/14/2001	14.51	--	--	26.46	<50	<0.50	<0.50	<0.50	<0.50	<5.0	--	--	--	--
	11/7/2001	15.85	--	--	25.12	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	1/30/2002	13.65	--	--	27.32	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	5/29/2002	14.10	--	--	26.87	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	8/14/2002	15.13	--	--	25.84	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	11/15/2002	--	--	--	--	--	--	--	--	--	--	--	--	--	--
	10/25/2004	Well not sampled. Unable to locate well since 10/25/04.													
MW-14	2/10/1995	16.28	--	--	26.91	12000	42	8	740	2100	--	--	--	--	--
	3/10/1995	16.33	--	--	26.86	--	--	--	--	--	--	--	--	--	--
43.19	3/14/1995	14.87	--	--	28.32	1400	6	2	36	298	--	--	--	--	--
	9/23/1996	16.67	--	--	26.52	6400	2.8	<	690	96	9.6	--	--	--	--
	12/4/1996	17.06	--	--	26.13	9500	6.3	<	1100	400	30	--	--	--	--
	4/8/1997	14.77	--	--	28.42	2900	<	2.7	220	21	<	--	--	--	--
	6/30/1997	16.22	--	--	26.97	74	1.3	<	0.51	0.68	<	--	--	--	--
	11/25/1997	17.52	--	--	25.67	<	<	<	<	<	<	--	--	--	--
	6/1/1998	11.46	--	--	31.73	<50	<0.5	<0.5	<0.5	<0.5	<5	--	--	--	--
	6/14/2001	16.53	--	--	26.66	470	<0.5	<0.5	2.8	1	<5	--	--	--	--
	11/7/2001	17.84	--	--	25.35	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	1/30/2002	15.55	--	--	27.64	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	5/29/2002	16.14	--	--	27.05	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	8/14/2002	17.12	--	--	26.07	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	11/15/2002	17.56	--	--	25.63	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	10/25/2004	Well not sampled. Unable to locate well due to parked cars.													
	2/25/2005	14.20	--	--	28.99	210	<0.5	<0.5	0.56	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5
	5/19/2005	13.71	--	--	29.48	230	<0.5	<0.5	0.72	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
	9/15/2005	Well not sampled due to lack of traffic control													
	11/10/2005	Well not sampled due to lack of traffic control					--	--	--	--	--	--	--	--	--
	3/20/2006	12.94	--	--	30.25	180	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	5/25/2006	12.68	--	--	30.51	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**15.32**	**--**	**--**	**27.87**	**99**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<0.50**	**<5.0**	**<0.50**

Table 1
Groundwater Analytical Data
Former EZ Serve Location #100877
525 West A St. Hayward CA, 94541

Well Casing Elevation (msl)	Sample Date	Depth to Water (feet)	Depth to Product (feet)	Free Product Thickness (feet)	Water Table Elevation (msl)	TPHg (µg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl-benzene (µg/L)	Total Xylenes (µg/L)	MTBE (µg/L)	DIPE (µg/L)	ETBE (µg/L)	TBA (µg/L)	TAME (µg/L)
EX-1	8/14/2002	16.58	--	--	--	250	31	<0.5	<0.5	4.2	1.4	<0.5	<0.5	<5.0	<0.5
	11/15/2002	17.02	--	--	--	67	4.1	<0.5	<0.5	<0.5	0.7	<0.5	<0.5	<5.0	<0.5
--	10/25/2004	16.91	--	--	--	96	2.1	<0.50	4.9	1.8	<0.5	<0.5	<0.5	<5.0	<0.50
	12/23/2004	16.60	--	--	--	<50	<0.50	<0.50	0.87	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	2/25/2005	13.72	--	--	--	59	1.4	<0.50	2	0.87	<0.50	<0.50	<0.50	<5.0	<0.50
	5/19/2005	13.13	--	--	--	200	3.4	<0.50	3.7	1.8	1.3	<0.50	<0.50	<5.0	<0.50
	9/15/2005	15.20	--	--	--	290	7.5	<0.50	2.8	0.66	1.2	<0.50	<0.50	<5.0	<0.50
	11/10/2005	15.80	--	--	--	270	5.1	<0.50	9.2	1.5	0.94	<0.50	<0.50	<5.0	<0.50
	3/20/2006	12.35	--	--	--	820	7.5	<0.50	15	7.2	0.94	<0.50	<0.50	<5.0	<0.50
	5/25/2006	11.88	--	--	--	100	<0.50	<0.50	1	0.9	0.79	<0.50	<0.50	<5.0	<0.50
	8/23/2006	**13.62**	**--**	**--**	**--**	**440**	**7.3**	**<0.50**	**0.72**	**0.61**	**1.2**	**<0.50**	**<0.50**	**<5.0**	**<0.50**
VEAS-2	2/25/2005*	13.68	--	--	--	90	1.1	<0.50	0.7	1.3	1.4	<0.50	<0.50	<5.0	<0.50
	5/19/2005*	13.11	--	--	--	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<5.0	<0.50
	11/10/2005	Dry	--	--	--	--	--	--	--	--	--	--	--	--	--

Notes: No known groundwater monitoring or sampling was conducted between June 1, 1998 and June 14, 2001, June 14, 2001 and November 7, 2001, Wellhead elevations resurveyed on January 30, 2002.

Explanations:

msl = mean seal level
(µg/L) = micrograms per liter
TBA = Tertiary butyl alcohol
MTBE = Methyl tertiary butyl ether
DIPE = Di-isopropyl ether
ETBE = Ethyl tertiary butyl ether
TAME = Tertiary amyl methyl ether
EDB = 1,2-Dibromoethane
-- = Not measured, or analyzed
DRY = Insufficient water to sample
TPHg = Total Petroleum Hydrocarbons as gasoline (EPA Method 8015).
SHEEN = Discontinuous, non-measurable thickness of PSH.
< = Sample reported as "not detected," in previous tables, reporting limit not known.

ENCLOSURE A

Field Methods and Procedures

FIELD METHODS AND PROCEDURES

The following section describes field procedures that are to be used by Delta personnel in the performance of the tasks involved with this project.

1.0 HEALTH AND SAFETY PLAN

Fieldwork performed by Delta and Delta's subcontractors at the site will be conducted according to guidelines established in a Site Health and Safety Plan (SHSP). The SHSP is a document that describes the hazards that may be encountered in the field and specifies protective equipment, work procedures and emergency information. A copy of the SHSP will be at the site and available for reference by appropriate parties during work at the site.

2.0 GROUNDWATER DEPTH ASSESSMENT

A water/product interface probe is used to assess the liquid-phase hydrocarbons (LPH) thickness, if present, and a water level indicator is used to measure the groundwater depth in monitoring wells that do not contain LPH. Depth to groundwater or LPH is measured from a datum point at the top of each monitoring well casing. The datum point is typically a notch cut in the north side of the casing edge. If a water level indicator is used, the tip is subjectively analyzed for LPH sheen.

3.0 SUBJECTIVE ANALYSIS OF GROUNDWATER

Prior to purging, a water sample is collected from the monitoring well for subjective assessment. The sample is retrieved by gently lowering a clean, disposable bailer to approximately one-half the bailer length past the air/liquid interface. The bailer is then retrieved and the sample contained within the bailer is examined for floating LPH and the appearance of a LPH sheen.

4.0 MONITORING WELL SAMPLING

Monitoring wells are purged using a pump or bailer until pH, temperature and conductivity of the purge water has stabilized and a minimum of three well volumes of water has been removed. The purge water is placed in 55-gallon drums and temporarily stored on-site pending evaluation of disposal options. If three well volumes cannot be removed in one-half an hour's time, the well is allowed to recharge to 80 percent of original level. After recharging, a groundwater sample is then removed from each of the wells using a pump or disposable bailer. The water sample is collected, labeled and handled according to the Quality Assurance Plan. Water generated during the monitoring event is disposed of according to the accepted regulatory method pertaining to the site.

5.0 QUALITY ASSURANCE PLAN

This section describes the field and analytical procedures to be followed by Delta throughout the investigation.

5.1 General Sample Collection and Handling Procedures

Proper collection and handling are essential to ensure the quality of a sample. Each sample will be collected in the appropriate container, preserved correctly for the intended analysis and stored, prior to analysis, for no longer than the maximum allowable holding time. Details on the procedures for collection and handling of soil samples from this project can be found in previous sections.

5.2 Sample Identification and Chain-of-Custody Procedures

Sample identification and chain-of-custody procedures ensure sample integrity and document sample possession from the time of collection to its ultimate disposal. Each sample container submitted for analysis will have a label affixed to identify the job number, sampler, date and time of sample collection and a sample number unique to that sample. During soil sampling, this information, in addition to a description of the sample, field measurements made, sampling methodology, names of on-site personnel and any other pertinent field observations will be recorded on the borehole log or in the field records.

ENCLOSURE B

Groundwater Sampling Information Sheets

Delta Environmental Consultants, Inc.
Groundwater/Liquid Level Data
(measurements in feet)

Project Address: 525 West A Street
Hayward, CA

Date: 11/29/06

Project No: RPMS-0877

Recorded By: Todd Skelton

Weather: Sunny 70° No Wind

Well No.	Time	Depth to Groundwater	Measured Total Depth	Diameter	Total Volume	Depth to Product	Product Description	Comments
MW-1	1:10	13.97	30.00	4	31.00			
MW-1A	4:20	13.12	30.00	2	8.00			Strong Hydro odor
MW-3	2:11	13.33	34.00	4	40.00			
MW-4	1:35	14.48	30.00	4	30.00			
MW-5	12:45	14.16	30.00	4	30.00			
MW-6	12:15	14.42	30.00	4	30.00			
MW-7	12:10	13.27	30.00	2	8.00			
MW-12	11:20	15.67	30.00	2	7.00			
MW-14	11:45	15.57	30.00	2	7.00			
EX-1	2:10	14.93	34.00	6	84.00			

Notes:

Waste: Drums 8 Date 11/29/06 Contents Purge Water/ Decon

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-1 Project Name Hayward Client RPMS 0877

Location (address) 525 West A Street, Hayward, CA

Date Sampled 11/29/06

Well Depth 36.00 ft below top of casing Casing diameter 4 inches

DTW (below top of casing) 13.97 ft. Time: 1:10

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 31

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
1:15	24.3	7.17	1237		Initial
1:20	22.9	7.04	1243		10.0
1:25	22.4	7.01	1218		20.0
1:30	22.2	6.98	1222		31.0

Comments: _____

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-1A Project Name Hayward Client RPMS-0877

Location (address) 525 W. A Street Hayward, CA

Date Sampled 11/29/06

Well Depth 30.0 ft below top of casing Casing diameter ~~4~~ 2 inches

DTW (below top of casing) 13.12 ft. Time: 4:20

DTP _____ ft.

Purging Method: ☐ Submersible pump ☒ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ ~~Disposable~~ bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 8.0

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
4:30	23.3	7.38	1134		Initial
4:34	22.8	7.22	1128		3.0
4:38	22.4	7.20	1124		6.0
4:42	22.2	7.25	1115		8.0

Comments: Strong Hydro odor

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-3 Project Name Brentwood Client RPMS-0877

Location (address) 525 West A Street, Brentwood, CA

Date Sampled 11/29/06

Well Depth 34.0 ft below top of casing Casing diameter 4 inches

DTW (below top of casing) 13.33 ft. Time: 12:11

DTP _____ ft.

Purging Method: ☐ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☐ Disposable bailer ☐ Sampling port Samples collected _____

GROUND WATER EVACUATION/STABILIZATION DATA 40

Time	Temperature (°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
4:00	22.8	6.95	1045		Initial
4:05	22.0	7.07	1056		13.0
4:10	21.7	7.08	1059		26.0
4:15	21.5	7.03	1048		40.0

Comments: _____

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-4 Project Name Hayward Client RPMS-0877

Location (address) 525 West A St. Hayward, CA

Date Sampled 11/29/06

Well Depth 30.0 ft below top of casing Casing diameter 4 inches

DTW (below top of casing) 14.48 ft. Time: 1:35

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 30

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
1:40	23.9	7.11	1220		Initial
1:45	22.8	7.16	1182		10.0
1:50	22.2	7.16	1174		20.0
1:55	21.8	7.11	1170		30.0

Comments: _____

Transportation(thermal preservation) All Smples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-5 Project Name Hayward Client RPMS-0877

Location (address) 525 W. "A" St. Hayward, CA

Date Sampled 11/29/06

Well Depth 30.0 ft below top of casing Casing diameter 4 inches

DTW (below top of casing) 14.16 ft. Time: 12:45

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
12:50	23.6	7.08	1113		Initial
12:55	22.6	6.93	1136		10.0
1:00	22.2	6.98	1150		20.0
1:05	22.0	7.01	1148		30.0

Comments: _____

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Skelton Sampled By Todd Skelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-6 Project Name Brentwood Client RPMS-0827

Location (address) 525 West A St. Hayward, CA

Date Sampled 11/29/06

Well Depth 30.0 ft below top of casing Casing diameter 4 inches

DTW (below top of casing) 14.42 ft. Time: 12:15

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 30

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
12:25	22.1	6.98	1172		Initial
12:30	21.3	7.11	1188		10.0
12:35	21.0	7.08	1180		20.0
12:40	20.7	7.03	1176		30.0

Comments: _____

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-7 Project Name Hayward Client _____

Location (address) 525 W. A St. Hayward, CA

Date Sampled 11/29/06

Well Depth 36.00 ft below top of casing Casing diameter 2 inches

DTW (below top of casing) 13.27 ft. Time: 12:10

DTP _____ ft.

Purging Method: ☐ Submersible pump ☒ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 8.0

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
12:15	21.8	6.80	998		Initial
12:18	21.6	6.83	1145		3.0
12:21	21.3	6.79	1189		6.0
12:24	21.2	6.83	1180		8.0

Comments: _____

Transportation(thermal preservation) All Samples iced IN Field

Form Completed By Todd Skelton Sampled By Todd Skelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-12 Project Name Hayward Client RPMS-0877

Location (address) 525 West A Street, Hayward, CA

Date Sampled 11/29/06

Well Depth 30.0 ft below top of casing Casing diameter 2 inches

DTW (below top of casing) 15.67 ft. Time: 11:20

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 6.8

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
11:25	19.3	7.22	676		Initial
11:28	18.8	7.11	683		2.0
11:31	18.6	7.08	686		4.0
11:34	18.5	7.04	685		7.0

Comments: _____

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. MW-14 Project Name Hayward Client RAMS-0877

Location (address) 525 West A St. Hayward, CA

Date Sampled 11/29/06

Well Depth 30.00 ft below top of casing Casing diameter 2 inches

DTW (below top of casing) 15.57 ft. Time: 11:45

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 7.0

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
11:50	18.9	6.76	876		Initial
11:53	18.7	7.11	858		2.0
11:56	18.5	7.08	849		4.0
11:59	18.3	7.03	853		7.0

Comments: _____

Transportation(thermal preservation) All Samples Iced IN Water

Form Completed By Todd Shelton Sampled By Todd Shelton

Delta Environmental Consultants, Inc.

SAMPLING INFORMATION SHEET

Well No. EX-1 Project Name Hayward Client 2ams-0877

Location (address) 525 West A Street, Hayward, CA

Date Sampled 11/29/06

Well Depth 34.0 ft below top of casing Casing diameter 6 inches

DTW (below top of casing) 14.93 ft. Time: 2:10

DTP _____ ft.

Purging Method: ☒ Submersible pump ☐ Bailer ☐ Centrifugal pump ☐ Other _____

Sampling Method: ☒ Disposable bailer ☐ Sampling port Samples collected 3

GROUND WATER EVACUATION/STABILIZATION DATA 84

Time	Temperature(°F)	pH units	Conductance (umnos/cm)	DTW (Nearest 0.01 ft)	Cumulative Volume of Water Removed From Well (gallons)
2:24	23.1	7.08	1096		Initial
2:28	22.5	7.01	1113		28.0
3:33	22.3	7.00	1124		56.0
3:46	22.4	7.02	1130		84.0

Comments: _____

Transportation(thermal preservation) All Samples iced in Field

Form Completed By Todd Shelton Sampled By Todd Shelton

ENCLOSURE C

Laboratory Analytical Results With
Chain-of-Custody Documentation

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Deborah Shulman
Delta Environmental Consultants, Inc.
3164 Gold Camp Drive, Suite 200
Rancho Cordova, CA 95670

Subject : 10 Water Samples
Project Name : Hayward
Project Number : RPMS-0877

Dear Ms. Shulman,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

Joel Kiff

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Subject : 10 Water Samples
Project Name : Hayward
Project Number : RPMS-0877

Case Narrative

Matrix Spike/Matrix Spike Duplicate Results associated with samples MW-1A, MW-12, MW-3, MW-5, MW-6, MW-7, MW-14, and EX-1 for the analyte Benzene were affected by the analyte concentrations already present in the un-spiked sample.

Approved By: Joel Kiff

2795 2nd St, Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-1** Matrix : Water Lab Number : 53654-01

Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**160**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**1.3**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**130**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**12**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**4.0**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**8.7**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**3900**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	95.0		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	101		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-1A** Matrix : Water Lab Number : 53654-02
Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**1.0**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**33**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**0.58**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**0.86**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**7.5**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**4500**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	94.4		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	103		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-3** Matrix : Water Lab Number : 53654-03
Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**1.1**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**3.3**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**0.53**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**620**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	96.7		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	101		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654

Date : 12/5/2006

Project Name : **Hayward**

Project Number : **RPMS-0877**

Sample : **MW-4** Matrix : Water Lab Number : 53654-04

Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**88**	0.50	ug/L	EPA 8260B	12/5/2006
Toluene	**11**	0.50	ug/L	EPA 8260B	12/5/2006
Ethylbenzene	**130**	0.50	ug/L	EPA 8260B	12/5/2006
Total Xylenes	**240**	0.50	ug/L	EPA 8260B	12/5/2006
Methyl-t-butyl ether (MTBE)	**5.5**	0.50	ug/L	EPA 8260B	12/5/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/5/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/5/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/5/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/5/2006
TPH as Gasoline	**4600**	50	ug/L	EPA 8260B	12/5/2006
Toluene - d8 (Surr)	92.2		% Recovery	EPA 8260B	12/5/2006
4-Bromofluorobenzene (Surr)	102		% Recovery	EPA 8260B	12/5/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-5** Matrix : Water Lab Number : 53654-05
Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**3.4**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**0.55**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**9.3**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**1.8**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**1.0**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**1700**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	101		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	102		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-6** Matrix : Water Lab Number : 53654-06

Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**0.97**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**3.1**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**1.1**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**2.5**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**1200**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	101		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	100		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-7** Matrix : Water Lab Number : 53654-07

Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**170**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	102		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	102		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-12** Matrix : Water Lab Number : 53654-08
Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**< 50**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	103		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	97.0		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **MW-14** Matrix : Water Lab Number : 53654-09
Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**59**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	104		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	107		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

Report Number : 53654
Date : 12/5/2006

Project Name : **Hayward**
Project Number : **RPMS-0877**

Sample : **EX-1** Matrix : Water Lab Number : 53654-10
Sample Date :11/29/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	**5.1**	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	**5.2**	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	**1.3**	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	**1.1**	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	**< 0.50**	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	**< 5.0**	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	**650**	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	102		% Recovery	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	104		% Recovery	EPA 8260B	12/2/2006

Approved By: Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800

Report Number : 53654

Date : 12/5/2006

QC Report : Method Blank Data

Project Name : **Hayward**

Project Number : **RPMS-0877**

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Toluene	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Total Xylenes	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Methyl-t-butyl ether (MTBE)	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Diisopropyl ether (DIPE)	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Ethyl-t-butyl ether (ETBE)	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Tert-amyl methyl ether (TAME)	< 0.50	0.50	ug/L	EPA 8260B	12/2/2006
Tert-Butanol	< 5.0	5.0	ug/L	EPA 8260B	12/2/2006
TPH as Gasoline	< 50	50	ug/L	EPA 8260B	12/2/2006
Toluene - d8 (Surr)	98.2		%	EPA 8260B	12/2/2006
4-Bromofluorobenzene (Surr)	104		%	EPA 8260B	12/2/2006
Benzene	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Toluene	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Ethylbenzene	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Total Xylenes	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Methyl-t-butyl ether (MTBE)	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Diisopropyl ether (DIPE)	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Ethyl-t-butyl ether (ETBE)	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Tert-amyl methyl ether (TAME)	< 0.50	0.50	ug/L	EPA 8260B	12/4/2006
Tert-Butanol	< 5.0	5.0	ug/L	EPA 8260B	12/4/2006
TPH as Gasoline	< 50	50	ug/L	EPA 8260B	12/4/2006
Toluene - d8 (Surr)	91.1		%	EPA 8260B	12/4/2006
4-Bromofluorobenzene (Surr)	99.8		%	EPA 8260B	12/4/2006

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed

Approved By: Joel Kiff

KIFF ANALYTICAL, LLC

2795 2nd St, Suite 300 Davis, CA 95616 530-297-4800

Report Number : 53654

QC Report : Matrix Spike/ Matrix Spike Duplicate

Date : 12/5/2006

Project Name : **Hayward**

Project Number : **RPMS-0877**

Parameter	Spiked Sample	Sample Value	Spike Level	Spike Dup. Level	Spiked Sample Value	Duplicate Spiked Sample Value	Units	Analysis Method	Date Analyzed	Spiked Sample Percent Recov.	Duplicate Spiked Sample Percent Recov.	Relative Percent Diff.	Spiked Sample Percent Recov. Limit	Relative Percent Diff. Limit
Benzene	53654-01	160	39.8	39.8	172	172	ug/L	EPA 8260B	12/2/06	29.2	29.1	0.395	70-130	25
Toluene	53654-01	1.3	39.8	39.8	38.1	37.3	ug/L	EPA 8260B	12/2/06	92.5	90.7	1.98	70-130	25
Tert-Butanol	53654-01	8.7	199	199	191	191	ug/L	EPA 8260B	12/2/06	91.8	91.6	0.239	70-130	25
Methyl-t-Butyl Ether	53654-01	4.0	39.8	39.8	39.5	41.1	ug/L	EPA 8260B	12/2/06	89.3	93.3	4.40	70-130	25
Benzene	53644-02	<0.50	40.0	40.0	39.7	38.7	ug/L	EPA 8260B	12/4/06	99.3	96.7	2.62	70-130	25
Toluene	53644-02	<0.50	40.0	40.0	36.0	35.7	ug/L	EPA 8260B	12/4/06	90.1	89.3	0.887	70-130	25
Tert-Butanol	53644-02	<5.0	200	200	210	211	ug/L	EPA 8260B	12/4/06	105	105	0.340	70-130	25
Methyl-t-Butyl Ether	53644-02	<0.50	40.0	40.0	40.0	39.0	ug/L	EPA 8260B	12/4/06	99.9	97.6	2.33	70-130	25

Approved By: Joel Kiff

KIFF ANALYTICAL, LLC

2795 2nd St, Suite 300 Davis, CA 95616 530-297-4800

Report Number : 53654

QC Report : Laboratory Control Sample (LCS)

Date : 12/5/2006

Project Name : **Hayward**

Project Number : **RPMS-0877**

Parameter	Spike Level	Units	Analysis Method	Date Analyzed	LCS Percent Recov.	LCS Percent Recov. Limit
Benzene	40.0	ug/L	EPA 8260B	12/2/06	97.6	70-130
Toluene	40.0	ug/L	EPA 8260B	12/2/06	97.4	70-130
Tert-Butanol	200	ug/L	EPA 8260B	12/2/06	93.8	70-130
Methyl-t-Butyl Ether	40.0	ug/L	EPA 8260B	12/2/06	98.3	70-130
Benzene	40.0	ug/L	EPA 8260B	12/4/06	101	70-130
Toluene	40.0	ug/L	EPA 8260B	12/4/06	92.2	70-130
Tert-Butanol	200	ug/L	EPA 8260B	12/4/06	109	70-130
Methyl-t-Butyl Ether	40.0	ug/L	EPA 8260B	12/4/06	99.5	70-130

Approved By: Joel Kiff

KIFF ANALYTICAL, LLC

2795 2nd St, Suite 300 Davis, CA 95616 530-297-4800

KIFF Analytical LLC

2795 2nd Street, Suite 300
Davis, CA 95616
Lab: 530.297.4800
Fax: 530.297.4802

SRG # / Lab No. 53654

Page 1 of 1

Chain-of-Custody Record and Analysis Request

Project Contact (Hardcopy or PDF To): Deborah Shulman	California EDF Report? ☒ Yes ☐ No
Company / Address: Delta Environmental	Sampling Company Log Code:
Phone #: 800 477-7411 / Fax #:	Global ID:
Project #: RPMS-0877 / P.O. #:	EDF Deliverable To (Email Address): dmate@deltaenv.com
Project Name: Hayward	Sampler Signature: Todd Shelton
Project Address: 525 West A St. Hayward, CA	

Sample Designation	Sampling: Date	Sampling: Time	Container: 40 ml VOA	Container: Sleeve	Container: Poly	Container: Glass	Container: Tedlar	Preservative: HCl	Preservative: HNO_3	Preservative: None	Matrix: Water	Matrix: Soil	Matrix: Air	Analysis Request: MTBE (EPA 8260B) per EPA 8021 level @ 5.0 ppb	Analysis Request: MTBE (EPA 8260B) @ 0.5 ppb	Analysis Request: BTEX (EPA 8260B)	Analysis Request: TPH Gas (EPA 8260B)	Analysis Request: 5 Oxygenates (EPA 8260B)	Analysis Request: 7 Oxygenates (EPA 8260B)	Analysis Request: Lead Scav.(1,2 DCA & 1,2 EDB-EPA 8260B)	Analysis Request: Volatile Halocarbons (EPA 8260B)	Analysis Request: Volatile Organics Full List (EPA 8260B)	Analysis Request: Volatile Organics (EPA 524.2 Drinking Water)	Analysis Request: TPH as Diesel (EPA 8015M)	Analysis Request: TPH as Motor Oil (EPA 8015M)	Analysis Request: Total Lead (EPA 6010)	Analysis Request: W.E.T. Lead (STLC)	TAT	For Lab Use Only
mw-1	11/29/06		3					X			X					X	X	X											1 wk	01
mw-1A																														02
mw-3																														03
mw-4																														04
mw-5																														05
mw-6																														06
mw-7																														07
mw-12																														08
mw-14																														09
EX-1																														10

Relinquished by: Todd Shelton / Todd Shelton	Date 12/6/06	Time	Received by:	
Relinquished by:	Date	Time	Received by:	
Relinquished by:	Date 120206	Time 1130	Received by Laboratory:	Kiff Analytical

Remarks: All Samples Iced IN Field

Bill to:

For Lab Use Only: Sample Receipt

Temp °C	Initials	Date	Time	Therm. ID #	Coolant Present
-.9	AOC	120206	1125	IR-4	(Yes) No

Distribution: White - Lab; Pink - Originator
Rev: 051805