

January 9, 1992

Alameda County Environmental Health Department 80 Swan Way, Room 200 Oakland, California 94621

Attention: Mr. Ed Howell

Gentlemen:

Quarterly Technical Reports Fourth Quarter 1991 Three Shell Oil Company Sites East Bay Retail District

Enclosed are copies of quarterly technical reports for two Shell Oil Company sites in Alameda County on which Shell service stations are/or were located. These reports are issued to you on behalf of Shell Oil Company.

The sites for which reports are enclosed are specifically:

- 5755 Broadway, Oakland
- · 6039 College Avenue, Oakland

We trust that this provides the information required at this time. Please call if you have questions.

Yours very truly,

HARDING LAWSON ASSOCIATES

Terence J. McManus

Associate Environmental Scientist

TJM/tls 017/TJM1

cc: Shell Oil Company (without enclosure)

Environmental Engineering

P.O. Box 5278

Concord, California 94520

Attention: Mr. E. Paul Hayes

## 22 111113 61 2:57

A Report Prepared for

Shell Oil Company Environmental Engineering P.O. Box 5278 Concord, California 94520

QUARTERLY TECHNICAL REPORT FOURTH QUARTER OF 1991 SHELL SERVICE STATION 5755 BROADWAY OAKLAND, CALIFORNIA SHELL WIC NO. 204-5510-0303

HLA Job No. 4022,218.03

94618

by

Michael J. Brink Project Engineer

Donald G. Gray

Geotechnical Engineer

GE 351 Exp 12/31/93

Harding Lawson Associates 1355 Willow Way, Suite 109 Concord, California 94520 510/687-9660

January 2, 1992

#### INTRODUCTION

This Quarterly Technical Report by Harding Lawson Associates (HLA) describes the status of our continuing evaluation of the presence of petroleum hydrocarbons in soil and groundwater in the vicinity of the Shell Oil Company (Shell) service station at 5755 Broadway in Oakland, California (Plate 1). This report discusses the site history and investigation progress through the fourth quarter of 1991, and summarizes activities we plan to undertake in the first quarter of 1992.

#### SITE HISTORY

HLA understands that this facility was a Thrifty service station prior to 1972, when Shell leased the parcel for its current activities. The facility consists of three underground storage tanks (USTs), four canopy-covered dispenser islands, and a combined office building and cashier booth (Plate 2). The current USTs, each of 10,000-gallon capacity and double-wall fiberglass construction, were installed in late 1985 and are used for the storage of gasoline (regular leaded, unleaded, and super unleaded).

As part of a soil and groundwater assessment in June 1985, Gettler-Ryan Inc. (GRI) installed one soil boring (S-A) and a separate 4-inch-diameter monitoring well (S-1) on the site to depths of approximately 12 feet. Boring logs, well construction details, and results of analyses on samples were presented to

Shell in a letter from EMCON Associates (subcontractor to GRI) dated August 1, 1985. Low concentrations (up to 3 parts per million [ppm]) of total petroleum hydrocarbons (TPH) as gasoline were detected in soil samples from 5 to 10 feet deep in S-A, although a deeper soil sample (about 11.5 feet below grade) contained no detectable concentrations of TPH as gasoline. Table 1 shows these results, along with results of subsequent soil sampling and analyses performed by HLA.

A groundwater sample collected in 1985 from the monitoring well (S-1) had TPH as gasoline at 2,400 parts per billion (ppb), and benzene at 240 ppb (Table 2). These data indicated that petroleum hydrocarbons had entered the soil and groundwater on site.

On August 10, 1989, Shell retained HLA to complete the site assessment and evaluate the need for remediation. On August 15, 1989, HLA obtained a groundwater sample from S-1. That sample contained concentrations of TPH as gasoline and benzene (Table 2) in respective concentrations of 170 and 0.6 ppb.

In September 1989, HLA drilled two soil borings, S-2 and S-3. Drilling was performed under the direction of an HLA field engineer, who obtained soil samples and converted the borings to groundwater monitoring wells in the manner outlined in HLA's work plan dated October 13, 1989. HLA has monitored the wells quarterly since November 1989, including collection and analysis of water samples. Results of analyses on soil and groundwater samples are summarized in Tables 1 and 2, respectively.

ACCOMPLISHMENTS DURING THE FOURTH QUARTER OF 1991

## Groundwater Sampling

On November 22, 1991, HLA collected groundwater samples from S-1 through S-3. Before sampling, approximately three casing volumes of water was purged from each well while monitoring temperature, pH, dissolved oxygen, and conductivity. After these parameters stabilized, groundwater samples were collected with a Teflon<sup>TM</sup> bailer, and decanted directly into laboratory-prepared volatile organic analysis (VOA) vials. Between wells, all purging and sampling equipment was cleaned with an Alconox solution and rinsed with deionized water. The sample containers were labeled and placed into an ice-chilled cooler and delivered under chain-of-custody to Sequoia Analytical Laboratory, a state-certified chemical testing laboratory in Redwood City, California. Samples were analyzed for TPH as gasoline (USEPA Test Method 8015, modified) and for benzene, toluene, ethylbenzene, and total xylenes (BTEX [USEPA Test Method 8020]).

#### Chemical Test Results

The results of chemical analyses on groundwater samples are presented in Table 2; concentrations of TPH as gasoline and benzene are shown on Plate 2. The laboratory report and chain-of-custody are in the appendix. Results of analysis on groundwater from S-1 indicated 2.3, 0.46, and 0.65 ppb of benzene, toluene, and xylenes, respectively; TPH as gasoline and ethylbenzene were not detected in groundwater from S-1. Results

of analyses on groundwater from S-2 indicated 1,600 ppb of TPH as gasoline, and 110, 9.3, 29 and 150 ppb, respectively, for the BTEX compounds. The water sample from S-3 showed non-detectable concentrations of all compounds tested. As shown in Table 2, the concentrations of petroleum hydrocarbons in groundwater from S-1 and S-2 have fluctuated since these wells were installed. Data for S-3 have consistently shown non-detectable concentrations of TPH and BTEX components since that well was installed in September, 1989.

#### Water-level Measurements

Water-level measurements were obtained on November 22, 1991, using a chalked steel tape accurate to 0.01 feet. Well survey and water-level data are presented in Table 3. Shallow groundwater, as measured in S-1 through S-3, was between 4 and 5 feet below grade. The direction of groundwater flow, as inferred from the calculated direction of the hydraulic gradient, is to the south (Plate 2). The groundwater elevation has dropped slightly during the last quarter. The rate of groundwater movement was not determined in this study.

#### ANTICIPATED ACTIVITIES FOR THE FIRST QUARTER 1992

The following tasks are planned by Shell for the first quarter of 1992:

- Conduct quarterly monitoring activities, including measurement of water levels, checking for free product, and sampling of groundwater from each of the monitoring wells.
- Submit groundwater samples for TPH and BTEX analyses.
- Prepare a quarterly report with results of the monitoring activities and results of groundwater analyses.

## LIST OF TABLES

Table	1	Summary of Analyses on Soil Samples
Table	2	Summary of Analyses on Groundwater Samples
Table	3	Well-survey and Water-level Data

## LIST OF ILLUSTRATIONS

Plate	1	Vicinity Map
Plate	2	Site Plan

#### APPENDIX

Laboratory Report and Chain-of-Custody

TABLES

Table 1. Summary of Analyses on Soil Samples

Sample <u>Number</u>	Depth (ft)	Sampling <u>Date</u>	TPH as Gasoline (ppm)	Benzene (ppm)	Toluene (ppm)	Ethyl- benzene (ppm)	Xylenes _(ppm)
S-A*	5.5	06/12/85	3				
S-A*	10	06/12/85	2				
S-A*	11.5	06/12/85	ND				
S-2-1	3.0	09/18/89	92	.120	.800	.580	4.20
s-3-1	3.0	09/18/89	ND (10)	ND (.025)	.062	ND (.025)	.120

Detection limits in parentheses

ND = Not detected

TPH = Total petroleum hydrocarbons

<sup>\*</sup> From Emcon report dated 08/01/85

<sup>--</sup> Not Tested

Table 2. Summary of Analyses on Groundwater Samples

Well <u>Number</u>	Sampling	TPH as Gasoline (ppb)	Benzene (ppb)	Toluene (ppb)	Ethyl- benzene (ppb)	Xylenes (ppb)
s-1	07/03/85* 08/15/89 11/13/89 01/18/90 04/11/90 07/27/90 10/17/90 01/25/91 06/03/91 08/30/91	2,400 170 90 ND (50) 520 ND (30) ND (30) ND (30) ND (30)	240 0.6 1.2 57 120 2.7 0.99 ND (.3) ND (.3) ND (.3)	9.8 ND (.5) ND (.5) 3.1 2.2 0.31 ND (.3) ND (.3) ND (.3) ND (.3)	380 ND (1.5) ND (1.5) 5.7 .44 ND (.3) ND (.3) ND (.3) ND (.3) ND (.3)	ND (1.5) ND (1.5) 10 6.0 0.47 ND (.3) ND (.3) ND (.3) ND (.3)
S-2	11/22/91 09/22/89 11/13/89 01/18/90 04/11/90 07/27/90 10/17/90 01/25/91 06/03/91 08/30/91 11/22/91	ND (30)  260 910 1,100 2,900 700 320 450 490 70 1,600	2.3 15 64 74 510 210 44 140 150 0.37 110	0.46 2 5.8 5.6 6.5 2.5 0.75 1.8 2.7 ND (.3) 9.3	ND (.3)  1 13 13 29 18 7.9 6.2 8.2 ND (.3)	0.65  13 84 45 120 33 4.6 15 7.0 ND (.3) 150
S-3	09/22/89 11/13/89 01/18/90 04/11/90 07/27/90 10/17/90 01/25/91 06/03/91 08/30/91 11/22/91	ND (50) ND (50) ND (50) ND (30)	ND (.5) ND (.5) ND (.5) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3)	ND (.5) ND (.5) ND (.5) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3)	ND(1.5) ND(1.5) ND (.5) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3)	ND(1.5) ND(1.5) ND (.5) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3) ND (.3)

Detection limits in parentheses

ND = Not present above detection limits

ppb = Parts per billion

TPH = Total petroleum hydrocarbons

\* From EMCON report dated 08/01/85


-- = Not tested

Table 3. Well-survey and Water-level Data

Well Number		Top of Casing (feet)	Depth to Groundwater (feet)	Relative Groundwater Elevation (feet)
S-1	10/05/89	*100.00	3.80	96.20
	11/13/89		3.72	96.12
	01/18/90		2.87	97.13
	02/20/90		2.71	97.29
	04/11/90		3.36	96.64
	07/27/90		3.60	96.40
	10/17/90		4.09	95.91
	01/25/91		3.88	96.12
	06/03/91		3.51	96.49
	08/30/91		4.24	95.76
	11/22/91		4.29	95.71
s-2	10/05/89	98.92	4.44	94.48
	11/13/89		4.44	94.48
	01/18/90		3.41	95.51
	02/20/90		3.19	95.73
	04/11/90		3.94	94.98
	07/27/90		4.13	94.79
	10/17/90		4.57	94.35
	01/25/91		4.52	94.40
	06/03/91		4.02	94.90
	08/30/91		4.70	94.22
	11/22/91		4.72	94.20
s-3	10/05/89	101.67	3.97	97.70
	11/13/89		3.76	97.91
	01/18/90		2.43	99.24
	02/20/90		2.27	99.40
	04/11/90		2.88	98.79
	07/27/90		3.55	98.12
	10/17/90		4.29	97.38
	01/25/91		3.84	97.83
	06/03/91		3.25	98.42
	08/30/91		4.73	96.94
	11/22/91		4.81	96.86

<sup>\*</sup> Temporary datum of 100.00 feet assigned to top-of-casing at well number S-1

ILLUSTRATIONS





Engineering and Environmental Services


JOB NUMBER DRAWN 4022,218.03 KΗ

Shell Service Station

5755 Broadway Oakland, California APPROVED

DATE 8/89

REVISED DATE



#### APPENDIX

LABORATORY REPORT AND CHAIN-OF-CUSTODY



Harding Lawson Associates 1355 Willow Way, Suite 109 Concord, CA 94520 Attention: Mike Brink

HARDING ASSOC.

Project: 5755 Broadway, Shell

DEC 9 1991

Enclosed are the results from 3 water samples received at Sequoia Analytical on November 22,1991. The requested analyses are listed below:

SAMPLE #	SAMPLE DESCRIPTION	DATE OF COLLECTION	TEST METHOD
1115111	Water, S-1	11/22/91	EPA 5030/8015/8020
1115112	Water, S-2	11/22/91	EPA 5030/8015/8020
1115113	Water, S-3	11/22/91	EPA 5030/8015/8020

Please contact me if you have any questions. In the meantime, thank you for the opportunity to work with you on this project.

Very truly yours,

SEQUOIA ANALYTICAL

Maile A. Springer Project Manager



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063 (415) 364-9600 • FAX (415) 364-9233

Harding Lawson Associates Client Project ID: 1355 Willow Way, Suite 109

Matrix Descript:

5755 Broadway, Shell Water

Sampled: Received:

Nov 22, 1991 Nov 22, 1991

Concord, CA 94520 Attention: Mike Brink Analysis Method: First Sample #:

EPA 5030/8015/8020 111-5111

Analyzed: Reported:

Dec 2, 1991 oorted: | Dec 3, 1991

# TOTAL PETROLEUM FUEL HYDROCARBONS with BTEX DISTINCTION (EPA 8015/8020)

Sample Number	Sample Description	Low/Medium B.P. Hydrocarbons μg/L (ppb)	Benzene μg/L (ppb)	Toluene μg/L (ppb)	Ethyl Benzene μg/L (ppb)	<b>Xylenes</b> μg/L (ppb)
111-5111	S-1	N.D.	2.3	0.46	N.D.	0.65
111-5112	S-2	1600	110	9.3	29	150
111-5113	S-3	N.D.	N.D.	N.D.	N.D.	N.D.

Detection Limits:	30	0.30	0.30	0.30	0.30
I					

Low to Medium Boiling Point Hydrocarbons are quantitated against a gasoline standard. Analytes reported as N.D. were not present above the stated limit of detection.

SEQUOIA ANALYTICAL

Maile A. Springer Project Manager

1115111 HAO <1>



1355 Willow Way, Suite 109

Concord, CA 94520

Client Project ID: 5755 Broadway, Shell

Attention: Mike Brink QC Sample Group: 1115111; 1115113 Reported: Dec 3, 1991

#### **QUALITY CONTROL DATA REPORT**

ANALYTE	<del></del>		Ethyl-				
	Benzene	Toluene	Benzene	Xylenes		t.	
						, ,	
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020			
Analyst:	A.P. Maralit	A.P. Maralit	A.P. Maralit	A.P. Maralit	•		
Reporting Units:	μg/L	μg/L	μg/L	μg/L			
Date Analyzed:	Dec 2, 1991	Dec 2, 1991	Dec 2, 1991	Dec 2, 1991			
QC Sample #:	GBLK120291	GBLK120291	GBLK120291	GBLK120291			
Sample Conc.:	N.D.	N.D.	N.D.	N.D.			
						1	
Spike Conc.							
Added:	10	10	10	30			
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				00			
Conc. Matrix			•				
Spike:	8.3	8.4	8.4	25			
Matrix Spike							
% Recovery:	83	84	84	83			
•							
Conc. Matrix	0.0	0.0	0.0	05			
Spike Dup.:	8.2	8.3	8.3	25			
Matrix Spike							
Duplicate							
% Recovery:	82	83	83	83			
•							
ana 1 a t							
Relative	1.0	1.0	1.0	0.0			
% Difference:	1.2	1.2	1.2	0.0			

**SEQUOIA ANALYTICAL** 

% Recovery:

Conc. of M.S. - Conc. of Sample Spike Conc. Added

x 100

Helative % Difference:

Conc. of M.S. - Conc. of M.S.D. (Conc. of M.S. + Conc. of M.S.D.) / 2 x 100

Maile A. Springer Project Manager

1115111.HAO <2>



Delta Environmental Consultants Client Project ID: 3725 Tracy Blvd., Shell

3330 Data Drive

Rancho Cordova, CA 95670

Attention: Mike Brink QC Sample Group: 111-4566 Reported: | Dec 3, 1991

### **QUALITY CONTROL DATA REPORT**

ANALYTE			Ethyl-		 
	Benzene	Toluene	Benzene	Xylenes	
Method: Analyst: Reporting Units: Date Analyzed: QC Sample #:	EPA 8020 M. Laikhtman μg/L Dec 3, 1991 GBLK120391	1			
Sample Conc.:	N.D.	N.D.	N.D.	N.D.	
Spike Conc. Added:	10	10	10	30	
Conc. Matrix Spike:	10	10	10	31	I
Matrix Spike % Recovery:	100	100	100	103	•
Conc. Matrix Spike Dup.:	9.4	9.7	10	30	
Matrix Spike Duplicate % Recovery:	94	97	100	100	
Relative % Difference:	6.2	3	0.0	3.3	

**SEQUOIA ANALYTICAL** 

<sup>I</sup>Maile A. Springer Project Manager

% Recovery:	Conc. of M.S Conc. of Sample	x 100	
	Spike Conc. Added		į
Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100	
	(Conc. of M.S. + Conc. of M.S.D.) / 2	•	1

1115111.HAO <3>

SHELI RETAIL	SHELL OIL COMPANY RETAIL ENVIRONMENTAL ENGINEERING - WES Site Address:								CHAIN OF CUSTODY RECORD Serial No.:									e: ///2			
5755 Brog	2404	. برم <sup>و</sup>					Analysis Required					T	LAB: Page / of /								
1 77 13 77			ANI			-	7-	1	, T		T -	1	T -		-						
204-5510 Shell Engineer:	-030 :	<u> </u>	Phone	Vo 57	6	-											_	BOX ONLY CT/DT			
PAUL H	AVES		Fax #:	65-	。 3052 <i>3943</i>											e inves		/- I		ours [	=
HARDON AC Addres	s:	20.0	e c			1									Soi	il for d	isposa	I <u></u> 5442		ours [	(Normal)
(355 Willow WAY, Ste 109 Concers CA94520 COnsultant Contact:  Phone No. 5/0 1887-9660				CA 94520	2	   <del> </del>	1	6							ter for	-		Other		( to the late	
MIKE BRINI	K		Fax #:	687	9660	Gas	Diesel)	1	8240)			1			1			O&M   5452			fy Lab as
Comments: Fax #: 687-9673					<u>-46+5</u>	Mod.	8015 Mod.	8020/602)	S (EPA						Oti		nple -	373 COLIN   3433	SOOR :	as possi hrs. TA	ble of
Sampled By: DOYECN Printed Name:		1	ı —ı		1	TPH (EPA 8015	EPA F	BTEX (EPA 80)	Volatile Organics	Test for Disposal					Container Size	Preparation Used	Composite Y/N	MATERIAL DESCRIPTION		COND	IPLE ITION/ ÆNTS
Sample ID	Date	Soil	Water	Air	No. of conts.	E	TPH	BT	Vo.	Tes					25		3			COM	ILITIO
5-1	11/22/91	<u> </u>	X		3	ĮХ		X							V <sub>0</sub> A	HCL	N	GROUNDWATE	2 1	1151	11
<u>S-Z</u>			X		3	X		X				J			VoA	HCL	N	"	7	$\overline{C}$	15
S-3		<u> </u>	入		3	X		X							VoA	HCL	N	/1	1	1	13
											<del></del> -										
															_						
			·																-	<del>-</del>	
Relinquished By (signature):			d name:	1/10	1101	Date:	11/22	191	Reg	cived	(sig	natur	ál):				Drints	d name:			
conquished By signature):			ech	MR	Mer	Time	6:1	Son	W	m	$_{\mathcal{U}}$	W	Ŏ.U	M	rod	1	ŒU	NVANSLAMBROD	K	Date: )	1.21.91 9.30am
Alex Youx Cambo	Art -		WAN	SIA		Bate: Time:			Rece	ived	(sigi	natur	.).				Printe	d name:		Date:	
clinquished By (signature):		Printed	name:		· · · · · · · · · · · · · · · · · · ·	Date:		777	Rece	ived	(sign	nature	:):		<del></del> -		D.:	d name:		Time:	
	771797 7 4			·- <del></del>		Time			12	1710		10 .		1125	103			, ,		Date: Time:	
est Revision Date: 10/15/91	THELA	OUKAT	ORY M	UST I	PROVIDE	A CC	PY	OF T	HIS	CH	NIN	ØF-	CUS	STOD	Y WI	AI HT	IVOI	NGUYEN CE AND RESULTS		inic.	

#### DISTRIBUTION

1 copy: Shell Oil Company

Environmental Engineering

P. O. Box 5278

Concord, California 94520 Attention: Mr. E. Paul Hayes

1 copy: Shell Oil Company

Environmental Engineering

P. O. Box 5278

Concord, California 94520 Attention: Ms. Lisa Foster

1 copy: San Francisco Bay Regional

Water Quality Control Board 2101 Webster Street, Suite 500 Oakland, California 94607

Attention: Mr. Tom Callaghan

1 copy: Alameda County Environmental

Health Department 80 Swan Way, Room 200

Oakland, California 94621 Attention: Mr. Ed Howell

MJB/DGG/pkp 032523M/R52

QUALITY CONTROL REVIEWER

Teren & Mc Mama

Terence J. McManus

Associate Environmental Scientist