

Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, CA 95076

(831) 722-3580 (831) 662-3100 Fax: (831) 722-1159 December 27, 2002 Project H9042:C/Q

Mr. Jerry Harbert 46765 Mountain Cove Drive Indian Wells, California 92210

Subject:

**Proposed Site-Specific Cleanup Goals** 

**Groundwater Monitoring Report - Third Quarter 2002** 

Harbert Transportation

19984 Meekland Avenue, Hayward, California

Dear Mr. Harbert:

This report presents proposed site-specific cleanup goals and documents groundwater monitoring activities conducted by Weber, Hayes and Associates at the former Harbert Transportation facility, 19984 Meekland Avenue, Hayward, California, during the third quarter 2002. This report has been prepared pursuant to a directive from the Alameda County Health Care Services Agency/Environmental Health Services (Environmental Health) regarding a release of petroleum hydrocarbons from underground storage tanks at the site.

#### **EXECUTIVE SUMMARY**

This quarter we completed calculations of site-specific cleanup goals for those petroleum hydrocarbons (PHCs) which had not yet had cleanup levels set (ethylbenzene, xylenes, and TPH-g, see Weber, Hayes and Associates, June 18, 2001, Environmental Health/Regional Board Memo, August 8, 2000). We then compared the calculated cleanup goals with residual concentrations of PHCs in soil and groundwater. This comparison indicates that concentrations of PHCs in soil and groundwater are below the calculated cleanup goals.

If concentrations of PHCs in groundwater remain below cleanup goals for one more quarter, we recommend that the fuel leak investigation and cleanup at the site be closed. This report also presents the results of the third quarter of post-cleanup groundwater monitoring which indicates that PHC concentrations in groundwater are below the proposed cleanup goals.

The groundwater monitoring event for the third quarter 2002 took place on August 27, 2002. Groundwater elevations at the site fell an average of approximately 0.90 feet since the previous quarter (June 2002). The calculated groundwater flow direction on August 27, 2002 was to the west, which appears to be generally consistent with historical data. Groundwater analytical results from the third quarter 2002 indicate that dissolved PHCs remain in groundwater, but at concentrations that are below the proposed site-specific cleanup goals.

Methyl-tert-Butyl Ether (MTBE) was not detected in the groundwater samples collected this quarter. MTBE has not been detected in soil or groundwater at the site. Groundwater samples in the third quarter 2000 were analyzed for the fuel oxygenates Di-isopropyl Ether, tertiary Butyl

Alcohol, Ethyl tertiary Butyl Ether, and tertiary Amyl Methyl Ether. No fuel oxygenates were detected in the groundwater samples.

The Alameda County Health Care Services Agency/Environmental Health agreed with our first quarter 2002 recommendation to decrease the sampling frequency of selected site monitoring wells. The revised sampling schedule will comprise sampling monitoring wells MW-3, 5, 6, 9, and 10 quarterly, monitoring well MW-7 semi-annually (second and fourth quarters only), and all of the wells annually in the fourth quarter.

#### At this time we recommend:

- Continuing quarterly groundwater monitoring of dissolved PHC concentrations at the site for one more quarter (three quarters of post cleanup groundwater monitoring have been completed since excavation of PHC-impacted soil in January 2002, and dissolved PHC concentrations have been below cleanup goals).
- Closing the fuel leak investigation and cleanup if PHC concentrations in groundwater remain below cleanup goals next quarter.

#### INTRODUCTION

This report presents proposed cleanup goals and documents groundwater monitoring activities at the former Harbert Transportation facility, 19984 Meekland Avenue, Hayward, California (the site) during the third quarter 2002. This report has been prepared pursuant to a directive from the Alameda County Health Care Services Agency/Environmental Health Services (Environmental Health, August 8, 2000) regarding a release of petroleum hydrocarbons (PHCs) from underground storage tanks (USTs) at the site.

This quarter we completed calculations of cleanup goals for those PHCs which had not yet had cleanup levels set (ethylbenzene, xylenes, and TPH-g, see Weber, Hayes and Associates, June 18, 2001, Environmental Health/Regional Board Memo, August 8, 2000). We then compared the calculated cleanup goals with residual concentrations of PHCs in soil and groundwater.

# Residual concentrations of PHCs in soil and groundwater at the site are BELOW the proposed cleanup goals.

Groundwater samples are collected and analyzed for PHCs according to the following schedule (Alameda County Health Care Services Agency Case Officer communication, July 29, 2002).

Quarterly: Wells MW- 3, 5, 6, 9, and 10.

Semi-Annually Well MW-7 (second and fourth quarter). Annually: All Wells (MW-3 - 12, fourth quarter).

Groundwater monitoring activities conducted during this quarter included:

- 1. Measuring groundwater levels and checking for the presence of free product in all of the monitoring wells associated with the site
- 2. Measuring the physical parameters of pH, temperature, electrical conductivity, and dissolved oxygen concentration in each well
- 3. Collecting groundwater samples from each of the appropriate monitoring wells
- 4. Submitting the groundwater samples to a state-certified analytical laboratory for analysis of dissolved PHC concentrations following proper chain-of-custody procedures
- 5. Determining groundwater elevations, flow direction, and gradient in the vicinity of the site
- 6. Mapping the extent of the dissolved PHC plume in groundwater beneath the site
- 7. Preparing this technical report

#### Site Description And Background

The site is located at the corner of Meekland Avenue and Blossom Way in Alameda County California, at an elevation of approximately 55 feet above sea level (Figure 1). The site is relatively flat and is currently vacant.

The site was operated as a motor vehicle fueling station since the 1940's. Harbert Transportation used the site as a vehicle and fueling yard before selling the site to Durham Transportation in 1986.

In August 1989, four underground storage tanks (USTs) were removed from the site and properly disposed of. Soil and groundwater investigations at the site, conducted by Applied Geosystems, CTTS, and AGI Technologies, indicated that PHCs were present in soil and groundwater at the site. A list of reports documenting the soil and groundwater investigations is included in the Reference section. Ten groundwater monitoring wells currently exist at the site. Groundwater samples were not collected from these wells between September 1996 and September 2000. Documentation indicates that excavated soil from the UST removals was returned to the (reportedly plastic-lined) excavations (CTTS, November 1, 1992).

Documentation also indicates that two USTs were removed from the site in the early 1950's (CTTS, November 27, 1990). These USTs were located near the dispensers for the USTs removed in 1989.

On February 14, 2001, we collected soil samples from the site to determine the extent of PHCs remaining in the unsaturated zone in accordance with our September 7, 2000 Work Plan. Analysis of the data collected indicated the predominant soil types were sandy clay and clay (see Figures 2 and 3), and confirmed that significant concentrations of PHCs remained in soils beneath the former dispensers and in the 1989 UST excavation which was backfilled with the excavated material. We recommended excavation of these residual PHCs as an Interim Remedial Action (Weber, Hayes and Associates, June 18, 2001). Environmental Health concurred with this recommendation in a letter dated June 26, 2001.

On January 7 - 10, 2002 we conducted an interim remedial action excavation using six foot diameter augers to remove contaminated soils from the subsurface. Approximately 594 yds³ of PHC-impacted soil was removed from the subsurface and transported to an appropriate landfill facility for disposal. A pump was installed in one of the large diameter boreholes and 3,000-gallons of PHC impacted water was removed from the subsurface and disposed of properly. Oxygen Release Compound® (ORC) was added to the saturated zone in each borehole to promote microbial growth and enhance the ability of aerobic microbes to degrade contaminants. Each borehole was backfilled with control density fill and clean fill soil to ground surface (Weber, Hayes and Associates, Large Diameter Excavation and 4th Quarter 2001 Quarterly Groundwater Monitoring, February 8, 2002).

In the first quarter 2002, we recommend that the frequency of sampling in monitoring well MW-7 be reduced to semi-annually (second and fourth quarters) and that the frequency of sampling in monitoring wells MW-4, 8, 11 and 12 be reduced to annually (fourth quarter only). Alameda County Environmental Health concurred with our recommendations in a telephone conversation on July 29, 2002.

#### SUMMARY OF QUARTERLY ACTIVITIES

#### **Proposed Cleanup Goals**

On August 8, 2000, we met with Environmental Health and San Francisco Regional Water Quality Control Board (Regional Board) staff to discuss the site status and future work. Environmental Health and Regional Board staff agreed with our recommendations for soil sampling and groundwater monitoring, and suggested developing soil and groundwater cleanup goals for all PHCs detected at the site. Environmental Health and Regional Board staff approved the following cleanup goals for the site:

#### Approved Soil Cleanup Goals (mg/kg, ppm)

Chemical	TPH-g	Benzene	Toluene	Ethylbenzene	Xylenes
Surface Soil		0.118	150		
Sub-Surface Soil	1,000	0.118	150		vaera

This quarter we completed calculations of cleanup goals for those PHCs which had not yet had cleanup levels set (ethylbenzene, xylenes, and TPH-g, see Weber, Hayes and Associates, June 18, 2001, Environmental Health/Regional Board Memo, August 8, 2000). Cleanup Goals were not developed for Methyl tert Butyl Ether (MTBE) because it has not been detected in soil or groundwater at the site. We then compared the calculated cleanup goals with residual concentrations of PHCs in soil and groundwater.

We calculated cleanup goals for PHCs using Groundwater Services, Inc.'s (GSI's) RBCA Tool Kit for Chemical Releases, Version 1.3 (RBCA Toolkit). This software is designed to complete all calculations required for Tiers 1 and 2 of the Risk-Based Corrective Action (RBCA) planning process as defined in the American Society for Testing and Materials (ASTM) PS-104 Standard Provisional Guide for Risk-Based Corrective Action. We used the RBCA Toolkit to calculate Site-Specific Target Levels (SSTLs) - the maximum concentrations of a chemical contaminant that may be left at a site that will not exceed the acceptable risk to human health (acceptable risk is defined as one excess cancer per million population, 1 x 10<sup>-6</sup>).

We used the following characteristics of the site in our calculations:

•	Predominant soil type	Sandy Clay, Clay
•	Contaminated soil area (see Figure 4) 40 ft X 40 ft	1,600 sq. ft.
•	Length of contaminated soil parallel to wind (maximum assumed)	40 ft.
•	Length of contaminated soil parallel to groundwater (maximum assume	ed) 40 ft.
•	Soil porosity	0.38
•	Depth to groundwater	23 ft.
•	On-site/local shallow groundwater not used for drinking water (drinking utilities from off-site sources	water supplied by
•	Site use	Residential
•	Distance to closest off-site residence	75 ft.
•	Distance to closest off-site groundwater receptor (assumed)	250 ft.

The Site-Specific Target Levels (SSTLs) we calculated for PHCs are summarized below. The RBCA Toolkit output tables for the calculations are presented as Appendix A.

# Proposed Site Specific Cleanup Goals (soil in mg/kg, ppm; groundwater in µg/L, parts per billion)

Chemical	TPH-g	Benzene	Toluene	Ethylbenzene	Xylenes
Surface Soil	38	0.118	150	87	480
Sub-Surface Soil	1,000	0.118	150	87	480
Groundwater	7,000	210	26,000	27,000	200,000

#### Comparison of Residual PHC Concentrations in Soil with Cleanup Goals

Residual concentrations of PHCs in soil are summarized on Figure 4 and in Table 1. Concentrations of PHCs in groundwater are summarized in Table 2.

The residual concentrations of PHCs in soil and groundwater at the site are below the proposed cleanup goals and fall within the limits of acceptable risk to human health and the environment.

If one more quarter of post-cleanup groundwater monitoring (this report documents the third quarter of post-cleanup monitoring, see below) indicates that PHC concentrations in groundwater remain below cleanup goals, we recommend that the fuel leak investigation and cleanup at the site be closed.

#### **Groundwater Monitoring**

The groundwater monitoring event for the third quarter 2002 took place on August 27, 2002. Field methods followed Weber, Hayes and Associates' standard field methodology for groundwater monitoring, which is described in Appendix B. Groundwater samples were collected from the appropriate monitoring wells at the site in accordance with directives from Environmental Health, and analyzed for Total Petroleum Hydrocarbons as gasoline (TPH-g) by EPA Method 8015M, and benzene, toluene, ethylbenzene, and xylenes (BTEX), and Methyl tert Butyl Ether (MTBE) by EPA Method 8020. Samples with elevated detection limits or detections of MTBE were analyzed by EPA Method 8260 to confirm the presence of MTBE and provide the proper detection limit. Field data forms are also presented in Appendix B.

#### Free Product

Free product was not observed in any of the monitoring wells at the site.

#### Groundwater Elevation and Flow Direction

Groundwater elevations were calculated by subtracting the measured depth-to-groundwater from the top-of-casing elevations, which were surveyed by a state-licensed Land Surveyor. Field measurements and the calculated groundwater elevations for the site are summarized in Table 2. Groundwater elevations at the site fell an average of approximately 0.90 feet since the previous quarter (June 2002). Calculated groundwater elevations from the gauging data collected on August 27, 2002 are shown on Figure 5. Data from this quarter indicate that groundwater flow is to the west (see Figure 5). The calculated groundwater gradient on August 27, 2002 was to the west at approximately 0.002 feet per foot. Previous reports indicate that the groundwater flow direction in the vicinity of the site has generally been in a westerly direction. A table and figures summarizing previous depth to groundwater data is presented as Appendix C.

#### Groundwater Analytical Results

Groundwater samples were collected from all of the monitoring wells associated with the site this quarter, in accordance with directives from Environmental Health. The groundwater analytical results for this quarter are summarized below.

Summary of Groundwater Sample Analytical Results, August 27, 2002 (µg/L, ppb)

Well ID	ТРН-g	Benzene	Toluene	Ethylbenzene	Xylenes	MTBE
MW-3	350	0.56	1.1	14	3.4	ND
MW-5	1,900	170	14	210	93	ND*
MW-6	1,900	< 2.5	7.2	210	55	ND*
MW-9	310	27	2.5	20	20	ND*
MW-10	1,800	< 2.5	15	3.9	5	ND*
Cleanup Goal	7,000	210	26,000	27,000	200,000	NA

<sup>\* =</sup> Confirmed by GC/MS method 8260

The concentrations of PHCs in all of the monitoring wells at the site are below the respective site-specific cleanup goals calculated for the site.

#### MTBE was not detected in any of the wells associated with the site.

Analytical results for the groundwater samples collected by Weber, Hayes and Associates are summarized in Table 2. PHC concentrations detected in groundwater during the current monitoring event are shown on Figure 6. The extent of dissolved PHCs greater than 1,000 ppb TPH-g and 10 ppb benzene in groundwater are shown on Figure 7. The trend in TPH-g and benzene concentrations in wells MW-5 and 9, along with groundwater elevations over time, are shown on Figures 9 and 10.

The Certified Analytical Report for the groundwater samples is presented as Appendix D. All laboratory quality control and quality assurance data were within acceptable limits. A table and figures summarizing analytical results of groundwater samples collected by previous consultants is presented as Appendix E.

#### Comparison of Residual PHC Concentrations in Soil with Cleanup Goals

Residual concentrations of PHCs in groundwater are summarized above and on Table 2.

The residual concentrations of PHCs in groundwater at the site are below the proposed cleanup goals and fall within the limits of acceptable risk to human health and the environment.

This report documents the third quarter of post-cleanup monitoring, with concentrations below proposed cleanup goals. If one more quarter of post-cleanup groundwater monitoring indicates that PHC concentrations in groundwater remain below cleanup goals, we recommend that the fuel leak investigation and cleanup at the site be closed.

#### **Dissolved Oxygen Measurements**

Current and historic dissolved oxygen measurements collected at the site indicate generally lower levels of dissolved oxygen in PHC impacted wells compared to levels in non-impacted, upgradient wells. The decrease in dissolved oxygen in the impacted wells is shown by the dissolved oxygen concentration contour map on Figure 8. We believe this, combined with the observed decrease in dissolved PHC concentrations over time (see Figures 9 and 10), indicates that natural attenuation of PHCs via biologic activity (bioremediation) is occurring in groundwater, with microbes using dissolved PHCs as a food source during aerobic respiration (see Bushek and O'Reilly, 1995, Table 1, Figures 5, 6, and 7, and Appendix E).

#### **SUMMARY**

- We calculated cleanup goals for PHCs this quarter. The residual concentrations of PHCs
  in soil and groundwater at the site are below the proposed cleanup goals and fall within
  the limits of acceptable risk to human health and the environment.
- Concentrations of dissolved PHCs in groundwater were generally similar to those reported last quarter. Dissolved PHC concentrations fell dramatically in MW-9 this quarter. Three quarters of post-cleanup groundwater monitoring indicate that residual PHC concentrations in groundwater are below cleanup goals.
- Free product has never been observed in any of the monitoring wells at the site.
- Groundwater elevations at the site fell an average of approximately 0.90 feet since the previous quarter (June 2002).
- The groundwater flow direction on August 27, 2002 was to the west at a gradient of approximately 0.002 feet per foot. This direction is in general agreement with data collected by us in the past three quarters and previous data collected by others at the site.

- MTBE was not detected in any of the groundwater samples collected this quarter.

  MTBE has not been detected in soil or groundwater samples collected at the site.
- Current and historic measurements of dissolved oxygen collected at the site indicate aerobic bioremediation is occurring in the PHC-impacted wells.

#### SITE CONCEPTUAL MODEL

The Site Conceptual Model (SCM) provides a compilation of our understanding of the existing site conditions:

- Soils encountered at the site generally consisted of fat clays and sandy clays. The predominance of these fine grained materials have likely retarded the movement of PHCs in the subsurface at the site.
- A review and comparison of historical groundwater analytical data with the current and recent data suggests there has been a reduction in PHC concentrations at the site of at least an order of magnitude since September 1996 (see Table 2, Figure 6, and Appendix E).
- Residual PHCs are present in soil and groundwater at the site at low levels.
- PHC concentrations in monitoring wells MW-5 and 6 were generally the same this quarter compared to last quarter. PHC concentrations in well MW-9 decreased significantly this quarter. Overall, PHC concentrations in wells MW-5, 6, and 9 show a general downward trend see Table 2 and Figures 9 and 10.
- We calculated site-specific cleanup goals based on site-specific characteristics that are protective of human health and the environment. Residual concentrations of PHCs in soil and groundwater at the site are BELOW the site-specific cleanup goals. Natural Attenuation should complete the cleanup of residual PHC concentrations in groundwater at the site to Drinking Water Action Levels/Maximum Contaminant Levels in a reasonable amount of time. Residual concentrations of PHCs in soil do not pose a threat to groundwater.
- We believe that natural attenuation/bioremediation has and will continue to remove PHCs from the site, and that natural attenuation will complete the cleanup of soil and groundwater at the site.
- MTBE has not been detected in any of the soil or groundwater samples collected at the site.
- 1,2-Dichloroethane (1,2-DCA), tetrachloroethane (PCE), and trichloroethane (TCE) were tested for as part of the original soil and groundwater investigation (by others). Low levels

of 1, 2-DCA were detected in some groundwater samples, most likely from an off-site source. Testing for these contaminants was not requested by Environmental Health as part of this investigation. We included representative concentrations of these compounds in the Risk Assessment and determined that the historical concentrations detected at the site would NOT pose a threat to human health or the environment (see Appendix A).

#### RECOMMENDATIONS

At this time we recommend:

- Continuing quarterly groundwater monitoring of dissolved PHC concentrations at the site for one more quarter (three quarters of post cleanup groundwater monitoring have been completed since excavation of PHC-impacted soil in January 2002, and dissolved PHC concentrations have been below cleanup goals).
- Closing the fuel leak investigation and cleanup if PHC concentrations in groundwater remain below cleanup goals next quarter.

#### SCHEDULE OF ACTIVITIES FOR THE FOLLOWING QUARTER

The following activities are scheduled for the next quarter:

• Quarterly groundwater monitoring according to the schedule referenced above. Groundwater monitoring will include measuring the depth-to-groundwater, dissolved oxygen concentration, and physical parameters, and collecting samples from the appropriate monitoring wells and analyzing them for TPH-g, BTEX and MTBE by EPA Methods 8015M and 8020. All detections of MTBE, or samples with no detections but elevated detection limits due to sample dilution will be confirmed by EPA Method 8260.

#### LIMITATIONS

Our service consists of professional opinions and recommendations made in accordance with generally accepted geologic and engineering principles and practices. This warranty is in lieu of all others, either expressed or implied. The analysis and proposals in this report are based on sampling and testing which are necessarily limited. Additional data from future work may lead to modification of the opinions expressed herein.

Thank you for the opportunity to aid in the assessment and cleanup of this site. If you have any questions or comments regarding this project please call us at (831) 722 - 3580.

Sincerely yours,

Weber, Hayes And Associates

Chad N. Taylor

Staff Geologist

Craig Drizin, P.

Senior Engineer

And:

Joseph Hayes

Certified Hydrogeologist #373

c: Mr. Amir Gholami, Alameda County Environmental Health

Mr. Jeff Lawson

Ms. Laurie Berger

Mr. Gregg Petersen, Durham Transportation

Mr. Chuck Headlee, San Francisco Bay Regional Water Quality Control Board

C 054081

#### Attachments:

Table 1	Summary of Soil Sample Analytical Results
Table 2	Summary of Groundwater Elevation and PHC Analytical Data
Figure 1	Location Map
Figure 2	Site Plan with Keys to Geologic Cross-Sections
Figure 3	Geologic Cross-Sections A - A' and B - B'
Figure 4	Large Diameter Auger Source Removal Footprint Map
Figure 5	Site Plan with Groundwater Elevations
Figure 6	Site Plan with PHC Concentrations in Groundwater
Figure 7	Site Plan with Extent of TPH-g and Benzene in Groundwater
Figure 8	Site Plan with Dissolved Oxygen Contours
Figure 9	TPH-g and Elevation MW-5 and MW-9
Figure 10	Benzene and Elevation MW-5 and MW-9
Appendix A	RBCA Toolkit Output Tables - Calculation of Cleanup Goals
Appendix B	Field Methodology for Groundwater Monitoring and Field Data Forms
Appendix C	Summary of Historical Depth to Groundwater Measurements, Groundwater
	Elevations, and Groundwater Flow Direction - AGI Technologies, Inc.
Appendix D	Certified Analytical Report - Groundwater Samples
Appendix E	Summary of Historical Groundwater Analytical Results - AGI Technologies, Inc.

#### REFERENCES

AGI Technologies, August 29, 1994. Quarterly Groundwater Monitoring 19984 Meekland Avenue, Hayward, California

AGI Technologies, September 19, 1994. Quarterly Groundwater Monitoring 19984 Meekland Avenue, Hayward, California

AGI Technologies, February 1, 1995. Quarterly Groundwater Monitoring 19984 Meekland Avenue, Hayward, California

AGI Technologies, August 16, 1995. Development of Risk-Based Cleanup Standards Harbert Transportation Site 19984 Meekland Avenue, Hayward, California

AGI Technologies, November 9, 1995. Work Plan Off-Site Contamination Assessment Harbert Transportation Inc. 19984 Meekland Avenue, Hayward, California

AGI Technologies, November 29, 1995. September 1996 Quarterly Groundwater Monitoring 19984 Meekland Avenue, Hayward, California

AGI Technologies, April 30, 1996. Quarterly Groundwater Monitoring 19984 Meekland Avenue, Hayward, California

AGI Technologies, January 6, 1997. September 1996 Quarterly Groundwater Monitoring 19984 Meekland Avenue, Hayward, California

AGI Technologies, February 4, 1998. Final Report Development of Risk-Based Cleanup Standards Harbert Transportation Site 19984 Meekland Avenue, Hayward, California

Alameda County Health Care Services Agency, Environmental Health Services, June 17, 1999. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Requests for Additions/Modifications to the Risk Assessment

Alameda County Health Care Services Agency, Environmental Health Services, July 11, 2000. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Groundwater Monitoring and Work Plan Request

Alameda County Health Care Services Agency, Environmental Health Services, August 8, 2000. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Groundwater Monitoring and Work Plan Request - Clarification

Alameda County Health Care Services Agency, Environmental Health Services, November 1, 2000. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Approval of Work Plan for Soil and Groundwater Sampling

#### REFERENCES (continued)

Alameda County Health Care Services Agency, Environmental Health Services, November 15, 2000. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Review of Third Quarter 2000 Groundwater Monitoring Report

Alameda County Health Care Services Agency, Environmental Health Services, December 4, 2000. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Approval of Work Plan for Soil and Groundwater Sampling

Alameda County Health Care Services Agency, Environmental Health Services, February 21, 2001. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Concur with work proposed in Fourth Quarter 2000 Groundwater Monitoring Report

Alameda County Health Care Services Agency, Environmental Health Services, June 26, 2001. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Concur with work proposed in First Quarter 2001 Groundwater Monitoring Report

Alameda County Health Care Services Agency, Environmental Health Services, November 29, 2001. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Receipt of "Status Report-UST Assessment and Cleanup" dated November 6, 2001, Concur with work proposed in Second Quarter 2001 Groundwater Monitoring Report

Alameda County Health Care Services Agency, Environmental Health Services, December 13, 2001. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - Concur with work proposed in Addendum to Interim Remedial Action and Modified Feasibility Study

Alameda County Health Care Services Agency, Environmental Health Services, January 14, 2002. Property at 19984 Meekland Avenue, Hayward, Ca 94541 - 10% Increase in Interim Remedial Action Costs Acceptable

Applied Geosystems, July 20, 1986. Subsurface Environmental Investigation, Two Soil Borings, and Monitoring Well Installation

American Society of Testing and Materials ASTM), 1998a, PS-104 Standard Provisional Guide for Risk-Based Corrective Action

Bushek, Tim, and Kirk O'Reilly, March 1995; Protocol for Monitoring Intrinsic Bioremediation in Groundwater, Chevron Research and Development Company, Health, Environment, and Safety Group

CTTS, Inc., Toxic Technology Services, September 13, 1989. Report on Underground Tank Removal at 19984 Meekland Road, Hayward, California

#### **REFERENCES** (continued)

CTTS, Inc., Toxic Technology Services, November 27, 1990. Phase II Report for Durham Transportation, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services. Amendment #1, Proposed Remediation for on Site Soil Contamination

CTTS, Inc., Toxic Technology Services, January 31, 1990. Report on Well Abandonment and Groundwater Monitoring Well Installations, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, July 2, 1990. Progress Report #1, Period Covering 3/23/90-6/30/90, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, August 2, 1990 Progress Report #2, Period Covering 7/1/90-7/31/90, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, September 21, 1990. Progress Report #3, Period Covering 8/1/90-8/31/90, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, November 12, 1990. Progress Report #4, Period Covering 9/l/90-10/31/90, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, December 28, 1990. Progress Report #5, Period Covering 11/l/90-11/30/90, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, January 25, 1991. Progress Report #7, Period Covering 1/l/91-1/31/91, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, February 11, 1991. Progress Report #6, Period Covering 12/l/90-12/31/90, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, February 19, 1991. Cost analysis, Remediation Alternatives 19984 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, April 4, 1991. Progress Report #8, Period Covering 2/l/91-3/31/91, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, June 30, 1991. Progress Report #11, Period Covering 6/l/91-6/30/9, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, September 30, 1991. Progress Report #12, Period Covering 7/l/91-9/30/91, Durham Transportation 19984 Meekland Road, Hayward, California

#### REFERENCES (continued)

CTTS, Inc., Toxic Technology Services, April 2, 1991. Report of Additional Well Installlations 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, November 1, 1992. Health and Safety Plan to Accompany Workplan for the Delineation, Containment and Remediation of Soil and Groundwater Contamination, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, November 1, 1992. Workplan for the Delineation, Containment and Remediation of Soil and Groundwater Contamination, 19984 Meekland Road, Hayward, California

CTTS, Inc., Toxic Technology Services, January 21, 1993. Progress Report #17, Period Covering 10/l/92-12/31/92, Durham Transportation 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services, March 10, 1993. Progress Report #18, Period Covering 12/l/92-1/31/93, Durham Transportation 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services, March 29, 1993. Progress Report #19, Period Covering 2/l/93-2/31/93, Durham Transportation 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services, April 1, 1993. Progress Report #20, Period Covering 3/l/93-3/31/93, Durham Transportation 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services. March 10, 1993. Remediation Progress Report 1, Period Covering 12/l/92-1/31/93, 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services. July 16, 1993. Progress Report #21, Period Covering 4/l/93-6/30/93 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services. October 11, 1993. Progress Report #22, Period Covering 6/l/93-9/30/93, 19984 Meekland Avenue, Hayward, California

CTTS, Inc., Toxic Technology Services, February 24, 1993. Progress Report #23, Period Covering 10/l/93-12/31/93, Durham Transportation 19984 Meekland Avenue, Hayward, California

Groundwater Services, Inc., 1998, RBCA Tool Kit for Chemical Releases, Version 1.3

Howard, Philip, H. 1990. Handbook of Fate and Exposure Data for Organic Chemicals, Lewis Publishers. Inc., Chelsea, Michigan

Weber, Hayes and Associates, October 29, 1999. Clarification of Development of Risk Based Cleanup Standards - Harbert Transportation Site, 19984 Meekland Avenue, Hayward, CA

#### REFERENCES (continued)

Weber, Hayes and Associates, September 7, 2000. Work Plan for Soil and Groundwater Sampling - Harbert Transportation Site, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, November 10, 2000. Groundwater Monitoring Report - Third Quarter 2000, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, January 30, 2001. Groundwater Monitoring Report - Fourth Quarter 2000, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, June 18, 2001. Additional Site Assessment and Groundwater Monitoring Report - First Quarter 2001, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, July 24, 2001. Groundwater Monitoring Report - Second Quarter 2001, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, November 6, 2001. Groundwater Monitoring Report - Third Quarter 2001, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, December 7, 2001. Addendum to Interim Remedial Action - 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, December 11, 2001. Feasibility Study and Modified Interim Remedial Action - 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, January 14, 2002. Facsimile with information regarding 10% Cost Overrun - Interim Remedial Action 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, February 8, 2002. Interim Remedial Action, Large-Diameter Auger Excavation Operations, and Fourth Quarter 2001 Quarterly Groundwater Monitoring, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, May 2, 2002. Groundwater Monitoring Report - First Quarter 2002, 19984 Meekland Avenue, Hayward, CA

Weber, Hayes and Associates, September 12, 2002. Groundwater Monitoring Report - Second Quarter 2002, 19984 Meekland Avenue, Hayward, CA

Table 1 Current and Previous Investigations Soil Sample Analytical Results Former Harbert Transportation Facility, 19984 Meekland Avenue, Hayward, CA

Investigation & Date	Sample ID	Sample Depth (feet,bgs)	TPH-g (mg/kg)	Benzene (mg/kg)	Toluene (mg/kg)	Ethylbenzene (mg/kg)	Xylenes (mg/kg)	MTBE (mg/kg
Proposed Cleanup Levels		_	38	0 118	150	87	480	NA
Interim Remedial Action	Soil Reuse #la,b,c,d	4-point composite (0 - 10')	NID	ND	ND	ND	ND	ND
Diameter Auger Drilling & Source Removal (January 7, 8, 9, 10, 2002)	Soil Reuse #2a,b,c,d	4-point composite (0 - 20')	ND	ND	ND	ND	ND	ND
	Soil Reuse #3a,b,c,d	4-point composite (0 = 20')	ИD	ИО	ИD	MD	ND	ND
	LD#1 SW-E	35'	ND	ND	ND	0 005	0 011	ND
	LD#2 SW-W	35'	ND	ND	ND	ND	ND	ND
	- LD#3 BC-N	40'	ND	ND	ND 0.012	0 005	ND 0 006	ND ND
	LD#4 SW-N	40'	12	ND	0 012 ND	ND	ND	ND
	LD#5 SW-N	40' 40'	ND ND	ND <sup>,</sup>	ND	ND	ND	ND
	LD#8 SW-S	40'	ND	ND	ND	ND	ND	ND
	LD#9 SW-E LD#10 SW-E	40'	ND	ND	ND	ND	ND	ND
	LD#10 SW-W	40'	- ND	ND	0 014	0.013	0 062	ND
	LD#12 SW-E	18'	ND	ND	ND	ND	ND	ND
	LD#13 SW-E	18'	ND	ND	ИD	ND	ND	ND
	LD#13 SW-E	40'	ND	ND	0 006	ND	0 022	ND
	LD#14 SW-W	40'	ND	ND	ND	ND	ND	ND
	LD#15 BC-8	40'	ND	ND	ND	ND	ND	NID
	LD#16 SW-W	18'	ND	ND	ND	ND	ND	ND
_	LD#16 SW-W	40'	34	0 041	ND	0 12	0.62	ND
Landfill Acceptance Borings	DP-1c,d;e,f	4-point composite (15-30')	ND	ND	ND	ND	ND	ND
(October 18, 2001)	DP-2c,d,e,f	4-point composite (15-30')	130	ND	0 13	0 37	12	NE
Soil Sampling	DP-1a	2	ND	ND	0.010	ND	0 025	NI
Additional Site Assessment	f	23	ND	ND	ND	ND	ND	NI.
(February 14, 2001)	g @ 24'	24	ND	ND	ND	ND	0.007	NI
(2.0021111)	g@27	27	ND	ND	ND	0 007	0 015	NI
	DP-2a	2	NĐ	ND	0 019	0 020	0 13	NI
	đ	13 5	1,800	< 0.5	4.5	19	270	ND <05
	е	18 5	8,700	18	720	230	1,600 250	ND
	g	24	1,800	3.5	52 0 017	39.0 0.006	0.054	NI
	DP-3a	2	ND	ND ND	0 063	0.000	0 12	NI
	ь	7.5 18.5	ND ND	ND	ND	ND ND	ND	NI
	e	27.5	18	0 036	0 067	0 070	0.060	ND
	DP-4a	27.3	ND	ND	0 014	0 008	0.058	М
	е	195	ND	ND	ND	ND	ND	NI
	g @ 25'	25	ND	ND	ND	ND	ND	NI
	g@27	27	ND	ND	ND	ND	ND	NI
	DP-54	2	ND	ND	ND	ND	ND	N
	d	12	ND	ND	ИD	ND	ND	NI
	f	20	ND	ND	ND	ND	ND	NI
	g	24	ND	ND	ND	ND	ND	М
	DP-6a	2	ND	ND	ND	ND	ND	N
	d	14	ND	ND	ND	ND	ND	N N
	c	18	ND	ND	ND	ND	ND ND	N.
	В	24	ND	ND	ND	0 009	ND	N.
	DP-7a	2	ND	ND	ND	ND	ND	N
	d	14	ND	ND	ND	ND	ND	N
	е	18	ND	ND	ND	ND	ND	N
	B	24	ND ND	ND	ND	ND	ND	N
	. DP-8a	1	ND ND	ND	ND	ND	ND	N
	d	13 18	ND	ND	ND	ND	ND	N
	· ·	24	ND	ND	ND	ND	ND	N
	DP 0a	24	ND	ND	ND	ND	ND	N
	DP-9a d	13	ND	ND	ND	ND	ND	N
	1 °	18	ND	ND	ND	ND	ND	N
			18	0 020	0 020	0 19	0.30	N
	g	24						

S:

TPH 2: Total Petrolsum Hydrocarbons as gasoline
BTEX: B Benzene, T Toluene, E Ethylbenzene, and X Total Xylenes
MTBE. Methyl-ter-Bunyl Ether
bgs: below ground surface
ND: Not detected at or shows the lab's practical quantitation limit

X: Not detected at the elevated PQL, X: PQL elevated due to laboratory dilution

A: MTBE Analysis confirmed by EPA Method 8260

#### Table 1: Summary of Groundwater Elevation and PHC Analytical Data Former Harbert Transportation Facility, 19984 Meekland Avenue, Hayward, Ca. Weber, Hayes and Associates Project H9042

Well	Date	Screened Interval	Surveyed T.O.C.	Depth to Groundwater	Calculated Groundwater	* +> ^ ^=/		Labor	atory Analytical	Results	·	<del>, , , , , , , , , , , , , , , , , , , </del>		eld rements
I.D.		(feet below ground surface)	Elevation (fees)	(feet below ground surface)	Elevation (feet)	TPH-g (ug/L)	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	Xylenes (ug/L)	MTBE (ug/L)	F.O. 's (ug/L)	D.O. (mg/L)	ORP (mV)
MW-3		20 - 40?	55.44											***
	27-Aug-2002	. 1		23.87	31 57	350	0 56	11	14	3 4	ND		0.13	216
	13-Jun-2002			22.92	32.52	300	11	1.4	40	1.8	ND		0 14	194
	21-Mar-2002			21.96	33.48	240	0.94	2.5	12	11.7	ND		0 1	-
	18-Dec-2001	]		23.59	31 85	270	1.6	1.7	13	54	ND			-
	20-Sep-2001	<u> </u>		24.16	31,28	380	17	2.6	32	8.9	ND		0.4	_
	20-Jun-2001			23.55	31.89	760	4.4	2.4	62	23	ND*			
	29-Mar-2001			22.02	33.42	170	11	ND	10	16	ND		06	
	12-Jan-2001			23.41	32 03	310	2.4	2.2	44	10	ND		0.7	
	27-Sep-2000			23.09	32.35	430	ND	ND	44	ND	ND	ND	1	
MW-4	7.00	20 - 40?	55 71											·
	27-Aug-2002			24.07	31 64								0 21	187
	13-Jun-2002			23.15	32,56	ND	ND	ND	ND	ИD	ND		0.20	392
	21-Mar-2002		'	22.15	33 56	МD	ND	ND	ND	ND	ND		0.2	
	18-Dec-2001	]		23.80	31 91	ND	ND	0.9	ND	ND	ND			
	20-Sep-2001	<u> </u>		24.32	31 39	ND	ND	ND	ND	ND	ND		0.4	
	20-Jun-2001			23.74	31.97	ND	ND	ND	ND	ND	ND			
	29-Mar-2001			22,22	33 49	ND	ND	4.2	ND	ND	ND		0.5	
	12-Jan-2001			23.60	32 11	ND	ND	ND	ND	ND	ND		0.7	
	27-Sep-2000			23,25	32 46	ND	ND	ИD	ND	ND	ND	ND	2.5	
MW-5		25 - 45	56.03											
	27-Aug-2002			24.42	31 61	1,900	170	14	210	93	ND*	T	0 43	207
	13-Jun-2002			23 57	32,46	1,500	24	16	120	110	ND*		0 06	144
	21-Mar-2002			24 69	31.34	360	11	9.4	28	62	ND		01	
	18-Dec-2001			23 15	32.88	780	21	12	86	94	ND*			
	20-Sep-2001			24.75	31 28	2,300	46	41	280	330	ND*	Ţ-	0.3	
	20-Jun-2001			24.15	31 88	6,500	120	130	740	940	ND*	1 -	-	
	29-Mar-2001	}		22.69	33.34	13,000	220	510	1,000	2,700	ND*	1	0.4	
	12-Jan-2001			23.97	32 06	1,100	62	40	150	290	ND*	_	0,3	
	27-Sep-2000			23.69	32,34	18,000	840	29	1,200	3,500	< 30	ND	0.4	
MW-6		25 - 45	56.01											
	27-Aug-2002			24.44	31 57	1,300	< 2.5	7.2	210	55	ND*		0.14	231
	13-Jun-2002			23.53	32 48	1,600	<1.25	4.7	67	5,3	< 1.5*		0.53	233
	21-Mar-2002	_	}	23 11	32 90	750	0.77	1,2	39	3 2	ND*		0.1	
	18-Dec-2001	_	}	24,16	31 85	3,700	33	8.7	320	110	< 1.5*			
	20-Sep-2001	]		24.72	31 29	2,500	11	8.6	240	94	ND*		0.3	
	20-Jun-2001			24.13	31 88	1,800	14	4.6	160	79	ND*	<del> </del>		
	29-Mar-2001			22 56	33.45	610	2.2	ND	37	4.6	ND*	<del>                                     </del>	0.5	
	12-Jan-2001	]	}	23.97	32.04	2,300	16	3.5	290	83	ND*	T -	0.5	
	27-Sep-2000			23 56	32,45	1,300	ND	43	200	17	ND	ND	0.5	···

#### Table 1: Summary of Groundwater Elevation and PHC Analytical Data Former Harbert Transportation Facility, 19984 Meekland Avenue, Hayward, Ca. Weber, Hayes and Associates Project H9042

Well	Date	Screened Interval	Surveyed T.O.C.	Depth to Groundwater	Calculated Groundwater	A 344 . W 4.00	<del></del>	Labor	atory Analytical	Results	45 4 . , , e	551 VA		eld rements
I.D.		(feet below ground surface)	Elevation (feet)	(feet below ground xurface)	Elevation (feet)	TPH-g (ug/L)	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	Xylenes (ug/L)	MTBE (ug/L)	F.O.'s (ug/L)	D.O. (mg/L)	ORP (my)
MW-7		25 - 45	56.66							· · · · · · · · · · · · · · · · · · ·		· · · · · · · · · · · · · · · · · · ·		·
	27-Aug-2002	1		24.98	31 68				-				0 22	369
	13-Jun-2002	]		24.07	32 59	ND	ND	ND	ND	ND	ND		0.20	370
	21-Mar-2002			23.05	33.61	ND	ND	ND	ND	ND	ND		0	_
	18-Dec-2001			24.70	31.96	290	ND	ND	119	4.6	ND		_	
	20-Sep-2001			25.27	31,39	290	0.98	ND	12	45	ND*		04	
	20-Jun-2001			24.68	31.98	430	2,4	0.96	30	97	ND*	_		
	29-Mar-2001	]		23.10	33.56	ND	ИD	ND	ND	ND	ND	<u> </u>	0.5	-
	12-Jan-2001	]		24.49	32.17	1,600	13	0 86	150	35	ND*		0.5	
	27-Sep-2000			24 18	32.48	270	13	6.6	11	ND	ND	ND	0.5	
MW-8		20 - 40	56 16				<del></del>	· · · · · · · · · · · · · · · · · · ·				<u> </u>	2:5	
	27-Aug-2002	]		24,43	31.73				_			T	1.98	402
	13-Jun-2002	1		23 54	32 62	ND	ND	ND	ND	ND	ND		1.96	394
	21-Mar-2002	]	'	22.51	33 65	ND	ND	ND	ND	ND	ND		2.4	
	18-Dec-2001	]	1	24.16	32.00	ND	ND	ND	ND	ND	ND			<u></u>
	20-Sep-2001	]		24.68	31 48	ND	ND	ND	ND	ND	ND		1.6	
	20-Jun-2001	]		24.09	32 07	ИD	ND	ND	ND	ND	ND	-		
	29-Mar-2001	]		22.56	33.60	ND	ND	0.8	ND	ND	ND		1.9	***
	12-Jan-2001	1		23 93	32.23	ND	ND	ND	ND	ND	ND	No.	21	
	27-Sep-2000	]		23 59	32.57	ND	ND	ND	ND	ND	ND	ND	19	
MW-9		20 - 40	55.21					1					<del></del>	·
	27-Aug-2002	1		23 69	31 52	310	27	25	20	20	ND*		0.18	154
	13-Jun-2002	1		22.76	32 45	5,100	140	21	490	300	< 1.5*		0.14	135
	21-Mar-2002			21.76	33 45	510	26	46	50	52	ND	_	0.1	
	18-Dec-2001		ŀ	23.38	31,83	6,400	640	120	630	1,300	< 1.5*			
	20-Sep-2001			23.94	31,27	3,400	270	38.0	390	430	ND*		0.3	
	20-Jun-2001			23.36	31 85	8,300	330	88 0	850	1,700	< 0.6*			
	29-Mar-2001			21.61	33.60	1,600	110	140	240	150	ND*		0.4	
	12-Jan-2001			23.17	32.04	10,000	550	1100	1,200	2,200	ND*		0.5	
	27-Sep-2000			22 90	32,31	1,000	40	6.7	110	55	ND	ND	0.5	
MW-10		25 - 40	54 74							<u> </u>		<del></del>		
	27-Aug-2002			23 46	31,28	1,800	<25	15	3 9	5	ND*		0.14	183
	13-Jun-2002	]		22 56	32.18	1,700	0.77	6.2	3.3	2.9	< 0.3*		0,28	201
	21-Mar-2002	_		21.53	33.21	1,500	ND	11	3 1	ND	ND*		01	
	18-Dec-2001	_		21 11	33.63	1,500	79	2.9	ND	ND	< 0.6*		-	
	20-Sep-2001	_		23 70	31.04	1,200	6	9.9	1.2	3.9	ND*		04	
	20-Jun-2001			23 17	31.57	810****	3	1.6	5.1	13	ND*		-	
	29-Mar-2001	]	-	21 63	33 11	600****	2	0.65	ND	0 72	ND		0.5	
	12-Jan-2001	]	1	22.99	31 75	530	3.7	1.9	2.1	4.5	ND		0.6	
	27-Sep-2000	1		22.72	32 02	880	ND	ND	ND	ND	NĐ	ND	0.4	-

#### Table 1: Summary of Groundwater Elevation and PHC Analytical Data Former Harbert Transportation Facility, 19984 Meekland Avenue, Hayward, Ca. Weber, Hayes and Associates Project H9042

Well	Datę	Screened Interval	Surveyed T.O.C.	Depth to Groundwater	Calculated Groundwater	- 4	, ,	Labora	tory Analytical	Results		· · · · · · · ·		eld rements
I.D.		(feet below ground surface)	Elevation (feet)	(feet below ground surface)	Elevation (Jeet)	TPH-g (ug/L)	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	Xylenes (ug/L)	MTBE (ug/L)	F.O.'s (ug/L)	D.O. (mg/L)	ORP (mV)
MW-II		25 - 40	55.20							W. C	****			
ļ	27-Aug-2002			23.68	31.06				1				0 13	369
	13-Jun-2002			22.78	31 96	ND	ND	DИ	ND	ΝЪ	ND		0 15	380
	21-Mar-2002	]	!	21.76	32.98	ND	ND	ND	ND	ND	ND		0,1	
	18-Dec-2001			23 39	31.35	ND	ND	0 56	ND	ДИ	ND	-	-	
	20-Sep-2001	]		23.87	30.87	ND	ND	ND	ND	ND	ND		0.4	
	20-Jun-2001	1		23 39	31.35	ND	ND	ND	ND	МD	ND		4	
	29-Mar-2001	<u> </u>		21.84	32 90	ЙD	ND	4.5	ND	ND	ND		06	
	12-Jan-2001	1	1	23.21	31 53	ND	ND	2.1	ND	ND	ND		0.6	
	27-Sep-2000			22.43	32.31	63	ND	מא	ND	ИД	ND	ND	0.6	
MW-12		25 - 40	56 49		<u>, </u>									
	27-Aug-2002	1		24 68	31.81					-			0 60	410
,	13-Jun-2002	]	·	23.86	32 63	ND	ND	ND	ND	ИД	МД		0.51	400
	21-Mar-2002			22.86	33 63	ND	ND	ND	ND	ND	ND		0.7	
	18-Dec-2001	1		24 49	32.00	מא	ND	0.86	ND	ИD	ND	_		
	20-Sep-2001	]		24 95	31.54	ND	ND	ND	ND	ND	ND		0.7	
	20-Jun-2001	]		24 47	32.02	ND	ND	ND	ND	ND	ND			
	29-Mar-2001	]		22.91	33 58	ND	ND	5.0	ND	ND	ND		1	
	12-Jan-2001	1		24.28	32 21	ND	ND	1.1	ND	ND	ND		1	
	27-Sep-2000			23 98	32.51	ND	ND	ND	ND	ND	ND	ND	1,2	~-
	Laborato			n Limit (PQL):		50	0.5	0.5	0.5	\$ 1 3 CT	5 / ·	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	Field	Fleid
7 - 40 ° C (\$15)	and the second of the second o	Proposed	Čleanup Go	als	CONTRACTOR STATES	7,000	210	26,000	27,000	200,000	NA	NA	Instrument	Instrument

Notes:
TOC = Top of Casing Elevation Calculated groundwater elevation = TOC - Depth to Groundwater Referenced to NGVD.

TPH-g = Total Petroleum Hydrocarbons as gasoline MTBE = Methyl - tert - Butyl Ether

F.O.'s = Fuel Oxygenates = Dr-Isopropyi ether (DIPE), terttary Butyl Alcohol (TBA), Ethyl tertiary Butyl Ether (ETBE), terttary amyl Methyl Ether (TAME)

VOC's = Volatile Organic Compounds DO = Dissolved Oxygen

ugil = micrograms per liter, parts per billion, mg/L = milligrams per liter, parts per million

ND = Not Detected at the Fractical Quantitation Limit (PQL), X = Not Detected at the elevated PQL, X = PQL elevated because of sample dilutic


- Data not collected on measured, or analysis not conducted

MCL = Maximum Contaminant Level for drinking water in California (Department of Health Services)

\* Confirmed by GC/MS method 8260

\*\* = Action Level \*\*\* = Secondary MCL / water quality goal

<sup>\*\*\*\* =</sup> Laboratory Report indicates results within quantitation range, chromatographic pattern not typical of fuel






Weber, Hayes & Associates
Hydrogeology and Environmental Engineering
120 Westgate Drive, Watsonville, Ca. 95076
(831) 722 - 3580 (831) 662 - 3100

#### **Location Map**

Former Harbert Transportation Facility 19984 Meekland Avenue Hayward, California

**Figure** Job# H9042






Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, Ca. 95076 (831) 722 - 3580 (831) 662 - 3100

# Site Plan with Keys to Geologic Cross Sections

Former Harbert Transportation Facility 19984 Meekland Avenue, Hayward, California Figure 2 Project H9042

Weber, Hayes & Associates
Hydrogeology and Environmental Engineering
120 Westgate Drive, Watsonville, Ca. 95076
(831) 722 - 3580 (831) 662 - 3100



30' Horizontal Scale = 1-inch = 30-feet

Vertical Scale = 1-inch = 15-feet A-A' and B-B' show 2x vertical exaggeration

**DP-2** 

**MW-4** 

#### LEGEND:

Asphalt.

Fat CLAY, very dark grayish brown to dark gray (10 YR 3/2 to 4/1), damp to wet, firm soft to firm, moderate to high plasticity, no dilatency, low toughness, dominantly clay with few fine to medium grained sands.

Sandy CLAY, brown to very dark grayish brown (10 YR 4/3 to 3/2), dry to damp, no to moderate plasticity, no dilatency, mostly clay with some fien to medium grain sands, subangular.

Clayey SAND, color varies, yellowish brown to dark gray (10 YR 3/6 to 5/1), dry to saturated, medium

dense, mostly fine grained sands, subangular, 35-40 % clay, slight plasticity.

Geologic contact, dashed were Poorly Graded SAND with Gravel, fill material. inferred.

Cement Seal, used in sealing driven probe borings. Soil sample analyzed at this depth.

**Excavated Native Soil used as Backfill in UST Excavation** 

Monitoring well-location designation completion depth and screened interval


Groundwater elevation in monitoring wells from March 29, 2001 groundwater monitoring event

First Encountered Groundwater elevation from Hydraulic Driven Probe investigation. February 14, 2001

#### NOTES

See Figure 2 for plan view of geologic cross-sections A-A' and B-B'
Lithology compiled from Geologic Logs MW-4 5 8 10 and 12 (completed by others) and DP-1-4 All elevations are referenced to National Geodetic Vertical Datum of 1929 Mean Sea Level (MSL)


# Oriented at North 3 East **DP-3** В DP-4 <u>MW-5</u> MW-12



Large Diameter Auger Source Removal Footprint Map and Soil Sampling Certified Analytical Results Harbert Transportation 19984 Meekland Avenue Hayward, California

4 Job# H9042

Weber, Hayes & Associates Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, Ca. 95076 (831) 722 - 3580 (831) 662 - 3100






Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, Ca. 95076 (831) 722 - 3580 (831) 662 - 3100

# August 27, 2002

Former Harbert Transportation Facility 19984 Meekland Avenue, Hayward, California






Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, Ca. 95076 (831) 722 - 3580 (831) 662 - 3100

# August 27, 2002

Former Harbert Transportation Facility 19984 Meekland Avenue, Hayward, California






Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, Ca. 95076 (831) 722 - 3580 (831) 662 - 3100

# in Groundwater, August 27, 2002

Former Harbert Transportation Facility 19984 Meekland Avenue, Hayward, California






Hydrogeology and Environmental Engineering 120 Westgate Drive, Watsonville, Ca. 95076 (831) 722 - 3580 (831) 662 - 3100

# August 27, 2002

Former Harbert Transportation Facility 19984 Meekland Avenue, Hayward, California


# Figure 9





Elevation MW-5 TPH-g MW-5 Elevation MW-9 TPH-g MW-9

Figure 10



## Appendix A

**RBCA** Toolkit Output Tables - Calculation of Cleanup Goals

#### RBCA Tool Kit for Chemical Releases, Version 1.3

						RBCA SITE	ASSESSME	VΤ							
Site Name: H	arbert Transportation	1	Completed By: 1	Weber, Hayes and	l Associates		Job ID: HS	9042 C							
Site Location	. 19984 Meekland Avenue, Haywar	d, CA	Date Completed	. 27-Dec-02											1 OF
			Targe	Risk (Class A & B)	1 0E-6										
SOIL (0	- 23 ft) SSTL VALUES		Ta	rget Rısk (Class C)	1 0E-5						Ground	twater DAF Option	Domenico - N	Decay	
			Tarç	et Hazard Quotient	1 0E+0								(One-direction	al vert. dispersi	on)
						SSTL Results Fo	or Complete Expo	Sure Pathways (*)	(" if Complete)						<del></del>
			X So	Leaching to Ground Ingestion	undwater	X Soil Vol. to Indoor Air	х		ation and Surface			Soil Inhalation, Dermal Contact	Applicable	SSTL	Required CI
CONSTITUENTS OF CONCERN		Representative Concentration	On-site (0 ft)	Off-site 1 (250 ft)	Off-site 2 (0 ft)	On-site (0 ft)	On-ast	te (0 ft)	Off-site 1 (75 ft)		On-site (0 ft)		SSTL	Exceeded?	? Only if "yes
CAS No.	Name	(mg/kg)	None	Residential	None	Residential	Residential	Construction Worker	Residential	None	Residential	Construction Worker	(mg/kg)	"m" if yes	left
0-00-0	TPH - Arom >C08-C10	2 0E-1	NA	>1.0E+3	NA	3 8E+1	>1.0E+3	NA	>1 0E+3	NA	9 4E+2	NA	3.8E+1		<1
71-43-2	Benzene	4 2E-3	NA NA	1 7E+0	NA NA	6.5E-3	8.6E+0	NA NA	9 6E+0	NA	1 8E+0	NA	6 5E-3		<1
108-88-3	Toluene	4 6E-3	NA	>7.5E+2	NA	1.5E+1	>7 5E+2	NA	>7.5E+2	NA	3 7E+3	NA	1.5E+1		<1
100-41-4	Ethylbenzene	6 1E-3	NA	>6.3E+2	NA	8 7E+1	>6.3E+2	NA	>6.3E+2	NA	2 3E+3	NA	8.7E+1		<1
1330-20-7	Xylene (mixed isomers)	1 0E-2	NA	>5.0E+2	NA	4.8E+2	>5.0E+2	NA	>5.0E+2	NA	4 3E+4	NA	4.8E+2		<1
107-06-2	Dichloroethane, 1,2-	4 1E-3	NA	5.2E-1	NΑ	6.5E-3	2.7E+0	NA	3 0E+0	NA	5.9E-1	NA	6 5E-3		<1
127-18-4	Tetrachloroethene	2.5E-3	NA	2 4E+0	NΑ	9.3E-2	1.2E+2	NA	1.4E+2	NA	1 1E+0	NA	9 3E-2		<1
79-01-6	Trichloroethene	2.5E-3	NΑ	9.2E+0	NA	3 2E-2	4.2E+1	NA	4.6E+1	NA	7.9E-1	NA	3 2E-2		<1

<sup>&</sup>quot;>" indicates risk-based target concentration greater than constituent residual saturation value. NA = Not applicable. NC = Not calculated

Site Name: Ha	ribert Transportation		Completed By:	Weber, Hayes a	nd Associates		Job ID: H9	)42 C				
	19984 Meekland Avenue, Hayward, C	CA .	Date Complete								1 OI	
	DWATER SSTL VALUES		Targ	Risk (Class A & B) get Risk (Class C) t Hazard Quotient	1.0E-5				Ground	water DAF Option:	Domenico - No (One-directiona	Decay
	•			SST	L Results For C	omplete Exposure Pa						
				Groundwater Ing		X GW Vol. to Indoor Air	X G	roundwater Volatil to Outdoor Ai		Applicable	SSTL	Required CF
CONSTITUENTS OF CONCERN		Representative Concentration	On-site (0 ft)	Off-site 1 (250 ft)	Off-site 2 (0 ft)	On-site (0 ft)	On-site (0 ft)	Off-site 1 (75 ft)	Off-site 2 (0 ft)		Exceeded?	Only if "yes
CAS No.	Name	(mg/L)	None	Residential	None	Residential	Residential	Residential	None	(mg/L)	"■" if yes	left
0-00-0	TPH - Arom >C08-C10	4.3E-1	NΑ	1.0E+1	NA	7.0E+0	>6.5E+1	>6.5E+1	NA	7.0E+0		<1
71-43-2	Benzene	2.7E-3	NA	2.1E-2	NA	2.1E-2	1.7E+1	1.9E+1	NA	2.1E-2		<1
108-88-3	Toluene	4.3E-3	NA	5.2E+1	NA	2.7E+1	>5.2E+2	>5.2E+2	NA	2.7E+1		<1
100-41-4	Ethylbenzene	9.5E-3	NA	2.6E+1	NA	6.5E+1	>1.7E+2	>1.7E+2	NA	2.6E+1		<1
1330-20-7	Xylene (mixed isomers)	9.9E-3	NA	>2.0E+2	NA	>2.0E+2	>2.0E+2	>2.0E+2	NA	>2.0E+2		NA
107-06-2	Dichloroethane, 1,2-	1.6E-3	NA	6.6E-3	NA	1.9E-2	1.3E+1	1.4E+1	NA	6.6E-3		<1
127-18-4	Tetrachloroethene	2.5E-4	NA	1.2E-2	NA	1.3E-1	1.1E+2	1.3E+2	NA	1.2E-2		<1
79-01-6	Trichloroethene	2.5E-4	NA	5.5E-2	NA	4.1E-2	2.4E+1	2.7E+1	NA	4.1E-2		<1

#### RBCA Tool Kit for Chemical Releases, Version 13

Date Completed: 27-Dec-02

#### **RBCA SITE ASSESSMENT**

TPH Criteria SSTL Worksheet

Site Name: Harbert Transportation

Completed By: Weber, Hayes and Associates

Job ID: H9042.C


1 OF 1

#### **CALCULATION OF SSTL VALUES FOR TPH**

Site Location: 19984 Meekland Avenue, Hayward, CA

				ractions	Representative	Concentrations	Calculated Conce	entration Limits	Appilcable SSTL Values		
	NTS OF CONCERN		Soil	Groundwater	Soil	Groundwater	Residual Soil Concentration	Solubility	Soils (0 - 23 ft)	Groundwater	
CAS No.	Name		(-)	(-)	(mg/kg)	(mg/L)	(mg/kg)	(mg/L)	(mg/kg)	(mg/L)	
0-00-0	TPH - Arom >C08-C10	花覧	1.0E+0	1.0E+0	2.0E-1	4.3E-1	1.0E+3	6.5E+1	3.8E+1	7.0E+0	
		<u> </u>									
		Total	1.0E+0	1.0E+0	2.0E-1	4.3E-1	Total T	PH SSTL value		1	

<sup>&</sup>quot;>" indicates risk-based target concentration greater than constituent residual saturation value. NC = Not calculated.



#### **RBCA SITE ASSESSMENT**

Input Parameter Summary

Site Name Harbert Transportation Site Location. 19984 Meekland Avenue, Hayward, CA

Completed By: Weber, Hayes and Associates Date Completed: 27-Dec-02

Job ID. H9042 C

1 OF 1

Exposur	e Parameters"	Anton to the colony of the	"Residential"	comparation of the same of	Commerci	alfindustrial
A.T		Adult	(1-6yrs)	(1-16 yrn)	Chronic	Construc
AT <sub>c</sub>	Averaging time for carcinogens (yr)	70				
AT,	Averaging time for non-carcinogens (yr)	30			25	1
₿W	Body weight (kg)	70	15	35	70	
€D	Exposure duration (yr)	30	6	16	25	1
τ	Averaging time for vapor flux (yr)	30			25	1
EF	Exposure frequency (days/yr)	350			250	180
<b>Ŀ</b> ⊦ <sub>D</sub>	Exposure frequency for dermal exposure	350			250	
R.,	Ingestion rate of water (L/day)	2			1	
R,	Ingestion rate of soil (mg/day)	100	200		50	100
SA.	Skin surface area (dermal) (cm^2)	5800		2023	5800	5800
A	Soil to skin adherence factor	1				
ΞT,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Swimming exposure time (hr/event)	3				
EV <sub>swen</sub>	Swimming event frequency (events/yr)	12	12	12		
R.	Water ingestion white swimming (L/hr)	0.05	0.5			
SA	Skin surface area for swimming (cm^2)	23000		8100		
iR <sub>ssi</sub> ,	Ingestion rate of fish (kg/yr)	0 025				
j-↓ <sub>ES</sub> h	Contaminated fish fraction (unitless)	1				

Groundwater	.1		
Groundwater Ingestion	None	Residential	None
Soil Leaching to Groundwater Ingestion	None	Residential	None
Applicable Surface Water Exposure Routes:			
Swimming			NA
Fish Consumption	Ĭ		NA
Aquatic Life Protection			NA
Soil:	-		
Direct Ingestion and Dermal Contact	Residential		
Outdoor Alr.			
Particulates from Surface Soils	Residential	Residential	None
Volatilization from Soils	Residential	Residential	None
Volatilization from Groundwater	Residential	Residential	None
Indoor Air			
Volatilization from Subsurface Soils	Residential	NA	NA
Volatilization from Groundwater	Residential	NA	NA

Receptor Distance from Source Media	On-site	Off-site 1	Off-site 2	(Units)
Groundwater receptor	NA	250	NA	(ft)
Soil leaching to groundwater receptor	NA	250	NA	(ft)
Outdoor air inhalation receptor	٥	75	NA	(ft)

Target I	lealth Risk Values	Individual	Cumulative
TR <sub>eb</sub>	Target Risk (class A&B carcinogens)	1 0E-6	1 0E-5
TR.	Target Risk (class C carcinogens)	10£-5	į
THQ	Target Hazard Quotient (non-carcinogenic risk)	1 0E+0	10E+0

RBCA tier	Tier 2
Outdoor air volatilization model	Surface & subsurface models
Indoor air votatilization model	Johnson & Ettinger model
Soil leaching model	ASTM leaching model
Use soil attenuation model (SAM) for leachate?	No
Air dilution factor	3-D Gaussian dispersion
Groundwater dilution-attenuation factor	Domenico model

NOTE NA = Not applicable

A	Source zone area	1.6E+3 NA	(ft^2)
W	Length of source-zone area parallel to wind	4 0E+1 NA	(ft)
N <sub>gw</sub>	Length of source-zone area parallel to GW flow	4 0E+1	(11)
ينيل	Ambient air velocity in mixing zone	7 4E+0	(fus)
δ	Air mixing zone fleight	6 6E+0	(6)
P	Areal particulate emission rate	6 9E-14	(g/cm^2/s)
Les	Thickness of affected surface soils	5 0E+9	(ft)

Surfac	e Soil Column Parameters	Value ·	a state of the safety of the safety	AN E PRODUNCALL WASHING	(Units)
h <sub>cep</sub>	Capillary zone thickness	1 6E-1			(ft)
h,	Vadose zone thickness	2 3E+1			(n)
$\rho_{s}$	Soil bulk density	1 7E+0			(q/cm^3)
loc	Fraction organic carbon	1 0E-2			(-)
θr	Soil total porosity	3 8E-1			(-)
K <sub>vs</sub>	Vertical hydraulic conductivity	2 8E+1			(fVa)
k,	Vapor permeability	1 1E-11			(ft^2)
L <sub>gw</sub>	Depth to groundwater	2 3E+1			(ft)
L <sub>z</sub>	Depth to top of affected soils	0 0E+0			(ñ)
Ltose	Depth to base of affected soils	2.3E+1			(ft)
Lsubs	Thickness of affected soils	2.3E+1			(ft)
pН	Soil/groundwater pH	6 8E+0			(-)
		capillary	vadose	foundation	''
Ð.,	Volumetric water content	0 342	0 12	0 12	(-)
űe	Volumetric air content	0 038	0 26	0.26	(-)

Lь	Building volume/area ratio	6 56E+0	NA	(ft)
Ab	Foundation area	7 53E+2	NA	(ft^2)
Xork	Foundation penmeter	1 12E+2	NA	(ft)
ER	Building air exchange rate	1 40E-4	NA	(1/s)
$L_{crk}$	Foundation thickness	4 92E-1	NA	(ft)
$Z_{crk}$	Depth to bottom of foundation stab	4 92E-1	NA	(ft)
η	Foundation crack fraction	1.00E-2	NA	(-)
dΡ	Indoor/outdoor differential pressure	0 00E+0	NA	(psi)
Q,	Convective air flow through slab	0 00E+0	NA	(ft^3/s)

δ <sub>gw</sub>	Groundwater mixing zone depth	2 0E+1	(Units)
į	Net groundwater infiltration rate	4 1E+0	(in/yr)
پيول	Groundwater Darcy velocity	2 2E-1	(fl/d)
/ <sub>gw</sub>	Groundwater seepage velocity	5 9E-1	(ft/d)
K.	Saturated hydraulic conductivity	2 2E+1	(ft/d)
	Groundwater gradient	1 0E-2	(-)
5₩	Width of groundwater source zone	4 0E+1	(n)
ತ್ತ	Depth of groundwater source zone	2 0E+1	(ft)
) <sub>alf</sub>	Effective porosity in water-bearing unit	3 8E-1	(-)
oc-sat	Fraction organic carbon in water-bearing unit	1 0E-3	6
$H_{sat}$	Groundwater pH	6 2E+0	1 6
	Biodegradation considered?	l No.	( "

Later	al Groundwater Transport	Groundwate	er Ingestion	Soil Leach	na to GW	
CL <sub>X</sub>	Longitudinal dispersivity	2 5E+1	NA	2 5E+1	NA	(ft)
αy	Transverse dispersivity	8 3E+0	NA	8 3E+0	NA	(ft)
αz	Vertical dispersivity	1 3E+0	NA	1 3E+0	NA	(ft)
Lateral Outdoor Air Transport		Soil to Outde	Soil to Outdoor Air Inhal.		or Air inhal.	
$\sigma_{y}$	Transverse dispersion coefficient	8 6E+0	NA	8 6E+0	NA	(ft)
σž	Vertical dispersion coefficient	5 8E+0	NA	58E+0	NA L	(ft)
ADF	Air dispersion factor	1 1E+0	NA	1 1E+0	NA	(-)

Surfac	Water Parameters	Off-sire 2	(Units)
Q <sub>sw</sub>	Surface water flowrate	NA NA	(ft^3/s)
Wpt	Width of GW plume at SW discharge	NA NA	(ft)
Òpi	Thickness of GW plume at SW discharge	NA NA	(ft)
DFsw	Groundwater-to-surface water dilution factor	NA NA	(-)

### RBCA SITE ASSESSMENT

**Baseline Risk Summary-All Pathways** 

Site Name: Harbert Transportation

Completed By: Weber, Hayes and Associates

Site Location: 19984 Meekland Avenue, Hayward, CA

Date Completed: 27-Dec-02

1 of 1

		BASELINE	CARCINOG	ENIC RISK			BASELI	NE TOXIC	FFECTS	
EXPOSURE PATHWAY	Individual Maximum Value	COC Risk Target Risk	Cumulativ Total Value	e COC Risk Target Risk	Risk Limit(s) Exceeded?	Hazard Maximum Value	Quotient Applicable Limit	Hazaı Total Value	d Index Applicable Limit	Toxicity Limit(s) Exceeded
DUTDOOR AIR	EXPOSURE F	ATHWAYS		and the second	u.5-,52 obj. (18-29 ož	S-Profession do unidad	s ra da la	Sindulation.	isezali idali (4)	L
Complete:	2.0E-9	1.0E-6	2.8E-9	1.0E-5		1.1E-4	1.0E+0	1.7E-4	1.0E+0	
NDOOR AIR E	XPOSURE PA	THWAYS				en application best	W. September 1991			
Complete:	7.7E-7	1.0E-6	1.6E-6	1.0E-5		6.7E-2	1.0E+0	1.2E-1	1.0E+0	
SOIL EXPOSU	RE PATHWAY:									
Complete:	6.6E-9	1.0E-6	1.4E-8	1.0E-5		2.0E-4	1.0E+0	2.9E-4	1.0E+0	
SROUNDWATI	R EXPOSURE	PATHWAYS							Market Control	Carlo III
Complete:	2.4E-7	1.0E-6	3.9E-7	1.0E-5		4.2E-2	1.0E+0	4.6E-2	1.0E+0	
SURFACE WA	TER EXPOSUR	RE PATHWAY	S							
Complete:	NA	NA	NA	NA		NA	NA	NA	NA	
CRITICAL EXP	OSURE PATH	VA¥ (Maxim	um Values Fr	om Complete	Pathways)					
	7.7E-7	1.0E-6	1.6E-6	1.0E-5		6.7E-2	1.0E+0	1.2E-1	1.0E+0	
	Indoo	or Air	Indo	or Air		Indo	or Air	Indo	or Air	
			<u>d</u> antinia							

### RBCA Tool Kit for Chemical Releases, Version 1.3

### RBCA SITE ASSESSMENT

Cumulative Risk Worksheet

Site Name: Harbert Transportation

Completed By: Weber, Hayes and Associates

Job ID: H9042.C

Site Location: 19984 Meekland Avenue, Hayward, CA

Date Completed: 27-Dec-02

1 OF 3

### **CUMULATIVE RISK WORKSHEET**

CONSTITUEN	ITS OF CONCERN	Representativ	e Concentration
CAS No.	Name	Soil (mg/kg)	Groundwater (mg/L)
0-00-0	TPH - Arom >C08-C10	2.0E-1	4.3E-1
71-43-2	Benzene	4.2E-3	2.7E-3
108-88-3	Toluene	4.6E-3	4.3E-3
100-41-4	Ethylbenzene	6.1E-3	9.5E-3
1330-20-7	Xylene (mixed isomers)	1.0F-2	9.9E-3
107-06-2	Dichloroethane, 1,2-	4.1E-3	1.6E-3
127-18-4	Tetrachloroethene	2.5E-3	2.5E-4
79-01-6	Trichloroethene	2.5E-3	2.5E-4

Proposed CRF										
Soil	GW									
<b>6</b> 1	<1									
<1	<1									
<4	<1									
<1	<1									
<1	NA									
<1	<1									
<1	<1									
<1	<1									

Resultant Target Concentration									
Soil	Groundwater								
(mg/kg)	(mg/L)								
2.0E-1	4.3E-1								
4.2E-3	2.7E-3								
4.6E-3	4.3E-3								
6.1E-3	9.5E-3								
1.0E-2	9.9E-3								
4.1E-3	1.6E-3								
2.5E-3	2.5E-4								
2.5E-3	2.5E-4								

#### Cumulative Values:

#### RBCA Tool Kit for Chemical Releases, Version 1.3

	RBCA SITE	ASSESSMENT					Cu	mulative Risk Worl	sheet	
Site Name: H	arbert Transportation	Site Name: Harb	ert Transportation		Completed By: V	Veber, Hayes and A	Associates	sociates Job ID: H9042.C		
Site Location:	19984 Meekland Avenue, Hayward, (	Site Location: 199	984 Meekland Ave	nue, Hayward, C/	Date Completed:	27-Dec-02			2 OF	
CUMULA	ATIVE RISK WORKSHEET			Cumulative Ta	arget Risk: 1.0E-5	Target Hazard In	ndex: 1 0E+0		1.0° ± lo-uni	
					ON-SITE R	ECEPTORS				
		Outdoor Air		Indoor Air	Exposure:	Soil Ex	oosure:	Groundwate	r Exposure:	
		Resid		Residential		Residential		None		
CONSTITUENTS OF CONCERN		Target Risk: 1.0E-6 / 1.0E-5	Target HQ: 1.0E+0	Target Risk: 1.0E-6 / 1.0E-5	Target HQ: 1.0E+0	Target Risk: 1.0E-6 / 1.0E-5	Target HQ: 1.0E+0	Target Risk: 1 0E-6 / 1.0E-5	Target HQ: 1 0E+0	
CAS No.	Name	Carcinogenic Rısk	Hazard Quotient	Carcinogenic Risk	Hazard Quotient	Carcinogenic Rısk	Hazard Quotient	Carcinogenic Rısk	Hazard Quotient	
0-00-0	TPH - Arom >C08-C10		1.1E-4		6.7E-2		2.0E-4			
71-43-2	Benzene	7.5E-10	3.6E-5	7.7E-7	3.7E-2	2.2E-9	5.7E-5			
108-88-3	Toluene		6.5E-7		4.6E-4		1.2E-6			
100-41-4	Ethylbenzene		4.2E-7		2.2E-4		2.6E-6			
1330-20-7	Xylene (mixed isomers)		8.2E-8		4.1E-5		2.3E-7			
107-06-2	Dichloroethane, 1,2-	2.0E-9	1.8E-5	7.2E-7	6.5E-3	6.6E-9				
127-18-4	Tetrachloroethene	2.7E-11	3.1E-6	2.9E-8	3.3E-3	2.3E-9	1.0E-5			
79-01-6	Trichloroethene	8.3E-11	5.4E-6	8.5E-8	5.5E-3	3.1E-9	1.7E-5			
	Cumulative Values:	2.8E-9	1.7E-4	1.6E-6	1.2E-1	1.4E-8	2.9E-4	0.0E+0	0.0E+0	

indicates risk level exceeding target risk

#### RBCA Tool Kit for Chemical Releases, Version 1.3

	RBCA SITE	ASSESSMENT	-				Cu	mulative Risk Worl	sheet	
Site Name. H	arbert Transportation	Site Name: Harb	ert Transportation	1	Completed By: V	Veber, Hayes and A	Associates	Job ID: H9042.C		
Site Location:	19984 Meekland Avenue, Hayward, (	Site Location: 19	984 Meekland Ave	enue, Hayward, CA	Date Completed:	27-Dec-02			3 OF	
CUMULA	ATIVE RISK WORKSHEET			Cumulative Ta	arget Risk: 1.0E-5	Target Hazard Ir Groun		n: Domenico - No Deca	у	
					OFF-SITE F	RECEPTORS				
			Outdoor A	îr Exposure:			Groundwa	ter Exposure:		
CONSTITUENTS OF CONCERN		Residential (75 ft) Target Risk; Target HQ: 5 OF CONCERN 1.0E-6 / 1.0E-5 1.0E+0		No Target Risk: 1.0E-6 / 1.0E-5			al (250 ft) Target HQ: 1.0E+0	No Target Risk: 1 0E-6 / 1.0E-5	Target HQ:	
CAS No.	Name	Carcinogenic Risk	Hazard Quotient	Carcinogenic Risk	Hazard Quotient	Carcinogenic Risk	Hazard Quotient	Carcinogenic Risk	Hazard Quotient	
0-00-0	TPH - Arom >C08-C10		9.9E-5				4.2E-2			
71-43-2	Benzene	6.8E-10	3.2E-5			1.3E-7	3.5E-3			
108-88-3	Toluene		5.8E-7				8.2E-5			
100-41 <u>-4</u>	Ethylbenzene		3.7E-7				3.7E-4			
1330-20-7	Xylene (mixed isomers)	Į.	7.3E-8				1.9E-5			
107-06-2	Dichloroethane, 1,2-	1.8E-9	1.6E-5			2.4E-7				
127-18-4	Tetrachloroethene	2.4E-11	2.8E-6			2.2E-8	9.7E-5			
79-01-6	Trichloroethene	7.5E-11	4.9E-6			4.5E-9	1.6E-4			
	Cumulative Values:	2.5E-9	1.6E-4	0.0E+0	0.0E+0	3.9E-7	4.6E-2	0.0E+0	0.0E+0	

indicates risk level exceeding target risk

# **//**

# Weber, Hayes & Associates

#### Hydrogeology and Environmental Engineering

120 Westgate Dr., Watsonville, CA 95076 (831) 722-3580 (831) 662-3100 Fax: (831) 722-1159

# Letter of Transmittal

to:

Mr. Jerry Harbert

46765 Mountain Cove Drive Indian Wells, California 92210

from:

Craig Drizin

re:

c:

Harbert Transportation, 19984 Meekland Avenue, Hayward, California

date:

January 9, 2001

Number of Copies	Date of Documents	Description
1	December 27, 2002	Groundwater Monitoring Report - Third Quarter 2002

Mr. Amir K. Gholami Alameda County Environmental Health Services 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502 - 6577

Mr. Jeff Lawson Silicon Valley Law Group 152 N. Third Street, Suite 900 San Jose, California 95112

Ms. Laurie Berger 905 Emerald Hill Road Redwood City, California 94061

Mr. Gregg Petersen Durham Transportation 9011 Mountain Ridge Drive, Travis Building, Suite 200 Austin, Texas 78759 - 7275

Mr. Chuck Headlee San Francisco Bay Regional Water Quality Control Board 1515 Clay Street, Suite 1400 Oakland, California 94612

#### Appendix B

#### Field Methodologies for Groundwater Monitoring

Weber, Hayes and Associates' groundwater monitoring field methodology is based on procedures specified in the LUFT Field Manual. The first step in groundwater well sampling is for Weber, Hayes and Associates field personnel to measure the depth-to-groundwater to the nearest hundredth (0.01) of a foot with an electric sounder. If the well appears to be pressurized, or the groundwater level is fluctuating, measurements are made until the groundwater levels stabilizes, and a final depth-to groundwater measurement is taken and recorded. After the depth-to-groundwater is measured, the well is then checked for the presence of free product with a clear, disposable polyethylene bailer. If free product is present, the thickness of the layer is recorded, and the product is bailed to a sheen. All field data (depth-to-groundwater, well purge volume, physical parameters, and sampling method) is recorded on field data sheets (see attached). Because removing free product may skew the data, wells that contain free product are not used in groundwater elevation and gradient calculations.

After measuring the depth-to-groundwater, each well, starting with the cleanest well (based on analytical results from the last sampling event), is purged with a low flow submersible electric pump. During purging the physical parameters of temperature, conductivity, pH, dissolved oxygen (D.O.) concentration, and Oxidation-Reduction Potential (ORP) of the purge water are monitored with a QED MP20 Micropurge Flow-Through-Cell and Meter to insure that these parameters have stabilized (are within ~ 15 percent of the previous measurement). The QED MP20 Meter is capable of contiguously monitoring the physical parameters of the purge water via the flow through cell and providing an alarm to indicate when the physical parameters have stabilized to the users specifications. Purging is determined to be complete (stabilized aquifer conditions reached) after the removal of approximately three to five well volumes of water or when the physical parameters have stabilized. Dissolved oxygen and ORP measurements are used as an indicator of intrinsic bioremediation within the contaminant plume. All field instruments are calibrated before use.

All purge water is stored on site in DOT-approved, 55-gallon drums for disposal by a state-licensed contractor pending laboratory analysis for fuel hydrocarbons.

After purging, the water level in the well is allowed to recover to 80 percent of its original depth before a sample is collected. After water level recovery, a groundwater sample is collected from each well with a new, disposable bailer, and decanted into the appropriate laboratory-supplied sample container(s). The sample containers at this site were 40-ml. vials. Each vial was filled until a convex meniscus formed above the vial rim, then sealed with a Teflon®-septum cap, and inverted to insure that there were no air bubbles or head space in the vial. All samples are labeled in the field and transported in insulated containers cooled with blue ice to state-certified laboratories under proper chain of custody procedures.

All field and sampling equipment is decontaminated before, between, and after measurements or sampling by washing in an Liqui-Nox and tap water solution, rinsing with tap water, and rinsing with distilled water.



# Weber, Hayes & Associates

### Hydrogeology and Environmental Engineering

120 Westgate Dr., Watsonville, CA 95076 (831) 722-3580 (831) 662-3100 Fax: (831) 722-1159

INDICATE ATTAC	HMENTS THAT APPLY
χЬ	Data Sheets
X [	COC's
	Site Map
	Photo Sheet
<u> </u>	Chargeable Materials

Job Name: Harbert Transportation	Date: 8/27/02		
Field Location: 19984 Meekland Avenue, Hayward	Study #: <b>H9042.Q</b>		
Field Tasks: Drilling Sampling Other  3 <sup>rd</sup> Quarter 2002 Well Sampling	Weather Conditions:		
Personnel/Company onsite: (Weber, Hayes and Associates	s) Chad Taylor		

FIEL	D	WORK	PL	ANNING:	Performed	on:	8/26/02

Meet with project manager: X yes, or no.

Number of wells to be sampled: Five Wells, with D.O. in all wells Sample wells: MW-3, 5, 6, 9, 10, for TPH-g, BTEX, and MTBE.

Proposed sampling date: 8/27/02

TIME: 0750

Arrive onsite to perform 34 Quarter Monitoring Well Sampling.

COMMENTS:
Send all analytical to Entech Analytical Laboratory.

#### **INITIALS**:

All sampling is conducted according to Standard Operating Procedure (SOP) 101/

-Water Quality Sampling Information for each well sampled is recorded on following pages:

-Upon sampling, all samples are placed immediately in coolers containing blue ice.

-After sampling each well all equipment is decontaminated according to SOP 10B/.

-All purge water is properly disposed in 55-gallon drums to be purged at a later date.

-All samples are recorded on field Chain-of-Custody Sheets for transport to Laboratory.

#### **BEGIN CALIBRATION:**

QED MP20 Flow Through Cell: Temp = 17.34C, pH = 7.03 & 10.05, EC = 1.413 Barometric Pressure = 470

D.O. % Saturation = 10.5 ORP = 1.413 Barometric Pressure = 470

#### **BEGIN SAMPLING ALL WELLS:**

<u>ოს.პ ოს.ხ ოს.ხ ოს.ნ ოს.৭</u>
-See information below for general monitoring well information this sampling round.

COMMENTS:

All well will be purged until the QED MP20 unit indicates that the water quality parameters (pH, Conductivity, Temp, D.O., and ORP) have stabilized to within ~ 15 % or once four casing volumes in the column requiring sampling have been removed(see Water Quality Sampling Field Forms for details). Wells will be purged from bottom-up and will follow standard operating procedures by WHA. Wells will be sampled using a bladder pump, or disposable bailer.

Signature of Field Personnel & Date

E:\AJOB\H9042.hbt\QM\QM2002\3q02\QMFIELD.WPD



# Weber, Hayes & Associates

### Hydrogeology and Environmental Engineering

120 Westgate Dr., Watsonville, CA 95076 (831) 722-3580 (831) 662-3100

Fax: (831) 722-1159

•					·
Location	GW Depth (TOC)	Total Depth of Well	D.O. (mg/L)	ORP (mV)	Floating Product (comments).
W7-7	23.87	40.	0.13	7.08216	NoFP, Very Slyht Odor
MW·Y	24.07	Чо	0.11	187	NoFP, No Oda
MW·5	2 4.42	48.	64.0	207	Noff, Mod-Hyh Udar
MO-6	<u> </u>	45.	0.14	694231	NoFP, Very Slyht Clar
MW.7	24.98	40.	0.72	369	NoFP, No Odur
M77 - 8	24.43	40.	1. 98	402	NoFP, No Odu
MW-4	23.69	40.	0.18	3-01-154	NoFP, Slyhtodor
MD-10	25.46.	4D.	0.14	182	NEFF Slyhtodar
MO-II	23.58	40.	0.13	369	No FP, No Odor
MW·12	54.68.	Чо-	0.60	410	NoFP, Noodor
- CI 8/ea	\w				
				-24024-00-7-00-2-00-7-00-7-00-7-00-7-00-	
HOW MA	NY PURGE DRU	MS WERE LEFT O	NSITE 6.	APPROXIMA	TE GAL. 100 .
CALL BA		TO HAVE			
COMME	NTS:		•	11 /	
			`	11+++	8/27/n
E:\A	JOB\H9042.hbt\QM\Q	M2002\3q02\QMFIELD.	WPD	Signat	ure of Field Personnel & Date

Project N	ame/No.:	Herbert T	vansporta	tion /H	904Z.Q	<u>)</u>	Date: 8	27/02			
Sample N	اه.: M	1-3					Sample L	ocation	: MU3		
Samplers	Name: C	haltar	-				Recorded	i by: (	<b>オ</b>	,	
Purge Eq	uipment:						Sample E	quipme	ent:		
	-	sposable or /	Acrylic			٠		Х	Dispo	osable Bailer	
	_Whaler#	•								ler #	
<del></del>	Bladder P	•						······································		der Pump	
-	_Submersit	ole Pump							Subn	nersible Pump	
		d (cricle all t							es of Bottle U		
		2 DGA, EDB, 8	260 Fuel Oxyg	enates	<del></del>			5 +40~	LLALY 7/H	<u>()</u>	
IPH-diese	i <del>, Stoddard</del> o. Paramet		<del></del>	· · · · · · · · · · · · · · · · · · ·				· · · · · · · · · · · · · · · · · · ·	<u>- · . · </u>		
Well Num		MW.3				Well Dia	meter:	ھ"	with Casing V	olume of:	
Depth to V		23.87	TOC	_					•	2" = (0.16 Ga	
Weil Dept Height W-		<u>40'</u> 16.13'	BGS or TO feet (well d		th to we	tor)				4" = (0.65 Ga 5" = (1.02 Ga	
Volume in		2-5808							,	6" = (1.47 Ga	
Gallons to	purge:	10.32	gallons (vo	lume X 4)						8" = (2.61 Ga	allon/Feet
Lab:	Entech			-		Transpo	rtation:	De	liver		
Time (24 hr.)	Volume Purged (Gallons)	Temperature (°C)	Conductivity (ms/cm)	D.O. (ppm)	рН	ORP (mV)		Tui	bidity: Color, Fine	s	Micropurge Paramaters Stabilized
0841	0	18.63	0.704	8.13	6.84	317	Moden	د، هم	-Brown	ModeleFue	
0844	۷	18.97	0. 709	3.81	7.00	224	، ساما	Cle	r - Gray	MinorFines	
०९५२	4	18.78	0.702	0.38	7.01	221	Low:	Cle	~~, Tr	ModeleFue, MinorFines Lac Fines	
o <del>হ</del> ণ৭	6	18.79	0.702	0.19	7.00	220	1		•		
1880	8	18.79	0.702	0.16	6.99	219					
0853	10	18.80	0.7W	0.13	7.00	216		\	<u> </u>	<u> </u>	سا
STOP-	Paracet	us Stubi	172cd. P	urge Ca			·	-	~~	- 4-1-IFEMA - 7-7	
\				J	<b>\</b>						
U	سادراه								· · · · · · · · · · · · · · · · · · ·	***************************************	
· · · · · · · · · · · · · · · · · · ·	81.	Wait	for 80% w	ell volu	me rec	covery p	rior to s	amplir	ng.		<del></del>
		Calcula	te depth to	water (fro	m TOC	, for 80%	well volum	e recove	ery:		
					-	nal well volui				- 1	
	Ori	ginal Height of '	Water Column	= 16.131	_ x 0.8 =	12,904	(Well Depti	h) 40'	= Depth to water	Z7. <b>♦</b> 0'	
Time: <b>0855</b>	1st measured	I depth to water	43.97	feet below			ls well wit	thin 80% c	of original well cas	ing volume: Yes	-No
		l depth to water I depth to water							_	ing volume: Yes	∑ No
Time: \G	1st measured	depth to water	14	feet below			ls well wit	thin 80% o	of original well cas	ing volume: Yes	NOT
				Sa	mple	Well					
			<del> </del>				· · · · · · · · · · · · · · · · · · ·				
Time:	<b>C45S</b>		Sample ID:	M	ა.კ				Depth:_	23.97' feet be	low TOC
Comments	·	Election	Ponda I	11	3L.L.F.	Odor					
Johnnon		6	1104 11	WY -							

E:\CT\FEILDLOG\H2O-QSI.WB2

Sample N	ame/No.:	1W·6			· ·		Same	ole Loc	ation:	MW	٠6	
Samplers	Name:	Charol Tz.	,lw						у: <i>С</i>			
Purge Eq									uipment:			
, argo Eq	-	sposable or a	Acrylic				<b></b>	•	χ		Disposable Bailer	
У	Whaler#	•	•								Whaler#	
	Bladder P	ump									Bladder Pump	
	Submersil	ole Pump									Submersible Pump	
Analyses	Requested	d (cricle all t	hat apply):				Numb	oer and	d Types	of Bot	tle Used:	
TPH-gas, BT	EXMTBE.	2 DCA, EDB, 8	<del>260 Fuel Oxy</del> g	enates				5 2	110ml	70X's	W/HCl	
	l <del>, Stoddard</del>											
Intrin <del>cio B</del> i	<del>o. Parame</del> l	t <del>er</del> s										
Well Num		MW.6	•			Well Dia	meter:		<u>!"                                    </u>	th Casi	ing Volume of:	
Depth to \		24.94°	TOC BGS or TO	C							2" = (0.16 G) $4" = (0.65 G)$	allon/Fe
Well Dept Height W-	n: Column:		feet (well d		ath to wa	ater)					5" = (1.02 G	
Volume in			gallons (ca	sing volun	ne X hei						6" = (1.47 G	allon/Fe
Gallons to	purge:	5246	gallons (voi	ume X 4)							8" = (2.61 G	allon/Fe
Lab:	Entuch			•		Transpo	rtation	:	Delin	wr		
Time (24 hr.)	Volume Purged (Gallons)	Temperature (°C)	Conductivity (ms/cm)	D.O. (ppm)	рН	ORP (mV)			Turbidi	ty: Coloi	r, Fines	Micropurg Paramater Stabilized
			M ( 74)	7 01	/ 0=	_ 2\	11	\	12		M E .	
0914	٥	19.04	0.674	7.21	6.98	230	4.9	<u>u. C</u>	- 12	m ww.	Fram thes	
3916		18.64	0.673	0.84	6.84	276	Lo-	<u> </u>	1200-G	***	Many Fres Minor First	
0919	۲	18.67	G. 677	0.45	6.86	290	Lou	7' C	<u>اد (</u>	<u>'Tr</u>	-ce fines	
0923	P	18.89	0.612	6.20	6.90	299						
0128	12	१४.९।	0.684	<b>6.</b> {4	6.93	278						
0934	16	18.92	0.685	ه. لځ	6.93	249						
09 38	20	18.94	D. 684	0.14	6.44	231						
0142	22	18.93	0.684	0.14	6.94	231	Ţ		$\downarrow$		Ţ	
STUP-	D. 1	3 Shb	T-2 -1 D	rye Ca	1.4.		· ···· · · · · · · · · · · · · · · · ·		······································		, <u>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</u>	
J/U1 -	) THE		for 80% w			coverv r	rior t	o sar	nplina.			<u> </u>
			te depth to									
			ı	Calculate 80	)% of orgi	nal well volu	ne:					
	Or	iginal Height of	Water Column	= 20.56	_ x_0.8 =	16.448	(Well	Depth)_	45' = D	epth to v	water <u>28.55</u>	
···· •	-	I depth to water	7 e m	fa at landario			l=		. 000/ -f	:!I	ell casing volume: Yes _	٠ ١٠١٥
					•		ls w	ell withir	1 80% of or	iginal we iginal we	ell casing volume: Yes ell casing volume: Yes ell casing volume: Yes	No
ime: \G	1st measured	i depth to water i depth to water	Ja	feet below	•		ls w	ell withir	1 80% of or	iginal we	ell casing volume Yes	No C
			<del> </del>	Sa	ample	Well			. ,			
Time:	0445		Sample ID:		1W-6					Dep	oth: <b>2.5.0%</b> feet be	elow TO(
		. \ .		~\ \\ \\ \	ام ۱							
Comments	· N~	Floating Pa	17 11.	~ ~ ~ h	τ Chla	<b>~</b> ^						

E:\CT\FEILDLOG\H2O-QSI.WB2

Project N	ame/No.:	Harbert	Trans por	then !	14904	12・0	Date:	8 27/	v2	<del></del>		
	10.: MV						Sample	Locatio	on: M	1W.9		
Samplers	Name: C	Chad Tay 1	يد				Recorde	d by: (	<u>a</u>		*	
Purge Eq		/					Sample i	Equipn	nent:			
	Bailer: Di	sposable or	Acrylic					Χ.		Dispos	able Bailer	
	_Whaler#							<u>-</u>		Whaler	#	
	_Bladder P	•								Bladde	•	
	Submersi	ole Pump								Subme	rsible Pump	
		d (cricle all t					Number		•	Bottle Use		
		2 DCA, EDB, 8	260 Fuel Oxyg	enates.				5×40	שר האו	13 w/HC1	·	
<del></del>	il <del>, Stoddard</del> io. Paramet	·									· · · · · · · · · · · · · · · · · · ·	<del> </del>
Well Num		MW.1				Well Die	motori		udth C	Casina Val	uma af:	
Depth to \		25.61	TOC			Well Dia	meter		_ with C	asing Volu	ume o₁. 2" =_(0.16 Ga	ailon/Feet
Well Dept		40.	BGS or TO								4" = (0.65 Ga	allon/Feet
Height W- Volume in		16.31	feet (well de			•					5" = (1.02 G	
Gallons to		42.41	gallons (ca: gallons (vol		ne X nei	gnt)					6" = (1.47 Ga 8" = (2.61 Ga	
Lab:			. 94 (14	w,		Transpo	rtation:	$\mathcal{T}$	el.ver		(2.5. 5.	
	Values				<del></del>							
Time (24 hr.)	Volume Purged (Gallons)	Temperature (°C)	Conductivity (ms/cm)	D.O. (ppm)	рН	ORP (mV)		Т	urbidity: C	Color, Fines		Micropurge Paramaters Stabilized
1008	0	11.07	0.515	7.35	6.97	177	17-zh:	81-	ck,	Many	Finis	
1010	2	19.11	0.621	2.01	7.05	177	Low	Cla	Luc'	Trace	Fines	
1013	4	19.19	0.621	1.20	7.08	189						
1016	b	19.21	0.620	0.86	7.09	180						_
1023	10	19.27	0.620	0.53	7.08	172						
1031	15	19.32	0.625	0.36	7.05	160						
१०५०	20	14.37	0.630	0.18	7.01	154	Ĵ	Į	,	J		·
9012	· Paran	i	stabilized	l. P-/	ړو کړ	rlete.						
-					<del>)</del>							
		Wait	or 80% w	ell volu	me rec	coverv r	prior to s	ampl	ina.			
			te depth to v					•	_			
					_	nai weli volur						
	Ori	ginal Height of	Water Column	= 16.51	_ x 0.8 =	13.049	≦- (Well Dep	th) <b>40</b>	_ = Depth	to water <u>2</u>	<u>6. 95</u>	
Time: Ice14	1st measured	I depth to water	2 4.77	feet helow			le mell m	ıthin 80%	of origins	ndises llaw la	volume: Yes	tslo
									~		volume: Yes	
Time: \alpha	1st measured	depth to water depth to water	<u> 19</u>	feet below			ls well w	ithin 80%	of origina	al well casing	volume: Yes	No. CT
					_							
				Sa	mple	Weil						
Time:	1044		Sample ID:	M	N-4				1	Depth: <b>23</b> .	77' feet be	low TOC
Comments		No Floot	n Product	. Sl.	htal	<b>~</b>						
- Januario			9	<u>F. c</u>		·						

Sample N		Harbert W.s	i		<u> </u>			e: 8/೭가/ nple Locatio		w-5		
		Lad Tay						orded by:				
Purge Eq								nple Equipn				
rarge Ly	•	sposable or A	Acrylic ·				Can	npie Equipii X	ileilt.	Disposal	ble Bailer	
X	Whaler#	_								Whaler #		
	Bladder P	ump						,		Bladder	Pump	
	Submersit	ole Pump								Submers	sible Pump	
Analys <u>es</u>	Requested	t (cricle all t	hat apply):				Nun	nber and Ty				
		2-DOA, EDB, 8	260 Fuel Oxyg	enates			<del>,</del>	5 * 4	omply	19, 17 th	<u> </u>	
	<del>l, Stoddard</del>											
	o <del>: Paramet</del>		<del></del>		<del></del>		···					·
Well Num Depth to V		24.42°	TOC			Well Dia	mete	er: <u> </u>	with (	Casing Volu	me of: 2"  = (0 <u>.16 G</u>	allon/Fo
Well Dept		45	BGS or TO	С						يئس	1" = (0.65 G	allon/Fe
Height W-			feet (well de							į	5'' = (1.02  G)	allon/Fe
Volume in Gallons to		53.51	gallons (ca: gallons (voi		ne x nei	gnt)					6" = (1.47 G; 3" = (2.61 G;	
	Enteih		. 9 (			Transpo	rtatio	nn.	Deliv		(4.0)	
Lab.				•		rranspo	, tatic	<i>711.</i>	<del></del>			
Time (24 hr )	Volume Purged (Gallons)	Temperature (°C)	Conductivity (ms/cm)	D.O. (ppm)	рН	ORP (mV)		7	urbidity: (	Color, Fines		Micropurg Paramate Stabilized
1116	0	₹0.60	0.575	7.88	7.06	२०।	}	yh: G	۲~۷ ,	Many F	نرسد <u>د</u>	
1117	2	18.88	0.624	1.75	b.89	229	1	·yh: G ov: Cle-	٠- ٥٠٠	y Min	.ar F 5	
1119	4	18.92	0.636	0.82	6.19	725				1		
1121	6	18.95	0.646	0.53	6.91	216						
1124	10	19.01	0.652	0.43	6.92	7.10						
1128	15	19.04	0.654	0.43	6.93	207	`		T		Į.	1-
STOP			oil-zed .	Porre		olete.						
\	1 = 1 = 1	,	.,,	1 9								<del></del>
\car												
(0)	8 4-	\Mait 1	or 90% w	roll volu	mo ro	201/05/4		r to sampl	ina	<del></del>		
								volume reco	_			
		- Consulta	-	Calculate 80				10141110 1000		<del> </del>		
	Оп	iginal Height of	Water Column	= <u>20.58</u>	_ x 0.8 =	16.46	(We	ell Depth) 45	_ = Deptl	n to water Z ?	54	
m lina	-	-	1 a ma:								t	NI-
		l depth to water I depth to water			•			well within 80% well within 80%	_	_		
		i depth to water						well within 80%				
	···	· · · · · · · · · · · · · · · · · · ·		Sa	ımple	Well				<del> </del>		<del></del>
Time:	Ilsi		Sample ID:			<del></del>				Depth: 28-	<b>23</b> feet be	olow TOC
O a wa wa a a sa 4 -		No Floaty	2.1.1	M.J.	Τ п	1. 1						
<u>Comments</u>	: <u> </u>	NO FlouThy	Prodice i	Procen	ינב - חין	" Ullur.				· · · · · · · · · · · ·		

E:\CT\FEILDLOG\H2O-QSI.WB2

Project N	lame/No.:	Harbert -	Trunspart	stem	14904	12-Q	Date:	8/27/0				
Sample N		NW-10	<b>,</b>				Sample	Location:	MW.	10		
Samplers	Name: (	Charle	<u></u>				Recorde	ed by: Cす			,	
Purge Eq		l					Sample	Equipment				
	•	sposable or	Acrylic				·	· · ×		isposable	Bailer	
<u> </u>	_Whaler#	3								Vhaler#_		
	_Bladder P	•								lladder Pu	•	
	_Submersil	ole Pump							s	Submersibl	e Pump	
		d (cricle all t						and Types				
		2 DCA, EDB, 8	<del>260 Fuel Oxyg</del>	<del>enates </del>			5	x40m L UV	11 : W	HC1		
	io, <del>Stoadar</del> a io, Paramet	<del>Solvent —</del> ers		······································								
Well Num	ber:	MW.10				Well Dia	meter:	<u> ។ </u> wi	ith Casir	na Volume	of:	
Depth to !	Water:	٤.3.46٠	TOC	_						2"	= (0.16 Ga	
Well Dept Height W-		16.54	BGS or TO feet (well de		ith to we	iter)				5"	= (0.65 Ga = (1.02 Ga	allon/Feet allon/Feet
Volume ir	n Well:	10.751	gallons (ca	sing volun	ne X hei					6"	= (1.47 Ga	allon/Feet
Gallons to	•	4 3.00	gallons (voi	ume X 4)				_	1		= (2.61 Ga	allon/Feet
Lab:	Entach			•		Transpo	rtation:	<u> </u>	but; ve			
Time (24 hr.)	Volume Purged (Gallons)	Temperature (°C)	Conductivity (ms/cm)	D.O. (ppm)	рH	ORP (mV)	·	Turbid	lity: Color,	Fines		Micropurga Paramaters Stabilized
1156	O	20.66	७.९५५	8-20	6.75	219	17; gh	: Gray-B Clear-	אישיי	Moder	tefus	
1158	2	18.87	0.930	2.13	6.67	201	Lows	Clear -	Brow	a Min	:orF.~>	
1200	4	18.92	0.890	0.81	6.64	tos						
1201	6	28.81	0.887	0.54	6.64	186		<del></del>	ļ			-
1205	10	18-96	0.813	0.15	6.65	180)		<u> </u>	ļ			<u> </u>
1204	15	18.46	0.879	0.14	6.67	182	V	•	<u> </u>		<u>ل</u>	
STOP	- P	meters	5 26. 17	red P.	سر د (	لماجسه	Z-1					
1		<u> </u>			U	1						
10gh	16-								<del></del>	<del> </del>		<u> </u>
101	I	Wait	for 80% w	eli volu	me red	covery r	orior to s	sampling				J
			te depth to v									
					-	nal well volu						
	Ori	iginal Height of	Water Column	= 16.24.	_ x 0.8 =	12.525.	(Well Dep	oth) 70 = 0	epth to w	ater <u>26.7</u>	<b>3</b> .	
Time: 12.11	1st measured	I depth to water	, 23.48'	feet below			ls well w	ithin 80% of o	riginal wel	I casing volu	ıme: Yes	No
Time:	1st measured	depth to water depth to water	,	feet below	-		ls well w	vithin 80% of o vithin 80% of o	rıgınal wel	I casing volu	ıme: Yes 🗻	No
Time: 19	1st measured	l depth to water	, 19	feet below	•		is well w	ithin 80% of o	riginal wel	I casing volu	me: Yes	_N0 <u>61</u>
				Sa	ample	Well						
Time:	1211		Sample ID:		10.10				Dep	th: <u>23.48</u>	feet be	low TOC
Comments	. <u>6</u> 1. e	Floaty T	1	SLLL	۔۔ لی							
Comments	<u>, (∨6)</u>	- Lea Em	reameT.	JIGHT	CUOY!			······································				
		<del> </del>								••••		

Groundwater Monitoring Report - Third Quarter 2002 19984 Meekland Avenue, Hayward, California December 27, 2002

# Appendix C

Summary of Historical Depth to Groundwater Measurements, Groundwater Elevations, and Groundwater Flow Direction - AGI Technologies, Inc.





Table 1
Groundwater Elevation Data
Harbert Transportation/Meekland Avenue
Hayward, California

		Top of Casing	Depth to	Groundwater
Weil	Date	Elevation	Groundwater	Elevation
Number	Samples	(feet)	(ft:bgs)	(feet)
MW3	10/20/94	100.00	27.12	72.88
	09/15/95	, , , , , ,	24.22	75.78
	03/14/96	ļ	19.02	80.98
	09/26/96		23.61	76.39
MW4	10/20/94	100.27	27.32	72.95
1	09/15/95		24.42	75.85
1	03/14/96		19.23	81.04
}	09/26/96		23.85	76.42
MW5	10/20/94	100.59	27.71	72,88
	09/15/95	ļ	24.87	75.72
İ	03/14/96		19.95	80.64
1	09/26/96	ł	24,38	76:21
MW6	10/20/94	100.57	27.68	72.89
}	09/15/95		24.79	75.78
	03/14/96		19.54	E0.18
ĺ	09/26/96		24.20	76.37
MW7	10/20/94	101.22	28.25	72.97
	09/15/95		25.35	75,87
j	03/14/96		20.06	81,16
·	09/26/96		24.75	76.47
8WM	10/20/94	100.72	27.73	72.99
,	09/15/95		24:81	75,91
	03/14/96		19.52	81_20
	09/26/96		24.13	76,59
eww.	10/20/94	99. <i>77</i>	26.90	72.87
-	09/15/95	Ì	24.01	<i>75.7</i> 6
l	03/14/96		18.80	80,97
	09/26/96		23.50	76.27
MW10	10/20/94	99.29	26.46	72.83
	09/15/95		23.79	75.50
]	03/14/96		18.62	80.67
	09/26/96		23.30	75,99
MW11	10/20/94	99.75	26.89	72.86
	09/15/95		24.05	75.70
	03/15/96		18.79	80.96
	09/26/96	494.69	23.53	76.22
MW12	10/20/94	101.03	28.11	72.92
ļ	09/15/95		25.19	75.84
ĺ	03/14/96		19.84	81.19
	09/26/96		24,57	76.46

Note:

ft bgs - Feet below ground surface.







Scale in Feet

Harbert Transportation/Meekland Avenue Hayward, California

PROJECT NO."





Groundwater Monitoring Report - Third Quarter 2002 19984 Meekland Avenue, Hayward, California December 27, 2002

# Appendix D

**Certified Analytical Report - Groundwater Samples** 

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

September 09, 2002

Chad Taylor Weber, Hayes and Associates 120 Westgate Drive Watsonville, CA 95076

Order:31041Date Collected:8/27/2002Project Name:Harbert TransportationDate Received:8/28/2002Project Number:H9042.QP.O. Number:H9042.Q

**Project Notes:** 

On August 28, 2002, samples were received under documentented chain of custody. Results for the following analyses are attached:

MatrixTestMethodLiquidEDF DeliverablesEDF

Gas/BTEX/MTBE EPA 8015 MOD. (Purgeable)

Chemical analysis of these samples has been completed. Summaries of the data are contained on the following pages. USEPA protocols for sample storage and preservation were followed.

Entech Analytical Labs, Inc. is certified by the State of California (#2346). If you have any questions regarding procedures or results, please call me at 408-588-0200.

Sincerely,

Patti Sandrock QA/QC Manager

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Weber, Hayes and Associates

120 Westgate Drive

Watsonville, CA 95076

Attn: Chad Taylor

Date: 9/9/02

Date Received: 8/28/2002

Project Name: Harbert Transportation

Project Number: H9042.Q P.O. Number: H9042.Q

Sampled By: Chad Taylor

#### **Certified Analytical Report**

Order ID: 33	1041	Lab Sa	mple I	<b>D:</b> 3104	1-001		Client San	nple ID: MV	V-3	
Sample Time:		Sam	ple Da	te: 8/27/	2002		I	<b>Matrix:</b> Liq	uid	
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	0.56		1	0.5	0.5	μg/L	N/A	8/29/2002	WGC62554	EPA 8020
Toluene	1.1		1	0.5	0.5	μg/L	N/A	8/29/2002	WGC62554	EPA 8020
Ethyl Benzene	14		1	0.5	0.5	μg/L	N/A	8/29/2002	WGC62554	EPA 8020
Xylenes, Total	3.4		1	1	1	$\mu$ g/L	N/A	8/29/2002	WGC62554	EPA 8020
•					Surroga	ite	Surr	ogate Recovery	Conti	ol Limits (%)
				4-B	romofluoro	benzene		100.1	6	5 - 135
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Methyl-t-butyl Ether	ND		1	5	5	μg/L	N/A	8/29/2002	WGC62554	EPA 8020
,					Surroga		Surre	ogate Recovery	Contr	ol Limits (%)
				4-Bi	romofluoro			100.1	65	5 - 135
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	350		1	50	50	μg/L	N/A	8/29/2002	WGC62554	EPA 8015 MOD. (Purgeable)
					Surroga	ite	Surr	ogate Recovery	Contr	ol Limits (%)
				4-Bi	romofluoro	benzene		153.7	65	5 - 135
				aas	-Trifluoro	toluene		123.1	65	5 - 135
Comment: Su	rrogate outside of cor	ntrol limits	due to m	atrix interf	erence.					

DF = Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Patti Sandrock, OA/OC Manager

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Weber, Hayes and Associates

120 Westgate Drive

Watsonville, CA 95076

Attn: Chad Taylor

Date: 9/9/02

Date Received: 8/28/02

Project Name: Harbert Transportation

Project Number: H9042.Q

P.O. Number: H9042.Q

Sampled By: Chad Taylor

#### **Certified Analytical Report**

Order ID: 31041		Lab Sa	mple ID:	3104	1-002		Client Sam	ple ID: MW	V-5	
Sample Time:		Sam	ple Date	8/27/	/02		I	<b>Matrix:</b> Liq	uid	
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	170		5	0.5	2.5	μg/L	' N/A	8/29/02	WGC62554	EPA 8020
Toluene	14		5	0.5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Ethyl Benzene	210		5	0.5	2.5	$\mu$ g/L	N/A	8/29/02	WGC62554	EPA 8020
Xylenes, Total	93		5	1	5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
					Surroga	ate	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluor	obenzene		95.5	65	5 - 135
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Methyl-t-butyl Ether	ND		1	5	5	μg/L	N/A	9/4/02	WMS21691B	EPA 8260B
					Surroga	ate	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		100.1	73	3 - 151
				Dıb	romofluoro	methane		113.9	57	7 - 156
					Toluene-	-d8		93.8	77	7 - 150
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	1900		5	50	250	μg/L	N/A	8/29/02	WGC62554	EPA 8015 MOD. (Purgeable)
					Surroga	ite	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		132.2	65	5 - 135

DF = Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Weber, Hayes and Associates

120 Westgate Drive Watsonville, CA 95076

Attn: Chad Taylor

Date: 9/9/02 Date Received: 8/28/02

Project Name: Harbert Transportation

Project Number: H9042.Q P.O. Number: H9042.Q Sampled By: Chad Taylor

**Certified Analytical Report** 

Order ID: 31041		Lab Sa	mple ID:	3104	1-003		Client Sam	ple ID: MW	7-6	
Sample Time:		Sam	ple Date:	8/27	/02		1	Matrix: Liqu	uid	
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	ND		5	0.5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Toluene	7.2		5	0.5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Ethyl Benzene	210		5	0.5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Xylenes, Total	55		5	1	5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
					Surroga	ıte	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		118.5	65	5 - 135
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Methyl-t-butyl Ether	ND		1	5	5	μg/L	N/A	9/4/02	WMS21691B	EPA 8260B
, ,					Surroga		Surre	gate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		99.4	73	- 151
				Dib	romofluoro	methane		101.6	57	' - 156
					Toluene-	d8		96.5	77	' - 150
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	1300		5	50	250	μg/L	N/A	8/29/02	WGC62554	EPA 8015 MOD (Purgeable)
					Surroga	ite	Surre	gate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		117.4	65	- 135

DF = Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Patti Sandrock, QA/QC Manager

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Weber, Hayes and Associates

120 Westgate Drive

Watsonville, CA 95076

Attn: Chad Taylor

Date: 9/9/02

Date Received: 8/28/02

Project Name: Harbert Transportation

Project Number: H9042.Q

P.O. Number: H9042.Q Sampled By: Chad Taylor

**Certified Analytical Report** 

Order ID: 31041		Lab Sa	mple II	<b>):</b> 3104	1-004		Client Sam	ple ID: MV	V-9	
Sample Time:		Sam	ple Dat	e: 8/27/	<b>02</b>			Matrix: Liq	uid	
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	27		1	0.5	0.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Toluene	2.5		1	0.5	0.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Ethyl Benzene	20		1	0.5	0.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Xylenes, Total	20		1	1	1	μg/L	N/A	8/29/02	WGC62554	EPA 8020
					Surroga	ate	Surr	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		93 7	65	5 - 135
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Methyl-t-butyl Ether	ND		1	5	5	μg/L	N/A	8/30/02	WMS21689	EPA 8260B
,,					Surroga	• -	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro			96.9	73	` ,
				Dib	romofluoro	methane		93.2	57	7 - 156
					Toluene-	-d8		97 9	77	7 - 150
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	310		1	50	50	μg/L	N/A	8/29/02	WGC62554	EPA 8015 MOD (Purgeable)
					Surroga	ite	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		134 4	65	5 - 135

DF = Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Patti Sandrock, QA/QC Manager

Environmental Analysis Since 1983

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Weber, Hayes and Associates

120 Westgate Drive

Watsonville, CA 95076

Attn: Chad Taylor

Date: 9/9/02

Date Received: 8/28/02
Project Name: Harbert Transportation

Project Number: H9042.Q P.O. Number: H9042.Q

Sampled By: Chad Taylor

Certified Analytical Report

<b>Order ID:</b> 31041		Lab Sa	mple II	<b>D:</b> 3104	1-005		Client Sam	ple ID: MW	7-10	
Sample Time:		Sam	ple Dat	e: 8/27/	02		I	Matrix: Liqu	uid	
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	ND		5	0 5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Toluene	15		5	0.5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Ethyl Benzene	3.9		5	0.5	2.5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
Xylenes, Total	5.0		5	1	5	μg/L	N/A	8/29/02	WGC62554	EPA 8020
					Surroga	ıte	Surr	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		132.0	65	5 - 135
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Methyl-t-butyl Ether	ND		1	5	5	μg/L.	N/A	8/30/02	WMS21689	EPA 8260B
					Surroga	ıte	Surr	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		97.1	73	- 151
				Dib	romofluoro	methane		93.5	57	- 156
					Toluene-	-d8		97.3	77	- 150
Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	1800		5	50	250	μg/L	N/A	8/29/02	WGC62554	EPA 8015 MOD. (Purgeable)
					Surroga	ite	Surre	ogate Recovery	Contr	ol Limits (%)
				4-B	romofluoro	benzene		127.2	65	- 135

DF = Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Patti Sandrock, QA/QC Manager

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Quality Control Results Summary

QC Batch #:

WGC62554

Units:

μg/L

Matrix: Liquid

**Date Analyzed:** 8/29/2002

Parameter	Method	Blank Result	Spike Sample ID	Spike Amount	Sample Result	Spike Result	QC Type	% Recovery	RPD	RPD Limits	Recovery Limits
Test: T	PH as Gasoline		**************************************								
TPH as Gasoii	ne EPA 8015 M	ND		100		95.2	LCS	95.2			65.0 - 135.0
	Surrogate		Surrog	ate Recover	<b>'y</b>	Control 1	Limits (%)				
	4-Bromofluorobe	enzene		96.4		65 -	135				
Test: B'	TEX										
Benzene	EPA 8020	ND		8		8.52	LCS	106.5			65.0 - 135 0
Ethyl Benzene	EPA 8020	ND		8		8.69	LCS	108.6			65.0 - 135.0
Toluene	EPA 8020	ND		8		8.57	LCS	107 1			65 0 - 135.0
Xylenes, total	EPA 8020	ND		24		26.6	LCS	110.8			65.0 - 135.0
	Surrogate		Surrog	ate Recover	у	Control 1	imits (%)	•			
	4-Bromofluorobe	nzene		96 3		65 -	135			*******	
Test: M	TBE by EPA 8020	)									
Methyl-t-butyl	•	ND		8		8.78	LCS	109 7			65.0 - 135.0
	Surrogate		Surrog	ate Recover	y	Control I	Limits (%)				
	4-Bromofluorobe	nzene		96.3		65 -	135				
Test: TI	PH as Gasoline				•						
TPH as Gasolii	ne EPA 8015 M	ND		100		94.	LCSD	94 0	1 27	25 00	65.0 - 135.0
	Surrogate		Surreg	ate Recover	у	Control I	Limits (%)				
	4-Bromofluorobe	nzene		98.3		65 -	135				
Test: B	rex										
Benzene	EPA 8020	ND		8		8.35	LCSD	104.4	2.02	25.00	65.0 - 135 0
Ethyl Benzene	EPA 8020	ND		8		8.5	LCSD	106.3	2.21	25.00	65.0 - 135.0
Toluene	EPA 8020	ND		8		8.3	LCSD	103.8	3.20	25.00	65.0 - 135.0
Xylenes, totai	EPA 8020	ND		24		25.	LCSD	104.2	6.20	25.00	65.0 - 135.0
	Surrogate		Surroga	ate Recover	y	Control I	imits (%)		-		
	4-Bromofluorobe	nzene		94.7		65 -	135				
Test: M	TBE by EPA 8020	)									·
Methyl-t-butyl	•	ND		8		8.49	LCSD	106.1	3.36	25.00	65.0 - 135.0
	Surrogate		Surroga	ate Recover	у	Control I	imits (%)				
	4-Bromofluorobe	nzene		94.7		65 -	135				

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

Quality Control Results Summary

QC Batch #:

Matrix:

WMS21691B

Liquid

Units:

Date Analyzed:

9/4/2002

 $\mu g/L$ 

Paramete	er	Method	Blank Result	Spike Sample ID	Spike Amount	Sample Result	Spike Result	QC Type	% Recovery	RPD	RPD Limits	Recovery Limits
Test:	MTBE b	y EPA 826	0B									
Methyl-t-	butyl Ether	EPA 8260B	ND		20		15.4687	LCS	77.3			65.0 - 135.0
ſ	Su	rrogate	•	Surrog	ate Recover	у	Control	Limits (%)				
	4-]	Bromofluorob	enzene		96.4		73 -	151				1
	Di	bromofluoron	nethane		91 5		57 -	156				
	To	luene-d8			97 2		77 •	150				
Test:	MTBE b	y EPA 826	0B			· · ·						
Methyl-t-l	butyl Ether	EPA 8260B	ND		20		17.4109	LCSD	87.1	11.81	25.00	65.0 - 135.0
	Su	rrogate		Surrog	ate Recover	<del>у</del>	Control	Limits (%)	•			
	4-]	Bromofluorob	enzene		94.9		73 -	151				
	Di	bromofluoron	nethane		94.2		57 -	156				
į	To	luene-d8			97.5		77 -	150				

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201 **Quality Control Results Summary** 

QC Batch #:

WMS21689

Matrix:

Liquid

Units:

 $\mu g/L$ 

Date Analyzed:

8/30/2002

Paramete	r Method Blan Resul		Sample Result	Spike Result	QC Type	% Recovery	RPD	RPD Limits	Recovery Limits
Test:	BTEX by EPA 8260B						•		
Benzene	EPA 8260B ND	20	2:	3.4092	LCS	117.0			90.9 - 124.5
Toluene	EPA 8260B ND	20		22.619	LCS	113.1			89.9 - 116.0
	Surrogate	Surrogate Recover	ry C	ontrol I	imits (%)				
	4-Bromofluorobenzene	100.3		65 -	135				İ
	Dibromofluoromethane	97.0		57 -	156				
	Toluene-d8	86.4		77 -	150				
Test:	Oxygenates by EPA 8260	3							
Methyl-t-b	outyl Ether EPA 8260B ND	20		19.995	LCS	100.0			56.0 - 135.0
	Surrogate	Surrogate Recover	ry C	ontroi I	imits (%)	1			
ļ	4-Bromofluorobenzene	100.3		73 -	151				
	Dibromofluoromethane	97.0		57 -	156				
L	Toluene-d8	86.4		77 -	150				
Test:	BTEX by EPA 8260B								
Benzene	EPA 8260B ND	20	22	2.2527	LCSD	111.3	5.07	25.00	90.9 - 124.5
Toluene	EPA 8260B ND	20	2	21.256	LCSD	106.3	6.21	25.00	89.9 - 116.0
	Surrogate	Surrogate Recover	у С	ontrol I	imits (%)				
	4-Bromofluorobenzene	101.1		65 -	135				
	Dibromofluoromethane	98.2		57 -	156				
	Toluene-d8	85.8		77 -	150				
Test:	Oxygenates by EPA 82601	3							
Methyl-t-b		20	19	9.2345	LCSD	96.2	3.88	25.00	56.0 - 135.0
· [	Surrogate	Surrogate Recover	y C	ontrol I	imits (%)				
	4-Bromofluorobenzene	101.1		73 -	151				
	Dibromofluoromethane	98.2		57 -	156				
	Toluene-d8	85.8		77 -	150				1



#### Weber, Hayes & Associates

### CHAIN -OF-CUSTODY RECORD

Hydrogeology and Environmental Engineering 120 Westgate Dr., Watsonville, CA 95076 (831) 722-3580 (831) 662-3100 Fax (831) 722-1159

TORY: Entech				
TIME. Normal	24hr Rush	48hr Rush	72hr Rush	

PROJECT NAME AND JOB #. Harbert Transporation / H9042.Q LABORA SEND CERTIFIED RESULTS TO: Chad Taylor TURNAROUNE ELECTRONIC DELIVERABLE FORMAT ... NO GLOBAL I D . T0600100475 REQUESTED ANALYSIS SAMPLE CONTAINERS Total Petroleum Hydrocarbons Volatile Organics Additional Analysis Field Point Name Sample Sample Date 40 mL 1 Liter mL. Liner Gasoline & BTEX-MTBE (GeoTracker) Identification Depth Sampled 1,2-DGA by Title 22. General Solvents by Purgeable Fuel-Scan Extractable Oxygenates by EPA Method 8260 VOAs Amber Poly Acetate by EPA Method# Physical and by EPA Method# by EPA Fuel-Scan 8015M-&-8020 8010 Inorganic Bottle Method# 8010 (preserved) Jars or Brass MW-3 MW.3 8 470 5 31041+00 23.97 S MU-5 MW 5 28.25 DUS M17. P MW-P 5 25.08 P.WM 25.77 5 40.9 MW-10 MW-10 23.46 5 SAMPLE CONDITION: pendiven by.

1) Sampler.	- 9/1/n 1360	RELEASED BY:	Date & Time	Ambient (Refingerated Froze	≆n
2) Mingh!	8/20/028:10		-	Ambient Refingerated Froze	şn
3) Joseph Hallado	8/28/02 9 35		<del></del>	Ambient Refingerated Froze	¥n
4)	*			Ambient Refingerated Froze	en.
5)	·		-	Ambient Refingerated Froze	en .

#### NOTES:

V If MTBE is detected by EPA Method 8020, please confirm detections by EPA Method 8260 with a minimum detection limit of 5 ug/L, and report only

For MTBE-analyzed samples with non-detectable results (ND) but having elevated detection limits, please confirm by EPA Method

Please use MDL (Minimum Detection Limit) for any diluted samples

#### ADDITIONAL COMMENTS

- Please produce and e-mail an EDF of these results to tina@weber-hayes.com.

Groundwater Monitoring Report - Third Quarter 2002 19984 Meekland Avenue, Hayward, California December 27, 2002

# Appendix E

Summary of Historical Groundwater Analytical Results - AGI Technologies, Inc.





		1600				EPA Test Meth	ods					
		8	016 Modified			8020				8010		
		TOUG						Total				
	Date	TPH-G	TPH-D	TPH-MO	Benzene	Ethylbenzene	Toluene	Xylenes	TCE	PCE	1,2-DCA	Other
Well	Sampled	2.000	HOLL			μα/Լ				μg/L		<b>ԱՈ</b> Մ
MW1	07/86	42,000	NA	NA	5,500	NA	4,900	6,100	NA	NA	NA	
	03/90	27,000	NA	NA	2,700	491	840	800	ND.	ND	ND	
	07/90	27,000	11,000	ND	4,000	ND	1,500	4,400	ND	ND	62	
	10/90	43,000	8,500	ND	3,400	1,200	2,700	5,300	0.4	ND	26	
	01/91	22,000	2,700	ND	3,000	990	1,800	2,800	ND	ND	27	
	04/91	42,000	3,100 "	NA	5,100	1,200	3,700	3,200	ND	ND	120	
	07/91	46,000	4,300 ª	NA	6,500	830	2,900	3,700	ND	ND	64	
	10/91	27,000	4,300	NA	4,400	1,100	1,400	3,200	ND	ND	25	
	01/92	27,000	14,000 *	NA	3,300	1,200	1,600		ND	ND	24	
	04/92	33,000	11,000 <sup>a</sup>	NA	8,900	1,200	3,500	* 1	ND	ND	120	,
	07/92	41,000	19,000 *	NA	5,600	1,300	2,600		ND	ND	49	
	10/92	33,000	3,500	NA	4,400	1,200	2,100		ND	, ND	61	
MW3	11/89	29,000	NA	NA	4,600	680	1,100		ND	ND	36	Lead 40
	11/89	NA NA	NA	NA	NA	NA	NA		ND	ND	36	Lead 40
	03/90	12,000	NA	NA	2,300	59	300	1	ND	ND	ND	E000 40
	07/90	7,300	990	ND	5,200	ND	440	480	ND	ND	67	
	10/90	6,200	970	ND	75	7.5	150	250	ND	ND	. 48	
	10/90	NA.	NA	NA	NA.	NA	NA	NA	ND	ИD	22	Lead 3
	01/91	4,600	680	ND	2,200	220	110		ND	ИD	40	roud o
	04/91	8,300	640	NA	2,800	370	490		ND	ND	43	
	07/91	6,600	890 *	NA	2,000	250	230	380	ND	ND	29	•
	10/91	6,300	1,700 *	NA	2,000	410	330	550	ND	ИD	27	
	01/92	4,000	790 <sup>a</sup>	NA	1,200	250	60		ND	ИD	22	
	04/92	7,400	1,800 <sup>a</sup>	NA	730	370	180		ND	ИD	19	
	07/92	3,000	2,400	NA	190	ND	2.8		ND	ND	30	~ ~
	10/92	5,000	970 ª	NĄ	1,300	320	.45	340	ND	ND	26	•
	01/93	2,300	680 <sup>8</sup>	NA (2)	630	180	31		ИD	ND	13	
	06/93	5,000	1,100 <sup>a</sup>	ND	730	240	43		ND	ND	13	

Table 2
Summary of Historical Groundwater Analytical Data
Harbert Transportation/Meekland Avenue
Hayward, California



						EPA Test Meth	ods				1	
		8	015 Modified			8020				8010		
								Total				
	Date	TPH-G	TPH-D	TPH-MO	Benzene	Ethylbenzene	Toluene	Xylenes	TCE	PCE	1,2-DCA	Other
Well	Sampled		hayr			μg/L				μg/L		μ <b>g/L</b> :
MW4	11/89	ND	NA	NA	33	1.3	1	5.2	NA	NA	A4A	· · · · · · · · · · · · · · · · · · ·
	03/90	СИ	NA	NA	7.4	2	2	1.1	ND	ND	NA	Lead 12
	07/90	ND <sup>1</sup>	ND	ND	ND	ND	ND	ND	ND	ND	ND	
	10/90	ND	ND	ND	ND	ND	ND	ND	0.7	ND	0.9 0.5	
	01/91	80	NĐ	ND	9.2	2.4	1.7	0.7	ND	ND	ND	
	04/91	1,400	130 *	NA	2,200	72	ND	17	ND	ND	ND	
	07/ <del>9</del> 1	130	ND	NA	14	3.3	9.7	ND	ND	ND	0.81	
	10/91	ND	ND	NA	5.3	1	ND	0.8	ND	ND	ND	
	01/92	ИD	ND	NA	6.8	1.3	ND	ND	ND	ND	ND	
	04/92	780	130 *	NA	ND	51	ND	4.8	ND	ND	1.6	
	07/92	ND	ND	NA	ND	ND	ND	ND	, ND	ND ND		
	10/92	100	ND	NA	9.5	ND	ND	2.6	ND	, ND	1.3 ND	
	01/93	960	240	NA	200	41	4.6	9.4	ND	ND	110	
	06/93	650	140 *	ND	150	21	ND	ND	ND	ND	3.7	
MW5	10/90	9,600	1,900	ND	1,200	70	160	520	ND	ND	22	10010
	01/91	10,000	1,200	ND	1,600	720	200	510	ND	ND	33	Lead 3
	04/91	18,000	860 *	NA	2,500	550	580	500	ND	ND	61	
	07/91	15,000	2,200 4	NA	4,800	610	1,100	760	ND	ND ND	62	
	10/91	14,000	3,300	NA	5,000	530	820	800	ND	ND	49	
	01/92	12,000	1,900 *	NA	4,300	390	380	590	ND	ND	56	
	04/92	23,000	6,400 °	NA	8,600	ND	2,600	1,900	NĐ	ND	125	
	07/92	27,000	5,900 *	NA	6,000	ND	1,500	1,600	ND	ND ND	1	
	10/92	13,000	2,100 ª	NA	4,600	140	470	550	ND ND	ND ND	93	
	01/93	18,000	1,900	NA	5,800	560	1,900	1,600	ND	ИD	59	
	01/93	19,000	2,100 *	NA	4,600	370	1,600	1,400	ND	ND ND	110 120	<b>3</b>
	06/93	22,000	2,900	ND	8,300	740	2,500	1,900	ND	ND ND	110	
	06/93	23,000	2,300 8	NĐ	9,600	730	3,000	1,900	ND	ND ND	110	

Table 2
Summary of Historical Groundwater Analytical Data
Harbert Transportation/Meekland Avenue
Hayward, California



						EPA Test Meth	ods				1	
			8015 Modified	i		8020				8010		
Well	Date Sampled	TPH-G	TPH-D µg/L	TPH-MO	Benzene	Ethylbenzene µg/L	Toluene	Total Xylenes	TOE	PCE µg/L	1,2-DCA	Other ug/L
MW6	10/90	27,000	4,700	ИD	2,700	450	2,900	3,300	ND	<u> </u>	40	
	01/91	7,200	1,600	ND	1,400	ND	200	830	ND	ND	40	Lead 9
	04/91	17,000	t 800 a	NA	2,800	610	1,200	1,800	ND	ND	23	
	07/91	11,000	1,400	NA	1,200	ND	380	750	ND ND	ND ND	53	
	10/91	4,800	1 600 <sup>a</sup>	NA	380	69	340	730	ND	ND	29	
	01/92	6,100	1,200	NA	460	180	200	590	ND	ND	22 26	
	04/92	7,200	1,800	NA	340	350	460	920	ND	ND		
	07/92	8,600	1,700	NA	1,300	380	280	1,100	ND	ND	30 35	
	10/92	1,600	110	NA	230	70	20	88	ND	ND	24	
	01/93	13,000	2,100 <sup>a</sup>	NA	2,500	370	540	2,400	ND	ND	36	•
	06/93	7,400	1,900	ND	1,500	480	120	1,400		ND	29	
MW7	10/90	14,000	2,700	ND	390	ND	18	1,200	ND	, 1.3	14	Lead 11
	01/91	4,500	1,400	ND	320	42	48	350	ND	ND	10	coud i i
!	04/91	2,400	NA	NA	320	77	. 62	130	ND	0.6	11	
	07/91	2,000	910 *	NA	470	ND	24	88	ND	ND	9.7	
	10/91	ND	370 *	NA	ND	ND	ND	ND	ND	0.68	4.5	
	01/92	1,100	290 *	NA	230	45	7	88	ND	3.5	6.4	
	04/92	1,700	520 ª	NA	310	78	28	170	ND	0.5	3.2	
	07/92	1,900	590 *	NA	410	78	21.	170	ND	2.1	8.7	
	07/92 (dup)	1,200		NA	21	1	2.6	90	ND	2	8.2	
	10/92	1,800		NA	410	31	11	75	ND	1	7.4	
i I	01/93	2,100		NA	390	100	21	270	ND	0.6	3.7	
	06/93	4,400	1,100 a	ND	830	330	49	620	ИD	ND	8.6	

Page 3 of 5





					EPA/Test Methods							
			8015 Modifie	ıd		8920				8010		
	Date	TPH-G	TPH-D	ТРН-МО		en a	_	Total				
Well	Sampled	16(179		IFN-MU	Benzene	Ethylbenzene	Toluene	Xylenes	TCE	PCE	1,2-DCA	Other
900.93949.00	Sampleu		h <b>air</b>			pg/L				μg/L		μg/L
MW8	02/91	. ND	ND	NA	ND.	ND	ND	ND	ND	ND	ND	
	04/91	ND	ND	NA	ND.	ND	ND	ND	ND	0.5	ND	
	07/91	ND	ND	NA	ND	ND	2	ND	ND	1.2	ND	
	10/91	ND	ND	NA	ND	ПИ	0.6	ND	ND	0.4	ND	
	01/92	ND	ND	NA	ND	ND	ND	ДИ	ND	0.68	ND.	
	04/92	ND	ND	NA	ND.	ND	ND	ND	ND	0.8	ND	
	07/92	ND	ND	NA	ND	ND	3.3	ND	ND	1.6	ND	
	10/92	ND	ND	NA	ND	ND	ND	ND	ND	1.4	ND	
	01/93	ND	ND	NA	ND	ND	ND	ND	ND	0.8	ND	
	06/93	ND	ND	ND	ND	ND	ND	ИD	ND	1.4	ND	
MW9	02/91	6,000	1,600	NA	180	19	170	200	ND	ND	-13	
	04/91	4,200	410 *	NA	520	130	410	580	ND	, ND	26	
	07/91	1,900	180	NA	190	12	52	77	ND	6.5	12	
	10/ <del>9</del> 1	880	300	NA	160	31	44	83	ND	ND	10	
	01/92	380	120	NA	14	7.6	2.2	14	ND	ND	9.6	
	04/92	2,900	700 *	NA	510	08	260	260	ND	ND	11	
	07/92	4,400	1,300 *	NA	860	210	340	640	ND	ND	22	
	10/92	200	290 ª	NA	6.8	1.4	2.1	7.8	ND	ND	12	
	01/93	8,500	740 *	NA	2,400	390	620	1,500	ND	ND	29	
	06/93	8,200	1,300	ND	2,400	360	480	1,500	ND	NĐ	29	
MW10	01/92	13,000	3,700	NA	130	580	110	3,000	ND	ND	33	
	05/92	15,000	5,000	NA	180	ND	18	2,700	ND	ND	20	
	05/92 (dup)	13,000	7,500	NA	240	490	65	2,500	ND	ND	22	
•	07/92	8,100	4,400	-NA	74	360	ND	1,100	ND	ND	29	
	10/92	3,200	1,500 2	NA	ND	NĎ	ND	320	ND	ND	25	٠ <u>٠</u>
	01/93	7,500	2,200 ª	NA	130	170	·20	710	ND	ND	18	:
	06/93	8,000	2,100	МD	69	7.9	ND	490	ND	ND	16	

Table 2
Summary of Historical Groundwater Analytical Data

Harbert Transportation/Meekland Avenue

Hayward, California



						EPA Test Met	iod <b>s</b>					
			8015 Modifie	d		8020				8010		
	□ate	TPH-G	трн-О	TPH-MO	Benzene	Ethylbenzene	Toluene	Total Xylenes	TCE	PGE	1,2-DCA	Other
Well	Sampled		μg/L			μg/L				µg/L	1,8 11 17	Hg/L
MW11	01/92	8,200	3,200 *	NA	23	250	ND	1,100	ND	ND	ND	
	04/92	160	1,200 *	NA	ND	ND	NĐ	ND	ND	ND	ND	
	07/92	2,100	710 *	NA	39	100	2,3	53	ND	ND	ND	
	10/92	660	220 *	NA	2.9	19	ND	3.8	ND	ND	ND	
	10/92	770	230	NA	3.2	26	ND	5.7	ND	ND	ND	
	01/93	780	370 ª	NA	10	2.1	ND	39	ND	ND	ND	
	06/93	2,500	160 <sup>a</sup>	ND	27	99	ND	34	ND	ND	ND	
MW12	12/92	2,800	1,700	NA	14	ND	ND	ND	ND	ND	ND	
	06/93	1,100	750 *	ND	19	21	ND	57	ND	ND	ND	
B1	01/93	ND	ND	NA	ND	ND	ND	ND	ND	ND	ND	·····
	06/93	ND	ND	ND	ND	ND	ND	ДИ	, ND	ND	ND	
F3	02/93	NA	NA NA	NA	NA	NA	NA	NA	NA	, NA	NA	
Well Abandoned	12/89	1,800	NA	NA	200	24	18	34	ND	ND	0.15	Lead 2,100
Average b		8,865	1,883	250	1,562	235	517	871	0.21	0.41	24.8	
Laboratory ( Limit	Detection	50	50	500	0.5	0.5	0.5	0.5	0.4	0.4	0 4	

#### Notes:

- a) The detection for petroleum hydrocarbons as diesel appears to be due to the presence of lighter hydrocarbons rather than diesel.
- b) Average of sampled data, ND equals 1/2 detection limit.

μg/L - Micrograms per liter is approximately equivalent to parts per billion, depending on density of water.

NA - Not analyzed.

ND - Not detected.

TPH-G - Total petroleum hydrocarbons quantified as gasoline.

TPH-D - Total petroleum hydrocarbons quantified as diesel.

TPH-MO - Total petroleum hydrocarbons quantified as motor oil.

TCE - Trichloroethylene.

PCE - Tetrachloroethylene.

1,2-DCA - 1,2-Dichloroethane.

٠.,.`



Table 2
Summary of Groundwater Chemical Analyses
Harbert Transportation/Meekland Avenue
Hayward, California

					EPA 1	est Metho	ids.				
		8015	М		BETX 5030	/8020		8010			
	Date	TPH Gasoline	TPH Diesel	Benzene	Ethylbenzene	Toluene	Kylenes	1,2-DCA	PCE	TCE	
Well	Sampled	µg/L	µg/L		µg/L			µg/L	µg/L	µg/L	
мWз	07/28/94	7,700	970 ª	1,800	810	ND	600	22	ND	ND	
	10/21/94	7,400	810	1,900	900	37	780	25	ND ND	ND ND	
	09/15/95	NS	NS	NS	NS	NS	NS	NS	NS NS	NS	
	03/14/96	NS	NS	NS	NS	NS	NS	NS	NS	NS	
	09/26/96	NS	NS	NS	NS	NS	NS	NS	NS	NS	
MW4	07/28/94	120	ND	7.9	0.7	1.1	ND	ND	ND	ND	
	10/21/94	69	ND	3.4	ND	ND	ND	ND	ND ·	ND	
	09/15/95	110	ND	2.5	ND	0.85	ND	2.3	ND	ND	
	03/14/96	300	69 b	3.3	0.74	ND	ND	- 1.6	ND	ND	
	09/26/96	ND	ND	ND	ND	ND	ND	1.2	, ND	ND	
MW5	07/29/94	30,000	2,200	9,300	1,100	1,800	2,300	110	ND	ND	
	10/21/94	23,000	1,500	7,900	780	1,500	2,900	85	ND	ND	
	09/15/95	NS	NS	เหล	NS	NS	้หร	NS	พร	NS	
	03/14/96	NS	NS	NS	NS	NS	NS	NS	NS	NS	
	09/26/96	NS	NS	NS	Ns	NS	NS	NS	NS	NS	
MW6	07/29/94	15,000	2,100 b	3,100	1,100	71	2,000	37	ND	ND	
	10/21/94	18,000	1,500	3,900	1,200	170	3,200	35	ND	ND	
	09/15/95	NS	เหล	NS	NS	NS	ัทธ	NS	พร	ИВ	
	03/14/96	NS	NS	NS	NS	NS	NS	NS	NS	ИВ	
	09/26/96	พร	NS	NS	NS	NS	NS	NS	NS	NS	
MW7	07/29/94	2,600	530 <sup>c</sup>	470	220	ND	310	2.7	6	ND	
	10/21/94	1,700	280	290	140	4.5	240	1.8	0.74	ND	
[	09/15/95	NS	NS	NS	NS	NS	. NS	NS	NS	NS	
	03/14/96	NS	NS	NS	NS	NS	NS	NS	NS	NS	
	09/26/96	NS	NS	NS	NS	NS	NS	NS	NS	NS	



Table 2
Summary of Groundwater Chemical Analyses
Harbert Transportation/Meekland Avenue
Hayward, California

					EPAT	est Metho	da			
		8015	M		BETX 6030.	/8020			8010	
	Date	TPH Gasoline	TPH Diesel	Benzene	Ethylbenzene	Toluene	Xvienes	1,2-DCA	PCE	TGE
Well	Sampled	pg/L	µg/L		µg/L			µg/L	µg/L	µg/L
MW8	07/28/94	™ ND	78 ª	ND	ND	ND	ND	ND	ND	ND
	10/21/94	ND	ND	ND	ND	ND	ND	ND	0.72	ND
	09/15/95	ND	ND	ND	ND	ND	ND	ND	0.74	ND
	03/14/96	ND	ND	ND	ND	ND	ND	ND	0.63	ND
	09/26/96	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW9	07/28/94	6,000	1,300 6	90	170	27	370	26	ND	ND
	10/21/94	6,900	600	1,800	280	220	1,500	31	ND	ND
	09/15/95	NS	NS	NS	NS	NS	NS	NS	NS	NS ·
	03/14/96	NŞ	NS	NS ·	NS	NS	NS	: NS	เล	NS
	09/26/96	NS	NS	หร	NS	NS	NS	NS	NS	NS
MW10	07/28/94	6,700	2,000 6	99	180	57	430	13	ND	ND
	10/21/94	8,600	2,000	93	200	ND	680	12	ND	ND
	09/15/95	2,100	1,900	9.9	49	ND	4.9	ND	ND	ND
	03/14/96	6,800	2,000 b	64	` 98	ND	33	6.5	ND	ND
	09/26/96	7,100	420	140	210	ND	32	9.1	ND	5.9
MW11	07/28/94	450	150 a	6.2	20	1.1	6.6	ND	ND	ND
	10/21/94	460	190	4.9	14	ND	12	ND	ND	ND
	09/15/95	9,600	550	130	180	ND	130	8.8	ND	5.6
	03/15/96	780	310 b	0.74	25	ND	1.8	ND	ND	ND
	09/26/96	480	710	ND	50	ND	ND	ND	ND	ND



Table 2
Summary of Groundwater Chemical Analyses
Harbert Transportation/Meekland Avenue
Hayward, California

		8015	M		EPA 1 BETX 5030	est Metho /8020	ds		8010	
Well	Date Sampled	TPH Gasoline µg/L	TPH Diesel ug/L	Benzene E	ithylbenzene pg/L		Xylenes	1,2:DGA ug/L	PGE ug/L	TCE
MW12	07/28/94 10/21/94 09/15/95 03/14/96	240 260 NS NS	160 190 NS NS	1.9 1.9 NS NS	12 4.5 NS NS	ND ND NS NS	5.8 6.8 NS NS	ND ND NS NS	ND ND NS NS	ND ND NS NS
	09/26/96	NS	NS	NS	NS	INO	NS	NS	NS	NS

#### Notes:

- a) Hydrocarbons quantified as diesel are primarily due to discrete peaks not indicative of diesel fuel.
- b) Hydrocarbons quantified as diesel are primarily due to the presence of a lighter petroleum product (C<sub>8</sub>-C<sub>12</sub>), possibly gasoline.
- c) Hydrocarbons quantified as diesel are due to the presence of a lighter petroleum product (C<sub>6</sub>-C<sub>12</sub>) and discrete peaks not indicative of diesel fuel. 1,2-DCE 1,2-dichloroethane.

PCE - Tetrachloroethene.

TCE - Trichloroethene.

ND - Not detected at or above method detection limit.

NS - Not sampled.

TPH-Gasoline - Total petroleum hydrocarbons quantified as gasoline.

TPH-Diesel - Total petroleum hydrocarbons quantified as diesel.

µg/L - Micrograms per liter, equivalent to parts per billion.

