



**ENVIRONMENTAL AND GENERAL ENGINEERING**

Llc #371497

Underground Fuel Tank Management  
Exploratory Drilling & Monitoring Wells  
Hazardous Waste Site Assessments  
Bioremediation  
Remedial Design  
Vapor Extraction Systems

Analytical Testing  
Hydrogeologic Testing  
Asbestos Surveys  
Environmental Audits  
Regulatory Permitting  
Soil Gas Investigations

September 16, 1993

Durham Transportation, Inc.  
9171 Capitol of Texas Highway North  
Travis Building, Suite 200  
Austin, Texas 78759  
Attention: Mr. David Delamotte

**SUBJECT: RESPONSE TO THE REQUEST FOR PROPOSAL DATED  
AUGUST 20, 1993.**

Dear Mr. Delamotte:

Excel Environmental and General Engineering (EEGE) is pleased to respond to the Request for Proposal (RFP) dated August 20, 1993 for the remediation of the Durham Transportation, Inc. (DTI) located at 19984 Meekland Avenue Hayward, California. The remediation of the site shall be divided into two phases, that could be addressed at the same time or separately. Based on the information provided to EEGE by DTI a comparison chart was developed to compare the remediation methods that may be feasible for the type of contamination and the physical state of the site (please see Comparisons Charts 1 & 2). Based on the comparison charts the following approaches were listed as possible remediation methods for the site:

## REMEDATION OPTIONS

### PHASE I: POSSIBLE SOIL REMEDIATION OPTIONS

A. OFF-SITE INCINERATION: Currently there are no permitted off-site incinerators located in Northern California, but REMCO is expected to be approved some time in late 1993. If REMCO isn't permitted, the material can be transported to the TPS facility in southern California for treatment at an additional cost for the transportation. This method is therefore recommended only if REMCO obtains the required permits to operate.

B. VAPOR EXTRACTION: Vapor Extraction Systems (VES) have been proven to be successful in the treatment of gasoline contaminated soils. The success of the system is dependent upon several properties of the impacted soils such as the soil porosity, soil density, and water content. If the soil porosity is low, such as clay the success of the VES method is moderate to poor. This site is composed of clay type soils and thus the VES approach is not recommended.

C. OFF-SITE RECYCLING: Currently there are two facilities located in the northern California area that will accept the soil to be excavated. The REMCO facility is the most cost effective of the in terms of transportation cost and disposal costs and thus is used to provide DTI with a cost estimate.

### PHASE II: PROPOSED GROUND WATER TREATMENT OPTIONS

A. CARBON TREATMENT WITH SEWER DISPOSAL: The ground water will be pumped from the subsurface from two existing ground water monitoring wells and one additional well to be installed, through a series of activated carbon canisters. The treated water will then be stored in a 10,000 gallon poly tank prior to discharge into the sewer system. Prior to discharge the water in the poly tank will be tested as requested by the Oro Loma Sanitary District. The carbon canisters will be required

to be removed from the site and reactivated or larger carbon tanks can be utilized at a greater initial costs but less cost for the regeneration.

**B. AIR STRIPPING WITH EFFLUENT DISCHARGE FLOW THROUGH ACTIVATED CARBON AND TREATED WATER DISCHARGE INTO THE SEWER SYSTEM:** This system evolves the pumping of the ground water through existing on-site wells and one additional well to be installed. The pumped water will then flow through a low profile air stripper with the effluent air stream treated by activated carbon. The treated ground water will flow through a series of carbon canisters to polish the removal of the contaminates. The treated ground water will then be stored in a 10,000 gallon poly tank prior to disposal into the sewer system. The carbon for both phases of treatment will require regeneration at periodic intervals of break through.

**COST ESTIMATES**

**PHASE I: POSSIBLE SOIL REMEDIATION OPTIONS**

**OPTION I: OFF-SITE INCINERATION**

|                                | CAPITAL COSTS<br>(\$) | INITIAL OUTLAY<br>(\$) | OPERATING<br>\$/YEAR |
|--------------------------------|-----------------------|------------------------|----------------------|
| Soil Excavation<br>and Loading |                       | 4,225                  |                      |
| Clean Import Fill              |                       | 8,350                  |                      |
| Bacfilling<br>Equipment/Labor  |                       | 4,600                  |                      |
| Laboratory Fees                |                       | 5,600                  |                      |
| Transportation<br>Costs(Local) |                       | 9,000                  |                      |
| Disposal Costs<br>(750 Tons)   |                       | 43,200                 |                      |
| <b>TOTAL</b>                   |                       | <b>\$74,975</b>        |                      |

**OPTION II: OFF-SITE RECYCLING**

|                                 | CAPITAL COSTS<br>(\$) | INITIAL OUTLAY<br>(\$) | OPERATING<br>\$/YEAR |
|---------------------------------|-----------------------|------------------------|----------------------|
| Soil Excavation<br>and Loading  |                       | 4,225                  |                      |
| Claen Import Fill               |                       | 8,350                  |                      |
| Clean Fill Import               |                       | 4,600                  |                      |
| Laboratory Fees                 |                       | 5,600                  |                      |
| Transportation<br>Costs (Local) |                       | 9,000                  |                      |
| Disposal Costs<br>(750 Tons)    |                       | 43,200                 |                      |
| <b>TOTAL</b>                    |                       | <b>\$74,975</b>        |                      |

**PHASE II: POSSIBLE GROUND WATER REMEDIATION OPTIONS**

**OPTION I: ACTIVATED CARBON TREATMENT WITH SEWER DISPOSAL**

|   | CAPITAL COSTS<br>(\$) | INITIAL OUTLAY<br>(\$) | OPERATING<br>\$/YEAR |
|---|-----------------------|------------------------|----------------------|
| Air Permits                               |                       | 1,500                  |                      |
| Carbon                                    |                       | 3,500                  | 9,950                |
| Disposal Costs*                           |                       |                        | 10,200               |
| Estimated Capital<br>Costs for<br>Pumping | 15,650                |                        |                      |
| Estimated Site<br>Preparation             |                       | 18,600                 |                      |
| Estimated Annual<br>Operating Costs       |                       |                        | 5,750                |
| Consultant Fees                           |                       |                        | 43,000               |
| Laboratory Fees                           |                       |                        | 20,000               |
| <b>Subtotal</b>                           | <b>15,650</b>         | <b>23,600</b>          | <b>88,895</b>        |
| <b>Total</b>                              |                       |                        | <b>\$128,145</b>     |

**OPTION II: AIR STRIPPING WITH DISCHARGE THROUGH ACTIVATED  
CARBON TREATMENT AND SEWER DISPOSAL**

|   | CAPITAL COSTS<br>(\$) | INITIAL OUTLAY<br>(\$) | OPERATING<br>\$/YEAR |
|---|-----------------------|------------------------|----------------------|
| Stripping Tower                           | 6,400                 |                        |                      |
| Air Permits                               |                       | 1,500                  |                      |
| Carbon                                    |                       | 3,500                  | 9,945                |
| Disposal Costs*                           |                       |                        | 10,200               |
| Estimated Capital<br>Costs for<br>Pumping | 15,650                |                        |                      |
| Estimated Site<br>Preparation             |                       | 18,600                 |                      |
| Estimated Annual<br>Operating Costs       |                       |                        | 5,750                |
| Consultant Fees                           |                       |                        | 43,000               |
| Laboratory Fees                           |                       |                        | 20,000               |
| <b>Subtotal</b>                           | <b>22,050</b>         | <b>23,600</b>          | <b>88,895</b>        |
| <b>Total</b>                              |                       |                        | <b>134,545</b>       |


**RECOMMENDATIONS**

EEGE recommends that DTI proceed with the remediation of the SITE by implementation of Option I for the both the soil and ground water contamination.

Should you require any further assistance, please call me at (310) 529-2511.

Sincerely,

Excel Environmental and General Engineering

  
Klaus P. Wojak, R.E.H.S./R.E.A.  
KPW/tw  
B0993056

## COMPARISON CHART 1: GROUND WATER REMEDIATION OPTIONS

|                                       | Carbon Treatment with Storm Drain Discharge | Carbon Treatment with Sewer Discharge | IV treatment with Storm Drain Discharge | Air Stripping with Sewer Discharge | Air Stripping with Storm Drain Discharge | Air Stripping with Carbon and Sewer Discharge | Air Stripping with Carbon and Storm Drain Discharge |
|---------------------------------------|---|---------------------------------------|---|------------------------------------|--|---|---|
| Permitting                            | HIGH  | HIGH                                  | HIGH                                    | LOW                                | LOW                                      | HIGH  | HIGH  |
| Approval                              | HIGH  | HIGH                                  | HIGH                                    | LOW                                | LOW                                      | HIGH  | HIGH  |
| Initial Costs                         | MODERATE                                    | MODERATE                              | HIGH                                    | HIGH                               | HIGH                                     | HIGH  | HIGH  |
| Recurring Costs                       | MODERATE                                    | MODERATE                              | MODERATE                                | MODERATE                           | MODERATE                                 | HIGH  | HIGH  |
| Laboratory Costs                      | MODERATE                                    | MODERATE                              | MODERATE                                | MODERATE                           | MODERATE                                 | MODERATE                                      | MODERATE  |
| Disposal Costs                        | MODERATE                                    | MODERATE                              | LOW                                     | LOW                                | LOW                                      | MODERATE                                      | MODERATE  |
| Sampling and Reporting Costs          | LOW   | LOW                                   | LOW                                     | LOW                                | LOW                                      | LOW   | LOW   |
| Annual Costs                          | MODERATE                                    | MODERATE                              | LOW                                     | LOW                                | LOW                                      | MODERATE                                      | MODERATE  |
| Feasibility of Method on this Project | LOW   | HIGH                                  | LOW                                     | LOW                                | LOW                                      | HIGH  | LOW   |

DURHAM TRANSPORTATION, INC. MEEKLAND SITE

## COMPARISON CHART 2: SOIL REMEDIATION OPTIONS

|                                       | Excavation and Class 1 Disposal | Excavation and Off-Site Incineration | Excavation and On-Site Incineration | Excavation and On-Site Chemical Fixation | Vapor Extraction | Excavation and Aeration | Excavation and Off-Site Recycling |
|---------------------------------------|---------------------------------|--------------------------------------|-------------------------------------|--|------------------|-------------------------|-----------------------------------|
| Soil Type "Clay"                      | HIGH                            | MODERATE                             | LOW                                 | LOW                                      | LOW              | MODERATE                | HIGH                              |
| Permitting                            | HIGH                            | HIGH                                 | LOW                                 | LOW                                      | LOW              | LOW                     | HIGH                              |
| Approval                              | HIGH                            | HIGH                                 | LOW                                 | LOW                                      | LOW              | LOW                     | HIGH                              |
| Initial Costs                         | LOW                             | LOW                                  | HIGH                                | HIGH                                     | HIGH             | HIGH                    | HIGH                              |
| Recurring Costs                       | COULD BE HIGH                   | LOW                                  | LOW                                 | COULD BE HIGH                            | LOW              | LOW                     | LOW                               |
| Laboratory Costs                      | MODERATE                        | MODERATE                             | MODERATE                            | HIGH                                     | HIGH             | HIGH                    | LOW                               |
| Disposal Costs                        | HIGH                            | MODERATE                             | LOW                                 | LOW                                      | MODERATE         | LOW                     | LOW                               |
| Sampling and Reporting Costs          | LOW                             | LOW                                  | LOW                                 | LOW                                      | LOW              | LOW                     | LOW                               |
| Annual Costs                          | NOT APPLICABLE                  | NOT APPLICABLE                       | NOT APPLICABLE                      | LOW                                      | LOW              | NOT APPLICABLE          | NOT APPLICABLE                    |
| Feasibility of Method on this Project | LOW                             | HIGH                                 | LOW                                 | LOW                                      | LOW              | LOW                     | HIGH                              |

### DURHAM TRANSPORTATION, INC. MEEKLAND SITE

### PAYMENT SCHEDULE

Excel Environmental and General Engineering (EEGE) will require a retainer of twenty percent (20%) of the contract price at the time of acceptance of this proposal, and prior to EEGE beginning work on the project. The remaining eighty percent of the contract will be billed upon completion of each phase or on a monthly bases. Upon the completion the remaining amount of the contract price including any additional costs will be due prior to submittal of the Final Closure Report.

### ACCEPTANCE

The undersigned herewith accepts the terms and conditions of EEGE's proposal dated September 16, 1993. The proposal refers to the job known as 19984 Meekland Avenue, Hayward, California. The contract price for the project will be based on the options chosen by DTI.

The undersigned, by having affixed their signature to this acceptance is stating that they are authorized by Durham Transportation, Inc. to enter into this contract with EEGE. The undersigned herewith gives EEGE the authorization to begin work on this project.

**Contractors are required by law to be licensed and regulated by the Contractors' State License Board. Any questions concerning a contractor may be referred to the Registrar, Contractors State License Board, P.O. Box 26000, Sacramento,**

Signed \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_