Orien Environmental **Associates** 

315 Washington St. Oakland, CA 94607 Tel (510) 763-1355 FAX (510) 452-9280



3315 Almaden Expressway, Suite 34 San Jose, CA 95118

Phone: (408) 264-7723 FAX: (408) 264-2435

Michele A. Bellows, P.E. Senior Associate

ADDITIONAL SUBSURFACE INVESTIGATION

> at ARCO Station 6148 5131 Shattuck Avenue Oakland, California

61035.05 01/21/93 Report prepared for

ARCO Products Company P.O. Box 5811 San Mateo, California 94402

by

RESNA Industries Inc.

Robert D. Campbell Staff Geologist

Joel Coffman

Project Geologist

GEOLOGY

JAMES LEWIS

NELSON

No. /1463 CERTHEIED

垃

ENGINEERING

OF CAUFOR GEOLOGIST

James L. Nelson

Certified Engineering Geologist 1463

January 27, 1993

#### Alameda County Department of Environmental Health Hazardous Materials Division

80 Swan Way, Rm. 200, Oakland, CA 94621 Ph: 510-271-4320

#### **BILLING FOR SERVICES**

StID# A. Site Name Site Address (If no address, Number description of area) Prior Business Name Prior Owner's Name.... PHONE - (510) 463-135. Service Requestor MICHELE BELLOWS-ORION 94609 5131 5500

You will receive an invoice in accordance with Article 11 of Chapter 6, Title 3 of the Ordinance Code	of Alameda Coun	Ý
<u>,, ,, ,, ,, ,, ,, ,, ,, ,, ,, ,, ,, ,, </u>		

Service Requestor	MICHELE B	ELLOWS	moule 6	Belling Date	0-26-93
HazMat Specialist	SUSAN L	HUGD	signature  Sustanture	Lity Date.	10/26/93
HM Bill for Svcs 4/92 mk	COPIES:	White: - Billing	Yellow - Office	Pink + Svc. Trèquestat	



3315 Almaden Expressway, Suite 34

San Jose, CA 95118 Phone: (408) 264-7723 FAX: (408) 264-2435

### TRANSMITTAL

TO: Ms. Susan Hugo Alameda County Health Care Services 80 Swan Way, Room 200 Oakland, California 94621 DATE: January 27, 1993
PROJECT-NUMBER: 61035.05
SUBJECT: Final - Additional Subsurface
Investigation at ARCO Station 6148, 5131
Shattuck Ave., Oakland, California.

FROM: Robert Campbell TITLE: Staff Geologist

WE ARE SENDING YOU:

COPIES	DATED	DESCRIPTION
1	1/27/93	Final - Additional Subsurface Investigation at the above subject site.
THESE A	RE TRANSMIT	TED as checked below:
[X] For	review and com	ment [] Approved as submitted [] Resubmit copies for approval
[X] As	requested	[] Approved as noted [] Submit_ copies for distribution
[] For	approval	[] Return for corrections [] Return corrected prints
[] For	your files	
REMAR	Mr. 1 Mr. 1	H.C. Winsor, ARCO Products Company Michael Whelan, ARCO Products Company Richard Hiett, RWQCB, San Francisco Bay Region Toel Coffman, RESNA Industries Inc.

Copies: 1 to RESNA project file no. 61035.05



#### **CONTENTS**

INTRODUCTION	
SITE DESCRIPTION AND BACKGROUND	
General	
Regional and Local Hydrogeology	2
WELL RESEARCH	
PRELIMINARY RECORDS RESEARCH	
PREVIOUS WORK	5
FIELD WORK	5
Drilling	5
Soil Sampling and Description	
Monitoring Well Construction and Development	
Groundwater Level Measurement and Sampling	6
Wellhead Survey	
LABORATORY METHODS	
Soil Samples	7
Stockpile Soil Samples	
Water Samples	8
FIELD WORK RESULTS	9
Drilling	9
Subjective Groundwater Analyses	
Groundwater Gradient	10
RESULTS OF LABORATORY ANALYSES	10
Soil Samples	10
Water Samples	11
DISCUSSION OF RESULTS	11
Hydrocarbon Impacted Soil	
Hydrocarbon Impacted Groundwater	12
CONCLUSIONS	12
LIMITATIONS	
DISTRIBUTION	
REFERENCES	



## CONTENTS (Continued)

#### **PLATES**

PLATE 1: SITE VICINITY MAP

PLATE 2: GENERALIZED SITE PLAN

PLATE 3: WELL LOCATION MAP

PLATE 4: UNIFIED SOIL CLASSIFICATION SYSTEM AND SYMBOL KEY

PLATES 5

through 12: LOGS OF BORINGS B-5/MW-4 THROUGH B-8/MW-7

PLATE 13: GEOLOGIC CROSS SECTION C-C'

PLATE 14: GEOLOGIC CROSS SECTION D-D'

PLATE 15: GEOLOGIC CROSS SECTION E-E'

PLATE 16: GROUNDWATER GRADIENT MAP, NOVEMBER 12, 1992

PLATE 17: GROUNDWATER GRADIENT MAP, DECEMBER 9, 1992

PLATE 18: PARTICLE SIZE DISTRIBUTION GRAPH

PLATE 19: CONCENTRATIONS OF TPHg/BENZENE IN GROUNDWATER

#### **TABLES**

TABLE 1: WELL SURVEY DATA

TABLE 2: CUMULATIVE GROUNDWATER MONITORING DATA

TABLE 3: RESULTS OF LABORATORY ANALYSES OF SOIL SAMPLES

TABLE 4: RESULTS OF LABORATORY ANALYSES OF WATER SAMPLES

#### **APPENDICES**

APPENDIX A: VISTA DATABASE SEARCH RESULTS

APPENDIX B: PREVIOUS WORK

PLATE 1B: GENERALIZED SITE PLAN

PLATE 2B: GEOLOGIC CROSS SECTIONS A-A' AND B-B'

TABLE B-1: RESULTS OF LABORATORY ANALYSES OF SOIL

**SAMPLES** 

TABLE B-2: CUMULATIVE RESULTS OF LABORATORY

ANALYSES OF WATER SAMPLES

APPENDIX C: FIELD METHODS

APPENDIX D: WELL CONSTRUCTION PERMIT

APPENDIX E: WELLHEAD SURVEY

APPENDIX F: WASTE MANIFEST FORMS

APPENDIX G: LABORATORY ANALYSES REPORTS AND CHAIN OF CUSTODY

RECORDS



# ADDITIONAL SUBSURFACE INVESTIGATION at ARCO Station 6148 5131 Shattuck Avenue Oakland, California

For ARCO Products Company

#### INTRODUCTION

At the request of ARCO Products Company (ARCO), RESNA Industries Inc. (RESNA) performed an additional subsurface investigation at ARCO Station 6148, located at 5131 Shattuck Avenue in Oakland, California. This investigation was initiated in response to the results of previous investigations conducted at the site. The purpose of this investigation was to further investigate the lateral and vertical extents of gasoline hydrocarbons in the subsurface soil and groundwater and to monitor the gradient of the first encountered groundwater beneath the site.

The work performed for this investigation included performing research to identify and locate water supply and monitoring wells within a ½-mile radius of the site, performing a records research to identify potential secondary sources for hydrocarbons detected in soil and groundwater at the site, drilling four soil borings, collecting and describing soil samples from the borings (B-5 through B-8), installing four 4-inch diameter groundwater monitoring wells (MW-4 through MW-7) in the borings, measuring groundwater levels, sampling groundwater from the monitoring wells, directing laboratory analysis of selected soil and groundwater samples, surveying wellhead elevations, and preparing this report which presents field procedures, results and conclusions. This work was performed as outlined in the RESNA Work Plan (RESNA, September 29, 1992).



January 27, 1993 61035.05

#### SITE DESCRIPTION AND BACKGROUND

#### <u>General</u>

The site is an operating gasoline station located on the southwestern corner of the intersection of 52nd Street and Shattuck Avenue in Oakland, California. The site location is shown on the Site Vicinity Map (Plate 1). The site is on a relatively flat lot at an elevation of approximately 110 feet above mean sea level.

Presently, according to information provided by ARCO, there are three 12,000 gallon underground gasoline-storage tanks (USTs) located in the western portion of the site. The locations of the USTs and pertinent site features are shown on the Generalized Site Plan (Plate 2).

#### Regional and Local Hydrogeology

ARCO Station 6148 is located west of the East Bay Hills. This area lies within the Berkeley Alluvial Plain, which is a subarea of the East Bay Alluvial Plain. Soils in this area are mapped as older alluvium which consist of a heterogeneous mixture of poorly consolidated to unconsolidated clay, silt, sand, and gravel units (Helley and others, 1979). The sediments were derived mainly from bedrock underlying the hills and represent successive coalescing alluvial fans deposited during the Pleistocene epoch.

The sediments found beneath the East Bay Alluvial Plain are believed to be about 200 feet thick in the Berkeley area. Water-yielding capabilities of the sediments are highly variable. Generally, high yields come only from wells that are screened through several water-bearing sand and gravel beds. Groundwater in the East Bay Plain occurs predominantly under confined conditions and tends to flow toward the San Francisco Bay to the west and southwest (Hickenbottom and Muir, 1988).



January 27, 1993 61035.05

#### WELL RESEARCH

Information regarding wells in the vicinity of the site was provided to RESNA by Andreas Godfry of County of Alameda Public Works Agency (CAPWA).

The research was performed for the area located within ½-mile radius of the site in order to evaluate groundwater usage in the vicinity of the site. The CAPWA records indicate that 19 wells are located within ½-mile of the site; six cathodic protection wells, seven monitoring wells, two piezometric wells, one industrial well, one geotechnical well, one abandoned well, and one domestic well. Well survey data is shown on Table 1 and locations of wells located within ½-mile radius of the site are shown on Plate 3, Well Location Map.

Four of the cathodic protection wells (D1, D2, L2, and N2) belong to East Bay Municipal Utility District (EBMUD) and are approximately 50 feet deep. The other two cathodic protection wells (D3 and M2) belong to Pacific Gas and Electric (PG&E) and are 120 feet deep. These cathodic protection wells are located 1/4- to 1/2-mile northeast and southeast of the site.

Three of the monitoring wells (M3 through M5) belong to Chevron USA Inc., and are approximately 30 feet deep, with depth to water levels (DTW) at approximately 13 feet. These wells are located approximately ¼-mile northeast of the site. Two monitoring wells (R2 and R3) belong to Pacific Rim Development and are located ¼-mile southeast of the site. Monitoring wells R2 and R3 are approximately 31 and 35 feet deep and DTW at approximately 17 feet. One of the monitoring wells (G8) belongs to the City Of Oakland and is located approximately ¼-mile to the east of the site. This well is approximately 33 feet deep with DTW at approximately 18 feet. Monitoring well (A1) belongs to Wayne Kelly Auto Parts and is located approximately ½-mile to the south of the site. Monitoring well A1 is approximately 35 feet deep with DTW at approximately 14 feet.

Two piezometric wells (G6 and G7) belong to the City of Oakland and are located ¼-mile to the east of the site. Wells (G6 and G7) are approximately 28 feet deep with DTW at approximately 18 and 23 feet, respectively.



January 27, 1993 61035.05

The one industrial well (J1) belongs to Marshall Steel Company and is located approximately ¼-mile north of the site. This well is approximately 40 feet deep. The one abandoned well (N1) belongs to Mrs. H. Gotelli and is located approximately ¼-mile to the east of the site. This former well was approximately 85 feet deep with DTW at approximately 9 feet. The one geotechnical well (R1) belongs to the Children's Hospital and is located approximately ¼-mile to the west of the site. This well is approximately 150 feet deep. The one domestic well (M1) belongs to Angela Delucchi and is located approximately ½-mile to the northeast of the site. Domestic well M1 is approximately 75 feet deep with DTW at approximately 5 feet.

#### PRELIMINARY RECORDS RESEARCH

A preliminary records research was conducted to locate possible secondary sources for hydrocarbons detected in the soil and groundwater within ½-mile radius on the site using aerial photographs and data obtained from Vista Environmental Information, Inc. (VISTA) of San Diego, California and Report on Releases of Hazardous Substances from Underground Storage Tanks (State Water Resources Control Board, January 1992). Aerial photographs taken in 1950, 1969, and in 1988 did not indicate the presence of other gasoline service stations immediately adjacent to the site. Before 1950, the subject site appears to have been a community park or vacant lot. During 1969, the subject site appears to have been occupied by a commercial building. The site appears to have been developed as a service station sometime between 1969 and 1988. The VISTA records search report and map showing known environmental risk sites within a 1-mile radius of the site is attached in Appendix A. The VISTA database search report indicates that nine leaking underground storage tank (LUST) facilities are situated within a ½-mile radius upgradient, crossgradient, and downgradient from the subject site. The closest potential secondary sources to the subject site include, AUTOPRO (designated as site 25) located at 5200 Telegraph Avenue in Oakland, California; two Chevron Service Stations (sites 23 and 26) located at 5101 and 5500 Telegraph Avenue in Oakland, California; Kelly Auto Parts (site 28) located at 4400 Telegraph Avenue in Oakland, California; BP Oil Service Station (former Mobile Station) located at 5425 Martin Luther King Avenue in Oakland, California (site 37); and Chevron Service Station (site 38) located at 5509 Martin Luther King in Oakland, California, which reportedly has two leaks at this address. According to the Report on Releases of Hazardous



January 27, 1993 61035.05

Substances from Underground Storage Tanks, all the above referenced sites are reported to have unauthorized releases of hydrocarbons into the soil and groundwater.

#### PREVIOUS WORK

Previous subsurface environmental investigations performed at the site are summarized in Appendix B, Previous Work.

#### FIELD WORK

#### **Drilling**

Field work at the site was conducted in accordance with the field protocol and the Site Safety Plan (RESNA, October 26, 1992). A description of the field methods is included in Appendix C, Field Methods. A well construction permit was acquired from the Alameda County Flood Control and Water Conservation District, Zone 7 (ACFCWCD) prior to drilling at the site. A copy of the permit is included in Appendix D, Well Construction Permit. On October 27 and 28, 1992, four soil borings (B-5 through B-8) were drilled using a Mobile Drill B-61 rig with 10.25 diameter hollow-stem augers and four groundwater wells (MW-4 through MW-7) were constructed in the borings to further evaluate the presence and extent of gasoline hydrocarbons in soil and groundwater beneath the site. Soil boring B-5 was drilled southeast (crossgradient) of the USTs, soil boring B-6 was drilled southwest (downgradient) of the existing USTs, soil boring B-7 was drilled north (upgradient) of the existing USTs. The locations of the borings/wells are indicated on Plate 2.

#### Soil Sampling and Description

A total of 45 soil samples were collected from the soil borings B-5 through B-8 for description and possible laboratory analysis. A summary of the Unified Soil Classification System used to identify the soil encountered during drilling is presented on Plate 4, and the description of the soil encountered in the borings is presented on the Logs of Borings, Plates 5 through 12. Soil samples from the borings B-5 through B-8 were collected at intervals of



January 27, 1993 61035.05

5 feet or less from the ground surface to the total depth of the borings. Sampling procedures are described in Appendix C. Field measure of organic vapors were also measured with an organic vapor meter (OVM) which provides a qualitative only field analysis of organic vapor content of soil samples. OVM readings are also shown on the boring logs, Plates 5 through 12 under the column titled P.I.D. (photoionization detector).

#### Monitoring Well Construction and Development

Four groundwater monitoring wells (MW-4 through MW-7) were constructed in borings B-5 through B-8, respectively. Groundwater monitoring wells MW-4 through MW-7 were completed with 4-inch-diameter, Schedule 40, poly vinylchloride (PVC) casing. Well casings were set in wells MW-4 through MW-7 to depths of approximately 26½, 25, 27, and 27 feet, respectively. The screened casings for the monitoring wells consist of 4-inch-diameter, 0.020 inch-wide machine-slotted PVC set from the total depth of the well to approximate depths of 11½, 10, 12, and 12 feet in wells MW-4 through MW-7, respectively. Blank PVC casing was set from the top of the screened casing to within a few inches below the ground surface and secured with 4-inch expandable locking well caps. Each well was covered with highway rated christie box cemented to grade. The monitoring wells were hand-developed by a RESNA field technician using a pneumatic pump on November 6, 1992, to remove fine-grained sediments and allow better communication between the water-bearing zone and the groundwater monitoring well. Details regarding well construction and development are described in Appendix C.

#### Groundwater Level Measurement and Sampling

Monitoring wells MW-1 through MW-7 were monitored on November 12 and December 9, 1992. DTW levels were measured in the groundwater monitoring wells and water samples were collected and visually inspected for floating product. Monitoring well MW-2 and MW-3 contained a sheen on November 12 and December 9, 1992. Groundwater elevations for the wells without floating product were calculated by subtracting the measured depth-to-water from the elevation of the wellhead top of casing. Groundwater monitoring wells MW-4 through MW-7 were purged and sampled on November 12, 1992. Samples were submitted to a State-certified laboratory in accordance with Chain of Custody protocol. Monitoring



January 27, 1993 61035.05

well MW-1 was not sampled on November 12, 1992 because it had previously been sampled by EMCON on October 7, 1992. Monitoring wells MW-2 and MW-3 were not sampled by EMCON on October 7, 1992, due to the presence of floating product (0.31 feet and sheen, respectively). Appendix C contains a description of subjective analyses and groundwater sampling procedures for the November 12, 1992 sampling.

#### Wellhead Survey

On November 9, 1992, the wellheads for the new groundwater monitoring wells were surveyed to a local National Geodetic Vertical Datum benchmark by John E. Koch, a California licensed surveyor. The results of this wellhead survey are included in Appendix E, Wellhead Survey.

#### LABORATORY METHODS

Soil and groundwater samples collected by RESNA field personnel were preserved as required by the applicable analytical method and delivered, with Chain of Custody Records, to Sequoia Analytical Laboratories of Redwood City, California, a State-certified laboratory (Hazardous Waste Testing Laboratory Certification #1210) for soil and water analyses. Water samples collected from MW-1 by EMCON field personnel on October 7, 1992, were preserved as required by the applicable analytical method and delivered with Chain of Custody Records to Columbia Analytical in San Jose, California, a State-certified laboratory (Hazardous Waste Testing Laboratory Certification #1426) for water analyses.

#### Soil Samples

Selected soil samples collected from borings B-5 through B-8 were analyzed in accordance with Alameda County Health Care Services Agency (ACHCSA) requirements for the gasoline constituents benzene, toluene, ethylbenzene, total xylenes (BTEX) and TPHg using modified Environmental Protection Agency (EPA) Methods 5030/8015/8020. Selected soil samples collected from boring B-6 were also tested for particle size distribution by weight to help determine the aquifer characteristics in the first encountered water beneath the site.



January 27, 1993 61035.05

The soil samples were selected for laboratory analysis based on:

- O Location above first-encountered groundwater;
- O Location in a potential confining or perching layer below first-encountered groundwater; and
- O Areas where the presence of gasoline hydrocarbons was suspected.

#### Stockpile Soil Samples

On October 27, 1992, four soil samples (CSS-A through D) were collected from the soil stockpile generated during the drilling of onsite borings B-5 through B-8. These samples were submitted under Chain of Custody Record to Sequoia Analytical, composited in the laboratory, and analyzed for TPHg using EPA Method 8015, Toxicity Characteristic Leaching Procedure (TCLP) for BTEX, and for Soluble Threshold Limit Concentration (STLC) for lead, and reactivity, corrosivity, and ignitability (RCI). The purpose for these analyses was to determine the proper method for disposal of the 4 cubic yards of drill cuttings. The drill cuttings were removed from the site and taken to BFI Landfill in Livermore, California on December 1, 1992. The Waste Manifest Forms are included in Appendix F. The Chain of Custody Record is attached in Appendix G.

#### Water Samples

Monitoring well MW-1 was sampled by EMCON on October 7, 1992, and analyzed for BTEX, TPHg, and total petroleum hydrocarbons as diesel (TPHd) by EPA Method 3510/California DHS LUFT Method, halogenated volatile organic compounds (VOCs) by EPA Methods 5030/601, and total oil and grease by SM 5520 C&F. Monitoring wells MW-4 through MW-7 were sampled by RESNA on November 12, 1992 and analyzed in accordance with ACHCSA requirements for BTEX and TPHg by modified EPA Methods 5030/8015/8020.



January 27, 1993 61035.05

#### FIELD WORK RESULTS

#### **Drilling**

The earth materials encountered at the site consisted primarily of silty clay to clayey sand with gravel and silty sand to sandy gravel. Clayey sand with silt, brick and glass fragments (fill) was encountered immediately below the baserock and pavement and extended to the depths of approximately 5 to 7 feet. Below this fill material, silty clay to silty gravel was encountered between approximate depths of 7 and 15 feet. Below this material a water-bearing silty sand to sandy gravel was encountered between approximate depths of 12 and 30 feet. Groundwater was first encountered within this water-bearing material at an approximate depth of 18 feet and stabilized at depths of approximately 14 and 18 feet. These data are summarized in the logs of borings, Plates 5 through 12. Graphic interpretation of the soil encountered beneath the site during this investigation and previous investigations is shown on the Geologic Cross Sections C-C', D-D', and E-E' (Plates 13 through 15). Interpretation of subsurface conditions encountered during previous investigations at the site are shown on Plate 2B (Geologic Cross Sections A-A' and B-B') included in Appendix B. The areas depicted on the geologic cross sections are shown on Plates 2 and 1B.

Field OVM readings collected during the drilling of borings B-5 through B-8 were nondetectable with exception to samples collected from the capillary fringe section located above the first encountered groundwater beneath the site. Field OVM readings for borings B-5 through B-8 are shown on the boring logs, Plates 5 through 12.

#### **Subjective Groundwater Analyses**

During measurement of DTW levels on October 7, November 12, and December 9, 1992, 0.31 feet of floating product was observed in well MW-2 on October 7, a sheen was observed in well MW-2 on November 12, and 0.02 feet of floating product was observed in well MW-2 on December 9, 1992. After purging well MW-3 on October 7, 1992, 0.02 feet of floating product was observed in well MW-3, while a sheen was observed on November 12 and product droplets were observed in well MW-3 on December 9, 1992. No evidence



January 27, 1993 61035.05

of product was observed in the new wells MW-4 through MW-7 on November 12 and December 9, 1992. Subjective analyses results for the presence of floating product in groundwater are summarized in Table 2, Cumulative Groundwater Monitoring Data.

#### **Groundwater Gradient**

The groundwater gradient and flow direction of first-encountered groundwater at the site, based on DTW levels collected from wells MW-1 and MW-4 through MW-7 in November and December 1992 is inferred to be approximately 0.02 to 0.03 to the southwest. DTW levels and groundwater elevations are summarized in Table 2. Plates 16 and 17, Groundwater Gradient Maps, are graphic interpretations of the groundwater elevations for November 12 and December 9, 1992.

#### RESULTS OF LABORATORY ANALYSES

#### Soil Samples

Analytical results of soil samples collected from borings B-5 through B-8 indicated nondetectable concentrations of TPHg (less than 1.0 ppm) and BTEX (less than 0.0050 ppm) with the following exceptions: 0.13 ppm benzene and 0.0050 ppm total xylenes in the sample collected from boring B-5 at a depth of 14½ feet; 190 ppm TPHg, 0.24 ppm benzene, 0.55 toluene, 1.0 ethylbenzene, and 1.3 total xylenes in the sample collected from boring B-6 at a depth 16½ feet; and 0.025 ppm total xylenes in the sampled collected from boring B-7 at a depth of 29½ feet.

Analytical results of composited stockpile soil samples (CSS-A through D) indicated nondetectable concentrations of TPHg and BTEX, 0.079 ppm lead, greater than 100 degrees centigrade ignitability, non-reactive with respect to cyanide and water, and corrosivity of pH 7.3. The detected lead is within normal background concentrations based on data from Lindsay (1979) and Scott (1991). The results of laboratory analyses of soil samples are summarized in Table 3, Results of Laboratory Analyses of Soil Samples-TPHg, BTEX, Lead, and RCI. Chain of Custody forms and copies of laboratory reports for soil samples are included in Appendix G.



January 27, 1993 61035.05

Results of particle size distribution tests of soil samples collected from the water-bearing unit in boring B-6, at depths of 17½, 19½, 21, and 25 feet indicate a material consisting predominantly of a fine to coarse grained sand with amounts of fines ranging from 2 to 18 percent of total volume. A Particle Size Distribution Graph (Plate 18) graphically depicts grain size versus cumulative percent passing through the various tyler sieves. The soil sample collected at 21 feet contained the greater percentage of fines.

#### Water Samples

The results of laboratory analyses of water samples are summarized in Table 4, Results of Laboratory Analyses of Water Samples and on Plate 19, Concentrations of TPHg/Benzene in Groundwater. Laboratory analytical results for water samples collected from monitoring wells MW-1 and MW-4 through MW-7 indicated TPHg concentrations of 2,900 parts per billion (ppb) in the sample collected from monitoring well MW-5, 590 ppb in the sample collected from MW-5, 77 ppb in the sample collected from well MW-4, 51 ppb in the sample collected from well MW-6, and nondetectable TPHg (less than 50 ppb) in the sample collected from monitoring well MW-7. Monitoring wells MW-2 and MW-3 contained floating product and were not sampled. Benzene was detected in samples collected from the monitoring wells in the following concentrations: 1,300 ppb in well MW-5; 200 ppb in well MW-1; 32 ppb in well MW-4; 2.6 ppb in well MW-6; and 1.8 in well MW-7. Toluene, ethylbenzene, and total xylenes concentrations of samples collected from the monitoring wells are shown on Table 4. Analytical results of water samples collected from well MW-1 indicated nondetectable concentrations of TOG (less than 0.5 ppm), TPHd (less than 50 ppb), and most volatile organic compounds (less than 5 ppb), with the exception of 23 ppb tetrachloroethene (PCE), 1.5 ppb trichloroethene (TCE), and 0.6 ppb chloroform (cf). Chain of Custody records and laboratory analyses reports are included in Appendix G.

#### DISCUSSION OF RESULTS

#### **Hydrocarbon Impacted Soil**

The presently interpreted extent of hydrocarbon impacted soil beneath the site is presented on the Geologic Cross Sections C-C' through E-E', Plates 13 through 15, and on Geologic



January 27, 1993 61035.05

Cross Sections A-A' and B-B', Plate 2B. The majority of gasoline hydrocarbons in the soil at the site were previously detected in borings B-1 through B-4 at approximately 17½ and 18½ feet, and recently in boring B-6 at depths between approximately 16½ and 18½ feet in the silty sand to sandy gravel unit, directly above first-encountered water. The majority of gasoline hydrocarbons in soil appear to be limited to the capillary fringe zone and maybe related to lateral migration of hydrocarbons along the top of water table.

#### Hydrocarbon Impacted Groundwater

Groundwater most impacted by gasoline hydrocarbons appear to be limited to the areas directly down gradient from the USTs and the former waste-oil tank at the site. Wells MW-2 and MW-3, in the immediate vicinity of the former waste-oil tank contained floating product (gasoline) and product sheen (gasoline), respectively. Water analyzed from well MW-1 also indicated concentrations of PCE, TCE, and chloroform. However, the method of analysis used, EPA Method 8010, is a gas chromatograph method. Verification of these compounds should be evaluated by analyzing future groundwater samples using EPA Method 8240, which provides more accurate VOC results.

#### **CONCLUSIONS**

RESNA concludes the following, based on the results of this investigation:

- There are approximately nineteen (19) wells within a ½-mile radius of the site including; six (6) cathodic protection wells, seven (7) monitoring wells, two (2) piezometric wells, one (1) industrial well, one (1) geotechnical well, one (1) domestic well, and one (1) abandoned well.
- A preliminary records research indicated that there were no gasoline-service stations in the immediate vicinity of the site and four (4) service stations and two (2) auto shops are present within a ½-mile radius of the site. All six above referenced sites have reported unauthorized releases of hydrocarbons, as according to the Report On Releases of Hazardous Substances From Underground Storage Tanks.



January 27, 1993 61035.05

- O The soil samples collected from the water-bearing zone in boring B-6 appears to be predominantly a well graded fine to coarse grained sand with fine sediment content ranging from 2 to 18 percent of total volume.
- O The majority of gasoline hydrocarbons in the soil at the site appears to be at depths between approximately 16 to 18½ feet, within the capillary fringe zone located above first encountered groundwater.
- The vertical extents of gasoline hydrocarbons in the soil has been delineated to nondetectable concentrations (less than 1.0 ppm TPHg) in the northwestern (B-7), in the northeastern (B-8), and southeastern (B-5) portion of the site.
- O Gasoline hydrocarbon impact to soils in the vadose zone (above capillary fringe to surface) appears to have been delineated to nondectectable concentrations (less than 1.0 ppm TPHg) at the perimeter of the site.
- O Groundwater most impacted by gasoline hydrocarbons at the site appears to be limited to the southeastern portion of the site near the USTs and former waste-oil tank.
- O Groundwater does not appear to be impacted by waste-oil hydrocarbons at the site as evidenced by nondectectable concentrations of TOG (less than 0.5 ppm) and diesel (less than 50 ppb) in samples collected from monitoring well MW-1.

#### **LIMITATIONS**

This report was prepared in accordance with generally accepted standards of environmental geological practice in California at the time this investigation was performed. This investigation was conducted solely for the purpose of evaluating environmental conditions of the soil and groundwater with respect to gasoline and waste-oil related hydrocarbons at the site. No soil engineering or geotechnical references are implied or should be inferred. Evaluation of the geologic conditions at the site for the purpose of this investigation is made



January 27, 1993 61035.05

from a limited number of observation points. Subsurface conditions may vary away from the data points available.

#### DISTRIBUTION

It is recommended that copies of this report be forwarded to:

Mr. Richard Hiett
Regional Water Quality Control Board
San Francisco Bay Region
2101 Webster Street, Suite 500
Oakland, California 94612

Ms. Susan Hugo
Alameda County Health Care Services Agency
80 Swan Way, Room 200
Oakland, California 94621

January 27, 1993 61035.05

#### REFERENCES

- Helley, E.S., K.R. Lajoie, W.E. Spangle, and M.L. Blair. 1979. <u>Flatland deposits of the San Francisco Bay Region, California</u>. U.S. Geological Survey Professional Paper 943.
- Hickenbottom, K. and Muir, K. 1988. <u>Geohydrology And Groundwater-Quality Overview</u>, East Bay Plain Area, Alameda County, California 205(J) Report.
- RESNA. August 30, 1991. Work Plan for Initial Subsurface Investigation Related to Former Waste-Oil Tank at ARCO Station 6148, 5131 Shattuck Avenue, Oakland, California. RESNA 61035.01.
- RESNA. October 10, 1991. Site Safety Plan. RESNA 61035.02S.
- RESNA. November 7, 1991. Addendum to Work Plan for Initial Subsurface Investigation Related to Former Waste-Oil Tank at ARCO Station 6148, 5131 Shattuck Avenue, Oakland, California. RESNA 61035.02.
- RESNA. June 6, 1992. <u>Letter Report, Quarterly Groundwater Monitoring First Quarter 1992</u> at ARCO Station 6148, 5131 Shattuck Avenue, Oakland, California. 61035.03
- RESNA. September 28, 1992. <u>Letter Report, Quarterly Groundwater Monitoring Second Quarter 1992 at ARCO Station 6148, 5131 Shattuck Avenue, Oakland, California.</u> 61035.03
- RESNA. September 29, 1992. <u>Initial Subsurface Investigation Related to Former Waste-Oil</u>

  <u>Tank at ARCO Station 6148, 5131 Shattuck Avenue, Oakland, California</u>. RESNA Report 61035.02.
- RESNA. September 29, 1992. Work Plan for Additional Subsurface Investigation at ARCO Station 6148, 5131 Shattuck Avenue in Oakland, California. RESNA Report 61035.04.
- RESNA. October 26, 1992. <u>Site Safety Plan for Additional Subsurface Investigation at ARCO Station 6148, 5131 Shattuck Avenue in Oakland, California</u>. RESNA Report 61035.05.
- RESNA. November 30, 1992. <u>Letter Report Quarterly Groundwater Monitoring Third Quarter 1992 at ARCO Station 6148, 5131 Shattuck Avenue in Oakland, California</u>. RESNA Report 61035.03.



January 27, 1993 61035.05

#### REFERENCES

(Continued)

Scott, C.M., 1991. <u>Background Metal Concentrations in Soils in Northern Santa Clara County.</u>
<u>California.</u> M.S. Thesis at the University of San Francisco, Environmental Management Program.

State Water Resources Control Board. January 1992. <u>Report on Releases of Hazardous Substances from Underground Storage Tanks</u>. 92-2CWP.



Base: U.S. Geological Survey
7.5—Minute Quadrangles
Oakland East/West, California.
Photorevised 1980

LEGEND

PROJECT


Site Location

Approximate Scale
2000 1000 0 2000 4000
feet

Working to Restore Nature

61035.05

SITE VICINITY MAP ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE



#### **EXPLANATION**

= Existing underground storage tanks


B-4 ● = Soil boring

(RESNA, December 1991)

B-8/ MW-7 **⊕** 

Monitoring well (RESNA, December 1991 and October 1992)

E' = Geologic cross section



Source: Based on data supplied by John Koch, Surveyor, 11/09/92.




Working to Restore Nature

PROJECT

61035.05

GENERALIZED SITE PLAN ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE



Source U.S. Geological Survey 7.5—Minute Quadrangle Oakland West, California. Photorevised 1980.

() = Industrial well

★ = Monitoring well


X = Destroyed well

= Cathodic well

 → = Domestic well

• Prezometric well

 $\otimes$  = Geotechnical well





WELL LOCATION MAP ARCO Station 6148 5131 Shattuck Avenue Oakland, California 2

PROJECT

61035.05

#### UNIFIED SOIL CLASSIFICATION SYSTEM

MAJOR (	MAJOR DIVISION		DESCRIPTION	MAJOR DIVISION		LTR	DESCRIPTION		
		GW	Well-graded gravels or gravel-sand mixtures, little or no fines.			ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight		
}	GRAVEL	GP	Poorly-graded gravels or gravel-sand mixtures,		SILTS	<u> </u>	plasticity.		
	AND GRAVELLY	0	little or no fines.		AND CLAYS	CL	Inorganic clays of low to medium plasticity, gravelly		
į	SOILS	GM	Silty gravels, grave—sand—	-	LL<50		clays, sandy clays, silty clays, lean clays.		
COARSE-	·	GC	Clayey gravel, gravel—sand—clay mixtures.	FINE-		OL	Organic silts and organic silt—clays of low plasticity		
GRAINED SOILS	SAND	SW	Well—graded sand or gravelly sands, little or no fines.	GRAINED SOILS	SILTS	мН	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts.		
	AND SANDY	AND SANDY	AND	SP	Poorly-graded sands or gravelly sands, little or no fines.		AND CLAYS LL>50	СН	Inorganic clays of high plasticity, fat clays.
	30.60	SM	Silty sands, sand—silt mixtures.			ОН	Organic clays of medium to high plasticity, organic silts.		
		SC	Clayey sands, sand-clay mixtures.	HIGHLY ORG	ANIC SOILS	PT	Peat and other highly organic soils.		

T	Depth through which sampler is driven		Sand pack	
<b>+</b>	Relatively undisturbed		Bentonite	Stratigraphic contact
	sample ´	<b>₽ ₽</b>	Neat cement	
図	No sample recovered		Caved native soil	 Gradational contact
<u></u>	Static water level observed in well/boring		Blank PVC	
<u>\</u>	Initial water level observed in boring		Machine—slotted PVC	 Inferred contact
S-10	Sample number	P.I.D.	Photoionization detector	merrea contact

BLOWS REPRESENT THE NUMBER OF BLOWS OF A 140-POUND HAMMER FALLING 30 INCHES TO DRIVE THE SAMPLER THROUGH EACH 6 INCHES OF AN 18-INCH PENETRATION.

GRADATIONAL AND INFERRED CONTACT LINES SEPARATING UNITS ON THE LOG REPRESENT APPROXIMATE BOUNDARIES ONLY. ACTUAL BOUNDARIES MAY BE GRADUAL. LOGS REPRESENT SUBSURFACE CONDITIONS AT THE BORING LOCATION AT THE TIME OF DRILLING ONLY.

R		5	A
Working	lФ	Restore	Nature

PROJECT 61035.05

## UNIFIED SOIL CLASSIFICATION SYSTEM PLATE AND SYMBOL KEY ARCO Station 6148

ARCO Station 6148 5131 Shattuck Avenue Oakland, California

Depth of boring: 32 feet	Diameter of boring: 10.25	inches Date drilled: 10/27/92	
Well depth: 26-1/2 feet	Material type: Sch 40 PV	VC Casing diameter: 4 inches	<u> </u>
Screen interval: $11-1/2$ to 2	6-1/2 feet Filter pack:	#3 Sand Slot size: 0.020-inc	ch
Drilling Company: Expiorat	ion GeoServices Driller:	Dave and Dennis	
Method Used: Hollow-S	Stem Auger	Field Geologist: Rob Campbell	
Signature of Re	egistered Professional <u>:</u>	1 A/L	
Registra	tion No.: CEG 1463 States	/CA	

Depth	Sampi No.	le —	Blow	P.I.D.	USCS Code	Description	Well Const
- 0 -						Asphalt—covered surface. Asphalt (4 inches).	
- 2 -					SC	Clayey sand with silt, dark brown, damp, medium dense; brick fragments, glass: fill.	
. 4 -	S-5	$\mp$	5 7 9	0	CL	Silty clay, dark brown, damp, low plasticity.	7 V V
6 -	3-3		9		ML	Clayey silt, brown, damp, stiff, low plasticity.	
8 -							7 V 7
10-	S-9.5	T X	6 8 9	0			
12-	ļ		ļ	30	GP-GM	Product odor at 11 feet.  Gravel with sand and silt, 1—2 inch gravel, olive— green, moist, medium dense; product odor.	
14 ~	S-14.5			210	SP-SM	Gravelly sand with silt, medium—grained sand and gravel, olive—green, moist, medium loose; product odor, root holes.	
16 -	}	X.	12	180			
18 -		į		20≟	GP-GM	Sandy gravel with silt and clay, brown, wet, medium dense; no product odor.	
20 -	S-20	H	13 15 14	0			
		-	[				-

PROJECT 61035.05

LOG OF BORING B-5/MW-4

ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE

Depth Sample No.		BLOWS	P.I.D.	USCS Code	Description	Well Const
				GP-GM	Sandy gravel with silt, brown, wet, dense; root holes.	
-22 -						
-24 -	S-25	14 18 22	0			
- 26 -		22				
-28 -				CL	Silty clay, brown, damp, low plasticity, hard.	
-30 -	S-30	15 19 27 9 13 15	0			
-32 —	S-30 S-31.5	9 13 15	0		Total depth = 32 feet.	
-34 —		ĺ			Total dopth = 32 feet.	į
- 36 –	į					
			į			
- 38 –			į	į		
40-						
42						
44 -			Į			
46						
48-		ŀ				
50 –		-				

PROJECT 61035.05

LOG OF BORING B-5/MW-4

ARCO Station 6148
5131 Shattuck Avenue
Oakland, California

PLATE

Depth of boring: 28 feet	Diameter of boring	:10.25 inches	Date drilled:_	10/28/92
Well depth: 25 feet	Material type: Sch	40 PVC	Casing diameter:	4 inches
Screen interval: 10 to 2	5 feet Filter p	ack: <u>#</u> 3 S	and Slot siz	e: 0.020-inch
Drilling Company: Explorat	on GeoServices Dri	ller: Da	ive and Dennis	
Method Used: Hollow-S	item Auger	Field	Geologist: Rob	Campbell
Signature of Re	gistered Professiona		L	
Registra	tion No.: CEG 1463 /	Stofe: CA	_	

Depth	Sample No.	Blov s	P.I.D.	USCS Code	Description	We Con	
- 0 -					Asphalt—covered surface. Asphalt (4 inches).	V	
2 -				SC	Clayey sand with silt, dark brown, damp, medium dense; brick fragments, glass fragments: fill.	7	2
4 -	S-45	11 12 13	0			∇ 7 ∇ 7 ∇ 7 ∇	2
6 7			:	GM	Silty gravel with sand, brown, damp, medium dense.	∇ ∇ ∇ ∇ ∇ ∇	\rangle \rangl
- 8 -				GM	Silty graver with sana, brown, dump, medium dense.		
- 10-	S-9.5	10 12 14	50		Slight product odor at 10 feet.		
12-		ļ		GP	Sandy gravel, olive—green, moist, loose; product odor.	     	1
- 14 -	S14.5	12 18 19	36	GP-GC	Sandy gravel with clay, olive—green, moist, dense; product odor.		
- 16 -	S-16 S-16.5	8 14	407				
- 18 -	S-17.5 S-18 S-18.5	16 7 8 9 12 18 19	210	<u></u>		}	1 1
- 20 -	S-19. S-19.5 S-20.5 S-20.5	12 18 19	10	SP	Gravelly sand, light brown, wet, dense; slight product odor.		1
	S-20.3	7	0	GP	Sandy gravel, gray, wet, medium dense; no product odor.	-	} }
	X	13		SM	Silty sand, gray with brown mottling, wet, medium dense. (Section continues downward)		]]

	ESNA	LOG OF BORING B-6/MW-5	PLATE
	to Restore Nature	ARCO Station 6148 5131 Shattuck Avenue	7
PROJECT	61035.05	Oakland, California	

epth	Sample No.	BLOWS	P.I.D.	USCS Code	Description	Well Cons
	S-20 5			SP	Gravelly sand, light brown, wet, dense; no product	TH
	S-20.5 S-21	7 10	0	GP	odor. Sandy gravel, gray, wet, medium dense.	1 1
-22 –	S-22_X	13	0	SM	Silty sand, gray with brown mottling, wet,	1.
	S-22.5	Ż	0		medium dense.	1.1
-24 -	S-20.5 S-21 S-22.5 S-23.5 S-24 S-25 X S-26	13 20	0	GW-GC	Gravelly sand with clay, brown with black mottling, wet dense.	
	S-25 🛎	12	0			-
- 26 -	S-26	15 19	0	CL	Silty clay, brown with gray mottling, wet, hard.	ngiya.Gr. wisaniinika w
	S-27.5		0		· · · · · · · · · · · · · · · · · · ·	
-28 -					Total depth = 28 feet.	
-30 —						
50						
70		ļ ļ				
-32 –						
-34 -			İ			
- 36 -						
· 38 –						Į
40 -						
	(					
42 -						
12						
44 -						
			i			
46	)					
İ						
48			ļ			
50						
	f   					

Working to Restore Nature
PROJECT 61035.05

LOG OF BORING B-6/MW-5 ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE

Depth of boring:  Well depth: 27		~ ~ <del></del>	
Screen interval:	12 to 27 feet Filt	er pack:	#3 Sand Slot size: 0.020—inch
· · · <u> </u>	Exploration GeoServices	Driller:	
Method Used:Signa	Hollow—Stem Auger ture of Registered Profes: Registration No.: CEG 14		Field Geologist: Rob Campbell

Sampl No.	е	Blows	P.I.D.	USUS Code	Description	Well Const.
				SC	Asphalt—covered surface.  Asphalt (4 inches).  Clayey sand, dark brown, damp, medium dense; no product odor, brick fragments: fill.	V V V V V V V V V V V V V V V V V V V
S-4.5	I K	4 7 7	0			
				SC	Clayey sand with gravel, brown with greenish—gray and black mottling, damp to moist, medium dense; root holes.	2
S-10		6 8 10	0			
					Color change to olive-green at 12 feet, moist. Color change to brown at 13-1/2 feet.	
S-15		11	42	SP	Gravelly sand, brown with orange and gray mottling, moist, medium dense; product odor, root holes.	
S-19	᠒᠂	10	0	- SM	Silty sand with gravel, gray with brown mottling, wet, medium dense; no product odor, cross—bedding lamination.	
	S-4.5 S-10	S-4.5 <b>X</b> S-10 S-19	S-4.5 X 7  S-10  10  S-15  10  S-19  9	$S-4.5$ $\frac{4}{7}$ 0 $\frac{4}{7}$ 0 $\frac{4}{7}$ $\frac{6}{7}$ 8 0 $\frac{10}{11}$ 42 $\frac{10}{10}$ 42 $\frac{10}{10}$ $\frac{10}{11}$ $\frac{42}{10}$	S-4.5	Asphalt—covered surface.  Asphalt (4 inches).  SC Clayey sand, dark brown, damp, medium dense; no product odor, brick fragments: fill.  SC Clayey sand with gravel, brown with greenish—gray and black mottling, damp to maist, medium dense; root holes.  S-10

61035.05

PROJECT

LOG OF BORING B-7/MW-6

ARCO Station 6148
5131 Shattuck Avenue
Oakland, California

PLATE

epth)	Sample No.	RI OWG	P.I.D.	USCS Code	Description	Well Const
				SM	Silty sand with gravel, gray with brown mottling, wet, medium dense; no product odor.	
22 –				GP	Sandy gravel, brown with orange mottling, wet, dense.	- °  -      -
24 -	S-25	13 18 22	0			
26		İ				
	S-28		1	CL	Sandy clay, brown, damp, low plasticity, hard; root holes.	
30 –	S-29.5	12 16 27	0	-	Tatal denth - 30 foot	
32 –		į			Total depth = 30 feet.	
				<u> </u>		į
34 –						]
36-						
38-						
40 –						
42 -						
44 -				7749		
46-		-				
48 –						
50 –						
	}	}_				

PROJECT 61035.05

LOG OF BORING B-7/MW-6

ARCO Station 6148
5131 Shattuck Avenue
Oakland, California

PLATE

Depth of boring: 3	<u> 34 feet</u> Diameter of b	oring: <u>10.25</u> in	<u>nches</u> Date dri	lled: 10/27/92
Well depth: 27 fe	eet Material type:_	Sch 40 PVC	Casing diar	meter: 4 inches
Screen interval:	12 to 27 feet Fil	ter pack:	#3 Sand Slo	ot size: 0.020-inch
Drilling Company:	Exploration GeoServices	Driller:	Dave and Denr	nis
Method Used:	Hollow-Stem Auger		Field Geologist:_	Rob Campbell
Signat	ure of Registered Profes	sional <u>:</u>	1//	
	Registration No.: CEG 14	163 State:		

Jepth	Sampl No.	c i	Blows	P.I.D.	USCS Code	Description	Well Const.
- 0 -	S-4.5	T :	533	0	SC	Asphalt—covered surface.  Asphalt (4 inches).  Clayey sand with silt, dark brown, damp, medium dense;  no product odor, brick fragments, glass: fill.	7
- 6 <del>-</del> - 8 <del>-</del>	S-9.5	1 2	1 7	0	CL	Gravelly clay with sand, brown, damp, low plasticity, very stiff; root holes.	2
12 -	S14.5	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	26	40	GW-GM	Sandy gravel with silt, olive—green, moist, dense; product odor, green decreases with depth in sample taken.  Grades to light brown at 14.9 feet.	
18 -	S-19.5 S-20	5 8	3	0	SW GW-GM	Sand with gravel, light brown, wet, medium dense; no product odor.  Sandy gravel with silt, brown, wet, dense.	

PROJECT 61035.05


LOG OF BORING B-8/MW-7


ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE


epth	Sample No.	BLOWS	P.I.D.	USCS Code	Description	Well Const.
				SW GW-GM	Sand with gravel, light brown, wet, medium dense; no product odor.	
22 -					Sandy gravel with silt, brown, wet, dense.	
						<u> </u>
24	S-25	13 15 18	0			
26	3-23	18	U			
	[ ]	12				
	S-28		0			
30 –	s-30	12 11	0			
		22		CL	Silty clay, brown, damp, low plasticity, hard.	
32 –		12				
-34	S-33.5	12 16 27	0			
					Total depth = 34 feet.	
36						
- 38 –						
40						į
42 –						
44						-
46			·			
48						ļ
50 _						


Working to Restore Nature
PROJECT 61035.05

LOG OF BORING B—8/MW—7 ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE










### EXPLANATION

\_\_\_\_92.0 = Line of equal elevation of groundwater in feet above mean sea level (MSL)

92.33 = Elevation of groundwater in feet above MSL, November 12, 1992

MW-7 = Monitoring well (RESNA, December 1991 and October 1992)

□ Underground storage tanks



Source: Based on data supplied by John Koch, Surveyor, 11/09/92.




Working to Restore Nature

GROUNDWATER GRADIENT MAP ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE 16

**PROJECT** 

61035.05







PROJECT 61035.05

GROUNDWATER GRADIENT MAP ARCO Station 6148 5131 Shattuck Avenue Oakland, California

17





#### **EXPLANATION**

= Well was sampled on 10/07/92

2,900/1,300 = Concentration of TPHg/Benzene in groundwater December 12, 1992


FΡ = Floating Product

MW-7 **⊕** 

**PROJECT** 

Monitoring well (RESNA, December 1991 and October 1992)

= Underground storage tanks



Based on data supplied by John Koch, Surveyor, 11/09/92. Source:



61035.05

610355Q4

CONCENTRATIONS OF TPHg/BENZENE PLATE IN GROUNDWATER ARCO Station 6148 19 5131 Shattuck Avenue Oakland, California



January 27, 1993 61035.05

#### TABLE 1 WELL SURVEY DATA ARCO Station 6148 Oakland, California (Page 1 of 1)

Map Section Number	Well Number	Well Well Type Owner	Well Depth (feet)	Depth to Water (feet)
13		Cathodic Protection EBMUD	50	NA
13	M2	Cathodic Protection PG&E	120	NA
13	N2	Cathodic Protection EBMUD	50	NA
24	D1	Cathodic Protection EBMUD	53	25
24	D2	Cathodic Protection EBMUD	53	NA
24	D3	Cathodic Protection PG&E	120	NA
13	G8	Monitoring City of Oakland	33	18
13	M3	Monitoring Chevron USA Inc	30	13
13	M4	Monitoring Chevron USA Inc	29	13
13	M5	Monitoring Chevron USA Inc	29	13
14	R2	Monitoring Pacific Rim Development	31	17
14	R3	Monitoring Pacific Rim Development		16
23	AI	Monitoring Wayne Kelly Auto Parts	35	14
13	G6	Piezometric City of Oakland	28	18
13	G7	Piezometric City of Oakland	28	23
14	Jl	Industrial Marshall Steel Company	40	NA
13	NI	Abandoned Mrs H. Gotelli	85	9
14	R1	Geotechnical Children's Hospital	150	NA
13	M1	Domestic Angela Delucchi	75	5

EBMUD: East Bay Municipal Utility District.

PG&E: Pacific Gas and Electric.

NA: Not available.

Source: Andreas Godfry, County of Alameda Public Works Department.



January 27, 1993 61035.05

# TABLE 2 CUMULATIVE GROUNDWATER MONITORING DATA ARCO Station 6148 Oakland, California (Page 1 of 2)

Date Well Measured	Well Elevation	Depth to Water	Water Elevation	Floating Product
MW-1				
12-23-91	108.03	18.26	89.77	Sheen
01-07-92		17.44	90.59	Sheen
01-19-92		17.17	90.86	None
02-19-92		16.52	91.51	None
03-18-92		16.81	91.22	None
04-20-92		17.56	90.47	None
05-15-92		17.96	90.07	None
06-12-92		18.16	89.87	None
07-15-92		18.32	89.71	None
08-07-92		18.34	89.69	None
09-14-92		18.46	89.57	None
10-07-92		18.52	89.51	None
11-12-92		18.11	89.92	None
12-09-92		17.10	90.93	None
MW-2		*****		1.4114
12-23-91	107.43	17.98	89.45	Sheen
01-07-92		17.15	90.28	Sheen
01-19-92		17.47	89.96	None
02-19-92		16.28	91.15	None
03-18-92		16.52	90.91	None
04-20-92		17.27	90.16	None
05-15-92		17.62	89.81	None
06-12-92		17.63*	89.80*	0.05
07-15-92		17.65	89.78	None
08-07-92		17.80	89.63	None
09-14-92		18.09*	89.34*	0.55
10-07-92		18.55*	88.88*	0.31
11-12-92		17.95	89.48	Sheen
12-09-92		16.85*	90.58*	0.02
MW-3		10.00		3.72
12-23-91	107 77	18.14	89.63	Sheen
01-07-92	10. 17	17.26	90.51	Sheen
01-19-92		17.63	90.14	None
02-19-92		16.34	91.43	None
03-18-92		16.62	91.15	None
04-20-92		17.38	90.39	None
05-15-92		17.80	89.97	None
06-12-92		18.01	89.76	None
07-15-92		18.17	89.60	None
08-07-92		18.23	89.54	None

See notes on page 2 of 2.



January 27, 1993 61035.05

# TABLE 2 CUMULATIVE GROUNDWATER MONITORING DATA ARCO Station 6148 Oakland, California (Page 2 of 2)

Date Well Measured	Well Elevation	Depth to Water	Water Elevation	Floating Product
MW-3 Cont.		· · · · · · · · · · · · · · · · · · ·		
09-14-92		18.36	89,41	None
10-07-92		18.90	88.87	Sheen
11-12-92		18.00	89.77	Sheen
12-09-92		16.85	90.92	Droplets
<u>MW-4</u>				
11-12-92	106.58	16.08	90,50	None
12-09-92		15.00	91.58	None
MW-5				
11-12-92	106.68	16.81	89.87	None
12-09-92		16.40	90.28	None
MW-6				
11-12-92	105.16	14.05	91.11	None
12-09-92		13.37	91.79	None
<u>MW-7</u>				
11-12-92	107.08	14.75	92.33	None
12-09-92		12.55	94.53	None

Measurements in feet.

Well elevation = Top of casing elevations.

Wells surveyed on November 9, 1992, by John Koch. Datum is City of Oakland = (USGS) + 3.00

Elevations in feet above mean sea level.

<sup>•</sup> indicates that the depth to water (DTW) and water elevation were corrected for the presence of floating product by the following method. Measured product thickness (PT) is multiplied by a correction factor of 0.8 and subtracted from DTW. (Adjusted DTW = DTW - [PT X 0.8]). The corrected DTW is then subtracted from the well elevation.



January 27, 1993 61035.05

# TABLE 3 RESULTS OF LABORATORY ANALYSES OF SOIL SAMPLES - TPHg, BTEX, Lead, and RCI ARCO Station 6148 Oakland, California October 27-28, 1992

Sample Identification	ТРН	В	T	E	x	Lead	RCI
S-9½-B5	<1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-141/2-B5	< 1.0	0.13	< 0.0050	< 0.0050	0.0050	NA	NA
S-31½-B5	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-9½-B6	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-16½-B6*	190	0.24	0.55	1.0	1.3	NA	NA
S-271/2-B6	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-10-B7	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-15-B7	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-29½-B7	< 1.0	< 0.0050	< 0.0050	< 0.0050	0.025	NA	NA
S-9½-S8	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-14½-B8	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
S-33½-B8	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	NA	NA
CSS-A-D	<1.0(<50)	<0.005(<0.50)	)<0.005(<0.50)	<0.005(<0.50)	<0.005(<0.50)	0.079	Non- hazardou

All results shown in parts per million (ppm)

TPHg: Total petroleum hydrocarbons as gasoline by EPA method 5030/8015/8020.

B: Benzene, T: Toluene, E: Ethylbenzene, T: Total Xylene isomers;

BTEX: Measured by EPA method 8030/8015/8020.

Lead: Analyzed by STLC.

RCI: Reactivity, corrosivity, and ignitability.

NA: Not analyzed.

Laboratory reported this as a gas and non-gas mix.
 Results reported as less than the detection limit.

(<50): Toxicity Characterization Leaching Procedure (TCLP) for TPHg reported in parts per billion (ppb).

(<0.50): TCLP for BTEX reported in ppb.

Sample Identification:

S-15-B7

| Boring number | Depth in feet | Soil sample |

CSS-A-D | Composite sample numbers | Composite soil sample |



January 27, 1993 61035.05

# TABLE 4 RESULTS OF LABORATORY ANALYSES OF WATER SAMPLES ARCO Station 6148 Oakland, California

WELL ID	ТРНд	TPHd	В	Т	Е	х	TOG*	PCE	TCE	Cf	
10/07/92											
MW-I	590	< 50	200	19	6.7	19	< 0.5	23	1.5	0.6	
MW-2	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	
MW-3	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	
11/12/92											
MW-4	77	NA	32	< 0.50	< 0.50	< 0.50	NA	NA	NA	NA	
MW-5	2,900	NA	1,300	12	67	18	NA	NA	NA	NA	
MW-6	51	NA	2.6	< 0.50	< 0 50	< 0.50	NA	NA	NA	NA	
MW-7	<50	NA	1.8	< 0.50	< 0.50	< 0.50	NA	NA	NA	NA	
MCL: DWAL:	-	-	1 -	100	680 -	1,750	- -	5	-	-	

<sup>\*</sup>Results in parts per billion (ppb) with the exception to TOG which is in parts per million (ppm).

BTEX: Analyzed by EPA method 5030/8015/8020.

TOG: Total oil and grease by Standard method 5520 C&F.

TCE: Trichloroethene analyzed by EPA Methods 5030/601.

PCE: Tetrachloroethene analyzed by EPA Methods 5030/601.

Cf: Chloroform analyzed by EPA Methods 5030/601.

NA: Not analyzed.

<: Results reported below the laboratory detection limit.

NS: Not sampled, due to floating product in the well.

MCL: Maximum contaminant level.

DWAL: Drinking water action level.

Sample Identification:

W-MW3

Monitoring well number

Water Sample

TPHg: Total petroleum hydrocarbons as gasoline by EPA method 5030/8015/8020.

B: benzene, T: toluene, E: ethylbenzene, X: total xylenes isomers

# APPENDIX A VISTA DATABASE SEARCH RESULTS

## VISTA ENVIRONMENTAL INFORMATION, INC.

3-RISJ0C-612010

RADIUS STATUS REPORT

Date of Report: 11/23/92

Loan #: ARCO STATION 6148 RESNA INDUSTRIES - SAN JOSE

3315 ALMADEN EXPRWY STE 34, SAN JOSE, CA 95118

Loan Property: 5131 SHATTUCK AVENUE OAKLAND, CA 94609


### VISTA DATABASE SEARCH RESULTS

### Records Located Within:

Database & Date	Agency & Type of Records	0 to 1/4 mi.	1/4 to 1/2 mi.	1/2 to 1 mi.	TOTAL
NPL 1/92	US EPA Superfund Sites	0	0	0	0
CERCLIS 1/92	US EPA Potential Superfund Sites	0	0	1	1
AWP 10/91	CAL. EPA CASITES / Sites Authorized for Cleanup under the California Annual Work Plan	0	0	0	0
LUST various	CAL. REGIONAL WATER QUALITY CONTROL BOARD Leaking Underground Storage Tanks	4	6	39	49
SWIS 7/91	CAL. WASTE MGMT. BOARD Active/Inactive Sanitary Landfills/ Disposal Sites	0	0	0	0
ASPIS 10/91	CAL. EPA CASITES / Abandoned Site Program	2	1	26	29
	Total:	6	7	66	79

Note: Sites often have more than one environmental record.

For More Information Call:
(c) VISTA Environmental Information, Inc.
(619) 450-6100



3-RISJOC-612010

Page:

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

Status Code: NFA: No Further Action.

	WI	THIN	1/4	MILE:
--	----	------	-----	-------

23	LUST Status Code:	CHEVRON 5500 TELEGRAPH AVE 3B: Preliminary site assessment underway.	OAKLAND	Direction:	NE
25	LUST Status Code:	AUTOPRO 5200 TELEGRAPH AVE 3A: Preliminary site assessment workplan submitted.	OAKLAND	Direction:	NE
26	LUST Status Code:	CHEVRON 5101 TELEGRAPH AVE 3B: Preliminary site assessment underway.	OAKLAND	Direction:	E ,
29	LUST Status Code:	ARCO 5131 SHATTUCK AVE 0: No action.	OAKLAND	Direction:	
27	ASPIS 01510011 Status Code:	MARKS PAINT SPOT 5025 TELEGRAPH AV NFA: No Further Action.	OAKLAND 94609	Direction:	SE
35		CHILDREN'S HOSPITAL GROVE AND 51ST ST.	OAKLAND 94609	Direction:	sw

2	3 LUST	KELLEY AUTO PARTS	OAKLAND	
		4400 TELEGRAPH AVE		Direction: S
	Status Code:	3B: Preliminary site assessment underway.		
3	7 LUST	BP OIL	OAKLAND	
		5425 MARTIN LUTHER KING		Direction: NW
	Status Code:	O: No action.		
37	LUST	MOBIL	OAKLAND	
		5425 GROVE ST		Direction: NW
	Status Code:	3B: Preliminary site assessment underway.		
37	LUST	BP OIL	OAKLAND	
		5425 MARTIN LUTHER KING		Direction: NW
	Status Code:	0: No action.		

3-RISJOC-612010

Page:

2

SITE #

AGENCY & 1D# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

Direction: NW

Direction: NE

Direction: SE

Direction: SE

Direction: NE

#### WITHIN 1/4 TO 1/2 MILE:

CHEVRON 38 LUST

OAKLAND

5509 MARTIN LUTHER KING Direction: NW

Status Code: 5C: Pollution characterization underway.

38 LUST CHEVRON OAKLAND

5509 MARTIN LUTHER KING

Status Code: 5C: Pollution characterization underway.

JAMES SLATON TRUCKING ASPIS OAKLAND 20

01420035 5707 VICENTE ST 94618

Status Code: NFA: No Further Action.

#### WITHIN 1/2 TO 1 MILE:

CERCLIS **GRANT LABORATORIES** OAKLAND

94608 CAD093982866 6020 ADELINE ST Direction: NW

Status Code: (None provided)

LUST LA MANCHA DEVELOPMENT COMPANY OAKLAND

4299 PIEDMONT AVE

Status Code: 0: No action.

FIRE STATION #19 LUST OAKLAND

> 5776 MILES AVE Direction: NE

Status Code: 3B: Preliminary site assessment underway.

UNOCAL OAKLAND LUST

5300 BROADWAY Direction: E

Status Code: 3B: Preliminary site assessment underway.

3 LUST UNOCAL OAKLAND

5300 BROADWAY Direction: E

Status Code: 3B: Preliminary site assessment underway.

YOUNG'S FOOD & LIQUOR LUST OAKLAND

4193 PIEDMONT AVE

Status Code: 0: No action.

5 LUST WILLIAM BROWN REALTY OAKLAND

5353 COLLEGE AVE

Status Code: 0: No action.

3-RISJ0C-612010

Page: 3

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

7	LUST	MEHDIZADEH PROPERTY 5175 BROADWAY	OAKLAND	Direction:	SE
	Status Code:	3B: Preliminary site assessment underway.			
7	LUST	MEHDIZADEH PROPERTY	OAKLAND		
		5175 BROADWAY		Direction:	SE
	Status Code:	3B: Preliminary site assessment underway.			
	• • • • • • • • • • • • • • • • • • • •	•			
8	LUST	CHEVRON	OAKLAND		
Ü	2001	5800 COLLEGE AVE		Direction:	NE
	Status Code:	5R: Remediation plan submitted.			
	Status couc.	SK. Remadiserer profit			
10	LUST	DRYER'S GRAND ICE CREAM	OAKLAND		
10	6001	5929 COLLEGE AVE		Direction:	NE
	Status Code:	3A: Preliminary site assessment workplan submitted.			
	Status couc.	5/4 (   6 ( )   1   1   1   1   1   1   1   1   1			
12	LUST	SHELL	OAKLAND		
,	2001	6039 COLLEGE AVE		Direction:	NE
	Status Code:	3B: Preliminary site assessment underway.			
	Status south	,			
14	LUST	7-ELEVEN	OAKLAND		
1-4	2031	4100 BROADWAY		Direction:	SE
	Statue Code:	3B: Preliminary site assessment underway.			
	Status couc.	,			
14	LUST	7-ELEVEN	OAKLAND		
17	F00.	4100 BROADWAY		Direction:	SE
	Status Code:	3B: Preliminary site assessment underway.			
	000000	,			
16	LUST	UNOCAL	OAKLAND		
	2001	3943 BROADWAY		Direction:	SE
	Status Code:	5C: Pollution characterization underway.			
	014143 33431				
16	LUST	UNOCAL	OAKLAND		
.0		3943 BROADWAY		Direction:	SE
	Status Code:	5C: Pollution characterization underway.			
	0(0(25 5525)				
17	LUST	FIRESTONE & RUBBER COMPANY	OAKLAND		
• • •		3785 BROADWAY		Direction:	SE
	Status Code:	(None)			
	244444 4-74				
17	LUST	FIRESTONE & RUBBER COMPANY	OAKLAND		
••		3785 BROADWAY		Direction:	SE
	Status Code:				
	acacas ovace	********			

3-RISJ0C-612010

Page: 4

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

18	LUST Status Code:	CHEVRON  3701 BROADWAY  5C: Pollution characterization underway.	OAKLAND	Direction: SE
18	LUST Status Code:	CHEVRON 3701 BROADWAY 5C: Pollution characterization underway.	OAKLAND	Direction: SE
21	LUST Status Code:	ARCO 6407 TELEGRAPH AVE 5C: Pollution characterization underway.	OAKLAND	Direction: NE
21	LUST Status Code:	GIVENS INVESTMENT COMPANY 6398 TELEGRAPH AVE 0: No action.	OAKLAND	Direction: NE
22	LUST Status Code:	THRIFTY OIL 6125 TELEGRAPH AVE 5R: Remediation plan submitted.	OAKLAND	Direction: NE
24	LUST Status Code:	UNOCAL 411 MACARTHUR BLVD W 3B: Preliminary site assessment underway.	OAKLAND	Direction: S
31	LUST Status Code:	SIMAS BROS. 4013 TELEGRAPH AVE 0: No action.	OAKLAND	Direction: S
31		SHELL 500 40TH ST 5R: Remediation plan submitted.	OAKLAND	Direction: S
32		CALIFORNIA HIGHWAY PATROL OAKL 3601 TELEGRAPH AVE 0: No action.	OAKLAND	Direction: S
33		SHATTUCK IMPORTS 6562 SHATTUCK AVE 0: No action.	OAKLAND	Direction: N
39		ARCO 731 MACARTHUR BLVD W 5C: Pollution characterization underway.	OAKLAND	Direction: SW

3-RISJOC-612010

Page: 5

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY 

11/23/92

	40	LUST	R.D. MINER CO.	OAKLAND	
			750 37TH ST		Direction: SW
		Status Code	: 0: No action.		
	45	LUST	DAMELE PROPERTY	OAKLAND	
			4401 MARKET ST		Direction: SW
		Status Code:	0: No action.		
	49	LUST	OAKLAND NATIONAL ENGRAVING	OAKLAND	
			1001 42ND ST		Direction: SW
		Status Code:	3B: Preliminary site assessment underway.		
!	50	LUST	CALIFORNIA LINEN RENTAL	OAKLAND	
			989 41ST ST		Direction: SW
		Status Code:	3B: Preliminary site assessment underway.		
:	50	LUST	DUNNE QUALITY PAINTS	OAKLAND	
			1007 41ST ST		Direction: SW
		Status Code:	3B: Preliminary site assessment underway.		
5	<b>i</b> 1	LUST	MOORE PROPERTY	BERKELEY	
			3155 SACRAMENTO ST		Direction: NW
		Status Code:	O: No action.		
5	3	LUST	SAN FRANCISCO BREAD COMPANY	EMERYVILLE	
			4070 SAN PABLO AVE		Direction: SW
		Status Code:	O: No action.		
5	4	LUST	CITY OF EMERYVILLE	EMERYVILLE	
			4300 SAN PABLO AVE		Direction: SW
		Status Code:	3B: Preliminary site assessment underway.		
5	6	LUST	BERKELEY FARMS	EMERYVILLE	
			4550 SAN PABLO AVE		Direction: SW
		Status Code:	0: No action.		
5	8	LUST	AC TRANSIT	EMERYVILLE	
			1140 45TH ST		Direction: SW
		Status Code:	5C: Pollution characterization underway.		
5.	9	LUST	PARINA ENTERPRISES	OAKLAND	
_	•		5433 SAN PABLO AVE		Direction: W
		Status Code:	0: No action.		

3-RISJ0C-612010

Page: 6

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

	*****			
6	ASPIS	IMPAC PHOTO	OAKLAND	
Ū	01730007	5604 COLLEGE AV	94618	Direction: NE
		: NFA: No Further Action.	• • • • • • • • • • • • • • • • • • • •	• · · · · · · · · · · · · · · · · · · ·
	014140 0040			
9	ASPIS	RYAN'S CUSTOM UPHOLSTERY	OAKLAND	
	01760010	5711 COLLEGE AV	94618	Direction: NE
	Status Code:	: NFA: No Further Action.		
10	ASPIS	EXPOSURE	OAKLAND	
	01730083	5940 COLLEGE AV	94618	Direction: NE
	Status Code:	NFA: No Further Action.		
11	ASPIS	SHIELDS, HARPER & CO.	OAKLAND	
	01730058	5107 BROADWAY	94611	Direction: SE
	Status Code:	NFA: No Further Action.		
13	ASPIS	CLARKS REFINISHING	OAKLAND	
	01760018	5200 CLAREMONT	94618	Direction: NE
	Status Code:	NFA: No Further Action.		
13	ASPIS	KAPS	OAKLAND	
	01760021	5301 CLAREMONT AV	94618	Direction: NE
	Status Code:	NFA: No Further Action.		
13	ASPIS	WILD FLOWER & COMPANY	OAKLAND	
	01320018	5400 CLAREMONT	94618	Direction: NE
	Status Code:	NFA: No Further Action.		
15	ASPIS	DAVANZO, LORNA	OAKLAND	
	01500084	6019 COLBY ST	94609	Direction: NE
	Status Code:	NFA: No Further Action.		
19	ASPIS	CALIF. SURGERY CENTER AND HOSPITAL	OAKLAND	
	01800018	390 40TH ST	94609	Direction: SE
	Status Code:	NFA: No Further Action.		
30	ASPIS	PAYLESS CLEANERS	OAKLAND	
		3936 TELEGRAPH	94609	Direction: S
		NFA: No Further Action.		
71	40010	LINERS CHIPS MEET	OAKLAND	
34	ASPIS 01330024	WHERE ENDS MEET 5926 WHITNEY ST	94609	Direction: NW
		NFA: No Further Action.	74007	Diffection: MM
	status Code:	arm: no rolliel Action.		

3-RISJ0C-612010

7 Page:

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

36	ASPIS	PHOTO LAB	BERKELEY		
30	01730043	1908 ALCATRAZ AV	94703	Direction:	NW
		: NFA: No Further Action.	7,1103	p11 coc1 o	
	010100				
40	ASPIS	R J S ENTERPRISES	OAKLAND		
	01350004	675 37TH ST	94609	Direction:	SW
	Status Code:	: NFA: No Further Action.			
41	ASPIS	EUUELL BATES CLEANERS	BERKELEY		
	01720023	1805 ALCATRAZ	94703	Direction:	NW
	Status Code:	NFA: No Further Action.			
42	ASPIS	TALLEY COSMETICS	BERKELEY		
44	01280056	1831 HARMON	94703	Direction:	NW
		NFA: No Further Action.	7 47 63	D11.00010111	
	States code:	With the Fall the Motrons			
43	ASPIS	SIERRA SOUND LABS	BERKELEY		
	01360002	1741 ALCATRAZ AV	94703	Direction:	NW
	Status Code:	NFA: No Further Action.			
44	ASPIS	GRANT LABORATORIES INC	OAKLAND		
7-7	01280062	6020 ADELINE ST	94607	Direction:	NW
		NFA: No Further Action.			
45	ASPIS	OLIVIA DECODDS	OAKLAND		
42	01720073	OLIVIA RECORDS 4400 MARKET ST	94609	Direction:	su.
		NFA: No Further Action.	74007	Direction.	J.,
	015155 00001	The transfer metrons			
46	ASPIS	CORVIT PHARMACEUTICALS	OAKLAND		
	01510014	5780 MARKET ST	94607	Direction:	ИW
	Status Code:	NFA: No Further Action.			
47	ASPIS	TOP LINE FIXTURES	OAKLAND		
	01350083	941-945 AILEEN ST	94609	Direction:	NW
	Status Code:	NFA: No Further Action.			
48	ASPIS	FLECTO INTERNATIONAL	OAKLAND		
,-	01510002	1000-12 45TH ST	94609	Direction:	SW
	Status Code:	NFA: No Further Action.			
52	ASPIS	PACIFIC TYPOGRAPHIC	EMERYVILLE		
26	01350017	1094 YERBA BUENA AV	94608	Direction: 5	sw
		NFA: No Further Action.		, == *, *, 110	

3-RISJ0C-612010

Page: 8

SITE # AGENCY & ID# ENVIRONMENTAL RISK SITE AND DIRECTION FROM SUBJECT PROPERTY

11/23/92

-----

WITHIN 1/2 TO 1 MILE:

55	ASPIS 01410002 Status Code:	A C TRANSIT - EMERYVILLE 45TH STREET & SAN PABLO AVENUE OAL: Other Agency Lead.	EMERYVILLE 94608	Direction: SW
57	ASPIS 01350016	ACCURATE MANUFACTURING 4770 SAN PABLO AV	EMERYVILLE 94608	Direction: W
	Status Code:	NFA: No Further Action.		
59	ASPIS	J R WATSON ASSOCIATES	OAKLAND	
	01500055	1133 55TH ST	94609	Direction: W
	Status Code:	NFA: No Further Action.		
59	ASPIS	GENERAL CLEANERS	OAKLAND	
	01720033	5426-28 SAN PABLO AV	94612	Direction: W
	Status Code:	NFA: No Further Action.		

### LIMITATIONS OF INFORMATION:

This report is provided under a subscription agreement with VISTA Environmental Information, Inc. and is subject to all the terms, conditions and limitations thereof. VISTA does not warrant the accuracy or completeness of the information.

> For More Information Call: (c) VISTA Environmental Information, Inc. (619) 450-6100

Agency	City	Zip	St #	Street Name	Site Name	NFA?
CERCLIS	EMERYVILLE	94608	1520	POWELL ST	AMERICAN BITUMALS & ASPHALT	NO
CERCLIS	OAKLAND	94621		727-66TH AVE.	ALLIED CRAIN, INC.	NO
CERCLIS	OAKLAND	94623		NAVAL SUPPLY CENTER OAKLAND	NAVY PUBLIC WORKS CENTER SAN FRANCIS	NO
CERCLIS	OAKLAND	94621		OAKLAND ARPT	PACIFIC AIRMOTIVE	NO
CERCLIS	OAKLAND	94621		OAKLAND ARPT	GOLDEN GATE AVIATION	МО
CERCLIS	OAKLAND	94621		OAKLAND ARPT	BUSINESS AIRCRAFT DISTR	NO
AWP	OAKLAND	•		CODE 6 BUILDING 322	OAKLAND NAVAL SUPPLY CENTER	-
ASPIS	OAKLAND	94625		CODE 6 BUILDING 322	OAKLAND NAVAL SUPPLY CENTER	NO
ASPIS	OAKLAND	94607		MARKET BETWEEN 1ST AND GROVE STREET	PG&E - OAKLAND	NO
ASPIS	OAKLAND	94626		PORT OF OAKLAND	OAKLAND ARMY BASE	NO
ASPIS	OAKLAND	94626		TULAGI ST.	OAKLAND ARMY BASE, WAREHOUSE AREA	NO
ASPIS	BERKELEY	94703	523	COVENTRY RD	DISCO CORPORATION	Y
ASPIS	BERKELEY	94703		GROVE ST	IMPAC PHOTO #2	Y
ASPIS	EMERYVILLE	94608		CHRISTIE #405	INTERMODAL TRANSPORTATION SERVICE	Y
ASPIS	OAKLAND	94623	1819	10TH	IRVING SUBWAY - DIVISION OF HARSCO	Y
ASPIS	OAKLAND	94607	2588	GROVE ST	PETER LEAF CABINET MAKER	Y
ASPIS	OAKLAND	94614		HANGER #5, OAKLAND INTERNATIONAL AIRPORT	POWER PAC ENGINEERING CORPORATION	Y
ASPIS	OAKLAND	94614		HANGER #6, OAKLAND INTERNATIONAL AIRPORT	AIR CALIFORNIA	Υ
ASPIS	OAKLAND	94611	4139	JULIO	ALVAREZ & ORTIZ	Υ
ASPIS	OAKLAND	94602	314	MAPLE ST	SHIELD TERMITE	Y
ASPIS	OAKLAND	94607		MARITIME STREET	GLOBAL INTERNATIONAL FORWARDERS	Y
ASPIS	OAKLAND	94621		OAKLAND INTERNATIONAL AIRPORT, BLDG 118	BUSINESS AIRCRAFT DISTRIBUTORS	Y
ASPIS	OAKLAND	94621		OAKLAND INTERNATIONAL AIRPORT, BLDG L230	PACIFIC AIRMOTIVE	Y
ASPIS	OAKLAND	94621		OAKLAND INTERNATIONAL AIRPORT, BLDG L310	GOLDEN GATE AVIATION	Y
ASPIS	OAKLAND	94662		PO BOX 8722	STAND COMPANY INDUSTRIES	Υ
LUST 2	OAKLAND				OAKLAND ARMY BASE	NO
LUST 2	OAKLAND			11TH ST	UNKNOWN	NO
LUST 2	OAKLAND			11TH ST	UNKNOWN	NO
LUST 2	DAKLAND			11TH STREET	UNKNOWN	NO
LUST 2	DAKLAND		190	96TH AVE	MOUIS DRAZAGE CO.	NO
LUST 2	DAKLAND	94621		ASR #9 FACILITY	FAA AIRWAY FACILITY	NO
LUST 2	DAKLAND		1	EARHART RD	NATIONAL AIRMOTIVE	NO
LUST 2	DAKLAND		İ	EARHART RD	NATIONAL AIROMOTIVE	NO
LUST 2	DAKLAND	94621	ĺ	N/A L-827 TRACON	FAA AIRWAY FACILITIES	NO
LUST 2	DAKLAND		1	OAKLAND AIRPORT	AVIS RENT A CAR	NO
.UST 2	DAKLAND		(	DAKLAND AIRPORT	AVIS RENT A CAR	NO
.ust 2	DAKLAND		(	DAKLAND INTN'L AIR	CHEVRON	NO
ust 2	DAKLAND		(	DAKLAND INTN'L AIR	CHEVRON	NO
JUST 2	DAKLAND		(	DAKPORT ST	EGMUD	NO

#### Mentions for report 3 - RISJOC - 612010

Agency	City	Zip	St #	Street Name	Site Name	NFA?
					***************************************	- +
LUST 2	OAKLAND			OAKPORT ST	EBMUD	NO
LUST 2	OAKLAND			PETROLEUM ST	MOBIL	NO
LUST 2	OAKLAND			PETROLEUM ST	MOBIL	ΝО
LUST 2	OAKLAND			PINE ST	SOUTHERN PACIFIC	NO
LUST 2	OAKLAND			PINE ST	SOUTHERN PACIFIC	NO
LUST 2	OAKLAND			PORT OF OAKLAND	MOBIL BULK PLANT	NO
LUST 2	OAKLAND			PORT OF OAKLAND	MOBIL BULK PLANT	NO
LUST 2	OAKLAND			PRIVATE RD	SOUTHERN PACIFIC	NO
LUST 2	OAKLAND			TERMINAL FACILITY	SHELL	NO
LUST 2	OAKLAND			TERMINAL FACILITY	SHELL	NO
LUST 2	OAKLAND			TERMINAL FACILITY	SHELL	NO
LUST 2	OAKLAND			TIDEWATER AVE	TIDEWATER BUSINESS PARK	NO
LUST 2	OAKLAND			TIDEWATER AVE	TIDEWATER BUSINESS PARK	NO
LUST 2	OAKLAND			VALDEZ & 13TH	OLD OAKLAND TRIBUNE GARAGE	NO
LUST 2	OAKLAND			VALDEZ & 13TH	OLD OAKLAND TRIBUNE GARAGE	NO
LUST 2	OAKLAND			VALDEZ & 13TH	OLD OAKLAND TRIBUNE GARAGE	NO

NFA code descriptions:

"-" indicates the agency did not supply this information; "Y" indicates there was "No Further Action" planned for the site (ASPIS/CAL-SITES) or "Case Closed" (LUST); "NO" indicates the agency did not mark the site "No Further Action" or "Case Closed", but does supply this information. For the CERCLIS database a "Y" indicates that all CERCLIS events for the site show an actual completion date and the most recent event indicates "no further remedial action planned."

D. . . 4 . . 1 A

# KEY TO TERMS/ABBREVIATIONS USED IN THIS REPORT:

N/A:

An entry having "N/A" in this field indicates no information available at this time.

MAP ID NO:

An entry having "--" in this field indicates a site, possibly in the radius, currently under investigation. The source agency was unable to provide sufficient locational information.

CERCLIS:

\* NFA FLAG - An entry indicating "N" means "No Further Action" is currently contemplated by U.S. EPA at this site.

## \* EVENT TYPE - Evaluation and disposition information:

Grants DS = Discovery CR = Remedial Community Relations PA = Preliminary Assessment RD = Remedial Design SI - Site Inspection FP = Forward Planning Activity ES = Expanded Site Inspection (for Historical Purposes only) SE = Site Access FM = Forward Planning/Management Assistance HR = Final Hazard Ranking Determined RM = RAMP -- Remedial Action Master Plan NP = Proposal to NPL (for Historical Purposes only) NR = Removed from Proposed NPL IM = Initial Remedial Measure NF = Final Listing on NPL RA = Remedial Action ND = NPL Deletion Process LA = Long-Term Response PD = Public Comments on Deletion Package Removal Activities (All Leads) EO = EDD PR = Planned Removal NA = NAA IR = Immediate Removal RO = ROD RV = Removal Action RC = Removal Community Relations Other Events UR = Underground Storage Tank Removal EV = Evacuation State/local TR = Temporary Relocation Remedial Activities (All Leads) TO = Topographical Mapping UP = RI/FS Workplan Approved by HQ TA = Technical Assistance co = Combined RI/SI DA = Design Assistance RI = Remedial Investigation (Primarity for Historical Purposes only) MA = Management Assistance OM = Operations and Maintenance fs = Feasibility Study (Primarily for Historical Purposes only) OS = Oversight of State by Fund ED = Endangerment Assessment ER = Expedited Response Action GS = Geophysical Support/Mapping CT = Community Relations Technical Assistance HA = Health Assessment TG = Community Relations Technical Assistance AS = Aerial Survey LR = Long-Term Response OH = Other Event

\* <u>REGIONAL UTILITY DESCRIPTION</u> - Provides information developed by U.S. EPA's regional office about the nature of contamination at a specific site.

## NPL:

\* NPL/STATUS INDICATOR -

"P" - Proposed for inclusion on the NPL.

"F" - Site qualified to receive CERCLA remedial funding.

"D" - Deleted from final NPL.

"R" - Removed from the proposed NPL and no longer considered for the final NPL.

"O"- Non-site indicator - not a valid site as defined in CERCLIS.

"S" - Has SCAP plan remedial activities.

"N" - Not currently nor formerly on proposed or final NPL.

#### NPL continued...

\* <u>SITE DESCRIPTION</u> - Provides a brief explanation of the contaminants and circumstances of a particular site.

### CORTESE:

- \* <u>SOURCE</u> Identifies which agency reported the site for publication in the Hazardous Waste and Substances Sites List. Codes for each agency are Identified on the original report page for the Hazardous Waste and Substances Sites List.
- \* <u>PROBLEM</u> Identifies the cause/source of the contamination or the facility affected.

### BEP:

\* <u>SITE INFORMATION</u> - Provides a brief description of the hazardous wastes on the site, the potential threat to public health and the status of the site.

# ASPIS:

- STATUS CODE Indicates the current status of a site and whether it is scheduled for further investigation by DHS Toxic Substances Control Division.
  - \* <u>SUPFD</u> Site is listed on the California BEP or the Federal National Priorities List.
  - \* <u>UNR</u> "Unresolved Sites" will be investigated by DHS to determine whether contamination exists on site.
  - \* SSR Site screening required.
  - \* PAL Preliminary assessment required low priority.
  - \* PAM Preliminary assessment required medium priority.
  - \* PAH Preliminary assessment required high priority.
  - \* SIRL Site inspection required low priority.
  - \* <u>SIRM</u> Site inspection required medium priority.
  - \* SIRH Site inspection required high priority.
  - \* <u>RENF</u> Site has been referred to a TSCP enforcement unit for follow-up.
  - \* <u>REF</u> Are those sites which have been formerly referred to another agency.

## ASPIS continued...

- \* PDS "Pending Status" site is currently undergoing investigation or mitigation activities by DHS, RWQCB, US EPA, or a local regulatory agency.
- \* NFA "No Further Action" means that the preliminary assessment indicates that no hazardous substances/wastes were ever used/produced on site or that such materials were used/produced at low volumes that would have a minimal impact or that all contamination has been mitigated. These determinations were not made via sampling and were made as a result of file surveys and "windshield surveys".
- \* RSM "Referred to Site Mitigation Sites" are those sites in which the site inspection shows on site contamination. Hazard Ranking Score is required and the site will be considered for the Bond Expenditure Plan.

### **HWIS:**

\* GEN/TSD - Indicates whether the listed facility is a generator of hazardous waste or is a treatment, storage or disposal facility.

# LUST:

## \* SUBSTANCE CODES

MOTOR OIL = 08 BOILER FUEL = 09 #6 FUEL OIL # 10 HEATER FUEL = 12 SOLVENTS = 13 HYDRAULIC OIL = 14 WASTE WATER = 32 MINERAL SPIRITS = 41 PAINT THINNER = 49 OIL\GREASE WASTE = 51 DRY CLEANING SOLVENT = 52 WATER WASTE OIL MIX = 61 LUBRICATING OIL = 71 HYDROCARBONS = 76 COOLANT = 77 ALIPHATIC HYDROCARBONS = 78 TRANSMISSION FLUID = 80 LACQUER THINNER # 84 NAPTHA DISTILLATE = 101 V,MEP NAPTHA # 116

CUTTING OIL = 122 #5 FUEL OIL = 127 CHLORINATED HYDROCARBONS = 142 FREON = 171 ALCOHOL = 172 UNLEADED GASOLINE = 12031 REGULAR GASOLINE = 12032 PREMIUM GASOLINE = 12033 DIESEL = 12034 WASTE OIL = 12035 MISC. VEHICLE FUEL = 12036 CYANIDES, SALTS = 57125 ETHYL ALCOLHOL = 64175 ACETIC ACID = 64197 METHYL ALCOLHOL = 67561 ISOPROPYL ALCOHOL = 67630 ACETONE = 67641 BENZENE = 71432 METHYLENE CHLORIDE = 75092 HETHYL ETHYL KETONES = 78933

TCE = 79016 PSEUDODOCUMENE = 95636 XYLENE = 106423 ETHYLENE DICHLORIDE = 107062 TOLUENE = 108883 TETRAHYDROFURAN = 109999 PERCHLORETHYLENE = 127184 DINITROTOLUENES = 610399 NICKEL OXIDE = 1313991 PCB = 1336363 LEAD = 7439921 NICKEL = 7440020 COPPER = 7440508 CRUDE OIL (HAZ.) = 8002059 GASOLINE = 8006619 COAL TAR = 8007452 KEROSENE = 8008206 STODDARD SOLVENTS = 8052413 ASPHALT = 8052424 POLYESTER RESIN = 25037665

# \* CASE TYPE CODES

- D One or more domestic or municipal supply wells have been contaminated.
- G Ground water has been affected.
- S Only soil has been affected.
- U The type of resources affected or extent of the resources affected are not known.

. 1 1 farmer in Can Blanc Colifornia

#### LUST continued...

### \* STATUS CODES

Remodial action (cleanup) in progress. C

- No funds available (no responsible party or responsible party has insufficient funds, and no public f funds available).
- Site investigation in progress (defining extent of problem). 1
- No action taken by lead agency (i.e., new case or backlog). N

Post remedial action monitoring in progress. P

- Remedial action alternative evaluation in progress. R
- Signed off: remedial action completed or deemed unnecessary. S

0 No Action

No action has been taken by the responsible party after the initial report of the leak.

Leak Being Confirmed 1

A leak is suspected at a site, includes inspection of the excavation, and tank and appurtenant plumbing to determine existence of leak.

Preliminary Site Assessment Workplan Submitted 34

A workplan/proposal has been requested of, or submitted by, the responsible party in order to determine whether groundwater has been, or will be, impacted as a result of a release from any underground tanks or associated piping.

Preliminary Site Assessment Underway 38

implementation of a workplan addressing the above described tasks.

5C Pollution Characterization

Responsible party is in the process of installing additional monitoring wells and or borings in order to fully define the lateral and vertical extent of contamination in soil and ground water and assess the Hydrogeology of the area. This phase of work may also include performing aquifer tests, soil gas surveys, continued ground water gradient determinations and monitoring, assessing impacts of surface and/or ground water.

5R Remediation plan

A remediation plan has been submitted evaluating long term remediation options. A proposal and implementation schedule for an appropriate remediation option has also beeen submitted. This phase of work may also include preparing and submitting the necessary information for any permits needed prior to implementation of the plan (NPDES or WDR).

Remedial Action 7

Implementation of corrective action plan.

8 Post Remedial Action Monitoring

Periodic ground water or other monitoring at the site, as necessary, in order to verify and/or evalutate the effectiveness of remedial activities.

9 Case Closed

The Regional Board and the Local Agency are in concurrence that no further work is necessary at the site.

## \* REMEDIAL ACTION CODES

- Containment Barrier -- install vertical dike to block horizontal movement of contaminant. CB
- Cap Site -- install horizontal impermeable layer to reduce rainfall infiltration. CD
- Excevate and Dispose -- remove contaminated soil and dispose in approved site. ED
- Excevate and Treat -- remove contaminated soil and treat (includes spreading or land farming), ET
- Remove free Product -- remove floating product from water table. FP
- Pump and Treat Ground Water -- generally employed to remove dissolved contaminants. GT
- HU treatment at Hookup -- install water treatment devices at each dwelling or other place of use.
- Enhanced Biodegradation -- use of any available technology to promote bacterial decomposition of 31
- No Action Required -- incident is minor, requiring no remedial action. NA
- No Action Taken -- no indication that action was taken. NT
- Replace Supply .. provide alternative water supply to affected parties. 29
- UK Unknown -- action not known, or unknown if action taken.
- ٧E Vapor Extraction
- Vent Soil -- bore holes in soil to allow volatilization of contaminants. VS, VT

### **COUNTY:**

Hazardous Haterials Accepted (No Radioactivity) Class I

Mixed Municipal rubbish Class II

Class III Solid waste (concrete) Type DB Debris Basin Type if Landfill Class LV Large Volume transfer station

Small Volume transfer station Type IS Transfer Station Class SV

NOTE: ALL DESIGNATIONS ARE SUBJECT TO CHANGE.

# APPENDIX B PREVIOUS WORK



January 27, 1993 61035.05

#### PREVIOUS WORK

### Waste-Oil Tank Removal

Previous work performed by Crosby and Oberton (C&O) and Erico Construction at the site included removal of a waste-oil tank and laboratory analyses of a soil sample from the bottom of the waste-oil tank pit on June 1, 1987, additional excavation and laboratory analyses of soil from the waste-oil tank pit on June 3, 1987, and June 10, 1987. Soil excavated from the waste-oil tank pit was transported to the Class I landfill in Casmalia, California on June 10, 1987, by Erico Construction and C&O.

## Initial Subsurface Investigation

In December 1991, an initial subsurface investigation related to the former waste-oil tank was conducted (RESNA, December 1992). The investigation included drilling four onsite borings (B-1 through B-4) and installing three 4-inch diameter groundwater monitoring wells (MW-1 through MW-3) in borings B-1 through B-3 in the immediate vicinity of the former waste-oil tank.

Soil samples with the greatest concentrations of TPHg were taken from borings B-1 and B-2 and indicated concentrations of 470 and 740 ppm, respectively, at a depth of approximately 17 feet below ground surface within the sandy gravel unit. The greatest concentrations of TPH as diesel (TPHd) in soil were also detected in the same sample interval (17 feet below ground surface) in borings B-1 and B-2 at concentrations of 370 and 540 ppm, respectively; however, the laboratory reported that the samples' matrix contained high boiling point fuel mixtures which were calculated as diesel, but could also be weathered gasoline. See Table B-1, Cumulative Results of Soil Samples.

Analytical results of water samples indicated concentrations of 20,000 ppb TPHg and 3,200 ppb TPHd in well MW-3, 8,400 ppb TPHg and 230 ppb TPHd in well MW-2, and 790 ppb TPHg in well MW-1. The laboratory reported that the samples' matrix contained high boiling point fuel mixture which was calculated as diesel, but could also be weathered gasoline. See Table B-2, Cumulative Results of Water Samples.

During the Second Quarter 1992 Quarterly Groundwater Monitoring, 0.55 feet of floating product was detected in well MW-2.



January 27, 1993 61035.05

The interpreted extent of hydrocarbon impacted soil detected during the subsurface investigation in the vicinity of the former waste-oil tank pit is graphically presented on the Geologic Cross Sections, Plate 2A. The locations of the geologic cross-sections are shown in horizonal view on Plate 1A, General Site Plan. Analytical results of soil and groundwater indicated concentrations of diesel. According to ARCO, diesel has never been stored at the site and the diesel detected in soil and groundwater may be whethered gasoline.



January 27, 1993 61035.05

# TABLE B-1 RESULTS OF LABORATORY ANALYSES OF SOIL SAMPLES ARCO Station 6148 Oakland, California

Sample ID	TPHg	TPHd	В	T	E	X	TOG	
S-17½-B1	470	370	2.3 [1.3]	5.1 [1.8]	5.1 [1.8]	24 [8.8]	<30	
S-2214-B1	< 1.0	< 1.0	0.010	< 0.0050	< 0.0050	< 0.0050	<30	
S-261/2-B1	2.0	< 1.0	0.026	0.014	0.011	0.049	< 30	
S-12-B2	< 1.0	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	<30	
S-17-B2	740	540	2.3 [4.3]	13 [92]	7.7 [57]	41 [360]	< 30	
S-251/2-B2	< 1.0	< 1.0	0.015	0.016	< 0.0050	0.019	< 30	
5-30½-B2	< 1.0	< 1.0	0.015	0.0080	< 0.0050	< 0.0050	< 30	
5-10½-B3	< 1.0	< 1.0	0.0070	< 0.0050	< 0.0050	< 0.0050	<30	
5-171⁄2-B3	320	230	0.65	0.65	2.3	5.9	< 30	
-261/2-B3	< 1.0	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	< 30	
5-10½-B4	< 1.0	< 1.0	< 0.0050	< 0.0050	< 0.0050	< 0.0050	< 30	
-1514-B4	<1.0	< 1.0	0.010	< 0.0050	< 0.0050	< 0.0050	< 30	
5-18½- <b>B</b> 4	65	41	0.42 [0.46]	0.22 [0.24]	0.54 [1.7]	0.77 [3.2]	< 30	
5-20-B4	<1.0	< 1.0	0.0070	< 0.0050	< 0.0050	< 0.0050	< 30	
5-1220-SP-(A-D)	25	11	0.11	0.14	0.11	0.38	< 30	

All results shown in parts per million (ppm)

TPHg: Total petroleum hydrocarbons as gasoline by EPA method 5030/8015/8020.

TPHd: Total petroleum hydrocarbons as diesel by EPA method 3550/8015. Laboratory reported samples matrix contained high boiling point fuel mixture calculated as diesel, possibly weathered gasoline.

B: Benzene, T: Toluene, E: Ethylbenzene, T: Total Xylene isomers;

BTEX: Measured by EPA method 8030/8015/8020.

TOG: Total oil and grease by Standard Method 5520 E&F.

[]: BTEX detected using EPA Method 8240.

<: Results reported as less than the detection limit.



January 27, 1993 61035.05

# TABLE B-2 CUMULATIVE RESULTS OF LABORATORY ANALYSES OF WATER SAMPLESTPHg, TPHd, BTEX, TOG, and Metals ARCO Station 6148 Oakland, California

WELL DATE	ТРН	TPHd	В	Т	E	Х	Cd	Cr	Pb	Ni	Zn	тоб
<u>MW-1</u>				-								
03/18/92	790	< 50	310	26	12	44	<3	5	3	< 20	31	<0.5 (1.4)
06-12-92	1,000	< 50	290	15	10	30	NA	NA	NA	NA	NA	< 0.5
09-14-92	1,000	<80*	370	6.5	6.5	17	NA	NA	NA	NA	NA	0.9
MW-2												
03/18/92	8,400	230**	1,400	1,000	220	870	< 3	21	9	38	54	1.2 (3.0)
06/12/92				N	ot sampl	edfloat	ing prod	uct				(5.0)
09/14/92						ledfloat	~ .					
MW-3												
03/18/92	20,000	2,800**	3,200	560	380	1,000	<3	67	27	113	156	7.8
04 110 100	44 000		2.400	4.200	1.300	5 400	NIA	N1 A	NIA	814	<b>N1</b> A	(8.1)
06/12/92		1,600**		4,200	1,300	5,400	NA	NA	NA	NA	NA	16
09/14/92	53,000	40,000**	4,300	5,700	1,300	7,300	NA	NA	NA	NA	NA	5.5
MCL:			1		680	1,750	10	50	50			
DWAL:				100								

Results in parts per billion (ppb), except TOG which is in parts per million (ppm).

TPHg: Total petroleum hydrocarbons as gasoline by EPA method 5030/8015/8020.

TPHd: Total petroleum hydrocarbons as diesel by EPA method 3510/California DHS LUFT Method.

B: benzene, T: toluene, E: ethylbenzene, X: total xylenes isomers

BTEX: Analyzed by EPA method 5030/8020/DHS LUFT Method.

TOG: Total oil and grease by Standard method 5520C&F (on 09/14/92 by EPA Method 418.1)

(): Concentrations in parentheses were results of Method 5520C.

: Raised MRL due to insufficient sample quantity.


Metals: By EPA method 6010 and 7421.

<: Results reported below the laboratory detection limit.

••: Laboratory reported sample contains a lower boiling point hydrocarbon mixture quantified as diesel. The chromatogram does not match the typical diesel fingerprint, but appears to be weathered gasoline.

MCL: Adopted Maximum Contaminant Levels in Drinking Water (DHS, October 1990).

DWAL: Recommended Drinking Water Action Level (DHS, October 1990).



#### EXPLANATION

 $\Delta$  —  $\Delta'$  = Geologic cross sections


B-3/MW-3

= Monitoring well (RESNA, December 1991)

8-4 = Soil boring (RESNA, December 1991)

*[[[]]*] =

= Underground storage tanks




Source: Based on John Kock, Surveyor, 11/09/92.



Working to Restore Nature

PROJECT 61035.05

GENERALIZED SITE PLAN ARCO Station 6148 5131 Shattuck Avenue Oakland, California PLATE 1B



# APPENDIX C FIELD METHODS



January 27, 1993 61035,05

#### FIELD METHODS

## Site Safety Plan

The Site Safety Plan (RESNA, June 24, 1991) describes the safety requirements for the evaluation of gasoline hydrocarbons in soil and groundwater at the site. The site Safety Plan is applicable to personnel of RESNA and its subcontractors. RESNA personnel and subcontractors of RESNA scheduled to perform the work at the site were briefed on the contents of the Site Safety Plan before work began. A copy of the Site Safety Plan was available for reference by appropriate parties during the work. The Staff Geologist of RESNA was Site Safety Officer for the project.

## Soil Borings

Prior to the drilling of borings and construction of monitoring wells, permits were acquired from the appropriate regulatory agency. Copies of the permits are included in Appendix A of this report. Prior to drilling, Underground Services Alert was notified of our intent to drill, and known underground utility lines and structures were marked. The borings were drilled by a truck-mounted drill rig equipped with 10 or 12-inch-diameter, hollow-stem augers. The augers were steam-cleaned prior to drilling each boring to minimize the possibility of cross-contamination. After the borings were drilled, monitoring wells were constructed in the borings, or the borings were backfilled to the ground surface with neat-cement grout and bentonite.

Borings for groundwater monitoring wells were drilled to a depth of no more than 20 feet below the depth at which a saturated zone was first encountered, or a short distance into a stratum beneath the saturated zone which was of moisture content and consistency to be judged as a perching layer by the field geologist, whichever was shallower.

## **Drill Cuttings**

Drill cuttings subjectively evaluated for hydrocarbons at levels greater than 100 parts per million (ppm) were separated from those subjectively evaluated for hydrocarbons at levels less than 100 ppm. Evaluation was based either on subjective evidence of soil discoloration, or on measurements made using a field calibrated organic vapor meter (OVM). Readings were taken by placing a soil sample into a ziplock-type plastic bag and allowing volatilization to occur. The intake probe of the OVM was then inserted into the headspace created in the plastic bag immediately after opening it. The drill cuttings from the borings were placed



January 27, 1993 61035.05

on plastic at the site, and covered with plastic. The cuttings were removed to a Sanitary Landfill by ARCO.

### Soil Sampling in Borings

Soil samples were collected at no greater than 5-foot intervals from the ground surface to the total depth of the borings. The soil samples were collected by advancing the boring to a point immediately above the sampling depth, and then driving a California-modified, split-spoon sampler containing brass sleeves through the hollow center of the auger into the soil. The sampler and brass sleeves were laboratory-cleaned, steam-cleaned, or washed thoroughly with Alconox® and water, prior to each use. The sampler was driven with a standard 140-pound hammer repeatedly dropped 30 inches. The number of blows to drive the sampler each successive six inches was counted and recorded to evaluate the relative consistency of the soil.

The samples selected for laboratory analysis were removed from the sampler and quickly sealed in their brass sleeves with aluminum foil, plastic caps, and aluminized duct tape. The samples were then labeled, promptly placed in iced storage, and delivered to a laboratory certified by the State of California to perform the analyses requested.

One of the samples in brass sleeves not selected for laboratory analysis at each sampling interval was tested in the field using an OVM that was field calibrated at the beginning of each day it was used. This testing was performed by inserting the intake probe of the OVM into the headspace created in the plastic bag containing the soil sample as described in the Drill Cuttings section above. The OVM readings are presented in Logs of Borings included in the report.

# Logging of Borings

A geologist was present to log the soil cuttings and samples using the Unified Soil Classification System. Samples not selected for chemical analysis, and the soil in the sampler shoe, were extruded in the field for inspection. Logs include texture, color, moisture, plasticity, consistency, blow counts, and any other characteristics noted. Logs also include subjective evidence for the presence of hydrocarbons, such as soil staining, noticeable or obvious product odor, and OVM readings.



Additional Subsurface Investigation ARCO Station 6148, Oakland, California

January 27, 1993 61035.05

#### Monitoring Well Construction

Monitoring wells were constructed in selected borings using clean 6- and 4-inch-diameter, thread-jointed, Schedule 40 PVC casing. No chemical cements, glues, or solvents were used in well construction. Each casing bottom was sealed with a threaded end-plug, and each casing top with a locking plug. The screened portions of the wells were constructed of machine-slotted PVC casing with 0.020-inch-wide slots for initial site wells. Slot size for subsequent wells will be based on sieve analysis and/or well development data. The screened sections in groundwater monitoring wells were placed to allow monitoring during seasonal fluctuations of groundwater levels.

The annular space of each well was backfilled with No. 2 by 12 sand, to approximately two feet above the top of the screened casing for initial site wells. The sand pack grain size for subsequent wells will be based on sieve analysis and/or well development data. A 1- to 2-foot-thick bentonite plug was placed above the sand as a seal against cement entering the filter pack. The remaining annulus was then backfilled with a slurry of water, neat cement, and bentonite to approximately one foot below the ground surface.

An aluminum utility box with a PVC apron was placed over each wellhead and set in concrete placed flush with the surrounding ground surface. Each wellhead cover has a seal to protect the monitoring well against surface-water infiltration and requires a special wrench to open. The design discourages vandalism and reduces the possibility of accidental disturbance of the well.

#### Groundwater Monitoring Well Development

The monitoring wells were developed by bailing or over-pumping and surge-block techniques. The wells were either bailed or pumped, allowed to recharge, and bailed or pumped again until the water removed from the wells was subjectively evaluated to be clear by the field geologist. The wells were allowed to equilibrate for at least 48 hours after development prior to sampling. Water generated by well development was stored in 17E Department of Transportation (DOT) 55-gallon drums on site and was removed in October 1991 by a state-licensed and ARCO contracted waste hauler under manifest. A copy of the manifest is included in Appendix F, Waste Manifest Forms.

#### Groundwater Sampling

The static water level in each well was measured to the nearest 0.01-foot using a Solinst® electric water-level sounder cleaned with Alconox® and water before use in each well. The



# Additional Subsurface Investigation ARCO Station 6148, Oakland, California

January 27, 1993 61035.05

liquid in the onsite wells was examined for visual evidence of hydrocarbons by gently lowering approximately half the length of a Teflon® bailer (cleaned with Alconox® and water) past the air/water interface. The sample was then retrieved and inspected for floating product, sheen, emulsion, color, and clarity. The thickness of floating product detected was recorded to the nearest 0.1-inch.

Wells which did not contain floating product were purged using a submersible pump. The pump, cables, and hoses were cleaned with Alconox® and water prior to use in each well. The wells were purged until withdrawal was of sufficient volume to result in stabilized Ph. temperature, and electrical conductivity of the water, as measured using portable meters calibrated to standard water solutions. If a purged well became de-watered, the water level was allowed to recover to at least 80 percent of the initial water level. Prior to the collection of each groundwater sample, the Teflon® bailer was cleaned with Alconox® and rinsed with tap water and deionized water, and the latex gloves worn by the sampler changed. Hydrochloric acid was added to the sample vials as a preservative (as required for specific laboratory analysis). A sample-method blank was collected by pouring distilled water into the bailer and then into sample vials. A sample of the groundwater was then collected from the surface of the water in each of the wells using the Teflon® bailer. The water samples were then gently poured into laboratory-cleaned, 40-milliliter (ml) glass vials, 500 ml plastic bottles, or 1-liter glass bottles (as required for specific laboratory analysis) and sealed with Teflon®-lined caps, and inspected for air bubbles to check for headspace. which would allow volatilization to occur. The samples were then labeled and promptly placed in iced storage. A field log of well purging procedures and parameter monitoring was maintained. Water generated by the purging of wells was stored in 17E DOT 55-gallon drums onsite, and was removed and disposed by a state-certified and ARCO approved contractor.

#### Sample Labeling and Handling

Sample containers are labeled in the field with the job number, sample location and depth, and date, and promptly placed in iced storage for transport to the laboratory. A Chain of Custody Record is initiated by the field geologist and updated throughout handling of the samples, and accompanies the samples to a laboratory certified by the State of California for the analyses requested. Samples are transported to the laboratory promptly to help ensure that recommended sample holding times are not exceeded. Samples are properly disposed of after their useful life has expired.

# APPENDIX D WELL CONSTRUCTION PERMIT



## ALAMEDA COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT

5997 PARKSIDE DRIVE

PLEASANTON, CALIFORNIA 94566

(415) 484-2600

## GROUNDWATER PROTECTION ORDINANCE PERMIT APPLICATION

FOR APPLICANT TO COMPLETE	FOR OFFICE USE
LOCATION OF PROJECT ARCO Station 6148	PERMIT NUMBER 92491
5131 Shattuck Avenue Oakland, CA	LOCATION NUMBER
CLIENT Name ARLO Products Company Address P.O. Box 5811 Phone (415) \$71/243 City Son Mateo Zip 9440Z	Approved Wyman Hong Date 5 Oct 92
Name KESNA Industries INC.	PERMIT CONDITIONS  Circled Permit Requirements Apply
Address 3315 Almadon Exp. Sul Phone (408) 264-7 City Son Juse Zip 95/18	7723 (A.) GENERAL
DESCRIPTION OF PROJECT Water Well Construction Geotechnical Cathodic Protection Well Destruction	<ol> <li>A permit application should be submitted so as tarrive at the Zone 7 office five days prior to proposed starting date.</li> <li>Notify this office (484-2600) at least one days.</li> </ol>
PROPOSED WATER WELL USE  Domestic Industrial Irrigation  Municipal Monitoring Other	prior to starting work on permitted work and before placing well seals.  3. Submit to Zone 7 within 60 days after completion of permitted work the original Department of
PROPOSED CONSTRUCTION Driffing Method: Mud Rotary Air Rotary Auger (hollow Cable Other	water Resources Water Well Drillers Report of equivalent for well projects, or bore hole log and location sketch for geotechnical projects Permitted work is completed when the last surface seal is placed or the last boring is completed.
WELL PROJECTS  Orill Hole Diameter 10 in. Depth(s) 30 ft.  Casing Diameter 4 in. Number  Surface Seal Depth 8 ft. of Wells 4  Driller's License No. C57-484288	4. Permit is void if project not begun within 9 days of approval date.  B. WATER WELLS, INCLUDING PIEZOMETERS  1. Minimum surface seal thickness is two inches o coment grout placed by tremia, or equivalent.  2. Minimum seal depth is 50 feet for municipal an industrial wells or 20 feet for domestic, irriga
GEOTECHNICAL PROJECTS Number Diameterin. Maximum Depthft.	tion, and monitoring wells unless a lesser depth is specially approved.  C. GEOTECHNICAL. Backfill bore hole with compacted cut tings or heavy bentonite and upper two feet with com-
ESTIMATED STARTING DATE 3 NOV 32 ESTIMATED COMPLETION DATE	pacted material.  D. CATHODIC. Fill hole above anode zone with concrete placed by tremie, or equivalent.
I hereby agree to comply with all requirements of this permittand Alameda County Ordinance No. 73-68.	E. WELL DESTRUCTION. See attached.
SIGNATURE DELLE STEEL OF 10/1/92	·
for RESNA	9198

# APPENDIX E WELLHEAD SURVEY

JOHN E. KOCH Land Surveyor CA. State Lic. No. LS4811 5427 Telegraph Ave., Suite A Oakland, CA 94609 (510)655-9956 FAX(510)655-9745

RESNA
3315 Almaden Expressway, Suite 34
San Jose CA 95118
(408) 264-7723
FAX(408) 264-2435



Tabulation of Elevations as of 11:00 a.m. 11/09/92

Job #92090
RESNA Project Job # 61035.05
Project Manager: Joel Coffman
Site: Arco Station 6148
5131 Shattuck Avenue
@ 52nd Street
Oakland, CA

BENCHMARK: #3172 Cut square in top of curb. Northeast end of island, triangle shaped, at east side of crosswalk at Telegraph Avenue and Claremont Avenue.
(Elev.116.271' City of Oakland Datum) \*see note 1.

#### MONITOR WELL DATA TABLE

Well Designation	Elevation	Description
MW-1*	108.03 108.27	Top of P.V.C. Casing Top of Box
MW-2*	107.43 107.70	Top of P.V.C. Casing Top of Box
MW-3*	107.77 108.06	Top of P.V.C. Casing Top of Box
MW-4	106.58 107.18	Top of P.V.C. Casing Top of Box
MW-5	106.68 106.96	Top of P.V.C. Casing Top of Box


JOHN E	. KOCH.	р.	L.	s.	RESNA PROJ.#61035.04	JEK JOB #92090
--------	---------	----	----	----	----------------------	----------------

MW-6	105.16 105.77	Top of P.V.C. Casing Top of Box
MW-7	107.08 107.66	Top of P.V.C. Casing Top Box

<sup>\*</sup> INDICATES WELLS SURVEYED ON 12/27/91 (JEK JOB #91084)

#### NOTES:

- 1. Datum is City of Oakland = (USGS) +3.00
- Top of Casing Elevation (T.O.C.El.) is at set mark on rim of PVC.
- 3. Ground Elevation (Gd. El.) is at set mark on top of box.
- 4. MW-2 was checked and found to be within 0.01' of previous report of 12/27/91.



# APPENDIX F WASTE MANIFEST FORMS

# Dillard Trucking, Inc.

ENVIRONMENTAL SERVICES
P.O. BOX 218 - BYRON, CALIFORNIA 94514
(510) 634-6850 FAX (510) 634-0569

December 10, 1992

RESNA 3315 Almaden Expressway #34 San Jose, CA 94118

Fax# (408)264-2435

Attn: Rob Campbell

Re: Arco Station #6148 - 5131 Shattuck Ave., Oakland - 4 yds drill cuttings

Dear Rob:

Please be advised that the drill cuttings from the above referenced site have been removed. They were taken to BFI Landfill, Livermore on December 1, 1992.

I trust that you will find everything in order. If you have any questions, please do not hesitate to call.

Sincerely,

DILLARD TRUCKING, INC.

Donna L. Pedersen

Estimator

DLP/st

cc: file

## APPENDIX G

## LABORATORY ANALYSES REPORTS CHAIN OF CUSTODY RECORDS

NOV 1 × 1992

**RESNA** 

3315 Almaden Expwy., Suite 34

San Jose, CA 95118 Attention: Joel Coffman

Project: ARCO 6148, Oakland

RESNA SAN JOSE

Enclosed are the results from 16 soil samples received at Sequoia Analytical on October 29,1992. The requested analyses are listed below:

SAMPLE #	SAMPLE DESCRIPTION	DATE OF COLLECTION	TEST METHOD
2104764	Soil, S-9.5-B5	10/27/92	EPA 5030/8015/8020
2104765	Soil, \$-14.5-B5	10/27/92	EPA 5030/8015/8020
2104766	Soil, S-31.5-B5	10/27/92	EPA 5030/8015/8020
2104767	Soil, S-9.5-B8	10/27/92	EPA 5030/8015/8020
2104768	Soil, S-14.5-B8	10/27/92	EPA 5030/8015/8020
2104769	Soil, S-33.5-B8	10/27/92	EPA 5030/8015/8020
2104770	Soil, S-9.5-B6	10/28/92	EPA 5030/8015/8020
2104771	Soil, S-16.5-B6	10/28/92	EPA 5030/8015/8020
2104772	Soil, S-17.5-B6	10/28/92	Particle Size Distrubition by Weight
2104773	Soil, S-19.5-B6	10/28/92	Particle Size Distrubition by Weight
2104774	Soil, S-21-B6	10/28/92	Particle Size Distrubition by Weight
2104775	Soil, S-25-B6	10/28/92	Particle Size Distrubition by Weight
2104776	Soil, S-27.5-B6	10/28/92	EPA 5030/8015/8020
2104777	Soil, S-10-B7	10/28/92	EPA 5030/8015/8020
2104778	Soil, S-15-B7	10/28/92	EPA 5030/8015/8020
2104779	Soil, S-29.5-B7	10/28/92	EPA 5030/8015/8020

Please contact me if you have any questions. In the meantime, thank you for the opportunity to work with you on this project.

Very truly yours,

SEQUOIA ANALYTICAL

Maria Lee Project Manager

2104764.RES <1>



3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman 

Client Project ID: Sample Matrix:

ARCO 6148, Oakland

Soil

Analysis Method: EPA 5030/8015/8020 First Sample #: 210-4764

Sampled: Received: Oct 27, 1992 Oct 29, 1992

Reported:

Nov 11, 1992

### TOTAL PURGEABLE PETROLEUM HYDROCARBONS with BTEX DISTINCTION

Analyte	Reporting Limit mg/kg	<b>Sample</b> <b>I.D.</b> 210-4764 S-9.5-B5	Sample I.D. 210-4765 S-14.5-B5	Sample I.D. 210-4766 S-31.5-B5	Sample I.D. 210-4767 S-9.5-B8	Sample I.D. 210-4768 S-14.5-B8	Sample I.D. 210-4769 S-33.5-B8
Purgeable Hydrocarbons	1.0	N.D.	N.D.	N.D.	N.D.	N.D.	N.D.
Benzene	0.0050	N.D.	0.13	N.D.	N.D.	N.D.	N.D.
Toluene	0.0050	N.D.	N.D.	N.D.	N.D.	N.D.	N.D.
Ethyl Benzene	0.0050	N.D.	N.D.	N.D.	N.D.	N.D.	N.D.
Total Xylenes	0.0050	N.D.	0.0050	N.D.	N.D.	N.D.	N.D.
Chromatogram Pat	tern:	••					

**Quality Control Data** 

Report Limit Multiplication Factor:	1.0	1.0	1.0	1.0	1.0	1.0
Date Analyzed:	11/2/92	11/2/92	11/2/92	11/2/92	11/2/92	11/2/92
Instrument Identification:	GCHP-7	GCHP-7	GCHP-7	GCHP-7	GCHP-7	GCHP-6
Surrogate Recovery, %: (QC Limits = 70-130%)	99	100	98	90	90	100

Purgeable Hydrocarbons are quantitated against a fresh gasoline standard. Analytes reported as N.D. were not detected above the stated reporting limit.

**SEQUOIA ANALYTICAL** 

Maria Lee Project Manager

2104764.RES <1>



3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman 

Client Project ID: Sample Matrix:

ARCO 6148, Oakland

Soil

EPA 5030/8015/8020 Analysis Method: First Sample #:

210-4770

Sampled: Received: Oct 28, 1992 Oct 29, 1992

Reported: Nov 11, 1992

### TOTAL PURGEABLE PETROLEUM HYDROCARBONS with BTEX DISTINCTION

Analyte	Reporting Limit mg/kg	Sample 1.D. 210-4770 S-9.5-86	Sample 1.D. 210-4771 S-16.5-B6	Sample 1.D. 210-4776 S-27.5-B6	Sample i.D. 210-4777 S-10-B7	Sample I.D. 210-4778 S-15-B7	Sample I.D. 210-4779 S-29.5-B7
Purgeable Hydrocarbons	1.0	N.D.	190	N.D.	N.D.	N.D.	N.D.
Benzene	0.0050	N.D.	0.24	N.D.	N.D.	N.D.	N.D.
Toluene	0.0050	N.D.	0.55	N.D.	N.D.	N.D.	N.D.
Ethyl Benzene	0.0050	N.D.	1.0	N.D.	N.D.	N.D.	N.D.
Total Xylenes	0.0050	N.D.	1.3	N.D.	N.D.	N.D.	0.025
Chromatogram Pat	tern:		Gas & Non-Gas Mix C4 - C12		••		

**Quality Control Data** 

Report Limit Multiplication Factor:	1.0	5.0	1.0	1.0	1.0	1.0
Date Analyzed:	11/2/92	11/2/92	11/2/92	11/2/92	11/2/92	11/2/92
Instrument Identification:	GCHP-7	GCHP-7	GCHP-7	GCHP-7	GCHP-1	GCHP-6
Surrogate Recovery, %: (QC Limits = 70-130%)	90	122	86	87	72	107

Purgeable Hydrocarbons are quantitated against a fresh gasoline standard. Analytes reported as N.D. were not detected above the stated reporting limit.

SEQUOIA ANALYTICAL

Project Manager

2104764.RES <2>



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063 (415) 364-9600 • FAX (415) 364-9233

RESNA 3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman

Client Project ID: Sample Descript: Soil, S-17.5-B6

Lab Number:

ARCO 6148, Oakland

Sampled: Received:

Oct 28, 1992 Oct 29, 1992@

Analyzed: Nov 10, 1992 Nov 11, 1992 Reported:

### PARTICLE SIZE DISTRIBUTION BY WEIGHT

210-4772

Seive # Tyler Sieve Units		<b>Weight</b> grams		Percent Distribution
_		66.5		38.4
5	***************************************	8.0		4.6
6	4:>143944105433944441344394494444444444444444444444		***************************************	4.2
7	***************************************	7.4	***************************************	
9	***************************************	13.7	14-24-54-4-54-4-4-4-4-4-4-4-4-4-4-4-4-4-4	7.9
		7.4		4.3
10		6.7		3,9
12	***************************************		***************************************	6.5
16	*************************************	11.7	***************************************	_
24	454545454544444444444444444444444444444	10.3	***************************************	6.0
		5.9	***************************************	3.4
28	***************************************	5.2		3.0
32		_	***************************************	4.3
42	*************************************	7.4	***************************************	2.1
48	***************************************	3.6	***************************************	
80		7.0	***************************************	4.0
	***************************************	4.3	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	2.5
120	***************************************			2.3
200		3.9	***************************************	2.5
Pan	***************************************	4.3	***************************************	٤,۵

**SEQUOIA ANALYTICAL** 

Project Manager

RESNA 3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman

Client Project ID: ARCO 6148, Oakland

Sample Descript: Soil, S-19.5-B6

Lab Number: 210-4773 Sampled: Oct 28, 1992

Oct 29, 1992 Received: Analyzed: Nov 10, 1992 Nov 11, 1992 Reported:

#### PARTICLE SIZE DISTRIBUTION BY WEIGHT

Seive # Tyler Sieve Units		<b>Weight</b> grams		Percent Distribution
5	***************************************	33.6	,	24
6	1010464124742474247424741742274174244747474747	5.0	***************************************	3.6
7	422444444444444444444444444444444444444	5.6	***************************************	4.0
9	***************************************	9.6	,	6.8
10		6.3	***************************************	4.5
12	*******************************	5.8	***********************	4.1
16	***************************************	10.9	***************************************	7. <del>9</del>
24	***************************************	9.1		6.5
28	**************************************	6.1	**!************************************	4.3
32	***************************************	4.0		2.8
42		7.7		5.5
48	***************************************	5.1	***************************************	3.6
80	***************************************	13.0	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	9.2
120		6.0		4.5
200	<b>*************************************</b>	6.0		4.3
Pan		6.8		4.8

SEQUOIA ANALYTICAL

Maria Lee Project Manager

2104764.RES <4>



RESNA 3315 Almaden Expwy., Suite 34

San Jose, CA 95118 Attention: Joel Coffman Lab Number:

Client Project ID: ARCO 6148, Oakland

Sample Descript: Soil, S-21-B6

Oct 28, 1992 Sampled: Received: Analyzed:

Oct 29, 1992 Nov 10, 1992 3 Nov 11, 1992 Reported:

#### PARTICLE SIZE DISTRIBUTION BY WEIGHT

210-4774

Seive # Tyler Sieve Units		<b>Weight</b> grams		Percent Distribution
5		0.92	***************************************	0.61
6		1.3		0.87
7	***************************************	9.6		1.7
9		9.2	**************************************	6.1
10	***************************************	6.7	494942744944444444444444444444444444444	4.5
12		7.8	***************************************	5.2
16	***************************************	13.9	14.44/0000000000000000000000000000000000	9.2
24		11.0	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	7.3
28	***************************************	5.6	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	3.7
32		3.9		2. <del>6</del>
42		5.6		3.8
48	***************************************	4.2		2.8
80		10.9		7.3
120		17.5		11.7
200	***************************************	24.0		16.0
Pan	***************************************	25.0	***************************************	16.7

**SEQUOIA ANALYTICAL** 

Project Manager

2104764.RES <5>



RESNA 3315 Almaden Expwy., Suite 34

Client Project ID: Sample Descript: ARCO 6148, Oakiand

Sampled: Oct 28, 1992 Received: Oct 29, 1992

San Jose, CA 95118

Sample Descript: Soil, S-25-B6

Analyzed: Nov 10, 1992 Reported: Nov 11, 1992

Attention: Joel Coffman

Lab Number: 210-4775

#### PARTICLE SIZE DISTRIBUTION BY WEIGHT

Seive # Tyler Sieve Units		<b>Weight</b> grams		Percent Distribution
5		4.7	***************************************	3.3
6	***************************************	2.4	***************************************	1.7
7	***************************************	2.3		1.6
9	***************************************	9.4	***************************************	6.7
10	++++++++++++++++++++++++++++++++++++++	8.2		5.9
12		8.8		6.2
16		16.7	***************************************	11.8
24	4424244444444444444444444	16.8	***************************************	11.8
28		4.4	***************************************	3.1
32		4.3	***************************************	3.0
42		9.4	***************************************	6.6
48	[PADPIDGD4[PADPIDGD4D4[PADAIPADAIPADAIPADAIPADAIPADAIPADAIPADA	3.7	***************************************	2.6
80	***************************************	12.4		8.7
120		7.9	***************************************	5.5
200		12.7	***************************************	9.0
Pan	(**************************************	17.8		12.6

SEQUOIA ANALYTICAL

Maria Lee Project Manager

2104764.RES <6>



Client Project ID: ARCO 6148, Oakland

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman QC Sample Group: 2104764-71, 76-9 Reported: Nov 11, 1992

#### **QUALITY CONTROL DATA REPORT**

ANALYTE			Ethyl-	
	Benzene	Toluene	benzene	Xylenes
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020
Analyst:	R. Lee	R. Le∌	R. Lee	R. Lee
Reporting Units:	mg/kg	mg/kg	mg/kg	mg/kg
Date Analyzed:	Nov 2, 1992	Nov 2, 1992	Nov 2, 1992	Nov 2, 1992
QC Sample #:	GBLK110292	GBLK110292	GBLK110292	GBLK110292
Sample Conc.:	N.D.	N.D.	N.D.	N.D.
Sample Conc	14.0.	14.5.	,	
Spike Conc.				
Added:	0.20	0.20	0.20	0.60
Conc. Matrix		2.22	0.00	0.66
Spike:	0.22	0.22	0.22	0.66
an it outle				
Matrix Spike % Recovery:	110	110	110	110
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				
Conc. Matrix				
Spike Dup.:	0.23	0.23	0.22	0.67
Matrix Spike				
Duplicate		446	110	112
% Recovery:	115	115	110	112
Dalati				
Relative % Difference:	4.4	4.4	0.0	1.5
/ Differences	•••			

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

**SEQUOIA ANALYTICAL** 

Maria Lee Project Manager

% Recovery:	Conc. of M.S Conc. of Sample	x 100	<u></u>
_	Spike Conc. Added		
Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100	
	(Conc. of M.S. + Conc. of M.S.D.) / 2	•	
			2104764.RES <7>



RESNA Client Project ID: ARCO 6148, Oakland

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman 

QC Sample Group: 2104764-71, 76-9

Reported: Nov 11, 1992

#### **QUALITY CONTROL DATA REPORT**

ANALYTE			Ethyl-	
	Benzene	Toluene	benzene	Xylenes
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020
Analyst:	B. Ali	B. Ali	B. Ali	B. Ali
Reporting Units:	mg/kg	mg/kg	mg/kg	mg/kg
Date Analyzed:	Nov 2, 1992	Nov 2, 1992	Nov 2, 1992	Nov 2, 1992
QC Sample #:	GBLK110292	GBLK110292	GBLK110292	GBLK110292
·	MS/MSD	MS/MSD	MS/MSD	MS/MSD
Sample Conc.:	N.D.	N.D.	N.D.	N.D.
Spike Conc.				
Added:	0.20	0.20	0.20	0.60
Conc. Matrix				
Spike:	0.19	0.18	0.19	0.55
•				
Matrix Spike				
% Recovery:	95	90	95	92
a necovery.	55	00	00	<b>-</b>
A Makete				
Conc. Matrix	0.00	0.19	0.20	0.58
Spike Dup.:	0.20	0.19	0.20	0.56
Matrix Spike				
Duplicate				
% Recovery:	100	95	100	97
Relative			•	
% Difference:	5.1	5.4	5.1	5.3

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

**SEQUOIA ANALYTICAL** 

Project Manager

% Recovery:	Conc. of M.S Conc. of Sample	x 100	
_	Spike Conc. Added		
Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100	
-	(Conc. of M.S. + Conc. of M.S.D.) / 2		
		· · · · · · · · · · · · · · · · · · ·	2104764.RES <8>



ŔĔŚŃĂ

Client Project ID: ARCO 6148, Oakland

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman QC Sample Group: 2104764-71, 76-9 QC Sample Group: 2104764-71, 76-9

Reported: Nov 11, 1992

#### QUALITY CONTROL DATA REPORT

ANALYTE			Ethyl-	-
	Benzene	Toluene	benzene	Xylenes
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020
Analyst:	C. Donohue	C. Donohue	C. Donohue	C. Donohue
Reporting Units:	mg/kg	mg/kg	mg/kg	mg/kg
Date Analyzed:	Nov 2, 1992	Nov 2, 1992	Nov 2, 1992	Nov 2, 1992
QC Sample #:	GBLK110292	GBLK110292	GBLK110292	GBLK110292
	MS/MSD	MS/MSD	MS/MSD	MS/MSD
Sample Conc.:	N.D.	N.D.	N.D.	N.D.
Caika Cana				
Spike Conc. Added:	0.20	0.20	0.20	0.60
Added:	0.20	0.20	0.20	0.00
Conc. Matrix	<del></del>	0.47	0.47	0.50
Spike:	0.17	0.17	0.17	0.50
Matrix Spike				
% Recovery:	85	85	85	83
-				
Conc. Matrix				
Spike Dup.:	0.18	0.18	0.18	0.51
•				
Matrix Spike				
Duplicate		00	00	0.5
% Recovery:	90	90	90	85
Relative				0.0
% Difference:	5.7	5.7	5.7	2.0

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

**SEQUOIA ANALYTICAL** 

**Project Manager** 

% Recovery:	Conc. of M.S Conc. of Sample Spike Conc. Added	x 100		
Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100		
_	(Conc. of M.S. + Conc. of M.S.D.) / 2			
			2104764.RES <9>	_

RC	TOQ! Division	of Atlantic	RichfieldC	any- ompany	<b>₹</b>			∕Task Or	der No.	67	48	- 0	する		25							- {	Chain of Custo	ody
ARCO Facilit	ty no.	148	_	City	y pility)	Oal	zlond			Project	manag	er	1/9	al "	$\overline{C}$	15	mo	~					Laboratory name	
ARCO Facilit	eer M ı	chre	又 し	shel	m		Telephon	e, no. (4, 5 243	2521-	Telepho	ne no.	(408	3)2	64-	7	Fax	no.	(49	<del>28)</del>	264	- 24	35	Sogovia	. 0
Consultant n	ame 1	750	JA	T- 1	4214	nes	Tare	Address (Consulta	271	5 /	<b>Δ</b>	a do	~ <del>_</del>	Ex	gra	1-1-4	1 Sultai	. s S	<u>_</u>	2.34			Contract number	
			-	Matrix		Preser		T(CONSUMA	ia <b>)</b>		S S						<u> </u>	G ∏ Ego	002/10				Method of shipment	
Sample I.D.	Lab no.	Container no.	Soil	Water	Other	Ice	Acid	Sampling date	Sampling time	BTEX 602/EPA 8020	BTEXITPH CALS	TPH Modified 8015 Gas Diesel	Oil and Grease 413.1 ☐ 413.2 ☐	TPH EPA 418.1/SM503E	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Semi	CAM Metals EPA 601	Lead Org./DHS  Lead EPA 7420/7421	4014			
5-5-135	2	1	X			×		10/27/92													X		Special detection Limit/reporting	
5-5-B5 5-9.5.	135	i	X			X					X			210	1764	1								
602 A	2	سلم	X			A			<b>\</b>												X		<del></del>	
5-14-5		1	X			7					X			210	476	15)							Special QA/QC	
5-20-B	5	1	7			7															X			
5-25-B	5	1	X			X								_							<b>/</b> ×		]	
5-30-13	5-	1	X			X															X		, ,	
5-31.5-	35	1	7			4					$\times$			210	476	6							- Remarks	À .
5-4.5-	38	1	7			7															X		]	
5-9.5-	38		4			7					X			210	471	·7							]	25
5-14-13	8	1_	$\times$			$\succ$															X			
5-14-5-B	છ	1	$\times$			7					X			210	47	68								
5-19.5-		1	1		<u></u>	<b>×</b>															X		Lab number	
5-20-1	<del></del>		7			$\geq$								·							X			
5-25-1		1	7			7		1		_											X		Turnaround time	
5-28-1	<u> </u>					7	<u> </u>	V.													X		Priority Rush 1 Business Day	
Condition of Berinquisher		//A			H	<del></del> -	Date/		Time		erature ved by	receive		n		20	91		11.0	,			Rush 2 Business Days	_
	44	M	1		<u>(                                     </u>	//		91 :	1435 Time 730	Redei	art	5 1/1/	El	7	, 10	~7·	12		7- )	<u>&gt;</u>		····	Expedited 5 Business Days	
Relinquished	d by	lle					Date	· / )	Time	Recei	,,	Taborat	1 111			,	Date 10 - 2	9.9		Time	30	Ρm	Standard 10 Business Days	<b>7</b>

Distribution: White copy — Laboratory; Canary copy — ARCO Environmental Engineering; Pink copy — Consultant APPC-3292 (2-91)

RC	Division	of Atlantic	Richfield	any Company				Task O	rder No.	61	18	- 9	2 -	. 2	5							C	hain of Custo	ody
ARCO Facilit	y no.	5148	8	City	/ cility\ <sub>o</sub>	Oak	elono	<u>d</u>		Project (Consul	manag	ger	To	فا		20	- inc						Laboratory name	· · · · · ·
ARCO engine		lich			relo		Telephon	10 no. (415 243	)5-71-	Telepho	ne no.	(40	8)	264		Fau	c no.	140	٤) زع	264 135			Segovia	,
Consultant na	ame 72		Λ .				Inc.	Address	3315	A L	tanti)	جوا	77	pre	Misc	<u>ا(۵۵</u>	nsultan	ان ما رو	-37 7	<del>/                                    </del>			Contract number	
	اک	<u> </u>	/1		<u>5741</u>			(Consulta	3315 int)	<del>ک</del> ا	<u>~~</u>	J	Sez	<del>,                                    </del>		1	95	~// <b>&amp;</b>	3	1			Method of shipment	
		_		Matrix		Prese	rvation				\ <u>\</u>	20		띯				TCLP Semi	2000 0000				Method of Shipment	
<u>a</u>		ır no.						Sampling date	Sampling time	<sub>&amp;</sub> (	BTEX/TPH CA EPA M602/8020/99	TPH Modified 8015 Gas Diesel	Oit and Grease 413.1 U 413.2	TPH EPA 418.1/SM503E	99	<del>5</del>	8	\ A \	EPA 6	밀	V			
Sample I.D.	Lab no.	Container	Soil	Water	Other	lce	Acid	nildr	illat	BTEX 602/EPA 8020	MS02		ğ	418.1	EPA 601/8010	EPA 624/8240	EPA 625/8270	ايً	Metals	Org./I	2	30	:	
		ပိ						San	San	BTE) 602/1	BTE) EPA	TPH	Ojt 8	TPH EPA	EPA	EPA	EPA		울는 S	Lead Org./DHS ☐ Lead EPA 7420/7421 ☐	丰	Se		
5-30-3	3	1	<b>&gt;</b>			×		0/27/92													X		Special detection Limit/reporting	
5-33.5	ß8	1	7			~		0/2 /42			X			210	176	q <sup>'</sup>								
5-4.5-	36	1	7			4		10/13/92						-10	£ <b>*1</b>						X			
5-9.5-	36	1	4			X					X				. 70	5							Special QA/QC	· <del></del>
5-14.5-	K	1	<b>X</b>			4							-	0	163						X			
5-16-136 5-16-5136 5-17.5-1	· >	ļ	<b>X</b>			*															X			
,-16.5B		1	×			X					X				7									
5-17.5-	36	1	X			×									7 J.	<b>D</b>						X	Remarks .	*
5-18-13	6	1	X			X			*				===		100						X		1	•
5-18-5-1		1	X			X							~;	11 11	76	.,					./			٥
5-19-12	, ,	1	~			1									16	1					7			
5-19-5-13	6	- 1	X			×							_	,,,,	77	20		-				$\times$		
4-20-13	9	1	×			×					l		*	1	1 160						X			w
5-20:5-	36	1	4			×															4		Lab number	
5-21-5	6	ı	4			1							<u> </u>		7:	L						X	Turnaround time	
5-27-13	6	1	X	,	/	X					<u> </u>		<u> </u>	_ ¥	<u>'</u>	<del> </del>					X	<u> </u>	Priority Rush	_
Condition of	1	,	<del></del>	-/	1	1	·	/	.1	Temp	erature	receive	ed:	1	<u> </u>	L		1	1				1 Business Day	
Minquished	by sam			$\sqrt{}$	ol/	1	Date /	160	Time		yed by			500	les		10	29-	92	19	1:3	5	Rush 2 Business Days	
Relinquished		700.		/	4	<i>X</i> —	Daye	1/76	Time	Becei	ved by	$v \wedge v$	V1 <u>(</u>	æ		,			-		<del></del>		Expedited	<u></u>
Reference		De	7/			/	01-294 Date	92	3:30	De	المالة المالة	43h			4	I.	D-1-		<del>- 1</del>		_		5 Business Days	
Relinquished			1				,		Time		T	1aborat		·			Date /O^2	797 <b>9</b>	1	Time	<u>;30</u>	P.m	Standard 10 Business Days	A
Distribution: V	White cor	v — lat	Wratner.	Canany o	onv — A	RCO Envir	ronmental i	Engineering; 1	Pink conv —	Concul	,-, ant	W									ī			

Distribution: White copy — Laberatory; Canary copy — ARCO Environmental Engineering; Pink copy — Consultar APPC-3292 (2-91)

RCC		of Atlantic	RichfieldC					Tasl	Org	der No.	61	48		92	- 2	25							• 6	hain of Custody
ARCO Facili		6148	3 -	City (Fa	cility), Č	Jak	lond	•			Project (Consul	manag tant)	er -	~@{\	L.	Ci	17	mo	~~	Манр				Laboratory name
ARCO engin	M	cha	الله	ابرز	relo	-~	Telephor	10 ло. (	715	) <u>5</u>	Telepho	ne no.	140	·८)_	26	4-	Fax	c no.	77	08	76	4-		Segovia
Consultant r	ame Z	ESN,	A 3			22 7	MC.	Add (Cor	ress nsultar	3315	S&	1	ولى كروس	à.		دو مر	95	1/8	Suit	<b>2</b> _ 9	43 <b>5</b>			Contract number
			1	Matrix		Preser	vation		-		<b>[</b> ]	14 ×						<u> </u>	E S	0007/0	Lead Org./DHS [☐ Lead EPA 7420/7421 ☐			Method of shipment
ا م		. IIO.						date		time	<sub>R</sub>	18 %	TPH Modified 8015 Gas Diesel	Oil and Grease 413.1 🗀 413.2	TPH EPA 418.1/SM503E	۰	8	ي ا	TCLP Semi Metals ☐ VOA ☐ VOA ☐	17 P		J		
Sample I.D.	no.	Container	Soil	Water	Other	ice	Acid	Sampling date		Sampling time	PA 80	7TPH 4602/8	Asidin C		118.178	04/80	24/82	25/82	Š	Sale Sale Sale Sale Sale Sale Sale Sale	24.45 0 7.55	子子	3/2	
Sarr	Lab no.	Con						Sam		Sam	BTEX 602/EPA 8020	BTEX	TPH ! Gas [	03.8 413.1	EPH 7	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Metals	18 S	Lead 7420/	1	1	
5-22.5-	36	ł	X			7		10/28	92								<u>-</u> -					X		Special detection Limit/reporting
5-13.5-	06		X														, ,					$\overline{\times}$		
5-24-B	6	1	X			1									-21	74 1	59					×		
5-25-13	6	4	1			7		17		_						2101	17	75				·	X	Special QA/QC
5-25.5-	36	1	X			X										·	Ìΰ					X		
5-26-13	-	1	X			7							1									×		
8-27.5		1	X			7						X				210	147	76						
5-4.5-	1		~			7										1	11	1				X		Remarks
5-10-13	7-		*	<del>-</del> -		7				<del>-</del>		X			•	17/	tz	76	17			<u> </u>		1.
5-15-13	7		7			7						X						77						
5-19-13	7		7			7		1							2		1					λ.		1
		1	7			7																×	† <del>-</del>	
5-25-12	トゥチ		4			7			/			X			٠١،	<b>1</b>	13	70	,				<del>                                     </del>	
5-28-13	7		X			X		10/2	3/4				-						-				h	Tap number
																								Turnaround time
, /		,		1	7	7											74					<b></b>		Priority Rush
Condition o	sample;	1		- //	11				<u>-</u>		Temp	erature	receive	ed: /)		1	<u> </u>	l	J	<del>!</del>	-l		<u> </u>	1 Business Day
Relinquishe	d by salv	ble	En 1			\	Date /	ا/بر	.2	Time	Recer	yed by	-1	1//	5//	la	/1	)- <sub>2</sub> ?	79	7	1:3	<u></u>		Rush 2 Business Days
Relinquishe	<u> </u>	Ell	7			10	Date -/29-	19~	<del></del>	Time 3.30	Recei	ved by		₩	<u>,/\/</u>	1			<u> </u>	· •	<u>, , , , , , , , , , , , , , , , , , , </u>	<del></del> .		Expedited 5 Business Days
Refineruishe Distribution:			<u>/</u>				Date			Time		1	laborat	огу		U		Date  D=	29 cj	FZ.	Time	-36	Jose	Standard 10 Business Days

APPC-3292 (2-91)



NOV 4 - 1992

RESNA SAN JOSE

RESNA 3315 Almaden Expwy., Suite 34 San Jose, CA 95118 Attention: Joel Coffman

Project: ARCO 6148, Oakland

Enclosed are the results from 1 soil sample received at Sequoia Analytical on October 29,1992. The requested analyses are listed below:

SAMPLE #	SAMPLE DESCRIPTION	DATE OF COLLECTION	TEST METHOD
2104586	Soil, CSS-A-D	10/28/92	EPA 5030/8015/8020 EPA 5030/8015/8020-TCLP Extract STLC Lead Corrosivity, Ignitability and Reactivity

Please contact me if you have any questions. In the meantime, thank you for the opportunity to work with you on this project.

Very truly yours,

Project Manager

SEQUOIA ANALYTICAL

2104586.RES <1>



3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Client Project ID:

ogradija programa programa programa programa programa programa programa programa programa programa programa pr ARCO 6148, Oakland Soil

Sampled: Received:

Oct 28, 1992 Oct 29, 1992

Sample Matrix: Analysis Method:

EPA 5030/8015/8020

Reported:

Nov 2, 1992%

First Sample #: Attention: Joel Coffman yy jary historia. Santanan kantanan kantanan kantan kantan kantan kantan kantan kantan kantan kantan kantan ka iro garata ingratara kilik pirobaga (s

210-4586

#### TOTAL PURGEABLE PETROLEUM HYDROCARBONS with BTEX DISTINCTION

Analyte	Reporting Limit mg/kg	Sample I.D. 210-4586 CSS-A-D
Purgeable Hydrocarbons	1.0	N.D.
Benzene	0.0050	N.D.
Toluene	0.0050	N.D.
Ethyl Benzene	0.0050	N.D.
Total Xylenes	0.0050	N.D.
Chromatogram Pat	tern:	

**Quality Control Data** 

Report Limit Multiplication Factor:

1.0

Date Analyzed:

10/29/92

Instrument Identification:

GCHP-7

Surrogate Recovery, %:

(QC Limits = 70-130%)

102

Purgeable Hydrocarbons are quantitated against a fresh gasoline standard. Analytes reported as N.D. were not detected above the stated reporting limit.

SEQUOIA ANALYTICAL

Project Manager

2104586.RES <1>



3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman

Sample Matrix: Analysis Method: First Sample #:

Client Project ID: ARCO 6148, Oakland TCLP Extract of Soil

EPA 5030/8015/8020

210-4586

Sampled: Received:

Oct 28, 1992 Oct 29, 1992

Reported: Nov 2, 1992

#### TOTAL PURGEABLE PETROLEUM HYDROCARBONS with BTEX DISTINCTION

Analyte	Reporting Limit μg/L	Sample I.D. 210-4586 CSS-A-D
Purgeable Hydrocarbons	50	N.D.
Benzene	0.50	N.D.
Toluene	0.50	N.D.
Ethyl Benzene	0.50	N.D.
Total Xylenes	0.50	N.D.
Chromatogram Patt	ern:	

**Quality Control Data** 

Report Limit Multiplication Factor: 20

11/2/92 Date Analyzed:

Instrument Identification: GCHP-2

109 Surrogate Recovery, %:

(QC Limits = 70-130%)

Purgeable Hydrocarbons are quantitated against a fresh gasoline standard. Analytes reported as N.D. were not detected above the stated reporting limit.

SEQUOIA ANALYTICAL

Project Manager

2104586.RES <2>



3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman 

Lab Number:

RESNA Client Project ID: ARCO 6148, Oakland

Sample Descript: Soil, CSS-A-D

210-4586

Sampled: Oct 28, 1992

Received: Analyzed:

Oct 29, 1992@ see below ::

Reported:

Nov 2, 1992

#### LABORATORY ANALYSIS by STLC

Analyte

Date Analyzed **Detection Limit** mg/L

Sample Result mg/L

0.0050 ...... 0.079

Analytes reported as N.D. were not present above the stated limit of detection.

**SEQUOIA ANALYTICAL** 

Project Manager

2104586.RES <3>



RESNA Client Project ID: ARCO 6148, Oakland 3315 Almaden Expwy., Suite 34

Sampled:

Oct 28, 1992 Oct 29, 1992

San Jose, CA 95118

Sample Descript: Soil, CSS-A-D

Received: Oct 30, 1992<sup>3</sup> Analyzed:

Attention: Joel Coffman

Lab Number:  210-4586

Reported: Nov 2, 1992#

## CORROSIVITY, IGNITABILITY, AND REACTIVITY

Analyte	<b>Detection Limit</b>	Sample Results	
Corrosivity:	N.A.		7.3
Ignitability: Flashpoint (Pensky-Martens), °C	N.A.		> 100 °C
Reactivity: Sulfide, mg/kg Cyanide, mg/kg Reaction with water	10 0.50 N.A.		N.D. N.D. Negative

Analytes reported as N.D. were not present above the stated limit of detection.

**SEQUOIA ANALYTICAL** 

Maria Lee Project Manager

2104586.RE\$ <4>



Client Project ID: ARCO 6148, Oakland

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman QC Sample Group: 210-4586

Reported: Nov 2, 1992

#### QUALITY CONTROL DATA REPORT

				······
ANALYTE			Ethyl-	
	Benzene	Toluene	benzene	Xylenes
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020
Analyst:	B. Ali	B. Ali	B. Ali	B. Ali
Reporting Units:	mg/kg	mg/kg	mg/kg	mg/kg
Date Analyzed:	Oct 29, 1992	Oct 29, 1992		Oct 29, 1992
QC Sample #:	GBLK102992	GBLK102992	GBLK102992	
QC Sample #:	GBLK102992	GDLN 102992	GDLN102992	GDERTOZSSZ
Sample Conc.:	N.D.	N.D.	N.D.	N.D.
Cnika Cana				
Spike Conc. Added:	0.20	0.20	0.20	0.60
Added:	0.20	0.20	0.20	0.00
Conc. Matrix				
Spike:	0.21	0.21	0.21	0.62
Matrix Cailes				
Matrix Spike	105	105	105	103
% Recovery:	105	105	105	103
Conc. Matrix				
Spike Dup.:	0.21	0.21	0.22	0.63
Фр				
Matrix Spike				
Duplicate				
% Recovery:	105	105	110	105
Relative				
% Difference:	0.0	0.0	4.7	1.6
% Difference.	0.0	0.0	1.7	1.0

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

**SEQUOIA ANALYTICAL** 

Project Manager

% Recovery:	Conc. of M.S Conc. of Sample	x 100
	Spike Conc. Added	
Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100
	(Conc. of M.S. + Conc. of M.S.D.) / 2	

2104586.RES <5>



Client Project ID: ARCO 6148, Oakland

.3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman QC Sample Group: 210-4586 Reported: Nov 2, 1992

#### QUALITY CONTROL DATA REPORT

ANALYTE			Ethyl-	
<del></del>	Benzene	Toluene	benzene	Xylenes
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020
Analyst:	M. Nipp	M. Nipp	M. Nipp	M. Nipp
Reporting Units:	μg/L	μg/L	μg/L	µg/L
Date Analyzed:	Oct 2, 1992	Oct 2, 1992	Oct 2, 1992	Oct 2, 1992
QC Sample #:	GBLk110292	GBLk110292	GBLk110292	GBLk110292
	MS/MSD	MS/MSD	MS/MSD	MS/MSD
Sample Conc.:	N.D.	N.D.	N.D.	N.D.
Spike Conc.				
Added:	10	10	10	30
Conc. Matrix				
Spike:	9.7	9.7	9.7	29
opiite.	<b>5</b>			_ <del>-</del>
Matrix Caika				
Matrix Spike	97	97	97	97
% Recovery:	91	31	91	31
Conc. Matrix		_		
Spike Dup.:	9.5	9.5	9.4	29
Matrix Spike				
Duplicate				
% Recovery:	95	95	94	97
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	•		2.	<del>* -</del>
Relative				
	0.4	2.1	3.1	0.0
% Difference:	2.1	۷, ۱	J. i	U.U

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

**SEQUOIA ANALYTICAL** 

Project Manager

% Recovery:	Conc. of M.S Conc. of Sample	x 100	
<u> </u>	Spike Conc. Added	•	
  Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100	
<u> </u>	(Conc. of M.S. + Conc. of M.S.D.) / 2		

2104586.RES <6>



Client Project ID: ARCO 6148, Oakland

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman 

QC Sample Group: 210-4586

Reported: Nov 2, 1992

#### **QUALITY CONTROL DATA REPORT**

ANALYTE	Lead			Reactive		
	STLC	рΗ	Flashpoint	Sulfide	Cyanide	
Method:	EPA 7421	EPA 9045	EPA 1010	EPA 9030	EPA 9010	
Analyst:	S. Chin	Y, Arteaga	K. Follett	K. Follett	N. Zahedi	
Reporting Units:	mg/L	N.A.	°C	mg/kg	mg/kg	
Date Analyzed:	Nov 2, 1992	Oct 30, 1992	Oct 28, 1992	Oct 26, 1992		
QC Sample #:	210-4390	210-4334	210-3713	209-4408	210-3565	
ao sampio "	<b></b>	2.0				
Sample Conc.:	0.12	8.5	> 100	N.D.	1.1	
Sample Conc	0.12	0.0	> 100	11.0.	***	
Spike Conc.						
Added:	0.50	N.A.	N.A.	1300	2.9	
Added:	0.50	IN.A.	IV.A.	1000	2.9	
Onna Maduir						
Conc. Matrix	0.50	N.A.	N.A.	1500	3.9	
Spike:	0.56	IV.A.	IN.A.	1500	3.5	
B. B. A. de L. Charles						
Matrix Spike	00	K E A	N.A.	115	97	
% Recovery:	88	N.A.	N.A.	113	91	
Como Matrix						
Conc. Matrix	0.54	8.5	>100	1300	4.2	
Spike Dup.:	0.54	ზ.ე	> 100	1300	4.4	
Matrix Spike						
Duplicate						
% Recovery:	84	N.A.	N.A.	106	107	
Relative						
% Difference:	3.6	0.0	0.0	14	7.4	

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

**SEQUOIA ANALYTICAL** 

**Froject Manager** 

% Recovery:	Conc. of M.S Conc. of Sample	x 100	
	Spike Conc. Added		
Relative % Difference:	Conc. of M.S Conc. of M.S.D.	x 100	
	(Conc. of M.S. + Conc. of M.S.D.) / 2		
			2104586.RES <7>

RC		odl Orvision	of Atlantic	Connection Control of Control	any Company				Task O	der No.	6	178	3=	9		2	<b>&gt;</b>	_						main of Custody	j
ARCO F	acility	no. Z	14	8	City (Fa	r cility)	Dak	lone	}		Project (Consul	manag tant)	er	Oe	又	2	J.	(·/·	<u> ۲</u>	<u>^</u>	, .			Laboratory name	
ARCO e	nginee	<u> </u>	ha	e)	wh	2 av	<u> </u>	Telephon (ARCO)	e no. (715 243	5 7571-	Telepho (Consul	ne no.	(4/0-1	3/20	34 ~ 2. Z		Fax (Co	no. (	408 1)	) 2	643	5		Contract number	_
Consulta	nt nan	10 2	265	NA	<b>エ</b>	مطه	Strie	s to	Address	737/5 <sup>1</sup>	A	ma	تحو	<del>, Z</del>	50.	CA.	,ite	34	-115	رگر <sup>5</sup>	<u>*</u>	<u>-</u>		Contract number	
·		<u> </u>			Matrix	•	Prese	rvation	1,1	,		15	)					,		8 <u>0</u>				Method of shipment	_
Sample I.D.		Lab no.	Container no.	Soil	Water	Other	Ice	Acid	Sampling date	emit buildings	BTEX 602/EPA 8020	BTEX/TPH EPA M602/8020/80	TPH Modified 8015 GRS TIT Diesel	Oil and Grease 413.1 ☐ 413.2 ☐	TPH EPA 418.1/SM503E	EPA 601/8010	EPA 624/8240	EPA 625/8270	TOLP SON TOWN	CAM Metals EPA 601	Lead Org./DHS	RCI			
:45- <i>j</i>	1-D	<u> </u>		X			X		10/23/92				X						¥	X		×		Special detection Limit/reporting	
								ļ																	
	_				<u> </u>			ļ	<u> </u>					-							ļ			Special QA/QC	
				1			<u> </u>	<u> </u>					ļ <u>.</u>	ļ						_	-				
					-	ļ	<u> </u>				-									<u> </u>	-				
				,				1												<u> </u>		<u> </u>		Remarks	
							<u> </u>	<del> </del>			<del>                                     </del>	-					<u> </u>			<del>                                     </del>					
									*								_			<u> </u>		<del> </del>		1	`
							1																, ,	1	
					ļ																			Lab number	_
					ļ	ļ		ļ <u>.</u> .			ļ													2104586	
	_		ļ				ļ						ļ											Turnaround time	
	1		/	1	1 /	1 1	h_	1	<u> </u>		<u> </u>					<u> </u>				1			<u> </u>	Priority Rush 1 Business Day	
Condition	11	- D	/ /			<i>W</i>		Pate /2	n/42	Time 1455	Recei	erature ived by	- H A	ed://	Ple	1 '	1a -	29-	92	14	1.3	5		Rush 2 Business Days	×
	ished W	1/	200					Date 0-29	-92	7:30		ved by				<del>                                     </del>	***************************************					<del>/</del>	<del>_</del>	Expedited 5 Business Days	Г.
Helingu				1			•	Date		Time	Recei	ived by	labora	tory				Date	•	•	Time			Standard 10 Business Days	

Distribution: White copy — Laboratory; Canary copy — ARCO Environmental Engineering, Pink copy — Consultant APPC-3292 (2-91)

· · ·



Consultar Manag Environm

# RECEIVED NOV 9 - 1992

RESNA

			SANJOSE
CON		Date	October 29, 1992
CIATES ints in Wastes		Project	0G70-039.01
gement and nental Control		•	
To:			
Mr. Joel Coffman			
RESNA/ Applied C	eosystems		
3315 Almaden Ex	pressway, Suite 34		
San Jose, Californ	ia 95050		
We are enclosing			
Copies	Description		
1	Depth To Water / Floatin	g Product	Survey Results
1	Summary of Groundwate	er Monitori	ng Data
1	Certified Analytical Repo	orts with Cl	nain-of-Custody
3	Water Sample Field Date	a Sheets	
For your: X	Information Sent	by:	X Mail
Comments:			
Enclosed are	the data from the fourth o	uarter 199	92 monitoring event at
ARCO service	station 6148, located at 513	31 Shattuc	k Avenue. Oakland CA.
Groundwater n	nonitoring is conducted cor	nsistent wit	th applicable regulatory
guidelines. Ple	ease call if you have any qu	iestions. (	<u>408) 453-2266.</u>
	RED CUNTIE	····	Jim Butera プβ
Reviewed by:	1618 CON		
	인 No: 4094		
	Exp. 6/3/44	Pal	Cut Cloto
	WAS USTBY SOM	Robert	Porter, Senior Project
	OF CAUFUL STATE		Engineer.

# FIELD REPORT DEPTH TO WATER/FLOATING PRODUCT SURVEY

			V— ,——						<u> </u>			1			
	PROJ	ECT#:	0G70-0	39.01	STA	TION A	DDRESS :	5131 Shattı	uck Ave., Oa	akland, CA	DATE :	10-	07-92		
Д	RCO STAT	ion # :	6148		FIE	ELD TEC	CHNICIAN :	3 to	coll. 4n	క	DAY:	DAY: WED			
DTW Order	WELL ID	Well Box Seal	Well Lid Secure	Lock Gasket	GNSK:T	Locking Well Cap	FIRST DEPTH TO WATER (feet)	SECOND DEPTH TO WATER (feet)	DEPTH TO FLOATING PRODUCT (feet)	l i	WELL TOTAL DEPTH (feet)	C	OMMENTS		
1	MW-1	ok	429	3259	Alf:	OK	1852	18:52	NO	ND	25.7	~-			
2	MW-2	OK	429	3259	NA	OK	18.80	18,80	19.0	.31	25-8	<b>D</b> 31	Totlow Buler		
3	MW-3	OK	725	3259	AN	OK	18.90	1850	NA	WD*	25.80	× .oZ	Tetlow Bailer		
								1							
										<u>.</u>					
								:							
	<u> </u>														
						<u> </u>									
			_	,											
				<u></u>		<u> </u>									
				SURV	EY PO	INTS A	ARE TOP	OF WELL	CASING	<u> </u>					

#### Summary of Groundwater Monitoring Data Fourth Quarter 1992 ARCO Service Station 6148 5131 Shattuck Avenue, Oakland, California micrograms per liter (µg/l) and milligrams per liter (mg/l)

Well ID and Sample Depth	Sampling Date	Depth To Water (feet)	Floating Product Thickness (feet)	TPH <sup>1</sup> as Gasoline (µg/l)	Benzene (µg/l)	Toluene (μg/l)	Ethyl- benzene (µg/l)	Total Xylenes (μg/l)	TPH as Diesel (µg/l)	Total Oil and Grease, 5520F (mg/l)
MW-1(25)	10/07/92	18.52	ND.2	590.	200.	19.	6.7	19.	<50.	<0.5
MW-2	10/07/92	18.80	0.31	FP.3	FP.	FP.	FP.	FP.	FP.	FP.
K-WM	10/07/92	18.90	0.02*	FP.	FP.	FP.	FP.	FP.	FP.	FP.
FB-1. <sup>4</sup>	10/07/92	NA. <sup>5</sup>	NA.	<50	<0.5	<0.5	< 0.5	<0.5	NR.6	NR.

<sup>1.</sup> TPH. = Total petroleum hydrocarbons

<sup>2.</sup> ND. = Not detected

<sup>3.</sup> FP.= Floating product detected in well, no sample was taken 4. FB. = Field Blank

<sup>5.</sup> NA. = Not applicable

<sup>6.</sup> NR. = Not reported; sample was not scheduled for analysis of the selected parameter

\* = Floating product came into the well after the purge was completed

# Summary of Analytical Results Halogenated Volatile Organic Compounds by EPA<sup>1</sup> Methods 5030/601 Fourth Quarter 1992 ARCO Service Station 6148

5131 Shattuck Avenue, Oakland, California micrograms per liter (µg/l) or parts per billion (ppb)

Well ID and Sample Depth	Sampling Date	Chloroform (ppb)	TCE <sup>2</sup> (ppb)	PCE <sup>3</sup> (ppb)
MW-1(25)	06/12/92	0.6	1.5	23.
MW-2	FP. <sup>4</sup>	FP.	FP.	FP.
MW-3	FP.	FP.	FP.	FP.

<sup>1.</sup> EPA = United States Environmental Protection Agency.

<sup>2.</sup> TCE = Trichloroethene

<sup>3.</sup> PCE = Tetrachloroethene

<sup>4.</sup> FP.= Floating product detected, well not sampled



October 20, 1992

Jim Butera EMCON Associates 1921 Ringwood Avenue San Jose, CA 95131

Re: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Dear Mr. Butera:

Enclosed are the results of the water samples submitted to our lab on October 7, 1992. For your reference, our service request number for this work is SJ92-1244.

All analyses were performed in accordance with the laboratory's quality assurance program.

Please call if you have any questions.

Respectfully submitted:

COLUMBIA ANALYTICAL SERVICES, INC.

Keoni A. Murphy

Laboratory Manager

Ymnelise Yade 15azar Annelise J. Bazar

Regional QA Coordinator

KAM/ajb

#### Analytical Report

Client:

**EMCON Associates** 

Project:

EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received:

10/07/92

Work Order #:

SJ92-1244

Sample Matrix:

Water

**Inorganic Parameters** mg/L (ppm)

Sample Name:

Date Sampled:

MW-1 (25)

Method Blank

10/07/92

**Analyte** 

Method

<u>MRL</u>

Hydrocarbons by IR

SM 5520F

0.5

ND

ND

MRL Method Reporting Limit

None Detected at or above the method reporting limit

Standard Methods for the Examination of Water and Wastewater, 17th Ed., 1989 SM

KeemiAMnyly

Date Detober 20/1992

#### **Analytical Report**

Client: EMCON Associates

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Sample Matrix: Water

Date Received: 10/07/92

Date Extracted: 10/12/92

Date Analyzed: 10/15/92

Work Order #: SJ92-1244

TPH as Diesel
EPA Method 3510/California DHS LUFT Method

µg/L (ppb)

Sample Name	<u>MRL</u>	TPH as Diesel
MW-1 (25)	50.	ND
Method Blank	50.	ND

MRL Method Reporting Limit

TPH Total Petroleum Hydrocarbons

ND None Detected at or above the method reporting limit

Approved by KyEllitMinhy

Date October 20,1992

#### Analytical Report

Client:

**EMCON Associates** 

Project:

EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received:

10/07/92

Work Order #:

SJ92-1244

Sample Matrix: Water

Halogenated Volatile Organic Compounds EPA Methods 5030/601  $\mu$ g/L (ppb)

Sample Name: Date Analyzed:		MW-1 (25) 10/09/92	Method Blank 10/09/92
<u>Analyte</u>	MRL		
Dichlorodifluoromethane (Freon 12)	1	ND	ND
Chloromethane	1	ND	ND
Vinyl Chloride	0.5	ND	ND
Bromomethane	0.5	ND	ND
Chloroethane	0.5	ND	ND
Trichlorofluoromethane (Freon 11)	0.5	ND	ND
1,1-Dichloroethene	0.5	ND	ND
Trichlorotrifluoroethane (Freon 113)	0.5	ND	ND
Methylene Chloride	0.5	ND	ND
trans-1,2-Dichloroethene	0.5	ND	ND
cis-1,2-Dichloroethene	0.5	ND	ND
1,1-Dichloroethane	0.5	ND	ND
Chloroform	0.5	0.6	ND
1,1,1-Trichloroethane (TCA)	0.5	ND	ND
Carbon Tetrachloride	0.5	ND	ND
Benzene	0.5	ND	ND
1,2-Dichloroethane	0.5	ND	ND
Trichloroethene (TCE)	0.5	1.5	ND
1,2-Dichloropropane	0.5	ND	ND
Bromodichloromethane	0.5	ND	ND
2-Chloroethyl Vinyl Ether	5	ND	ND
trans-1,3-Dichloropropene	0.5	ND	ND
Toluene	1	ND	ND
cis-1,3-Dichloropropene	0.5	ND	ND
1,1,2-Trichloroethane	0.5	ND	ND
Tetrachloroethene (PCE)	0.5	23.	ND
Dibromochloromethane	0.5	ND	ND
Chlorobenzene	0.5	ND	ND
Ethylbenzene	1	ND	ND
Bromoform	0.5	ND	ND
1,1,2,2-Tetrachloroethane	0.5	ND	ND
1,3-Dichlorobenzene	1	ND	ND
1,4-Dichlorobenzene	1	ND	ND
1,2-Dichlorobenzene	1	ND	ND
Total Xylenes	1	ND	ND

MRL

Method Reporting Limit

ND

None Detected at or above the method reporting limit

Date October 20,1992

#### Analytical Report

Client: EMCON Associates

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received:

10/07/92

Work Order #: SJ92-1244

Sample Matrix: Water



### BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method $\mu g/L$ (ppb)

Sai Dat	<u>MW-1 (25)</u> 10/12/92	<u>FB-1</u> 10/12/92	Method Blank 10/12/92	
<u>Analyte</u>	MRL			
Benzene	0.5	200.	ND	ND
Toluene	0.5	19.	ND	ND
Ethylbenzene	0.5	6.7	ND	ND
Total Xylenes	0.5	19.	ND	ND
TPH as Gasoline	50	590.	ND	ND

TPH Total Petroleum Hydrocarbons

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by Kellin Muylly

Date October 22/1992



## APPENDIX A LABORATORY QC RESULTS



Client: EMCON Associates

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received: 10.
Work Order #: SJ

10/07/92 SJ92-1244

Sample Matrix: Water

QA/QC Report Continuing Calibration Summary Inorganics SM 5520F mg/L

	True		Percent	Percent Recovery Acceptance
<u>Analyte</u>	Value	<u>Result</u>	Recovery	<u>Criteria</u>
Hydrocarbons by IR	100.	106.	106.	90-110

approved by Keeni Minghy

Date October 20,1992

7



Client: Project: **EMCON Associates** 

EMCON Project No. 0G70-039.01

Arco Facility No. 6148

**Date Received:** Work Order #:

10/07/92 SJ92-1244

Sample Matrix: Water

QA/QC Report Matrix Spike Summary Inorganic Parameters mg/L (ppm)

Sample Name: MW-1 (25)

Date Sampled: 10/07/92

				Percent	Recovery
<u>Parameter</u>	Spike <u>Level</u>	Sample <u>Result</u>	Spike Result MS DMS	MS DMS	Acceptance <u>Criteria</u>
Hydrocarbons by IR	5.71	ND	5.72 5.72	100. 100.	56-106

None Detected at or above the method reporting limit ND

KEEndMuychy

Date Adober 20,1992



Client:

**EMCON Associates** 

Project:

EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received: Work Order #:

10/07/92

SJ92-1244

Sample Matrix:

Water

QA/QC Report Initial Calibration Verification TPH as Diesel EPA Methods 3510/DHS LUFT Method mg/L (ppm)

Date Analyzed:

10/15/92

				CAS Percent Recovery
<u>Analyte</u>	True <u>Value</u>	Result	Percent <u>Recovery</u>	Acceptance <u>Criteria</u>
TPH as Diesel	1,000.	1,100.	110.	90-110

TPH Total Petroleum Hydrocarbons

Kitchi Aminghy Date October 20,1992



Client: EMCON Associates

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received: 10/07/92 Work Order #: SJ92-1244

Sample Matrix: Water

QA/QC Report
Surrogate Recovery Summary
TPH as Diesel
EPA Method 3510/DHS LUFT Method

Sample Name	Date Analyzed	Percent Recovery P-Terphenyl
MW-1 (25)	10/15/92	94.
MS DMS	10/15/92 10/15/92	81. 77.
Method Blank	10/15/92	106.
	CAS Acceptance Criteria	61-121

TPH Total Petroleum Hydrocarbons

Approved by KEEMIAM myly

Date October 20/992\_

**EMCON Associates** 

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received: Work Order #:

10/07/92 SJ92-1244

Sample Matrix:

Water

QA/QC Report Matrix Spike/Duplicate Matrix Spike Summary Total Petroleum Hydrocarbons as Diesel DHS LUFT Method  $\mu$ g/L (ppb)

Date Analyzed:

10/15/92

Percent Recovery

<u>Parameter</u>	Spike <u>Level</u>	Sample <u>Result</u>	Spike Result MS DMS	MS DMS	Acceptance <u>Criteria</u>
Diesel	4,000.	ND	3,770. 3,340.	93. 84.	46-133

None Detected at or above the method reporting limit

Leenwith manyly

Date October 20,1992

#### QA/QC Report



Client: EMCON Associates

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received: 10/07/92 Work Order #: SJ92-1244

#### Initial Calibration Verification Halogenated Volatile Organic Compounds EPA Methods 5030/601 Nanograms

<u>Analyte</u>	True <u>Value</u>	Result	Percent Recovery	EPA Percent Recovery Acceptance Criteria
Chloromethane	50	43.5	87.	D-193
Vinyl Chloride	50	48.4	97.	28-163
Bromomethane	50	48.0	96.	D-144
Chloroethane	50	50.1	100.	46-137
Trichlorofluoromethane (Freon 11)	50	47.8	96.	21-156
1,1-Dichloroethene	50	44.8	90.	28-167
Methylene Chloride	50	48.5	97.	25-162
trans-1,2-Dichloroethene	50	51.3	103.	38-155
1,1-Dichloroethane	50	52.1	104.	47-132
Chloroform	50	50.6	101.	49-133
1,1,1-Trichloroethane (TCA)	50	53.0	106.	41-138
Carbon Tetrachloride	50	54.4	109.	43-143
1,2-Dichloroethane	50	58.4	117.	51-147
Trichloroethene (TCE)	50	53.3	107.	35-146
1,2-Dichloropropane	50	56.0	112.	44-156
Bromodichloromethane	50	54.8	110.	42-172
trans-1,3-Dichloropropene	50	74.3	149.	22-178
cis-1,3-Dichloropropene	50	59.2	118.	22-178
1,1,2-Trichloroethane	50	55.6	111.	39-136
Tetrachloroethene (PCE)	50	54.6	109.	26-162
Dibromochloromethane	50	54.6	109.	24-191
Chlorobenzene	50	54.4	109.	38-150
Bromoform	50	55.6	111.	13-159
1,1,2,2-Tetrachloroethane	50	54.9	110.	8-184
1,3-Dichlorobenzene	50	53.6	107.	7-187
1,4-Dichlorobenzene	50	57. <del>9</del>	1 <b>1</b> 6.	42-143
1,2-Dichlorobenzene	50	57.3	115.	D-208

D Detected

Approved by KENIAManyly

Date Oxfoler 20/992

Client:

**EMCON Associates** 

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received: Work Order #:

10/07/92 SJ92-1244 Sample Matrix: Water

QA/QC Report
Surrogate Recovery Summary
Halogenated Volatile Organic Compounds
EPA Methods 5030/601

Sample Name	Date Analyzed	Percent Recovery 4-Bromofluorobenzene		
MW-1 (25)	10/09/92	89.		
MS DMS	10/09/92 10/09/92	105. 106.		
Method Blank	10/09/92	76.		

CAS Acceptance Criteria

70-130

Approved by Herry Munty

Date 10 10 10 20/1992

Client:

**EMCON Associates** 

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

Date Received:

10/07/92

SJ92-1244 Work Order #:

Sample Matrix: Water



QA/QC Report Matrix Spike/Duplicate Matrix Spike Summary Halogenated Volatile Organic Compounds EPA Methods 5030/601  $\mu$ g/L (ppb)

Date Analyzed:

10/09/92

Percent Recovery

<u>Analyte</u>	Spike <u>Level</u>	Sample Result	Spike R MS	esult DMS	MS	<u>DMS</u>	EPA Acceptance <u>Criteria</u>
1,1-Dichloroethene	10.	ND	10.4	10.8	104.	108.	28-167
Trichloroethene	10.	ND	10.4	11.0	104.	110.	35-146
Tetrachloroethene	10.	ND	10.7	11.3	107.	113.	26-162

None Detected at or above the method reporting limit

Keen Murphy

Date Ectober 201992



Client:

**EMCON Associates** 

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

10/07/92 **Date Received:** Work Order #: SJ92-1244

QA/QC Report Initial Calibration Verification BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method Nanograms

Date Analyzed: 10/12/92

<u>Analyte</u>	True <u>Value</u>	Result	Percent Recovery	CAS Percent Recovery Acceptance <u>Criteria</u>
Benzene	250.	261.	104.	85-115
Toluene	250.	266.	107.	85-115
Ethylbenzene	250.	253.	101.	85-115
Total Xylenes	750.	709.	95.	85-115
TPH as Gasoline	2,500.	2,431.	97.	90-110

TPH Total Petroleum Hydrocarbons

Ktom Muythy Date Popo Ser 201992

**EMCON Associates** Client:

Project: EMCON Project No. 0G70-039.01

Arco Facility No. 6148

10/07/92 Date Received: Work Order #: SJ92-1244 Sample Matrix: Water

QA/QC Report Surrogate Recovery Summary BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method

Sample Name	Date Analyzed	<u>Percent Recovery</u> a,a,a-Trifluorotoluene
MW-1 (25)	10/12/92	109.
FB-1	10/12/92	107.
MS	10/12/92	110. *
DMS	10/12/92	106. *
Method Blank	10/12/92	108.

CAS Acceptance Criteria

70-130

**TPH** Total Petroleum Hydrocarbons

The surrogate used on this sample was 4-Bromofluorobenzene.

KeeniaMuyly Date October 20,1892

Client:

**EMCON Associates** 

EMCON Project No. 0G70-039.01 Project:

Arco Facility No. 6148

Date Received: Work Order #:

10/07/92

The s

SJ92-1244

Sample Matrix: Water

QA/QC Report Matrix Spike/Duplicate Matrix Spike Summary BTE EPA Methods 5030/8020  $\mu$ g/L (ppb)

Date Analyzed:

10/12/92

Percent Recovery

<u>Analytes</u>	Spike Level	Sample <u>Result</u>	Spike Resu MS DM		<u>DMS</u>	Acceptance <u>Criteria</u>
Benzene	25.	5.8	28.2 28	.6 90.	91.	39-150
Toluene	25.	ND	23.6 24	.0 94.	96.	46-148
Ethylbenzene	25.	ND	23.5 24	.1 94.	96.	32-160

None Detected at or above the method reporting limit

Approved by Kennt Munhy

Date October 20/992



### APPENDIX B

CHAIN OF CUSTODY

THE CO		of Atlantic	RichfieldC					Task Or	der No.	E	uce	5 <i>C</i> -	90	1-0	7						— (	Chain of Custody
ARCO Facilit	•	0148		City (Fa	/ cility)	OAK	LANK	)	ĺ	Project Consul	manag lant)	er	Tiv	n	BU	a	QA.					Laboratory name
ARCO engin		ile	Chr	istic	ė		Telephoni (ARCO)	15 571	2434	Consul	ne no. lant)	49	45	3-0	719	Fax (Co	no. nsultan	1) 40	R4.	53-6	252	CA-S Contract number
Consultant n	ame Z	-MC	ON	ASS	ocii	HES		Address (Consulta	nt) <i>193</i>									ک ہر	6Se	2		75070
				Matrix		!	rvation				1	r						VO#   OA	3077000			Method of shipment Sunpley
Sample I.D.	Гар по.	Container no.	Soil	Water	Other	lce	Acid	Sampling date	Sampling time	BTEX 602/EPA 8020	ВТЕХ/ГРН <b>СЛ</b> \$ ЕРА М602/8020/8015	TPH Modified 8015 Gas Diesel	On and Grease 413.2	TPH EPA 418.1/SM503E	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Metals □ VOA □ VOA	CAM Metals EPA 60 TTLC [ ] STLC [	Lead Org /DHS CLead EPA 7420/7421 CL		Method of shipment Scanp Cer Will deliver
New-1 (25)	j-6	6		x		×	HCI	10-7-94	1146		X		ኦ		Х							Special detection Limit/reporting
uw2(	)	4		x		Х	HC1	WOSH	nple		X		×		Х							louist louiste
MW &		6		X		X	HCI	NOSA	nple		X		×		X							
MW 1/25	<b>\</b> 7-8	2		γ		x	NP	10-7-92	1146			χ					_					Special QA/QC AS Normal
Mw 2 (	)	2		X		Х	NP	NO 51				X										Normal
Mw-3 (	)	2		<b>x</b>		次	NP	No 51-	in pla			x										
																						7-40MI HCI
FB-1	9-10	2_		X		X	Hel	1D-792	1222		X											2-Liter HC/
																						Remarks 7-40Ml HCl 2-4ter Hcl 2-4ter Nl 0670-034.0
																	_					Lab number 1244
		ļ						***************************************			ļ	ļ		ļ		ļ						Turnaround time
Condition of	sample	<u> </u>				Ok				Temp	erature	receiv	eq.		iv-							Priority Rush  1 Business Day
Relinquished by sampler Date Time						Time 1410		ved by		<u> </u>		You	<i>u</i> 1						Rush 2 Business Days			
Relinquishe							Date	<del></del>	Time	Recei	ved by											Expedited 5 Business Days
Relinquishe	d by			,			Date	· · · · · · · · · · · · · · · · · · ·	Time	Rece	ved by	labora AUV	tory 15	2			Date 10-	7-0	12	Time 14	: 10	Standard 10 Business Days

Distribution: White copy — Laboratory; Canary copy — ARCO Environmental Engineering; Pink copy — Consultant APPC-3292 (2-91)

EMCON PURGED I		11.4ms		D: <u>MW-1</u> =: <u>ARCO</u>	
ASSOCIATES		Minu S		v: 5131 S	
/PE: Ground Water	Surface I	Matar Troots	nont Efficant	Oakland	C14
ASING DIAMETER (inches):					
CASING ELEVATION (feet/	<del></del>				
DEPTH TO WATER		<b>~</b> ~		RGE (gal.):	
		.7 (3.75) AC			
DATE PURGED: 10-0		Start (2400 Hr)	103	End (2400 Hr) .	1139
DATE SAMPLED: 10-0	7-52	Start (2400 Hr) 🗸	[4]	End (2400 Hr) .	1146
TIME VOLUME	pН	E.C.	TEMPERATURE		TURBIDIT
(2400 Hr) (gal.) // 0 <sup>c</sup> / 5	(units)	(μmhos/cm @ 25° C)	(°F) 78, 6	(visual) (LEAR	(visual) _CLEAR
1118 18	6.33	471	72,9	11	//
124 15	6.27	49.8	73.1	//	1 (
134 20	6.35	466	72.2	1,	1/
139 24	6.32	456	73,3		11
O. O. (ppm):		ODOR: Shock F	_	N.R.	W.R
	<b></b>		,	(COBALT 0 - 100)	(NTU 0 - 200
TELD QC SAMPLES COLLEC	CIED AT THIS	WELL (i.e. FB-1, XDU)	P-1):		
PURGING EQ	UIPMENT		SAMPLIN	IG EQUIPMENT	
2° Bladder Pump	- Bailer (Teflo	n®)	2" Bladder Pump	Bailer	(Teflon®)
Centrifugal Pump — Submersible Pump —	Bailer (PVC)		DDL Sampler		(Stainless Stee
— Submersible Pump — — Well Wizard <sup>M</sup> —	<ul><li>Bailer (Stain)</li><li>Dedicated</li></ul>	iess Steei)	Dipper Weii Wizard™	Subme	ersible Pump
her:		Other:			
L INTEGRITY: OK				I OCY #	3759
				LOOK#:	
MARKS:	<del></del>				<del></del>
					····

Reviewed By:

Page \_/\_ of \_3\_

Location of previous calibration: \_\_

WATER SAMPLE FIELD	DATA SHEET	lev. 2, 5/1
PROJECT NO: <u>6670-039-01</u>	SAMPLEID: MW-7	
EMCON PURGED BY: 5 Williams C		148
SAMPLED BY: Juliam		<del>-</del> -
	Oakland C	<b>7</b> 4
TYPE: Ground Water Surface Water Treatment	Effluent Other	
CASING DIAMETER (inches): 2 3 4		
CASING ELEVATION (feet/MSL): VOLUM	ME IN CASING (gal.):	
DEPTH TO WATER (feet): CALCUI	LATED PURGE (gal.):	/
DEPTH OF WELL (feet): ACTUAL	PURGE VOL (gal.):	
	7	
DATE PURGED: NR Start (2400 Hr)	End (2400 Hr)	
1	End (2400 Hr)	
DATE SAIN CLES.	Lina (2400 / ii)	
TIME VOLUME pH E.C. TEM (2400 Hr) (gal.) (units) (umhos/cm@ 25° C)		BIDITY
(2400 Hr) (gal.) (units) (μmhos/cm@ 25° C)	(1) (Visual) (Vi	isuai)
D. O. (ppm): <u>WP</u> ODOR: <u>510 WS</u>	ar ar	<u>e_</u>
	(COBALT 0 - 100) (NTU	0 - 200)
FIELD QC SAMPLES COLLECTED AT THIS WELL (i.e. FB-1, XDUP-1):	VR.	<del></del>
	CAACURE FOURTH	
PURGING EQUIPMENT	SAMPLING EQUIPMENT	
2° Bladder Pump Bailer (Teffon®) 2° Bl	ladder Pump —— Bailer (Teflon®	))
	Sampler — Bailer (Stainles	s Steel)
Submersible Pump —— Bailer (Stainless Steel) —— Dipp		ump
Others	Wizard <sup>TM</sup> — Dedicated	
Other: Other:		
VELL INTEGRITY:	LOCK#: 3259	
Oradin + Mickales	3/	
EMARKS:		

REMARKS:	Product	TRICK NESS	3/	
		153 Meter Serial #: 9		
(EC 1000/_	) ( DI) ( pH 7	7) (pH 10	/) ( pl	H 4/)

Signature: Joe Walter \_\_ Page <u>こ</u> of <u>3</u> \_\_\_\_ Reviewed By: \_\_\_

WATER SAMPLE FIELD DATA SHEET Rev. 2.	, 5/91
PROJECT NO: <u>0670-039-01</u> <b>SAMPLE ID:</b> <u>MW-3</u>	
EMCON PURGED BY: 5 William 5 CLIENT NAME: 4RCO 6148	
SAMPLED BY: 5Williams LOCATION: 5/31 Shattus	cktu
Oakland CA	
TYPE: Ground Water Surface Water Treatment Effluent Other	
CASING DIAMETER (inches): 2 3 4 4.5 6 Other	
CASING ELEVATION (feet/MSL): WR VOLUME IN CASING (gal.): 41.52	
DEPTH TO WATER (feet):	<del>-</del>
DEPTH OF WELL (feet): 25.80 ACTUAL PURGE VOL. (gal.):	<del>-</del>
DEL TITO CONTROL TO THE TOTAL	
DATE PURGED: 10-07-92 Start (2400 Hr) 1220 End (2400 Hr) 1247	
DATE SAMPLED: 10-07-92 Start (2400 Hr) 1250 End (2400 Hr)	-
,	-
TIME VOLUME pH E.C. TEMPERATURE COLOR TURBIDITY (2400 Hr) (gal.) (units) (umhos/cm@ 25° C) (°F) (visual) (visual)	Y
1228 5 6.33 473 75.8 GRZY HEAVY	
1233 10 6.41 575 73,7 BREY HEAVY	١١
1239 15 6.41 560 72.2 CLEAR CLEAR	-
1244 20 6.45 567 71.9 CLEAR CLEAR	- ; ;
1247 24 6.41 568 72,1 CLEAR LLEAR	
D. O. (ppm): WR ODOR: STROWS WR NR	-
(COBALT 0 - 100) (NTU 0 - 200)	-
FIELD OC SAMPLES COLLECTED AT THIS WELL (i.e. FB-1, XDUP-1): FB-1 (12:27)	_
CLUCING SCHUDNENT SAMPLING SCHUDNENT	
PURGING EQUIPMENT  SAMPLING EQUIPMENT	
2° Bladder Pump Bailer (Teflon®) 2° Bladder Pump Bailer (Teflon®)	-
Centrifugal Pump — Bailer (PVC) - DDL Sampler — Bailer (Stainless Steet)  Submersible Pump — Bailer (Stainless Steet) — Dipper — Submersible Pump	'
Submersible Pump — Bailer (Stainless Steel) — Dipper — Submersible Pump — Submersible Pump — Dedicated — Well Wizard <sup>TM</sup> — Dedicated	} }
Other: Other:	.
22 F9	_
LL INTEGRITY: OR LOCK #: 3259	-
MARKS: NO SAMPLE TAKE AFTER PURGANG PFTER DURRELLE PRODUCT CAME IN 02 FETION	-
HI THE TUPE INC FORME CITIES ON SECTION	_

WELL INTEGRITY: OR  REMARKS: NO SAMPLE TAKE AFTER A  PFTER PUREEINTE Product CAME. IN  barler	LOCK#: 3259 DIRGING OZ Fetlon
Meter Calibration: Date: 10-07-92 Time: 10:55 Meter Senai #: 9/1/  (EC 1000/) (DI) (pH 7/) (pH 10/	Temperature °F:
Signature: Joe W. Heviewed By: TB	Page <u>3</u> of <u>3</u>

Anteg !	Division	of Atlantic	Office RichfieldC	carry 4		•		Task Or	der No.	61	48		72	- 2	2.5							Chain of Custo	dy
ARCO Facilit	y no.	148		City	/ cility) /	Jak	lan	<u></u>		Project	manag	er -	Toe	Q	Co	4	m	~N				Laboratory name	
ARCO engine	er M	ncha	بعا	143	مه ام	·^	Telephon	e no. 4 15	1)20	Telepho	ne no.	(400	7 2	3V-7	72	} Fax	no. (	408	26	4- Z	1/35	Segoura	~
Consultant na	ame	PESNI	Δ -	r _l	1.	0 - 7	T(ARCO)	Address	737 7315	Consul	tant)	4-			<u>۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ ۔ </u>	(Co	nsultan	<u>()</u>	<del>/</del> - 5	· U		Contract number	
	- 14	.671	/\ _	WCM.	579/-	د حد	n(.	(Consulta	int)	<del></del>	500	3	تَعِكَ	7	*	951	Ø /	>-/	دما	> 7		07-073	)
				Matrix	:	Prese	vation						1	1				Ęŏ	001700			Method of shipment	
Sample I.D.	Lab no.	Container no.	Soit	Water	Other	lce	Acid	Sampling date	Sampling time	BTEX 602/EPA 8020	BTEX/TPH EPA M602/8020/8015	TPH Modified 8015 Gas Diesel	Oil and Grease 413.1 C 413.2 C	TPH EPA 418.1/SM503E	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Se Metals   VOA   V	CAM Metals EPA 6010/7000	Lead Org./DHS CLead EPA			
- 16 -MW	1	3		X		X	×	11/12/92	1510		$\times$							-	1	,		Special detection Limit/reporting	
16-WW		3		X		$\succ$	X		1200		X							,	4				
14-MW	6	3		7		7	$\succ$		1330		X								1	1			
14-MW	7	3		X		メ	×	$\checkmark$	1420		$\prec$							U	4	,		Special QA/QC	
				ļ																			
																					-		
	•	,							- ***													Remarks	÷
																			-				
																				-		<del></del> :	·
	1								7	ļ			_					ļ		ļ			
								7	<del></del>							<u> </u>		-	<u> </u>			<del></del>	
									·									$\vdash$		<u> </u>	-		
		-						<del></del> -						-					<del> </del>	<u> </u>		Lab number	
																						Turnaround time	
														<del> </del>								Priority Rush	
Condition of		<b>\</b>			$\Box$	nd				Temp	erature	receive	ed:	J	1	Δ/	10	\r	1	<u> </u>	<u> </u>	1 Business Day	
Relinquishe	4-7	/ · ·	E.	D		1	Date   1 / 1 3 /	92	Time 1000	Rece	lved/by	nil	D.C	1	Te			<u> </u>	./1			Rush 2 Business Days	
Refinquistle 10	W	<b>(1)</b>	Co		ell			92	113 <sup>Time</sup>		ived by		Wife		\	u.JV	h	-	1397	L 1	175	Expedited 5 Business Days	
Relinquiste	a by V	11/11	.	W/M	<u> </u>	· · · · · · · · · · · · · · · · · · ·	Date /	3/12	Time	Rece	- 1	laborat	tory	e E	<i>}</i>	V	Date	3-0	7)	Time	X Dr	Standard 10 Business Days	$\nearrow$

000.1 - 1992

-Ferna - Land Confi

**RESNA** 

3315 Almaden Expwy., Suite 34

San Jose, CA 95118 Attention: Joel Coffman

Project: ARCO 6148, Oakland

Enclosed are the results from 4 water samples received at Sequoia Analytical on November 13,1992. The requested analyses are listed below:

SAMPLE #	SAMPLE DESCRIPTION	DATE OF COLLECTION	TEST METHOD
2112545	Water, W-16-MW4	11/12/92	EPA 5030/8015/8020
2112546	Water, W-16-MW5	11/12/92	EPA 5030/8015/8020
2112547	Water, W-14-MW6	11/12/92	EPA 5030/8015/8020
2112548	Water, W-14-MW7	11/12/92	EPA 5030/8015/8020

Please contact me if you have any questions. In the meantime, thank you for the opportunity to work with you on this project.

Very truly yours,

SEQUOIA ANALYTICAL

Maria Lee Project Manager



RESNA

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman First Sample #:

Client Project ID: Sample Matrix: ARCO 6148, Oakland

\*\*\*\*\*

Sampled: Nov 12, 1992

Water EPA 5030/8015/8020 Received:

Nov 13, 1992

Analysis Method: First Sample #:

211-2545

Reported:

Nov 25, 1992

#### TOTAL PURGEABLE PETROLEUM HYDROCARBONS with BTEX DISTINCTION

Analyte	Reporting Limit μg/L	Sample I.D. 211-2545 W-16-MW4	Sample I.D. 211-2546 W-16-MW5	Sample I.D. 211-2547 W-14-MW6	Sample I.D. 211-2548 W-14-MW7
Purgeable Hydrocarbons	50	77	2,900	51	N.D.
Benzene	0.50	32	1,300	2.6	1.8
Toluene	0.50	N.D.	12	N.D.	N.D.
Ethyl Benzene	0.50	N.D.	67	N.D.	N.D.
Total Xylenes	0.50	N.D.	18	N.D.	N.D.
Chromatogram Patte	ern:	Gas & Discrete Peaks	Gas & Discrete Peaks	Gas & Discrete Peaks	••

**Quality Control Data** 

Report Limit Multiplication Factor:	1.0	20	1.0	1.0
Date Analyzed:	11/20/92	11/20/92	11/20/92	q
Instrument Identification:	GCHP-2	GCHP-2	GCHP-2	GCHP-2
Surrogate Recovery, %: (QC Limits = 70-130%)	97	92	93	97

Purgeable Hydrocarbons are quantitated against a fresh gasoline standard. Analytes reported as N.D. were not detected above the stated reporting limit.

**SEQUOIA ANALYTICAL** 

Maria Lee Project Manager

2112545.RES <1>



Client Project ID: ARCO 6148, Oakland

3315 Almaden Expwy., Suite 34

San Jose, CA 95118

Attention: Joel Coffman

QC Sample Group: 2112545-8 

Reported: Nov 25, 1992 

#### **QUALITY CONTROL DATA REPORT**

ANALYTE	Ethyl-				
	Benzene	Toluene	benzene	Xylenes	
Method:	EPA 8020	EPA 8020	EPA 8020	EPA 8020	
Analyst:	M. Nipp	M. Nipp	M. Nipp	M. Nipp	
Reporting Units:	μg/L	μg/L	μg/L	μg/L	
Date Analyzed:	Nov 20, 1992	Nov 20, 1992		Nov 20, 1992	
QC Sample #:	GBLK112092	GBLK112092	GBLK112092	GBLK112092	
	MS/MSD	MS/MSD	MS/MSD	MS/MSD	
Sample Conc.:	N.D.	N.D.	N.D.	N.D.	
Spike Conc.					
Added:	10	10	10	30	
<b>Dana</b>		, 5			
Conc. Matrix					
	11	11	11	32	
Spike:	11	• •	11	UZ.	
Matrix Spike			440	407	
% Recovery:	110	110	110	107	
Conc. Matrix					
Spike Dup.:	11	11	10	32	
- h					
Matrix Spike					
Duplicate					
% Recovery:	110	110	100	107	
-					
Relative					
% Difference:	0.0	0.0	9.5	0.0	
A Dilicicitor.	0.0	4.0			

Quality Assurance Statement: All standard operating procedures and quality control requirements have been met.

SEQUOIA ANALYTICAL

Conc. of M.S. - Conc. of Sample x 100 % Recovery: Spike Conc. Added Conc. of M.S. - Conc. of M.S.D. x 100 Relative % Difference: (Conc. of M.S. + Conc. of M.S.D.) / 2 2112545.RES <2>

Project Manager