SUD 12)7



EN YOUGHNINTAL PERFECTION

CONTROL OF A INTER-COMPANY MEMORANDUM

To: Tom Peacock - ACHA-DEP

Date: 29 December 1998

Tele: 650.569.4020/Fax: 650.569.4023

From: Woody Lovejoy - ProTech

cc: Project File

Re:

Letter Reports - 969 San Pablo Avenue, Albany

Tom:

As directed by Susan Hugo, I am forwarding these documents to you. Ms. Hugo has informed me that you will be taking over responsibility for this site

As we discussed, here are copies of the letter reports prepared for the above-referenced site. The May 1998 report was prepared to document groundwater sampling, performed at the site during the due diligence investigation, prior to Kelly-Moore's purchase of the property. The December 1998 report was prepared to document the removal and closure of 5 hydraulic lifts at the site.

As agreed with Ms. Hugo, Kelly-Moore will be installing two new wells on the site. One is to gain groundwater data up-gradient of the former UST location and the second is to better monitor groundwater in the vicinity of former hydraulic ram #1. We will be preparing a workplan in January for this work and will be sending it to you for review and approval.

Please review this information and let me know if you have any questions and/or comments. The best way to reach me is to page me(415.998.1992).

Thank you for your help with this project.



SOUTE SO PM 2:40

ENVIRONMENTAL SERVICES

23 December 1998

CONSULTING & ENGINEERING

Mr. W. E. Berry Manager Store Planning & Real Estate **Kelly-Moore Paint Company** 987 Commercial Street, PO Box 3016 San Carlos, CA 94070

Re: Letter Report

Hydraulic Lift Removal

969 San Pablo Avenue, Albany, California

ProTech Project #731-OH98

Dear Mr. Berry:

We have prepared this letter report to document the closure of five hydraulic lifts that were present at the above-referenced site (Figures 1 and 2). The scope-of-work performed and the results of soil sample analyses are described below. Tables, Figures, and laboratory reports and chain-of-custody (COC) forms are attached.

Scope-of-Work

Hydraulic Lift Removal

On 12 September 1998, five hydraulic rams were excavated and removed from their in-ground locations. The rams were wrapped in plastic and transported to Kelly/Moore's paint processing plant in San Carlos for proper handling and disposal. Kelly/Moore drained the rams of oil, placed the drained oil into their recycling waste oil container in San Carlos, and recycled the rams at SimsMetal America (Attachment 1). Soil was excavated during the ram removal and stockpiled on-site. The ram locations and numbering scheme is shown on Figure 3.

Ram #1 was excavated to approximately 8.5 feet below grade (fbg). The ram was compromised, in bad condition and appeared to have leaked. Soil was stained grey and had a strong petroleum odor. The excavation was extended down to 8.5 fbg in an attempt to clean out the contamination prior to sampling. A soil sample (#1) was collected from approximately 8.5 fbg by driving a brass tube into a backhoe bucket full of soil from this depth. The tube was capped, labeled and placed on ice pending transport to ChromaLab, Inc. (ChromaLab), of Pleasanton, a California-certified analytical laboratory.

TELE: 650.569.4020/FAX: 650.569.4023

Depth-to-water (DTW) was measured in May in the two on-site groundwater monitor wells at between 7.33 and 7.52 fbg.

Ram #2 was excavated down to approximately 7 fbg. The ram was in good condition with its bitumen coating still intact, and did not appear to have leaked. The soil exposed during excavation did not indicate the presence of petroleum hydrocarbons. No soil sample was collected from this excavation.

Ram #3 was excavated down to approximately 7 fbg. The ram was in good condition with its bitumen coating still intact, and did not appear to have leaked. The soil exposed during excavation did not indicate the presence of petroleum hydrocarbons. No soil sample was collected from this excavation.

Ram #4 was excavated to approximately 10 fbg. The ram appeared to be in good condition, but the exposed soil indicated that leakage had occurred. Soil was stained grey and had a faint petroleum odor. The excavation was extended down to 10 fbg in an attempt to clean out the contamination prior to sampling. A soil sample (#4) was collected from approximately 10 fbg by driving a brass tube into a backhoe bucket full of soil from this depth. The tube was capped, labeled and placed on ice pending transport to ChromaLab.

Ram #5 was excavated to approximately 8 fbg. The ram appeared to be in good condition, but the exposed soil indicated that leakage had occurred. Soil was stained grey and had a faint petroleum odor. The excavation was extended down to 8 fbg in an attempt to clean out the contamination prior to sampling. A soil sample (#5) was collected from approximately 8 fbg by driving a brass tube into a backhoe bucket full of soil from this depth. The tube was capped, labeled and placed on ice pending transport to ChromaLab.

The excavated soil was segregated based on odors and visual inspection, and stockpiled into "likely dirty" and "likely clean" piles. Shallow soil (upper 3 feet of soil) from all five ram excavations were stockpiled as "likely clean." Soil excavated from around rams #s 2 and 3 were also stockpiled as "likely clean." Soil from ram #s 1, 4 sand 5 were stockpiled as "likely dirty." Four soil samples (SP-1, 2, 3, 4) were collected from the two "likely dirty" stockpiles that were generated. The samples were collected by driving a brass tube into a backhoe bucket full of soil from this depth. The tube was capped, labeled and placed on ice pending transport to ChromaLab.

Additional soil was removed from Pit #1 on 10 October 1998. An additional 2 feet of soil was removed from the pit and stockpiled with the "likely dirty" soil. The excavation was extended to 10.5 fbg, where soil was removed for the collection of a sample. The sample (#1-2) was collected by driving a brass tube into a backhoe bucket full of soil from the 10.5 fbg depth. The tube was capped, labeled and placed on ice pending transport to ChromaLab.

Soil Sample Analyses

The results of soil sample analyses are presented below. They are tabled in Table 1, and shown on Figure 3. Laboratory reports and COC forms are included as Attachment 2.

The three soil samples (#1, #4, and #5) that were collected from soil from the bottom of the



excavations for the rams were analyzed for: the five LUFT metals (cadmium (Cd), total chromium (Cr), lead (Pb), nickel (Ni), and zinc (Zn); total extractible petroleum hydrocarbons, characterized as hydraulic oil (TEPH-ho); and aromatic hydrocarbons (benzene, toluene, ethyl-benzene, and xylenes, [BTEX]).

The results of LUFT metals analyses indicated that soil from the pits were within expected, and regulatory acceptable ranges for each of the five metals. Results of TEPH-ho analyses indicated soil from pit #1 contained 500 parts-per-million (ppm), while soil from pit #s 4 and 5 were both below the method detection limit (MDL). Results of BTEX analyses indicated that all three pit soil samples were below the MDLs for each compound.

The composite group (SP-1, 2, 3, 4) collected from the "likely dirty" stockpiles were analyzed for LUFT metals, TEPH-ho, BTEX, and volatile organic compounds (VOCs). The results for LUFT metals analyses indicated that all five metals were within expected, and regulatory acceptable concentrations. Results of the TEPH-ho analysis indicated that 1900 ppm was present in the soil composite sample. Results of the BTEX analyses were all below MDLs for the analyzed compounds. Results of VOCs analyses were also below MDLs for the analyzed compounds.

Given the analytical results from pit #1, an additional sample (#1-2) was collected for analysis for TEPH-ho only. Results of this analysis indicated that TEPH-ho was present at 1400 ppm.

Management of Stockpiled Soil

Four stockpiles were created during this work, two were "likely clean" and two are "likely dirty." The locations and designation of the stockpiles are shown on Figure 3. Approximately 18 yds³ of "likely dirty" soil was generated during the removal of the 5 hydraulic rams. The results of stockpile analysis and a profile request form were submitted to Forward Landfill of Manteca, California (Forward), a Subtitle D - Class II - "designated" landfill, for their review and acceptance. The soil was accepted by Forward as a Class II - "designated" solid waste. The soil was loaded and transported to Forward on 10 October 1998 for proper disposal. The non-hazardous waste manifest is included as Attachment 3.

Conclusions

The five hydraulic rams were removed from the site on 12 September 1998. Excavated soil from the upper 3 feet of each excavation and the soil from Pit #2 and 3 were stockpiled as "likely clean" because there was no visual or olfactory evidence of contamination. Excavated soil from below 3 fbg in pit #s 1, 4, and 5 were stockpiled as "likely dirty" because there was visual and olfactory evidence of contamination. Soil samples were collected from soil from the bottom of the excavations for pit #s 1, 4, and 5 for analysis for LUFT metals, TEPH-ho, and BTEX. Results indicated that soil from pit #s 4 and 5 were within expected ranges for metals and below the MDLs for TEPH-ho and BTEX, while soil from pit #1 was within the expected ranges for LUFT metals, contained 500 ppm TEPH-ho, and was below the MDLs for BTEX. The second sample (#1-2) collected from pit #1 was analyzed for TEPH-ho and found to contain 1400 ppm.



The "likely dirty" stockpile soil composite sample contained TEPH-ho at 1900 ppm, was within acceptable ranges for LUFT metals and was below the MDLs for BTEX and VOCs. The soil was profiled at Forward as a non-hazardous, Class II - "designated" waste. The soil was loaded, transported, and disposed of at Forward on 10 October 1998.

The 5 pits were backfilled with the approval of the Alameda County Health Agency - Division of Environmental Protection (County) after the results of sampling were transmitted to them for review and approval. The "likely clean" soil was used, with County approval, to top off the excavations after engineered fill was used as backfill, especially in the area below the water table.

The remaining contamination in pit #1 is below the water table at the site. Since there are two groundwater monitor wells on-site and two more are being planned, monitoring for TEPH-ho will be added to the analysis protocol.

Please review this letter report and attached information and let me know if you have any questions and/or comments (650.569.4020). We look forward to continuing work on this project if the purchase is successful.

Sincerely,

PROTECH CONSULTING AND ENGINEERING

Sherwood Lovejoy, Jr.

Principal Environmental Assessor

Cal-REA #03171

Table: 1 - LUFT Metals, and TPH Analytical Results

2 - VOC Analytical Results

Figure:

1 - Site Location Map

2 - Site Vicinity Map

3 - Site Plan w/ Analytical Results

Attachment:

1 - SimsMetal America Documentation

2 - Laboratory Reports and COC Forms

3 - Non-Hazardous Waste Manifest

TABLES

TABLE 1: LUFT METALS, and TPH ANALYTICAL RESULTS Hydraulic Lift Removal - Pit Soil Sampling Kelly-Moore Paint, 969 San Pablo Avenue, Albany, California

Constituent	#1	#1-2	#4	#5	SP-1,2,3,4
Matrix	Soil	Soil	Soil	Soil	Soil
	2. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3.	. E. Gippilpik Elabbida 2200 bir Jakan biraki salabada 3. Sanbada			
Cadmium	ND(0.5)		ND(0.5)	ND(0.5)	ND(0.5)
Total Chromium	32		40	25	42
Lead	3.7	-	9.6	3.7	4.2
Nickel	57		110	35	46
Zinc	31		38	22	30
TEPH - ho	500	1400	ND(50)	ND(50)	1900
Benzene	ND(0.005)		ND(0.005)	ND(0.005)	ND(0.005)
Toluene	ND(0.005)		ND(0.005)	ND(0.005)	ND(0.005)
Ethyl Benzene	ND(0.005)		ND(0.005)	ND(0.005)	ND(0.005)
Total Xylenes	ND(0.005)		ND(0.005)	ND(0.005)	ND(0.005)

tes: #1 = Pit number and sample number; #1-2 =deeper sample in same pit #; SP-1,2,3,4 = stockpiled soil sample; ND(0.5) = not detected (detection limit), TEPH-ho = total extractible petroleum hydrocarbons, characterized as hydraulic oil; Total Chromium = trivalent and hexavalent forms, Total Xylenes = three isomers (ortho, meta, and para).


TABLE 2: VOC ANALYTICAL RESULTS Hydraulic Lift Removal - Pit Soil Sampling Kelly-Moore Paint, 969 San Pablo Avenue, Albany, California

Kelly-Moore Paint, 969 San Pablo Avenue, Albany, Ca	morna
	SP-1,2,3,4
Constituent Matrix	Soil
Acetone	ND(50)
Benzene	ND(5)
Bromodichloromethane	ND(5)
Bromoform	ND(5)
Bromomethane	ND(10)
2-Butanone (MEK)	ND(50)
Carbon Tetrachloride	ND(5)
Chlorobenzene	ND(5)
Chloroethane	ND(5)
2-Chloroethylvinylether	ND(10)
Chloroform	ND(5)
Chloromethane	ND(10)
Dibromochloromethane	ND(5)
1,1-Dichloroethane	ND(5)
1,2-Dichloroethane	ND(5)
1,1-Dichloroethylene	ND(5)
cis 1,2-Dichloroethylene	ND(5)
trans 1,2-Dichloroethylene	ND(5)
1,2-Dichloropropane	ND(5)
1,2-Dichloropropene	ND(5)
trans-1,3-Dichloropropene	ND(5)
Ethyl Benzene	ND(5)
2-Hexanone (MBK)	ND(50)
Methylene Chloride	ND(5)
4-Methyl-2-Pentanone (MIBK)	ND(50)
Styrene	ND(5)
1,1,2,2-Tetrachloroethane	ND(5)
Tetrachloroethylene	ND(5)
Toluene	ND(5)
1,1,1-Trichloroethane	ND(5)

TABLE 2: VOC ANALYTICAL RESULTS Hydraulic Lift Removal - Pit Soil Sampling Kelly-Moore Paint, 969 San Pablo Avenue, Albany, California

		SP-1,2,3,4
Constituent	Matrix	Soil
1,1,2-Trichloroethane		ND(5)
Trichloroethylene		ND(5)
Trichlorofluoromethane		ND(5)
Vinyl Acetate		ND(50)
Vinyl Chloride		ND(5)
Total Xylenes		ND(5)

FIGURES



ProTech Consulting & Engineering


Job No. 980116 Date 22 Dec 1998 Drawn by WL Rev. WL Apprvd. WL

Project
Site Location Map
Hydraulic Lift Removal Program
Kelly-Moore Paint Compant
969 San Pablo Avenue, Albany, CA



Figure

1



ProTech Consulting & Engineering

Job No. 980116 Date 22 Dec 1998 Drawn by WL Rev-WL Apprvd. WI


Site Vicinity Map Hydraulic Lift Removal Program Kelly-Moore Paint Compant 969 San Pablo Avenue, Albany, CA





Project

Figure

2







ProTech Consulting & Engineering

Job No.	980116
Date 2	2 Dec 1998
Drawn by	WL.
Rev WL	Apprvd WL

Site Plan w/Analytical Results
Hydraulic Lift Removal Program
Kelly-Moore Paint Company
969 San Pablo Avenue, Albany, California

∢z


Project

3

Figure

ATTACHMENT 1 SIMSMETAL AMERICA DOCUMENTATION





OIL WAS PICKED UP BY EVERGREEN OIL NEWARK CA 5107954400

ATTACHMENT 2 LABORATORY REPORTS & COC FORMS



Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for TEPH analysis.

Method: EPA 8015M

Client Sample ID: #1

Sp1#: 205875 Sampled: September 12, 1998

Matrix: SOIL Run#:14916

Extracted: September 16, 1998

Analyzed: September 21, 1998

REPORTING BLANK BLANK DILUTION RESULT LIMIT RESULT SPIKE FACTOR <u>ANALYTE</u> (mg/Kg)

HYDRAULIC OIL

Note: Quantitation for the above Analyte is based on the response factor

of Motor Oil. Hydrocarbon reported does not match the pattern of our Hydraulic Oil Standard. Surrogate Recoveries biased high due to

Hydrocarbon co-elution.

Bruce Havlik

Analyst

20

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for BTEX analysis.

Method: SW846 8020A Nov 1990

Client Sample ID: #1

Spl#: 205875

Matrix: SOIL

Sampled: September 12, 1998 Run#:14926

Analyzed: September 16, 1998

ANALYTE	RESULT (mq/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK SPIKE (%)	PACTOR	
BENZENE	N.D.	0.0050	N.D.	99	1	
TOLUENE	N.D.	0.0050	N.D.	95	1	
ETHYL BENZENE	N.D.	0.0050	N.D.	99	1	
XYLENES	N.D.	0.0050	N.D.	97	1	

Vincent Vancil

Analyst

Environmental Services (SDB)

September 18, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for Miscellaneous Metals analysis.

Method: EPA 3010A/3050A/6010A Nov 1990

Client Sample ID: #1

Spl#: 205875

Matrix: SOIL

Extracted: September 16, 1998

Sampled: September 12, 1998 Run#:

14905

Analyzed: September 16, 1998

ANALYTE	RESULT (mg/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK SPIKE (%)	DILUTION FACTOR
CADMIUM	N.D.	0.50	N.D.	99.9	1
CHROMIUM	32	1.0	N.D.	97.9	1
LEAD	3.7	1.0	N.D.	99.6	ī
NICKEL	57	1.0	N.D.	98.9	ĩ
ZINC	31	1.0	N.D.	97.8	ī

Analyst

Verona

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for TEPH analysis.

Method: EPA 8015M

Client Sample ID: #4

Sp1#: 205876

Matrix: SOIL

Extracted: September 16, 1998

Sampled: September 12, 1998 Run#:14916 Analyzed: September 19, 1998

REPORTING BLANK BLANK DILUTION RESULT LIMIT RESULT SPIKE FACTOR

<u>ANALYTE</u> (mg/Kg) <u>(mg/Kg)</u> (mg/Kg) HYDRAULIC OIL N.D.

Bruce Havlik FA

Analyst

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for BTEX analysis.

Method: SW846 8020A Nov 1990

Client Sample ID: #4

Spl#: 205876

Matrix: SOIL

Sampled: September 12, 1998 Run#:14926

D----# 1400C

Analyzed: September 16, 1998

ANALYTE	RESULT (mg/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK SPIKE (%)	DILUTION FACTOR
BENZENE	N.D.	0.0050	N.D.	99	1
TOLUENE	N.D.	0.0050	N.D.	95	1
ETHYL BENZENE	N.D.	0.0050	N.D.	99	1
XYLENES	N.D.	0.0050	N.D.	97	1

Vincent Vancil

Analyst

Michael Verona

Environmental Services (SDB)

September 18, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for Miscellaneous Metals analysis.

Method: EPA 3010A/3050A/6010A Nov 1990

Client Sample ID: #4

Spl#: 205876

Matrix: SOIL

Extracted: September 16, 1998

Sampled: September 12, 1998 Run#: 14905 Analyzed: September 16, 1998

	RESULT	REPORTING LIMIT	Blank Result	BLANK SPIKE	DILUTION FACTOR
ANALYTE	(mg/Kg)	(mg/Kg)	(mg/Kg)	(%)	
CADMIUM	N.D.	0.50	N.D.	99.9	1
CHROMIUM	40	1.0	N.D.	97.9	1
LEAD	9.6	1.0	N.D.	99.6	1
NICKEL	110	1.0	N.D.	98.9	1
ZINC	38	1.0	N.D.	97.8	1

Christopher Arndt

Analyst

Niehael Verona

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for TEPH analysis.

Method: EPA 8015M

Client Sample ID: #5

Spl#: 205877

Matrix: SOIL

Extracted: September 16, 1998

Sampled: September 12, 1998

Run#:14916

Analyzed: September 21, 1998

REPORTING

BLANK BLANK DILUTION

RESULT (mg/Kg)

LIMIT (mg/Kg) RESULT

SPIKE FACTOR

(mg/Kg)

HYDRAULIC OIL

Bruce Havlik Fr Analyst

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for BTEX analysis.

Method: SW846 8020A Nov 1990

Client Sample ID: #5

Sp1#: 205877

Matrix: SOIL

Sampled: September 12, 1998 Run#:14926

ACTIX: BOID

Analyzed: September 16, 1998

ANALYTE	RESULT (mg/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK SPIKE (%)	DILUTION FACTOR
BENZENE	N.D.	0.0050	N.D.	99	1
TOLUENE	N.D.	0.0050	N.D.	95	1
ETHYL BENZENE	N.D.	0.0050	N.D.	99	1
XYLENES	N.D.	0.0050	N.D.	97	1

Vincent Vancil

Analyst

Michael Veron

Environmental Services (SDB)

September 18, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116 -

Received: September 14, 1998

re: One sample for Miscellaneous Metals analysis.

Method: EPA 3010A/3050A/6010A Nov 1990

Client Sample ID: #5

Spl#: 205877

Matrix: SOIL

Extracted: September 16, 1998

Sampled: September 12, 1998 Run#:

14905

Analyzed: September 16, 1998

ANALYTE	RESULT (mg/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK SPIKE (%)	DILUTION FACTOR
CADMIUM	N.D.	0.50	N.D.	99.9	1
CHROMIUM	2 5	1.0	N.D.	97.9	1
LEAD	3.7	1.0	N.D.	99.6	$ar{f 1}$
NICKEL	35	1.0	N.D.	98.9	ī
ZINC	22	1.0	N.D.	97.8	ī

Analyst

Verona

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Received: September 14, 1998

Project#: 980116

re: One sample for TEPH analysis.

Method: EPA 8015M

Client Sample ID: SP-1,2,3,4

Sp1#: 205878

Matrix: SOIL

Extracted: September 16, 1998

Sampled: September 12, 1998

Run#:14916

Analyzed: September 21, 1998

ANALYTE

RESULT

REPORTING LIMIT

BLANK RESULT BLANK DILUTION SPIKE

FACTOR

(mg/Kg)

(mg/Kg)

(mg/Kg)

50

HYDRAULIC OIL

500

Note:

Quantitation for the above Analyte is based on the response factor of Motor Oil. Hydrocarbon reported does not match the pattern of our Hydraulic Oil Standard. Surrogate diluted out.

Bruce Havlik

Analyst

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

980116 Project#:

Received: September 14, 1998

re: One sample for BTEX analysis.

Method: SW846 8020A Nov 1990

Client Sample ID: SP-1,2,3,4

Spl#: 205878

Matrix: SOIL

Sampled: September 12, 1998 Run#:14942

Analyzed: September 16, 1998

ANALYTE	RESULT (mg/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK I SPIKE (%)	DILUTION FACTOR
BENZENE	N.D.	0.0050	N.D.	102	1
TOLUENE	N.D.	0.0050	N.D.	. 99	1
ETHYL BENZENE	N.D.	0.0050	N.D.	99	1
XYLENES	N.D.	0.0050	N.D.	100	1

Vincent Vancil

Analyst

Environmental Services (SDB)

September 18, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for Miscellaneous Metals analysis.

Method: EPA 3010A/3050A/6010A Nov 1990

Client Sample ID: SP-1,2,3,4

Sp1#: 205878 Matrix: SOIL Extracted: September 16, 1998

Sampled: September 12, 1998 Run#: 14905 Analyzed: September 16, 1998

ANALYTE	RESULT (mg/Kg)	REPORTING LIMIT (mg/Kg)	BLANK RESULT (mg/Kg)	BLANK : SPIKE (%)	DILUTION FACTOR
CADMIUM	N.D.	0.50	N.D.	99.9	1
CHROMIUM	42	1.0	N.D.	97.9	ī
LEAD	4.2	$\bar{1}.\bar{0}$	N.D.	99.6	ī
NICKEL	46	1.0	N.D.	98.9	วิ
ZINC	30	1.0	N.D.	97.8	ī

Analyst

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#: 980116

Received: September 14, 1998

re: One sample for Volatile Organics by GC/MS analysis.

Method: SW846 Method 8260A Sept 1994

Client Sample ID: SP-1,2,3,4

Spl#: 205878 Matrix: SOIL

Sampled: September 12, 1998 Run#: 14974 Analyzed: September 15, 1998

bampied. September 12, 1990	ittiin.	145/4	mary nout	<u> </u>	
		REPORTING	BLANK	BLANK	DILUTION
	RESULT	LIMIT	RESULT	SPIKE	FACTOR
			(ug/Kg)	(%)	PACTOR
ANALYTE	(ug/Kg)	<u>(ਪੂਰ੍ਹ/Kਰ)</u>			1
ACETONE	N.D	50	N.D.	90.9	
BENZENE	Ŋ.D.	5.0	N.D.	90.9	1 1 1
BROMODICHLOROMETHANE	N.D.	5.0	Ŋ.D.		
BROMOFORM	N.D.	5.0	N.D.		#
BROMOMETHANE	N.D.	10	N.D.		1 1 1
CARBON TETRACHLORIDE	N.D.	5.0	N.D.		Ť
CHLOROBENZENE	N.D.	5.0	N.D.	95.8	
CHLOROETHANE	N.D.	10	N.D.		1 1
2-BUTANONE (MEK)	N.D.	50	N.D.		1
2-CHLOROETHYLVINYLETHER	N.D.	50	N.D.		1 1
CHLOROFORM	N.D.	5.0	N.D.		1
CHLOROMETHANE	N.D.	10	N.D.		1
DIBROMOCHLOROMETHANE	N.D.	5.0	N.D.		1
1,2-DICHLOROBENZENE	N.D.	5.0	N.D.	-	1 1 1
1,3-DICHLOROBENZENE	N.D.	5.0	N.D.		
1,4-DICHLOROBENZENE	N.D.	5.0	N.D.		ī
1,2-DIBROMO-3-CHLOROPROPANE	N.D.	50	N.D.	<u></u>	ī
1,2-DIBROMOETHANE	N.D.	10	N.D.		ī
DIBROMOMETHANE	N.D.	10	N.D.		ī
DICHLORODIFLUOROMETHANE	N.D.	10	N.D.		ī
1,1-DICHLOROETHANE	N.D.	5.0	N.D.		1 1 1 1 1 1 1 1
	N.D.	5.0	N.D.		†
1,2-DICHLOROETHANE		5.0	N.D.	99.3	÷
1,1-DICHLOROETHENE	Ŋ.D.	5.0		22.3	÷ 1
1,2-DICHLOROETHENE (CIS)	N.D.	5.0	N.D.		, ,
1,2-DICHLOROETHENE (TRANS)	N.D.	5.0	N.D.		<u>+</u>
1,2-DICHLOROPROPANE	N.D.	5.0	N.D.		1 1 1
CIS-1,3-DICHLOROPROPENE	N.D.	5.0	Ŋ.D.		Ţ.
TRANS-1,3-DICHLOROPROPENE	N.D.	5.0	Ŋ.D.		<u> </u>
ETHYLBENZENE	N.D.	5.0	N.D.		<u>_</u>
2-HEXANONE	Ŋ.D.	50	N.D.		1 1 1 1 1
METHYLENE CHLORIDE	N.D.	5.0	N.D.		1
4-METHYL-2-PENTANONE (MIBK)	N.D.	50	N.D.		ļ
NAPHTHALENE	N.D.	50	N.D.		1
STYRENE	N.D.	5.0	N.D.		1
1,1,2,2-TETRACHLOROETHANE	N.D.	5.0	N.D.		1
TETRACHLOROETHENE	N.D.	5.0	N.D.		1 1
TOLUENE	N.D.	5.0	N.D.	85.2	1
1,1,1-TRICHLOROETHANE	N.D.	5.0	N.D.		1
1,1,2-TRICHLOROETHANE	N.D.	5.0	N.D.		1
TRICHLOROETHENE	N.D.	5.0	N.D.	91.6	1 1 1
1,1,1,2-TETRACHLOROETHANE	N.D.	5.0	N.D.		1
VINYL ACETATE	N.D.	50	N.D.		ī
VINYL CHLORIDE	N.D.	5.0	N.D.		$ar{ exttt{1}}$
		~ . ~			-

Environmental Services (SDB)

September 21, 1998

Submission #: 9809176

page 2

TCG

Atten: Woody Lovejoy

Project: KELLY-MOORE (ALBANY)

Project#:

980116

Received: September 14, 1998

re: One sample for Volatile Organics by GC/MS analysis, continued.

Method: SW846 Method 8260A Sept 1994

Client Sample ID: SP-1,2,3,4

Sp1#: 205878

Matrix: SOIL

Sampled: September 12, 1998 Run#: 14974

Analyzed: September 15, 1998

ANALYTE	RESULT (ug/Kg)	REPORTING LIMIT (ug/Kg)	BLANK RESULT (ug/Kg)	BLANK SPIKE (%)	DILUTION FACTOR
TOTAL XYLENES	N.D.	10	N.D.		1
TRICHLOROTRIFLUOROETHANE	N.D.	5.0	N.D.		1
CARBON DISULFIDE	N.D.	5.0	N.D.		1
ISOPROPYLBENZENE	N.D.	5.0	N.D.		1
BROMOBENZENE	N.D.	5.0	N.D.		1
BROMOCHLOROMETHANE	N.D.	20	N.D.		1
TRICHLOROFLUOROMETHANE	N.D.	5.0	N.D.		1

Alex Tam Analyst

Michael Verona

91 N/205875-205616 CHROMALAB, INC.

REF ##41954

#: 4/954

Chain of Custody

9809176 DATE 12 Sept 98 PAGE 1 OF 1 Environmental Services (SDB) (DOHS 1094) projuga WOOR Lavegoing company TCG/Protech ADDRESS 394 Cecilic Way Tiburan CA 94720 ANALYSIS REPORT PURGEABLE AROMATICS BTEX (EPA 8020) TOTAL OIL AND GREASE (SM 5520 B+F. E+F) TPH-Diesel (EPA 8015M) PESTICIDES(EPA 8080) PCB'S (EPA 8080) TOTAL RECOVERABLE HYDROCARBONS (EPA O Spec. Cond. CAM 17 METALS (EPA 6010/7470/747 PNA's by | 8270 SEMIVOLATILES LUFT METALS: Cd. Cr. Pb. Ni. Zi SAMPLERS (SIGNATURE) (PHONE NO.) TOTAL LEAD NUMBER OF O W.E.T. (FAX NO.) F SS SAMPLE ID. TIME MATRIX PRESERV. OD 4 امركيهك PHOJECT INFORMATION SAMPLE RECEIPT RELINQUISHED BY RELINQUISHED BY **RELINQUISHED BY** Moore (Albany) 10"AL NO OF CONTAINERS HE, D SPACE SIGNATUREL 980116 TEMPERATURE PRINTED NAMEL TCG/Protee CONFORMS TO RECORD BTANDARD COMPANY 72 OTHER RECEIVED BY RECEIVED BY Report: | Routine | Level 2 | Level 3 | Level 4 SPECIAL INSTRUCTIONS/COMMENTS: - Sent Roults de Madylanja -4K.581-174)
-B.11 Protect for Analyses (SIONATURE COMPANY

Environmental Services (SDB)

October 19, 1998

Submission #: 9810194

TCG

Atten: Woody Lovejoy

Project: KELLY MOORE ALBANY

Project#: 980116

Received: October 12, 1998

re: One sample for TEPH analysis.

Method: EPA 8015M

Client Sample ID: #1-2

Spl#: 210083

Matrix: SOIL

Extracted: October 15, 1998

Sampled: October 10, 1998

Run#:15416

REPORTING

Analyzed: October 19, 1998

RESULT <u>ANALYTE</u>

LIMIT

BLANK RESULT

BLANK DILUTION SPIKE FACTOR

(mg/Kg)(mg/Kg)

(mg/Kg)

HYDRAULIC OIL

500

50

Note: Quantitation for the above Analyte is based on the response factor of Motor Oil. Surrogate diluted out.

Bruce Havlik Analyst

9910194/210085.

CHROMALAB, INC.

Environmental Services (SDB) (DOHS 1094)

SUBM #: 9810194 REP: GC

10/19/98 REF #: 42496

DATE 10 Oct 98 PAGE J OF 1

Reference #: 42496

Chain of Custody

PURGEABLE AROMATICS BTEX (EPA \$020) 94920

1/15-35/-25/0

(PHONE NO.)

1/15-35/-25/0

(FAX NO.)

1/15-55/-17-11

THE MATHIX PRESERV SAMPLERS (SIGNATURE) 100AF PROJECT INFORMATION SAMPLE RECEIPT RELINQUISHED BY RELINCUISHED BY PHOLECI MANE Selly Moore Aldery TOTAL NO OF CONTAINERS **TEMPERATURE** CONFORMS TO RECORD STANDARD RECEIVED BY special instructions/comments:

i) flow results be worth leverying

R. 11 Potech

ATTACHMENT 3 NON-HAZARDOUS WASTE MANIFEST