## **Harding Lawson Associates**



## Transmittal/Memorandum

To:

Alameda County Environmental Health Service 470 - 27th Street, Room 324 Oakland, California 94612

Attention: Mr. Storm Goranson, P.E.

From:

Daniel Louis/Norman Shopay

Date:

January 12, 1988

Subject:

City Blue Production Facility

Job No.:

18106,004.04

Remarks: In regards to our telephone conversations on January 4, 1988, enclosed are the following documents:

- "Subsurface Venting of Vapors Emanating from Hydrocarbon Product in Ground Water," from the winter 1987 issue of Ground Water Monitoring Review.
- 2. "Manipulation of Vadose Zone to Enhance Toxic Organic Chemical Removal," by Robert S. Bowman.
- HLA soil permeability test results.

Underlined sections of both articles may be of particular interest to you regarding the City Blue project. More specific information and data regarding soil venting at the City Blue project will be hand delivered to you later in the week.

If you have any questions, please call.



Blue Print Service Company - Attention: Mr. Paul Koze

HLA, Novato - Attention: Mr. Bruce Sheibach

Engineers and Geoscientists


cc:

666 Howard St. San Francisco California 94105

Telephone 415/543-8422

Alaska California Colorado Hawaii Nevada Texas

Telecopy 415/777-9706 DRY DENSITY (pcf)



COEFFICIENT OF PERMEABILITY (K) AT 20 °C (cm/sec)

PHYSICAL CONDITIONS		TEST NO		
		ΑO	В∆	С
INITIAL	Diameter (in)	2.43	2.43	
	Height (in)	1.50	1.50	<del></del>
	Water Content (%)	15.8	15.6	
	Dry Density (pcf)	99.8	109.7	
	Void Ratio	0.681	0.541	
	Saturation (%)	62	78	
FINAL	Consolidation Pressure (psf)		576	·
	Water Content (%)	23.6	19.5	
	Dry Density (pcf)	103.4	1110	
	Void Ratio	0.620	0.523	
	Saturation (%)	100	100	
Pe	ermeability At 20°C (cm/sec)	3.11X10-4	9.87×10-6	Í
Sa	ample Source:			

A= BORING 24.5' B=BORING & M.O.

A=BROWN CLAYEY SAND(SC) B=BROWN CLAYEY SAND(SC)

TEST TYPE: FALLING HEAD

SATURATION

METHOD: BACK PRESSURE

DRAFT



**Harding Lawson Associates** 

Engineers, Geologists & Geophysicists

Classification:

Permeability Test Report CITY BLUE FACILITY

PLATE TMZ

DRAWN JOB NUMBER APPROVED DATE REVISED DATE
87-1330.04 11-3-87



SHEET_	1	OF	1					
JOB NO.	_181	06,004	04					
DATE	Jan.	4,1988						
COMPUTED BY DAL								
CHECKE	D BY							

City Blue Production Facility **PROJECT** SUBJECT\_

Monitoring Well Location Sketch

Not to Scale

★ MW-5 (proposed)

## Eighteenth Street

