

Date

November 8, 1995

Project

20805-131.02

To:

Ms. Juliet Shin Alameda County Health Care Services Agency Department of Environmental Health 1131 Harborbay Parkway, Suite 250 Alameda, California 94502-6577

We are enclosing:

Copies		Description			
1		Status Letter,	Additional Site	Characteriz	ation,
		ARCO service	e station 6002,	Oakland, Ca	difornia
For your:	X	Use	Sent by:		Regular Mail
		Approval			Standard Air
		Review			Courier
		Information		X	Other: Cert. Mail

#### Comments:

The enclosed status letter detailing additional site characterization activities is being sent to you per the request of ARCO Products Company. Please call if you have questions or comments.

Rob Davis Staff Geologist

Robert W. Dois

cc: Kevin Graves, RWQCB - SFBR
Michael Whelan, ARCO Products Company
John Young, EMCON
File

#### **ARCO Products Company**

Environmental Engineering 2155 South Bascom Avenue, Suite 202 Campbell, California 95008



Date: November 9, 1995

Re: ARCO Station #

6002 • 6235 Seminary Avenue • Oakland, CA


Additional Site Characterization

"I declare, that to the best of my knowledge at the present time, that the information and/or recommendations contained in the attached proposal or report are true and correct."

Submitted by:

Michael R. Whelan Environmental Engineer

Michael R. Whelon





November 8, 1995 Project 20805-131.002

Ms. Juliet Shin Alameda County Health Care Services Agency Department of Environmental Health 1131 Harbor Bay Parkway Alameda, California 94502-6577

Additional Site Characterization, ARCO service station 6002, 6235 Seminary

Avenue, Oakland, California.

Dear Ms. Shin:

EMCON, on behalf of ARCO Products Company (ARCO), is pleased to submit this letter regarding recent site characterization activities conducted at ARCO station 6002, 6235 Seminary Avenue, Oakland, California. The work performed was consistent with the scope of work proposed in EMCON's workplan dated January 12, 1995.

A total of 8 exploratory borings were drilled at the project site on June 26 and 27, 1995. Four borings (SB-1 through SB-4) were drilled onsite beneath the service station's canopy, to assess the extent of petroleum hydrocarbon-impacted soil in the vicinity of the pump islands (Figure 1). These borings were drilled to depths of 15.5 to 21.5 feet below ground surface (BGS) using limited-access drilling equipment. Three additional borings (AS-1, VW-3, and VW-4) were drilled in the area between the UST complex and the pump islands (Figure 1). Borings VW-3 and VW-4 were drilled to 15 feet BGS and completed as vapor extraction (VE) wells, using 4-inch-diameter polyvinyl chloride (PVC) casing and screen. Boring AS-1 was drilled to 31.5 feet BGS and completed as an air-sparge (AS) well using 2-inch-diameter PVC casing and screen. The AS and VE wells will be used to evaluate the impacted soil and groundwater at the site. One boring (MW-6) was drilled east of the site to a depth of 32 feet BGS and was completed as a 2 limit. monitoring well. Well MW-6 was installed to investigate a potential up-gradient source for the impacted groundwater observed at the site.

Selected soil samples collected from each of the eight borings and groundwater samples collected from wells MW-6, and AS-1 were submitted to a state-certified laboratory and analyzed for total petroleum hydrocarbons as gasoline (TPHG), and benzene, toluene, ethylbenzene, and total xylenes (BTEX). Certified Analytical Reports and exploratory

Ms. Juliet Shin November 8, 1995 Page 2

boring logs are attached. Groundwater analytical results for wells MW-6 and AS-1 and second quarter 1995 analytical results from the existing on-site wells are presented on Figure 2.

EMCON is currently pursuing encroachment permission with property owners southwest and southeast of the site, along Seminary and Sunnymere Avenues, in order to proceed with the installation of groundwater monitoring wells or temporary monitoring points downgradient of the site. Upon receiving encroachment permission, EMCON will proceed with the installation and sampling of the wells or monitoring points, and prepare a letter report summarizing the findings of the additional on- and off-site characterization work.

Lynn Gallagher R.G. 6090

Project Geologist

Sincerely,

**EMCON** 


Rob Davis Staff Geologist

Robit UD

Attachments: Figure 1 - Site Plan

Figure 2 - Groundwater Data Certified Analytical Reports Exploratory Boring Logs

cc: Mike Whelan, ARCO John Young, EMCON






SCALE: 0 30 60 FEET

SERVICE STATION 6002, 6235 SEMINARY AVE.
OAKLAND, CALIFORNIA

TROJECT NO

SITE PLAN

PROJECT NO. 805-131.02





SCALE: 0 30 60 FEET

SERVICE STATION 6002, 6235 SEMINARY AVE.
OAKLAND. CALIFORNIA

GROUNDWATER ANALYTICAL DATA

2

PROJECT NO. 805-131.02



July 11, 1995

Service Request No. S950839

John Young EMCON 1921 Ringwood Avenue San Jose, CA 95131

Re:

ARCO Facility No. 6002 / EMCON Project No. 0805-131.03

Dear Mr. Young:

Attached are the results of the water sample(s) submitted to our lab on June 30, 1995. For your reference, these analyses have been assigned our service request number S950839.

All analyses were performed consistent with our laboratory's quality assurance program. All results are intended to be considered in their entirety, and CAS is not responsible for use of less than the complete report. Results apply only to the samples analyzed.

Please call if you have any questions.

Respectfully submitted:

COLUMBIA ANALYTICAL SERVICES, INC.

Steven L. Green

**Project Chemist** 

SLG/ajb

Annelise J. Bazar Regional QA Coordinator

#### Acronyms

ASTM American Society for Testing and Materials

A2LA American Association for Laboratory Accreditation

CARB California Air Resources Board

CAS Number Chemical Abstract Service registry Number

CFC Chlorofluorocarbon CFU Colony-Forming Unit

**DEC** Department of Environmental Conservation

**DEQ** Department of Environmental Quality

**DHS** Department of Health Services

DOE Department of Ecology
DOH Department of Health

EPA U. S. Environmental Protection Agency

ELAP Environmental Laboratory Accreditation Program

GC Gas Chromatography

GC/MS Gas Chromatography/Mass Spectrometry

LUFT Leaking Underground Fuel Tank

M Modified

MCL Maximum Contaminant Level is the highest permissible concentration of a

substance allowed in drinking water as established by the U. S. EPA.

MDL Method Detection Limit
MPN Most Probable Number
MRL Method Reporting Limit

NA Not Applicable
NAN Not Analyzed
NC Not Calculated

NCASI National Council of the paper industry for Air and Stream Improvement

ND Not Detected at or above the MRL

NIOSH National Institute for Occupational Safety and Health

PQL Practical Quantitation Limit

RCRA Resource Conservation and Recovery Act

SIM Selected Ion Monitoring

TPH Total Petroleum Hydrocarbons

ACRONLST.DOC

12/22/94

## Analytical Report

Client:

**EMCON** 

Project:

ARCO Facility No. 6002/EMCON Project No.0805-131.03

Sample Matrix:

Water

Service Request: \$950839

Date Collected: 6/30/95

Date Received: 6/30/95

Date Extracted: NA

**Date Analyzed: 7/10-11/95** 

## BTEX and TPH as Gasoline EPA Methods 5030/8020/California DHS LUFT Method

	Analyte: Units: Method Reporting Limit:	TPH as Gasoline ug/L (ppb) 50	Benzene  ug/L (ppb)  0.5	Toluene ug/L (ppb) 0.5	Ethyl- benzene ug/L (ppb) 0.5	Xylenes, Total ug/L (ppb) 0.5
Sample Name	Lab Code					
MW-6 (31) AS-1 (22) Method Blank Method Blank	S950839-001 S950839-002 S950710-WB2 S950711-WB1	ND ND ND ND	ND 1.6 ND ND	ND ND ND ND	ND 0.9 ND ND	ND 0.9 ND ND

Approved By

5ABTXGAS/061694

## QA/QC Report

Client:

**EMCON** 

Project:

ARCO Facility No. 6002/EMCON Project No.0805-131.03

Sample Matrix:

Water

Service Request: \$950839

Date Collected: 6/30/95

Date Received: 6/30/95

Date Extracted: NA

**Date Analyzed:** 7/10-11/95

Matrix Spike/Duplicate Matrix Spike Summary

BTE

EPA Methods 5030/8020 Units: ug/L (ppb)

Sample Name:

Batch QC

Lab Code:

S950833-001

Percent Recovery CAS Relative Spike Level Sample Spike Result Acceptance Percent Analyte MS DMS Result MS **DMS** MS Limits Difference **DMS** Benzene 25 25 21.2 47.1 46.5 104 101 75-135 I Toluene 25 25 ND 23.9 95 73-136 1 23.7 96 Ethylbenzene 25 25 ND 24.4 24.2 98 97 69-142 1

Approved By:

DMS15/060194

## QA/QC Report

Client:

**EMCON** 

Project:

ARCO Facility No. 6002/EMCON Project No.0805-131.03

Sample Matrix: Water

Service Request: S950839 Date Collected: 6/30/95

Date Received: 6/30/95

Date Extracted: NA

Date Analyzed: 7/10-11/95

Surrogate Recovery Summary BTEX and TPH as Gasoline EPA Methods 5030/8020/California DHS LUFT Method

•	*A	Percent Recovery
Sample Name	Lab Code	$\alpha,\alpha,\alpha$ -Trifluorotoluene
MW-6 (31)	S950839-001	88
AS-1 (22)	S950839-002	94
(MS)	\$950833-001MS	92
(DMS)	\$950833-001DMS	92
Method Blank	S950710-WB2	93
Method Blank	\$950711-WBI	89

CAS Acceptance Limits: 69-116

Approved By:

SUR1/062994

# QA/QC Report

Client:

**EMCON** 

Service Request: S950839

Project:

ARCO Facility No. 6002/EMCON Project No.0805-131.03

Date Analyzed: 7/10/95

## Initial Calibration Verification (ICV) Summary BTEX and TPH as Gasoline EPA Methods 5030/8020/California DHS LUFT Method Units: ppb

			CAS Percent Recovery
True		Percent	Acceptance
Value	Result	Recovery	Limits
25	26.1	104	85-115
25	24.9	100	85-115
25	25.1	100	85-115
75	72.1	96	85-115
250	231	92	90-110
	Value  25 25 25 75	Value     Result       25     26.1       25     24.9       25     25.1       75     72.1	Value         Result         Recovery           25         26.1         104           25         24.9         100           25         25.1         100           75         72.1         96

Approved By:

ICV25AL/060194

ARCO	Prod Division	ucts (	Comp	ompany	<b>\$</b>			Task Or	rder No.	170	 75.0	20					······································				· · · · · · · · · · · · · · · · · · ·	Chain of Custody
RCO Facil	ity no.	002		Cit	ly acillity) /	Oakle	and			Project (Consu	manaç	jer ),	2hn	You	10/					•		Laboratory name
ARCO engi	neer M	10	Nho	down		<u> </u>	Telephon (ARCO)	19 NO.	-	Teleph	one no.	(1/3	7) L/	フーフ		Fax	no.	.(1.	(a)	1100	~~~	Laboratory name  C/+S  Contract number
Consultant	name	W//	<u>'''''</u>	IUII			[[ARCO]	Address	1001	(Consu	manı) [	100	<i>y</i> 7:	1	NAZ.	7(00	nsumar }		ZDL ~/1	435 O/	72457 121	Contract number
								(Consulta	int)/92/	<i>/(  </i>		<i>100</i>	AF	IVE	٠- ٢	CAD.	JCS		8	75 / 	<u>'S /.</u>	Method of shipment
				Matrix		Prese	rvation			1	ş	₩.		l w	1		:	Sem.		L		Sampler Will
Sample I.D.	Lab no.	Container no.	Soil	Water	Other	lce	Acid	Sampling date	Sampling time	BTEX 602/EPA 8020	BTEXTPH EPK WEEZ/8020/	TPH Modified 8015 Gas	Oë and Grease 413.1 □ 413.2	TPH EPA 418.1/SM503E	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Semi Netais □ VOA □ VOA □	CAM Metals EPA 6	Lead Org./DHS C		Sampler Will Deliver
YW-61	31)	2		×		×	HCL	6-30	10:59		×		į									Special detection Limit/reporting
-		2		×		×	HCL		11:48		X											Lowest
S-1 (		3		*			HE I		<del>- 1 1 - 1 - 1 - 1</del> - 1	ļ	是											Possible
	<u> </u>																					Special QA/QC
																		,				1 '
													······································									As Normal
				<u> </u>		<del></del>																
																						Remarks
																						7 - 40ml HC
																					•	2-40m1 HCI VOAS
																						#0905-131.03 Lab number 5950839
			<u></u>																			5950839
					<u> </u>		ļ								[							Turnaround time
																						Priority Rush 1 Business Day
ondition o												receive	d:									Rush
lelinguishe	<b>-</b> /	Par					Date 4-30-	25	Time /3:20	Receiv	ved by							-				2 Business/Days, Change 7/5/75 pw [d
Relinquishe		<u>-av</u>	<del>-</del>				Date	• -	Time	Recei	ved by		·									Expedited 5 Business Days
lelinquishe	d by		<del>"</del>				Date		Time			iaborate		w		p	ate	sola	, ,	Time	20	Standard 10 Business Days





July 6, 1995

Service Request No. <u>S950811</u>

Regional QA Coordinator

John Young **EMCON** 1921 Ringwood Avenue San Jose, CA 95131

ARCO Facility No. 6002 / EMCON Project No. 0805-131.04 Re:

Dear Mr. Young:

Attached are the results of the soil sample(s) submitted to our lab on June 28, 1995. For your reference, these analyses have been assigned our service request number S950811.

All analyses were performed consistent with our laboratory's quality assurance program. All results are intended to be considered in their entirety, and CAS is not responsible for use of less than the complete report. Results apply only to the samples analyzed.

Please call if you have any questions.

Respectfully submitted:

COCUMBIA ANALYTICAL SERVICES, INC.

Steven L. Green

Project Chemist

SLG/ajb

#### Acronyms

ASTM American Society for Testing and Materials

A2LA American Association for Laboratory Accreditation

CARB California Air Resources Board

CAS Number Chemical Abstract Service registry Number

CFU Chlorofluorocarbon
CFU Colony-Forming Unit

**DEC** Department of Environmental Conservation

**DEQ** Department of Environmental Quality

**DHS** Department of Health Services

DOE Department of Ecology
DOH Department of Health

EPA U. S. Environmental Protection Agency

ELAP Environmental Laboratory Accreditation Program

GC Gas Chromatography

GC/MS Gas Chromatography/Mass Spectrometry

LUFT Leaking Underground Fuel Tank

M Modified

MCL Maximum Contaminant Level is the highest permissible concentration of a

substance allowed in drinking water as established by the U. S. EPA.

MDL Method Detection Limit
MPN Most Probable Number
MRL Method Reporting Limit

NA Not Applicable
NAN Not Analyzed
NC Not Calculated

NCASI National Council of the paper industry for Air and Stream Improvement

ND Not Detected at or above the MRL

NIOSH National Institute for Occupational Safety and Health

PQL Practical Quantitation Limit

RCRA Resource Conservation and Recovery Act

SIM Selected Ion Monitoring

TPH Total Petroleum Hydrocarbons

ACRONLST.DOC

12/22/94

## Analytical Report

Client:

**EMCON** 

Project:

Sample Matrix:

Soil

ARCO Facilty No. 6002/EMCON Project No.0805-131.04

Service Request: \$950811 Date Collected: 6/27/95

Date Received: 6/28/95 Date Extracted: NA

**Date Analyzed:** 6/30 - 7/3/95

## BTEX and TPH as Gasoline EPA Methods 5030/8020/California DHS LUFT Method As Received Basis

	Analyte: Units: Method Reporting Limit:	TPH as Gasoline mg/Kg (ppm)	Benzene mg/Kg (ppm) 0.005	Toluene mg/Kg (ppm) 0.005	Ethyl- benzene mg/Kg (ppm) 0.005	Xylenes, Total mg/Kg (ppm) 0.005
Sample Name	Lab Code					
SB-3, 6'	S950811-001	ND	ND	ND	ND	ND
SB-3, 11'	S950811-002	ND	ND	ND	ND	ND
SB-3, 21'	S950811-004	ND	ND	ND	ND	ND
SB-4, 6'	S950811-005	ND	ND	ND	ND	ND
SB-4, 21.5'	S950811-008	ND	ND	ND	ND	ND
SB-2, 5'	S950811-009	2	0.066	0.028	0.018	0.14
SB-2, 15.5'	S950811-013	ND	ND	ND	ND	ND
SB-1, 5'	S950811-014	ND	0.007	ND	0.028	0.047
SB-1, 9'	S950811-015	2	0.008	ND	0.034	0.14
SB-1, 12.5'	S950811-017	ND	ND	ND	ND	ND
Method Blank	S950630-SB1	ND	ND	ND	ND	ND
Method Blank	\$950703-\$B1	ND	ND	ND	ND	ND

Approved By: 5ABTXGAS/061694

#### Analytical Report

Client:

**EMCON** 

Service Request: \$950811

Project:

ARCO Facilty No. 6002/EMCON Project No.0805-131.04

Date Collected: 6/27/95

Sample Matrix:

Soil

Date Received: 6/28/95

Date Extracted: NA

**Date Analyzed:** 6/30 - 7/5/95

## BTEX and TPH as Gasoline EPA Methods 5030/8020/California DHS LUFT Method As Received Basis

	Analyte: Units: Method Reporting Limit;*	TPH as Gasoline mg/Kg (ppm) 5	Benzene mg/Kg (ppm) 0.05	Toluene mg/Kg (ppm) 0.1	Ethyl- benzene mg/Kg (ppm) 0.1	Xylenes, Total mg/Kg (ppm) 0.1
Sample Name	Lab Code	W.				
SB-4, 11'	S950811-006	10	ND	ND	ND	ND
SB-2, 9.5'	S950811-010	260	<0.5**	2.6	4.3	18
SB-1, 11'	S950811-016	730	<0.5**	4.4	10	49
Method Blank	S950630-SB2	ND	ND	ND	ND	ND
Method Blank	S950630-SB2	ND	ND	ND	ND	ND
Method Blank	S950630-SB2	ND	ND	ND	ND	ND

Raised MRL due to high analyte concentration requiring methanol extraction of sample.

Raised MRL due to high analyte concentration requiring methanol extraction and dilution of sample.

Approved By: 5ABTXGAS/061694

# QA/QC Report

Client: Project:

Sample Matrix: Soil

**EMCON** 

ARCO Facilty No. 6002/EMCON Project No.0805-131.04

**Date Collected:** 6/27/95

Date Received: 6/28/95

Service Request: S950811

Date Extracted: NA

Date Analyzed: 6/30 - 7/3/95

Surrogate Recovery Summary BTEX and TPH as Gasoline EPA Methods 5030/8020/California DHS LUFT Method

		Percent Recovery
Sample Name	Lab Code	$\alpha$ , $\alpha$ , $\alpha$ -Trifluorotoluene
SB-3, 6'	S950811-001	92
SB-3, 11'	S950811-002	96
SB-3, 21'	\$950811-004	90
SB-4, 6'	S950811-005	97
SB-4, 21.5'	S950811-008	90
SB-2, 5'	\$950811-009	79
SB-2, 15.5'	S950811-013	81
SB-1, 5'	S950811-014	95
SB-1, 9'	\$950811-015	115
SB-1, 12.5'	\$950811-017	95
SB-3, 6' (MS)	\$950811-001M\$	92
SB-3, 6' (DMS)	\$950811-001DMS	85
Method Blank	\$950630-SB1	80
Method Blank	S950703-SB1	104

CAS Acceptance Limits: 51-137

Approved By:

SUR1/062994

# QA/QC Report

Client: Project:

Sample Matrix: Soil

**EMCON** 

EMCON

ARCO Facilty No. 6002/EMCON Project No.0805-131.04

Service Request: S950811

Date Collected: 6/27/95

Date Received: 6/28/95
Date Extracted: NA

Date Analyzed: 6/30 - 7/5/95

Surrogate Recovery Summary
BTEX and TPH as Gasoline
EPA Methods 5030/8020/California DHS LUFT Method

Sample Name	Lab Code	Percent Recovery $\alpha, \alpha, \alpha$ -Trifluorotoluene
SB-4, 11'	S950811-006	92
SB-2, 9.5'	S950811-010	96
SB-1, 11'	S950811-016	99
Method Blank	S950630-SB2	88
Method Blank	S950630-SB2	93
Method Blank	S950630-SB2	95

CAS Acceptance Limits: 59-115

Approved By SUR1/062994

Date: Z

. Page 7

## QA/QC Report

Client: Project:

EMCON -

ARCO Facilty No. 6002/EMCON Project No.0805-131.04

Service Request: S950811

Date Analyzed: 6/30/95

Initial Calibration Verification (ICV) Summary
BTEX and TPH as Gasoline
EPA Methods 5030/8020/California DHS LUFT Method
Units: ppm

				CAS Percent
Analyte	True Value	Result	Percent Recovery	Recovery Acceptance Limits
Benzene	0.050	0.054	108	85-115
Toluene	0.050	0.052	104	85-115
Ethylbenzene	0.050	0.053	106	85-115
Xylenes, Total	0.15	0.147	98	85-115
Gasoline	1.0	0.96	96	90-110
	-			

Approved By:

ICV25AL/060194

Date: 7/6/9

### QA/QC Report

Client:

**EMCON** 

Service Request: S950811

Project:

Sample Matrix:

ARCO Facilty No. 6002/EMCON Project No.0805-131.04 Soil

98

Date Collected: 6/27/95

Date Received: 6/28/95

Date Extracted: NA

Date Analyzed: 6/30/95

Matrix Spike/Duplicate Matrix Spike Summary

BTE

EPA Methods 5030/8020

Units: mg/Kg (ppm) As Received Basis

MS

0.0492 0.0528

Sample Name:

SB-3, 6'

Lab Code:

Analyte

Benzene

Toluene

Ethylbenzene

S950811-001

Spike Level

**DMS** 

0.05

0.05

0.05

Result

ND

ND

ND

MS

0.05

0.05

0.05

Percent Recovery CAS Relative Sample Spike Result Acceptance Percent **DMS** MS **DMS** Limits Difference 0.0527 0.0556 105 111 57-154 5 9 0.0468 0.0511 94 102 60-142

46-150

7

106


Approved By DM\$15/060194

Task Order No.   Tolephone   Tolephone	EPA 6248240  EPA 6248240  (Consultant) (# 88 ) #37 - 952 (@)  (Consultant) (# 88 )	Laboratory name  AS  Contract number  Method of shipment  Special detection Limit/reporting
Address (Consultant)   1921   72   72   72   72   72   72   72	Som Jose, (A	Contract number  Method of shipment  Special detection
Address (Consultant)   1921   72   72   72   72   72   72   72	Som Jose, (A	Contract number  Method of shipment  Special detection
Matrix   Preservation   Soli   Water   Other   Ice   Acid   Sampling time   Sampling time	EPA 6248240  EPA 6258270  TCLP Semi Meeus DVOA UVOA UVOA UVOA UVOA UVOA UVOA UVOA U	Special detection
B-3,6 / 6/27/95  B-3,16 3  B-3,21 4  B-4,6 5  B-4,11 6  B-4,16 7	EPA 601/8010  EPA 624/8240  EPA 625/8270  TCLP Semi Metals EPA 60107  TTLC STLC CAM Metals EPA 60107  TTLC STLC CAM Metals EPA 60107  TTLC CAM Metals EPA 60107  TTLC CAM Metals EPA 60107  TAYON 421 CAM AVON 421 CA	Special detection
B-3,6 / 6/27/95  B-3,11 2  B-3,21 4  B-4,6 5  B-4,11 6  B-4,16 7	EPA 601/8010 EPA 62/8240 EPA 62/8270 TCLP Metals EPA TTLC = \$11 Lead 6PA 742077421	
B-3,6 / 6/27/95  B-3,16 3  B-3,21 4  B-4,6 5  B-4,11 6  B-4,16 7		
B-3, 11 2 B-3, 16 3 B-4, 6 5 B-4, 11 6 B-4, 11 6		,
B-3, 16 3 3-4, 6 5 3-4, 11 6 3-4, 16 7		
8-3, 21 4 8-4, 6 5 8-4, 11 6 3-4, 16 7		
B-4,11 6 3-4,165 7		Special QA/QC
B-4,11 6 3-4,165 7		
3-4,165		
3-4, 11.5' 8		
		Remarks  [M(aN Prajuc)]
1-2,51 9		0805-131.04
-1,95 10 -2/11 11 5-1,13 12		_]
	The state of the s	<b>_</b>
-2,15.5' /3		
-1,5' 14		Lab number
3-1,9 /5		59508//
9-1, 11 16		Turnaround time
3-1,12-5/7		Priority Rush 1 Business Day
ondition of sample:  Temperature received:  Date  Time Received by		Rush
Received by  Tobert 4: Date 6/38/15 16:15 Received by	<b></b>	2 Business Days
elinquished by Date Time Received by	\	Expedited 5 Business Days
elinquished by Date Time Received by laboratory  AuthOrotor	Date 1-28-95 Time 635	Standard 10 Business Days



# EXPLANATION OF SYMBOLS ON EXPLORATORY BORING LOGS

# Well Details Column



# Sample Column

BAG/BULK SAMPLES

FIVE-FOOT SPLIT BARREL SAMPLER (CONTINUOUS SAMPLER)

MODIFIED CALIFORNIA SPLIT SPOON

OTHER SAMPLERS (SEE REMARKS FOR TYPE AND SIZE)

PITCHER BARREL

ROCK CORE (SEE REMARKS FOR TYPE AND SIZE)

SHELBY TUBE SAMPLER

STANDARD PENETRATION TEST SPLIT SPOON SAMPLER (2" OD)

# EXPLANATION OF SYMBOLS ON EXPLORATORY BORING LOGS (CONTINUED)

# Ground-Water Level Column

DEPTH TO FIRST OBSERVED GROUND WATER

DEPTH TO STABILIZED GROUND WATER

## Miscellaneous

2.5 YR 6/2 Color as field checked to Munsell Soil Color Chart (1975 Edition)

PENETRATION Blows required to drive sampler 1 foot into soil.

Standard drive hammer weight: 140 pounds.

Standard drop: 30 inches



PROJECT NUMBER: 805-131.04

BORING NO.: AS-1

PROJECT NAME: ARCO Service Station 6002

PAGE: 1 of 2

BY: R. Davis

DATE: 6/26/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PIO (ppm)	I TION	GROUND DE WATER LEVELS F	IN L	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
			_			ASPHALT FILL.	
100%	26	2 4 5	-	5-		CLAYEY SAND (SC), dark grayish brown (2.5Y, 3/3); 50% medium plasticity fines; 20-30% fine to coarse sand; 20-30% fine to coarse gravel, to 2.5 "; damp; product odor.	
60%	156	4 7 7	- 1 -	10-		CLAYEY SAND (SC), olive brown (2.5Y, 4/4); 40% medium plasticity fines; 30% fine to coarse sand; 20% fine to coarse gravel, up to 1.5"; medium dense; moist; product odor.	
100%	0	4 6 9	- - - 1 -	15		SANDY CLAY (CL), dark yellowish brown (10YR, 4/4); 55-60% medium plasticity fines; 30-35% fine to coarse sand; 10% fine gravel; stiff; damp to moist; product odor.	
			- - - <u>∇</u> 20	0		CLAYEY SAND (SC), 20-30% medium plasticity fines; 70-80% fine to coarse sand; wet; no product odor.	



#### REMARKS

Boring drilled with 8" diameter hollow-stem augers. Samples were taken using a 2" diameter modified-California split spoon sampler. Boring converted into a 2" diameter polyvinyl chloride (PVC) air-sparge well. See explanation sheet for definition of symbols used in well detail and sample columns of this log. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: AS-1

PROJECT NAME: ARCO Service Station 8002

PAGE: 2 of 2

BY: R. Davis

DATE: 8/28/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PIO (ppm)	PENETRA- TION (blws/ft)	GROUND DEPT WATER IN LEVELS FEET	SAMPLES	DESCRIPTION	WELL ETAIL
25%	0	2 2 8	-	-	CLAYEY SAND (SC), continued.	
100%	0	7 7 7	- 25- -		SILTY CLAY (CL), dark olive gray (5Y, 3/2); 75-80% low plasticity fines; 20-25% fine to medium sand; stiff; moist; no product odor.	
90%		2 7 8 6 14 25	- 30 35 35-		@28-28.5': 55-60% low plasticity fines; 40-45% fine to coarse sand; trace fine gravel; damp; no product odor.  CLAYEY SAND (SC), dark olive gray (5y, 3/2); 20-30% low to medium plasticity fines; 70-80% fine to coarse sand; medium dense; moist; no product odor.  @30-31.5': dark brown (7.5YR, 4/4); 30% low to medium plasticity fines; 50% fine to coarse sand; 20% fine gravel; damp; no product odor.  BORING TERMINATED AT 31.5 FEET BGS.	



#### REMARKS

Boring drilled with 8" diameter hollow-stem augers. Samples were taken using a 2" diameter modified-California split spoon sampler. Boring converted into a 2" diameter polyvinyl chloride (PVC) air-sparge well. See explanation sheet for definition of symbols used in well detail and sample columns of this log. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: MW-8

mw-6

PROJECT NAME: ARCO Service Station 8002

PAGE: 1 of 2

BY: R. Davis

DATE: 6/26/95

SURFACE ELEVATION: NA ft.

RECOVERY (ft/ft)	PIO (ppm)	PENETRA- TION (blws/ft)	GROUND DEPTH HATER IN LEVELS FEET	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
					CONCRETE  FILL - CLAYEY GRAVEL (GC), brown, 20-30% low to medium plasticity fines; 30-40% fine to coarse sand; 40% fine to coarse gravel; damp; no product odor.	
100%	0	6 14 16	5-			
60%	0	3 13 14	- 10-		CLAYEY SAND (SC), dark grayish brown (IOYR, 4/2); 40% medium plasticity fines; 40% fine to coarse gravel, up to 1"; medium dense; moist of wet; no product odor.	
100%	0	4 8 10	15-		SANDY CLAY (CL), mottled gray (2.5Y, 5/0) and light olive brown (2.5Y, 5/6); 70% low to medium plasticity fines; 20% fine to coarse sand; 10% fine gravel, subangular; thin (<1mm) organic fragments present; very stiff; damp; no product odor.	
	0	4 7	20		@19.0-20.5': as above at 14.0-15.5'.	



#### REMARKS

Boring drilled with 8" diameter hollow-stem augers. Samples were taken using a 2" diameter modified-California split spoon sampler. Boring converted into a 2" diameter polyvinyl chloride (PVC) groundwater monitoring well. See explanation sheet for definition of symbols used in well detail and sample columns of this log. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: MW-8

PROJECT NAME: ARCO Service Station 8002

PAGE: 2 of 2

BY: R. Davis

DATE: 6/26/95

SURFACE ELEVATION: NA ft.

RECOVERY (ft/ft)	PID (ppm)	PENETRA- TION (blws/ft)	GROUND WATER LEVELS	DEPTH IN FEET	SAMPLES	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL
		9	Δ̈́				SANDY CLAY (CL), continued. @20.5': moist to wet.	
			<b>-</b>	-				
100%	0	9 11 17 7	<del>-</del>	- 25—			CLAYEY SAND (SC), strong brown (7.5YR, 4/6); 40-45% low plasticity fines; 50-55% fine to medium sand; 5% fine to coarse gravel, up to 1-in; medium dense; moist to wet; no odor.	
80%	0	14 16	-	-			@25.5-27': 20% low plasticity fines; 60% fine to coarse sand; 20% fine to coarse gravel, up to 2"; very moist; no odor.	
80%	0	12 14 18	-	-			@27.5-28.5': dark brown (10YR, 4/3); moist to wet.	
85%	0	6 16 13		30-			@30-31.5': 25-30% low to medium plasticity fines; 65-70% fine to medium sand; 5% fine gravel; wet; no product odor.	
			-	_			BORING TERMINATED AT 32.0 FEET BGS.	
			<del>-</del>	35-				
			-	-				
			<u>.</u>	40				:



#### REMARKS

Boring drilled with 8" diameter hollow-stem augers. Samples were taken using a 2" diameter modified-California split spoon sampler. Boring converted into a 2" diameter polyvinyl chloride (PVC) groundwater monitoring well. See explanation sheet for definition of symbols used in well detail and sample columns of this log. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: SB-1

PROJECT NAME: ARCO Service Station 6002

PAGE: 1 of 1

BY: R. Davis

DATE: 6/27/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PID (ppm)	PENETRA- TION (blws/ft)	SAMPLES STANDORSAPHIC	DESCRIPTION	WELL DETAIL
	· • · · · · · · · · · · · · · · · · · ·		××××	CONCRETE CONCRETE (CO.)	
95% 40% 90%	6.4 2.1 29.1 608 36	4 5 5 5 11 9 21 18	5-	CLAYEY SAND (SC), dark brown (10YR, 3/3); 40% medium plasticity fines; 45% fine to coarse sand (f:m:c=1:1:2); 15% fine to coarse gravel; medium dense; damp; no product odor.  @5.8-6.5': very dark grayish brown (2.5Y, 3/2); moist; product odor.  @8-9.5': as above at 5.8'-6.5' with ~30% coarse gravel, up to 2-in.  @10-11.5': dark grayish brown (2.5Y, 4/2); 40 low to medium plasticity fines; 40% fine to coarse sand (f:m:c=2:2:1); 20% fine to coarse gravel; dense; wet; product odor.  @11.5-12.5': damp; no product odor.	upla of the office of the offi
90%	0	11 15	15-	SANDY CLAY (CL), dark yellowish brown (10YR, 4/4); 55-60% low to medium plasticity fines; 35-40% fine to coarse sand; 5% fine to coarse gravel; damp; no product odor.  BORING TERMINATED AT 16.5 FEET BELOW GROUND SURFACE.	



REMARKS

Boring drilled with 6-inch-diameter solid-stem augers. Boring sampled using 2-inch-diameter modified California split spoon samplers. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: SB-2

PROJECT NAME: ARCO Service Station 6002

PAGE: 1 of 1

BY: R. Davis

DATE: 8/27/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PIO (ppm)	TION	GROUND DEPTH WATER IN LEVELS FEET	르	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
			 			CONCRETE  FILL: GRAVELLY CLAYEY SAND (SC), 30% fines (clay); 40% fine to coarse sand; 30% fine to coarse gravel, up to 3-in.	
70%	8.1	5 8 9	- 5- 			CLAYEY SAND (SC), dark brown (10YR, 3/3); 25-30% medium plasticity fines; 55-60% fine to coarse sand (f:m:c=1:1:1); 10-15% fine to coarse gravel, up to 2-in.; medium dense; damp; product odor.	
70%	6.9	7 8 7				@8-9.5': moist to wet; product odor. 3 Supplies  The Plant	differ t
40%	0	10 10 10	- 10-			@10-11.5': 20% medium plasticity fines; 60% fine to coarse sand (f:m:c=1:1:1); 20% fine to coarse gravel; medium dense; no product odor.	
80%	0	7 8 9				SANDY CLAY (CL), mottled grayish brown (10YR, 5/2) and dark yellowish brown (10YR, 4/4); 55-60% medium plasticity fines; 35-40% fine to coarse sand, poorly graded; 5% fine gravel; moist;	
90%	0	6 9 11	<u> </u>			no product odor.	
			 -			BORING TERMINATED AT 15.5 FEET BELOW GROUND SURFACE.	



REMARKS

Boring drilled with 6-inch-diameter solid-stem augers. Boring sampled using 2-inch-diameter modified California split spoon samplers. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: SB-3

PROJECT NAME: ARCO Service Station 6002

PAGE: 1 of 2

BY: R. Davis

DATE: 8/27/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PID (ppm)	TION	GROUND DEPTH WATER IN LEVELS FEET	SAMPLES LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
					CONCRETE	
					FILL: GRAVELLY CLAYEY SAND (SC), 30% fines (clay); 40% fine to coarse sand; 30% fine to coarse gravel, up to 3-in.	
70%	0	5 6 7	- 5 <u>-</u> - 5		CLAYEY SAND (SC), dark brown (10YR, 3/3); 25-30% low to medium plasticity fines; 40% fine to coarse sand, poorly graded; 30-35% fine to coarse gravel, subangular; medium dense; damp; no product odor.	100000000000000000000000000000000000000
90%	0	2 3 3	- 10— 		@10-11.5': dark olive gray (5Y, 3/2); 15-20% low to medium plasticity fines; 45-50% fine to coarse sand; well sorted; 35% fine to coarse gravel, subangular; loose; wet; product odor.	
60%	0	12 18 27	- 15-		@15-15.3': Sandy Clay (SC), same as SB-2 at 12-13.5'.  SANDY CLAY (CL), mottled grayish brown (10YR, 5/2) and dark yellowish brown (10YR, 4/4); 55-60% medium plasticity fines; 35-40% fine to coarse sand, poorly graded; 5% fine gravel; moist; no product odor.  CLAYEY GRAVEL (GC), yellowish brown (10YR, 5/4); 15% medium plasticity fines; 35% fine to coarse sand, poorly graded; 50% fine to coarse gravel, up to 2.5-in.; dense; wet; no product	



#### REMARKS

Boring drilled with 6-inch-diameter solid-stem augers. Boring sampled using 2~inch-diameter modified California split spoon samplers. See explanation sheet for definition of symbols on this log. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: SB-3

PROJECT NAME: ARCO Service Station 6002

PAGE: 2 of 2

BY: R. Davis

DATE: 6/27/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PID (ppm)	PENETRA- TION (blws/ft)	GROUND WATER LEVELS	OEPTH IN FEET	SAMPLES	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL
100%	0	12 15 19	-				SANDY CLAY (CL), dark reddish brown (5YR, 3/4); 60% medium plasticity fines; 25% fine to coarse sand; 15% fine to coarse gravel, up to 1-in.; hard; damp; no product odor. BORING TERMINATED AT 21.5 FEET BELOW GROUND SURFACE.	
			-	30				
			- -	35-				
			-	40				



#### REMARKS

Boring drilled with 6-inch-diameter solid-stem augers. Boring sampled using 2-inch-diameter modified California split spoon samplers. See explanation sheet for definition of symbols on this log. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: SB-4

PROJECT NAME: ARCO Service Station 6002

PAGE: 1 of 2

BY: R. Davis

DATE: 6/27/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PID (ppm)	PENETRA- TION (blws/ft)	GROUND DEPTH WATER IN LEVELS FEET	SAMPLES LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
			-		CONCRETE  FILL: GRAVELLY CLAYEY SAND (SC), 30% fines	
					(clay); 40% fine to coarse sand; 30% fine to coarse gravel, up to 3-in.	
100%		6	5-		CLAYEY SAND (SC), dark brown (10YR, 3/3); 20-25% low to medium plasticity fines; 40-45% fine to coarse sand, poorly graded; 35% fine to coarse gravel, subangular, moderately weathered;	
	0	9	  -  -  -		medium dense; damp; no product odor.	
60%	0	5 8 9	10 <i></i>		@10-11.5': dark olive gray (5Y, 3/2); 15-20% low to medium plasticity fines; 45-50% fine to coarse sand; well sorted; 35% coarse gravel, subangular,	
		9	 		up to 2-in; loose; wet; faint product odor.	
		:			CLAVEY CRAVEL (CO) vellaviah beaum (IOVR	
70%	0	13 8 10	-		CLAYEY GRAVEL (GC), yellowish brown (10YR, 5/4); 10-20% low to medium plasticity fines; 20% fine to coarse sand; 60-70% fine to coarse gravel, up to 2.5-in.; medium dense; wet; no product odor.	
			- "		SANDY CLAY (CL), yellowish brown (10YR, 5/4); 55% medium plasticity fines; 35% fine to coarse sand; 10% fine gravel; firm; moist; no product odor.	
			20	<u> Y//</u>		



#### REMARKS

Boring drilled with 6-inch-diameter solid-stem augers. Boring sampled using 2-inch-diameter modified California split spoon samplers. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO.: SB-4

PROJECT NAME: ARCO Service Station 6002

PAGE: 2 of 2

BY: R. Davis

DATE: 6/27/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PID (ppm)	PENETRA- TION (blws/ft)	GROUND DEPTH WATER IN LEVELS FEET	SAMPLES LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL
90%	0	11 18 21	25-		@20.0-21.5': dark reddish brown (5YR, 3/4);60% medium plasticity fines; 25% fine to coarse sand; 15% fine to coarse gravel, up to 1-in.;hard; damp; no product odor.  BORING TERMINATED AT 21.5 FEET BELOW GROUND SURFACE.	
			  - 30-			
			- - - - 35—			
			- 40			



#### REMARKS

Boring drilled with 6-inch-diameter solid-stem augers. Boring sampled using 2-inch-diameter modified California split spoon samplers. See explanation sheet for definition of symbols on this log.

PROJECT NUMBER: 805-131.04

BORING NO .: VW-3

PROJECT NAME: ARCO Service Station 8002

PAGE: 1 of 1

BY: R. Davis

DATE: 6/26/95

SURFACE ELEVATION: ft.

RECOVERY (III/ft)	PID (ppm)	PENETRA- TION (blws/ft)	GROUND WATER LEVELS	DEPTH IN FEET	SAMPLES	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL
			_	-			ASPHALT FILL.	• •
100%	0.5	2 3 5	-	5—			SANDY CLAY (CL) TO CLAYEY SAND: (SC), very dark grayish brown (2.5Y, 3/2); 50% medium plasticity fines; 20-30% fine to coarse sand; 20-30% fine to coarse gravel, up to 2-in; damp; product odor at 5'.	
100%	665	2 3 5	- <u>\</u> _ -	10			@9-10.2': CLAYEY SAND (SC), very dark grayish brown (2.5Y, 3/2); 35-40% medium plasticity fines; 35% fine to coarse sand; 25-30% fine to coarse gravel; loose; wet; product odor. @10.2-10.5': dark brown (IOYR, 4/3).	
100%	0	8 13 7	-	15			CLAYEY GRAVEL (GC), brown (2.5Y, 5/4); 20% medium plasticity fines; 30% fine to coarse sand, subangular; 50% fine to coarse gravel, subangular; medium dense; no product odor. CLAY (CL), mottled brown (7.5YR, 5/2) & (7.5YR, 5/4); 80-85% medium plasticity fines; 15-20% fine to medium sand; very stiff; damp; no product odor.  BORING TERMINATED AT 15.0 FEET BELOW GROUND SURFACE.	



REMARKS

Boring drilled with 10" diameter hollow-stem augers. Samples were taken using a 2" diameter modified-California split spoon sampler. Boring converted into a 4" diameter polyvinyl chloride (PVC) vapor extraction well. See explanation sheet for definition of symbols used in well detail and sample columns of this log.

PROJECT NUMBER: 805-131.04

BORING NO.: VW-4

PROJECT NAME: ARCO Service Station 6002

PAGE: 1 of 1

BY: R. Davis

DATE: 8/28/95

SURFACE ELEVATION: ft.

RECOVERY (ft/ft)	PIO (ppm)	PENETRA- TION (blws/ft)	GROUND WATER LEVELS	DEPTH IN FEET	SAMPLES	LTIHOGRAPHIC COLUMN	DESCRIPTION	WELL DETAIL
			_	-			ASPHALT  FILL - SANDY CLAYEY GRAVEL.	
100%	95	1 3 5	- - - -	5— -			CLAYEY SAND (SC), very dark grayish brown (2.5Y, 3/2); 30-40% medium plasticity fines; 50-60% fine to coarse sand; 10% fine gravel; loose; damp; product odor.	
100%	698	3 3 4		10-			@8-9.5': 30% fines; 50% fine to coarse sand; 20% fine to coarse gravel; moist; product odor.	
25%	0	489 356	-	15—			SANDY CLAY (CL), brown (IOYR, 4/3) with grayish brown and block mottling; 70-75% medium plasticity fines; 20-25% fine to coarse sand; 5% fine to coarse gravel; stiff to very stiff; moist; no product odor. @15-15.5': 45-50% low to medium plasticity fines. BORING TERMINATED AT 15.5 FEET BELOW GROUND SURFACE.	



#### REMARKS

Boring drilled with 10" diameter hollow-stem augers. Samples were taken using a 2" diameter modified-California split spoon sampler. Boring converted into a 4" diameter polyvinyl chloride (PVC) vapor extraction well. See explanation sheet for definition of symbols used in well detail and sample columns of this log.