

March 1, 2002

3164 Gold Camp Drive Suite 200 Rancho Cordova, CA 95670-6021 U.S.A. 916/638-2085 FAX: 916/638-8385

3/5/02 Pm

Mr. Robert Weston

Alameda County Health Care Services Agency Department of Environmental Health 1131 Harbor Bay Parkway, 2<sup>nd</sup> Floor Alameda, CA 94502

Subject: Tank Basin, Product Line and Dispenser Island Sampling Results

ARCO Station No. 5387 20200 Hesperian Boulevard

Hayward, California

Delta Project No. D000-318

Dear Mr. Weston:

Delta Environmental Consultants, Inc. (Delta) has been authorized by Atlantic Richfield Company to conduct soil sampling during the removal of the underground storage tanks (USTs), product distribution lines, and product dispenser islands at ARCO Service Station No. 5387, located at 20200 Hesperian Boulevard, Hayward, California (Figure 1). Site details are illustrated in Figure 2. This report summarizes the sampling activities and analytical results for samples collected during the UST, product line and dispenser removal activities. Field activities were performed in accordance with Delta's field methods and procedures outlined in Enclosure A.

### **Underground Storage Tank Removal**

On February 1, and 5 through 7, 2002, four USTs (12,000; 10,000; 8,000; and 6,000 gallon) were excavated and inspected upon removal. Paradiso Mechanical, Inc. was contracted by Atlantic Richfield Company to obtain all necessary tank removal permits, make all required preliminary notifications, and to clean, remove and dispose of the USTs. ECI Services transported the tanks to their facility in Richmond, California under a uniform hazardous waste manifest. Pertinent information concerning the UST removal activities is summarized below: Copies of the Uniform Hazardous Waste Manifests are included in Enclosure B.

Lead Agency: Alameda County Health Care Services Agency

Agency Contact Name: Robert Weston Agency Phone Number: (510) 567-6781

UST Cleaning Contractor: Paradiso Mechanical, Inc.

2600 Williams Street, San Leandro, CA 94577

Final Disposition of Rinseate: Romic Environmental, 2081 Bay Road, East Palo Alto, CA 94303

Final Disposition of USTs: Ecology Control Industries, 255 Parr Blvd., Richmond, California

Due to the locations of sparging wells AS-5 and AS-8 and vapor extraction well AV-3 near the UST basin, the wells were permitted for and abandoned by grouting methods. A well abandonment completion letter is currently being prepared.

Mr. Robert Weston Alameda County Health Care Services Agency Department of Environmental Health March 1, 2002 Page 2

#### Product Lines and Dispenser Islands Soil Sampling Results

A Delta representative was on site March 1, 2002 to conduct soil sampling during product line and dispenser removal activities. A representative from Alameda County Health Care Services Agency (ACHCSA) was on site to observe the sampling. Soil samples were collected beneath the dispensers following their removal. Dispenser soil samples DP-1 through DP-4 were collected at depths ranging from 3.5 to 7.0 feet below surface grade (bsg). Product line soil samples PL-1 and PL-2 were collected within the product line trench at depths ranging from 4.5 to 5.0 feet bsg. The soil sample locations are shown in Figure 3.

Soil samples were submitted to Sequoia Analytical Laboratory (Sequoia) in Sacramento, California for chemical analyses of benzene, toluene, ethylbenzene, and total xylenes (BTEX) and total petroleum hydrocarbons as gasoline (TPHg) using DHS LUFT method, tert-butyl alcohol (TBA), di-isopropyl ether (DIPE), ethyl tert-butyl ether (ETBE), ethanol, and methyl tertiary butyl ether (MTBE) using EPA Method 8260B, and total lead using EPA 6000/7000 Series Methods. Soil sample analytical results are summarized in Tables 1 and 2.

Total petroleum hydrocarbon as gasoline concentrations were reported in soil samples DP-1-3.5 at 16 milligrams per kilogram (mg/kg) and DP-1-7 at 1,800 mg/kg. Benzene concentrations ranged from 0.0060 mg/kg in soil sample PL-2-5 to 0.19 mg/kg in soil sample DP-1-3. Methyl tertiary butyl ether concentrations ranged from 0.033 mg/kg in soil sample PL-2-5 to 19 mg/kg in soil sample DP-1-7. A copy of the laboratory analytical reports with chain-of-custody documentation is included in Enclosure C.

### Underground Storage Tanks Sampling Results

A Delta representative was on site February 1 and 5, 2002 to conduct soil sampling following the removal of the USTs. A representative from ACHCSA was on site to observe the sampling. Soil samples were collected at approximately one foot beneath the USTs following their removal. Tank samples UST-1-14 through UST-8-14 were collected at a depth of approximately 14.0 feet bsg. The soil samples were submitted to Sequoia for analyses of TPHg, BTEX, MTBE, TBA, DIPE, ETBE, ethanol, and total lead using the previously described methods. The soil sample analytical results are summarized in Tables 1 and 2. The sample locations are shown on Figure 3.

Total petroleum hydrocarbon as gasoline concentrations ranged from 0.76 mg/kg in soil sample UST-3-14 to 110 mg/kg in soil sample UST-8-4. The laboratory did not detect benzene concentrations at or above the laboratory reporting limits. Methyl tertiary butyl ether concentrations ranged from 0.50 mg/kg in UST-2-14 to 2.0 mg/kg in UST-8-14. A copy of the laboratory analytical reports with chain-of-custody documentation is included in Enclosure C.

### Over-excavation and Sampling

Following receipt of the analytical results from the February 1, 2002, sampling event, Delta was on site February 6 and 7, 2002, to observe and direct the over-excavation of the upper two feet of soil from beneath the former 6,000 and 8000-gallon USTs and limited over-excavation of soil in the area of dispenser one (DP-1). Approximately 60 and 40 cubic yards of soil were over-excavated from the tank basin area and around DP-1, respectively. Following completion of the over-excavation activities, confirmation soil samples UST-5-15 through UST-8-15, OE-DP-1-12 and OE-DP-1-12.3 were collected from the base of the over-excavations. The soil samples were submitted to Sequoia for analyses of

Mr. Robert Weston Alameda County Health Care Services Agency Department of Environmental Health March 1, 2002 Page 3

TPHg, BTEX, MTBE, TBA, DIPE, ETBE, ethanol, and total lead using the previously described methods. Soil sample analytical results are summarized in Tables 1 and 2. A copy of the laboratory analytical reports with chain-of-custody documentation is included in Enclosure C. The soil sample locations and the extent of the over-excavations are shown on Figure 4.

Total petroleum hydrocarbon as gasoline concentrations ranged from 16 mg/kg in soil sample OE-DP-1-12.3 to 360 mg/kg in soil sample OE-DP-1-12. A benzene concentration of 0.13 mg/kg was detected in soil sample OE-DP-1-12.3. Methyl tertiary butyl ether concentrations ranged from 0.22 mg/kg in soil sample UST-6-15 to 1.3 mg/kg in soil sample UST-8-15.

#### **Disposal of Soil Stockpile**

The excavated overburden from the gasoline UST basin, dispensers, and lines was stockpiled on site for disposal profile analysis. Two composite soil samples were collected and submitted to Sequoia for chemical analyses of BTEX, TPHg, and lead using the previously described methods. Upon verbal approval of the ACHCSA, the soil was re-used as backfill.

The impacted soil from the over-excavation activities was stockpiled and covered with visqueen separately from the re-usable stockpile. On February 14 and 15, 2002, Dillard Environmental Services removed 184.54 tons of over-excavated soil and transported it to Forward landfill in Manteca, California. A copy of the soil stockpile analytical reports with chain-of-custody documentation is included in Enclosure C. A copy of the completion letter for soil removed is included in Enclosure D.

#### Remarks/Signatures

The interpretations contained in this document represent our professional opinions and are based, in part, on information supplied by the client. These opinions are based on currently available information and are arrived at in accordance with currently accepted hydro-geologic and engineering practices at this time and location. Other than this, no warranty is implied or intended.

If you have any questions regarding this project, please contact Steven W. Meeks at (916) 536-2613.

**DELTA ENVIRONMENTAL CONSULTANTS, INC.** 

Brett A. Bardsiev

Staff Geologist

Steven W. Meeks, P.E.

Project Manager

California Registered Civil Engineer No. C057461

BAB (Lrp003.318) Enclosures

cc: Mr. Paul Supple - Atlantic Richfield Company

Mr. Amir Gholami - Alameda County Health Care Services

# TABLE 1 SOIL SAMPLE LABORATORY ANALYTICAL RESULTS

## ARCO Service Station No. 5387 20200 Hesperian Blvd. Hayward, California

					Ethyl-	Total			
Sample ID	Date	Depth (ft)	Benzene (mg/kg)	Toluene (mg/kg)	benzene (mg/kg)	Xylenes (mg/kg)	TPHg (mg/kg)	MTBE (mg/kg)	Lead (mg/kg)
		(117)	(mgmg)	(Hg/kg)	(119,19)	(1119/1197	(1119719)	(1119/119)	(55)
Dispenser Island	<u>Samples</u>								
DP-1-3.5	02/01/02	3.5	0.19	1.6	0.47	2.8	16	0.27	<10
DP-1-7	02/01/02	7.0	<1.0	36	25	140	1800	19	<10
DP-2 <del>-4</del>	02/01/02	4.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.50	<0.0050	<10
DP-3-3.5	02/01/02	3.5	<0.0050	<0.0050	<0.0050	<0.0050	<0.50	<0.0050	<10
DP-4-4	02/01/02	4.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.50	<0.0050	<10
Product Line Sam	nples								
PL-1-4.5	02/01/02	4.5	<0.0050	<0.0050	<0.0050	<0.0050	<0.50	<0.0050	<10
PL-2-5	02/01/02	5.0	0.0060	0.014	<0.0050	0.0080	<0.050	0.033	130
FL-2-3	02/01/02	5.0	0.0000	0.014	10,0000	0.0000	40.000	0.000	,00
Tank Basin Samp	les		•						
UST-1-14	02/01/02	14.0	< 0.025	<0.025	<0.025	0.029	8.1	<0.0050	<10
UST-2-14	02/01/02	14.0	<0.50	<0.0050	<0.0050	0.025	1.4	0.50	<12
UST-3-14	02/01/02	14.0	<0.025	0.041	<0.025	<0.025	0,76	0.67	<12
UST-4-14	02/01/02	14.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.50	<0.0050	<10
UST-5-14	02/05/02	14.0	<0.050	0.099	0.23	0.050	56	1.2	<10
ŲST-6-14	02/05/02	14.0	<0.050	0.28	0.70	2.2	100	0.74	20
UST-7-14	02/06/02	14.0	<0.050	<0.050	0.18	<0.050	42	1.5	<10
UST-8-14	02/06/02	14.0	<0.050	0.18	0.49	0.073	110	2.0	<10
Over-excavation i	Results								
OE-DP-1-12	12/06/02	12.0	<0.50	0.76	2.1	2.5	360	0.85	<10
OE-DP-1-12.3	12/06/02	12.3	0.13	0.42	0.15	0.12	16	0.59	<12
UST-5-15	02/07/02	15.0	<0.050	0.080	<0.050	<0.050	45	0.47	<10
UST-6-15	02/07/02	15.0	<0.050	0.87	0.80	0.70	270	0.22	<10
UST-7-15	02/07/02	15.0	<0.050	0.065	0.23	0.12	50	0.53	<10
UST-8-15	02/07/02	15.0	<0.050	0.081	0.086	0.28	43	1.3	<10
Soil Stockpile Res	<u>sults</u>								
SP-(1,2,3,4)	02/01/02		<0.0050	0.012	<0.0050	0.011	0.66	NA	17
SP-(5,6,7,8)	02/01/02		<0.0050	<0.0050	<0.0050	<0.0050	<0.5	NA	660 <sup>1</sup> /14
SP-(9,10,11,12)	02/01/02		0.23	2.9	3.2	14	250	NA	<10

Sample result was believed to be anomolous based on other lead results from same stockpile and site soil samples.
The exact same sample was re-run with a result of 14 mg/kg.

TPHg = Total petroleum hydrocarbons as gasoline

MTBE = Methyl tertiary butyl ether

NA = Not analyzed

<sup>--- =</sup> Not applicable

TABLE 2
SOIL SAMPLE OXYGENATES LABORATORY ANALYTICAL RESULTS

## ARCO Service Station No. 5387 20200 Hesperian Blvd. Hayward, California

Sample ID	Date	Depth (ft)	TBA (mg/kg)	MTBE (mg/kg)	DIPE (mg/kg)	ETBE (mg/kg)	TAME (mg/kg)	Ethanol (mg/kg)
Dispenser Islan	d Samples	<del>.</del>						
DP-1-1-3.5	02/01/02	3.5	<0.050	0.27	<0.0050	<0.0050	0.0050	NA
DP-1-7	02/01/02	7.0	4.1	19	<0.050	<0.050	21	NA
DP-2-4	02/01/02	4.0	<0.050	<0.0050	< 0.0050	<0.0050	<0.0050	NA
DP-3-3.5	02/01/02	3.5	<0.050	<0.0050	<0.0050	<0.0050	<0.0050	NA
DP-4-4	02/01/02	4.0	<0,050	<0.0050	<0,0050	<0.0050	<0.0050	NA
Product Line Sa	ımples							
PL-1-4.5	02/01/02	4.5	<0.050	<0.0050	<0.0050	<0.0050	<0.0050	NA
PL-2-5	02/01/02	5.0	<0.050	0.033	<0.0050	<0.0050	<0.0050	NA
Tank Basin Sam	<u>ıples</u>							
UST-1-14	02/01/02	14.0	<0.050	<0.0050	<0.0050	<0.0050	<0.0050	NA
UST-2-14	02/01/02	14.0	<0.25	0.50	<0.025	<0.025	<0.025	NA
UST-3-14	02/01/02	14.0	<0.25	0.67	<0.025	<0.025	<0.025	NA
UST-4-14	02/01/02	14.0	<0.050	<0.0050	<0.0050	<0.0050	<0.0050	NA
UST-5-14	02/05/02	14.0	<1.0	1.2	<0.10	0.10	<0.10	<10
UST-6-14	02/05/02	14.0	<5.0	0.74	<0.50	<0.50	<0.50	<50
UST-7-14	02/06/02	14.0	<2.0	1,5	<0.20	<0.20	<0.20	20
UST-8-14	02/06/02	14.0	<1.0	2.0	<0.10	<0.10	<0.10	<10
Over-excavation	Results							
OE-DP-1-12	12/06/02	12.0	<5.0	<0.50	<0.50	<0.50	0.85	<50
OE-DP-1-12.3	12/06/02	12.3	<2.0	0.59	<0.20	<0.20	<20	<20
UST-5-15	02/07/02	15.0	<1.0	0.47	<0.10	<0.10	<0.10	<10
UST-6-15	02/07/02	15.0	<1.0	0.22	<0.10	<0.10	<0.10	<10
UST-7-15	02/07/02	15.0	<1.0	0.53	<0.10	<0.10	<0.10	<10
UST-8-15	02/07/02	15.0	<1.0	1.3	<0.10	<0.10	<0.10	<10

TBA = Tert-butyl alcohol


MTBE = Methyl tertiary butyl ether (analyzed by DHS LUFT)

DIPE = Di-isopropyl ether

ETBE =Ethyl ter-butyl ether


TAME = Tert-amyl methyl ether

NA = Not Analyzed



GENERAL NOTES:
BASE MAP FROM U.S.G.S.
SAN LEANDRO & HAYWARD, CA.
7.5 MINUTE TOPOGRAPHIC
PHOTOREVISED 1980





North


## FIGURE 1


SITE TOPOGRAPHIC MAP


ARCO SERVICE STATION NO. 05387 20200 HESPERIAN BOULEVARD HAYWARD, CA.

PROJECT NO.	DRAWN BY
D000-318	M.L. 8/8/00
FILE NO.	PREPARED BY
D000318A	JWS
REVISION NO.	REVIEWED BY









## **ENCLOSURE A**

Field Methods and Procedures

#### **FIELD METHODS AND PROCEDURES**

ARCO Station No. 5387 20200 Hesperian Boulevard, Hayward, California

#### 1.1 Health and Safety Plan

Delta personnel performed fieldwork in accordance with a Health and Safety Plan developed for the site. This plan described the basic safety requirements for the subsurface investigation at the site. The Health and Safety Plan was applicable to personnel and subcontractors of Delta. Personnel at the site were informed of the contents of the Health and Safety Plan prior to beginning work. A copy of the Health and Safety Plan was kept at the work site and was available for reference by appropriate parties during the work. The Delta geologist acted as the Site Safety Officer.

### 1.2 Soil Sampling and Contamination Reduction

Soil sampling was performed under the direction of Delta geologists. To reduce the chances of cross-contamination between samples, all sampling equipment was either steam-cleaned or washed with a non-phosphatic detergent between each sample location. To reduce cross-contamination between samples, the sampler was washed in a soap solution and double-rinsed between each sampling event.

### 1.3 Soil Sample Collection

Soil at the sample location was excavated to a depth of approximately 6 inches above the sampling depth. At this depth, a hand operated impact sampler lined with a 6-inch clean brass sampling tube was used to collect the soil sample. Soil cuttings collected immediately above the soil sample were placed into a Ziploc® bag and sealed for later screening with a PID. That part of the soil sample collected in the brass tube within the impact sampler was sealed with Teflon® sheeting and plastic caps, labeled and stored on ice at approximately 4° C for transport to the laboratory.

#### 1.4 Soil Sample Screening/hNu Portable Photoionization Detector Method

After the soil sample Ziploc® bags had been brought to ambient temperature, the headspace vapors of the soil sample in the bag were screened with a PID equipped with a 10.2 eV lamp. The corner of the sample bag was opened and the detector probe immediately placed within the headspace. The highest observed reading was recorded. Field instruments such as the PID are useful for indicating relative levels of hydrocarbon vapors, but do not detect concentrations with the same precision as laboratory analyses.

#### 1.5 Product Distribution Lines and Dispenser Sampling

Soil samples were collected following the removal of the product distribution lines and dispensers. Samples were collected approximately 2 feet below the backfill/native soil interface within the product line trench. If groundwater was encountered above the base of the excavation, soil samples were collected from the sidewalls of the excavations immediately above the groundwater. Following removal of the dispensers, one soil sample was collected approximately 2 feet below the backfill/native soil interface beneath each dispenser.

#### 1.6 Soil Stockpile Sampling

Four soil samples will be collected from each 50 cubic yards of stockpiled soil, with each set of four samples to be composited in the laboratory prior to analyses. Soil samples will be collected in 2-inch diameter brass tubes that will be sealed with Teflon sheeting and plastic caps. The samples will be labeled, stored in an ice chest and cooled to approximately 4°C for transport to the laboratory.

#### 2.0 ANALYTICAL PROCEDURES

Selected soil samples submitted to the laboratory were analyzed for BTEX, TPHg and MTBE using EPA Method 8260 and total lead using EPA Method 6010.

### 3.0 QUALITY ASSURANCE PLAN

This section describes the field and analytical procedures followed throughout the investigation.

#### 3.1 General Sample Collection and Handling Procedures

Proper collection and handling are essential to ensure the quality of a sample. Each sample was collected in a suitable container, preserved correctly for the intended analysis, and stored prior to analysis for no longer than the maximum allowable holding time. Details on the procedures for collection and handling of soil samples used on this project can be found in Section 1.0 (Methods).

#### 3.2 Sample Identification and Chain-of-Custody Procedures

Sample identification and chain-of-custody procedures ensure sample integrity and document sample possession from the time of collection to its ultimate disposal. Each sample container submitted for analysis had a label affixed to identify the job number, sampler, date and time of sample collection, and a sample number unique to that sample. This information, in addition to a description of the sample, field measurements made, sampling methodology, names of on-site personnel, and any other pertinent field observations, was recorded on the borehole log or in the field records. A California-certified laboratory analyzed samples.

A chain-of-custody form was used to record possession of the sample from time of collection to its arrival at the laboratory. When the samples were shipped, the person in custody of them relinquished the samples by signing the chain-of-custody form and noting the time. The sample-control officer at the laboratory verified sample integrity and confirmed that the samples were collected in the proper container, preserved correctly, and that there was an adequate volume for analysis.

If these conditions were met, the sample was assigned a unique log number for identification throughout analysis and reporting. The log number was recorded on the chain-of-custody form and in the legally-required logbook maintained by the laboratory in the laboratory. The sample description, date received, client's name, and other relevant information was also recorded.

## **ENCLOSURE B**

Uniform Hazardous Waste Manifests

		C/CZ/CUUC 10:33 PAA 31U 014 6390	PARADISU MECHAI					经以以
	Pleon Pleon	Approved OMB-No. 2050-0039 (Expires 6-30-99) print or type. Form designed for use on elite (12-pitch)	See Instructions	on back	و ا	a 6.	Рерага	mant of Toxic Substances Co
		UNIFORM HAZARDOUS 1. Generalor's	US EPA ID No. Ma	nilasi Documer	M No.	2. Page 1	Informati	Sacramento, California on in the shaded areas
		WASTE MANIFEST	999326129	14 13	9.	7 1 1 4 1		uired by Federal law.
		3. Generator's Name and Mailing Address ARCO PRODUCTS		<del>-1</del>	A. Shale	Manifed Document	Number _	34.0.0.4.0.0
	ا ا	4 CENTER POINT LA PALMA CA 90823	!,					? <b>139</b> 4997
75.5		4. Generator's Phone ( (?14) 679-5300)			B. State	Generator's ID		
5		5. Transporter I Company Name	6. US EPA ID Number	<u> </u>	C. Stole	Transporter's ID Res	erved.]	
1.900.052.7250	š	EGOLOGY CONTROL INDUSTRIES	CAPSSAGG	C. 1. 7. 3	D. Trens	porter's Phone		10-235-1393
	<u>-    </u>	7. Transporter 2 Company Name	a. US EPA ID Number		L	Transporter's ID (Res		10-235-1393
, E	ξ		111111111	1 1 1		porter's Phone	<del></del>	<u> </u>
		2. Petignolod Facility Name and Site Address ECOLOGY CONTROL INDUSTRIES	10. US EPA ID Number	<del></del>		Facility's (D		<u> </u>
;		255 PARR BLVD			LL P - 17	Y's Phone		
CALIFORNIA		піснмойо, сд 94801	<u>CA4999491</u>	9392	n. rucili	ry a Priorite	5	10-235-1393
		11 US DOT Description (including Proper Shipping Name, Hazard C		12. Con	loiners Type	13. Total Quantity	I.4. Unit WI/Vol	Linear in the second
NHIX.		WASTE EMPTY STORAGE TA	NK		7754	Gleanny	171/ 101	Stale 512
		NON-RCRA HAZARDOUS WA	STE SOLID	601	TP	10000	P	EPA/Other
-800-424-8602	Ñ	b.		001		1000C		State
4-8i	R						;	7 (S) (S) (S) (S)
0-42	A	ε,					• • • •	EPA/Other
ģ	Ó		•					Strain
~ ~	î	d			1		-	EPA/Other 5
CENTER	Н	· ·	•	• ]		·		Sing Test State to Jack
		·	•		ì			EPA/Other
ő		2. Additional Descriptions for Materials Listed Above OTY EMPTY STORAGE TANK(S) **	190519	the state of the s	K., Handlis	ng Codes for Wastes	منطم إمونيا	
ESP		ANK(S) H	AUP REEN INCOTED MOT		1	<b>建筑市 48-4</b> 0		<b>和</b> 护大学。
¥		15 LBS DRY ICE PER 1000 GALLONS CAPACITY			- 10	NO TO	Harry V	
NATIONAL RESPONSE		Wear appropriate protective slothing	IO When handling.	4 (3/9); <b>SITE</b> (	, 1030 AAA			
NA1		24 Hour Emergency Telephone Nur	nber: X   200 AR	SO Fix		HUN; ARI	200 PI	ATION ESPERIAN
뿔		24 Hour Emergency Contact: X 10		RG 171	•			ARD, CA
		16. GENERATOR'S CERTIFICATION: I have by declare that the analysis	. Ed.	-7			<u> </u>	<u> </u>
3		16. GENERATOR'S CERTIFICATION: I hereby declare that the contants marked, and labeled, and are in all respects in proper condition is	or transport by highway according to	rately describe opplicable int	d above by emotional	proper shipping not and national govern	ne and are o meat regula	lassified, packed, '
SPILL								
õ		if an 8 large quantity generator, I certify that I have a program practicable and that I have a selected the practicable method of tree and the environment; OR, if I am a small quantity generator, I have a valiable to me and that I can afford.	olment, storage, or disposal currently we made a good faith effort to minim	ovsiloble to m iza my waste :	e which m deneration	inimizes the present	and future i	hreat to human health
	1	Printed/Typed Name	Signoty/6	1				
Ž	<b>▼</b>	Darryk Hawl		Le.	7		Mont	ပြေပျိုင်းကို
EMEKGENCY	Ŕ	17. Transparter 1 Acknowledgement of Receipt of Moterials Printed/Typed Name	Signature				7	
	Ë	Lawria Major	Jaw is con	-m			Month	301/102
5	Ĭ	16. Transporter 2 Acknowledgement of Receipt of Mistarials Printed/Typed Name	Signature					
찱	Ř	19. Discrepancy Indication Space			•		Month	Doy Year
Ξ	F A	Ty. Size oponey marcanan space						<del></del>
	Ċ	عائد · .		-		•		•
	ŀ	20. Facility Owner or Operator Cortification of receipt of hazardous mot Printed/Typed Name	derinis serve J.L. de					
	Ţ	Printed/Typed Name	⊅ighalura	i est noted in th	zen 19		Month	Day Year
L						•	<u> </u>	TT Lie
			NOT WRITE DELONG THE					

	1 D.J. A 17P 1 A.				
,	Printed/Typed Name	Signature	1 70		Month Day 1: Year
	Darry K Attaile	ر ا	$\mathcal{L}$		の区の頂側のに
	17. Transporter 1 Acknowledgement of Receipt of Moterials				T and
	Printed Typed Name	Signature		•	Month Day Year
	Trea locasmaler	Fiel	Toeismer		012011012
	18. Transporter 2 Acknowledgement of Receipt of Materials				·
	Printed/Typed Name	Signalura			Month of Day him Year
_		ļ			
	19. Discreponcy Indication Space		-	•	

20. Facility Owner or Operator Certification of receipt of hazardous materials covered by this monifest except as noted in item 19, Printed/Typed Name

#1 / ...


DO NOT WRITE BELOW THIS LINE.

EMERGENCY

UZ/ Stale pi	ZZ/ZUUZ 15:34 FAX 510 614 8396 Colitornia—Environmental Projection Agency	PARADISU MECHAN					<b>⊯</b> 004
Form A Please	peroved OMB No. 2050-0039 (Expires 9-30-99) print or type. Form designed for use on elite (12-pitcl riter,	See Instructions	on back o	ge	6.		ent of Toxic Substances Coat Secremento, California
1	UNIFORM HAZARDOUS WASTE MANIFEST	01013121611129	ifesi Document	No. 4,4	2. Page 1	Informatio	n in the shaded areas ired by Federal Law.
	3. Generator's Alama and Mailing Address ARCO Products 4 CENTER POINT LAPALMA CA. 908		<u> </u>	A. State M	Ionifest Document N	lumber 2	1394944
220	4. Generalar's Phone (7/4) 670-5360	<i>43</i> ,		B. Slote G	enerator's ID		
852-7	5. Transporter 1 Company Nome 6.	. US EPA ID Number			onsporter's ID [Rese	rved.)	- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1
CALL 1-800-852-7550	Ecology Control Industries  7. Trunsporter 2 Company Name  8.	A D 9 8 2 0 3 0 . US EPA ID Number	173		orter's Phone		10-235-1393
Y SE	,,				rter_s Phone	<del></del>	
	9. Dasignated Facility Name and Site Address 10. ECOLOGY CONTROL INDUSTRIES 255 PARR BLVD	. US EPA ID Number		G. State Fo			
CALIFORNIA,	RICHMOND CA 94801 C	AID 0 0 9 4 6 6		·			) 235-1393
	11. US DOT Description (including Proper Shipping Name, Hazard Class, NON RCRA HAZARDOUS WASTE SOIL		No.	Type	13. Total Quantity	14. Unit Wt/Vol	1. Woste Number
1-800-424-8802: WIIHIN	WASTE EMPTY STORAGE TANK		01012	TP	1 RIDIGS	P	EPA/Other 9
N E 8	<b>b</b> .	•					State EPA/Other
300-4 0 1 0 1	c.						Stoke
	d.			1		···	State
KESPONSE C	1. Additional Descriptions for Motorials Listed Above QTY STORAGE TANK 295	70 - 2957132	19.6825191	K. Handin	g Codes for Westes	Listed Abo	EPA/Other 1997
AL NEST	TANKS WITH 15 LBS DRY ICE PER 1000 GALLONS CAPAC	HAVE BEEN INERTED					
	15. Special Handling Instructions and Additional Information WEAR PROPER PROTECTIVE EQUIPMENT V 24 HOUR EMERGENCY CONTACT: /-		VEIGHTS		LUMES AR		
	24 HOUR EMERGENCY TELEPHONE	NUMBER: /-800-	IRCO-FIX	ZZOO HAVU	HESPERIAN MED CA.	Ì	OT ERG # 171
\$	<ol> <li>GENERATOR'S CERTIFICATION: I hereby deduce that the contents of t marked, and labeled, and are in all respects in proper condition for to</li> </ol>	this considerant on fully and aco	فانعميماء بطميحينا	hd abada bu	nean altata an	me and are	clossified, packed, alians.
OR SPIECE	If I am a large quantity generator, I certify that I have a program in practicable and that I have salected the practicable method of treatment and the environment; OR, if I am a small quantity generator, I have a available to me and that I can afford.	place to reduce the volume and ont, sharage, or disposal currently made a good faith effort to minin	foxicity of was ovailable to o nize my waste	generation no which mi	d to the degree I ha inimizes the present and select the best	ve delemi and blure wase man	ned to be economically threat to busine health agament method that is
	Printed/Typed Name IN BEHALF of ARCO	Signature	THE	La .		Moni	21015702
THE WAR	17. Transporter 1 Acknowledgement of Receipt of Materials Printed/Typed Name	Signoury /	<u> </u>			Moni	h Doy Year
5   [	18. Transporter 2 Acknowledgement of Receipt of Materials Printed/Typed Name	Fignalure	regress	<i>J</i>		Mont	H Day Year
	19. Discrepancy Indication Space	<u></u>	•	-,	<u> </u>		
A C	-5.					٠	
	20. Facility Owner or Operator Certification of receipt of hazardous material Printed/Typed Name	rials covered by this menifest exce	pt as nated in	Nem 19.	·	Mont	h Duy Year .
Y			•	٠.	•		

## ENCLOSURE C

Soil Sample Laboratory Analytical Reports



February 05, 2002

Steven Meeks
Delta Environmental Consultants (Rancho Cordova)
3164 Gold Camp Drive Ste. 200
Rancho Cordova, CA 95670
RE: Arco 5387, Hayward, CA / S202019

Enclosed are the results of analyses for samples received by the laboratory on 02/01/02. If you have any questions concerning this report, please feel free to contact me.

Sincerely,


Ron Chew

Client Services Representative

Lito Diaz

**Laboratory Director** 

CA ELAP Certificate Number 1624



Delta Environmental Consultants (Rancho Cordove

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA Project Manager: Steven Mecks Reported:

02/05/02 14:01

#### ANALYTICAL REPORT FOR SAMPLES

Sample 10	Laboratory ID	Matrix	Date Sampled	Data Received
DP-1-3.5	S202019-01	Soil	02/01/02 11:11	02/01/02 17:25
DP-1-7.0	S202019-02	Soil	02/01/02 11:24	02/01/02 17:25
DP-2-4.0	S202019-03	Soil	02/01/02 11:02	02/01/02 17:25
DP-3-3.5	\$202019-04	Soil	02/01/02 11:42	02/01/02 17:25
DP-4-4.0	\$202019-05	Soil	02/01/02 10:49	02/01/02 17:25
PL-14.5	S202019-06	Soil	02/01/02 11:05	02/01/02 17:25
PL-2-5.0	S202019-07	Soil	02/01/02 10:52	02/01/02 17:25
UST-1-14.0	S202019-08	Soil	02/01/02 13:36	02/01/02 17:25
UST-2-14.0	S202019-09	Soil	02/01/02 13:40	02/01/02 17:25
UST-3-14.0	S202019-10	Soil	02/01/02 13:45	02/01/02 17:25
UST-4-14.0	\$202019-11	Soil	02/01/02 13:51	02/01/02 17:25



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Total Purgeable Hydrocarbons and BTEX by DHS LUFT

	Sei	quoia Ana	пуцсат	- Dacra	шеню				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
DP-1-3-5 (S202019-01) Soil	Sampled: 02/01/02 11:11	Received: 0	2/01/ <b>0</b> 2 1	7:25					
Purgeable Hydrocarbons	16	10	mg/kg	2	2020027	02/04/02	02/04/02	DHS LUFT	
Benzene	0.19	0.10	-	-	u	17	**	•	
Toluene	1.6	0.10	16	-	77	m	m	**	
Ethylbenzene	0.47	0.10	<b>p</b>	-	•	TP	**		
Xylenes (total)	2.8	0.10	и	t•	il	н	"	M	
Surrogate: a,a,a-Trifluorotoli	uehė	106%	60-	140	п	#	#	, u	
DP-1-7.0 (S202019-02) Soil	Sampled: 02/01/02 11:24	Received: 0	2/01/02 1	7:25					
Purgeable Hydrocarbons	1800	100	mg/kg	20	2020027	02/04/02	02/04/02	DHS LUFT	
Benzene -	ND	1.0	n		•	11.	ls.	16	
Toluene	36	1.0	11	"	13	•	ਸ	Ħ	
Ethylbenzene	25	1.0	**	"	**	-	ır	*	
Xylenes (total)	140	1.0	•1		*	4	H	**	
Surrogate: a,a,a-Trifluorosoli	uene	87.7 %	60-	140	H	*	#	*	
DP-2-4.0 (S202019-03) Soil	Sampled: 02/01/02 11:02	Received: 0	2/01/02 1	7:25					
Purgeable Hydrocarbons	ND	0.50	mg/kg	1	2020025	02/01/02	02/01/02	DHS LUFT	
Benzene	ND	0.0050	**	*	-	H*	*	4	
Toluene	מא	0.0050	11	ч	*	И	ęi	H	
Ethylbenzenc	ND	0.0050	10	н	n	•	n	P	
Xylenes (total)	ND	0.0050	ıı	И	h	11	16	и	
Surrogate: a,a,a-Trifluorotols	uene	90.0 %	60-	140	н	н	n	"	
DP-3-3.5 (\$202019-04) Soil	Sampled: 02/01/02 11:42	Received: 0	2/01/02 1	7:25					
Purgeable Hydrocarbons	ИĎ	0.50	mg/kg	1	2020025	02/01/02	02/01/02	DHS LUFT	
Benzene	ND	0.0050	m	11	"	IJ	11	h	
Tolucne	ND	0.0050				**	n	п	
Ethylbenzene	ND	0.0050		H	P		4		
Xylenes (total)	ND	0.0050			H	n	-	#	
Surrogate: a,a,a-Trifluorosoli	uene	69.0 %	60-	140	#	n	17	W	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA


Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Total Purgeable Hydrocarbons and BTEX by DHS LUFT

	56	quota Au	aryucai	- GALI A	шеию				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
DP-4-4.0 (S202019-05) Soil	Sampled: 02/01/02 10:49	Received: 0	2/01/02 1	7:25					
Purgeable Hydrocarbons	ND	0.50	mg/kg	1	2020025	02/01/02	02/01/02	DHS LUFT	
Benzene	ND	0.0050	11	K	**	4.	**	n	
Toluene	ND	0.0050	71	"	Ħ	-	**	•	
Ethylbenzene	ЙD	0.0050	п	U	я	•	"	n	
Xylenes (total)	ND	0.0050	π	п	н	11	n	. "	
Surrogale: a,a,a-Trifluorotoli	tene	70.0 %	<b>60-</b>	140		æ	*	**	
PL-14.5 (\$202019-06) Soil	Sampled: 02/01/02 11:05	Received:	02/01/02 1	7:25					
Purgeable Hydrocarbons	ND	0.50	mg/kg	l	2020025	02/01/02	02/01/02	DHS LUFT	
Benzene	ND	0.0050	T.	r /	"	u	**	*	
Toluene	ND	0.0050	•	π	•	lr	11	•	
Ethylbenzene	ND	0.0050	н	10	-	u	46	-	
Xylenes (total)	סא	0.0050	*	4	н				.,
Surrogate: a,a,a-Trifluorotoli	uene	71.0%	60-	140	и	*	7	es	
PL-2-5.0 (S202019-07) Soil	Sampled: 02/01/02 10:52	Received: 0	12/01/02 1	7:25					
Purgeable Hydrocarbons	ND	0.50	mg/kg	1	2020026	02/04/02	02/04/02	DHS LUFT	
Benzene	0.0060	0.0050	p	И	×	4	*	**	
Toluene	0.014	0.0050	TF.	и	r*	Ħ	41	•	
Ethylbenzene	ND	0.0050	×	a	н	-	м	m	
Xylenes (total)	0.0080	0.0050	n	TI	rt	"	"		
Surrogase: a,a,a-Trifluorotols	uene	61.5 %	60-	140	"	<b>"</b>	"	"	
UST-1-14.0 (S202019-08) So	il Sampled: 02/01/02 13:5	36 Received	l: 02/01/0:	2 17:25					
Purgeable Hydrocarbons	8.1	2.5	mg/kg	5	2020026	02/04/02	02/04/02	DHS LUFT	HC-1
Benzene	ND	0.025		-	n	n	71	Þ	
Toluene	ND	0.025	-	••	Ħ	"	11	π	
Ethylbenzene	ND	0.025	-	-	11	-	p	n	
Xylenes (totał)	0.029	0.025	P		n	n		<b>3</b> t	
Surrogate: a,a,a-Trifluorotoli	iene	84.5 %	60-	140	*	~	=	PF .	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Total Purgeable Hydrocarbons and BTEX by DHS LUFT

	7-4-	V x	,	- Datia					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
UST-2-14.0 (S202019-09) Soil	Sampled: 02/01/02 13:40	Received	: 02/01/0	2 17:25			_		
Purgeable Hydrocarbons	1.4	0.50	mg/kg	I	2020026	02/04/02	02/04/02	DHS LUFT	HC-12
Benzene	ND	0.0050	4		H	ļi.	71	*	
Toluene	ND	0.0050		-	n		**	×	
Ethylbenzene	ND	0.0050		••		"		•	
Xylenes (total)	0.025	0.0050	-	-	•	п	••		
Surrogate: a.a.a-Trifluorotoluen	ie	86.0 %	60	140	"	17	#	r.	
UST-3-14.0 (S202019-10) Soil	Sampled: 02/01/02 13:45	Received	: 02/01/02	2 17:25					
Purgeable Hydrocarbons	0.76	0.50	tng/kg	5	2020026	02/04/02	02/04/02	DHS LUFT	HC-12
Benzene	ND	0.025	n	"	u	•	•	•	
Toluene	0.041	0.025	H			"	"	•	
Ethylbenzene	ND	0.025	71	n	ır	•	er	il	
Xylenes (total)	ND	0.025	at	n		•	•	•	
Surrogate: a,a,a-Trifluorotoluen	e	82.5 %	60-	140	"	*	*	"	_
UST-4-14.0 (S202019-11) Soil	Sampled: 02/01/02 13:51	Received	: 02/01/02	17:25					
Purgeable Hydrocarbons	ND	0.50	mg/kg	1	2020026	02/04/02	02/04/02	DHS LUFT	
Benzene	ND	0.0050	4	•	-	4	-	•	
Toluene	ND	0.0050		И	-	21	-	m	
Ethylbenzene	ND	0.0050	n	п	11	ej	ls.		
Xylenes (total)	ND	0.0050	"	H		11	u		
Surrogate: a,a,a-Trifluorotoluen	e	78.5 %	60	140	, , , , , , , , , , , , , , , , , , ,	*	ø		




Delta Environmental Consultants (Rancho Cordova

Project: Arco 5387, Hayward, CA

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project Number: 5387, Hayward, CA Project Manager: Steven Meeks Reported: 02/05/02 14:01

## Total Metals by EPA 6000/7000 Series Methods

Апајује	Result	Reporting Limit	Units	Dilution	Baich	Prepared	Analyzed	Method	Notes
DP-1-3.5 (S202019-01) Soil	Sampled: 02/01/02 11:11	Received: 0	2/01/02 1	7:25					
Lead	ИD	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
DP-1-7.0 (S202019-02) Soil	Sampled: 02/01/02 11:24	Received: 0	2/01/02 1	7:25					
Lcad	ND	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
DP-2-4.0 (\$202019-03) Soil	Sampled: 02/01/02 11:02	Received: 0	2/01/02 1	7:25					
Lead	ND	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
DP-3-3.5 (S202019-04) Soil	Sampled: 02/01/02 11:42	Received: 0	2/01/02 1	7:25					
Lead	ND	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
DP-4-4.0 (S202019-05) Soil	Sampled: 02/01/02 10:49	Received: 0	2/01/02 1	7:25					
Lead	ND	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
PL-14.5 (S202019-06) Soil	Sampled: 02/01/02 11:05	Received; (	2/01/02	17:25				,	
Lead	ND	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
PL-2-5.0 (S202019-07) Soil	Sampled: 02/01/02 10:52	Received: 0	2/01/02 1	7:25					
Lead	130	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
UST-1-14.0 (S202019-08) So	il Sampled: 02/01/02 13:3	6 Received	: 02/01/0	2 17:25					
Lead	ND	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	
UST-2-14.0 (S202019-09) So	il Sampled: 02/01/02 13:4	0 Received	: 02/01/0	2 17:25					
Lead	ND	12	mg/kg	5	2020029	02/04/02	02/05/02	EPA 6010B	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported:

02/05/02 14:01

## Total Metals by EPA 6000/7000 Series Methods

Analyte	Rosult	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
UST-3-14.0 (S202019-10) Soil	Sampled: 02/01/02 13:45	Received	: 02/01/0	2 17:25					
Lead	ND	12	mg/kg	5	2020029	02/04/02	02/05/02	5PA 6010B	
UST-4-14.0 (S202019-11) Soil	Sampled: 02/01/02 13:51	Received	: 02/01/0	2 17:25	•	·			
Lead	ND	10	nig/kg	4	2020029	02/04/02	02/05/02	BPA 6010B	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA Project Manager: Steven Meeks Reported: 02/05/02 14:01

## Volatile Organic Compounds by EPA Method 8260B

	Sec	quoia Ana	пунсаі	- Sacra	mento				
Analyte	Result	Reporting Limit	Units	Dilution	Barch	Prepared	Analyzed	Method	Notes
DP-1-3.5 (S202019-01) Soil	Sampled: 02/01/02 11:11	Received: 0	2/01/02 1	7:25					R-0:
Tert-butyl alcohol	ND	0.050	mg/kg	1	2020019	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	0.27	0.0050		Ħ	p	ţ=	n	*	
Di-isopropyl ether	ND	0.0050		n	i.	11-	p	*	
Ethyl tert-butyl ether	ND	0.0050	п		IP	**	н	e e	
Tert-amyl methyl ether	ND	0.0050	•		н			u	
Surrogate: 1,2-DCA-d4		101 %	60-	140	H	#	#	-	
DP-1-7.0 (S202019-02) Soil	Sampled: 02/01/02 11:24	Received: 0	2/01/02 1	7:25					R-05
Tert-butyl alcohol	4.1	0.50	mg/kg	10	2020019	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	19 '	0.050	-	-	•	u	*	п	
Di-isopropyl ether	ND	0.050	-	•	*	17	•		
Ethyl tert-butyl ether	ND	0.050	-	•	11	н	-	• .	
Tert-amyl methyl ether	21	0.050		-	"	<u> </u>		н	<del> </del>
Surrogate: 1,2-DCA-d4		88.0 %	60-	140	*	7	7	o	
DP-2-4.0 (\$202019-03) Soil	Sampled: 02/01/02 11:02	Received: 0	2/01/02 1	7:25		•			
Tert-butyl alcohol	ND	0.050	mg/kg	1	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	ND	0.0050	11	si-	4	-		н	
Di-isopropyl ether	ND	0.0050	H	H	Ħ	10		п	
Ethyl tert-butyl ether	ND	0.0050	И	Ħ		u	•	4	
Tert-amyl methyl ether	ND	0.0050	IN	u		W		· · · · · · · · · · · · · · · · · · ·	
Surrogate: 1,2-DCA-d4		86.8 %	60-	140	17	rt	1/	*	
DP-3-3.5 (S202019-04) Soil	Sampled: 02/01/02 11:42	Received: 0	2/01/02 1	7:25					
Tert-butyl alcohol	ND	0.050	mg/kg	1	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl cther	ND	0.0050	•		•	IT		•	
Di-isopropyl ether	ND	0.0050	•	-	h	II.	π	4	
Ethyl tert-butyl cther	ND	0.0050	**	•	п	p	4	•	
Tert-amyl methyl ether	ΝĎ	0.0050	*	И	н			**************************************	
Surrogate: 1,2-DCA-d4		84.8 %	60-	140	*	н	#	Ħ	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Volatile Organic Compounds by EPA Method 8260B

		Idoia Ana	a, aca						
Алајус	Result	Reponing Limit	Units	Dilution	Baich	Prepared	Analyzed	Method	Note
DP-4-4.0 (S202019-05) Soil	Sampled: 02/01/02 10:49	Received: 0	2/01/02 1	7:25					
Tert-butyl alcohol	ND	0.050	mg/kg	1	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl terr-butyl ether	ND	0.0050		•	•		P	н	
Di-isopropyl ether	ND	0.0050	•	И	•	u	-	n.	
Ethyl tert-butyl ether	ND	0.0050	-	•	•		**	•	
Terr-amyl methyl ether	ND	0.0050	•	Ð	•	n	•		
Surrogate: 1,2-DCA-d4		86.2 %	60-	140	"	7	π	Ħ	
PL-14.5 (\$202019-06) Soil	Sampled: 02/01/02 11:05	Received: 0	2/01/02 1	17:25					
Tert-butyl alcohol	ND	0.050	mg/kg	1	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	ND	0.0050	•	٦			*		
Di-isopropyl ether	ND	0.0050	ı	Ħ	M	B	-	н	
Ethyl tert-butyl ether	ND	0.0050	77	-	p3	10	H	<b>H</b>	
Tert-amyl methyl ether	ND	0.0050	11	**		N.			
Surrogate: 1,2-DCA-d4		86.8 %	60-	140	Ħ	"	N	н	
PL-2-5.0 (S202019-07) Soil	Sampled: 02/01/02 10:52	Received: 0	2/01/02 1	7:25					
Tert-buryl alcohol	ND	0.050	mg/kg	1	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	0.033	0.0050	u	Ħ	•	H	•	ri	
Di-isopropyl ether	ND	0.0050		ч	-	11	t-	17	
Ethyl tert-butyl ether	ND	0.0050	•	•	-	"		"	
Tert-amyl methyl ether	ND	0.0050				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			
Surrogate: 1,2-DCA-d4		98.0 %	60-	140	"	"	W	#	
UST-1-14.0 (\$202019-08) So	oil Sampled: 02/01/02 13:3	6 Received	: 02/01/0	2 17:25					
Tert-butyl alcohol	ND	0.050	mg/kg	I	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	ND	0.0050	н	P	•	п	•	-	
Di-isopropyl ether	ND	0.0050	*	-	le .	•	ч	-	
Ethyl tert-butyl other	ND	0.0050	Ħ	۳	n	**	u	-	
Tert-amyl methyl ether	סא	0.0050	n	,,			π	41	
Surrogate: 1,2-DCA-d4		17.8 %	60-	140	#	"	*	"	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Stc. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA


Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Upits	Dilution	Batch	Prepared	Analyzed	Method	Notes
UST-2-14.0 (S202019-09) Soil	Sampled: 02/01/02 13:40	Received	: 02/01/02 1	7:25			-		R-05
Tert-butyl alcohol	ND	0.25	mg/kg	5	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl other	0.50	0.025	-	-		i f	"		
Di-isopropyl ether	ND	0.025	*	**	71	n	-	P	
Ethyl tert-butyl ether	ND	0.025	•	**	"		н	• .	
Tert-amyl methyl other	ND	0.025		W	¥	h .	11	11	
Surrogate: 1,2-DCA-d4		79.2 %	60-14	0	er	"	. *	*	
UST-3-14.0 (S202019-10) Soil	Sampled: 02/01/02 13:45	Received	: 02/01/02 1	7:25					R-05
Tert-butyl alcohol	· ND	0.25	mg/kg	5	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	0.67	0.025	III	14	-	**	•	п	
Di-isopropyl ether	ND	0.025	-	н	•	**	•	н	
Ethyl tert-butyl ether	ND	0.025	•	•		a	-	II	
Tcrt-amyl methyl ether	ND	0.025	-	•		<b>3</b> 4	•		
Surrogate: 1,2-DCA-d4		75.6 %	60-14	0	<b>"</b>	•	77	"	
UST-4-14.0 (S202019-11) Soil	Sampled: 02/01/02 13:51	Received	: 02/01/02 1	7:25			_		
Tert-butyl alcohol	ND	0.050	mg/kg	1	2020011	02/04/02	02/04/02	EPA 8260B	
Methyl tert-butyl ether	ND	0.0050	"	н	-	It	-	П	
Di-isopropyl ether	ND	0.0050	•	9	•	11	*	-	
Ethyl tert-butyl ether	ND	0.0050	*	н	#1	17	. 11	-	
Tert-arnyl methyl ether	ND	0.0050	4	-	-	u		10	
Surrogale: 1,2-DCA-d4		80.0 %	60-14	o	7	μ	*	N	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA Project Manager: Steven Meeks Reported: 02/05/02 14:01

# Total Purgeable Hydrocarbons and BTEX by DHS LUFT - Quality Control Sequoia Analytical - Sacramento

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%rec	VREC Limius	RPD	RPD Limit	Notes
Batch 2020025 - EPA 5030B (P/T)						***				
Blank (2020025-BLK1)				Prepared &	k Analyze	d: 02/01/0	02			
Purgeable Hydrocarbons	ИD	0.50	mg/kg							
Benzene	מא	0.0050								
Toluene	מא	0.0050	H							
Ethylbenzono	ND	0.0050								
Xylanes (total)	ND	0.0050								
Surrogate: a,a,a-Trifluorotoluene	0.0178		Ħ	0.0200		89.0	60-140			
LCS (2020025-BS1)				Prepared &	& Analyze	d: 02/01/0				
Benzene	0.0177	0.0050	mg/kg	0.0200		88.5	70-130			
Tolucne	0.0166	0.0050		0.0200		83.0	70-130			
Ethylbenzene	0.0177	0.0050	-	0.0200		88.5	70-130			
Xylenes (total)	0.0503	0.0050	•	0.0600		83.8	70-130			
Surrogate: a,a,a-Trifluorotoluene	0.0158	., ,	n	0.0200		79.0	60-140			
Batch 2020026 - EPA 5030B (P/T)										
Blank (2020026-BLK1)				Prepared &	& Analyze	d: 02/04/0	02			
Purgeable Hydrocarbons	ND	0.50	πg/kg							
Benzene	ND	0.0050	7							
Toluene	ND	0.0050	-							
Ethylbenzene	ND	0.0050	н							
Xylenes (total)	NД	0.0050	n							
Surrogate: a,a,a-Trifluorotolvene	0.0179		r	0.0200	· · · · · · · · · · · · · · · · · · ·	89.5	60-140			
LCS (2020026-BS1)				Prepared &	& Analyze	d: 02/04/	02			
Benzene	0.0170	0.0050	mg/kg	0.0200		85.0	70-130			
Toluene	0.0155	0.0050		0.0200		77.5	70-130			
Ethylbenzene	0.0170	0.0050	•	0.0200		85.0	70-130			
Xylenes (total)	0.0480	0.0050	•	0.0600		80.0	70-130			
Surrogate: a,4,a-Trifluorotoluene	0.0157		)1	0.0200		78.5	60-140			

Sequoia Analytical - Sacramento

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its onlivery.





Delta Environmental Consultants (Rencho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA Project Manager: Steven Meeks Reported: 02/05/02 14:01

## Total Purgeable Hydrocarbons and BTEX by DHS LUFT - Quality Control Sequoia Analytical - Sacramento

		guvia Au		- QEC1 E.						
Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2020026 - EPA 5030B (P/T)								_		
LCS Dup (2020026-BSD1)				Prepared &	& Analyze	ed: 02/04/	02			,,
Всписле	0.0193	0.0050	mg/kg	0.0200		96.5	70-130	12.7	25	
Toluene	0.0205	0.0050		0.0200		102	70-130	27.8	25	QR-0
Ethylbenzene	0.0200	0.0050		0.0200		100	70-130	16.2	25	
Xylenes (total)	0.0580	0.0050	•	0.0600		96.7	70-130	18.9	25	
Surrogate: a,a,a-Trifluorotoluene	0.0169		<i>a</i>	0.0200	, ,	84.5	60-140			
Batch 2020027 - EPA 5030B (MeOH)										
Blank (2020027-BLK1)				Prepared o	& Analyz	ed: 02/04/	02			~
Purgeable Hydrocarbons	ND	5.0	mg/kg							
Benzene	ND	0.050	11							
Toluene	ND	0.050	н							
Ethylbenzene	ND	0.050	и							
Xylenes (total)	ND	0.050	и			•				
Surrogate: a,a,a-Trifluoratoluene	1.05		# 1° *	1.00		105	60-140			
LCS (2020027-BS1)				Prepared o	& Analyza	ed: 02/04/	02			
Benzene	0.894	0.050	mg/kg	00.1		89.4	70-130			••••
Toluene	1.08	0.050	N	1.00		108	70-130			
Ethylbenzonc	1.20	0.050	н	1.00		120	70-130			
Xylenes (total)	3. <b>5</b> l	0.050	-	3.00		117	70-130			
Surrogate: a.a.a-Trifluorotoluene	1.10		#	1.00		1/0	60-140	-		
LCS Dup (2020027-BSD1)				Prepared 4	& Analyz	ed: 02/04/	02			
Benzene	0.853	0.050	mg/kg	1.00		85.3	70-130	4.69	25	•
Toluene	1.29	0.050	-	1.00		129	70-130	17.7	25	
Ethylbenzene	1.21	0.050	-	1.00		121	70-130	0.830	25	
Xylenes (total)	3.86	0,050	*	3.00		129	70-130	9.50	25	

Surrogate: a.a.u-Trifluorotoluene

60-140

90.7



1.00

0.907



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Mccks

Reported:

02/05/02 14:01

## Total Metals by EPA 6000/7000 Series Methods - Quality Control

Analytė	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2020029 - EPA 3050B										
Blank (2020029-BLK1)				Prepared:	02/04/02	Analyzed	3: 02/05/02			
Lead	מא	2.5	mg/kg							
LCS (2020029-BS1)				Prepared:	02/04/02	Analyzet	1: 02/05/02	······································	<b>-</b>	
Lead	47.3	2.5	mg/kg	50.0		94.6	80-120			
Matrix Spike (2020029-MS1)	Sei	ırce: S20201	9-05	Prepared	: 02/04/02	Analyzeg	1: 02/05/02			
Lcad	49.8	10	mg/kg	50.0	ND	87.2	80-120		•	
Matrix Spike Dup (2020029-MSD1)	Soi	ırce: S20201	9-05	Prepared	02/04/02	Analyze	1: 02/05/02			· · · · · · · · · · · · · · · · · · ·
Lead	50.2	10	mg/kg	50.0	ND	88.0	80-120	0.800	20	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA
Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Volatile Organic Compounds by EPA Method 8260B - Quality Control Sequoia Analytical - Sacramento

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	rpd	RPD Limit	Notes
Batch 2020011 - EPA 5030B [P/T]									-	
Blank (2020011-BLK1)				Prepared &	& Analyz	ed: 02/04/	02			
Tert-butyl alcohol	ND	0.050	mg/kg							
Methyl text-butyl ether	ND	0.0050	-							
Di-isopropyl ether	ND	0.0050	•							
Ethyl tert-butyl ether	ND	0.0050	-							
Tert-amyl mothyl ether	סא	0.0050								
Surrogate: 1,2-DCA-d4	0.0411		ri ri	0.0500		82.2	60-140			
LCS (2020011-BS1)				Prepared d	& Analyz	ed: 02/04/	02			
Methyl tert-butyl other	0.0488	0.0050	mg/kg	0.0500		97.6	60-140			
Surrogate: 1,2-DCA-d4	0.0392	, , <del></del>	"	0.0500		78.4	60-140	***		
Matrix Spike (2020011-MS1)	Sor	ırce: S20201	9-03	Prepared &	& Analyz	ed: 02/04/	02 ·			
Methyl tert-butyl ether	0.0385	0.0050	mg/kg	0.0500	ND	75.8	60-140			
Surrogate: 1,2-DCA-d4	0.0366		#	0.0500		73.2	60-140			
Matrix Spike Dup (2020011-MSD1)	Sor	arce: \$20201	9-03	Prepared &	& Analyz	ed: 02/04/	02			
Methyl tert-butyl ether	0.0405	0.0050	mg/kg	0.0500	ND	79.8	60-140	5.06	25	
Surrogate: 1,2-DCA-d4	0.0397		~	0.0500		79.4	60-140	·	_4 21	
Batch 2020019 - EPA 5030В [Р/Г]										
Blank (2020019-BLK1)				Prepared &	& Analyz	ed: 02/04/	02			
Fert-butyl alcohol	ND	0.050	mg/kg	-	-					
Methyl tort-butyl other	מא	0.0050	11							
Di-isopropyl ether	ND	0.0050	ìı							
Ethyl tert-butyl ether	ND	0.0050	н							
Ferr-amyl methyl ether	ND	0.0050	10							
Surrogate: 1,2-DCA-d4	2.74		#	2.50	•	110	60-140			



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Stc. 200 Rancho Cordova CA, 95670 Project: Arco 5387, Hayward, CA Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 14:01

## Volatile Organic Compounds by EPA Method 8260B - Quality Control Sequoia Analytical - Sacramento

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%rec	%REC Limits	RPD	RPD Limit	Notes
Batch 2020019 - EPA 5030B [P/T]	<del>,</del>					***				
LCS (2020019-BS1)				Prepared	& Analyze	4: 02/04/	02			
Methyl teri-butyl ether	2.47	0.0050	nsg/kg	2.50		98.8	60-140			
Surrogate: 1,2-DCA-d4	2.76		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	2.50		110	60-140			
LCS Dup (2020019-BSD1)				Prepared	& Analyza	d: 02/04/	02			
Methyl tert-buryl ether	2.64	0.0050	mg/kg	- 2.50		106	60-140	6.65	25	
Surrogate: 1,2-DCA-d4	2.82		,- ,	2.50		113	60-140			



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Reported: 02/05/02 14:01

Project Manager: Steven Meeks

#### Notes and Definitions

HC-12 Hydrocarbox	a pattern is present in the requeste	ed fuel quantitation range 1	but does not resemble the	pattern of the requested fuel.
-------------------	--------------------------------------	------------------------------	---------------------------	--------------------------------

The RPD result exceeded the control limits; however, both percent recoveries were acceptable. Sample results for the QC batch OR-02

were accepted based on percent recoveries and completeness of QC data.

The sample was diluted due to the presence of high levels of non-target analytes resulting in elevated reporting limits. R-05

DET Analyte DETECTED


Analyte NOT DETECTED at or above the reporting limit ND

NR Not Reported

Sample results reported on a dry weight basis dry

RPD Relative Percent Difference

ARCO Facilit	Olvision 	of Allantic	Richfield (	Company LC1	hr.			Task O	rder No.	16													chain of Custod	<b>ly</b> 
ARCO engine	5 Ser 5	387		(Fi	acility) H	haywa	rd, Ca	lifornia		Project (Const	ı manaç ultanı)	ST.	وبر	Mee t	<b>&lt;</b> \$						•		Laboratory name	•
ARCO engine	Par	A 5 14	PPIC	<u></u> _			Telephor (ARCO)			Teleph (Const	one no. ultant)	716	- 43	<b>ن</b> - ي	613	Fa (C	x no. onsulta:	nt) 416	639	8 835	すら		Contract number	
Consultant na	Ter E	nui ran	Menta	Cons	ulTan	Te, In	٤,	Address (Consulta	nl) 3 164	Gala	d car	√P D	د¦باد:	# 2 <i>0</i>	o, F		•						_ Otenset, reaching	
				Matrix		Prese	rvation	40			550	ניט		щ			1/2	DV0	7,000		-7		Method of shipment	
Sample I.D.	Lab no.	Container no.	Soll	Water	Other	Ice	Acid	Sampling date	Sampling time	BTEX 602/EPA 8020	BTEVTPH 31 EPA M802/8020/1015	TPH Modified 801 Gas □ Diesel □	Oil and Greese 413.1 © 413,2 ©	TPH EPA 418.1/SMS03E	EPA 601/9010	EPA 624/8240	BILLY OXXXX BOLESCENT J	TCLP Semi	CAN METALS EPA 6010 TTLC   STLC	Lead Org /DHS   1 Lead EPA 7420/7421   1	Total Lead	MTGE by		
DP-1-35			S			×		2/1/02	pH		X			S		<b>₹</b> – }	Х				X	X	Special detection Limit/reporting	
01-1-70			\$			×		2/1/02	1124		×					-2	×				×	×	1	
DP-2-4,0			5			×		2/1/02	בסוו		×					3	×				×	×		
DP-343-5			S			<u>×</u>		2/1/02	1142		×	Ĺ				4	X				×	X	Special QA/QC	
P-4-46			S			×		21/02	1049		×					5	X				×	X		
PL-1-4.5			5			×		2/1/02	1105		Х					9	×				×	×		
PL-J-50			5			<u>×</u>		2/1/02	१०५३		×				-	77	X				×	X	Remarks	
15 <sup>7</sup> - [-140			S			×		3/√02	1336		×					20	X				X	X	MIKE	
15T-2-14,0			X			×		2/1/02	1340		×				_	9	X				×	Х	OP-1 is possible high	<
15T-3-14 <sub>10</sub>			X			_×	_	2/1/02	1345		X				-	-10	X				×	X	<del>-</del>	
5T-9-140			×			X		2/1/02	1351		X					-11	X				X	×		
																_						<u> </u>		
								<del> </del>		<u> </u>													Lab number	
														_						ا 2 لوم				
										_										_19			emit bnuorsariuT	
<u> </u>		-																					Priority Rush 1 Business Day	Ø
condition of s telinguished (	•	<u> </u>	, ,			<del></del> _	Date	<del></del>	Time	Tempe	rature r	eceivec	: 	17	a				_				Rush 2 Business Days	
lelingvished     STU     lelinguished 1		<u>S</u> 10√2	chal	en			`>/1/6; Dale	<u> </u>	1725 Time	Receiv			we		<u>_</u>	*	2/1/	02		725	<u> </u>	·	Expedited 5 Business Days	
telinquished t	oy .			<del>-</del>	- <u></u>		Date		Time	Receiv	red by					<u> </u>	)ate			Time			Standard 10 Business Days	



February 05, 2002

Steven Meeks
Delta Environmental Consultants (Rancho Cordova)
3164 Gold Camp Drive Ste. 200
Rancho Cordova, CA 95670
RE: Arco 5387, Hayward, CA / S202020

Enclosed are the results of analyses for samples received by the laboratory on 02/01/02. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Ron Chew Client Services Representative

CA ELAP Certificate Number 1624

Lito Diaz

Laboratory Director



Delta Bavironmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 13:56

#### ANALYTICAL REPORT FOR SAMPLES

	<u> </u>			
Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SP-(1,2,3,4) COMPOSITE	S202020-01	Soil	02/01/02 14:15	02/01/02 17:25
SP-(5,6,7,8) COMPOSITE	S202020-02	Soil	02/01/02 14:15	02/01/02 17:25



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported: 02/05/02 13:56

## Total Purgeable Hydrocarbons and BTEX by DHS LUFT

Acalyce	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notas
SP-(1,2,3,4) COMPOSITE (S202020-01) Soil	Sample	1: 02/01/02 1	4:15 Re	eived: 02	/01/02 17::	25	•		
Purgeable Hydrocarbons	0.66	0.50	mg/kg	ı	2020026	02/04/02	02/04/02	DHS LUFT	HC-12
Benzene	ND	0.0050	п	•		Ħ	И	•	
Toluene	0.012	0.0050	И	-	u		19	N	
Ethylbenzene	ND	0.0050	п	*	n	•	И	M	
Xylenes (total)	0.011	0.0050	10	•	ń	•	10	n	
Surrogate: a,a,a-Trifluorotoluene	· · · · · · · · · · · · · · · · · · ·	84.5 %	60-	140	п	π	,,,	F	
SP-(5,6,7,8) COMPOSITE (\$202020-02) Soil	Sample	i: 02/01/02 1	4:15 Rec	eived: 02,	/01/02 17:3	25			
Purgeable Hydrocarbons	ND	0.50	mg/kg	1	2020026	02/04/02	02/04/02	DHS LUFT	-
Benzene	ИD	0.0050	•	н	P	η	7	-	
Toluene	ND	0.0050	M	PP .	π	,		•	
Ethylbenzene	ND	0.0050	4	*	H	n	**	17	
Xylenes (total)	ND	0.0050	17	ŧı	11	17	11	4	
Surrogate: a,a,a-Trifluorotoluene		48.2 %	60-1	40	*	ø	n	,,	S-04



Delta Environmental Consultants (Rancho Cordova 3164 Gold Camp Drive Ste. 200

Rancho Cordova CA, 95670

Project Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA Project Manager: Steven Meeks Reported: 02/05/02 13:56

## Total Metals by EPA 6000/7000 Series Methods

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
SP-(1,2,3,4) COMPOSITE (S202020-01) Sail	Sample	l: 02/01/02 1	4:15 Re	ceived: 02	/01/02 17:	25		•	•
Lead	17	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	-
SP-(5,6,7,8) COMPOSITE (S202020-02) Soil	Sampleo	i: 02/01/02 1	4:15 Re	ceived: 02	/01/02 17:	25			
Lead	660	10	mg/kg	4	2020029	02/04/02	02/05/02	EPA 6010B	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670 Project Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA. Project Manager: Steven Mecks Reported: 02/05/02 13:56

## Total Purgeable Hydrocarbons and BTEX by DHS LUFT - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2020026 - EPA 5030B (P/T)			************							
Blank (2020026-BLK1)				Prepared	& Analyze	d: 02/04/	02			
Purgeable Hydrocarbons	ND	0.50	mg/kg	****						
Benzene	ND	0.0050	И							
Toluene	ND	0.0050	•							
Ethylbenzene	ND	0.0050	•					•		
Xylenes (total)	ND	0.0050	•							
Surrogate: a, a, a-Trifluorotoluene	0.0179		77	0.0200		89.5	60-140			
LCS (2020026-BS1)				Prepared	& Analyze	ed: 02/04/	02			
Benzene	0.0170	0.0050	mg/kg	0.0200		85.0	70-130			
Toluene	0.0155	0.0050	-	0.0200		77 <i>5</i>	70-130			
Ednylbenzene	0.0170	0.0050	<b>.</b> -	0.0200		85.0	70-130			
Xylenes (total)	0.0480	0.0050	•	0.0600		80.0	70-130			
Surrogate: a.a.a-Trifluorotoluene	0.0157		H	0.0200		78.5	60-140			
LCS Dup (2020026-BSD1)				Prepared	& Analyze	d: 02/04/	02			
Benzene	0.0193	0.0050	mg/kg	0.0200		96.5	70-130	12.7	25	
Toluene	0.0205	0.0050	-	0.0200		102	70-130	27.8	25	QR-0
Ethylbenzene	0.0200	0.0050	71	0.0200		100	70-130	16.2	25	
Xylenes (total)	0.0580	0.0050	n	0.0600		96.7	70-130	18.9	25	•
Surrogate: a.a.a-Trifluorotoluene	0.0169		*	0.0200		84.5	60-140			



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Ste. 200 Rancho Cordova CA, 95670

Project Arco 5387, Hayward, CA

Project Number 5387, Hayward, CA

Reported:

Project Manager: Steven Meeks

02/05/02 13:56

## Total Metals by EPA 6000/7000 Series Methods - Quality Control Sequoia Analytical - Sacramento

A-al-m	Danila	Reporting Limit	T1-:-	Spike L	Source	WDEC	%REC Limits	RPD	RFD Limit	Notes
Analyte	Result	Limit	Unio	Level	Result	%REC	Limite	KPD	LARGE	(NOBES
Batch 2020029 - EPA 3050B			- 1,							
Blank (2020029-BLK1)				Prepared:	02/04/02	Analyzed	1: 02/05/02			
Lead	ND	2.5	mg/kg							
LCS (2020029-BS1)				Prepared:	02/04/02	Analyzed	l: 02/05/02			*
Lead	47.3	2.5	mg/kg	50.0		94.6	80-120			
Matrix Spike (2020029-MS1)	So:	Source: S202019-05 Pro				Analyzed				
Lead	49.8	10	mg/kg	50.0	ND	87.2	80-120			
Matrix Spike Dup (2020029-MSD1)	Sou	ırce: S20201	9-05	Prepared:	02/04/02	Analyzed	1: 02/05/02			
Lead	50.2	10	mg/kg	50.0	ND	88.0	80-120	0.800	20	



Delta Environmental Consultants (Rancho Cordova

3164 Gold Camp Drive Stc. 200

Rancho Cordova CA, 95670

Project: Arco 5387, Hayward, CA

Project Number: 5387, Hayward, CA

Project Manager: Steven Meeks

Reported:

02/05/02 13:56

#### Notes and Definitions

HC-12	Hydrocarbon pattern is	present in the requested fuel	nuantitation range but does no	t resemble the pattern of the requested fuel.
-------	------------------------	-------------------------------	--------------------------------	---

QR-02 The RPD result exceeded the control limits; however, both percent recoveries were acceptable. Sample results for the QC batch

were accepted based on percent recoveries and completeness of QC data.

S-04 The surrogate recovery for this sample is outside control limits due to interference from the sample matrix.

DET Analym DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

				pany (				Task O	rder No.	74						_							hain of Custod	τ,
ARCO Facili	California   Project manager   STEUE MEEK S     Telephone no.   Telephone no. 916-536-2613   Fa (Consultant)   Project manager   STEUE MEEK S     Telephone no. 916-536-2613   Fa (Consultant)   Project manager   STEUE MEEK S     Telephone no. 916-536-2613   Telephone no. 916-												Laboratory neme											
ACO engin	Pa	u   <	uppie	:			Telaphor (ABCO)	16 NO.		Teleph (Consu	one no. Atent)	916-	53	·-2(	13	(Co	( no. Maultai	<sub>nt)</sub> 91(	, 63	4 4	385		Contract number	
onsultent n	De BITTE	ITA E	Paliny	WENT.	ممک ا	SULTAN	Ts, In	C. (Consulta	nt) 3164	واها	Car	4~	Drie	e 6	uiTe	200	, R	anch	0 L	ordo	Va			
	1			Matrix			rvation				1	7		i	1			Mai VOAD			Lead		Method of shipment	
Sample I.D.	Lab no.	Container no.	Soll	Water	Other	ice	Açid	Sampling date	Sampling time	BTEX 902/EPA 8020	BTEXTIPH 9 EPA MG02/B0239015	TPH Modified 8015 Gas □ Dieset □	Oll and Grease 413.1 [] 615.2 []	TPH EPA 416.1/SM503E	EPA 601/8010	EPA 6248240	0.258/925) 1643	TCLP Semi Metals UOA VOA	CAMMEDLS BY BOOTOD TILCI STICI	Lead Ong /DHS C Lead EPA 7420/7421 C	Total Le			
P-1			×			×		2/1/02	1415		X										X		Special detection Limit/reporting	•
6P-2			X			×		2/1/02	1415		X			3	6	208	)()_	1			×		Composite 4; )	
≤P-3_			×			×		2/1/02		ļ	X										X	/_	,•	
SP-4			X			×		2/1/02		ļ	X	<u>/_</u>	<u></u>			<u></u>					<u>X'</u>		Special QA/QC	
sr-5			X			×		2/1/62		ļ	×										X		Composite	
sP-6			X			X		2/1/02		ļ <u>.</u>	X		_								X		4:1	
≤P-7			×			X		2/1/02	· · · · · · · · · · · · · · · · · · ·	<u> </u>	X			þ٤	Box	XX	双	<u> </u>	<b>}</b> _		X		Remarks	
6P-8		<del></del> -	×			×		2/1/02	1415	<u> </u>	X						<u> </u>				<u> </u>			
										<del>                                     </del>		<u></u>		,										
										<del> </del>				_										
									*												, t.	_		
					_		<del></del>		<del></del>								,						Lab number	<u></u>
		_																						
																	:			2	210		Tumaround time	
																					10		Priority Rush 1 Business Day	X
condition of		1	<u> </u>				D.L	•	Time	Tempe Recel	rature o	eceive	حا	4/1									Rush 2 Business Days	
	W B	valu	Asle	V)			Date 2/1/0	) <b>1</b>	1726	_		100	YYY)		_	. 2	11/	02	1	726	<b>,</b>		Expedited	
hedelupnilef "	l b <del>y</del>			//			Date		Time	Recelv	ved bý										,	·	6 Business Days Standard	
Pelinquished	by			······		•	Date		Time	Receiv	ed by	-				C	ate			Time			10 Susiness Days	