

Phone: 510-886-7706 ◆ Fax: 510-886-4131 3137 Castro Valley Blud., #209, Castro Valley, California 94546-3244

FACSIMILE TRANSMITTAL SHEET

DATE SENT:	7/31/96	
TO BE DELIVER	RD TO: Susan	
FACSIMILE NU	MBER: 510-337-9335	
SENT BY:	Jonathan Bamer	
NUMBER OF PA	AGES TO FOLLOW THIS COVER SHEET:	5
SPECIAL INSTR	EUCTIONS:	
Susan;		
As promised, he	re is a copy of our safety plan for 2856 Helen St.,	, Oakland, CA.
Please call me A	SAP to let me know you have received this and	I if there is anything
further needed.		
	Thank you.	

Please call (510) 886-7706 if there is any problems with this transmission.

BAMER CONSTR. CO

BAMER CONSTRUCTION CO. HEALTH & SAFETY PLAN

x 510 8864131

3137 Castro Valley Blud., #209, Castro Valley, California 94546-3244 Phone: 510-886-7706 ♦ Fax: 510-886-4131

FOR: 2856 Helen Street, Oakland, CA

ATTENTION: SITE FOREMAN & SAFETY DIRECTOR,

Jonathan Bamer, Lic. #452888

R, B, and Haz-Certified UST Removal and Installation

IMPORTANT NUMBERS:

FIRE DEPARTMENT:

911

 HOSPITAL: (510) 655-4000 -- SUMMIT MEDICAL CENTER (Take 32nd St. East to San Pablo Rue.-San Pablo Rue. North to 34th St. - 34th St. East to corner of Broadway-Rt. on Broadway)

SAFETY:

FIRE AND EXPLOSIVE HAZARDS for a SAFE WORK PLACE

- Post appropriate warnings (signs)
- Use caution tape and barricades to keep others clear of site or fence off area entirely
- On site fire extinguisher
- Meetings with employees
 - Remind employees NOT to lean over excavation
 - Remind employees where extinguisher is
 - Advise employees of nearest phone
 - Advise employees of effects of gas fumes
 - Be aware of signs of heat exhaustion
- Inert tank before moving or hacksawing lines.
- Use 15 lbs. of dry ice per 1,000 gallon tank capacity.
- Allow sufficient time for dry ice to evacuate flammable gasses from tank. NOTE: Be cautious of low areas such as excavations.

ENUIRONMENTAL:

WASHING TANKS
SOIL SAMPLING

BAMER CONSTR. CO

PURGING:

BONDING and GROUNDING

Make sure all tools and equipment are properly grounded

HAZARDS ASSOCIATED WITH OPERATING EQUIPMENT TEMPORARY - SLUDGE REGENERATES FLAMMABLE VAPORS

INERTING:

EXCAUATING

- Use 15 lbs of dry ice per 1,000 gallons of tank capacity to inert. Allow time for fumes to dissipate.
- Do not move tanks or cut lines before inerting.
- Cut all lines with hacksaw

TRANSPORTING

LIFTING TANKS:

LIFTING EQUIPMENT IS APPROPRIATE FOR TANK BEING LIFTED DO NOT DRAG TANKS

 Tanks over 5,000 gallon capacity are to be loaded with a crane.

STAY AWARE OF LIFTING EQUIPMENTS MOVEMENTS

FXCAUATION SAFETY:

- Stand back 2' from excavation
- If at all possible, DO NOT enter excavation.
- For excavations over 5', use shoring and have ladder before entering excavation.
- Observe soil conditions for possible cave-ins. Keep men and equipment away from edges of excavation.

SOIL SAMPLING:

 Have backhoe remove soil sample. DO NOT lean over excavation site or enter excavation to take soil sample.

DOCUMENTS, RECORDS, AND REPORTS:

HISTORICAL RECORDS

 Keep records of depth of soll sample by numbering and numbering locations.

ENUIRONMENTAL REPORTS

- Look at tank for general condition and note.
- Take pictures.

MONITORING - 02 AND L.E.L.

WARM UP AND ZERO EQUIPMENT MONITOR ROUTINELY FOR FLAMMABLE DAPORS

- Use meter to monitor L.E.L.
- Have tank hauler bring L.E.L. meter.

CUTTING OPERATIONS:

NON SPARKING / NO FLAME

Use hacksaw or pipe cutter. DO NOT use sawsall.

WASHING OPERATIONS:

BONDING AND GROUNDING **URCUUM TRUCK**

Make sure truck is properly grounded.

SAFE WORK PLACE:

SOURCES OF IGNITION

02 - FUEL - IGNITION

- No Smoking
- Electrical and Internal combustion equipment "EXPLOSION PROOF"
- Shutdown open flame and spark producing equipment
- Use only non sparking tools for working on tanks
- Control static electricity

PREVENTION

- Have meeting with all employees to determine expectations and possible problems with job site.
- When traffic is a concern, post appropriate signs and if necessary post a flag man.


SECURE AREA FROM UNAUTHORIZED ENTRY LOCATE ALL UTILITIES, GAS, AND WATER LINES HAVE KNOWLEDGE AND UNDERSTANDING OF CONTENTS OF TANK

Always Inert tank and test for L.E.L. before moving tank.

SRFETY MANUAL ON SITE

l	her	eby acknowledge that I have read
•	and will comply with the si	te health and safety plan.
DATE		SIGNATURE

Bamer Construction Co. 3137 Castro Dalley Blud., #209, Castro Dalley, California 94546-3244 Phone: 510-886-7706 + Fax: 510-886-4131



DIATEO