



3315 Almaden Expressway, Suite 34

San Jose, CA 95118 Phone: (408) 264-7723 Fax: (408) 264-2435

TRANSMITTAL

TO: Ms. Susan Hugo Alameda County Health Care Services 80 Swan Way Room 200

Oakland, California 94621

DATE: September 28, 1992
PROJECT NUMBER: 60000.13
SUBJECT: Final - Second Quarter 1992
Quarterly Groundwater Monitoring at ARCO Station 771, 899 Rincon Avenue, Livermore, California.

FROM: Erin McLucas TITLE: Staff Geologist

WE ARE SENDING YOU:

COPIES	DATED	DESCRIPTION
1	9/28/92	Final - Second Quarter 1992, Groundwater Monitoring at the above subject site.
THESE A	RE TRANSMIT	TED as checked below:
[] For 1	review and comm	ent [] Approved as submitted [] Resubmit copies for approval
[X] As :	requested	[] Approved as noted [] Submit copies for distribution
[] For a	approval	[] Return for corrections [] Return corrected prints
[] For :	our files	
REMAR	Mr. M Mr. E Ms. D	C.C. Winsor, ARCO Products Company Iichael Whelan, ARCO Products Company ddy So, CRWQCB, San Francisco Bay Region anielle Stefani, Livermore Fire Department oel Coffman, RESNA Industries Inc.

Copies: 1 to RESNA project file no. 60000.13



A RESNA Company



3315 Almaden Expressway, Suite 34 San Jose, CA 95118 Phone: (408) 264-7723

Fax: (408) 264-2435

LETTER REPORT QUARTERLY GROUNDWATER MONITORING Second Quarter 1992 at ARCO Station 771 899 Rincon Avenue Livermore, California

60000.13





3315 Almaden Expressway, Suite 34

San Jose, CA 95118 Phone: (408) 264-7723 Fax: (408) 264-2435



Mr. Michael Whelan ARCO Products Company P.O. Box 5811 San Mateo, California 94402

Subject:

Second Quarter 1992 Groundwater Monitoring Report for ARCO Station 771,

899 Rincon Avenue, Livermore, California.

Mr. Whelan:

As requested by ARCO Products Company (ARCO), this letter report summarizes the results of second quarter 1992 groundwater monitoring performed by ARCO's contractor, EMCON Associates (EMCON) of San Jose, California, at the above-referenced site. The objectives of this quarterly groundwater monitoring are to evaluate changes in the groundwater flow direction and gradient, and changes in concentrations of petroleum hydrocarbons in the local groundwater associated with the former gasoline-storage tanks and former waste-oil tank at the site. The field work and laboratory analyses of groundwater samples during this quarter were performed under the direction of EMCON and included measuring depths to groundwater, subjectively analyzing groundwater for the presence of petroleum product, collecting groundwater samples from the wells for laboratory analyses, and directing a State-certified laboratory to analyze the groundwater samples. procedures and acquisition of field data were performed under the direction of EMCON; evaluation and warrant of their field data and field protocols is beyond RESNA Industries Inc.'s (RESNA's) scope of work. RESNA's scope of work was limited to interpretation of field and laboratory analytical data, which included evaluating trends in reported hydrocarbon concentrations in the local groundwater, the groundwater gradient, and direction of groundwater flow beneath the site.

The operating ARCO Station 771 is located on the southwestern corner of the intersection of Rincon Avenue and Pine Street in Livermore, California, as shown on the Site Vicinity Map, Plate 1.

Prior to this quarterly monitoring period, RESNA (formerly Applied GeoSystems [AGS]) and Roux Associates of Concord, California, performed environmental assessments and investigations related to the removal and replacement of four underground gasoline-storage tanks (USTs) at the site. In February 1990, RESNA performed an environmental site assessment (AGS, June 1990), which included the drilling of three borings (B-1 through B-3). In December 1990, RESNA performed a supplemental subsurface investigation which included the drilling of three soil borings (B-4 through B-6) and installation of three monitoring wells, MW-1, MW-2, and MW-3 (AGS, April 1991). In January 1991, RESNA began quarterly monitoring of the onsite monitoring wells. In July 1991, RESNA performed an additional subsurface investigation which included the drilling of five soil borings (B-7 through B-11) and installation of four monitoring wells MW-4 through MW-7 (RESNA, October 1991). The results of these environmental assessments and investigations are presented in the reports listed in the References Cited section located at the end of this letter report. UST removal and replacement began in December 1991. In April 1992, RESNA installed groundwater recovery well RW-1, vapor extraction well VW-1, and one offsite groundwater monitoring well MW-11, as a part of an additional onsite and initial offsite subsurface investigation. Additional offsite groundwater monitoring wells (MW-8 through MW-10) will be installed upon gaining offsite access. Results of this investigation will be discussed in a forthcoming report. RESNA is proceeding with design and permitting of a remediation system to be installed at the site. The locations of soil borings, groundwater monitoring wells, and other pertinent site features are shown on the Generalized Site Plan, Plate 2.

Groundwater Sampling and Gradient Evaluation

Depth to water measurements (DTW) were performed by EMCON field personnel on April 24, May 20, and June 12, 1992. Quarterly sampling was performed by EMCON field personnel on June 12, 1992. The results of EMCON's field work on the site, including DTW measurements and subjective analysis for the presence of product in the groundwater in MW-1 through MW-7, MW-11 and RW-1 are presented on EMCON's field report sheets and EMCON's Summary of Groundwater Monitoring Data. These data are included in Appendix A.

The DTW levels, wellhead elevations, groundwater elevations, and subjective observations of product in the groundwater from MW-1 through MW-7, and MW-11 for this quarter and previous quarterly groundwater monitorings at the site are summarized in Table 1, Cumulative Groundwater Monitoring Data. Groundwater monitoring well MW-1 was not accessible during the April monitoring because it was covered by plastic and the pile of soil cuttings generated during drilling activities. Wellhead elevations were resurveyed on May 8, 1992 due to changes in well casing elevations caused by the previous construction on the



site. Groundwater elevations in monitoring wells MW-1 through MW-7 decreased between 0.03 and 1.68 feet between April 24, and June 12, 1992. Groundwater elevations in monitoring well MW-11 and recovery well RW-1 increased 0.58 feet and 0.13 feet respectively in the same time period. The groundwater gradients interpreted from the April, May and June 1992 monitorings ranged from 0.05 to 0.08 with flow directions to the north-northwest. The groundwater gradients and flow directions are shown on Plates 3 through 5, Groundwater Gradient Maps. EMCON reported floating product in well MW-1 in June; no evidence of product or sheen was observed in the other wells by EMCON's field personnel during this quarter (EMCON field report sheets, Appendix A).

Groundwater monitoring wells MW-2 through MW-7 were purged and sampled by EMCON field personnel on June 12, 1992; well MW-1 was not sampled because it contained floating product. The purge water was removed from the site by a licensed hazardous waste hauler.

Laboratory Methods and Results

Under the direction of EMCON, water samples collected from the wells were analyzed by Columbia Analytical Services, Inc., located in San Jose, California (Hazardous Waste Testing Laboratory Certification No. 1426). The water samples from MW-2 through MW-7 were analyzed for total petroleum hydrocarbons as gasoline (TPHg) and benzene, toluene, ethylbenzene, and total xylenes (BTEX) using modified Environmental Protection Agency (EPA) Methods 5030/8020. Concentrations of TPHg and benzene in the groundwater are shown on Plate 6, TPHg Concentrations in Groundwater and Plate 7, Benzene Concentrations in Groundwater. Well MW-6, nearest downgradient well from the former waste-oil tank, was also analyzed for total petroleum hydrocarbons as diesel (TPHd) and total oil and grease (TOG) using EPA Methods 3510 and 5520C/5520F-IR, respectively. The Chain of Custody Records and Laboratory Analysis Reports are attached in Appendix A. Results of these and previous water analyses are summarized in Table 2, Cumulative Results of Laboratory Analyses of Groundwater--TPHg, TPHd, BTEX, and TOG.

Results of this quarter's groundwater monitoring indicate:

- o TPHg was detected in groundwater samples from MW-2 through MW-7 and RW-1 at concentrations ranging from 280 parts per billion (ppb) to 110,000 ppb. The concentration of TPHg in MW-11 was nondetectable (less that 50 ppb);
- o Benzene was detected in groundwater samples from MW-2, MW-4 through MW-7, and RW-1 at concentrations ranging from 480 ppb to 8,900 ppb. Concentrations of benzene were nondetectable (<0.5 ppb) in MW-3 and MW-11; Benzene



concentrations exceeded the State Maximum Contaminant Level (MCL) in all wells except MW-3 and MW-11.

- Toluene, ethylbenzene, and total xylenes (TEX) were detected in groundwater samples from MW-2, MW-4 through MW-7, and RW-1 at concentrations ranging from 17 ppb to 16,000 ppb; TEX were nondetectable (<0.5 ppb) in MW-11 and near nondetectable (less than 2.1 ppb) in MW-3.
- Lower boiling point fuel mixture quantified as TPHd (chromatograms included in Appendix A) was detected in the groundwater sample from MW-6 at a concentration of 1,100 ppb. These results appear to actually be within the weathered gasoline range. According to ARCO, diesel has never been stored at this site.
- TOG was detected in the groundwater sample from MW-6 at a concentration of 1.2 parts per million (ppm).

The following is a general summary of changes in the concentrations of hydrocarbon constituents in the groundwater from wells MW-2 through MW-7 since the last quarterly monitoring. Because RW-1 and MW-11 were constructed in April 1992, trends have not been established for the groundwater in these wells. Concentrations of TPHg and total xylenes decreased in monitoring wells MW-2 through MW-7 since the last quarterly monitoring. Benzene and toluene decreased in wells MW-3 through MW-7; ethylbenzene decreased in wells MW-2 through MW-4 and MW-6. Generally, the petroleum hydrocarbon concentrations decreased this quarter. This may be a seasonal effect due to an overall drop in groundwater elevations, or an effect caused by the use of free product skimmers.

Product Recovery

Floating product was measured and removed on a monthly basis, as summarized in Table 3, Approximate Cumulative Product Recovered. In January 1992, Horner EZY Skimmers were installed in wells MW-1, MW-2, and MW-5, as a method of an interim remediation at the site. The total 1992 year-to-date product recovered is 0.29 gallons, of which 93 percent was removed from well MW-1 and the remaining 7 percent from wells MW-2 and MW-5. The total product recovered at the site is 3.06 gallons for 1991 and 1992 combined.

Conclusions

The groundwater at the site has been impacted by petroleum hydrocarbons. The groundwater sample results from recently installed offsite well MW-11 showed levels of TPHg and BTEX to be nondetectable. These constituents have been delineated to the



north. The extent of the petroleum hydrocarbons has not yet been defined to the south, east or west. Attempts to gain access to install wells to delineate in these directions are ongoing.

Construction Plans and Specifications for an Interim Vapor Extraction System were issued for Bid on September 11, 1992. The preliminary date for construction startup is November 9, 1992.

RESNA also recommends that copies of this letter report be forwarded to:

Ms. Susan Hugo
Alameda County Health Care Services Agency
Department of Environmental Health
80 Swan Way, Room 200
Oakland, California 94621

Mr. Eddy So Regional Water Quality Control Board San Francisco Bay Region 2101 Webster Street, Suite 500 Oakland, California 94612

Ms. Danielle Stefani
Livermore Fire Department
4550 East Avenue
Livermore, California 94550



If you have any questions or comments, please call us at (408) 264-7723.

Sincerely, RESNA Industries Inc.

Erin McLucas Staff Geologist

Joan E. Tiernan Registered Civil Engineer No. 044600

cc: W. C. Winsor, ARCO Product Company

Enclosures: References

Plate 1, Site Vicinity Map

Plate 2, Generalized Site Plan

Plate 3, Groundwater Gradient Map, April 24, 1992

Plate 4, Groundwater Gradient Map, May 20, 1992

Plate 5, Groundwater Gradient Map, June 12, 1992

Plate 6, TPHg Concentrations in Groundwater, June 12, 1992

Plate 7, Benzene Concentrations in Groundwater, June 12, 1992

Table 1, Cumulative Groundwater Monitoring Data

Table 2, Cumulative Results of Laboratory Analyses of Groundwater Samples-TPHg, TPHd, BTEX, and TOG

Table 3, Approximate Cumulative Product Recovered

Appendix A: EMCON's Depth to Water/Floating Product Survey Form (2),

Certified Analytical Reports with Chain-of-Custody,

Water Sample Field Data Sheets,

Monitoring Well Purge Water Disposal Form, and

Chromatograms and Maxima 820 Custom Reports for TPHd

Analyses




REFERENCES CITED

- Applied GeoSystems, June 22, 1990. <u>Limited Subsurface Environmental Assessment, ARCO Station No. 771, Livermore, California</u>. AGS 60000-1.
- California Department of Health Services, Office of Drinking Water, October 24, 1990, Summary of Drinking Water Standards.
- RESNA/Applied Geosystems, April 12, 1991. <u>Supplemental Subsurface Investigation at ARCO Station No. 771, Livermore, California</u>. AGS 60000.
- RESNA/Applied GeoSystems, July 12, 1991. <u>Letter Report Quarterly Ground-Water Monitoring Second Quarter 1991 at ARCO Station 771, 899 Rincon Avenue</u>, Livermore, California. AGS 60000.05
- RESNA, October 17, 1991. Report on Additional Subsurface Investigation at ARCO Station 771, 899 Rincon Avenue, Livermore, California. 60000.06
- RESNA, November 21, 1991. <u>Letter Report Quarterly Ground-Water Monitoring Third</u>

 <u>Quarter 1991 at ARCO Station 771, 899 Rincon Avenue, Livermore, California.</u>

 60000.05
- RESNA, April 7, 1992. <u>Letter Report Quarterly Groundwater Monitoring Fourth Quarter</u> 1991 at ARCO Station 771, 899 Rincon Avenue, Livermore, California. 60000.05
- RESNA, May 1, 1992. <u>Letter Report Quarterly Groundwater Monitoring First Quarter</u> 1992 at ARCO Station 771, 899 Rincon Avenue, Livermore, California. 60000.05
- Roux, July 10, 1992. <u>Underground Storage Tank Removal and Soil Sampling, ARCO Facility No. 771, 899 Rincon Avenue, Livermore, California.</u> A135W01



Base: U.S. Jeological Survey 7,5-Minute Quadrangles Livermore, California. Photorevised 1980

. = = = \n

i = Site Location

Approximate Scale
2000 1000 0 2000 ±000


THE SAME NOTICE ASSESSED TO AS

SITE VICINITY MAP ARCO Station 771 899 Rincon Avenue Livermore, California PLATE

1

PROJECT

60000.13








PROJECT 60000.13

GENERALIZED SITE PLAN ARCO Station 771 899 Rincon Avenue Livermore, California

2










PINE STREET



EXPLANATION

10,000 Line of equal concentration of TPHg in groundwater in parts per billion (ppb)

= Concentration of TPHg in groundwater in ppb, June 12, 1992 110,000

= Monitoring well (RESNA, 1991 and 1992) MW−11

= Recovery well (RESNA, April 1992) RW-1

Vapor extraction well (RESNA, April 1992)

T4

= Underground gasoline-storage tank

NS Not sampled, floating product

= Existing underground gasoline—storage tank Approximate Scale 30 60 30 15 0 feet Source: Surveyed by John Koch, Licensed Land Surveyor.




PROJECT 60000.13 TPHg CONCENTRATIONS IN GROUNDWATER **ARCO Station 771** 899 Rincon Avenue Livermore, California

PLATE

6

PINE STREET



EXPLANATION

0000 = Line of equal concentration of benzene in groundwater in parts per billion (ppb)

= Concentration of benzene in groundwater in ppb, 8900

June 12, 1992

= Monitoring well (RESNA, 1991 and 1992) MW-11

= Recovery well (RESNA, April 1992)

Vapor extraction well (RESNA, April 1992)

= Underground gasoline—storage tank

N5 = Not sampled, floating product

= Existing underground gasoline-storage tank T-4 Approximate Scale 60 30 30 15 0 feet

Source: Surveyed by John Koch, Licensed Land Surveyor.



Working to Restore Nature

PROJECT 60000,13 BENZENE CONCENTRATIONS IN GROUNDWATER ARCO Station 771 899 Rincon Avenue Livermore, California

PLATE

7

TABLE 1 CUMULATIVE GROUNDWATER MONITORING DATA ARCO Station 771 Livermore, California (Page 1 of 4)

<u>Well</u> Date	Well Elevation	Depth-to- Water	Water Elevation	Floating Product	
MW-1					
01-15-91	451.80**	32.77	419.03	Sheen	
02-27-91		32.23	419.57	None	
03-20-91		27.38	424.42	Sheen	
04-10-91		26.49	425.31	None	
05-20-91	451.80***	NM	NM	Sheen	
06-20-91		33.95	417.85	Sheen	
07-25-91		36.59*	415.21*	0.10	
08-13-91		37.72*	414.08*	0.20	
09-12-91		39.25*	412.55*	0.23	
10-30-91		39.14*	412.66*	0.20	
11-13-91		Dry	Dry	None	
12-26-91		39.30*	412.50	0.01	
01-18-92		37.81**	NC	Skimmer	
02-21-92	Well i	naccessible due to c	onstruction		
03-31-92		31.90**	NC	Skimmer	
04-24-92	451.42**** Well i	naccessible due to o	onstruction		
05-20-92		33.00	418.42	Skimmer	
06-12-92		33.25	418.17	0.02	

MW-2					
01-15-91	449.52**	30.89*	418.63*	0.16	
02-27-91		29.11*	420.41*	0.02	
03-20-91		24.57*	424.95*	0.02	
04-10-91		22.85*	426.67*	0.05	
05-20-91	449.51***	NM	NM	NM	
06-20-91		31.42*	418.09*	0.15	
07-25-91		33.69*	415.82*	0.49	
08-13-91		34.80*	414.71*	0.47	
09-12-91		36.39*	413.12*	0.45	
10-30-91		Dry	Dry	None	
11-13-91		Dry	Dry	None	
12-26-91		36.45	413.06	Sheen	
01-18-92	Well i	naccessible due to c			
02-21-92		26.27**	NC	Skimmer	
03-31-92		28.85**	NC	Skimmer	
04-24-92	449.51***	30.95	418.56	Skimmer	
05-20-92		30.69	418.82	Skimmer	
06-12-92		31.25	418.26	None	
MW-3		•			
01-15-91	450.29**	32.34	417.95	None	
02-27-91		31. 7 8	418.51	None	
03-20-91		27.74	422.55	None	

See notes on Page 4 of 4.



TABLE 1
CUMULATIVE GROUNDWATER MONITORING DATA
ARCO Station 771
Livermore, California
(Page 2 of 4)

Well Date	Well Elevation	Depth-to- Water	Water Elevation	Floating Product	
			·-	· · · · · · · · · · · · · · · · · · ·	
<u>MW-3</u>					
04-10-91		25.05	425.24	None	
05-20-91	450.28***	27.06	423.22	None	
06-20-91		32.35	417.93	None	
07-25-91		35.02	415.26	None	
08-13-91		36.50	413.78	None	
09-12-91		38.47	413.81	None	
10-30-91		Dry	Dry	None	
11-13-91		D ry	Dry	None	
12-26-91		38.53	411.75	None	
01-18-92	Well i	naccessible due to c	onstruction		
02-21-92	Well i	naccessible due to c	onstruction		
03-31-92		30.61	NC	None	
04-24-92	450.28****	32.83	417.45	None	
05-20-92		33.85	416.43	None	
06-12-92		34.51	415.77	None	
<u>MW-4</u>					
07-25-91	451.56***	36.07	415.49	None	
08-13-91		37.54	414.02	None	
09-12-91		38.73	412.83	None	
10-10-91		39.90	411.66	None	
11-13-91		40.56	411.00	None	
12-26-91		38.78	412.78	None	
01-18-92		38.71	NC	None	
02-21-92		31.91	NC	None	
03-31-92		30.36	NC	None	
04-24-92	450.99****	32.65	418.34	None	
05-20-92	,	32.62	418.37	None	
06-12-92		32.73	418.26	None	
00-12-72		52.75	,20,20		
MW-5					
07-25-91	451.41***	36.67	414.74	Sheen	
08-13-91	IDAITA	37.98*	413.43*	0.01	
09-12-91		39.01*	412.40*	0.05	
10-30-91		38.28	412.13	Sheen	
11-13-91		39.24	412.17	Sheen	
12-26-91		39.11	412.30	Sheen	
01-18-92		38.15**	NC	Skimmer	
02-21-92		30.59**	NC	Skimmer	
03-18-92		30.84**	NC	Skimmer	
04-24-92	451.40****	33.00	418.40	Skimmer	
05-20-92	7J1.4U	32.86	418.54	Skimmer	
06-12-92		33.03	418.37	None	
UU=14=74		CD.CC	410-01		

See notes on Page 4 of 4.



TABLE 1 CUMULATIVE GROUNDWATER MONITORING DATA ARCO Station 771 Livermore, California (Page 3 of 4)

Well Date	Well Elevation	Depth-to- Water	Water Elevation	Floating Product	
MW-6					
07-25-91	451.38***	37.68	413.70	None	
08-13-91		39.17	412.21	None	
09-12-91		41.14	410.24	None	
10-30-91		42.10	409.28	None	
11-13-91		41.45	409.93	None	
12-26-91		41.23	410.15	None	
01-18-92		38.23	NC	None	
02-21-92		35.21	NC NC	None	
03-31-92		32.26	NC	None	
04-24-92	451.37****	33.24	418.13	None	
05-20-92		33.14	418.23	None	
06-12-92		33.43	417.94	None	
<u>MW-7</u>					
07-25-91	450.65***	34.88	415.77	Sheen	
08-13-91		36.17	414.48	None	
09-12-91		37.81	412.84	None	
10-30-91		38.50	412.15	None	
11-13-91		38.31	412.34	None	
12-26-91		37.90	412.75	None	
01-18-92	Well i	naccessible due to o			
02-21-92		31.50	NC	None	
03-31-92		29.40	NC	None	
04-24-92	450.63****	32.14	418.49	None	
05-20-92		32.51	418.12	None	
06-12-92		32.45	418.18	None	
MW-11					
04-24-92	448.02****	35.06	412.96	None	
05-20-92		34.10	413.92	None	
06-12-92		34.48	413.54	None	
<u>RW-1</u>					
04-24-92	451.44****	32.85	418.59	None	
05-20-92		32.60	418.84	None	
06-12-92		32.72	418.72	None	

See notes on Page 4 of 4,



TABLE 1 CUMULATIVE GROUNDWATER MONITORING DATA ARCO Station 771 Livermore, California (Page 4 of 4)

Measurements in feet.

- * = Floating product present in well; calculated DTW when floating product is present is calculated using the attached protocol (Appendix A).
- ** = Surveyed by Ron Archer, Civil Engineer, in January 1991.
- *** = Surveyed by John Koch, Licensed Land Surveyor, in July 1991.

NM = Not measured (instrument failure-interface probe).

The static water level in each well that was suspected to contain floating product was measured with an ORS® interface probe; this instrument is accurate to the nearest 0.01 foot. The probe contains two different sensor units, one for detecting the liquid/air interface, and one for distinguishing between water and hydrocarbon. The thickness of the floating product and the groundwater depths were recorded. The recorded thickness of the floating product was then multiplied by 0.80 to obtain an approximate value for the displacement of water by the floating product. This approximate displacement value is then subtracted from the measured depth to water to obtain a calculated depth to water. These calculated groundwater depths were subtracted from wellhead elevations to calculate the differences in groundwater elevations.

NC = Not calculated; wellhead elevations may no longer be correct due to construction activities related to the removal and replacement of underground storage tanks. Wellhead elevations will be resurveyed in April 1992.

**** = Surveyed by John Koch, Licensed Land Surveyor, in May 1992



TABLE 2
CUMULATIVE RESULTS OF LABORATORY ANALYSES OF GROUNDWATER - TPHg, TPHd, BTEX, and TOG
ARCO Station 771
Livermore, California
(Page 1 of 2)

Sample	ТРНg	В	T	E	x	TPHd	TOG	
MW-1			-					
01-15-91	No	ot sampled—she	een					
04-10-91	98,000	11,000	18,000	2,800	20,000	NA	NA	
07-25-91	Not san	npled—floating	product					
10-30-91	Not san	pled-floating	product					
03-31-92		npled-floating						
06-12-92	Not san	npled-floating	product	-				
MW-2								
01-15-91	Not san	pled-floating	product					
04-10-91	Not san	pled-floating	product		•			
07-25-91	Not san	pled-floating	product					
10-30-91		ot sampled-sh		•				
03-31-92	270,000	7,000	12,000	4,400	40,000	NA	NA	
06-12-92	110,000	8,900	13,000	2,800	16,000	NA	NA	
MW-3								
01-15-91	230	<0.5	< 0.5	2.2	2.1	NA	NA	
04-10-91	530	12	8.4	4.0	7.0	NA	NA	
07-25-91	110	0.32	0.75	1.2	1.0	NA	NA	
10-30-91	N	lot sampled-d	ry					
03-31-92	670	12	1.1	7.4	27	NA	NA	
06-12-92	280	<0.5	< 0.5	2.1	2.0	NA	NA	
<u>MW-4</u>								
07-25-91	23,000	590	7 30	360	3,500	NA	NA	
10-30-91	19,000	320	340	230	180	NA	NA	
03-31-92	30,000	1,300	740	77 0	4,800	NA	NA	
06-12-92	28,000	990	440	550	3,200	NA	NA	
MW-5								
07-25-91	57,000	2,300	4,200	7 7	14,000	NA	NA	
10-30-91		ot sampled—sh	,		*			
03-31-92	80,000	7,100	9,100	2,000	16,000	NA	NA	
06-12-92	69,000	4,000	5,300	2,200	12,000	NA.	NA	
	•	•	,	,	•			
MW-6	10.000	a coo		A 45	4 000	NTA	NIA	
07-25-91	10,000	3,000	200	340	1,000	NA NA	NA NA	
10-30-91	970	150	4.4	4.9	6.6	NA 2 400*		
03-31-92	16,000	3,600	1,500	660	1,700	2,400*	2.5(4.0)	
06-12-92	2,900	480	17	190	170	1,100**	1.2	

See notes on Page 2 of 2.



TABLE 2
CUMULATIVE RESULTS OF LABORATORY ANALYSES OF GROUNDWATER - TPHg, TPHd, BTEX, and TOG
ARCO Station 771
Livermore, California
(Page 2 of 2)

Sample	ТРНg	В	T	E	. X	TPHd	TOG	
MW-7								
07-25-91	45,000	1,500	2,700	1,200	9,200	NA	NA	
10-30-91	93,000	1,800	770	780	6,700	NA	NA	
03-31-92	35,000	960	350	300	5,900	NA	NA	
06-12-92	27,000	900	270	340	4,800	NA	NA	
MW-11								
06-12-92	<50	<0.5	< 0.5	<0.5	<0.5	NA	NA	
RW-1								
06-12-92	54,000	2,300	4,400	1,200	12,000	NA	NA	
MCLs		1		680	1,750	- 		
DWAL			100		•			

All results in parts per billion (ppb), except TOG, which is reported in parts per million (ppm).

TPHg: Total petroleum hydrocarbons as gasoline (measured by EPA Method 5030/8015).

B: Benzene T: toluene E: ethylbenzene X: total xylene isomers

BTEX: Measured by EPA Method 5030/8020.

TPHd: Total petroleum hydrocarbons as diesel (measured by EPA Method 3510). May be weathered gasoline.

TOG: Total oil and grease.

NA: Not analyzed.

MCL:

<: Less than the laboratory detection limit.

*: Laboratory reported sample matrix contains low boiling point fuel mixture calculated as diesel.

*: Sample contains a lower boiling point hydrocarbon mixture quantified as diesel. The chromatogram does not match the

typical diesel fingerprint, but appears to be weathered gasoline. State Maximum Contaminant Level in ppb (October 1990).

DWAL: State Recommended Drinking Water Action Level in ppb (October 1990).



TOTAL:

0.29 Gallons

TABLE 3 APPROXIMATE CUMULATIVE PRODUCT RECOVERED ARCO Station 771 Livermore, California

	Livermore, California	
Year	Floating Product Removed (gallons)	
1991	TOTAL: 2.77 Gallons	
Date	Floating Product Removed (galions)	
1992:		
<u>MW-1</u>		
01-15-92	Well inaccessible due to construction	
02-28-92	Well inaccessible due to construction	
03-26-92	0.25	
04-27-92	Well inaccessible due to construction	
05-14-92	None present	
06-30-92	0.02	
MW-2		
01-15-92	Well inaccessible due to construction	
02-28-92	None present	
03-26-92	0.01	
04-27-92	None present	
05-14-92	None present	
06-30-92	None present	
<u>MW-5</u>		
01-15-92	Well inaccessible due to construction	
02-28-92	None present	
03-26-92	0.01	
04-27-92	None present	
05-14-92	None present	
06-30-92	None present	



APPENDIX A
EMCON'S DEPTH TO WATER/FLOATING PRODUCT SURVEY FORMS (2),
CERTIFIED ANALYTICAL REPORTS WITH CHAIN-OF-CUSTODY,
AND WATER SAMPLE FIELD DATA SHEETS



Consultants in Wastes Management and Environmental Control

		Project	<u>G70-12.01</u>	
		•		
To:				
Mr. Joel Coffman				
RESNA/ Applied Geos	ystems			
3315 Almaden Expres	sway, Suite 34	_		
San Jose, California 9	<u>95118</u>			
We are enclosing:				
Copies	Description			
1	•	r/Floating Produc	t Survey Results	
		thly water level s		
		9 Rincon Avenue		
	· · · · · · · · · · · · · · · · · · ·			
For your: X	Information	Sent by:	XMail	
Comments:				
Monthly water leve	el data for the abo	ve mentioned sit	e are attached. Plea	<u>se</u>
call if you have an				
· · •				
	EOFESSION S		Mark Knuttel	
Reviewed by:	2 4094			
	OUSTE SUSTE		A Clorto	
	CALIF	Ŕobert	Porter, Senior Projec	t

April 27, 1992

Engineer.

Date

FIELD REPORT DEPTH TO WATER/FLOATING PRODUCT SURVEY

STATION ADDRESS: 899 Rincon Avenue, Livermore, CA PROJECT # : G70-12.01

STATION ADDRESS: 899 Rincon Avenue, Livermore, CA DATE: 4-24-92

FIELD TECHNICIAN: Mark Kmuttel DAY: FRIDAY ARCO STATION #: 771

			1		<u> </u>		FIROT	OFOOND	DEDTILE	.		
	NATE:	Well	Well			Locking	FIRST	SECOND	DEPTH TO	FLOATING	WELL	
DTW	WELL	Вох	Lid			Well	DEPTH TO		FLOATING	PRODUCT	TOTAL	
Order	ID	Seal	Secure	Gasket	Lock	Cap	WATER	WATER		THICKNESS	DEPTH	COMMENTS
		ļ		,			(feet)	(feet)	(feet)	(feet)	(feet)	
1	MW-11	OK	4ES	<i>\</i>	3259	YÉS	35.06	35.06	ND	ND	38.6	_
2	RW-1	or	4E>	V	3259	YES	32.85	32.85	ND	ND	39.45	-
3	MW-3	OK	YES		3259	YES	32.83	32.83	MD	ND	39.62	_
4	MW-6	CK	YES	/	3259	463	33.24	33.24	~D	ND	43.21	_
5	MW-4	OK	4és	V	3259	YES	32.65	32.65	MD	~D	40.85	CIRCLEAR METAL CASINA
6	MW-7	OK	YES.	V	3259	YES	32.14	32.14	ND	MD	39.80	CITCULAR METAL CASINL
7	MW-5	OK	yes	\checkmark	3259	yE5	33.0	33.1	NO	NΛ	40.5	SKIMMER IN WELL
8	MW-2	OK	465	/	3259	4E3	30.95	30.95	ND	ND	37.85	CIRCULAR METAL CASING SKIMMER IN WELL
9	MW-1	MA	NΑ	NA	NA	NA	NA	NA	NA	MA	NA	SOIL PILE ON TOP OF WELL
						}						
					Į.							
									1			
		<u> </u>	<u> </u>									
								ļ				
L	<u> </u>	<u> </u>		!	<u> </u>	L	L		L	<u> </u>	L	<u> </u>



RECEIVED MAY 27 1992

> RESNA SAN JOSE

nts in Wastes ement and		Date	May 21, 1992
ental Control		Project	G70-12.01
To:			
Mr. Joel Coffman			
RESNA/ Applied Ge	osystems		
3315 Almaden Expr			
San Jose, California		-	
We are enclosing:			
Copies	Description		
1	Depth To Water/	Floating Product	Survey Results
	May 1992 month	ly water level sur	vey, ARCO
	station 771, 899	Rincon Avenue,	Livermore, CA
For your: X	Information	Sent by: X	Mail
Comments:			
Monthly water le	vel data for the above	e mentioned site	are attached. Please
·	any questions: (408)		
	•		
	COFESSION		
	CORT IS A STATE OF THE PARTY OF		Jim Butera
Reviewed by:	Pala ADDA TE		
	\ Exp. 6 30 90		
1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1			1
Ŷ,	Sylvery (Sylvery)	Role	+ (Pate)
	CALL.	Robert P	orter, Senior Project
			Engineer.

FIELD REPORT DEPTH TO WATER/FLOATING PRODUCT SURVEY

PROJECT #: <u>G70-12.01</u> STATION ADDRESS: 899 Rincon Avenue, Livermore, CA

STATION ADDRESS: 899 Rincon Avenue, Livermore, CA DATE: 5-20-92

FIELD TECHNICIAN: M. Km. tal / St. Buter DAY: Wodnesday ARCO STATION #: 771

		Well	Well		1	Locking	FIRST	SECOND	DEPTH TO	FLOATING	WELL		
DTW	WELL	Box	Lid			Well	DEPTH TO		FLOATING	PRODUCT	TOTAL		
Order	ID	Seal	Secure	Gasket	Lock	Cap	WATER	WATER	PRODUCT	THICKNESS	DEPTH		COMMENTS
0.00.			332473		Look	Jup	(feet)	(feet)	(feet)	(feet)	(feet)		OOMMERTO
1	MW-11	OF	راء ١	425	325"7	403	34.10	34.10	8	ND	38.60		
2	RW-1	OK	403	₩¢ S	3259	423	72.60	32.60	MD	ND	39.45		
3	MW-3	OK	LJe 3	4-3	3259	yes	33.85	33.85	29	NO	39.60		
4	MW-6	or	це	405	3259	yes	33.14	33.15	20	MO	43.20		
5	MW-4	CXL	ધ્ યત	Hoyes	3259	५०.९	32.62	32.62	20	25	41.0	3 ft.	DIAMETER OTER
6	MW-7	ar	400	No ye	3259	yes	32.51	32.51	Mu	מט	39.8		
7	MW-5	DK	yes	40.91	3259	405	32.86	32.86	מא	ND	40.5		SKIMMER IN WELL
8	MW-2	OK	yes	ye1	3257	405	30.69	30.70	M	Nn	37.85		SKIMMER IN VOLL
9	MW-1	61/	izes	yes	3259	445	33.00	33.01	ND	СИ	40.15	•	SKIMMER W
												ALL	SKIMMERS WERE
												ゼル	Pry.



RECEIVED

JUL 1 3 1882

RESNA SANJOSE

VIII			SAN JOSE
CIATES unts in Wastes gement and		Date	July 9, 1992
nental Control		Project	G70-12.01
То:			
Mr. Joel Coffman		_	
RESNA/ Applied	Geosystems		
3315 Almaden E	Expressway, Suite 34	_	
San Jose, Califor	rnia 95050	_	
We are enclosin			
Copies	Description		
Copies 1	Description Depth To Water / Fk	pating Product S	urvey Results
Copies 1 1	•		
Copies112	Depth To Water / Flo Summary of Ground	lwater Monitorin	g Data
1 1	Depth To Water / Flo	lwater Monitoring Reports with Cha	g Data
1 2	Depth To Water / Flo Summary of Ground Certified Analytical I	lwater Monitoring Reports with Cha	g Data

Comments:

Enclosed are the data from the second quarter 1992 monitoring event at ARCO service station 771. Please note that well MW-6 was resampled for diesel analysis on June 30, 1992 due to quality assurance deficiencies associated with the original analysis of this sample. Both the original and resample diesel results are enclosed for your review. Groundwater monitoring is conducted consistent with applicable regulatory guidelines.

Reviewed by:



Jim Butera

Shreerang N. Dharasker, Senior Project Engineer.



FIELD REPORT DEPTH TO WATER/FLOATING PRODUCT SURVEY

PROJECT #: G70-12.01 STATION ADDRESS: 899 Rincon Avenue, Livermore, CA DATE: 6-12-5-2

ARCO STATION #: 771 FIELD TECHNICIAN: Stilling S DAY: FR

			,									
		Well	Well			Locking	FIRST	SECOND	DEPTH TO	FLOATING	WELL	
DTW	WELL	Вох	Lid			Well	DEPTH TO		FLOATING	PRODUCT	TOTAL	
Order	ID	Seal	Secure	Gasket	Lock	Cap	WATER	WATER	PRODUCT	THICKNESS	DEPTH	COMMENTS
							(feet)	(feet)	(feet)	(feet)	(feet)	
1	MW-11	e/	1		3259		34,40	34.47	ND	1050	3860	
2	RW-1	1.5.	∮ >	ÆS	Sund F	Cl part	32.72	32.72	NA	NV	3945	
3	MW-3	0.	2	۷	i	r	3451	34.50	NO	NO	39,67	_
4	MW-6	~/	L	c	/	v	33,43	33,43	wp	NO	43.24	f
5	MW-4	V	v	ν	c	L	32,73	9 2.73	NO	NO	41.0	~
6	MW-7	i.	c	<i>'</i>	ı	L	32,45	32,45	ND	NO	25,₹0	
7	MW-5	V	L	V	1	۷	33.03	33,03	ND	KD	40,50	_
8	MW-2	.6	v	٤	i	سن	31.25	31,75	NO	200	3785	-
9	MW-1	V	V	ı	V	L	33.25		· 1	,02	40.20	
											,	
											-	
												·

Summary of Groundwater Monitoring Data Second Quarter 1992 ARCO Service Station 771 899 Rincon Avenue, Livermore, California micrograms per liter (µg/l) and milligrams per liter (mg/l)

Well ID and Sample Depth	Sampling Date	Depth To Water (feet)	Floating Product Thickness (feet)	TPH ¹ as Gasoline (μg/l)	Benzene (μg/l)	Toluene (μg/l)	Ethyl- benzene (μg/l)	Total Xylenes (μg/l)	TPH as Diesel (ug/l)	Total Oil and Grease, 5520C (mg/l
MW-1	06/12/92	33.25	0.02	FP ² .	FP.	FP	FP	FP	FP	FP
MW-2(37)	06/12/92	31.25	ND.3	110,000.	8,900.	13,000.	2,800.	16,000.	NR.4	NR.
MW-3(38)	06/12/92	34.51	ND.	280.	<0.5	<0.5	2.1	2.0	NR.	NR.
MW-4(40)	06/12/92	32.73	ND.	28,000.	990.	440.	550.	3,200.	NR.	NR.
MW-5(39)	06/12/92	33.03	ND.	69,000.	4,000.	5,300.	2,200.	12,000.	NR.	NA.
MW-6(42)	06/12/92	33.43	ND.	2,900.	480.	17.	190.	170.	1,100*.	1.2*
MW-7(39)	06/12/92	32.45	ND.	27,000.	900.	270.	340.	4,800.	NR.	NR.
MW-11(37)	06/12/92	34.48	ND.	<50	<0.5	<0.5	<0.5	<0.5	NR	NR
RW-1(38)	06/12/92	32.72	ND.	54,000.	2,300.	4,400.	1,200.	12,000.	NR	NR
FB-1. ⁵	06/12/92	NA. ⁶	NA.	<50	<0.5	<0.5	<0.5	<0.5	NR.	NR.

TPH. = Total petroleum hydrocarbons
 FP. = Not sampled; well was not sampled due to detection of floating product

^{3.} ND. = Not detected

^{4.} NR. = Not reported; sample was not scheduled for analysis of the selected parameter 5. FB. = Field blank

^{6.} NA. = Not applicable

* = Sampling date was 6/30/92



June 29, 1992

Jim Butera EMCON Associates 1921 Ringwood Avenue San Jose, CA 95131

Re: EMCON Project No. G70-12.01

Arco Facility No. 771

Dear Mr. Butera:

Enclosed are the results of the water samples submitted to our lab on June 15, 1992. For your reference, our service request number for this work is SJ92-0733.

All analyses were performed in accordance with the laboratory's quality assurance program.

Please call if you have any questions.

Respectfully submitted:

COLUMBIA ANALYTICAL SERVICES, INC.

Keoni A. Murphy

Laboratory Manager

Annelise J. Bazar

Regional QA Coordinator

annelise Jade Bargon

le/KAM

Analytical Report

Client:

EMCON Associates

Project:

EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received:

06/15/92

Work Order #:

SJ92-0733

Sample Matrix: Water

Inorganic Parameters¹ mg/L (ppm)

Sample Name: Date Sampled: MW-6 (42)

Method Blank

06/12/92

Analyte

Method MRL

Total Oil and Grease

413.2

0.5

1.2

ND

MRL Method Reporting Limit

None Detected at or above the method reporting limit

Unless otherwise noted, all analyses were performed within EPA recommended maximum holding times specified in Test Methods for Evaluating Solid Waste, (SW-846, 3rd Edition) and Methods for Chemical Analysis of Water and Waste (EPA-600/4-79-020, Revised March 1983).

Date June 29/992

Analytical Report

Client:

EMCON Associates

Project:

EMCON Project No. G70-12.01

Arco Facility No. 771

Sample Matrix: Water

06/15/92 Date Received: Date Extracted: 06/19/92

Date Analyzed: 06/22/92

Work Order #: SJ92-0733

Total Petroleum Hydrocarbons as Diesel EPA Methods 3510/California DHS LUFT Method μ g/L (ppb)

Sample Name	MRL	TPH as Diesel
MW-6 (42)	50	1,200.1,2
Method Blank	50	2,100.1

MRL Method Reporting Limit

TPH Total Petroleum Hydrocarbons

None Detected at or above the method reporting limit

The sample matrix contains a lower boiling point fuel mixture calculated as diesel. The chromatogram does not match typical diesel fingerprint.

2 Analyte concentration is an estimate because this analyte was found in the Method Blank.

Kom AMayshy

Analytical Report

Client: EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92 SJ92-0733

Sample Matrix: Water



BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method μ g/L (ppb)

-	ole Name: Analyzed:	<u>MW-2 (37)</u> 06/23/92	<u>MW-3 (38)</u> 06/22/92	MW-4 (40) 06/24/92
<u>Analyte</u>	<u>MRL</u>			
Benzene	0.5	8,900.	ND	990.
Toluene	0.5	13,000.	ND	440.
Ethylbenzene	0.5	2,800.	2.1	550.
Total Xylenes	0.5	16,000.	2.0	3,200.
TPH as Gasoline	50	110,000.	280.	28,000.

TPH Total Petroleum Hydrocarbons

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by KOM AMMyly

Date JMC29/1982

Analytical Report

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received:

06/15/92

Work Order #: Sample Matrix:

SJ92-0733

Water



BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method μ g/L (ppb)

	ample Name: nte Analyzed:	<u>MW-5 (39)</u> 06/23/92	<u>MW-6 (42)</u> 06/24/92	MW-7 (39) 06/23/92
<u>Analyte</u>	MRL			
Benzene	0.5	4,000.	480.	900.
Toluene	0.5	5,300.	17.	270.
Ethylbenzene	0.5	2,200.	190.	340.
Total Xylenes	0.5	12,000.	170.	4,800.
TPH as Gasoline	50	69,000.	2,900.	27,000.

TPH

Total Petroleum Hydrocarbons

MRL

Method Reporting Limit

Kom AM nighty

June 29,1992 Date___

Analytical Report

Client: EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #: Sample Matrix:

06/15/92 SJ92-0733

Water



BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method μ g/L (ppb)

	Sample Name: Date Analyzed:		<u>MW-11 (37)</u> 06/22/92	RW-1 (38) 06/23/92	<u>FB-1</u> 06/22/92
<u>Analyte</u>		MRL			
Benzene		0.5	ND	2,300.	ND
Toluene		0.5	ND	4,400.	ND
Ethylbenzene		0.5	ND	1,200.	ND
Total Xylenes		0.5	ND	12,000.	ND
TPH as Gasoline		50	ND	54,000.	ND

TPH Total Petroleum Hydrocarbons

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by Nom Ammyly

Date JMC 29/992

Analytical Report

EMCON Associates Client:

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92 SJ92-0733

Sample Matrix: Water



BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method μ g/L (ppb)

	Sample Name: Date Analyzed:	<u>Method Blank</u> 06/22/92	Method Blank 06/23/92	Method Blank 06/24/92
Analyte	<u>MRL</u>			
Benzene	0.5	ND	ND	ND
Toluene	0.5	ND	ND	ND
Ethylbenzene	0.5	ND	ND	ND
Total Xylenes	0.5	ND	ND	ND
TPH as Gasoline	50	ND	ND	ND

TPH Total Petroleum Hydrocarbons

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Kom AMayshy Date Jine 29/1982

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92

SJ92-0733

Sample Matrix: Water



QA/QC Report Continuing Calibration Summary Inorganics EPA Method 413.2 mg/L

				CAS
				Percent
				Recovery
	True		Percent	Acceptance
<u>Analyte</u>	<u>Value</u>	<u>Result</u>	Recovery	<u>Criteria</u>
Total Oil & Grease	80.	80.5	101.	53-149

Monthly Date June 29/992



Client:

EMCON Associates

Project:

EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92 SJ92-0733

Sample Matrix: Water

QA/QC Report Matrix Spike Summary Inorganic Parameters mg/L (ppm)

Sample Name: MW-6 (42) Date Sampled: 06/12/92

> Percent Recovery

<u>Parameter</u>	Spike <u>Level</u>	Sample <u>Result</u>	Spike Result MS DMS	MS DMS	Acceptance <u>Criteria</u>
Total Oil & Grease	6.3	1.2	5.3 5.7	65. 71.	53-149

Kon A Mayely

Junc 29, 1982 Date

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received:

06/15/92

~ 4 6

Work Order #: SJ92-0733

Sample Matrix: Water



QA/QC Report Continuing Calibration Summary TPH as Diesel EPA Methods 3510/DHS LUFT Method mg/L (ppm)

Date Analyzed: 06/22/92

				Percent Recovery
<u>Analyte</u>	True <u>Value</u>	<u>Result</u>	Percent Recovery	Acceptance <u>Criteria</u>
TPH as Diesel	1,000.	972.	97.	90-110

TPH Total Petroleum Hydrocarbons

Krom AM myly Date June 29/992

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92 SJ92-0733

Sample Matrix: Water

QA/QC Report Surrogate Recovery Summary TPH as Diesel EPA Method 3510/DHS LUFT Method

Sample Name	<u>Date Analyzed</u>	Percent Recovery P-Terphenyl
MW-6 (42)	06/22/92	80.
MW-6 (42) MS MW-6 (42) DMS	06/22/92 06/22/92	63. 88.
Method Blank	06/22/92	103.
	CAS Acceptance Criteria	55-145

TPH Total Petroleum Hydrocarbons

Hom AMmyly Date Jine 29,1992

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received:

06/15/92

Work Order #: SJ92-0733

Sample Matrix: Water



QA/QC Report

Matrix Spike/Duplicate Matrix Spike Summary

Total Petroleum Hydrocarbons as Diesel

DHS LUFT Method μ g/L (ppb)

Sample Name: <u>MW-6 (42)</u> Date Analyzed: 06/22/92

Percent Recovery

<u>Parameter</u>	Spike <u>Level</u>	Sample <u>Result</u>	Spike Result MS DMS	MS DMS	Acceptance <u>Criteria</u>
Diesel	3,640.	1,170.	4,860. 4,460.	101. 90.	55-145

Approved by Away Amang A

_Date____

June 29/882

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01


Arco Facility No. 771

Date Received: Work Order #:

06/15/92 SJ92-0733

Sample Matrix:

Water



Date Analyzed:

06/22/92

<u>Analyte</u>	True <u>Value</u>	<u>Result</u>	Percent <u>Recovery</u>	CAS Percent Recovery Acceptance <u>Criteria</u>
Paggana	350	240	ne	95 11E
Benzene	250.	240.	96.	85-115
Toluene	250.	261.	104.	85-115
Ethylbenzene	250.	251.	100.	85-115
Total Xylenes	7 50.	725.	97.	85-115
TPH as Gasoline	2,500.	2,556.	102.	90-110

Date Analyzed:

06/23/92

				CAS
				Percent
				Recovery
	True		Percent	Acceptance
<u>Analyte</u>	<u>Value</u>	<u>Result</u>	Recovery	<u>Criteria</u>
Benzene	250.	258.	103.	85-115
Toluene	250.	267.	107.	85-115
Ethylbenzene	250.	282.	113.	85-115
Total Xylenes	750.	764.	101.	85-115
TPH as Gasoline	2,500.	2,393.	96.	90-110

TPH Total Petroleum Hydrocarbons

Date TMC 29/982

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92

Sample Matrix:

SJ92-0733 Water

QA/QC Report Continuing Calibration Summary BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method Nanograms

Date Analyzed:

06/24/92

	True		Percent	CAS Percent Recovery Acceptance
<u>Analyte</u>	<u>Value</u>	Result	Recovery	<u>Criteria</u>
Benzene	250.	259.	104.	85-115
Toluene	250.	273.	109.	85-115
Ethylbenzene	250.	271.	108.	85-115
Total Xylenes	750.	759.	101.	85-115
TPH as Gasoline	2,500.	2,342.	94.	90-110

TPH Total Petroleum Hydrocarbons

KOWAMMy Date JM 29/882

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/15/92 SJ92-0733

Sample Matrix: Water

QA/QC Report Surrogate Recovery Summary BTEX and TPH as Gasoline EPA Methods 5030/8020/DHS LUFT Method

Sample Name	<u>Date Analyzed</u>	<u>Percent Recovery</u> α,α,α-Trifluorotoluene
MW-2 (37)	06/23/92	118.
MW-3 (38)	06/22/92	114.
MW-4 (40)	06/24/92	117.
MW-5 (39)	06/23/92	115.
MW-6 (42)	06/24/92	110.
MW-7 (39)	06/23/92	115.
MW-11 (37)	06/22/92	109.
RW-1 (38)	06/23/92	114.
FB-1	06/22/92	109.
MS	06/22/92	109.
DMS	06/22/92	109.
Method Blank	06/22/92	112.
Method Blank	06/23/92	110.
Method Blank	06/24/92	110.
	CAS Acceptance Criteria	70-130

TPH Total Petroleum Hydrocarbons

KEOnit Mushy Date Jine 29/1992

16

Client: **EMCON Associates**

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: 06/15/92 Work Order #: SJ92-0733 Sample Matrix: Water



QA/QC Report Matrix Spike/Duplicate Matrix Spike Summary EPA Methods 5030/8020 μ g/L (ppb)

Sample Name: MW-11 (37) 06/22/92 Date Analyzed:

Percent Recovery

		Sample	Spike	Result			Acceptance
<u>Analytes</u>	Spike Level	<u>Result</u>	MS	<u>DMS</u>	MS	DMS	<u>Criteria</u>
Benzene	25.	ND	24.3	24.4	97.	98.	39-150
Toluene	25.	ND	25.9	26.0	104.	104.	46-148
Ethylbenzene	25.	ND	26.2	26.4	105.	106.	32-160

ND None Detected at or above the method reporting limit

Leon AMuydy

ARCO	Division	of Atlantic	Comp	oany (X			Task Or	der No.	E	MIC	260	<u>, </u>	92	-/							C	hain of Custod	y
ARCO Facili	ty no.	171		City	/ cility)	LIVE	uno			Project	manag	er T	ins	£	307	71	A						Laboratory name	
ARCO engin	eer	<u> </u>	راط	nrist	Cility)	<u> </u>	Telephop	4/15)571		Telepho	one no	<u> </u>	153			Fax	no.	FILE	121 11	グラー	مرا ز ب		CHS	
Consultant n	ame E	4/5		<u> 11/191</u>	16		(ARCO)	4/3) 5 7 / Address	- L434 11	(Consul	tant)(4	100	450	····	1] (Co	nsultan	440	2) 4	35-	<u>0</u> 4=	> /-	Contract number	Ì
Consultant n	L	MCC	<u>///</u>	14550	2011	TES_		(Consulta	ni) 193	5	וטנ	10	70		<u>//</u>	<u>e</u>		-		— — ү			67077	
				Matrix		Prese	rvation				- ±2	<i> </i>	ر					jĒ&	0/7000				Method of shipment	1
. ·		ē		·		•	1	late	39	_	₹08	8 8 5 3	3.2 🕟	4503E				S. C	74 601 LC [
9 1.0	, i		Soil	Water	Other	Ice	Acid	ampling date	î <u>ûl</u>	4 80Z(F. 502/30	dified	Greas 7 41	8.1/SN	1/801(4/824(5/827(/O/	tals EF	후<2			Method of shipment Gampler Will deliver	1
Sample I.D.	ab no	Container				,,,,		атъ	Sampling time	BTEX 602/EPA 8020	BTEXTPH € 7 → EPA M602/8020/8015	TPH Modified 8015 Gas Diesel	Oil and Grease 413.1 □ 413.2 【	TPH EPA 418.1/SM503E	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Metals □ VOA □ VOA	AM Me	Lead Org./DHS C Lead EPA 7420/7421 C			401100	
							1101	<u> </u>	(i)	<u>т</u>	-X	1-9				ш		-≥	O.L	336	5_14	32	Special detection	
M≈-/()	2	ļ <u>.</u>	X		<u> </u>	HC1			<u> </u>			40	ρd	1C4	_JV	M	611	pa	1	B>44	144	i DUEST	Ì
MW-2 (57)) -2	2		χ		Х		6-12-92	1737		X								•				Special detection Limit/reporting LOWEST POSS(b le	
MW3(38))3-Y	2		Х_		<u></u>		4-12-52	1524		X												, -	
MW-4(40		2		Х	;	×		6-12-52	1515		1												Special QA/QC	
uw-5(34				Х		x	1 (6-12-52			χ												As,	
14W-6(42)	9-10	2		х		K		4-12-92			X												Norma/	
mw 7(39')11-12	7		χ		χ		4-12-52			X												,	
nw-11(37	. n_1U	1		X		እ		4-12-42			X												2 40 ml VOA'S Per Well	91
PW-1 (38	157b	Z				X	 	4-12-52			K												WOA'S PET	
	17-18	2		Х		<u>^</u>					×												well	
FB)		<i>C</i>		Χ			47	4-12-92	1424_		<u> </u>				-								MAHE TO	
				1						<u> </u>	ļ	 			.								JUH-9-5-6A	9
MW-6(42)14- <u>5</u> 0	2		X		X	NP	4-12-92	1625			X											106 - 2 Lite HC/	9 سرد
							<u> </u>																Lab number	
MW-C(42	7422	2		χ		メ	HCI	4-12.92	1425			j	X			<u>. </u>	•						SJ92-0733	,
																•							Turnaround time	
																							Priority Rush	
Condition of	sample:				t t	ΣK			<u> </u>	Temp	erature	receive		·	(0)	T		·	1	1			1 Business Day	
Relinquished	y by fam	ple	111.		·	-	Date		Time	Recei	ved by		1/		Ca				0	7 1	17		Rush 2 Business Days	□
Relinquishe	1 4	10	<u>YY</u> J				Ca-15	-92	0848 Time	Becci	ved by						6-	<u>[2-1</u>	1	084	70		Expedited	
THE INIQUISTIES	11			at 200	4) .	£-13	-92	0848								5 Business Days							
Relinquishe	d by	ر <u>ي</u> ما اد در	1,		<u> </u>		Date		Time		ved by	laborat	ory			[ate			Time			Standard	ا پ
Man	- /L	6,1	1/49	Sing		ノ	4-15	-52	0848.										l				10 Business Days	X



July 7, 1992

Jim Butera **EMCON Associates** 1921 Ringwood Avenue San Jose, CA 95131

EMCON Project No. G70-12.01 Re:

Arco Facility No. 771

Dear Mr. Butera:

Enclosed are the results of the water sample submitted to our lab on June 30, 1992. For your reference, our service request number for this work is SJ92-0787.

All analyses were performed in accordance with the laboratory's quality assurance program.

Please call if you have any questions.

Respectfully submitted:

COLUMBIA ANALYTICAL SERVICES, INC.

Keoni A. Murphy

Laboratory Manager

Annelise J. Bazar

Regional QA Coordinator

le/KAM

Analytical Report

Client:

EMCON Associates

Project:

EMCON Project No. G70-12.01

Arco Facility No. 771

Sample Matrix: Water

Date Received:

06/30/92

Date Extracted: 07/01/92

Date Analyzed:

07/01/92

Work Order #: SJ92-0787

Total Petroleum Hydrocarbons as Diesel EPA Method 3510/California DHS LUFT Method μ g/L (ppb)

Sample Name	<u>MRL</u>	TPH as Diesel
MW-6 (42)	50	1,100.*
Method Blank	50	ND

MRL Method Reporting Limit

TPH Total Petroleum Hydrocarbons

ND None Detected at or above the method reporting limit

Kom AMenylly

The sample matrix contains a lower boiling point fuel mixture calculated as diesel. chromatogram does not match typical diesel fingerprint.

Date 70ly 7, 1992

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: Work Order #:

06/30/92

Sample Matrix:

SJ92-0787

Water

QA/QC Report
Continuing Calibration Summary
TPH as Diesel
EPA Method 3510/DHS LUFT Method
mg/L (ppm)

Date Analyzed:

07/01/92

				CAS Percent
<u>Analyte</u>	True <u>Value</u>	<u>Result</u>	Percent <u>Recovery</u>	Recovery Acceptance <u>Criteria</u>
TPH as Diesel	1,000.	1,005.	101.	90-110

TPH Total Petroleum Hydrocarbons

Approved by

Date

Client: EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received: 06/30/92 Work Order #: SJ92-0787 Sample Matrix: Water

QA/QC Report
Surrogate Recovery Summary
TPH as Diesel
EPA Method 3510/DHS LUFT Method

Sample Name	Date Analyzed	Percent Recovery P-Terphenyl
MW-6 (42)	07/01/92	72.
MW-6 (42) MS MW-6 (42) DMS	07/01/92 07/01/92	90. 75.
Method Blank	07/01/92	85.
	CAS Acceptance Criteria	55-145

TPH Total Petroleum Hydrocarbons

Approved by Kon AMuyly

Date Jy 7,1892

Client:

EMCON Associates

Project: EMCON Project No. G70-12.01

Arco Facility No. 771

Date Received:

06/30/92 Work Order #: SJ92-0787 Sample Matrix: Water

QA/QC Report Matrix Spike/Duplicate Matrix Spike Summary Total Petroleum Hydrocarbons as Diesel DHS LUFT Method μ g/L (ppb)

Sample Name:

MW-6 (42)

Date Analyzed: 07/01/92

Percent Recovery

Parameter	Spike <u>Level</u>	Sample <u>Result</u>	Spike Result MS DMS	MS DMS	Acceptance <u>Criteria</u>
Diesel	4,000.	1,060.	4,350. 4,230.	82. 79.	55-1 45

Feomot Muyly Date July 7,1982

ARCO Products Company Chivision of AtlanticRichfieldCompany						Task Or	der No.	E	mc	G	ر -	92	-1						(Chain of Custody		
ARCO Facili	y no.	77	7	Cit (Fa	y icility)	Lin	ermo	ne_		Project (Consul	manag tant)	er	Jin	B	., Le	يمور	ı			****		Laboratory name
ARCO engin	eer	tille					Telephor	264 77	8 2 3 2	Telepho	ne no	-10C	1616		710	Fax	no.	n Li a	<u></u>		- / 1 = 7	CAS
Consultant n	ame		con	<u>.</u>		T	10:100)	Address (Consulta	nt)	(00::50:	- Carrier	100	<u> </u>	ی د	-/17	1(00)	iisuitai	'') <u>1.0</u>	57	3.3	0436	Laboratory name Contract number Method of shipment
				Matrix		Prese	rvation				15			(a)				ĕĕ	0,7000			Method of shipment
Sample I.D.	Lab no.	Container no.	Soil	Water	Other	lce	Acid	Sampling date	Sampling time	BTEX 602/EPA 8020	BTEX/TPH EPA M602/8020/8015	TPH Modified 8015 Gas ☐ Diesel ☐	Oil and Grease 413.1 🗀 413.2	TPH-DIESEI EPA 418-115NESSE	EPA 601/8010	EPA 624/8240	EPA 625/8270	TCLP Semi Metats ☐ VOA ☐ VOA ☐	CAM Metals EPA 601	Lead Org./DHS ☐ Lead EPA 7420/7421 ☐		Will Pelver
MW-6	$\sqrt{\gamma}$	2		×		\vee		6-30-92	1310					X			·					Special detection Limit/reporting
<i>™</i> • •								3- 72														
										 												Special QA/QC
										<u> </u>												ļ
								<u> </u>		<u> </u>						·			-			
			<u> </u>							†												Remarks
									·													Fish
																						ush. TAT
																						PUSH 48hr. THT 6-30-92 HF.
•										 												C 70-R01
		ļ	-		ļ					—												Lab number
										ļ												G70-/201 Lab number GJ92-078
																						Turnaround time
																						Priority Rush 1 Business Day
Condition of sample: Relinquished by sampler Date Time 6-30-92 1424				Temperature received: 100 \ Received by 6-20-92 (44)				124	Rush 2 Business Days													
Relinquished							Date		Time	Recei	ved by	1 3								<u>, , , , , , , , , , , , , , , , , , , </u>		Expedited 5 Business Days
Relinquishe	d by						Date		Time	Recei	ved by	laborat	ory			D	ate	-		Time		Standard 10 Business Days

EMC	ON

Rev. 2, 5/91

PROJECT NO: _ 670-1201 SAMPLEID: RW-1 PURGED BY: M. GAllegas CLIENT NAME: AROUT 771 LOCATION: Livermere TYPE: Ground Water _____ Surface Water ____ Treatment Effluent ____ Other____ CASING DIAMETER (inches): 6_X 3 ___ 4____ 4.5 ____ Other____ 9.87 CASING ELEVATION (feet/MSL): __ VOLUME IN CASING (gal.): DEPTH TO WATER (feet): <u>3277</u> 49.39 CALCULATED PURGE (gal.): DEPTH OF WELL (feet): 39.45. 27,5 ACTUAL PURGE VOL. (gal.): DATE PURGED: (c- 12-92. Start (2400 Hr) // 3 Z End (2400 Hr) _1203 DATE SAMPLED: 12-92 1214 Start (2400 Hr) _ End (2400 Hr) . TIME **VOLUME TEMPERATURE** рΗ E.C. COLOR TURBIDITY (2400 Hr) (gal.) (µmhos/cm@ 25° C) (units) (°F) (visual) (visual) 1145 1497 BROWN 4812114 1200 1 20 1430 *[...* 1461 4 17 4 BROW Co ODOR: Streng D. O. (ppm): (COBALT 0 - 100) (NTU 0 - 200) PURGING EQUIPMENT SAMPLING EQUIPMENT X Bailer (Teflon®) 2" Bladder Pump Bailer (Teflon®) ____ 2" Bladder Pump ____ Centrifugal Pump Bailer (PVC) **DDL Sampler** Bailer (Stainless Steet) Submersible Pump Bailer (Stainless Steel) Dipper Submersible Pump Well Wizard™ Dedicated Well Wizard™ Dedicated Other: _ Other: . WELL INTEGRITY: 600d. ____ LOCK#: 3259 REMARKS: DRIED ACTER 23.5 BACKOW Time 1203 Meter Calibration: Date: _____ Time: 1136 Meter Serial #: ____ Temperature °F: 1136 (EC 1000 977 / 1000) (DI _____) (pH 7 (4 3 / 700) (pH 10 10 20 23 / 1000) (pH 4 (4/0 / / _ - _) Location of previous calibration: ____ R to -/ J. 16 ______ Reviewed By: _ _ Page _____ of _ Signature: -

WATER SAMPLE FIELD DATA SHEET PROJECT NO: <u>670-12-01</u> SAMPLE ID: <u>JUW/</u>

ASSOCIATES PURGED BY: NA	CLIENT NAME:ACC 77/
SAMPLED BY: MY	LOCATION: LIVERMOVE CX
TYPE: Ground Water <u>X</u> Surface Water	Treatment Effluent Other
CASING ELEVATION (feet/MSL): 102 DEPTH TO WATER (feet): 33-25 DEPTH OF WELL (feet): 40.2	VOLUME IN CASING (gal.): WR/
/	(2400 Hr) End (2400 Hr) [VA /
	E.C. TEMPERATURE COLOR TURBIDITY s/cm@ 25° C) (°F) (visual) (visual) CH Product (N)
NO - SAI	UPLE
D. O. (ppm): ODOR:	(COBALT 0 - 100) (NTU 0 - 200)
FIELD QC SAMPLES COLLECTED AT THIS WELL (i.	e. FB-1, XDUP-1):
PURGING EQUIPMENT	SAMPLING EQUIPMENT
2° Bladder Pump Bailer (Teflon®)	2° Bladder Pump Bailer (Tefton®)
— Centrifugal Pump — Bailer (PVC)	DDL Sampler Bailer (Stainless Steel)
— Submersible Pump — Bailer (Stainless Steel)	· · · · · · · · · · · · · · · · · · ·
Other: Well Wizard™	Other: Well Wizard™ Dedicated
NELL INTEGRITY: FILE	LOCK#: 3259
ILIMATINO .	
Meter Calibration: Date: Time:	Meter Serial #: Temperature °F:
(EC 1000/) (DI) (pH 7	_/) (pH 10/) (pH 4/)
Location of previous calibration:	
ignature: Joe Whiteans	Reviewed By: Page 2 of 9

	******			D DAIA	SHEET	
	PROJECT NO:			SAMPLE ID:	Mic-*	ζ
EMCON ASSOCIATES			2145	CLIENT NAME:	MRCO	171
	SAMPLED BY:	Sw.lla	4.25	LOCATION:	hiverM	ONE CA
TVDE: Group	d Water	Curto a a Mada	.	/ 		
				nent Effluent		
CASING DIAME	TEN (Inches).	23	4	4.5	6 Oth	er
DEPTH	'ATION (feet/MSI TO WATER (fee I OF WELL (fee	t): <u>36.2</u> <	<u> </u>	DLUME IN CASING LCULATED PURG TUAL PURGE VO	iE (gal.) :	21.64
ſ	ED: <u>66-72</u> ED: <u>66-7</u> 2		tart (2400 Hr)		End (2400 Hr) . End (2400 Hr) .	19:26 19:39
TIME	VOLUME	pН	E.C.	TEMPERATURE	COLOR	TURBIDITY
(2400 Hr)	(gal.)		umhos/cm @ 25° C) / 3 5 3 3	(°F) 66,9	(visual) GCAF	(visual)
1715			1331	67-8	<u> </u>	145/708
17 23	<u> </u>	7.03	132C	<u>-668</u>		
	IN MV	1.07	7,5 00	<u> </u>		
17:40	echane	7.65	17 F G	66.8		
	'_	_				
D. O. (ppm):	<u> </u>	_ ODG	DR: STREET		<u>/('/)</u> COBALT 0 - 100)	(NTU 0 - 200)
FIELD QC SAM	PLES COLLECTE	D AT THIS WEL	L (i.e. FB-1, XDUF	'-1):	·	(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
			,			
	PURGING EQUIP	_ 		· ·	3 EQUIPMENT	
	Pump —	,		2" Bladder Pump	——Bailer	(Teffon®)
Centrifugal		Bailer (PVC)		DDL Sampler		(Stainless Steel)
— Submersibl — Well Wizar		Bailer (Stainless : Dedicated		Dipper Well Wizard™	Submo	ersible Pump
Other:		Decidated			Dedica	
usi usanan					2	209
WELL INTEGRITY						<i>U</i> 3/
REMARKS: ———	16/1/ 1447.	EK (60)	GALLEYUS	Trace 1.		
		 				
	/) (DI_) (pH 7 _)(#:/		
_				ву:	Page	3 of 9

PROJECT NO: 670-12:01	SAMPLE ID: MCC-3
	T. WILLIA-S CLIENT NAME: ARCOLD 77/
,	When LOCATION: Livermore.
TYPE: Ground Water Surface Water	Treatment Effluent Other
CASING DIAMETER (inches): 2 3	4_X_ 4.5 6 Other
	VOLUME IN CASING (gal.): 3.35 CALCULATED PURGE (gal.): 16.76 ACTUAL PURGE VOL. (gal.): 834/1005
DATE PURGED: (c-12-92) Start (2-92) DATE SAMPLED: (c-12-92) Start (2-92)	100 Hr) 1500 End (2400 Hr) 157) 100 Hr) 157(c End (2400 Hr) 31530
(2400 Hr) (gal.) (units) (µmhos/oi 150 (c 3.5 7.54 8	C. TEMPERATURE COLOR TURBIDITY m@ 25° C) (°F) (visual) (visual) 75 70.0 (+cavy)
1530 Recharge 7.70 941	5 71.4 " -
D. O. (ppm): <u>し</u> と. ODOR: _	(COBALT 0 - 100) (NTU 0 - 200)
FIELD QC SAMPLES COLLECTED AT THIS WELL (i.e.	FB-1, XDUP-1):
PURGING EQUIPMENT	SAMPLING EQUIPMENT
2" Bladder Pump Bailer (Teffon®)	2" Bladder Pump Bailer (Tefion®)
—— Centrifugal Pump ——— Bailer (PVC)	DDL Sampler Bailer (Stainless Steel)
Submersible Pump —— Bailer (Stainless Steel)	— Dipper — Submersible Pump
— Well Wizard™ — Dedicated Other:	— Well Wizard™ — Dedicated Other:
WELL INTEGRITY: Good REMARKS: [well bried At Tragallons]	DOCK#: 3259.
Meter Calibration: Date: (C-12-92 Time: 1435 1	Meter Serial #: Temperature °F: 72.4 → → → → → → → → → → → → → → → → → → →
Location of previous calibration:	
	Reviewed By: The Page 4 of 4

WATER SAMPLE FIELD DATA SHEET PROJECT NO: <u>670-12-01</u> SAMPLEID: __ MW-Y PURGED BY: 50 Menon C CLIENT NAME: MRCO 471 SAMPLED BY: Still MYRS LOCATION: 1700 more Ca TYPE: Ground Water ____ Surface Water ____ Treatment Effluent ____ Other____ 4____ CASING DIAMETER (inches): 4.5 ____ 6 ____ VOLUME IN CASING (gal.): CASING ELEVATION (feet/MSL): ___ DEPTH TO WATER (feet): 32.73 CALCULATED PURGE (gal.): _

Rev. 2, 5/91

Other.....

DEPTH	H OF WELL (fee	t): <u>4/.</u> 6	AC	TUAL PURGE V	OL. (gal.) :/	14.0			
DATE PURGE	ED: <u>6-/2-</u> ED: <u>6-/2-</u>		Start (2400 Hr)	_	End (2400 Hr) .				
TIME (2400 Hr) 14:50	VOLUME (gal.) G	pH (units) 7.27	E.C. (µmhos/cm@25°C) /285 /263	TEMPERATURE (°F) 74, 3 69,3	COLOR (visual) BLOWN	TURBIDITY (visual) HEROF			
<u>15:18:</u>	- 12 Pollarg	e707	1313	68.4	Borne a	HEROY			
D. O. (ppm): .			DOR: <u>STROM</u>		(COBALT 0 - 100)	(NTU 0 - 200)			
2° Bladder Centrifugal Submersib	PURGING EQUIPMENT 2' Bladder Pump — Bailer (Teflon®) — 2' Bladder Pump — Bailer (Teflon®) — Centrifugal Pump — Bailer (PVC) — DDL Sampler — Bailer (Stainless Steel) — Submersible Pump — Bailer (Stainless Steel) — Dipper — Submersible Pump — Well Wizard™ — Dedicated Other: — Other: — Other:								
VELL INTEGRITY: OK LOCK#: 3259 JEMARKS: DRIED MOFER 146ALLOW TIME 1508									
			Meter Seria						

Signature: Aco William Reviewed By: 70 Page 5 of 9

PROJECT NO: 670-12.01 EMCON ASSOCIATES PURGED BY: M. Galleges SAMPLED BY: 14. Castleges	LOCATION: Livermore
TYPE: Ground Water Surface Water Trescaled CASING DIAMETER (inches): Z 3 4_2	
DEPTH TO WATER (feet): 3303	VOLUME IN CASING (gal.): 4.90 CALCULATED PURGE (gal.): 24.50 ACTUAL PURGE VOL. (gal.): 17.5
DATE SAMPLED: 6-12-62 Start (2400 Hr) TIME VOLUME pH (2400 Hr) (gal.) (units) (µmhos/cm@ 25° 0) 1716 5 8-09 11.60 1735 Recharge 7-82 1175	End (2400 Hr) 1729 1735 End (2400 Hr) 1738 TEMPERATURE COLOR TURBIDITY (visual) (°F) (visual) (visual) (close decired
D. O. (ppm): DR ODOR: Strong FIELD QC SAMPLES COLLECTED AT THIS WELL (i.e. FB-1, XE PURGING EQUIPMENT	(COBALT 0 - 100) (NTU 0 - 200)
	SAMPLING EQUIPMENT 2° Bladder Pump
WELL INTEGRITY: Good REMARKS: Alich ALLC 12.5 gullons - A	LOCK#: 3759
Meter Calibration: Date: 6-12-92 Time: Meter Se (EC 1000/) (DI) (pH 7/ Location of previous calibration:	
	red By: Page _b of

EMCON	PROJECT NO: PURGED BY: SAMPLED BY:	M.Gal	legal		CLIENT NAM	ID: <u>MU</u> ME: <u>A2</u> DN: <u>LIV</u>	(0 #7	
TYPE: Ground		z	3	,	nent Effluent _ 4.5			
DEPTH T	ATION (feet/MSI O WATER (fee OF WELL (fee	-): <u> </u>	.43	_ CA	OLUME IN CAS ALCULATED PL TUAL PURGE	JRGE (ga	l.): <u> </u>	71.58
DATE PURGED	D: 6-12-92 D: 6-12-92		Start (240 Start (240	о Hr) <u>/</u> о Hr) <u>/</u>	554 625		400 Hr) _ 400 Hr) _	[604. 1631
TIME (2400 Hr) (606 (63)	VOLUME (gal.)	pH (units) 8.28 8.04 8.51		25° C)	TEMPERATUR (°F) 70 8 70.9 71.6	(vis Ga		TURBIDITY (visual) Heavy
D. O. (ppm):	NR NR		ODOR: 56				T 0 - 100)	人 亿. (NTU 0 - 200)
	JRGING EQUIP		**************************************	, XDO.		ING EQU	 JIPMENT	
2* Bladder P Centrifugal F Submersible Well Wizard Other:	Pump —	Bailer (Teflor Bailer (PVC) Bailer (Staini Dedicated		Other:	2° Bladder Pum DDL Sampler Dipper Well Wizard [™]		Bailer Bailer	(Teflon®) (Stainless Steel) ersible Pump ated
ELL INTEGRITY			allon S		1 SAIM			

Meter Calibration: Date: 12-12-92 Time: _____ Meter Serial #: _____ Temperature °F: _____ (EC 1000 ____/__) (DI ____) (pH 7 ____/___) (pH 10 ____/___) (pH 4 ____/___)

Reviewed By: $\frac{73}{9}$ Page $\frac{7}{9}$ of $\frac{9}{9}$

Location of previous calibration:

Signature: Mall Wall

	ì
EMC	
TYPF.	G

	PROJECT NO: <u>670</u>	- 17 - 6 /		Maria	<u>م</u> ــــر
EMCON	PURGED BY: 54			: MIW-	
ASSOCIATES	SAMPLED BY: 50			ARCC !	
				"	
TYPE: Groui	nd Water Surface	Water Trea	atment Effluent	Other	
	TER (inches): 2				
DEPTH	VATION (feet/MSL): TO WATER (feet): H OF WELL (feet):	37,45	VOLUME IN CASING CALCULATED PURG ACTUAL PURGE VO	GE (gal.) :	24,10
	ED: <u>06-12-9</u> 2 ED: <u>06-12-9</u> 2		16:00	End (2400 Hr) . End (2400 Hr) .	
TIME (2400 Hr)	VOLUME pH (gal.) (units)	E.C. (μπhos/cm@ 25° C	TEMPERATURE		TURBIDITY
1 ''		/2 <i>8</i> 5	68.4	(visual) CKB4	(visual) HEMOC
1613	10 698			<u>d</u>	2
11:00	Porto and Arriva	1000			
16:35	Lectrarge 7/10		65,4	<u>CKAU</u>	1/2007
D. O. (ppm):	h.	ODOR: STROA		<u>/k/K</u> (COBALT 0 - 100)	(NTU 0 - 200)
FIELD QC SAM	MPLES COLLECTED AT THI	S WELL (i.e. FB-1, XD	UP-1):	·	 .
1	PURGING EQUIPMENT		SAMPLIN	G EQUIPMENT	
2* Bladder	r Pump — Bailer (Te		2° Bladder Pump	Bailer	(Teffon®)
—— Centrifuga		•	DDL Sampler		(Stainless Steel)
Submersit Well Wiza	,	·	— Dipper — Well Wizard™		ersible Pump
Other:			:	—— Dedica	Della
WELL INTEGRIT	v. Good		<u></u>	1004 # 7	12 EG
	RIED AFFER 12				
HEMARKS: ———		1340200 10			
. <u> </u>		<u></u>			
	: Date: Time:				
	/ <u>(((()</u> (DI)()	_) (pH 10 <u>lØØ<i>O l [l</i>Ø</u>	<u>7.00</u>) (pH 4 <u>3°</u>	19/
	ous calibration: Mu-				
Signature:	hellen	Review	ed By:	Page <i>ပ</i>	of 9

EMC	ON

PROJECT NO: 670-17:01 SAMPLE ID: MW-11	
EMCON PURGED BY: M. C. LLCG J. WILLIAM CLIENT NAME: ARCOTT 71	
SAMPLED BY: 5 W. Marker 2 LOCATION: Liver more.	
TYPE: Ground Water Surface Water Treatment Effluent Other	
CASING DIAMETER (inches): 2 4 4.5 6 Other	
CASING ELEVATION (feet/MSL): DEPTH TO WATER (feet): 34.48 DEPTH OF WELL (feet): 38.40 ACTUAL PURGE VOL. (gal.): 2.4	
DATE PURGED: (e-12-97. Start (2400 Hr) 12 2 4 End (2400 Hr) 12 3 7 DATE SAMPLED: (e-12-92. Start (2400 Hr) End (2400 Hr) End (2400 Hr) 12 19 2	
TIME (2400 Hr) (gal.) (units) (units) (unhos/cm@25°C) (°F) (visual) (visual) (visual) (2:26)
12:30 2,4 7,89 1028 62.6 L L 3.EDRY 12:44 4 Rechange 7.40 1223 67.8 BROWN MERU D. O. (ppm): NR ODOR: Abaz NR NR	14
(COBALT 0 - 100) (NTU 0 - 2 FIELD QC SAMPLES COLLECTED AT THIS WELL (i.e. FB-1, XDUP-1):	00)
PURGING EQUIPMENT SAMPLING EQUIPMENT	
2° Bladder Pump Bailer (Teflon®) 2° Bladder Pump Bailer (Teflon®) Bailer (Teflon®) Bailer (Stainless Stories Bailer (Stainless Bailer (Stainless Bailer (Stainless Bailer (Stainless	
Centrifugal PumpX Bailer (PVC) DDL Sampler Bailer (Stainless Steel) Dipper Submersible Pump	
— Well Wizard™ — Dedicated — Well Wizard™ — Dedicated Other:	
WELL INTEGRITY: Cood. REMARKS: DRIED After 2.4 GALLOW Time 13:31	
	<u> </u>
Meter Calibration: Date: Time: Meter Serial #: Temperature °F: (EC 1000/) (DI) (pH 7) (pH 10/) (pH 4/)	
Location of previous calibration: Ra-/	
Signature: 71 Reviewed By: 1B Page 9 of 9	} _

TF NUMBER: 1047

GIB-92-056

MONITORING WELL PURGE WATER TRANSPORT FORM

	GENERATOR IN	FORMATION					
	NAME:	ARCO PRODUCTS HECEIVED					
ADDRESS: P.O. BO		P.O. BOX 5811	O. BOX 5811 JUL 3 0 1992				
	CITY, STATE, ZIP: SAN MATEO,		94402 RESNA PHONE #: (415) 571-243	34			
SITES, AUGER RENSATE G THE WATER MAY CONTAI THE GENERATOR CERTIFIES THAT THIS WATER			D DURING SAMPLING OR DEVELOPMENT OF MONITORING WELLS LOCATED AT VARIOUS ENERATED DURING THE INSTALLATION OF MONITORING WELLS AT VARIOUS SITES. IN DISSOLVED HYDROCARBONS.	2-92 (Date)			
	AS DESCRIBED IS NON-HAZARD						
	SITE INFORMA' STA#	JOB#	ADDRESS	GALS			
1	A-697	20598&20665	420W. SHAW AVE., FRESNO, CA	58			
2	A-335	20597-PW	4595 E. CLINTON ST., FRESNO, CA	5			
3	A-6100	20717-DW	25775 SO. PATTERSON PASS RD., TRACY, CA	102			
4	A-771	20656-PW	899 RINCON AVE., LIVERMORE, CA	90			
5	A-6041	20657-PW	7249 VILLAGE PARKWAY, DUBLIN, CA	31			
6	A-5387	20655-PW	20200 HESPERIAN BLVD., SAN LORENZO, CA	187			
7	A-761	20599-PW	1985 BROADWAY AVE., VALLEJO, CA	109			
8	A-2035	20659-PW	1001 SAN PABLO AVE., ALBANY, CA	165			
9	A-414	20660-PW	5000 SHATTUCK AVE., BERKELEY, CA	80			
10	A-6148	20658-PW	5131 SHATTUCK AVE., OAKLAND, CA	54			
			TOTAL GALLONS:	881			
	TRANSPORTER	INFORMATIO	N				
	NAME:	BALCH PETROL	EUM				
	ADDRESS: 930 AMES A CITY, STATE, ZIP: MILPITAS, 0						
			5035 PHONE #: (408) 942-868	66			
	TRUCK ID #:	PETERBILT	(Typed or printed full name & signature)	(Date)			
	TSD FACILITY	INFORMATION	V				
	NAME:	GIBSON OIL & R	EFINING				
	ADDRESS:	475 SEAPORT BI	VD				
	CITY, STATE, ZIP:	REDWOOD CITY	PHONE #: (415) 368-553	1			
	RELEASE #:	11320	(Typed or printed full name & signature)	7-2-92 (Date)			
	and the second		/-/I				

GORIIOU