

December 1, 2003

Alameda County
DEC 01 2003
Environmental Health

GROUNDWATER MONITORING REPORT
4th Quarter, 2003

245 8th Street
Oakland, California

Project No. 4332

Prepared For

Mr. Vic Lum
Vic's Automotive
245 8th Street
Oakland, CA 94607

Prepared By

AEI Consultants
2500 Camino Diablo Blvd., Suite 200
Walnut Creek, CA 94597
(925) 283-6000

AEI



December 1, 2003

Mr. Vic Lum
Vic's Automotive
245 8th Street
Oakland, CA 94607

**Subject: Quarterly Groundwater Monitoring Report
4th Quarter, 2003
245 8th Street
Oakland, California
Project No. 4332**

Dear Mr. Lum:

AEI Consultants (AEI) has prepared this report on your behalf to document the continued groundwater investigation at the above referenced site (Figure 1: Site Location Map). This work is being performed in accordance with the requirements of the Alameda County Health Care Services Agency (ACHCSA) to document the groundwater quality and free product recovery associated with the release of fuel hydrocarbons from the former underground storage tank system. This report presents the findings of the 4th quarter, 2003 episode of groundwater monitoring and sampling for the four onsite wells conducted on November 3, 2003.

Site Description and Background

The subject property (hereafter referred to as the "site" or "property") is located in a commercial and residential area of Oakland. The site is a lot on the south corner of Alice Street and 8th Street, and is currently developed with a gasoline station and auto repair facility. Refer to Figure 2 for a visual description of the site.

Between June 1993 and August 1994, AEI removed a total of seven (7) underground storage tanks (USTs) from the property. The tanks consisted of four (4) 1,000 gallon and two (2) 6,000 gallon gasoline tanks and one (1) 250 gallon waste oil tank. The former locations of the tanks are shown on Figure 2. Impacted soil was removed from beneath the former tank area. Groundwater was encountered beneath the former 6,000 gallon tanks. Light non-aqueous phase liquid (LNAPL) was observed on the water table beneath the southern tank. The excavated soil was transported to an appropriate disposal facility and the excavation was backfilled with clean fill material. A new tank system was installed just west of the dispenser island.

Two groundwater monitoring wells (MW-1 and MW-2) were installed in July 1995. The first two episodes of monitoring revealed total petroleum hydrocarbons as gasoline (TPH-g) and benzene up to 210,000 µg/l and 720 µg/l, respectively, in MW-2. Floating gasoline product, a LNAPL, was

discovered in MW-1, which ranged from 1.20 to 4.39 feet thick between December 1995 and March 1996.

Three soil borings (SB-1 through SB-3) were advanced in August 1996. Groundwater samples collected from each of the borings contained TPH-g and benzene ranging from 120,000 to 140,000 µg/l, and from 12,000 to 19,000 µg/l, respectively. Methyl tertiary-butyl ether (MTBE) was also present in all three samples, up to 27,000 µg/l. Although free product was not observed in the field, qualitative laboratory observations indicated immiscible sheen. Manual bailing and pumping of NAPL from MW-1, and monitoring of MW-2 occurred intermittently through 1997.

Two additional groundwater monitoring wells (MW-3 and MW-4) were installed in May 2001. Refer to Tables 1 and 2 for data collected from these wells. A free product recovery pump was installed in MW-1 in June 2001.

This report documents the results of the 10th episode of groundwater monitoring and sample collection of the four wells performed at the site.

Summary of Monitoring Activities

Monitoring of water and product levels and sample collection occurred on November 3, 2003. The well locations are shown in Figure 2. The depth to static groundwater from the top of the well casings was measured prior to sampling with an electric water level indicator. A floating product interface meter was used in MW-1 and MW-2. The three wells with no measurable thickness of floating product (MW-2 through MW-4) were purged using a battery powered submersible pump, and groundwater samples were collected from the wells using clean, disposable plastic bailers.

Temperature, pH, dissolved oxygen (DO), oxidation-reduction potential (ORP), and specific conductivity were measured and the turbidity was visually noted during the purging of the wells. Approximately three well volumes of water were purged from each well prior to sample collection. Once the above parameters had stabilized, and the wells were allowed to recharge to a minimum of 90% of their original water volume, a water sample was collected.

Water was poured from the bailers into two 40 ml volatile organic analysis (VOA) vials and capped so no head space or air bubbles were visible within the sample containers. Samples were shipped on ice under proper chain of custody protocol to McCampbell Analytical, Inc. of Pacheco, California (Department of Health Services Certification #1644).

The three groundwater samples collected were analyzed for TPH-g (EPA method 8015C), benzene, toluene, ethylbenzene, and xylenes (BTEX) (EPA method 8021B), and MTBE (EPA method 8021B).

Field Results

Well MW-1 had approximately 1.27 feet of LNAPL when measured with an interface meter, which was consistent with values measured the previous quarter. For this reason, no samples were collected from MW-1, and the depth to water reading was not used in the calculation of groundwater flow direction and gradient. No measurable thickness of free product was apparent using an interface meter in any of the remaining wells.

Groundwater levels for the current monitoring episode ranged from 11.29 to 12.06 feet above mean sea level (msl) in the three wells (MW-2 through MW-4). These groundwater elevations were an average of 0.63 feet lower than the previous monitoring episode. The slight decrease in water table elevation appears to be a seasonal occurrence. The groundwater flow direction at the time of measurement was south-southeast. The hydraulic gradient of the water table was 0.006 ft/ft, which is similar to the previous episode.

Groundwater elevation data are summarized in Table 1. The water table contours and the groundwater flow direction are depicted in Figure 2. Refer to Appendix B for the Groundwater Monitoring Well Field Sampling Forms.

Groundwater Quality

Hydrocarbon concentrations in the wells sampled remained highest in MW-2, as they have been for the previous nine monitoring events. TPH-g, MTBE, and benzene were detected at 120,000 micrograms per liter ($\mu\text{g/l}$), 24,000 $\mu\text{g/l}$, and 33,000 $\mu\text{g/l}$, respectively, in this well. Contaminant of concern concentrations remained at levels comparable to the previous (8/3/2003) monitoring event. A decrease in all contaminant of concern concentrations was detected in wells MW-3 and MW-4. A summary of groundwater quality data is presented in Table 2. Laboratory results and chain of custody documents are included in Appendix C.

Conclusions

A slight increase in apparent free product thickness was observed in well MW-1 this episode. Following the additional soil and groundwater investigation and the recent quarterly groundwater monitoring event, active site remediation may be necessary in the near future.


Quarterly groundwater monitoring will continue and the next episode is scheduled for February 2003.

Report Limitations and Signatures


This report presents a summary of work completed by AEI Consultants, including observations and descriptions of site conditions. Where appropriate, it includes analytical results for samples taken during the course of the work. The number and location of samples are chosen to provide required information, but it cannot be assumed that they are entirely representative of all areas not sampled. All conclusions and recommendations are based on these analyses, observations, and the governing regulations. Conclusions beyond those stated and reported herein should not be inferred from this document.

These services were performed in accordance with generally accepted practices in the environmental engineering and construction field that existed at the time and location of the work.

Sincerely,
AEI Consultants



Jeff Rosenberg
Project Engineer



Robert F. Flory, R.G.
Senior Geologist



Figures

- Figure 1 Site Location Map
- Figure 2 Site Plan with Water Table Contours
- Figure 3 Site Plan with Dissolved Hydrocarbons

Appendix A

- Table 1 Groundwater Elevation Data
- Table 2 Groundwater Sample Analytical Data

Appendix B Well Field Sampling Forms

Appendix C Laboratory Reports With Chain of Custody Documentation

cc: Mr. Barney Chan
ACHCSA
1131 Harbor Bay Parkway, Suite 250
Alameda, CA 94502




TN MN
15°



Printed from TOPO! ©2001 National Geographic Holdings (www.topo.com)

AEI CONSULTANTS 2500 CAMINO DIABLO BLVD, STE 200, WALNUT CREEK	
SITE LOCATION MAP	
245 8 th STREET OAKLAND, CALIFORNIA	FIGURE 1 PROJECT No. 4332




SCALE: 1 inch = 25 feet

0 12.5 25

AEI CONSULTANTS
2500 CAMINO DIABLO BLVD, STE 200, WALNUT CREEK, CA

WATER TABLE CONTOURS


245 8th STREET OAKLAND, CALIFORNIA	FIGURE 2 PROJECT NO. 4332
---------------------------------------	-------------------------------------



- MONITORING WELLS WITH WATER TABLE ELEVATIONS EXPRESSED IN FEET ABOVE MEAN SEA LEVEL (FP = Floating Product)
- SCALE: 1 in = 25 ft

12.8

WATER TABLE CONTOURS WITH ELEVATIONS ABOVE SEA LEVEL. CONTOUR INTERVAL IS 0.05 FEET (drawn with Surfer V.7.0) Well MW-1 not used in calculating groundwater flow direction or gradient




AEI CONSULTANTS
2500 CAMINO DIABLO BLVD, STE 200, WALNUT CREEK, CA

DISSOLVED HYDROCARBONS

245 8th STREET
OAKLAND, CALIFORNIA

FIGURE 3
PROJECT NO. 4332



SCALE: 1 inch = 25 feet
0 12.5 25

● MONITORING WELLS:
HYDROCARBON CONCENTRATION
EXPRESSED IN ug/l IN WATER

SCALE: 1 in = 25 ft

TPHg = Total Petroleum Hydrocarbons
as gasoline
MTBE = Methyl tert-Butyl Ether
FP = Floating Product (LNAPL)

Table 1
Groundwater Elevation Data

Well ID	Date Collected	Well Elevation (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)
MW-1	6/29/2001	27.73	16.52	*	14.89	1.63
	10/10/2001	27.73	15.45	*	15.37	0.08
	1/9/2002	27.73	12.61	15.12*	-	<0.01
	4/24/2002	27.73	13.35	14.38*	-	<0.01
	7/24/2002	27.73	14.19	13.44*	-	<0.01
	11/5/2002	27.73	14.85	12.88*	-	<0.01
	2/4/2003	27.73	14.91	12.82*	-	<0.01
	5/2/2003	27.73	14.43	13.30*	-	0.08
	8/4/2003	27.73	15.24	12.49*	15.01	0.23
	11/3/2003	27.73	16.94	10.79*	15.67	1.27
MW-2	6/29/2001	28.16	16.14	12.02	-	-
	10/10/2001	28.16	16.43	11.73	-	-
	1/9/2002	28.16	13.50	14.66	-	-
	4/24/2002	28.16	14.40	13.76	-	-
	7/24/2002	28.16	14.91	13.25	-	-
	11/5/2002	28.16	16.96	11.20	-	-
	2/4/2003	28.16	15.42	12.74	-	-
	5/2/2003	28.16	15.24	12.92	-	-
	8/4/2003	28.16	15.98	12.18	-	-
	11/3/2003	28.16	16.60	11.56	-	Sheen
MW-3	6/29/2001	29.21	16.60	12.61	-	-
	10/10/2001	29.21	16.92	12.29	-	-
	1/9/2002	29.21	14.20	15.01	-	-
	4/24/2002	29.21	15.07	14.14	-	-
	7/24/2002	29.21	16.40	12.81	-	-
	11/5/2002	29.21	16.47	12.74	-	-
	2/4/2003	29.21	16.92	12.29	-	-
	5/2/2003	29.21	15.45	13.76	-	-
	8/4/2003	29.21	16.46	12.75	-	-
	11/3/2003	29.21	17.15	12.06	-	-
MW-4	6/29/2001	29.38	17.71	11.67	-	-
	10/10/2001	29.38	18.00	11.38	-	-
	1/9/2002	29.38	15.02	14.36	-	-
	4/24/2002	29.38	15.74	13.64	-	-
	7/24/2002	29.38	16.69	12.69	-	-
	11/5/2002	29.38	17.64	11.74	-	-
	2/4/2003	29.38	16.02	13.36	-	-
	5/2/2003	29.38	16.72	12.66	-	-
	8/4/2003	29.38	17.51	11.87	-	-
	11/3/2003	29.38	18.09	11.29	-	-

Episode #	Date	Average Water Table Elevation**	Change from Previous Episode	Flow direction (gradient)
1	6/29/2001	12.10	-	SSE (0.0074)
2	10/10/2001	11.80	-0.30	SSE (0.0071)
3	1/9/2002	14.68	2.88	SE (0.0054)
4	4/24/2002	13.85	-0.83	SSW (0.005)
5	7/24/2002	12.92	-0.93	NE (0.021)
6	11/5/2002	11.89	-1.02	SW (0.019)
7	2/4/2003	12.80	0.90	NNW (0.01)
8	5/2/2003	13.11	0.32	SSE (0.01)
9	8/4/2003	12.27	-0.85	SSE(0.007)
10	11/3/2003	11.64	-0.63	SSE (0.006)

LNAPL = light non-aqueous phase liquid (floating free product)

* = Measured groundwater level affected by LNAPL and/or pump presence, not used to calculate water table elevation

All well elevations are measured from the top of the casing

- = not applicable

ft amsl = feet above mean sea level

Note = Historical groundwater elevation and quality data for wells MW-1 and MW-2 was not available

Table 2
Groundwater Sample Analytical Data

Well/Sample ID	Date Collected	Apparent LNAPL thickness (ft)	TPHg $\mu\text{g/L}$	MTBE $\mu\text{g/L}$	Benzene $\mu\text{g/L}$	Toluene $\mu\text{g/L}$	Ethylbenzene $\mu\text{g/L}$	Xylenes $\mu\text{g/L}$
MW-1	6/29/2001	1.63	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	10/10/2001	0.08	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	1/9/2002	<0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	4/24/2002	<0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	7/24/2002	-0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/5/2002	-0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/4/2003	-0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/2/2003	0.08	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/4/2003	0.23	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/3/2003	-0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
MW-2	6/29/2001	0.0	69,000	4100/4400*	7,200	6,100	1,500	7,000
	10/10/2001	0.0	87,000	14,000	22,000	12,000	2,700	9,100
	1/9/2002	0.0	130,000	11,000	30,000	19,000	3,800	14,000
	4/24/2002	Sheen	210,000	32,000	38,000	23,000	4,600	19,000
	7/24/2002	Sheen	170,000	36,000	48,000	12,000	3,700	8,600
	11/5/2002	Sheen	190,000	36,000	45,000	25,000	4,600	16,000
	2/4/2003	Sheen	150,000	27,000	51,000	24,000	4,200	14,000
	5/2/2003	Sheen	150,000	35,000	39,000	11,000	3,800	9,900
	8/4/2003	Sheen	120,000	29,000	32,000	5,000	3,200	7,200
	11/3/2003	Sheen	120,000	24,000	33,000	4,300	3,200	5,400
MW-3	6/29/2001	0.0	550	ND<5.0	ND<0.5	3.1	3.2	1.2
	10/10/2001	0.0	470	ND<5.0	0.77	5.3	3.3	5.9
	1/9/2002	0.0	1,000	ND<5.0	0.90	7.6	7.8	25
	4/24/2002	0.0	1,500	ND<5.0	0.64	7.2	12	14
	7/24/2002	0.0	1,200	ND<5.0	10	17.0	11	25
	11/5/2002	0.0	1,800	ND<25	33	43.0	18	31
	2/4/2003	0.0	450	ND<5.0	ND<0.5	5.0	ND<0.5	0.77
	5/2/2003	0.0	340	ND<5.0	7.3	10.0	2.5	7.3
	8/4/2003	Sheen	170	ND<5.0	5.8	5.9	1.5	4.9
	11/3/2003	0.0	54	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
MW-4	6/29/2001	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/10/2001	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	1/9/2002	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	4/24/2002	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	7/24/2002	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	11/5/2002	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	2/4/2003	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	5/2/2003	0.0	500	10	68	71	18	65
	8/4/2003	Sheen	270	ND<5.0	30	29	9.2	32
	11/3/2003	0.0	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5

$\mu\text{g/L}$ micrograms per liter

TPHg total petroleum hydrocarbons as gasoline

MTBE methyl tertiary butyl ether

* samples re-analyzed by EPA Method 8260 (expressed as EPA 8020 / EPA 8260)

ns/fp = not sampled / free product

ND = not detected

Please refer to Appendix B: Lab Results for further detailed lab information including dilution factors

LNAPL = Light Non Aqueous Phase Liquid

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-1

Project Name:	Vic's Automotive	Date of Sampling:	11/3/2003
Job Number:	4332	Name of Sampler:	AN
Project Address:	245 8th Street, Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	4		
Wellhead Condition	OK		▼
Elevation of Top of Casing (feet above msl)	27.73		
Depth of Well	25.00		
Depth to Water (from top of casing)	16.94		
Depth to Free Product (from top of casing)	15.67		
Water Elevation (feet above msl)	10.79		
Well Volumes Purged			
Gallons Purged: formula valid only for casing sizes of 2" (.16 gal/ft), 4" (.65 gal/ft), and 6" (1.44 gal/ft)	0.0		
Actual Volume Purged (gallons)	na		
Appearance of Purge Water	na		
Free Product Present?	Yes	Thickness (ft):	1.27

GROUNDWATER SAMPLES

Number of Samples/Container Size				(2) 40mL VOA			
Time	Vol Removed (gal)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

well not sampled, free product present

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: **MW-2**

Project Name:	Vic's Automotive	Date of Sampling:	11/3/2003
Job Number:	4332	Name of Sampler:	AN
Project Address:	245 8th Street, Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK		▼
Elevation of Top of Casing (feet above msl)	28.16		
Depth of Well	25.00		
Depth to Water (from top of casing)	16.60		
Water Elevation (feet above msl)	11.56		
Well Volumes Purged	3		
Gallons Purged: formula valid only for casing sizes of 2" (.16 gal/ft), 4" (.65 gal/ft), and 6" (1.44 gal/ft)	4.0		
Actual Volume Purged (gallons)	6.0		
Appearance of Purge Water	dark gray initially, clear at 2.5 gallon, dark gray at 4 gallon		
Free Product Present?	yes	Thickness (ft):	sheen present

GROUNDWATER SAMPLES

Number of Samples/Container Size				(2) 40mL VOA			
Time	Vol Removed (gal)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
	2	18.43	6.70	1042	0.53	-239.1	
	4	18.38	6.64	983	0.24	-234.2	
	6	18.38	6.61	882	0.18	-230.1	

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

Strong hydrocarbon odor noted

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: **MW-3**

Project Name:	Vic's Automotive	Date of Sampling:	11/3/2003
Job Number:	4332	Name of Sampler:	AN
Project Address:	245 8th Street, Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	4		
Wellhead Condition	OK		
Elevation of Top of Casing (feet above msl)	29.21		
Depth of Well	25.00		
Depth to Water (from top of casing)	17.15		
Water Elevation (feet above msl)	12.06		
Well Volumes Purged	3		
Gallons Purged: formula valid only for casing sizes of 2" (.16 gal/ft), 4" (.65 gal/ft), and 6" (1.44 gal/ft)	15.3		
Actual Volume Purged (gallons)	18		
Appearance of Purge Water	gray initially, turned clear quickly, light gray @ 12.5 gallon		
Free Product Present?	No	Thickness (ft):	-

GROUNDWATER SAMPLES

Number of Samples/Container Size				(2) 40mL VOA			
Time	Vol Removed (gal)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
	3	20.28	7.19	237	0.75	-116.8	
	6	20.53	7.14	233	0.83	-113.9	
	9	20.61	7.05	238	0.60	-133.9	
	12	20.47	6.92	228	0.23	-164.5	
	15	20.36	6.89	200	0.18	-171.9	
	18	20.31	6.89	191	0.19	-165.4	

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

Slight hydrocarbon odor

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: **MW-4**

Project Name:	Vic's Automotive	Date of Sampling:	11/3/2003
Job Number:	4332	Name of Sampler:	AN
Project Address:	245 8th Street, Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	4	
Wellhead Condition	OK	▼
Elevation of Top of Casing (feet above msl)	29.38	
Depth of Well	25.00	
Depth to Water (from top of casing)	18.09	
Water Elevation (feet above msl)	11.29	
Well Volumes Purged	3	
Gallons Purged: formula valid only for casing sizes of 2" (.16 gal/ft), 4" (.65 gal/ft), and 6" (1.44 gal/ft)	13.5	
Actual Volume Purged (gallons)	15.0	
Appearance of Purge Water	light brown, clear at 1.5 gallon	
Free Product Present?	No	Thickness (ft): -

GROUNDWATER SAMPLES

Number of Samples/Container Size				(2) 40mL VOA			
Time	Vol Removed (gal)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
	3	18.79	6.88	355	1.76	-35.5	
	6	19.00	6.75	346	1.81	-31.9	
	9	18.91	6.56	377	1.76	-28.5	
	12	18.78	6.52	385	1.78	-28.5	
	15	18.74	6.51	395	1.75	-29.3	

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odor noted



McC Campbell Analytical Inc.

110 2nd Avenue South, #D7, Pacheco, CA 94553-5560

Telephone : 925-798-1620 Fax : 925-798-1622

http://www.mcccampbell.com E-mail: main@mcccampbell.com

All Environmental, Inc.

2500 Camino Diablo, Ste. #200

Walnut Creek, CA 94597

Client Project ID: #4332; (Lam's) Vic's
Auto

Client Contact: Peter McIntyre

Client P.O.:

Date Sampled: 11/03/03

Date Received: 11/03/03

Date Extracted: 11/05/03-11/07/03

Date Analyzed: 11/05/03-11/07/03

Gasoline Range (C6-C12) Volatile Hydrocarbons as Gasoline with BTEX and MTBE*

Extraction method: SW5030B

Analytical methods: SW8021B/8015Cm

Work Order: 0311015

Lab ID	Client ID	Matrix	TPH(g)	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes	DF	% SS
001A	MW-2	W	120,000,a	24,000	33,000	4300	3200	5400	500	109
002A	MW-3	W	54,b	ND	ND	ND	ND	ND	1	104
003A	MW-4	W	ND	ND	ND	ND	ND	ND	1	97.8


Reporting Limit for DF =1; ND means not detected at or above the reporting limit	W	50	5.0	0.5	0.5	0.5	0.5	0.5	1	µg/L
	S	NA	NA	NA	NA	NA	NA	NA	1	mg/Kg

* water and vapor samples and all TCLP & SPLP extracts are reported in ug/L, soil/sludge/solid samples in mg/kg, wipe samples in µg/wipe, product/oil/non-aqueous liquid samples in mg/L.

cluttered chromatogram; sample peak coelutes with surrogate peak.

+The following descriptions of the TPH chromatogram are cursory in nature and McC Campbell Analytical is not responsible for their interpretation: a) unmodified or weakly modified gasoline is significant; b) heavier gasoline range compounds are significant(aged gasoline?); c) lighter gasoline range compounds (the most mobile fraction) are significant; d) gasoline range compounds having broad chromatographic peaks are significant; biologically altered gasoline?; e) TPH pattern that does not appear to be derived from gasoline (stoddard solvent / mineral spirit?); f) one to a few isolated non-target peaks present; g) strongly aged gasoline or diesel range compounds are significant; h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~2 vol. % sediment; j) reporting limit raised due to high MTBE content; k) TPH pattern that does not appear to be derived from gasoline (aviation gas). m) no recognizable pattern.

DHS Certification No. 1644

 Angela Rydelius, Lab Manager



QC SUMMARY REPORT FOR SW8021B/8015Cm

Matrix: W

WorkOrder: 0311015

EPA Method: SW8021B/8015Cm		Extraction: SW5030B		BatchID: 9205			Spiked Sample ID: 0311028-001A			
	Sample	Spiked	MS*	MSD*	MS-MSD*	LCS	LCSD	LCS-LCSD	Acceptance Criteria (%)	
	µg/L	µg/L	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	Low	High
TPH(btex) [£]	ND	60	97	93.7	3.47	97.4	96.7	0.720	70	130
MTBE	ND	10	110	104	5.60	105	105	0	70	130
Benzene	ND	10	109	95.4	13.3	106	106	0	70	130
Toluene	ND	10	109	97.1	11.7	107	104	2.86	70	130
Ethylbenzene	ND	10	109	90.3	19.1	107	107	0	70	130
Xylenes	ND	30	110	103	6.25	110	110	0	70	130
%SS:	107	100	108	103	5.16	104	106	1.88	70	130

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:
 NONE

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 * (MS-Sample) / (Amount Spiked); RPD = 100 * (MS - MSD) / (MS + MSD) * 2.

* MS and / or MSD spike recoveries may not be near 100% or the RPDs near 0% if: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) if that specific sample matrix interferes with spike recovery.

£ TPH(btex) = sum of BTEX areas from the FID.

cluttered chromatogram; sample peak coelutes with surrogate peak.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.

0311015

McCAMPBELL ANALYTICAL INC.

110 2nd AVENUE SOUTH, HD7
 PACIFIC, CA 94553-5560
 Telephone: (925) 798-1620 Fax: (925) 798-1622

CHAIN OF CUSTODY RECORD

TURN AROUND TIME RUSH 24 HR 48 HR 72 HR 5 DAY
 EDF Required? Yes No

Report To: Peter McIntyre Bill To:
 Company: AEI Consultants
 2500 Camino Diablo, Suite 200
 Walnut Creek, CA 94597 E-Mail:
 Tele: () 925/283-6000 Fax: () 925/283-6121
 Project #: 4332 Project Name: (Lam's) Vic's Data
 Project Location: 245 8th St Oakland
 Sampler Signature: Adrian Nieto

Analysis Request												Other	Comments
BTEX & TPH as Gas (602/8020 + 8015) M/T/B/E													
TPH as Diesel (8015)													
Total Petroleum Oil & Grease (5520 E&F/B&F)													
Total Petroleum Hydrocarbons (418.1)													
EPA 601 / 8010													
BTEX ONLY (EPA 602 / 8020)													
EPA 608 / 8080													
EPA 608 / 8080 PCB's ONLY													
EPA 624 / 8240 / 8260													
EPA 625 / 8270													
PAH's / PNA's by EPA 625 / 8270 / 8310													
CAM-17 Metals													
LUFT 5 Metals													
Lead (7240/7421/239.2/6010)													
RCL													

SAMPLE ID (Field Point Name)	LOCATION	SAMPLING		# Containers	Type Containers	MATRIX					METHOD PRESERVED			
		Date	Time			Water	Soil	Air	Sludge	Other	Ice	HCl	HNO ₃	Other
+ MW-2		11/03/03	Pm	2	Vials	X					X	X		X
+ MW-3			Am			X					X	X		X
+ MW-4			Pm			X					X	X		X

Relinquished By: Adrian Nieto Date: 11/03 Time: 2:28 Received By: [Signature]
 Relinquished By: Date: Time: Received By:
 Relinquished By: Date: Time: Received By:

ICE/✓
 GOOD CONDITION ✓
 HEAD SPACE ABSENT ✓
 DECHLORINATED IN LAB ✓
 PRESERVATION APPROPRIATE ✓
 CONTAINERS PRESERVED IN LAB ✓
 VOAS O&G METALS OTHER

via: mail

McC Campbell Analytical Inc.



110 Second Avenue South, #D7
 Pacheco, CA 94553-5560
 (925) 798-1620

CHAIN-OF-CUSTODY RECORD

WorkOrder: 0311015

Client:

All Environmental, Inc.
 2500 Camino Diablo, Ste. #200
 Walnut Creek, CA 94597

TEL: (925) 283-6000
 FAX: (925) 283-6121
 Project No. #4332; (Lam's) Vic's Auto
 PO:

Date Received: 11/3/03
 Date Printed: 11/3/03

Sample ID	ClientSampID	Matrix	Collection Date	Hold	Requested Tests		
					G-MBTX_W		
0311015-001	MW-2	Water	11/3/03	<input type="checkbox"/>	A		
0311015-002	MW-3	Water	11/3/03	<input type="checkbox"/>	A		
0311015-003	MW-4	Water	11/3/03	<input type="checkbox"/>	A		

Prepared by: Melissa Valles

Comments:

NOTE: Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.