

RECEIVED

By dehloptoxic at 1:32 pm, Oct 11, 2006

September 29, 2006

**SOIL GAS PROBE
INSTALLATION & SAMPLING REPORT**

245 8th Street
Oakland, CA 94607

AEI Project No. 116907
ACEH Case No. RO0000202 / State ID 263

Prepared For:

Mr. Victor Lum
Vic's Automotive
245 8th Street
Oakland, CA 94607

Prepared By:

AEI Consultants
2500 Camino Diablo, Suite 200
Walnut Creek, CA 94597
(925) 283-6000

AEI

TABLE OF CONTENTS

1.0 INTRODUCTION	1
2.0 SITE DESCRIPTION AND BACKGROUND.....	1
3.0 GEOLOGY AND HYDROGEOLOGY.....	3
4.0 SOIL GAS PROBE INSTALLATION	3
4.1 Summary of Activities.....	3
4.2 Permits and Boring Clearances	4
4.3 Soil Gas Probe Construction / Installation	4
4.4 Analytical Methodology / Sample Analyses.....	5
4.5 Equipment Decontamination	5
4.6 Investigation Derived Waste Storage	5
5.0 SOIL GAS SAMPLING	5
5.1 Summary of Activities.....	5
5.2 Sampling Locations and Rationale	6
5.3 Soil Gas Sampling Protocol	6
5.3.1 Sample Flow Rate	7
5.3.2 Purge Volume	7
5.3.3 Leak Test.....	7
5.3.4 Sample Handling	7
5.4 Analytical Methodology / Sample Analyses.....	8
6.0 SOIL GAS AND SOIL SAMPLE ANALYTICAL RESULTS	8
6.1 Soil Sample Results.....	8
6.2 Soil Gas Sample Results.....	8
6.3 Leak Check Compound Results.....	9
7.0 SUMMARY AND RECOMMENDATIONS.....	9
8.0 REFERENCES	11
9.0 REPORT LIMITATIONS AND SIGNATURES	12

FIGURES

- 1 SITE LOCATION MAP
- 2 SITE PLAN
- 3 SOIL SAMPLE ANALYTICAL DATA (7/13/06)
- 4 SOIL GAS SAMPLE ANALYTICAL DATA (8/4/06)

TABLES

- 1 GROUNDWATER ELEVATION DATA
- 2 GROUNDWATER FLOW SUMMARY
- 3 GROUNDWATER SAMPLE ANALYTICAL DATA

- 4 SOIL SAMPLE ANALYTICAL DATA
- 5 SOIL GAS SAMPLE ANALYTICAL DATA
- 6 HISTORICAL SOIL SAMPLE ANALYTICAL DATA
- 7 HISTORICAL SOIL VAPOR SAMPLE ANALYTICAL DATA
- 8 SOIL BORING GROUNDWATER SAMPLE ANALYTICAL DATA
- 9 GROUNDWATER SAMPLE ANALYTICAL DATA: FUEL OXYGENATES

APPENDICES

- A** PERMIT DOCUMENTATION
- B** BORING LOGS
- C** SOIL GAS PROBE FIELD SAMPLING FORMS
- D** LABORATORY ANALYTICAL REPORTS WITH CHAIN OF CUSTODY DOCUMENTATION

1.0 INTRODUCTION

AEI Consultants (AEI) has prepared this report on behalf of Mr. Victor Lum of Vic's Automotive and documents the soil gas probe installation and sampling and ongoing soil gas investigation at the property located at 245 8th Street, Oakland, Alameda County, California (Figure 1). The investigation was initiated by the property owner in accordance with the requirements of Alameda County Environmental Health (ACEH) local oversight program. The purpose of this investigation is to monitor shallow soil gas concentrations associated with the release of fuel hydrocarbons from the former underground storage tank system. This report describes the installation of the soil gas probes and presents the findings of the first soil gas sampling episode conducted on August 4, 2006.

In a technical comment letter, dated March 20, 2006, ACEH requested the installation and sampling of permanent soil gas probes at the subject and adjacent properties to evaluate the potential for vapor intrusion into two residential buildings located at 712 and 718 Alice Street. At the request of ACEH, AEI submitted a *Soil Gas Investigation Workplan*, dated May 12, 2006, which outlined a scope of work for the installation and sampling of four (4) permanent soil gas probes.

A total of eight (8) temporary soil borings were advanced from which four (4) nested soil gas probes were constructed. A stainless steel soil gas implant was completed at 5 and 10 feet bgs at each of the four locations in order to assess the vertical attenuation of volatile organic compounds in the soil gas.

Soil gas probe installation and sampling was performed in accordance with the most recent *Advisory – Active Soil Gas Investigations (ASGI)*, dated January 28, 2003, jointly issued by the Department of Toxic Substances Control (DTSC) and Los Angeles Regional Water Quality Control Board (LARWQCB). Furthermore, evaluation and interpretation of the sampling results were performed in conformance with the DTSC's *Guidance for the Evaluation and Mitigation of Subsurface Vapor Intrusion to Indoor Air*, dated December 15, 2004 (revised February 7, 2005).

There were no significant deviations from the approved scope of work.

2.0 SITE DESCRIPTION AND BACKGROUND

The subject property (hereafter referred to as the “site” or “property”) is located in a mixed commercial and residential area of Oakland, Alameda County, California. The site is a single lot on the south corner of Alice Street and 8th Street, and is currently developed with a gasoline station and automotive repair facility (Figure 2). The property covers approximately 9,375 square feet and is improved with an approximately 1,200 square foot building located centrally on the property used for automotive repair, cashier, and office. The current UST hold and the dispenser island are located to the north of the building, along 8th Street. The remainder of the property is paved with asphalt.

Between June 1993 and August 1994, AEI removed a total of seven (7) underground storage tanks (USTs) from the property. The tanks consisted of four (4) 1,000-gallon and two (2) 6,000-gallon gasoline tanks and one (1) 250-gallon waste oil tank. The former locations of the tanks are shown on Figure 2. Impacted soil was removed from beneath the former tank area. Groundwater was encountered beneath the former 6,000-gallon tanks. Light non-aqueous phase liquid (LNAPL) was observed on the water table beneath the southern tank. The excavated soil was transported to an appropriate disposal facility and the excavation was backfilled with clean fill material. A new tank system was installed just west of the dispenser island.

Two groundwater monitoring wells (MW-1 and MW-2) were installed in July 1995. The first two episodes of monitoring revealed total petroleum hydrocarbons as gasoline (TPH-g) and Benzene up to 210,000 µg/L and 720 µg/L, respectively, in MW-2. LNAPL was discovered in MW-1, which ranged from 1.20 to 4.39 feet thick between December 1995 and March 1996.

Three soil borings (SB-1 through SB-3) were advanced in August 1996. Groundwater samples collected from each of the borings contained TPH-g and Benzene ranging from 120,000 to 140,000 µg/L, and from 12,000 to 19,000 µg/L, respectively. Methyl tertiary-butyl ether (MTBE) was also present in all three samples, up to 27,000 µg/L. Although free phase product was not observed in the field, qualitative laboratory observations indicated an immiscible sheen in the samples. Manual bailing and pumping of LNAPL from MW-1, and monitoring of MW-2 occurred intermittently through 1997.

Two additional groundwater monitoring wells (MW-3 and MW-4) were installed in May 2001. Refer to Tables 1 and 2 for data collected from these wells. A free product recovery pump was installed in MW-1 in June 2001.

Fourteen (14) additional soil borings were performed on and offsite in 2003, from which soil, groundwater, and soil vapor samples were collected to further characterize the extent of the release.

On January 11, 19, and 20, 2005, AEI installed a total of six (6) additional wells; three (3) extraction/monitoring wells on the subject site (MW-5 to MW-7) and three (3) extraction/monitoring wells at 708 Alice Street (MW-10 to MW-12). The locations of the six (6) additional wells (labeled MW-5 through MW-7 and MW-10 through MW-12) are shown on Figure 2. Note that wells MW-8 and MW-9 were proposed for installation in the public right of way, north of and west of the site. However, due to insurance and permitting limitations imposed by the City of Oakland, these wells were not been installed, and likely cannot be installed in City of Oakland right-of-way.

A high vacuum dual phase extraction (HVDPE) pilot test was performed at the site from July 11 to July 27, 2005, using wells MW-1 through MW-3 and MW-10 through MW-12. Vapor flow rates ranged from approximately 170 to 190 standard cubic feet per minute (scfm) under a sustained vacuum of 16 to 17 inches of mercury. Significant drawdown and vacuum response was observed in many of the monitoring points. A total of 80,740 gallons of water was recovered and treated for an average flow rate of about 4.1 gallons per minute over the 15-day

pilot test. Approximately 5 pounds per day of dissolved phase and 697 lbs/day of vapor phase hydrocarbons were recovered. Based on the favorable results, and following review and approval by ACEH, implementation of a fixed base HVDPE system is currently underway.

Surveying of the six new wells was complete as of January 2006.

3.0 GEOLOGY AND HYDROGEOLOGY

The elevation of the site is approximately 27 to 29 feet above mean sea level (amsl). The site is flat; however, the topography of the area slopes gently to the southwest. The site is located between Lake Merritt and the Oakland Inner Harbor channel, approximately one-half mile from each. The near surface sediments are mapped as Holocene and Pleistocene Merritt Sand Deposits (Qms) (Helley, et al, 1997). Depth to the Franciscan Formation basement underlying the unconsolidated deposits is approximately 400 feet (Norfleet, 1998).

Based on the logs of soil borings advanced at the site, the native soils generally consist of fine to medium grained sands with silt and clay present to at least 28 feet bgs, the deepest explored at the site. Typically, silty and clayey fine grained sand have been encountered to depths of 15 to 18 feet bgs. This is underlain by poorly graded, clean to slightly clayey and silty fine to medium sand. Both sand bodies represent a single hydrologic system. Sediments have been relatively uniform throughout the investigation area.

Groundwater depths have typically ranged from 13 to 17 feet bgs, corresponding to elevation of approximately 10 to 14 feet above mean sea level (msl). Annual water levels fluctuate by approximately 3 to 4 feet. Groundwater has consistently flowed to the south-southeast with a hydraulic gradient of approximately 10^{-3} ft/ft.

4.0 SOIL GAS PROBE INSTALLATION

4.1 Summary of Activities

On July 13, 2006, a total of eight (8) soil borings were advanced from which four (4) permanent nested soil gas probes (GP-1, GP-2, GP-3, and GP-4) were constructed. Borings were twinned at each probe location and a soil gas implant was completed at 5 and 10 feet bgs in each borehole in order to assess the vertical attenuation of volatile organic compounds in the soil gas. Please refer to Figure 2 for the soil gas probe locations.

Borings were advanced with a truck-mounted Geoprobe® Model 5410 direct push drilling machine equipped with the GH42 soil probing hammer running 2-inch nominal diameter probe rods and the DT21 dual tube continuous soil core sampler.

The direct push drilling work was performed by Vironex of San Leandro, California, a C57-

licensed drilling contractor working under the direction of an AEI project engineer. Vironex was the selected contractor because they have extensive experience in installing soil gas probes and performing soil gas surveys.

Continuous soil core samples were collected into 1.75-inch diameter clear glycol-modified polyethylene terephthalate (PETG) liners. Soil samples were cut from the PETG liners at minimum of 5-foot intervals, at lithologic breaks, and at the discretion of AEI's project engineer for field screening via olfactory and other sensory perceptions. Soil samples were sealed using Teflon[®] tape and plastic caps, and stored over water-ice pending transportation to the laboratory.

Duplicate samples were also collected into 1-Liter zipper locking bags for headspace analysis. These samples were screened in the field with a Mini-RAE Plus Classic (PGM-76) photoionization detector (PID). The PID is calibrated regularly in the office with standard 100 ppm isobutylene calibration gas prior to use in the field.

The borings were logged by an AEI project engineer according to the unified soil classification system (USCS). Please refer to Appendix B for detailed logs of the borings, including depth of samples collected.

4.2 Permits and Boring Clearances

Prior to commencing drilling activities, a soil boring installation permit (Permit #W2006-0625) was submitted and approved on June 22, 2006 by Mr. James Yoo of the Alameda County Public Works Agency. Copies of the permit documentation are included in Appendix A.

At least three days prior to drilling, the boring locations were marked with white paint and Underground Service Alert (USA) was notified for their members to identify any public utility conflicts in the work zone. The members' markings were also used to identify underground utilities, utility corridors, and other potential preferential pathways near the adjacent buildings. No significant preferential pathways were identified in the immediate vicinity of the work area during the drilling activities.

4.3 Soil Gas Probe Construction / Installation

Each soil gas probes was constructed of 1/4-inch outside diameter (O.D.), 1/8-inch inside diameter, Kynar[®] PolyVinylidene DiFluoride (PVDF) tubing with a 6-inch stainless steel screened implant attached to the end. The soil gas probes are nested constructions placed in twined boreholes (i.e., borings installed next to one another) advanced to final depths of 5 and 10 feet bgs, respectively.

The stainless steel implants attached to the 1/4-inch O.D. Kynar[®] tubing were installed down the open borehole once the probe rods were retracted and sampling barrel retrieved. Glass beads were poured down the open borehole to form a sand pack from the bottom to 1-foot above the stainless steel implant. Approximately 2-feet of dry bentonite chips were placed above the sand pack and

hydrated with water. The remainder of the boring was filled to 1/2-foot below grade with a mixture of bentonite and cement grout.

A 12-inch diameter raised well box was installed over the casing and cemented in place. A gas-tight Swagelok® ball valve was secured to the end of the ¼-inch tubing with gripping ferrules and a compression nut. The tubing was marked at the surface with white and red vinyl electrical tape to identify the probe depths of 5 and 10-feet, respectively. Color coded valve handles will be installed during the next soil gas sampling episode. Refer to Appendix B for the boring logs and the soil gas probe construction details.

4.4 Analytical Methodology / Sample Analyses

A total of eight (8) soil samples were transported on water-ice under proper chain of custody protocol to McCampbell Analytical, Inc. of Bay Point, California (Department of Health Services Certification (DHS) #1644). Samples were analyzed for TPH-g by Method SW8015Cm and for BTEX and MTBE by Method SW8021B. Laboratory procedures included appropriate quality assurance / quality control analyses, including method blanks and use of surrogates during sample analyses.

4.5 Equipment Decontamination

Probe rods, drive points, and other subsurface probing tools used to install the soil gas probes were decontaminated between installations with a triple rinse system. The triple rinse system consisted of cleaning the sample tools with Liquinox® or similar detergent, followed by a rinsing with clean tap water, and a second rinsing with tap water.

4.6 Investigation Derived Waste Storage

Investigation derived wastes (IDWs) generated during the drilling activities, such as soil cuttings and rinsate, were containerized in sealed 55-gallon drums. The drums were labeled appropriately and secured onsite pending the results of the sample analyses. Upon receipt of the necessary analytical data, the waste will be profiled for proper disposal. IDWs will be handled and disposed of in accordance with all applicable federal, state, and local requirements.

5.0 SOIL GAS SAMPLING

5.1 Summary of Activities

On August 4, 2006, soil gas samples were collected from soil gas probe GP-1 through GP-4, at two depths, 5 feet bgs and 10 feet bgs.

After the probes were adequately purged of three well volumes using a dedicated 6-L purge canister, soil gas samples were collected into laboratory-evacuated 1-L Summa™ canisters pending transportation to the laboratory. A flow control regulator affixed with a vacuum gauge was placed inline between the soil gas probe and Summa™ canister to ensure that it was filled at a constant rate of 100 to 200 milliliters per minute (mL/min) as recommend by the ASGI.

The soil gas sample analysis was performed by Air Toxics, Ltd. of Folsom, California, a DHS-certified laboratory. Air Toxics was the selected laboratory because they have extensive experience in soil gas sample methodology and analyses according to the ASGI guidelines.

5.2 Sampling Locations and Rationale

Soil gas probes were installed and soil gas samples were collected from the more permeable and most-impacted depth in the unsaturated zone, which may contain highest vapor phase contaminant concentrations. Exhibit 1 below summarizes the soil gas probe installation locations and the rationale behind selecting these locations, which were approved by ACEH in the workplan.

EXHIBIT 1: SOIL GAS PROBE LOCATIONS

Boring ID	Location	Purpose
GP-1	Western corner of subject property E-SE of MW-6	Investigate soil gas concentrations closest to the former source areas and near the front of 718 Alice Street
GP-2	Southern portion of property E-SE of MW-2 near the rear corner of 718 Alice Street	Investigate soil gas concentrations furthest away from the former source areas and near the rear of 718 Alice Street
GP-3	Southern corner of 712 Alice Street E-SE of MW-12	Investigate soil gas concentrations offsite near the rear of 712 Alice Street
GP-4	Southeastern corner of 712 Alice Street N-NE of MW-11	Investigate soil gas concentrations offsite near the front of 712 Alice Street

5.3 Soil Gas Sampling Protocol

Soil gas probe installation and sampling was performed in accordance with the currently accepted protocols of the state and local regulatory oversight agencies and the standards and practices of the environmental engineering and geology fields that existed at the time and location of the subject work.

Specifically, soil gas sampling was performed in accordance with the most recent *Advisory – Active Soil Gas Investigations* (ASGI), dated January 28, 2003, jointly issued by the Department of Toxic Substances Control (DTSC) and Los Angeles Regional Water Quality Control Board

(LARWQCB). The sampling flow rate, purge volume, leak testing, sample handling, analytical methodology, and sample analyses are discussed in more detail below.

5.3.1 Sample Flow Rate

Critical orifice flow controllers designed and provided by Air Toxics were used to regulate the flow of air during sampling. The evacuated Summa™ canisters were filled at a constant rate of 167 milliliters per minute (mL/min), within the 100 to 200 mL/min flow range as recommended by the ASGI. A new or laboratory-certified clean flow controller was used at each sampling point. Low or no flow conditions were not encountered.

5.3.2 Purge Volume

Prior to sample collection, the soil gas probes were purged of three (3) dead volumes or air using a 6-L Summa™ dedicated purge canister. A default value of three purge volumes was selected based on a phone conversation with Mr. Jerry Wickham of ACEH in late July 2006. This helped to ensure that a sufficient volume of ambient air was removed from the sampling point and that samples collected were representative of subsurface conditions. The purge volume was calculated by summing the volume of the sample tubing and annular space around the probe tip. One purge volume for the 5 and 10-foot probes are 16.1 and 27.6 mL, respectively. Three default purge volumes for the 5 and 10-foot probes are 48.3 and 82.8 mL, respectively. Therefore, to adequately purge the 5 and 10 foot probes (at 167 mL/min) it took approximately 18 and 30 seconds, respectively.

5.3.3 Leak Test

A rag moistened with the leak check compound, isopropyl alcohol, was placed inside the well box where the soil gas tubing the grout seal meet. A leak test dome made of a 12-inch round plastic bowl was then placed upside-down over the top of the well box and secured using the well box lid. Cotton strips moistened with isopropyl alcohol were placed around the Swagelok® valves, fittings, connections, and other potential leak points. To avoid possible cross contamination, the isopropyl alcohol leak check compound was stored separately from the other sampling tools in a zipper locking bag.

5.3.4 Sample Handling

Soil gas samples collected in Summa™ canisters were not chilled nor shipped by air in order to avoid drastic changes in ambient pressure and temperature. The soil gas samples were labeled with unique identifiers, recorded on the chain of custody record, and shipped via ground under proper chain of custody protocol to Air Toxics Ltd. of Folsom, California (DHS Certification #02110CA) for analysis.

5.4 Analytical Methodology / Sample Analyses

A total of nine (9) soil gas samples, including one field duplicate (GP-4-10D) were shipped via UPS ground under proper chain of custody protocol to Air Toxics, Ltd. of Folsom, California (Department of Health Services Certification #02110CA). Samples were analyzed for TPH-g by EPA Method Modified TO-3 and for volatile organic compounds (VOCs), including BTEX and MTBE by EPA Method Modified TO-15 along with the 2-Propanol leak check compound. Laboratory procedures included appropriate quality assurance and quality control analyses, including method blanks and use of surrogates during sample analyses. According to Air Toxics, the analytical equipment was calibrated in conformance with the most current ASGI and the modified analytical method(s).

6.0 SOIL GAS AND SOIL SAMPLE ANALYTICAL RESULTS

6.1 Soil Sample Results

From each boring, a soil sample collected at 5 and 10 feet bgs was analyzed for TPH-g by Method SW8015Cm and BTEX and MTBE by Method SW8021B.

No concentrations of fuel hydrocarbons or MTBE were detected above the laboratory reporting limits in any of the samples, except GP-4-10. TPH-g was detected at a concentration of 1.6 milligrams per kilogram (mg/kg) of soil. Benzene, toluene, ethylbenzene, and total xylenes were detected at concentrations of 0.049, 0.060, 0.019, and 0.079 mg/kg, respectively. MTBE was not detected above the laboratory reporting limits of 0.05 mg/kg.

The soil sample analytical data is summarized in Table 4. Laboratory analytical reports and chain of custody documentation are included in Appendix D.

6.2 Soil Gas Sample Results

From each soil gas probe, a soil gas sample collected from 5 and 10 feet bgs was analyzed for TPH-g by EPA Method Modified TO-3 and VOCs, including BTEX and MTBE, by EPA Method Modified TO-15.

The highest concentrations of fuel hydrocarbons (TPH-g) were detected in GP-4-5' and GP-4-10' at concentrations of 705 $\mu\text{g}/\text{m}^3$ and 564 $\mu\text{g}/\text{m}^3$, respectively.

TPH-g was detected in all other samples, excluding GP-3-5', at concentrations up to 564 $\mu\text{g}/\text{m}^3$.

Benzene was detected in only two samples, GP-4-5' and GP-4-10' at concentrations of 5.4 $\mu\text{g}/\text{m}^3$ and 6.1 $\mu\text{g}/\text{m}^3$, respectively. Toluene was detected in samples GP-2-5', GP-2-10', and GP-4-10' at concentrations up to 18 $\mu\text{g}/\text{m}^3$. Ethylbenzene was detected in only one sample, GP-4-10', at a

concentration of 5.7 µg/m³. Xylenes was detected in GP-2-5' and GP-4-10' at concentrations of 10 µg/m³ and 16 µg/m³, respectively.

Carbon disulfide was detected in all the samples, excluding GP-3-5', at concentrations up to 270 µg/m³. 2-Butanone (MEK) was detected six samples, at concentrations up to 11 µg/m³.

In addition, tetrachloroethene (PCE) was detected in four samples, at concentrations up to 600 µg/m³ (GP-2-5').

A summary of soil gas sample analytical data is presented in Table 4 and on Figure 4. Laboratory analytical reports and chain of custody documentation are included in Appendix B.

6.3 Leak Check Compound Results

The leak check compound isopropyl alcohol (i.e., 2-Propanol) was detected slightly above reporting limits in only one sample, GP-1-5'. 2-Propanol was detected in GP-1-5' at a concentration of 23 µg/m³. However, this does not necessarily indicate a leak occurred in the soil gas sampling train. Low levels, parts per billion (ppb) or sub-ppb, of leak check compound can be detected as the result of diffusion through the walls of the soil gas probe tubing (Air Toxics, 2006).

While detection of 23 ug/L is not considered to be significant, detection of leak check compound in excess of 100 ug/L may indicate a leak. If this were to occur, prompt review of the data and further evaluation of the sampling train integrity, and possibly re-sampling would be necessary (Missouri DNR, April 2005).

The soil gas sample analytical data is summarized in Table 5. Laboratory analytical reports and chain of custody documentation are included in Appendix D.

7.0 SUMMARY AND RECOMMENDATIONS

This investigation was designed to evaluate the potential for vapor intrusion into two residential buildings located at 712 and 718 Alice Street, Oakland, Alameda County, California and presents the findings of the first soil gas sampling event conducted at the subject property.

TPH-g along with other gasoline constituents (BTEX) were detected all of the soil gas samples with the exception of GP-3-5'. However, the concentrations of fuel hydrocarbons detected in the soil gas samples were all well below the shallow soil gas Environmental Screening Levels (ESLs) and the California Human Health Screening Levels (CHHSLs) for residential land use.

While no elevated levels of fuel hydrocarbons (TPH-g or BTEX), MTBE, or other fuel oxygenates were detected in the soil gas samples collected from GP-1 to GP-4, PCE was detected for the first time on the site in four of the eight soil gas samples. PCE was detected in one of the soil gas samples, GP-2-5', at a concentration of 600 ug/m³. This exceeded the shallow soil gas ESL and

CHHSL of $410 \mu\text{g}/\text{m}^3$ and $180 \mu\text{g}/\text{m}^3$, respectively for residential land use.

Possible sources of the elevated levels of PCE may be the former waste oil tanks onsite or possibly an up-gradient current or former dry cleaning facility.

Based on the results of this investigation AEI recommends the following:

- Sample and monitor the soil gas probes (GP-1 through GP-4) on a quarterly basis and report the results in conjunction with quarterly groundwater monitoring reports with the next soil gas sampling episode schedule for early November 2006.
- Continue quarterly soil gas sampling and monitoring activities in conjunction with groundwater monitoring and sampling activities and analyze soil gas samples for TPH-g by EPA Modified Method TO-3 and for BTEX, MTBE, PCE, trichloroethene (TCE), 1,2-dichloroethene (1,2-DCE), and vinyl chloride (VC) by EPA Method Modified TO-15 in order to establish soil gas concentration trends and to verify if PCE concentrations detected in the shallow soil pose a potential vapor intrusion risk.
- If elevated levels of PCE are confirmed in the shallow soil gas, further evaluation of potential vapor intrusion risk into the two residential buildings located at 712 and 718 Alice Street may be required.
- Since elevated concentrations of PCE were detected in the shallow soil gas, test a round of groundwater samples for Halogenated Volatile Organic Compounds (HVOCs), mainly PCE, by Method SW8260B (i.e., the 8010 basic target list) during the 4th Quarter, 2006 groundwater monitoring event.
- If up and running by the next event, shutdown the HVDPE system for a period of at least 24 hours prior to sampling to allow subsurface conditions to equilibrate and to ensure that negative pressure in the subsurface does not biased the soil gas sampling results.
- At the discretion of an AEI remediation engineer, the soil gas probes may also be used to monitor signs of aerobic biodegradation and remedial progress. In-situ respiration data, such as soil gas oxygen and carbon dioxide concentrations can be collected with minimal effort on a quarterly basis in conjunction with soil gas sampling. This information can be used in conjunction with concentrations of VOCs in the soil gas overtime to evaluate how much biological activity or aerobic biodegradation is occurring and its overall impact on remediation.

8.0 REFERENCES


1. California Department of Toxic Substances Control and the Los Angeles Regional Water Quality Control Board (DTSC-L.A.RWQCB). "Advisory – Active Soil Gas Investigations." Glendale and Los Angeles, CA, January 28, 2003.
2. Air Toxics Ltd. "Evaluating Leaks in a Soil Gas Sample Train." Folsom, CA, 2006.
3. California Department of Toxic Substances Control and the California Environmental Protection Agency. "Guidance for the Evaluation and Mitigation of Subsurface Vapor Intrusion to Indoor Air (Interim-Final)." Glendale and Sacramento, CA, December 15, 2004, revised February 7, 2005.
4. Geoprobe Systems. "Soil Implants Operation." Salina, KA, 2005.
5. Alameda County Environmental Health. "Subject: Fuel Leak Case No. RO0000202, Vic's Automotive, 245 8th Street, Oakland, CA, Alameda, CA." March 20, 2006.
6. San Mateo County Environmental Health Services Agency. "Groundwater Protection Program Guidelines, Subsurface Vapor Sampling Using a Geoprobe and Summa Canisters (DRAFT)." Redwood City, CA, June 2004.
7. Missouri Department of Natural Resources. "Soil Gas Sampling Protocol." April 21, 2005.

9.0 REPORT LIMITATIONS AND SIGNATURES


This report presents a summary of work completed by AEI, including observations and descriptions of site conditions. Where appropriate, it includes analytical results for samples taken during the course of the work. The number and location of samples are chosen to provide required information, but it cannot be assumed that they are entirely representative of all areas not sampled. All conclusions and recommendations are based on these analyses, observations, and the governing regulations. Conclusions beyond those stated and reported herein should not be inferred from this document.

These services were performed in accordance with generally accepted practices in the environmental engineering and geology fields that existed at the time and location of the subject scope of work.

Sincerely,
AEI Consultants



Richard J. Bradford
Senior Staff Engineer



Peter J. McIntyre, PG
Senior Project Manager




Report Distribution


Mr. Victor Lum
Vic's Automotive
245 8th Street
Oakland, California 94607

Mr. Jerry Wickham (electronic copy)
Alameda County Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502

FIGURES



TN \star MN
15 1/2°



Printed from TOPO! ©2001 National Geographic Holdings (www.topo.com)

AEI CONSULTANTS
2500 CAMINO DIABLO BLVD, STE 100, WALNUT CREEK

SITE LOCATION MAP

245 8th STREET
OAKLAND, CALIFORNIA


FIGURE 1
PROJECT No. 116907



0' 10' 20' 30'
SCALE: 1 in = 30 ft

LEGEND

- SOIL BORING (8/9/96)
- SOIL BORING (4/02 & 3/03)
- MONITORING WELL
- SOIL GAS PROBE LOCATION
- FORMER UST LOCATION
- BUILDING FOOTPRINT



AEI CONSULTANTS 2500 CAMINO DIABLO, STE 100, WALNUT CREEK, CA	
SITE PLAN	
245 8th STREET OAKLAND, CALIFORNIA	FIGURE 2 PROJECT NO. 116907




0' 10' 20' 30'
SCALE: 1 in = 30 ft

LEGEND

- SOIL GAS PROBE
- MONITORING WELL
- FORMER UST LOCATION
- BUILDING FOOTPRINT

GP-1		Soil Analytical Data (mg/kg)
TPH-g	<1.0	
MTBE	<0.05	
Benzene	<0.005	
Toluene	<0.005	
Ethylbenzene	<0.005	
Xylenes	<0.005	

TPH-g = Total Petroleum Hydrocarbons as gasoline
MTBE = Methyl tertiary-butyl ether



PRINGLE MEATS AND POULTRY
216 7th STREET

RESIDENTIAL
(227 8th STREET)

RESIDENTIAL
(228 7th STREET)

RESIDENTIAL
(230 7th STREET)

RESIDENTIAL
(234 7th STREET)

PROPERTY BOUNDARY

CANOPY & PUMP ISLAND

EXISTING TANK HOLD

GP-1	
TPH-g	<1.0
MTBE	<0.05
Benzene	<0.005
Toluene	<0.005
Ethylbenzene	<0.005
Xylenes	<0.005

GP-3	
TPH-g	<1.0
MTBE	<0.05
Benzene	<0.005
Toluene	<0.005
Ethylbenzene	<0.005
Xylenes	<0.005

GP-3-10'	
TPH-g	<1.0
MTBE	<0.05
Benzene	<0.005
Toluene	<0.005
Ethylbenzene	<0.005
Xylenes	<0.005

GP-4	
TPH-g	<1.0
MTBE	<0.05
Benzene	<0.005
Toluene	<0.005
Ethylbenzene	<0.005
Xylenes	<0.005

GP-4-5'	
TPH-g	1.6
MTBE	<0.05
Benzene	0.049
Toluene	0.060
Ethylbenzene	0.019
Xylenes	0.079

GP-4-10'	
TPH-g	<1.0
MTBE	<0.05
Benzene	<0.005
Toluene	<0.005
Ethylbenzene	<0.005
Xylenes	<0.005

ALICE STREET

SIDEWALK

COMMERCIAL AND RESIDENTIAL

AEI CONSULTANTS
2500 CAMINO DIABLO, STE 100, WALNUT CREEK, CA

SOIL ANALYTICAL DATA (7/13/06)

245 8th STREET
OAKLAND, CALIFORNIA

FIGURE 3
PROJECT NO. 116907



0' 10' 20' 30'
SCALE: 1 in = 30 ft


LEGEND

- SOIL GAS PROBE
- MONITORING WELL
- FORMER UST LOCATION
- BUILDING FOOTPRINT

GP-1	
TPH-g	331
MTBE	<8.0
Benzene	<7.1
Toluene	<8.4
Ethylbenzene	<9.7
Xylenes	<9.7
PCE	270

Soil Gas
Analytical
Data
(ug/m3)

TPH-g = Total Petroleum Hydrocarbons as gasoline
MTBE = Methyl tertiary-butyl ether
PCE = Tetrachloroethene



SIDEWALK

COMMERCIAL AND RESIDENTIAL

AEI CONSULTANTS
2500 CAMINO DIABLO, STE 100, WALNUT CREEK, CA

SOIL GAS ANALYTICAL DATA (8/4/06)

245 8th STREET
OAKLAND, CALIFORNIA

FIGURE 4
PROJECT NO. 116907

TABLES

TABLE 1: GROUNDWATER ELEVATION DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID (screen interval)	Date Collected	TOC Well^{1,2} Elevation (ft amsl)	Depth to Water (ft)	Groundwater³ Elevation (ft amsl)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)
MW-1 (8-28)	6/29/2001	27.73	16.52	11.21	14.89	1.63
	10/10/2001	27.73	15.45	12.28	15.37	0.08
	1/9/2002	27.73	12.61	15.12	-	<0.01
	4/24/2002	27.73	13.35	14.38	-	<0.01
	7/24/2002	27.73	14.19	13.54	-	<0.01
	11/5/2002	27.73	14.85	12.88	-	<0.01
	2/4/2003	27.73	14.91	12.82	-	<0.01
	5/2/2003	27.73	14.43	13.30	-	0.08
	8/4/2003	27.73	15.24	12.49	15.01	0.23
	11/3/2003	27.73	16.94	10.79	15.67	1.27
	2/9/2004	27.73	14.61	13.12	14.43	0.18
	5/10/2004	27.73	Inaccessible	-	-	-
	8/9/2004	27.73	15.24	12.49	15.03	0.21
	11/9/2004	27.73	15.95	11.78	15.71	0.24
	2/3/2005	32.55	13.75	18.80	13.58	0.17
	5/9/2005	32.55	13.93	18.62	13.81	0.12
	8/5/2005	32.55	15.40	17.15	15.39	0.01
	11/9/2005	32.55	15.76	16.79	15.75	0.01
	2/9/2006	32.55	13.52	19.03	13.50	0.02
	5/4/2006	32.55	12.47	20.08	12.46	0.01
	8/4/2006	32.55	15.11	17.44	15.09	0.02
MW-2 (8-28)	6/29/2001	28.16	16.14	12.02	-	-
	10/10/2001	28.16	16.43	11.73	-	-
	1/9/2002	28.16	13.50	14.66	-	-
	4/24/2002	28.16	14.40	13.76	-	-
	7/24/2002	28.16	14.91	13.25	-	-
	11/5/2002	28.16	16.96	11.20	-	-
	2/4/2003	28.16	15.42	12.74	-	-
	5/2/2003	28.16	15.24	12.92	-	-
	8/4/2003	28.16	15.98	12.18	-	-
	11/3/2003	28.16	16.60	11.56	-	Sheen
	2/9/2004	28.16	15.22	12.94	-	Sheen
	5/10/2004	28.16	15.34	12.82	-	Sheen
	8/9/2004	28.16	15.92	12.24	-	Sheen
	11/9/2004	28.16	16.51	11.65	-	Sheen
	2/3/2005	33.24	14.44	18.80	-	Sheen
	5/9/2005	33.24	14.67	18.57	-	Sheen
	8/5/2005	33.24	16.27	16.97	-	Sheen
	11/9/2005	33.24	16.53	16.71	-	Sheen
	2/9/2006	33.24	14.36	18.88	-	Sheen
	5/4/2006	33.24	13.46	19.78	-	Sheen
	8/4/2006	33.24	15.95	17.29	-	Sheen

TABLE 1: GROUNDWATER ELEVATION DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID (screen interval)	Date Collected	TOC Well^{1,2} Elevation (ft amsl)	Depth to Water (ft)	Groundwater³ Elevation (ft amsl)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)
MW-3 (10-25)	6/29/2001	29.21	16.60	12.61	-	-
	10/10/2001	29.21	16.92	12.29	-	-
	1/9/2002	29.21	14.20	15.01	-	-
	4/24/2002	29.21	15.07	14.14	-	-
	7/24/2002	29.21	16.40	12.81	-	-
	11/5/2002	29.21	16.47	12.74	-	-
	2/4/2003	29.21	16.92	12.29	-	-
	5/2/2003	29.21	15.45	13.76	-	-
	8/4/2003	29.21	16.46	12.75	-	-
	11/3/2003	29.21	17.15	12.06	-	-
	2/9/2004	29.21	15.78	13.43	-	-
	5/10/2004	29.21	15.77	13.44	-	-
	8/9/2004	29.21	16.45	12.76	-	-
	11/9/2004	29.21	17.26	11.95	-	-
	2/3/2005	34.25	15.92	18.33	-	-
	5/9/2005	34.25	15.03	19.22	-	-
	8/5/2005	34.25	16.59	17.66	-	-
11/9/2005	34.25	16.82	17.43	-	-	
2/9/2006	34.25	14.65	19.60	-	-	
5/4/2006	34.25	13.61	20.64	-	-	
	8/4/2006	34.25	16.28	17.97	-	-
MW-4 (10-25)	6/29/2001	29.38	17.71	11.67	-	-
	10/10/2001	29.38	18.00	11.38	-	-
	1/9/2002	29.38	15.02	14.36	-	-
	4/24/2002	29.38	15.74	13.64	-	-
	7/24/2002	29.38	16.69	12.69	-	-
	11/5/2002	29.38	17.64	11.74	-	-
	2/4/2003	29.38	16.02	13.36	-	-
	5/2/2003	29.38	16.72	12.66	-	-
	8/4/2003	29.38	17.51	11.87	-	-
	11/3/2003	29.38	18.09	11.29	-	-
	2/9/2004	29.38	16.67	12.71	-	-
	5/10/2004	29.38	16.89	12.49	-	-
	8/9/2004	29.38	17.44	11.94	-	-
	11/9/2004	29.38	17.89	11.49	-	-
	2/3/2005	34.42	14.98	19.44	-	-
	5/9/2005	34.42	16.20	18.22	-	-
	8/5/2005	34.42	17.73	16.69	-	-
11/9/2005	34.42	17.91	16.51	-	-	
2/9/2006	34.42	15.62	18.80	-	-	
5/4/2006	34.42	15.12	19.30	-	-	
	8/4/2006	34.42	17.39	17.03	-	-

TABLE 1: GROUNDWATER ELEVATION DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID (screen interval)	Date Collected	TOC Well^{1,2} Elevation (ft amsl)	Depth to Water (ft)	Groundwater³ Elevation (ft amsl)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)
MW-5 (12-22)	2/3/2005	33.33	14.23	19.10	-	-
	5/9/2005	33.33	14.33	19.00	-	-
	8/5/2005	33.33	15.89	17.44	-	-
	11/9/2005	33.33	16.18	17.15	-	-
	2/9/2006	33.33	14.02	19.31	-	-
	5/4/2006	33.33	12.97	20.36	-	-
	8/4/2006	33.33	15.63	17.70	-	-
MW-6 (12-22)	2/3/2005	32.82	13.99	18.83	-	Sheen
	5/9/2005	32.82	13.61	19.21	-	Sheen
	8/5/2005	32.82	15.50	17.32	15.13	0.37
	11/9/2005	32.82	15.87	16.95	15.50	0.37
	2/9/2006	32.82	13.93	18.89	13.22	0.71
	5/4/2006	32.82	12.88	19.94	12.13	0.75
	8/4/2006	32.82	15.22	17.60	14.81	0.41
MW-7 (12-22)	2/3/2005	33.07	14.17	18.90	-	Sheen
	5/9/2005	33.07	14.47	18.60	14.44	0.03
	8/5/2005	33.07	16.07	17.00	16.02	0.05
	11/9/2005	33.07	16.47	16.60	16.35	0.12
	2/9/2006	33.07	14.18	18.89	14.11	0.07
	5/4/2006	33.07	13.12	19.95	13.11	0.01
	8/4/2006	33.07	15.74	17.33	-	Sheen
MW-10 (12-22)	2/3/2005	31.17	12.65	18.52	-	-
	5/9/2005	31.17	13.09	18.08	-	-
	8/5/2005	31.17	14.68	16.49	-	-
	11/9/2005	31.17	14.94	16.23	-	-
	2/9/2006	31.17	12.82	18.35	-	-
	5/4/2006	31.17	12.11	19.06	-	-
	8/4/2006	31.17	14.38	16.79	-	-
MW-11 (12-22)	2/3/2005	31.78	13.39	18.39	-	Sheen
	5/9/2005	31.78	13.89	17.89	-	Sheen
	8/5/2005	31.78	15.47	16.31	-	Sheen
	11/9/2005	31.78	15.73	16.05	-	Sheen
	2/9/2006	31.78	13.53	18.25	-	Sheen
	5/4/2006	31.78	12.73	19.05	-	Sheen
	8/4/2006	31.78	15.17	16.61	-	Sheen

TABLE 1: GROUNDWATER ELEVATION DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID (screen interval)	Date Collected	TOC Well^{1,2} Elevation (ft amsl)	Depth to Water (ft)	Groundwater³ Elevation (ft amsl)	Depth to LNAPL (ft)	Apparent LNAPL Thickness (ft)
MW-12 (12-22)	2/3/2005	32.05	13.70	18.35	-	Sheen
	5/9/2005	32.05	14.17	17.88	-	Sheen
	8/5/2005	32.05	15.69	16.36	-	Sheen
	11/9/2005	32.05	15.93	16.12	-	Sheen
	2/9/2006	32.05	13.78	18.27	-	Sheen
	5/4/2006	32.05	12.98	19.07	-	Sheen
	8/4/2006	32.05	15.39	16.66	-	Sheen

1) Monitoring well top of casing (TOC) elevations were resurveyed by Morrow Surveying on January 10, 2006 and February 7, 2006

2) Groudwater elevations for the February 3, 2005 and subsequent monitoring episodes use the new well survey data

3) When LNAPL is present at >0.10 ft, the groundwater elevations are assumed to be affected by the LNAPL

All well elevations are measured from the top of the casing (TOC)

- = not applicable

LNAPL = light non-aqueous phase liquid (floating free product)

ft amsl = feet above mean sea level

TABLE 2: GROUNDWATER FLOW SUMMARY

**Vic's Automotive
245 8th Street, Oakland, California**

Episode #	Date	Average Groundwater Elevation¹ (ft amsl)	Change from Previous Episode (ft)	Flow direction (gradient)
1	6/29/2001	12.10	-	SSE (0.0074)
2	10/10/2001	11.80	-0.30	SSE (0.0071)
3	1/9/2002	14.68	2.88	SE (0.0054)
4	4/24/2002	13.85	-0.83	SSW (0.005)
5	7/24/2002	12.92	-0.93	NE (0.021)
6	11/5/2002	11.89	-1.02	SW (0.019)
7	2/4/2003	12.80	0.90	NNW (0.01)
8	5/2/2003	13.11	0.32	SSE (0.01)
9	8/4/2003	12.27	-0.85	SSE(0.007)
10	11/3/2003	11.64	-0.63	SSE (0.006)
11	2/9/2004	13.03	1.39	SSE (0.006)
12	5/10/2004	12.92	-0.11	SSE (0.008)
13	8/9/2004	12.31	-0.60	SSE (0.006)
14	11/9/2004	11.70	-0.62	SSE (0.004)
15	2/3/2005	18.75	-	W (0.007)
16	5/9/2005	18.53	-0.22	S (0.010)
17	8/5/2005	16.94	-1.59	S (0.010)
18	11/9/2005	16.65	-0.28	S (0.010)
19	2/9/2006	18.83	1.89	SSW (0.010)
20	5/4/2006	19.72	3.07	SSW (0.012)
21	8/4/2006	17.24	-1.59	SSW (0.010)

1) MW-2 to MW-4 only used for episodes 1 through 14; all wells used for episodes 15 and later

- = not applicable

ft amsl = feet above mean sea level

TABLE 3: GROUNDWATER SAMPLE ANALYTICAL DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID	Date Collected	Apparent LNAPL Thickness (ft)	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
			µg/L <i>Method SW8015Cm</i>	µg/L	µg/L	µg/L	µg/L	µg/L
MW-1	6/29/2001	1.63	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	10/10/2001	0.08	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	1/9/2002	<0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	4/24/2002	<0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	7/24/2002	~0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/5/2002	~0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/4/2003	~0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/2/2003	0.08	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/4/2003	0.23	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/3/2003	1.27	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/9/2004	0.18	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/10/2004	Inaccessible	-	-	-	-	-	-
	8/9/2004	0.21	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/9/2004	0.24	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/3/2005	0.17	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/9/2005	0.12	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/5/2005	0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/9/2005	0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/9/2006	0.02	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/4/2006	0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/4/2006	0.02	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
MW-2	6/29/2001	0.0	69,000	4100/4400*	7,200	6,100	1,500	7,000
	10/10/2001	0.0	87,000	14,000	22,000	12,000	2,700	9,100
	1/9/2002	0.0	130,000	11,000	30,000	19,000	3,800	14,000
	4/24/2002	Sheen	210,000	32,000	38,000	23,000	4,600	19,000
	7/24/2002	Sheen	170,000	36,000	48,000	12,000	3,700	8,600
	11/5/2002	Sheen	190,000	36,000	45,000	25,000	4,600	16,000
	2/4/2003	Sheen	150,000	27,000	51,000	24,000	4,200	14,000
	5/2/2003	Sheen	150,000	35,000	39,000	11,000	3,800	9,900
	8/4/2003	Sheen	120,000	29,000	32,000	5,000	3,200	7,200
	11/3/2003	Sheen	120,000	24,000	33,000	4,300	3,200	5,400
	2/9/2004	Sheen	130,000	19,000	27,000	7,700	3,100	7,600
	5/10/2004	Sheen	67,000	13,000	20,000	3,000	2,300	4,100
	8/9/2004	Sheen	100,000	22,000	27,000	7,100	2,800	6,600
	11/9/2004	Sheen	100,000	23,000	27,000	6,100	3,000	5,600
	2/3/2005	Sheen	84,000	11,000	23,000	5,000	3,000	5,500
	5/9/2005	Sheen	74,000	14,000	21,000	4,200	2,300	3,300
	7/27/2005	Sheen	9,500	910	1,400	1,000	180	960
	8/5/2005	Sheen	74,000	4,000	8,800	11,000	1,300	7,600
	11/9/2005	Sheen	120,000	16,000	21,000	14,000	2,300	13,000
	2/9/2006	Sheen	120,000	10,000	18,000	16,000	2,200	13,000
5/4/2006	Sheen	71,000	8,300	14,000	11,000	1,500	7,600	
	8/4/2006	Sheen	160,000	14,000	22,000	14,000	2,400	11,000

TABLE 3: GROUNDWATER SAMPLE ANALYTICAL DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID	Date Collected	Apparent LNAPL Thickness (ft)	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
			µg/L <i>Method SW8015Cm</i>	µg/L	µg/L	µg/L	µg/L	µg/L
MW-3	6/29/2001	0.00	550	<5.0	<0.5	3.1	3.2	1.2
	10/10/2001	0.00	470	<5.0	0.77	5.3	3.3	5.9
	1/9/2002	0.00	1,000	<5.0	0.90	7.6	7.8	25
	4/24/2002	0.00	1,500	<5.0	0.64	7.2	12	14
	7/24/2002	0.00	1,200	<5.0	10	17.0	11	25
	11/5/2002	0.00	1,800	<25	33	43.0	18	31
	2/4/2003	0.00	450	<5.0	<0.5	5.0	<0.5	0.77
	5/2/2003	0.00	340	<5.0	7.3	10.0	2.5	7.3
	8/4/2003	0.00	170	<5.0	5.8	5.9	1.5	4.9
	11/3/2003	0.00	54	<5.0	<0.5	<0.5	<0.5	<0.5
	2/9/2004	0.00	190	<5.0	<0.5	3.6	<0.5	<0.5
	5/10/2004	0.00	280	<5.0	<0.5	3.4	<0.5	<0.5
	8/9/2004	0.00	290	<5.0	<0.5	3.8	<0.5	<0.5
	11/9/2004	0.00	220	<5.0	<0.5	4.0	<0.5	<0.5
	2/3/2005	0.00	160	<5.0	13	30	3.0	21
	5/9/2005	0.00	200	<5.0	<0.5	3.9	<0.5	<0.5
	8/5/2005	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	11/9/2005	0.00	130	<5.0	<0.5	2.3	<0.5	<0.5
	2/9/2006	0.00	270	<5.0	<0.5	5.6	<0.5	<0.5
	5/4/2006	0.00	220	<5.0	<0.5	4.3	<0.5	<0.5
	8/4/2006	0.00	93	<5.0	<0.5	1.5	<0.5	<0.5
MW-4	6/29/2001	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	10/10/2001	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	1/9/2002	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	4/24/2002	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	7/24/2002	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	11/5/2002	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	2/4/2003	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	5/2/2003	0.00	500	10	68	71	18	65
	8/4/2003	0.00	270	<5.0	30	29	9.2	32
	11/3/2003	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	2/9/2004	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	5/10/2004	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	8/9/2004	0.00	130	<5.0	14	13	5.3	17
	11/9/2004	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	2/3/2005	0.00	370	<5.0	<0.5	4.1	<0.5	0.64
	5/9/2005	0.00	840	<5.0	50	180	21	110
	7/27/2005	0.00	<50	<5.0	<0.5	<0.5	<0.5	<0.5
	8/5/2005	0.00	310	<5.0	7.5	57	10	53
	11/9/2005	0.00	290	<5.0	12	61	8.8	49
	2/9/2006	0.00	250	<5.0	9.9	42	7.5	45
5/4/2006	0.00	300	<5.0	37	76	7.8	42	
	8/4/2006	0.00	270	<5.0	7.3	33	5.6	32
MW-5	2/3/2005	0.0	78,000	<1,000	7,600	13,000	2,200	9,600
	5/9/2005	0.0	60,000	<900	6,100	9,900	1,600	6,600
	7/27/2005	nm	120,000	1,100	10,000	19,000	2,100	13,000
	8/5/2005	0.0	59,000	<500	4,100	10,000	1,200	6,600
	11/9/2005	0.0	44,000	<500	3,300	7,400	1,100	4,900
	2/9/2006	0.0	110,000	<500	10,000	22,000	2,400	13,000
	5/4/2006	0.0	110,000	<250	11,000	22,000	2,900	15,000
		8/4/2006	0.0	73,000	<500	4,700	8,600	1,700

TABLE 3: GROUNDWATER SAMPLE ANALYTICAL DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Well/Sample ID	Date Collected	Apparent LNAPL Thickness (ft)	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
			µg/L <i>Method SW8015Cm</i>	µg/L	µg/L	µg/L	µg/L	µg/L
MW-6	2/3/2005	Sheen	130,000	<1,000	2,400	33,000	2,400	15,000
	5/9/2005	Sheen	170,000	<4,000	11,000	43,000	3,100	16,000
	8/5/2005	0.37	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/9/2005	0.37	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/9/2006	0.71	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/4/2006	0.75	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/4/2006	0.41	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
MW-7	2/3/2005	Sheen	220,000	18,000	45,000	44,000	3,500	18,000
	5/9/2005	0.03	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/5/2005	0.05	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	11/9/2005	0.12	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	2/9/2006	0.07	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	5/4/2006	0.01	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp	ns/fp
	8/4/2006	Sheen	230,000	19,000	37,000	37,000	3,100	14,000
MW-10	2/3/2005	0.00	36,000	<500	4,700	7,200	660	3,400
	5/9/2005	0.00	88,000	<1,500	6,900	20,000	2,300	9,900
	8/5/2005	0.00	88,000	<1,100	10,000	21,000	1,900	9,800
	11/9/2005	0.00	63,000	<1,100	5,400	13,000	1,900	7,900
	2/9/2006	0.00	100,000	<500	6,600	19,000	2,900	13,000
	5/4/2006	0.00	100,000	<500	8,500	25,000	3,000	13,000
	8/4/2006	0.00	190,000	<2,200	17,000	35,000	2,800	13,000
MW-11	2/3/2005	Sheen	170,000	<3,000	23,000	35,000	3,100	16,000
	5/9/2005	Sheen	210,000	3,500	29,000	40,000	3,400	16,000
	7/27/2005	Sheen	220,000	2,500	26,000	37,000	3,200	18,000
	8/5/2005	Sheen	210,000	<2,500	35,000	42,000	3,300	16,000
	11/9/2005	Sheen	180,000	9,100	32,000	47,000	3,600	18,000
	2/9/2006	Sheen	210,000	10,000	33,000	39,000	3,800	20,000
	5/4/2006	Sheen	190,000	12,000	34,000	41,000	3,500	17,000
	8/4/2006	Sheen	290,000	11,000	33,000	43,000	3,300	15,000
MW-12	2/3/2005	Sheen	250,000	100,000	52,000	41,000	3,400	15,000
	5/9/2005	Sheen	210,000	91,000	44,000	28,000	3,300	13,000
	8/5/2005	Sheen	170,000	52,000	38,000	28,000	3,000	12,000
	11/9/2005	Sheen	180,000	52,000	39,000	25,000	2,900	12,000
	2/9/2006	Sheen	170,000	34,000	40,000	23,000	3,500	15,000
	5/4/2006	Sheen	160,000	47,000	33,000	28,000	2,800	10,000
	8/4/2006	Sheen	240,000	55,000	40,000	24,000	3,200	12,000

µg/L = micrograms per liter (ppb)

ns/fp = not sampled / free product

TPH-g = total petroleum hydrocarbons as gasoline

MTBE = methyl tertiary-butyl ether

* samples re-analyzed by Method SW8260B (expressed as SW8021B / SW8260B)

Non-detectable concentrations are noted by a less than sign (<) followed by the laboratory reporting limit

Please refer to Appendix B: Lab Analytical and Chain of Custody Documentation for detailed analytical reports including dilution factors

TABLE 4: SOIL SAMPLE ANALYTICAL DATA
Vic's Automotive
245 8th Street, Oakland, California

Probe/Sample ID	Date Collected	Sample Depth (ft bgs)	PID Reading (ppmv)	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
				mg/kg <i>Method SW8015Cm</i>	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
GP-1-5	7/13/2006	5	3	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-1-10	7/13/2006	10	11	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-2-5	7/13/2006	5	2	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-2-10	7/13/2006	10	5	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-3-5	7/13/2006	5	1	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-3-10	7/13/2006	10	10	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-4-5	7/13/2006	5	2	<1.0	<0.05	<0.005	<0.005	<0.005	<0.005
GP-4-10	7/13/2006	10	11	1.6	<0.05	0.049	0.060	0.019	0.079

mg/kg = milligrams per kilograms

TPH-g = total petroleum hydrocarbons as gasoline

Background PID readings <1 ppmv

Non-detectable concentrations are noted by a less than sign (<) followed by the laboratory reporting limit

Please refer to Appendix B: Lab Analytical Reports w/ Chain of Custody Documentation for detailed analytical data, including dilution factors and reporting limits

TABLE 5: SOIL GAS SAMPLE ANALYTICAL DATA
Vic's Automotive
245 8th Street, Oakland, California

Probe/Sample ID	Date Collected	Sample Depth (ft bgs)	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes	Ethanol	PCE	CD	MEK	Acetone	2-Propanol ¹
			$\mu\text{g}/\text{m}^3$ <i>EPA Method Modified TO-3</i>	$\mu\text{g}/\text{m}^3$										
GP-1-5	8/4/2006	5	331	<8.0	<7.1	<8.4	<9.7	<9.7	<17	17	72	<6.6	82	23
GP-1-5D ₁	8/4/2006	5	-	<8.0	<7.1	<8.4	<9.7	<9.7	<17	18	71	<6.6	78	23
GP-1-10	8/4/2006	10	493	<4.1	<3.6	<4.3	<5.0	<5.0	<8.6	20	71	11	120	<11
GP-2-5	8/4/2006	5	493	<4.4	<3.9	6.9	<5.4	10	<9.3	600	120	4.1	110	<12
GP-2-10	8/4/2006	10	352	<10	<9.0	18	<12	<12	<21	270	18	<8.4	62	<28
GP-3-5	8/4/2006	5	<240	<4.2	<3.7	<4.4	<5.0	<5.0	<8.8	<7.9	<3.6	4.8	110	<11
GP-3-10	8/4/2006	10	564	<4.2	<3.7	<4.4	<5.0	<5.0	<8.8	<7.9	9.0	5.6	240	<11
GP-4-5	8/4/2006	5	705	<4.4	5.4	<4.6	<5.4	<5.4	<9.3	<8.4	270	4.3	100	<12
GP-4-5 ₁	8/4/2006	5	599	-	-	-	-	-	-	-	-	-	-	-
GP-4-10	8/4/2006	10	564	<4.1	6.1	17	5.7	16	12	<7.8	250	9.4	130	<11
GP-4-10D _f	8/5/2006	10	529	<3.8	4.2	18	<4.6	17	18	<7.2	130	9.4	130	<10
ESLs			26,000	9,400	85	63,000	420,000	150,000	19,000,000	410	-	210,000	660,000	-
CHHSLs			-	4,000	36.2	135,000	postponed	315,000	-	180	-	-	-	-

1) 2-Propanol (i.e., isopropyl alcohol) is the tracer/leak check compound

ft bgs = feet below ground surface

$\mu\text{g}/\text{m}^3$ = micrograms per cubic meter

TPH-g = total petroleum hydrocarbons as gasoline

MTBE = methyl tertiary-butyl ether

PCE = tetrachloroethene

CD = carbon disulfide

MEK = methyl ethyl ketone (i.e., 2-Butanone)

D_f = after the probe/sample ID indicates a duplicate sample collected in the field

D₁ = after the probe/sample ID indicates a duplicate sample prepared and analyzed by the lab

Non-detectable concentrations are noted by a less than sign (<) followed by the laboratory reporting limit

Please refer to Appendix B: Lab Analytical Reports w/ Chain of Custody Documentation for detailed analytical data, including dilution factors and reporting limits

ESLs = Environmental Screening Levels - for residential land use

CHHSLs = California Human Health Screening Levels

TABLE 6: HISTORICAL SOIL SAMPLE ANALYTICAL DATA

**Vic's Automotive
245 8th Street, Oakland, California**

Sample ID	Date Collected	TPH-g	TOG	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
		mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
		<i>Method SW8015Cm</i>		<i>Method SW8021B</i>				
MW-1 (6')	7/14/95	390	-	-	0.280	0.290	0.290	0.620
MW-1 (11')	7/14/95	370	-	-	0.240	0.240	0.230	0.610
MW-2 (6')	7/14/95	ND	24	-	ND	ND	ND	ND
MW-2 (11')	7/14/95	300	38	-	0.300	0.230	0.240	0.630
SB-1 (18')	8/18/96	9,100	-	47.0	57	580	190	1,000
SB-1 (24')	8/18/96	30	-	0.20	0.37	1.4	0.52	2.5
SB-2 (24')	8/18/96	1.1	-	0.032	0.11	0.17	0.018	0.099
SB-3 (24')	8/18/96	16	-	4.7	1.6	2.5	0.21	0.95
MW-3 15'	5/25/01	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
MW-3 20'	5/25/01	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
MW-4 15'	5/25/01	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
MW-4 20'	5/25/01	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-4 12'	4/2/03	25	-	ND<0.5	0.41	1.0	0.2	1.3
SB-4 15'	4/2/03	260	-	ND<1.7	3.5	15	4.5	23
SB-5 11'	4/3/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-6 16'	4/2/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-7 12'	4/2/03	700	-	ND<10	6.0	25	9.3	50
SB-7 18'	4/2/03	4,900	-	ND<25	65	260	77	400
SB-8 17'	4/2/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-9 16'	4/3/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-10 12'	4/3/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-11 12'	4/3/03	1.4	-	ND<0.05	0.12	0.10	0.026	0.066
SB-11 16'	4/3/03	2,700	-	ND<30	29	170	49.0	250
SB-12 15'	4/2/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-13 14'	4/3/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-14 14'	4/3/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
SB-15 14'	4/3/03	ND<1.0	-	ND<0.05	ND<0.005	ND<0.005	ND<0.005	ND<0.005
MW-5 16'	1/11/2005	100	-	ND<5.0	2.6	6.0	1.5	8.4
MW-5 20'	1/11/2005	37	-	ND<0.50	2.6	5.6	0.91	4.6
MW-7 16'	1/11/2005	19	-	2.9	3.3	3.5	0.4	1.9
MW-7 20.5'	1/11/2005	340	-	ND<5.0	9.6	25	7.0	35
MW-6 20'	1/19/2005	14	-	ND<0.25	0.099	4.1	0.33	1.7
MW-10 15.5'	1/20/2005	840	-	ND<2.0	11	58	16	83
MW-11 15.5'	1/19/2005	3,200	-	ND<10	35	320	85	430
MW-12 15.5'	1/19/2005	13	-	8.5	2.5	2.8	0.22	1.1

ND = not detected

mg/kg = milligrams per kilogram of soil

TPH-g = total petroleum hydrocarbons as gasoline

TOG = Total Oil and Grease

MTBE = methy tertiary-butyl ether

TABLE 7: HISTORICAL SOIL VAPOR SAMPLE ANALYTICAL DATA
Vic's Automotive
245 8th Street, Oakland, California

Sample ID	Date Collected	TPH-g µg/L	MTBE µg/L	Benzene µg/L	Toluene µg/L	Ethylbenzene µg/L	Xylenes µg/L
SB-4 4' V	4/2/03	ND<25	ND<2.5	ND<0.25	ND<0.25	ND<0.25	ND<0.25
SB-7 4' V	4/2/03	ND<25	ND<2.5	ND<0.25	ND<0.25	ND<0.25	ND<0.25
SB-8 4' V	4/2/03	ND<25	ND<2.5	ND<0.25	ND<0.25	ND<0.25	ND<0.25
SB-16 4' V	4/2/03	ND<25	ND<2.5	ND<0.25	ND<0.25	ND<0.25	ND<0.25
SB-17 4' V	4/2/03	ND<25	ND<2.5	ND<0.25	ND<0.25	ND<0.25	ND<0.25

ND = not detected

µg/L = micrograms per liter

TPH-g = total petroleum hydrocarbons as gasoline

MTBE = methyl tertiary-butyl ether

TABLE 8: SOIL BORING GROUNDWATER SAMPLE ANALYTICAL DATA
Vic's Automotive
245 8th Street, Oakland, California

Boring/Sample ID	Date Collected	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
		$\mu\text{g/L}$ <i>SW8015Cm</i>	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$
SB-1 W	8/18/96	140,000	480	12,000	30,000	3,900	19,000
SB-2 W	8/18/96	130,000	2,300	15,000	20,000	2,800	15,000
SB-3 W	8/18/96	120,000	27,000	19,000	29,000	1,900	9,500
SB-4 W	4/2/03	310,000	17,000	45,000	65,000	4,500	23,000
SB-5 W	4/3/03	420	ND<5.0	11	3.7	18	1.1
SB-6 W	4/2/03	210	ND<5.0	0.57	4.2	1.1	1.4
SB-7 W	4/2/03	240,000	69,000	42,000	45,000	3,100	16,000
SB-8 W	4/2/03	51	360	ND<0.5	ND<0.5	ND<0.5	ND<0.5
SB-9 W	4/3/03	7,300	ND<100	2,100	280	300	140
SB-10 W	4/3/03	210,000	ND<5000	22,000	38,000	3,400	18,000
SB-11 W	4/3/03	200,000	ND<2000	18,000	39,000	3,600	18,000
SB-12 W	4/2/03	ND<50	ND<5.0	ND<0.5	0.85	ND<0.5	0.53
SB-13 W	4/3/03	190	ND<20	ND<0.5	1.1	1.9	1.8
SB-14 W	4/3/03	ND<50	140	ND<0.5	0.95	ND<0.5	1.3
SB-15 W	4/3/03	ND<50	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5

ND = not detected

$\mu\text{g/L}$ = micrograms per liter

TPH-g = total petroleum hydrocarbons as gasoline

MTBE = methyl tertiary-butyl ether

TABLE 9: GROUNDWATER SAMPLE ANALYTICAL DATA: FUEL OXYGENATES
Vic's Automotive
245 8th Street, Oakland, California

Well/Sample ID	Date Collected	DIPE µg/L	ETBE µg/L	MTBE µg/L	TAME µg/L	TBA µg/L	EDB µg/L	1,2-DCA µg/L
MW-2	7/24/02	ND<1,000	ND<1,000	43,000	ND<1,000	ND<10,000	ND<1,000	ND<1,000
MW-3	7/24/02	ND<0.5	ND<0.5	1.3	ND<0.5	ND<5.0	ND<0.5	ND<0.5
MW-4	7/24/02	ND<0.5	ND<0.5	ND<0.5	ND<0.5	ND<5.0	ND<0.5	ND<0.5
SB-4 W	4/2/03	ND<500	ND<500	14,000	ND<500	ND<5000	ND<500	ND<500
SB-5 W	4/3/03	ND<5.0	ND<5.0	6.5	ND<5.0	790	ND<5.0	ND<5.0
SB-6 W	4/2/03	ND<0.5	ND<0.5	ND<0.5	ND<0.5	ND<5.0	ND<0.5	ND<0.5
SB-7 W	4/2/03	ND<1,200	ND>1,200	52,000	ND<1,200	ND<12,000	ND<1,200	ND<1,200
SB-8 W	4/2/03	ND<10	ND<10	480	14	ND<100	ND<10	ND<10
SB-9 W	4/3/03	ND<5.0	ND<5.0	41	ND<5.0	68	ND<5.0	ND<5.0
SB-10 W	4/3/03	ND<50	ND<50	2,800	110	ND<500	ND<50	ND<50
SB-11 W	4/3/03	ND<50	ND<50	74	ND<50	ND<500	ND<50	ND<50
SB-12 W	4/2/03	ND<0.5	ND<0.5	ND<0.5	ND<0.5	ND<5.0	ND<0.5	ND<0.5
SB-13 W	4/3/03	ND<0.5	ND<0.5	3.7	ND<0.5	ND<5.0	ND<0.5	ND<0.5
SB-14 W	4/3/03	ND<2.5	ND<2.5	180	ND<2.5	ND<25	ND<2.5	ND<2.5
SB-15 W	4/3/03	ND<0.5	ND<0.5	ND<0.5	ND<0.5	ND<5.0	ND<0.5	ND<0.5

Analysis for fuel additives by EPA Method 8260

µg/L - micrograms per liter

ns/fp - not sampled / free product

DIPE - Diisopropyl ether

ETBE - Ethyl tert-butyl ether

MTBE - Methyl tert-butyl ether

TAME - tert-Amyl methyl ether

TBA - t-Butyl Alcohol

EDB - 1,2-Dibromomethane

1,2-DCA - 1,2-Dichloroethane

All by EPA method 8260

APPENDIX A
PERMIT DOCUMENTATION

Alameda County Public Works Agency - Water Resources Well Permit



399 Elmhurst Street
Hayward, CA 94544-1395
Telephone: (510)670-6633 Fax:(510)782-1939

Application Approved on: 06/22/2006 By jamesy
Permits Issued: W2006-0625

Receipt Number: WR2006-0308
Permits Valid from 07/03/2006 to 07/03/2006

Application Id: 1150908243081
Site Location: 245 8th St, Oakland, CA 94607
Project Start Date: 07/03/2006

City of Project Site: Oakland

Completion Date: 07/03/2006

Applicant: AEI - Richard Bradford
2500 Camino Diablo #200, Walnut Creek, CA 94597

Phone: 925-283-6000

Property Owner: Vic Lum's Vic's Auto
245 8th St., Oakland, CA 94607

Phone: 510-832-9014

Client: ** same as Property Owner **

Total Due: \$200.00
Total Amount Paid: \$200.00
Paid By: CHECK **PAID IN FULL**

Payer Name : All Environmental

Works Requesting Permits:

Borehole(s) for Investigation-Geotechnical Study/CPT's - 4 Boreholes
Driller: Vironex - Lic #: 705927 - Method: DP

Work Total: \$200.00

Specifications

Permit Number	Issued Dt	Expire Dt	# Boreholes	Hole Diam	Max Depth
W2006-0625	06/22/2006	10/01/2006	4	2.00 in.	10.00 ft

Specific Work Permit Conditions

1. Backfill bore hole by tremie with cement grout or cement grout/sand mixture. Upper two-three feet replaced in kind or with compacted cuttings. All cuttings remaining or unused shall be containerized and hauled off site.
2. Boreholes shall not be left open for a period of more than 24 hours. All boreholes left open more than 24 hours will need approval from Alameda County Public Works Agency, Water Resources Section. All boreholes shall be backfilled according to permit destruction requirements and all concrete material and asphalt material shall be to Caltrans Spec or County/City Codes. No borehole(s) shall be left in a manner to act as a conduit at any time.
3. Permittee shall assume entire responsibility for all activities and uses under this permit and shall indemnify, defend and save the Alameda County Public Works Agency, its officers, agents, and employees free and harmless from any and all expense, cost, liability in connection with or resulting from the exercise of this Permit including, but not limited to, properly damage, personal injury and wrongful death.
4. Permittee, permittee's contractors, consultants or agents shall be responsible to assure that all material or waters generated during drilling, boring destruction, and/or other activities associated with this Permit will be safely handled, properly managed, and disposed of according to all applicable federal, state, and local statutes regulating such. In no case shall these materials and/or waters be allowed to enter, or potentially enter, on or off-site storm sewers, dry wells, or waterways or be allowed to move off the property where work is being completed.
5. Copy of approved drilling permit must be on site at all times. Failure to present or show proof of the approved permit application on site shall result in a fine of \$500.00.
6. Permit is valid only for the purpose specified herein. No changes in construction procedures, as described on this

Alameda County Public Works Agency - Water Resources Well Permit

permit application. Boreholes shall not be converted to monitoring wells, without a permit application process.

7. No Inspector Assigned to this site.

Applicant shall contact this office by email at wells@acpwa.org and certify in writing that work was completed and according to County Standards within 5 working days after the completion of work.

APPENDIX B
BORING LOGS

X:\PROJECTS\CHARACTERIZATION & REMEDIATION\ADVANCED REMEDIATION\116907_SGI - HVDPE (Vic's Automotive)\Oakland_RJB\116907_Soil Gas Investigation\116907_Soil Gas Investigation\SGI Boring Logs GP-1 to GP-4.bgs [Basic Boring Log.rpt]

Project: Vic's Automotive Project Location: 245 8th Street, Oakland, California Project Number: 116907	<h2 style="margin: 0;">Log of Boring GP-1</h2> <p style="margin: 0;">Sheet 1 of 1</p>
---	---

Date(s) Drilled July 13, 2006	Logged By Richard J. Bradford	Checked By Peter McIntyre
Drilling Method Direct Push Technology	Drill Bit Size/Type 2 inch Probe Rods w/ DT21 Dual Tube Sampler	Total Depth of Borehole 10.5 feet bgs
Drill Rig Type GeoProbe Model 5410	Drilling Contractor Vironex	Approximate Surface Elevation ~33 feet MSL
Groundwater Level and Date Measured Not Encountered ATD	Sampling Method(s) None	Hammer Data
Borehole Backfill Bentonite/Cement Slurry	Location Western corner of the property E-SE of MW-6	




Figure GP-1

Project: Vic's Automotive Project Location: 245 8th Street, Oakland, California Project Number: 116907	<h2 style="margin: 0;">Log of Boring GP-2</h2> <p style="margin: 0;">Sheet 1 of 1</p>
---	---

Date(s) Drilled July 13, 2006	Logged By Richard J. Bradford	Checked By Peter McIntyre
Drilling Method Direct Push Technology	Drill Bit Size/Type 2 inch Probe Rods w/ DT21 Dual Tube Sampler	Total Depth of Borehole 10.5 feet bgs
Drill Rig Type GeoProbe Model 5410	Drilling Contractor Vironex	Approximate Surface Elevation ~33 feet MSL
Groundwater Level and Date Measured Not Encountered ATD	Sampling Method(s) None	Hammer Data
Borehole Backfill Bentonite/Cement Slurry	Location Western corner of the property E-SE of MW-6	




Figure GP-2

X:\PROJECTS\CHARACTERIZATION & REMEDIATION\ADVANCED REMEDIATION\116907_SGI - HVDPE (Vic's Automotive)\Oakland, RJB\116907_Soil Gas Investigation\116907_Soil Gas Investigation\SGI Boring Logs GP-1 to GP-4.bgs [Basic Boring Log.rpt]

Project: Vic's Automotive Project Location: 245 8th Street, Oakland, California Project Number: 116907	<h2 style="margin: 0;">Log of Boring GP-3</h2> <p style="margin: 0;">Sheet 1 of 1</p>
---	---

Date(s) Drilled July 13, 2006	Logged By Richard J. Bradford	Checked By Peter McIntyre
Drilling Method Direct Push Technology	Drill Bit Size/Type 2 inch Probe Rods w/ DT21 Dual Tube Sampler	Total Depth of Borehole 10.5 feet bgs
Drill Rig Type GeoProbe Model 5410	Drilling Contractor Vironex	Approximate Surface Elevation ~33 feet MSL
Groundwater Level and Date Measured Not Encountered ATD	Sampling Method(s) None	Hammer Data
Borehole Backfill Bentonite/Cement Slurry	Location Western corner of the property E-SE of MW-6	




Figure GP-3

Project: Vic's Automotive Project Location: 245 8th Street, Oakland, California Project Number: 116907	<h2 style="margin: 0;">Log of Boring GP-4</h2> <p style="margin: 0;">Sheet 1 of 1</p>
---	---

Date(s) Drilled July 13, 2006	Logged By Richard J. Bradford	Checked By Peter McIntyre
Drilling Method Direct Push Technology	Drill Bit Size/Type 2 inch Probe Rods w/ DT21 Dual Tube Sampler	Total Depth of Borehole 10.5 feet bgs
Drill Rig Type GeoProbe Model 5410	Drilling Contractor Vironex	Approximate Surface Elevation ~33 feet MSL
Groundwater Level and Date Measured Not Encountered ATD	Sampling Method(s) None	Hammer Data
Borehole Backfill Bentonite/Cement Slurry	Location Western corner of the property E-SE of MW-6	




Figure GP-4

APPENDIX C

SOIL GAS PROBE FIELD SAMPLING FORMS

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-1-5

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	900
Project Address:	245 8th Street, Oakland	End Time:	1015
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	29
Ending Vacuum (in. Hg)	4
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="v"/>
Depth of Probe (ft bgs)	5.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	48.3
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	31775
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

white tape = 5-foot probe

1 mL = 1 cc

red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-1-10

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	940
Project Address:	245 8th Street, Oakland	End Time:	945
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	29
Ending Vacuum (in. Hg)	3.5
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="v"/>
Depth of Probe (ft bgs)	10.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	82.8
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	12374
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

white tape = 5-foot probe

1 mL = 1 cc

red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-2-5

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	1050
Project Address:	245 8th Street, Oakland	End Time:	1100
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	28.5
Ending Vacuum (in. Hg)	5
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="▼"/>
Depth of Probe (ft bgs)	5.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	48.2
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	25289
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter mL = milliliter L = liter in. Hg = inches of mercury

1 L = 1000 mL white tape = 5-foot probe
1 mL = 1 cc red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-2-10

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	1033
Project Address:	245 8th Street, Oakland	End Time:	1040
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	29
Ending Vacuum (in. Hg)	3.5
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="▼"/>
Depth of Probe (ft bgs)	10.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	82.8
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	2074
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

white tape = 5-foot probe

1 mL = 1 cc

red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-3-5

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	1209
Project Address:	245 8th Street, Oakland	End Time:	1220
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	28.5
Ending Vacuum (in. Hg)	3
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="v"/>
Depth of Probe (ft bgs)	5.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	48.3
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	34623
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

1 mL = 1 cc

white tape = 5-foot probe

red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-3-10

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	1156
Project Address:	245 8th Street, Oakland	End Time:	1206
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	29
Ending Vacuum (in. Hg)	3.5
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="▼"/>
Depth of Probe (ft bgs)	10.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	82.8
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	2176
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

white tape = 5-foot probe

1 mL = 1 cc

red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-4-5

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	1140
Project Address:	245 8th Street, Oakland	End Time:	1146
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	29
Ending Vacuum (in. Hg)	5
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="v"/>
Depth of Probe (ft bgs)	5.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	48.3
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	11434
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

1 mL = 1 cc

white tape = 5-foot probe

red tape = 10-foot probe

AEI CONSULTANTS
SOIL GAS SAMPLING FIELD FORM

Soil Gas Probe Number: GP-4-10

Project Name:	Vic's Automotive	Date of Sampling:	8/4/2006
Job Number:	116907	Start Time:	1121
Project Address:	245 8th Street, Oakland	End Time:	1129
		Name of Sampler:	R. Bradford

SOIL GAS PROBE DATA

Starting Vacuum (in. Hg)	29
Ending Vacuum (in. Hg)	2
Flow Controller / Sampling Flow Rate (ml/min)	167
Tubing Inside Diameter (1/8" or 1/4")	1/8"
Tubing Type	Kynar - PVDF
Wellbox Condition	OK <input type="button" value="▼"/>
Depth of Probe (ft bgs)	10.0
Number of Purge Volumes (default = 3 purge volumes)	3
Total Volume Purged (cc): formula valid only for tubing sizes of 1/8" I.D. (2.30 cc/ft) and 1/4" I.D. (9.20 cc/ft)	82.8
Appreciable Amount of Rain (>1/2") in Last Five Days?	No
Moisture Present in Tubing?	No

SOIL GAS SAMPLES

Number of Samples / Container Size and Type	One (1) 1-Liter Summa Canister
Canister Number	11384 and 11893 (duplicate sample)
Leak Check Compound	Isopropyl Alcohol (i.e., Rubbing Alcohol)

NOTES & COMMENTS

cc = cubic centimeter

mL = milliliter

L = liter

in. Hg = inches of mercury

1 L = 1000 mL

1 mL = 1 cc

white tape = 5-foot probe

red tape = 10-foot probe

APPENDIX D

**LABORATORY ANALYTICAL REPORTS WITH
CHAIN OF CUSTODY DOCUMENTATION**



McC Campbell Analytical, Inc.

"When Quality Counts"

1534 Willow Pass Road, Pittsburg, CA 94565-1701
Web: www.mcccampbell.com E-mail: main@mcccampbell.com
Telephone: 877-252-9262 Fax: 925-252-9269

AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597	Client Project ID: #116907; Vic's Automotive	Date Sampled: 07/13/06
		Date Received: 07/20/06
	Client Contact: Ricky Bradford	Date Reported: 07/27/06
	Client P.O.:	Date Completed: 07/27/06

WorkOrder: 0607358

July 27, 2006

Dear Ricky:

Enclosed are:

- 1). the results of **8** analyzed samples from your **#116907; Vic's Automotive project**,
- 2). a QC report for the above samples
- 3). a copy of the chain of custody, and
- 4). a bill for analytical services.

All analyses were completed satisfactorily and all QC samples were found to be within our control limits.

If you have any questions please contact me. McC Campbell Analytical Laboratories strives for excellence in quality, service and cost. Thank you for your business and I look forward to working with you again.

Best regards,

Angela Rydelius, Lab Manager

McC Campbell Analytical, Inc.



1534 Willow Pass Rd
 Pittsburg, CA 94565-1701
 (925) 252-9262

CHAIN-OF-CUSTODY RECORD

WorkOrder: 0607358

ClientID: AEL

EDF: YES

Report to:

Ricky Bradford
 AEI Consultants
 2500 Camino Diablo, Ste. #200
 Walnut Creek, CA 94597

TEL: (925) 283-6000
 FAX: (925) 283-6121
 ProjectNo: #116907; Vic's Automotive
 PO:

Bill to:

Denise Mockel
 AEI Consultants
 2500 Camino Diablo, Ste. #200
 Walnut Creek, CA 94597

Requested TAT:

5 days

Date Received: **07/20/2006**

Date Printed: **07/21/2006**

Sample ID	ClientSampID	Matrix	Collection Date	Hold	Requested Tests (See legend below)													
					1	2	3	4	5	6	7	8	9	10	11	12		
0607358-001	GP-1-5'	Soil	7/13/06 1:45:00 PM	<input type="checkbox"/>	A	A												
0607358-002	GP-1-10'	Soil	7/13/06 2:00:00 PM	<input type="checkbox"/>	A													
0607358-003	BP-3-10'	Soil	7/13/06 10:00:00	<input type="checkbox"/>	A													
0607358-004	GP-3-4'	Soil	7/13/06 9:40:00 AM	<input type="checkbox"/>	A													
0607358-005	GP-2-5'	Soil	7/13/06 12:40:00	<input type="checkbox"/>	A													
0607358-006	GP-2-10'	Soil	7/13/06 1:00:00 PM	<input type="checkbox"/>	A													
0607358-007	GP-4-10'	Soil	7/13/06 11:15:00	<input type="checkbox"/>	A													
0607358-008	GP-4-5'	Soil	7/13/06 10:59:00	<input type="checkbox"/>	A													

Test Legend:

1	G-MBTX_S	2	PREFD REPORT	3		4		5	
6		7		8		9		10	
11		12							

Prepared by: Melissa Valles

Comments:

NOTE: Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.



McC Campbell Analytical, Inc.

"When Quality Counts"

1534 Willow Pass Road, Pittsburg, CA 94565-1701
Web: www.mcccampbell.com E-mail: main@mcccampbell.com
Telephone: 877-252-9262 Fax: 925-252-9269

AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597	Client Project ID: #116907; Vic's Automotive	Date Sampled: 07/13/06
		Date Received: 07/20/06
	Client Contact: Ricky Bradford	Date Extracted: 07/20/06
	Client P.O.:	Date Analyzed 07/21/06-07/24/06

Gasoline Range (C6-C12) Volatile Hydrocarbons as Gasoline with BTEX and MTBE*

Extraction method SW5030B

Analytical methods SW8021B/8015Cm

Work Order: 0607358

Lab ID	Client ID	Matrix	TPH(g)	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes	DF	% SS
001A	GP-1-5'	S	ND	ND	ND	ND	ND	ND	1	89
002A	GP-1-10'	S	ND	ND	ND	ND	ND	ND	1	101
003A	BP-3-10'	S	ND	ND	ND	ND	ND	ND	1	88
004A	GP-3-4'	S	ND	ND	ND	ND	ND	ND	1	93
005A	GP-2-5'	S	ND	ND	ND	ND	ND	ND	1	101
006A	GP-2-10'	S	ND	ND	ND	ND	ND	ND	1	100
007A	GP-4-10'	S	1.6,a	ND	0.049	0.060	0.019	0.079	1	116
008A	GP-4-5'	S	ND	ND	ND	ND	ND	ND	1	95

Reporting Limit for DF =1; ND means not detected at or above the reporting limit	W	NA	NA	NA	NA	NA	NA	NA	1	ug/L
	S	1.0	0.05	0.005	0.005	0.005	0.005	0.005	1	mg/Kg

* water and vapor samples and all TCLP & SPLP extracts are reported in µg/L, soil/sludge/solid samples in mg/kg, wipe samples in µg/wipe, product/oil/non-aqueous liquid samples in mg/L.

cluttered chromatogram; sample peak coelutes with surrogate peak.

+The following descriptions of the TPH chromatogram are cursory in nature and McC Campbell Analytical is not responsible for their interpretation: a) unmodified or weakly modified gasoline is significant; b) heavier gasoline range compounds are significant(aged gasoline?); c) lighter gasoline range compounds (the most mobile fraction) are significant; d) gasoline range compounds having broad chromatographic peaks are significant; biologically altered gasoline?; e) TPH pattern that does not appear to be derived from gasoline (stoddard solvent / mineral spirit?); f) one to a few isolated non-target peaks present; g) strongly aged gasoline or diesel range compounds are significant; h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~1 vol. % sediment; j) reporting limit raised due to high MTBE content; k) TPH pattern that does not appear to be derived from gasoline (aviation gas). m) no recognizable pattern; n) TPH(g) value derived using a client specified carbon range; o) results are reported on a dry weight basis.



QC SUMMARY REPORT FOR SW8021B/8015Cm

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0607358

EPA Method: SW8021B/8015Cm		Extraction: SW5030B			BatchID: 22784			Spiked Sample ID: 0607355-025A		
Analyte	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance Criteria (%)	
	mg/Kg	mg/Kg	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	MS / MSD	LCS / LCSD
TPH(btex) £	ND	0.60	104	105	0.430	107	99	7.27	70 - 130	70 - 130
MTBE	ND	0.10	106	111	4.63	110	107	2.68	70 - 130	70 - 130
Benzene	ND	0.10	94.1	95.7	1.70	101	95.6	5.85	70 - 130	70 - 130
Toluene	ND	0.10	78.9	80.5	1.94	85.2	79.4	7.01	70 - 130	70 - 130
Ethylbenzene	ND	0.10	95.7	96.9	1.18	101	95.7	5.69	70 - 130	70 - 130
Xylenes	ND	0.30	90.3	90.7	0.368	94.7	90	5.05	70 - 130	70 - 130
%SS:	92	0.10	100	101	0.995	104	99	4.23	70 - 130	70 - 130

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:
NONE

BATCH 22784 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0607358-001A	7/13/06 1:45 PM	7/20/06	7/22/06 5:40 AM	0607358-002A	7/13/06 2:00 PM	7/20/06	7/24/06 6:17 PM
0607358-003A	7/13/06 10:00 AM	7/20/06	7/22/06 6:16 AM	0607358-004A	7/13/06 9:40 AM	7/20/06	7/21/06 8:20 PM
0607358-005A	7/13/06 12:40 PM	7/20/06	7/24/06 6:49 PM	0607358-006A	7/13/06 1:00 PM	7/20/06	7/22/06 11:45 PM
0607358-007A	7/13/06 11:15 AM	7/20/06	7/24/06 7:21 PM	0607358-008A	7/13/06 10:59 AM	7/20/06	7/22/06 1:55 PM

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.
 % Recovery = 100 * (MS-Sample) / (Amount Spiked); RPD = 100 * (MS - MSD) / ((MS + MSD) / 2).
 MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.
 £ TPH(btex) = sum of BTEX areas from the FID.
 # cluttered chromatogram; sample peak coelutes with surrogate peak.
 N/A = not enough sample to perform matrix spike and matrix spike duplicate.
 NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and international laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.O.T. Hotline (800) 467-4922.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

Page 1 of 1

CHAIN-OF-CUSTODY RECORD

Contact Person Ricky Bradford
Company AEI Consultants Email rbradford@aeiconsultants.com
Address 2500 Camino Diablo City Walnut Creek State CA Zip 94597
Phone (925) 293-6000 ext. 140 Fax (925) 944-2995
Collected by: (Signature) R. Bradford

Project Info:		Turn Around Time:	<small>Lab Use Only</small>
P.O. # <u>100685</u>		Presurized by: <u>VR</u>	
Project # <u>116909</u>		Date: <u>8/8/06</u>	
Project Name: <u>Vic's Auto</u>		Presurization Gas: <u>(N₂) He</u>	
		<input checked="" type="checkbox"/> Normal	
		<input type="checkbox"/> Rush	
		<small>specify</small>	

Lab I.D.	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Receipt	Final (psi)
<u>01A</u>	<u>GP-1-5</u>	<u>31775</u>	<u>8/4/06</u>	<u>9:58</u>	<u>TPH-g (TO-3) VOCs (TO-15)</u>	<u>29</u>	<u>4</u>	<u>4.0" Hg</u>	<u>15.0 psi</u>
<u>02A</u>	<u>GP-1-10</u>	<u>12374</u>		<u>9:40</u>		<u>29.5</u>	<u>3.5</u>	<u>3.5" Hg</u>	
<u>03A</u>	<u>GP-2-5</u>	<u>25289</u>		<u>10:50</u>		<u>26.5</u>	<u>5</u>	<u>5.5" Hg</u>	
<u>04A</u>	<u>GP-2-10</u>	<u>62074</u>		<u>10:33</u>		<u>29</u>	<u>3.5</u>	<u>3.0" Hg</u>	
<u>05A</u>	<u>GP-3-5</u>	<u>34623</u>		<u>12:09</u>		<u>29.5</u>	<u>3</u>	<u>4.0" Hg</u>	
<u>06A</u>	<u>GP-3-10</u>	<u>02176</u>		<u>11:56</u>		<u>29</u>	<u>3.5</u>	<u>4.0" Hg</u>	
<u>07A</u>	<u>GP-4-5</u>	<u>11434</u>		<u>11:40</u>		<u>29</u>	<u>5</u>	<u>5.5" Hg</u>	
<u>08A</u>	<u>GP-4-10</u>	<u>13884</u>		<u>11:21</u>		<u>29</u>	<u>2</u>	<u>3.5" Hg</u>	
<u>09A</u>	<u>GP-4-10 Duplicate</u>	<u>11893</u>		<u>11:21</u>		<u>29</u>	<u>0</u>	<u>1.5" Hg</u>	

Relinquished by: (signature) <u>[Signature]</u> Date/Time <u>8/4/06 3:15pm</u>	Received by: (signature) <u>[Signature]</u> Date/Time <u>8/5/06 1330</u>	Notes: <u>ATL</u>
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	

Lab Use Only	Shipper Name <u>DHL</u>	Air Bill # <u>1729815155</u>	Temp (°C) <u>NA</u>	Condition <u>good</u>	Customer Seals Intact? <u>Yes No None</u>	Work Order # <u>0608172</u>
--------------	-------------------------	------------------------------	---------------------	-----------------------	---	-----------------------------

Air Toxics Ltd. Introduces the Electronic Sample Receipt Confirmation

Thank you for choosing Air Toxics Ltd. To better serve our customers, we are providing the sample login confirmation by e-mail. This document is provided in Portable Document Format which can be viewed with Acrobat Reader by Adobe.

This sample receipt confirmation includes the following:

- Cover Page noting any sample receiving discrepancies;
- Sample Receipt Summary;
- Chain of custody (copy);
- Compound Listing; and
- Unreturned Equipment.

Air Toxics Ltd. Sample Receipt Confirmation Cover Page

Thank you for choosing Air Toxics Ltd. We have received your samples and have listed any Sample Receipt Discrepancies below.

In order to expedite analysis and reporting, please review the attached information for accuracy.

For corrections call: **Nicole Danbacher at 916-985-1000**

ATL will proceed with the analysis as specified on the Chain of Custody and Sample Receipt Summary page.

Please note : The Sample Receipt Confirmation, including the total workorder charge, is subject to change upon secondary review. Our aim is to provide a confirmation to you in a timely manner. Sample Receipt Discrepancies, if any, may not include discrepancies regarding sample receipt pressure(s). If additional discrepancies are found you will be contacted via telephone or revised Sample Receipt Confirmation.

SAMPLE RECEIPT SUMMARY

WORKORDER 0608172A

Client
Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

Phone
925-283-6000
Fax
925-283-6121

Date Promised: 08/22/06
Date Completed:
Date Received: 8/5/06
PO#: 100685
Project#: 116907 Vic's Auto

Sales Rep: R9

Total \$: \$ 2,323.00
Logged By: SP

<u>Fraction</u>	<u>Sample #</u>	<u>Analysis</u>	<u>Collected</u>	<u>Amount\$</u>
01A	GP-1-5	Modified TO-15	08/04/06	\$185.00
02A	GP-1-10	Modified TO-15	08/04/06	\$185.00
03A	GP-2-5	Modified TO-15	08/04/06	\$185.00
04A	GP-2-10	Modified TO-15	08/04/06	\$185.00
05A	GP-3-5	Modified TO-15	08/04/06	\$185.00
06A	GP-3-10	Modified TO-15	08/04/06	\$185.00
07A	GP-4-5	Modified TO-15	08/04/06	\$185.00
08A	GP-4-10	Modified TO-15	08/04/06	\$185.00
09A	GP-4-10 Duplicate	Modified TO-15	08/04/06	\$185.00

Misc. Charges Client Specific Disk Format (9) @ \$5.00 each.	\$45.00
1 Liter Summa Canister (9) @ \$30.00 each.	\$270.00
6 Liter Summa Canister (1) @ \$50.00 each.	\$50.00
Blue Body Flow Controller (9) @ \$30.00 each.	\$270.00
Duplicate Sampling T (1) @ \$5.00 each.	\$5.00
Fuel Surcharge (9) @ \$2.00 each.	\$18.00

Note: Samples received after 3 P.M. PST are considered to be received on the following work day.
Atlas Project Name/Profile#: Vick's Automotive/9309

BILL TO: Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

Analysis Code: TO-14A

Reporting Method: Modified TO-15

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020

SAMPLE RECEIPT SUMMARY

WORKORDER 0608172B

Client
Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

Phone
925-283-6000
Fax
925-283-6121

Date Promised: 08/22/06
Date Completed:
Date Received: 8/5/06
PO#: 100685
Project#: 116907 Vic's Auto

Sales Rep: R9

Total \$: \$ 675.00
Logged By: SP

<u>Fraction</u>	<u>Sample #</u>	<u>Analysis</u>	<u>Collected</u>	<u>Amount\$</u>
01A	GP-1-5	Modified TO-3	08/04/06	\$75.00
02A	GP-1-10	Modified TO-3	08/04/06	\$75.00
03A	GP-2-5	Modified TO-3	08/04/06	\$75.00
04A	GP-2-10	Modified TO-3	08/04/06	\$75.00
05A	GP-3-5	Modified TO-3	08/04/06	\$75.00
06A	GP-3-10	Modified TO-3	08/04/06	\$75.00
07A	GP-4-5	Modified TO-3	08/04/06	\$75.00
08A	GP-4-10	Modified TO-3	08/04/06	\$75.00
09A	GP-4-10 Duplicate	Modified TO-3	08/04/06	\$75.00

Note: Samples received after 3 P.M. PST are considered to be received on the following work day.
Atlas Project Name/Profile#: Vick's Automotive/9309

BILL TO: Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

Analysis Code: TO-3/12

Reporting Method: Modified TO-3 (Sh)-TPHg only

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and international laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.C.T. Hotline (800) 467-4922.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

CHAIN-OF-CUSTODY RECORD

Contact Person Ricky Bradford
Company AEI Consultants Email rbradford@aeiconsultants.com
Address 2500 Camino Diablo City Walnut Creek State CA Zip 94597
Phone (925) 253-6000 ext. 148 Fax (925) 944-2895
Collected by: (Signature) R. Bradford

Project Info: P.O. # <u>100685</u> Project # <u>116907</u> Project Name <u>Vic's Auto</u>	Turn Around Time: <input checked="" type="checkbox"/> Normal <input type="checkbox"/> Rush <small>specify</small>	<small>Lab Use Only</small> Pressurized by: _____ Date: _____ Pressurization Gas: N ₂ He
---	---	---

Lab I.D.	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Receipt	Final (PSI)
01A	GP-1-5	31775	8/4/06	9:58	TPH-g (TO-3) VOC's (TO-15)	29	4		
02A	GP-1-10	12374		9:40		29.5	3.5		
03A	GP-2-5	25289		10:50		29.5	5		
04A	GP-2-10	02074		10:33		29	3.5		
05A	GP-3-5	34623		12:09		29.5	3		
06A	GP-3-10	03176		11:56		29	3.5		
07A	GP-4-5	11434		11:40		29	5		
08A	GP-4-10	13384		11:21		29	2		
09A	GP-4-10 Duplicate	11893		11:21		29	0		

Relinquished by: (signature) <u>[Signature]</u> Date/Time <u>8/4/06 3:15pm</u>	Received by: (signature) <u>[Signature]</u> Date/Time <u>8/5/06 1330</u>	Notes:
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	

Lab Use Only	Shipper Name <u>DHL</u>	Air Bill # <u>1729815155</u>	Temp (°C) <u>NA</u>	Condition <u>good</u>	Customer Seals Intact? <u>Yes No None</u>	Work Order # <u>0608172</u>
---------------------	-------------------------	------------------------------	---------------------	-----------------------	---	-----------------------------

Compound Listing

Modified TO-15

CAS Number	Compound	Detection Limit	Type
		ppbv	
75-71-8	Freon 12	0.50	
76-14-2	Freon 114	0.50	
56-23-5	Carbon Tetrachloride	0.50	
540-84-1	2,2,4-Trimethylpentane	0.50	
71-43-2	Benzene	0.50	
107-06-2	1,2-Dichloroethane	0.50	
142-82-5	Heptane	0.50	
79-01-6	Trichloroethene	0.50	
78-87-5	1,2-Dichloropropane	0.50	
123-91-1	1,4-Dioxane	2.0	
75-27-4	Bromodichloromethane	0.50	
10061-01-5	cis-1,3-Dichloropropene	0.50	
108-10-1	4-Methyl-2-pentanone	0.50	
108-88-3	Toluene	0.50	
10061-02-6	trans-1,3-Dichloropropene	0.50	
79-00-5	1,1,2-Trichloroethane	0.50	
127-18-4	Tetrachloroethene	0.50	
591-78-6	2-Hexanone	2.0	
124-48-1	Dibromochloromethane	0.50	
106-93-4	1,2-Dibromoethane (EDB)	0.50	
108-90-7	Chlorobenzene	0.50	
100-41-4	Ethyl Benzene	0.50	
108-38-3	m,p-Xylene	0.50	
95-47-6	o-Xylene	0.50	
100-42-5	Styrene	0.50	
75-25-2	Bromoform	0.50	
98-82-8	Cumene	0.50	
79-34-5	1,1,2,2-Tetrachloroethane	0.50	
103-65-1	Propylbenzene	0.50	
622-96-8	4-Ethyltoluene	0.50	
108-67-8	1,3,5-Trimethylbenzene	0.50	
95-63-6	1,2,4-Trimethylbenzene	0.50	
541-73-1	1,3-Dichlorobenzene	0.50	
106-46-7	1,4-Dichlorobenzene	0.50	
100-44-7	alpha-Chlorotoluene	0.50	
95-50-1	1,2-Dichlorobenzene	0.50	
120-82-1	1,2,4-Trichlorobenzene	2.0	
87-68-3	Hexachlorobutadiene	2.0	
2037-26-5	Toluene-d8		
17060-07-0	1,2-Dichloroethane-d4		
460-00-4	4-Bromofluorobenzene		
74-87-3	Chloromethane	2.0	
75-01-4	Vinyl Chloride	0.50	
106-99-0	1,3-Butadiene	0.50	
74-83-9	Bromomethane	0.50	
75-00-3	Chloroethane	0.50	

Compound Listing

Modified TO-15

CAS Number	Compound	Detection Limit	Type
		ppbv	
75-69-4	Freon 11	0.50	
64-17-5	Ethanol	2.0	
76-13-1	Freon 113	0.50	
75-35-4	1,1-Dichloroethene	0.50	
67-64-1	Acetone	2.0	
67-63-0	2-Propanol	2.0	
75-15-0	Carbon Disulfide	0.50	
107-05-1	3-Chloropropene	2.0	
75-09-2	Methylene Chloride	0.50	
1634-04-4	Methyl tert-butyl ether	0.50	
156-60-5	trans-1,2-Dichloroethene	0.50	
110-54-3	Hexane	0.50	
75-34-3	1,1-Dichloroethane	0.50	
78-93-3	2-Butanone (Methyl Ethyl Ketone)	0.50	
156-59-2	cis-1,2-Dichloroethene	0.50	
109-99-9	Tetrahydrofuran	0.50	
67-66-3	Chloroform	0.50	
71-55-6	1,1,1-Trichloroethane	0.50	
110-82-7	Cyclohexane	0.50	

Compound Listing

Modified TO-3 (Sh)-TPHg only

CAS Number	Compound	Detection Limit	Type
9999-9999-208	TPH (Gasoline Range)	0.025	
462-06-602	Fluorobenzene (FID)		

Air Toxics Ltd. Introduces the Electronic Report

Thank you for choosing Air Toxics Ltd. To better serve our customers, we are providing your report by e-mail. This document is provided in Portable Document Format which can be viewed with Acrobat Reader by Adobe.

This electronic report includes the following:

- Work order Summary;
- Laboratory Narrative;
- Results; and
- Chain of Custody (copy).

WORK ORDER #: 0608172B

Work Order Summary

CLIENT: Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

BILL TO: Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

PHONE: 925-283-6000

FAX: 925-283-6121

DATE RECEIVED: 08/05/2006


DATE COMPLETED: 08/21/2006

P.O. # 100685

PROJECT # 116907 Vic's Auto

CONTACT: Nicole Danbacher

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT VAC./PRES.</u>
01A	GP-1-5	Modified TO-3	4.0 "Hg
02A	GP-1-10	Modified TO-3	3.5 "Hg
03A	GP-2-5	Modified TO-3	5.5 "Hg
04A	GP-2-10	Modified TO-3	3.0 "Hg
05A	GP-3-5	Modified TO-3	4.0 "Hg
06A	GP-3-10	Modified TO-3	4.0 "Hg
07A	GP-4-5	Modified TO-3	5.5 "Hg
07AA	GP-4-5 Duplicate	Modified TO-3	5.5 "Hg
08A	GP-4-10	Modified TO-3	3.5 "Hg
09A	GP-4-10 Duplicate	Modified TO-3	1.5 "Hg
10A	Lab Blank	Modified TO-3	NA
11A	LCS	Modified TO-3	NA

CERTIFIED BY: 

DATE: 08/21/06

Laboratory Director

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,
Accreditation number: E87680, Effective date: 07/01/06, Expiration date: 06/30/07

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020

LABORATORY NARRATIVE
Modified TO-3 (Gas range)
AEI Consultants, Inc.
Workorder# 0608172B

Nine 1 Liter Summa Canister samples were received on August 05, 2006. The laboratory performed analysis for volatile organic compounds in air via modified EPA Method TO-3 using gas chromatography with flame ionization detection. The method involves concentrating up to 200 mL of sample. The concentrated aliquot is then dry purged to remove water vapor prior to entering the chromatographic system. The TPH (Gasoline Range) results are calculated using the response factor of Gasoline and correspond to the range of hydrocarbons from C5 to C10. A molecular weight of 100 is used to convert the TPH (Gasoline Range) ppmv result to ug/L.

See the data sheets for the reporting limits for each compound.

Method modifications taken to run these samples include:

<i>Requirement</i>	<i>TO-3</i>	<i>ATL Modifications</i>
Daily Calibration Standard Frequency	Prior to sample analysis and every 4 - 6 hrs	Prior to sample analysis and after the analytical batch < /= 20 samples
Initial Calibration Calculation	4-point calibration using a linear regression model	5-point calibration using average Response Factor
Initial Calibration Frequency	Weekly	When daily calibration standard recovery is outside 75 - 125 %, or upon significant changes to procedure or instrumentation
Moisture Control	Nafion system	Sorbent system
Minimum Detection Limit (MDL)	Calculated using the equation $DL = A + 3.3S$, where A is intercept of calibration line and S is the standard deviation of at least 3 reps of low level standard	40 CFR Pt. 136 App. B
Preparation of Standards	Levels achieved through dilution of gas mixture	Levels achieved through loading various volumes of the gas mixture

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

There were no analytical discrepancies.



Definition of Data Qualifying Flags

Seven qualifiers may have been used on the data analysis sheets and indicate as follows:

B - Compound present in laboratory blank greater than reporting limit.

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the detection limit.

M - Reported value may be biased due to apparent matrix interferences.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-3 GC/FID

Client Sample ID: GP-1-5

Lab ID#: 0608172B-01A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.058	0.24	0.094	0.38

Client Sample ID: GP-1-10

Lab ID#: 0608172B-02A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.057	0.23	0.14	0.57

Client Sample ID: GP-2-5

Lab ID#: 0608172B-03A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.062	0.25	0.14	0.56

Client Sample ID: GP-2-10

Lab ID#: 0608172B-04A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.056	0.23	0.10	0.42

Client Sample ID: GP-3-5

Lab ID#: 0608172B-05A

No Detections Were Found.

Client Sample ID: GP-3-10

Lab ID#: 0608172B-06A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.058	0.24	0.16	0.65

Client Sample ID: GP-4-5

Lab ID#: 0608172B-07A



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-3 GC/FID

Client Sample ID: GP-4-5

Lab ID#: 0608172B-07A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.062	0.25	0.20	0.80

Client Sample ID: GP-4-5 Duplicate

Lab ID#: 0608172B-07AA

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.062	0.25	0.17	0.69

Client Sample ID: GP-4-10

Lab ID#: 0608172B-08A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.057	0.23	0.16	0.65

Client Sample ID: GP-4-10 Duplicate

Lab ID#: 0608172B-09A

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.053	0.22	0.15	0.63

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-5

Lab ID#: 0608172B-01A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081411	Date of Collection:	8/4/06
Dil. Factor:	2.33	Date of Analysis:	8/14/06 01:45 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.058	0.24	0.094	0.38

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	96	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-10

Lab ID#: 0608172B-02A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081412	Date of Collection:	8/4/06
Dil. Factor:	2.29	Date of Analysis:	8/14/06 02:18 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.057	0.23	0.14	0.57

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	98	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-2-5

Lab ID#: 0608172B-03A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:

d081413

Date of Collection: 8/4/06

Dil. Factor:

2.47

Date of Analysis: 8/14/06 02:52 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.062	0.25	0.14	0.56

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	88	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-2-10

Lab ID#: 0608172B-04A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:

d081421

Date of Collection: 8/4/06

Dil. Factor:

2.24

Date of Analysis: 8/14/06 08:37 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.056	0.23	0.10	0.42

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	100	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-3-5

Lab ID#: 0608172B-05A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:

d081416

Date of Collection: 8/4/06

Dil. Factor:

2.33

Date of Analysis: 8/14/06 05:28 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.058	0.24	Not Detected	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	96	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-3-10

Lab ID#: 0608172B-06A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:

d081417

Date of Collection: 8/4/06

Dil. Factor:

2.33

Date of Analysis: 8/14/06 06:05 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.058	0.24	0.16	0.65

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	95	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-5

Lab ID#: 0608172B-07A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081418	Date of Collection:	8/4/06
Dil. Factor:	2.47	Date of Analysis:	8/14/06 06:45 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.062	0.25	0.20	0.80

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	94	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-5 Duplicate

Lab ID#: 0608172B-07AA

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081422	Date of Collection:	8/4/06
Dil. Factor:	2.47	Date of Analysis:	8/14/06 09:30 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.062	0.25	0.17	0.69

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	92	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-10

Lab ID#: 0608172B-08A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081419	Date of Collection:	8/4/06
Dil. Factor:	2.29	Date of Analysis:	8/14/06 07:22 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.057	0.23	0.16	0.65

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	92	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-10 Duplicate

Lab ID#: 0608172B-09A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081420	Date of Collection:	8/4/06
Dil. Factor:	2.13	Date of Analysis:	8/14/06 08:04 PM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.053	0.22	0.15	0.63

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	92	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0608172B-10A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081403	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	8/14/06 08:45 AM

Compound	Rpt. Limit (ppmv)	Rpt. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH (Gasoline Range)	0.025	0.10	Not Detected	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	92	75-150

@ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0608172B-11A

MODIFIED EPA METHOD TO-3 GC/FID

File Name:	d081423	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/14/06 10:04 PM

Compound	%Recovery
TPH (Gasoline Range)	104

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Fluorobenzene (FID)	105	75-150



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and international laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.D.T. Hotline (800) 467-4922.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

Page 1 of 1

CHAIN-OF-CUSTODY RECORD

Contact Person Ricky Bradford
Company AEI Consultants Email rbradford@aeiconsultants.com
Address 2500 Camino Diablo City Walnut Creek State CA Zip 94597
Phone (925) 253-6000 ext. 146 Fax (925) 944-2995
Collected by: (Signature) R. Bradford

Project Info:	Turn Around Time:	Lab Use Only:
P.O. # <u>100685</u>	<input checked="" type="checkbox"/> Normal <input type="checkbox"/> Rush	Pressurized by: <u>VFR</u>
Project # <u>116907</u>	specify _____	Date: <u>8/8/06</u>
Project Name <u>Vic's Auto</u>		Pressurization Gas: <u>(No) He</u>

Lab I.D.	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Receipt	Final (psi)
01A	GP-1-5	31775	8/4/06	9:58	TPH-g (TO-3) VOCs (TO-15)	29	4	4.0	15.0 psi
02A	GP-1-10	12374		9:40		29.5	3.5	3.5	
03A	GP-2-5	25289		10:50		24.5	5	5.5	
04A	GP-2-10	62074		10:33		29	3.5	3.0	
05A	GP-3-5	34623		12:09		29.5	3	4.0	
06A	GP-3-10	02176		11:56		29	3.5	4.0	
07A	GP-4-5	11434		11:40		29	5	5.5	
08A	GP-4-10	13384		11:21		29	2	3.5	
09A	GP-4-10 Duplicate	11893		11:21		29	0	1.5	

Relinquished by: (signature) <u>[Signature]</u> Date/Time <u>8/4/06 3:15pm</u>	Received by: (signature) <u>[Signature]</u> Date/Time <u>8/5/06 1330</u>	Notes: <u>Chemo-ATL</u>
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	

Lab Use Only	Shipper Name <u>DHL</u>	Air Bill # <u>1729815155</u>	Temp (°C) <u>NA</u>	Condition <u>good</u>	Customer Seals Intact? <u>Yes No None</u>	Work Order # <u>0608172</u>
--------------	-------------------------	------------------------------	---------------------	-----------------------	---	-----------------------------

Air Toxics Ltd. Introduces the Electronic Report

Thank you for choosing Air Toxics Ltd. To better serve our customers, we are providing your report by e-mail. This document is provided in Portable Document Format which can be viewed with Acrobat Reader by Adobe.

This electronic report includes the following:

- Work order Summary;
- Laboratory Narrative;
- Results; and
- Chain of Custody (copy).

WORK ORDER #: 0608172A

Work Order Summary

CLIENT: Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

BILL TO: Mr. Ricky Bradford
AEI Consultants, Inc.
2500 Camino Diablo
Suite 200
Walnut Creek, CA 94597

PHONE: 925-283-6000

FAX: 925-283-6121

DATE RECEIVED: 08/05/2006

DATE COMPLETED: 08/20/2006

P.O. # 100685

PROJECT # 116907 Vic's Auto

CONTACT: Nicole Danbacher

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT VAC./PRES.</u>
01A	GP-1-5	Modified TO-15	4.0 "Hg
01AA	GP-1-5 Duplicate	Modified TO-15	4.0 "Hg
02A	GP-1-10	Modified TO-15	3.5 "Hg
03A	GP-2-5	Modified TO-15	5.5 "Hg
04A	GP-2-10	Modified TO-15	3.0 "Hg
05A	GP-3-5	Modified TO-15	4.0 "Hg
06A	GP-3-10	Modified TO-15	4.0 "Hg
07A	GP-4-5	Modified TO-15	5.5 "Hg
08A	GP-4-10	Modified TO-15	3.5 "Hg
09A	GP-4-10 Duplicate	Modified TO-15	1.5 "Hg
10A	Lab Blank	Modified TO-15	NA
10B	Lab Blank	Modified TO-15	NA
11A	CCV	Modified TO-15	NA
11B	CCV	Modified TO-15	NA
12A	LCS	Modified TO-15	NA
12B	LCS	Modified TO-15	NA

CERTIFIED BY: 

DATE: 08/21/06

Laboratory Director

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,
Accreditation number: E87680, Effective date: 07/01/06, Expiration date: 06/30/07

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020

LABORATORY NARRATIVE
Modified TO-15
AEI Consultants, Inc.
Workorder# 0608172A

Nine 1 Liter Summa Canister samples were received on August 05, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 0.2 liters of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
Daily CCV	+/- 30% Difference	<= 30% Difference with two allowed out up to <=40%.; flag and narrate outliers
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

The reported LCS for each daily batch has been derived from more than one analytical file.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction no performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: GP-1-5

Lab ID#: 0608172A-01A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	8.9	34	21	82
2-Propanol	8.9	9.3	22	23
Carbon Disulfide	2.2	23	7.0	72
1,4-Dioxane	8.9	15	32	54
Tetrachloroethene	2.2	2.6	15	17

Client Sample ID: GP-1-5 Duplicate

Lab ID#: 0608172A-01AA

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	8.9	33	21	78
2-Propanol	8.9	9.2	22	23
Carbon Disulfide	2.2	23	7.0	71
1,4-Dioxane	8.9	16	32	56
Tetrachloroethene	2.2	2.7	15	18

Client Sample ID: GP-1-10

Lab ID#: 0608172A-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	4.6	51	11	120
Carbon Disulfide	1.1	10	3.6	32
2-Butanone (Methyl Ethyl Ketone)	1.1	3.6	3.4	11
Tetrachloroethene	1.1	2.9	7.8	20

Client Sample ID: GP-2-5

Lab ID#: 0608172A-03A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	4.9	48	12	110
Carbon Disulfide	1.2	38	3.8	120
2-Butanone (Methyl Ethyl Ketone)	1.2	1.4	3.6	4.1
Toluene	1.2	1.8	4.6	6.9
Tetrachloroethene	1.2	88	8.4	600
m,p-Xylene	1.2	2.4	5.4	10



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: GP-2-10

Lab ID#: 0608172A-04A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	11	26	27	62
Carbon Disulfide	2.8	6.0	8.8	18
Methylene Chloride	2.8	6.8	9.8	24
2,2,4-Trimethylpentane	2.8	3.2	13	15
Toluene	2.8	4.8	11	18
Tetrachloroethene	2.8	40	19	270

Client Sample ID: GP-3-5

Lab ID#: 0608172A-05A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	4.7	46	11	110
2-Butanone (Methyl Ethyl Ketone)	1.2	1.6	3.4	4.8

Client Sample ID: GP-3-10

Lab ID#: 0608172A-06A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	4.7	100	11	240
Carbon Disulfide	1.2	2.9	3.6	9.0
2-Butanone (Methyl Ethyl Ketone)	1.2	1.9	3.4	5.6

Client Sample ID: GP-4-5

Lab ID#: 0608172A-07A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Acetone	4.9	42	12	100
Carbon Disulfide	1.2	86	3.8	270
2-Butanone (Methyl Ethyl Ketone)	1.2	1.4	3.6	4.3
Benzene	1.2	1.7	3.9	5.4

Client Sample ID: GP-4-10

Lab ID#: 0608172A-08A



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: GP-4-10

Lab ID#: 0608172A-08A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Ethanol	4.6	6.2	8.6	12
Acetone	4.6	55	11	130
Carbon Disulfide	1.1	81	3.6	250
2-Butanone (Methyl Ethyl Ketone)	1.1	3.2	3.4	9.4
Benzene	1.1	1.9	3.6	6.1
Toluene	1.1	4.4	4.3	17
Ethyl Benzene	1.1	1.3	5.0	5.7
m,p-Xylene	1.1	3.7	5.0	16

Client Sample ID: GP-4-10 Duplicate

Lab ID#: 0608172A-09A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Ethanol	4.3	9.6	8.0	18
Acetone	4.3	55	10	130
Carbon Disulfide	1.1	42	3.3	130
2-Butanone (Methyl Ethyl Ketone)	1.1	3.2	3.1	9.4
Benzene	1.1	1.3	3.4	4.2
Toluene	1.1	4.8	4.0	18
m,p-Xylene	1.1	3.9	4.6	17



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-5

Lab ID#: 0608172A-01A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081513	Date of Collection:	8/4/06
Dil. Factor:	4.47	Date of Analysis:	8/15/06 07:34 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	2.2	Not Detected	11	Not Detected
Freon 114	2.2	Not Detected	16	Not Detected
Chloromethane	8.9	Not Detected	18	Not Detected
Vinyl Chloride	2.2	Not Detected	5.7	Not Detected
1,3-Butadiene	2.2	Not Detected	4.9	Not Detected
Bromomethane	2.2	Not Detected	8.7	Not Detected
Chloroethane	2.2	Not Detected	5.9	Not Detected
Freon 11	2.2	Not Detected	12	Not Detected
Ethanol	8.9	Not Detected	17	Not Detected
Freon 113	2.2	Not Detected	17	Not Detected
1,1-Dichloroethene	2.2	Not Detected	8.9	Not Detected
Acetone	8.9	34	21	82
2-Propanol	8.9	9.3	22	23
Carbon Disulfide	2.2	23	7.0	72
3-Chloropropene	8.9	Not Detected	28	Not Detected
Methylene Chloride	2.2	Not Detected	7.8	Not Detected
Methyl tert-butyl ether	2.2	Not Detected	8.0	Not Detected
trans-1,2-Dichloroethene	2.2	Not Detected	8.9	Not Detected
Hexane	2.2	Not Detected	7.9	Not Detected
1,1-Dichloroethane	2.2	Not Detected	9.0	Not Detected
2-Butanone (Methyl Ethyl Ketone)	2.2	Not Detected	6.6	Not Detected
cis-1,2-Dichloroethene	2.2	Not Detected	8.9	Not Detected
Tetrahydrofuran	2.2	Not Detected	6.6	Not Detected
Chloroform	2.2	Not Detected	11	Not Detected
1,1,1-Trichloroethane	2.2	Not Detected	12	Not Detected
Cyclohexane	2.2	Not Detected	7.7	Not Detected
Carbon Tetrachloride	2.2	Not Detected	14	Not Detected
2,2,4-Trimethylpentane	2.2	Not Detected	10	Not Detected
Benzene	2.2	Not Detected	7.1	Not Detected
1,2-Dichloroethane	2.2	Not Detected	9.0	Not Detected
Heptane	2.2	Not Detected	9.2	Not Detected
Trichloroethene	2.2	Not Detected	12	Not Detected
1,2-Dichloropropane	2.2	Not Detected	10	Not Detected
1,4-Dioxane	8.9	15	32	54
Bromodichloromethane	2.2	Not Detected	15	Not Detected
cis-1,3-Dichloropropene	2.2	Not Detected	10	Not Detected
4-Methyl-2-pentanone	2.2	Not Detected	9.2	Not Detected
Toluene	2.2	Not Detected	8.4	Not Detected
trans-1,3-Dichloropropene	2.2	Not Detected	10	Not Detected
1,1,2-Trichloroethane	2.2	Not Detected	12	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-5

Lab ID#: 0608172A-01A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081513	Date of Collection:	8/4/06
Dil. Factor:	4.47	Date of Analysis:	8/15/06 07:34 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	2.2	2.6	15	17
2-Hexanone	8.9	Not Detected	37	Not Detected
Dibromochloromethane	2.2	Not Detected	19	Not Detected
1,2-Dibromoethane (EDB)	2.2	Not Detected	17	Not Detected
Chlorobenzene	2.2	Not Detected	10	Not Detected
Ethyl Benzene	2.2	Not Detected	9.7	Not Detected
m,p-Xylene	2.2	Not Detected	9.7	Not Detected
o-Xylene	2.2	Not Detected	9.7	Not Detected
Styrene	2.2	Not Detected	9.5	Not Detected
Bromoform	2.2	Not Detected	23	Not Detected
Cumene	2.2	Not Detected	11	Not Detected
1,1,2,2-Tetrachloroethane	2.2	Not Detected	15	Not Detected
Propylbenzene	2.2	Not Detected	11	Not Detected
4-Ethyltoluene	2.2	Not Detected	11	Not Detected
1,3,5-Trimethylbenzene	2.2	Not Detected	11	Not Detected
1,2,4-Trimethylbenzene	2.2	Not Detected	11	Not Detected
1,3-Dichlorobenzene	2.2	Not Detected	13	Not Detected
1,4-Dichlorobenzene	2.2	Not Detected	13	Not Detected
alpha-Chlorotoluene	2.2	Not Detected	12	Not Detected
1,2-Dichlorobenzene	2.2	Not Detected	13	Not Detected
1,2,4-Trichlorobenzene	8.9	Not Detected	66	Not Detected
Hexachlorobutadiene	8.9	Not Detected	95	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	96	70-130
1,2-Dichloroethane-d4	97	70-130
4-Bromofluorobenzene	99	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-5 Duplicate

Lab ID#: 0608172A-01AA

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081514	Date of Collection:	8/4/06
Dil. Factor:	4.47	Date of Analysis:	8/15/06 08:13 PM

Compound	Rot. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	2.2	Not Detected	11	Not Detected
Freon 114	2.2	Not Detected	16	Not Detected
Chloromethane	8.9	Not Detected	18	Not Detected
Vinyl Chloride	2.2	Not Detected	5.7	Not Detected
1,3-Butadiene	2.2	Not Detected	4.9	Not Detected
Bromomethane	2.2	Not Detected	8.7	Not Detected
Chloroethane	2.2	Not Detected	5.9	Not Detected
Freon 11	2.2	Not Detected	12	Not Detected
Ethanol	8.9	Not Detected	17	Not Detected
Freon 113	2.2	Not Detected	17	Not Detected
1,1-Dichloroethene	2.2	Not Detected	8.9	Not Detected
Acetone	8.9	33	21	78
2-Propanol	8.9	9.2	22	23
Carbon Disulfide	2.2	23	7.0	71
3-Chloropropene	8.9	Not Detected	28	Not Detected
Methylene Chloride	2.2	Not Detected	7.8	Not Detected
Methyl tert-butyl ether	2.2	Not Detected	8.0	Not Detected
trans-1,2-Dichloroethene	2.2	Not Detected	8.9	Not Detected
Hexane	2.2	Not Detected	7.9	Not Detected
1,1-Dichloroethane	2.2	Not Detected	9.0	Not Detected
2-Butanone (Methyl Ethyl Ketone)	2.2	Not Detected	6.6	Not Detected
cis-1,2-Dichloroethene	2.2	Not Detected	8.9	Not Detected
Tetrahydrofuran	2.2	Not Detected	6.6	Not Detected
Chloroform	2.2	Not Detected	11	Not Detected
1,1,1-Trichloroethane	2.2	Not Detected	12	Not Detected
Cyclohexane	2.2	Not Detected	7.7	Not Detected
Carbon Tetrachloride	2.2	Not Detected	14	Not Detected
2,2,4-Trimethylpentane	2.2	Not Detected	10	Not Detected
Benzene	2.2	Not Detected	7.1	Not Detected
1,2-Dichloroethane	2.2	Not Detected	9.0	Not Detected
Heptane	2.2	Not Detected	9.2	Not Detected
Trichloroethene	2.2	Not Detected	12	Not Detected
1,2-Dichloropropane	2.2	Not Detected	10	Not Detected
1,4-Dioxane	8.9	16	32	56
Bromodichloromethane	2.2	Not Detected	15	Not Detected
cis-1,3-Dichloropropene	2.2	Not Detected	10	Not Detected
4-Methyl-2-pentanone	2.2	Not Detected	9.2	Not Detected
Toluene	2.2	Not Detected	8.4	Not Detected
trans-1,3-Dichloropropene	2.2	Not Detected	10	Not Detected
1,1,2-Trichloroethane	2.2	Not Detected	12	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-5 Duplicate

Lab ID#: 0608172A-01AA

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081514	Date of Collection:	8/4/06
Dil. Factor:	4.47	Date of Analysis:	8/15/06 08:13 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	2.2	2.7	15	18
2-Hexanone	8.9	Not Detected	37	Not Detected
Dibromochloromethane	2.2	Not Detected	19	Not Detected
1,2-Dibromoethane (EDB)	2.2	Not Detected	17	Not Detected
Chlorobenzene	2.2	Not Detected	10	Not Detected
Ethyl Benzene	2.2	Not Detected	9.7	Not Detected
m,p-Xylene	2.2	Not Detected	9.7	Not Detected
o-Xylene	2.2	Not Detected	9.7	Not Detected
Styrene	2.2	Not Detected	9.5	Not Detected
Bromoform	2.2	Not Detected	23	Not Detected
Cumene	2.2	Not Detected	11	Not Detected
1,1,2,2-Tetrachloroethane	2.2	Not Detected	15	Not Detected
Propylbenzene	2.2	Not Detected	11	Not Detected
4-Ethyltoluene	2.2	Not Detected	11	Not Detected
1,3,5-Trimethylbenzene	2.2	Not Detected	11	Not Detected
1,2,4-Trimethylbenzene	2.2	Not Detected	11	Not Detected
1,3-Dichlorobenzene	2.2	Not Detected	13	Not Detected
1,4-Dichlorobenzene	2.2	Not Detected	13	Not Detected
alpha-Chlorotoluene	2.2	Not Detected	12	Not Detected
1,2-Dichlorobenzene	2.2	Not Detected	13	Not Detected
1,2,4-Trichlorobenzene	8.9	Not Detected	66	Not Detected
Hexachlorobutadiene	8.9	Not Detected	95	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	96	70-130
1,2-Dichloroethane-d4	100	70-130
4-Bromofluorobenzene	97	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-10

Lab ID#: 0608172A-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081426	Date of Collection:	8/4/06
Dil. Factor:	2.29	Date of Analysis:	8/15/06 05:09 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.1	Not Detected	5.7	Not Detected
Freon 114	1.1	Not Detected	8.0	Not Detected
Chloromethane	4.6	Not Detected	9.4	Not Detected
Vinyl Chloride	1.1	Not Detected	2.9	Not Detected
1,3-Butadiene	1.1	Not Detected	2.5	Not Detected
Bromomethane	1.1	Not Detected	4.4	Not Detected
Chloroethane	1.1	Not Detected	3.0	Not Detected
Freon 11	1.1	Not Detected	6.4	Not Detected
Ethanol	4.6	Not Detected	8.6	Not Detected
Freon 113	1.1	Not Detected	8.8	Not Detected
1,1-Dichloroethene	1.1	Not Detected	4.5	Not Detected
Acetone	4.6	51	11	120
2-Propanol	4.6	Not Detected	11	Not Detected
Carbon Disulfide	1.1	10	3.6	32
3-Chloropropene	4.6	Not Detected	14	Not Detected
Methylene Chloride	1.1	Not Detected	4.0	Not Detected
Methyl tert-butyl ether	1.1	Not Detected	4.1	Not Detected
trans-1,2-Dichloroethene	1.1	Not Detected	4.5	Not Detected
Hexane	1.1	Not Detected	4.0	Not Detected
1,1-Dichloroethane	1.1	Not Detected	4.6	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.1	3.6	3.4	11
cis-1,2-Dichloroethene	1.1	Not Detected	4.5	Not Detected
Tetrahydrofuran	1.1	Not Detected	3.4	Not Detected
Chloroform	1.1	Not Detected	5.6	Not Detected
1,1,1-Trichloroethane	1.1	Not Detected	6.2	Not Detected
Cyclohexane	1.1	Not Detected	3.9	Not Detected
Carbon Tetrachloride	1.1	Not Detected	7.2	Not Detected
2,2,4-Trimethylpentane	1.1	Not Detected	5.3	Not Detected
Benzene	1.1	Not Detected	3.6	Not Detected
1,2-Dichloroethane	1.1	Not Detected	4.6	Not Detected
Heptane	1.1	Not Detected	4.7	Not Detected
Trichloroethene	1.1	Not Detected	6.2	Not Detected
1,2-Dichloropropane	1.1	Not Detected	5.3	Not Detected
1,4-Dioxane	4.6	Not Detected	16	Not Detected
Bromodichloromethane	1.1	Not Detected	7.7	Not Detected
cis-1,3-Dichloropropene	1.1	Not Detected	5.2	Not Detected
4-Methyl-2-pentanone	1.1	Not Detected	4.7	Not Detected
Toluene	1.1	Not Detected	4.3	Not Detected
trans-1,3-Dichloropropene	1.1	Not Detected	5.2	Not Detected
1,1,2-Trichloroethane	1.1	Not Detected	6.2	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-1-10

Lab ID#: 0608172A-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081426	Date of Collection:	8/4/06
Dil. Factor:	2.29	Date of Analysis:	8/15/06 05:09 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.1	2.9	7.8	20
2-Hexanone	4.6	Not Detected	19	Not Detected
Dibromochloromethane	1.1	Not Detected	9.8	Not Detected
1,2-Dibromoethane (EDB)	1.1	Not Detected	8.8	Not Detected
Chlorobenzene	1.1	Not Detected	5.3	Not Detected
Ethyl Benzene	1.1	Not Detected	5.0	Not Detected
m,p-Xylene	1.1	Not Detected	5.0	Not Detected
o-Xylene	1.1	Not Detected	5.0	Not Detected
Styrene	1.1	Not Detected	4.9	Not Detected
Bromoform	1.1	Not Detected	12	Not Detected
Cumene	1.1	Not Detected	5.6	Not Detected
1,1,2,2-Tetrachloroethane	1.1	Not Detected	7.9	Not Detected
Propylbenzene	1.1	Not Detected	5.6	Not Detected
4-Ethyltoluene	1.1	Not Detected	5.6	Not Detected
1,3,5-Trimethylbenzene	1.1	Not Detected	5.6	Not Detected
1,2,4-Trimethylbenzene	1.1	Not Detected	5.6	Not Detected
1,3-Dichlorobenzene	1.1	Not Detected	6.9	Not Detected
1,4-Dichlorobenzene	1.1	Not Detected	6.9	Not Detected
alpha-Chlorotoluene	1.1	Not Detected	5.9	Not Detected
1,2-Dichlorobenzene	1.1	Not Detected	6.9	Not Detected
1,2,4-Trichlorobenzene	4.6	Not Detected	34	Not Detected
Hexachlorobutadiene	4.6	Not Detected	49	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	96	70-130
1,2-Dichloroethane-d4	96	70-130
4-Bromofluorobenzene	102	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-2-5

Lab ID#: 0608172A-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081420	Date of Collection:	8/4/06
Dil. Factor:	2.47	Date of Analysis:	8/15/06 12:21 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.2	Not Detected	6.1	Not Detected
Freon 114	1.2	Not Detected	8.6	Not Detected
Chloromethane	4.9	Not Detected	10	Not Detected
Vinyl Chloride	1.2	Not Detected	3.2	Not Detected
1,3-Butadiene	1.2	Not Detected	2.7	Not Detected
Bromomethane	1.2	Not Detected	4.8	Not Detected
Chloroethane	1.2	Not Detected	3.2	Not Detected
Freon 11	1.2	Not Detected	6.9	Not Detected
Ethanol	4.9	Not Detected	9.3	Not Detected
Freon 113	1.2	Not Detected	9.5	Not Detected
1,1-Dichloroethene	1.2	Not Detected	4.9	Not Detected
Acetone	4.9	48	12	110
2-Propanol	4.9	Not Detected	12	Not Detected
Carbon Disulfide	1.2	38	3.8	120
3-Chloropropene	4.9	Not Detected	15	Not Detected
Methylene Chloride	1.2	Not Detected	4.3	Not Detected
Methyl tert-butyl ether	1.2	Not Detected	4.4	Not Detected
trans-1,2-Dichloroethene	1.2	Not Detected	4.9	Not Detected
Hexane	1.2	Not Detected	4.4	Not Detected
1,1-Dichloroethane	1.2	Not Detected	5.0	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.2	1.4	3.6	4.1
cis-1,2-Dichloroethene	1.2	Not Detected	4.9	Not Detected
Tetrahydrofuran	1.2	Not Detected	3.6	Not Detected
Chloroform	1.2	Not Detected	6.0	Not Detected
1,1,1-Trichloroethane	1.2	Not Detected	6.7	Not Detected
Cyclohexane	1.2	Not Detected	4.2	Not Detected
Carbon Tetrachloride	1.2	Not Detected	7.8	Not Detected
2,2,4-Trimethylpentane	1.2	Not Detected	5.8	Not Detected
Benzene	1.2	Not Detected	3.9	Not Detected
1,2-Dichloroethane	1.2	Not Detected	5.0	Not Detected
Heptane	1.2	Not Detected	5.1	Not Detected
Trichloroethene	1.2	Not Detected	6.6	Not Detected
1,2-Dichloropropane	1.2	Not Detected	5.7	Not Detected
1,4-Dioxane	4.9	Not Detected	18	Not Detected
Bromodichloromethane	1.2	Not Detected	8.3	Not Detected
cis-1,3-Dichloropropene	1.2	Not Detected	5.6	Not Detected
4-Methyl-2-pentanone	1.2	Not Detected	5.0	Not Detected
Toluene	1.2	1.8	4.6	6.9
trans-1,3-Dichloropropene	1.2	Not Detected	5.6	Not Detected
1,1,2-Trichloroethane	1.2	Not Detected	6.7	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-2-5

Lab ID#: 0608172A-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081420	Date of Collection:	8/4/06
Dil. Factor:	2.47	Date of Analysis:	8/15/06 12:21 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.2	88	8.4	600
2-Hexanone	4.9	Not Detected	20	Not Detected
Dibromochloromethane	1.2	Not Detected	10	Not Detected
1,2-Dibromoethane (EDB)	1.2	Not Detected	9.5	Not Detected
Chlorobenzene	1.2	Not Detected	5.7	Not Detected
Ethyl Benzene	1.2	Not Detected	5.4	Not Detected
m,p-Xylene	1.2	2.4	5.4	10
o-Xylene	1.2	Not Detected	5.4	Not Detected
Styrene	1.2	Not Detected	5.3	Not Detected
Bromoform	1.2	Not Detected	13	Not Detected
Cumene	1.2	Not Detected	6.1	Not Detected
1,1,2,2-Tetrachloroethane	1.2	Not Detected	8.5	Not Detected
Propylbenzene	1.2	Not Detected	6.1	Not Detected
4-Ethyltoluene	1.2	Not Detected	6.1	Not Detected
1,3,5-Trimethylbenzene	1.2	Not Detected	6.1	Not Detected
1,2,4-Trimethylbenzene	1.2	Not Detected	6.1	Not Detected
1,3-Dichlorobenzene	1.2	Not Detected	7.4	Not Detected
1,4-Dichlorobenzene	1.2	Not Detected	7.4	Not Detected
alpha-Chlorotoluene	1.2	Not Detected	6.4	Not Detected
1,2-Dichlorobenzene	1.2	Not Detected	7.4	Not Detected
1,2,4-Trichlorobenzene	4.9	Not Detected	37	Not Detected
Hexachlorobutadiene	4.9	Not Detected	53	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	98	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	98	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-2-10

Lab ID#: 0608172A-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name: 1081512 Date of Collection: 8/4/06
Dil. Factor: 5.67 Date of Analysis: 8/15/06 06:54 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	2.8	Not Detected	14	Not Detected
Freon 114	2.8	Not Detected	20	Not Detected
Chloromethane	11	Not Detected	23	Not Detected
Vinyl Chloride	2.8	Not Detected	7.2	Not Detected
1,3-Butadiene	2.8	Not Detected	6.3	Not Detected
Bromomethane	2.8	Not Detected	11	Not Detected
Chloroethane	2.8	Not Detected	7.5	Not Detected
Freon 11	2.8	Not Detected	16	Not Detected
Ethanol	11	Not Detected	21	Not Detected
Freon 113	2.8	Not Detected	22	Not Detected
1,1-Dichloroethene	2.8	Not Detected	11	Not Detected
Acetone	11	26	27	62
2-Propanol	11	Not Detected	28	Not Detected
Carbon Disulfide	2.8	6.0	8.8	18
3-Chloropropene	11	Not Detected	35	Not Detected
Methylene Chloride	2.8	6.8	9.8	24
Methyl tert-butyl ether	2.8	Not Detected	10	Not Detected
trans-1,2-Dichloroethene	2.8	Not Detected	11	Not Detected
Hexane	2.8	Not Detected	10	Not Detected
1,1-Dichloroethane	2.8	Not Detected	11	Not Detected
2-Butanone (Methyl Ethyl Ketone)	2.8	Not Detected	8.4	Not Detected
cis-1,2-Dichloroethene	2.8	Not Detected	11	Not Detected
Tetrahydrofuran	2.8	Not Detected	8.4	Not Detected
Chloroform	2.8	Not Detected	14	Not Detected
1,1,1-Trichloroethane	2.8	Not Detected	15	Not Detected
Cyclohexane	2.8	Not Detected	9.8	Not Detected
Carbon Tetrachloride	2.8	Not Detected	18	Not Detected
2,2,4-Trimethylpentane	2.8	3.2	13	15
Benzene	2.8	Not Detected	9.0	Not Detected
1,2-Dichloroethane	2.8	Not Detected	11	Not Detected
Heptane	2.8	Not Detected	12	Not Detected
Trichloroethene	2.8	Not Detected	15	Not Detected
1,2-Dichloropropane	2.8	Not Detected	13	Not Detected
1,4-Dioxane	11	Not Detected	41	Not Detected
Bromodichloromethane	2.8	Not Detected	19	Not Detected
cis-1,3-Dichloropropene	2.8	Not Detected	13	Not Detected
4-Methyl-2-pentanone	2.8	Not Detected	12	Not Detected
Toluene	2.8	4.8	11	18
trans-1,3-Dichloropropene	2.8	Not Detected	13	Not Detected
1,1,2-Trichloroethane	2.8	Not Detected	15	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-2-10

Lab ID#: 0608172A-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081512	Date of Collection:	8/4/06
Dil. Factor:	5.67	Date of Analysis:	8/15/06 06:54 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	2.8	40	19	270
2-Hexanone	11	Not Detected	46	Not Detected
Dibromochloromethane	2.8	Not Detected	24	Not Detected
1,2-Dibromoethane (EDB)	2.8	Not Detected	22	Not Detected
Chlorobenzene	2.8	Not Detected	13	Not Detected
Ethyl Benzene	2.8	Not Detected	12	Not Detected
m,p-Xylene	2.8	Not Detected	12	Not Detected
o-Xylene	2.8	Not Detected	12	Not Detected
Styrene	2.8	Not Detected	12	Not Detected
Bromoform	2.8	Not Detected	29	Not Detected
Cumene	2.8	Not Detected	14	Not Detected
1,1,2,2-Tetrachloroethane	2.8	Not Detected	19	Not Detected
Propylbenzene	2.8	Not Detected	14	Not Detected
4-Ethyltoluene	2.8	Not Detected	14	Not Detected
1,3,5-Trimethylbenzene	2.8	Not Detected	14	Not Detected
1,2,4-Trimethylbenzene	2.8	Not Detected	14	Not Detected
1,3-Dichlorobenzene	2.8	Not Detected	17	Not Detected
1,4-Dichlorobenzene	2.8	Not Detected	17	Not Detected
alpha-Chlorotoluene	2.8	Not Detected	15	Not Detected
1,2-Dichlorobenzene	2.8	Not Detected	17	Not Detected
1,2,4-Trichlorobenzene	11	Not Detected	84	Not Detected
Hexachlorobutadiene	11	Not Detected	120	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	100	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-3-5

Lab ID#: 0608172A-05A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081421	Date of Collection:	8/4/06
Dil. Factor:	2.33	Date of Analysis:	8/15/06 01:11 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.2	Not Detected	5.8	Not Detected
Freon 114	1.2	Not Detected	8.1	Not Detected
Chloromethane	4.7	Not Detected	9.6	Not Detected
Vinyl Chloride	1.2	Not Detected	3.0	Not Detected
1,3-Butadiene	1.2	Not Detected	2.6	Not Detected
Bromomethane	1.2	Not Detected	4.5	Not Detected
Chloroethane	1.2	Not Detected	3.1	Not Detected
Freon 11	1.2	Not Detected	6.5	Not Detected
Ethanol	4.7	Not Detected	8.8	Not Detected
Freon 113	1.2	Not Detected	8.9	Not Detected
1,1-Dichloroethene	1.2	Not Detected	4.6	Not Detected
Acetone	4.7	46	11	110
2-Propanol	4.7	Not Detected	11	Not Detected
Carbon Disulfide	1.2	Not Detected	3.6	Not Detected
3-Chloropropene	4.7	Not Detected	14	Not Detected
Methylene Chloride	1.2	Not Detected	4.0	Not Detected
Methyl tert-butyl ether	1.2	Not Detected	4.2	Not Detected
trans-1,2-Dichloroethene	1.2	Not Detected	4.6	Not Detected
Hexane	1.2	Not Detected	4.1	Not Detected
1,1-Dichloroethane	1.2	Not Detected	4.7	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.2	1.6	3.4	4.8
cis-1,2-Dichloroethene	1.2	Not Detected	4.6	Not Detected
Tetrahydrofuran	1.2	Not Detected	3.4	Not Detected
Chloroform	1.2	Not Detected	5.7	Not Detected
1,1,1-Trichloroethane	1.2	Not Detected	6.4	Not Detected
Cyclohexane	1.2	Not Detected	4.0	Not Detected
Carbon Tetrachloride	1.2	Not Detected	7.3	Not Detected
2,2,4-Trimethylpentane	1.2	Not Detected	5.4	Not Detected
Benzene	1.2	Not Detected	3.7	Not Detected
1,2-Dichloroethane	1.2	Not Detected	4.7	Not Detected
Heptane	1.2	Not Detected	4.8	Not Detected
Trichloroethene	1.2	Not Detected	6.3	Not Detected
1,2-Dichloropropane	1.2	Not Detected	5.4	Not Detected
1,4-Dioxane	4.7	Not Detected	17	Not Detected
Bromodichloromethane	1.2	Not Detected	7.8	Not Detected
cis-1,3-Dichloropropene	1.2	Not Detected	5.3	Not Detected
4-Methyl-2-pentanone	1.2	Not Detected	4.8	Not Detected
Toluene	1.2	Not Detected	4.4	Not Detected
trans-1,3-Dichloropropene	1.2	Not Detected	5.3	Not Detected
1,1,2-Trichloroethane	1.2	Not Detected	6.4	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-3-5

Lab ID#: 0608172A-05A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081421	Date of Collection:	8/4/06
Dil. Factor:	2.33	Date of Analysis:	8/15/06 01:11 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.2	Not Detected	7.9	Not Detected
2-Hexanone	4.7	Not Detected	19	Not Detected
Dibromochloromethane	1.2	Not Detected	9.9	Not Detected
1,2-Dibromoethane (EDB)	1.2	Not Detected	9.0	Not Detected
Chlorobenzene	1.2	Not Detected	5.4	Not Detected
Ethyl Benzene	1.2	Not Detected	5.0	Not Detected
m,p-Xylene	1.2	Not Detected	5.0	Not Detected
o-Xylene	1.2	Not Detected	5.0	Not Detected
Styrene	1.2	Not Detected	5.0	Not Detected
Bromoform	1.2	Not Detected	12	Not Detected
Cumene	1.2	Not Detected	5.7	Not Detected
1,1,2,2-Tetrachloroethane	1.2	Not Detected	8.0	Not Detected
Propylbenzene	1.2	Not Detected	5.7	Not Detected
4-Ethyltoluene	1.2	Not Detected	5.7	Not Detected
1,3,5-Trimethylbenzene	1.2	Not Detected	5.7	Not Detected
1,2,4-Trimethylbenzene	1.2	Not Detected	5.7	Not Detected
1,3-Dichlorobenzene	1.2	Not Detected	7.0	Not Detected
1,4-Dichlorobenzene	1.2	Not Detected	7.0	Not Detected
alpha-Chlorotoluene	1.2	Not Detected	6.0	Not Detected
1,2-Dichlorobenzene	1.2	Not Detected	7.0	Not Detected
1,2,4-Trichlorobenzene	4.7	Not Detected	34	Not Detected
Hexachlorobutadiene	4.7	Not Detected	50	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	100	70-130
4-Bromofluorobenzene	99	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-3-10

Lab ID#: 0608172A-06A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081422	Date of Collection:	8/4/06
Dil. Factor:	2.33	Date of Analysis:	8/15/06 01:55 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.2	Not Detected	5.8	Not Detected
Freon 114	1.2	Not Detected	8.1	Not Detected
Chloromethane	4.7	Not Detected	9.6	Not Detected
Vinyl Chloride	1.2	Not Detected	3.0	Not Detected
1,3-Butadiene	1.2	Not Detected	2.6	Not Detected
Bromomethane	1.2	Not Detected	4.5	Not Detected
Chloroethane	1.2	Not Detected	3.1	Not Detected
Freon 11	1.2	Not Detected	6.5	Not Detected
Ethanol	4.7	Not Detected	8.8	Not Detected
Freon 113	1.2	Not Detected	8.9	Not Detected
1,1-Dichloroethene	1.2	Not Detected	4.6	Not Detected
Acetone	4.7	100	11	240
2-Propanol	4.7	Not Detected	11	Not Detected
Carbon Disulfide	1.2	2.9	3.6	9.0
3-Chloropropene	4.7	Not Detected	14	Not Detected
Methylene Chloride	1.2	Not Detected	4.0	Not Detected
Methyl tert-butyl ether	1.2	Not Detected	4.2	Not Detected
trans-1,2-Dichloroethene	1.2	Not Detected	4.6	Not Detected
Hexane	1.2	Not Detected	4.1	Not Detected
1,1-Dichloroethane	1.2	Not Detected	4.7	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.2	1.9	3.4	5.6
cis-1,2-Dichloroethene	1.2	Not Detected	4.6	Not Detected
Tetrahydrofuran	1.2	Not Detected	3.4	Not Detected
Chloroform	1.2	Not Detected	5.7	Not Detected
1,1,1-Trichloroethane	1.2	Not Detected	6.4	Not Detected
Cyclohexane	1.2	Not Detected	4.0	Not Detected
Carbon Tetrachloride	1.2	Not Detected	7.3	Not Detected
2,2,4-Trimethylpentane	1.2	Not Detected	5.4	Not Detected
Benzene	1.2	Not Detected	3.7	Not Detected
1,2-Dichloroethane	1.2	Not Detected	4.7	Not Detected
Heptane	1.2	Not Detected	4.8	Not Detected
Trichloroethene	1.2	Not Detected	6.3	Not Detected
1,2-Dichloropropane	1.2	Not Detected	5.4	Not Detected
1,4-Dioxane	4.7	Not Detected	17	Not Detected
Bromodichloromethane	1.2	Not Detected	7.8	Not Detected
cis-1,3-Dichloropropene	1.2	Not Detected	5.3	Not Detected
4-Methyl-2-pentanone	1.2	Not Detected	4.8	Not Detected
Toluene	1.2	Not Detected	4.4	Not Detected
trans-1,3-Dichloropropene	1.2	Not Detected	5.3	Not Detected
1,1,2-Trichloroethane	1.2	Not Detected	6.4	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-3-10

Lab ID#: 0608172A-06A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081422	Date of Collection:	8/4/06
Dil. Factor:	2.33	Date of Analysis:	8/15/06 01:55 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.2	Not Detected	7.9	Not Detected
2-Hexanone	4.7	Not Detected	19	Not Detected
Dibromochloromethane	1.2	Not Detected	9.9	Not Detected
1,2-Dibromoethane (EDB)	1.2	Not Detected	9.0	Not Detected
Chlorobenzene	1.2	Not Detected	5.4	Not Detected
Ethyl Benzene	1.2	Not Detected	5.0	Not Detected
m,p-Xylene	1.2	Not Detected	5.0	Not Detected
o-Xylene	1.2	Not Detected	5.0	Not Detected
Styrene	1.2	Not Detected	5.0	Not Detected
Bromoform	1.2	Not Detected	12	Not Detected
Cumene	1.2	Not Detected	5.7	Not Detected
1,1,2,2-Tetrachloroethane	1.2	Not Detected	8.0	Not Detected
Propylbenzene	1.2	Not Detected	5.7	Not Detected
4-Ethyltoluene	1.2	Not Detected	5.7	Not Detected
1,3,5-Trimethylbenzene	1.2	Not Detected	5.7	Not Detected
1,2,4-Trimethylbenzene	1.2	Not Detected	5.7	Not Detected
1,3-Dichlorobenzene	1.2	Not Detected	7.0	Not Detected
1,4-Dichlorobenzene	1.2	Not Detected	7.0	Not Detected
alpha-Chlorotoluene	1.2	Not Detected	6.0	Not Detected
1,2-Dichlorobenzene	1.2	Not Detected	7.0	Not Detected
1,2,4-Trichlorobenzene	4.7	Not Detected	34	Not Detected
Hexachlorobutadiene	4.7	Not Detected	50	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	94	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-5

Lab ID#: 0608172A-07A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081423	Date of Collection:	8/4/06
Dil. Factor:	2.47	Date of Analysis:	8/15/06 02:43 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.2	Not Detected	6.1	Not Detected
Freon 114	1.2	Not Detected	8.6	Not Detected
Chloromethane	4.9	Not Detected	10	Not Detected
Vinyl Chloride	1.2	Not Detected	3.2	Not Detected
1,3-Butadiene	1.2	Not Detected	2.7	Not Detected
Bromomethane	1.2	Not Detected	4.8	Not Detected
Chloroethane	1.2	Not Detected	3.2	Not Detected
Freon 11	1.2	Not Detected	6.9	Not Detected
Ethanol	4.9	Not Detected	9.3	Not Detected
Freon 113	1.2	Not Detected	9.5	Not Detected
1,1-Dichloroethene	1.2	Not Detected	4.9	Not Detected
Acetone	4.9	42	12	100
2-Propanol	4.9	Not Detected	12	Not Detected
Carbon Disulfide	1.2	86	3.8	270
3-Chloropropene	4.9	Not Detected	15	Not Detected
Methylene Chloride	1.2	Not Detected	4.3	Not Detected
Methyl tert-butyl ether	1.2	Not Detected	4.4	Not Detected
trans-1,2-Dichloroethene	1.2	Not Detected	4.9	Not Detected
Hexane	1.2	Not Detected	4.4	Not Detected
1,1-Dichloroethane	1.2	Not Detected	5.0	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.2	1.4	3.6	4.3
cis-1,2-Dichloroethene	1.2	Not Detected	4.9	Not Detected
Tetrahydrofuran	1.2	Not Detected	3.6	Not Detected
Chloroform	1.2	Not Detected	6.0	Not Detected
1,1,1-Trichloroethane	1.2	Not Detected	6.7	Not Detected
Cyclohexane	1.2	Not Detected	4.2	Not Detected
Carbon Tetrachloride	1.2	Not Detected	7.8	Not Detected
2,2,4-Trimethylpentane	1.2	Not Detected	5.8	Not Detected
Benzene	1.2	1.7	3.9	5.4
1,2-Dichloroethane	1.2	Not Detected	5.0	Not Detected
Heptane	1.2	Not Detected	5.1	Not Detected
Trichloroethene	1.2	Not Detected	6.6	Not Detected
1,2-Dichloropropane	1.2	Not Detected	5.7	Not Detected
1,4-Dioxane	4.9	Not Detected	18	Not Detected
Bromodichloromethane	1.2	Not Detected	8.3	Not Detected
cis-1,3-Dichloropropene	1.2	Not Detected	5.6	Not Detected
4-Methyl-2-pentanone	1.2	Not Detected	5.0	Not Detected
Toluene	1.2	Not Detected	4.6	Not Detected
trans-1,3-Dichloropropene	1.2	Not Detected	5.6	Not Detected
1,1,2-Trichloroethane	1.2	Not Detected	6.7	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-5

Lab ID#: 0608172A-07A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081423	Date of Collection:	8/4/06
Dil. Factor:	2.47	Date of Analysis:	8/15/06 02:43 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.2	Not Detected	8.4	Not Detected
2-Hexanone	4.9	Not Detected	20	Not Detected
Dibromochloromethane	1.2	Not Detected	10	Not Detected
1,2-Dibromoethane (EDB)	1.2	Not Detected	9.5	Not Detected
Chlorobenzene	1.2	Not Detected	5.7	Not Detected
Ethyl Benzene	1.2	Not Detected	5.4	Not Detected
m,p-Xylene	1.2	Not Detected	5.4	Not Detected
o-Xylene	1.2	Not Detected	5.4	Not Detected
Styrene	1.2	Not Detected	5.3	Not Detected
Bromoform	1.2	Not Detected	13	Not Detected
Cumene	1.2	Not Detected	6.1	Not Detected
1,1,2,2-Tetrachloroethane	1.2	Not Detected	8.5	Not Detected
Propylbenzene	1.2	Not Detected	6.1	Not Detected
4-Ethyltoluene	1.2	Not Detected	6.1	Not Detected
1,3,5-Trimethylbenzene	1.2	Not Detected	6.1	Not Detected
1,2,4-Trimethylbenzene	1.2	Not Detected	6.1	Not Detected
1,3-Dichlorobenzene	1.2	Not Detected	7.4	Not Detected
1,4-Dichlorobenzene	1.2	Not Detected	7.4	Not Detected
alpha-Chlorotoluene	1.2	Not Detected	6.4	Not Detected
1,2-Dichlorobenzene	1.2	Not Detected	7.4	Not Detected
1,2,4-Trichlorobenzene	4.9	Not Detected	37	Not Detected
Hexachlorobutadiene	4.9	Not Detected	53	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	96	70-130
4-Bromofluorobenzene	101	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-10

Lab ID#: 0608172A-08A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081424	Date of Collection:	8/4/06
Dil. Factor:	2.29	Date of Analysis:	8/15/06 03:33 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.1	Not Detected	5.7	Not Detected
Freon 114	1.1	Not Detected	8.0	Not Detected
Chloromethane	4.6	Not Detected	9.4	Not Detected
Vinyl Chloride	1.1	Not Detected	2.9	Not Detected
1,3-Butadiene	1.1	Not Detected	2.5	Not Detected
Bromomethane	1.1	Not Detected	4.4	Not Detected
Chloroethane	1.1	Not Detected	3.0	Not Detected
Freon 11	1.1	Not Detected	6.4	Not Detected
Ethanol	4.6	6.2	8.6	12
Freon 113	1.1	Not Detected	8.8	Not Detected
1,1-Dichloroethene	1.1	Not Detected	4.5	Not Detected
Acetone	4.6	55	11	130
2-Propanol	4.6	Not Detected	11	Not Detected
Carbon Disulfide	1.1	81	3.6	250
3-Chloropropene	4.6	Not Detected	14	Not Detected
Methylene Chloride	1.1	Not Detected	4.0	Not Detected
Methyl tert-butyl ether	1.1	Not Detected	4.1	Not Detected
trans-1,2-Dichloroethene	1.1	Not Detected	4.5	Not Detected
Hexane	1.1	Not Detected	4.0	Not Detected
1,1-Dichloroethane	1.1	Not Detected	4.6	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.1	3.2	3.4	9.4
cis-1,2-Dichloroethene	1.1	Not Detected	4.5	Not Detected
Tetrahydrofuran	1.1	Not Detected	3.4	Not Detected
Chloroform	1.1	Not Detected	5.6	Not Detected
1,1,1-Trichloroethane	1.1	Not Detected	6.2	Not Detected
Cyclohexane	1.1	Not Detected	3.9	Not Detected
Carbon Tetrachloride	1.1	Not Detected	7.2	Not Detected
2,2,4-Trimethylpentane	1.1	Not Detected	5.3	Not Detected
Benzene	1.1	1.9	3.6	6.1
1,2-Dichloroethane	1.1	Not Detected	4.6	Not Detected
Heptane	1.1	Not Detected	4.7	Not Detected
Trichloroethene	1.1	Not Detected	6.2	Not Detected
1,2-Dichloropropane	1.1	Not Detected	5.3	Not Detected
1,4-Dioxane	4.6	Not Detected	16	Not Detected
Bromodichloromethane	1.1	Not Detected	7.7	Not Detected
cis-1,3-Dichloropropene	1.1	Not Detected	5.2	Not Detected
4-Methyl-2-pentanone	1.1	Not Detected	4.7	Not Detected
Toluene	1.1	4.4	4.3	17
trans-1,3-Dichloropropene	1.1	Not Detected	5.2	Not Detected
1,1,2-Trichloroethane	1.1	Not Detected	6.2	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-10

Lab ID#: 0608172A-08A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081424	Date of Collection:	8/4/06
Dil. Factor:	2.29	Date of Analysis:	8/15/06 03:33 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.1	Not Detected	7.8	Not Detected
2-Hexanone	4.6	Not Detected	19	Not Detected
Dibromochloromethane	1.1	Not Detected	9.8	Not Detected
1,2-Dibromoethane (EDB)	1.1	Not Detected	8.8	Not Detected
Chlorobenzene	1.1	Not Detected	5.3	Not Detected
Ethyl Benzene	1.1	1.3	5.0	5.7
m,p-Xylene	1.1	3.7	5.0	16
o-Xylene	1.1	Not Detected	5.0	Not Detected
Styrene	1.1	Not Detected	4.9	Not Detected
Bromoform	1.1	Not Detected	12	Not Detected
Cumene	1.1	Not Detected	5.6	Not Detected
1,1,2,2-Tetrachloroethane	1.1	Not Detected	7.9	Not Detected
Propylbenzene	1.1	Not Detected	5.6	Not Detected
4-Ethyltoluene	1.1	Not Detected	5.6	Not Detected
1,3,5-Trimethylbenzene	1.1	Not Detected	5.6	Not Detected
1,2,4-Trimethylbenzene	1.1	Not Detected	5.6	Not Detected
1,3-Dichlorobenzene	1.1	Not Detected	6.9	Not Detected
1,4-Dichlorobenzene	1.1	Not Detected	6.9	Not Detected
alpha-Chlorotoluene	1.1	Not Detected	5.9	Not Detected
1,2-Dichlorobenzene	1.1	Not Detected	6.9	Not Detected
1,2,4-Trichlorobenzene	4.6	Not Detected	34	Not Detected
Hexachlorobutadiene	4.6	Not Detected	49	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	99	70-130
4-Bromofluorobenzene	100	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-10 Duplicate

Lab ID#: 0608172A-09A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081425	Date of Collection:	8/4/06
Dil. Factor:	2.13	Date of Analysis:	8/15/06 04:10 AM

Compound	Rot. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	1.1	Not Detected	5.3	Not Detected
Freon 114	1.1	Not Detected	7.4	Not Detected
Chloromethane	4.3	Not Detected	8.8	Not Detected
Vinyl Chloride	1.1	Not Detected	2.7	Not Detected
1,3-Butadiene	1.1	Not Detected	2.4	Not Detected
Bromomethane	1.1	Not Detected	4.1	Not Detected
Chloroethane	1.1	Not Detected	2.8	Not Detected
Freon 11	1.1	Not Detected	6.0	Not Detected
Ethanol	4.3	9.6	8.0	18
Freon 113	1.1	Not Detected	8.2	Not Detected
1,1-Dichloroethene	1.1	Not Detected	4.2	Not Detected
Acetone	4.3	55	10	130
2-Propanol	4.3	Not Detected	10	Not Detected
Carbon Disulfide	1.1	42	3.3	130
3-Chloropropene	4.3	Not Detected	13	Not Detected
Methylene Chloride	1.1	Not Detected	3.7	Not Detected
Methyl tert-butyl ether	1.1	Not Detected	3.8	Not Detected
trans-1,2-Dichloroethene	1.1	Not Detected	4.2	Not Detected
Hexane	1.1	Not Detected	3.8	Not Detected
1,1-Dichloroethane	1.1	Not Detected	4.3	Not Detected
2-Butanone (Methyl Ethyl Ketone)	1.1	3.2	3.1	9.4
cis-1,2-Dichloroethene	1.1	Not Detected	4.2	Not Detected
Tetrahydrofuran	1.1	Not Detected	3.1	Not Detected
Chloroform	1.1	Not Detected	5.2	Not Detected
1,1,1-Trichloroethane	1.1	Not Detected	5.8	Not Detected
Cyclohexane	1.1	Not Detected	3.7	Not Detected
Carbon Tetrachloride	1.1	Not Detected	6.7	Not Detected
2,2,4-Trimethylpentane	1.1	Not Detected	5.0	Not Detected
Benzene	1.1	1.3	3.4	4.2
1,2-Dichloroethane	1.1	Not Detected	4.3	Not Detected
Heptane	1.1	Not Detected	4.4	Not Detected
Trichloroethene	1.1	Not Detected	5.7	Not Detected
1,2-Dichloropropane	1.1	Not Detected	4.9	Not Detected
1,4-Dioxane	4.3	Not Detected	15	Not Detected
Bromodichloromethane	1.1	Not Detected	7.1	Not Detected
cis-1,3-Dichloropropene	1.1	Not Detected	4.8	Not Detected
4-Methyl-2-pentanone	1.1	Not Detected	4.4	Not Detected
Toluene	1.1	4.8	4.0	18
trans-1,3-Dichloropropene	1.1	Not Detected	4.8	Not Detected
1,1,2-Trichloroethane	1.1	Not Detected	5.8	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: GP-4-10 Duplicate

Lab ID#: 0608172A-09A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081425	Date of Collection:	8/4/06
Dil. Factor:	2.13	Date of Analysis:	8/15/06 04:10 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	1.1	Not Detected	7.2	Not Detected
2-Hexanone	4.3	Not Detected	17	Not Detected
Dibromochloromethane	1.1	Not Detected	9.1	Not Detected
1,2-Dibromoethane (EDB)	1.1	Not Detected	8.2	Not Detected
Chlorobenzene	1.1	Not Detected	4.9	Not Detected
Ethyl Benzene	1.1	Not Detected	4.6	Not Detected
m,p-Xylene	1.1	3.9	4.6	17
o-Xylene	1.1	Not Detected	4.6	Not Detected
Styrene	1.1	Not Detected	4.5	Not Detected
Bromoform	1.1	Not Detected	11	Not Detected
Cumene	1.1	Not Detected	5.2	Not Detected
1,1,2,2-Tetrachloroethane	1.1	Not Detected	7.3	Not Detected
Propylbenzene	1.1	Not Detected	5.2	Not Detected
4-Ethyltoluene	1.1	Not Detected	5.2	Not Detected
1,3,5-Trimethylbenzene	1.1	Not Detected	5.2	Not Detected
1,2,4-Trimethylbenzene	1.1	Not Detected	5.2	Not Detected
1,3-Dichlorobenzene	1.1	Not Detected	6.4	Not Detected
1,4-Dichlorobenzene	1.1	Not Detected	6.4	Not Detected
alpha-Chlorotoluene	1.1	Not Detected	5.5	Not Detected
1,2-Dichlorobenzene	1.1	Not Detected	6.4	Not Detected
1,2,4-Trichlorobenzene	4.3	Not Detected	32	Not Detected
Hexachlorobutadiene	4.3	Not Detected	45	Not Detected

Container Type: 1 Liter Summa Canister

Surrogates	%Recovery	Method Limits
Toluene-d8	99	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	100	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0608172A-10A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081405	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	8/14/06 12:02 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	0.50	Not Detected	2.5	Not Detected
Freon 114	0.50	Not Detected	3.5	Not Detected
Chloromethane	2.0	Not Detected	4.1	Not Detected
Vinyl Chloride	0.50	Not Detected	1.3	Not Detected
1,3-Butadiene	0.50	Not Detected	1.1	Not Detected
Bromomethane	0.50	Not Detected	1.9	Not Detected
Chloroethane	0.50	Not Detected	1.3	Not Detected
Freon 11	0.50	Not Detected	2.8	Not Detected
Ethanol	2.0	Not Detected	3.8	Not Detected
Freon 113	0.50	Not Detected	3.8	Not Detected
1,1-Dichloroethene	0.50	Not Detected	2.0	Not Detected
Acetone	2.0	Not Detected	4.8	Not Detected
2-Propanol	2.0	Not Detected	4.9	Not Detected
Carbon Disulfide	0.50	Not Detected	1.6	Not Detected
3-Chloropropene	2.0	Not Detected	6.3	Not Detected
Methylene Chloride	0.50	Not Detected	1.7	Not Detected
Methyl tert-butyl ether	0.50	Not Detected	1.8	Not Detected
trans-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
Hexane	0.50	Not Detected	1.8	Not Detected
1,1-Dichloroethane	0.50	Not Detected	2.0	Not Detected
2-Butanone (Methyl Ethyl Ketone)	0.50	Not Detected	1.5	Not Detected
cis-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
Tetrahydrofuran	0.50	Not Detected	1.5	Not Detected
Chloroform	0.50	Not Detected	2.4	Not Detected
1,1,1-Trichloroethane	0.50	Not Detected	2.7	Not Detected
Cyclohexane	0.50	Not Detected	1.7	Not Detected
Carbon Tetrachloride	0.50	Not Detected	3.1	Not Detected
2,2,4-Trimethylpentane	0.50	Not Detected	2.3	Not Detected
Benzene	0.50	Not Detected	1.6	Not Detected
1,2-Dichloroethane	0.50	Not Detected	2.0	Not Detected
Heptane	0.50	Not Detected	2.0	Not Detected
Trichloroethene	0.50	Not Detected	2.7	Not Detected
1,2-Dichloropropane	0.50	Not Detected	2.3	Not Detected
1,4-Dioxane	2.0	Not Detected	7.2	Not Detected
Bromodichloromethane	0.50	Not Detected	3.4	Not Detected
cis-1,3-Dichloropropene	0.50	Not Detected	2.3	Not Detected
4-Methyl-2-pentanone	0.50	Not Detected	2.0	Not Detected
Toluene	0.50	Not Detected	1.9	Not Detected
trans-1,3-Dichloropropene	0.50	Not Detected	2.3	Not Detected
1,1,2-Trichloroethane	0.50	Not Detected	2.7	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0608172A-10A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081405	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	8/14/06 12:02 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	0.50	Not Detected	3.4	Not Detected
2-Hexanone	2.0	Not Detected	8.2	Not Detected
Dibromochloromethane	0.50	Not Detected	4.2	Not Detected
1,2-Dibromoethane (EDB)	0.50	Not Detected	3.8	Not Detected
Chlorobenzene	0.50	Not Detected	2.3	Not Detected
Ethyl Benzene	0.50	Not Detected	2.2	Not Detected
m,p-Xylene	0.50	Not Detected	2.2	Not Detected
o-Xylene	0.50	Not Detected	2.2	Not Detected
Styrene	0.50	Not Detected	2.1	Not Detected
Bromoform	0.50	Not Detected	5.2	Not Detected
Cumene	0.50	Not Detected	2.4	Not Detected
1,1,2,2-Tetrachloroethane	0.50	Not Detected	3.4	Not Detected
Propylbenzene	0.50	Not Detected	2.4	Not Detected
4-Ethyltoluene	0.50	Not Detected	2.4	Not Detected
1,3,5-Trimethylbenzene	0.50	Not Detected	2.4	Not Detected
1,2,4-Trimethylbenzene	0.50	Not Detected	2.4	Not Detected
1,3-Dichlorobenzene	0.50	Not Detected	3.0	Not Detected
1,4-Dichlorobenzene	0.50	Not Detected	3.0	Not Detected
alpha-Chlorotoluene	0.50	Not Detected	2.6	Not Detected
1,2-Dichlorobenzene	0.50	Not Detected	3.0	Not Detected
1,2,4-Trichlorobenzene	2.0	Not Detected	15	Not Detected
Hexachlorobutadiene	2.0	Not Detected	21	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	98	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	100	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0608172A-10B

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081506	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	8/15/06 01:10 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Freon 12	0.50	Not Detected	2.5	Not Detected
Freon 114	0.50	Not Detected	3.5	Not Detected
Chloromethane	2.0	Not Detected	4.1	Not Detected
Vinyl Chloride	0.50	Not Detected	1.3	Not Detected
1,3-Butadiene	0.50	Not Detected	1.1	Not Detected
Bromomethane	0.50	Not Detected	1.9	Not Detected
Chloroethane	0.50	Not Detected	1.3	Not Detected
Freon 11	0.50	Not Detected	2.8	Not Detected
Ethanol	2.0	Not Detected	3.8	Not Detected
Freon 113	0.50	Not Detected	3.8	Not Detected
1,1-Dichloroethene	0.50	Not Detected	2.0	Not Detected
Acetone	2.0	Not Detected	4.8	Not Detected
2-Propanol	2.0	Not Detected	4.9	Not Detected
Carbon Disulfide	0.50	Not Detected	1.6	Not Detected
3-Chloropropene	2.0	Not Detected	6.3	Not Detected
Methylene Chloride	0.50	Not Detected	1.7	Not Detected
Methyl tert-butyl ether	0.50	Not Detected	1.8	Not Detected
trans-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
Hexane	0.50	Not Detected	1.8	Not Detected
1,1-Dichloroethane	0.50	Not Detected	2.0	Not Detected
2-Butanone (Methyl Ethyl Ketone)	0.50	Not Detected	1.5	Not Detected
cis-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
Tetrahydrofuran	0.50	Not Detected	1.5	Not Detected
Chloroform	0.50	Not Detected	2.4	Not Detected
1,1,1-Trichloroethane	0.50	Not Detected	2.7	Not Detected
Cyclohexane	0.50	Not Detected	1.7	Not Detected
Carbon Tetrachloride	0.50	Not Detected	3.1	Not Detected
2,2,4-Trimethylpentane	0.50	Not Detected	2.3	Not Detected
Benzene	0.50	Not Detected	1.6	Not Detected
1,2-Dichloroethane	0.50	Not Detected	2.0	Not Detected
Heptane	0.50	Not Detected	2.0	Not Detected
Trichloroethene	0.50	Not Detected	2.7	Not Detected
1,2-Dichloropropane	0.50	Not Detected	2.3	Not Detected
1,4-Dioxane	2.0	Not Detected	7.2	Not Detected
Bromodichloromethane	0.50	Not Detected	3.4	Not Detected
cis-1,3-Dichloropropene	0.50	Not Detected	2.3	Not Detected
4-Methyl-2-pentanone	0.50	Not Detected	2.0	Not Detected
Toluene	0.50	Not Detected	1.9	Not Detected
trans-1,3-Dichloropropene	0.50	Not Detected	2.3	Not Detected
1,1,2-Trichloroethane	0.50	Not Detected	2.7	Not Detected



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0608172A-10B

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081506	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	8/15/06 01:10 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Tetrachloroethene	0.50	Not Detected	3.4	Not Detected
2-Hexanone	2.0	Not Detected	8.2	Not Detected
Dibromochloromethane	0.50	Not Detected	4.2	Not Detected
1,2-Dibromoethane (EDB)	0.50	Not Detected	3.8	Not Detected
Chlorobenzene	0.50	Not Detected	2.3	Not Detected
Ethyl Benzene	0.50	Not Detected	2.2	Not Detected
m,p-Xylene	0.50	Not Detected	2.2	Not Detected
o-Xylene	0.50	Not Detected	2.2	Not Detected
Styrene	0.50	Not Detected	2.1	Not Detected
Bromoform	0.50	Not Detected	5.2	Not Detected
Cumene	0.50	Not Detected	2.4	Not Detected
1,1,2,2-Tetrachloroethane	0.50	Not Detected	3.4	Not Detected
Propylbenzene	0.50	Not Detected	2.4	Not Detected
4-Ethyltoluene	0.50	Not Detected	2.4	Not Detected
1,3,5-Trimethylbenzene	0.50	Not Detected	2.4	Not Detected
1,2,4-Trimethylbenzene	0.50	Not Detected	2.4	Not Detected
1,3-Dichlorobenzene	0.50	Not Detected	3.0	Not Detected
1,4-Dichlorobenzene	0.50	Not Detected	3.0	Not Detected
alpha-Chlorotoluene	0.50	Not Detected	2.6	Not Detected
1,2-Dichlorobenzene	0.50	Not Detected	3.0	Not Detected
1,2,4-Trichlorobenzene	2.0	Not Detected	15	Not Detected
Hexachlorobutadiene	2.0	Not Detected	21	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	95	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	99	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0608172A-11A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081402	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/14/06 09:30 AM

Compound	%Recovery
Freon 12	107
Freon 114	106
Chloromethane	90
Vinyl Chloride	90
1,3-Butadiene	77
Bromomethane	97
Chloroethane	88
Freon 11	103
Ethanol	81
Freon 113	105
1,1-Dichloroethene	92
Acetone	81
2-Propanol	87
Carbon Disulfide	86
3-Chloropropene	95
Methylene Chloride	85
Methyl tert-butyl ether	124
trans-1,2-Dichloroethene	91
Hexane	88
1,1-Dichloroethane	99
2-Butanone (Methyl Ethyl Ketone)	101
cis-1,2-Dichloroethene	101
Tetrahydrofuran	87
Chloroform	109
1,1,1-Trichloroethane	121
Cyclohexane	101
Carbon Tetrachloride	121
2,2,4-Trimethylpentane	92
Benzene	105
1,2-Dichloroethane	107
Heptane	102
Trichloroethene	103
1,2-Dichloropropane	97
1,4-Dioxane	91
Bromodichloromethane	98
cis-1,3-Dichloropropene	103
4-Methyl-2-pentanone	92
Toluene	102
trans-1,3-Dichloropropene	114
1,1,2-Trichloroethane	110



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0608172A-11A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081402	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	8/14/06 09:30 AM

Compound	%Recovery
Tetrachloroethene	116
2-Hexanone	92
Dibromochloromethane	109
1,2-Dibromoethane (EDB)	114
Chlorobenzene	110
Ethyl Benzene	109
m,p-Xylene	109
o-Xylene	109
Styrene	116
Bromoform	114
Cumene	92
1,1,2,2-Tetrachloroethane	102
Propylbenzene	99
4-Ethyltoluene	101
1,3,5-Trimethylbenzene	101
1,2,4-Trimethylbenzene	106
1,3-Dichlorobenzene	112
1,4-Dichlorobenzene	113
alpha-Chlorotoluene	103
1,2-Dichlorobenzene	108
1,2,4-Trichlorobenzene	84
Hexachlorobutadiene	84

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	90	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	106	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0608172A-11B

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081502	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/15/06 09:55 AM

Compound	%Recovery
Freon 12	116
Freon 114	114
Chloromethane	101
Vinyl Chloride	94
1,3-Butadiene	82
Bromomethane	102
Chloroethane	86
Freon 11	103
Ethanol	79
Freon 113	102
1,1-Dichloroethene	89
Acetone	76
2-Propanol	85
Carbon Disulfide	82
3-Chloropropene	90
Methylene Chloride	82
Methyl tert-butyl ether	108
trans-1,2-Dichloroethene	85
Hexane	84
1,1-Dichloroethane	95
2-Butanone (Methyl Ethyl Ketone)	97
cis-1,2-Dichloroethene	98
Tetrahydrofuran	84
Chloroform	109
1,1,1-Trichloroethane	122
Cyclohexane	98
Carbon Tetrachloride	123
2,2,4-Trimethylpentane	89
Benzene	101
1,2-Dichloroethane	106
Heptane	97
Trichloroethene	109
1,2-Dichloropropane	102
1,4-Dioxane	97
Bromodichloromethane	107
cis-1,3-Dichloropropene	110
4-Methyl-2-pentanone	95
Toluene	108
trans-1,3-Dichloropropene	113
1,1,2-Trichloroethane	109



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0608172A-11B

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081502	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/15/06 09:55 AM

Compound	%Recovery
Tetrachloroethene	116
2-Hexanone	90
Dibromochloromethane	110
1,2-Dibromoethane (EDB)	115
Chlorobenzene	110
Ethyl Benzene	109
m,p-Xylene	110
o-Xylene	108
Styrene	115
Bromoform	115
Cumene	92
1,1,2,2-Tetrachloroethane	102
Propylbenzene	100
4-Ethyltoluene	102
1,3,5-Trimethylbenzene	96
1,2,4-Trimethylbenzene	105
1,3-Dichlorobenzene	111
1,4-Dichlorobenzene	111
alpha-Chlorotoluene	101
1,2-Dichlorobenzene	106
1,2,4-Trichlorobenzene	79
Hexachlorobutadiene	81

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	97	70-130
4-Bromofluorobenzene	105	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0608172A-12A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081403	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/14/06 10:30 AM

Compound	%Recovery
Freon 12	102
Freon 114	100
Chloromethane	86
Vinyl Chloride	83
1,3-Butadiene	86
Bromomethane	95
Chloroethane	84
Freon 11	96
Ethanol	88
Freon 113	98
1,1-Dichloroethene	83
Acetone	89
2-Propanol	92
Carbon Disulfide	102
3-Chloropropene	92
Methylene Chloride	77
Methyl tert-butyl ether	119
trans-1,2-Dichloroethene	99
Hexane	98
1,1-Dichloroethane	91
2-Butanone (Methyl Ethyl Ketone)	109
cis-1,2-Dichloroethene	93
Tetrahydrofuran	90
Chloroform	100
1,1,1-Trichloroethane	110
Cyclohexane	111
Carbon Tetrachloride	111
2,2,4-Trimethylpentane	95
Benzene	94
1,2-Dichloroethane	97
Heptane	110
Trichloroethene	101
1,2-Dichloropropane	96
1,4-Dioxane	108
Bromodichloromethane	109
cis-1,3-Dichloropropene	77
4-Methyl-2-pentanone	105
Toluene	101
trans-1,3-Dichloropropene	105
1,1,2-Trichloroethane	100



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0608172A-12A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081403	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/14/06 10:30 AM

Compound	%Recovery
Tetrachloroethene	105
2-Hexanone	99
Dibromochloromethane	119
1,2-Dibromoethane (EDB)	103
Chlorobenzene	101
Ethyl Benzene	104
m,p-Xylene	96
o-Xylene	88
Styrene	106
Bromoform	125
Cumene	89
1,1,2,2-Tetrachloroethane	95
Propylbenzene	97
4-Ethyltoluene	97
1,3,5-Trimethylbenzene	79
1,2,4-Trimethylbenzene	64 Q
1,3-Dichlorobenzene	98
1,4-Dichlorobenzene	99
alpha-Chlorotoluene	85
1,2-Dichlorobenzene	94
1,2,4-Trichlorobenzene	83
Hexachlorobutadiene	77

Q = Exceeds Quality Control limits.

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	98	70-130
1,2-Dichloroethane-d4	97	70-130
4-Bromofluorobenzene	100	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0608172A-12B

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081504	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/15/06 11:35 AM

Compound	%Recovery
Freon 12	96
Freon 114	93
Chloromethane	84
Vinyl Chloride	78
1,3-Butadiene	79
Bromomethane	95
Chloroethane	81
Freon 11	94
Ethanol	84
Freon 113	95
1,1-Dichloroethene	81
Acetone	84
2-Propanol	91
Carbon Disulfide	97
3-Chloropropene	87
Methylene Chloride	76
Methyl tert-butyl ether	108
trans-1,2-Dichloroethene	94
Hexane	95
1,1-Dichloroethane	88
2-Butanone (Methyl Ethyl Ketone)	105
cis-1,2-Dichloroethene	91
Tetrahydrofuran	89
Chloroform	100
1,1,1-Trichloroethane	111
Cyclohexane	109
Carbon Tetrachloride	112
2,2,4-Trimethylpentane	93
Benzene	92
1,2-Dichloroethane	96
Heptane	107
Trichloroethene	99
1,2-Dichloropropane	93
1,4-Dioxane	107
Bromodichloromethane	109
cis-1,3-Dichloropropene	76
4-Methyl-2-pentanone	103
Toluene	98
trans-1,3-Dichloropropene	104
1,1,2-Trichloroethane	100



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0608172A-12B

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1081504	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 8/15/06 11:35 AM

Compound	%Recovery
Tetrachloroethene	108
2-Hexanone	98
Dibromochloromethane	119
1,2-Dibromoethane (EDB)	102
Chlorobenzene	101
Ethyl Benzene	104
m,p-Xylene	95
o-Xylene	87
Styrene	106
Bromoform	126
Cumene	89
1,1,2,2-Tetrachloroethane	94
Propylbenzene	96
4-Ethyltoluene	97
1,3,5-Trimethylbenzene	71
1,2,4-Trimethylbenzene	62 Q
1,3-Dichlorobenzene	93
1,4-Dichlorobenzene	92
alpha-Chlorotoluene	79
1,2-Dichlorobenzene	88
1,2,4-Trichlorobenzene	74
Hexachlorobutadiene	72

Q = Exceeds Quality Control limits.

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	96	70-130
1,2-Dichloroethane-d4	98	70-130
4-Bromofluorobenzene	102	70-130