

RECEIVED

OCTOBER 17,2005

**ALAMEDA COUNTY
ENVIRONMENTAL HEALTH**

**THIRD QUARTER 2005
SITE MONITORING REPORT**

**REDWOOD REGIONAL PARK
SERVICE YARD
OAKLAND, CALIFORNIA**

Prepared for:

**EAST BAY REGIONAL PARK DISTRICT
OAKLAND, CALIFORNIA**

October 2005

October 13, 2005

Mr. Jerry Wickham, P.G.
Hazardous Materials Specialist / Local Oversight Program
Alameda County Department of Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502

RECEIVED

OCTOBER 17, 2005

**ALAMEDA COUNTY
ENVIRONMENTAL HEALTH**

Subject: Third Quarter 2005 Site Monitoring Report
Redwood Regional Park Service Yard Site – Oakland, California
Alameda County Health Fuel Leak Case No. RO0000246

Dear Mr. Wickham:

Attached is the referenced Stellar Environmental Solutions, Inc. report for the underground fuel storage tank (UFST) site at the Redwood Regional Park Service Yard, located at 7867 Redwood Road, Oakland, California. This project is being conducted for the East Bay Regional Park District (EBRPD), and follows previous site investigation and remediation activities (conducted since 1993) associated with former leaking UFSTs. The key regulatory agencies for this investigation are the Alameda County Department of Environmental Health, the Regional Water Quality Control Board, and the California Department of Fish and Game.

This report summarizes groundwater and surface monitoring and sampling activities conducted between July 1 and September 30, 2005 (Third Quarter 2005). The EBRPD has previously proposed to the regulatory agencies to implement bioventing as a site corrective action, and is currently conducting planning and procurement activities. When implemented, bioventing activities will be reported in technical submittals separate from the ongoing groundwater and surface water monitoring quarterly reports; salient summary discussions will be included in the quarterly groundwater monitoring reports.

If you have any questions regarding this report, please contact Mr. Neal Fujita of the EBRPD, or contact us directly at (510) 644-3123.

Sincerely,



Bruce M. Rucker, R.G., R.E.A.
Project Manager



Richard S. Makdisi, R.G., R.E.A.
Principal

cc: Carl Wilcox, California Department of Fish and Game
John Wolfenden, Regional Water Quality Control Board
Neal Fujita, East Bay Regional Park District
Water Board "GeoTracker" and Alameda County Health "ftp" System

**THIRD QUARTER 2005
SITE MONITORING REPORT**

**REDWOOD REGIONAL PARK
SERVICE YARD
OAKLAND, CALIFORNIA**

Prepared for:

**EAST BAY REGIONAL PARK DISTRICT
P.O. Box 5381
OAKLAND, CALIFORNIA 94605**

Prepared by:

**STELLAR ENVIRONMENTAL SOLUTIONS, INC.
2198 SIXTH STREET
BERKELEY, CALIFORNIA 94710**

October 13, 2005

Project No. 2005-02

TABLE OF CONTENTS

Section	Page
1.0 INTRODUCTION.....	1
Project Background.....	1
Objectives and Scope of Work.....	1
Historical Corrective Actions and Investigations	1
Related Site Activities.....	2
Site Description.....	2
Regulatory Oversight.....	3
2.0 PHYSICAL SETTING.....	6
Site Lithology.....	6
Hydrogeology.....	10
3.0 Q3-2005 GROUNDWATER AND SURFACE WATER MONITORING EVENT ACTIVITIES.....	13
Groundwater Level Monitoring and Sampling	14
Creek Surface Water Sampling.....	15
4.0 REGULATORY CONSIDERATIONS.....	16
Groundwater Contamination.....	16
Surface Water Contamination.....	16
5.0 MONITORING EVENT ANALYTICAL RESULTS.....	18
Current Event Groundwater and Surface Water Results	18
Quality Control Sample Analytical Results.....	18
6.0 SUMMARY, CONCLUSIONS AND PROPOSED ACTIONS.....	22
Summary and Conclusions.....	22
Proposed Actions	23

TABLE OF CONTENTS (continued)

Section	Page
7.0 REFERENCES AND BIBLIOGRAPHY	25
8.0 LIMITATIONS	29

Appendices

Appendix A	Historical Groundwater Monitoring Well Water Level Data
Appendix B	Groundwater Monitoring Field Documentation
Appendix C	Analytical Laboratory Report and Chain-of-Custody Record
Appendix D	Historical Groundwater and Surface Water Analytical Results

TABLES AND FIGURES

Tables	Page
Table 1 Groundwater Monitoring Well Construction and Groundwater Elevation Data – September 13, 2005 Monitoring Event Redwood Regional Park Corporation Yard, Oakland, California	14
Table 2 Groundwater and Surface Water Sample Analytical Results – September 13, 2005 Redwood Regional Park Corporation Yard, Oakland, California	20

Figures	Page
Figure 1 Site Location Map	3
Figure 2 Site Plan and Historical Sampling Locations	4
Figure 3 Geologic Cross-Section Locations	7
Figure 4 Geologic Cross-Sections A-A' through C-C'	8
Figure 5 Geologic Cross-Sections D-D' through F-F'	9
Figure 6 Groundwater Elevation Map – September 13, 2005	11
Figure 7 Groundwater Analytical Results and Gasoline Plume – September 2005	21

1.0 INTRODUCTION

PROJECT BACKGROUND

The subject property is the East Bay Regional Park District (EBRPD) Redwood Regional Park Service Yard located at 7867 Redwood Road in Oakland, Alameda County, California. The site has undergone site investigations and remediation since 1993 to address subsurface contamination caused by leakage from one or both of two former underground fuel storage tanks (UFSTs) that contained gasoline and diesel fuel. The Alameda County Department of Environmental Health (Alameda County Health) has provided regulatory oversight of the investigation since its inception (Alameda County Health Fuel Leak Case No. RO0000246). Other regulatory agencies with historical involvement in site review include the Regional Water Quality Control Board (Water Board) and the California Department of Fish and Game (CDFG).

OBJECTIVES AND SCOPE OF WORK

This report discusses the following activities conducted/coordinated by Stellar Environmental Solutions, Inc. (SES) between July 1 and September 30, 2005:

- Collecting water levels in site wells to determine shallow groundwater flow direction;
- Sampling site wells for contaminant analysis and natural attenuation indicators; and
- Collecting surface water samples for contaminant analysis.

HISTORICAL CORRECTIVE ACTIONS AND INVESTIGATIONS

Previous SES reports have provided a full discussion of previous site remediation and investigations; site geology and hydrogeology; residual site contamination; conceptual model for contaminant fate and transport; and evaluation of hydrochemical trends and plume stability. Section 7.0 (References and Bibliography) of this report provides a listing of all technical reports for the site. The following is a summary of the general phases of site work:

- An October 2000 Feasibility Study report for the site, submitted to Alameda County Health, provided detailed analyses of the regulatory implications of the site contamination and an assessment of viable corrective actions (SES, 2000d).

- Two instream bioassessment events were conducted in April 1999 and January 2000 to evaluate potential impacts to stream biota associated with the site contamination (no impacts were documented).
- Additional monitoring well installations and corrective action by ORC™ injection proposed by SES were approved by Alameda County Health in its January 8, 2001 letter to the EBRPD. Two phases of ORC™ injection were conducted—in September 2001 and July 2002.
- A total of 35 groundwater monitoring events have been conducted on a quarterly basis since project inception (November 1994), and a total of 11 groundwater monitoring wells are currently available for monitoring. Seven site wells are included in the current groundwater monitoring program (the remaining four wells are outside the contaminant plume and are currently utilized only for water level monitoring).
- A bioventing pilot test was conducted in September and October 2004 to evaluate the feasibility of this corrective action strategy, and a full-scale bioventing system design was submitted to Alameda County Health. Bioventing activities conducted to date have been discussed in bioventing-specific technical reports. The EBRPD is currently preparing a Request for Bid package for installation and operation of the system.

RELATED SITE ACTIVITIES

The EBRPD has proposed to implement bioventing as a corrective action to mitigate residual site contamination, the primary source of ongoing groundwater contamination. In May 2004, Alameda County Health approved a bioventing pilot test to evaluate the feasibility of this strategy. In June 2004, four bioventing pilot test wells (one vent well and three vapor monitoring points) were installed; soil sampling during well installations was conducted; and water levels were measured (SES, 2004f). The pilot tests results report recommended, and EBRPD has proposed, to implement full-scale bioventing as a site corrective action; the pilot tests results report included a design for the full-scale system. In May 2005, Alameda County Health requested modifications to the full-scale design (Alameda County Health, 2005). Alameda County Health subsequently approved the original design (not including the requested modifications). The EBRPD is currently preparing a Request for Bid package for installation of the system. Bioventing activities have been/will be discussed in detail in separate technical reports. No bioventing field activities were conducted in the current quarter.


SITE DESCRIPTION

Figure 1 shows the location of the project site. The site slopes to the west, from an elevation of approximately 564 feet above mean sea level (amsl) at the eastern edge of the service yard to approximately 545 feet amsl at Redwood Creek, which defines the approximate western edge of the project site with regard to this investigation. Figure 2 shows the site plan.




3-D TopoQuads Copyright © 1999 DeLorme Yarmouth, ME 04096 Source Data: USGS 750 ft Scale: 1 : 25,000 Detail: 13-0 Datum: WGS84



SITE LOCATION ON U.S.G.S. TOPOGRAPHIC MAP		
Redwood Reg. Park Service Yard Oakland, CA	By: MJC	APRIL 2004
Figure 1		 Stellar Environmental Solutions, Inc. Geoscience & Engineering Consulting

2004-02-01



LEGEND

- BH-20 Exploratory borehole
- MW-1 Groundwater monitoring well
- VW-1 Vent Well
- ▲ VMP-1 Vapor Monitoring point
- 🌳 Tree

UFST = Underground fuel storage tank

0 25
Scale in feet

REGULATORY OVERSIGHT

The lead regulatory agency for the site investigation and remediation is Alameda County Health, with oversight provided by the Water Board. The CDFG is also involved with regard to water quality impacts to Redwood Creek. All workplans and reports are submitted to these agencies.

Historical Alameda County Health-approved revisions to the groundwater sampling program have included: 1) discontinuing hydrochemical sampling and analysis in wells MW-1, MW-3, MW-5, and MW-6; 2) discontinuing creek surface water sampling at upstream location SW-1; and 3) reducing the frequency of creek surface water sampling from quarterly to semi-annually (Alameda County Health, 1996). EBRPD has pro-actively elected not to implement the latter-approved revision due to continued concern over potential impacts to Redwood Creek.

In May 2005, Alameda County Health requested that groundwater monitoring well MW-4 be replaced due to progressive reduced groundwater entry into the well (Alameda County Health, 2005). The EBRPD is currently soliciting subcontractor bids to have that work conducted.

Since 2001, Electronic Data Format (EDF) groundwater analytical results, well construction and water level data, and site maps have been successfully uploaded to the State Water Resources Control Board's GeoTracker database, in accordance with that agency's requirements for EDF submittals. This report was also uploaded to the Alameda County Health's Electronic Upload "ftp" system.

2.0 PHYSICAL SETTING


This section discusses the site hydrogeologic conditions based on geologic logging and water level measurements collected at the site since September 1993. Previous SES reports have included detailed discussions of site lithologic and hydrogeologic conditions. In May 2004, Alameda County Health requested, via email, additional evaluation of site lithology—specifically, the preparation of multiple geologic cross-sections parallel to and perpendicular to the contaminant plume's long axis.

SITE LITHOLOGY

Figure 3 shows the location of geologic cross-sections. Figure 4 shows three sub-parallel geologic cross-sections (A-A' through C-C') along the long axis of the groundwater contaminant plume (i.e., along local groundwater flow direction). Figure 5 shows three sub-parallel geologic cross-sections (D-D' through F-F') roughly perpendicular to groundwater direction. In each figure, the three sub-parallel sections are presented together for ease of comparison. Due to the small scale, these sections show only lithologic conditions (i.e., soil type and bedrock depth). Additional information on water level depths, historical range of water levels, and inferred thickness of soil contamination) were presented in a previous report (SES, 2004c) for cross-section B-B'.

Shallow soil stratigraphy consists of a surficial 3- to 10-foot-thick clayey silt unit underlain by a 5- to 15-foot-thick silty clay unit. In the majority of boreholes, a 5- to 10-foot-thick clayey coarse-grained sand and clayey gravel unit that laterally grades to a clay or silty clay was encountered. This unit overlies a weathered siltstone at the base of the observed soil profile. Soils in the vicinity of MW-1 are inferred to be landslide debris.

A previous SES report (SES, 2004c) presented a bedrock surface isopleth map (elevation contours for the top of the bedrock surface) in the contaminant plume area. That isopleth map and Figures 4 and 5 indicate the following: The bedrock surface slopes steeply, approximately 0.3 feet/foot from east to west (toward Redwood Creek) in the upgradient portion of the site (from the service yard to under the entrance road), then shows a gentle east-to-west slope in the downgradient portion of the site (under the gravel parking area) toward Redwood Creek. This general gradient corresponds to the local groundwater flow direction. On the southern side of the plume area, bedrock slopes gently from south to north (the opposite of the general topographic gradient). Bedrock topography on the northern side of the plume cannot be determined from the available data.



LEGEND

- Vw-1 Vapor Monitoring Point or Vent Well
- BH-20 Exploratory borehole BH-20
- MW-1 Groundwater monitoring well MW-1
- SW-2 Area of discolored soil and creek soil and surface water sample location SW-2
- A-A'** Geologic cross section
- Tree

NOTES

Locations and dimensions of roads, trails, creek, and parking lot are approximate

UFST = Underground fuel storage tank


0 20
Scale in feet

2004-02-14

★ Stellar Environmental Solutions, Inc.
Geoscience & Engineering Consulting

GEOLOGIC CROSS-SECTION LOCATIONS
Redwood Regional Park Service Yard, Oakland, CA

Figure 3	
by: MJC	JULY 2004





In the central and downgradient portions of the groundwater contaminant plume (under the entrance road and the parking area), the bedrock surface has local, fairly steep elevation highs and lows, expressing a hummocky surface. Bedrock elevations vary by up to 10 feet over distances of less than 20 feet in this area. Local bedrock elevation highs are observed at upgradient location BH-13 (see Cross Section F-F') and at downgradient location B15/HP-02 (see Cross-Section B-B'). Intervening elevation lows create troughs that trend north-south in the central portion of the plume and east-west in the downgradient portion of the plume.


The bedrock surface (and overlying unconsolidated sediment lithology) suggest that the bedrock surface may have at one time undergone channel erosion from a paleostream(s) flowing sub-parallel to present-day Redwood Creek. Because groundwater flows in the unconsolidated sediments that directly overlie the bedrock surface, it is likely that the hummocky bedrock surface affects local groundwater depth and flow direction. This is an important hydrogeologic control that should be considered if groundwater-specific corrective action is contemplated.

HYDROGEOLOGY

Groundwater at the site occurs under unconfined and semi-confined conditions, generally within the clayey, silty, sand-gravel zone. The top of this zone varies between approximately 12 and 19 feet below ground surface (bgs), and the bottom of the water-bearing zone (approximately 25 to 28 feet bgs) corresponds to the top of the siltstone bedrock unit. Seasonal fluctuations in groundwater depth create a capillary fringe of several feet that is saturated in the rainy period (late fall through early spring) and unsaturated during the remainder of the year. The thickness of the saturated zone plus the capillary fringe varies between approximately 10 and 15 feet in the area of contamination. Local perched water zones have been observed well above the top of the capillary fringe.

Figure 6 is a groundwater elevation map constructed from the current event monitoring well static water levels. Table 1 (in Section 3.0) summarizes current event groundwater elevation data. Appendix A contains historical groundwater elevation data. Consistent with the bedrock isopleth map showing an elevation depression in the vicinity of MW-11, historical groundwater elevations in MW-11 are generally lower than in the surrounding area. As discussed in the previous subsection, local groundwater flow direction is likely more variable than expressed by groundwater monitoring well data, due to localized bedrock surface topography.

In the upgradient portion of the site (between well MW-1 and the former UFST source area, in landslide debris), the groundwater gradient is approximately 0.2 feet per foot. Downgradient from (west of) the UFST source area (between MW-2 and Redwood Creek), the groundwater gradient is



approximately 0.1 feet per foot. The direction of shallow groundwater flow during the current event was to the west-southwest (toward Redwood Creek), which is consistent with historical site groundwater flow direction.

We assume a site groundwater velocity of 7 to 10 feet per year using general look-up tables for permeability characteristics for the site-specific lithologic data obtained from site investigations. This velocity estimate is conservatively low, but does meet minimum-distance-traveled criteria from the date when contamination was first observed in Redwood Creek (1993) relative to the time of the UST installations (late 1970s). Locally, however, the groundwater velocity could vary significantly. Calculating the specific hydraulic conductivity critical to accurately estimating site-specific groundwater velocity would require direct testing of the water-bearing zone through a slug or pumping test.

Redwood Creek, which borders the site to the west, is a seasonal creek known for the occurrence of rainbow trout. Creek flow in the vicinity of the site shows significant seasonal variation, with little to no flow during the summer and fall dry season, and vigorous flow with depths exceeding 1 foot during the winter and spring wet season. The creek is a gaining stream (i.e., it is recharged by groundwater seeps and springs) in the vicinity of the site, and discharges into Upper San Leandro Reservoir located approximately 1 mile southeast of the site. During low-flow conditions, the groundwater table is below the creek bed in most locations (including the area of historical contaminated groundwater discharge); consequently, there is little to no observable creek flow at these times.

3.0 Q3-2005 GROUNDWATER AND SURFACE WATER MONITORING EVENT ACTIVITIES

This section presents the creek surface water and groundwater sampling and analytical methods for the most recent groundwater monitoring event (Q3 2005), conducted in September 2005. Groundwater and surface water analytical results are summarized in Section 5.0. Monitoring and sampling protocols were in accordance with the Alameda County Health-approved SES technical workplan (SES, 1998a). Current event activities included:

- Measuring static water levels and field analyzing pre-purge groundwater samples for indicators of natural attenuation (dissolved oxygen [DO], ferrous iron, and oxidation-reduction potential [ORP]) in all 11 site wells.
- Collecting post-purge groundwater samples for laboratory analysis of site contaminants from wells located within (or potentially within) the groundwater plume (MW-2, MW-4, MW-7, MW-8, MW-9, MW-10, and MW-11).
- Collecting Redwood Creek surface water samples for laboratory analysis from locations SW-2 and SW-3.

Creek sampling and groundwater monitoring/sampling was conducted on September 13, 2005. Creek sampling was conducted by the SES project manager. The locations of all site monitoring wells and creek water sampling locations are shown on Figure 2 (in Section 1.0). Well construction information and water level data are summarized in Table 1. Appendix B contains the groundwater monitoring field records for the current event.

Because it appears that the previously-injected ORC™ has been depleted, continued monitoring of the natural attenuation parameters—DO, ORP, nitrate, ferrous iron, and sulfate—is of marginal value until such time as additional corrective actions that would increase oxygen concentrations (e.g., bioventing) are implemented. Therefore, monitoring for natural attenuation parameters was discontinued following the Q3 2004 event.

Table 1
Groundwater Monitoring Well Construction and Groundwater Elevation Data –
September 13, 2005 Monitoring Event
Redwood Regional Park Corporation Yard, Oakland, California

Well	Well Depth	Screened Interval	TOC Elevation	Groundwater Depth ^(a)	Groundwater Elevation ^(b)
MW-1	18	7 to 17	565.9	3.62	562.3
MW-2	36	20 to 35	566.5	23.05	543.5
MW-3	42	7 to 41	560.9	21.24	539.7
MW-4	26	10 to 25	548.1	13.75	534.4
MW-5	26	10 to 25	547.5	16.60	530.9
MW-6	26	10 to 25	545.6	13.37	532.2
MW-7	24	9 to 24	547.7	13.38	534.3
MW-8	23	8 to 23	549.2	12.49	536.7
MW-9	27	12 to 27	549.4	13.30	536.1
MW-10	28	13 to 28	547.3	12.65	534.7
MW-11	26	11 to 26	547.9	15.48	532.4

Notes:

^(a) Depths are in feet relative to top of well casing.

^(b) All elevations are relative to top of well casing, and are expressed as feet above U.S. Geological Survey (USGS) mean sea level. Elevations of wells MW-1 through MW-6 were surveyed by EBRPD relative to USGS Benchmark No. JHF-49. Wells MW-7 through MW-11 were surveyed by a licensed land surveyor using existing site wells as datum.

TOC = Top of casing.

Wells MW-1 through MW-6 are 4-inch-diameter; all other wells are 2-inch-diameter.

GROUNDWATER LEVEL MONITORING AND SAMPLING

Groundwater monitoring well water level measurements, purging, sampling, and field analyses were conducted by Blaine Tech Services under the supervision of SES personnel. Groundwater sampling was conducted in accordance with State of California guidelines for sampling dissolved analytes in groundwater associated with leaking UFSTs (State Water Resources Control Board, 1989), and followed the methods and protocols approved by Alameda County Health in the SES 1998 workplan (SES, 1998a).

As the first task of the monitoring event, static water levels were measured using an electric water level indicator. Pre-purge groundwater samples were then collected for field and laboratory analysis of natural attenuation indicators. The wells to be sampled for contaminant analyses were then purged (by bailing and/or pumping) of three wetted casing volumes. Aquifer stability parameters (temperature, pH, and electrical conductivity) were measured after each purged casing volume to ensure that representative formation water would be sampled. To minimize the

potential for cross-contamination, wells were purged and sampled in order of increasing contamination (based on the analytical results of the previous quarter).

The sampling-derived purge water and decontamination rinseate (approximately 60 gallons) from the current event was containerized in the onsite plastic tank. Purge water from future events will continue to be accumulated in the onsite tank until it is full, at which time the water will be transported offsite for proper disposal.

CREEK SURFACE WATER SAMPLING

Surface water sampling was conducted by SES on September 13, 2005. Surface water samples were collected from Redwood Creek location SW-2 (immediately downgradient of the former UFST source area and within the area of documented creek bank soil contamination), and SW-3 (approximately 500 feet downstream of the SW-2 location). In accordance with a previous SES recommendation approved by the Alameda County Health, upstream sample location SW-1 is no longer part of the surface water sampling program.

At the time of sampling, the creek was stagnant between the two sampling locations; water depth was between 2 and 6 inches. At the SW-2 location, where contaminated groundwater discharge to the creek has historically been observed, an orange algae was observed growing on the saturated portion of the creek bank. This algae likely is utilizing the petroleum as a carbon source, and therefore is a good indicator of the presence of petroleum contamination. However, neither petroleum sheen nor odor were evident on the water surface.

4.0 REGULATORY CONSIDERATIONS

The following is a summary of regulatory considerations regarding surface water and groundwater contamination. There are no Alameda County Health or Water Board cleanup orders for the site, although all site work has been conducted under oversight of these agencies.

GROUNDWATER CONTAMINATION

As specified in the Water Board's San Francisco Bay Region Water Quality Control Plan (Regional Water Quality Control Board, 1986), all groundwater are considered potential sources of drinking water unless otherwise approved by the Water Board, and are also assumed to ultimately discharge to a surface water body and potentially impact aquatic organisms. While it is likely that site groundwater would satisfy geology-related criteria for exclusion as a drinking water source (excessive total dissolved solids and/or insufficient sustained yield), Water Board approval for this exclusion has not been obtained for the site. As summarized in Table 2 (in Section 5.0), site groundwater contaminant levels are compared to two sets of criteria: 1) Water Board Tier 1 Environmental Screening Levels (ESLs) for sites where groundwater is a current or potential drinking water source; and 2) ESLs for sites where groundwater is not a current or potential drinking water source.

As stipulated in the ESL document (Water Board, 2004), the ESLs are not cleanup criteria; rather, they are conservative screening-level criteria designed to be protective of both drinking water resources and aquatic environments in general. The groundwater ESLs are composed of multiple components, including ceiling value, human toxicity, indoor air impacts, and aquatic life protection. Exceedance of ESLs suggests that additional investigation and/or remediation is warranted. While drinking water standards [e.g., Maximum Contaminant Levels (MCLs)] are published for the site contaminants of concern, Alameda County Health has indicated that impacts to nearby Redwood Creek are of primary importance, and that site target cleanup standards should be evaluated primarily in the context of surface water quality criteria.

SURFACE WATER CONTAMINATION

As summarized in Table 2 (in Section 5.0), site surface water contaminant levels are compared to the most stringent screening level criteria published by the State of California, U.S. EPA, and U.S. Department of Energy. These screening criteria address chronic and acute exposures to aquatic life.

As discussed in the ESL document (Water Board, 2004), benthic communities at the groundwater/surface water interface (e.g., at site groundwater discharge location SW-2) are assumed to be exposed to the full concentration of groundwater contamination prior to dilution/mixing with the surface water). This was also a fundamental assumption in the instream benthic macroinvertebrate bioassessment events, which documented no measurable impacts.

Historical surface water sampling in the immediate vicinity of contaminated groundwater discharge (SW-2) has sporadically documented petroleum contamination, usually in periods of low stream flow, and generally at concentrations several orders of magnitude less than adjacent (within 20 feet) groundwater monitoring well concentrations. It is likely that mixing/dilution between groundwater and surface water precludes obtaining an “instantaneous discharge” surface water sample that is wholly representative of groundwater contamination at the discharge location. Therefore, the most conservative assumption is that surface water contamination at the groundwater/surface water interface is equivalent to the upgradient groundwater contamination (e.g., site downgradient wells MW-4, MW-7, and MW-9).

While site target cleanup standards for groundwater have not been determined, it is likely that no further action will be required by regulatory agencies when groundwater (and surface water) contaminant concentrations are all below their respective screening level criteria. Residual contaminant concentrations in excess of screening level criteria might be acceptable to regulatory agencies if a more detailed risk assessment (e.g., Tier 2 and/or Tier 3) demonstrates that no significant impacts are likely.

5.0 MONITORING EVENT ANALYTICAL RESULTS

This section presents the field and laboratory analytical results of the most recent monitoring event. Table 2 summarizes the contaminant analytical results of the current monitoring event. Figure 7 shows the current event contaminant analytical results and the inferred limits of the gasoline groundwater plume. Appendix C contains the certified analytical laboratory report and chain-of-custody record for the current event. Appendix D contains a summary of historical groundwater and surface analytical results.

CURRENT EVENT GROUNDWATER AND SURFACE WATER RESULTS

Current quarter site groundwater maximum concentrations exceed their respective groundwater ESLs for all analytes except toluene (under the *drinking water resource is threatened* criterion) and for all contaminants except toluene and MTBE (under the *drinking water resource is not threatened* criterion). Maximum site groundwater contaminant concentrations also exceed all surface water screening levels, with the exception of toluene and MTBE.

Except for benzene and MTBE, maximum groundwater contaminant concentrations were all detected in well MW-11 (located approximately three-quarters of the distance between the former source area and the creek). Maximum benzene concentrations were detected in upgradient well MW-8, while maximum MTBE concentrations were detected in upgradient well MW-2. Elevated contaminant concentrations were also detected in downgradient wells MW-7 and MW-9. The northern and southern edges of the plume in the downgradient area of the plume appear to be well defined by wells MW-4 and MW-10. The current event contaminant plume geometry is consistent with recent historical contaminant distribution, showing the center of contaminant mass in groundwater located downgradient of the former source area.

Neither of the two surface water samples collected (SW-3 and SW-3) had detectable concentrations for any of the site contaminants analyzed.

QUALITY CONTROL SAMPLE ANALYTICAL RESULTS

Laboratory QC samples (e.g., method blanks, matrix spikes, surrogate spikes, etc.) were analyzed by the laboratory in accordance with requirements of each analytical method. All laboratory QC

sample results and sample holding times were within the acceptance limits of the methods (see Appendix C).

Table 2
Groundwater and Surface Water Sample
Analytical Results – September 13, 2005
Redwood Regional Park Corporation Yard, Oakland, California

Location	Contaminant						
	TVHg	TEHd	Benzene	Toluene	Ethyl-benzene	Total Xylenes	MTBE
GROUNDWATER SAMPLES							
MW-2	<50	<50	2.5	<0.5	<0.5	<1.0	23
MW-4	<50	<50	<0.5	<0.5	<0.5	<1.0	<2.0
MW-7	7,600	2,700	110	<1.0	310	54.2	<4.0
MW-8	5,600	1,200	270	6.6	400	390	<20
MW-9	3,600	1,200	250	<0.5	330	35.7	<2.0
MW-10	87	<50	5	<0.5	3.6	<1.0	<2.0
MW-11	12,000	3,100	220	<1.0	840	762	<4.0
Groundwater ESLs ^(a)	100 / 500	100 / 640	1.0 / 46	40 / 130	30 / 290	13 / 13	5 / 1,800
REDWOOD CREEK SURFACE WATER SAMPLES							
SW-2	<50	<50	<0.5	<0.5	<0.5	<1.0	<2.0
SW-3	<50	<50	<0.5	<0.5	<0.5	<1.0	<2.0
Surface Water Screening Levels ^(a, b)	500	100	46	130	290	13	8,000

Notes:

^(a) Water Board Environmental Screening Levels (drinking water resource threatened/not threatened) (Water Board, 2004).

^(b) Lowest of chronic and acute surface water criteria published by the State of California, U.S. Environmental Protection Agency, or U.S. Department of Energy.


MTBE = methyl *tertiary*-butyl ether

TVHg = total volatile hydrocarbons - gasoline range

TEHd = total extractable hydrocarbons - diesel range

All concentrations expressed in µg/L (equivalent to parts per billion).

Samples in **bold-face type** exceed the ESL and/or surface water screening levels.



LEGEND & NOTES

- MW-1 Groundwater monitoring well MW-1
 - SW-2 Area of discolored soil and creek soil and "grab" surface water sample location SW-2
 - 1,000 TVHg isoconcentration in µg/L
 - Tree
 - Locations and dimensions of roads, trails, creek, and parking lot are approximate
 - All concentrations in µg/L (micrograms per liter)
 - UFST = Underground fuel storage tank
 - = Not sampled
 - = Not detected
 - MTBE = Methyl tertiary butyl ether
 - TVHg = Total volatile hydrocarbons – gasoline range
 - TEHd = Total extractable hydrocarbons – diesel range
 - BTEX = Benzene, toluene, ethylbenzene and total xylenes
- 0 20
Scale in feet

6.0 SUMMARY, CONCLUSIONS AND PROPOSED ACTIONS

The following conclusions and proposed actions are based on the findings of the current event activities, as well as on salient historical findings.

SUMMARY AND CONCLUSIONS

- Groundwater sampling has been conducted on an approximately quarterly basis since November 1994 (34 events in the initial site wells). A total of 11 site wells are available for monitoring; 7 of the available wells are currently monitored for contamination.
- Site contaminants of concern include gasoline, diesel, BTEX, and MTBE. Current groundwater concentrations exceed regulatory screening levels for groundwater and surface water.
- The primary environmental risk is discharge of contaminated groundwater to the adjacent Redwood Creek. A stream bioassessment concluded that there were no direct impacts to the surface water benthic community; however, groundwater contamination is sporadically detected in surface water samples, and there is historical visual evidence of plume discharge at the creek/groundwater interface. Surface water samples have sporadically exceeded surface water ESL criteria for gasoline, diesel, and benzene, and generally only under low creek flow conditions. An in-stream bioassessment evaluation in 1999-2000 determined no impacts to the benthic macroinvertebrate community.
- The existing well layout adequately constrains the lateral extent of groundwater contamination, and the vertical limit is very likely the top of the near-surface (25 to 28 feet) siltstone bedrock. The saturated interval extends approximately 12 to 15 feet from top of bedrock through the capillary fringe. Groundwater elevations fluctuate seasonally, creating a capillary fringe that varies seasonally in thickness.
- The groundwater contaminant plume has become disconnected from its original source, but continues to be fed from the residual hydrocarbon concentrations in the soil. The groundwater plume has migrated well beyond the former source area (represented by well MW-2) toward Redwood Creek. The plume of groundwater contamination above screening levels appears to be approximately 120 feet long and approximately 50 feet wide. The zone of greatest contamination (greater than 10,000 µg/L TPH) is an approximately 20- to 30-foot-wide by 50-foot-long area extending from mid-plume well MW-8 to the most downgradient wells MW-7 and MW-9.

- The contaminant plume is neither stable nor reducing, as groundwater contaminant concentrations fluctuate seasonally, and the center of mass of the contaminant plume (represented by maximum concentrations) has alternated between mid-plume and downgradient wells in recent history. While recent groundwater contaminant concentrations are at or near sitewide historical maxima, there is no indication that maximum site groundwater concentrations are increasing, suggesting that “worst case” contaminant concentrations may have been reached.
- A two-phase ORC™ injection corrective action program was implemented at the site. In September 2001, approximately 3,000 pounds of ORC™ was injected into 44 boreholes over a 4,400-square foot area of the maximum groundwater contamination. In June 2002, approximately 1,000 pounds of ORC™ was injected in 30 boreholes over a smaller area that showed residual high contaminant concentrations following the initial injection phase. The ORC™ was injected over the full saturated interval (including the capillary fringe). The findings indicate that the corrective action was partially effective in reducing the lateral extent of the groundwater contaminant plume; however, initial contaminant reductions were followed by rebounding to pre-injection concentrations. The data suggest that site conditions support aerobic biodegradation when not limited by oxygen concentrations, notably on the plume margins and upgradient former source area, but not along the centerline of the contaminant plume.
- A September 2003 exploratory borehole program confirmed that sorbed-phase contamination in the seasonally-unsaturated zone is a primary source of long-term contaminant contribution to the groundwater plume. Reduction/removal of this contamination will be necessary to eliminate continued discharge of contaminated groundwater to Redwood Creek and ultimately obtain site closure.
- Soil bioventing is to be applied at the site to mitigate the residual unsaturated zone hydrocarbon contamination that continues to provide contaminant input to the groundwater. The bioventing project is currently under review and procurement by the EBRPD following approval of the remedy by Alameda County Health.

PROPOSED ACTIONS

The EBRPD proposes to implement the following actions to address regulatory concerns:

- Continue the quarterly program of creek and groundwater sampling and reporting.
- Continue to inform regulators of site progress and seek their concurrence with proposed actions.
- Install the proposed bioventing system as a corrective action to move the site toward closure.

- Decommission well MW-4 and install a replacement well.
- Continue to evaluate analytical results (and bioventing contaminant removal data) in the context of hydrochemical trends, impacts of groundwater contamination on Redwood Creek, and effectiveness of the corrective action.
- Continue to make required Electronic Data Format uploads to the Water Board's GeoTracker database, and upload an electronic copy of technical reports to Alameda County Health's "ftp" system.

7.0 REFERENCES AND BIBLIOGRAPHY

Alameda County Health, 2005. Letter responding to October 2004 SES full-scale bioventing system design. May 31.

Parsons Engineering Science (Parsons), 1998. Quarterly Progress Report 11, Redwood Regional Park Service Yard, Oakland, California. January 28.

Parsons, 1997a. Quarterly Progress Report 7, Redwood Regional Park Service Yard, Oakland, California. January 31.

Parsons, 1997b. Quarterly Progress Report 8 and Annual Summary Assessment, Redwood Regional Park Service Yard, Oakland, California. April 4.

Parsons, 1997c. Quarterly Progress Report 9, Redwood Regional Park Service Yard, Oakland, California. June 30.

Parsons, 1997d. Quarterly Progress Report 10, Redwood Regional Park Service Yard, Oakland, California. September 22.

Parsons, 1996a. Quarterly Progress Report 5, Redwood Regional Park Service Yard, Oakland, California. June 6.

Parsons, 1996b. Quarterly Progress Report 6, Redwood Regional Park Service Yard, Oakland, California. September 24.

Parsons, 1995a. Quarterly Progress Report 2, Redwood Regional Park Service Yard, Oakland, California. March 8.

Parsons, 1995b. Quarterly Progress Report 3, Redwood Regional Park Service Yard, Oakland, California. June 23.

Parsons, 1995c. Quarterly Progress Report 4 and Annual Summary Assessment (November 1994 - August 1995), Redwood Regional Park Service Yard, Oakland, California. November 13.

- Parsons, 1994a. Creek and Soil Sampling at Redwood Regional Park, Oakland, California. March 2.
- Parsons, 1994b. Creek Surface Water at Redwood Regional Park, Oakland, California. May 13.
- Parsons, 1994c. Workplan for Groundwater Characterization Program at East Bay Regional Park Service Yard, Oakland, California. August 17.
- Parsons, 1994d. Quarterly Progress Report 1, Redwood Regional Park Service Yard, Oakland, California. December 28.
- Parsons, 1993a. Closure of Underground Fuel Storage Tanks and Initial Site Characterization at Redwood Regional Park Service Yard, Oakland, California. December 16.
- Parsons, 1993b. Workplan for Site Characterization at East Bay Regional Park District, Redwood Regional Park Corporation Yard, Oakland, Alameda County, California. September 3.
- Regional Water Quality Control Board, San Francisco Bay Region (Water Board), 2004. Screening for Environmental Concerns at Sites with Contaminated Soil and Groundwater. February.
- Regional Water Quality Control Board, San Francisco Bay Region (Water Board), 1995. *San Francisco Bay Region Water Quality Control Plan*.
- State Water Resources Control Board, 1989. Leaking Underground Fuel Tank Field Manual: Guidelines for Site Assessment, Cleanup, and Underground Storage Tank Closure. State of California Leaking Underground Fuel Tank Task Force. October.
- Stellar Environmental Solutions, Inc. (SES), 2005a. Fourth Quarter 2004 Groundwater Monitoring and Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 24.
- Stellar Environmental Solutions, Inc. (SES), 2005b. First Quarter 2005 Groundwater Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. March 31.
- Stellar Environmental Solutions, Inc. (SES), 2005C. Second Quarter 2005 Groundwater Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 12.
- SES, 2004a. Year 2003 Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 15.

- SES, 2004b. Bioventing Feasibility Letter Report - Redwood Regional Park Service Yard, Oakland, California. February 6.
- SES, 2004c. First Quarter 2004 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 14.
- SES, 2004d. Second Quarter 2004 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 16.
- SES, 2004e. Third Quarter 2004 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 12.
- SES, 2004f. Bioventing Pilot Test Results Report, Redwood Regional Park Service Yard, Oakland, California. October 29.
- SES, 2003a. Year 2002 Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 27.
- SES, 2003b. First Quarter 2003 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. May 5.
- SES, 2003c. Second Quarter 2003 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 29.
- SES, 2003d. Third Quarter 2003 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 3.
- SES, 2003e. Letter to Alameda County Health Care Services Agency proposing bioventing as a corrective action remedy at Redwood Regional Park Service Yard, Oakland, California. November 6.
- SES, 2002a. First Quarter 2002 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 16.
- SES, 2002b. Second Quarter 2002 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 23.
- SES, 2002c. Third Quarter 2002 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 14.
- SES, 2001a. Monitoring Well Installation and Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. February 8.

- SES, 2001b. Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. May 4.
- SES, 2001c. Well Installation, Site Monitoring, and Corrective Action Report, Redwood Regional Park Service Yard, Oakland, California. October 26.
- SES, 2000a. Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 21.
- SES, 2000b. Workplan for Groundwater Monitoring Well Installations, Redwood Regional Park Service Yard, Oakland, California. October 19.
- SES, 2000c. Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 19.
- SES, 2000d. Site Feasibility Study Report, Redwood Regional Park Service Yard, Oakland, California. October 20.
- SES, 1999a. Workplan for Subsurface Investigation, Redwood Regional Park Service Yard, Oakland, California. April 8.
- SES, 1999b. Residual Contamination Investigation and Remedial Action Assessment Report, Redwood Regional Park Service Yard, Oakland, California. June 9.
- SES, 1998a. Workplan for Continued Site Investigation and Closure Assessment, Redwood Regional Park Service Yard, Oakland, California. October 9.
- SES, 1998b. Site Investigation and Closure Assessment Report, Redwood Regional Park Service Yard, Oakland, California. December 4.

8.0 LIMITATIONS

This report has been prepared for the exclusive use of the East Bay Regional Park District, its authorized representatives, and the regulatory agencies. No reliance on this report shall be made by anyone other than those for whom it was prepared.

The findings and conclusions presented in this report are based on the review of previous investigators' findings at the site, as well as onsite activities conducted by SES since September 1998. This report provides neither a certification nor guarantee that the property is free of hazardous substance contamination. This report has been prepared in accordance with generally accepted methodologies and standards of practice. The SES personnel who performed this limited remedial investigation are qualified to perform such investigations and have accurately reported the information available, but cannot attest to the validity of that information. No warranty, expressed or implied, is made as to the findings, conclusions, and recommendations included in the report.

The findings of this report are valid as of the present. Site conditions may change with the passage of time, natural processes, or human intervention, which can invalidate the findings and conclusions presented in this report. As such, this report should be considered a reflection of the current site conditions as based on the investigation and remediation completed.

APPENDIX A

Historical Groundwater Monitoring Well Water Level Data

**HISTORICAL GROUNDWATER ELEVATIONS IN MONITORING WELLS
REDWOOD REGIONAL PARK SERVICE YARD
7867 REDWOOD ROAD, OAKLAND, CALIFORNIA**

Well I.D.	MW-1	MW-2	MW-3	MW-4	MW-5	MW-6	MW-7	MW-8	MW-9	MW-10	MW-11
TOC Elevation	565.90	566.50	560.90	548.10	547.50	545.60	547.70	549.20	549.40	547.30	547.90
Date Monitored	Groundwater Elevations (feet above mean sea level)										
September 18, 1998	563.7	544.2	540.8	534.5	531.1	545.6					
April 6, 1999	565.2	546.9	542.3	535.6	532.3	532.9					
December 20, 1999	562.9	544.7	541.5	534.9	531.2	532.2					
September 28, 2000	562.8	542.7	538.3	532.2	530.9	532.0					
January 11, 2001	562.9	545.1	541.7	535.0	531.2	532.3	534.9	538.1			
April 13, 2001	562.1	545.7	541.7	535.1	531.5	532.4	535.3	539.8			
September 1, 2001	560.9	542.0	537.7	533.9	530.7	531.8	534.0	535.6			
December 17, 2001	562.2	545.2	542.2	534.8	531.4	532.4	534.8	538.4	534.6	535.7	535.2
March 14, 2002	563.0	547.1	542.2	535.5	532.4	533.3	535.7	541.8	535.0	537.6	536.6
June 18, 2002	562.1	544.7	541.1	534.6	531.2	532.2	534.8	537.9	534.7	535.6	535.3
September 24, 2002	561.4	542.2	537.3	533.5	530.6	531.8	533.5	535.5	535.3	533.8	531.7
December 18, 2002	562.4	545.0	542.0	534.8	531.5	532.5	534.6	537.1	536.5	535.2	532.8
March 27, 2003	562.6	545.7	541.7	534.8	531.6	532.4	535.1	539.9	537.2	536.2	533.6
June 19, 2003	562.3	544.9	541.5	534.8	531.3	532.3	534.9	538.2	536.9	535.7	533.2
September 10, 2003	561.6	542.1	537.9	533.8	530.8	531.9	533.7	535.6	535.6	534.1	531.9
December 10, 2003	562.4	542.7	537.6	533.7	530.9	531.9	533.7	535.2	535.5	533.8	531.7
March 18, 2004	563.1	546.6	541.9	535.0	531.7	532.4	535.2	540.9	537.4	536.6	533.8
June 17, 2004	562.1	544.3	540.7	534.3	531.0	532.1	534.6	537.4	536.5	535.1	532.7
September 21, 2004	561.5	541.1	536.5	533.1	530.5	531.6	533.1	534.7	532.7	533.2	533.2
December 14, 2004	562.2	545.3	541.7	534.7	531.4	532.2	534.6	540.4	536.7	535.5	532.9
March 16, 2005	563.8	547.3	541.7	535.3	532.4	532.8	535.6	541.8	538.0	537.1	534.2
June 15, 2005	562.9	545.9	541.6	535.0	531.7	532.5	535.0	540.0	535.0	536.1	535.6
September 13, 2005	562.3	543.5	539.7	534.4	530.9	532.2	534.3	536.7	536.1	534.7	532.4

TOC = Top of well Casing

APPENDIX B

Groundwater Monitoring Field Documentation

WELL GAUGING DATA

Project # 050913-WC-1 Date 9/13/05 Client Stellar

Site Redwood Regional Park Service Yard, Oakland

Well ID	Well Size (in.)	Sheen / Odor	Depth to Immiscible Liquid (ft.)	Thickness of Immiscible Liquid (ft.)	Volume of Immiscibles Removed (ml)	Depth to water (ft.)	Depth to well bottom (ft.)	Survey Point: TOB or TOC
MW-1	4					3.62	19.20	g.o. g.o. g.o. g.o. g.o. g.o. g.o. g.o. g.o. g.o. g.o. ↓
MW-2	4					23.05	38.95	
MW-3	4					21.24	45.14	
MW-4	4					13.75	26.41	
MW-5	4					16.60	27.01	
MW-6	4					13.37	27.45	
MW-7	2					13.38	25.39	
MW-8	2					12.49	22.14	
MW-9	2					13.30	38.25	
MW-10	2					12.65	28.28	
MW-11	2					15.48	26.25	

WELL MONITORING DATA SHEET

Project #: <u>050913w-1</u>	Client: <u>Stellar</u>
Sampler: <u>wc</u>	Date: <u>9/13/05</u>
Well I.D.: <u>MW-#7</u>	Well Diameter: <u>(2)</u> 3 4 6 8
Total Well Depth (TD): <u>25.39</u>	Depth to Water (DTW): <u>13.38</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>00</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer	Waterra	Sampling Method: Bailer
Disposab le Bailer	Peristaltic	Disposab le Bailer
Positive Air Displacement	Extraction Pump	Extraction Port
Electric Submersible	Other _____	Dedicated Tubing
Other: _____		

$1.9 \text{ (Gals.)} \times 3 = 5.7 \text{ Gals.}$ <p style="font-size: small; margin: 0;"> 1 Case Volume Specified Volumes Calculated Volume </p>	<table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F or °C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1155	59.3	7.2	892	359	1.9	grey/odor
1159	59.4	7.1	881	287	3.8	
1202	59.4	7.1	877	246	5.7	↓

Did well dewater? Yes Gallons actually evacuated: ~~1.9~~ 5.7

Sampling Date: 9/13/05 Sampling Time: 1207 Depth to Water:

Sample I.D.: MW-7 Laboratory: Kiff CalScience Other C&T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other:

EB I.D. (if applicable): @ _____ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

WELL MONITORING DATA SHEET

Project #: <u>050913-well</u>	Client: <u>Stellar</u>
Sampler: <u>wc</u>	Date: <u>9/13/05</u>
Well I.D.: <u>MW-8</u>	Well Diameter: <u>2</u> 3 4 6 8 _____
Total Well Depth (TD): <u>22.14</u>	Depth to Water (DTW): <u>12.49</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Disposable Bailer Positive Air Displacement Electric Submersible	Waterra Peristaltic Extraction Pump Other _____	Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing Other: _____
--	--	---

$1.5 \text{ (Gals.)} \times 3 = 4.5 \text{ Gals.}$ I Case Volume Specified Volumes Calculated Volume	<table border="1" style="width: 100%; border-collapse: collapse; font-size: small;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F or °C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1025	58.4	6.7	868	354	1.5	odor/cloudy grey
1030	58.3	6.7	879	413	3	↓
1033	58.2	6.8	899	509	4.5	↓

Did well dewater? Yes No Gallons actually evacuated: 4.5

Sampling Date: 9/13/05 Sampling Time: 1038 Depth to Water: _____

Sample I.D.: MW-8 Laboratory: Kiff CalScience Other C&T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

WELL MONITORING DATA SHEET

Project #: <u>0509613-WC-1</u>	Client: <u>Stellar</u>
Sampler: <u>we</u>	Date: <u>9/13/05</u>
Well I.D.: <u>MW-9</u>	Well Diameter: <u>(2)</u> 3 4 6 8 _____
Total Well Depth (TD): <u>30.25</u>	Depth to Water (DTW): <u>13.30</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer Disposable Bailer Positive Air Displacement Electric Submersible Waterra Peristaltic Extraction Pump Other _____

Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing Other: _____

$$2.7 \text{ (Gals.)} \times 3 = 8.1 \text{ Gals.}$$
 I Case Volume Specified Volumes Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F or °C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1105	58.8	7.4	767	673	2.7	odor/cloudy
1110	58.8	7.1	789	668	5.4	↓
1114	58.6	7.0	817	660	8.1	↓

Did well dewater? Yes No Gallons actually evacuated: 8.1

Sampling Date: 9/13/05 Sampling Time: 1119 Depth to Water: _____

Sample I.D.: MW-9 Laboratory: Kiff CalScience Other C&T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

WELL MONITORING DATA SHEET

Project #: <u>050913-WC1</u>	Client: <u>Stellar</u>
Sampler: <u>WL</u>	Date: <u>9/13/05</u>
Well I.D.: <u>MW-11</u>	Well Diameter: <u>0</u> 3 4 6 8 <u> </u>
Total Well Depth (TD): <u>26.25</u>	Depth to Water (DTW): <u>15.48</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>GC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:	

Purge Method: Bailer	Waterra	Sampling Method: Bailer
Disposible <u>B</u> Bailer	Peristaltic	Disposible <u>B</u> Bailer
Positive Air Displacement	Extraction Pump	Extraction Port
Electric Submersible	Other _____	Dedicated Tubing
Other: _____		

	Well Diameter	Multiplier	Well Diameter	Multiplier
<u>1.7</u> (Gals.) X	<u>3</u>	=	<u>5.1</u>	Gals.
1 Case Volume	Specified Volumes		Calculated Volume	

1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (<u>F</u> or °C)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
<u>1127</u>	<u>59.2</u>	<u>6.8</u>	<u>1140</u>	<u>289</u>	<u>1.7</u>	<u>grey/light sheen</u> ↓
<u>1131</u>	<u>59.2</u>	<u>6.8</u>	<u>1132</u>	<u>338</u>	<u>3.4</u>	
<u>1135</u>	<u>59.4</u>	<u>6.7</u>	<u>1121</u>	<u>417</u>	<u>5.1</u>	

Did well dewater? Yes No Gallons actually evacuated: 5.1

Sampling Date: 9/13/05 Sampling Time: 091140 Depth to Water: _____

Sample I.D.: MW-11 Laboratory: Kiff CalScience Other C&T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

APPENDIX C

Analytical Laboratory Report and Chain-of-Custody Record



Curtis & Tompkins, Ltd., Analytical Laboratories, Since 1878

2323 Fifth Street, Berkeley, CA 94710, Phone (510) 486-0900

A N A L Y T I C A L R E P O R T


Prepared for:

Stellar Environmental Solutions
2198 6th Street
Suite 201
Berkeley, CA 94710


Date: 26-SEP-05
Lab Job Number: 181851
Project ID: 2005-02
Location: Redwood Regional Park

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the following signatures. The results contained in this report meet all requirements of NELAC and pertain only to those samples which were submitted for analysis.

Reviewed by:


Project Manager

Reviewed by:


Operations Manager

This package may be reproduced only in its entirety.

CASE NARRATIVE

Laboratory number: 181851
Client: Stellar Environmental Solutions
Project: 2005-02
Location: Redwood Regional Park
Request Date: 09/13/05
Samples Received: 09/13/05

This hardcopy data package contains sample and QC results for nine water samples, requested for the above referenced project on 09/13/05. The samples were received cold and intact.

TPH-Purgeables and/or BTXE by GC (EPA 8015B and EPA 8021B):

High surrogate recovery was observed for trifluorotoluene (PID) in MW-7 (lab # 181851-005), due to interference from coeluting hydrocarbon peaks; the corresponding bromofluorobenzene (PID) surrogate recovery was within limits. High surrogate recovery was observed for trifluorotoluene (FID) in MW-9 (lab # 181851-007), due to interference from coeluting hydrocarbon peaks; the corresponding bromofluorobenzene (FID) surrogate recovery was within limits. No other analytical problems were encountered.

TPH-Extractables by GC (EPA 8015B):

No analytical problems were encountered.

181851

Chain of Custody Record

Lab job no. 050915
Date 9/13/05
Page 1 of 1

Laboratory Curtis and Tompkins, Ltd. Method of Shipment Hand Delivery
 Address 2323 Fifth Street Shipment No. _____
Berkeley, California 94710 Airbill No. _____
510-486-0900 Cooler No. _____
 Project Owner East Bay Regional Park District Project Manager Bruce Rucker
 Site Address 7867 Redwood Road Telephone No. (510) 644-3123
Oakland, California Fax No. (510) 644-3859
 Project Name Redwood Regional Park Samplers: (Signature) Will Crow / Will Crow
 Project Number 2005-02

Field Sample Number	Location/Depth	Date	Time	Sample Type	Type/Size of Container	Preservation		Filtered	No. of Containers	Analysis Required										Remarks					
						Cooler	Chemical			1	2	3	4	5	6	7	8	9	10		11	12			
-1 SW-3	-	9/13	800	H ₂ O	VOHS + 1-L glass	✓	HCl (VOHs)		3	X	X														
-2 SW-2	-	"	805	"	" "	✓	"		3	X	X														
-3 MW-2	-		1240						4	X	X														
-4 MW-4	-		1215							X	X														
-5 MW-7	-		1207							X	X														
-6 MW-8	-		1038							X	X														
-7 MW-9	-		1119							X	X														
-8 MW-10	-		1015							X	X														
-9 MW-11	-		1140							X	X														
-10 TB-09132005	-	↓	-	↓	VOA	↓	↓	✓	1																on hold

-1
-2
-3
-4
-5
-6
-7
-8
-9
-10

Relinquished by: Signature <u>Will Crow</u> Printed <u>Will Crow</u> Company <u>Blaine Tech</u>	Date <u>9/13/05</u> Time <u>2:00</u>	Received by: Signature <u>Lavanna Curtis</u> Printed <u>Lavanna Curtis</u> Company <u>CTT</u>	Date <u>9/13</u> Time <u>2:00</u>	Relinquished by: Signature _____ Printed _____ Company _____	Date _____ Time _____	Received by: Signature _____ Printed _____ Company _____	Date _____ Time _____
Turnaround Time: <u>5 Day TAT</u>				Relinquished by: Signature _____ Printed _____ Company _____			
Comments: <u>Please provide a GeoTracker EDD as well as hard copy of report.</u> <u>SW-2 + SW-3 collected by Bruce Rucker of SES</u>				Received by: Signature _____ Printed _____ Company _____			

2000-00-01

Received by: Blaine Tech
 Cool Ambient Direct

Curtis & Tompkins Laboratories Analytical Report

Lab #: 181851	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2005-02	
Matrix: Water	Sampled: 09/13/05
Units: ug/L	Received: 09/13/05

Field ID: SW-3 Diln Fac: 1.000
 Type: SAMPLE Batch#: 105744
 Lab ID: 181851-001 Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	99	62-141	EPA 8015B
Bromofluorobenzene (FID)	112	78-134	EPA 8015B
Trifluorotoluene (PID)	79	67-127	EPA 8021B
Bromofluorobenzene (PID)	89	80-122	EPA 8021B

Field ID: SW-2 Diln Fac: 1.000
 Type: SAMPLE Batch#: 105744
 Lab ID: 181851-002 Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	105	62-141	EPA 8015B
Bromofluorobenzene (FID)	120	78-134	EPA 8015B
Trifluorotoluene (PID)	81	67-127	EPA 8021B
Bromofluorobenzene (PID)	92	80-122	EPA 8021B

Curtis & Tompkins Laboratories Analytical Report

Lab #: 181851	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2005-02	
Matrix: Water	Sampled: 09/13/05
Units: ug/L	Received: 09/13/05

Field ID: MW-2	Diln Fac: 1.000
Type: SAMPLE	Batch#: 105744
Lab ID: 181851-003	Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	23	2.0	EPA 8021B
Benzene	2.5	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	105	62-141	EPA 8015B
Bromofluorobenzene (FID)	111	78-134	EPA 8015B
Trifluorotoluene (PID)	79	67-127	EPA 8021B
Bromofluorobenzene (PID)	88	80-122	EPA 8021B

Field ID: MW-4	Diln Fac: 1.000
Type: SAMPLE	Batch#: 105744
Lab ID: 181851-004	Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	98	62-141	EPA 8015B
Bromofluorobenzene (FID)	116	78-134	EPA 8015B
Trifluorotoluene (PID)	81	67-127	EPA 8021B
Bromofluorobenzene (PID)	90	80-122	EPA 8021B

*= Value outside of QC limits; see narrative
 C= Presence confirmed, but RPD between columns exceeds 40%
 ND= Not Detected
 RL= Reporting Limit
 Page 2 of 5

Curtis & Tompkins Laboratories Analytical Report

Lab #: 181851	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2005-02	
Matrix: Water	Sampled: 09/13/05
Units: ug/L	Received: 09/13/05

Field ID: MW-7	Diln Fac: 2.000
Type: SAMPLE	Batch#: 105744
Lab ID: 181851-005	Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	7,600	100	EPA 8015B
MTBE	ND	4.0	EPA 8021B
Benzene	110	1.0	EPA 8021B
Toluene	ND	1.0	EPA 8021B
Ethylbenzene	310	1.0	EPA 8021B
m,p-Xylenes	49	1.0	EPA 8021B
o-Xylene	5.2 C	1.0	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	85	62-141	EPA 8015B
Bromofluorobenzene (FID)	118	78-134	EPA 8015B
Trifluorotoluene (PID)	134 *	67-127	EPA 8021B
Bromofluorobenzene (PID)	97	80-122	EPA 8021B

Field ID: MW-8	Diln Fac: 10.00
Type: SAMPLE	Batch#: 105744
Lab ID: 181851-006	Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	5,600	500	EPA 8015B
MTBE	ND	20	EPA 8021B
Benzene	270	5.0	EPA 8021B
Toluene	6.6	5.0	EPA 8021B
Ethylbenzene	400	5.0	EPA 8021B
m,p-Xylenes	370	5.0	EPA 8021B
o-Xylene	20	5.0	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	103	62-141	EPA 8015B
Bromofluorobenzene (FID)	100	78-134	EPA 8015B
Trifluorotoluene (PID)	77	67-127	EPA 8021B
Bromofluorobenzene (PID)	83	80-122	EPA 8021B

*= Value outside of QC limits; see narrative

C= Presence confirmed, but RPD between columns exceeds 40%

ND= Not Detected

RL= Reporting Limit

Page 3 of 5

Curtis & Tompkins Laboratories Analytical Report

Lab #: 181851	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2005-02	
Matrix: Water	Sampled: 09/13/05
Units: ug/L	Received: 09/13/05

Field ID: MW-9	Diln Fac: 1.000
Type: SAMPLE	Batch#: 105744
Lab ID: 181851-007	Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	3,600	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	250	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	330	0.50	EPA 8021B
m,p-Xylenes	33 C	0.50	EPA 8021B
o-Xylene	2.7	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	143 *	62-141	EPA 8015B
Bromofluorobenzene (FID)	124	78-134	EPA 8015B
Trifluorotoluene (PID)	104	67-127	EPA 8021B
Bromofluorobenzene (PID)	99	80-122	EPA 8021B

Field ID: MW-10	Diln Fac: 1.000
Type: SAMPLE	Batch#: 105744
Lab ID: 181851-008	Analyzed: 09/14/05

Analyte	Result	RL	Analysis
Gasoline C7-C12	87	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	5.0	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	3.6	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	104	62-141	EPA 8015B
Bromofluorobenzene (FID)	116	78-134	EPA 8015B
Trifluorotoluene (PID)	82	67-127	EPA 8021B
Bromofluorobenzene (PID)	93	80-122	EPA 8021B

*= Value outside of QC limits; see narrative

C= Presence confirmed, but RPD between columns exceeds 40%

ND= Not Detected

RL= Reporting Limit

Page 4 of 5

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	181851	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2005-02	Analysis:	EPA 8021B
Type:	LCS	Diln Fac:	1.000
Lab ID:	QC308830	Batch#:	105744
Matrix:	Water	Analyzed:	09/14/05
Units:	ug/L		

Analyte	Spiked	Result	%REC	Limits
MTBE	20.00	20.05	100	72-124
Benzene	20.00	19.74	99	80-120
Toluene	20.00	19.39	97	80-120
Ethylbenzene	20.00	19.63	98	80-120
m,p-Xylenes	20.00	19.11	96	80-120
o-Xylene	20.00	19.96	100	80-120

Surrogate	%REC	Limits
Trifluorotoluene (PID)	77	67-127
Bromofluorobenzene (PID)	88	80-122

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	181851	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2005-02	Analysis:	EPA 8015B
Type:	LCS	Diln Fac:	1.000
Lab ID:	QC308831	Batch#:	105744
Matrix:	Water	Analyzed:	09/14/05
Units:	ug/L		

Analyte	Spiked	Result	%REC	Limits
Gasoline C7-C12	2,000	1,954	98	80-120

Surrogate	%REC	Limits
Trifluorotoluene (FID)	133	62-141
Bromofluorobenzene (FID)	116	78-134

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	181851	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2005-02	Analysis:	EPA 8015B
Field ID:	SW-3	Batch#:	105744
MSS Lab ID:	181851-001	Sampled:	09/13/05
Matrix:	Water	Received:	09/13/05
Units:	ug/L	Analyzed:	09/15/05
Diln Fac:	1.000		

Type: MS Lab ID: QC308866

Analyte	MSS Result	Spiked	Result	%REC	Limits
Gasoline C7-C12	10.82	2,000	1,956	97	80-120

Surrogate	%REC	Limits
Trifluorotoluene (FID)	140	62-141
Bromofluorobenzene (FID)	128	78-134

Type: MSD Lab ID: QC308867

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
Gasoline C7-C12	2,000	1,927	96	80-120	2	20

Surrogate	%REC	Limits
Trifluorotoluene (FID)	136	62-141
Bromofluorobenzene (FID)	122	78-134

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	181851	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2005-02	Analysis:	EPA 8021B
Type:	BS	Diln Fac:	1.000
Lab ID:	QC309086	Batch#:	105803
Matrix:	Water	Analyzed:	09/15/05
Units:	ug/L		

Analyte	Spiked	Result	%REC	Limits
Ethylbenzene	20.00	20.44	102	80-120

Surrogate	%REC	Limits
Trifluorotoluene (PID)	80	67-127
Bromofluorobenzene (PID)	94	80-122

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	181851	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2005-02	Analysis:	EPA 8021B
Type:	BSD	Diln Fac:	1.000
Lab ID:	QC309175	Batch#:	105803
Matrix:	Water	Analyzed:	09/15/05
Units:	ug/L		

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
Ethylbenzene	20.00	19.14	96	80-120	7	20

Surrogate	%REC	Limits
Trifluorotoluene (PID)	76	67-127
Bromofluorobenzene (PID)	85	80-122



Batch QC Report

Total Extractable Hydrocarbons			
Lab #:	181851	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 3520C
Project#:	2005-02	Analysis:	EPA 8015B
Matrix:	Water	Batch#:	106058
Units:	ug/L	Prepared:	09/22/05
Diln Fac:	1.000	Analyzed:	09/23/05

Type: BS
 Lab ID: QC310180

Cleanup Method: EPA 3630C

Analyte	Spiked	Result	%REC	Limits
Diesel C10-C24	2,500	1,931	77	53-138

Surrogate	%REC	Limits
Hexacosane	93	60-135

Type: BSD
 Lab ID: QC310181

Cleanup Method: EPA 3630C

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
Diesel C10-C24	2,500	1,987	79	53-138	3	36

Surrogate	%REC	Limits
Hexacosane	102	60-135

APPENDIX D

Historical Groundwater and Surface Water Analytical Results

HISTORICAL GROUNDWATER MONITORING WELLS ANALYTICAL RESULTS
REDWOOD REGIONAL PARK SERVICE YARD, OAKLAND, CALIFORNIA
(all concentrations in ug/L, equivalent to parts per billion [ppb])

Well MW-2									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Nov-94	66	< 50	3.4	< 0.5	< 0.5	0.9	4.3	NA
2	Feb-95	89	< 50	18	2.4	1.7	7.5	30	NA
3	May-95	< 50	< 50	3.9	< 0.5	1.6	2.5	8.0	NA
4	Aug-95	< 50	< 50	5.7	< 0.5	< 0.5	< 0.5	5.7	NA
5	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Aug-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Dec-96	< 50	< 50	6.3	< 0.5	1.6	< 0.5	7.9	NA
8	Feb-97	< 50	< 50	0.69	< 0.5	0.55	< 0.5	1.2	NA
9	May-97	67	< 50	8.9	< 0.5	5.1	< 1.0	14	NA
10	Aug-97	< 50	< 50	4.5	< 0.5	1.1	< 0.5	5.6	NA
11	Dec-97	61	< 50	21	< 0.5	6.5	3.9	31	NA
12	Feb-98	2,000	200	270	92	150	600	1,112	NA
13	Sep-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	7.0
14	Apr-99	82	710	4.2	< 0.5	3.4	4.0	12	7.5
15	Dec-99	57	< 50	20	0.6	5.9	< 0.5	27	4.5
16	Sep-00	< 50	< 50	0.72	< 0.5	< 0.5	< 0.5	0.7	7.9
17	Jan-01	51	< 50	8.3	< 0.5	1.5	< 0.5	9.8	8.0
18	Apr-01	110	< 50	10	< 0.5	11	6.4	27	10
19	Aug-01	260	120	30	6.7	1.6	6.4	45	27
20	Dec-01	74	69	14	0.8	3.7	3.5	22	6.6

Well MW-2 (continued)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
21	Mar-02	< 50	< 50	2.3	0.51	1.9	1.3	8.3	8.2
22	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	7.7
23	Sep-02	98	< 50	5.0	< 0.5	< 0.5	< 0.5	—	13
24	Dec-02	< 50	< 50	4.3	< 0.5	< 0.5	< 0.5	—	< 2.0
25	Mar-03	130	82	39	< 0.5	20	4.1	63	16
26	Jun-03	< 50	< 50	1.9	< 0.5	< 0.5	< 0.5	1.9	8.7
27	Sep-03	120	< 50	8.6	0.51	0.53	< 0.5	9.6	23
28	Dec-03	282	<100	4.3	1.6	1.3	1.2	8.4	9.4
29	Mar-04	374	<100	81	1.2	36	7.3	126	18
30	Jun-04	< 50	< 50	0.75	< 0.5	< 0.5	< 0.5	< 0.5	15
31	Sep-04	200	< 50	23	< 0.5	< 0.5	0.70	24	16
32	Dec-04	80	< 50	14	< 0.5	2.9	0.72	18	20
33	Mar-05	190	68	27	<0.5	14	11	52	26
34	Jun-05	68	< 50	7.1	< 0.5	6.9	1.8	16	24
35	Sep-05	< 50	< 50	2.5	< 0.5	< 0.5	< 1.0	2.5	23
Well MW-4									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Nov-94	2,600	230	120	4.8	150	88	363	NA
2	Feb-95	11,000	330	420	17	440	460	1,337	NA
3	May-95	7,200	440	300	13	390	330	1,033	NA
4	Aug-95	1,800	240	65	6.8	89	67	227	NA
5	May-96	1,100	140	51	< 0.5	< 0.5	47	98	NA
6	Aug-96	3,700	120	63	2.0	200	144	409	NA
7	Dec-96	2,700	240	19	< 0.5	130	93	242	NA
8	Feb-97	3,300	< 50	120	1.0	150	103	374	NA
9	May-97	490	< 50	2.6	6.7	6.4	6.7	22	NA
10	Aug-97	1,900	150	8.6	3.5	78	53	143	NA
11	Dec-97	1,000	84	4.6	2.7	61	54	123	NA
12	Feb-98	5,300	340	110	24	320	402	856	NA
13	Sep-98	1,800	< 50	8.9	< 0.5	68	27	104	23
14	Apr-99	2,900	710	61	1.2	120	80	263	32
15	Dec-99	1,000	430	4.0	2.0	26	14	46	< 2.0

Well MW-4 (continued)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
16	Sep-00	570	380	< 0.5	< 0.5	16	4.1	20	2.4
17	Jan-01	1,600	650	4.2	0.89	46	13.8	65	8.4
18	Apr-01	1,700	1,100	4.5	2.8	48	10.7	66	5.0
19	Aug-01	1,300	810	3.2	4.0	29	9.7	46	< 2.0
20	Dec-01	< 50	110	< 0.5	< 0.5	< 0.5	1.2	1.2	< 2.0
21	Mar-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
22	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
23	Sep-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
24	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
25	Mar-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
26	Jun-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
27	Sep-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
28	Dec-03	< 50	< 100	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
29	Mar-04	< 50	< 100	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
30	Jun-04	< 50	2,500	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
31	Sep-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
32	Dec-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
33	Mar-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
34	Jun-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
35	Sep-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0

Well MW-5									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Nov-94	50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
2	Feb-95	70	< 50	0.6	< 0.5	< 0.5	< 0.5	0.6	NA
3	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	Aug-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Aug-96	80	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
9	May-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Aug-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
11	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
12	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
13	Sep-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2
Groundwater monitoring in this well discontinued in 1998 with Alameda County Health Care Services Agency approval.									
Subsequent groundwater monitoring conducted to confirm plume's southern limit									
14	Jun-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	5.9
15	Sep-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0

Well MW-7									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Jan-01	13,000	3,100	95	4	500	289	888	95
2	Apr-01	13,000	3,900	140	< 0.5	530	278	948	52
3	Aug-01	12,000	5,000	55	25	440	198	718	19
4	Dec-01	9,100	4,600	89	< 2.5	460	228	777	< 10
5	Mar-02	8,700	3,900	220	6.2	450	191	867	200
6	Jun-02	9,300	3,500	210	6.3	380	155	751	18
7	Sep-02	9,600	3,900	180	< 0.5	380	160	720	< 2.0
8	Dec-02	9,600	3,700	110	< 0.5	400	189	699	< 2.0
9	Mar-03	10,000	3,600	210	12	360	143	725	45
10	Jun-03	9,300	4,200	190	< 10	250	130	570	200
11	Sep-03	10,000	3,300	150	11	300	136	597	< 2.0
12	Dec-03	9,140	1,100	62	45	295	184	586	89
13	Mar-04	8,170	600	104	41	306	129	580	84
14	Jun-04	9,200	2,700	150	< 0.5	290	91	531	< 2.0
15	Sep-04	9,700	3,400	98	< 0.5	300	125	523	< 2.0
16	Dec-04	8200	4,000	95	< 0.5	290	124	509	< 2.0
17	Mar-05	10,000	4,300	150	<0.5	370	71	591	<2.0
18	Jun-05	10,000	3,300	210	<1.0	410	56	676	<4.0
19	Sep-05	7,600	2,700	110	<1.0	310	54	474	<4.0

Well MW-8									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Jan-01	14,000	1,800	430	17	360	1230	2,037	96
2	Apr-01	11,000	3,200	320	13	560	1,163	2,056	42
3	Aug-01	9,600	3,200	130	14	470	463	1,077	14
4	Dec-01	3,500	950	69	2.4	310	431	812	< 4.0
5	Mar-02	14,000	3,800	650	17	1,200	1,510	3,377	240
6	Jun-02	2,900	1,100	70	2.0	170	148	390	19
7	Sep-02	1,000	420	22	< 0.5	64	50	136	< 2.0
8	Dec-02	3,300	290	67	< 0.5	190	203	460	< 2.0
9	Mar-03	13,000	3,500	610	12	1,100	958	2,680	< 10
10	Jun-03	7,900	2,200	370	7.4	620	562	1,559	< 4.0
11	Sep-03	3,600	400	120	3.3	300	221	644	< 2.0
12	Dec-03	485	100	19	1.5	26	36	83	< 5.0

Well MW-8 (continued)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
13	Mar-04	16,000	900	592	24	1,060	1,870	3,546	90
14	Jun-04	5,900	990	260	9.9	460	390	1,120	< 10
15	Sep-04	2,000	360	100	< 2.5	180	102	382	< 10
16	Dec-04	15,000	4,000	840	21	1,200	1,520	3,581	< 10
17	Mar-05	24,000	7,100	840	51	1,800	2,410	5,101	<10
18	Jun-05	33,000	5,700	930	39	2,500	3,860	7,329	<20
19	Sep-05	5,600	1,200	270	6.6	400	390	1,067	<20

Well MW-9									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Aug-01	11,000	170	340	13	720	616	1,689	48
2	Dec-01	9,400	2,700	250	5.1	520	317	1,092	< 10
3	Mar-02	1,700	300	53	4.2	120	67	244	20
4	Jun-02	11,000	2,500	200	16	600	509	1,325	85
5	Sep-02	3,600	2,800	440	11	260	39	750	< 4.0
6	Dec-02	7,000	3,500	380	9.5	730	147	1,266	< 10
7	Mar-03	4,400	1,400	320	6.9	400	93	820	< 2.0
8	Jun-03	7,600	1,600	490	10	620	167	1,287	< 4.0
9	Sep-03	8,300	2,900	420	14	870	200	1,504	< 10
10	Dec-03	7,080	700	287	31	901	255	1,474	< 10
11	Mar-04	3,550	600	122	15	313	84	534	35
12	Jun-04	6,800	1,700	350	< 2.5	620	99	1,069	< 10
13	Sep-04	7,100	1,900	160	8.1	600	406	1,174	< 10
14	Dec-04	4,700	2,800	160	< 2.5	470	< 0.5	630	< 10
15	Mar-05	4,200	1,600	97	<2.5	310	42	449	< 10
16	Jun-05	9,900	2,000	170	<2.5	590	359	1,119	< 10
17	Sep-05	3,600	1,200	250	<0.5	330	36	616	< 2.0

Well MW-10									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Aug-01	550	2,100	17	< 0.5	31	44	92	40
2	Dec-01	< 50	81	< 0.5	< 0.5	< 0.5	< 0.5	—	25
3	Mar-02	< 50	< 50	0.61	< 0.5	< 0.5	< 0.5	0.61	6.0
4	Jun-02	< 50	< 50	0.59	< 0.5	0.58	< 0.5	1.2	9.0
5	Sep-02	160	120	10	< 0.5	6.7	3.6	20	26
6	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	16
7	Mar-03	110	< 50	11	< 0.5	12	1.3	24	15
8	Jun-03	110	< 50	9.6	< 0.5	6.8	< 0.5	16	9.0
9	Sep-03	< 50	< 50	1.1	< 0.5	1.5	< 0.5	2.6	7.0
10	Dec-03	162	<100	6.9	<0.3	8.0	<0.6	15	9.9
11	Mar-04	94	<100	2.8	<0.3	5.7	7.0	16	<5.0
12	Jun-04	150	56	11	< 0.5	12	< 0.5	23	15
13	Sep-04	< 50	< 50	1.6	< 0.5	1.9	< 1.0	3.5	5.8
14	Dec-04	64	< 50	3.7	< 0.5	3.7	0.7	8.1	10
15	Mar-05	95	98	8.3	<0.5	7.7	0.77	17	13
16	Jun-05	150	57	14	<0.5	10	1.0	25	<2.0
17	Sep-05	87	< 50	5.0	<0.5	3.6	<1.0	9	<2.0

Well MW-11									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Aug-01	17,000	7,800	390	17	820	344	1,571	< 10
2	Dec-01	5,800	2,800	280	7.8	500	213	1,001	< 10
3	Mar-02	100	94	< 0.5	< 0.5	0.64	< 0.5	0.64	2.4
4	Jun-02	8,200	2,600	570	13	560	170	1,313	< 4
5	Sep-02	12,000	4,400	330	13	880	654	1,877	< 10
6	Dec-02	18,000	4,500	420	< 2.5	1,100	912	2,432	< 10
7	Mar-03	7,800	2,600	170	4.7	530	337	1,042	53
8	Jun-03	14,000	3,800	250	< 2.5	870	693	1,813	< 10
9	Sep-03	10,000	3,000	250	9.9	700	527	1,487	< 4
10	Dec-03	15,000	1,100	314	60	1,070	802	2,246	173
11	Mar-04	4,900	400	72	17	342	233	664	61
12	Jun-04	10,000	2,300	210	2.8	690	514	1,417	< 10
13	Sep-04	7,200	2,300	340	< 2.5	840	75	1,255	< 10
14	Dec-04	11,000	3,900	180	5.1	780	695	1,660	< 10
15	Mar-05	4,600	1,900	69	< 2.5	300	206	575	< 10
16	Jun-05	1,400	590	85	< 0.5	110	8.2	203	< 2.0
17	Sep-05	12,000	3,100	220	< 1.0	840	762	1,822	< 4.0

HISTORICAL SURFACE WATER ANALYTICAL RESULTS
REDWOOD REGIONAL PARK SERVICE YARD, OAKLAND, CALIFORNIA

(all concentrations in ug/L, equivalent to parts per billion [ppb])

Sampling Location SW-1 (Upstream of Contaminated Groundwater Discharge Location SW-2)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Feb-94	50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
2	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
3	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	Aug-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Aug-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
9	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Sep-98	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
11	Apr-99	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
Sampling at this location discontinued after April 1999 with Alameda County Health Services Agency approval.									

Sampling Location SW-2 (Area of Historical Contaminated Groundwater Discharge)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Feb-94	130	< 50	1.9	< 0.5	4.4	3.2	9.5	NA
2	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
3	Aug-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	Aug-96	200	< 50	7.5	< 0.5	5.4	< 0.5	13	NA
6	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Aug-97	350	130	13	0.89	19	11	44	NA
9	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
11	Sep-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
12	Apr-99	81	< 50	2.0	< 0.5	2.5	1.3	5.8	2.3
13	Dec-99	1,300	250	10	1.0	47	27	85	2.2
14	Sep-00	160	100	2.1	< 0.5	5.2	1.9	9.2	3.4
15	Jan-01	< 50	< 50	< 0.5	< 0.5	0.53	< 0.5	0.5	< 2.0
16	Apr-01	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
17	Sep-01	440	200	2.1	< 0.5	17	1.3	20	10
18	Dec-01	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
19	Mar-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
20	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
21	Sep-02	220	590	10	< 0.5	13	< 0.5	23	< 2.0
22	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
23	Mar-03	< 50	< 50	< 0.5	< 0.5	0.56	< 0.5	0.56	2.8
24	Jun-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
25	Sep-03	190	92	2.1	< 0.5	4.2	< 0.5	6.3	< 2.0
26	Dec-03	86	< 100	< 0.3	< 0.3	< 0.3	< 0.6	-	< 5.0
27	Mar-04	< 50	< 100	< 0.3	< 0.3	1.1	< 0.6	1.1	< 5.0
28	Jun-04	< 50	< 50	< 0.5	< 0.5	0.83	< 0.5	0.83	< 2.0
29	Sep-04	260	370	4.4	< 0.5	6.3	< 1.0	11	< 2.0
30	Dec-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	-	< 2.0
31	Mar-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	-	< 2.0
32	Jun-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	-	< 2.0
33	Sep-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	-	< 2.0

Sampling Location SW-3 (Downstream of Contaminated Groundwater Discharge Location SW-2)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
2	Aug-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
3	May-96	< 50	74	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	Aug-96	69	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Aug-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
9	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Sep-98	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
11	Apr-99	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
12	Dec-99	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
13	Sep-00	NS	NS	NS	NS	NS	NS	—	NS
14	Jan-01	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
15	Apr-01	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
16	Sep-01	NS	NS	NS	NS	NS	NS	—	NS
17	Dec-01	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
18	Mar-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
19	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	2.4
20	Sep-02	NS	NS	NS	NS	NS	NS	—	NS
21	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
22	Mar-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
23	Jun-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	-	< 2.0
24	Sep-03	NS	NS	NS	NS	NS	NS	—	NS
25	Dec-03	60	< 100	< 0.3	< 0.3	< 0.3	< 0.6	-	< 5.0
26	Mar-04	<50	<100	<0.3	<0.3	<0.6	<0.6	-	< 5.0
27	Jun-04	NS	NS	NS	NS	NS	NS	—	NS
28	Sep-04	NS	NS	NS	NS	NS	NS	—	NS
29	Dec-04	<50	<50	<0.5	<0.5	<0.5	< 1.0	-	< 2.0
30	Mar-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	-	< 2.0
31	Jun-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	-	< 2.0
32	Sep-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	-	< 2.0

NS = Not Sampled (no surface water present during sampling event)