

RECEIVED

2:12 pm, Jun 10, 2008

Alameda County
Environmental Health

**FOURTH QUARTER 2006
GROUNDWATER MONITORING AND
ANNUAL SUMMARY REPORT**

**REDWOOD REGIONAL PARK
SERVICE YARD
OAKLAND, CALIFORNIA**

Prepared for:

**EAST BAY REGIONAL PARK DISTRICT
OAKLAND, CALIFORNIA**

January 2007

**FOURTH QUARTER 2006
GROUNDWATER MONITORING
AND ANNUAL SUMMARY REPORT**

**REDWOOD REGIONAL PARK
SERVICE YARD
OAKLAND, CALIFORNIA**

Prepared for:

**EAST BAY REGIONAL PARK DISTRICT
OAKLAND, CALIFORNIA**

Prepared by:

**STELLAR ENVIRONMENTAL SOLUTIONS, INC.
2198 SIXTH STREET
BERKELEY, CALIFORNIA 94710**

January 9, 2007

Project No. 2006-17

January 9, 2007

Mr. Jerry Wickham, P.G.
Hazardous Materials Specialist
Local Oversight Program
Alameda County Department of Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, California 94502

Subject: Fourth Quarter 2006 Groundwater Monitoring and Annual Summary Report
Redwood Regional Park Service Yard Site – Oakland, California
Alameda County Environmental Health Fuel Leak Case No. RO0000246

Dear Mr. Wickham:

Attached is the referenced Stellar Environmental Solutions, Inc. report for the underground fuel storage tank (UFST) site at the Redwood Regional Park Service Yard, located at 7867 Redwood Road, Oakland, California. This project is being conducted for the East Bay Regional Park District (EBRPD), and follows previous site investigation and remediation activities (conducted since 1993) associated with former leaking UFSTs. The key regulatory agencies for this investigation are the Alameda County Environmental Health Care Services Agency, Department of Environmental Health; the Regional Water Quality Control Board; and the California Department of Fish and Game.

This report summarizes groundwater and surface monitoring and sampling activities conducted between October 1 and December 31, 2006 (Fourth Quarter 2006). This report also presents an evaluation of hydrochemical trends over the year of monitoring, including an evaluation of the plume extent and stability. In our professional opinion, continued groundwater monitoring is warranted to evaluate plume stability over time. Ongoing bioventing activities are reported in technical submittals separate from the ongoing groundwater and surface water monitoring quarterly reports; salient summary discussions will be included in the quarterly groundwater monitoring reports.

I declare, under penalty of perjury, that the information and/or recommendations contained in the attached document or report is true and correct to the best of my knowledge. If you have any questions regarding this report, please contact Mr. Neal Fujita of the EBRPD, or contact me directly at (510) 644-3123.

Sincerely,



Richard S. Makdisi, R.G., R.E.A.
Principal and Project Manager



cc: Carl Wilcox, California Department of Fish and Game
Neal Fujita, East Bay Regional Park District,
State of California GeoTracker, Alameda County Environmental Health ftp System

TABLE OF CONTENTS

Section	Page
1.0 INTRODUCTION	1
Project Background.....	1
Objectives and Scope of Work	1
Historical Corrective Actions and Investigations	1
Site Description.....	2
Regulatory Oversight	2
2.0 PHYSICAL SETTING	6
Site Lithology.....	6
Hydrogeology	10
3.0 FOURTH QUARTER 2006 ACTIVITIES.....	13
Groundwater Level Monitoring and Sampling	14
Creek Surface Water Sampling.....	15
Bioventing-Related Activities.....	15
4.0 REGULATORY CONSIDERATIONS.....	16
Groundwater Contamination.....	16
Surface Water Contamination.....	16
5.0 FOURTH QUARTER 2006 ANALYTICAL RESULTS.....	18
Groundwater and Surface Water Analytical Results	18
Quality Control Sample Analytical Results.....	19
6.0 EVALUATION OF HYDROCHEMICAL TRENDS AND PLUME STABILITY ..	21
Contaminant Source Assessment.....	21
Water Level Trends.....	22
Hydrochemical Trends.....	22
Plume Geometry and Migration Indications.....	31
Closure Criteria Assessment and Proposed Actions	33

TABLE OF CONTENTS (continued)

Section	Page
7.0 SUMMARY, CONCLUSIONS AND PROPOSED ACTIONS	34
Summary and Conclusions	34
Proposed Actions	36
8.0 REFERENCES AND BIBLIOGRAPHY	37
9.0 LIMITATIONS.....	41

Appendices

Appendix A	Historical Groundwater Monitoring Well Water Level Data
Appendix B	Groundwater Monitoring Field Documentation
Appendix C	Analytical Laboratory Report and Chain-of-Custody Record
Appendix D	Historical Analytical Results and Plume Maps

TABLES AND FIGURES

Tables	Page
Table 1 Groundwater Monitoring Well Construction and Groundwater Elevation Data – December 14, 2006 Monitoring Event Redwood Regional Park Corporation Yard, Oakland, California	14
Table 2 Groundwater and Surface Water Sample Analytical Results – December 14, 2006 Redwood Regional Park Corporation Yard, Oakland, California	19

Figures	Page
Figure 1 Site Location Map.....	3
Figure 2 Site Plan and Historical Sampling Locations.....	4
Figure 3 Geologic Cross-Section Locations.....	7
Figure 4 Geologic Cross-Sections A-A’ through C-C’	8
Figure 5 Geologic Cross-Sections D-D’ through F-F’	9
Figure 6 Groundwater Elevation Map –December 14, 2006	11
Figure 7 Groundwater Analytical Results and Gasoline Plume – December 2006	20
Figure 8 Historical Groundwater Elevations in Key Site Wells	23
Figure 9 Gasoline and Diesel Hydrochemical Trends in Well MW-8	25
Figure 10 Gasoline and Diesel Hydrochemical Trends in Well MW-11	27
Figure 11 Gasoline and Diesel Hydrochemical Trends in Well MW-7	28
Figure 12 Gasoline and Diesel Hydrochemical Trends in Well MW-9	29
Figure 13 Gasoline and Diesel Hydrochemical Trends in Well MW-10	30
Figure 14 Gasoline and Diesel Hydrochemical Trends in Well MW-12	32

1.0 INTRODUCTION

PROJECT BACKGROUND

The subject property is the East Bay Regional Park District (EBRPD) Redwood Regional Park Service Yard located at 7867 Redwood Road in Oakland, Alameda County, California. The site has undergone site investigations and remediation since 1993 to address subsurface contamination caused by leakage from one or both of two former underground fuel storage tanks (UFSTs) that contained gasoline and diesel fuel. The Alameda County Environmental Health Care Services Agency, Department of Environmental Health (Alameda County Environmental Health) has provided regulatory oversight of the investigation since its inception (Alameda County Environmental Health Fuel Leak Case No. RO0000246). Other regulatory agencies with historical involvement in site review include the Regional Water Quality Control Board (Water Board) and the California Department of Fish and Game (CDFG).

OBJECTIVES AND SCOPE OF WORK

This report discusses the following activities conducted/coordinated by Stellar Environmental Solutions, Inc. (SES) between October 1 and December 31, 2006 (Fourth Quarter 2006):

- Collecting water levels in site wells to determine shallow groundwater flow direction;
- Sampling site wells for contaminant analysis and natural attenuation indicators;
- Collecting surface water samples for contaminant analysis;
- Conducting monthly monitoring and maintenance of bioventing system operation; and
- Conducting a microbial respiration test (discussed in Fourth Quarter 2006 bioventing status report).

HISTORICAL CORRECTIVE ACTIONS AND INVESTIGATIONS

Previous SES reports have provided a full discussion of previous site remediation and investigations; site geology and hydrogeology; residual site contamination; conceptual model for contaminant fate and transport; and evaluation of hydrochemical trends and plume stability. Section 7.0 (References and Bibliography) of this report provides a listing of all technical reports for the site. The following is a summary of the general phases of site work:

- In 2000, a Feasibility Study report for the site was submitted to Alameda County Environmental Health. The study provided detailed analyses of the regulatory

implications of site contamination and an assessment of viable corrective actions (SES, 2000d).

- Two instream bioassessment events were conducted in April 1999 and January 2000 to evaluate potential impacts to stream biota associated with the site contamination (no impacts were documented).
- Additional monitoring well installations and corrective action by ORC™ injection proposed by SES were approved by Alameda County Environmental Health in its January 8, 2001 letter to the EBRPD. Two phases of ORC™ injection were conducted—in September 2001 and July 2002.
- A bioventing pilot test was conducted in September and October 2004 to evaluate the feasibility of this corrective action strategy, and the full-scale bioventing system was installed in November and December 2005. Bioventing activities conducted to date have been, and will continue to be, discussed in bioventing-specific technical reports, and updates will be provided in groundwater monitoring progress reports as they relate to this ongoing program.
- On November 30, 2005, groundwater monitoring well MW-4 was properly decommissioned by over-drilling. Well MW-12 was installed adjacent to the location of former well MW-4, as requested by Alameda County Health. Well MW-4 was decommissioned due to its inability to properly recharge, and because it was considered not to be adequately characterizing local groundwater conditions
- A total of 40 groundwater monitoring events have been conducted on a quarterly basis since project inception (November 1994), and a total of 11 groundwater monitoring wells are currently available for monitoring.

SITE DESCRIPTION

Figure 1 shows the location of the project site. The site slopes to the west, from an elevation of approximately 564 feet above mean sea level (amsl) at the eastern edge of the service yard to approximately 530 feet amsl at Redwood Creek, which defines the approximate western edge of the project site with regard to this investigation. Figure 2 shows the site plan.

REGULATORY OVERSIGHT

The lead regulatory agency for the site investigation and remediation is Alameda County Environmental Health (Case No. RO0000246), with oversight provided by the Water Board (State of California GeoTracker Global ID T0600100489). The CDFG is also involved with



3-D TopoQuads Copyright © 1999 DeLorme Yarmouth, ME 04096 Source Data: USGS 750 ft Scale: 1 : 25,000 Detail: 13-0 Datum: WGS84



SITE LOCATION ON U.S.G.S. TOPOGRAPHIC MAP

Redwood Reg. Park Service Yard
Oakland, CA


By: MJC

MARCH 2006

Figure 1



2006-17-01



LEGEND

- BH-20 Exploratory borehole
- MW-1 Groundwater monitoring well
- VW-1 Vent well
- ▲ VMP-1 Vapor monitoring point
- 🌳 Tree

UFST = Underground fuel storage tank

0 25
Scale in feet

SITE PLAN AND WELL LOCATIONS
Redwood Regional Park Service Yard, Oakland, CA

Figure 2

by: MJC

JANUARY 2006

regard to water quality impacts to Redwood Creek. All workplans and reports have been submitted to these agencies. Historical Alameda County Environmental Health-approved revisions to the groundwater sampling program have included:

- Discontinuing hydrochemical sampling and analysis in wells MW-1, MW-3, MW-5, and MW-6;
- Discontinuing creek surface water sampling at upstream location SW-1;
- Discontinuing field measurement and laboratory analyses for natural attenuation indicators, to be re-implemented following the bioventing corrective action; and
- Reducing the frequency of creek surface water sampling from quarterly to semi-annually. The latter recommendation has not yet been implemented due to the EBRPD's continued concern over potential impacts to Redwood Creek.

The site is in compliance with the State Water Resources Control Board's GeoTracker requirements for uploading electronic data and reports. In addition, electronic copies of technical documentation reports published since Q2 2005 have been uploaded to Alameda County Environmental Health's file transfer protocol (ftp) system. Per Alameda County Environmental Health's October 31, 2005 directive entitled "Miscellaneous Administrative Topics and Procedures," effective January 31, 2006, paper copies of reports will no longer be provided to Alameda County Environmental Health.

2.0 PHYSICAL SETTING


This section discusses the site hydrogeologic conditions based on geologic logging and water level measurements collected at the site since September 1993. Previous SES reports have included detailed discussions of site lithologic and hydrogeologic conditions. In May 2004, Alameda County Environmental Health requested, via email, additional evaluation of site lithology—specifically, the preparation of multiple geologic cross-sections parallel to and perpendicular to the contaminant plume’s long axis.

SITE LITHOLOGY


Figure 3 shows the location of geologic cross-sections. Figure 4 shows three sub-parallel geologic cross-sections (A-A’ through C-C’) along the long axis of the groundwater contaminant plume (i.e., along local groundwater flow direction). Figure 5 shows three sub-parallel geologic cross-sections (D-D’ through F-F’) roughly perpendicular to groundwater direction. In each figure, the three sub-parallel sections are presented together for ease of comparison. Due to the small scale, these sections show only lithologic conditions (i.e., soil type and bedrock depth). Additional information on water level depths, historical range of water levels, and inferred thickness of soil contamination were presented in a previous report (SES, 2004c) for cross-section B-B’.

Shallow soil stratigraphy consists of a surficial 3- to 10-foot-thick clayey silt unit underlain by a 5- to 15-foot-thick silty clay unit. In the majority of boreholes, a 5- to 10-foot-thick clayey coarse-grained sand and clayey gravel unit that laterally grades to a clay or silty clay was encountered. This unit overlies a weathered siltstone at the base of the observed soil profile. Soils in the vicinity of MW-1 are inferred to be landslide debris.

A previous SES report (SES, 2004c) presented a bedrock surface isopleth map (elevation contours for the top of the bedrock surface) in the contaminant plume area. That isopleth map and Figures 4 and 5 indicate the following: The bedrock surface slopes steeply, approximately 0.3 feet/foot from east to west (toward Redwood Creek) in the upgradient portion of the site (from the service yard to under the entrance road), then shows a gentle east-to-west slope in the downgradient portion of the site (under the gravel parking area) toward Redwood Creek. This general gradient corresponds to the local groundwater flow direction. On the southern side of the



2005-66-11



GEOLOGIC CROSS SECTIONS — A-A' through C-C'
Redwood Regional Park Service Yard, Oakland, CA

Figure 4

by: MJC

DECEMBER 2005



GEOLOGIC CROSS SECTIONS — D-D' through F-F'
Redwood Regional Park Service Yard, Oakland, CA

Figure 5

by: MJC

DECEMBER 2005

plume area, bedrock slopes gently from south to north (the opposite of the general topographic gradient). Bedrock topography on the northern side of the plume cannot be determined from the available data.

In the central and downgradient portions of the groundwater contaminant plume (under the entrance road and the parking area), the bedrock surface has local, fairly steep elevation highs and lows, expressing a hummocky surface. Bedrock elevations vary by up to 10 feet over distances of less than 20 feet in this area. Local bedrock elevation highs are observed at upgradient location BH-13 (see cross-section F-F') and at downgradient location B15/HP-02 (see cross-section B-B'). Intervening elevation lows create troughs that trend north-south in the central portion of the plume and east-west in the downgradient portion of the plume.


The bedrock surface (and overlying unconsolidated sediment lithology) suggests that the bedrock surface may have at one time undergone channel erosion from a paleostream(s) flowing sub-parallel to present-day Redwood Creek. Because groundwater flows in the unconsolidated sediments that directly overlie the bedrock surface, it is likely that the hummocky bedrock surface affects local groundwater depth and flow direction. This is an important hydrogeologic control that should be considered if groundwater-specific corrective action is contemplated.

HYDROGEOLOGY

Groundwater at the site occurs under unconfined and semi-confined conditions, generally within the clayey, silty, sand-gravel zone. The top of this zone varies between approximately 12 and 19 feet below ground surface (bgs); the bottom of the water-bearing zone (approximately 25 to 28 feet bgs) corresponds to the top of the siltstone bedrock unit. Seasonal fluctuations in groundwater depth create a capillary fringe of several feet that is saturated in the rainy period (late fall through early spring) and unsaturated during the remainder of the year. The thickness of the saturated zone plus the capillary fringe varies between approximately 10 and 15 feet in the area of contamination. Local perched water zones have been observed well above the top of the capillary fringe. Consistent with the bedrock isopleth map showing an elevation depression in the vicinity of MW-11, historical groundwater elevations in MW-11 are sporadically lower than in the surrounding area. As discussed in the previous subsection, local groundwater flow direction likely is more variable than expressed by groundwater monitoring well data, due to local variations in bedrock surface topography.

Figure 6 is a groundwater elevation map constructed from the current event monitoring well equilibrated water levels. Table 1 (in Section 3.0) summarizes current event groundwater elevation data. Appendix A contains historical groundwater elevation data.

In the upgradient portion of the site (between well MW-1 and MW-2, in landslide debris and the former UFST excavation backfill), the groundwater gradient is approximately 0.25 foot per foot.



GROUNDWATER ELEVATION MAP-DECEMBER 14, 2006
Redwood Regional Park Service Yard, Oakland, CA

Figure 6

by: MJC DECEMBER 2006

2006-17-09



Downgradient from (west of) the UFST source area (between MW-2 and Redwood Creek), the groundwater gradient is approximately 0.11 foot per foot. The average groundwater elevation was 0.6 feet lower than the previous (October 2006) event, with the greatest lowering of 2.5 feet measured in MW-3 and a slight increase of 0.4 feet in MW-7. The smallest changes in groundwater elevations are observed in wells nearest to Redwood Creek. The direction of shallow groundwater flow during the current event was to the west-southwest (toward Redwood Creek), which is consistent with historical site groundwater flow direction.

We assume a site groundwater velocity of 7 to 10 feet per year using general look-up tables for permeability characteristics for the site-specific lithologic data obtained from site investigations. This velocity estimate is conservatively low, but does meet minimum-distance-traveled criteria from the date when contamination was first observed in Redwood Creek (1993) relative to the time of the UST installations (late 1970s). Locally, however, the groundwater velocity could vary significantly. Calculating the specific hydraulic conductivity critical to accurately estimating site-specific groundwater velocity would require direct testing of the water-bearing zone through a slug or pumping test.

Redwood Creek, which borders the site to the west, is a seasonal creek known for the occurrence of rainbow trout. Creek flow in the vicinity of the site shows significant seasonal variation, with little to no flow during the summer and fall dry season, and vigorous flow with depths exceeding 1 foot during the winter and spring wet season. The creek is a gaining stream (i.e., it is recharged by groundwater seeps and springs) in the vicinity of the site, and discharges into Upper San Leandro Reservoir located approximately 1 mile southeast of the site. During low-flow conditions, the groundwater table is below the creek bed in most locations (including the area of historical contaminated groundwater discharge); consequently, there is little to no observable creek flow at these times.

3.0 FOURTH QUARTER 2006 ACTIVITIES

This section presents the creek surface water and groundwater sampling and analytical methods for the most recent groundwater monitoring event (Q4 2006), conducted in December 2006. A summary of bioventing-related activities is also provided.

Groundwater and surface water analytical results are summarized in Section 5.0. Monitoring and sampling protocols were in accordance with the Alameda County Environmental Health-approved SES technical workplan (SES, 1998a). Current Q4 2006 event activities included:

- Measuring static water levels in all 11 of the site wells.
- Collecting post-purge groundwater samples for laboratory analysis of site contaminants from wells located within (or potentially within) the groundwater plume (MW-2, MW-7, MW-8, MW-9, MW-10, MW-11, and MW-12).
- Collecting Redwood Creek surface water samples for laboratory analysis from locations SW-2 and SW-3.
- Conducting a respiration test to assess the degree of microbial biodegradation activity at the site (discussed in Quarterly bioventing status reports).

Redwood Creek surface water sampling and groundwater monitoring and sampling were conducted on December 14, 2006. The locations of all site monitoring wells and creek water sampling locations are shown on Figure 2 (in Section 1.0). Well construction information and water level data are summarized in Table 1. Appendix B contains the groundwater monitoring field records for the current event.

Because it appears that the previously-injected ORC™ has been depleted, continued monitoring of the natural attenuation parameters—dissolved oxygen (DO), oxidation-reduction potential (ORP), nitrate, ferrous iron, and sulfate—is of marginal value until such time as additional corrective actions that would increase oxygen concentrations (e.g., bioventing) are implemented. Therefore, monitoring for natural attenuation parameters was discontinued following the Q3 2004 event.

Table 1
Groundwater Monitoring Well Construction and Groundwater Elevation Data –
December 14, 2006 Monitoring Event
Redwood Regional Park Corporation Yard, Oakland, California

Well	Well Depth	Screened Interval	TOC Elevation	Groundwater Elevation (12/14/06)
MW-1	18	7 to 17	565.83	562.87
MW-2	36	20 to 35	566.42	544.23
MW-3	42	7 to 41	560.81	541.51
MW-5	26	10 to 25	547.41	531.10
MW-6	26	10 to 25	545.43	532.33
MW-7	24	9 to 24	547.56	534.71
MW-8	23	8 to 23	549.13	536.65
MW-9	26	11 to 26	549.28	533.97
MW-10	26	11 to 26	547.22	534.83
MW-11	26	11 to 26	547.75	535.23
MW-12	25	10 to 25	544.67	535.04

Notes:

TOC = Top of casing.

Wells MW-1 through MW-6 are 4-inch diameter; all other wells are 2-inch diameter.

All elevations are feet above U.S. Geological Survey mean sea level.

GROUNDWATER LEVEL MONITORING AND SAMPLING

Groundwater monitoring well water level measurements, purging, sampling, and field analyses were conducted by Blaine Tech Services under the supervision of SES personnel. Groundwater sampling was conducted in accordance with State of California guidelines for sampling dissolved analytes in groundwater associated with leaking UFSTs (State Water Resources Control Board, 1989), and followed the methods and protocols approved by Alameda County Environmental Health in the SES 1998 workplan (SES, 1998a).

As the first task of the monitoring event, static water levels were measured using an electric water level indicator. The wells to be sampled for contaminant analyses were then purged (by bailing and/or pumping) of three wetted casing volumes. Aquifer stability parameters (temperature, pH, electrical conductivity, and turbidity) were measured after each purged casing volume to ensure that representative formation water would be sampled. To minimize the

potential for cross-contamination, wells were purged and sampled in order of increasing contamination (based on the analytical results of the previous quarter).

The sampling-derived purge water and decontamination rinseate (approximately 50 gallons) from the current event was containerized in the onsite plastic tank. Purge water from future events will continue to be accumulated in the onsite tank until it is full, at which time the water will be transported offsite for proper disposal.

CREEK SURFACE WATER SAMPLING

Surface water sampling was conducted by SES personnel on December 14, 2006. Surface water samples were collected from Redwood Creek location SW-2 (immediately downgradient of the former UFST source area and within the area of documented creek bank soil contamination), and SW-3 (approximately 500 feet downstream of the SW-2 location). In accordance with a previous SES recommendation approved by the Alameda County Environmental Health, upstream sample location SW-1 is no longer part of the surface water sampling program.

At the time of sampling, the creek was at a low stage—water depths ranged from approximately 0.5 to 1 foot, with a slow flow. At the SW-2 location, where contaminated groundwater discharge to the creek historically has been observed, an orange algae was seen growing on the saturated portion of the creek bank. This algae likely is utilizing the petroleum as a carbon source, and therefore is a good indicator of the presence of petroleum contamination. During the Q4 creek sampling, a diesel odor was detected at creek level, and a petroleum sheen was visible on the creek bank.

BIOVENTING-RELATED ACTIVITIES

The bioventing system was installed and started up in December 2005/January 2006. Monthly bioventing system operations and maintenance (O&M) events have been conducted since February 2006. A respiration test to evaluate the degree of microbial biodegradation activity at the site was conducted from October 31 to November 2, 2006. Bioventing activities are discussed in detail in separate technical documents.

4.0 REGULATORY CONSIDERATIONS

This chapter summarizes the regulatory considerations regarding surface water and groundwater contamination. There are no Alameda County Environmental Health or Water Board cleanup orders for the site, although all site work has been conducted under oversight of these agencies.

GROUNDWATER CONTAMINATION

As specified in the Water Board's San Francisco Bay Region Water Quality Control Plan (Regional Water Quality Control Board, 1986), all groundwater are considered potential sources of drinking water unless otherwise approved by the Water Board, and are also assumed to ultimately discharge to a surface water body and potentially impact aquatic organisms. While it is likely that site groundwater would satisfy geology-related criteria for exclusion as a drinking water source (excessive total dissolved solids and/or insufficient sustained yield), Water Board approval for this exclusion has not been obtained for the site. As summarized in Table 2 (in Section 5.0), site groundwater contaminant levels are compared to two sets of criteria: 1) Water Board Tier 1 Environmental Screening Levels (ESLs) for sites where groundwater is a current or potential drinking water source; and 2) ESLs for sites where groundwater is not a current or potential drinking water source.

As stipulated in the ESL document (Water Board, 2005), the ESLs are not cleanup criteria; rather, they are conservative screening-level criteria designed to be protective of both drinking water resources and aquatic environments in general. The groundwater ESLs are composed of multiple components, including ceiling value, human toxicity, indoor air impacts, and aquatic life protection. Exceedance of ESLs suggests that additional investigation and/or remediation is warranted. While drinking water standards [e.g., Maximum Contaminant Levels (MCLs)] are published for the site contaminants of concern, Alameda County Environmental Health has indicated that impacts to nearby Redwood Creek are of primary importance, and that site target cleanup standards should be evaluated primarily in the context of surface water quality criteria.

SURFACE WATER CONTAMINATION

As summarized in Table 2 (in Section 5.0), site surface water contaminant levels are compared to the most stringent screening level criteria published by the State of California, U.S. Environmental Protection Agency, and U.S. Department of Energy. These screening criteria address chronic and acute exposures to aquatic life. As discussed in the ESL document (Water

Board, 2005), benthic communities at the groundwater/surface water interface (e.g., at site groundwater discharge location SW-2) are assumed to be exposed to the full concentration of groundwater contamination prior to dilution/mixing with the surface water). This was also a fundamental assumption in the instream benthic macroinvertebrate bioassessment events, which documented no measurable impacts.

Historical surface water sampling in the immediate vicinity of contaminated groundwater discharge (SW-2) has sporadically documented petroleum contamination, usually in periods of low stream flow, and generally at concentrations several orders of magnitude less than adjacent (within 20 feet) groundwater monitoring well concentrations. It is likely that mixing/dilution between groundwater and surface water precludes obtaining an “instantaneous discharge” surface water sample that is wholly representative of groundwater contamination at the discharge location. Therefore, the most conservative assumption is that surface water contamination at the groundwater/surface water interface is equivalent to the upgradient groundwater contamination (e.g., site downgradient wells MW-7, MW-9, and MW-12).

While site target cleanup standards for groundwater have not been determined, it is likely that no further action will be required by regulatory agencies when groundwater (and surface water) contaminant concentrations are all below their respective screening level criteria. Residual contaminant concentrations in excess of screening level criteria might be acceptable to regulatory agencies if a more detailed risk assessment (e.g., Tier 2 and/or Tier 3) demonstrates that no significant impacts are likely.

5.0 FOURTH QUARTER 2006 ANALYTICAL RESULTS

This section presents the field and laboratory analytical results of the most recent monitoring event. Table 2 summarizes the contaminant analytical results of the current monitoring event. Figure 7 shows the current event contaminant analytical results and the inferred limits of the gasoline groundwater plume. Appendix C contains the certified analytical laboratory report and chain-of-custody record for the current event. Appendix D contains a summary of historical groundwater and surface analytical results.

GROUNDWATER AND SURFACE WATER ANALYTICAL RESULTS

Fourth Quarter 2006 site groundwater contaminant concentrations in wells MW-7, MW-8, MW-9 and MW-11 exceed their respective groundwater ESLs for total volatile hydrocarbons as gasoline (TVH_g), total extractable hydrocarbons as diesel (TEH_d), benzene, ethylbenzene, and total xylenes under the *drinking water resource is threatened* criterion and under the *drinking water resource is not threatened* criterion. MW-2 also exceeded the ESL for benzene and methyl tertiary-butyl ether (MTBE) under the *drinking water resource is threatened* criterion. The ESLs for TVH_g was exceeded in MW-12 under the *drinking water resource is threatened* criterion and exceeded for TEH_d under the *drinking water resource is not threatened* criterion. Maximum groundwater contaminant concentrations also exceeded all surface water screening levels. Contaminant concentrations below their respective ESLs were detected in the following wells: MW-10 (benzene, ethylbenzene, and MTBE); MW-12 (ethylbenzene and total xylenes); and MW-8 and MW-9 (toluene).

The maximum groundwater contaminant concentrations were detected in well MW-9 (located in the downgradient area of the plume approximately 30 feet from Redwood creek) that was also the historical maximum concentrations of total petroleum hydrocarbons as gasoline (TPH_g) and total petroleum hydrocarbons as diesel (TPH_d) in this well. The northern edge of the plume in the downgradient area of the plume is defined by well MW-12. The southern edge of the plume in the downgradient area is not strictly defined; however, based on historical groundwater data, it appears to be located between well MW-9 and well MW-5. The current event contaminant plume geometry is consistent with recent historical contaminant distribution, showing the center of contaminant mass in groundwater located downgradient of the former source area.

Surface water samples SW-2 and SW-3 showed no detectable contaminant concentrations, except for a trace of ethylbenzene in SW-2.

Table 2
Groundwater and Surface Water Sample
Analytical Results – December 14, 2006
Redwood Regional Park Corporation Yard, Oakland, California

Location	Contaminant						
	TVHg	TEHd	Benzene	Toluene	Ethyl- benzene	Total Xylenes	MTBE
GROUNDWATER SAMPLES							
MW-2	<50	<50	2.1	<0.5	<0.5	<0.5	16
MW-7	7,300	2,400	50	<0.5	220	41.8	<2.0
MW-8	4,400	800	75	4.2	320	246	<2.0
MW-9	12,000	2,800	140	9.4	880	634	<10
MW-10	<50	<50	0.61	<0.5	0.55	<0.5	3.7
MW-11	6,000	3,500	83	<1.0	260	16.4	<4.0
MW-12	770	230	<0.5	<0.5	7.4	1.95	<2.0
Groundwater ESLs ^(a)	100 / 500	100 / 640	1.0 / 46	40 / 130	30 / 290	13 / 13	5.0 / 1,800
REDWOOD CREEK SURFACE WATER SAMPLES							
SW-2	<50	<50	<0.5	<0.5	0.81	<0.5	<2.0
SW-3	<50	<50	<0.5	<0.5	<0.5	<0.5	<2.0
Surface Water Screening Levels ^(a, b)	500	100	46	130	290	13	8,000

Notes:

^(a) Water Board Environmental Screening Levels (drinking water resource threatened/not threatened) (Water Board, 2005).

^(b) Lowest of chronic and acute surface water criteria published by the State of California, U.S. Environmental Protection Agency, or U.S. Department of Energy.

MTBE = methyl *tertiary*-butyl ether

TEHd = total extractable hydrocarbons - diesel range


TVHg = total volatile hydrocarbons - gasoline range

All concentrations expressed in µg/L (equivalent to parts per billion).

Samples in **bold-face type** exceed the ESL and/or surface water screening levels.

QUALITY CONTROL SAMPLE ANALYTICAL RESULTS

Laboratory quality control (QC) samples (e.g., method blanks, matrix spikes, surrogate spikes) were analyzed by the laboratory in accordance with requirements of each analytical method. All laboratory QC sample results and sample holding times were within the acceptance limits of the methods (see Appendix C).



2006-17-10

6.0 EVALUATION OF HYDROCHEMICAL TRENDS AND PLUME STABILITY

This section evaluates the observed hydrochemical trends with regard to plume stability and migration of the center of contaminant mass toward Redwood Creek. An assessment is made as to the nature of residual contaminated soil that acts as a continued source of groundwater contamination. A conceptual model (incorporating site lithology, hydrogeology, and hydro-chemistry) is presented to explain the spatial extent and magnitude of the dissolved hydrocarbon plume.

CONTAMINANT SOURCE ASSESSMENT

Site UFSTs were removed (i.e., discharge was discontinued) in 1993, and some but not all of the source area excavation contaminated soil was removed. Borehole soil sampling has provided data on the extent and magnitude of soil contamination in the vicinity of the former UFSTs (“source area”) and the outlying area (in the capillary fringe above the groundwater plume). Soil contamination is constrained to the unsaturated zone and the underlying saturated sediments on the weathered bedrock surface.

A large mass of residual TPH contamination in the unsaturated zone overlies the contaminant plume, primarily in the area between the former UFSTs and the park entrance roadway, with the contaminated zone thinning toward Redwood Creek. Seasonal desorption of contamination in this unsaturated zone occurs during the rainy season and during high-water periods, acting as a long-term source of dissolved contamination. Previous ORC™ injection programs—which resulted in permanent reductions at the peripheral plume margins, but were followed by rebound (to pre-injection conditions) within the central portions of the plume—indicate that site conditions support aerobic biodegradation. However, biodegradation is limited by oxygen deficiency in the unsaturated zone.

Based on this conceptual model—and using conservative assumptions for equilibrium partitioning, contaminant geometry, soil moisture, and previous laboratory analytical results for TPH in soil—estimates of TPH mass in soil were calculated. Residual TPH in vadose zone soil is estimated at 1,400 to 7,000 pounds (100 to 600 gallons of gasoline), compared to a mass of TPH in groundwater estimated at 1 to 10 pounds (0.1 to 1.0 gallon of gasoline).

Soil and groundwater contamination distribution and site lithologic and hydrogeologic conditions have shown that residual soil contamination will continue to be a source of long-term groundwater contamination via seasonal desorption and migration, unless abated.

WATER LEVEL TRENDS

Appendix D contains historical groundwater elevation data and flow direction maps. Figure 8 shows a trendline of site groundwater elevations in key wells (those within the contaminant plume). The data support the following conclusions:

- Groundwater elevations at all site wells have shown a seasonal fluctuation of 1.5 feet to 6.6 feet, with an average elevation change in individual wells of 3.9 feet. Wells within the plume have shown a similar range.
- In all wells, lowest elevations have generally been observed during the end of the dry season and highest elevations at the peak of the rainy season. This is a common seasonal trend observed in the upper water-bearing zone in the Bay Area.
- Groundwater elevation trends and magnitudes are similar between wells.
- Overall groundwater flow direction is consistently to the west-southwest (toward Redwood Creek). Localized (on the scale of tens of feet) groundwater flow direction appears to vary within the general flow direction, likely controlled by bedrock surface topography.
- Historical groundwater gradient is consistently approximately 0.1 feet/foot in the area of the contaminant plume.


HYDROCHEMICAL TRENDS

Contaminant concentrations in an individual well can fluctuate over time for one or more reasons—contaminant migration, seasonal effects due to fluctuating groundwater levels (i.e., desorption from the unsaturated zone and/or dilution of saturated zone contamination), and/or natural attenuation (plus enhancement by active remediation such as ORC™ injection and bioventing). These hydrochemical trends can result in changes in the lateral extent and magnitude of a dissolved contaminant plume.

The most consistent trend over time in those wells within the centerline of the plume has been a seasonal influence of desorption following the winter rains, with a resultant increase in concentration of the dissolved hydrocarbon in the groundwater.

Because the quarter-to-quarter comparisons can be unduly influenced by seasonal effects that mask longer trends, it is useful to compare same-season data over time to determine if

**Figure 8: Historical Groundwater Elevations in Site Wells
Redwood Regional Park Service Yard - Oakland, California**



concentrations are increasing, decreasing, or remaining stable. Our evaluation of hydrochemical trends focuses on gasoline and diesel, which, when combined, represent the majority of contaminant mass. To more closely evaluate plume stability differences, the following discussion focuses on four separate portions of the plume relative to the long axis (along the hydraulic gradient): “upgradient” (trailing edge of plume); “mid-plume”; “downgradient”; and “plume fringe.”

Important components of plume stability include: degree of contaminant fluctuations in individual wells over time; changes in the lateral extent of the plume; and changes in the location of the center of contaminant mass within the plume. Historical gasoline isoconcentration contour maps in Appendix A are presented to show temporal changes in plume lateral extent and center of contaminant mass, which are discussed below.


In general, the contaminant plume has disconnected from the source such that recent historical downgradient concentrations are higher than upgradient (near the source) concentrations. To evaluate plume stability with regard to changes in the center of contaminant mass, we evaluated concentrations of TPH (gasoline and diesel combined) in individual wells over time. The data show no obvious correlation between maximum TPH concentrations and well location, suggesting high plume instability. Since January 2001, maximum TPH concentrations have been variously detected in upgradient, mid-plume, and downgradient wells. These variations are likely due in large part to differing contaminant mass in unsaturated zone soils at particular locations, resulting in variable amounts of desorbed mass to the plume during high water conditions. The following discusses hydrochemical trends in each of the upgradient, mid-plume, and downgradient portions of the site, as well as the fringes of the plume.

Upgradient Hydrochemical Trends

Well MW-2, installed in the area of the former UFSTs, historically has shown relatively low (sometimes non-detectable) contaminant levels. Well MW-8, located approximately 60 feet downgradient of MW-2, historically has shown much higher concentrations. These data suggest that the plume has become disconnected from the former source area near MW-2, and that the center of contaminant mass has moved downgradient, with significant contaminant mass entrained in the soil that continues to “feed” the dissolved concentration represented by MW-8 (the first well downgradient of MW-2 along the inferred centerline of the plume).

Figure 9 shows hydrochemical trends for gasoline and diesel in MW-8. Both gasoline and diesel concentrations have fluctuated widely, but follow a well established seasonal fluctuation pattern. The strong seasonal effect is visually apparent, with annual maximum concentrations generally occurring in late winter/early spring (usually the March event), and annual minimum

**Figure 9: Gasoline and Diesel Hydrochemical Trends: Well MW-8
Redwood Regional Park Service Yard, Oakland, California**



concentrations generally occurring in the fall/winter (usually the September or December events). Figure 9 trends show a strong correlation with the seasonal hydrologic trends shown in Figure 8. Neither contaminant has shown an overall reducing concentration trend (i.e., annual maxima and minima are approximately the same over the previous 3 years).

In the previous four March events (high water conditions), MW-8 has shown sitewide maxima (or near maxima) for gasoline, benzene, and MTBE. Maximum concentrations in other events have been in other wells. Current (December 2006) TPHg and TPHd concentrations in MW-8 are below their historical maxima, and have been between the historical maxima and minima over the past 3 years.

Mid-Plume Trends

Well MW-11 is located along the plume centerline, approximately midway between upgradient well MW-8 and downgradient well MW-7. Figure 10 shows hydrochemical trends for gasoline and diesel for this well. Gasoline and diesel concentrations showed a large reduction in 2001, followed by an equally large increase by late 2002. Since that time, concentrations have fluctuated widely, with a strong seasonal effect. Both diesel and gasoline concentrations in this well have shown a generally reducing trend over the past year. Current (December 2006) TPHg and TPHd concentrations in MW-11 are below their historical maximum.

Downgradient Hydrochemical Trends

Wells MW-7 and MW-9 represent the high-concentration centerline of the plume at the downgradient area approximately 20 feet from Redwood Creek.


Figure 11 shows hydrochemical trends for gasoline and diesel for MW-7. Gasoline has shown strong fluctuations in concentration but a downward trend. Current diesel concentration is between the historical maximum and minimum.

Figure 12 shows hydrochemical trends for gasoline and diesel for MW-9. Current (December 2006) and September 2006 have been historical maximums in gasoline concentration in MW-9. These data suggest that the plume has become disconnected from the former source area near MW-2, and that the center of contaminant mass has moved downgradient.


Plume Fringe Zone Trends

Well MW-10 is located on the southern edge of the plume, in the mid-plume portion relative to the longitudinal axis. Figure 13 shows hydrochemical trends for gasoline and diesel for this well. Concentrations of both gasoline and diesel showed a sharp reduction between the August


**Figure 10: Gasoline and Diesel Hydrochemical Trends: Well MW-11
Redwood Regional Park Service Yard, Oakland, California**




**Figure 11: Gasoline and Diesel Hydrochemical Trends: Well MW-7
Redwood Regional Park Service Yard, Oakland, California**



**Figure 12: TPH-gasoline and TPH-diesel Hydrochemical Trends: Well MW-9
Redwood Regional Park Service Yard, Oakland, California**



**Figure 13: Gasoline and Diesel Hydrochemical Trends: Well MW-10
Redwood Regional Park Service Yard, Oakland, California**



and December 2001 events (following the first ORC™ injection phase). Since that time, gasoline has been detected at or below approximately 160 micrograms per liter (µg/L), and diesel has been detected above 100 µg/L only once.

Well MW-4 was located on the northern edge of the plume, just upgradient of Redwood Creek. Other than an apparent anomalous diesel detection in June 2004, no contamination had been detected in this well since December 2001. Due to poor recharge in this well, the well was destroyed in November 2005 and replaced by well MW-12 (which was located in an adjacent position). The initial sampling of MW-12 shows elevated petroleum concentrations up to 1,300 µg/L, but has since generally been on the decline. Figure 14 shows hydrochemical trends for gasoline and diesel for this well.

As of the most recent groundwater monitoring event, over 4 years have passed since the second phase of ORC™ injection. This is well beyond the useful life of injected ORC™ (generally 6 to 9 months), and the data reflect that the previously-injected ORC™ is no longer substantially contributing to contamination reduction.


PLUME GEOMETRY AND MIGRATION INDICATIONS

As discussed in detail in Section 4.0, the plume of groundwater contamination above screening levels appears to be approximately 120 feet long and approximately 50 feet wide. The zone of greatest contamination fluctuates between the mid-portion of the plume (near MW-8) and the downgradient portion of the plume (at MW-7 and MW-9).

As shown on the historical plume contour maps in Appendix A, the plume geometry has not varied substantially over the past 4 years of monitoring, although seasonal fluctuations in contaminant concentrations have been observed. This is exhibited by higher concentrations in downgradient wells in some events, and in mid-plume or upgradient wells in other events.

Over the past 2 years, maximum sitewide contaminant concentrations have remained approximately the same, including at downgradient wells, suggesting that “worst-case” groundwater contaminant concentrations have been reached across the lateral extent of the plume.

**Figure 14: Gasoline and Diesel Hydrochemical Trends: Well MW-12
Redwood Regional Park Service Yard, Oakland, California**



CLOSURE CRITERIA ASSESSMENT AND PROPOSED ACTIONS

The Water Board and Alameda County Health generally require that the following criteria be met before issuing regulatory closure of contaminant cases:

1. ***The contaminant source has been removed (i.e., the source of the discharge and obviously-contaminated soil).*** This criterion has not been fully met. While the UFSTs have been removed, borehole soil sampling has shown a substantial mass of residual source area soil contamination that will act as an ongoing source of groundwater contamination. As discussed below, a soil bioventing system has been installed as a corrective action to reduce contaminant mass. The bioventing system began operating in December 2005.
2. ***The groundwater contaminant plume is well characterized, and is stable or reducing in magnitude and extent.*** As discussed above, in our professional opinion, this criterion has not been met, and continued groundwater monitoring will be needed to demonstrate plume stability.
3. ***If residual contamination (soil or groundwater) exists, there is no reasonable risk to sensitive receptors (i.e., contaminant discharge to surface water or water supply wells) or to site occupants.*** This criterion is generally met by conducting a Risk-Based Corrective Action assessment that models the fate and transport of residual contamination in the context of potential impacts to sensitive receptors (e.g., water wells, residential land use). For this site, Redwood Creek is considered the primary sensitive receptor. The proposed corrective action is designed specifically to reduce the magnitude and duration of future contaminated groundwater discharge to Redwood Creek.

7.0 SUMMARY, CONCLUSIONS AND PROPOSED ACTIONS

The following conclusions and proposed actions are based on the findings of the current event activities, as well as on salient historical data.

SUMMARY AND CONCLUSIONS

- Groundwater sampling has been conducted on an approximately quarterly basis since November 1994 (40 events in the initial site wells). A total of 11 site wells are available for monitoring; 7 of the available wells are currently monitored for contamination.
- Site contaminants of concern include gasoline, diesel, BTEX, and MTBE. Current groundwater concentrations exceed regulatory screening levels for groundwater and surface water.
- The primary environmental risk is discharge of contaminated groundwater to the adjacent Redwood Creek. A stream bioassessment concluded that there were no direct impacts to the surface water benthic community; however, groundwater contamination is sporadically detected in surface water samples, and there is historical visual evidence of plume discharge at the creek/groundwater interface. Surface water samples have sporadically exceeded surface water ESL criteria for gasoline, diesel, and benzene, and generally only under low creek flow conditions. An in-stream bioassessment evaluation conducted in 1999 to 2000 determined that there were no impacts to the benthic macroinvertebrate community.
- The existing well layout adequately constrains the lateral extent of groundwater contamination, and the vertical limit is very likely the top of the near-surface (25 to 28 feet) siltstone bedrock. The saturated interval extends approximately 12 to 15 feet from top of bedrock through the capillary fringe. Groundwater elevations fluctuate seasonally, creating a capillary fringe that varies seasonally in thickness.
- The groundwater contaminant plume has become disconnected from its original source, but continues to be fed from the residual hydrocarbon concentrations in the soil. The groundwater plume has migrated well beyond the former source area (represented by well MW-2) toward Redwood Creek. The plume of groundwater contamination above screening levels appears to be approximately 100 feet long and approximately 40 feet wide. The zone of greatest contamination (greater than 10,000 µg/L of TVHg) is currently an approximately 10-foot-wide by 20-foot-long area centered around well

MW-9, which has also been the historical maximum gasoline concentration in this well for the past two events.

- The contaminant plume is neither stable nor reducing, as groundwater contaminant concentrations fluctuate seasonally, and the center of mass of the contaminant plume (represented by maximum concentrations) has alternated between mid-plume and downgradient wells in recent history. Recent groundwater contaminant concentrations are below site historical maxima, and there is no indication that maximum site groundwater concentrations are increasing, which suggests that “worst case” contaminant concentrations may have been reached.
- A two-phase ORC™ injection corrective action program was implemented at the site. In September 2001, approximately 3,000 pounds of ORC™ was injected into 44 boreholes over a 4,400-square foot area of the maximum groundwater contamination. In June 2002, approximately 1,000 pounds of ORC™ was injected in 30 boreholes over a smaller area that showed residual high contaminant concentrations following the initial injection phase. The ORC™ was injected over the full saturated interval (including the capillary fringe). The findings indicate that the corrective action was partially effective in reducing the lateral extent of the groundwater contaminant plume; however, initial contaminant reductions were followed by rebounding to pre-injection concentrations. The data suggest that site conditions support aerobic biodegradation when not limited by oxygen concentrations, notably on the plume margins and upgradient former source area, but not along the centerline of the contaminant plume.
- A September 2003 exploratory borehole program confirmed that sorbed-phase contamination in the seasonally-unsaturated zone is a primary source of long-term contaminant contribution to the groundwater plume. Reduction/removal of this contamination will be necessary to eliminate continued discharge of contaminated groundwater to Redwood Creek and ultimately obtain site closure.
- Soil bioventing is a proven technology for contaminant mass removal in the unsaturated zone, under conditions similar to the site, and appears to be the most appropriate corrective action strategy giving consideration to technical, cost, safety, and aesthetic issues. A 2- to 3-year program of bioventing likely will reduce unsaturated zone contamination such that it will no longer be a long-term source of contamination to groundwater. A full-scale bioventing system was installed in November/December 2005, and began operating in December 2005.
- Respiration test results conducted from October to November 2006 indicate that moderate microbial biodegradation of site contaminants is occurring. The microbial activity should increase with less pronounced recharge from rainfall (discussed in quarterly bioventing status reports).

PROPOSED ACTIONS

The EBRPD proposes to implement the following actions to address regulatory concerns:

- Continue the quarterly program of creek and groundwater sampling and reporting.
- Continue to inform regulators of site progress and seek their concurrence with proposed actions.
- Operate the bioventing system as a corrective action to move the site toward closure, and report those results in bioventing-specific technical reports.
- Conduct another in-situ respiration test to assess oxygenation and microbial activity in the contaminated zone.
- Continue to evaluate analytical results (and bioventing contaminant removal data) in the context of hydrochemical trends, impacts of groundwater contamination on Redwood Creek, and effectiveness of the corrective action.
- Continue to make required Electronic Data Format uploads to the State of California GeoTracker database, and upload an electronic copy of technical reports to Alameda County Environmental Health's ftp system.

8.0 REFERENCES AND BIBLIOGRAPHY

- Parsons Engineering Science (Parsons), 1998. Quarterly Progress Report 11, Redwood Regional Park Service Yard, Oakland, California. January 28.
- Parsons Engineering Science (Parsons), 1997a. Quarterly Progress Report 7, Redwood Regional Park Service Yard, Oakland, California. January 31.
- Parsons Engineering Science (Parsons), 1997b. Quarterly Progress Report 8 and Annual Summary Assessment, Redwood Regional Park Service Yard, Oakland, California. April 4.
- Parsons Engineering Science (Parsons), 1997c. Quarterly Progress Report 9, Redwood Regional Park Service Yard, Oakland, California. June 30.
- Parsons Engineering Science (Parsons), 1997d. Quarterly Progress Report 10, Redwood Regional Park Service Yard, Oakland, California. September 22.
- Parsons Engineering Science (Parsons), 1996a. Quarterly Progress Report 5, Redwood Regional Park Service Yard, Oakland, California. June 6.
- Parsons Engineering Science (Parsons), 1996b. Quarterly Progress Report 6, Redwood Regional Park Service Yard, Oakland, California. September 24.
- Parsons Engineering Science (Parsons), 1995a. Quarterly Progress Report 2, Redwood Regional Park Service Yard, Oakland, California. March 8.
- Parsons Engineering Science (Parsons), 1995b. Quarterly Progress Report 3, Redwood Regional Park Service Yard, Oakland, California. June 23.
- Parsons Engineering Science (Parsons), 1995c. Quarterly Progress Report 4 and Annual Summary Assessment (November 1994 - August 1995), Redwood Regional Park Service Yard, Oakland, California. November 13.
- Parsons Engineering Science (Parsons), 1994a. Creek and Soil Sampling at Redwood Regional Park, Oakland, California. March 2.

- Parsons Engineering Science (Parsons), 1994b. Creek Surface Water at Redwood Regional Park, Oakland, California. May 13.
- Parsons Engineering Science (Parsons), 1994c. Workplan for Groundwater Characterization Program at East Bay Regional Park Service Yard, Oakland, California. August 17.
- Parsons Engineering Science (Parsons), 1994d. Quarterly Progress Report 1, Redwood Regional Park Service Yard, Oakland, California. December 28.
- Parsons Engineering Science (Parsons), 1993a. Closure of Underground Fuel Storage Tanks and Initial Site Characterization at Redwood Regional Park Service Yard, Oakland, California. December 16.
- Parsons Engineering Science (Parsons), 1993b. Workplan for Site Characterization at East Bay Regional Park District, Redwood Regional Park Corporation Yard, Oakland, Alameda County, California. September 3.
- Regional Water Quality Control Board, San Francisco Bay Region (Water Board), 2005. Screening for Environmental Concerns at Sites with Contaminated Soil and Groundwater.
- Regional Water Quality Control Board, San Francisco Bay Region (Water Board), 1995. San Francisco Bay Region Water Quality Control Plan.
- State Water Resources Control Board, 1989. Leaking Underground Fuel Tank Field Manual: Guidelines for Site Assessment, Cleanup, and Underground Storage Tank Closure. State of California Leaking Underground Fuel Tank Task Force. October.
- Stellar Environmental Solutions, Inc. (SES), 2006a. Fourth Quarter 2005 Groundwater Monitoring and Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 20.
- Stellar Environmental Solutions, Inc. (SES), 2006b. First Quarter 2006 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 21.
- Stellar Environmental Solutions, Inc. (SES), 2006c. Second Quarter 2006 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 5.
- Stellar Environmental Solutions, Inc. (SES), 2006d. Third Quarter 2006 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. November 21.

Stellar Environmental Solutions, Inc. (SES), 2005a. First Quarter 2005 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. March 31.

Stellar Environmental Solutions, Inc. (SES), 2005b. Second Quarter 2005 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 12.

Stellar Environmental Solutions, Inc. (SES), 2005c. Third Quarter 2005 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 13.

Stellar Environmental Solutions, Inc. (SES), 2005d. Fourth Quarter 2004 Groundwater Monitoring and Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 24.

Stellar Environmental Solutions, Inc. (SES), 2004a. Year 2003 Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 15.

Stellar Environmental Solutions, Inc. (SES), 2004b. First Quarter 2004 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 14.

Stellar Environmental Solutions, Inc. (SES), 2004c. Second Quarter 2004 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 16.

Stellar Environmental Solutions, Inc. (SES), 2004d. Third Quarter 2004 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 12.

Stellar Environmental Solutions, Inc. (SES), 2003a. Year 2002 Annual Summary Report, Redwood Regional Park Service Yard, Oakland, California. January 27.

Stellar Environmental Solutions, Inc. (SES), 2003b. First Quarter 2003 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. May 5.

Stellar Environmental Solutions, Inc. (SES), 2003c. Second Quarter 2003 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 29.

Stellar Environmental Solutions, Inc. (SES), 2003d. Third Quarter 2003 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 3.

Stellar Environmental Solutions, Inc. (SES), 2002a. First Quarter 2002 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 16.

Stellar Environmental Solutions, Inc. (SES), 2002b. Second Quarter 2002 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. July 23.

- Stellar Environmental Solutions, Inc. (SES), 2002c. Third Quarter 2002 Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 14.
- Stellar Environmental Solutions, Inc. (SES), 2001a. Monitoring Well Installation and Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. February 8.
- Stellar Environmental Solutions, Inc. (SES), 2001b. Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. May 4.
- Stellar Environmental Solutions, Inc. (SES), 2001c. Well Installation, Site Monitoring, and Corrective Action Report, Redwood Regional Park Service Yard, Oakland, California. October 26.
- Stellar Environmental Solutions, Inc. (SES), 2000a. Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. April 21.
- Stellar Environmental Solutions, Inc. (SES), 2000b. Workplan for Groundwater Monitoring Well Installations, Redwood Regional Park Service Yard, Oakland, California. October 19.
- Stellar Environmental Solutions, Inc. (SES), 2000c. Site Monitoring Report, Redwood Regional Park Service Yard, Oakland, California. October 19.
- Stellar Environmental Solutions, Inc. (SES), 2000d. Site Feasibility Study Report, Redwood Regional Park Service Yard, Oakland, California. October 20.
- Stellar Environmental Solutions, Inc. (SES), 1999a. Workplan for Subsurface Investigation, Redwood Regional Park Service Yard, Oakland, California. April 8.
- Stellar Environmental Solutions, Inc. (SES), 1999b. Residual Contamination Investigation and Remedial Action Assessment Report, Redwood Regional Park Service Yard, Oakland, California. June 9.
- Stellar Environmental Solutions, Inc. (SES), 1998a. Workplan for Continued Site Investigation and Closure Assessment, Redwood Regional Park Service Yard, Oakland, California. October 9.
- Stellar Environmental Solutions, Inc. (SES), 1998b. Site Investigation and Closure Assessment Report, Redwood Regional Park Service Yard, Oakland, California. December 4.

9.0 LIMITATIONS

This report has been prepared for the exclusive use of the East Bay Regional Park District, its authorized representatives, and the regulatory agencies. No reliance on this report shall be made by anyone other than those for whom it was prepared.

The findings and conclusions presented in this report are based on the review of previous investigators' findings at the site, as well as onsite activities conducted by SES since September 1998. This report has been prepared in accordance with generally accepted methodologies and standards of practice. The SES personnel who performed this work are qualified to perform such investigations and have accurately reported the information available, but cannot attest to the validity of that information. No warranty, expressed or implied, is made as to the findings, conclusions, and recommendations included in the report.

The findings of this report are valid as of the present. Site conditions may change with the passage of time, natural processes, or human intervention, which can invalidate the findings and conclusions presented in this report. As such, this report should be considered a reflection of the current site conditions as based on site characterization and corrective actions completed.

APPENDIX A

Historical Groundwater Monitoring Well Water Level Data

**HISTORICAL GROUNDWATER ELEVATIONS IN MONITORING WELLS
REDWOOD REGIONAL PARK SERVICE YARD
7867 REDWOOD ROAD, OAKLAND, CALIFORNIA**

Well I.D.	MW-1	MW-2	MW-3	MW-4	MW-5	MW-6	MW-7	MW-8	MW-9	MW-10	MW-11	MW-12
TOC Elevation (a)	565.83	566.42	560.81	548.10	547.41	545.43	547.56	549.13	549.28	547.22	547.75	544.67
Date Monitored	Groundwater Elevations (feet above mean sea level)											
09/18/98	563.7	544.2	540.8	534.5	531.1	545.6						
04/06/99	565.2	546.9	542.3	535.6	532.3	532.9						
12/20/99	562.9	544.7	541.5	534.9	531.2	532.2						
09/28/00	562.8	542.7	538.3	532.2	530.9	532.0						
01/11/01	562.9	545.1	541.7	535.0	531.2	532.3	534.9	538.1				
04/13/01	562.1	545.7	541.7	535.1	531.5	532.4	535.3	539.8				
09/01/01	560.9	542.0	537.7	533.9	530.7	531.8	534.0	535.6				
12/17/01	562.2	545.2	542.2	534.8	531.4	532.4	534.8	538.4	534.6	535.7	535.2	
03/14/02	563.0	547.1	542.2	535.5	532.4	533.3	535.7	541.8	535.0	537.6	536.6	
06/18/02	562.1	544.7	541.1	534.6	531.2	532.2	534.8	537.9	534.7	535.6	535.3	
09/24/02	561.4	542.2	537.3	533.5	530.6	531.8	533.5	535.5	535.3	533.8	531.7	
12/18/02	562.4	545.0	542.0	534.8	531.5	532.5	534.6	537.1	536.5	535.2	532.8	
03/27/03	562.6	545.7	541.7	534.8	531.6	532.4	535.1	539.9	537.2	536.2	533.6	
06/19/03	562.3	544.9	541.5	534.8	531.3	532.3	534.9	538.2	536.9	535.7	533.2	
09/10/03	561.6	542.1	537.9	533.8	530.8	531.9	533.7	535.6	535.6	534.1	531.9	
12/10/03	562.4	542.7	537.6	533.7	530.9	531.9	533.7	535.2	535.5	533.8	531.7	
03/18/04	563.1	546.6	541.9	535.0	531.7	532.4	535.2	540.9	537.4	536.6	533.8	
06/17/04	562.1	544.3	540.7	534.3	531.0	532.1	534.6	537.4	536.5	535.1	532.7	
09/21/04	561.5	541.1	536.5	533.1	530.5	531.6	533.1	534.7	532.7	533.2	533.2	
12/14/04	562.2	545.3	541.7	534.7	531.4	532.2	534.6	540.4	536.7	535.5	532.9	
03/16/05	563.8	547.3	541.7	535.3	532.4	532.8	535.6	541.8	538.0	537.1	534.2	
06/15/05	562.9	545.9	541.6	535.0	531.7	532.5	535.0	540.0	535.0	536.1	535.6	
09/13/05	562.3	543.5	539.7	534.4	530.9	532.2	534.3	536.7	536.1	534.7	532.4	
12/15/05	562.2	544.3	541.4	(b)	531.0	532.2	534.5	537.3	534.1	534.7	534.9	535.1
03/30/06	565.8	548.6	542.7	(b)	533.9	534.4	536.2	542.3	536.4	537.3	537.6	535.7
06/20/06	563.6	545.4	541.6	(b)	531.5	532.5	534.9	538.6	534.6	536.2	535.5	535.0
09/29/06	561.9	542.8	539.0	(b)	530.7	532.1	535.1	536.1	533.7	534.6	534.7	534.7
12/14/06	562.9	544.2	541.5	(b)	531.1	532.3	534.7	536.7	534.0	534.8	535.2	535.0

TOC = Top of well Casing

(a) TOC Elevations resurveyed on December 15, 2005 in accordance GeoTracker requirements.

(b) Well decommissioned and replaced by MW-12 in December 2005.

APPENDIX B

Groundwater Monitoring Field Documentation

WELL GAUGING DATA

Project # 061219-0P1 Date 12-14-06 Client Stellar

Site Redwood Regional Park Oakland

	Well ID	Time	Well Size (in.)	Sheen / Odor	Depth to Immiscible Liquid (ft.)	Thickness of Immiscible Liquid (ft.)	Volume of Immiscibles Removed (ml)	Depth to water (ft.)	Depth to well bottom (ft.)	Survey Point: TOB or <u>TOC</u>	Notes
6/0	MW-1	843	4	* No	SPT			2.96	19.18		
	MW-2	848	4					22.19	38.87		
6/0	MW-3	837	4					19.30	45.10		
4/0	MW-5	808	4					16.31	27.00		
4/0	MW-6	830	4					13.10	14.55		
	MW-7	816	2					12.85	25.44		
	MW-8	825	2					12.48	22.34		
	MW-9	815	2					15.31	30.30		
	MW-10	823	2					12.99	28.42		
	MW-11	818	2					12.52	28.80		
	MW-12	828	2					9.63	23.90		

WELL MONITORING DATA SHEET

Project #: <u>061214-B/1</u>	Client: <u>Stella</u>
Sampler: <u>B Pump</u>	Date: <u>12-14-06</u>
Well I.D.: <u>mw-2</u>	Well Diameter: 2 3 <u>4</u> 6 8 _____
Total Well Depth (TD): <u>38.87</u>	Depth to Water (DTW): <u>22.19</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: <u>25.53</u>	

Purge Method: <u>Bailer</u>	Water: <u>Peristaltic</u>	Sampling Method: <u>Bailer</u>
<u>Disposable Bailer</u>	<u>Extraction Pump</u>	<u>Disposable Bailer</u>
<u>Positive Air Displacement</u>	Other _____	<u>Extraction Port</u>
<u>Electric Submersible</u>		<u>Dedicated Tubing</u>
		Other: _____

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

<u>10.8</u> (Gals.) X	<u>3</u>	<u>=</u>	<u>32.5</u> Gals.
1 Case Volume	Specified Volumes		Calculated Volume

Time	Temp (F or °C)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
<u>8:55</u>	<u>59.7</u>	<u>7.4</u>	<u>865</u>	<u>86</u>	<u>11.0</u>	
	<u>well dewatered @</u>				<u>20.0</u>	<u>DTW = 36.88</u>
<u>1140</u>	<u>59.2</u>	<u>7.3</u>	<u>841</u>	<u>36</u>	<u>-</u>	

Did well dewater? Yes No Gallons actually evacuated: 20.0

Sampling Date: 12-14-06 Sampling Time: 1140 Depth to Water: 23.62

Sample I.D.: mw-2 Laboratory: Kiff CalScience Other: LIF

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
------------------	------------	------	-------------	------

O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV
--------------------	------------	----	-------------	----

WATER MONITORING DATA SHEET

Project #: 061214-13P1	Client: Stellan
Sampler: B Prowd	Date: 12-14-06
Well I.D.: MW-7	Well Diameter: <u>(2)</u> 3 4 6 8
Total Well Depth (TD): 25.44	Depth to Water (DTW): 12.85
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>(PVS)</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: <u>(5.37)</u>	

Purge Method: Bailer Waterra Sampling Method: Bailer

Disposible Bailer Peristaltic Disposible Bailer

Positive Air Displacement Extraction Pump Extraction Port

Electric Submersible Other _____ Dedicated Tubing

Other: _____

$$2.0 \text{ (Gals.)} \times 3 = 6.0 \text{ Gals.}$$

I Case Volume Specified Volumes Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°C or °F)	pH	Cond. (mS or <u>(uS)</u>)	Turbidity (NTUs)	Gals. Removed	Observations
928	57.7	7.1	799	>1000	2.0	
931	57.5	7.1	795	>1000	4.0	
934	57.5	7.2	799	>1000	6.0	

Did well dewater? Yes Gallons actually evacuated: 6.0

Sampling Date: 12-14-06 Sampling Time: 940 Depth to Water: 14.70

Sample I.D.: MW-7 Laboratory: Kiff CalScience Other C+T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other See CoC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
------------------	------------	------	-------------	------

O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV
--------------------	------------	----	-------------	----

WELL MONITORING DATA SHEET

Project #: <u>061214-BP1</u>	Client: <u>Stella</u>
Sampler: <u>B P_{low}</u>	Date: <u>12-14-06</u>
Well I.D.: <u>MW-8</u>	Well Diameter: <u>Ø</u> 3 4 6 8 _____
Total Well Depth (TD): <u>22.34</u>	Depth to Water (DTW): <u>12.48</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVC</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: <u>14.45</u>	

Purge Method:	Bailer	Waterra	Sampling Method:	Bailer
	Disposable Bailer <input checked="" type="checkbox"/>	Peristaltic		Disposable Bailer <input checked="" type="checkbox"/>
	Positive Air Displacement	Extraction Pump		Extraction Port
	Electric Submersible	Other _____		Dedicated Tubing

Other: _____

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

<u>1.6</u>	(Gals.) X	<u>3</u>	=	<u>4.7</u>	Gals.
1 Case Volume		Specified Volumes		Calculated Volume	

Time	Temp (<u>Ø</u> or °C)	pH	Cond. (mS or <u>µS</u>)	Turbidity (NTUs)	Gals. Removed	Observations
1031	59.5	7.2	809	>1000	2.0	
1034	59.6	7.2	799	>1000	3.5	
1038	59.5	7.2	818	>1000	5.0	

Did well dewater? Yes No Gallons actually evacuated: 5.0

Sampling Date: 12-14-06 Sampling Time: 1045 Depth to Water: 13.75

Sample I.D.: MW-8 Laboratory: Kiff CalScience Other CIT

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other see loc

EB I.D. (if applicable): @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
------------------	------------	------	-------------	------

O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV
--------------------	------------	----	-------------	----

WELL MONITORING DATA SHEET

Project #: 061214-BP1	Client: Stellar
Sampler: B Crowd	Date: 12-14-06
Well I.D.: mw-9	Well Diameter: \varnothing 3 4 6 8 _____
Total Well Depth (TD): 30.30	Depth to Water (DTW): 15.31
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 18.31	

Purge Method: Bailer Disposable Bailer <input checked="" type="checkbox"/> Positive Air Displacement Electric Submersible	Waterra Peristaltic Extraction Pump Other: _____	Sampling Method: Bailer Disposable Bailer <input checked="" type="checkbox"/> Extraction Port Dedicated Tubing Other: _____
--	---	---

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

2.4 (Gals.) X	3	=	7.2 Gals.
1 Case Volume	Specified Volumes		Calculated Volume

Time	Temp (\varnothing or $^{\circ}$ C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1010	58.2	6.9	915	>1000	2.5	
1014	58.3	7.1	883	>1000	5.0	
1018	58.2	7.2	863	>1000	7.5	

Did well dewater? Yes No Gallons actually evacuated: 7.5

Sampling Date: 12-14-06 Sampling Time: 1025 Depth to Water: 18.00

Sample I.D.: mw-9 Laboratory: Kiff CalScience Other: C&T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) ~~Other~~ see COC

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

WELL MONITORING DATA SHEET

Project #: <i>061214-BP1</i>	Client: <i>Stellar</i>
Sampler: <i>B Prowl</i>	Date: <i>12-14-06</i>
Well I.D.: <i>Mw-10</i>	Well Diameter: <input checked="" type="radio"/> 3 <input type="radio"/> 4 <input type="radio"/> 6 <input type="radio"/> 8 _____
Total Well Depth (TD): <i>28.42</i>	Depth to Water (DTW): <i>12.39</i>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <input checked="" type="checkbox"/> PVD <input type="checkbox"/> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: <i>15.60</i>	

Purge Method: Bailer Disposable Bailer Positive Air Displacement Electric Submersible Waterra Peristaltic Extraction Pump Other _____ Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing Other: _____

$2.6 \text{ (Gals.)} \times 3 = 7.7 \text{ Gals.}$	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </tbody> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														
I Case Volume	Specified Volumes	Calculated Volume															

Time	Temp (°F or °C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
908	59.0	7.8	799	>1000	3.0	
912	58.7	7.7	785	>1000	5.5	
916	58.5	7.6	762	>1000	8.0	
<i>Mt @ 802</i>						

Did well dewater? Yes No Gallons actually evacuated: *8.0*

Sampling Date: *12-14-06* Sampling Time: *1120* Depth to Water: *12.44*

Sample I.D.: *Mw-10* Laboratory: Kiff CalScience Other: *LET*

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: *see coc*

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd): Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd): Pre-purge:	mV	Post-purge:	mV

WELL MONITORING DATA SHEET

Project #: <u>061214-BP1</u>	Client: <u>Stellar</u>
Sampler: <u>B Prowl</u>	Date: <u>12-14-06</u>
Well I.D.: <u>mw-11</u>	Well Diameter: <u>2</u> 3 4 6 8 _____
Total Well Depth (TD): <u>28.80</u>	Depth to Water (DTW): <u>12.52</u>
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>(VOC)</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: <u>15.78</u>	

Purge Method: Bailer	Waterra	Sampling Method: Bailer
Disposable Bailer <input checked="" type="checkbox"/>	Peristaltic	Disposable Bailer <input checked="" type="checkbox"/>
Positive Air Displacement	Extraction Pump	Extraction Port
Electric Submersible	Other _____	Dedicated Tubing

Other: _____

$\frac{2.6 \text{ (Gals.)} \times 3}{1 \text{ Case Volume}} = \frac{7.8 \text{ Gals.}}{\text{Specified Volumes}} = \text{Calculated Volume}$	<table border="1" style="width: 100%; border-collapse: collapse; font-size: small;"> <tr> <th>Well Diameter</th> <th>Multiplier</th> <th>Well Diameter</th> <th>Multiplier</th> </tr> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.65</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.65	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier														
1"	0.04	4"	0.65														
2"	0.16	6"	1.47														
3"	0.37	Other	radius ² * 0.163														

Time	Temp (°F or °C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
1055	58.1	7.4	780	>1000	3.0	
1059	58.0	7.4	797	>1000	5.5	
1103	58.0	7.4	800	>1000	8.0	

Did well dewater? Yes No Gallons actually evacuated: 8.0

Sampling Date: 12-14-06 Sampling Time: 1110 Depth to Water: 13.30

Sample I.D.: mw-11 Laboratory: Kiff CalScience Other GT

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other see coc

EB I.D. (if applicable): _____ @ _____ Time Duplicate I.D. (if applicable): _____

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: _____

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
------------------	------------	------	-------------	------

O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV
--------------------	------------	----	-------------	----

WELL MONITORING DATA SHEET

Project #: 061214-13P1	Client: Stellar
Sampler: B Proud	Date: 12-14-06
Well I.D.: mw-12	Well Diameter: \varnothing 3 4 6 8 _____
Total Well Depth (TD): 23.90	Depth to Water (DTW): 9.63
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>PVD</u> Grade	D.O. Meter (if req'd): YSI HACH
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 12.48	

Purge Method: Bailer Waterra Sampling Method: Bailer
 Disposable Bailer Peristaltic Disposable Bailer
 Positive Air Displacement Extraction Pump Extraction Port
 Electric Submersible Other _____ Dedicated Tubing

Other: _____

2.3 (Gals.) X 3	= 6.8 Gals.	
I Case Volume	Specified Volumes	Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (F or °C)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	Gals. Removed	Observations
951	57.4	7.1	753	>1000	2.5	
955	57.3	7.0	737	>1000	5.0	
959	57.1	7.0	725	>1000	7.0	
	Mut @	80%				

Did well dewater? Yes No Gallons actually evacuated: 7.0

Sampling Date: 12-14-06 Sampling Time: 1130 Depth to Water: 9.63

Sample I.D.: mw-12 Laboratory: Kiff CalScience Other C+T

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other: see coc

EB I.D. (if applicable): @ Time Duplicate I.D. (if applicable):

Analyzed for: TPH-G BTEX MTBE TPH-D Oxygenates (5) Other:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
------------------	------------	------	-------------	------

O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV
--------------------	------------	----	-------------	----

APPENDIX C

Analytical Laboratory Report and Chain-of-Custody Record

Curtis & Tompkins Laboratories Analytical Report

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2006-16	
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Batch#: 120376	

Field ID: SW-2	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/15/06
Lab ID: 191506-001	

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	99	69-137	EPA 8015B
Bromofluorobenzene (FID)	101	80-133	EPA 8015B
Trifluorotoluene (PID)	100	64-132	EPA 8021B
Bromofluorobenzene (PID)	102	80-120	EPA 8021B

Field ID: SW-3	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/14/06
Lab ID: 191506-002	

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	127	69-137	EPA 8015B
Bromofluorobenzene (FID)	133	80-133	EPA 8015B
Trifluorotoluene (PID)	128	64-132	EPA 8021B
Bromofluorobenzene (PID)	134 *	80-120	EPA 8021B

*= Value outside of QC limits; see narrative
 C= Presence confirmed, but RPD between columns exceeds 40%
 H= Heavier hydrocarbons contributed to the quantitation
 ND= Not Detected
 RL= Reporting Limit

Curtis & Tompkins Laboratories Analytical Report

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2006-16	
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Batch#: 120376	

Field ID: MW-2	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/14/06
Lab ID: 191506-003	

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	16	2.0	EPA 8021B
Benzene	2.1	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	113	69-137	EPA 8015B
Bromofluorobenzene (FID)	115	80-133	EPA 8015B
Trifluorotoluene (PID)	109	64-132	EPA 8021B
Bromofluorobenzene (PID)	114	80-120	EPA 8021B

Field ID: MW-7	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/14/06
Lab ID: 191506-004	

Analyte	Result	RL	Analysis
Gasoline C7-C12	7,300 H	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	50	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	220	0.50	EPA 8021B
m,p-Xylenes	40	0.50	EPA 8021B
o-Xylene	1.8 C	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	92	69-137	EPA 8015B
Bromofluorobenzene (FID)	139 *	80-133	EPA 8015B
Trifluorotoluene (PID)	113	64-132	EPA 8021B
Bromofluorobenzene (PID)	126 *	80-120	EPA 8021B

*= Value outside of QC limits; see narrative
 C= Presence confirmed, but RPD between columns exceeds 40%
 H= Heavier hydrocarbons contributed to the quantitation
 ND= Not Detected
 RL= Reporting Limit

Curtis & Tompkins Laboratories Analytical Report

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2006-16	
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Batch#: 120376	

Field ID: MW-8	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/14/06
Lab ID: 191506-005	

Analyte	Result	RL	Analysis
Gasoline C7-C12	4,400 H	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	75	0.50	EPA 8021B
Toluene	4.2	0.50	EPA 8021B
Ethylbenzene	320	0.50	EPA 8021B
m,p-Xylenes	230	0.50	EPA 8021B
o-Xylene	16	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	132	69-137	EPA 8015B
Bromofluorobenzene (FID)	135 *	80-133	EPA 8015B
Trifluorotoluene (PID)	136 *	64-132	EPA 8021B
Bromofluorobenzene (PID)	130 *	80-120	EPA 8021B

Field ID: MW-9	Diln Fac: 5.000
Type: SAMPLE	Analyzed: 12/15/06
Lab ID: 191506-006	

Analyte	Result	RL	Analysis
Gasoline C7-C12	12,000 H	250	EPA 8015B
MTBE	ND	10	EPA 8021B
Benzene	140	2.5	EPA 8021B
Toluene	9.4	2.5	EPA 8021B
Ethylbenzene	880	2.5	EPA 8021B
m,p-Xylenes	610	2.5	EPA 8021B
o-Xylene	24	2.5	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	119	69-137	EPA 8015B
Bromofluorobenzene (FID)	113	80-133	EPA 8015B
Trifluorotoluene (PID)	119	64-132	EPA 8021B
Bromofluorobenzene (PID)	112	80-120	EPA 8021B

*= Value outside of QC limits; see narrative
 C= Presence confirmed, but RPD between columns exceeds 40%
 H= Heavier hydrocarbons contributed to the quantitation
 ND= Not Detected
 RL= Reporting Limit

Curtis & Tompkins Laboratories Analytical Report

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2006-16	
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Batch#: 120376	

Field ID: MW-10	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/15/06
Lab ID: 191506-007	

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	3.7	2.0	EPA 8021B
Benzene	0.61	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	0.55	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	126	69-137	EPA 8015B
Bromofluorobenzene (FID)	130	80-133	EPA 8015B
Trifluorotoluene (PID)	125	64-132	EPA 8021B
Bromofluorobenzene (PID)	129 *	80-120	EPA 8021B

Field ID: MW-11	Diln Fac: 2.000
Type: SAMPLE	Analyzed: 12/14/06
Lab ID: 191506-008	

Analyte	Result	RL	Analysis
Gasoline C7-C12	6,000 H	100	EPA 8015B
MTBE	ND	4.0	EPA 8021B
Benzene	83	1.0	EPA 8021B
Toluene	ND	1.0	EPA 8021B
Ethylbenzene	260	1.0	EPA 8021B
m,p-Xylenes	14	1.0	EPA 8021B
o-Xylene	2.4 C	1.0	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	131	69-137	EPA 8015B
Bromofluorobenzene (FID)	126	80-133	EPA 8015B
Trifluorotoluene (PID)	130	64-132	EPA 8021B
Bromofluorobenzene (PID)	115	80-120	EPA 8021B

*= Value outside of QC limits; see narrative
 C= Presence confirmed, but RPD between columns exceeds 40%
 H= Heavier hydrocarbons contributed to the quantitation
 ND= Not Detected
 RL= Reporting Limit

Curtis & Tompkins Laboratories Analytical Report

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 5030B
Project#: 2006-16	
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Batch#: 120376	

Field ID: MW-12	Diln Fac: 1.000
Type: SAMPLE	Analyzed: 12/15/06
Lab ID: 191506-009	

Analyte	Result	RL	Analysis
Gasoline C7-C12	770 H	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	7.4	0.50	EPA 8021B
m,p-Xylenes	1.3	0.50	EPA 8021B
o-Xylene	0.65	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	152 *	69-137	EPA 8015B
Bromofluorobenzene (FID)	119	80-133	EPA 8015B
Trifluorotoluene (PID)	130	64-132	EPA 8021B
Bromofluorobenzene (PID)	117	80-120	EPA 8021B

Type: BLANK	Diln Fac: 1.000
Lab ID: QC368332	Analyzed: 12/14/06

Analyte	Result	RL	Analysis
Gasoline C7-C12	ND	50	EPA 8015B
MTBE	ND	2.0	EPA 8021B
Benzene	ND	0.50	EPA 8021B
Toluene	ND	0.50	EPA 8021B
Ethylbenzene	ND	0.50	EPA 8021B
m,p-Xylenes	ND	0.50	EPA 8021B
o-Xylene	ND	0.50	EPA 8021B

Surrogate	%REC	Limits	Analysis
Trifluorotoluene (FID)	102	69-137	EPA 8015B
Bromofluorobenzene (FID)	106	80-133	EPA 8015B
Trifluorotoluene (PID)	102	64-132	EPA 8021B
Bromofluorobenzene (PID)	104	80-120	EPA 8021B

*= Value outside of QC limits; see narrative
 C= Presence confirmed, but RPD between columns exceeds 40%
 H= Heavier hydrocarbons contributed to the quantitation
 ND= Not Detected
 RL= Reporting Limit

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	191506	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2006-16	Analysis:	EPA 8021B
Type:	LCS	Diln Fac:	1.000
Lab ID:	QC368333	Batch#:	120376
Matrix:	Water	Analyzed:	12/14/06
Units:	ug/L		

Analyte	Spiked	Result	%REC	Limits
MTBE	20.00	19.93	100	72-124
Benzene	20.00	18.85	94	80-120
Toluene	20.00	19.83	99	80-120
Ethylbenzene	20.00	19.40	97	80-120
m,p-Xylenes	20.00	18.92	95	80-120
o-Xylene	20.00	19.49	97	80-120

Surrogate	%REC	Limits
Trifluorotoluene (PID)	104	64-132
Bromofluorobenzene (PID)	104	80-120

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	191506	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2006-16	Analysis:	EPA 8015B
Type:	LCS	Diln Fac:	1.000
Lab ID:	QC368334	Batch#:	120376
Matrix:	Water	Analyzed:	12/14/06
Units:	ug/L		

Analyte	Spiked	Result	%REC	Limits
Gasoline C7-C12	2,000	1,940	97	80-120

Surrogate	%REC	Limits
Trifluorotoluene (FID)	121	69-137
Bromofluorobenzene (FID)	127	80-133

Batch QC Report

Curtis & Tompkins Laboratories Analytical Report

Lab #:	191506	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 5030B
Project#:	2006-16	Analysis:	EPA 8015B
Field ID:	ZZZZZZZZZZ	Batch#:	120376
MSS Lab ID:	191493-010	Sampled:	12/13/06
Matrix:	Water	Received:	12/14/06
Units:	ug/L	Analyzed:	12/14/06
Diln Fac:	1.000		

Type: MS Lab ID: QC368335

Analyte	MSS Result	Spiked	Result	%REC	Limits
Gasoline C7-C12	13.11	2,000	1,866	93	80-120

Surrogate	%REC	Limits
Trifluorotoluene (FID)	111	69-137
Bromofluorobenzene (FID)	119	80-133

Type: MSD Lab ID: QC368336

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
Gasoline C7-C12	2,000	1,843	91	80-120	1	20

Surrogate	%REC	Limits
Trifluorotoluene (FID)	115	69-137
Bromofluorobenzene (FID)	130	80-133

Total Extractable Hydrocarbons			
Lab #:	191506	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 3520C
Project#:	2006-16	Analysis:	EPA 8015B
Matrix:	Water	Sampled:	12/14/06
Units:	ug/L	Received:	12/14/06
Diln Fac:	1.000	Prepared:	12/17/06
Batch#:	120441		

Field ID:	SW-2	Lab ID:	191506-001
Type:	SAMPLE	Analyzed:	12/19/06

Analyte	Result	RL
Diesel C10-C24	ND	50

Surrogate	%REC	Limits
Hexacosane	101	65-130

Field ID:	SW-3	Lab ID:	191506-002
Type:	SAMPLE	Analyzed:	12/19/06

Analyte	Result	RL
Diesel C10-C24	ND	50

Surrogate	%REC	Limits
Hexacosane	101	65-130

Field ID:	MW-2	Lab ID:	191506-003
Type:	SAMPLE	Analyzed:	12/19/06

Analyte	Result	RL
Diesel C10-C24	ND	50

Surrogate	%REC	Limits
Hexacosane	102	65-130

Field ID:	MW-7	Lab ID:	191506-004
Type:	SAMPLE	Analyzed:	12/19/06

Analyte	Result	RL
Diesel C10-C24	2,400 L Y	50

Surrogate	%REC	Limits
Hexacosane	88	65-130

L= Lighter hydrocarbons contributed to the quantitation
Y= Sample exhibits chromatographic pattern which does not resemble standard
q= Draft result - ending instrument QC not yet analyzed
ND= Not Detected
RL= Reporting Limit

Total Extractable Hydrocarbons

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 3520C
Project#: 2006-16	Analysis: EPA 8015B
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Diln Fac: 1.000	Prepared: 12/17/06
Batch#: 120441	

Field ID: MW-8	Lab ID: 191506-005
Type: SAMPLE	Analyzed: 12/19/06

Analyte	Result	RL
Diesel C10-C24	800 L Y	50
Surrogate	%REC	Limits
Hexacosane	90	65-130

Field ID: MW-9	Lab ID: 191506-006
Type: SAMPLE	Analyzed: 12/19/06

Analyte	Result	RL
Diesel C10-C24	2,800 L Y	50
Surrogate	%REC	Limits
Hexacosane	98	65-130

Field ID: MW-10	Lab ID: 191506-007
Type: SAMPLE	Analyzed: 12/19/06

Analyte	Result	RL
Diesel C10-C24	ND	50
Surrogate	%REC	Limits
Hexacosane	101	65-130

Field ID: MW-11	Lab ID: 191506-008
Type: SAMPLE	Analyzed: 12/19/06

Analyte	Result	RL
Diesel C10-C24	3,500 L Y	50
Surrogate	%REC	Limits
Hexacosane	100	65-130

L= Lighter hydrocarbons contributed to the quantitation
 Y= Sample exhibits chromatographic pattern which does not resemble standard
 q= Draft result - ending instrument QC not yet analyzed
 ND= Not Detected
 RL= Reporting Limit

Total Extractable Hydrocarbons

Lab #: 191506	Location: Redwood Regional Park
Client: Stellar Environmental Solutions	Prep: EPA 3520C
Project#: 2006-16	Analysis: EPA 8015B
Matrix: Water	Sampled: 12/14/06
Units: ug/L	Received: 12/14/06
Diln Fac: 1.000	Prepared: 12/17/06
Batch#: 120441	

Field ID: MW-12	Lab ID: 191506-009
Type: SAMPLE	Analyzed: 12/19/06

Analyte	Result	RL
Diesel C10-C24	230 L Y	50

Surrogate	%REC	Limits
Hexacosane	92	65-130

Type: BLANK	Analyzed: 12/20/06
Lab ID: QC368606	

Analyte	Result	RL
Diesel C10-C24	ND q	50

Surrogate	%REC	Limits
Hexacosane	90 q	65-130

L= Lighter hydrocarbons contributed to the quantitation
 Y= Sample exhibits chromatographic pattern which does not resemble standard
 q= Draft result - ending instrument QC not yet analyzed
 ND= Not Detected
 RL= Reporting Limit

Batch QC Report

Total Extractable Hydrocarbons			
Lab #:	191506	Location:	Redwood Regional Park
Client:	Stellar Environmental Solutions	Prep:	EPA 3520C
Project#:	2006-16	Analysis:	EPA 8015B
Matrix:	Water	Batch#:	120441
Units:	ug/L	Prepared:	12/17/06
Diln Fac:	1.000	Analyzed:	12/19/06

Type: BS Cleanup Method: EPA 3630C
 Lab ID: QC368607

Analyte	Spiked	Result	%REC	Limits
Diesel C10-C24	2,500	2,036	81	61-133

Surrogate	%REC	Limits
Hexacosane	87	65-130

Type: BSD Cleanup Method: EPA 3630C
 Lab ID: QC368608

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
Diesel C10-C24	2,500	2,104	84	61-133	3	31

Surrogate	%REC	Limits
Hexacosane	86	65-130

RPD= Relative Percent Difference

Chain of Custody Record

Lab job no. 191506
 Date 12-14-06
 Page 1 of 1

Laboratory Curtis and Tompkins, Ltd. Method of Shipment Hand Delivery
 Address 2323 Fifth Street Shipment No. _____
Berkeley, California 94710 Airbill No. _____
510-486-0900 Cooler No. _____
 Project Owner East Bay Regional Park District Project Manager Richard Makdisi
 Site Address 7867 Redwood Road Telephone No. (510) 644-3123
Oakland, California Fax No. (510) 644-3859
 Project Name Redwood Regional Park Samplers: (Signature) [Signature]
 Project Number 2006-16

Field Sample Number	Location/Depth	Date	Time	Sample Type	Type/Size of Container	Preservation		Filtered	No. of Containers	Analysis Required				Remarks
						Cooler	Chemical			TVH-gps	BTEX	MTBE	TEH-diesel	
-1 SW-2	2	12/14/06	0955	W	3-40m, 2 Lamber	yes	HCC to VOAS	NO	5	X	X	X		
-2 SW-3	3	↓	1015	W	"	"	"	NO	5	X	X	X		
-3 MW-2		12-14	1140	W	3 40 mL HCL, 1 Lamber			N	4	X	X	X		
-4 mw-7		↓	940		"				4	X	X	X		
-5 mw-8		↓	1045		"				4	X	X	X		
-6 mw-9		↓	1025		"				4	X	X	X		
-7 mw-10		↓	1120		"				4	X	X	X		
-8 mw-11		↓	1110		"				4	X	X	X		
-9 mw-12		↓	1130		"				4	X	X	X		
													Cold Once Intact	

-1
-2
-3
-4
-5
-6
-7
-8
-9

Relinquished by: Signature: <u>[Signature]</u> Printed: <u>Blaine Tech</u> Company: <u>Stellar Environmental</u>	Date: <u>12/14/06</u> Time: <u>1145</u>	Received by: Signature: <u>Brian Proud</u> Printed: <u>Brian Proud</u> Company: <u>Blaine Tech</u>	Date: _____ Time: _____	Relinquished by: Signature: <u>[Signature]</u> Printed: <u>Brian Proud</u> Company: <u>Blaine Tech</u>	Date: _____ Time: _____	Received by: Signature: <u>Joel Ingram</u> Printed: <u>Joel Ingram</u> Company: <u>C&T</u>	Date: <u>12/14/06</u> Time: <u>12:42</u>		
Turnaround Time: <u>5 Day TAT</u>				Relinquished by: Signature: _____ Printed: _____ Company: _____				Received by: Signature: _____ Printed: _____ Company: _____	
Comments: <u>Please provide a GeoTracker EDD as well as hard copy of report.</u> <u>Surface water samples collected by Stellar Environmental Solutions.</u> <u>Groundwater samples collected by Blaine Tech Services.</u>								Date: _____ Time: _____	

2000-00-01

APPENDIX D

Historical Analytical Results and Plume Maps

HISTORICAL GROUNDWATER MONITORING WELLS ANALYTICAL RESULTS
REDWOOD REGIONAL PARK SERVICE YARD, OAKLAND, CALIFORNIA
(all concentrations in ug/L, equivalent to parts per billion [ppb])

Well MW-2									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Nov-94	66	< 50	3.4	< 0.5	< 0.5	0.9	4.3	NA
2	Feb-95	89	< 50	18	2.4	1.7	7.5	30	NA
3	May-95	< 50	< 50	3.9	< 0.5	1.6	2.5	8.0	NA
4	Aug-95	< 50	< 50	5.7	< 0.5	< 0.5	< 0.5	5.7	NA
5	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Aug-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Dec-96	< 50	< 50	6.3	< 0.5	1.6	< 0.5	7.9	NA
8	Feb-97	< 50	< 50	0.69	< 0.5	0.55	< 0.5	1.2	NA
9	May-97	67	< 50	8.9	< 0.5	5.1	< 1.0	14	NA
10	Aug-97	< 50	< 50	4.5	< 0.5	1.1	< 0.5	5.6	NA
11	Dec-97	61	< 50	21	< 0.5	6.5	3.9	31	NA
12	Feb-98	2,000	200	270	92	150	600	1,112	NA
13	Sep-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	7.0
14	Apr-99	82	710	4.2	< 0.5	3.4	4.0	12	7.5
15	Dec-99	57	< 50	20	0.6	5.9	< 0.5	27	4.5
16	Sep-00	< 50	< 50	0.72	< 0.5	< 0.5	< 0.5	0.7	7.9
17	Jan-01	51	< 50	8.3	< 0.5	1.5	< 0.5	9.8	8.0
18	Apr-01	110	< 50	10	< 0.5	11	6.4	27	10
19	Aug-01	260	120	30	6.7	1.6	6.4	45	27
20	Dec-01	74	69	14	0.8	3.7	3.5	22	6.6

Well MW-2 (continued)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
21	Mar-02	< 50	< 50	2.3	0.51	1.9	1.3	8.3	8.2
22	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	7.7
23	Sep-02	98	< 50	5.0	< 0.5	< 0.5	< 0.5	—	13
24	Dec-02	< 50	< 50	4.3	< 0.5	< 0.5	< 0.5	—	< 2.0
25	Mar-03	130	82	39	< 0.5	20	4.1	63	16
26	Jun-03	< 50	< 50	1.9	< 0.5	< 0.5	< 0.5	1.9	8.7
27	Sep-03	120	< 50	8.6	0.51	0.53	< 0.5	9.6	23
28	Dec-03	282	<100	4.3	1.6	1.3	1.2	8.4	9.4
29	Mar-04	374	<100	81	1.2	36	7.3	126	18
30	Jun-04	< 50	< 50	0.75	< 0.5	< 0.5	< 0.5	< 0.5	15
31	Sep-04	200	< 50	23	< 0.5	< 0.5	0.70	24	16
32	Dec-04	80	< 50	14	< 0.5	2.9	0.72	18	20
33	Mar-05	190	68	27	<0.5	14	11	52	26
34	Jun-05	68	< 50	7.1	< 0.5	6.9	1.8	16	24
35	Sep-05	< 50	< 50	2.5	< 0.5	< 0.5	< 1.0	2.5	23
36	Dec-05	< 50	< 50	3.9	< 0.5	< 0.5	< 1.0	3.9	23
37	Mar-06	1300	300	77	4.4	91	250	422	18
38	Jun-06	< 50	60	< 0.5	< 0.5	< 0.5	< 1.0	—	17
39	Sep-06	270	52	31	< 0.5	15	6.69	53	17
40	Dec-06	< 50	< 50	2.1	< 0.5	< 0.5	< 0.5	2	16

Well MW-4									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Nov-94	2,600	230	120	4.8	150	88	363	NA
2	Feb-95	11,000	330	420	17	440	460	1,337	NA
3	May-95	7,200	440	300	13	390	330	1,033	NA
4	Aug-95	1,800	240	65	6.8	89	67	227	NA
5	May-96	1,100	140	51	< 0.5	< 0.5	47	98	NA
6	Aug-96	3,700	120	63	2.0	200	144	409	NA
7	Dec-96	2,700	240	19	< 0.5	130	93	242	NA
8	Feb-97	3,300	< 50	120	1.0	150	103	374	NA
9	May-97	490	< 50	2.6	6.7	6.4	6.7	22	NA
10	Aug-97	1,900	150	8.6	3.5	78	53	143	NA
11	Dec-97	1,000	84	4.6	2.7	61	54	123	NA
12	Feb-98	5,300	340	110	24	320	402	856	NA
13	Sep-98	1,800	< 50	8.9	< 0.5	68	27	104	23
14	Apr-99	2,900	710	61	1.2	120	80	263	32
15	Dec-99	1,000	430	4.0	2.0	26	14	46	< 2.0
16	Sep-00	570	380	< 0.5	< 0.5	16	4.1	20	2.4
17	Jan-01	1,600	650	4.2	0.89	46	13.8	65	8.4
18	Apr-01	1,700	1,100	4.5	2.8	48	10.7	66	5.0
19	Aug-01	1,300	810	3.2	4.0	29	9.7	46	< 2.0
20	Dec-01	< 50	110	< 0.5	< 0.5	< 0.5	1.2	1.2	< 2.0
21	Mar-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
22	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
23	Sep-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
24	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
25	Mar-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
26	Jun-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
27	Sep-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
28	Dec-03	< 50	< 100	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
29	Mar-04	< 50	< 100	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
30	Jun-04	< 50	2,500	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
31	Sep-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
32	Dec-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
33	Mar-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
34	Jun-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0
35	Sep-05	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0

Groundwater monitoring in this well discontinued with Alameda County Health Care Services Agency approval.

Well MW-5									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Nov-94	50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
2	Feb-95	70	< 50	0.6	< 0.5	< 0.5	< 0.5	0.6	NA
3	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	Aug-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Aug-96	80	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
9	May-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Aug-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
11	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
12	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
13	Sep-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2
Groundwater monitoring in this well discontinued in 1998 with Alameda County Health Care Services Agency approval.									
Subsequent groundwater monitoring conducted to confirm plume's southern limit									
14	Jun-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	5.9
15	Sep-04	< 50	< 50	< 0.5	< 0.5	< 0.5	< 1.0	—	< 2.0

Well MW-7									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Jan-01	13,000	3,100	95	4	500	289	888	95
2	Apr-01	13,000	3,900	140	< 0.5	530	278	948	52
3	Aug-01	12,000	5,000	55	25	440	198	718	19
4	Dec-01	9,100	4,600	89	< 2.5	460	228	777	< 10
5	Mar-02	8,700	3,900	220	6.2	450	191	867	200
6	Jun-02	9,300	3,500	210	6.3	380	155	751	18
7	Sep-02	9,600	3,900	180	< 0.5	380	160	720	< 2.0
8	Dec-02	9,600	3,700	110	< 0.5	400	189	699	< 2.0
9	Mar-03	10,000	3,600	210	12	360	143	725	45
10	Jun-03	9,300	4,200	190	< 10	250	130	570	200
11	Sep-03	10,000	3,300	150	11	300	136	597	< 2.0
12	Dec-03	9,140	1,100	62	45	295	184	586	89
13	Mar-04	8,170	600	104	41	306	129	580	84
14	Jun-04	9,200	2,700	150	< 0.5	290	91	531	< 2.0
15	Sep-04	9,700	3,400	98	< 0.5	300	125	523	< 2.0
16	Dec-04	8200	4,000	95	< 0.5	290	124	509	< 2.0
17	Mar-05	10,000	4,300	150	< 0.5	370	71	591	< 2.0
18	Jun-05	10,000	3,300	210	< 1.0	410	56	676	< 4.0
19	Sep-05	7,600	2,700	110	< 1.0	310	54	474	< 4.0
20	Dec-05	2,900	3,300	31	< 1.0	140	41	212	< 4.0
21	Mar-06	6,800	3,000	110	< 1.0	280	42	432	110
22	Jun-06	6,900	3,600	63	< 2.5	290	43	396	< 10
23	Sep-06	7,900	3,600	64	< 0.5	260	58	382	49
24	Dec-06	7,300	2,400	50	< 0.5	220	42	312	< 2.0

Well MW-8									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Jan-01	14,000	1,800	430	17	360	1230	2,037	96
2	Apr-01	11,000	3,200	320	13	560	1,163	2,056	42
3	Aug-01	9,600	3,200	130	14	470	463	1,077	14
4	Dec-01	3,500	950	69	2.4	310	431	812	< 4.0
5	Mar-02	14,000	3,800	650	17	1,200	1,510	3,377	240
6	Jun-02	2,900	1,100	70	2.0	170	148	390	19
7	Sep-02	1,000	420	22	< 0.5	64	50	136	< 2.0
8	Dec-02	3,300	290	67	< 0.5	190	203	460	< 2.0
9	Mar-03	13,000	3,500	610	12	1,100	958	2,680	< 10
10	Jun-03	7,900	2,200	370	7.4	620	562	1,559	< 4.0
11	Sep-03	3,600	400	120	3.3	300	221	644	< 2.0
12	Dec-03	485	100	19	1.5	26	36	83	< 5.0
13	Mar-04	16,000	900	592	24	1,060	1,870	3,546	90
14	Jun-04	5,900	990	260	9.9	460	390	1,120	< 10
15	Sep-04	2,000	360	100	< 2.5	180	102	382	< 10
16	Dec-04	15,000	4,000	840	21	1,200	1,520	3,581	< 10
17	Mar-05	24,000	7,100	840	51	1,800	2,410	5,101	<10
18	Jun-05	33,000	5,700	930	39	2,500	3,860	7,329	<20
19	Sep-05	5,600	1,200	270	6.6	400	390	1,067	<20
20	Dec-05	3,700	1,300	110	< 5.0	320	356	786	<20
21	Mar-06	22,000	4,300	550	30	1,800	2,380	4,760	<20
22	Jun-06	19,000	5,000	500	28	1,800	1,897	4,225	<20
23	Sep-06	9,000	820	170	7.7	730	539	1,447	<10
24	Dec-06	4,400	800	75	4.2	320	246	645	< 2.0

Well MW-9									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Aug-01	11,000	170	340	13	720	616	1,689	48
2	Dec-01	9,400	2,700	250	5.1	520	317	1,092	< 10
3	Mar-02	1,700	300	53	4.2	120	67	244	20
4	Jun-02	11,000	2,500	200	16	600	509	1,325	85
5	Sep-02	3,600	2,800	440	11	260	39	750	< 4.0
6	Dec-02	7,000	3,500	380	9.5	730	147	1,266	< 10
7	Mar-03	4,400	1,400	320	6.9	400	93	820	< 2.0
8	Jun-03	7,600	1,600	490	10	620	167	1,287	< 4.0
9	Sep-03	8,300	2,900	420	14	870	200	1,504	< 10
10	Dec-03	7,080	700	287	31	901	255	1,474	< 10
11	Mar-04	3,550	600	122	15	313	84	534	35
12	Jun-04	6,800	1,700	350	< 2.5	620	99	1,069	< 10
13	Sep-04	7,100	1,900	160	8.1	600	406	1,174	< 10
14	Dec-04	4,700	2,800	160	< 2.5	470	< 0.5	630	< 10
15	Mar-05	4,200	1,600	97	< 2.5	310	42	449	< 10
16	Jun-05	9,900	2,000	170	< 2.5	590	359	1,119	< 10
17	Sep-05	3,600	1,200	250	< 0.5	330	36	616	< 2.0
18	Dec-05	8,700	1,500	150	4	650	551	1,355	< 4.0
19	Mar-06	3,600	880	37	< 1.0	210	165	412	< 4.0
20	Jun-06	3,200	1,300	39	< 1.0	220	144	403	4.2
21	Sep-06	12,000	3,300	130	8	850	604	1,592	< 1.0
22	Dec-06	12,000	2,800	140	9.4	880	634	1,663	< 10

Well MW-10									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Aug-01	550	2,100	17	< 0.5	31	44	92	40
2	Dec-01	< 50	81	< 0.5	< 0.5	< 0.5	< 0.5	—	25
3	Mar-02	< 50	< 50	0.61	< 0.5	< 0.5	< 0.5	0.61	6.0
4	Jun-02	< 50	< 50	0.59	< 0.5	0.58	< 0.5	1.2	9.0
5	Sep-02	160	120	10	< 0.5	6.7	3.6	20	26
6	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	16
7	Mar-03	110	< 50	11	< 0.5	12	1.3	24	15
8	Jun-03	110	< 50	9.6	< 0.5	6.8	< 0.5	16	9.0
9	Sep-03	< 50	< 50	1.1	< 0.5	1.5	< 0.5	2.6	7.0
10	Dec-03	162	<100	6.9	<0.3	8.0	<0.6	15	9.9
11	Mar-04	94	<100	2.8	<0.3	5.7	7.0	16	<5.0
12	Jun-04	150	56	11	< 0.5	12	< 0.5	23	15
13	Sep-04	< 50	< 50	1.6	< 0.5	1.9	< 1.0	3.5	5.8
14	Dec-04	64	< 50	3.7	< 0.5	3.7	0.7	8.1	10
15	Mar-05	95	98	8.3	<0.5	7.7	0.77	17	13
16	Jun-05	150	57	14	<0.5	10	1.0	25	<2.0
17	Sep-05	87	< 50	5.0	<0.5	3.6	<1.0	8.6	<2.0
18	Dec-05	< 50	< 50	1.2	<0.5	<0.5	<1.0	1.2	7.8
19	Mar-06	58	71	3.2	<0.5	2.2	<1.0	5.4	8.8
20	Jun-06	73	140	4.9	<0.5	2.5	<1.0	7.4	5.3
21	Sep-06	88	51	<0.5	<0.5	<0.5	<0.5	<0.5	9.6
22	Dec-06	<50	<50	0.61	<0.5	0.55	<0.5	1.2	3.7

Well MW-11									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Aug-01	17,000	7,800	390	17	820	344	1,571	< 10
2	Dec-01	5,800	2,800	280	7.8	500	213	1,001	< 10
3	Mar-02	100	94	< 0.5	< 0.5	0.64	< 0.5	0.64	2.4
4	Jun-02	8,200	2,600	570	13	560	170	1,313	< 4
5	Sep-02	12,000	4,400	330	13	880	654	1,877	< 10
6	Dec-02	18,000	4,500	420	< 2.5	1,100	912	2,432	< 10
7	Mar-03	7,800	2,600	170	4.7	530	337	1,042	53
8	Jun-03	14,000	3,800	250	< 2.5	870	693	1,813	< 10
9	Sep-03	10,000	3,000	250	9.9	700	527	1,487	< 4
10	Dec-03	15,000	1,100	314	60	1,070	802	2,246	173
11	Mar-04	4,900	400	72	17	342	233	664	61
12	Jun-04	10,000	2,300	210	2.8	690	514	1,417	< 10
13	Sep-04	7,200	2,300	340	< 2.5	840	75	1,255	< 10
14	Dec-04	11,000	3,900	180	5.1	780	695	1,660	< 10
15	Mar-05	4,600	1,900	69	< 2.5	300	206	575	< 10
16	Jun-05	1,400	590	85	< 0.5	110	8.2	203	< 2.0
17	Sep-05	12,000	3,100	220	< 1.0	840	762	1,822	< 4.0
18	Dec-05	2,500	2,100	120	< 2.5	260	16	396	< 10
19	Mar-06	2,200	1,300	27	< 2.5	130	5.2	162	< 10
20	Jun-06	3,700	1,900	170	< 1.0	230	14	414	< 4.0
21	Sep-06	3,600	2,100	80	< 0.5	230	8.8	319	< 2.0
22	Dec-06	6,000	3,500	83	< 1.0	260	16.4	359	< 4.0

Well MW-12									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Dec-05	1,300	700	< 0.5	< 0.5	33	5.6	39	< 2.0
2	Mar-06	1,100	540	< 0.5	< 0.5	8.5	1.5	10	49
3	Jun-06	680	400	< 0.5	< 0.5	5.8	1.4	7.2	< 2.0
4	Sep-06	910	480	< 0.5	< 0.5	9.9	1.5	11.4	21
5	Dec-06	770	230	< 0.5	< 0.5	7.4	2.0	9.4	< 2.0

**HISTORICAL SURFACE WATER ANALYTICAL RESULTS
REDWOOD REGIONAL PARK SERVICE YARD, OAKLAND, CALIFORNIA**


(all concentrations in ug/L, equivalent to parts per billion [ppb])


Sampling Location SW-1 (Upstream of Contaminated Groundwater Discharge Location SW-2)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Feb-94	50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
2	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
3	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	Aug-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Aug-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
9	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Sep-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
11	Apr-99	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
Sampling at this location discontinued after April 1999 with Alameda County Health Services Agency approval.									


Sampling Location SW-2 (Area of Historical Contaminated Groundwater Discharge)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	Feb-94	130	< 50	1.9	< 0.5	4.4	3.2	9.5	NA
2	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
3	Aug-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	May-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	Aug-96	200	< 50	7.5	< 0.5	5.4	< 0.5	13	NA
6	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Aug-97	350	130	13	0.89	19	11	44	NA
9	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
11	Sep-98	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
12	Apr-99	81	<50	2.0	< 0.5	2.5	1.3	5.8	2.3
13	Dec-99	1,300	250	10	1.0	47	27	85	2.2
14	Sep-00	160	100	2.1	< 0.5	5.2	1.9	9.2	3.4
15	Jan-01	< 50	< 50	< 0.5	< 0.5	0.53	< 0.5	0.5	< 2.0
16	Apr-01	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
17	Sep-01	440	200	2.1	< 0.5	17	1.3	20	10
18	Dec-01	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
19	Mar-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
20	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
21	Sep-02	220	590	10	< 0.5	13	< 0.5	23	< 2.0
22	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
23	Mar-03	< 50	< 50	< 0.5	< 0.5	0.56	< 0.5	0.56	2.8
24	Jun-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
25	Sep-03	190	92	2.1	< 0.5	4.2	< 0.5	6.3	< 2.0
26	Dec-03	86	< 100	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
27	Mar-04	<50	<100	<0.3	<0.3	1.1	<0.6	1.1	< 5.0
28	Jun-04	<50	<50	<0.5	<0.5	0.83	<0.5	0.83	< 2.0
29	Sep-04	260	370	4.4	<0.5	6.3	< 1.0	11	< 2.0
30	Dec-04	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
31	Mar-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
32	Jun-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
33	Sep-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
34	Dec-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
35	Mar-06	<50	62	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
36	Jun-06	<50	110	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
37	Sep-06	62	94	<0.5	<0.5	0.81	<0.5	0.8	< 2.0
38	Dec-06	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0

Sampling Location SW-3 (Downstream of Contaminated Groundwater Discharge Location SW-2)									
Event	Date	TVHg	TEHd	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	MTBE
1	May-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
2	Aug-95	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
3	May-96	< 50	74	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
4	Aug-96	69	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
5	Dec-96	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
6	Feb-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
7	Aug-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
8	Dec-97	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
9	Feb-98	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	NA
10	Sep-98	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
11	Apr-99	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
12	Dec-99	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
13	Sep-00	NS	NS	NS	NS	NS	NS	—	NS
14	Jan-01	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
15	Apr-01	< 50	<50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
16	Sep-01	NS	NS	NS	NS	NS	NS	—	NS
17	Dec-01	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
18	Mar-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
19	Jun-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	2.4
20	Sep-02	NS	NS	NS	NS	NS	NS	—	NS
21	Dec-02	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
22	Mar-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
23	Jun-03	< 50	< 50	< 0.5	< 0.5	< 0.5	< 0.5	—	< 2.0
24	Sep-03	NS	NS	NS	NS	NS	NS	—	NS
25	Dec-03	60	< 100	< 0.3	< 0.3	< 0.3	< 0.6	—	< 5.0
26	Mar-04	<50	<100	<0.3	<0.3	<0.6	<0.6	—	< 5.0
27	Jun-04	NS	NS	NS	NS	NS	NS	—	NS
28	Sep-04	NS	NS	NS	NS	NS	NS	—	NS
29	Dec-04	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
30	Mar-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
31	Jun-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
32	Sep-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
33	Dec-05	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
34	Mar-06	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
35	Jun-06	<50	120	<0.5	<0.5	<0.5	< 1.0	—	< 2.0
36	Sep-06	<50	120	<0.5	<0.5	<0.5	<0.5	—	7.8
37	Dec-06	<50	<50	<0.5	<0.5	<0.5	< 1.0	—	< 2.0

NS = Not Sampled (no surface water present during sampling event)








LEGEND & NOTES

- MW-1 Groundwater monitoring well MW-1
- ▲ SW-2 Area of discolored soil and creek soil and "grab" surface water sample location SW-2
- 1,000 — TVHg isoconcentration in µg/L
- 🌳 Tree
- Locations and dimensions of roads, trails, creek, and parking lot are approximate
- All concentrations in µg/L (micrograms per liter)
- UFST = Underground fuel storage tank
- NS = Not sampled
- ND = Not detected
- MTBE = Methyl tertiary butyl ether
- TVHg = Total volatile hydrocarbons – gasoline range
- TEHd = Total extractable hydrocarbons – diesel range
- BTEX = Benzene, toluene, ethylbenzene and total xylenes

0 20
Scale in feet



2006-17-08