

December 29, 2003

Mr. Scott O. Seery  
Alameda County Health  
Care Services Agency  
1131 Harbor Bay Parkway  
Suite 250  
Alameda, CA 94502-6577

Alameda County  
JAN 13 2004  
Environmental Health

**Subject: Fourth Quarter 2003 Groundwater Monitoring Report, 17715 Mission Boulevard, Hayward, California**


**Dear Mr. Seery:**

Enclosed please find a copy of 4<sup>th</sup> Quarter Groundwater Monitoring Report dated December 29, 2003, for the subject property. With my authorization, the work was performed by Sierra Environmental, Inc. (Sierra).

I Declare, under penalty of perjury, that the information and/or recommendations contained in the report is true and correct to the best of my knowledge.

Please call me at (925) 383-5131 if you have questions.

**Sincerely Yours,**



**Paul Garg  
ABE Petroleum LLC**

**FOURTH QUARTER 2003  
GROUNDWATER MONITORING**

**ABE Petroleum LLC  
17715 Mission Boulevard  
Hayward, California 94539**

**Prepared for  
Mr. Paul Garg  
ABE Petroleum LLC**

**Prepared by  
Sierra Environmental, Inc.**

**December 29, 2003  
Project 03-103.07**



**Sierra Environmental, Inc.**  
*Environmental Consultants*

**December 29, 2003**  
**Project 03-103.07**

**Mr. Paul Garg**  
**ABE Petroleum LLC**  
**33090 Mission Boulevard**  
**Union City, California 94587**

**Subject: Report for Fourth Quarter 2003 Groundwater Monitoring, ABE Petroleum LLC, 17715 Mission Boulevard, Hayward, California**

**Dear Mr. Garg:**

Sierra Environmental, Inc. (Sierra) is pleased to present this report summarizing the results of the Fourth quarter 2003 groundwater monitoring at the subject location, hereafter, referred to as Site. Figure 1 shows the Site location. The groundwater monitoring was concurred by Alameda County Health Care Services (ACHCS) in a letter dated February 16, 2000, as result of gasoline impact to groundwater beneath the Site.

On December 4, 2003, Sierra obtained and recorded groundwater data, and collected groundwater samples from three groundwater monitoring wells (MW1 through MW3) at the Site for chemical analysis. Sierra submitted the samples to Entech Analytical Labs, Inc. (Entech) of Santa Clara, California for chemical analysis. Entech is an independent State-certified analytical laboratory (# 2346).

## **BACKGROUND**

On September 16, 1997, Balch Petroleum Contractors & Builders, Inc. (Balch) of Milpitas, California, removed one 2,000-gallon, two 6,000-gallon, one 10,000-gallon single-wall steel gasoline, and one 500-gallon single-wall steel waste oil USTs from the Site. Former UST locations are shown in Figure 2. No hole or damage was observed in the tanks. No groundwater was encountered in the tank excavations. After UST removal, Sierra collected soil samples from the tank excavations for chemical analysis.

---

980 W. Taylor Street  
San Jose, CA 95126  
Phone (408) 971-6758  
Fax (408) 971-6759

---

Up to 2,300 parts per million (ppm) total petroleum hydrocarbons as gasoline (TPHG) was detected in the soil samples collected from beneath the tanks at approximately 14 feet below ground surface (bgs). The soil sample locations are shown in Figure 2.

On August 14, 2000, Sierra drilled three exploratory borings and converted them to groundwater monitoring well MW1 through MW3. The wells are approximately 35 feet deep. Sierra collected soil and groundwater samples from the borings/wells for chemical analysis. The analytical results showed up to 720 ppm TPHG, 2.2 ppm benzene, and 3.4 ppm MTBE in the soil samples. Up to 290000 ppb TPHG, 10000 ppb benzene, and 4300 ppb MTBE were detected in the groundwater samples. Gasoline constituents were detected in groundwater samples collected from all three monitoring wells. Groundwater monitoring well locations are shown on Figure 3.

On March 30, 2001, Sierra performed first quarter 2001 groundwater monitoring at the Site. The field and analytical results are presented in Table I and II. Groundwater was measured at approximately 20 to 21 feet from top of the well casing (TOC) at the Site with a northwesterly flow direction.

On June 22, 2001, Sierra performed second quarter 2001 groundwater monitoring at the Site. Groundwater levels were measured at approximately 22 to 23 feet below TOC with a northwesterly flow direction during this monitoring event.

On September 20, 2001, Sierra performed third quarter 2001 groundwater monitoring at the Site. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 24 to 25 feet below TOC with a northwesterly flow direction during this monitoring event.

On December 27, 2001, Sierra performed fourth quarter 2001 groundwater monitoring at the Site. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 22.59 to 23.82 feet below TOC with a northwesterly flow direction during this monitoring event.

On September 24, 2002, Sierra performed third quarter 2002 groundwater monitoring at the Site. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 23.69 to 24.89 feet below TOC with a northwesterly flow direction during this monitoring event.

On December 17, 2002, Sierra performed fourth quarter 2002 groundwater monitoring at the Site. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 22.75 to 23.99 feet below TOC with a northwesterly flow direction during this monitoring event.

On April 2, 2003, Sierra performed first quarter 2003 groundwater monitoring at the Site. Depth of groundwater was measured to the TOC. Groundwater levels were measured

at approximately 21.25 to 22.32 feet below TOC with a westerly flow direction during this monitoring event.

On June 12, 2003, Sierra performed second quarter 2003 groundwater monitoring at the site. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 20.64 to 20.94 feet below TOC with a westerly flow direction during this monitoring event.

Sierra prepared soil and Groundwater investigation plan and addendum to the plan dated May 27 and September 10, 2003 respectively for the site. The Addendum to the plan dated September 10, 2003 is being reviewed by ACHCS.

On September 29, 2003, Sierra performed third quarter 2003 groundwater monitoring at the site. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 22.95 to 24.15 feet below TOC with a westerly flow direction during this monitoring event.

## **GROUNDWATER MONITORING**

On December 4, 2003, Sierra performed third quarter 2003 groundwater monitoring at the Site. Sierra's field personnel measured the groundwater levels at MW1 through MW3 (Figure 3) using an electronic sounder. Depth of groundwater was measured to the TOC. Groundwater levels were measured at approximately 23.70 to 24.91 feet below TOC with a northwesterly flow direction during this monitoring event. Table I presents the groundwater measurement data.

Sierra's field personnel purged the wells using bailers. pH, temperature, and electrical conductivity of groundwater was recorded during the purging activities to affirm that groundwater in the wells have stabilized. After completion of the purging, groundwater samples MW-1 through MW-3 were collected from the wells. After collection, the groundwater from each well was transferred into clean volatile organic analysis (VOA) vials. The VOAs were sealed with Teflon-septum screw caps, labeled, placed in a cooler, and delivered to Entech with chain-of-custody documentation.

All sampling and measurement equipment were washed with Liqui-Nox® (a phosphate free laboratory detergent), and rinsed with tap water at each measurement and sampling interval. Purged and wash water was stored in 55-gallon drums at a designated location at the Site. Sierra's quality assurance/quality control (QA/QC) protocol is presented in Appendix A. Copies of the field notes are presented in Appendix B.

## **CHEMICAL ANALYSIS**

The samples were analyzed for TPHG using the United States Environmental Protection Agency (EPA) modified method 8015, and for benzene, toluene, ethyl benzene, and total xylenes (BTEX) and methyl tertiary butyl ether (MTBE) using EPA method 8020. Additionally, the samples were analyzed for fuel oxygenates using EPA method 8260B. Copies of certified analytical results and chain-of-custody documentation are presented in Appendix C.

## **ANALYTICAL RESULTS**

Table II presents Summary of the analytical results.

## **CONCLUSION**

The groundwater data obtained during this monitoring event show a consistent high concentrations of the gasoline constituents in the groundwater beneath the Site.

Sierra will proceed with the soil and groundwater investigation, after obtaining approval of its Addendum to Work Plan for Soil and Groundwater Investigation from ACHSA.

## **LIMITATIONS**


The content and conclusion provided by Sierra in this report are based on information collected during its assessment/monitoring, which include, but are not limited to field observations and analytical results for the groundwater samples collected at the Site.

Sierra assumes that the samples collected and laboratory results are reasonably representative of the whole Site, which may not be the case at unsampled areas.

This assessment/monitoring was performed in accordance with generally accepted principles and practices of environmental engineering and assessment in Northern California at the time of the work. This report presents our professional opinion based on our findings, technical knowledge, and experience working on similar projects. No warranty, either expressed or implied, is made. The conclusions presented are based on the analytical results and current regulatory requirements. We are not responsible for the impact of any changes in environmental standards or regulations in the future.

Please feel welcome to call us if you have questions.

**Very Truly Yours,**  
**Sierra Environmental, Inc.**



**Reza Baradaran, PE, GE**  
**Principal**

A handwritten signature in black ink, appearing to read "Reza Baradaran".

A handwritten signature in black ink, appearing to read "Mitch Hajiaghai".

**Mitch Hajiaghai, REA II, CAC**  
**Principal**

- Attachments:
- Table I - Groundwater Elevation Data
  - Table II - Analytical Results for Groundwater Samples
  - Figure 1 - Site Location Map
  - Figure 2 - Former UST and Soil Sample Locations
  - Figure 3 - Groundwater Monitoring Well Locations
  - Appendix A - QA/QC Protocol
  - Appendix B - Field Notes
  - Appendix C - Certified Analytical Results and Chain-of-Custody Documentation

cc: Mr.Scott O. Seery, ACHCS (1 Copy)

R02-103.06\4thQ2003GWMH12232003

**TABLE I  
GROUNDWATER ELEVATION DATA**

Well ID	Measurement Date	Well Casing Diameter (in)	Well Casing Elevation (ft)	Depth to Water <sup>1</sup> (ft)	Water Table <sup>2</sup> Elevation (ft)
MW1	8-18-00	2	99.46	20.32	79.14
	3-30-01			20.30	79.16
	6-22-01			21.91	77.55
	9-20-01			23.56	75.90
	12-27-01			22.59	76.87
	9-24-02			23.69	75.77
	12-17-02			22.75	76.71
	4-2-03			21.15	78.31
	6-12-03			20.64	78.82
	9-29-03			22.95	76.51
	12-04-03			23.70	75.76
MW2	8-18-00	2	100.58	21.55	79.03
	3-30-01			21.55	79.03
	6-22-01			23.15	77.43
	9-20-01			24.78	75.80
	12-27-01			23.82	76.76
	9-24-02			24.89	75.69
	12-17-02			23.99	76.59
	4-2-03			22.32	78.26
	6-12-03			21.84	78.74
	9-29-03			24.15	76.43
	12-04-03			24.91	75.67
MW3	8-18-00	2	99.69	20.68	79.01
	3-30-01			20.68	79.01
	6-22-01			22.31	77.38
	9-20-01			23.92	75.77
	12-27-01			22.95	76.74
	9-24-02			24.03	75.66
	12-17-02			23.09	76.60
	4-2-03			21.46	78.23
	6-12-03			20.99	78.70
	9-29-03			23.30	76.39
	12-04-03			24.05	75.64

1. Depths to groundwater were measured to the top of the well casings
2. Water table elevations were measured in relation to an assumed datum (100') relative elevation



**TABLE II  
ANALYTICAL RESULTS FOR GROUNDWATER SAMPLES**

Sample ID	Sample Date	Sample Location	TPHG <sup>1</sup> ppb <sup>3</sup>	Benzene ppb	Toluene ppb	Ethylbenzene ppb	Xylenes ppb	MTBE <sup>2</sup> ppb
MW-1	8-18-00	MW1	280,000	10,000	16,000	11,000	49,000	4,000
*	3-30-01		98,000	8,600	14,000	6,300	26,000	7,600
*	6-22-01		110,000	7,500	12,000	5,700	24,000	3,800
*	9-20-01		93,000	8,700	11,000	6,300	27,000	4,600
*	12-27-01		140,000	7,700	11,000	6,500	28,000	7,700
*	9-24-02		110,000	4,600	4,000	4,000	18,000	3,400
*	12-17-02		110,000	6,600	6,700	5,400	23,000	2,900
*	4-2-03		89,000	4,800	6,000	4,600	20,000	5,900
*	6-12-03		69,000	4,100	4,300	3,900	17,000	4,700
*	9-29-03		96,000	7,000	7,700	5,100	22,000	6,200
*	12-04-03		110,000	5,800	5,900	4,300	18,000	4,500
MW-2	8-18-00		MW2	290,000	3700	990	7,300	26,000
*	3-30-01	47,000		3,200	470	4,500	13,000	3,100
*	6-22-01	57,000		2,500	350	4,200	12,000	1,800
*	9-20-01	42,000		2,300	230	4,300	12,000	2,200
*	12-27-01	70,000		2,900	390	4,800	14,000	2,400
*	9-24-02	110,000		1,600	200	3,400	9,100	2,500
*	12-17-02	66,000		2,400	340	4,600	13,000	1,900
*	4-2-03	29,000		1,000	130	2,300	5,100	2,000
*	6-12-03	8,700		380	52	790	2,000	2,200
*	9-29-03	52,000		1,700	200	4,500	9,800	2,300
*	12-04-03	66,000		1,500	210	4,500	9,200	1,900
MW-3	8-18-00	MW3		46,000	3,200	550	3,700	14,000
*	3-30-01		30,000	3,300	340	2,800	9,100	4,700
*	6-22-01		35,000	4,000	340	2,900	7,600	4,100
*	9-20-01		30,000	3,800	260	2,500	6,600	5,300
*	12-27-01		39,000	4,400	340	3,000	6,700	5,500
*	9-24-02		53,000	4,100	270	3,100	6,600	6,400
*	12-17-02		40,000	3,600	240	2,200	5,700	5,200
*	4-2-03		24,000	2,000	130	1,800	3,300	3,000
*	6-12-03		26,000	2,700	180	2,000	4,200	5,500
*	9-29-03		39,000	4,000	220	3,200	5,300	4,800
*	12-04-03		40,000	3,200	180	2,200	4,300	4,400


1. TPHG = Total Petroleum Hydrocarbons as Gasoline

2. MTBE = Methyl Tertiary Butyl Ether

3. ppb = Parts Per Billion [ppb (µg/liter)]

4. ND = Not Detected

\* The Sample was analyzed for Fuel Oxygenates using EPA Method 8260B. Analytical result is for MTBE



Source: Hayward Quadrangle, California, 7.5-Minute Series (Topographic)

0' 1,000' 2,000'



**SIERRA ENVIRONMENTAL, INC.**  
Environmental Consultants

980 W. Taylor St., San Jose, CA 95126  
Phone [408]971-6758 • Fax [408] 971-6759

**Site Location Map**

**Fourth Quarter 2003 Groundwater Monitoring  
ABE Petroleum LLC**

**17715 Mission Boulevard • Hayward • California**

**FIGURE**

**1**


Dec 29, 2003  
Project 03-103.07

**LEGEND**

● T1-14



- 1 = 2,000-gallon Premium Unleaded Gasoline UST
- 2 = 6,000-Gallon Premium Unleaded Gasoline UST
- 3 = 6,000-Gallon Unleaded Plus Gasoline UST
- 4 = 500-gallon Waste Oil UST
- 5 = 10,000-gallon Regular Unleaded Gasoline UST



Approximate Scale: 1"=30'



**SIERRA ENVIRONMENTAL, INC.**  
Environmental Consultants

980 W. Taylor Street, San Jose, CA 95126  
Phone [408]248-3700 • Fax [408] 248-4700

Former UST and Soil Sample Locations

Fourth Quarter 2003 Groundwater Monitoring  
ABE Petroleum LLC




17715 Mission Boulevard • Hayward • California


FIGURE

**2**

December 29, 2003  
Project 03-103.07

**LEGEND**

-  MW-1 Groundwater Monitoring Well Location and Designation
-  Over-Head High Voltage Power Lines
-  Assumed Datum Elevation = 100'



Approximate Scale: 1" = 30'



**SIERRA ENVIRONMENTAL, INC.**  
Environmental Consultants

980 W. Taylor St., San Jose, CA 95128  
Phone [408]971-6758 • Fax [408] 971-6759

**Groundwater Monitoring Well Locations**  
**Fourth Quarter 2003 Groundwater Monitoring**  
**ABE Petroleum LLC**  
**17715 Mission Boulevard • Hayward • California**

**FIGURE**  
**3**  
 December 29, 2003  
 Project 03-103.07

**Appendix A**  
**QA/QC PROTOCOL**

## **QA/QC PROTOCOL**

### **Groundwater Level and Well Depth Measurements**

Groundwater level and well depths are measured using electrical sounder. An electrical sounder consists of a reel, two-conductor cable, a water sensor, and a control panel with a buzzer. To measure groundwater level, the sensor is lowered into a well. A low current circuit is completed when the sensor makes contact with water. The current in the circuit is then amplified and activates a buzzer which produce an audible signal. Cable markings are divided at 0.05-foot increments. Well depths are measured to the nearest 0.01 foot. Groundwater levels are measured before and after sample collection to ensure data accuracy.

### **Well Purging**

Low flow submersible electrical pumps or bailers are used to purge groundwater monitoring wells. Approximately 3 to 5 well casing volume of water is removed from the well as a measure to stabilize natural, and representative groundwater in each well. pH, electrical conductivity, and temperature of the purged water is measured and recorded at approximately each casing volume interval. Purge water is stabilized when pH is recorded within 0.5 unit, electrical conductivity is within 5 percent, and temperature is within 1.0 degree Celsius.

### **Groundwater Sampling**

Groundwater samples are transferred into appropriate containers provided by certified analytical laboratories. The containers include proper preservatives, and labels with appropriate project information. Groundwater is transferred into the containers with as little agitation as possible. After collection, containers are sealed and checked to ensure that no head space or air bubbles are present in the sample.

After collection, if required, samples are kept in a cooler to be delivered to analytical laboratory with chain-of-custody documentation.

### **Equipment Decontamination**

All sampling equipment are washed with Liqui-Nox<sup>®</sup> (a phosphate free laboratory detergent), and rinsed with tap water before each sampling event, and at each sampling interval. To reduce the risk of cross contamination, wells which have shown lower levels of contamination historically are purged and sampled first.

## **Analytical Procedures**

Samples are analyzed by an accredited State-certified analytical laboratory using procedures prescribed by United State Environmental Protection Agency (EPA) and other Federal, State, and Local agencies. At minimum a field blank is analyzed with each group of samples for quality assurance measures. At minimum two qualified personnel review analytical results and compare them with historical data for consistency and accuracy.

## **Field Reports**

All field observations are documented in field reports. A field report contain project information, climatic condition, contractor/subcontractor information, field observation, discussions and communications during each particular field activity. Field reports are stored in appropriate project files. Project managers review field reports to obtain necessary information regarding the status of each project on daily basis.

**Appendix B**  
**FIELD NOTES**



**Appendix B**  
**FIELD NOTES**



GROUNDWATER MONITORING DATA FORM

Project No: 03-103 07

Date: 12/4/03

Project Name: ABE

Well No: MW1

Field Personnel: Mike Hagi

Weather: Cloudy

Project Location: 17715 Mission Blvd., Hayward

PURGE WATER VOLUME CALCULATION	Total Well Depth (ft)	Depth to Water (ft)	Water Column (ft)	Multiplier Casing Diameter			Casing Volume (gal)	Purged Volume (gal)
				2"	4"	6"		
	<del>20.25</del> 33.25	23.70	9.55	0.16	0.64	1.44	1.5 g	4.5 g

Purge Method: \_\_\_\_\_ Measuring Reference: \_\_\_\_\_

Time						
Volume Purged (gal)		0	1.5	3.0	4.5	
Temperature (° F)		68.7	67.1	68.2	68.5	
pH		5.95	5.86	5.75	5.83	
Specific Conductivity (umhos/cm)		4500	4700	4700	4800	
Turbidity/Color		light green	→	→	→	
Odor		yes	→	→	→	

Comments: HC odor and streaks



GROUNDWATER MONITORING DATA FORM

Project No: 03-103 07

Date: 12/4/03

Project Name: ABE

Well No: MW2

Field Personnel: Mike Hargi

Weather: cloudy

Project Location: 17715 Mission Blvd, Hayward

PURGE WATER VOLUME CALCULATION	Total Well Depth (ft)	Depth to Water (ft)	Water Column (ft)	Multiplier Casing Diameter			Casing Volume (gal)	Purged Volume (gal)
				2"	4"	6"		
	<del>33.75</del> 33.75	24.91	8.8	0.16	0.64	1.44	1.41	4.24 x 4.5

Purge Method: Bailer Measuring Reference: TOC

Time						
Volume Purged (gal)		0	1.5	3.0	4.5	
Temperature (° F)		66.8	67.0	67.3	67.9	
H		5.80	5.85	5.91	5.93	
Specific Conductivity (umhos/cm)		4400	4300	4500	→	
Turbidity/Color		light grey	→	→	→	
odor		yes	→	→	→	

Comments: HC odor



GROUNDWATER MONITORING DATA FORM

Project No: 03-103 67

Date: 12/4/03

Project Name: ABE

Well No: MW-3

Field Personnel: Mike/MAR

Weather: Cloudy

Project Location: 17715 Mission Blvd, Hayward

PURGE WATER VOLUME CALCULATION	Total Well Depth (ft)	Depth to Water (ft)	Water Column (ft)	Multiplier Casing Diameter			Casing Volume (gal)	Purged Volume (gal)
				2"	4"	6"		
	<del>28.25</del> 33.75	24.05	9.70	0.16	0.64	1.44	1.62	4.6 25.0

Purge Method: \_\_\_\_\_ Measuring Reference: \_\_\_\_\_

Time						
Volume Purged (gal)		0	1.5	3.0	5.0	
Temperature (° F)		67.6	66.6	66.2	66.4	
pH		5.54	5.70	5.81	5.90	
Specific Conductivity (umhos/cm)		4700	5200	5100	5400	
Turbidity/Color		4 FTO grey	→	→	→	
Odor		yes	→	→	→	

Comments: smells like the odor and sheens

**Appendix C**  
**CERTIFIED ANALYTICAL REPORTS AND**  
**CHAIN-OF-CUSTODY DOCUMENTATION**

# Entech Analytical Labs, Inc.

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

December 18, 2003

Mitch Hajlaghai  
Sierra Environmental, Inc.  
980 West Taylor Street  
San Jose, CA 95126

**Order:** 36867  
**Project Name:** ABE  
**Project Number:** 03-103 07  
**Project Notes:**

**Date Collected:** 12/04/03  
**Date Received:** 12/04/03  
**P.O. Number:** 03-103 07

On December 04, 2003, samples were received under documented chain of custody. Results for the following analyses are attached:

<u>Matrix</u>	<u>Test</u>	<u>Method</u>
Liquid	EDF Deliverables	EDF
	Gas/BTEX	EPA 8015 MOD. (Purgeable)
		EPA 8020
	Oxygenates by EPA 8260B	EPA 8260B

Chemical analysis of these samples has been completed. Summaries of the data are contained on the following pages. USEPA protocols for sample storage and preservation were followed.

Entech Analytical Labs, Inc. is certified by the State of California (#2346). If you have any questions regarding procedures or results, please call me at 408-588-0200.

Sincerely,



Patti Sandrock  
QA/QC Manager

# Entech Analytical Labs, Inc.

3334 Victor Court, Santa Clara, CA 95054 Phone: (408) 588-0200 Fax: (408) 588-0201

Sierra Environmental, Inc.  
 980 West Taylor Street  
 San Jose, CA 95126  
 Attn: Mitch Hajiaghai

Date: 12/8/03  
 Date Received: 12/4/03  
 Project Name: ABE  
 Project Number: 03-103 07  
 P.O. Number: 03-103 07  
 Sampled By: Client

## Certified Analytical Report

Order ID: 36867

Lab Sample ID: 36867-001

Client Sample ID: MW-1

Sample Time:

Sample Date: 12/4/03

Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	5800		500	0.5	250	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Toluene	5900		500	0.5	250	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Ethyl Benzene	4300		500	0.5	250	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Xylenes, Total	18000		500	1	500	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Surrogate							Surrogate Recovery		Control Limits (%)	
4-Bromofluorobenzene							107.8		65 - 135	

Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	110000		500	50	25000	µg/L	N/A	12/5/03	WGC43007B	EPA 8015 MOD. (Purgeable)
Surrogate							Surrogate Recovery		Control Limits (%)	
4-Bromofluorobenzene							118.3		65 - 135	

Comment:

DF = Dilution Factor      ND = Not Detected      DLR = Detection Limit Reported      PQL = Practical Quantitation Limit  
 Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

    Ja              12, 9, 03              [Signature]              12/9/03      
 Analyst                      Date                      Supervisor                      Date

Environmental Analysis Since 1983

# Entech Analytical Labs, Inc.

3334 Victor Court , Santa Clara, CA 95054 Phone: (408) 588-0200 Fax: (408) 588-0201

Sierra Environmental, Inc.  
 980 West Taylor Street  
 San Jose, CA 95126  
 Attn: Mitch Hajiaghai

Date: 12/15/03  
 Date Received: 12/4/2003  
 Project Name: ABE  
 Project Number: 03-103 07  
 P.O. Number: 03-103 07  
 Sampled By: Client

## Certified Analytical Report

Order ID: 36867

Lab Sample ID: 36867-001

Client Sample ID: MW-1

Sample Time:

Sample Date: 12/4/2003

Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Analysis Date	QC Batch ID	Method
Diisopropyl Ether	ND		100	5	500	µg/L	12/10/2003	WMS510408	EPA 8260B
Ethyl-t-butyl Ether	ND		100	5	500	µg/L	12/10/2003	WMS510408	EPA 8260B
Methyl-t-butyl Ether	4500		100	1	100	µg/L	12/10/2003	WMS510408	EPA 8260B
tert-Amyl Methyl Ether	ND		100	5	500	µg/L	12/10/2003	WMS510408	EPA 8260B
tert-Butanol (TBA)	ND		100	10	1000	µg/L	12/10/2003	WMS510408	EPA 8260B

Surrogate	Surrogate Recovery	Control Limits (%)
4-Bromofluorobenzene	77.8	68 - 118
Dibromofluoromethane	87.8	57 - 156
Toluene-d8	92.8	77 - 150

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Analyzed by: [Signature]

Reviewed by: [Signature]



# Entech Analytical Labs, Inc.

3334 Victor Court, Santa Clara, CA 95054 Phone: (408) 588-0200 Fax: (408) 588-0201

Sierra Environmental, Inc.  
 980 West Taylor Street  
 San Jose, CA 95126  
 Attn: Mitch Hajiaghai

Date: 12/8/03  
 Date Received: 12/4/03  
 Project Name: ABE  
 Project Number: 03-103 07  
 P.O. Number: 03-103 07  
 Sampled By: Client

## Certified Analytical Report

Order ID: 36867

Lab Sample ID: 36867-002

Client Sample ID: MW-2

Sample Time:

Sample Date: 12/4/03

Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method	
Benzene	1500		100	0.5	50	µg/L	N/A	12/5/03	WGC43007B	EPA 8020	
Toluene	210		100	0.5	50	µg/L	N/A	12/5/03	WGC43007B	EPA 8020	
Ethyl Benzene	4500		100	0.5	50	µg/L	N/A	12/5/03	WGC43007B	EPA 8020	
Xylenes, Total	9200		100	1	100	µg/L	N/A	12/5/03	WGC43007B	EPA 8020	
Surrogate							Surrogate Recovery		Control Limits (%)		
							4-Bromofluorobenzene		129.8		65 - 135
							aaa-Trifluorotoluene		.0		65 - 135

Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method	
TPH as Gasoline	66000		100	50	5000	µg/L	N/A	12/5/03	WGC43007B	EPA 8015 MOD. (Purgeable)	
Surrogate							Surrogate Recovery		Control Limits (%)		
							4-Bromofluorobenzene		180.9		65 - 135
							aaa-Trifluorotoluene		92.0		65 - 135

Comment: High surrogate recovery for 4-BFB due to matrix interference. See TFT results.

DF - Dilution Factor

ND = Not Detected

DLR = Detection Limit Reported

PQL = Practical Quantitation Limit

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Ja  
 Analyst

12/9/03  
 Date

WLS  
 Supervisor

12/9/03  
 Date

Environmental Analysis Since 1983

# Entech Analytical Labs, Inc.

3334 Victor Court , Santa Clara, CA 95054 Phone: (408) 588-0200 Fax: (408) 588-0201

Sierra Environmental, Inc.  
980 West Taylor Street  
San Jose, CA 95126  
Attn: Mitch Hajiaghai

Date: 12/15/03  
Date Received: 12/4/2003  
Project Name: ABE  
Project Number: 03-103 07  
P.O. Number: 03-103 07  
Sampled By: Client

## Certified Analytical Report

Order ID: 36867

Lab Sample ID: 36867-002

Client Sample ID: MW-2

Sample Time:

Sample Date: 12/4/2003

Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Analysis Date	QC Batch ID	Method
Diisopropyl Ether	ND		200	5	1000	µg/L	12/10/2003	WMS510408	EPA 8260B
Ethyl-t-butyl Ether	ND		200	5	1000	µg/L	12/10/2003	WMS510408	EPA 8260B
Methyl-t-butyl Ether	1900		200	1	200	µg/L	12/10/2003	WMS510408	EPA 8260B
tert-Amyl Methyl Ether	ND		200	5	1000	µg/L	12/10/2003	WMS510408	EPA 8260B
tert-Butanol (TBA)	ND		200	10	2000	µg/L	12/10/2003	WMS510408	EPA 8260B

Surrogate	Surrogate Recovery	Control Limits (%)
4-Bromofluorobenzene	73.9	68 - 118
Dibromofluoromethane	85.3	57 - 156
Toluene-d8	94.1	77 - 150

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Analyzed by:                     Reviewed by:

# Entech Analytical Labs, Inc.

3334 Victor Court, Santa Clara, CA 95054 Phone: (408) 588-0200 Fax: (408) 588-0201

Sierra Environmental, Inc.  
 980 West Taylor Street  
 San Jose, CA 95126  
 Attn: Mitch Hajiaghai

Date: 12/8/03  
 Date Received: 12/4/03  
 Project Name: ABE  
 Project Number: 03-103 07  
 P.O. Number: 03-103 07  
 Sampled By: Client

## Certified Analytical Report

Order ID: 36867      Lab Sample ID: 36867-003      Client Sample ID: MW-3  
 Sample Time:      Sample Date: 12/4/03      Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
Benzene	3200		200	0.5	100	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Toluene	180		200	0.5	100	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Ethyl Benzene	2200		200	0.5	100	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
Xylenes, Total	4300		200	1	200	µg/L	N/A	12/5/03	WGC43007B	EPA 8020
			Surrogate				Surrogate Recovery		Control Limits (%)	
			4-Bromofluorobenzene				114.1		65 - 135	

Parameter	Result	Flag	DF	PQL	DLR	Units	Extraction Date	Analysis Date	QC Batch ID	Method
TPH as Gasoline	40000		200	50	10000	µg/L	N/A	12/5/03	WGC43007B	EPA 8015 MOD. (Purgeable)
			Surrogate				Surrogate Recovery		Control Limits (%)	
			4-Bromofluorobenzene				123.8		65 - 135	

DF = Dilution Factor      ND = Not Detected      DLR = Detection Limit Reported      PQL = Practical Quantitation Limit  
 Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Jc      12/9/03      MJ      12/9/03  
 Analyst      Date      Supervisor      Date

Environmental Analysis Since 1983

**Entech Analytical Labs, Inc.**

3334 Victor Court , Santa Clara, CA 95054 Phone: (408) 588-0200 Fax: (408) 588-0201

Sierra Environmental, Inc.  
 980 West Taylor Street  
 San Jose, CA 95126  
 Attn: Mitch Hajiaghai

Date: 12/15/03  
 Date Received: 12/4/2003  
 Project Name: ABE  
 Project Number: 03-103 07  
 P.O. Number: 03-103 07  
 Sampled By: Client

**Certified Analytical Report**

Order ID: 36867

Lab Sample ID: 36867-003

Client Sample ID: MW-3

Sample Time:

Sample Date: 12/4/2003

Matrix: Liquid

Parameter	Result	Flag	DF	PQL	DLR	Units	Analysis Date	QC Batch ID	Method
Diisopropyl Ether	ND		100	5	500	µg/L	12/10/2003	WMS510408	EPA 8260B
Ethyl-t-butyl Ether	ND		100	5	500	µg/L	12/10/2003	WMS510408	EPA 8260B
Methyl-t-butyl Ether	4400		100	1	100	µg/L	12/10/2003	WMS510408	EPA 8260B
tert-Amyl Methyl Ether	ND		100	5	500	µg/L	12/10/2003	WMS510408	EPA 8260B
tert-Butanol (TBA)	ND		100	10	1000	µg/L	12/10/2003	WMS510408	EPA 8260B

Surrogate	Surrogate Recovery	Control Limits (%)
4-Bromofluorobenzene	72.0	68 - 118
Dibromofluoromethane	83.5	57 - 156
Toluene-d8	94.6	77 - 150

Analysis performed by Entech Analytical Labs, Inc. (CA ELAP #2346)

Analyzed by: UspReviewed by: 2

### Quality Control Results Summary

QC Batch #: WMS510408  
 Matrix: Liquid

Units: µg/L  
 Date Analyzed: 12/10/03

Parameter	Method	Blank Result	Spike Sample ID	Spike Amount	Sample Result	Spike Result	QC Type	% Recovery	RPD	RPD Limits	Recovery Limits
<b>Test: Oxygenates by EPA 8260B</b>											
Methyl-t-butyl Ether	EPA 8260B	ND		20		21	LCS	105.0			58.0 - 127.0
			<b>Surrogate</b>		<b>Surrogate Recovery</b>		<b>Control Limits (%)</b>				
			4-Bromofluorobenzene		100.2		68 - 118				
			Dibromofluoromethane		93.6		57 - 156				
			Toluene-d8		91.3		77 - 150				
<b>Test: Oxygenates by EPA 8260B</b>											
Methyl-t-butyl Ether	EPA 8260B	ND		20		20.8	LCSD	104.0	0.96	25.00	58.0 - 127.0
			<b>Surrogate</b>		<b>Surrogate Recovery</b>		<b>Control Limits (%)</b>				
			4-Bromofluorobenzene		99.3		68 - 118				
			Dibromofluoromethane		96.0		57 - 156				
			Toluene-d8		90.9		77 - 150				

# Entech Analytical Labs, Inc.

3334 Victor Court • Santa Clara, CA 95054 • (408) 588-0200 • Fax (408) 588-0201

## Quality Control Results Summary

QC Batch #: WGC43007B  
Matrix: Liquid

Units: µg/L  
Date Analyzed: 12/05/03

Parameter	Method	Blank Result	Spike Sample ID	Spike Amount	Sample Result	Spike Result	QC Type	% Recovery	RPD	RPD Limits	Recovery Limits
<b>Test:</b> TPH as Gasoline											
TPH as Gasoline	EPA 8015 M	ND		250		253	LCS	101.2			65.0 - 135.0
			<b>Surrogate</b>	<b>Surrogate Recovery</b>		<b>Control Limits (%)</b>					
			4-Bromofluorobenzene	82.7		65 - 135					
<b>Test:</b> BTEX											
Benzene	EPA 8020	ND		8		7.04	LCS	88.0			65.0 - 135.0
Ethyl Benzene	EPA 8020	ND		8		7.9	LCS	98.8			65.0 - 135.0
Toluene	EPA 8020	ND		8		7.29	LCS	91.1			65.0 - 135.0
Xylenes, total	EPA 8020	ND		24		23	LCS	95.8			65.0 - 135.0
			<b>Surrogate</b>	<b>Surrogate Recovery</b>		<b>Control Limits (%)</b>					
			4-Bromofluorobenzene	99.7		65 - 135					
<b>Test:</b> TPH as Gasoline											
TPH as Gasoline	EPA 8015 M	ND		250		251.6	LCSD	100.6	0.55	25.00	65.0 - 135.0
			<b>Surrogate</b>	<b>Surrogate Recovery</b>		<b>Control Limits (%)</b>					
			4-Bromofluorobenzene	86.4		65 - 135					
<b>Test:</b> BTEX											
Benzene	EPA 8020	ND		8		7.22	LCSD	90.3	2.52	25.00	65.0 - 135.0
Ethyl Benzene	EPA 8020	ND		8		7.82	LCSD	97.8	1.02	25.00	65.0 - 135.0
Toluene	EPA 8020	ND		8		7.42	LCSD	92.8	1.77	25.00	65.0 - 135.0
Xylenes, total	EPA 8020	ND		24		23.4	LCSD	97.5	1.72	25.00	65.0 - 135.0
			<b>Surrogate</b>	<b>Surrogate Recovery</b>		<b>Control Limits (%)</b>					
			4-Bromofluorobenzene	99.9		65 - 135					



CHAIN OF CUSTODY

Project Name: ABE Project No: 03-103 27 Date: 12-4-03

Project Location: 17715 Mission Blvd., Hayward Client: ABE Sampler: Mike Hagi

Sample ID	Date Sampled	Sampling Time	Matrix	Nº of Containers	Analysis Requested							Turnaround Time		
					8015/8020 TPHG BTEX, MMBE	8016 TPHD	418.1 TRPH	8010 VOCs	8270 SVOCs	BTEX 8020	8210 LSP Fugate 8260	24-hour Other		
MW-1	12/04/03		Water	4	X				36867-001			X	24-hour Other	Normal
MW-2	X		X	X	X					002		X	24-hour Other	Normal
MW-3	X		X	X	X					003		X	24-hour Other	Normal
													24-hour Other	Normal
													24-hour Other	Normal
													24-hour Other	Normal
													24-hour Other	Normal

Remarks:

Relinquished by Mohammed Hagi Date 12/04/03 Time 2:30 Received by Maachado Date 12/4/03 Time 2:30

1670 Newhall St. • Suite 212 • Santa Clara • California • 95050  
Phone (408) 248-3700 • Fax (408) 248-4700