



April 10, 2017

Mr. Martin Musonge
Regional Water Quality Control Board
San Francisco Bay Region
1515 Clay Street, Suite 1400
Oakland, California 94612

RECEIVED

By Alameda County Environmental Health 8:51 am, Apr 11, 2017

Subject: **File No. 01-0098 (MYM)**

Site Located at 2844 Mountain Boulevard, Oakland, California

Dear Mr. Musonge:

Enclosed for your review is SOMA's "First Quarter 2017 Groundwater Monitoring Report" for the subject property. It has been uploaded to the State's GeoTracker database and Alameda County's FTP site.

Thank you for your time in reviewing our report. Please do not hesitate to call me at (925) 734-6400, if you have any questions or comments.

Sincerely,

A handwritten signature in blue ink, appearing to read "Dilan Roe". Above the signature is a short horizontal line and a larger, more elaborate blue ink signature that appears to read "Mansour Sepehr".

Mansour Sepehr, Ph.D., PE
Principal Hydrogeologist

cc: Mr. Tejindar Singh w/enclosure
Ms. Dilan Roe – Alameda County Env. Health



**First Quarter 2017
Groundwater Monitoring Report**

**2844 Mountain Boulevard
Oakland, California
Regional Board File Number 01-0098**

April 10, 2017

Project 5081

Prepared for

**Tejindar Singh
6400 Dublin Blvd.
Dublin, California, 94568**

ACKNOWLEDGEMENT STATEMENT

Site Location: 2844 Mountain Boulevard, Oakland, California


"I have read and acknowledge the content, recommendations and/or conclusions contained in the attached document or report submitted on my behalf to ACDEH's FTP server and the SWRCB's Geotracker website."



Tejindar Singh
6400 Dublin Boulevard
Dublin, California 94568
Responsible Party

CERTIFICATION

SOMA Environmental Engineering, Inc. has prepared this report on behalf of Tejindar Singh, property owner of 2844 Mountain Blvd., Oakland, California, to comply with requirements of the San Francisco Bay Regional Water Quality Control Board for the First Quarter 2017 groundwater monitoring event.



Mansour Sepehr, PhD, PE
Principal Hydrogeologist



TABLE OF CONTENTS

CERTIFICATION	i
TABLE OF CONTENTS.....	ii
LIST OF FIGURES	iii
LIST OF TABLES.....	iii
LIST OF APPENDICES	iii
1. INTRODUCTION	1
1.1 Previous Activities	1
1.2 Summary of Field Activities and Laboratory Analysis	3
1.2.1 Field Activities	3
1.2.2 Laboratory Analysis	3
2. RESULTS	3
2.1 Field Measurements	3
2.2 Laboratory Analysis	4
3. CONCLUSIONS AND RECOMMENDATIONS.....	5
4. REPORT LIMITATIONS	6

LIST OF FIGURES

- Figure 1 Site Vicinity Map
- Figure 2 Site Map Showing Locations of Former USTs, Soil Borings, and Groundwater Monitoring Wells
- Figure 3 Groundwater Elevation Contour Map in feet, March 18, 2017
- Figure 4 Map Showing TPH-g and Benzene Concentrations in Groundwater, March 18, 2017
- Figure 5 Contour Map Showing Current MtBE Concentrations in Groundwater
- Figure 6 Contour Map Showing Current TBA Concentrations in Groundwater
- Figure 7 Contour Map Showing Current TAME Concentrations in Groundwater

LIST OF TABLES

- Table 1 Historical Groundwater Analytical Results

LIST OF APPENDICES

- Appendix A Standard Operating Procedures for Conducting Groundwater Monitoring Activities
- Appendix B Tables of Elevations and Coordinates on Wells, Field Measurements of Physical and Chemical Parameters of the Groundwater Samples and Groundwater Gradient Calculations
- Appendix C Laboratory Report and Chain of Custody Form

1. INTRODUCTION

SOMA Environmental Engineering, Inc. (SOMA) has prepared this report on behalf of Mr. Tejindar Singh, property owner of 2844 Mountain Blvd., Oakland, California. The site is located east of Highway 13 and west of Joaquin Miller Park (Figure 1). Former underground storage tank (UST) locations and site features are shown in Figure 2.

This report summarizes results of the First Quarter 2017 groundwater monitoring event conducted at the site on March 18, 2017. It includes physical and chemical properties measured in the field for each groundwater sample and laboratory analytical results for groundwater samples. This monitoring event was conducted based on an email directive from the San Francisco Regional Water Quality Control Board (SFRWQCB) dated March 22, 2017 requesting quarterly groundwater monitoring events until the site obtains closure.

1.1 Previous Activities

In March 1989 soil contamination was identified during replacement of product lines. Analytical results for a soil sample collected from the southern edge of a premium unleaded tank reported total petroleum hydrocarbons (TPHs) as gasoline (TPH-g) concentration of 8,400 mg/kg. Samples from beneath the lines near the pump islands reported TPH concentrations of less than 100 mg/kg.

In July 1989, contaminated soil was excavated and from the area of the southern end of the premium unleaded UST disposed of. Analysis of 12 soil samples collected from the sides of the excavation reported TPH concentrations ranging between ND to 3,300 mg/kg.

In May 1990, further site investigation including installation of four monitoring wells (RS-1 through RS-4) was conducted. Analysis of soil samples collected above the water table reported TPH concentrations ranging from 1 to 240 mg/kg. Hydrocarbons were detected in groundwater samples collected from all the wells; the highest concentration was found in a sample monitoring well RS-2.

In June 1991 soil vapor extraction began in June 1991. Groundwater remediation began in October 1992. Remediation was suspended in 1992, apparently due to responsible party financial issues.

In April 1994, one 280-gallon waste oil UST was removed with approximately 280 gallons of fluid and rinsate. The site operated as a retail gasoline station. Three USTs, two pump islands and an office/garage building were among the site features. The USTs contained various grades of unleaded gasoline and diesel with storage capacities of 3,000, 4,000, and 10,000 gallons.

In 1996 free product was reported in RS-1.

In July 1998, one 4,000-gallon gasoline UST was excavated and disposed of off-site.

Between July 29 and August 18, 2011, two USTs, one 10,000 gallon and one 3,000 gallon capacity, were excavated and disposed of off-site. The site is currently fenced in, which limits public access to the property.

Further soil and groundwater investigation was conducted at the site in March 2012. In October 2012, two wells (RS-1 and RS-2) were decommissioned in anticipation of excavation activities onsite. Excavation activities commenced on October 3, 2012, and an area of approximately 1,200 square feet was excavated to a depth of 15 feet. A total of 788.65 tons of waste soil was removed and replaced with clean fill material.

On May 9 and 10, 2013, two groundwater monitoring wells (MW-1 and MW-2) and soil and groundwater borings (DPT-5/5W) were installed as approved and requested by the San Francisco Bay Regional Water Quality Control Board (SFRWQCB). All site wells were surveyed by a licensed surveyor on May 28, 2013.

Based on the success of a multi-phase extraction (MPE) pilot test conducted at the site in December 2013, SFRWQCB approved an extended MPE event. This event was conducted at the site from September 17, 2014 to November 5, 2014. Details and results of this event are documented in SOMA's report dated December 12, 2014.

Based on SFRWQCB's approval, SOMA installed an additional MPE well (MW-3) on May 1, 2015, in the vicinity of historical groundwater sample T-1, where high contaminant concentrations were observed during UST removal of August 2011. An extended MPE event was conducted utilizing this well and other site wells during May and June 2015.

SOMA submitted a workplan on December 4, 2015 for delineation of horizontal and vertical extent of soil and groundwater contamination of MtBE and TBA. This workplan was approved on February 11, 2016. Therefore, in March 2016, SOMA advanced four soil borings (DPT-6 through DPT-9) for collection of soil and groundwater samples. Results and recommendations are documented in SOMA's 'Additional Site Investigation Report' report dated April 14, 2016.

1.2 Summary of Field Activities and Laboratory Analysis

1.2.1 Field Activities

On March 18, 2017, five monitoring wells (RS-3, RS-4, MW-1, MW-2, and MW-3) were measured for depth to groundwater. Additional field measurements and groundwater samples were collected from all five wells. Properties measured in the field were pH, temperature, and electrical conductivity (EC). This monitoring event was conducted in accordance with procedures and guidelines of SFBRWQCB.

Figure 2 shows well locations. Appendix A details groundwater monitoring procedures followed during this event.

Purged groundwater was temporarily stored and secured on-site in 55-gallon drums pending transport to an appropriate disposal facility.

1.2.2 Laboratory Analysis

Groundwater samples were submitted to a California state-certified laboratory Curtis and Tompkins Laboratories, for the following analysis:

- TPH-g (gasoline by EPA Method 8260),
- BTEX (benzene, toluene, ethylbenzene, and total xylenes), MtBE, gasoline oxygenates (by EPA Method 8260).

2. RESULTS

Results of field measurements and laboratory analyses for the groundwater monitoring event conducted on March 18, 2017 follow below.

2.1 Field Measurements

Monitoring wells MW-1, MW-2, MW-3, RS-3 and RS-4 were measured for depth to groundwater (Table 1). Depths to groundwater ranged from 4.65 feet in RS-3 to 7.63 feet in RS-4. Groundwater elevations ranged from 667.64 feet in RS-4 to 671.43 feet in RS-3.

Figure 3 displays the groundwater elevation map. The groundwater flows southeasterly at a gradient of 0.08 ft/ft. Since the previous monitoring event (November 2016), the groundwater flow direction has remained the same and gradient has increased. Groundwater gradient calculations are included in Appendix B.

2.2 Laboratory Analysis

Groundwater analytical data for this monitoring event is shown in Table 1. Appendix C includes the laboratory report and chain of custody form. No measurable floating product was observed during this monitoring event.

TPH-g was detected in MW-1 at 920 µg/L and was below laboratory-reporting limit in other groundwater samples. Since the previous monitoring event (November 2016), TPH-g concentrations increased in MW-1 and remained below laboratory-reporting limits in RS-3, RS-4, MW-2, and MW-3. Figure 4 shows a map of TPH-g concentrations in groundwater. The TPH-g plume appears to be centered in the vicinity of the pump islands around MW-1.

TPH-d was not analyzed during this monitoring event due to low concentrations detected during the previous monitoring event. Samples for the analysis of TPH-d will be collected during the next monitoring event.

The following BTEX concentrations were observed during this monitoring event:

- All BTEX analytes were below laboratory-reporting limits in RS-3, RS-4, MW-1, and MW-3.
- Benzene was detected in MW-2 at 10 µg/L. Other BTEX analytes were below laboratory-reporting limits in this sample.
- Since the previous monitoring event (November 2016) benzene has slightly increased in MW-2. Figure 4 shows a map of benzene concentrations in groundwater. The benzene plume appears to be centered to the south of the pump islands in the vicinity of MW-2.

Methyl tertiary-butyl ether (MtBE) was below laboratory reporting-limits in RS-3 and was detected at concentrations ranging from 34 µg/L in MW-1 to 820 µg/L in RS-4. Since the previous monitoring event (November 2016), MtBE has increased in RS-4, MW-1, MW-2, and MW-3.

Figure 5 shows a contour map of current MtBE concentrations in groundwater. This figure includes the results of First Quarter 2017 groundwater monitoring event as well as the results of recent site investigations. As illustrated, high MtBE concentrations were detected in on-site and off-site borings during recent site investigations. The MtBE plume appears to be centered in the southwestern corner of the site.

Tertiary-butyl alcohol (TBA) was below laboratory-reporting limit in RS-3. Detectable TBA concentrations ranged from 140 µg/L in MW-3 to 33,000 µg/L in RS-4. Since the previous monitoring event (November 2016), TBA increased in RS-4, MW-1, MW-2 and MW-3. The increase was significant in RS-4 and MW-2.

Figure 6 shows a contour map of current TBA concentrations in groundwater. Similar to MtBE, this figure includes the results of First Quarter 2017 groundwater

monitoring event as well as the results of recent site investigations. As illustrated, high TBA concentrations were detected in on-site and off-site borings during recent site investigations. The TBA plume appears to be centered in the southwestern corner of the site.

Tertiary amyl methyl ether (TAME) was below laboratory reporting-limit in RS-3 and MW-2 and was detected at concentrations ranging from 2.40 µg/L in MW-1 to 45 µg/L in RS-4. Since the previous monitoring event (November 2016), TAME has increased in RS-4, MW-1, and MW-3. Figure 7 shows a contour map of current TAME concentrations in groundwater. This figure includes the results of First Quarter 2017 groundwater monitoring event as well as the results of recent site investigations.

3. CONCLUSIONS AND RECOMMENDATIONS

Conclusions and recommendations based on results of First Quarter 2017 groundwater monitoring are summarized below.

- The groundwater flows southeasterly across the site.
- No free/floating product was observed in any monitoring wells during this monitoring event.
- The highest TPH-g was detected to the southwest of the pump islands around MW-1. The highest benzene, MtBE, TBA, and TAME concentrations were detected around the southeastern corner of the pump islands in RS-4. Since the previous monitoring event (November 2016), TBA increased in RS-4, MW-1, MW-2 and MW-3. The increase was significant in RS-4 and MW-2.
- During the recent site investigations, significantly high concentrations of MtBE, TBA, and TAME were observed in on and off-site borings, as illustrated in Figures 6 through 8. MtBE and TBA plume appear to be centered in the southwestern corner of the site in the vicinity of DPT-2.
- Since the previous monitoring event in November 2016, increased in MW-1 and remained below laboratory-reporting limits in RS-3, RS-4, MW-2, and MW-3; benzene slightly increased in MW-2; MtBE increased in RS-4, MW-1, MW-2, and MW-3; TBA increased in RS-4, MW-1, MW-2 and MW-3; and TAME increased in RS-4, MW-1, and MW-3.

Based on SFRWQCB's email directive dated March 22, 2017, SOMA is currently preparing a workplan to advance borings in order to define the extent of contaminant plume downgradient of the site.

4. REPORT LIMITATIONS

This report is the summary of work done by SOMA, including observations and descriptions of site conditions. It includes analytical results produced by Curtis and Tompkins, Laboratories for the current groundwater monitoring event. Quantities and locations of wells were selected to provide the required information, but may not be completely representative of entire site conditions. All conclusions and recommendations are based on results of laboratory analysis. Conclusions beyond those specifically stated in this document should not be inferred from this report.


SOMA warrants that services were provided in accordance with generally accepted environmental engineering and consulting practices at the time of this sampling.

Figures



approximate scale in feet
0 100 200

Figure 1: Site Vicinity Map



approximate scale in feet



Figure 2: Site Map Showing Locations of Former USTs, Soil Borings, and Groundwater Monitoring Wells





Figure 3: Groundwater Elevation Contour Map in Feet, March 18, 2017



- 0.0 TPH-g Concentrations (ug/L)
- 0.0 Benzene Concentrations (ug/L)
- ▽ Groundwater Monitoring Wells
- ✗ Decommissioned Monitoring Wells
- ◆ Confirmation Soil Samples
- Confirmation Groundwater Samples
- CPT/MIP/DPT borings (2012)
- Shallow Soil Borings (2012)
- ⊕ DPT Boring (2013)
- Recent DPT Borings (2016)

approximate scale in feet




0 20 40

Figure 4: Map Showing TPH-g and Benzene Concentrations in Groundwater, March 18, 2017



ENVIRONMENTAL ENGINEERING, INC.








Figure 6: Contour Map Showing Current TBA Concentrations in Groundwater




Figure 7: Contour Map Showing Current TAME Concentrations in Groundwater

Tables

Table 1
Historical Groundwater Analytical Results
2844 Mountain Boulevard, Oakland, CA

Monitoring Well	Date	Casing Elevation (Ft.)	Depth to Top Fluid (Ft.)	Depth to Groundwater (Ft.)	Free-Product Thickness	Groundwater Elevation	TPH-g µg/L	TPH-d µg/L	TPH-mo µg/L	Benzene µg/L	Toluene µg/L	Ethylbenzene µg/L	Xylenes µg/L	MtBE µg/L	TBA µg/L	TAME µg/L
RS-1	5/1/90	675.63	7.20	7.20	0.00	668.43	2,700	-	-	370	420	40	320	-	-	-
	5/1/91	675.63	8.35	8.35	0.00	667.28	1,300	-	-	580	130	62	240	-	-	-
	10/1/91	675.63	10.22	10.22	0.00	665.41	1,100	-	-	140	100	45	210	-	-	-
	1/1/92	675.63	8.06	8.06	0.00	667.57	1,700	-	-	9.9	31	9.7	170	-	-	-
	1/1/93	675.63	5.30	5.30	0.00	670.33	3,700	-	-	650	9.2	51	170	-	-	-
	8/1/93	675.63	8.56	8.56	0.00	667.07	900	-	-	14	0.6	2.1	8	-	-	-
	11/1/93	675.63	8.44	8.44	0.00	667.19	1,400	-	-	9.6	ND	0.9	5	-	-	-
	1/1/94	675.63	6.88	6.88	0.00	668.75	4,200	-	-	95	3.1	58	130	-	-	-
	5/1/94	675.63	7.87	7.87	0.00	667.76	7,500	-	-	270	11	37	96	-	-	-
	8/1/94	675.63	16.28	16.28	0.00	659.35	130	-	-	12	0.5	2.6	5	-	-	-
	11/1/94	675.63	8.02	8.02	0.00	667.61	270	-	-	4.7	0.7	0.6	15	-	-	-
	2/1/95	675.63	6.51	6.51	0.00	669.12	12,000	-	-	81	2.3	1	12	-	-	-
	6/1/95	675.63	7.34	7.34	0.00	668.29	37,000	-	-	460	ND	ND	ND	63,000	-	-
	11/1/95	675.63	8.71	8.71	0.00	666.92	ND	-	-	660	16	140	330	31,000	-	-
	2/1/96	675.63	6.95	6.95	0.00	668.68	66,000	-	-	110	ND	12	21	84,000	-	-
	9/18/96	675.63	8.44	8.52	0.08	667.17	1 INCH FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	12/11/96	675.63	6.42	6.62	0.20	669.17	79,000	-	-	4,000	37,000	8,000	45,000	220,000	-	-
	2/21/97	675.63	6.88	6.92	0.04	668.74	1/2 INCH FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	5/28/97	675.63	7.88	7.96	0.08	667.73	156,000	-	-	9,400	51,000	7,000	45,000	112,000	-	-
	9/2/97	675.63	8.34	8.38	0.04	667.28	1/2 INCH FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	11/24/97	675.63	6.98	7.00	0.02	668.65	1/4 INCH FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	2/25/98	675.63	3.51	3.52	0.01	672.12	1/8 INCH FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	5/27/98	675.63	7.31	7.31	0.00	668.32	40,000	-	-	2,200	4,000	2,300	19,000	350,000	-	-
	9/16/98	675.63	8.10	8.10	0.00	667.53	62,000	-	-	2,400	2,300	2,100	14,000	250,000	-	-
	11/23/98	675.63	7.10	7.10	0.00	668.53	99,000	-	-	2,600	5,800	2,500	18,000	130,000	-	-
	2/23/99	675.67	4.82	4.87	0.05	670.84	5/8 INCH FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	5/5/99	675.67	6.86	6.90	0.04	668.80	FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	8/24/99	675.67	7.87	7.90	0.03	667.80	FLOATING PRODUCT	-	-	-	-	-	-	-	-	-
	2/8/12	675.67	6.80	6.80	0.00	668.87	60,000 x	8,200 x	<936	790	<6.4	2,000	430	65,000	41,000	5,100
	5/4/12	675.67	6.57	6.57	0.00	669.10	18,000	10,000	NA	600	<36	2,000	870	22,000	11,000	1,800
	8/6/12	675.67	7.61	7.61	0.00	668.06	16,000	12,000	NA	940	<130	2,000	560	42,000	35,000	3,400
Well Destroyed October 1, 2012																
RS-2	5/1/90	689.00	7.06	7.06	0.00	681.94	23,000	-	-	7,200	4,800	300	3,300	-	-	-
	5/1/91	689.00	7.14	7.14	0.00	681.86	26,000	-	-	14,000	1,800	750	2,900	-	-	-
	10/1/91	688.89	8.84	8.84	0.00	680.05	13,000	-	-	4,300	910	300	2,300	-	-	-
	1/1/92	688.89	7.34	7.34	0.00	681.55	8,300	-	-	1,800	920	140	1,700	-	-	-
	1/1/93	688.89	4.10	4.10	0.00	684.79	41,000	-	-	7,000	210	1,200	4,200	-	-	-
	8/1/93	688.89	7.32	7.32	0.00	681.57	19,000	-	-	5,300	62	810	1,600	-	-	-
	11/1/93	688.89	7.34	7.34	0.00	681.55	9,300	-	-	2,400	3.90	46	800	-	-	-
	1/1/94	688.89	5.52	5.52	0.00	683.37	30,000	-	-	4,900	ND	880	2,600	-	-	-
	5/1/94	675.25	6.40	6.40	0.00	668.85	120,000	-	-	3,300	330	ND	2,200	-	-	-
	8/1/94	675.25	9.82	9.82	0.00	675.25	510	-	-	7.30	3.80	3.50	32	-	-	-
	11/1/94	675.25	9.82	9.82	0.00	665.43	620	-	-	6.60	3.90	1.10	47	-	-	-

Table 1
Historical Groundwater Analytical Results
2844 Mountain Boulevard, Oakland, CA

Monitoring Well	Date	Casing Elevation (Ft.)	Depth to Top Fluid (Ft.)	Depth to Groundwater (Ft.)	Free-Product Thickness	Groundwater Elevation	TPH-g µg/L	TPH-d µg/L	TPH-mo µg/L	Benzene µg/L	Toluene µg/L	Ethylbenzene µg/L	Xylenes µg/L	MtBE µg/L	TBA µg/L	TAME µg/L	
RS-2 cont.	2/1/95	675.25	4.81	4.81	0.00	670.44	22,000	-	-	228	80	2	463	-	-	-	
	6/1/95	675.25	5.80	5.80	0.00	669.45	49,000	-	-	1,300	160	200	1,600	71,000	-	-	
	11/1/95	675.25	7.64	7.64	0.00	667.61	ND	-	-	670	25	150	360	65,000	-	-	
	2/1/96	675.25	4.69	4.69	0.00	670.56	75,000	-	-	1,400	170	59	460	71,000	-	-	
	9/18/96	675.25	7.34	7.34	0.00	667.91	6,300	-	-	2,000	48	350	570	160,000	-	-	
	12/11/96	675.25	5.08	5.08	0.00	670.17	16,000	-	-	2,000	840	200	3,200	180,000	-	-	
	2/21/97	675.25	5.42	5.42	0.00	669.83	22,000	-	-	2,100	1,300	600	5,100	56,000	-	-	
	5/28/97	675.25	6.40	6.40	0.00	668.85	156,000	-	-	4,200	89	1,000	6,900	390,000	-	-	
	9/2/97	675.25	6.93	6.93	0.00	668.32	<50	-	-	1,300	25	360	1,400	180,000	-	-	
	11/24/97	675.25	5.93	5.93	0.00	669.32	<50	-	-	600	ND	ND	ND	610,000	-	-	
	2/25/98	675.25	4.59	4.59	0.00	670.66	11,000	-	-	1,100	<50	320	2,400	330,000	-	-	
	5/27/98	675.25	5.61	5.61	0.00	669.64	13,000	-	-	2,000	150	600	2,700	380,000	-	-	
	9/16/98	675.25	6.84	6.84	0.00	668.41	11,000	-	-	1,600	20	1,600	1,600	280,000	-	-	
	11/23/98	675.25	6.24	6.24	0.00	669.01	12,000	-	-	1,200	84	<5	960	140,000	-	-	
	2/23/99	675.28	4.62	4.62	0.00	670.66	8,800	-	-	1,500	650	640	1,500	450,000	-	-	
	5/5/99	675.28	7.55	7.55	0.00	667.73	29,000	-	-	2,000	1,300	500	3,700	270,000	-	-	
	8/24/99	675.28	6.62	6.62	0.00	668.66	12,000	-	-	1,900	20	370	980	340,000	-	-	
	2/8/12	675.28	5.52	5.52	0.00	669.76	18,000 x	6,800 x	<378	540	<6.4	120	710	2,800	64,000	420	
	5/4/12	675.28	5.18	5.18	0.00	670.10	16,000	13,000	NA	690	23	460	1,140	6,800	21,000	960	
	8/6/12	675.28	6.33	6.33	0.00	668.95	11,000	10,000	NA	810	<25	210	473	3,300	18,000	580	
Well Destroyed October 1, 2012																	
RS-3	5/1/90	670.00	6.00	6.00	0.00	664.00	330	-	-	2	1	1	150	-	-	-	
	5/1/91	670.00	6.76	6.76	0.00	663.24	ND	-	-	0.40	ND	0.80	8	-	-	-	
	10/1/91	670.00	8.98	8.98	0.00	661.02	ND	-	-	ND	ND	ND	ND	-	-	-	
	1/1/92	670.00	6.81	6.81	0.00	663.19	ND	-	-	2.20	7.20	0.60	4	-	-	-	
	1/1/93	670.00	4.05	4.05	0.00	665.95	ND	-	-	ND	ND	ND	ND	-	-	-	
	8/1/93	670.00	7.19	7.19	0.00	662.81	ND	-	-	30	6	2.40	5	-	-	-	
	11/1/93	670.00	7.12	7.12	0.00	662.88	ND	-	-	4.80	0.40	0.60	2	-	-	-	
	1/1/94	670.00	5.42	5.42	0.00	664.58	330	-	-	25	3.20	3.90	12	-	-	-	
	5/1/94	676.20	5.78	5.78	0.00	670.42	670	-	-	34	4	28	70	-	-	-	
	8/1/94	676.20	5.86	5.86	0.00	670.34	ND	-	-	ND	ND	ND	ND	-	-	-	
	11/1/94	676.20	5.08	5.08	0.00	671.12	69	-	-	2.50	3.10	1	4	-	-	-	
	2/1/95	676.20	4.51	4.51	0.00	671.69	ND	-	-	0.30	0.40	ND	1	-	-	-	
	6/1/95	676.20	5.29	5.29	0.00	670.91	ND	-	-	ND	ND	ND	ND	66	-	-	
	11/1/95	676.20	7.10	7.10	0.00	669.10	ND	-	-	ND	ND	ND	ND	44	-	-	
	2/1/96	676.20	4.48	4.48	0.00	671.72	120	-	-	ND	ND	ND	ND	110	-	-	
	9/18/96	676.20	6.92	6.92	0.00	669.28	1,000	-	-	13	8.60	10	17	33	-	-	
	12/11/96	676.20	4.90	4.90	0.00	671.30	85	-	-	20	2	<0.5	14	4,700	-	-	
	2/21/97	676.20	4.94	4.94	0.00	671.26	120	-	-	5	2	2	6	850	-	-	
	5/28/97	676.20	7.92	7.92	0.00	668.28	<50	-	-	6	<0.5	<0.5	<2	2,400	-	-	
	9/2/97	676.20	6.60	6.60	0.00	669.60	<50	-	-	0.90	<0.5	<0.5	<2	8,600	-	-	
	11/24/97	676.20	5.89	5.89	0.00	670.31	140	-	-	13	2	1	12	3,600	-	-	
	2/25/98	676.20	4.29	4.29	0.00	671.91	<50	-	-	<0.5	<0.5	<0.5	4	850	-	-	
	5/27/98	676.20	5.01	5.01	0.00	671.19	<50	-	-	7	<0.5	<0.5	11	940	-	-	

Table 1
Historical Groundwater Analytical Results
2844 Mountain Boulevard, Oakland, CA

Monitoring Well	Date	Casing Elevation (Ft.)	Depth to Top Fluid (Ft.)	Depth to Groundwater (Ft.)	Free-Product Thickness	Groundwater Elevation	TPH-g µg/L	TPH-d µg/L	TPH-mo µg/L	Benzene µg/L	Toluene µg/L	Ethylbenzene µg/L	Xylenes µg/L	MtBE µg/L	TBA µg/L	TAME µg/L
RS-3 cont.	9/16/98	676.20	6.21	6.21	0.00	669.99	<50	-	-	2	2	10	670	-	-	-
	11/24/98	676.20	5.58	5.58	0.00	670.62	85	-	-	9	23	<0.5	19	180	-	-
	2/24/99	676.23	4.30	4.30	0.00	671.93	<50	-	-	<0.5	0.90	<0.5	<1.0	150	-	-
	5/5/99	676.23	4.92	4.92	0.00	671.31	<50	-	-	1	2	1	6	130	-	-
	8/24/99	676.23	6.64	6.64	0.00	669.59	80	-	-	0.80	<0.5	0.60	<1	300	-	-
	2/8/12	676.23	5.72	5.72	0.00	670.51	130 x	<42	<94	<0.13	0.59	2.90	18.1	7.9	<1.5	<0.17
	5/4/12	676.23	5.25	5.25	0.00	670.98	<50	330 Y	NA	<0.5	<0.5	<0.5	<0.5	10	18	2.4
	8/6/12	676.23	6.65	6.65	0.00	669.58	<50	390 Y	NA	<0.5	<0.5	<0.5	<0.5	13	<10	3.2
	3/29/13	676.23	6.01	6.01	0.00	670.22	<50	90 Y	NA	<0.5	<0.5	<0.5	<0.5	3.6	<10	<0.5
	6/6/13	676.08	6.45	6.45	0.00	669.63	<50	66 Y	NA	<0.5	<0.5	<0.5	<0.5	1.5	<10	<0.5
	9/4/13	676.08	6.91	6.91	0.00	669.17	<50	170 Y	NA	<0.5	<0.5	<0.5	<0.5	<0.5	<10	<0.5
	12/30/13	676.08	7.21	7.21	0.00	668.87	<50	61 Y	NA	<0.5	<0.5	<0.5	<0.5	21	680	0.64
	3/10/14	676.08	5.68	5.68	0.00	670.40	<50	<50	NA	<0.5	<0.5	<0.5	<0.5	14	320	0.61
	6/3/14	676.08	6.72	6.72	0.00	669.36	<50	<50	NA	<0.5	<0.5	<0.5	<0.5	41	490	1.70
	8/27/14	676.08	7.10	7.10	0.00	668.98	<50	120 Y	NA	<0.5	<0.5	<0.5	<0.5	27	<10	1.20
	11/13/14	676.08	6.53	6.53	0.00	669.55	<50*	58 Y	NA	<0.5	<0.5	<0.5	<0.5	19	<10	0.60
post-MPE	2/12/15	676.08	5.95	5.95	0.00	670.13	<50	56 Y	NA	<0.5	<0.5	<0.5	<0.5	19	<10	<0.5
	5/13/15	676.08	6.93	6.93	0.00	669.15	<50	<50	NA	<0.5	<0.5	<0.5	<0.5	4.6	<10	<0.5
	6/22/15	676.08	8.87	8.87	0.00	667.21	<50	<50	NA	<0.5	<0.5	<0.5	<0.5	<0.5	<10	<0.5
	8/12/15	676.08	7.79	7.79	0.00	668.29	<50	<52	NA	<0.5	<0.5	<0.5	<0.5	0.57	<10	<0.5
	11/12/15	676.08	7.85	7.85	0.00	668.23	<50	<49	NA	<0.5	<0.5	<0.5	<0.5	1.10	<10	<0.5
	2/15/16	676.08	5.88	5.88	0.00	670.20	<50	<49	NA	<0.5	<0.5	<0.5	<0.5	5.40	<10	<0.5
	5/6/16	676.08	5.93	5.93	0.00	670.15	<50	<50	NA	<0.5	<0.5	<0.5	<0.5	4.80	<10	<0.5
	8/17/16	676.08	6.70	6.70	0.00	669.38	<50	81Y	NA	<0.5	<0.5	<0.5	<0.5	0.51	<10	<0.5
	11/18/16	676.08	6.18	6.18	0.00	669.90	<50	62Y	NA	<0.5	<0.5	<0.5	<0.5	<0.5	<10	<0.5
	3/18/17	676.08	4.65	4.65	0.00	671.43	<50	NA	NA	<0.5	<0.5	<0.5	<0.5	<0.5	<10	<0.5
RS-4	5/1/90	675.38	8.34	8.34	0.00	667.04	440	-	-	9	11	9	49	-	-	-
	5/1/91	675.38	9.50	9.50	0.00	665.88	ND	-	-	8	4	3	5	-	-	-
	10/1/91	675.38	10.82	10.82	0.00	664.56	830	-	-	280	120	24	170	-	-	-
	1/1/92	675.38	9.31	9.31	0.00	666.07	620	-	-	34	8.30	2.10	21	-	-	-
	1/1/93	675.38	6.89	6.89	0.00	668.49	150	-	-	32	1.70	5.80	13	-	-	-
	8/1/93	675.38	9.68	9.68	0.00	665.70	ND	-	-	0.90	0.70	ND	0	-	-	-
	11/1/93	675.38	9.83	9.83	0.00	665.55	ND	-	-	ND	ND	ND	ND	-	-	-
	1/1/94	675.38	8.17	8.17	0.00	667.21	ND	-	-	1.70	ND	0.81	2	-	-	-
	5/1/94	675.38	8.69	8.69	0.00	666.69	ND	-	-	ND	ND	ND	1	-	-	-
	8/1/94	675.38	9.04	9.04	0.00	666.34	420	-	-	6.50	4.10	1.90	40	-	-	-
	11/1/94	675.38	8.00	8.00	0.00	667.38	130	-	-	4.10	0.70	1.70	8	-	-	-
	2/1/95	675.38	7.93	7.93	0.00	667.45	ND	-	-	6	1.20	3.50	13	-	-	-
	6/1/95	675.38	8.61	8.61	0.00	666.77	ND	-	-	ND	ND	ND	ND	69	-	-
	11/1/95	675.38	10.43	10.43	0.00	664.95	ND	-	-	ND	ND	ND	ND	47	-	-
	2/1/96	675.38	7.44	7.44	0.00	667.94	960	-	-	ND	ND	0.60	ND	80	-	-
	9/18/96	675.38	9.58	9.58	0.00	665.80	<50	-	-	<0.5	<0.5	<0.5	<0.5	200	-	-
	12/11/96	675.38	7.50	7.50	0.00	667.88	75	-	-	<0.5	0.60	<0.5	<0.5	104	-	-

Table 1
Historical Groundwater Analytical Results
2844 Mountain Boulevard, Oakland, CA

Monitoring Well	Date	Casing Elevation (Ft.)	Depth to Top Fluid (Ft.)	Depth to Groundwater (Ft.)	Free-Product Thickness	Groundwater Elevation	TPH-g µg/L	TPH-d µg/L	TPH-mo µg/L	Benzene µg/L	Toluene µg/L	Ethylbenzene µg/L	Xylenes µg/L	MtBE µg/L	TBA µg/L	TAME µg/L
RS-4 cont.	2/21/97	675.38	8.26	8.26	0.00	667.12	<50	-	-	1	1	<0.5	1	190	-	-
	5/28/97	675.38	8.92	8.92	0.00	666.46	<50	-	-	6	<0.5	<0.5	<2	110	-	-
	9/2/97	675.38	9.39	9.39	0.00	665.99	100	-	-	3	<0.5	<0.5	<2	39	-	-
	11/24/97	675.38	8.22	8.22	0.00	667.16	41	-	-	<0.5	2	<0.5	<2	210	-	-
	2/25/98	675.38	7.19	7.19	0.00	668.19	<50	-	-	3	<0.5	<0.5	<1	5,600	-	-
	5/27/98	675.38	8.40	8.40	0.00	666.98	<50	-	-	<0.5	<0.5	<0.5	<1	2,400	-	-
	9/16/98	675.38	9.26	9.26	0.00	666.12	<50	-	-	<0.5	<0.5	<0.5	<1	230	-	-
	11/24/98	675.38	8.50	8.50	0.00	666.88	<50	-	-	2	<0.5	<0.5	<1	100	-	-
	2/24/99	675.42	7.20	7.20	0.00	668.22	<50	-	-	2	3	0.80	5	670	-	-
	5/5/99	675.42	8.37	8.37	0.00	667.05	100	-	-	<0.5	<0.5	<1	440	-	-	-
	8/24/99	675.42	8.36	8.36	0.00	667.06	<50	-	-	<0.5	<0.5	<1	<500	-	-	-
	2/8/12	675.42	8.11	8.11	0.00	667.31	140,000	130,000 x	<9,360	120	2,600	4,700	28,200	28,000	100,000	1,800
	5/4/12	675.42	8.31	8.31	0.00	667.11	67,000	12,000 Y	NA	61	900	2,100	9,700	32,000	69,000	1,700
	8/6/12	675.42	9.01	9.01	0.00	666.41	49,000	8,900	NA	<130	350	1,700	8,100	19,000	90,000	1,300
	3/29/13	675.42	8.49	8.49	0.00	666.93	14,000	14,000	NA	<100	440	1,340	14,000	110,000	590	
	6/6/13	675.27	8.48	8.48	0.00	666.79	12,000	7,200	NA	11	<3.6	420	886	16,000	66,000	970
	9/4/13	675.27	9.39	9.39	0.00	665.88	20,000	5,100	NA	<100	<100	660	2,830	18,000	75,000	1,200
	12/30/13	675.27	9.57	9.57	0.00	665.70	<13,000	9,900	NA	<130	<130	150	16,000	37,000	1,100	
	3/10/14	675.27	7.65	7.65	0.00	667.62	<10,000	3,700	NA	<100	<100	<100	<100	11,000	38,000	640
	6/3/14	675.27	9.27	9.27	0.00	666.00	<3,600	4,400	NA	<36	<36	40	<36	3,700	27,000	260
	8/27/14	675.27	9.43	9.43	0.00	665.84	2,500	4,700	NA	<20	<20	40	<20	2,100	28,000	150
	11/13/14	675.27	9.56	9.56	0.00	665.71	2,200*	3,500	NA	<20	<20	36	11,000	15,000	910	
	2/12/15	675.27	8.03	8.03	0.00	667.24	<1,300	1,900	NA	<13	<13	<13	<13	500	14,000	25
	5/13/15	675.27	9.05	9.05	0.00	666.22	<1,300	1,100	NA	<13	<13	<13	<13	460	25,000	21
	6/22/15	675.27	10.62	10.62	0.00	664.65	<1,300	770	NA	<13	<13	<13	<13	5,900	7,900	500
	8/12/15	675.27	9.93	9.93	0.00	665.34	320	1,300	NA	<1.3	<1.3	1.3	1.7	230	6,400	18
	11/12/15	675.27	9.58	9.58	0.00	665.69	170	440	NA	<0.5	<0.5	1.4	0.55	12	1,400	0.66
	2/15/16	675.27	8.43	8.43	0.00	666.84	<100	350 Y	NA	<1.0	<1.0	<1.0	<1.0	8.80	270	<1.0
	5/6/16	675.27	6.47	6.47	0.00	668.80	<50	850 Y	NA	<0.5	<0.5	<0.5	<0.5	160	21	5.60
	8/17/16	675.27	9.38	9.38	0.00	665.89	100	710 Y	NA	<0.5	<0.5	<0.5	<0.5	47	8,100	2.80
	11/18/16	675.27	8.80	8.80	0.00	666.47	<100	690	NA	<1.0	<1.0	<1.0	<1.0	190	5,400	13
	3/18/17	675.27	7.63	7.63	0.00	667.64	<710	NA	NA	<7.1	<7.1	<7.1	<7.1	820	33,000	45
MW-1	6/6/13	674.92	6.03	6.03	0.00	668.89	<17,000	13,000	NA	930	370	470	1,760	55,000	32,000	7,200
	9/4/13	674.92	7.10	7.10	0.00	667.82	<50,000	13,000	NA	2,000	<500	1,400	4,200	70,000	48,000	7,700
	12/30/13	674.92	7.27	7.27	0.00	667.65	34,000	13,000	NA	920	1,000	1,300	4,900	43,000	43,000	4,500
	3/10/14	674.92	5.51	5.51	0.00	669.41	<20,000	11,000	NA	720	<200	890	1,970	25,000	30,000	2,600
	6/3/14	674.92	6.74	6.74	0.00	668.18	8,900	7,400	NA	350	<83	550	1,420	11,000	28,000	1,300
	8/27/14	674.92	7.23	7.23	0.00	667.69	8,100	12,000	NA	640	<63	610	720	8,400	23,000	1,500
	11/13/14	674.92	7.36	7.36	0.00	667.56	7,400*	7,900	NA	270	<63	360	880	6,100	12,000	910
	2/12/15	674.92	5.80	5.80	0.00	669.12	4,300	11,000	NA	200	<25	200	350	3,400	18,000	500
	5/13/15	674.92	7.00	7.00	0.00	667.92	2,700	7,100	NA	150	<8.3	170	76	1,000	12,000	150
	6/22/15	674.92	12.11	12.11	0.00	662.81	<1,300	2,600	NA	<13	<13	<13	<13	4,800	17,000	450
	8/12/15	674.92	8.25	8.25	0.00	666.67	2,000	8,100	NA	31	<8.3	27	46	530	10,000	57
	11/12/15	674.92	7.79	7.79	0.00	667.13	2,500	5,100	NA	16	<5.0	34	6.9	120	6,200	13

Table 1
Historical Groundwater Analytical Results
2844 Mountain Boulevard, Oakland, CA

Monitoring Well	Date	Casing Elevation (Ft.)	Depth to Top Fluid (Ft.)	Depth to Groundwater (Ft.)	Free-Product Thickness	Groundwater Elevation	TPH-g µg/L	TPH-d µg/L	TPH-mo µg/L	Benzene µg/L	Toluene µg/L	Ethylbenzene µg/L	Xylenes µg/L	MtBE µg/L	TBA µg/L	TAME µg/L
MW-1 cont.	2/15/16	674.92	5.94	5.94	0.00	668.98	970	3,700	NA	3.20	<2.5	27	11	75	4,100	7.40
	5/6/16	674.92	5.92	5.92	0.00	669.00	690	2,900	NA	1.80	<1.7	<1.7	<1.7	26	2,900	2.50
	8/17/16	674.92	6.62	6.62	0.00	668.30	940	5,000 Y	NA	<1.7	<1.7	<1.7	<1.7	17	2,300	<1.7
	11/18/16	674.92	6.08	6.08	0.00	668.84	340	3,900	NA	<2.0	<2.0	<2.0	<2.0	12	1,800	<2.0
	3/18/17	674.92	4.73	4.73	0.00	670.19	920	NA	NA	<2.0	<2.0	<2.0	<2.0	34	2,300	2.40
MW-2	6/6/13	675.02	6.70	6.70	0.00	668.32	16,000	5,400	NA	910	<130	610	2,290	59,000	64,000	7,700
	9/4/13	675.02	7.79	7.79	0.00	667.23	<25,000	3,900	NA	860	<250	710	1,580	32,000	31,000	4,600
	12/30/13	675.02	8.05	8.05	0.00	666.97	<13,000	6,300	NA	180	<130	<130	330	18,000	53,000	1,800
	3/10/14	675.02	6.08	6.08	0.00	668.94	14,000	11,000	NA	210	<130	360	700	15,000	40,000	1,800
	6/3/14	675.02	7.54	7.54	0.00	667.48	<7,100	6,200	NA	170	<71	310	150	8,000	29,000	920
	8/27/14	675.02	7.90	7.90	0.00	667.12	3,400	5,000	NA	100	<8.3	120	88	2,300	25,000	310
	11/13/14	675.02	8.12	8.12	0.00	666.90	1,000*	4,700	NA	120	<8.3	11	<8.3	4,000	22,000	460
	2/12/15	675.02	6.33	6.33	0.00	668.69	<4,200	5,400	NA	98	<42	58	<42	6,300	42,000	610
	5/13/15	675.02	7.72	7.72	0.00	667.30	<2,000	4,900	NA	86	<20	45	<20	870	34,000	96
	6/22/15	675.02	11.30	11.30	0.00	663.72	<2,000	3,300	NA	<20	<20	<20	<20	3,400	18,000	460
Post-MPE	8/12/15	675.02	8.86	8.86	0.00	666.16	<2,000	2,800 Y	NA	<20	<20	<20	<20	470	23,000	31
	11/12/15	675.02	8.30	8.30	0.00	666.72	<2,000	1,800	NA	<20	<20	<20	<20	340	37,000	25
	2/15/16	675.02	6.67	6.67	0.00	668.35	620	1,900	NA	32	<2.0	8.2	<2.0	180	26,000	15
	5/6/16	675.02	5.72	5.72	0.00	669.30	1,200	1,700	NA	43	<2.5	14	<2.5	220	19,000	20
	8/17/16	675.02	7.67	7.67	0.00	667.35	<710	1,100	NA	20	<7.1	<7.1	<7.1	140	10,000	10
	11/18/16	675.02	6.95	6.95	0.00	668.07	<710	1,100	NA	9.80	<7.1	<7.1	<7.1	40	6,400	<7.1
	3/18/17	675.02	5.68	5.68	0.00	669.34	<50	NA	NA	10	<7.1	<7.1	<7.1	88	12,000	<7.1
MW-3	5/13/15	675.58	6.60	6.60	0.00	668.98	<50	7,000	NA	<0.5	<0.5	<0.5	0.75	160	380	8.4
	6/22/15	675.58	14.31	14.31	0.00	661.27	<100	650 Y	NA	<1.0	<1.0	<1.0	<1.0	190	17	6.3
	8/12/15	675.58	7.80	7.80	0.00	667.78	<170	410 Y	NA	<1.7	<1.7	<1.7	<1.7	590	41	20
	11/12/15	675.58	7.78	7.78	0.00	667.80	<50	220 Y	NA	<0.5	<0.5	<0.5	<0.5	67	<10	1.70
	2/15/16	675.58	5.40	5.40	0.00	670.18	<50	370 Y	NA	<0.5	<0.5	<0.5	<0.5	140	<10	3.20
	5/6/16	675.58	5.68	5.68	0.00	669.90	140	490 Y	NA	<0.5	<0.5	<0.5	<0.5	190	9,000	10
	8/17/16	675.58	6.37	6.37	0.00	669.21	<50	870 Y	NA	<0.5	<0.5	<0.5	<0.5	30	19	1.30
Post-MPE	11/18/16	675.58	5.71	5.71	0.00	669.87	<50	460 Y	NA	<0.5	<0.5	<0.5	<0.5	2,10	<10	<0.5
	3/18/17	675.58	4.11	4.11	0.00	671.47	<50	NA	NA	<0.5	<0.5	<0.5	<0.5	160	140	10
ESLs (µg/L)	Ground-water					100	100	NA	1.00	40	13	20	5.00	12	NL	
	Vapor Intrusion					NV	NV	NV	1.10	3,600	13	1,300	1,200	NV	NL	

Note:

< : Below Laboratory Reporting Limit (Method Detection Limit)

x : Does not match pattern of reference Gasoline standard/ Not typical of diesel standard pattern (possibly fuel lighter than diesel)

* : Laboratory instruments for EPA8260 were down. Therefore, TPH-g was analyzed by EPA8015B instead of EPA8260 for samples collected on 11/13/2014

ESL: Environmental Screening Level by California Regional Water Quality Control Board San Francisco Bay Region, February 2016

NL: Not Listed

NV: No Value

Appendix A

Standard Operating Procedures for Conducting Groundwater Monitoring Activities

Standard Operating Procedures for Conducting Groundwater Monitoring Activities

Water Level Measurements

Prior to measurement of groundwater depth at each monitoring well, equalization with the surrounding aquifer must be achieved. Initially, the well cap is removed and the pressure is allowed to dissipate, creating a more stable water table level within the well. After about 10-15 minutes, once the water level in the well stabilizes, the depth to groundwater in each monitoring well is measured from the top of the casing to the nearest 0.01 foot using an electric sounder.

Purging and Field Measurements

Prior to sample collection, each monitoring well is purged using a battery-operated, 2-inch-diameter pump (Model ES-60 DC). To ensure that final samples are in equilibrium with, and representative of, the surrounding groundwater, during purging several samples are taken for field measurements of pH, temperature and electrical conductivity (EC). These parameters are measured with a Hanna pH, conductivity, and temperature meter. Equipment is calibrated on-site using standard solutions and procedures provided by the manufacturer.

The pH of groundwater has an effect on the activity of microbial populations in the groundwater. The groundwater temperature affects the metabolic activity of bacteria. The groundwater EC is directly related to the concentration of total dissolved solids (TDS) in solution.

Purging continues until these parameters stabilize or three casing volumes are purged.

Sampling

For sampling purposes, after purging a disposable polyethylene bailer is used to collect sufficient samples from each monitoring well for laboratory analyses. Groundwater samples are transferred to 40-mL VOA vials and preserved with hydrochloric acid. The vials are sealed to prevent air bubbles from forming within the headspace. For TPH-d and TPH-mo analysis, groundwater samples are collected using 1-L, amber, nonpreserved glass containers. Samples are placed in an ice-filled cooler and maintained at 4°C. A chain of custody form for all samples is prepared to accompany the samples, which are promptly delivered to a California state-certified analytical laboratory.

Appendix B

Tables of Elevations and Coordinates on Wells,
Field Measurements of Physical and Chemical
Parameters of the Groundwater Samples
and Groundwater Gradient Calculations

DATE: 5/28/2013
JOB# 13004

**TABLE OF ELEVATIONS & COORDINATES
ON MONITORING WELLS**

SOMA ENVIRONMENTAL ENGINEERING
2844 MOUNTAIN BLVD
OAKLAND, CA 94602

HORIZONTAL CONTROL: CALIFORNIA COORDINATE SYSTEM ZONE 3, NAD83.

ELLIPSOID: WGS 1984

EPOCH: NAD 83 (2011) 2010.0000

GEOID MODEL: GEOID12A

VERTICAL CONTROL: BENCH MARK: CITY OF OAKLAND BM 2806

CINCH NAIL IN SOUTHWESTERLY CURB OF MOUNTAIN BLVD, 150' SOUTHEASTERLY FROM THE CENTERLINE OF KEARNEY AVE EXTENDED. NORTHING 2,122,547.687', EASTING 6,070,956.301' ELEVATION= 674.892' NAVD 88 DATUM



EQUIPMENT USED: TRIMBLE GPS-R8 & TS S6, TOPCON AT-G2 LEVEL

**EDGIS LAND SURVEYING
LAND SURVEYING AND MAPPING**
1374 Garland Avenue, Clovis, CA 93612
Phone (559) 803-2679
email: edgis@aol.com

DATE: 5/16/2015
JOB# 15006

TABLE OF ELEVATIONS & COORDINATES ON MONITORING WELLS

SOMA ENVIRONMENTAL ENGINEERING
2844 MOUNTAIN BLVD
OAKLAND, CA 94602

HORIZONTAL CONTROL:

SURVEY BASED ON PREVIOUS SURVEY BY EDGIS LAND SURVEYING DATED: 5/28/2013
COORDINATE VALUES ARE BASED ON THE CALIFORNIA COORDINATE SYSTEM, ZONE 3, NAD83.

VERTICAL CONTROL: BENCH MARK: CITY OF OAKLAND BM 2806

CINCH NAIL IN SOUTHWESTERLY CURB OF MOUNTAIN BLVD, 150' SOUTHEASTERLY FROM THE CENTERLINE OF KEARNEY AVE EXTENDED. NORTHING 2,122,547.687', EASTING 6,070,956.301' ELEVATION= 674.892' NAVD 88 DATUM



EQUIPMENT USED: TRIMBLE TS S6, TOPCON AT-G2 LEVEL

**EDGIS LAND SURVEYING
LAND SURVEYING AND MAPPING**
2519 Shaw Ave., Ste. 111
Fresno, CA 93711
Phone (559) 803-2679
Email: edgis@aol.com



ENVIRONMENTAL ENGINEERING, INC

Well No.: R5-3 Project No.: 5081
Casing Diameter: 4 inches Address: 2844 Mountain Blvd.
Depth of Well: 23.50 feet Oakland, CA
Top of Casing Elevation: 676.08 feet Date: March 18, 2017
Depth to Groundwater: 4.65 feet Sampler: Mansour Sepehr
Groundwater Elevation: 671.43 feet
Water Column Height: 18.85 feet
Purged Volume: 6 gallons

Purging Method: Bailer Pump

Sampling Method: Bailer Pump

Color: Yes No Describe: _____

Sheen: Yes No Describe: _____

Odor: Yes No Describe: _____

Field Measurements:

Time	Vol (gallons)	pH	Temp (°C)	E.C. (μs/cm)
9:38	2	7.07	17.0	567
9:41	4	7.10	16.6	565
9:45	6	7.12	16.1	565
	Sampled			

Notes:



ENVIRONMENTAL ENGINEERING, INC

Well No.: RS-4 Project No.: 5081
Casing Diameter: 4 inches Address: 2844 Mountain Blvd.
Depth of Well: 25.50 feet Oakland, CA
Top of Casing Elevation: 675.27 feet Date: March 18, 2017
Depth to Groundwater: 7.63 feet Sampler: Mansour Sepehr
Groundwater Elevation: 667.64 feet
Water Column Height: 17.87 feet
Purged Volume: 6 gallons

Purging Method: Bailer Pump

Sampling Method: Bailer Pump

Color: Yes No Describe: _____

Sheen: Yes No Describe: _____

Odor: Yes No Describe: _____

Field Measurements:

Time	Vol (gallons)	pH	Temp (°C)	E.C. (μs/cm)
12:18	2	7.07	17.5	737
12:21	4	7.11	17.8	811
12:25	6	7.06	18.0	812
	Sampled			

Notes:



ENVIRONMENTAL ENGINEERING, INC

Well No.: MW-1
Casing Diameter: 4 inches
Depth of Well: 19.65 feet
Top of Casing Elevation: 674.92 feet
Depth to Groundwater: 4.73 feet
Groundwater Elevation: 670.19 feet
Water Column Height: 14.92 feet
Purged Volume: 6 gallons

Project No.: 5081
Address: 2844 Mountain Blvd.
Oakland, CA
Date: March 18, 2017
Sampler: Mansour Sepehr

Purging Method: Bailer Pump

Sampling Method: Bailer Pump

Color: Yes No Describe: _____

Sheen: Yes No Describe: _____

Odor: Yes No Describe: _____

Field Measurements:

Time	Vol (gallons)	pH	Temp (°C)	E.C. (µs/cm)
11:39	2	7.21	17.8	590
11:41	4	7.19	17.2	587
11:45	6	7.17	17.3	591
	Sampled			

Notes:



ENVIRONMENTAL ENGINEERING, INC

Well No.: MW-2 Project No.: 5081
Casing Diameter: 4 inches Address: 2844 Mountain Blvd.
Depth of Well: 19.75 feet Oakland, CA
Top of Casing Elevation: 675.02 feet Date: March 18, 2017
Depth to Groundwater: 5.68 feet Sampler: Mansour Sepehr
Groundwater Elevation: 669.34 feet
Water Column Height: 14.07 feet
Purged Volume: 6 gallons

Purging Method: Bailer Pump

Sampling Method: Bailer Pump

Color: Yes No Describe: _____

Sheen: Yes No Describe: _____

Odor: Yes No Describe: _____

Field Measurements:

Time	Vol (gallons)	pH	Temp (°C)	E.C. (μs/cm)
11:56	2	7.10	17.6	600
12:00	4	7.35	17.5	558
12:04	6	7.41	17.6	566

Notes:



ENVIRONMENTAL ENGINEERING, INC

Well No.: MW-3 Project No.: 5081
Casing Diameter: 4 inches Address: 2844 Mountain Blvd.
Depth of Well: 24.60 feet Oakland, CA
Top of Casing Elevation: 675.58 feet Date: March 18, 2017
Depth to Groundwater: 4.11 feet Sampler: Mansour Sepehr
Groundwater Elevation: 671.47 feet
Water Column Height: 20.49 feet
Purged Volume: 6 gallons

Purging Method: Bailer Pump

Sampling Method: Bailer Pump

Color: Yes No Describe: _____

Sheen: Yes No Describe: _____

Odor: Yes No Describe: _____

Field Measurements:

Time	Vol (gallons)	pH	Temp (°C)	E.C. (μs/cm)
11:10	2	7.77	19.2	593
11:15	4	7.57	18.2	586
11:19	6	7.61	17.9	575
	Sampled			

Notes:

EPA On-line Tools for Site Assessment Calculation

Hydraulic Gradient -- Magnitude and Direction

Gradient Calculation from fitting a plane to as many as thirty points

$$a x_1 + b y_1 + c = h_1$$

$$a x_2 + b y_2 + c = h_2$$

$$a x_3 + b y_3 + c = h_3$$

...

$$a x_{30} + b y_{30} + c = h_{30}$$


where (x_i, y_i) are the coordinates of the well and

h_i is the head

$i = 1, 2, 3, \dots, 30$

The coefficients a, b, and c are calculated by a least-squares fitting of the data to a plane

The gradient is calculated from the square root of $(a^2 + b^2)$ and the angle from the arctangent of a/b or b/a depending on the quadrant



Inputs

<input type="button" value="Example Data Set 1"/>	<input type="button" value="Example Data Set 2"/>	<input type="button" value="Calculate"/>	<input type="button" value="Clear"/>
<input type="button" value="Save Data"/>	<input type="button" value="Recall Data"/>	<input type="button" value="Go Back"/>	
Site Name	2844 Mountain Blvd, Oakla		
Date	March 18, 2017	<input type="button" value="Current Date"/>	
Calculation basis	<input type="button" value="Head"/>		
Coordinates	<input type="button" value="ft"/>		
I.D.	x-coordinate	y-coordinate	head
1) RS-3	6071215.111	2122442.671	671.43
2) RS-4	6071195.458	2122379.324	667.64
3) MW-1	6071174.931	2122404.178	670.19
4) MW-2	6071186.39	2122393.492	669.34
5) MW-3	6071190.453	2122428.874	671.47
6)			
7)			
8)			
9)			
10)			
11)			
12)			
13)			
14)			
15)			
16)			

17)		
18)		
19)		
20)		
21)		
22)		
23)		
24)		
25)		
26)		
27)		
28)		
29)		
30)		

Results

Number of Points Used in Calculation	5
Max. Difference Between Head Values	1.167
Gradient Magnitude (i)	0.08098
Flow direction as degrees from North (positive y axis)	150.8
Coefficient of Determination (R^2)	0.992

WCMS

Last updated on 2/23/2016

Appendix C

Laboratory Report and Chain of Custody Form



Curtis & Tompkins, Ltd., Analytical Laboratories, Since 1878

2323 Fifth Street, Berkeley, CA 94710, Phone (510) 486-0900

Laboratory Job Number 287165
ANALYTICAL REPORT

SOMA Environmental Engineering Inc. Project : 5081
6620 Owens Dr. Location : 2844 Mountain Blvd., Oakland
Pleasanton, CA 94588 Level : II

<u>Sample ID</u>	<u>Lab ID</u>
RS-3	287165-001
RS-4	287165-002
MW-1	287165-003
MW-2	287165-004
MW-3	287165-005

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the following signature. The results contained in this report meet all requirements of NELAC and pertain only to those samples which were submitted for analysis. This report may be reproduced only in its entirety.

Signature:

Date: 03/24/2017

Tracy Babjar
Project Manager
tracy.babjar@ctberk.com
(510) 204-2226 Ext 13107

CA ELAP# 2896, NELAP# 4044-001

CASE NARRATIVE

Laboratory number: **287165**
Client: **SOMA Environmental Engineering Inc.**
Project: **5081**
Location: **2844 Mountain Blvd., Oakland**
Request Date: **03/20/17**
Samples Received: **03/20/17**

This data package contains sample and QC results for five water samples, requested for the above referenced project on 03/20/17. The samples were received cold and intact.

Volatile Organics by GC/MS (EPA 8260B):
No analytical problems were encountered.

CHAIN OF CUSTODY

Curtis & Tompkins, Ltd

Analytical Laboratory Since 1878
2323 Fifth Street
Berkeley, CA 94710
(510)486-0900 Phone
(510)486-0532 Fax

LOGIN # 287165

LOGIN # 287152

Sampler: Mansour Sepehr

Project No: 5081

Project Name: 2844 Mountain Blvd., Oakland

Turnaround Time: Standard

卷之三

Report To: Joyce Bohek

Company : SOMA Environmental

卷之三

Fax: 925-734-6401

Lab No.	Sample ID.	Sampling Date Time	Water O ₂	# of Containers	Preservative			
					HCl	H ₂ SO ₄	HNO ₃	CE
RS-3		3/18/17 11:07	*	3 VOAs	*	*	*	*
RS-4		3/18/17 12:30	*	3 VOAs	*	*	*	*
MW-1		3/18/17 11:50	*	3 VOAs	*	*	*	*
MW-2		3/18/17 12:10	*	3 VOAs	*	*	*	*
MW-3		3/18/17 11:35	*	3 VOAs	*	*	*	*

Notes: EDF OUTPUT REQUIRED

— 1 —

RECEIVED BY:

John	3-20-17	11:37	DATE/TIME	John	3-20	11:37	DATE/TIME
John	3-20	16:02	DATE/TIME	John	3-20	16:02	DATE/TIME

Analyses

COOLER RECEIPT CHECKLIST



Curtis & Tompkins, Ltd.

Login # 287165 Date Received 3.20.17 Number of coolers 1
 Client SOMA Environmental Project 5081

Date Opened 3.20.17 By (print) DC (sign) [Signature]
 Date Logged in 3.20.17 By (print) DC (sign) [Signature]
 Date Labeled _____ By (print) _____ (sign) _____

1. Did cooler come with a shipping slip (airbill, etc) _____ YES NO
 Shipping info _____

2A. Were custody seals present? YES (circle) on cooler on samples NO
 How many _____ Name _____ Date _____

2B. Were custody seals intact upon arrival? _____ YES NO N/A

3. Were custody papers dry and intact when received? YES NO

4. Were custody papers filled out properly (ink, signed, etc)? YES NO

5. Is the project identifiable from custody papers? (If so fill out top of form) YES NO

6. Indicate the packing in cooler: (if other, describe) _____

Bubble Wrap Foam blocks Bags None
 Cloth material Cardboard Styrofoam Paper towels

7. Temperature documentation: * Notify PM if temperature exceeds 6°C

Type of ice used: Wet Blue/Gel None Temp(°C) 3.1

Temperature blank(s) included? Thermometer# _____ IR Gun# _____

Samples received on ice directly from the field. Cooling process had begun

8. Were Method 5035 sampling containers present? YES NO
 If YES, what time were they transferred to freezer? _____

9. Did all bottles arrive unbroken/unopened? YES NO

10. Are there any missing / extra samples? YES NO

11. Are samples in the appropriate containers for indicated tests? YES NO

12. Are sample labels present, in good condition and complete? YES NO

13. Do the sample labels agree with custody papers? YES NO

14. Was sufficient amount of sample sent for tests requested? YES NO

15. Are the samples appropriately preserved? YES NO N/A

16. Did you check preservatives for all bottles for each sample? YES NO N/A

17. Did you document your preservative check? (pH strip lot# _____) YES NO N/A

18. Did you change the hold time in LIMS for unpreserved VOAs? YES NO N/A

19. Did you change the hold time in LIMS for preserved terracores? YES NO N/A

20. Are bubbles > 6mm absent in VOA samples? YES NO N/A

21. Was the client contacted concerning this sample delivery? YES NO

If YES, Who was called? _____ By _____ Date: _____

COMMENTS



Curtis & Tompkins, Ltd.

Detections Summary for 287165

Results for any subcontracted analyses are not included in this summary.

Client : SOMA Environmental Engineering Inc.
Project : 5081
Location : 2844 Mountain Blvd., Oakland

No Detections

Analyte	Result	Flags	RL	Units	Basis	IDF	Method	Prep Method
tert-Butyl Alcohol (TBA)	33,000		710	ug/L	As Recd	71.43	EPA 8260B	EPA 5030B
Methyl tert-Amyl Ether (TAME)	45		7.1	ug/L	As Recd	14.29	EPA 8260B	EPA 5030B
MTBE	820		7.1	ug/L	As Recd	14.29	EPA 8260B	EPA 5030B

Analyte	Result	Flags	RL	Units	Basis	IDF	Method	Prep Method
Gasoline C7-C12	920		200	ug/L	As Recd	4.000	EPA 8260B	EPA 5030B
tert-Butyl Alcohol (TBA)	2,300		40	ug/L	As Recd	4.000	EPA 8260B	EPA 5030B
Methyl tert-Amyl Ether (TAME)	2.4		2.0	ug/L	As Recd	4.000	EPA 8260B	EPA 5030B
MTBE	34		2.0	ug/L	As Recd	4.000	EPA 8260B	EPA 5030B

Analyte	Result	Flags	RL	Units	Basis	IDF	Method	Prep Method
tert-Butyl Alcohol (TBA)	12,000		140	ug/L	As Recd	14.29	EPA 8260B	EPA 5030B
MTBE	88		7.1	ug/L	As Recd	14.29	EPA 8260B	EPA 5030B
Benzene	10		7.1	ug/L	As Recd	14.29	EPA 8260B	EPA 5030B

Analyte	Result	Flags	RL	Units	Basis	IDF	Method	Prep Method
tert-Butyl Alcohol (TBA)	140		10	ug/L	As Recd	1.000	EPA 8260B	EPA 5030B
Methyl tert-Amyl Ether (TAME)	10		0.50	ug/L	As Recd	1.000	EPA 8260B	EPA 5030B
MTBE	160		13	ug/L	As Recd	25.00	EPA 8260B	EPA 5030B

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Field ID:	RS-3	Batch#:	245784
Lab ID:	287165-001	Sampled:	03/18/17
Matrix:	Water	Received:	03/20/17
Units:	ug/L	Analyzed:	03/22/17
Diln Fac:	1.000		

Analyte	Result	RL
Gasoline C7-C12	ND	50
tert-Butyl Alcohol (TBA)	ND	10
Isopropyl Ether (DIPE)	ND	0.50
Ethyl tert-Butyl Ether (ETBE)	ND	0.50
Methyl tert-Amyl Ether (TAME)	ND	0.50
Ethanol	ND	1,000
MTBE	ND	0.50
1,2-Dichloroethane	ND	0.50
Benzene	ND	0.50
Toluene	ND	0.50
1,2-Dibromoethane	ND	0.50
Ethylbenzene	ND	0.50
m,p-Xylenes	ND	0.50
o-Xylene	ND	0.50

Surrogate	%REC	Limits
Dibromofluoromethane	97	80-120
1,2-Dichloroethane-d4	111	73-136
Toluene-d8	96	80-120
Bromofluorobenzene	96	80-120

ND= Not Detected

RL= Reporting Limit

Page 1 of 1

3.0

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Field ID:	RS-4	Units:	ug/L
Lab ID:	287165-002	Sampled:	03/18/17
Matrix:	Water	Received:	03/20/17

Analyte	Result	RL	Diln Fac	Batch#	Analyzed
Gasoline C7-C12	ND	710	14.29	245784	03/22/17
tert-Butyl Alcohol (TBA)	33,000	710	71.43	245794	03/23/17
Isopropyl Ether (DIPE)	ND	7.1	14.29	245784	03/22/17
Ethyl tert-Butyl Ether (ETBE)	ND	7.1	14.29	245784	03/22/17
Methyl tert-Amyl Ether (TAME)	45	7.1	14.29	245784	03/22/17
Ethanol	ND	14,000	14.29	245784	03/22/17
MTBE	820	7.1	14.29	245784	03/22/17
1,2-Dichloroethane	ND	7.1	14.29	245784	03/22/17
Benzene	ND	7.1	14.29	245784	03/22/17
Toluene	ND	7.1	14.29	245784	03/22/17
1,2-Dibromoethane	ND	7.1	14.29	245784	03/22/17
Ethylbenzene	ND	7.1	14.29	245784	03/22/17
m,p-Xylenes	ND	7.1	14.29	245784	03/22/17
o-Xylene	ND	7.1	14.29	245784	03/22/17

Surrogate	%REC	Limits	Diln Fac	Batch#	Analyzed
Dibromofluoromethane	95	80-120	14.29	245784	03/22/17
1,2-Dichloroethane-d4	113	73-136	14.29	245784	03/22/17
Toluene-d8	97	80-120	14.29	245784	03/22/17
Bromofluorobenzene	93	80-120	14.29	245784	03/22/17

ND= Not Detected

RL= Reporting Limit

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Field ID:	MW-1	Batch#:	245784
Lab ID:	287165-003	Sampled:	03/18/17
Matrix:	Water	Received:	03/20/17
Units:	ug/L	Analyzed:	03/22/17
Diln Fac:	4.000		

Analyte	Result	RL
Gasoline C7-C12	920	200
tert-Butyl Alcohol (TBA)	2,300	40
Isopropyl Ether (DIPE)	ND	2.0
Ethyl tert-Butyl Ether (ETBE)	ND	2.0
Methyl tert-Amyl Ether (TAME)	2.4	2.0
Ethanol	ND	4,000
MTBE	34	2.0
1,2-Dichloroethane	ND	2.0
Benzene	ND	2.0
Toluene	ND	2.0
1,2-Dibromoethane	ND	2.0
Ethylbenzene	ND	2.0
m,p-Xylenes	ND	2.0
o-Xylene	ND	2.0

Surrogate	%REC	Limits
Dibromofluoromethane	95	80-120
1,2-Dichloroethane-d4	112	73-136
Toluene-d8	97	80-120
Bromofluorobenzene	94	80-120

ND= Not Detected

RL= Reporting Limit

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Field ID:	MW-2	Batch#:	245784
Lab ID:	287165-004	Sampled:	03/18/17
Matrix:	Water	Received:	03/20/17
Units:	ug/L	Analyzed:	03/22/17
Diln Fac:	14.29		

Analyte	Result	RL
Gasoline C7-C12	ND	710
tert-Butyl Alcohol (TBA)	12,000	140
Isopropyl Ether (DIPE)	ND	7.1
Ethyl tert-Butyl Ether (ETBE)	ND	7.1
Methyl tert-Amyl Ether (TAME)	ND	7.1
Ethanol	ND	14,000
MTBE	88	7.1
1,2-Dichloroethane	ND	7.1
Benzene	10	7.1
Toluene	ND	7.1
1,2-Dibromoethane	ND	7.1
Ethylbenzene	ND	7.1
m,p-Xylenes	ND	7.1
o-Xylene	ND	7.1

Surrogate	%REC	Limits
Dibromofluoromethane	94	80-120
1,2-Dichloroethane-d4	115	73-136
Toluene-d8	96	80-120
Bromofluorobenzene	91	80-120

ND= Not Detected

RL= Reporting Limit

Page 1 of 1

6.0

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Field ID:	MW-3	Units:	ug/L
Lab ID:	287165-005	Sampled:	03/18/17
Matrix:	Water	Received:	03/20/17

Analyte	Result	RL	Diln Fac	Batch#	Analyzed
Gasoline C7-C12	ND	50	1.000	245784	03/22/17
tert-Butyl Alcohol (TBA)	140	10	1.000	245784	03/22/17
Isopropyl Ether (DIPE)	ND	0.50	1.000	245784	03/22/17
Ethyl tert-Butyl Ether (ETBE)	ND	0.50	1.000	245784	03/22/17
Methyl tert-Amyl Ether (TAME)	10	0.50	1.000	245784	03/22/17
Ethanol	ND	1,000	1.000	245784	03/22/17
MTBE	160	13	25.00	245794	03/23/17
1,2-Dichloroethane	ND	0.50	1.000	245784	03/22/17
Benzene	ND	0.50	1.000	245784	03/22/17
Toluene	ND	0.50	1.000	245784	03/22/17
1,2-Dibromoethane	ND	0.50	1.000	245784	03/22/17
Ethylbenzene	ND	0.50	1.000	245784	03/22/17
m,p-Xylenes	ND	0.50	1.000	245784	03/22/17
o-Xylene	ND	0.50	1.000	245784	03/22/17

Surrogate	%REC	Limits	Diln Fac	Batch#	Analyzed
Dibromofluoromethane	96	80-120	1.000	245784	03/22/17
1,2-Dichloroethane-d4	110	73-136	1.000	245784	03/22/17
Toluene-d8	97	80-120	1.000	245784	03/22/17
Bromofluorobenzene	94	80-120	1.000	245784	03/22/17

ND= Not Detected

RL= Reporting Limit

Batch QC Report
Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Matrix:	Water	Batch#:	245784
Units:	ug/L	Analyzed:	03/22/17
Diln Fac:	1.000		

Type: BS Lab ID: QC877956

Analyte	Spiked	Result	%REC	Limits
tert-Butyl Alcohol (TBA)	62.50	70.47	113	42-149
Isopropyl Ether (DIPE)	12.50	12.60	101	57-128
Ethyl tert-Butyl Ether (ETBE)	12.50	12.52	100	67-124
Methyl tert-Amyl Ether (TAME)	12.50	11.61	93	71-120
MTBE	12.50	11.75	94	63-120
1,2-Dichloroethane	12.50	13.28	106	66-130
Benzene	12.50	12.70	102	78-123
Toluene	12.50	12.41	99	80-120
1,2-Dibromoethane	12.50	10.62	85	76-120
Ethylbenzene	12.50	12.99	104	80-122
m,p-Xylenes	25.00	25.24	101	79-123
o-Xylene	12.50	10.91	87	77-120

Surrogate	%REC	Limits
Dibromofluoromethane	97	80-120
1,2-Dichloroethane-d4	110	73-136
Toluene-d8	96	80-120
Bromofluorobenzene	96	80-120

Type: BSD Lab ID: QC877957

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
tert-Butyl Alcohol (TBA)	62.50	61.01	98	42-149	14	38
Isopropyl Ether (DIPE)	12.50	11.92	95	57-128	6	20
Ethyl tert-Butyl Ether (ETBE)	12.50	12.06	96	67-124	4	20
Methyl tert-Amyl Ether (TAME)	12.50	11.14	89	71-120	4	20
MTBE	12.50	11.19	89	63-120	5	20
1,2-Dichloroethane	12.50	12.62	101	66-130	5	20
Benzene	12.50	12.23	98	78-123	4	20
Toluene	12.50	12.05	96	80-120	3	20
1,2-Dibromoethane	12.50	10.47	84	76-120	1	20
Ethylbenzene	12.50	12.34	99	80-122	5	20
m,p-Xylenes	25.00	24.51	98	79-123	3	20
o-Xylene	12.50	11.70	94	77-120	7	20

Surrogate	%REC	Limits
Dibromofluoromethane	97	80-120
1,2-Dichloroethane-d4	109	73-136
Toluene-d8	96	80-120
Bromofluorobenzene	95	80-120

RPD= Relative Percent Difference

Page 1 of 1

8.0

Batch QC Report

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Type:	BLANK	Diln Fac:	1.000
Lab ID:	QC877958	Batch#:	245784
Matrix:	Water	Analyzed:	03/22/17
Units:	ug/L		

Analyte	Result	RL
Gasoline C7-C12	ND	50
tert-Butyl Alcohol (TBA)	ND	10
Isopropyl Ether (DIPE)	ND	0.50
Ethyl tert-Butyl Ether (ETBE)	ND	0.50
Methyl tert-Amyl Ether (TAME)	ND	0.50
Ethanol	ND	1,000
MTBE	ND	0.50
1,2-Dichloroethane	ND	0.50
Benzene	ND	0.50
Toluene	ND	0.50
1,2-Dibromoethane	ND	0.50
Ethylbenzene	ND	0.50
m,p-Xylenes	ND	0.50
o-Xylene	ND	0.50

Surrogate	%REC	Limits
Dibromofluoromethane	94	80-120
1,2-Dichloroethane-d4	106	73-136
Toluene-d8	96	80-120
Bromofluorobenzene	95	80-120

ND= Not Detected

RL= Reporting Limit

Batch QC Report

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Matrix:	Water	Batch#:	245784
Units:	ug/L	Analyzed:	03/22/17
Diln Fac:	1.000		

Type: BS Lab ID: QC877959

Analyte	Spiked	Result	%REC	Limits
Gasoline C7-C12	1,000	1,098	110	80-120

Surrogate	%REC	Limits
Dibromofluoromethane	97	80-120
1,2-Dichloroethane-d4	107	73-136
Toluene-d8	97	80-120
Bromofluorobenzene	96	80-120

Type: BSD Lab ID: QC877960

Analyte	Spiked	Result	%REC	Limits	RPD Lim
Gasoline C7-C12	1,000	1,088	109	80-120	1 20

Surrogate	%REC	Limits
Dibromofluoromethane	95	80-120
1,2-Dichloroethane-d4	104	73-136
Toluene-d8	96	80-120
Bromofluorobenzene	95	80-120

RPD= Relative Percent Difference

Page 1 of 1

10.0

Batch QC Report
Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Matrix:	Water	Batch#:	245794
Units:	ug/L	Analyzed:	03/23/17
Diln Fac:	1.000		

Type: BS Lab ID: QC878009

Analyte	Spiked	Result	%REC	Limits
tert-Butyl Alcohol (TBA)	62.50	68.39	109	42-149
Isopropyl Ether (DIPE)	12.50	14.96	120	57-128
Ethyl tert-Butyl Ether (ETBE)	12.50	13.69	110	67-124
Methyl tert-Amyl Ether (TAME)	12.50	12.25	98	71-120
MTBE	12.50	12.64	101	63-120
1,2-Dichloroethane	12.50	10.05	80	66-130
Benzene	12.50	14.39	115	78-123
Toluene	12.50	13.18	105	80-120
1,2-Dibromoethane	12.50	11.88	95	76-120
Ethylbenzene	12.50	12.95	104	80-122
m,p-Xylenes	25.00	27.31	109	79-123
o-Xylene	12.50	13.50	108	77-120

Surrogate	%REC	Limits
Dibromofluoromethane	102	80-120
1,2-Dichloroethane-d4	82	73-136
Toluene-d8	104	80-120
Bromofluorobenzene	103	80-120

Type: BSD Lab ID: QC878010

Analyte	Spiked	Result	%REC	Limits	RPD	Lim
tert-Butyl Alcohol (TBA)	62.50	72.04	115	42-149	5	38
Isopropyl Ether (DIPE)	12.50	14.89	119	57-128	0	20
Ethyl tert-Butyl Ether (ETBE)	12.50	13.61	109	67-124	1	20
Methyl tert-Amyl Ether (TAME)	12.50	12.01	96	71-120	2	20
MTBE	12.50	12.84	103	63-120	2	20
1,2-Dichloroethane	12.50	9.752	78	66-130	3	20
Benzene	12.50	13.71	110	78-123	5	20
Toluene	12.50	13.05	104	80-120	1	20
1,2-Dibromoethane	12.50	12.04	96	76-120	1	20
Ethylbenzene	12.50	12.64	101	80-122	2	20
m,p-Xylenes	25.00	26.90	108	79-123	2	20
o-Xylene	12.50	13.60	109	77-120	1	20

Surrogate	%REC	Limits
Dibromofluoromethane	103	80-120
1,2-Dichloroethane-d4	79	73-136
Toluene-d8	104	80-120
Bromofluorobenzene	101	80-120

RPD= Relative Percent Difference

Page 1 of 1

11.0

Batch QC Report

Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Matrix:	Water	Batch#:	245794
Units:	ug/L	Analyzed:	03/23/17
Diln Fac:	1.000		

Type: BS Lab ID: QC878011

Analyte	Spiked	Result	%REC	Limits
Gasoline C7-C12	1,000	917.1	92	80-120

Surrogate	%REC	Limits
Dibromofluoromethane	105	80-120
1,2-Dichloroethane-d4	81	73-136
Toluene-d8	103	80-120
Bromofluorobenzene	101	80-120

Type: BSD Lab ID: QC878012

Analyte	Spiked	Result	%REC	Limits	RPD Lim
Gasoline C7-C12	1,000	911.2	91	80-120	1 20

Surrogate	%REC	Limits
Dibromofluoromethane	104	80-120
1,2-Dichloroethane-d4	80	73-136
Toluene-d8	105	80-120
Bromofluorobenzene	105	80-120

RPD= Relative Percent Difference

Page 1 of 1

12.0

Batch QC Report
Purgeable Organics by GC/MS

Lab #:	287165	Location:	2844 Mountain Blvd., Oakland
Client:	SOMA Environmental Engineering Inc.	Prep:	EPA 5030B
Project#:	5081	Analysis:	EPA 8260B
Type:	BLANK	Diln Fac:	1.000
Lab ID:	QC878013	Batch#:	245794
Matrix:	Water	Analyzed:	03/23/17
Units:	ug/L		

Analyte	Result	RL
Gasoline C7-C12	ND	50
tert-Butyl Alcohol (TBA)	ND	10
Isopropyl Ether (DIPE)	ND	0.50
Ethyl tert-Butyl Ether (ETBE)	ND	0.50
Methyl tert-Amyl Ether (TAME)	ND	0.50
Ethanol	ND	1,000
MTBE	ND	0.50
1,2-Dichloroethane	ND	0.50
Benzene	ND	0.50
Toluene	ND	0.50
1,2-Dibromoethane	ND	0.50
Ethylbenzene	ND	0.50
m,p-Xylenes	ND	0.50
o-Xylene	ND	0.50

Surrogate	%REC	Limits
Dibromofluoromethane	100	80-120
1,2-Dichloroethane-d4	81	73-136
Toluene-d8	106	80-120
Bromofluorobenzene	113	80-120

ND= Not Detected

RL= Reporting Limit

Data File: \\gcmsserver\\DD\\chem\\MSWD08.i\\032217\\HCM15.D

Date : 22-Mar-2017 19:37

Client ID:

Sample Info: s,287165-003


Column phase:

\\gcmsserver\\DD\\chem\\MSWD08.i\\032217\\HCM15.D

Instrument: MSWD08.i

Operator: VOC

Column diameter: 2.00



Data File: \\gcmsserver\DD\chem\MSWD08.i\032217\HCM07.D

Date : 22-Mar-2017 15:07

Client ID:

Sample Info: bs,qc877959,245784,s31872,.01/100

Column phase:

\\gcmsserver\DD\chem\MSWD08.i\032217\HCM07.D

Instrument: MSWD08.i

Operator: VOC

Column diameter: 2.00

