

**R.T. NAHAS COMPANY** *Since 1947*  
REAL ESTATE DEVELOPERS AND INVESTORS

SEP 24 2001

20630 PATIO DRIVE  
CASTRO VALLEY, CALIFORNIA 94546  
TELEPHONE (510) 538-9600  
FAX (510) 881-7618

September 18, 2001

Mr. Scott Seery  
Hazardous Materials Specialist  
Alameda County Health Care Services  
1131 Harbor Bay Pkwy., Room 250  
Oakland, CA 94502-6577

Dear Scott:

Enclosed is the Fourth Semi-Annual Groundwater Monitoring report for the third quarter of 2001.

I wonder if you would consider relieving our obligation of monitoring Well No. 7, and perhaps No. 6, as the TPH gasoline appears to be cleaning fluid and not gasoline. I would just as soon not be responsible for having to dispose of this stuff. You can continue to monitor Wells 2, 3 and 101.

Please let me know your feelings on this.

Sincerely,

  
Randall E. Nahas

Enclosure  
REN/tar

SEP 24 2001

**Report – Fourth Semi-Annual  
Groundwater Monitoring  
(Third Quarter of 2001)  
Former Unocal 76 Service Station  
20405 and 20629 Redwood Road  
Castro Valley, California**

7/01

**BSK & ASSOCIATES  
Geotechnical Consultants, Inc.**

**BSK JOB NO. P92057.3**

**Submitted to:  
R.T. Nahas Company  
Castro Valley, California**

**September 17, 2001**

---

© BSK & ASSOCIATES, GEOTECHNICAL CONSULTANTS, INC., 2001  
All rights reserved

**BSK**



1181 Quarry Lane, Building 300  
Pleasanton, CA 94566  
(925) 462-4000 • FAX (925) 462-6283

September 17, 2001

**BSK JOB NO. P92057.3**

R. T. Nahas Company/Eden Managements  
20630 Patio Drive  
Castro Valley, CA 94546

Attention: Mr. Randy T. Nahas

Subject: **Report**  
Fourth Semi-Annual Groundwater Monitoring  
(Third Quarter of 2001)  
Former Unocal 76 Service Station  
20405 and 20629 Redwood Road  
Castro Valley, California

Dear Mr. Nahas:

As requested and authorized, we have performed groundwater monitoring well sampling at the above-referenced facility. This report presents the groundwater data obtained during this and previous sampling events, conclusions based on this event's data, and recommendations for further action. The site location is shown on Figure 1, Vicinity Map. The well locations are shown on Figure 2, Site Plan.

## **GROUNDWATER MONITORING ACTIVITIES – AUGUST 2001**

### **General**

Fourth semi-annual monitoring of groundwater Monitoring Wells MW-2, MW-3, MW-6, MW-7 and MW-101 (Figure 2, Site Plan) was performed on August 23, 2001. The groundwater monitoring well MW-4 was abandoned during the remediation activities carried out in 1999 by others at the Site. The semi-annual sampling schedule—with monitoring activities in the first and third quarter of each year—was requested by Mr. Scott Seery, case officer for the ACDEH, in a letter, dated November 2, 1999, addressed to the R. T. Nahas Company. Further, in accordance with Mr. Seery's letter of April 24, 2001, sampling of Well MW-5 was discontinued as of this sampling round. Field procedures and observations are provided in the following text.

### **Field Work**

All wells were purged using a disposable bailer. Three to four well casing volumes of water were removed from each well. Purge effluent was field monitored for pH, temperature and conductivity during purging to assess the influx of fresh formation water into the well. Purged water was transferred to 55-gallon, DOT-approved steel drums for holding. Each drum was labeled according to its contents, content source, and date of accumulation.

Prior to purging, the depth to water in each well was measured using a Solinst Electric Well Sounder, marked in twentieths of a foot. The water depth was then interpolated to the 0.01 foot increment from the tape. Each well was subsequently examined for floating and sinking immiscible product layers and sheen, using a clear bailer having dual check valves for point-source sampling. The piezometric contour and elevation, and well water elevations, are presented in Figure 3, Groundwater Elevation Contour Map.

Upon purge completion, each well was again measured to confirm a minimum of 80% well recovery prior to sampling. Water sampling was then performed with a Teflon® point-source bailer. Sampling for contaminants was performed in the order of decreasing contaminant volatility. Each water sample was decanted into the appropriate container with preservative (as necessary), sealed, labeled and refrigerated for delivery to our State-certified laboratory.

A Well Field Log was prepared for each well sampled, recording the water depth, well volume, pH, water temperature, conductivity and other data. The Well Field Logs are presented as Figures 4.1 through 4.6.

### **Site Hydrology**

The groundwater level in all six wells was measured on August 23, 2001, in order to assess the flow direction and gradient. On that date, groundwater flow was generally to the south, with a gradient of 0.011 ft/ft (Figure 3).

### **Chemical Analyses**

Water samples obtained from each of the wells were analyzed for constituents related to gasoline, Total Petroleum Hydrocarbons as Gasoline (TPHg), Benzene, Toluene, Ethylbenzene and Xylene (BTEX) and Methyl-t-Butyl Ether (MTBE).

The contaminants tested for are those specified by ACDEH, in their letter dated, November 2, 1999. Current and former analysis results are presented for comparison in Table 1. Records of current and past concentrations of BTEX and MTBE in the groundwater samples from MW-2 and MW-3 are graphically presented on Figures 5 and 6, respectively. The Chemical Test Data Sheets are presented in Appendix A along with the Project Chain-of-Custody record.

## CONCLUSIONS AND RECOMMENDATIONS

### Conclusions

Trace contaminant concentrations associated with gasoline (BTEX compounds) are generally at lower concentrations compared to the previous results from the March 2001 sampling event in Wells MW-2 and MW-101. Total Petroleum Hydrocarbons as Gasoline, BTEX and MTBE were not detected in Well MW-3. The Total Petroleum Hydrocarbons as Gasoline detected in well MW-7 probably represents Perchloroethane as was demonstrated in past sampling events.

MTBE was detected in Wells MW-2, MW-3, MW-6 and MW-101. The MTBE detected in majority of wells was confirmed using EPA Method 8260.

### Recommendations

The five groundwater monitoring wells located at the Site should be sampled on a semi-annual basis as requested by ACDEH (letter dated April 24, 2001). The next semi-annual sampling event is scheduled for March 2002.

## REPORT DISTRIBUTION

Copies of this report should be submitted to the Alameda County Department of Environmental Health for their review. We are providing you with extra copies for this purpose. We understand that copies of the report may be forwarded by ACDEH to the Regional Water Quality Control Board in Oakland for their review.

Alameda County Department of Environmental Health  
1181 Harbor Bay Parkway  
Alameda, CA 94502

## LIMITATIONS

The findings and conclusions presented in this report are based on field review and observations, and from the limited testing program described in this report. This report has been prepared in accordance with generally accepted methodologies and standards of practice in the area. No other warranties, expressed or implied, are made as to the findings, conclusions and recommendations included in the report.

The findings of this report are valid as of the present. The passage of time, natural processes or human intervention on the property or adjacent property can cause changed conditions which can invalidate the findings and conclusions presented in this report.


\* \* \*

BSK is pleased to continue to be of service to you during this project. If you have questions concerning the contents of the report, please do not hesitate to contact us.

The following are attached and complete this report:

|              |         |   |
|--------------|---------|---|
| TABLE        | 1       | Summary of Groundwater Analysis   |
| FIGURE       | 1       | Vicinity Map  |
| FIGURE       | 2       | Site Plan   |
| FIGURE       | 3       | Groundwater Elevation Contour Map   |
| FIGURES      | 4.1-4.6 | Well Field Logs   |
| FIGURE       | 5       | BTEX/MTBE Concentrations in Groundwater - MW-2                                      |
| FIGURE       | 6       | BTEX/MTBE Concentrations in Groundwater - MW-3                                      |
| Appendix "A" |         | Laboratory Chemical Test Data Sheets and Project Chain-of-Custody Record (7 sheets) |

Respectfully submitted,  
*BSK & Associates*



Girish Agrawal, Ph.D., P.E., G.E.  
Senior Project Engineer  
C.E. 53867, G.E. 2478



Alex Y. Eskandari, P.E.  
Project Manager  
C.E. 38101

AYE/GA:ga

(G:\DOCUMENT\Environmental\Projects\NAHAS\2001-Q3\P92057(September2001).wpd)

Distribution:

R. T. Nahas Company (4 copies)

TABLE 1, SUMMARY OF GROUNDWATER ANALYSIS, Results in ug/L

| Sample Date    | Well Number | Benzene | Toluene | Ethyl-Benzene | Xylenes | Methyl-Butyl Ether                   | TPH Gasoline | TPH Diesel | Total Oil & Grease | EPA 601 |
|----------------|-------------|---------|---------|---------------|---------|--------------------------------------|--------------|------------|--------------------|---------|
| August 2001    | MW-2        | ND      | ND      | ND            | ND      | 690 <sup>2</sup> /820 <sup>3</sup>   | 160          | --         | --                 | --      |
|                | MW-3        | ND      | ND      | ND            | ND      | 26                                   | ND           | --         | --                 | --      |
|                | MW-5 *      | --      | --      | --            | --      | --                                   | --           | --         | --                 | --      |
|                | MW-6        | ND      | ND      | ND            | ND      | 280 <sup>2</sup> /358 <sup>3</sup>   | 79           | --         | --                 | --      |
|                | MW-7        | ND      | ND      | ND            | ND      | 7.3 <sup>3</sup> /ND <sup>3</sup>    | 800          | --         | --                 | --      |
|                | MW-101      | 630     | ND      | 1500          | 480     | 1400                                 | 12000        | --         | --                 | --      |
| March 2001     | MW-2        | 22      | 1.5     | 17            | 27      | 1300 <sup>2</sup> /1200 <sup>3</sup> | 1000         | --         | --                 | --      |
|                | MW-3        | ND      | ND      | ND            | ND      | 190                                  | ND           | --         | --                 | --      |
|                | MW-5        | ND      | ND      | ND            | ND      | ND                                   | ND           | --         | --                 | --      |
|                | MW-6        | ND      | ND      | ND            | ND      | 440                                  | 130          | --         | --                 | --      |
|                | MW-7        | ND      | ND      | ND            | ND      | ND                                   | 630          | --         | --                 | --      |
|                | MW-101      | 1400    | 62      | 3400          | 7700    | 970                                  | 34000        | --         | --                 | --      |
| September 2000 | MW-2        | 0.89    | ND      | 1             | 0.65    | 620                                  | 180          | --         | --                 | --      |
|                | MW-3        | ND      | ND      | ND            | ND      | 98                                   | ND           | --         | --                 | --      |
|                | MW-5        | ND      | ND      | ND            | ND      | ND                                   | ND           | --         | --                 | --      |
|                | MW-6        | ND      | ND      | ND            | ND      | 170                                  | 54           | --         | --                 | --      |
|                | MW-7        | 3       | 0.32    | 13            | 27      | ND                                   | 770          | --         | --                 | --      |
|                | MW-101      | 1100    | 35      | 2900          | 400     | 1600 <sup>2</sup> /1800 <sup>3</sup> | 12000        | --         | --                 | --      |
| September 1995 | MW-101      | 170     | 94      | 150           | 710     | --                                   | 9400         | --         | --                 | --      |
| March 2000     | MW-2        | 14      | 0.92    | 16            | 24      | 1400                                 | 560          | --         | --                 | --      |
|                | MW-3        | 0.61    | ND      | ND            | ND      | 240                                  | 96           | --         | --                 | --      |
|                | MW-5        | ND      | ND      | ND            | ND      | ND                                   | ND           | --         | --                 | --      |
|                | MW-6        | ND      | 0.49    | ND            | ND      | 260                                  | 78           | --         | --                 | --      |
|                | MW-7        | 890     | ND      | ND            | ND      | ND                                   | ND           | --         | --                 | --      |
|                | MW-101      | 2500    | 490     | 4300          | 10000   | 2400 <sup>2</sup> /1400 <sup>3</sup> | 40000        | --         | --                 | --      |
| November 1997  | MW-2        | 6.8     | 0.64    | 4.7           | 8.2     | 1200                                 | 360          | --         | --                 | --      |
|                | MW-3        | 1.7     | 1.4     | 2.3           | 8.3     | 65                                   | 62           | --         | --                 | --      |
|                | MW-4        | ND      | ND      | ND            | ND      | ND                                   | ND           | ND         | --                 | --      |
|                | MW-5        | ND      | ND      | ND            | ND      | ND                                   | ND           | ND         | --                 | --      |
|                | MW-6        | ND      | ND      | ND            | ND      | 9                                    | ND           | ND         | --                 | --      |
|                | MW-7        | --      | --      | --            | --      | --                                   | --           | --         | --                 | --      |

TABLE 1, SUMMARY OF GROUNDWATER ANALYSIS, Results in ug/L

| Sample Date  | Well Number  | Benzene | Toluene | Ethyl-Benzene | Xylenes | Methyl-t-Butyl Ether | TPH Gasoline | TPH Diesel | Total Oil & Grease | EPA 601 |
|--------------|--------------|---------|---------|---------------|---------|----------------------|--------------|------------|--------------------|---------|
| April 1997   | MW-2         | 23      | 1.6     | 21            | 31.4    | 1800                 | 470          | --         | --                 | --      |
|              | MW-3         | 7.3     | ND      | 3.3           | 5.4     | 230                  | 120          | --         | --                 | --      |
|              | MW-4         | ND      | ND      | ND            | ND      | ND                   | ND           | ND         | --                 | --      |
|              | MW-5         | ND      | ND      | ND            | ND      | ND                   | ND           | --         | --                 | --      |
|              | MW-6         | ND      | ND      | ND            | ND      | ND                   | ND           | --         | --                 | --      |
|              | MW-7         | --      | --      | --            | --      | --                   | --           | --         | --                 | --      |
|              | October 1996 | MW-2    | 9.4     | 0.5           | 7.2     | 9.4                  | 1400         | 180        | --                 | --      |
| MW-3         |              | 3.8     | 1.5     | 2.1           | 6.8     | 55                   | 79           | --         | --                 | --      |
| MW-4         |              | ND      | ND      | ND            | ND      | ND                   | ND           | ND         | --                 | --      |
| MW-5         |              | ND      | ND      | ND            | ND      | ND                   | ND           | --         | --                 | --      |
| MW-6         |              | ND      | ND      | ND            | ND      | 17                   | ND           | --         | --                 | --      |
| MW-7         |              | --      | --      | --            | --      | --                   | --           | --         | --                 | --      |
| April 1996   |              | MW-2    | 41      | 2.8           | 27      | 50                   | --           | 690        | --                 | --      |
|              | MW-3         | 8.4     | 1.6     | 4.7           | 14      | --                   | 170          | --         | --                 | --      |
|              | MW-4         | ND      | ND      | ND            | ND      | --                   | ND           | ND         | --                 | --      |
|              | MW-5         | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --      |
|              | MW-6         | 2.9     | 2.9     | ND            | ND      | --                   | ND           | --         | --                 | --      |
|              | MW-7         | ND      | ND      | ND            | ND      | --                   | --           | --         | --                 | --      |
|              | October 1995 | MW-2    | 7.4     | ND            | 5.1     | 5.5                  | --           | 450        | --                 | --      |
| MW-3         |              | 9       | 3.9     | 8.5           | 34      | --                   | 340          | --         | --                 | --      |
| MW-4         |              | ND      | ND      | ND            | ND      | --                   | ND           | ND         | --                 | --      |
| MW-5         |              | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --      |
| MW-6         |              | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --      |
| MW-7         |              | ND      | ND      | ND            | ND      | --                   | --           | --         | --                 | --      |
| April 1995   |              | MW-2    | 72      | 2.8           | 47      | 22                   | --           | 480        | --                 | --      |
|              | MW-3         | 26      | 0.6     | 40            | 19      | --                   | 450          | --         | --                 | --      |
| April 1995   | MW-4         | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --      |
|              | MW-5         | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --      |
|              | MW-6         | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --      |
|              | MW-7         | ND      | ND      | ND            | ND      | --                   | --           | --         | --                 | --      |
| January 1995 | MW-2         | 48      | 2.8     | 15            | 27      | --                   | 440          | --         | --                 | --      |
|              | MW-3         | 26      | 0.6     | 14            | 45      | --                   | 250          | --         | --                 | --      |
|              | MW-4         | ND      | ND      | ND            | ND      | --                   | ND           | ND         | 2000               | --      |



TABLE 1, SUMMARY OF GROUNDWATER ANALYSIS, Results in ug/L

| Sample Date  | Well Number | Benzene | Toluene | Ethyl-Benzene | Xylenes | Methyl-t-Butyl Ether | TPH Gasoline | TPH Diesel | Total Oil & Grease | EPA 601                                      |
|--------------|-------------|---------|---------|---------------|---------|----------------------|--------------|------------|--------------------|--|
| October 1994 | MW-2        | 2.8     | ND      | 2.9           | 1.8     | --                   | 97           | --         | --                 | --   |
|              | MW-3        | 0.9     | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|              | MW-4        | ND      | 36      | ND            | 1.3     | --                   | 70           | ND         | ND                 | --   |
|              | MW-5        | ND      | 71      | 0.4           | 1.7     | --                   | 87           | --         | --                 | --   |
|              | MW-6        | 0.4     | 140     | 0.5           | 2.3     | --                   | 160          | --         | --                 | --   |
| July 1994    | MW-2        | 14      | 0.7     | 5.8           | 12      | --                   | 180          | --         | --                 | --   |
|              | MW-3        | 7.2     | 0.4     | 1.6           | 4.6     | --                   | 52           | --         | --                 | --   |
|              | MW-4        | ND      | 0.6     | ND            | ND      | --                   | ND           | 86         | ND                 | --   |
| April 1994   | MW-2        | 23      | 1.1     | 8.2           | 17      | --                   | 270          | --         | --                 | --   |
|              | MW-3        | 17      | 1       | 4.9           | 24      | --                   | 62           | --         | --                 | --   |
|              | MW-4        | ND      | ND      | ND            | 0.4     | --                   | ND           | ND         | ND                 | --   |
|              | MW-5        | ND      | 0.4     | ND            | 1       | --                   | ND           | --         | --                 | --   |
|              | MW-6        | ND      | 0.3     | ND            | 0.4     | --                   | ND           | --         | --                 | --   |
|              | MW-7        | ND      | ND      | ND            | ND      | --                   | 360 (1)      | --         | --                 | --   |
| January 1994 | MW-2        | 13      | 3.4     | 4.9           | 9.2     | --                   | 130          | --         | --                 | --   |
|              | MW-3        | 5.5     | 2.1     | 2.6           | 14      | --                   | 69           | --         | --                 | --   |
|              | MW-7        | ND      | ND      | ND            | ND      | --                   | 330 (1)      | --         | --                 | --   |
| October 1993 | MW-2        | 4       | ND      | 2.3           | 3.1     | --                   | 98           | --         | --                 | --   |
|              | MW-3        | 5       | ND      | 0.6           | 1.2     | --                   | ND           | --         | --                 | --   |
|              | MW-4        | 0.4     | ND      | ND            | 0.4     | --                   | ND           | ND         | ND                 | Tetrachloroethene 0.7<br>Trichloroethene 0.9 |
|              | MW-5        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|              | MW-6        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|              | MW-7        | ND      | ND      | ND            | 0.7     | --                   | 360 (1)      | --         | --                 | --   |
|              | MW-7        | ND      | ND      | ND            | 0.7     | --                   | 360 (1)      | --         | --                 | --   |
| July 1993    | MW-2        | 17      | 1.1     | 6             | 12      | --                   | 220          | --         | --                 | --   |
|              | MW-3        | 24      | 11      | 14            | 82      | --                   | 330          | --         | --                 | --   |
|              | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | 1000               | --   |
|              | MW-5        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|              | MW-6        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|              | MW-7        | ND      | ND      | ND            | ND      | --                   | 680 (1)      | --         | --                 | --   |
| March 1993   | MW-2        | 110     | 32      | 67            | 28      | --                   | 720          | --         | --                 | 1,2-Dichloroethane 0.6                       |
|              | MW-3        | 32      | 0.9     | 64            | 13      | --                   | 330          | --         | --                 | --   |
|              | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | ND   |

TABLE 1, SUMMARY OF GROUNDWATER ANALYSIS, Results in ug/L

| Sample Date   | Well Number | Benzene | Toluene | Ethyl-Benzene | Xylenes | Methyl-t-Butyl Ether | TPH Gasoline | TPH Diesel | Total Oil & Grease | EPA 601  |
|---------------|-------------|---------|---------|---------------|---------|----------------------|--------------|------------|--------------------|--|
| March 1993    | MW-5        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | Tetrachloroethane 0.8  |
|               | MW-6        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | Tetrachloroethane 3.5  |
|               | MW-7        | ND      | ND      | ND            | ND      | --                   | 830 (1)      | --         | --                 | Tetrachloroethene 3,700<br>Trichloroethene 210   |
| January 1993  | MW-2        | 11      | 5.1     | 1.4           | 6.3     | --                   | 170          | --         | --                 | --   |
|               | MW-3        | 1.2     | 1       | 0.6           | 4.1     | --                   | ND           | --         | --                 | --   |
|               | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --   |
|               | MW-5        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-6        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-7        | ND      | ND      | ND            | ND      | --                   | 1900 (1)     | --         | --                 | --   |
| November 1992 | MW-7        | --      | --      | --            | --      | --                   | 2700 (1)     | ND         | --                 | Chlorobenzene 2.0<br>Chloroform 2.0<br>cis-1,2-Dichloroethene 180<br>trans-1,2-Dichloroethene 1.5<br>Tetrachloroethene 14,000<br>Trichloroethene 660 |
| October 1992  | MW-2        | 2.3     | ND      | 2.3           | 3       | --                   | ND           | --         | --                 | --   |
|               | MW-3        | 2.1     | ND      | ND            | 0.3     | --                   | ND           | --         | --                 | --   |
|               | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | 120        | ND                 | --   |
|               | MW-5        | ND      | 0.4     | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-6        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-7        | ND      | ND      | ND            | ND      | --                   | 3900 (1)     | --         | --                 | --   |
| July 1992     | MW-2        | 10      | ND      | 0.6           | 2.3     | --                   | 84           | --         | --                 | --   |
|               | MW-3        | 1.3     | 0.4     | ND            | 1.3     | --                   | ND           | --         | --                 | --   |
|               | MW-5        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-7        | ND      | ND      | ND            | ND      | --                   | 830 (1)      | --         | --                 | --   |
| April 1992    | MW-2        | 70      | 0.3     | 15            | 7       | --                   | 300          | --         | --                 | --   |
|               | MW-3        | 1       | 0.4     | ND            | 0.9     | --                   | ND           | --         | --                 | --   |
|               | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --   |
| April 1992    | MW-5        | ND      | ND      | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-6        | ND      | 0.3     | ND            | ND      | --                   | ND           | --         | --                 | --   |
|               | MW-7        | 0.4     | 0.3     | 0.3           | 0.9     | --                   | 1300 (1)     | --         | --                 | --   |

TABLE 1, SUMMARY OF GROUNDWATER ANALYSIS, Results in ug/L

| Sample Date                     | Well Number | Benzene | Toluene | Ethyl-Benzene | Xylenes | Methyl-t-Butyl Ether | TPH Gasoline | TPH Diesel | Total Oil & Grease | EPA 601  |
|---------------------------------|-------------|---------|---------|---------------|---------|----------------------|--------------|------------|--------------------|--|
| January 1992                    | MW-2        | 480     | 870     | 160           | 860     | --                   | 5200         | --         | --                 | --   |
|                                 | MW-3        | 4       | 10      | 2             | 8       | --                   | 60           | --         | --                 | --   |
| October 1991                    | MW-2        | 2.9     | ND      | 2.5           | 6       | --                   | 170          | --         | --                 | --   |
|                                 | MW-3        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --   |
|                                 | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --   |
| July 1991                       | MW-2        | 14      | 1       | 17            | 8       | --                   | 220          | --         | --                 | --   |
|                                 | MW-3        | 14      | 14      | 33            | 8       | --                   | 220          | --         | --                 | --   |
| April 1991                      | MW-2        | 640     | 520     | 170           | 790     | --                   | 4800         | --         | --                 | --   |
|                                 | MW-3        | 450     | 270     | 150           | 760     | --                   | 3600         | --         | --                 | --   |
|                                 | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --   |
| January 1991                    | MW-2        | 50      | 33      | 22            | 110     | --                   | 430          | --         | --                 | --   |
|                                 | MW-3        | 29      | 3.3     | 9.7           | 34      | --                   | 110          | --         | --                 | --   |
| August 1990                     | MW-2        | 21      | 3.9     | 7.2           | 28      | --                   | 180          | --         | --                 | --   |
|                                 | MW-3        | 55      | 3.8     | 20            | 59      | --                   | 290          | --         | --                 | --   |
|                                 | MW-4        | ND      | ND      | ND            | ND      | --                   | ND           | ND         | ND                 | --   |
| Maximum Contaminant Level (MCL) |             | 1       | 150     | 700           | 1750    | NA                   | NA           | NA         | NA                 | Chlorobenzene - NA<br>Chloroform - NA<br>cis-1,2-Dichloroethene 6.0<br>trans-1,2-Dichloroethene 10.0<br>1,2-Dichloroethane 0.5<br>Tetrachloroethene 5.0<br>Trichloroethene 5.0 |

ND = None Detected

-- = Not Analyzed

\* = Water level sounding only. No sampling.

NA = Not Available

1 = TPHg values have demonstrated to represent Perchloroethane presence

2 = MTBE by EPA 8015/8020

3 = MTBE by EPA 8260

MCLs from California Code of Regulations Title 22, Article 5.5






Semi-Annual  
 Groundwater Monitoring Report  
 Former Unocal 76 Service Station  
 20405 and 20629 Redwood Road  
 Castro Valley, California


VICINITY MAP  
 FIGURE: 1  
 BSK Job No. P92057.3







Redwood Road


|   |  |  |  |
|---|--|--|--|
| <p><b>LEGEND</b></p> <p> Groundwater Monitoring Well Location &amp; Designation</p> | <p>0                      50                      100</p> <p>Approximate Scale in Feet</p> | <p>BSK Job No. P92057.3</p> <p><b>SITE PLAN</b></p> <p><b>FIGURE 2</b></p> |  |
|---|--|--|--|



Modified by: Girish Agrawal  
 Date: April 23, 2001

**LEGEND**

- 
 Groundwater Monitoring Well  
 (Groundwater Elevation)
- 
 Groundwater Elevation Contour  
 in feet above MSL



BSK Job No. P92057.3  
**GROUNDWATER ELEVATION CONTOUR MAP**  
 August 2001  
**FIGURE 3**



## WELL FIELD LOG

**Well Observation:**                      **Date:** 08/23/2001  
**Sample Collection:**                    **Date:** 08/23/2001

**Project Name:**            Groundwater Monitoring  
**Location:**                Nahas/Former Union 76  
**Personnel:**                JD  
**Weather:**                 Sunny, Hot

**WELL INFORMATION:**

|  |                               |                     |            |
|--|-------------------------------|---------------------|------------|
| <b>Well Number</b>                     | MW-2                          | <b>Date Purged</b>  | 08/23/2001 |
| <b>Depth to Water - feet( TOC)</b>     | 9.65                          | <b>Purge Method</b> | Bailer     |
| <b>Well Depth (feet)</b>               | 28.85                         |                     |            |
| <b>Water Volume (gallons)</b>          | 3.2                           | <b>Purge Begin</b>  | 14:30      |
| <b>Reference Elevation - feet(TOC)</b> | +183.47                       | <b>Purge End</b>    | 14:27      |
| <b>Groundwater Elevation (feet)</b>    | 173.82                        | <b>Purge Rate</b>   | 0.27 gpm   |
| <b>Measurement Technique</b>           | Solinst Electric Well Sounder |                     |            |

**IMMISCIBLE LAYERS:**

**Top:** None Observed  
**Bottom:** None Observed  
**Detection Method:** Visual  
**Collection Method:** Clear Point-Source Bailer

**WELL DEVELOPMENT/PURGE DATA:**

| TIME  | VOLUME REMOVED (gallons) | ELECTRICAL CONDUCTIVITY (micromhos) | pH   | TEMP. (°F) | COLOR/COMMENTS |
|-------|--------------------------|-------------------------------------|------|------------|----------------|
| 14:42 | 3.25                     | 594                                 | 6.43 | 72         | Clear          |
| 14:52 | 6.50                     | 500                                 | 6.32 | 75         | Clear          |
| 15:04 | 9.75                     | 487                                 | 6.34 | 71         | Clear          |
| 15:18 | 13.00                    | 483                                 | 6.60 | 71         | Clear          |

**SAMPLE COLLECTION DATA**

**Sampling Equipment:** Teflon Bailer

| TIME  | ANALYSIS         | AMOUNT/CONTAINER USED     | SAMPLE INTERVAL |
|-------|------------------|---------------------------|-----------------|
| 15:20 | BTEX/MTBE & TPHg | 2-40ml glass VOA with HCl |                 |

**Field Notes:**

## WELL FIELD LOG

Well Observation:                      Date: 08/23/2001  
 Sample Collection:                    Date: 08/23/2001

Project Name: Groundwater Monitoring  
 Location:        Nahas/Former Union 76  
 Personnel:      JD  
 Weather:        Sunny, Hot

**WELL INFORMATION:**

|                                 |                               |              |            |
|---------------------------------|-------------------------------|--------------|------------|
| Well Number                     | MW-3                          | Date Purged  | 08/23/2001 |
| Depth to Water - feet(IOC)      | 10.02                         | Purge Method | Bailer     |
| Well Depth (feet)               | 28.85                         |              |            |
| Water Volume (gallons)          | 3.06                          | Purge Begin  | 15:30      |
| Reference Elevation - feet(IOC) | +184.03                       | Purge End    | 16:13      |
| Groundwater Elevation (feet)    | 174.01                        | Purge Rate   | 0.30 gpm   |
| Measurement Technique           | Solinst Electric Well Sounder |              |            |

**IMMISCIBLE LAYERS:**

Top: Slight Yellow Tint, No Odor  
 Bottom: None Observed  
 Detection Method: Visual  
 Collection Method: Clear Point-Source Bailer

**WELL DEVELOPMENT/PURGE DATA:**

| TIME  | VOLUME REMOVED (gallons) | ELECTRICAL CONDUCTIVITY (micromhos) | pH   | TEMP. (°F) | COLOR/COMMENTS   |
|-------|--------------------------|-------------------------------------|------|------------|------------------|
| 15:40 | 3.25                     | 705                                 | 6.57 | 71         | Light brown tint |
| 15:50 | 6.50                     | 710                                 | 6.42 | 71         | Clearing         |
| 16:01 | 9.75                     | 705                                 | 6.40 | 70         | Clear            |
| 16:13 | 13.00                    | 705                                 | 6.40 | 70         | Clear            |

**SAMPLE COLLECTION DATA**

Sampling Equipment: Teflon Bailer

| TIME  | ANALYSIS         | AMOUNT/CONTAINER USED     | SAMPLE INTERVAL |
|-------|------------------|---------------------------|-----------------|
| 16:15 | BTEX/MTBE & TPHg | 2-40ml glass VOA with HCl |                 |

Field Notes:



## WELL FIELD LOG

Well Observation:                      Date: 08/23/2001

Sample Collection:                      Date: 08/23/2001

Project Name: Groundwater Monitoring

Location: Nahas/Former Union 76

Personnel: JD

Weather: Sunny, Hot

**WELL INFORMATION:**

|                                 |                               |              |            |
|---------------------------------|-------------------------------|--------------|------------|
| Well Number                     | MW-101                        | Date Purged  | 08/23/2001 |
| Depth to Water - feet(TOC)      | 9.70                          | Purge Method | Bailer     |
| Well Depth (feet)               | 29.0                          |              |            |
| Water Volume (gallons)          | 12.6                          | Purge Begin  | 17:20      |
| Reference Elevation - feet(TOC) | —                             | Purge End    | 18:13      |
| Groundwater Elevation (feet)    | —                             | Purge Rate   | 0.96gpm    |
| Measurement Technique           | Solinst Electric Well Sounder |              |            |

**IMMISCIBLE LAYERS:**

Top: None observed

Bottom: None Observed

Detection Method: Visual

Collection Method: Clear Point-Source Bailer

**WELL DEVELOPMENT/PURGE DATA:**

| TIME  | VOLUME REMOVED (gallons) | ELECTRICAL CONDUCTIVITY (micromhos) | pH   | TEMP. (°F) | COLOR/COMMENTS  |
|-------|--------------------------|-------------------------------------|------|------------|-----------------|
| 17:31 | 12.75                    | 510                                 | 6.55 | 77         | Light Gray Tint |
| 17:45 | 25.5                     | 521                                 | 6.48 | 74         | Clearing        |
| 17:58 | 38.25                    | 523                                 | 6.54 | 72         | Clearing        |
| 18:13 | 51.00                    | 527                                 | 6.52 | 72         | Clear           |

**SAMPLE COLLECTION DATA**

Sampling Equipment: Teflon Bailer

| TIME  | ANALYSIS         | AMOUNT/CONTAINER USED     | SAMPLE INTERVAL |
|-------|------------------|---------------------------|-----------------|
| 18:15 | BTEX/MTBE & TPHg | 2-40ml glass VOA with HCl |                 |

Field Notes:

**WELL FIELD LOG**

Well Observation: Date: 08/23/2001

Sample Collection: Date: 08/23/2001

Project Name: Groundwater Monitoring

Location: Nahas/Former Union 76

Personnel: JD

Weather: Sunny, Hot

**WELL INFORMATION:**

|                                 |                               |              |        |
|---------------------------------|-------------------------------|--------------|--------|
| Well Number                     | MW-5                          | Date Purged  | N/A    |
| Depth to Water - feet(TOC)      | 11.06                         | Purge Method | Bailer |
| Well Depth (feet)               | 34.5                          |              |        |
| Water Volume (gallons)          | 3.82                          | Purge Begin  | --     |
| Reference Elevation - feet(TOC) | +183.92                       | Purge End    | --     |
| Groundwater Elevation (feet)    | 172.76                        | Purge Rate   | --     |
| Measurement Technique           | Solinst Electric Well Sounder |              |        |

**IMMISCIBLE LAYERS:**

Top: None Observed

Bottom: None Observed

Detection Method: Visual

Collection Method: Clear Point-Source Bailer

**WELL DEVELOPMENT/PURGE DATA:**

| TIME  | VOLUME REMOVED (gallons) | ELECTRICAL CONDUCTIVITY (micromhos) | pH  | TEMP. (°F) | COLOR/COMMENTS   |
|-------|--------------------------|-------------------------------------|-----|------------|------------------|
| 12:32 | 4                        | 656                                 | 6.8 | 78         | Light brown tint |
| 12:35 | 8                        | 620                                 | 6.6 | 77         | Clearing         |
| 12:37 | 12                       | 605                                 | 6.6 | 76         | Clearing         |
| 12:39 | 16                       | 598                                 | 6.6 | 75         | Clear            |

**SAMPLE COLLECTION DATA**

Sampling Equipment: Teflon Bailer

| TIME  | ANALYSIS         | AMOUNT/CONTAINER USED     | SAMPLE INTERVAL |
|-------|------------------|---------------------------|-----------------|
| 12:45 | BTEX/MTBE & TPHg | 2-40ml glass VOA with HCl |                 |

Field Notes: Groundwater Level Reading Only

## WELL FIELD LOG

**Well Observation:** Date: 08/23/2001  
**Sample Collection:** Date: 08/23/2001

**Project Name:** Groundwater Monitoring  
**Location:** Nahas/Former Union 76  
**Personnel:** JD  
**Weather:** Sunny, Hot

**WELL INFORMATION:**

|                                 |                               |              |            |
|---------------------------------|-------------------------------|--------------|------------|
| Well Number                     | MW-6                          | Date Purged  | 08/23/2001 |
| Depth to Water - feet(TOC)      | 11.21                         | Purge Method | Bailer     |
| Well Depth (feet)               | 26.78                         |              |            |
| Water Volume (gallons)          | 2.53                          | Purge Begin  | 12:10      |
| Reference Elevation - feet(TOC) | +183.60                       | Purge End    | 13:34      |
| Groundwater Elevation (feet)    | 172.39                        | Purge Rate   | 0.43 gpm   |
| Measurement Technique           | Solinst Electric Well Sounder |              |            |

**IMMISCIBLE LAYERS:**

**Top:** None Observed  
**Bottom:** None Observed  
**Detection Method:** Visual  
**Collection Method:** Clear Point-Source Bailer

**WELL DEVELOPMENT/PURGE DATA:**

| TIME  | VOLUME REMOVED (gallons) | ELECTRICAL CONDUCTIVITY (micromhos) | pH   | TEMP. (°F) | COLOR/COMMENTS  |
|-------|--------------------------|-------------------------------------|------|------------|-----------------|
| 12:40 | 2.75                     | 710                                 | 6.29 | 73         | Light Turbidity |
| 13:15 | 5.50                     | 720                                 | 6.28 | 73         | " "             |
| 13:25 | 8.25                     | 724                                 | 6.31 | 72         | Clearing        |
| 13:34 | 11.00                    | 727                                 | 6.28 | 72         | Clearing        |

**SAMPLE COLLECTION DATA**

**Sampling Equipment:** Teflon Bailer

| TIME  | ANALYSIS         | AMOUNT/CONTAINER USED     | SAMPLE INTERVAL |
|-------|------------------|---------------------------|-----------------|
| 13:36 | BTEX/MTBE & TPHg | 2-40ml glass VOA with HCl |                 |

**Field Notes:**

## WELL FIELD LOG

**Well Observation:**                      **Date:** 08/23/2001  
**Sample Collection:**                      **Date:** 08/23/2001

**Project Name:** Groundwater Monitoring  
**Location:**     Nahas/Former Union 76  
**Personnel:**     JD  
**Weather:**     Sunny, Hot

**WELL INFORMATION:**

|                                 |                               |              |            |
|---------------------------------|-------------------------------|--------------|------------|
| Well Number                     | MW-7                          | Date Purged  | 08/23/2001 |
| Depth to Water - feet(TOC)      | 10.18                         | Purge Method | Bailer     |
| Well Depth (feet)               | 28.0                          |              |            |
| Water Volume (gallons)          | 2.9                           | Purge Begin  | 13:40      |
| Reference Elevation - feet(TOC) | +182.42                       | Purge End    | 14:08      |
| Groundwater Elevation (feet)    | 172.24                        | Purge Rate   | 0.32 gpm   |
| Measurement Technique           | Solinst Electric Well Sounder |              |            |

**IMMISCIBLE LAYERS:**

**Top:** None Observed  
**Bottom:** Dark Tint  
**Detection Method:** Visual  
**Collection Method:** Clear Point-Source Bailer

**WELL DEVELOPMENT/PURGE DATA:**

| TIME  | VOLUME REMOVED (gallons) | ELECTRICAL CONDUCTIVITY (micromhos) | pH   | TEMP (°F) | COLOR/COMMENTS   |
|-------|--------------------------|-------------------------------------|------|-----------|------------------|
| 13:50 | 3                        | 739                                 | 6.45 | 74        | Light brown tint |
| 13:11 | 6                        | 750                                 | 6.34 | 74        | Clearing         |
| 13:13 | 9                        | 768                                 | 6.33 | 74        | Clear            |
|       |                          |                                     |      |           |                  |


**SAMPLE COLLECTION DATA**

**Sampling Equipment:** Teflon Bailer

| TIME  | ANALYSIS         | AMOUNT/CONTAINER USED     | SAMPLE INTERVAL |
|-------|------------------|---------------------------|-----------------|
| 14:10 | BTEX/MTBE & TPHg | 2-40ml glass VOA with HCL |                 |

Field Notes

## BTEX/MTBE CONCENTRATIONS IN GROUNDWATER(MW-2)




BSK Job No. P92057.3

AUGUST 2001

FIGURE 5

**BSK**

### BTEX/MTBE CONCENTRATIONS IN GROUNDWATER(MW-3)



BENZENE     
  TOLUENE     
  XYLENE     
  ETHYLBENZENE     
  MTBE

BSK Job No. P92057.3

AUGUST 2001

FIGURE 6

**BSK**

**APPENDIX "A"**

**CHEMICAL TEST DATA SHEETS**  
**AND**  
**PROJECT CHAIN-OF-CUSTODY RECORD**  
**(7 SHEETS)**

NO 2260 job sheets included

# BSK ANALYTICAL LABORATORIES

## Cover Letter

09/11/2001

Alex Y. Eskandari  
BSK and Associates - Pleasanton  
1181 Quarry Lane Suite 300  
Pleasanton, CA 94566

BSK Submission Number: 2001081186

Dear Alex Y. Eskandari:

BSK Analytical Laboratories adheres to a quality assurance plan that has been approved by the State of California Department of Health Services. Our Environmental Laboratory Accreditation Program (ELAP) certification number is 1180.

BSK Analytical Laboratories has prepared this certificate of analysis in response to your request for analytical services. All information was taken from your Chain of Custody or related correspondence. BSK completed all sample handling and analytical procedures within the Laboratory's standard acceptability criteria with any exceptions noted below.

### Sample Comments


| Submission Order  | Test / Analyte | Comment  |
|-------------------|----------------|--|
| 2001081186 136930 | BTEX           | Not enough sample remains to confirm MtBE by EPA 8260. |

If additional clarification of any information is required, please contact our Client Services Department at (800)877-8310 or (559)497-2888.

Sincerely,

BSK Analytical Laboratories

Authorizing Signature(s)

  
Juliane Adams  
Organic Laboratory Supervisor

Ko Yang  
Inorganic Laboratory Supervisor

Cynthia Pigman  
QA/QC Supervisor





# BSK ANALYTICAL LABORATORIES

Alex Y. Eskandari  
 BSK and Associates - Pleasanton  
 1181 Quarry Lane Suite 300  
 Pleasanton, CA 94566

## Certificate of Analysis

ELAP Certificate #1180

Report Issue Date: 09/11/2001

BSK Submission #: 2001081186

BSK Sample ID #: 136929

Project ID: 92057.3

Project Desc: R.T. Nahas

Submission Comments:

Sample Type: Liquid  
 Sample Description: MW-2 \*  
 Sample Comments:

Date Sampled: 08/23/2001

Time Sampled: 1520

Date Received: 08/24/2001

### Organics

| Analyte              | Method        | Result | Units | PQL | Dilution | DLR | Prep Date  | Analysis Date |
|----------------------|---------------|--------|-------|-----|----------|-----|------------|---------------|
| TPH as Gasoline      | EPA 8015(M)   | 160    | µg/L  | 50  | 1        | 50  | 08/29/2001 | 08/29/2001    |
| Methyl-t-Butyl Ether | EPA 8015/8020 | 690    | µg/L  | 5   | 20       | 100 | 08/29/2001 | 08/30/2001    |
| Benzene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Ethylbenzene         | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Toluene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Total Xylenes        | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Methyl-t-Butyl Ether | EPA 8260      | 820    | µg/L  | 5   | 20       | 100 | 09/05/2001 | 09/05/2001    |

### Surrogate

|               |          |      |       |   |   |     |            |            |
|---------------|----------|------|-------|---|---|-----|------------|------------|
| Fluorobenzene | EPA 8020 | 85.4 | % Rec | - | 1 | N/A | 08/29/2001 | 08/29/2001 |
|---------------|----------|------|-------|---|---|-----|------------|------------|

### LUFT Comments

TPH as Gasoline Individual peaks inconsistent with fuel fingerprint

mg/L: Milligrams/Liter (ppm)  
 mg/Kg: Milligrams/Kilogram (ppm)  
 µg/L: Micrograms/Liter (ppb)  
 µg/Kg: Micrograms/Kilogram (ppb)  
 %Rec: Percent Recovered (surrogates)

PQL: Practical Quantitation Limit  
 DLR: Detection Limit for Reporting  
 : PQL x Dilution  
 ND: None Detected at DLR

H: Analyzed outside of hold time  
 P: Preliminary result  
 S: Suspect result. See Cover Letter for comments.  
 E: Analysis performed by External laboratory.  
 See External Laboratory Report attachments.

Report Authentication Code:

11861369290108230808240001

3 of 5

# BSK ANALYTICAL LABORATORIES

Alex Y. Eskandari  
 BSK and Associates - Pleasanton  
 1181 Quarry Lane Suite 300  
 Pleasanton, CA 94566

## Certificate of Analysis ELAP Certificate #1180

Report Issue Date: 09/11/2001

**BSK Submission #: 2001081186**

**BSK Sample ID #: 136930**

Project ID: 92057.3

Project Desc: R.T. Nahas

Submission Comments:

Sample Type: Liquid

Date Sampled: 08/23/2001

Sample Description: ~~MW-3~~

Time Sampled: 1615

Sample Comments:

Date Received: 08/24/2001

### Organics

| Analyte              | Method        | Result | Units | PQL | Dilution | DLR | Prep Date  | Analysis Date |
|----------------------|---------------|--------|-------|-----|----------|-----|------------|---------------|
| TPH as Gasoline      | EPA 8015(M)   | ND     | µg/L  | 50  | 1        | 50  | 08/29/2001 | 08/30/2001    |
| Methyl-t-Butyl Ether | EPA 8015/8020 | 26     | µg/L  | 5   | 1        | 5   | 08/29/2001 | 08/30/2001    |
| Benzene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/30/2001    |
| Ethylbenzene         | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/30/2001    |
| Toluene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/30/2001    |
| Total Xylenes        | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/30/2001    |

### Surrogate

|               |          |      |       |   |   |     |            |            |
|---------------|----------|------|-------|---|---|-----|------------|------------|
| Fluorobenzene | EPA 8020 | 84.4 | % Rec | - | 1 | N/A | 08/29/2001 | 08/30/2001 |
|---------------|----------|------|-------|---|---|-----|------------|------------|

mg/L: Milligrams/Liter (ppm)  
 mg/Kg: Milligrams/Kilogram (ppm)  
 µg/L: Micrograms/Liter (ppb)  
 µg/Kg: Micrograms/Kilogram (ppb)  
 %Rec: Percent Recovered (surrogates)

PQL: Practical Quantitation Limit  
 DLR: Detection Limit for Reporting  
 : PQL x Dilution  
 ND: None Detected at DLR

H: Analyzed outside of hold time  
 P: Preliminary result  
 S: Suspect result. See Cover Letter for comments.  
 E: Analysis performed by External laboratory.  
 See External Laboratory Report attachments.

Report Authentication Code:



# BSK ANALYTICAL LABORATORIES

Alex Y. Eskandari  
 BSK and Associates - Pleasanton  
 1181 Quarry Lane Suite 300  
 Pleasanton, CA 94566

## Certificate of Analysis

ELAP Certificate #1180

Report Issue Date: 09/11/2001

BSK Submission #: 2001081186

BSK Sample ID #: 136931

Project ID: 92057.3

Project Desc: R.T. Nahas

Submission Comments:

Sample Type: Liquid

Date Sampled: 08/23/2001

Sample Description: MW-101

Time Sampled: 1815

Sample Comments:

Date Received: 08/24/2001

### Organics

| Analyte              | Method        | Result | Units | PQL | Dilution | DLR  | Prep Date  | Analysis Date |
|----------------------|---------------|--------|-------|-----|----------|------|------------|---------------|
| TPH as Gasoline      | EPA 8015(M)   | 12000  | µg/L  | 50  | 20       | 1000 | 08/29/2001 | 08/30/2001    |
| Methyl-t-Butyl Ether | EPA 8015/8020 | 1400   | µg/L  | 5   | 20       | 100  | 08/29/2001 | 08/30/2001    |
| Benzene              | EPA 8020      | 630    | µg/L  | 0.3 | 20       | 6.0  | 08/29/2001 | 08/30/2001    |
| Ethylbenzene         | EPA 8020      | 1500   | µg/L  | 0.3 | 20       | 6.0  | 08/29/2001 | 08/30/2001    |
| Toluene              | EPA 8020      | ND     | µg/L  | 0.3 | 20       | 6.0  | 08/29/2001 | 08/30/2001    |
| Total Xylenes        | EPA 8020      | 480    | µg/L  | 0.3 | 20       | 6.0  | 08/29/2001 | 08/30/2001    |

### Surrogate

|               |          |      |       |   |    |     |            |            |
|---------------|----------|------|-------|---|----|-----|------------|------------|
| Fluorobenzene | EPA 8020 | 82.3 | % Rec | - | 20 | N/A | 08/29/2001 | 08/30/2001 |
|---------------|----------|------|-------|---|----|-----|------------|------------|

mg/L: Milligrams/Liter (ppm)  
 mg/Kg: Milligrams/Kilogram (ppm)  
 µg/L: Micrograms/Liter (ppb)  
 µg/Kg: Micrograms/Kilogram (ppb)  
 %Rec: Percent Recovered (surrogates)

PQL: Practical Quantitation Limit  
 DLR: Detection Limit for Reporting  
 : PQL x Dilution  
 ND: None Detected at DLR

H: Analyzed outside of hold time  
 P: Preliminary result  
 S: Suspect result. See Cover Letter for comments.  
 E: Analysis performed by External laboratory.  
 See External Laboratory Report attachments.

Report Authentication Code:

5 of 5

# BSK ANALYTICAL LABORATORIES

Alex Y. Eskandari  
 BSK and Associates - Pleasanton  
 1181 Quarry Lane Suite 300  
 Pleasanton, CA 94566

## Certificate of Analysis

ELAP Certificate #1180

Report Issue Date: 09/11/2001

BSK Submission #: 2001081186

BSK Sample ID #: 136927

Project ID: 92057.3

Project Desc: R.T. Nahas

Submission Comments:

Sample Type: Liquid

Date Sampled: 08/23/2001

Sample Description: MW-6

Time Sampled: 1336

Sample Comments:

Date Received: 08/24/2001

### Organics

| Analyte              | Method        | Result | Units | PQL | Dilution | DLR | Prep Date  | Analysis Date |
|----------------------|---------------|--------|-------|-----|----------|-----|------------|---------------|
| TPH as Gasoline      | EPA 8015(M)   | 79     | µg/L  | 50  | 1        | 50  | 08/29/2001 | 08/29/2001    |
| Methyl-t-Butyl Ether | EPA 8015/8020 | 280    | µg/L  | 5   | 1        | 5   | 08/29/2001 | 08/29/2001    |
| Benzene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Ethylbenzene         | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Toluene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Total Xylenes        | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Methyl-t-Butyl Ether | EPA 8260      | 350    | µg/L  | 5   | 10       | 50  | 09/05/2001 | 09/05/2001    |

### Surrogate

|               |          |      |       |   |   |     |            |            |
|---------------|----------|------|-------|---|---|-----|------------|------------|
| Fluorobenzene | EPA 8020 | 86.4 | % Rec | - | 1 | N/A | 08/29/2001 | 08/29/2001 |
|---------------|----------|------|-------|---|---|-----|------------|------------|

### LUFT Comments

TPH as Gasoline Individual peaks inconsistent with fuel fingerprint

mg/L: Milligrams/Liter (ppm)  
 mg/Kg: Milligrams/Kilogram (ppm)  
 µg/L: Micrograms/Liter (ppb)  
 µg/Kg: Micrograms/Kilogram (ppb)  
 %Rec: Percent Recovered (surrogates)

PQL: Practical Quantitation Limit  
 DLR: Detection Limit for Reporting  
 : PQL x Dilution  
 ND: None Detected at DLR

H: Analyzed outside of hold time  
 P: Preliminary result  
 S: Suspect result. See Cover Letter for comments.  
 E: Analysis performed by External laboratory.  
 See External Laboratory Report attachments.

Report Authentication Code:



1 of 5

# BSK ANALYTICAL LABORATORIES

Alex Y. Eskandari  
 BSK and Associates - Pleasanton  
 1181 Quarry Lane Suite 300  
 Pleasanton, CA 94566

## Certificate of Analysis

ELAP Certificate #1180

Report Issue Date: 09/11/2001

BSK Submission #: 2001081186

BSK Sample ID #: 136928

Project ID: 92057.3

Project Desc: R.T. Nahas

Submission Comments:

Sample Type: Liquid

Date Sampled: 08/23/2001

Sample Description: MW-7

Time Sampled: 1410

Sample Comments:

Date Received: 08/24/2001

### Organics

| Analyte              | Method        | Result | Units | PQL | Dilution | DLR | Prep Date  | Analysis Date |
|----------------------|---------------|--------|-------|-----|----------|-----|------------|---------------|
| TPH as Gasoline      | EPA 8015(M)   | 800    | µg/L  | 50  | 1        | 50  | 08/29/2001 | 08/29/2001    |
| Methyl-t-Butyl Ether | EPA 8015/8020 | 7.3    | µg/L  | 5   | 1        | 5   | 08/29/2001 | 08/29/2001    |
| Benzene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Ethylbenzene         | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Toluene              | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Total Xylenes        | EPA 8020      | ND     | µg/L  | 0.3 | 1        | 0.3 | 08/29/2001 | 08/29/2001    |
| Methyl-t-Butyl Ether | EPA 8260      | ND     | µg/L  | 5   | 1        | 5   | 09/05/2001 | 09/05/2001    |

### Surrogate

|               |          |       |       |   |   |     |            |            |
|---------------|----------|-------|-------|---|---|-----|------------|------------|
| Fluorobenzene | EPA 8020 | 100.0 | % Rec | - | 1 | N/A | 08/29/2001 | 08/29/2001 |
|---------------|----------|-------|-------|---|---|-----|------------|------------|

### LUFT Comments

TPH as Gasoline Individual peaks inconsistent with fuel fingerprint

mg/L: Milligrams/Liter (ppm)  
 mg/Kg: Milligrams/Kilogram (ppm)  
 µg/L: Micrograms/Liter (ppb)  
 µg/Kg: Micrograms/Kilogram (ppb)  
 %Rec: Percent Recovered (surrogates)

PQL: Practical Quantitation Limit  
 DLR: Detection Limit for Reporting  
 : PQL x Dilution  
 ND: None Detected at DLR

H: Analyzed outside of hold time  
 P: Preliminary result  
 S: Suspect result. See Cover Letter for comments.  
 E: Analysis performed by External laboratory.  
 See External Laboratory Report attachments.

Report Authentication Code:



2 of 5



1414 Stanislaus Street  
Fresno, CA 93706  
(209) 485-8310  
(800) 877-8310  
(209) 485-6935 FAX

BSK\_P

TAT: Standard

BSK Log Number:

824021



Analytical Due Date:

Environmental Services

BSK-P

Shaded areas for LAB use only

Requested Analyses

|  |  |                            |
|--|--|----------------------------|
| Client Name<br><b>R.T. Nahas</b>         | Report Attention:<br><b>ALEX ESKANDARI</b> | Phone #<br><b>462-4000</b> |
| Address                                  | Project, Quote or PO #<br><b>P92057.3</b>  | FAX #<br><b>462-6283</b>   |
| City, State, Zip<br><b>CASTRO VALLEY</b> | Copy to:                                   | System #                   |

| LAB use only |      |         | Date Sampled | Time Sampled | Sampled by:<br><b>John Davis</b> | Sample Description/Location | Comment or Station Code                       | TPH-0 | BTEX | MTBE |
|--------------|------|---------|--------------|--------------|----------------------------------|-----------------------------|---|-------|------|------|
| Sample #     | Type | # Cont. |              |              |                                  |                             |   |       |      |      |
| 1            | L    | 2       | 8-23-01      | 13:36        | John Davis                       | MW-6                        | 1360927                                       | X     | X    | X    |
| 2            | L    | 2       | 8-23-01      | 14:10        | John Davis                       | MW-7                        | 1360928                                       | X     | X    | X    |
| 3            | L    | 2       | 8-23-01      | 15:20        | John Davis                       | MW-2                        | 1360929                                       | X     | X    | X    |
| 4            | L    | 2       | 8-23-01      | 16:15        | John Davis                       | MW-3                        | 1360930                                       | X     | X    | X    |
| 5            | L    | 2       | 8-23-01      | 18:15        | John Davis                       | MW-101                      | 1360931                                       | X     | X    | X    |
|              |      |         |              |              |                                  |                             | *CONFIRM HIGHEST MTBE CONCENTRATION WITH 8260 |       |      |      |

\*8260  
SEE NOTE BELOW

Matrix Type: L - Liquid S - Solid G - Gas  
Type of Hazards Associated with Samples:

Additional Services:

Rush Priority:  - 2 Day  - 5 Day  
 - Formal Chain of Custody  - QC Data package

Additional Services Authorized by:

(Signature)

Payment Received with Delivery

Date: \_\_\_\_\_ Amount: \$ \_\_\_\_\_  
Check # \_\_\_\_\_ Initials \_\_\_\_\_  
Receipt # \_\_\_\_\_

| Signature         | Print Name | Company | Date    | Time  |
|-------------------|------------|---------|---------|-------|
| <i>John Davis</i> | John Davis | BSK-P   | 8/24/01 | 12:00 |
|                   |            |         |         |       |
|                   |            |         |         |       |
|                   |            |         |         |       |
| <i>Janbar</i>     | Tan Yang   | BSK     | 8/24/01 | 12:00 |