DUBLIN TOYOTA

RECEIVED
By Alameda County Environmental Health at 3:49 pm, Apr 09, 2014

April 4, 2014

Alameda County Department of
Environmental Health
1131 Harbor Bay Parkway, 2nd Floor
Alameda, CA 94502

Attention: Mr. Jerry Wickham

Subject: Second Semi-Annual 2013 Groundwater Monitoring Report
Dublin Toyota UST Site, 6450 Dublin Court, Dublin, California
Alameda County LOP Site ID No. 0000333

Ladies and Gentlemen:

Attached please find a copy of the *Second Semi-Annual 2013 Groundwater Monitoring Report, Dublin Toyota UST Site, 6450 Dublin Court, Dublin, California,* prepared by Gribi Associates. I declare, under penalty of perjury, that the information and/or recommendations contained in the attached document or report is true and correct to the best of my knowledge.

Very truly yours,

Scott F. Anderson
Chief Financial Officer
Dublin Toyota

Doin' It Right!
6450 DUBLIN COURT • DUBLIN • CA 94568 • 925 829-7700 • FAX 925 829-9025
www.dublintoyota.com

GRIBI
ASSOCIATES

April 4, 2014

Alameda County Department of
Environmental Health
1131 Harbor Bay Parkway, 2nd Floor
Alameda, CA 94502

Attention: Mr. Jerry Wickham

Subject: Second Semi-Annual 2013 Groundwater Monitoring Report
Dublin Toyota UST Site, 6450 Dublin Court, Dublin, California
Alameda County LOP Site ID No. 0000333, Geotracker Global ID T0600102153

Ladies and Gentlemen:

Gribi Associates is pleased to submit this Second Semi-Annual 2013 Groundwater Monitoring Report on behalf of Dublin Toyota for the underground storage tank (UST) site located at 6450 Dublin Court in Dublin, California (Figures 1, 2, and 3). This report summarizes groundwater monitoring activities conducted at the site on December 17 and 18, 2013.

DESCRIPTION OF MONITORING ACTIVITIES

1. Gribi Associates personnel conducted groundwater monitoring activities for 18 site wells (MW-1, MW-2, MW-3, MW-4S, MW-4D, MW-5S, MW-5D, MW-6S, MW-6D, MW-7 through MW-10, MW-12, and MW-14 through MW-17,) on December 10, 20, and 21, 2012.
   a. Monitoring wells MW-11, MW-13, EW-1, and EW-2 were not accessible during the sampling event.
2. Groundwater monitoring was conducted in accordance with California LUFT Field Manual, including the following:
   a. measuring static water levels;
   b. checking for presence of free-product; and
   c. purging of approximately three well volumes while recording temperature, pH, electroconductivity, and clarity.
3. Collected groundwater samples were placed in an ice-chilled cooler and submitted to a state-certified laboratory for analyses.
4. Copies of groundwater sampling field data sheets are provided as Attachment A.

RESULTS OF GROUNDWATER MONITORING

Hydrologic Conditions

1. Groundwater depths ranged from approximately 3.38feet (MW-14) to 7.55 feet (MW-12).
2. Groundwater elevations, which are shown on Figures 4 and 5, ranged from 320.55 feet (MW-15) to 321.72 feet (MW-2).
3. Groundwater elevations in shallow ("A" Zone) and deeper ("B" Zone) wells are variable and relatively flat.
    a. Based on the MTBE plume configuration, groundwater flow direction trends in a southwest to southerly direction.
4. Free-product was not present in any of the wells.

Laboratory Analytical Results

1. Groundwater samples from the 18 wells were analyzed for the following parameters with standard method turn around time on results:
    a. USEPA 8260B Total Petroleum Hydrocarbons as Gasoline (TPH-G)
    b. USEPA 8260B Benzene, Toluene, Ethylbenzene, Xylenes (BTEX)
    c. USEPA 8260B Oxygenates (TBA, MTBE, DIPE, ETBE, and TAME)
2. Groundwater analytical results are summarized in Table 1.
3. Groundwater hydrocarbon results for this monitoring event are summarized on Figures 4 and 5.
4. The laboratory analytical data report and chain-of custody are contained in Attachment B.

OZONE REMEDIATION

1. Gribi Associates initiated ozone remediation at the site on February 27, 2012.
2. The system experienced moderate amounts of downtime due to general wear and tear on various components that required repair and/or replacement.
3. The system was shut down in late November 2012 when the present site tenants discontinued business activities and electrical service at the site.

CONCLUSIONS

1. During this monitoring event, groundwater MTBE and TBA concentrations were generally similar to or lower than previous sampling events.
2. Post-ozone injection groundwater MTBE/TBA concentrations in "A" Zone and "B" Zone wells within the main plume area have generally remained low, indicating that concentration rebound is not occurring to a significant degree.

PLANNED ACTIVITIES

1. Unless otherwise directed by ACDEH, Gribi Associates plans to conducted semi-annual groundwater monitoring at the site during the second quarter of 2014.
2. Gribi Associates is currently preparing a Site Conceptual Model for the site;
3. After completing the SCM, Gribi Associates will evaluate the Site relative to the State Water Quality Control Board's *Low-Threat Closure Policy*.

We appreciate this opportunity to provide this report for your review. Please contact us if there are questions or if additional information is required.

Very truly yours,

Matthew A. Rosman
Project Engineer

James E. Gribi
Professional Geologist
California No. 5843

Enclosure

c: Mr. Scott Anderson, Dublin Toyota, 4321 Toyota Drive, Dublin, CA 94568
Mr. Nolan Davis, 50 Oak Court, Danville, CA 94526-4039

TABLE

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
MW-1	12/15/98	5.74	323.14	**46,000**	<100	<100	<100	<100	–	–	–	–	**62,000**	–	–
"A" Zone	04/06/99	5.09	323.79	**45,000**	<50	<50	<50	<50	–	–	–	–	**86,000**[1]	–	–
<328.88>	07/14/99	6.18	322.7	**2,800**	<100	<100	<100	<100	–	–	–	–	**65,000**[1]	–	–
	10/14/99	6.86	322.02	**11,000**	<17	<17	<17	<17	–	–	–	–	**98,000**[1]	–	–
	08/18/00	6.98	321.9	**36,000**	<50	<50	<50	<50	–	–	–	–	**66,000**[1]	–	–
	05/29/02	6.42	322.46	**29,100**	<15	<15	<15	<30	**841**	<500	<100	N50	**27,800**[1]	–	–
	11/20/02	6.65	322.23	**110**	<0.5	<0.5	<0.5	<1.0	<20	<50	<20	<20	**20,000**	–	–
	04/06/03	5.95	322.93	**1,300**	<1.0	<1.0	<1.0	<1.0	**10**	**360**	<2.0	**2.2**	**15,000**	–	–
	07/13/03	6.55	322.33	**74**	<0.50	<0.50	<0.50	<1.0	**10**	**42**	<5.0	<5.0	**15,000**	–	–
	02/11/04	5.74	323.14	<50	<0.50	<0.50	<0.50	<1.0	**10**	**420**	<2.0	**2.5**	**34,000**	–	–
	06/16/04	6.37	322.51	**180**	<0.50	<0.50	<0.50	<1.0	**6.8**	**290**	<2.0	<2.0	**7,600**	–	–
	10/16/04	7.29	321.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6,720**	–	–
	12/30/04	5.84	323.04	**92**	<0.50	<0.50	<0.50	<1.0	**5.2**	<10	<2.0	<2.0	**2,600**	–	–
	03/22/05	5.22	323.66	<50	<0.50	<0.50	<0.50	<1.0	**7.3**	<10	<2.0	<2.0	**6,900**	–	–
	06/10/05	6.17	322.71	**100**	<0.50	<0.50	<0.50	<1.0	**9.8**	<10	<2.0	<2.0	**25,000**	–	–
	10/04/05	7.49	321.39	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,500**	–	–
	12/21/05	7.18	321.70	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6,800**	–	–
	03/30/06	5.81	323.07	<50	<0.50	<0.50	**1.1**	**2.6**	<2.0	<10	<2.0	<2.0	**6,900**	–	–
	06/01/06	7.20	321.68	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5,100**	–	–
	09/12/06	6.39	322.49	<50	<0.50	<0.50	<0.50	<1.0	**2.2**	**960**	<2.0	<2.0	**2,400**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	11/21/06	7.68	321.2	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,200**	<2.0	<2.0	**930**	–	–
	02/27/07	5.06	323.82	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**1,000**	<2.0	<2.0	**1,100**	–	–
	06/07/07	7.57	321.31	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**1,500**	<2.0	<2.0	**1,100**	–	–
	09/14/07	7.52	321.36	NA	<0.50	<0.50	<0.50	<1.0	<20	**640**	<2.0	<2.0	**280**	–	–
	11/17/07	7.28	321.60	NA	<0.50	<0.50	<0.50	<1.0	<20	**1,400**	<2.0	<2.0	**260**	–	–
	02/28/08	5.56	323.32	NA	<0.50	<0.50	<0.50	<1.0	<20	**1,300**	<2.0	<2.0	**130**	–	–
	06/04/08	6.96	321.92	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,700**	<2.0	<2.0	**290**	–	–
	09/11/08	7.24	321.64	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,000**	<2.0	<2.0	**160**	–	–
	12/23/08	6.84	322.04	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**13**	–	–
	03/17/09	5.91	322.97	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**17**	–	–
	06/26/09	7.21	321.67	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**390**	<2.0	<2.0	**74**	–	–
	12/03/09	7.29	321.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**2,800**	<2.0	<2.0	**15**	–	–
	06/11/10	6.59	322.29	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**58**	–	–
	11/11/10	7.65	321.23	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**29**	–	–
	06/01/11	6.64	322.24	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**150**	<2.0	<2.0	**14**	–	–
	12/06/11	7.43	321.45	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**10**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	7.29	321.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**88**	<2.0	<2.0	**8.3**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/10/12	6.21	322.67	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**38**	<2.0	<2.0	**8.0**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	06/26/13	7.70	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**51**	<2.0	<2.0	**4.2**	–	–
	12/17/13	7.32	321.56	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**4.1**	–	–
MW-2	12/15/98	4.3	323.34	<50	<0.50	**0.90**	<0.50	**1.5**	–	–	–	–	<5.0	–	–
"A" Zone	04/06/99	3.42	324.22	<50	<0.50	<0.50	<0.50	<0.50	–	–	–	–	<5.0	–	–
<327.64>	07/14/99	4.76	322.88	<50	<0.50	<0.50	<0.50	<0.50	–	–	–	–	<5.0	–	–
	10/14/99	5.48	322.16	<50	<0.50	<0.50	<0.50	<0.50	–	–	–	–	<5.0	–	–
	08/18/00	5.72	321.92	<50	<0.50	<0.50	<0.50	**1.1**	–	–	–	–	**16**	–	–
	05/29/02	5.18	322.46	<50	<0.3	<0.3	<0.3	**3.9**	<2.0	<10	<2.0	<2.0	**2.6**	–	–
	11/20/02	5.52	322.12	**57**	<0.50	<0.50	<0.50	<1.0	<20	<50	<20	<20	**9.1**	–	–
	04/06/03	4.59	323.05	<50	<1.0	<1.0	<1.0	<1.0	<2.0	<10	<2.0	<2.0	**5.7**	–	–
	07/13/03	5.24	322.40	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<10	<5.0	<5.0	**6.5**	–	–
	02/11/04	4.45	323.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**8.5**	–	–
	06/16/04	4.93	322.71	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**120**	–	–
	10/16/04	5.97	321.67	**78**	<0.50	<0.50	<0.50	<1.0	**4.1**	<10	<2.0	<2.0	**43.2**	–	–
	12/30/04	4.74	322.9	<50	<0.50	<0.50	<0.50	<1.0	**4.1**	<10	<2.0	<2.0	**14**	–	–
	03/22/05	3.86	323.78	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**13**	–	–
	06/10/05	4.83	322.81	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**14**	–	–
	10/04/05	6.19	321.45	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.2**	–	–
	12/21/05	5.81	321.83	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	03/30/06	4.55	323.09	<50	<0.50	<0.50	<0.50	**3.9**	<2.0	<10	<2.0	<2.0	**13**	–	–
	06/01/06	5.93	321.71	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**14**	–	–
	09/12/06	8.65	318.99	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**22**	–	–
	11/21/06	6.42	321.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**19**	–	–
	02/27/07	5.14	322.50	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**13**	–	–
	06/07/07	6.18	321.46	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**30**	–	–
	09/14/07	6.31	321.33	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**25**	–	–
	11/17/07	5.90	321.74	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**13**	–	–
	02/28/08	4.19	323.45	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10.0	<2.0	<2.0	**14**	–	–
	06/04/08	5.58	322.06	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**18**	–	–
	09/11/08	5.92	321.72	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**38**	–	–
	12/23/08	5.56	322.08	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**39**	–	–
	03/17/09	4.64	323.00	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**36**	–	–
	06/26/09	5.90	321.74	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**18**	–	–
	12/03/09	5.98	321.66	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**11**	–	–
	06/11/10	5.30	322.34	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**4.6**	–	–
	11/11/10	6.39	321.25	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.4**	–	–
	06/01/11	5.39	322.25	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6.1**	–	–
	12/07/11	6.17	321.47	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.8**	–	–

Ozone Remediation Initiated on February 27, 2012

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	07/12/12	6.07	321.57	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.0**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/10/12	5.00	322.64	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.9**	–	–
	06/26/13	6.45	321.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1.9**	–	–
	12/17/13	5.92	321.72	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1.3**	–	–
MW-3	08/18/00	5.67	321.77	**210**	<0.50	**0.58**	<0.50	**0.59**	–	–	–	–	**570**[1]	–	–
"A" Zone	05/29/02	5.1	322.34	<50	<0.3	<0.3	<0.3	**219**	<2.0	<10	<2.0	<2.0	**281**	–	–
<327.44>	11/20/02	5.56	321.88	**200**	<0.50	<0.50	<0.50	<1.0	<20	<50	<20	<20	**460**	–	–
	04/06/03	4.64	322.8	**270**	<1.0	<1.0	<1.0	<1.0	<2.0	<10	<2.0	<2.0	**340**	–	–
	07/13/03	5.48	321.96	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<10	<5.0	<5.0	**460**	–	–
	02/11/04	4.47	322.97	<50	<0.50	<0.50	<0.50	<1.0	**2.2**	**1,000**	<2.0	<2.0	**4,000**	–	–
	06/16/04	5.23	322.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**240**	–	–
	10/16/04	5.92	321.52	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**210**	–	–
	12/30/04	4.54	322.9	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**190**	–	–
	03/22/05	3.9	323.54	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**210**	–	–
	06/10/05	4.83	322.61	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**230**	–	–
	10/04/05	6.02	321.42	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**380**	–	–
	12/21/05	5.74	321.7	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**320**	–	–
	03/30/06	4.35	323.09	<50	<0.50	<0.50	**1.3**	**3.0**	<2.0	<10	<2.0	<2.0	**160**	–	–
	06/01/06	5.69	321.75	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**270**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	09/12/06	6.21	321.23	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**130**	–	–
	11/21/06	6.29	321.15	<50	<0.50	<0.50	<0.50	<0.50	<2.0	<10	<2.0	<2.0	**90**	–	–
	02/27/07	–	–	NA	<0.50	<0.50	<0.50	<0.50	<2.0	<10	<2.0	<2.0	**39**	–	–
	06/7/07	5.98	321.46	NA	<0.50	<0.50	<0.50	<0.50	<2.0	<10	<2.0	<2.0	**270**	–	–
	09/14/07	6.11	321.33	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**59**	–	–
	11/17/07	5.86	321.58	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**75**	–	–
	02/28/08	4.12	323.32	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**36**	–	–
	06/04/08	5.47	321.97	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**20**	<2.0	<2.0	**30**	–	–
	09/11/08	5.75	321.69	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**51**	<2.0	<2.0	**36**	–	–
	12/23/08	5.45	321.99	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**41**	–	–
	03/17/09	4.55	322.89	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**12**	–	–
	06/26/09	5.78	321.66	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**12**	–	–
	12/03/09	5.87	321.57	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**62**	<2.0	<2.0	**15**	–	–
	06/10/10	5.19	322.25	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**20**	–	–
	11/11/10	6.20	321.24	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**26**	<2.0	<2.0	**27**	–	–
	06/01/11	5.17	322.27	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**10**	<2.0	<2.0	**7.9**	–	–
	12/06/11	6.03	321.41	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**8.5**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	5.83	321.61	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**8.8**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	5.02	322.42	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**7.2**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	06/26/13	6.29	321.15	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**8.4**	–	–
	12/17/13	5.92	321.52	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**7.7**	–	–
MW-4S	04/27/06	5.03	322.77	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
"A" Zone	06/01/06	3.72	324.08	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
<327.80>	9/12/06	6.01	321.79	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	11/21/06	6.68	321.12	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2.1**	–	–
	02/27/07	5.39	322.41	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.0**	–	–
	06/07/07	6.38	321.42	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**27**	–	–
	09/14/07	–	–	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**15**	–	–
	11/17/07	6.39	321.41	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**73**	–	–
	02/28/08	4.65	323.15	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**360**	–	–
	06/04/08	5.93	321.87	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**110**	<2.0	<2.0	**820**	–	–
	09/11/08	6.09	321.71	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**190**	<2.0	<2.0	**400**	–	–
	12/23/08	5.93	321.87	**86**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**310**	–	–
	03/17/09	4.98	322.82	**540**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,100**	–	–
	06/26/09	6.13	321.67	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**170**	–	–
	12/03/09	6.33	321.47	**280**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**590**	–	–
	06/10/10	5.56	322.24	**160**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**690**	–	–
	11/11/10	6.50	321.30	**250**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**460**	–	–
	06/03/11	5.46	322.34	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**150**	<2.0	<2.0	**670**	–	–
	12/07/11	6.34	321.46	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**380**	<2.0	<2.0	**640**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	5.48	322.32	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**370**	<2.0	<2.0	**540**	<0.40	<5,000
	04/27/12	5.07	322.73	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**460**	<2.0	<2.0	**770**	<0.40	<5,000
	07/13/12	6.22	321.58	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**370**	<2.0	<2.0	**1,100**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	5.35	322.45	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**250**	<2.0	<2.0	**290**	–	–
	06/27/13	6.53	321.27	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**250**	<2.0	<2.0	**110**	–	–
	12/18/13	6.44	321.36	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**62**	–	–
MW-4D	04/27/06	5.00	322.67	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
"B" Zone	06/01/06	--	--	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
<327.67>	09/12/06	4.23	323.44	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	11/21/06	6.51	321.16	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	02/27/07	–	–	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/07/07	7.51	320.16	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	09/14/07	–	--	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	11/17/07	6.43	321.24	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	02/28/08	6.05	321.62	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/04/08	6.49	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1.2**	–	–
	09/11/08	7.06	320.61	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.0**	–	–
	12/23/08	6.60	321.07	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.0**	–	–
	03/17/09	5.05	322.62	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6.9**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	06/26/09	5.93	321.74	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.9**	–	–
	12/03/09	6.21	321.46	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**56**	–	–
	06/10/10	5.44	322.23	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**54**	–	–
	11/10/10	6.33	321.34	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**59**	–	–
	06/03/11	5.07	322.60	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**11**	<2.0	<2.0	**40**	–	–
	12/07/11	6.12	321.55	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**40**	<2.0	<2.0	**60**	–	–
Ozone Remediation Initiated on February 27, 2012															
	3/22/12	5.43	322.24	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**51**	<0.20	<5,000
	04/27/12	4.92	322.75	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**66**	<0.20	<5,000
	07/13/12	6.19	321.48	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**12**	<2.0	<2.0	**41**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	4.97	322.70	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**87**	–	–
	06/27/13	6.29	321.38	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**53**	–	–
	12/18/13	6.07	321.60	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**80**	–	–
MW-5S	04/27/06	4.25	322.84	<50	<0.50	<0.50	<0.50	<1.0	**4.6**	<10	<2.0	<2.0	**10,000**	–	–
"A" Zone	06/01/06	5.41	321.68	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**8,300**	–	–
<327.09>	09/12/06	5.85	321.24	<50	<0.50	<0.50	<0.50	<1.0	**3.5**	**340**	<2.0	<2.0	**6,500**	–	–
	11/21/06	5.57	321.52	<50	<0.50	<0.50	<0.50	<1.0	**3.5**	**1,200**	<2.0	<2.0	**4,700**	–	–
	02/27/07	4.61	322.48	NA	<0.50	<0.50	<0.50	<1.0	**2.9**	**1,400**	<2.0	<2.0	**3,800**	–	–
	06/07/07	5.61	321.48	NA	<0.50	<0.50	<0.50	<1.0	**3.2**	<10	<2.0	<2.0	**7,800**	–	–
	09/14/07	5.83	321.26	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**640**	<2.0	<2.0	**2,700**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	11/17/07	5.61	321.48	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**47**	<2.0	<2.0	**4,700**	–	–
	02/28/08	3.86	323.23	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,700**	–	–
	06/04/08	5.21	321.88	<50	<0.50	<0.50	<0.50	<1.0	**2.7**	**1,500**	<2.0	<2.0	**7,300**	–	–
	09/11/08	–	–	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,800**	<2.0	<2.0	**2,700**	–	–
	12/23/08	5.15	321.94	**600**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,400**	–	–
	03/17/09	4.29	322.80	**830**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,900**	–	–
	06/26/09	5.49	321.60	**150**	<0.50	<0.50	<0.50	<1.0	<2.0	**590**	<2.0	<2.0	**620**	–	–
	12/03/09	5.66	321.43	**160**	<0.50	<0.50	<0.50	<1.0	<2.0	**1,200**	<2.0	<2.0	**190**	–	–
	06/09/10	4.91	322.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**390**	<2.0	<2.0	**60**	–	–
	11/11/10	5.90	321.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,200**	<2.0	<2.0	**51**	–	–
	06/03/11	4.81	322.28	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**23**	<2.0	<2.0	**9.2**	–	–
	12/07/11	5.70	321.39	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**16**	–	–
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	4.81	322.28	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**4.6**	<0.2	<50
	04/27/12	4.46	322.63	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**13**	<2.0	<2.0	**20**	<0.2	<50
	07/13/12	5.56	321.53	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**53**	<2.0	<2.0	**35**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	4.65	322.44	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**94**	–	–
	06/27/13	5.89	321.20	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**11**	–	–
	12/18/13	5.76	321.33	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1.8**	–	–
MW-5D	04/27/06	4.01	323.29	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**<10**	<2.0	<2.0	**1,900**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
"B" Zone	06/01/06	5.85	321.45	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,300**	–	–
<327.30>	09/12/06	6.50	320.80	<50	<0.50	<0.50	<0.50	<1.0	**2.6**	**150**	<2.0	<2.0	**3,900**	–	–
	11/21/06	6.11	321.19	<50	<0.50	<0.50	<0.50	<1.0	**4.0**	**1,300**	<2.0	<2.0	**2,600**	–	–
	02/27/07	5.51	321.79	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**440**	<2.0	<2.0	**1,900**	–	–
	06/07/07	6.72	320.58	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,700**	–	–
	09/14/07	–	–	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**170**	<2.0	<2.0	**1,600**	–	–
	11/17/07	5.55	321.75	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3,000**	–	–
	02/28/08	5.22	322.08	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**890**	–	–
	06/04/08	6.11	321.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**160**	<2.0	<2.0	**1,500**	–	–
	09/11/08	–	–	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,000**	<2.0	<2.0	**2,500**	–	–
	12/23/08	7.57	319.73	**670**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,800**	–	–
	03/17/09	5.35	321.95	**720**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,100**	–	–
	06/26/09	6.54	320.76	**360**	<0.50	<0.50	<0.50	<1.0	<2.0	**1,000**	<2.0	<2.0	**1,600**	–	–
	12/03/09	5.81	321.49	**1,100**	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**1,500**	–	–
	06/09/10	5.09	322.21	**560**	<0.50	<0.50	<0.50	<1.0	<2.0	**560**	<2.0	<2.0	**2,200**	–	–
	11/11/10	6.08	321.22	**700**	<0.50	<0.50	<0.50	<1.0	<2.0	**360**	<2.0	<2.0	**2,300**	–	–
	06/03/11	4.98	322.32	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**610**	<2.0	<2.0	**1,200**	–	–
	12/07/11	5.91	321.39	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**430**	<2.0	<2.0	**690**	–	–
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	5.14	322.16	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**390**	<0.2	<10,000
	04/27/12	4.59	322.71	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**16**	<2.0	<2.0	**450**	<0.2	<10,000

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	07/13/12	5.64	321.66	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**35**	<2.0	<2.0	**93**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	4.84	322.46	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**63**	–	–
	06/27/13	6.10	321.20	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**15**	–	–
	12/18/13	5.94	321.36	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**140**	–	–
MW-6S	04/27/06	12.32	314.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**190**	–	–
"A" Zone	06/01/06	11.39	315.14	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**73**	–	–
<326.53>	09/12/06	16.49	310.04	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**130**	–	–
	11/21/06	7.93	318.60	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**140**	–	–
	02/27/07	–	–	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**87**	–	–
	06/07/07	6.08	320.45	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**83**	–	–
	09/14/07	6.32	320.21	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**72**	–	–
	11/17/07	7.69	318.84	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**72**	–	–
	02/28/08	5.03	321.50	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**68**	–	–
	06/04/08	5.34	321.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**65**	–	–
	09/11/08	5.74	320.79	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**130**	–	–
	12/23/08	5.86	320.67	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**83**	–	–
	03/17/09	4.80	321.73	**61**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**160**	–	–
	06/26/09	5.44	321.09	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**81**	–	–
	12/03/09	5.03	321.50	**130**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**220**	–	–
	06/11/10	4.05	322.48	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**120**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	11/11/10	5.50	321.03	**110**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**170**	–	–
	06/03/11	4.06	322.47	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**31**	<2.0	<2.0	**110**	–	–
	12/07/11	4.73	321.80	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**62**	<2.0	<2.0	**98**	–	–
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	1.21	325.32	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**90**	–	–
	04/27/12	8.14	318.39	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**39**	–	–
	07/13/12	6.30	320.23	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**15**	<2.0	<2.0	**35**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	5.14	321.39	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**70**	–	–
	06/27/13	5.26	321.27	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**19**	–	–
	12/18/13	5.31	321.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**86**	–	–
MW-6D	04/27/06	4.09	322.63	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**22**	–	–
"B" Zone	06/01/06	4.85	321.87	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**11**	–	–
<326.72>	09/12/06	5.40	321.32	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**7.3**	–	–
	11/21/06	5.52	321.20	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**7.8**	–	–
	02/27/07	4.09	322.63	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**4.6**	–	–
	06/07/07	5.14	321.58	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**8.5**	–	–
	09/14/07	5.42	321.3	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**15**	–	–
	11/17/07	5.20	321.52	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**26**	–	–
	02/28/08	3.41	323.31	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**9.3**	–	–
	06/04/08	4.78	321.94	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**18**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	09/11/08	5.10	321.62	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**64**	–	–
	12/23/08	4.67	322.05	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.8**	–	–
	03/17/09	3.88	322.84	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**26**	–	–
	06/26/09	5.06	321.66	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	12/03/09	5.25	321.47	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**52**	–	–
	06/11/10	4.50	322.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**19**	–	–
	11/11/10	5.51	321.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**44**	–	–
	06/03/11	4.41	322.31	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**17**	–	–
	12/07/11	5.38	321.34	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**24**	–	–
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	4.41	322.31	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**19**	–	–
	04/27/12	4.06	322.66	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**11**	–	–
	07/13/12	5.12	321.60	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**13**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	4.28	322.44	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**20**	–	–
	06/27/13	5.52	321.20	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**20**	–	–
	12/18/13	5.42	321.30	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**27**	–	–
MW-7	04/27/06	3.33	322.83	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
"A" Zone	06/01/06	4.47	321.69	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**16**	–	–
<326.16>	09/12/06	4.92	321.24	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**81**	–	–
	11/21/06	5.02	321.14	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**180**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	02/27/07	3.46	322.70	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**350**	–	–
	06/07/07	4.71	321.45	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**520**	–	–
	09/14/07	4.92	321.24	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**13**	<2.0	<2.0	**270**	–	–
	11/17/07	4.69	321.47	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**710**	–	–
	02/28/08	3.07	323.09	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,800**	–	–
	06/04/08	4.31	321.85	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,100**	<2.0	<2.0	**4,300**	–	–
	09/11/08	4.62	321.54	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**1,100**	<2.0	<2.0	**3,200**	–	–
	12/23/08	4.24	321.92	**590**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,300**	–	–
	03/17/09	3.41	322.75	**1,700**	<0.50	<0.50	<0.50	<1.0	**2.9**	<10	<2.0	<2.0	**4,100**	–	–
	06/26/09	4.61	321.55	**440**	<0.50	<0.50	<0.50	<1.0	<2.0	**2,000**	<2.0	<2.0	**2,400**	–	–
	12/03/09	4.75	321.41	**2,500**	<0.50	<0.50	<0.50	<1.0	<2.0	**21**	<2.0	<2.0	**3,400**	–	–
	06/11/10	4.03	322.13	**630**	<0.50	<0.50	<0.50	<1.0	<2.0	**680**	<2.0	<2.0	**2,700**	–	–
	11/10/10	4.92	321.24	**790**	<0.50	<0.50	<0.50	<1.0	<2.0	**790**	<2.0	<2.0	**2,700**	–	–
	06/03/11	3.92	322.24	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**830**	<2.0	<2.0	**2,000**	–	–
	12/07/11	4.88	321.28	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**950**	<2.0	<2.0	**1,200**	–	–
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	3.64	322.52	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**320**	<2.0	<2.0	**780**	<0.40	<5,000
	04/27/12	3.47	322.69	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**23**	<2.0	<2.0	**530**	<0.40	<5,000
	07/13/12	4.55	321.61	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**16**	<2.0	<2.0	**49**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	3.84	322.32	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**18**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	06/26/13	5.02	321.14	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**170**	<2.0	<2.0	**130**	–	–
	12/17/13	4.92	321.24	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**230**	<2.0	<2.0	**240**	–	–
MW-8	04/27/06	3.05	322.83	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,000**	–	–
"B" Zone	06/01/06	4.09	321.79	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,000**	–	–
<325.88>	09/12/06	4.58	321.3	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**150**	<2.0	<2.0	**2,500**	–	–
	11/21/06	5.73	320.15	<50	<0.50	<0.50	<0.50	<1.0	**2.2**	**430**	<2.0	<2.0	**1,900**	**–**	**–**
	02/27/07	3.03	322.85	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**330**	<2.0	<2.0	**1,600**	**–**	**–**
	06/07/07	4.32	321.56	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,500**	**–**	**–**
	09/14/07	4.45	321.43	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**58**	<2.0	<2.0	**630**	**–**	**–**
	11/17/07	4.39	321.49	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**640**	**–**	**–**
	02/28/08	–	–	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/04/08	4.02	321.86	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**870**	–	–
	09/11/08	4.26	321.62	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**290**	<2.0	<2.0	**1,300**	–	–
	12/23/08	3.91	321.97	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**150**	**–**	**–**
	03/17/09	3.11	322.77	**640**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,400**	**–**	**–**
	06/26/09	4.27	321.61	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**85**	**–**	**–**
	12/03/09	4.45	321.43	**540**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**770**	**–**	**–**
	06/11/10	3.74	322.14	**220**	<0.50	<0.50	<0.50	<1.0	<2.0	**130**	<2.0	<2.0	**1,100**	**–**	**–**
	11/10/10	4.63	321.25	**220**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**350**	–	–
	06/03/11	3.67	322.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**220**	<2.0	<2.0	**100**	–	–
	12/06/11	4.62	321.26	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**110**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	3.92	321.96	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**130**	<2.0	<2.0	**58**	<0.40	<5,000
	04/27/12	3.51	322.37	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**110**	<2.0	<2.0	**110**	<0.40	<5,000
	07/13/12	4.51	321.37	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**42**	<2.0	<2.0	**87**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	3.59	322.29	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**120**	–	–
	06/27/13	4.71	321.17	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**53**	–	–
	12/17/13	4.70	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**34**	–	–
MW-9	04/27/06	2.45	322.84	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2,200**	–	–
"B" Zone	06/01/06	3.52	321.77	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,000**	–	–
<325.29>	09/12/06	4.01	321.28	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**130**	<2.0	<2.0	**2,100**	–	–
	11/21/06	4.08	321.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**180**	<2.0	<2.0	**1,200**	–	–
	02/27/07	2.69	322.60	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**270**	<2.0	<2.0	**930**	–	–
	06/07/07	3.73	321.56	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,400**	–	–
	09/14/07	4.02	321.27	NA	<0.50	<0.50	<0.50	<1.0	<2.0	**35**	<2.0	<2.0	**460**	–	–
	11/17/07	–	–	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**910**	–	–
	02/28/08	2.13	323.16	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,200**	–	–
	06/04/08	3.41	321.88	<50	<0.50	<0.50	<0.50	<1.0	**2.4**	**1,400**	<2.0	<2.0	**5,500**	–	–
	09/11/08	3.70	321.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**810**	<2.0	<2.0	**2,700**	–	–
	12/23/08	3.29	322.00	**62**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**260**	–	–
	03/17/09	2.59	322.70	**1,800**	<0.50	<0.50	<0.50	<1.0	**3.0**	<10	<2.0	<2.0	**3,800**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	06/26/09	3.73	321.56	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**41**	–	–
	12/03/09	–	–	**2,200**	<0.50	<0.50	<0.50	<1.0	<2.0	**12**	<2.0	<2.0	**2,800**	–	–
	06/09/10	3.20	322.09	**850**	<0.50	<0.50	<0.50	<1.0	<2.0	**660**	<2.0	<2.0	**3,800**	–	–
	11/10/10	–	–	**400**	<0.50	<0.50	<0.50	<1.0	<2.0	**1,200**	<2.0	<2.0	**800**	–	–
	06/03/11	3.07	322.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**460**	<2.0	<2.0	**260**	–	–
	12/06/11	4.07	321.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**330**	<2.0	<2.0	**47**	–	–
Ozone Remediation Initiated on February 27, 2012															
	03/22/12	3.37	321.92	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**860**	<2.0	<2.0	**470**	<0.2	<5.0
	04/27/12	3.00	322.29	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**340**	<2.0	<2.0	**1,500**	<0.2	<5.0
	07/13/12	3.85	321.44	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**400**	<2.0	<2.0	**410**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	2.95	322.34	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**700**	<2.0	<2.0	**140**	–	–
	06/26/13	4.15	321.14	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**19**	–	–
	12/17/13	4.11	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**32**	–	–
MW-10	04/27/06	2.65	322.89	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**15**	–	–
"B" Zone	06/01/06	3.72	321.82	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
<325.54>	09/12/06	4.27	321.27	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**12**	–	–
	11/21/06	4.35	321.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**15**	–	–
	02/27/07	3.78	321.76	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**11**	–	–
	06/07/07	3.91	321.63	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**12**	–	–
	09/14/07	4.22	321.32	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	11/17/07	4.06	321.48	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6.1**	–	–
	02/28/08	2.83	322.71	NA	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/04/08	–	–	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**9.5**	–	–
	09/11/08	4.33	321.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**7.8**	–	–
	12/23/08	3.44	322.10	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	03/17/09	3.50	322.04	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/26/09	4.63	320.91	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	12/03/09	4.11	321.43	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**7.4**	–	–
	06/09/10	3.42	322.12	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6.4**	–	–
	11/10/10	4.32	321.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**6.4**	–	–
	06/03/11	3.29	322.25	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.0**	–	–
	12/06/11	4.27	321.27	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.2**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/13/12	3.96	321.58	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.9**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	3.24	322.30	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.2**	–	–
	06/26/13	4.39	321.15	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**4.1**	–	–
	12/17/13	4.31	321.23	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**5.7**	–	–
MW-11	06/11/10	6.68	322.36	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**550**	<2.0	<2.0	**160**	–	–
"A" Zone	11/11/10	7.81	321.23	**110**	<0.50	<0.50	<0.50	<1.0	<2.0	**530**	<2.0	<2.0	**180**	–	–
<329.04>	06/01/11	6.53	322.51	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**150**	<2.0	<2.0	**66**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	12/07/11	7.54	321.50	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**120**	<2.0	<2.0	**59**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	7.48	321.56	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**84**	<2.0	<2.0	**51**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/10/12	6.45	322.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**28**	<2.0	<2.0	**38**	–	–
	06/26/13	7.86	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**23**	–	–
	12/17/13			**Well Not Accessible**											
MW-12	06/11/10	6.83	322.29	**190**	<0.50	<0.50	<0.50	<1.0	<2.0	**2,400**	<2.0	<2.0	**870**	–	–
"A" Zone	11/11/10	7.92	321.20	**380**	<0.50	<0.50	<0.50	<1.0	<2.0	**1,300**	<2.0	<2.0	**680**	–	–
<329.12>	06/01/11	6.90	322.22	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**230**	<2.0	<2.0	**230**	–	–
	12/07/11	7.69	321.43	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**87**	<2.0	<2.0	**110**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	7.54	321.58	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**26**	<2.0	<2.0	**8.6**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/10/12	6.53	322.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**11**	–	–
	06/26/13	7.94	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.9**	–	–
	12/17/13	7.55	321.57	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**3.9**	–	–
MW-13	06/11/10	6.64	322.29	**150**	<0.50	<0.50	<0.50	<1.0	<2.0	**780**	<2.0	<2.0	**800**	–	–
"A" Zone	11/11/10	7.72	321.21	**320**	<0.50	<0.50	<0.50	<1.0	<2.0	**810**	<2.0	<2.0	**550**	–	–
<328.93>	06/01/11	6.72	322.21	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**210**	<2.0	<2.0	**160**	–	–
	12/07/11	7.53	321.40	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**110**	<2.0	<2.0	**110**	–	–

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	7.33	321.60	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**35**	<2.0	<2.0	**40**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/10/12	6.34	322.59	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**24**	–	–
	06/26/13	7.74	321.19	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**13**	–	–
	12/17/13			**Well Not Accessible**											
MW-14	06/10/10	2.48	321.90	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**150**	–	–
"B" Zone	11/10/10	3.20	321.18	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**4.8**	–	–
<324.38>	06/01/11	2.38	322.00	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**12**	<2.0	<2.0	**36**	–	–
	12/06/11	3.23	321.15	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1.4**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	2.87	321.51	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	2.18	322.20	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/26/13	3.33	321.05	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	12/17/13	3.38	321.00	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
MW-15	06/10/10	4.24	321.52	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
"B" Zone	11/10/10	4.84	320.92	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
<325.76>	06/01/11	4.18	321.58	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	12/06/11	4.95	320.81	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
Ozone Remediation Initiated on February 27, 2012															

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	07/12/12	4.40	321.36	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
Ozone Remediation Ended on November 23, 2012															
	12/21/12	3.96	321.80	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/26/13	5.01	320.75	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	12/17/13	5.21	320.55	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
MW-16	06/10/10	4.65	321.64	**230**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**1,200**	**–**	**–**
"B" Zone	11/10/10	5.42	320.87	**520**	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**830**	**–**	**–**
<326.29>	06/01/11	4.58	321.71	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**230**	<2.0	<2.0	**960**	**–**	**–**
	12/06/11	5.47	320.82	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**510**	<2.0	<2.0	**730**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	5.00	321.29	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**350**	<2.0	<2.0	**750**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/20/12	4.36	321.93	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**220**	<2.0	<2.0	**950**	–	–
	06/26/13	5.48	320.81	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**90**	<2.0	<2.0	**1,000**	–	–
	12/17/13	5.67	320.62	<50	<0.50	<0.50	<0.50	<1.0	<2.0	**61**	<2.0	<2.0	**870**	–	–
MW-17	06/10/10	3.50	322.96	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
"B" Zone	11/10/10	5.63	320.83	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
<326.46>	06/01/11	4.78	321.68	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	**–**	**–**
	12/06/11	5.68	320.78	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	**2.8**	**–**	**–**
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	5.18	321.28	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	**–**	**–**

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
Ozone Remediation Ended on November 23, 2012															
	12/20/12	4.56	321.90	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	06/26/13	5.91	320.55	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
	12/17/13	5.85	320.61	<50	<0.50	<0.50	<0.50	<1.0	<2.0	<10	<2.0	<2.0	<1.0	–	–
EW-1	06/10/10	6.47	322.47	**170**	**15**	<0.50	**4.4**	**1.2**	<2.0	<10	<2.0	<2.0	**76**	–	–
"A" Zone	11/11/10	7.69	321.25	**740**	**53**	<0.50	**7.5**	<1.0	<2.0	**150**	<2.0	<2.0	**140**	–	–
<328.94>	06/03/11	6.68	322.26	<50	**11**	<0.50	**1.7**	<1.0	<2.0	**140**	<2.0	<2.0	**35**	–	–
	12/07/11	7.53	321.41	**440**	**38**	<0.50	**3.5**	<1.0	<2.0	**110**	<2.0	<2.0	**48**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	7.38	321.56	**980**	**22**	**1.4**	**4.6**	<1.0	<2.0	**180**	<2.0	<2.0	**36**	–	–
Ozone Remediation Ended on November 23, 2012															
	12/10/12	6.36	322.58	**320**	**42**	<0.50	**37**	**1.8**	<2.0	**150**	<2.0	<2.0	**53**	–	–
	06/26/13	7.78	321.16	**350**	**7.4**	<0.50	**8.0**	**24.8**	<2.0	**60**	<2.0	<2.0	**20**	–	–
	12/17/13			**Well Not Accessible**											
EW-2	06/10/10	6.62	322.37	**99**	**11**	**1.0**	**3.0**	**3.3**	<2.0	<10	<2.0	<2.0	**110**	–	–
"A" Zone	11/11/10			**Well was not gauged or sampled on this date.**										–	–
<328.99>	06/01/11			**Well was not gauged or sampled on this date.**											
	12/07/11	7.49	321.50	**570**	**26**	<0.50	**42**	**1.9**	<2.0	**490**	<2.0	<2.0	**150**	–	–
Ozone Remediation Initiated on February 27, 2012															
	07/12/12	7.41	321.58	**570**	**19**	<0.5	**8.1**	<1.0	<2.0	**620**	<2.0	<2.0	**100**	–	–
Ozone Remediation Ended on November 23, 2012															

Table 1
CUMULATIVE GROUNDWATER LABORATORY ANALYTICAL RESULTS
Dublin Toyota UST Site

Sample ID	Sample Date	GW Depth	GW Elevation	Concentrations, in micrograms per liter (ug/l)											
				TPH-G	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	Cr6	Br
	12/10/12	6.36	322.63	**99**	**14**	<0.5	**6.2**	**8.9**	<2.0	**2,100**	<2.0	<2.0	**100**	–	–
	06/26/13	7.78	321.16	**270**	**3.1**	<0.50	**3.3**	<1.0	<2.0	**740**	<2.0	<2.0	**62**	–	–
	12/17/13			**Well Not Accessible**											

Table Notes:

GW Depth = Groundwater depth below top of casing.
GW Elevation = Groundwater mean sea level elevation.
TPH-G = Total Petroleum Hydrocarbons as Gasoline
B = Benzene
T = Toluene
E = Ethylbenzene
X = Xylenes
TAME = Tert-amyl Methyl EtherTBA = tert-Butanol
DIPE = Diisopropyle ether
ETBE = Ethyl-tert-butyl ether
MTBE = Methyl-t-Butyl Ether
Cr6 = Hexavalent Chromium
Br = Bromate
NA = Not analyzed for particular parameter
<0.050 = Not detected above the expressed value.
<328.88> = Surveyed top of casing mean sea level elevation.
“A” Zone = Discontinuous sand and gravel layers shallower than 25 feet in depth.
“B” Zone = Semi-continuos sand and gravel layer between about 30 and 35 feet in depth.
1 = MTBE result was confirmed using USEPA Method 8260B.

FIGURES



DESIGNED BY:	CHECKED BY:	**SITE VICINITY MAP**	DATE: 04/04/2014
DRAWN BY: MAR	SCALE:	DUBLIN TOYOTA UST SITE 6450 DUBLIN COURT DUBLIN, CALIFORNIA	FIGURE: **1**
PROJECT NO:			GRIBI



DESIGNED BY:	CHECKED BY:	**SITE AREA PLAN**	DATE: 04/04/2014	FIGURE: **2**
DRAWN BY: MAR	SCALE:	DUBLIN TOYOTA UST SITE 6450 DUBLIN COURT DUBLIN, CALIFORNIA	GRIBI	
PROJECT NO:				



DESIGNED BY:	CHECKED BY:	**SITE PLAN**	DATE: 04/04/2014	FIGURE: 3
DRAWN BY: MAR	SCALE:	DUBLIN TOYOTA UST SITE 6450 DUBLIN COURT DUBLIN, CALIFORNIA	GRIBI	
PROJECT NO:				



DESIGNED BY:	CHECKED BY:	**"A" ZONE GROUNDWATER ELEVATIONS AND HYDROCARBON RESULTS, 06/2013** DUBLIN TOYOTA UST SITE 6450 DUBLIN COURT DUBLIN, CALIFORNIA	DATE: 04/04/2014	FIGURE: **4**
DRAWN BY: MAR	SCALE:			GRIBI
PROJECT NO:				



DESIGNED BY:	CHECKED BY:	**"B" ZONE GROUNDWATER ELEVATIONS AND HYDROCARBON RESULTS, 06/2013** DUBLIN TOYOTA UST SITE 6450 DUBLIN COURT DUBLIN, CALIFORNIA	DATE: 04/04/2014	FIGURE: **5**
DRAWN BY: MAR	SCALE:			
PROJECT NO:				

ATTACHMENT A

GROUNDWATER MONITORING FIELD DATA RECORDS

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**

Sampling Personnel: MAR | Date: 12/17/2012

Weather Conditions: Cloudy, cool

Well ID: **MW-1**

Casing Diameter (inches): **2.0** | Total Depth (feet): **20.2**

Depth to Water: 7.32 | Depth to Free Product: —

Water Column (ft): 12.88 | Product Thickness: 4

One Well Volume (gal): 2.19 | 3x Well Volume (gal): 6.6

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V purge pump
Sample Method		X	12V purge pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1225							
1228	2	20.3	2.77		6.95		
1230	4	20.2	2.79		6.96		
1233	6	20.2	2.83		6.96		
1234	7	20.1	2.84		6.95		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1235 **Sampler's Signature** MAR

Groundwater Gauging Field Sheet

Client Name: Dublin Toyota | Project Name: Dublin Toyota

Field Personnel: M. Rosman | Date: 12/17-18/2013

Weather Conditions: PC, cold & cool

Well ID	*Depth to Free Product (feet)*	*Depth to Groundwater (feet)*	*Casing Elevation (msl)*	*Groundwater Elevation (msl)*	*Total Well Depth (feet)*	*Well Box Conditions*
MW-1	—	7.32	328.88	321.56	20.2	
MW-2	—	5.92	327.64	321.72	20.2	
MW-3	—	5.92	327.44	321.52	20	
MW-4S	—	6.44	327.80	321.36	20	
MW-4D	—	6.077	327.67	321.60	30.8	
MW-5S	—	5.76	327.09	321.33	20.2	
MW-5D	—	5.94	327.30	321.36	25.3	
MW-6S	—	5.31	326.53	321.22	19.0	
MW-6D	—	5.42	326.72	321.30	33.9	
MW-7	—	4.92	326.16	321.24	20.0	
MW-8	—	4.70	325.88	321.18	35.0	
MW-9	—	4.11	325.39	321.18	40	
MW-10	—	4.31	325.54	321.23	39.4	
MW-11	—	7.55	329.04	—	19.6	Not Accessible
MW-12	—		329.12	321.57	19.6	
MW-13	—		328.93	—	19.6	Not Accessible
MW-14	—	3.38	324.38	321.00	39.5	
MW-15	—	5.21	325.76	320.55	39.6	
MW-16	—	5.67	326.29	320.62	39.5	
MW-17	—	5.85	326.46	320.61	38.5	
EW-1	—		328.94	—	14.4	Not Accessible
EW-2	—		328.99	—	14.3	Not Accessible

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, cool

Well ID: **MW-2**
Casing Diameter (inches): **2.0** | Total Depth (feet): **20.2**
Depth to Water: 5.92 | Depth to Free Product: —
Water Column (ft): 14.28 | Product Thickness: Ø
One Well Volume (gal): 2.43 | 3x Well Volume (gal): 7.3

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V purge pump
Sample Method		X	12V purge pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1200							
1202	2	19.7	1.83		7.07		
1205	4	19.6	1.86		7.17		
1208	6	19.5	1.87		7.20		
1209	7	19.5	1.87		7.21		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1210 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, Cool

Well ID: **MW-3**
Casing Diameter (inches): **2.0** | Total Depth (feet): **20**
Depth to Water: 5.92 | Depth to Free Product: —
Water Column (ft): 14.08 | Product Thickness: Ø
One Well Volume (gal): 2.39 | 3x Well Volume (gal): 7.2

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V purge pump
Sample Method		X	12V purge pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1131							
1133	2	22.7	2.61		6.43		
1136	4	22.5	2.80		7.00		
1138	6	23.0	4.47		7.06		
1140	7	23.0	4.97		7.02		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1140 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/18/2013
Weather Conditions: PC, Cool

Well ID: **MW-4S**
Casing Diameter (inches): **0.75** | Total Depth (feet): **20**
Depth to Water: 6.44 | Depth to Free Product: —
Water Column (ft): 13.56 | Product Thickness: Ø
One Well Volume (gal): 0.80 | 3x Well Volume (gal): 2.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V, peristaltic pump
Sample Method		X	12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1011							
1018	1	22.4	5.06		6.72		
1025	2	22.1	5.09		6.75		
1032	3	22.1	5.07		6.75		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1035 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/18/2013
Weather Conditions: PC, Cool

Well ID: **MW-4D**
Casing Diameter (inches): **0.75** | Total Depth (feet): **30.8**
Depth to Water: 6.07 | Depth to Free Product: —
Water Column (ft): 24.73 | Product Thickness: Ø
One Well Volume (gal): 1.46 | 3x Well Volume (gal): 4.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V peristaltic pump
Sample Method		X	12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1000							
1005	1.5	21.6	2.53		7.34		Dry @ ~1.5 gal
	3						
	4						
	5						

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1040 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/18/2013
Weather Conditions: PC, cold

Well ID: **MW-5S**
Casing Diameter (inches): **0.75** | Total Depth (feet): **20.2**
Depth to Water: 5.76 | Depth to Free Product: —
Water Column (ft): 14.44 | Product Thickness: Ø
One Well Volume (gal): 0.85 | 3x Well Volume (gal): 2.6

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V peristaltic pump
Sample Method			12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
0905							
0913	1	22.0	3.48		6.77		
0919	2	22.0	3.51		6.77		
0926	3	22.0	3.50		6.77		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 0930 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/18/2013
Weather Conditions: PC, cold

Well ID: **MW-5D**
Casing Diameter (inches): **0.75** | Total Depth (feet): **25.3**
Depth to Water: 5.94 | Depth to Free Product: —
Water Column (ft): 19.36 | Product Thickness: Ø
One Well Volume (gal): 1.14 | 3x Well Volume (gal): 3.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V peristaltic pump
Sample Method		X	12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
0856							
0903	1	21.0	6.50		7.04		Dry @ ~1.5gl
	2						
	3						
	4						

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 0940 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/18/2013
Weather Conditions: PC, cool

Well ID: **MW-6S**
Casing Diameter (inches): **0.75** | Total Depth (feet): **19.0**
Depth to Water: 5.31 | Depth to Free Product: —
Water Column (ft): 13.69 | Product Thickness: Ø
One Well Volume (gal): 0.81 | 3x Well Volume (gal): 2.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V peristaltic pump
Sample Method		X	12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1111							
1119	1	21.7	5.23		6.75		DRY @ 1 gal.
	2						
	3						

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color					
Odor					
Turbidity					
Sheen					
Other:					

Sample Time _____ **Sampler's Signature** _____

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/18/2013
Weather Conditions: PC, cool

Well ID: **MW-6D**
Casing Diameter (inches): **0.75** | Total Depth (feet): **33.9**
Depth to Water: 5.42 | Depth to Free Product: —
Water Column (ft): 28.48 | Product Thickness: Ø
One Well Volume (gal): 1.68 | 3x Well Volume (gal): 5.0

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V peristaltic pump
Sample Method		X	12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1125							
1134	2	20.1	4.87		6.89		
1139	3	20.1	4.65		6.90		
1144	4	20.0	4.51		6.91		
1149	5	20.0	4.51		6.91		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1150 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, Cool

Well ID: **MW-7**
Casing Diameter (inches): **0.75** | Total Depth (feet): **20.0**
Depth to Water: 4.92 | Depth to Free Product: —
Water Column (ft): 15.08 | Product Thickness: Ø
One Well Volume (gal): 0.89 | 3x Well Volume (gal): 2.7

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V Peristaltic Pump
Sample Method		X	12V Peristaltic Pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1609							
1618	1	21.1	5.29		6.86		
1625	2	21.2	5.09		6.85		
1634	3	21.2	5.05		6.84		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1635 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, Cool

Well ID: **MW-8**
Casing Diameter (inches): **0.75** | Total Depth (feet): **35.0**
Depth to Water: 4.70 | Depth to Free Product: —
Water Column (ft): 30.30 | Product Thickness: Ø
One Well Volume (gal): 1.79 | 3x Well Volume (gal): 5.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V Peristaltic pump
Sample Method		X	12V Peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1525							
1533	2	19.8	3.41		6.95		
1543	4	19.8	3.42		6.96		
1552	6	19.7	3.41		6.96		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1555 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, cool

Well ID: **MW-9**
Casing Diameter (inches): **0.75** | Total Depth (feet): **40**
Depth to Water: 4.11 | Depth to Free Product: —
Water Column (ft): 35.89 | Product Thickness: 0
One Well Volume (gal): 2.12 | 3x Well Volume (gal): 6.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V Peristaltic Pump
Sample Method		X	12V Peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1445							
1454	2	19.5	4.51		6.82		
1504	4	19.5	4.44		6.82		
1513	6	19.5	4.48		6.81		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1515 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: ~~Clear~~ PC, cool

Well ID: **MW-10**
Casing Diameter (inches): **0.75** | Total Depth (feet): **39.4**
Depth to Water: 4.31 | Depth to Free Product: —
Water Column (ft): 35.09 | Product Thickness: 0
One Well Volume (gal): 2.07 | 3x Well Volume (gal): 6.2

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V peristaltic pump
Sample Method		X	12V peristaltic pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1359							
1408	2	19.7	4.26		6.90		
1418	4	19.7	4.26		6.89		
1427	6	19.7	4.32		6.90		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1430 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, cool

Well ID: **MW-12**
Casing Diameter (inches): **2.0** | Total Depth (feet): **19.6**
Depth to Water: 7.55 | Depth to Free Product: —
Water Column (ft): 12.05 | Product Thickness: ϕ
One Well Volume (gal): 2.05 | 3x Well Volume (gal): 6.1

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V Purge Pump
Sample Method		X	12V Purge Pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1255							
1258	2	18.7	4.36		6.94		
1301	4	18.8	4.27		6.92		
1304	6	18.8	4.12		6.91		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1305 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, cool

Well ID: **MW-14**
Casing Diameter (inches): **2.0** | Total Depth (feet): **39.5**
Depth to Water: 3.38 | Depth to Free Product: —
Water Column (ft): 36.12 | Product Thickness: ϕ
One Well Volume (gal): 6.14 | 3x Well Volume (gal): 18.4

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V Purge Pump
Sample Method		X	12V Purge Pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
1103							
1106	5	19.3	5.08		6.93		
1109	10	19.3	5.04		6.92		
1112	15	19.3	5.05		6.92		
1114	19	19.3	4.99		6.92		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1115 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, cold

Well ID: **MW-15**
Casing Diameter (inches): **2.0** | Total Depth (feet): **39.6**
Depth to Water: 5.21 | Depth to Free Product: —
Water Column (ft): 34.39 | Product Thickness: Ø
One Well Volume (gal): 5.85 | 3x Well Volume (gal): 17.5

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V purge pump
Sample Method		X	12V purge pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
0840							
0845	5	18.6	6.35		7.00		
0850	10	18.5	6.15		7.02		
0856	15	18.5	5.95		7.01		
0859	18	18.5	5.89		7.01		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 0900 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**
Sampling Personnel: MAR | Date: 12/17/2013
Weather Conditions: PC, cold

Well ID: **MW-16**
Casing Diameter (inches): **2.0** | Total Depth (feet): **39.5**
Depth to Water: 5.67 | Depth to Free Product: —
Water Column (ft): 33.83 | Product Thickness: Ø
One Well Volume (gal): 5.75 | 3x Well Volume (gal): 17.3

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V purge pump
Sample Method		X	12V purge pump

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
0946							
0949	5	19.2	5.34		6.79		
0952	10	19.2	5.34		6.80		
0955	15	19.2	5.35		6.80		
0957	18	19.2	5.33		6.80		

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color	X				
Odor	X				
Turbidity	X				
Sheen	X				
Other:					

Sample Time 1000 **Sampler's Signature** MAR

Groundwater Monitoring Field Sheet

Client Name: **Dublin Toyota** | Project Name: **Dublin Toyota**

Sampling Personnel: MAR | Date: 12/17/2013

Weather Conditions: PC, Cold

Well ID: **MW-17**

Casing Diameter (inches): **2.0** | Total Depth (feet): **38.5**

Depth to Water: 5.85 | Depth to Free Product: —

Water Column (ft): 32.65 | Product Thickness: 0

One Well Volume (gal): 5.55 | 3x Well Volume (gal): 16.7

Notes:
One Well Volume is determine by multiplying "Water Column" by:
- 0.059 for 3/4-inch well, 0.17 for 2-inch well, 0.38 for 3-inch well, 0.66 for 4-inch well, 1.50 for 6-inch well

FIELD METHODS

Activity	*Bailer*	*Pump*	*Comments*
Purge Method		X	12V purge pump
Sample Method	X		

FIELD PARAMETERS

Time	*Volume Purged*	*Temp. (F or C)*	*E.C. (mS/cm)*	*D.O. (mg/L)*	*pH*	*ORP (mV)*	*Comments*
0913							
0917	5	19.8	6.01		6.84		
0922	10	19.6	5.95		6.93		
0927 14	~~15~~	19.4	5.98		6.91		Dry @ ~14 gal
	17						

SAMPLE OBSERVATIONS

Characteristic	*None*	*Slight*	*Moderate*	*Strong*	*Comments*
Color		X			gray-brown
Odor	X				
Turbidity		X			
Sheen	X				
Other:					

Sample Time: 0935 | **Sampler's Signature**: MAR

ATTACHMENT B

LABORATORY DATA REPORTS AND CHAIN-OF-CUSTODY RECORDS

SunStar Laboratories, Inc.
PROVIDING QUALITY ANALYTICAL SERVICES NATIONWIDE

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

03 January 2014

Jim Gribi
Gribi Associates
1090 Adam Street, Suite K
Benicia, CA 94510

RE: Dublin Toyota

Enclosed are the results of analyses for samples received by the laboratory on 12/20/13 09:45. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Katherine RunningCrane
Project Manager

SunStar Laboratories, Inc.
PROVIDING QUALITY ANALYTICAL SERVICES NATIONWIDE

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
MW-1	T132719-01	Water	12/17/13 12:35	12/20/13 09:45
MW-2	T132719-02	Water	12/17/13 12:10	12/20/13 09:45
MW-3	T132719-03	Water	12/17/13 11:40	12/20/13 09:45
MW-4S	T132719-04	Water	12/18/13 10:35	12/20/13 09:45
MW-4D	T132719-05	Water	12/18/13 10:40	12/20/13 09:45
MW-5S	T132719-06	Water	12/18/13 09:30	12/20/13 09:45
MW-5D	T132719-07	Water	12/18/13 09:40	12/20/13 09:45
MW-6S	T132719-08	Water	12/18/13 12:00	12/20/13 09:45
MW-6D	T132719-09	Water	12/18/13 11:50	12/20/13 09:45
MW-7	T132719-10	Water	12/17/13 16:35	12/20/13 09:45
MW-8	T132719-11	Water	12/17/13 15:55	12/20/13 09:45
MW-9	T132719-12	Water	12/17/13 15:15	12/20/13 09:45
MW-10	T132719-13	Water	12/17/13 14:30	12/20/13 09:45
MW-12	T132719-14	Water	12/17/13 13:05	12/20/13 09:45
MW-14	T132719-15	Water	12/17/13 11:15	12/20/13 09:45
MW-15	T132719-16	Water	12/17/13 09:00	12/20/13 09:45
MW-16	T132719-17	Water	12/17/13 10:00	12/20/13 09:45
MW-17	T132719-18	Water	12/17/13 09:35	12/20/13 09:45

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-1
T132719-01 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**4.1**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*93.2 %*	*88.8-117*		"	"	"	"	
Surrogate: 4-Bromofluorobenzene		*99.2 %*	*83.5-119*		"	"	"	"	
Surrogate: Dibromofluoromethane		*102 %*	*81.1-136*		"	"	"	"	

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-2
T132719-02 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**1.3**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*92.8 %*	*88.8-117*		"	"	"	"	
Surrogate: 4-Bromofluorobenzene		*95.0 %*	*83.5-119*		"	"	"	"	
Surrogate: Dibromofluoromethane		*103 %*	*81.1-136*		"	"	"	"	

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-3

T132719-03 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**7.7**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*93.4 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*91.8 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*103 %*	*81.1-136*		*"*	*"*	*"*	*"*	

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-4S

T132719-04 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**62**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*91.1 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*92.9 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*103 %*	*81.1-136*		*"*	*"*	*"*	*"*	

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-4D

T132719-05 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**80**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*101 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*106 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*106 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-5S

T132719-06 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**1.8**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*104 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*104 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*105 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-5D

T132719-07 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	12/31/13	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**140**	5.0	"	5	"	"	"	"	
C6-C12 (GRO)	ND	50	"	1	"	"	"	"	
Surrogate: Toluene-d8		*98.9 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*108 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*101 %*	*81.1-136*		*"*	*"*	*"*	*"*	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-6S

T132719-08 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**86**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*102 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*107 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*103 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-6D
T132719-09 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**27**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*93.1 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*107 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*104 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-7
T132719-10 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	**230**	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**240**	10	"	10	"	"	"	"	
C6-C12 (GRO)	ND	50	"	1	"	"	"	"	
Surrogate: Toluene-d8		*96.0 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*108 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*102 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-8

T132719-11 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**34**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*107 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*106 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*97.1 %*	*81.1-136*		*"*	*"*	*"*	*"*	

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-9

T132719-12 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**32**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*105 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*115 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*106 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-10
T132719-13 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**5.7**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*88.9 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*107 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*109 %*	*81.1-136*		*"*	*"*	*"*	*"*	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-12
T132719-14 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**3.9**	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*97.5 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*103 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*109 %*	*81.1-136*		*"*	*"*	*"*	*"*	

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-14
T132719-15 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	ND	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*111 %*	*88.8-117*		"	"	"	"	
Surrogate: 4-Bromofluorobenzene		*104 %*	*83.5-119*		"	"	"	"	
Surrogate: Dibromofluoromethane		*110 %*	*81.1-136*		"	"	"	"	

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-15
T132719-16 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	ND	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*106 %*	*88.8-117*		"	"	"	"	
Surrogate: 4-Bromofluorobenzene		*109 %*	*83.5-119*		"	"	"	"	
Surrogate: Dibromofluoromethane		*109 %*	*81.1-136*		"	"	"	"	

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-16
T132719-17 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	**61**	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	**870**	10	"	10	"	"	"	"	
C6-C12 (GRO)	ND	50	"	1	"	"	"	"	
Surrogate: Toluene-d8		*105 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*110 %*	*83.5-119*		*"*	*"*	*"*	*"*	
Surrogate: Dibromofluoromethane		*115 %*	*81.1-136*		*"*	*"*	*"*	*"*	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

MW-17
T132719-18 (Water)

SunStar Laboratories, Inc.

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.50	ug/l	1	3122019	12/20/13	01/01/14	EPA 8260B	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
m,p-Xylene	ND	1.0	"	"	"	"	"	"	
o-Xylene	ND	0.50	"	"	"	"	"	"	
Tert-amyl methyl ether	ND	2.0	"	"	"	"	"	"	
Tert-butyl alcohol	ND	10	"	"	"	"	"	"	
Di-isopropyl ether	ND	2.0	"	"	"	"	"	"	
Ethyl tert-butyl ether	ND	2.0	"	"	"	"	"	"	
Methyl tert-butyl ether	ND	1.0	"	"	"	"	"	"	
C6-C12 (GRO)	ND	50	"	"	"	"	"	"	
Surrogate: Toluene-d8		*103 %*	*88.8-117*		*"*	*"*	*"*	*"*	
Surrogate: 4-Bromofluorobenzene		*125 %*	*83.5-119*		*"*	*"*	*"*	*"*	*S-GC*
Surrogate: Dibromofluoromethane		*107 %*	*81.1-136*		*"*	*"*	*"*	*"*	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

Volatile Organic Compounds by EPA Method 8260B - Quality Control

SunStar Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 3122019 - EPA 5030 GCMS										
Blank (3122019-BLK1)				Prepared: 12/20/13 Analyzed: 12/31/13						
Benzene	ND	0.50	ug/l							
Toluene	ND	0.50	"							
Ethylbenzene	ND	0.50	"							
m,p-Xylene	ND	1.0	"							
o-Xylene	ND	0.50	"							
Tert-amyl methyl ether	ND	2.0	"							
Tert-butyl alcohol	ND	10	"							
Di-isopropyl ether	ND	2.0	"							
Ethyl tert-butyl ether	ND	2.0	"							
Methyl tert-butyl ether	ND	1.0	"							
C6-C12 (GRO)	ND	50	"							
Surrogate: Toluene-d8	*7.79*		*"*	*8.00*		*97.4*	*88.8-117*			
Surrogate: 4-Bromofluorobenzene	*8.00*		*"*	*8.00*		*100*	*83.5-119*			
Surrogate: Dibromofluoromethane	*7.66*		*"*	*8.00*		*95.8*	*81.1-136*			
LCS (3122019-BS1)				Prepared: 12/20/13 Analyzed: 12/31/13						
Chlorobenzene	18.1	1.0	ug/l	20.0		90.6	75-125			
1,1-Dichloroethene	17.8	1.0	"	20.0		89.2	75-125			
Trichloroethene	15.9	1.0	"	20.0		79.7	75-125			
Benzene	18.1	0.50	"	20.0		90.6	75-125			
Toluene	17.5	0.50	"	20.0		87.4	75-125			
Surrogate: Toluene-d8	*7.90*		*"*	*8.00*		*98.8*	*88.8-117*			
Surrogate: 4-Bromofluorobenzene	*9.03*		*"*	*8.00*		*113*	*83.5-119*			
Surrogate: Dibromofluoromethane	*7.83*		*"*	*8.00*		*97.9*	*81.1-136*			
Matrix Spike (3122019-MS1)	**Source: T132719-01**			Prepared: 12/20/13 Analyzed: 12/31/13						
Chlorobenzene	20.9	1.0	ug/l	20.0	ND	104	75-125			
1,1-Dichloroethene	17.9	1.0	"	20.0	ND	89.4	75-125			
Trichloroethene	17.2	1.0	"	20.0	ND	86.2	75-125			
Benzene	20.1	0.50	"	20.0	ND	101	75-125			
Toluene	18.5	0.50	"	20.0	ND	92.4	75-125			
Surrogate: Toluene-d8	*7.98*		*"*	*8.00*		*99.8*	*88.8-117*			
Surrogate: 4-Bromofluorobenzene	*9.71*		*"*	*8.00*		*121*	*83.5-119*			*S-GC*
Surrogate: Dibromofluoromethane	*8.04*		*"*	*8.00*		*100*	*81.1-136*			

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

Volatile Organic Compounds by EPA Method 8260B - Quality Control

SunStar Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 3122019 - EPA 5030 GCMS										
Matrix Spike Dup (3122019-MSD1)	**Source: T132719-01**			Prepared: 12/20/13 Analyzed: 12/31/13						
Chlorobenzene	21.1	1.0	ug/l	20.0	ND	105	75-125	0.954	20	
1,1-Dichloroethene	17.9	1.0	"	20.0	ND	89.7	75-125	0.335	20	
Trichloroethene	16.6	1.0	"	20.0	ND	83.2	75-125	3.48	20	
Benzene	18.7	0.50	"	20.0	ND	93.5	75-125	7.32	20	
Toluene	17.4	0.50	"	20.0	ND	87.0	75-125	6.02	20	
Surrogate: Toluene-d8	*7.53*		*"*	*8.00*		*94.1*	*88.8-117*			
Surrogate: 4-Bromofluorobenzene	*8.79*		*"*	*8.00*		*110*	*83.5-119*			
Surrogate: Dibromofluoromethane	*8.08*		*"*	*8.00*		*101*	*81.1-136*			

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane, Project Manager

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

25712 Commercentre Drive
Lake Forest, California 92630
949.297.5020 Phone
949.297.5027 Fax

Gribi Associates	Project: Dublin Toyota	
1090 Adam Street, Suite K	Project Number: 147-01-03	**Reported:**
Benicia CA, 94510	Project Manager: Jim Gribi	01/03/14 17:09

Notes and Definitions

S-GC	Surrogate recovery outside of established control limits. The data was accepted based on valid recovery of the remaining surrogate(s).
DET	Analyte DETECTED
ND	Analyte NOT DETECTED at or above the reporting limit
NR	Not Reported
dry	Sample results reported on a dry weight basis
RPD	Relative Percent Difference

SunStar Laboratories, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Katherine RunningCrane

Katherine RunningCrane, Project Manager

SUNSTAR LABORATORIES

25712 COMMERCENTRE DRIVE
LAKE FOREST, CA 92630
Website: www.SUNSTARLABS.com E-mail: john@sunstarlabs.com
Telephone: (949) 297-5020 Fax: (949) 297-5027

CHAIN OF CUSTODY RECORD

TURN AROUND TIME ☐ RUSH ☐ 24 HR ☐ 48 HR ☐ 72 HR ■ 5 DAY
■ GeoTracker EDF ☐ PDF ☐ Excel ☐ Write On (DW)

Report To: James Gribi — Bill To:
Company: Gribi Associates
1090 Adams Street, Suite K
Benicia, CA 94510
Tele: (707) 748-7743 E-Mail: Fax: (707) 748-7763
Client Name: Dublin Toyota Global ID: T0600102153
Project Name: Dublin Toyota
Sampler Signature:

SAMPLE ID	LOCATION/ Field Point Name	SAMPLING Date	SAMPLING Time	# Containers	Type Containers	MATRIX: Water	Soil	Air	Sludge	Other	METHOD PRESERVED: Ice	HCl	HNO_3	Other
MW-1	01	12/17	1235	4	voa	X					X	X		
MW-2	02	12/17	1210	4	voa	X					X	X		
MW-3	03	12/17	1140	4	voa	X					X	X		
MW-4S	04	12/18	1035	4	voa	X					X	X		
MW-4D	05	12/18	1010	4	voa	X					X	X		
MW-5S	06	12/18	0830	4	voa	X					X	X		
MW-5D	07	12/18	0940	4	voa	X					X	X		
MW-6S	08	12/18	1200	4	voa	X					X	X		
MW-6D	09	12/18	1150	4	voa	X					X	X		
MW-7	10	12/17	1635	4	voa	X					X	X		
MW-8	11	12/17	1555	4	voa	X					X	X		
MW-9	12	12/17	1515	4	voa	X					X	X		
MW-10	13	12/17	1430	4	voa	X					X	X		
MW-11				1	voa	X					X			

Relinquished By: Date: 12/18/13 Time: 1700 Received By:
Relinquished By: Date: 12-20-13 Time: 9:45 Received By:
Relinquished By: Date: Time: Received By:

ICE/t° 2.6
GOOD CONDITION ✓
HEAD SPACE ABSENT ✓
DECHLORINATED IN LAB
APPROPRIATE CONTAINERS ✓
PRESERVED IN LAB

PRESERVATION VOAS O&G METALS OTHER
pH<2

COMMENTS: STD. TAT

Analysis Request	Other	Comments
TPH-Gas, BTEX, MTBE (8015M/8021B)		
TPH-Gas (8015M)		
TPH-Diesel (8015M)		
TPH-Motor Oil (8015M)		
TPH-Gas, BTEX, MTBE (8260B)		
TPH-Gas, BTEX, 5 Oxygenates (8260B)		
TPH-Gas, BTEX, 7 Oxygenates (8260B)		
5 Oxygenates (8260B)		
Lead Scavengers [1,2 DCA & 1,2 EDB] (8260B)		
VOC's – Full List (8260B)		
Halogenated VOC's (8260B)		
SVOC's (8270)		

Filter Samples for Metals analysis: Yes / No

Page 1 of 2



SUNSTAR LABORATORIES
25712 COMMERCENTRE DRIVE
LAKE FOREST, CA 92630
Website: www.SUNSTARLABS.com Email: john@sunstarlabs.com
Telephone: (949) 297-5020 Fax: (949) 297-5027

T132719

CHAIN OF CUSTODY RECORD
TURN AROUND TIME: RUSH ☐ 24 HR ☐ 48 HR ☐ 72 HR ☐ 5 DAY ■
■ GeoTracker EDF ☐ PDF ☐ Excel ☐ Write On (DW)

Report To: James Gribi | Bill To:
Company: Gribi Associates
1090 Adams Street, Suite K
Benicia, CA 94510 | E-Mail:
Tele: (707) 748-7743 | Fax: (707) 748-7763
Client Name: Dublin Toyota | Global ID: T0600102153
Project Name: Dublin Toyota
Sampler Signature:

SAMPLE ID	LOCATION/ Field Point Name	SAMPLING Date	SAMPLING Time	# Containers	Type Containers	MATRIX Water	MATRIX Soil	MATRIX Air	MATRIX Sludge	MATRIX Other	METHOD PRESERVED Ice	METHOD PRESERVED HCl	METHOD PRESERVED HNO_3	METHOD PRESERVED Other	Analysis Request: TPH-Gas, BTEX, MTBE (8015M/8021B)	TPH-Gas (8015M)	TPH-Diesel (8015M)	TPH-Motor Oil (8015M)	TPH-Gas, BTEX, MTBE (8260B)	TPH-Gas, BTEX, 5 Oxygenates (8260B)	TPH-Gas, BTEX, 7 Oxygenates (8260B)	5 Oxygenates (8260B)	Lead Scavengers [1,2 DCA & 1,2 EDB] (8260B)	VOC's – Full List (8260B)	Halogenated VOC's (8260B)	SVOC's (8270)	Other	Comments: Filter Samples for Metals analysis: Yes / No
MW-12	14	12/1/17	1305	4	VOA	X					X	X			X				X									
MW-13	14			4	VOA	X					X	X			X				X									
MW-14	15	12/1/17	1115	4	VOA	X					X	X			X				X									
MW-15	16	12/1/17	0940	4	VOA	X					X	X			X				X									
MW-16	17	12/1/17	1000	4	VOA	X					X	X			X				X									
MW-17	18	12/1/17	0935	4	VOA	X					X	X			X				X									
EW-1				4	VOA	X					X	X			X				X									
EW-2				4	VOA	X					X	X			X				X									

Relinquished By: Date: 12/1/17 Time: 1700 Received By: Date: Time:
Relinquished By: Date: 12/1/17 Time: 2115 Received By: Date: Time:
Relinquished By: Date: 12/01/17 Time: 9:45 Received By: Date: Time:

ICE/t° 3.6
GOOD CONDITION Y
HEAD SPACE ABSENT
DECHLORINATED IN LAB
APPROPRIATE CONTAINERS Y
PRESERVED IN LAB
PRESERVATION VOAS O&G METALS OTHER pH<2

COMMENTS:
ID. TAT
12/20/17

Page 2 of 2

SunStar Laboratories, Inc.
Providing Quality Analytical Services Nationwide

SAMPLE RECEIVING REVIEW SHEET

BATCH # T132719

Client Name: GRIBI Project: DUBLIN TOYOTA

Received by: BRIANA Date/Time Received: 12/20/17 9:45

Delivered by : ☐ Client ☐ SunStar Courier ☒ GSO ☐ FedEx ☐ Other

Total number of coolers received 1 **Temp criteria = 6°C > 0°C (no frozen containers)**

Temperature: cooler #1 3.8 °C +/- the CF (- 0.2°C) = 3.6 °C corrected temperature

cooler #2 _____ °C +/- the CF (- 0.2°C) = _____ °C corrected temperature

cooler #3 _____ °C +/- the CF (- 0.2°C) = _____ °C corrected temperature

Samples outside temp. but received on ice, w/in 6 hours of final sampling.	☒Yes	☐No*	☐N/A
Custody Seals Intact on Cooler/Sample	☒Yes	☐No*	☐N/A
Sample Containers Intact	☒Yes	☐No*	
Sample labels match COC ID's	☒Yes	☐No*	
Total number of containers received match COC	☒Yes	☐No*	
Proper containers received for analyses requested on COC	☒Yes	☐No*	
Proper preservative indicated on COC/containers for analyses requested	☒Yes	☐No*	☐N/A

Complete shipment received in good condition with correct temperatures, containers, labels, volumes preservatives and within method specified holding times. ☒ **Yes** ☐**No***

* Complete Non-Conformance Receiving Sheet if checked Cooler/Sample Review - Initials and date BC 12/20/17

Comments: