
ARCADIS GERAGHTY& MILLEROTION

99 MAR -1 PM 4: 38





Results of Quarterly Groundwater Monitoring, Fourth Quarter 1998 Former Penske Truck Leasing Company Facility 725 Julie Ann Way Oakland, California

Dear Mr. Chan:

The above referenced report is being forwarded to you at the request of Penske Truck Leasing Co. The report details the results of quarterly groundwater monitoring and sampling for the fourth quarter 1998 at the Former Penske Truck Leasing Facility at 725 Julie Ann Way, Oakland.

Please note that the requested information related to additional measurements for dissolved oxygen and redox have been included in Table 1 and new Figure 4. Please also note the reductions in concentrations for most constituents since mid-1997 as shown in Table 2.

If you have any questions, please do not hesitate to call

Sincerely,

ARCADIS Geraghty & Miller, Inc.

Paul Hehn, R.G.

Project Geologist/Project Manager

Copies:

Mr. Richard G. Saut Penske Truck Leasing Co.

Files - Project No. RC000019.0010

ARCADIS Geraghty & Miller, Inc. 1050 Marina Way South Richmond California 94804 Tel 510 233 3200 Fax 510 233 3204

WESTERN REGION

Richmond, California, February 26, 1999

Contact:

Paul V. Hehn

Extension:

(510) 233-3200

Our ref.: Project No. RC000321,0002/aclt1298.doc



RECEIVED

FEB 2 4 1999

ARCADIS Geraghty & Miller

Via Fax 510-233-3204

February 22, 1999

Mr. Paul Hehn Arcadis, Inc. 1050 Marina Way South Richmond, CA 94804

Re:

Fourth Quarter 1998

Groundwater Monitoring Report

Former Penske Truck Leasing Facility

725 Julie Ann Way

Oakland, CA

Dear Paul,

I have reviewed and approve the above referenced report. Please forward the appropriate number of copies to the required regulatory agencies. Please provide two copies for my file with a copy of your report transmittal letters to the agencies. If you have questions or need assistance, please call my office at 610-775-6010.

Sincerely,

Richard G. Saut

Environmental Project Manager

RGS/csk L1022299.rgs

Results of Quarterly Groundwater Monitoring

Fourth Quarter 1998

Former Penske Truck Leasing Facility 725 Julie Ann Way Oakland, California



1050 Marina Way South Richmond, CA 94804 (510) 233-3200

QUARTERLY REPORT

Prepared February 5, 1999



Mr. Richard G. Saut Environmental Project Manager Penske Truck Leasing Company, L.P. Route 10, Green Hills P.O. Box 7635 Reading, Pennsylvania 19603-7635 ARCADIS Geraghty & Miller, Inc. 1050 Marina Way South Richmond California 94804 Tel 510 233 3200 Fax 510 233 3204

WESTERN REGION

Subject:

Results of Quarterly Groundwater Monitoring, Fourth Quarter 1998, Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

Dear Mr. Saut:

This report presents the results of the fourth quarter 1998 quarterly groundwater monitoring and sampling activities performed on December 22, 1998, at the former Penske Truck Leasing Co. (Penske) facility referenced above (Figure 1).

The scope of work for this project was presented to Penske in an ARCADIS Geraghty & Miller letter dated January 25, 1996. The scope of work for groundwater monitoring and sampling consists of collecting depth-to-water measurements, total-well-depth measurements, and water samples for laboratory analysis from selected wells. The scope of work also includes preparation of quarterly groundwater sampling and monitoring reports based on the data and groundwater samples collected during each quarterly event.

This quarterly groundwater sampling and monitoring program is related to the containment zone (CZ) concept remedial approach approved by the Alameda County Health Care Services Agency (ACHCSA) and the California Regional Water Quality Control Board – San Francisco Bay Region (RWQCB) in its letter to Penske dated March 25, 1994.

Richmond, February 5, 1999

Contact: Paul V. Hehn

Extension: 510 233 3200

Field Procedures

The subject quarterly groundwater monitoring was performed on December 22, 1998. The monitoring-well locations are shown in Figure 2. Monitoring was completed and groundwater samples were collected from Monitoring Wells MW-1, MW-2, MW-4, MW-5, and MW-7 in accordance with the CZ remedial approach monitoring and sampling plan referenced above. Recent changes authorized by the ACHCSA for reduction in sampling from Wells MW-3 and MW-6 are discussed in

the section on Recent Regulatory Requested Changes. Monitoring Well MW-8 was not sampled during the current sampling event since the analytical results of the groundwater samples collected during the previous quarter were within the authorized compliance level. Further discussion of the compliance results is presented in the Discussion and Compliance with Containment Zone Approach section of this report.

The current fourth quarter sampling event represents the initial semi-annual sampling event for Monitoring Well MW-5. A discussion of the circumstance surrounding the revision of the sampling interval is also provided in the section on Recent Regulatory Requested Changes.

Prior to sampling, depth-to-water measurements were obtained from all on-site wells. Additionally, the wells were checked for the presence of liquid-phase hydrocarbons. All equipment that entered the well was washed in a solution of nonphosphate detergent and water and then triple rinsed in deionized water. Each well sampled was purged of at least four casing volumes of water. At Penske's request, additional purging was performed to remove dissolved-phase petroleum hydrocarbons from the groundwater. Due to the purging equipment used to perform the extra purging, the exact amount of water purged from each well cannot be accurately determined but definitely exceeded the amount necessary for a minimum full four well volume purge. The approximate well volume estimated by the field personnel indicates that the extra purge volume exceeded the four volume purge requirements by 15 to 50%. During the current event, it was estimated that 800 gallons were purged from the five wells sampled at the site. This total is approximately 50% more groundwater purged than would normally be required by a four volume well purge.

Purged water was monitored for pH, temperature, and specific conductance. A summary of the field data is presented in Table 1. Following purging, groundwater samples were collected using a new disposable polyethylene bailer for each well. The purged water was removed by a Penske-contracted vacuum truck for proper disposal.

Groundwater samples were put into the appropriate USEPA-approved containers, placed on ice, and transported to Quanterra Laboratory in West Sacramento, California, under appropriate chain-of-custody documentation. The water samples were analyzed for total petroleum hydrocarbons (TPH) as gasoline (USEPA Method 8015, modified); TPH as diesel (USEPA Method 8015, modified); benzene, toluene, ethylbenzene, and total xylenes (BTEX) (USEPA Method 8020); and methyl tertiary butyl ether (MTBE) (USEPA Method 8020).

Ost TRZh x 7.5 golfm3

800 : 160 gal/well

Results

Shallow Groundwater Flow

A summary of the depth-to-water data is presented in Table 1. Depth to water ranged from 5.40 feet (Monitoring Well MW-5) to 6.73 feet (Monitoring Well MW-3) below the ground surface. A contour map based on the groundwater elevation data collected December 22, 1998, is presented in Figure 2. The historic shallow groundwater flow is toward the west; however, there are local variations in flow directions at the facility, as indicated by the groundwater contours from the data collected during December 1998. Liquid-phase hydrocarbons were measured in Wells MW-1 (0.01 foot) and MW-7 (0.04 foot) during this monitoring event.

The difference in the elevation of the groundwater surface between Wells MW-2 and MW-1 is 0.42 feet, producing a hydraulic gradient (slope of the groundwater surface) of approximately 0.0046 feet/foot in a southwesterly direction. The groundwater gradient and groundwater contours for the current quarter are consistent with those presented during previous quarters.

Field Parameters

As in all previous quarterly sampling events at this facility, the specific conductance measurements for the groundwater purged during the sampling continue to be high (Table 1).

Groundwater Analytical Results

A summary of the groundwater analytical results is presented in Table 2. Copies of the certified laboratory reports and chain-of-custody documentation are included in Attachment 1. TPH as gasoline was detected in the groundwater samples from Monitoring Wells MW-1 (2,000 μ g/L), MW-2 (67 μ g/L), and MW-7 (3,900 μ g/L). TPH as diesel was detected in the groundwater samples collected from Monitoring Wells MW-1 (79,000 μ g/L), MW-2 (1,200 μ g/L), MW-4 (3,700 μ g/L), MW-5 (890 μ g/L), and MW-7 (240,000 μ g/L). Benzene was only detected in the groundwater samples collected from Monitoring Wells MW-1 (32 μ g/L) and MW-7 (51 μ g/L) (Figure 3). All other BTEX constituent results are presented in Table 2. TPH as gasoline, BTEX and MTBE were not detected in the trip blank.

Discussion and Compliance with Containment Zone Approach

Benzene was not detected at concentrations exceeding the compliance concentration of 71 µg/L in the shallow groundwater sample collected from designated CZ-concept

Guard Well MW-7 (51 μ g/L). Since the benzene concentration detected in Guard Well MW-7 was below the compliance level during the previous quarterly sampling event (third quarter 1998), downgradient Well MW-8 was not sampled during the current fourth quarter sampling event. Sampling of Well MW-8 will be suspended. If any future quarterly sampling event detects benzene concentrations in excess of the compliance level in Guard Well MW-7, downgradient Well MW-8 will again be sampled during the next quarterly event following the out of compliance detection.

Increases in TPH as gasoline concentrations were detected in the samples collected from Wells MW-1 (from 1,300 μ g/L to 2,000 μ g/L) and MW-7 (from 710 μ g/L to 3,900 μ g/L). Decreases were detected in the groundwater samples collected from Wells MW-2 (from 3,200 μ g/L to 67 μ g/L) and MW-4 (from 2,400 μ g/L to ND). TPH as gasoline was not detected (ND) in Well MW-5.

Increases in TPH as diesel concentrations were detected in the samples collected from Wells MW-1 (from 63,000 μ g/L to 79,000 μ g/L), MW-5 (from 630 μ g/L to 890 μ g/L), and MW-7 (from 89,000 μ g/L to 240,000 μ g/L). Decreases were detected in the groundwater samples collected from Wells MW-2 (from 3,500 μ g/L to 1,200 μ g/L) and MW-4 (from 670,000 μ g/L to 3,700 μ g/L).

Increases in benzene concentrations were only detected in the samples collected from Well MW-7 (from 39 μ g/L to 51 μ g/L). Decreases in benzene concentrations were detected in the groundwater samples collected from Well MW-1 (from 43 μ g/L to 32 μ g/L) and MW-4 (from 5.7 μ g/L to ND). Benzene was not detected (ND) in Wells MW-2 and MW-5.

Concentrations of petroleum hydrocarbons continue to be detected in Wells MW-1, MW-4 and MW-7, all of which are located immediately downgradient from the former UST excavation. The concentrations that continue to be detected from these wells indicate that a mass of petroleum hydrocarbons remains downgradient from the former UST excavation. However, decreases in the concentrations of petroleum hydrocarbons detected in the groundwater samples collected from Wells MW-1, MW-4 and MW-7 may indicate that the mass of petroleum hydrocarbons present is being reduced by the additional vacuum-enhanced purging. The reductions could also indicate increased biodegradation activity taking place in the vicinity of these wells as a result of the addition of the ORCTM socks in Observation Wells OW-1 and OW-2 which are both located upgradient from Wells MW-1, MW-4 and MW-7.

At the request of Penske, additional groundwater purging using the vacuum-enhanced purging method will be continued during future quarterly events. The additional purging will help to remove additional mass of petroleum hydrocarbons from the groundwater downgradient from the former tank excavation which will aid in the remediation of the groundwater at this former facility.

Discussion on Recent Regulatory Requested Changes

A letter dated December 9, 1997 from Mr. Barney Chan at the ACHCSA was received by Penske. In his letter, Mr. Chan stated that Monitoring Wells MW-3 and MW-6 no longer need to be sampled. He also stated that there was no need to run total dissolved solids (TDS) from any of the wells being sampled at the site. Consequently, TDS is no longer being analyzed for groundwater samples collected, and Monitoring Wells MW-3 and MW-6 are no longer being sampled.

Mr. Chan also requested that dissolved oxygen (DO) and oxygen-reduction potential (redox) measurements be collected from all wells during all future quarterly sampling events (Figure 4). ARCADIS Geraghty & Miller recommends, and Penske would prefer that these measurements be collected twice a year rather than every quarter. It is recommended that these measurements be collected during the spring quarterly sampling event (higher average groundwater levels) and during the fall quarterly sampling event (lower average groundwater levels). This recommended frequency of measurements would collect sufficient information to monitor biodegradation activity.

NO 1

In order to provide a baseline of DO and redox information, these measurements were collected from all available wells during the current fourth quarter sampling event. Measurements were collected from Wells MW-2, MW-3, MW-5, MW-6, and MW-8. DO and redox measurements were not collected from Wells MW-1, MW-4 and MW-7 since globular masses of weathered product in the water in these wells coated the measuring instruments making measurements inaccurate.

In another letter from the ACHCSA to Penske dated June 25, 1998, Mr. Chan stated that the monitoring of Well MW-5 could be reduced to semi-annual. The current fourth quarter sampling event represents the initial semi-annual sampling of this well. Monitoring Well MW-5 will be sampling again during the second quarter of 1999 and then every other quarter thereafter.

Additional Activities During the Next Quarter

During the first quarter of 1999, the ORC[™] socks placed in Observation Wells OW-1 and OW-2 will be changed. To complete this change, the existing ORC[™] socks will be removed from the wells. Once the socks are removed from the wells, the wells will be monitored for dissolved oxygen and redox measurements using down well field instruments. Following these measurements, the wells will be purged, monitored and sampled using the normal well purging and sampling procedures followed for this site. The groundwater samples collected from Observation Well

OW-1 and OW-2 will be analyzed for TPH as gasoline, TPH as diesel, BTEX, and MTBE. Groundwater samples will also be collected and analyzed for biodegradation parameters for nitrate, sulfate and ferrous iron as requested by the ACHCSA. Following the collection of the groundwater samples, additional groundwater will be purged from the wells using the vacuum-enhanced purging method. Upon completion of the well purging and sampling, the replacement ORCTM socks will be installed in Wells OW-1 and OW-2.

The results of the measurements and analytical results of the groundwater sampled from Observation Wells OW-1 and OW-2 will be reported as part of the first quarter 1999 sampling event report.

ARCADIS Geraghty & Miller appreciates the opportunity to be of service to Penske. If you have any questions regarding this report, please do not hesitate to call us.

Sincerely,

ARCADIS Geraghty & Miller, Inc.

Paul V. Hehn, R.G.

Project Geologist/Project Manager,

Donald C. Trueblood Regional Manager

Attachments: References

Table 1 Summary of Field Sampling, Depth-to-Water, and

Casing Elevation Data

Table 2 Summary of Groundwater Analytical Results-

Monthly and Quarterly Sampling

Figure 1 Site Location Map

Figure 2 Shallow Groundwater Contours - Fourth Quarter

1998

Figure 3 Benzene Concentrations - Fourth Quarter 1998

Figure 4 Biodegradation Parameter Results - Fourth Quarter

1998

Attachment 1 Copies of Certified Laboratory Reports and Chain-

of-Custody Documentation

No. 6571

References

Alameda County Health Care Services Agency. December 6, 1996. Letter to Penske Truck Leasing Co. on Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, CA 94621.
———. December 9, 1997. Letter to Penske Truck Leasing Co. on Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, CA 94621.
———. May 20, 1998. Letter to Penske Truck Leasing Co. on Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, CA 94621.
June 25, 1998. Letter to Penske Truck Leasing Co. on Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, CA 94621.
——. December 28, 1998. Letter to Penske Truck Leasing Co. on Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, CA 94621.
Geraghty & Miller, Inc. November 15, 1990. Results of Initial Soil and Ground-Water Assessment Activities, Former Penske Truck Leasing Co. Facility, 725 Julie Ann Way, Oakland, California.
——. February 7, 1991. Scope of Work and Project Budget Estimate for Ground-Water Monitoring Activities for the Period February 1991 through February 1992, Former Penske Truck Leasing Co. Facility, 725 Julie Ann Way, Oakland, California.
January 25, 1995. Work Plan and Budget Cost Estimate for Groundwater Sampling Coordination, Quarterly Report Preparation, and Purge Water Disposal Assistance, Former Penske Truck Leasing Co. Facility, 725 Julie Ann Way, Oakland, California.
———. January 25, 1996. Work Plan and Budget Cost Estimate for Groundwater Sampling Coordination, Quarterly Report Preparation, and Purge Water Disposal Assistance, Former Penske Truck Leasing Co. Facility, 725 Julie Ann Way, Oakland, California.

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	ments			Casing
		Water (a)	Elevation	Elevation	of Well (a)	Purge Volume (b)	Volume		Temp.	SC	DO	Redox	Diameter
Well	Date	(feet)	(feet)	(feet)	(feet)	(gallons)	(gallons)	pН	(°F)	(µS/cm)	(mg/L)	(mv)	(inches)
MW-1	2-Oct-90	9.76	5.42	-4.34	37.28	58.56	47	6.71	87.5	5,280			4
1111111	28-Feb-91	8.54		-3.12	33.58	65.00	70	6.30	66.0	9,700			
	25-Маг-91	7,35		-1.93	33.50	71.00	75	6.50	64.0	7,200			
	1-May-91	7.91		-2.49	33.70	67.00	51	6.20	65.0	3,500			
	5-Aug-91	8.63		-3.21	NM	51.00	68	NM	63.6	7,690			
	23-Oct-91	9.00		-3.58	33.77	67,00	67	9.40	64.2	7,470			
	6-Jan-92	8.52		-3.10	33.87	65.00	69	9.40	63.2	6,640			
	20-Jul-92	7.94		-2.52	33.95	65.02	66	7.20	65.7	6,410			
	23-Oct-92	8.62		-3.20	33.57	64.80	60	7.50	69.8	1,930			
	4-Feb-93	6.55	5.43 (c)	-1.12	33.84	70.96	71	8.02	65.0	9,520			
	8-Apr-93	6.37	()	-0.94	33.80	71.32	65	6.60	66.7	>2,000			
	6-Aug-93	7.39		-1.96	33.88	68.67	69	7.22	68.1	5,890			
	28-Oct-93	7.85		-2.42	33.80	67.48	68	7.00	68.3	5,910			
	1-Feb-94			-1.82	33.99	69.52	70	7.63	63.2	7,610			
	12-Sep-94			-1.32	33.95	70.72	70	6.90	75.8	7,950			
	23-Nov-94			-0.70	33.93	72.28	73	6.10	66.2	>2,000			
	21-Feb-95			-0.57	34.00	55.44	56	7.36	70	890			
	23-May-95			-0.61	34.00	54.52	56	7.11	66.2	5,920			
	16-Aug-95			-0.60	34.00	55.94	56	7.27	69.3	5,510			
	21-Nov-95			-1.47	34.00	52.85	54	7.19	67.8	5,720			
	13-Feb-96			0,25	33.87	74.59	>75	7	71.2	6,070			
	13-May-96			-0.67	NM	72.20 (f)	>73	6.5	76.4	14,370			
	28-Aug-96			-0.74	33.85	71.96	>72	7	85.5	4,820			
	28-Aug-96 21-Nov-96			-0.66	33.92	72.43	>73	6.5	77.8	7,890			
	20-Feb-97			0,02	33.94	74.17	>75	6,0	66.3	1,900			
	28-May-97			-0.55	NM	72.69 (f)	>73	8.0	77	9,000			
	19-Sep-97			-1.02	33.80	71.12	>72	7.4	71.3	5,500			
	17-Nov-97			-0.71	34.03	72.51	>73	7.12	75	6,690			
	27-Feb-98			0.60	33.97	75.76	>76	6.80	65	6,680			
	27-May-98			-0.99	34.00	71.60	72	6.79	62.42	7,990			
	1-Oct-98			-1.06	34.00	71.52	>72	8.01	65.7	5,220			
	22-Dec-98			-0.92	34.00	71.89	>72	6.82	63.4	5,860	NM	NM	

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	ments			Casing
		Water (a)	Elevation	Elevation	of Well (a)	Purge Volume (b)	Volume		Temp.	SC	DO	Redox	Diamete
Well	Date	(feet)	(feet)	(feet)	(feet)	(gallons)	(gallons)	рH	(°F)	(µ5/cm)	(mg/L)	(mv)	(inches)
MW-2	2-Oct-90	10.38	6.21	-4.17	32.97	48.07	47	6.92	86.4	5,460			4
	28-Feb-91	9.19		-2.98	29.39	53.00	55	6.60	64.0	9,000			
	25-Mar-91	7.95		-1.74	29.39	57.00	70	6.60	63.0	6,400			
	1-May-91	8.58		-2.37	29.60	55,00	50	6.20	64.0	3,000			
	5-Aug-91	9.33		-3.12	NM	40.00	54	NM	65.1	5,680			
	23-Oct-91	9.57		-3.36	29.35	52.00	53	7.60	65.4	7,970			
	6-Jan-92	9.08		-2.87	29.50	53.00	53	9.18	62.8	6,990			
	20-Jul-92	8.60		-2.39	29.45	54.21	55	6.50	65.2	6,690			
	23-Oct-92	9.33		-3.12	29.18	51.60	55	7.20	69.8	1,900			
	4-Feb-93	7.17	6.20 (c)	-0.97	29.37	57.72	55	8.25	64.0	10,310			
	8-Apr-93	6.95		-0.75	29.32	58.16	60	6.90	66.7	>2,000			
	6-Aug-93	8.05		-1.85	29.33	55.33	66.5	7.26	66.4	6,250			
	28-Oct-93	8.50		-2.30	29.43	54.40	55	7.08	71.2	6,780			
	1-Feb-94	7.87		-1.67	29.54	56.32	57	8.35	62.4	8,250			
	12-Sep-94	7.42		-1.22	29.45	57. 2 4	66	(e)	69.9	8,130			
	22-Nov-94	6.75		-0.55	29.50	59.15	60	6,8	67.6	>2,000			
	21-Feb-95	6.20		0.00	30.00	47.12	48	6.97	64	1,050			
	23-May-95	6.10		0.10	30.00	46,60	48	7.18	70.3	7,710			
	16-Aug-95	6.69		-0.49	30.00	46.62	46	7.42	65	6,790			
	21-Nov-95	7.62		-1.42	30.00	43.64	45	7.30	67.6	7,250			
	13-Feb-96	5.81	•	0.39	29.47	61.51	>62	7	71.8	2,890			
	13-May-96	6.40		-0.20	NM	59.98 (f)	>60	5.5	74.4	860			
	28-Aug-96	7.11		-0.91	29.42	58.00	>58	6	83.5	590			
	21-Nov-96	6.41		-0.21	29.43	59.85	>60	6.5	76.3	4,160			
	20-Feb-97	6.26		-0.06	29.54	60,52	>61	6.5	65.2	1,940			
	28-May-97	6.65		-0.45	NM	59.51 (f)	>60	7.0	73.6	5,540			
	19-Sep-97	6.90		-0.70	29.47	58.68	>59	6.9	69.7	12,630			
	17-Nov-97	6.75		-0.55	29.56	59.31	>60	8.08	75.7	710			
	27-Feb-98	5.31		0.89	29.45	62.76	>63	6.50	67.3	530			
	27-May-98	5.87		0,33	29.47	61.36	62	6.95	63.5	5,870			
	1-Oct-98	6.95		-0.75	29.45	58,52	>59	7.96	66. ?	1,100			
	22-Dec-98	6.70		-0.50	29.23	58.58	>59	6.74	52.8	450	0.30	-242	(u_l)

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measure	ments			Casing
		Water (a)	Elevation	Elevation	of Well (a)	Purge Volume (b)	Volume		Temp.	SC	DO	Redox	Diameter
Well	Date	(feet)	(feet)	(feet)	(feet)	(gallons)	(gallons)	рН	(°F)	(µS/cm)	(mg/L)	(mv)	(inches)
MW-3	2-Oct-90	10.38	6.10	-4.28	37.08	56.82	54	6.89	88.4	639			4
	28-Feb-91	9.45		-3.35	31.61	58.00	60	6.10	66.0	1,020			
	25-Mar-91	7.98		-1.88	31.60	70.00	75	6,40	65.0	8,200			
	1-May-91	8,58		-2.48	33.70	65.00	50	6,40	67.0	4,100			
	5-Aug-91	9,26		-3.16	NM	50.00	67	NM	64.1	6,190			
	23-Oct-91	9.60		-3.50	33.48	66.00	66	7.30	67.3	8,430			
	6-Jan-92	9.08		-2.98	33.66	64.00	64	9,98	61.7	7,010			
	20-Jul-92	8.59		-2.49	33.76	65,44	66	6.80	66.0	7,540			
	23-Oct-92	9.30		-3.20	33.47	63.40	65	7.50	71.6	1,800			
	4-Feb-93	7.19	6.10 (c)	-1.09	33.65	68.79	65	8.29	64.0	10,290			
	8-Apr-93	6.98		-0.88	33.55	69.08	72	6.90	68.2	>2,000			
	6-Aug-93	8.01		-1. 9 1	33.55	66,40	56 (d)	7.43	67.3	6,490			
	28-Oct-93	8.45		-2,35	33.60	65.40	66	7.02	72.0	6,590			
	1-Feb-94	8.03	•	-1.93	33.74	66.84	67	8.32	63.3	8,400			
	12-Sep-94	7.39		-1. 2 9	33.70	68.40	70	7.73	68.7	8,030			
	22-Nov-94	6.76		-0.66	33.75	70.17	70	6.60	65.8	>2,000			
	21-Feb-95	6.36		-0.26	33.50	53.74	54	6.99	85,4	880			
	23-May-95	6.48		-0.38	33.50	52.69	54	7.25	68.7	6,060			
	16-Aug-95	6.63		-0.53	33.50	53.74	54	7.53	66.1	5,390			
	21-Nov-95	7.51		-1.41	33.50	50.68	52	7.34	67.4	5,730			•
	13-Feb-96	5.91		0.19	33.69	72.24	>73	7	71.5	6,790			
	13-May-96	6.36		-0.26	NM	71.06 (f)	>72	6.5	76.7	14,360			
	28-Aug-96	7.15		-1.05	33.52	68.56	>69	8.	79.2	2,930			
	21-Nov-96			-0.54	33.54	69.94	>70	6.5	77.0	7,500			
	20-Feb-97			-0.26	33.67	71.00	>72	6,5	68.7	4,180			
	28-May-97	6.62		-0.52	NM	70.33 (f)	>71	7.0	74.1	6,580			
	19-Sep-97	6.83		-0.73	33.55	69.48	>70	7.0	70.8	8,570			
	17-Nov-97			-0.67	33.59	69.73	>70	7.08	75.0	6,580			
	27-Feb-98	5.38		0.72	33.60	73,37	>74	7.0	65.9	7,530			•
	27-May-98	6.05		0.05	33.63	71.72	72	8.28	64.8	6,880			
	1-Oct-98	6.95		-0.85	33.70	69.56	>70	7.71	67.1	6,380			
	22-Dec-98	6.73	•	-0.63	33.60	NS	NS	NS	NS	NS	0.80	118	upgrad
													. [/ 1

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	nents			Casing
Well	Date	Water (a) (feet)	Elevation (feet)	Elevation (feet)	of Well (a) (feet)	Purge Volume (b) (gallons)	Volume (gallons)	pН	Temp. (°F)	SC (µS/cm)	DO (mg/L)	Redox (mv)	Diamete (inches)
MW-4	4-Feb-93	6.68	5.18 (c)	-1.50	32.70	64.38	60 (d)	NM	63.5	14,100			4
	8-Apr-93	6.21	• •	-1.03	33.04	69.76	70	6.80	69.1	>2,000			
	6-Aug-93	7.20		-2.02	32.92	66.87	60 (d)	7.44	68.9	13,900			
	28-Oct-93	7.64		-2.46	32.98	65.88	66	6.79	72.1	11,940			
	1-Feb-94	7.26		-2.08	33.31	67. 72	68	8.65	63.6	18,110			
	12-Sep-94	6.55		-1.37	33.41	69.84	60 (d)	6.03	77.5	16,710			
	23 Nov-94	6.08		-0.90	33.35	70.90	55 (d)	5.60	66.7	>2,000			
	21-Feb-95	5.36		-0.18	33.50	55.71	48 (d)	6.83	80.2	880			
	23-May-95	5.05		0.13	33.50	55.48	59	6.71	66.5	12,090			
	16-Aug-95	5.63		-0.45	33.50	55.74	33 (d)	7.34	69.8	8,670			
	21-Nov-95	6.63		-1.45	33.50	52.39	34 (d)	7.03	68.2	10,380			
	13-Feb-96	5.14		0.04	33.25	73.08	>74	7	75.3	6,090			
	13-May-96	5.75		-0.57	NM	71.50 (f)	>72	7	76.1	>20,000			
	28-Aug-96	6.04		-0.86	33.20	70.61	>71	7.4	83.9	2,600			
	21-Nov-96	7.90		-2.72	33.17	65.70	>66	6.5	75.9	8,940			
	20-Feb-97	5.29		-0.11	33.28	72.77	>73	6.5	66.1	2,110			
	28-May-97	5.66		-0.48	NM	71.81 (f)	>72	7.0	74	6,480		•	
	19-Sep-97	6.00		-0,82	33.31	71.00	>71	7.4	71	4,330			
	17-Nov-97	6.06		-0.88	33.35	70.95	>71	6.81	70	11,020			
	27-Feb-98	4.66		0.52	33.22	74.25	>75	7.30	65,9	15,720			
	27-May-98	5.98		-0.80	33.00	70.40	35 (d)	6.89	62.4	10,980			
	1-Oct-98	5.23		-0.05	33.26	72.88	>73	7.87	66,8	3,390			
	22-Dec-98	6.57		-1.39	33.52	70.07	>70	6.25	57.7	13,000	NM	NM	

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measure	ments			Casing
		Water (a)	Elevation	Elevation	of Well (a)	Purge Volume (b)	Volume		Temp.	SC (vE(cm)	DO (mg/l)	Redox (mv)	Diamet (inches
Well	Date	(feet)	(feet)	(feet)	(feet)	(gallons)	(gallons)	pН	(°F)	(µ5/cm)	(mg/L)	(1117)	(IIICI1ES
MW-5	4-Feb-93	8.94	4.71 (c)	-4.23	31.40	61.65	40 (d)	8.43	63.2	16,870			4
	8-Apr-93	5.43		-0.72	31.36	67.42	68	7.20	68.0	>2,000			
	6-Aug-93	6.19		-1.48	31.30	65.29	68	7.47	63,6	5,180			
	28-Oct-93	6,86		-2.15	31.43	62.72	48 (d)	7.12	70.6	4,980			
	1-Feb-94	6.48		-1.77	31.43	64.84	49 (d)	(e)	63.1	6,120			
	12-Sep-94	5.89		-1.18	31.43	66.40	39 (d)	(e)	69.4	5,020			
	22-Nov-94	5.66		-0.95	31.44	67.02	58 (d)	6.80	68.4	>2,000			
	21-Feb-95	4.90		-0.19	31.00	51.68	45 (d)	7.30	82.5	880			
	23-May-95	4.86		-0.15	31.00	50.97	52	7.03	66.5	4,320			
	16-Aug-95	4.97		-0.26	31.00	52.06	36 (d)	7.48	67.5	3,900			
	21-Nov-95	5.82		-1.11	31.00	49.10	32 (d)	7.26	67.0	4,110			
	13-Feb-96	4.86		-0.15	31.41	69.03	>69	7	68.3	5,950			
	13-May-96	5.06		-0.35	NM	68.51 (f)	>69	6.5	71.9	9,830			
	28-Aug-96	5.29		-0.58	31.34	67.73	>68	7.9	79.6	2,590			
	21-Nov-96	5.44		-0.73	31.33	67.31	>67	6.5	76.0	7,2 60			
	20-Feb-97	4.68		0.03	31.46	69.62	>70	6.5	60.7	1,990			
	28-May-97	5.21		-0.50	NM	68.25 (f)	>69	7.8	70.7	11,500			
	19-Sep-97	5.43		-0.72	31.46	67.68	>68	7.1	67.9	3,920			
	17-Nov-97	5.28		-0.57	31.44	68.02	>69	7.0	73.0	5,180			
	27-Feb-98	4.10		0.61	31.49	71.21	>72	6.8	62.5	1,650			
	27-May-98	5.40		-0.69	32.00	70.40	70	6.89	64.2	4,830		,	
	1-Oct-98	5.42		-0.71	31.45	67.68	>68	7.65	65.6	4,290	griren		
	22-Dec-98			-0.69	31.45	67.73	>68	7.21	57.7	3,920	/ 0.30	67.3)

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	nents			Casing
		Water (a)	Elevation	Elevation	of Well (a)	Purge Volume (b)	Volume		Temp.	\$C	DO	Redox	Diamete
Well	Date	(feet)	(feet)	(feet)	(feet)	(gallons)	(gallons)	рΗ	(°F)	(µ\$/cm)	(mg/L)	(mv)	(inches)
MW-6	12-Sep-94	6.56	5.37	-1.19	24.85	47.55	41 (d)	(e)	71.2	12,970			4
	22-Nov-94	6.04		-0.67	24.88	48.98	50	6.70	66.4	>2,000			
	21-Feb-95	NS		NS	NS	NS	NS	NS	NS	NS			
	23-May-95	5.32		0.05	24.70	NS	NS	NS	NS	NS			
	16-Aug-95	5.97		-0.60	24.70	NS	NS	NS	NS	NS			
	21-Nov-95	6.78		-1.41	24.70	NS	NS	NS	NS	NS			
	13-Feb-96	5.14		0.23	24.71	NS	'ns	NS	NS	NS			
	13-May-96	5.64		-0.27	NM	NS	NS	NS	NS	NS			
	28-Aug-96	6.15		-0.78	24.67	NS	NS	NS	NS	NS			
	21-Nov-96	5.71		-0.34	24.65	NS	NS	NS	NS	NS			
	20-Feb-97	5.38		-0.01	24.79	NS	NS	NS	NS	NS			
	28-May-97	5.93		-0.56	NM	NS	NS	NS	NS	NS			
	19-Sep-97	6.15		-0.78	24.76	NS	NS	NS	NS	NS			
	17-Nov-97	6.06		-0.69	27.71	NS	NS	NS	NS	NS			
	27-Feb-98	4.74		0.63	24.64	NS	NS	NS	NS	· NS			
	27-May-98	5.40		-0.03	29	NS	NS	NS	NS	NS			
	1-Oct-98	6.37		-1.00	24.72	NS	NS	NS	NS	NS			
	22-Dec-98	6.06		-0.69	24.70	NS	NS	NS	NS	NS	5.4	202	

BG ligh lucks or

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	ments		-	Casing
Well	Date	Water (a) (feet)	Elevation (feet)	Elevation (feet)	of Well (a) (feet)	Purge Volume (b) (gallons)	Volume (gallons)	рН	Temp. (°F)	SC (µS/cm)	DO (mg/L)	Redox (mv)	Diameter (inches)
MW-7	12-Sep-94	6.16	5,38	-0.78	28.51	58.08	60	6.65	73.5	7,920			4
	23-Nov-94	5.61		-0.23	28.46	59.40	60	6.00	64.6	>2,000			
	21-Feb-95	5,25		0.13	28.30	45.64	46	7.46	69.5	910			
	23-May-95	5,10		0.28	28.30	45.24	46	7.21	65.0	5,740			
	16-Aug-95	5.42		-0.04	28.30	45.76	46	7.36	66.8	5,560			
	21-Nov-95	6.28		-0.90	28.30	42.99	44	7.29	65.9	5,650			
	13-Feb-96	4.64		0.74	28.39	61.75	>62	7	70.1	7,050			
	13-May-96	5.36		0.02	NM	59.88 (f)	>60	6.5	76.6	15,030			
	28-Aug-96			-0.82	28.30	57.46	>58	7.4	76.4	3,980			
	21-Nov-96			-0.74	28.30	57.66	>58	6.5	75.2	8,400			
	20-Feb-97	5,70		-0.32	28.46	59.17	>60	6.5	63.9	4,410			
	28-May-97	5.46		-0.08	NM	59.80 (f)	>60	7.5	71.3	9,790			
	19-Sep-97			-0.53	28.49	58.7 2	>59	7.3	71.4	4,910			
	17-Nov-97			-0.21	23.39	46.28	>47	6.97	71.0	6,410			
	27-Feb-98	4.68		0.70	23.40	74.63	>75	6.80	64.0	7,070			
	27-May-98			0.21	30.00	66,00	65	6.89	63.0	4,980			
	1-Oct-98			-0.42	30.00	62.92	>63	7.58	64.1	4,000			
	22-Dec-98			-0.40	30.00	62.97	>63	7.07	64.2	4,210	NM	NM	

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

·		Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	ments			Casing
Well	Date	Water (a) (feet)	Elevation (feet)	Elevation (feet)	of Well (a) (feet)	Purge Volume (b) (gallons)	Volume (gallons)	рН	Temp. (°F)	SC (µS/cm)	DO (mg/L)	Redox (mv)	Diamete (inches)
MW-8	12-Sep-94	6.46	5,44	-1.02	25,15	48.56	55	(e)	(e)	11,400			4
	23-Nov-94	6.01		-0.57	25.66	78.60	75	5.60	61.5	>2,000			
	21-Feb-95	NS		NS	NS	NS	NS	NS	NS	NS			
	23-May-95	5.53		-0.09	2 5.40	NS	NS	NS	NS	NS			
	16-Aug-95	5.68		-0.24	25.40	NS	NS	NS	NS	NS			
	21-Nov-95	6.37		-0.93	2 5.40	NS	NS	NS	NS	NS			
	13-Feb-96	5.36		0.08	25.54	NS	NS	NS	NS	NS			
	13-May-96	5.62		-0.18	NM	NS	NS NS	NS	NS	NS			
	28-Aug-96	6.17		-0.73	25.52	NS	NS	NS	NS	NS			
	21-Nov-96	5.74		-0.30	25.45	51.24	>52	6.5	73.6	9,300			
	20-Feb-97	5.10		0.34	25.54	53.14	>54	6.5	61.5	4,950			
	28-May-97	5.68		-0.24	NM	51.63 (f)	>54	7.5	71.2	14,930			
	19-Sep-97	5.95		-0.51	25.41	50.60	>51	7.0	67.8	7,860			
	17-Nov-97	5.91		-0.47	25.59	51.17	>52	7.49	70.2	8,320			
	27-Feb-98	4.50		0.94	25.58	54.80	>55	7.00	63.8	6,310			
	27-May-98	6.10		-0.66	31.00	65.00	65	7.19	63.9	6,460			
	1-Oa-98	6.13		-0.69	25.50	50.36	>51	7.74	63.7	6,880			
	22-Dec-98	6.10		-0.66	31.00	NS	NS	NS	NS	NS	0.30	123	

Notes appear on the following page.

Bc?

ARCADIS GERAGHTY&MILLER

Table 1: Summary of Field Sampling, Depth-to-Water, and Casing Elevation Data

Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

	<u></u>	Depth to	Top of Casing	Top of Water	Measured Depth	Calculated	Actual Purge	Field	Measurer	nents			Casing
Well	Date	Water (a) (feet)	Elevation (feet)	Elevation (feet)	of Well (a) (feet)	Purge Volume (b) (gallons)	Volume (gallons)	рН	Temp. (*F)	SC (µS/cm)	DO (mg/L)	Redox (mv)	Diameter (inches)
(a) (b) (c) (d) (e) (f)	Well went dry d No reading - ins	asing volume ns resurveyed uring purging trument malf	es. d to site benchmar g. function.		, 1993. nts from previous qu	arter.							
SC (µS/cm) (mg/L) (mv) NM NS	Specific Conduct Microsiemens p milligrams per li millivolt Not measured	er centimeter iter	r ed during this qua	rterly event									

All elevations are measured relative to a site benchmark (elevation 6.62') based on the City of Oakland datum which is 3 feet higher than mean sea level.

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (µg/L)	TPH Diesel (a) (µg/L)	Benzene (b) (μg/L)	Toluene (b) (µg/L)	Ethylbenzene (b) (µg/L)	Xytenes (b) (μg/L)	MTBE (b) (µg/L)	Total Dissolved Solids (c) (mg/L)
MW-1	2-Oct-90	170	2,900	20 -	18	1.9	5.7		
	28-Feb-91	260	550	43	. 1	7	1		
	25-Mar-91	73	160	10	ND(<0.3)	0.5	ND(<0.3)		
	1-May-91	ND(<50)	(d)	2.2	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	5-Aug-91	310	330	22	5.5	9.5	23		
	23-Oct-91	440	1,800	23	21	6.2	35		
	6-Jan-92	430	1,600	56	8.4	18	22		
	20-Jul-92	ND(<50)	25,000	0.4	8.0	1	2.1		
	23-Oct-92	280	6,500	9.3	13	8.2	15		
	4-Feb-93	68 (f)	320	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	8-Apr-93	180	7,800	0.5	2.1	8,0	13		
	6-Aug-93	740	17,000	75	100	25	130		3,500
	28-Oct-93	140	7,600	4.7	1.9	3.2	5.4		3,500
	1-Feb-94	430	10,000	8.2	1.1	3.5	4.8		3,800
	12-Sep-94	230	22,000	0.7	1.7	2.0	3.7		4,000
	23-Nov-94	ND(<50)	1,700	ND(<0.5)	ND(<0.5)	ND(<0.5)	0.6		3,600
	21-Feb-95	ND(<50)	4,200	ND(<0.5)	ND(<0.5)	0.8	0.6		4,200
	23-May-95	ND(<50)	300	ND(<0.5)	ND(<0.5)	2.1	2.0		3,800
	16-Aug-95	ND(<50)	740	ND(<0.5)	ND(<0.5)	1.4	1.4		3,800
	21-Nov-95	ND(<50)	410	ND(<0.5)	ND(<0.5)	0.7	0.8		4,100
	13-Feb-96	ND(<50)	400	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,600
	13-May-96	310 (k)	12,000	13	14	2.4	11		3,500
	28-Aug-96	11,000 (k)	56,000	110	ND(<50)	ND(<50)	ND(<50)		3,300
	21-Nov-96	65 (k)	1,500	3.3	0.51	0.59	0.84		3,400
	20-Feb-97	2,900 (k)	200,000	260	61	42	96		1,400
	28-May-97	2,100	28,000 (o)	230	42	55	110		3,100
	19-Sep-97	110,000	2,700,000	230	140	250	700	ND (<500)	3,200
	17-Nov-97	40,000 (r)	950,000 (r)	240 (r)	190 (r)	270 (r)	880 (r)	ND (<300) (r)	3,400
	27-Feb-98	380,000	1,200,000	50	50	200	800	ND (<500)	3,600
	29-May-98	13,000	280,000	110	13	66	390	ND (<50)	
	1-Oct-98	1,300 (t)	63,000	43	1.2	15	84	ND (<10)	
	22-Dec-98	2,000 (y,z)	79,000 (y,aa)	32 (y)	ND(<5.0) (y)	23 (y)	130 (y)	ND(<50) (y)	

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

MW-2 2-Oet-90 ND(<50) 80 0.4 ND(<0.3) ND(<0.3) 0.5 28-Feb-91 ND(<50) ND(<50) ND(<0.3) ND(<0.5) ND	Well	Date	TPH Gasoline (a) (μg/L)	TPH Dieset (a) (μg/L)	Benzene (b)	Toluene (b) (μg/L)	Ethylbenzene (b) (µg/L)	Xylenes (b) (μg/L)	MTBE (b) (µg/L)	Total Dissolved Solids (c) (mg/L)
28-Feb-91 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<	MW-2	2-Oct-90	ND(<50)	80	0.4	ND(<0,3)	ND(<0.3)	0.5		
25.Mar-91 ND(<50) ND(<50) ND(<50) ND(<0.3)				ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
1-May-91 ND(<50) (d) ND(<0.3) ND(<0.4) ND(<0.5)		25-Mar-91			ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		~ -
5-Aug-91 ND(<50) ND(<50) ND(<0.3) ND(<0.5) ND(<0				(d)		ND(<0.3)	ND(<0.3)	ND(<0.3)		
23-Oct-91 ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) 6.Jan-92 11,000 1200 (e) ND(<0.3) 83 82 940 20-Jul-92 73 120 1.7 3.3 1.1 9.6 23-Oct-92 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) 0.5 4.Feb-93 ND(<50) 330 (e) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) 8.Apr-93 150 74 (h) 1 1 2.1 1 13 6.Aug-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 990 28-Oct-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) ND(<0.9) 1.Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 1.2-sep-94 ND(<50) ND(<50) ND(<0.5)		•			ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
6-Jan-92 11,000 1200 (e) ND(<0.3) 83 82 940 20-Jul-92 73 120 1.7 3.3 1.1 9.6 23-Oct-92 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) 0.5 4-Feb-93 ND(<50) 330 (e) ND(<0.3) ND(<0.4) ND(<0.5) ND(_	, ,	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
20-Jul-92 73 120 1.7 3.3 1.1 9.6 23-Oct-92 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) 0.5 4.Feb-93 ND(<50) 330 (e) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) 8.Apr-93 150 74 (h) 1 2.1 1 13 6.Aug-93 ND(<50) ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) ND(<0.9) 990 28-Oct-93 ND(<50) ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) ND(<0.9) 1.Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-96 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-96 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-96 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-96 ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-96 ND(<50) 1.500 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1.Feb-96 ND(<50) 1.500 ND(<0.5) ND		6-Jan-92		1200 (e)	ND(<0.3)	83	82	940		 .
4-Feb-93 ND(<50) 330 (e) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) 8-Apr-93 150 74 (h) 1 2.1 1 1 13 6-Aug-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 990 28-Oet-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 1,500 1-Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.3) ND(<0.5) ND(<0.		20-Jul-92		120	1.7	3.3	1.1	9.6		
4-Feh-93 ND(<50) 330 (e) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) 8-Apr-93 150 74 (h) 1 2.1 1 13 6-Aug-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 990 28-Oct-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 1,500 1-Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 1,500 1-Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 2,000 12-Sep-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 2,100 22-Nov-94 ND(<50) 51 (h) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 2,400 21-Feb-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 5,700 23-May-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 5,400 16-Aug-95 ND(<50) 190 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,400 13-Feb-96 ND(<50) 1,500 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-Feb-96 ND(<50) 25,000 (l) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1,100 13-May-96 ND(<50) 1,800 (l) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 1,100 28-Aug-96 ND(<50) 1,800 (l) ND(<0.5) N		23-Oct-92	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	0.5		
6-Aug-93 ND(<50) ND(<50) ND(<3.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 990 28-Oct-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 1,500 1.Feb-94 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5		4-Feh-93			ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
6-Aug-93 ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 990 28-Oct-93 ND(<50) ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.5) ND					1	2.1	1	13		
28-Oct-93 ND(<50) ND(<50) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.3) ND(<0.9) 1,500 1-Feb-94 ND(<50) ND(<50) ND(<0.5)			ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)		990
1-Feb-94 ND(<50) ND(<50) ND(<0.5) ND(<		_		ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)		1,500
22-Nov-94 ND(<50) 51 (h) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,700 21-Feb-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,700 23-May-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,100 16-Aug-95 ND(<50) 190 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,400 21-Nov-95 ND(<50) 180 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-Feb-96 ND(<50) 1,500 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-May-96 ND(<50) 25,000 (l) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,400 21-Nov-96 ND(<50) 680 ND(<0.5) N		1-Feb-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		
21-Feb-95 ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,700 23-May-95 ND(<50) ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,100 16-Aug-95 ND(<50) 190 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,400 21-Nov-95 ND(<50) 180 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-Feb-96 ND(<50) 1,500 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-May-96 ND(<50) 25,000 (1) ND(<0.5) ND(<0		12-Sep-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		
23-May-95 ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) SQ.00.5 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) SQ.00.5 SQ		22-Nov-94	ND(<50)	51 (h)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,400
23-May-95 ND(<50) ND(<50) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,100 16-Aug-95 ND(<50) 190 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,400 21-Nov-95 ND(<50) 180 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-Feb-96 ND(<50) 1,500 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) S,800 13-May-96 ND(<50) 25,000 (I) ND(<0.5) ND(<0.50) ND(<0.5		21-Feb-95	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		5,700
21-Nov-95 ND(<50) 180 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 5,800 13-Feb-96 ND(<50) 1,500 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 8.7 1,100 13-May-96 ND(<50) 25,000 (l) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 150 28-Aug-96 ND(<50) 680 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 120 21-Nov-96 ND(<50) 1,800 (n) ND(<0.5) ND(23-May-95	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		5,100
13-Feb-96 ND(<50) 1,500 ND(<0.5) ND(<0.50) ND(<0.5) ND(16-Aug-95	ND(<50)	190	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		5,400
13-May-96 ND(<50) 25,000 (l) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) 150 28-Aug-96 ND(<50) 680 ND(<0.5) ND(<0.50) ND(<0.5) ND		21-Nov-95	ND(<50)	180	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		
13-May-96 ND(<50) 25,000 (l) ND(<0.5) ND(<0.50) ND(<0.		13-Feb-96	ND(<50)	1,500	ND(<0.5)	ND(<0.5)	ND(<0.5)	8.7		1,100
28-Aug-96 ND(<50) 680 ND(<0.5) ND(<0.50) ND(<0.50) <t< td=""><td></td><td>13-May-96</td><td></td><td>25,000 (1)</td><td>ND(<0.5)</td><td>ND(<0.5)</td><td>ND(<0.5)</td><td>ND(<0.5)</td><td></td><td>150</td></t<>		13-May-96		25,000 (1)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		150
$\begin{array}{cccccccccccccccccccccccccccccccccccc$		•		680	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		410
28-May-97 ND(<50) 3,700 (n) (o) ND(<0.50) ND(<0.50) ND(<0.50) ND(<0.50) ND(<0.50) ND(<0.50) S30 19-Sep-97 ND(<50) 4,100 ND(<0.5)		-	ND(<50)	1,800 (n)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		720
28-May-97 ND(<50) 3,700 (n) (o) ND(<0.50) ND(<0.5) ND(<0.		20-Feb-97	ND(<50)	1,000 (n)	ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<0.50)		1,400
19-Sep-97 ND(<50) 4,100 ND(<0.5) ND(<0.5) ND(<0.5) ND(<2) ND(<5) 1,200 17-Nov-97 ND(<50) 1,300 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<2) ND(<5) 340 27-Feb-98 ND(<50) 340 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<2) ND(<5) 210 27-May-98 ND(<50) 1,300 ND(<0.5) ND(<0.5) ND(<0.5) ND(<0.5) ND(<2) ND(<5) 1-Oct-98 3,200 (t) 3,500 (v) ND(<1.0) ND(<1.0) ND(<1.0) ND(<1.0) ND(<1.0) ND(<1.0)		28-May-97			ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<0.50)		830
17-Nov-97 ND(<50) 1,300 ND(<0.5) ND(<0.5) ND(<0.5) ND(<2) ND(<5) 340 27-Feb-98 ND(<50) 340 ND(<0.5) 0.9 ND(<0.5) ND(<2) ND(<5) 210 27-May-98 ND(<50) 1,300 ND(<0.5) ND(<0.5) ND(<0.5) ND(<2) ND(<5) 1-Oct-98 3,200 (t) 3,500 (v) ND(<1.0) ND(<1.0) ND(<1.0) ND(<1.0) ND(<1.0) ND(<2) ND(<10)		-	ND(<50)	4,100	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	1,200
27-Feb-98 ND(<50) 340 ND(<0.5) 0.9 ND(<0.5) ND(<2) ND(<5) 210 27-May-98 ND(<50)		-		1,300	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)		340
1-Oct-98 3,200 (t) 3,500 (v) ND(<1.0) ND(<1.0) ND(<1.0) ND(<2) ND(<10)		27-Feb-98		340	ND(<0.5)	0.9	ND(<0.5)	ND(<2)		210
1-Oct-98 3,200 (t) 3,500 (v) ND(<1.0) ND(<1.0) ND(<1.0) ND(<2) ND(<10)		27-May-98	ND(<50)	1,300	ND(<0.5)	ND(<0.5)	ND(<0.5)		ND(<5)	
			3,200 (t)	3,500 (v)	ND(<1.0)	ND(<1.0)	ND(<1.0)	ND(<2)	ND(<10)	
		22-Dec-98	67 (t)	1,200 (ab)	ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<1)	ND(<5)	

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling
Former Penske Truck Leasing Facility,
725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (μg/L)	TPH Diesel (a) (µg/L)	Benzene (b) (µg/L)	Toluene (b) (μg/L)	Ethylbenzene (b) (μg/L)	Xylenes (b) (μg/L)	MTBE (b) (µg/L)	Total Dissolved Solids (c) (mg/L)
MW-3	2-Oct-90	ND(<50)	90	28	3.1	0.6	1.5		
	28-Feb-91	ND(<50)	ND(<50)	6	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	25-Mar-91	ND(<50)	ND(<50)	0.6	ND(<0.3)	ND(<0.3)	ND(<0.3)		 .
	1-May-91	ND(<50)	(d)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	5-Aug-91	ND(<50)	ND(<50)	1.7	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	23-Oct-91	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	6-Jan-92	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	20-Jul-92	66	ND(<50)	1.1	2.2	0.7	6.4		
	23-Oct-92	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	4-Feb-93	270	ND(<100)(g)	9.8	4.6	4.5 '	8.7		
	8-Apr-93	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)		
	6-Aug-93	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)	•	3,400
	28-Oct-93	ND(<50)	ND(<50)	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)		2,700
	1-Feb-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,400
	12-Sep-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,500
	22-Nov-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,400
	21-Feb-95	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		4,200
	23-May-95	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		4,100
	16-Aug-95	ND(<50)	240	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		4,100
	21-Nov-95	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		4,200
	13-Feb-96	ND(<50)	72	16	ND(<0.5)	ND(<0.5)	0.73		3,400
	13-May-96	ND(<50)	250 (m)	1.7	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,700
	28-Aug-96	ND(<50)	1,200	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,200
	21-Nov-96	ND(<50)	ND(<50)	0.82	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,500
	20-Feb-97	ND(<50)	140 (n)	ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<0.50)		2,900
	28-May-97	ND(<50)	240 (n) (o)	ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<0.50)		1,900
	19-Sep-97	ND(<50)	ND(<50)	0.7	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	3,300
	17-Nov-97	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	3,400
	27-Feb-98	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	3,800
	27-May-98	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	
	1-Oct-98	ND(<50)	56 (w)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<1)	ND(<5)	
	22-Dec-98	NS	NS	NS	NS	NS	NS	NS	

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (μg/L)	TPH Diesel (a) (μg/L)	Benzene (b) (µg/L)	Toluene (b)	Ethylbenzene (b) (μg/L)	Xylenes (b) (μg/L)	MTBE (b)	Total Dissolved Solids (c) (mg/L)
MW-4	4-Feb-93	58 (f)	450	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	8-Apr-93	74	220	19	0.4	ND(<0.3)	ND(<0.9)		• •
	6-Aug-93	95	ND(<50)	68	0.9	1.1	ND(<0.9)		5,800
	28-Oct-93	160	600	46	0.7	1.6	1.2		5,200
	1-Feb-94	320	160	290	0.6	6.7	3.2		6,200
	12-Sep-94	390	95	120	3.9	14	14		6,000
	23-Nov-94	100	1,800	9.9	0.7	1.6	3.8		5,600
	21-Feb-95	91	680	23	ND(<0.5)	1.0	ND(<0.5)		7,100
	23-May-95	ND(<50)	270	5.3	ND(<0.5)	ND(<0.5)	ND(<0.5)		8,300
	16-Aug-95	ND(<50)	610	4.1	ND(<0.5)	ND(<0:5)	ND(<0.5)	•	7,100
	21-Nov-95	ND(<50)	280	1.0	ND(<0.5)	ND(<0.5)	ND(<0.5)		9,800
	13-Feb-96	980 (i)	7,500	570	ND(<0.5)	9.2	13		3,600
	13-May-96	150 (k)	1,200	45	ND(<1.0)	ND(<1.0)	1.5		7,900
	28-Aug-96	70,000 (k)	1,300,000	340	ND(<200)	ND(<200)	ND(<200)		1,800
	21-Nov-96	52,000 (i)	40,000	130	ND(<100)	ND(<100)	ND(<100)		5,400
	20-Feb-97	64,000 (i)	470,000	ND(<100)	ND(<100)	ND(<100)	ND(<100)		1,500
	28-May-97	11,000 (i)	1,000,000 (a)	ND(<100)	ND(<100)	ND(<100)	ND(<100)		1,700
	19-Sep-97	37,000	2,600,000	260	ND(<30)	ND(<30)	ND(<100)	ND(<300)	2,700
	17-Nov-97	4,400 (r)	57,000 (r)	25 (r)	$ND(\leq 5)(r)$	ND(<5) (r)	ND(<20) (r)	ND(<50) (r)	7,900
	27-Feb-98	580	9,300	2.7	0.8	0.8	3	ND(<50)	9,700
	29-May-98	3,900	11,000	1.4	0.6	ND(<0.5)	ND(<2)	ND(<5)	
	1-Oct-98	2,400 (u)	670,000	5.7	ND(<2.0)	ND(<10)	4.6	ND(<10)	
	22-Dec-98	ND(<250) (y)	3,700 (y,ac)	ND(<2.5) (y)	ND(<2.5) (y)	ND(<2.5) (y)	ND(<5) (y)	ND(<25) (y)	

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling
Former Penske Truck Leasing Facility,
725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (μg/L)	TPH Diesel (a) (μg/L)	Benzene (b) (µg/L)	Toluene (b) (μg/L)	Ethylbenzene (b) (µg/L)	Xylenes (b) (μg/L)	MTBE (b) (μg/L)	Total Dissolved Solids (c) (mg/L)
MW-5	4-Feb-93	ND(<50)	240	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.3)		
	8-Apr-93	ND(<50)	480	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)		
	6-Aug-93	ND(<50)	120	0.8	ND(<0.3)	ND(<0.3)	ND(<0.9)		2,800
	28-Oct-93	ND(<50)	370	ND(<0.3)	ND(<0.3)	ND(<0.3)	ND(<0.9)		2,400
	1-Feb-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,500
	12-Sep-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,600
	22-Nov-94	ND(<50)	160	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,600
	21-Feb-95	ND(<50)	170	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,800
	23-May-95	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		4,100
	16-Aug-95	ND(<50)	590	ND(<0.5)	ND(<0.5)	ND(<0!5)	ND(<0.5)		2,800
	21-Nov-95	ND(<50)	500	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,800
	13-Feb-96	ND(<50)	830	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,000
	13-May-96	ND(<50)	870	0.59	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,700
	28-Aug-96	ND(<50)	1,000	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,000
	21-Nov-96	ND(<50)	610	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		2,700
	20-Feb-97	ND(<50)	1,100 (n)	ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<0.50)		1,300
	28-May-97	60 (i)	560 (p) (o)	ND(<0.50)	ND(<0.50)	ND(<0.50)	ND(<0.50)		2,500
	19-Sep-97	70	1,000	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	2,400
	17-Nov-97	70	1,100	0.6	0.7	0.5	ND(<2)	5	2,800
	27-Feb-98	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	5	330
	29-May-98	ND(<50)	770	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	
	1-Oct-98	ND(<50)	630	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<1.0)	ND(<5.0)	
	22-Dec-98	ND(<50)	890 (ab)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<1.0)	ND(<5.0)	

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (μg/L)	TPH Diesel (a) (μg/L)	Benzene (b)	Toluene (b) (μg/L)	Ethylbenzene (b) (μg/L)	Xylenes (b) (μg/L)	MTBE (b) (μg/L)	Total Dissolved Solids (c) (mg/L)
MW-6	12-Sep-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		560
	22-Nov-94	ND(<50)	ND(<50)	ND(<0.5)	ND(<0.5)	ND(<0.5)	1.5		1,800
	21-Feb-95	NS	NS	NS	NS	NS	NS		NS
	23-May-95	NS	NS	NS	NS	NS	NS		NS
	16-Aug-95	NS	NS	NS	NS	NS	NS		NS
	21-Nov-95	NS	NS	NS	NS	NS	NS		NS
	13-Feb-96	NS	NS	NS	NS	NS	NS		NS
	13-May-96	NS	NS	NS	NS	NS	NS		NS
•	28-Aug-96	NS	NS	NS	NS	NS	NS		NS
	21-Nov-96	NS	NS	NS	NS	NS '	NS		NS
	20-Feb-97	NS	NS	NS	NS	NS	NS		NS
	28-May-97	NS	NS	NS	NS	NS	NS		NS
	19-Sep-97	NS	NS	NS	NS	NS	NS	NS	NS
	17-Nov-97	NS	NS	NS	NS	NS	NS	NS	NS
	27-Feb-98	NS	NS	NS	NS	NS	NS	NS	NS
	29-May-98	NS	NS	NS	NS	NS	NS	NS	••
	1-Oct-98	NS	NS	NS	NS	NS	NS	NS	
	22-Dec-98	NS	NS	NS	NS	NS	NS	NS	- ~

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (μg/L)	TPH Diesel (a) (µg/L)	Benzene (b)	Toluene (b) (μg/L)	Ethylbenzene (b) (µg/L)	Xylenes (b) (μg/L)	MTBE (b) (μg/L)	Total Dissolved Solids (c) (mg/L)
MW-7	12-Sep-94	160	620	2.7	1.3	ND(<0.5)	2.1		1,100
	23-Nov-94	ND(<50)	150	2.4	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,600
	21-Feb-95	93	1,400	0.6	0.8	0.8	3.3		4,000
	23-May-95	ND(<50)	360	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,400
	16-Aug-95	53	1,100	0,5	ND(<0.5)	ND(<0.5)	0.5		4,000
	21-Nov-95	87	9,100	1.4	ND(<0.5)	1.0	1.5		4,200
	13-Feb-96	1,800,000 (j)	5,000,000	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<0.5)		3,900
	13-May-96	ND(<50,000)	2,300,000	ND(<500)	ND(<500)	ND(<500)	500 (i)		3,500
	28-Aug-96	59,000 (k)	640,000	ND(<200)	ND(<200)	ND(<200)	600		3,100
	21-Nov-96	3,800 (k)	780,000	130	93	33*	64		3,400
	20-Feb-97	15,000 (i)	1,500,000	81	51	ND(<50)	ND(<50)		3,300
	28-May-97	390,000 (i)	440,000 (o)	ND(<1000)	ND(<1000)	ND(<1000)	ND(<1000)		3,500
	19-Sep-97	3,600	910,000	110	64	37	ND(<100)	ND(<300)	3,200
	17-Nov-97	15,000 (r)	18,000,000 (r)	110 (r)	41 (r)	12 (r)	110 (r)	ND(<50) (r)	3,300
	27-Feb-98	45,000	290,000	80	60	ND(<50)	ND(<200)	ND(<500)	3,300
	29-May-98	140	1,600	2.3	0.9	0.9	3	ND(<5)	
	1-Oct-98	710 (u)	89,000	39	2.4	11	31	ND(<10)	
	22-Dec-98	3,900 (z)	240,000 (ac)	51	ND(<25)	ND(<25)	ND(<50)	ND(<250)	

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

Well	Date	TPH Gasoline (a) (μg/L)	TPH Diesel (a) (μg/L)	Benzene (b)	Toluene (b) (µg/L)	Ethylbenzene (b) (µg/L)	Xylenes (b) (μg/L)	MTBE (b) (µg/L)	Total Dissolved Solids (c) (mg/L)
MW-8	12-Sep-94	170	850	2.7	0.5	ND(<0.5)	. 2		5,500
	23-Nov-94	ND(<50)	570	1.5	ND(<0.5)	ND(<0.5)	ND(<0.5)		6,300
	21-Feb-95	NS	NS	NS	NS	NS	NS		NS
	23-May-95	NS	NS	NS	NS	NS	NS		NS
	16-Aug-95	NS	NS	NS	NS	NS	NS		NS
	21-Nov-95	NS	NS	NS	NS	NS	NS		NS
	13-Feb-96	NS	NS	NS	NS	NS	NS		NS
	13-May-96	NS	NS	NS	NS	NS	NS		NS
	28-Aug-96	NS	NS	NS	NS	NS	NS		NS
	21-Nov-96	400 (k)	2,200	4.6	37	4.6	68		5,100
	20-Feb-97	340 (k)	2,500	2.1	53	7.1	94		3,800
	28-May-97	480 (k)	200 (q) (o)	2.5	12	ND(<2.5)	76		4,100
	19-Sep-97	1,000	7,000	0.8	5.0	0.5	130	ND(<5)	5,000
	17-Nov-97	250	520	1.4	2.1	0.7	3	ND(<5)	4,600
	27-Feb-98	ND(<50)	150	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	3,500
	29-May-98	ND(<50)	70	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<2)	ND(<5)	
	1-Oct-98	ND(<50)	440 (x)	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<1)	ND(<5)	
	22-Dec-98	NS	NS	NS	NS	NS	NS	NS	
TB-LB	22-Dec-98	ND(<50)	NA	ND(<0.5)	ND(<0.5)	ND(<0.5)	ND(<1)	ND(<5.0)	NA

Notes appear on the following page.

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

		enske truck Leasin	~						
Well	725 Julie	Ann Way, Oakland TPH Gasoline (a) (µg/L)	I, California. TPH Diesel (α) (μg/L)	Benzène (b) (µg/L)	Tolucne (b) (µg/L)	Ethylbenzene (b) (µg/L)	Xylenes (b) (μg/L)	MTBE (b) (µg/L)	Total Dissolved Solids (c) (mg/L)
(a)	Analyzed by l	USEPA Method 8015, modific	d .						
(b)	Analyzed by I	USEPA Method 8020.							
(c)	Analyzed by l	USEPA Method 160.1.							
(d)	No results - s	ample for TPH as diesel not co	llected.						
(c)	Diesel range	concentration reported. A non	standard diesel pattern w	as observed in the					
	chromatogran	n.							
(f)	Does not mat	ch typical gasoline pattern. Pat	ttern of peaks observed in	n the chromatograms	ı				
	is indicative o	f hydrocarbons heavier than ga	soline.						
(g)		it increased due to insufficient	=					,	
(h)		concentration reported. The ch			diesel range.	l l			
(i)	Laboratory re	ports that chromatogram indica	ates unidentified hydroca	rbons >C8.					
(i)		ports that chromatogram indica							
(k)		ports that chromatogram indica							
(l)		ports that chromatogram indica			16.				
(m)		ports that chromatogram indica							
(n)		ports that chromatogram indica							
(0)		ports that the laboratory contro				yzed on 6/3/97.			
		ould be considered as estimated							
(p)		ports that chromatogram indica							
(q)		ports that chromatogram indica							
(1)		ports reporting limits for diese							
(a)		eports analysis was performed o							
(t)		ports the peak pattern present							
	n-C09 to gre	eater than n-C12. Quantitation i	is based on a gasoline ref	ference in the range of	of n-C07 to n-C12 o	nly.			

n-C09 to greater than n-C12. Quantitation is based on a gasoline reference in the range of n-C07 to n-C12 only.

(u) Laboratory reports the peak pattern present in this sample represents an unknown mixture atypical of gasoline in the range of

 Laboratory reports the peak pattern present in this sample represents an unknown mixture atypical of gasoline in the range of n-C07 to greater than n-C12. Quantitation is based on a gasoline reference in the range of n-C07 to n-C12 only.

(v) Laboratory reports the hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C08 to n-C40. Quantitation is based on a diesel reference between n-C10 and n-C24 only.

(w) Laboratory reports the hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C12 to n-C28.

Quantitation is based on a diesel reference between n-C10 and n-C24 only.

(x) Laboratory reports the hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C10 to n-C28.

Quantitation is based on a diesel reference between n-C10 and n-C24 only.

Notes continue on the following page.

Total Dissalved

ARCADIS GERAGHTY&MILLER

Table 2: Summary of Groundwater Analytical Results - Monthly and Quarterly Sampling Former Penske Truck Leasing Facility, 725 Julie Ann Way, Oakland, California.

									10 010 0100
Well	Date	TPH Gasoline (a)	TPH Diesel (a)	Benzene (b)	Toluene (b)	Ethylbenzene (b)	Xylenes (b)	MTBE (b)	Solids (c)
		(μg/L)	(μg/L)	(µg/L)	(µg/L)	(µg/L)	(μg/L)	(µg/L)	(mg/L)

- (y) Laboratory reports reporting limit(s) raised due to high level of analyte present in sample.
- (z) Laboratory reports the peak pattern present in this sample represents an unknown mixture atypical of gasoline in the range of n-C10 to greater than n-C12. Quantitation is based on a gasoline reference in the range of n-C07 to n-C12 only.
- (aa) Laboratory reports the hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C09 to n-C36.


 Ouantitation is based on a diesel reference between n-C10 and n-C24 only.
- (ab) Laboratory reports the hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C10 to n-C40.

 Quantitation is based on a diesel reference between n-C10 and n-C24 only.
- (ac) Laboratory reports the hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C10 to n-C26. Quantitation is based on a diesel reference between n-C10 and n-C24 only.
- () Reported detection limit
- Not analyzed
- ND Not detected
- μg/L Micrograms per liter
- mg/L Milligrams per liter
 - NS Well not sampled or monitored during this quarterly event.

Analysis prior to May 28, 1997 by Sequoia Analytical, Walnut Creek, California.

Analysis after May 28, 1997 by American Environmental Netwark (AEN), Pleasant Hill, California.

Analysis beginning October 1, 1998 by Quanterra Incorporated, West Sacramento, California.



7000 FEET 1 KILOMETER 0

CONTOUR INTERVAL 20 FEET



Reference: U.S.G.S. 7-minute Quadrangle, Oakland East, California, revised, Photorevised 1980.





SITE LOCATION MAP


Former Penske Truck Leasing Co. Facility 725 Julie Ann Way Oakland, California

RC000019.0000

FIGURE







ATTACHMENT 1

COPIES OF CERTIFIED LABORATORY REPORTS

AND CHAIN-OF-CUSTODY DOCUMENTATION



Quanterra Incorporated 880 Riverside Parkway West Sacramento, California 95605

916 373-5600 Telephone 916 372-1059 Fax

January 19, 1999

QUANTERRA INCORPORATED PROJECT NUMBER: 303382

PO/CONTRACT: RC000019.0010

Paul Hehn ARCADIS Geraghty & Miller, Inc. 1050 Marina Way South Richmond, CA 94804

Dear Mr. Hehn,

This report contains the analytical results for the six samples received under chain of custody by Quanterra Incorporated on December 23, 1998. These samples are associated with your Penske Oakland project.

The case narrative is an integral part of this report.

buk

If you have any questions, please feel free to call me at (916)374-4383.

Sincerely,

Calvin Tanaka

Project Manager



TABLE OF CONTENTS

QUANTERRA INCORPORATED PROJECT NUMBER 303382

Case Narrative

Quanterra's Quality Assurance Program

Sample Description Information

Chain of Custody Documentation

Total Petroleum Hydrocarbons - Gas/BTEX - Method 8015

Samples: 1 - 6

Sample Data Sheets Method Blank Reports Laboratory QC Reports

Total Petroleum Hydrocarbons - Diesel - Method 8015

Samples: 1 - 5

Sample Data Sheets Method Blank Reports Laboratory QC Reports



CASE NARRATIVE

QUANTERRA INCORPORATED PROJECT NUMBER 303382

General Comments

The sample containers were received intact and in good condition.

Where applicable, the reporting limits are adjusted to reflect any dilutions.

The method blank and LCS results for this set met the specified QC criteria for acceptance. Where QC criteria were not initially met, corrective actions are documented.

Total Petroleum Hydrocarbons - Gas/BTEX - Method 8015

Sample MW-4 (303382-003) was analyzed at a dilution due to the matrix interferences present.

There were no other anomalies associated with this project.



Quanterra - Western Region Quality Control Definitions

QC Parameter	Definition
QC Batch	A set of up to 20 field samples plus associated laboratory QC samples that are similar in composition (matrix) and that are processed within the same time period with the same reagent and standard lots.
Duplicate Control Sample (DCS)	Consist of a pair of LCSs analyzed within the same QC batch to monitor precision and accuracy independent of sample matrix effects. This QC is performed only if required by client or when insufficient sample is available to perform MS/MSD.
Duplicate Sample (DU)	A second aliquot of an environmental sample, taken from the same sample container when possible, that is processed independently with the first sample aliquot. The results are used to assess the effect of the sample matrix on the precision of the analytical process. The precision estimated using this sample is not necessarily representative of the precision for other samples in the batch.
Laboratory Control Sample (LCS)	A volume of reagent water for aqueous samples or a contaminant-free solid matrix (Ottawa sand) for soil and sediment samples which is spiked with known amounts of representative target analytes and required surrogates. An LCS is carried through the entire analytical process and is used to monitor the accuracy of the analytical process independent of potential matrix effects.
Matrix Spike and Matrix Spike Duplicate (MS/MSD)	A field sample fortified with known quantities of target analytes that are also added to the LCS. Matrix spike duplicate is a second matrix spike sample. MSs/MSDs are carried through the entire analytical process and are used to determine sample matrix effect on accuracy of the measurement system. The accuracy and precision estimated using MS/MSD is only representative of the precision of the sample that was spiked.
Method Blank (MB)	A sample composed of all the reagents (in the same quantities) in reagent water carried through the entire analytical process. The method blank is used to monitor the level of contamination introduced during sample preparation steps.
Surrogate Spike	Organic constituents not expected to be detected in environmental media and are added to every sample and QC at a known concentration. Surrogates are used to determine the efficiency of the sample preparation and the analytical process.

Source: Quanterra® Quality Control Program, Policy QA-003, Rev. 0. 8/19/96.



SAMPLE DESCRIPTION INFORMATION for Geraghty & Miller, Inc.

·		•		Sampled	Received	
	Lab ID	Client ID	Matrix	Date Time	Date	
	303382-0001-SA 303382-0002-SA 303382-0003-SA 303382-0004-SA 303382-0005-SA 303382-0006-TB		AQUEOUS AQUEOUS AQUEOUS AQUEOUS AQUEOUS AQUEOUS	22 DEC 98 22 DEC 98 22 DEC 98 22 DEC 98 22 DEC 98 22 DEC 98	23 DEC 98 23 DEC 98 23 DEC 98 23 DEC 98 23 DEC 98 23 DEC 98	

ARCADIS GERAGHTY&MILLER	Laboratory Task	Order No./F	P.O. No		CH	IAIN-OF	-custo	DY REC	ORD	Page —	<u>/</u> o	f_ <u> </u>
Project Number/Name	000014,00	<u>10</u>				ANALYSIS	/ METHOD	/ SIZE				
Project Location 1605	<u>Le l'UHKU</u>	400			7							
Laboratory_BUAU	TELRA		/	\ \X_{\chi}\	//	/ /	/ /	/	/	/		
Project Manager	VH				\sqrt{g}					•		
Troject Mariager	21			1 1	7x. \							
Sampler(s)/Affiliation $\underline{-\int}$	V !>		W.	6/ Y	`/							
Complete ID/I anaking	Date/Tim		\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \							Remarks		Total
Sample ID/Location MU) -	Matrix Samples	V Fap in	1	7	(f -			4
MW-2	15/10	<i>y</i>	Ī	12								4
MW - 4	1/ 1000	~	1	7		<u> </u>						4
	 		7	1 ×								4.
MW-5			1	7		 						-4
TB-6-B	 		7									2
			1			SAN	PE_	DISSO	WE			
						F	HASE	ONLY	<u> </u>			
Reid												
in apped												
,) ·												
- condition -												
10031	1 14											
iample Matrix: L = Ljqu	id: / s = Solid:	A = Air		-1						Total No. of	Bottles/ ntainers	22
	PAIRO		ration: Af	CANS CIE	CATY + M	MER D	ate A-10	23,98	 Time	1015	Seal Ir	ntacti
Relinquished by Received by	11/2	Organiz Organiz		JES .		D	ate/ 🐊 💪	3198	Time 7	015	Yes No	
Relinquished by	10 4	_	zation: Q	E5		D	ate <u>/ 2_/</u> 6	3198	ب_ Time ہ	1/45	Seal Ir	- 7
Received by:	TX (010)	Organiz	zation:	QE	<u> </u>	D	ate /ak	23148	Time _	3:1 <i>()</i>	Yes N	0 N/
Special Instructions/Remarks								. <u>. </u>	· _			
										- · · · · · · · · · · · · · · · · · · ·		
11		[*					C.	ar 🗐		Sr See	<u> </u>	
delivery Method: L	in reison —	Liconm	on Calin	S1	SPECIFY		Assess Co				SPECIFY	AG 05



Total Petroleum Hydrocarbons -Gas/BTEX - Method 8015



Client Name: Geraghty & Miller, Inc.

Client ID:

MW-1

LAB ID: 303382-0001-SA

AQUEOUS Matrix: Authorized: 23 DEC 98

Prepared: NA

Sampled: 22 DEC 98

Received: 23 DEC 98

Analyzed: 05 JAN 99

Dilution Factor: 10

Parameter	Result	Units	Reporting Limit	Qualifier	
Benzene Toluene Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE)	32 ND 23 130 ND	ug/L ug/L ug/L ug/L ug/L	5.0 5.0 5.0 10 50	. О	
Surrogate	- Recove	ry	Acceptable Range		
a,a,a-Trifluorotoluene	98	%	75 - 124		

Note o = Reporting limit(s) raised due to high level of analyte present in sample.
NA = Not Applicable
ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Client Name:

Geraghty & Miller, Inc.

Client ID:

MW-2

LAB ID: Matrix:

303382-0002-SA

Authorized:

AQUEOUS 23 DEC 98

Sampled: 22 DEC 98

Prepared: NA

Received: 23 DEC 98 Analyzed: 05 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier
Benzene Toluene Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE)	ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.50 0.50 0.50 1.0 5.0	

Surrogate	 Recovery	Acceptable Range
a,a,a-Trifluorotoluene	105 %	75 - 124

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Geraghty & Miller, Inc. Client Name:

Client ID: LAB ID:

MW-4

303382-0003-SA

Matrix: Authorized: AQUEOUS

Sampled: 22 DEC 98

Received: 23 DEC 98

23 DEC 98

Prepared: NA

Analyzed: 04 JAN 99

Dilution Factor: 5.0

Parameter	Result	Units	Reporting Limit	Qualifier	
Benzene Toluene Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE)	ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	2.5 2.5 2.5 5.0 25	. 0	
Surrogate	Recovery		Acceptable Range		
a,a,a-Trifluorotoluene	96	%	75 - 124		

Note o = Reporting limit(s) raised due to high level of analyte present in sample. NA = Not Applicable

ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Client Name: Geraghty & Miller, Inc.

Client ID: LAB ID:

MW-5

303382-0004-SA

Matrix: Authorized: AQUEOUS 23 DEC 98 Sampled: 22 DEC 98 Prepared: NA

Received: 23 DEC 98 Analyzed: 04 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier	
Benzene Toluene Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE)	ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.50 0.50 0.50 1.0 5.0		
Surrogate	Recovery		Acceptable Range		
a,a,a-Trifluorotoluene	94 %		75 - 124		

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Geraghty & Miller, Inc. Client Name:

Client ID: LAB ID:

MW-7

303382-0005-SA AQUEOUS

Matrix: Authorized:

23 DEC 98

Sampled: 22 DEC 98 Prepared: NA

Received: 23 DEC 98 Analyzed: 04 JAN 99

Dilution Factor: 50

Parameter	Result	Units	Reporting Limit	Qualifier	
Benzene Toluene Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE)	51 ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	25 25 25 50 250		
Surrogate	Recove	ry	Acceptable Range		
a,a,a-Trifluorotoluene	94	%	75 - 124		

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Geraghty & Miller, Inc. TB-LB 303382-0006-TB Client Name:

Client ID: LAB ID:

Matrix: Authorized:

23 DEC 98

AQUEOUS

Sampled: 22 DEC 98 Prepared: NA

Received: 23 DEC 98

Analyzed: 02 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier	
Benzene Toluene Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE)	ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.50 0.50 0.50 1.0 5.0		
Surrogate	Recovery		Acceptable Range		
a,a,a-Trifluorotoluene	97 %		75 - 124		

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



QC LOT ASSIGNMENT REPORT Volatile Organics by GC

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (LCS/BLANK)
303382-0001-SA	AQUEOUS	602-A	04 JAN 99-64A	04 JAN 99-64A
303382-0002-SA	AQUEOUS	602-A	04 JAN 99-64A	04 JAN 99-64A
303382-0003-SA	AQUEOUS	602-A	04 JAN 99-64A	04 JAN 99-64A
303382-0004-SA	AQUEOUS	602-A	04 JAN 99-64A	04 JAN 99-64A
303382-0005-SA	AQUEOUS	602-A	04 JAN 99-64A	04 JAN 99-64A
303382-0006-TB	AQUEOUS	602-A	02 JAN 99-64A	02 JAN 99-64A



Qualifier

METHOD BLANK REPORT Volatile Organics by GC

Project: 303382

Test: Method: 8020-BTX-A

8020

Matrix:

AQUEOUS

QC Lot:

04 JAN 99-64A

Analyzed: 04 JAN 99

Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)

QC Run:

04 JAN 99-64A

Time: 12:55

Result Limit Qualifier Units Analyte ND 0.50 ug/L Benzene ND ug/L 0.50 Toluene ND ug/L 0.50 Ethylbenzene Xylenes (total) Methyl-t-butyl ether (MTBE) ug/L 1.0 ND 5.0 ND ug/L

Surrogate

a, a, a-Trifluorotoluene

% Recovery

Acceptable Range

Reporting

87

75 -124

8020-BTX-A Test: Method: 8020

AQUEOUS Matrix:

QC Lot:

02 JAN 99-64A

Analyzed: 02 JAN 99

Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)

OC Run: 02 JAN 99-64A 13:55 Time:

Reporting Result Units Limit Analyte 0.50 ND ug/L Benzene ND 0.50 ug/L Toluene 0.50 Ethy1benzene ND ug/L ug/L 1.0 Xylenes (total) ND 5.0 ND ug/L Methyl-t-butyl ether (MTBE)

Surrogate

a,a,a-Trifluorotoluene

% Recovery

Acceptable Range

108

75 -124



UPLICATE CONTROL SAMPLE REPORT

Volatile Organics by GC Project: 303382

Aromatic Volatile Organics Category: 602-A

Method: 8020 Testcode: 8020-BTX-A AQUEOUS Concentration Units: ug/L latrix:

04 JAN 99-64A Analyzed Date: 04 JAN 99 Time: 14:11 C Lat:

nalyte	Concentration SpikedMeasured		Accuracy (%)		Precision (RPD)		
		DCS1	DCS2	DCS1`	DCS2	Limits	DCS Limit
Benzene Toluene Ethylbenzene Xylenes (total) 1,3-Dichlorobenzene	10.0 10.0 10.0 30.0 10.0	9.61 8.52 9.33 26.9 8.98	9.47 8.38 9.26 26.5 8.81	96 85 93 90	95 84 93 88 88	72-116 78-118 79-119 79-119 75-126	1.5 15 1.6 15 0.79 15 1.5 15 1.8 21
. —			4				
urrogate	Spiked		ionasured DCS2	Accu DCS1	racy(%) DCS2	Limits	·

18.8

97

94

75-124

Category: 602-A Aromatic Volatile Organics

a,a,a-Trifluorotoluene 20.0

Testcode: 8020-BTX-A Method: 8020

Matrix: AQUEOUS Concentration Units: ug/L

19.4

02 JAN 99-64A Analyzed Date: 02 JAN 99 Time: 15:11 QC Lot:

Analyte	Spiked		ion easured DCS2	Accu (S DCS1	racy %) DCS2	Limits	Precis (RPD DCS L)
Benzene Toluene Ethylbenzene Kylenes (total) 1,3-Dichlorobenzene	10.0 10.0 10.0 30.0 10.0	10.2 9.41 9.40 27.1 9.47	10.2 9.51 9.51 27.4 9.71	102 94 94 90 95	102 95 95 91 97	72-116 78-118 79-119 79-119 75-126	0.75 1.1 1.1 1.1 2.5	15 15 15 15 21
_		•						

-----Concentration-----Accuracy(%) DCS1 DCS2 -----Measured---urrogate Spiked Limits DCS2 75-124 104 a,a-Trifluorotoluene 20.0 20.6 20.8 103

Calculations are performed before rounding to avoid round-off errors in calculated results.



Client Name: Geraghty & Miller, Inc.

Client ID: M

MW-1 303382-0001-SA

LAB ID: 303382-000 Matrix: AQUEOUS

Authorized: 23 DEC 98

Sampled: 22 DEC 98

Prepared: NA

Received: 23 DEC 98

Analyzed: 05 JAN 99

Dilution Factor: 10

Parameter	Result	Units	Reporting Limit	Qualifier
Gasoline Unknown hydrocarbon	ND 2000	ug/L ug/L	500 500	lo
Surrogate	Recove	Recovery		e Range
4-Bromofluorobenzene	. 96	96 %		122

Note I = The peak pattern present in this sample represents an unknown mixture atypical of gasoline in the range of n-ClO to greater than n-Cl2. Quantitation is based on a gasoline reference in the range of n-CO7 to n-Cl2 only.

Note o = Reporting limit(s) raised due to high level of analyte present in sample.

NA = Not Applicable

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Geraghty & Miller, Inc. Client Name:

Client ID: MW-2

LAB ID: 303382-0002-SA

Matrix: AQUEOUS Authorized: 23 DEC 98 Sampled: 22 DEC 98

Prepared: NA

Received: 23 DEC 98

Analyzed: 05 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier
Gasoline Unknown hydrocarbon	ND 67	ug/L ug/L	50 50	1
Surrogate	Recove	ry	Acceptab	le Range
4-Bromofluorobenzene	105 %		87 -	122

Note 1 = The peak pattern present in this sample represents an unknown mixture atypical of gasoline in the range of n-CO9 to n-Cl2. Quantitation is based on a gasoline reference in the range of n-C07 to n-C12 only. NA = Not Applicable

ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Client Name:

Geraghty & Miller, Inc.

Client ID:

MW-4

LAB ID:

303382-0003-SA

Matrix: Authorized: AQUEOUS

23 DEC 98

Sampled: 22 DEC 98

Prepared: NA

Received: 23 DEC 98

Analyzed: 04 JAN 99

Dilution Factor: 5.0

Parameter	Result	Units	Reporting Limit	Qualifier
Gasoline Unknown hydrocarbon	ND ND	ug/L ug/L	250 250	o
Surrogate	Recovery		Acceptab	le Range
4-Bromofluorobenzene	₂ 96 %		87 -	122

Note o = Reporting limit(s) raised due to high level of analyte present in sample. NA = Not ApplicableND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Client Name: Geraghty & Miller, Inc.

Client ID:

MW-5

LAB ID:

303382-0004-SA

Matrix:

AQUEOUS

Sampled: 22 DEC 98

D = = = = + + + = =

Received: 23 DEC 98

Authorized:

23 DEC 98

Prepared: NA

Analyzed: 04 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier
Gasoline Unknown hydrocarbon	ND ND	ug/L ug/L	50 50	
Surrogate	Recovery		Acceptab	le Range
4-Bromofluorobenzene	98 %		87 -	122

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Client Name:

Geraghty & Miller, Inc.

Client ID:

MW-7

LAB ID:

303382-0005-SA

Matrix:

AOUEOUS

Authorized:

23 DEC 98

Sampled: 22 DEC 98

Prepared: NA

Received: 23 DEC 98

Analyzed: 04 JAN 99

Dilution Factor: 50

Parameter	Result	Units	Reporting Limit	Qualifier	
Gasoline Unknown hydrocarbon	ND 3900	ug/L ug/L	2500 2500	1	
Surrogate	Recove	Recovery		le Range	
4-Bromofluorobenzene	. 97	%	87 -	122	

Note 1 = The peak pattern present in this sample represents an unknown mixture atypical of gasoline in the range of n-ClO to greater than n-Cl2. Quantitation is based on a gasoline reference in the range of n-CO7 to n-C12 only.

NA = Not Applicable ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



Client Name: Geraghty & Miller, Inc.

Client ID: LAB ID:

TB-LB

303382-0006-TB

Matrix:

AQUEOUS

Sampled: 22 DEC 98

Received: 23 DEC 98

Authorized:

23 DEC 98

Prepared: NA

Analyzed: 02 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit Qualifie	-
Gasoline	ND	ug/L	50	
Unknown hydrocarbon	ND	ug/L	50	

Acceptable Range Recovery Surrogate 97 % 87 - 122 4-Bromofluorobenzene

NA = Not Applicable -ND = Not Detected

Reported By: Karen Mason

Approved By: Mike Orbanosky



QC LOT ASSIGNMENT REPORT Volatile Organics by GC

Laboratory Sample Number	QC Matrix	:QC Category	QC Lot Number (DCS)	QC Run Number (LCS/BLANK)
303382-0001-SA	AQUEOUS	TPH-GAS-A	04 JAN 99-64A	04 JAN 99-64A
303382-0002-SA	AQUEOUS	TPH-GAS-A	04 JAN 99-64A	04 JAN 99-64A
303382-0003-SA	AQUEOUS	TPH-GAS-A	04 JAN 99-64A	04 JAN 99-64A
303382-0004-SA	AQUEOUS	TPH-GAS-A	04 JAN 99-64A	04 JAN 99-64A
303382-0005-SA	AQUEOUS	TPH-GAS-A	04 JAN 99-64A	04 JAN 99-64A
303382-0006-TB	AQUEOUS	TPH-GAS-A	02 JAN 99-64A	02 JAN 99-64A



METHOD BLANK REPORT Volatile Organics by GC Project: 303382

Test:

TPH-GAS-TR-A

Method:

P/T-GAS-TR

Matrix:

AQUEOUS

QC Lot:

04 JAN 99-64A

Analyzed: 04 JAN 99

QC Run:

04 JAN 99-64A

Total Petroleum Hydrocarbons (Gasoline)

Time: 12:55

Result

ND

ND

Reporting Units Limit

Qualifier

Gasoline

Analyte

Unknown hydrocarbon

% Recovery

Acceptable Range

50

50

88

87 -122

Surrogate

4-Bromofluorobenzene

Test:

TPH-GAS-TR-A P/T-GAS-TR

Method:

Matrix:

AQUEOUS

QC Lot:

02 JAN 99-64A

Analyzed: 02 JAN 99

QC Run:

02 JAN 99-64A

Result

ND

ND

Total Petroleum Hydrocarbons (Gasoline)

13:55 Time:

Units

ug/L

ug/L

ug/L

ug/L

Reporting Limit

50

50

Qualifier

Analyte Gasoline

Unknown hydrocarbon

% Recovery

98

Acceptable Range

87 -122

Surrogate

4-Bromofluorobenzene



UPLICATE CONTROL SAMPLE REPORT volatile Organics by GC Project: 303382

Category: TPH-GAS-A TPH by Purge and Trap GC-FID Lestcode: TPH-GAS-TR-A

Method: P/T-GAS-TR

atrix: Concentration Units: ug/L 04 JAN 99 Time: 16:06 AQUEOUS 04 JAN 99-64A Analyzed Date: 04 JAN 99 C Lot:

nalyte		oncentrati Mea DCS1		Accur (% DCS1	acy) DCS2	Limits	Precis (RPD DCS L)
asoline	1000	930	931	93	93	74-120	0.10	15
urrogate		oncentrati Mea DCSl		Accur DCSI	acy(%) DCS2	Limits		
-Bromofluorobenzene	20.0	20.4	20.3	102	101	87-122		
Category: TPH-GAS-A Testcode: TPH-GAS-TR-A Jatrix: AQUEOUS QC Lot: 02 JAN 99-64	1		GC-FID Concentra 02 JAN 99	tion Un	hod: P/T its: ug/ ime: 16:	L		

nalyte		Concentration kedMeasured DCS1 DCS2			Accuracy (%) DCS1 DCS2		Precision (RPD) DCS Limit
asoline	1000	959	950	96	95	74-120	0.95 15
Surrogate		-Concentrat			racy(%)		

DCS1 DCS2 DCS1 Limits DCS2 20.6 104 103 87-122 Bromofluorobenzene 20.0 20.8

Calculations are performed before rounding to avoid round-off errors in calculated results.



Total Petroleum Hydrocarbons -Diesel - Method 8015



Client Name: Geraghty & Miller, Inc.

Client ID:

Authorized:

MW - 1

303382-0001-SA

LAB ID: Matrix:

AQUEOUS

23 DEC 98

Sampled: 22 DEC 98

Received: 23 DEC 98

Prepared: 28 DEC 98

Analyzed: 04 JAN 99

Dilution Factor: 100

Reporting Result Units Qualifier Parameter Limit Diesel Fuel ND ug/L 5000 0 79000 ug/L 5000 1 Unknown hydrocarbon

Surrogate

Recovery

Acceptable Range

o-Terphenyl

ND %

73 - 134

Н

= The hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C09 to n-C36. Quantitation is based on a diesel reference between n-C10 and n-C24 only.

= Spiked analyte not detected because of required sample dilution.

Note o = Reporting limit(s) raised due to high level of analyte present in sample.

ND = Not Detected

Reported By: Cindy Jervi

Approved By: Emily Uebelhoer



Geraghty & Miller, Inc. Client Name:

Client ID: LAB ID:

MW - 2

303382-0002-SA

Matrix: Authorized: AQUEOUS

23 DEC 98

Sampled: 22 DEC 98

Prepared: 28 DEC 98

Received: 23 DEC 98 Analyzed: 14 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier	
Diesel Fuel Unknown hydrocarbon	ND 1200	ug/L ug/L	50 50	1.	
Surrogate	Recovery		Acceptab	le Range	
o-Terphenyl	- 138 %		73 -	134 I	

Note 1 = The hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C10 to n-C40. Quantitation is based on a diesel reference between n-C10 and n-C24 only.

Note I = Surrogate recovery outside of limits due to sample matrix interference.

ND = Not Detected

Reported By: Cindy Jervi

Approved By: Lisa Stafford



Client Name: Geraghty & Miller, Inc.

Client ID: MW-4

LAB ID: 303382-0003-SA

Matrix: AQUEOUS Authorized: 23 DEC 98

Sampled: 22 DEC 98 Prepared: 28 DEC 98 Received: 23 DEC 98 Analyzed: 04 JAN 99

Dilution Factor: 20

Reporting Parameter Result Units Limit Qualifier Diesel Fuel ND ug/L 1000 0 3700 Unknown hydrocarbon ug/L 1000 1

Surrogate Recovery Acceptable Range
o-Terphenyl : ND % 73 - 134 H

Note 1 = The hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-C10 to n-C26. Quantitation is based on a diesel reference between n-C10 and n-C24 only.

Note H = Spiked analyte not detected because of required sample dilution.

Note o = Reporting limit(s) raised due to high level of analyte present in sample.

ND = Not Detected

Reported By: Cindy Jervi

Approved By: Emily Uebelhoer



Client Name: Geraghty & Miller, Inc.

Client ID: LAB ID:

MW-5

303382-0004-SA

Matrix: Authorized: **AQUEOUS**

23 DEC 98

Sampled: 22 DEC 98

Prepared: 28 DEC 98

Received: 23 DEC 98

Analyzed: 14 JAN 99

Dilution Factor: 1.0

Parameter	Result	Units	Reporting Limit	Qualifier	
Diesel Fuel Unknown hydrocarbon	ND · 890	ug/L ug/L	50 50	1	
Surrogate	Recovery		Acceptab	le Range	
o-Terphenyl	<i>:</i> 132 %		73 -	134	I

Note 1 = The hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-ClO to n-C4O. Quantitation is based on a diesel reference between n-C10 and n-C24 only. Note I = Surrogate recovery outside of limits due to sample matrix interference.

ND = Not Detected

Reported By: Cindy Jervi

Approved By: Lisa Stafford



Client Name: Geraghty & Miller, Inc.

Client ID:

MW-7

303382-0005-SA

LAB ID: Matrix:

AQUEOUS

Authorized:

23 DEC 98

Sampled: 22 DEC 98

Received: 23 DEC 98

Prepared: 28 DEC 98

Analyzed: 04 JAN 99

Dilution Factor: 500

Parameter

Result

Units

Limit

Qualifier

Diesel Fuel

Unknown hydrocarbon

ND 240000

uq/L ug/L

25000 25000

Reporting

0 1

Surrogate

Recovery

Acceptable Range

o-Terphenyl

ND %

73 - 134

Н

= The hydrocarbon pattern present in this sample represents an unknown mixture in the range of n-ClO to n-C26. Quantitation is based on a diesel reference between n-C10 and n-C24 only.

= Spiked analyte not detected because of required sample dilution.

= Reporting limit(s) raised due to high level of analyte present in sample.

ND = Not Detected

Reported By: Cindy Jervi

Approved By: Emily Uebelhoer



QC LOT ASSIGNMENT REPORT - MS QC Hydrocarbon Work Cell

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (BLANK/LCS)	MS QC Run Number (SA,MS,SD,DU)
303382-0001-SA 303382-0002-SA 303382-0003-SA 303382-0004-SA 303382-0005-SA	AQUEOUS AQUEOUS AQUEOUS AQUEOUS AQUEOUS	TPH-D-TR-A TPH-D-TR-A TPH-D-TR-A TPH-D-TR-A TPH-D-TR-A	28 DEC 98-11C 28 DEC 98-11C 28 DEC 98-11C 28 DEC 98-11C 28 DEC 98-11C	28 DEC 98-11C 28 DEC 98-11C 28 DEC 98-11C 28 DEC 98-11C 28 DEC 98-11C	



METHOD BLANK REPORT Hydrocarbon Work Cell

Project: 303382

Test:

TPH-D-TR-A

Method:

TPH-D-TRIREGIONAL

Matrix:

AQUEOUS

QC Lot: 28 DEC 98-11C Analyzed: 31 DEC 98

QC Run:

28 DEC 98-11C

Time:

22:42

Result

Units

ug/L

ug/L

Total Petroleum Hydrocarbons by GC/FID (Triregional)

Reporting Limit

50

50

Qualifier

Analyte

Diesel Fuel Unknown hydrocarbon

Surrogate

o-Terphenyl

% Recovery

Acceptable Range

103

ND

ND

73 -134



DUPLICATE CONTROL SAMPLE REPORT

Hydrocarbon Work Cell

Project: 303382

Category: TPH-D-TR-A Petroleum Hydrocarbons (Diesel), Tri-Regional

Testcode: TPH-D-TR-A Method: TPH-

Method: TPH-D-TRIREGIONA

Matrix: AQUEOUS Concentration Units: ug/L QC Lot: 28 DEC 98-11C Analyzed Date: 31 DEC 98 Time: 23:43

-----Concentration-----Accuracy Precision (RPD) -----Measured----Analyte Spiked DCS1 DCS2 DCS1 DCS2 DCS Limit Limits 300 256 243 85 Diesel Fuel 81 57-112 5.2 23

-----Concentration-----Surrogate Spiked -----Measured----Accuracy(%) DCS1. DCS2 DCS1 DCS2 Limits 41.6 40.0 41.0 104 102 73-134 o-Terphenyl

Calculations are performed before rounding to avoid round-off errors in calculated results.