December 26, 1991

Mr. Paul Smith Alameda County Environmental Health Department 80 Swan Way, Room 200 Oakland, CA 94621

Dear Mr. Smith:

Enclosed is a copy of our Quarterly Technical Report dated December 16, 1991 for our former Texaco Service Station located at 2225 Telegraph Avenue in Oakland, California. This report covers the third quarter of 1991.

Please call me at (510) 236-1770 if you have any questions.

Best Regards,

Supervisor

RRZ:pap

Enclosure

Mr. Tom Callaghan California Regional Water Quality Control Board San Francisco Bay Area Region 2101 Webster Street, Ste. 500

Oakland, CA 94612

HP

2225TA.PS3

# DISTRIBUTION

4 copies: Texaco Refining and Marketing Inc.

108 Cutting Boulevard

Richmond, California 94804 Attention: Mr. R. R. Zielinski

MAS/JSH/mlw 032782P/R51

QUALITY CONTROL REVIEWER

Stephen J. Osborne Principal Engineer A Report Prepared for

Texaco Refining and Marketing Inc. 10 Universal City Plaza Universal City, California 91608

QUARTERLY TECHNICAL REPORT THIRD QUARTER OF 1991 FORMER TEXACO STATION 2225 TELEGRAPH AVENUE OAKLAND, CALIFORNIA

HLA Job No. 2251,162.03 December 16, 1991 1991 Report No. 3

by

Jeanna S. Hudson

Registered Geologist

Michael A. Sides

Environmental Engineer

JEANNA S. HUDSON NO. 4492

No. C047851 Exp. 12/31/91

Harding Lawson Associates 1355 Willow Way, Suite 109 Concord, California 94520 510/687-9660

#### INTRODUCTION

This quarterly technical report (QTR) presents the results of site investigation and remediation activities conducted by Harding Lawson Associates (HLA) at a service station site formerly owned by Texaco Refining and Marketing Inc. The station, at 2225 Telegraph Avenue, Oakland, California (see Plate 1), is currently owned and operated by Exxon Company U.S.A. This QTR summarizes HLA's work at the site, ongoing since May 1988, and presents results of the recent quarter's work.

#### SITE DESCRIPTION

The site is on the southwest corner of the intersection of Telegraph and West Grand Avenues (Plate 2). The surrounding area contains commercial/retail businesses, including a Chevron service station immediately across Telegraph Avenue and an abandoned Beacon service station northeast of the site. Adjacent to the site on the south is the First Baptist Church of Oakland. There is an apartment building, currently occupied, immediately west of the site.

Surface elevation at the site is approximately 20 feet above mean sea level. The land surface slopes gently southeast, toward Lake Merritt and the Oakland/Alameda Inner Harbor, an area of former tidal flats that has been filled. This area has been extensively developed, and surface runoff is mainly controlled by the municipal storm sewer system.

As shown on Plate 3, structures at the service station include a building, three fuel pump islands, one underground waste oil tank, and three underground fuel storage tanks. Leaded and unleaded gasoline are dispensed from these tanks; automotive repair services are also provided.

#### HYDROGEOLOGIC SETTING

The East Bay Plain has been divided into seven groundwater subareas, defined by the California Department of Water Resources (DWR) on the basis of hydrologic and geologic conditions. This site lies within the Oakland Upland and Alluvial Plain subarea. Most groundwater used in the East Bay Plain is for agricultural or industrial, rather than domestic, purposes. The majority of domestic water is supplied by the East Bay Municipal Utility District (EBMUD) from surface sources.

The groundwater aquifers at the site are primarily contained with the Alameda and Temescal Formations; these permeable formations have an aggregate thickness of more than 1,100 feet. According to maps of the area the Temescal Formation, an alluvial fan deposit, is present locally at the surface. Approximately 1,000 feet west of the site is an outcrop of the Merritt Sand. Direction of regional groundwater flow is south-southwest, toward San Francisco Bay.

Subsurface materials at the site, down to the maximum explored depth of 20 feet, generally consist of stiff, silty clay

underlain by a dense layer of silty sand that ranges from 3 to 8 feet in thickness. According to slug test results, the hydraulic conductivity of the shallow, saturated sand aquifer beneath the site ranges from 1.2 to 5.9 feet per day (Table 1).

Static groundwater levels are encountered at approximately 13 feet below grade; water level measurements and survey data are presented in Table 2. The estimated direction of the groundwater gradient, prior to groundwater extraction at the site, was to the southwest, as shown on Plate 4.

# SUMMARY OF PREVIOUS INVESTIGATIONS

# Previous Reports

Since May 1988, HLA has investigated soil and groundwater conditions at this site. To date, results of the investigation and remedial planning have been presented in the following reports:

1.	Sensitive Receptor Study	May 24, 1988
2.	Subsurface Investigation	July 20, 1988
3.	Environmental Assessment	June 22, 1989
4.	Groundwater Remediation Plan	November 30, 1989

# Field Investigation

Boring locations are shown on Plate 3. Because of restricted subsurface access on Telegraph and West Grand Avenues, no off-site exploration was conducted north or east of the site.

These restrictions were imposed by the City of Oakland and the Bay Area Rapid Transit District (BART), whose tunnel is in this area (see Plate 2).

During previous investigations, the following tasks were completed:

- Conducted a soil-gas survey on site and in city streets near the site. Probe locations are shown on Plate 3 and soil-gas survey results are presented in Table 3.
- Drilled and sampled seven shallow soil borings (B-1 through B-7); locations are shown on Plate 3.
- Drilled, constructed, developed, and sampled six onsite monitoring wells (MW-6A through MW-6F) and three off-site wells (MW-6G through MW-6I); locations are shown on Plate 5. Two of these wells, MW-6C and MW-6D, were subsequently converted to groundwater extraction wells.
- Ordered chemical analyses on soil and water samples to determine concentrations of petroleum hydrocarbons; results of soil and water analyses are presented in Tables 4 and 5, respectively.
- Conducted slug tests in MW-6D, MW-6E, and MW-6H to estimate hydraulic conductivity and transmissivity values for the shallow aquifer; slug test results are presented in Table 1.

## Vadose-zone Soil Condition

No significant concentrations of petroleum hydrocarbons have been found in shallow vadose-zone soils. However, the fuel constituents benzene, toluene, ethylbenzene, and xylenes (BTEX) and total petroleum hydrocarbons (TPH) as gasoline have been detected in soils from 12 to 13.5 feet below the ground surface; this depth is within the capillary fringe zone. TPH as gasoline

concentrations exceeded 100 parts per million (ppm) in some of the soil samples (Table 4).

# Groundwater Condition

Free floating product (gasoline) has been observed on the groundwater in two recovery wells. As shown on Plate 5, hydrocarbon-bearing groundwater is present in the vicinity of the underground tanks and pump islands.

Groundwater analyses from seven monitoring wells and one recovery well indicated that groundwater contains levels of TPH as gasoline ranging from 540 to 3,800 parts per billion (ppb). As of August 1991, the lateral limits of the plume are delineated by MW-6A, MW-6E, MW-6G, and MW-6I; samples from these wells show no detectable hydrocarbons (detection limit for TPH = 50 ppb). Upgradient plume definition is incomplete because of the restricted subsurface access, mentioned above, which is imposed by the City of Oakland and BART.

## SUMMARY OF REMEDIAL ACTIVITIES

The following tasks were completed during installation and start-up of the remedial system:

- Redrilled two monitoring wells and converted them to recovery wells (RW-2 and RW-3 replaced MW-6D and MW-6C, respectively). Drilled and installed RW-1 in the location of B-3. Locations are shown on Plate 3.
- Installed groundwater extraction and collection system.
- Fabricated and installed skid-mounted groundwater treatment system.

- Obtained a Wastewater Discharge Permit from the EBMUD to discharge treated effluent water directly to the Sanitary Sewer.
- Extracted, treated, and discharged approximately 134,500 gallons of groundwater between the fourth quarter 1990 and the end of the second quarter 1991.
- Sampled water from influent, effluent, and midstream in accordance with permit requirements.

## WORK PERFORMED DURING THE THIRD QUARTER OF 1991

- Extracted, treated, and discharged approximately 75,000 gallons of groundwater to the sanitary sewer (210,000 gallons cumulative since startup).
- Added a fourth carbon cannister in series to the remediation system.
- Sampled water from influent, effluent, and midstream for carbon breakthrough and performed chemical analysis as specified in EBMUD Wastewater Discharge Permit No. 001-00007 (see Table 6).
- Prepared and submitted EBMUD status reports as required by the EBMUD wastewater discharge permit.
- Measured free product thickness in recovery wells RW-1 and RW-2. Removed free product from RW-1 and RW-2 on a weekly basis (Table 7).
- Checked RW-3 for free product on a monthly basis.
- Measured water levels in monitoring wells and updated the potentiometric map accordingly (see Table 2 and Plate 6).
- Conducted quarterly groundwater sampling in seven monitoring wells and one recovery well, chemical analyses results are summarized in Table 5 and laboratory reports are attached in the Appendix.

During the third quarter 1991, a fourth carbon cannister was added to the remediation system with approval from EBMUD. Water samples were collected from midstream sampling points to check

for potential breakthrough of hydrocarbons downstream of the carbon cannisters. In addition, influent and effluent samples were collected on a monthly basis and analyzed for BTEX and TPH as gasoline. Analytical results from the samples taken during the third quarter are presented in Table 6.

Free product was discovered in recovery well RW-2 during early August. The gasoline has a much fresher appearance than that previously recovered from RW-1. Product was bailed from RW-1 and RW-2 on a weekly schedule during the remainder of the third quarter, recovering a total of approximately 22 gallons from RW-1 and 10 gallons from RW-2 for the quarter (Table 7).

Water levels were measured in monitoring wells and recovery wells three times during the quarter (Table 2). The water level data collected on September 11, 1991 are presented on Plate 6, a contour map of the potentiometric surface. Plate 4 is a map of the potentiometric surface based on data collected in October 1990, before startup of the groundwater extraction system. A comparison of the October 1990 and May 1991 data indicates that the extraction of groundwater has resulted in a cone of depression in the water table over much of the site.

Groundwater samples were collected from seven monitoring wells and one recovery well during the third quarter. Samples were analyzed for BTEX and TPH as gasoline. Results of those analyses are presented in Table 5.

## WORK PLANNED FOR THE FOURTH QUARTER OF 1991

- Monitor carbon canisters for breakthrough as required by the EBMUD wastewater discharge permit.
- Prepare EBMUD quarterly status reports as required by the EBMUD wastewater discharge permit.
- Check water levels in recovery wells and monitoring wells in order to observe effects of pumping on local groundwater gradient. Measure free product thickness in RW-1 and RW-2. Check for free product in RW-3.
- Remove free product from RW-1 and RW-2 on a weekly basis.
- Sample groundwater from all monitoring wells and recovery wells, excluding wells which may contain free product. Analyze samples for BTEX and TPH as gasoline.
- Observe operations to be conducted by Exxon during tank and line removal. Remove and replace recovery well RW-3, if necessary.

# LIST OF TABLES

Table	1	Slug Test Results
Table	2	Water Level Measurements and Survey Data
Table	3	Results of Soil-gas Survey
Table	4	Results of Soil Chemical Analyses
Table	5	Results of Groundwater Chemical Analyses
Table	6	Results of Chemical Analyses, Groundwater Treatment System - Periodic Sampling
Table	7	Free Product Thickness in Groundwater Extraction Wells and Recovered Volumes

# LIST OF ILLUSTRATIONS

Plate	1	Site Location Map
Plate	2	Vicinity Plan
Plate	3	Site Plan
Plate	4	Potentiometric Surface October 16, 1990
Plate	5	TPH (gasoline) Concentrations in Groundwater, August 14, 1991
Plate	6	Potentiometric Surface September 11, 1991

# **Harding Lawson Associates**

# Table 1. Slug Test Results 2225 Telegraph Avenue Oakland, California

Well		ratum Adjacent to Well Scre	Thickness	Estimated Hydraulic Conductivity
<u>Number</u>	Lithology	Classification	<u>(feet)</u>	(feet/day)
NW-6D	sand	confined	2	5.9
MW-6E	sand, fine-grained	confined	2.5	1.2
MM-6H	sand, medium-grained	unconfined	6	4.8

Table 2. Water Level Measurements and Survey Data 2225 Telegraph Avenue Oakland, California

Well No.	Date	Top of Casing Elevation <sup>1</sup> (feet)	Depth to Groundwater <u>(feet)</u>	Groundwater Surface Elevation <sup>2</sup> (feet)	Incremental Water Elevation Change <sup>3</sup> (feet)	Total Water Elevation Change Since 12/15/88* (feet)
MW-6A	12/15/88	98.99	13.77	85.22		
	10/03/89		13.40	85.59	+0.37	+0.37
	05/11/90		12.87	86.12	+0.53	+0.90
	10/16/90		13.27	85.72	-0,40	+0.50
	12/06/90		13.28	85.71	-0.01	+0.49
	01/14/91					
	02/08/91		12,49	86.50	+0.79	+1.28
	04/02/91		••			
	05/07/91		11.94	87.05	+0.55	+1.83
	05/31/91		• •			Blocked
	06/26/91		12.87	86.12	-0.93	+0,90
	08/05/91		13.44	85.55	-0.57	+0.33
	08/14/91		13.47	85.52	-0.03	+0.30
	09/11/91		13.48	85.51	-0.01	+0.29
MW-6B	12/15/88	98.81	13.01	85.80		
TIM OLD	10/03/89	70.01	12.94	85.87	+0.07	.0.07
	04/30/90		12.53	86.28	+0.41	+0.07 +0.48
	10/16/90		12.73	86.08	-0.20	
	12/06/90		12.74	86.07	-0.20	+0.28 +0.27
	01/14/91		12.57	86.24	+0.17	+0.44
	02/08/91		12.16	86.65	+0.41	+0.85
	04/02/91		11.50	87.31	+0.66	+1.51
	05/07/91		12.02	86.79	-0.52	+0.99
	05/31/91		12.40	86.41	-0.38	+0.61
	06/26/91		12.69	86.12	-0.29	+0.32
	08/05/91		12.95	85.86	-0.26	+0.06
	08/14/91		12.93	85.88	+0.02	+0.08
	09/11/91		13.01	85.80	-0.08	0.0
MW-6C	12/15/88	99.89	14.41	85.48		
	10/03/89		14.10	85.79	+0.31	+0.31
	04/30/90		13.81	86.68	+0.29	+0.60
(RW-3)	10/16/90	98.97 <sup>5</sup>	13.29	85.68	-0.40	+0.20
•	01/14/91		14.50	84.47	-1.21	-1.01
	02/08/91		12.54	86.43	+1.96	+0.95
	04/02/91		11.39	87.58	+1.15	+2.10
	05/07/91		12.47	86.50	-1.08	+1.02
	05/31/91		16.31	82.66	-3.84	-2.82
	06/26/91		15.50	83.47	+0.81	-2.01
	08/05/91		13.69	85.28	+1.81	-0.20
	08/13/91		13.67	85.30	+0.02	-0.18
	09/11/91		13.77	85.20	-0.10	-0.28
07270257				· · <del>-</del> ·		

032782P/R51

Table 2. continued

Well No.	Date	Top of Casing Elevation <sup>1</sup> (feet)	Depth to Groundwater <u>(feet)</u>	Groundwater Surface Elevation <sup>2</sup> (feet)	Incremental Water Elevation Change <sup>3</sup> (feet)	Total Water Elevation Change Since 12/15/88 <sup>4</sup> (feet)
MW-6D	12/15/88	98.78	13.53	<b>8</b> 5.25		
	10/03/89		13.44	85.34	+0.09	+0.09
	04/30/90		13.19	85.59	+0.25	+0.34
(RW-2)	10/16/90	98.11 <sup>5</sup>	12.77	85.34	-0.25	+0.09
	01/14/91				an an	4-
	02/08/91		13.11	85.00	-0.34	-0.25
	04/02/91		11.70	86.41	+1_41	+1.16
	05/07/91		14.09	84.02	-2.39	-1.23
	05/31/91		16.01	82.10	-1.92	-3.15
	06/26/91		14.60	83.51	+1.41	-1.74
	08/05/91		14.00	84.11	+0.60	-1.14
	08/13/91		21.30	76.81	-7.30	-8.44
	09/11/91		19.97	78.14	+1.33	-7.11
MW-6E	12/15/88	98.99	13.84	85.15		••
	10/03/89		13.70	85.29	+0.14	+0.14
	04/30/90		13.43	85.56	+0.27	+0.41
	10/16/90		13.77	85.22	-0.34	+0.07
	12/06/90		13.95	85.04	-0.18	-0.11
	01/14/91		13.95	85.04	0.0	-0.11
	02/08/91		13.20	85.79	+0.75	+0.64
	04/02/91		12.28	86.71	+0.92	+1.56
	05/07/91		13.48	85.51	-1.20	+0.36
	05/31/91		14.09	84.90	-0.61	-0.25
	06/26/91		12.54	86.45	+1.55	+1.31
	08/05/91		14.39	84.60	-1.85	-0.55
	08/14/91		14.18	84.81	+0.21	-0.34
	09/11/91		14.73	84.26	-0.55	-0.89
MW-6F	12/15/88	99.91	14.73	85.18		
	10/03/89		14.48	85.43	+0.25	+0.25
	04/30/90		14.14	85.77	+0.34	+0.59
	10/16/90		14.77	85.14	-0.63	-0.04
	12/06/90		14.81	85.10	-0.04	-0.08
	01/14/91		14.73	85.18	+0.08	0.0
	02/08/91		13.73	86.18	+1.00	+1.00
	04/02/91		12.38	87.53	+1.35	+2.35
	05/07/91		13.67	86.24	-1.29	+1.06
	05/31/91		14.43	85.48	-0.76	+0.30
	06/26/91		14.81	85.10	-0.38	-0.08
	08/05/91		14.96	84.95	-0.15	-0.23
	08/14/91		14.87	85.04	+0.09	-0.14
	09/11/91		15.11	84.80	-0.24	-0.38

Table 2. continued

Well No.	<u>Date</u>	Top of Casing Elevation <sup>1</sup> (feet)	Depth to Groundwater (feet)	Groundwater Surface Elevation <sup>2</sup> (feet)	Incremental Water Elevation Change <sup>3</sup> (feet)	Total Water Elevation Change Since 12/15/88 <sup>4</sup> (feet)
MW-6G	12/15/88	99.16	12.39	86.77		
	10/03/89		12,22	86.94	+0.17	+0.17
	04/30/90		11.73	87.43	+0.49	+0.66
	10/16/90		12.28	86.88	-0.55	+0.11
	12/06/90		12.27	86.89	+0.01	+0.12
	01/14/91		12,14	87.02	+0.13	+0.25
	02/08/91		11.44	87.72	+0.70	+0.95
	04/02/91		10.03	89.13	+1.41	+2.36
	05/07/91		11.00	88.16	-0.97	+1.39
	05/31/91		11.75	87.41	-0.75	+0.64
	06/26/91		12.91	86.25	-1.16	-0.52
	08/05/91		12.43	86.73	+0.48	-0.04
	08/14/91		12.43	86.73	0.0	-0.04
	09/11/91		12.48	86.68	-0.05	-0.09
MW-6H	12/15/88	97.93	12.39	85.54		
	10/03/89	71.00	12.36	85.57	+0.03	+0.03
	04/30/90		12.10	85.83	+0.26	+0.29
	10/16/90		12.18	85.75	-0.08	+0.21
	12/06/90		12.29	85.64	-0.11	+0.10
	01/14/91		12.22	85.71	+0.07	+0.17
	02/08/91		11.93	86.00	+0.29	+0.46
	04/02/91		11.59	86.34	+0.34	+0.80
	05/07/91		12.24	85.69	-0.65	+0.15
	05/31/91		12.22	85.71	+0.02	+0.17
	06/26/91		14.34	83.59	-2.12	-1.95
	08/05/91		12.62	85.31	-1.72	-0.23
	08/14/91		12.43	85.50	+0.19	-0.04
	09/11/91		12.83	85.10	-0.40	-0.44
MW-61	12/15/88	97.60	12.82	84.78		
11W Q1	10/03/89	77.00	12.83	84.77	-0.01	-0.01
	04/30/90		12.66	84.94	+0.17	+0.16
	10/16/90		12.71	84.89	-0.05	+0.11
	12/06/90		12.75	84.85	0.04	+0.07
	01/14/91		12.55	85.05	+0.20	+0.27
	02/08/91		12.32	85.28	+0.23	+0.50
	04/02/91		12.22	85.38	+0.10	+0.60
	05/07/91		12.61	84.99	-0.39	+0.21
	05/31/91		12.82	84.78	-0.21	0.0
	06/26/91		12.93	84.67	-0.11	-0.11
	08/05/91		13.01	84.59	-0.08	-0.19
	08/14/91		12.98	84.62	+0.03	-0.16
	09/11/91		13.11	84.49	-0.13	-0.29

Table 2. continued

Well No.	Date	Top of Casing Elevation <sup>1</sup> (feet)	Depth to Groundwater (feet)	Groundwater Surface Elevation <sup>2</sup> (feet)	Incremental Water Elevation Change <sup>3</sup> (feet)	Total Water Elevation Change Since 12/15/88 <sup>4</sup> (feet)
RW-1	10/16/90	97.89	12.24	85.65		
	01/14/91		12.80	85.09	-0.56	••
	02/08/91		12.53	85.36	+0.27	
	04/02/91		••			
	05/07/91					
	05/31/91		12.86	85.03	-0.33	
	08/05/91		13.19	84.70	-0.33	
	08/13/91		14.05	83.84	-0.86	
	09/11/91		15.96	81.93	-1.91	

#### Notes:

- 1 Elevation relative to HLA temporary benchmark located at the western end of the dispenser island nearest West Grand Avenue, with an arbitrary elevation of 100.0 feet (see Plate 3).
- 2 Groundwater surface elevation = top of casing elevation depth to water
- 3 Incremental groundwater elevation change = groundwater elevation previous groundwater elevation
- Total groundwater elevation change = groundwater elevation groundwater elevation on 12/15/88
- Top of casing elevation changed when monitoring wells were converted into recovery wells.
- -- Water levels not measured/values not applicable.

Table 3. Results of Soil-gas Survey 2225 Telegraph Avenue Oakland, California

# Conducted on September 19, 1988 Concentrations in micrograms per liter ( $\mu \text{g/L})$

<u>Sample</u>	Depth <u>(feet)</u>	<u>Benzene</u>	Ethyl- <u>benzene</u>	<u> Toluene</u>	<u>Xylenes</u>	Total Petroleum <u>Hydrocarbons</u>
Air	N/A	<0.7	<0.8	<0.8	<0.8	<0.7
SG-01				~ <del>~</del>		
SG-02	5.0	<0.7	<0.8	<0.8	<0.8	<0.7
SG-03	12.0	10	4	<0.8	2,800	6,100
SG-04	13.0	<0.7	<0.8	<0.8	140	780
WS-05*	12.0	<75	<76	<77	<77	<75
SG-06	13.0	<0.7	<0.8	<0.8	<0.8	<0.7
SG-07						
Aîr	N/A	<0.7	<0.8	<0.8	<0.8	<0.7

-- - Not able to obtain sample

N/A - Not applicable
Air - Ambient air sample

\* - WS-05 was a sample of groundwater

Table 4. Results of Soil Chemical Analyses
2225 Telegraph Avenue
Oakland, California

Concentrations in milligrams per kilogram (mg/kg)

Sample <u>Number</u>	Depth (feet)	1 <u>Benzene</u>	Ethyl- 2 <u>benzene</u>	3 <u>Toluene</u>	3 Xylenes	TPH as 4 Gasoline
B-1	8.0	0.05	ND	ND	ND	ND
B-1	13.0	ND (5)	10 (10)	16 (10)	41 (10)	2,000 (1,000)
B-2	7.0	ND	ND	ND	ND	ND
B-2	13.5	ND	ND	ND	ND	ND
B-3	7.0	0.06	ND	ND	ND	ND
B-3	13.5	40 (25)	84 (50)	390 (50)	370 (50)	11,000 (5,000)
B-4	13.5	ND	ND	ND	ND	ND
B-5	5.5	ND	ND	ND	ND	ND
B-5	9.5	ND	ND	ND	ND	ND
B-5	12.5	ND	ND	ND	ND	ND
B-6	6.0	ND	ND	ND	ND	ND
B-6	9.5	ND	ND	ND	ND	ND
B-6	12.0	40 (5)	40 (20)	110 (10)	450 (10)	3,000 (1,000)
B-7	6.0	0.64	0.4	0.9	3.4	24
B-7	9.5	0.5	ND	0.7	1.0	ND
8-7	12.0	20 (5)	20 (20)	72 (10)	190 (10)	1,400 (1,000)
MW-6E	13.0	ND	ND	ND	ND	ND
MW-6F	13.0	ND	ND	ND	ND	ND
MW-6G	13.5	ND	ND	ND	ND	5.2
MW-6H	13.5	11 (0.5)	8.8 (2)	3.2 (1)	19 (1)	1,000 (495)
MM-61	13.5	ND	ND	ND	ND	ND

ND = Not detected.

<sup>1</sup> Detection limit 0.05 mg/kg except as noted in parentheses.

Detection limit 0.2 mg/kg except as noted in parentheses.

<sup>3</sup> Detection limit 0.1 mg/kg except as noted in parentheses.

<sup>4</sup> Detection limit 10 mg/kg except as noted in parentheses.

Table 5. Results of Groundwater Chemical Analyses 2225 Telegraph Avenue Oakland, California

Concentrations in micrograms per liter (pg/L)

# EPA TEST METHOD 602

			ETT TEST HETHOR			
Well <u>Number</u>	Date <u>Sampled</u>	1 Benzene	Ethylbenzene <sup>2</sup>	<u>Toluene</u> 3	3 Xylenes	TPH <sup>4</sup> <u>(as gasoline)</u>
MW-6A	06/24/88	ND	ND	ND	ND	
	10/20/88	1	ND	ND	ND	
	09/07/89	2	ND	ND	ND	ND
	05/11/90	150	ND (0.25)	6.2	13	ND (500)
	05/07/91	700	67	64	74	2,700
	68/14/91	3.6	ND (0.5)	ND (0.5)	ND (0.5)	ND
MW-6B	06/24/88	ND	ND	ND	5	-
	10/20/88	4	ND	3	ND	-
	09/07/89	70 (2.5)	60 (3)	8 (3)	160 (4)	2,700 (25)
	04/30/90	45 (5)	20 (5)	6 (5)	22 (5)	168
	05/07/91	240	310	42	660	3,300
	08/14/91	9.1	85	ND (5)	150	980
MW-6C	06/24/88	7,400	170	7	2,300	-
	10/20/88	9,500 (50)	170 (2)	65 (100)	850 (1)	-
	09/07/89	7,900 (25)	350 (25)	430 (25)	1,100 (38)	18,000 (2,500)
	04/30/90	6,100 (250)	1,000 (250)	1,500 (250)	2,700 (250)	30,000 (25,000)
(RW-3)	05/07/91	4,200	220	640	670	5,800
	08/14/91	2,390	49	330	360	3,800
MW-6D	07/11/88	220 (5)	ND (20)	27 (10)	ND (10)	-
	10/20/88	710 (5)	22 (20)	74 (10)	110 (10)	•
	09/07/89	600 (12.5)	58 (13)	26 (13)	31 (19)	2,200 (1,250)
	04/30/90	800 (50)	310 (50)	150 (50)	280 (50)	3,600 (500)
(RV-2)	(05/07/91)	(3,200)	150	480	780	(11,000)
MW-6E	10/20/88	1	ND	ND	3	
	09/07/89	3	ND	ND	ND	220
	04/30/90	57 (5)	ND (5)	ND (5)	53 (5)	250)
	05/07/91	32	2.2	1.0	1.4	160
	08/14/91	0.9	ND (0.5)	ND (0.5)	ND (0.5)	ND
MW-6F	10/25/88	ND	ND	ND	2	
	09/07/89	ND	ND	ND	ND	ND
	04/30/90	ND	ND	ND	ND	ND
	05/07/91	ND	ND (0.5)	ND (0.5)	ND (0.5)	ND
	08/14/91	ND	ND (0.5)	ND (0.5)	ND (0.5)	ND
MW-6G	12/07/88	ND	ND	ND	ND	-
	09/07/89	ND	ND	ND	ND	ND
	04/30/90	ND	ND	ND	ND	ND
	05/07/91	ND	ND (0.5)	ND (0.5)	ND (0.5)	ND
	08/14/91	ND	ND (0.5)	ND (0.5)	ND (0.5)	ND

Table 5. Results of Groundwater Chemical Analyses (continued)

Well <u>Number</u>	Date Sampled	1 <u>Benzene</u>	Ethylbenzene <sup>2</sup>	<u>Toluene<sup>3</sup></u>	3 Xytenes	TPH <sup>4</sup> (as gasoline)
MW-6H	12/07/88	1,200 (25)	110 (20)	320 (10)	220 (10)	-
	09/07/89	480 (10)	16 (10)	ND (10)	ND (15)	660 (500)
	04/30/90	700 (50)	31 (5)	39 (5)	50 (5)	630 (500)
	05/07/91	95	15	14	21	570
	08/14/981	52	11	9.9	18	540
MW-6I	12/07/88	ND	ND	ND	ND	-
	09/07/89	ND	ND	ND	ND	ND
	04/30/90	ND	ND	ND	ND	ND
	05/07/91	ND	ND (0.5)	ND (0.5)	ND (0.5)	ND
	08/14/91	ND	ND (0.5)	ND (0.5)	ND (0.5)	ND

ND = Not detected.

Detection limits given in parentheses, where applicable. If not:

<sup>1.</sup> Detection limit = 0.5

Detection limit = 2

Detection limit = 1

<sup>4.</sup> Detection limit = 50

Table 6. Results of Chemical Analyses, Groundwater Treatment System
- Periodic Sampling
2225 Telegraph Avenue, Oakland, California

Sampling Date	Sample	TPH (ppb)	Benzene (ppb)	Toluene (ppb)	Ethyl- benzene (ppb)	Xylenes (ppb)	COD F (ppb)	TSS (ppb)	Tempera- ture (°C)	рH	Conduc- tivity (umhos/cm)	Flow Meter (gallons)
EBMUD Requiremen	ts	NS	3	31	5	42	Fee	Fee	NS	NS	NS	
07/03/91	EFF-16 BT-2-30	ND 560	ND 32	ND 2.9	ND 3.8	ND 19						141,900
07/10/91	BT-2-31	ND	ND	ND	ND	ND				••		148,880
07/17/91	EFF-17	70	ND	ND	0.9	0.8						156,230
08/05/91	INF-18 Eff-18	12,000 ND	3,600 ND	3,100 ND	33 ND	1,300 ND			 	 		173,850
08/13/91	EFF-19 BT-3-1	ND ND	ND ND	ND ND	ND ND	ND ND			 			179,430
08/22/91	BT-3-2	ND	ND	ND	ND	ND						
09/04/91	BT-3-3 INF-20 EFF-20	ND 9,900 ND	ND 2,900 ND	ND 1,300 ND	ND ND ND	ND 1,400 ND		 	 		- <del>-</del> 	194,540
09/11/91	BT-3-4	ND	ND	ND	ND	ND					**	
09/18/91	BT-3-5	ND	ND	ND	ND	ND						
09/25/91	BT-3-6	ND	ND	ND	ND	ND					••	
Detection Limit		50	0.5	0.5	0.5	0.5	20,000	1,000			1,0	

<sup>-- =</sup> Not tested

ND = Not detected above laboratory detection limit

NS = Not specified

Fee = Used to determine discharge fee ppb = Parts per billion (μg/l)

TPH = Total petroleum hydrocarbons as gasoline (EPA 8015 modified)

CODF = Chemical oxygen demand, filtered (SMWWA 2540D)


TSS = Total suspended solids (SMWWA 5220D)

Table 7. Free Product Thickness in Groundwater Extraction Wells and Recovered Volumes\*

<u>Date</u>	Free Product Thickness in	Approximate Volume Recovered from RW-1 (gallons)	Free Product Thickness in <u>RW-2 (feet)</u>	Approximate Volume Recovered from RW-2 (gallons)
1st QTR Cumulative	0.30 - 2.5	4.80	0	0
2nd QTR 1991 Cumulative	0.02 - 1.46	8.04	0	O
07/10/91	2.06	2.00		
07/17/91	1.75	1.50		
07/22/91	1.75	1.56	<b></b>	
07/29/91	2.16	2.14	••	
08/05/91		1.98		
08/13/91	1.7	2.19	4.5	4.70
08/14/91	••	••	0.16	
08/22/91	1.92	1.64	0.86	0.61
08/24/91	0.72	0.79	0.47	0.24
08/26/91	0.27	0.13	0.59	0.32
08/28/91	0.40	0.28	0.23	0.21
08/30/91	0.34	0.22	0.30	0.11
09/06/91	2.19	1.89	1.78	1.56
09/11/91	2.30	2.08	1.84	1.26
09/18/91	1.50	1.12	1.00	0.62
09/25/91	2.73	2.57	1.23	0.86
3rd QTR Cumulative	0.27-2.73	22.09	0.23-4.5	10.49

<sup>\*</sup> Free product recovered using a graduated lucite bailer -- Free product thickness not measured/free product not recovered







**Harding Lawson Associates** 

Engineers and Geoscientists

Site Location Map

Former Texaco Service Station 2225 Telegraph Avenue Oakland, California 1


YC JOB NUMBER 2251,111.03


APPROVED


2/89


REVISED


DATE











# APPENDIX

RESULTS OF LABORATORY ANALYSES ON QUARTERLY GROUNDWATER SAMPLES



# NATIONAL ENVIRONMENTAL TESTING, INC.

NET Pacific, Inc. 435 Tesconi Circle Santa Rosa, CA 95401

Tel: (707) 526-7200 Fax: (707) 526-9623

HARDING ASSOC.

SEP 4 1991

Jeanna Hudson Harding Lawson Associates 1355 Willow Way, Ste. 109 Concord, CA 94520

Date: 08-29-91 NET Client Acct No: 10.0 NET Pacific Log No: 9257

Received: 08-15-91 0800

Client Reference Information

Texaco, 6 Oakland, Job: 2251,162.03

Sample analysis in support of the project referenced above has been completed and results are presented on following pages. Please refer to the enclosed "Key to Abbreviations" for definition of terms. Should you have questions regarding procedures or results, please feel welcome to contact Client Services.

Approved by:

Jules Skamarack Laboratory Manager

JS:rct Enclosure(s)



Client No: 10.01

©Client Name: Harding Lawson Associates 9257

Date: 08-29-91

Page: 2

Ref: Texaco, 6 Oakland, Job: 2251,162.03

		_	MW-6A 08-14-91	MW-6B 08-14-91	<del></del>
Parameter	Method	Reporting Limit	94703	94704	Units
DEMOCI DAY AND DOOR DOOR	<del>-</del>				
PETROLEUM HYDROCARBONS			<b></b>		
VOLATILE (WATER) DILUTION FACTOR *			1		
DATE ANALYZED			1 08-20-91	10 08-19-91	
METHOD GC FID/5030			08-20-91	08-13-31	
as Gasoline		0.05	ND	0.98	ma /T
METHOD 602		0.05	ND	0.30	mg/L
DILUTION FACTOR *			1	10	
DATE ANALYZED			08-20-91	08-19-91	
Benzene		0.5	3.6	9.1	ug/L
Ethylbenzene		0.5	ND	85	ug/L
Toluene		0.5	ND	ND	ug/L
Xylenes, total		0.5	ND	150	ug/L



Client No: 10.01

®Client Name: Harding Lawson Associates

Date: 08-29-91

NET Log No: 9257

Page: 3

Ref: Texaco, 6 Oakland, Job: 2251,162.03

			MW-6E 08-14-91	MW-6F 08-14-91	
Parameter	Method	Reporting Limit	94705	94706	Units
PETROLEUM HYDROCARBONS					
VOLATILE (WATER)					
DILUTION FACTOR *			1	1	
DATE ANALYZED			08-19-91	08-19-91	
METHOD GC FID/5030					
as Gasoline		0.05	ND	ND	mg/L
METHOD 602					
DILUTION FACTOR *			1	1	
DATE ANALYZED			08-19-91	08-19-91	
Benzene		0.5	0.9	ND	ug/L
Ethylbenzene		0.5	ND	ND	ug/L
Toluene		0.5	ND	ND	ug/L
Xylenes, total		0.5	ND	ND	ug/L



Client No:

10.01

©Client Name: Harding Lawson Associates

Date: 08-29-91

NET Log No:

9257

Page:

Ref: Texaco, 6 Oakland, Job: 2251,162.03

		<del></del>	***************************************		
			MW-6G 08-14-91	MW-6H 08-14-91	
Parameter	Method	Reporting Limit	94707	94708	Units
PETROLEUM HYDROCARBONS			·		
VOLATILE (WATER)			<del></del>		
DILUTION FACTOR *			1	5	
DATE ANALYZED			08-19-91	08-20-91	
METHOD GC FID/5030					
as Gasoline		0.05	ND	0.54	mg/L
METHOD 602					<b>5</b> .
DILUTION FACTOR *			1	5	
DATE ANALYZED			08-19-91	08-20-91	
Benzene		0.5	ND	52	ug/L
Ethylbenzene		0.5	ND	11	ug/L
Toluene		0.5	ND	9.9	ug/L
Xylenes, total		0.5	ND	18	ug/L



Client No: 10.01

®Client Name: Harding Lawson Associates

Date: 08-29-91

NET Log No: 9257

Page: 5

Ref: Texaco, 6 Oakland, Job: 2251,162.03

·			MW-61 08-14-91	RW-3 08-14-91	
Parameter	Method	Reporting Limit	94709	94710	Units
PETROLEUM HYDROCARBONS		···	44 44		
VOLATILE (WATER)					
DILUTION FACTOR *			1	10	
DATE ANALYZED			08-19-91	08-20-91	
METHOD GC FID/5030					
as Gasoline		0.05	ND	3.8	mg/L
METHOD 602		3.33			mg/ L
DILUTION FACTOR *			1	10	
DATE ANALYZED			08-19-91	08-20-91	
Benzene		0.5	ND	2,300	ug/L
Ethylbenzene		0.5	ND	49	ug/L
Toluene		0.5	ND	330	ug/L
Xylenes, total		0.5	ND	360	ug/L



Client Acct: 10.01

©Client Name: Harding Lawson Associates

Date: 08-27-91

Page: 6

ET Pacific, Inc. NET Log No: 9257

Ref: Texaco, 6 Oakland, Job: 2251,162.03

# QUALITY CONTROL DATA

Parameter	Reporting Limits	Units	Cal Verf Stand % Recovery	Blank Data	Spike % Recovery	Duplicate Spike % Recovery	RPD
Gasoline	0.05	mg/L	82	ND	104	96	8.0
Benzene	0.5	ug/L	78	ND	108	109	4.7
Toluene	0.5	ug/L	84	ND	103	105	1.9
Gasoline	0.05	mg/L	94	ND	104	100	3.9
Benzene	0.5	ug/L	103	ND	112	136	19
Toluene	0.5	ug/L	111	ND	106	106	< 1
Benzene	0.5	ug/L	107	ND	119	97	20

COMMENT: Blank Results were ND on other analytes tested.



#### KEY TO ABBREVIATIONS and METHOD REFERENCES

 Less than; When appearing in results column indicates analyte not detected at the value following. This datum supercedes the listed Reporting Limit.

Reporting Limits are a function of the dilution factor for any given sample. To obtain the actual reporting limits for this sample, multiply the stated Reporting Limits by the dilution factor (but do not multiply reported values).

ICVS : Initial Calibration Verification Standard (External Standard).

mean : Average; sum of measurements divided by number of measurements.

mg/Kg (ppm): Concentration in units of milligrams of analyte per kilogram of sample,

(parts per million).

mg/L : Concentration in units of milligrams of analyte per liter of sample.

mL/L/hr : Milliliters per liter per hour.

MPN/100 mL : Most probable number of bacteria per one hundred milliliters of sample.

N/A : Not applicable.

NA : Not analyzed.

ND : Not detected; the analyte concentration is less than applicable listed

reporting limit.

NTU : Nephelometric turbidity units.

RPD : Relative percent difference, 100 [Value 1 - Value 2]/mean value.

SNA : Standard not available.

ug/Kg (ppb) : Concentration in units of micrograms of analyte per kilogram of sample,

(parts per billion).

ug/L : Concentration in units of micrograms of analyte per liter of sample.

umhos/cm : Micromhos per centimeter.

# Method References

Methods 100 through 493: see "Methods for Chemical Analysis of Water & Wastes", U.S. EPA, 600/4-79-020, rev. 1983.

Methods 601 through 625: see "Guidelines Establishing Test Procedures for the Analysis of Pollutants" U.S. EPA, 40 CFR, Part 136, rev. 1988.

Methods 1000 through 9999: see "Test Methods for Evaluating Solid Waste", U.S. EPA SW-846, 3rd edition, 1986.

SM: see "Standard Methods for the Examination of Water & Wastewater, 17th Edition, APHA, 1989.

# Harding Lawson Associations 1355 Willow Way, Suite 109 Concord, California 94520 415/687-9660 Telecopy: 415/687-9673

# CHAIN OF CUSTODY FORM

Lab: NET 9257

RECEIVED BY: (Signature)

DATE/TIME

RECEIVED FOR LAB BY:

							Samplers: Steve Hanson									ANALYSIS REQUESTED																							
Job	Nu	mb	er:	_ Z	2	54	16	Z.	0	3							_												1	$\top$	T	Π		$\prod$			Τ	Τ	$\prod$
Nam	e/L	.00	ati	on:	7	E	X4	00	, #	*6		A	4/9	ME	2		_															1							
Proj	Project Manager: Teanna Hudson Recor								rd	lei	r: .	(Sign	Lat	tun B. Harne							7																		
	_	1AT	_,		# <b>C</b> C	PRE	AIN SE	IER: RV.	s		S	AME	LE														020	240	270	S E		20	þ						
SOURCE CODE	ater	diment	Soil Oil		pres.	HNO,				OR LAB NUMBER					DATE							STATION DESCRIPTION/ NOTES			4 601/8	4 602/8	EPA 624/8240	4 625/8	ICP METALS	X 100 100 100 100 100 100 100 100 100 10	0 4								
	<u> </u>	တ္တု	βįō	_  -	2 I	Ē	-		Ļ	Yr	W	k	S	eq		Υr	M	o	Dy	1	Ti	me	•	Ш		EP/	EP/	E	E .	미합	BTEX 8	3							
213	X	$\sqcup$	Ш	4	4	$\perp$	3		-	1 4	+ +	_ <u>k</u>	_		9	1	0 8	3 /	7		Γ	L			STANDARD			1		十	TX	1	Г	H	+	+	t	$\vdash$	
2/3	X		44	4	1	$\perp$	1	_ _		لها 1	†	·  6	3	Ш	$\perp$	L	A	1			L				TURNAROUND			1	7	$\top$	K	1	<u> </u>	П	_	十	$\dagger$	T	<del>       </del>
23	λ		-	_	4	$oldsymbol{\perp}$	3	_		1 14	+	6	E		_	L		╧		$\downarrow$	L							1	1	1	X	1		П	+	+	$\dagger$	†	
2/3	┼	4	+1	4	$\perp$	$\bot$	3	_ _	_	Ų		6	_	$\sqcup$	$\perp$	<u> </u>	$\downarrow \downarrow$	1	$\perp$	┸			Ц					Ī	1	T	1	X	П	П	7	7	T		
2 3	X	$\perp$	+		+	+	3	4	-	1 14	1	- 16		$\sqcup$	┺		$\downarrow$	1	<u> </u>	$\perp$	$\downarrow$		Ц						T	$\top$	1	T	П		$\top$	1	T	1	
2)	X	+	+	-	$\bot$	<b>.</b>	3	-		1 1		4		-	$\bot$		4	4	$\perp$	$\perp$	_		Ц	Ļ	/		1	<u>.</u>	Ī	$\top$	X	X		П		十			
2 7	1	$\vdash$	-   -	-	+	-	3	<u> </u>		111	₩	6	<b>-</b> F	_	丄	<u></u>	Ψ,	$\perp$	$\perp$		$\perp$	(	Ц		STODY SEALED &		3/	V	T	T	1/	X	П	П	$\top$	7	T	Γ	
14	K	$\dashv$	+	-	╁	-	3	_	ᄮ	4	H	ا	3   -		$\perp$		4	$\perp$	┸	1	_	<u>L</u>				ĺ					K	N	П	П	$\top$	$\top$		<b> </b>	
HH	+	-	+	╌	+	+	$\vdash$	-	╀	+	$\vdash$	+	$\bot$	$\vdash$	1	-	$\downarrow$	$\bot$	1	$\prod$		10	<u>U</u>		19:00 5.10.			I						$\prod$	T	$\top$	Τ		
	نــــــــــــــــــــــــــــــــــــــ		Ш	L	1_		Ц		L	L	Ш		$\perp$				$\perp$		L		L		Ш	L	intact VS					L				П	T		T		
				Т			<u> </u>		7			_			_								_																
	L/ NUN	AB BE	₹		•	PTI	ı	COL MTD CD	þ	co o	A DE			ħ	/ISC	CE L	LA	NEC	วบเ	s					CHAIN OF CL	JST	OD	)Y I	RE(	COR	TD								
	Wk		eq		r	EET	1	CD															_																
			$\prod$	Ŧ	F			$-\Gamma$			П	1										_	7	tem B. Harren of	Sective BY: (Signature) DATE								./ı		E ごo				
		$\downarrow$		1	<b>†</b>	L		‡	L			1											RE	7	INQUISHED BY: (Signature) +/14 The	CEI	√E1	D B	<b>Y</b> : <i>(</i> :	Signa	3ture	ij				DAT			
<del></del>	+	+	+		╀	┰	H	4	1	<u> </u>	Ш	_										į,	RE	Ľ	,	CEI	VE	D B	<b>Υ</b> : ί.	Signa	aturi	 e J	—	—		DAT	<u>_</u>	LIMI	

RELINQUISHED BY: (Signature)

DISPATCHED BY: (Signature)

WILL NCS METHOD OF SHIPMENT DATE/TIME

DATE/TIME