Jennifer C. Sedlachek Project Manager

ExxonMobil Refining & Supply Company Global Remediation - US Retail

4096 Piedmont Avenue #194 Oakland, California 94611 510.547.8196 510.547.8706 Fax jennifer.c.sedlachek@exxonmobil.com



April 27, 2007

Mr. Steven Plunkett Alameda County Health Care Services Agency Department of Environmental Health 1131 Harbor Bay Parkway, Room 250 Alameda, California 94502-6577

RECEIVED

2:35 pm, May 01, 2007

Alameda County Environmental Health

Former Exxon RAS #7-0235/2225 Telegraph Avenue, Oakland California. RE:

Dear Mr. Plunkett:

Attached for your review and comment is a copy of the letter report entitled Off-Site Delineation Investigation Report, dated April 27, 2007, for the above-referenced site. The report was prepared by Environmental Resolutions, Inc. (ERI) of Petaluma, California, and details assessment activities pertaining to the subject site.

I declare, under penalty of perjury, that the information and/or recommendations contained in the attached document or report is true and correct to the best of my knowledge.

If you have any questions or comments, please contact me at 510.547.8196.

Sincerely,

Jennifer C. Sedlachek Project Manager

Attachment:

ERI's Off-Site Delineation Investigation Report, dated April 27, 2007

cc:

w/ attachment

Mr. Chuck Headlee, California Regional Water Quality Control Board, San Francisco Bay Region Mr. Robert C. Elhers, M.S., P.E., The Valero Companies, Environmental Liability Management

w/o attachment

Ms. Paula Sime, Environmental Resolutions, Inc.



Southern California Northern California Pacific Northwest Southwest Texas Montana

April 27, 2007 ERI 222912.R22

Ms. Jennifer C. Sedlachek ExxonMobil Refining & Supply-Global Remediation 4096 Piedmont Avenue #194 Oakland, California 94611

SUBJECT

Off-Site Delineation Investigation Report Former Exxon Service Station 7-0235 2225 Telegraph, Oakland, California

Ms. Sedlachek:

At the request of Exxon Mobil Corporation (Exxon Mobil), Environmental Resolutions, Inc. (ERI) advanced and sampled five soil borings at the subject site. This work was conducted to further define the extent of petroleum hydrocarbons in soil and groundwater south and southwest of the site. ERI performed the fieldwork in accordance with the Reponse to Agency Comments and Addendum to Preferential Pathway Study and Work Plan for Off-Site Delineation, dated December 8, 2003, and Addendum to Response to Agency Comments and Addendum to Preferential Pathway Study and Work Plan for Off-Site Delineation, dated April 26, 2004. The first work plan was prepared in response to a directive from the Alameda County Health Care Services Agency (the County) dated October 10, 2003, and the second work plan was prepared in response to a letter from the County dated March 15, 2004. The County approved the scope of work in a letter dated January 11, 2007. Copies of the three agency correspondences are presented in Attachment A.

SITE BACKGROUND

Site Location and Land Use

The site is located on the southwestern corner of Telegraph Avenue and West Grand Avenue in Oakland, California, as shown on the Site Vicinity Map (Plate 1). The locations of existing underground storage tanks (USTs), dispenser islands, and other select site features are shown on the Generalized Site Plan (Plate 2). Land use in the vicinity of the site is a mix of industrial and residential.

Site History and Previous Investigations

Texaco Refining and Marketing, Incorporated (Texaco) operated a service station at the site from 1963 until 1988 when the site property was transferred to Exxon Mobil. Exxon Mobil sold the site to Valero Refining Company (Valero) in 2000. In 2001, Valero sold the site to Mr. Lam Truong who currently owns and operates the station and dispenses three grades of gasoline and diesel. The locations of the former and current USTs, dispenser islands, groundwater monitoring wells, and select site features are shown on Plate 2. Groundwater monitoring has been conducted at the site since June 1988.

The following is a summary of activities at the site.

May 1988

Texaco retained Harding Lawson Associates (HLA) to oversee environmental assessment activities at the subject site (HLA, 1989). HLA conducted a sensitive receptor survey.

June and July 1988 HLA observed the installation of four groundwater monitoring wells (MW6A through MW6D) to approximately 20 feet below ground surface (fbgs) (HLA, 1988).

September 1988 HLA observed Tracer Research Corporation advance seven soil-gas probes. Four soil-gas samples and one water sample were collected and analyzed onsite using an on-site mobile laboratory (HLA, 1989). The maximum concentrations of total petroleum hydrocarbons (TPH) and benzene in soil-gas were reported in sample SG03 at 6,100 micrograms per liter (μg/L) and 10 μg/L, respectively.

October and November 1988

HLA observed the advancement of nine soil borings. Five of the borings were completed as groundwater monitoring wells MW6E through MW6I (HLA, 1989).

December 1988 to June 1989

HLA performed slug tests on three wells (MW6D, MW6E, and MW6H). The hydraulic conductivity was reported at between 1.2 to 5.9 feet per day (ft/day) (HLA, 1989).

1990

HLA installed three recovery wells (RW1, RW2, and RW3). Well RW1 was installed at the same location as boring B3. Wells MW6C and MW6D were drilled out and deepened to 25 feet and completed as groundwater recovery wells RW3 and RW2, respectively (HLA, 1990).

1991

Recovery well RW3 was destroyed (HLA, 1992).

March 1991

Alton Geoscience Inc. (Alton) drilled and sampled 10 exploratory borings (B1 through B10) (Alton, 1991).

November 1991 EA Engineering, Science, and Technology (EA) observed the removal and replacement of three single-walled USTs and associated piping from the subject site. The tanks were replaced with double-walled FRP tanks and piping (EA, 1992).

November 1991

Two vapor extraction wells were installed in the backfill of the new tank field during retrofit operations (HLA, 1992).

1992

Groundwater monitoring well MW6A was destroyed. Recovery well RW3A was installed to replace well RW3 (ERI, 2002).

March 1998

Exxon Mobil acquired responsibility for the environmental case at the site upon property transfer from Texaco (ERI, 2002).

March 2000

ERI observed Vironex Environmental Field Services advance two direct-push soil borings (GP1 and GP2) to approximately 23 fbgs (ERI, 2000).

April 2001

ERI observed Gregg Drilling and Testing Inc. install one groundwater monitoring well (MW6J) to approximately 23 fbgs (ERI, 2001a).

September 2001

ERI performed a continuous (24 hours per day) nine-day dual-phase extraction (DPE) pilot test at the subject site. ERI estimated that a total of approximately 187.5 pounds of total petroleum hydrocarbons as gasoline (TPHg) and 2.36 pounds of methyl tertiary butyl ether (MTBE) were removed during the DPE feasibility test and that a total of 0.329 pounds of TPHg and 0.0374 pounds of MTBE were removed by groundwater extraction during the DPE test. The effective vacuum radius of influence (ROI) was calculated at less than 20 feet, and a total of 9,000 gallons of groundwater was extracted and treated during the nine day DPE test. The average extraction rate for the test was 1.06 gallons per minute (gpm) (ERI, 2001b)

October 2002

ERI conducted an underground utility survey in the vicinity of the site. The utility agencies that responded to ERI's request for information include the following: Pacific Gas and Electric (PG&E), City of Oakland Engineering Services Department, and East Bay Water. Per individual agency policies, depths of gas, electric, and water trenches

were not provided to ERI. The elevation of the sewer trench along Telegraph Avenue is estimated at 13 feet above mean sea level (fmsl). The maximum groundwater elevation recorded at the site is approximately 13 fmsl (ERI, 2002).

Currently, there are seven groundwater monitoring wells (MW6B and MW6E through MW6J) and three groundwater extraction wells (RW1, RW2, and RW3A) on and in the vicinity of the site as shown on Plate 2.

Laboratory analytical results for groundwater samples collected from the wells indicate the presence of total petroleum hydrocarbons as diesel (TPHd); TPHg; total petroleum hydrocarbons as motor oil (TPHmo); MTBE; tertiary butyl alcohol (TBA); and benzene, toluene, ethylbenzene, and total xylenes (BTEX). Groundwater monitoring data are summarized in Tables 1A and 1B. Well construction details are presented in Table 2. Soil sample analytical results are summarized in Tables 3A, 3B, and 3C. Grab groundwater analytical results are summarized in Tables 4A, 4B, and 4C.

REGIONAL GEOLOGY AND HYDROGEOLOGY

Regional Geology and Hydrogeology

The site is located along the eastern margin of the San Francisco Bay within the East Bay Plain (Hickenbottom and Muir, 1988). The surficial deposits in the site vicinity are mapped as Merritt sand consisting of fine-grained, very well sorted, well-drained eolian deposits of the Pleistocene and Holocene age (Graymer, 2000). The site is located approximately 2,200 feet east-northeast of the shores of Lake Merritt. The active northwest trending Hayward fault is located approximately 3½ miles east of the site.

The East Bay Plain is regionally divided into two major groundwater basins: the San Pablo and the San Francisco Basin. These basins are tectonic depressions that are filled primarily with a sequence of coalescing alluvial fans. The San Francisco Basin is further divided into seven sub-areas. The site is located in the Oakland Sub-Area, which is filled primarily by alluvial deposits that range from 300 to 700 feet thick with no well-defined aquitards (CRWQCB, 1999). Under natural conditions, the direction of groundwater flow in the East Bay Plain is east to west and correlates with topography.

The site is located approximately 2,200 feet west of the Lake Merritt. Lake Merritt is connected to the Oakland Inner Harbor to the west, which connects to the San Francisco Bay. The San Francisco Bay is located approximately 2.7 miles west and 3.5 miles south of the site. Groundwater flow direction is predominantly to the southwest towards the San Francisco Bay, consistent with site data and the local topography. Groundwater recharge of the East Bay Plain occurs by infiltration from precipitation, irrigation, pipe leakage, and stream flow.

SITE CONDITIONS

Site Geology

The local geology and hydrogeology of the site was evaluated using boring logs from the most recent investigation and earlier investigations. The lithology of site consists primarily of tight clay and silt units extending approximately 10 to 12 fbgs. Underlying this unit is a sand unit extending to approximately 17 fbgs. Silts and clay, with lenses of sand (up to 1 foot thick), extend beneath the sand unit to approximately 30 fbgs, the total depth explored. Boring logs for the most recent investigation are presented in Attachment B.

Site Hydrogeology

The depth to groundwater beneath the site has varied over time and has ranged from approximately 9 fbgs to 15 fbgs. Currently, groundwater is encountered at depths ranging from approximately 11 fbgs to 14 fbgs. Cumulative results of groundwater monitoring and sampling indicate that the groundwater flow direction is predominantly towards the southwest. The most recent groundwater data from January 19, 2007, indicate that the groundwater flow direction is towards the southwest with a hydraulic

gradient of 0.015. A groundwater elevation map for the January 19, 2007, sampling event is shown on Plate 3. Cumulative results of groundwater monitoring and sampling events are summarized in Tables 1A and 1B.

Petroleum Hydrocarbon Concentrations in Soil

Historical analytical data indicate that the maximum concentrations of residual TPHg and benzene were located in the vicinity of borings B1A, B3A, B1, B2, MW6H, TG2, and TG3 at the north and east part of the site. Soil sample locations are shown on Plate 2. Cumulative soil analytical results are summarized in Tables 3A, 3B, and 3C.

Dissolved Constituent Distribution in Groundwater

Historical analytical data indicate that the maximum dissolved TPHg, benzene, and MTBE concentrations were reported in samples collected from wells MW6H and RW1. Cumulative groundwater analytical results are summarized in Tables 1A and 1B, and grab groundwater results are summarized in Tables 4A, 4B, and 4C. A plan view showing select analytical results for the January 19, 2007, sampling event is presented on Plate 4.

SUBSURFACE INVESTIGATION

On Monday February 5, 2007, ERI obtained drilling permits from the Alameda County Public Works Agency. On Thursday February 8, 2007, ERI obtained approved traffic control plans, an excavation permit, and an obstruction permit from the City of Oakland Public Works Department (the City), to perform drilling activities in the public right-of-way along Telegraph Avenue. However, on February 13, 2007, during activities to locate subsurface utilities, it was concluded that the permitted locations were too close to underground utilities. The boring locations were adjusted, and the City required ERI to submit new traffic control plans for the adjusted locations. ERI submitted the adjusted traffic plans to the City on February 14, 2007. In addition Mr. Joe Watson of the City recommended to ERI that fieldwork activities be rescheduled to allow 10 business days until approval of the new traffic control plans. Based on this recommendation, ERI moved clearance and drilling activities from February 20, 2007, to March 1, 2007. The new traffic control plans were approved on February 26, 2007, and a new obstruction permit was obtained from the City on February 27, 2007. Copies of the permits are included as Attachment C.

ERI observed the advancement of five direct-push soil borings (B5 through B9) between March 1 and March 7, 2007. The locations of the borings are shown on Plate 2. Field work was performed in accordance with the Work Plans, ERI's field protocol (Attachment D), and a site-specific health and safety plan.

Subsurface Clearance

Prior to drilling, ERI contacted Underground Service Alert (USA) and contracted a private utility locating company to locate underground utilities at the site. Between March 1 and 7, 2007, ERI observed Woodward Drilling Company (Woodward) of Rio Vista, California, perform clearance activities at six locations (B5, B5R, and B6 through B9) using a water knife and/or hand auger.

Subsurface utility pipes were discovered during clearance activities at locations B5, B5R, and B6, and the locations were abandoned. Borings B7, B8, and B9 were cleared to depths of 10.5 fbgs, 10.5 fbgs, and 11.5 fbgs, respectively. Though a subsurface utility pipe was not encountered at boring B8, the trend of the pipe discovered at borings B5R and B6 suggested close proximity to the boring. ERI personnel concluded that use of a direct-push rig could shake a filter pack and destabilize or crack the pipe. Therefore, the boring was advanced to a depth of 14.0 fbgs by use of a hand auger, to obtain a grab groundwater sample.

Soil Assessment

Between March 2 and March 7, 2007, ERI observed Woodward advance soil borings B7 and B9 to depths of 26 fbgs and 30 fbgs, respectively, using a direct-push drill rig with dual-walled sampling rods. Continuous-core soil samples were collected with a piston-type sampler. Soil samples were identified using visual and manual methods and classified according to the Unified Soil Classification System (USCS), and boring logs were constructed. Boring logs are presented in Attachment B. Select soil samples were preserved for laboratory analysis.

Groundwater Assessment

Between March 2 and March 7, 2007, ERI observed Woodward advance soil borings B7 through B9 to obtain depth-discrete grab groundwater samples from within identified water-bearing units. A grab groundwater sample of first encountered groundwater was bailed through a temporary casing at boring B8. Grab groundwater samples were obtained at borings B7 and B9 by advancing a dual-walled sampling rod and exposing a screen within each water-bearing unit.

Upon completion of sampling, each boring was filled with cement/bentonite grout using a tremie, and the surface was refinished to match the surrounding ground conditions.

<u>Laboratory Analytical Methods – Soil Samples</u>

ERI collected soil samples and submitted them for analysis to TestAmerica Analytical Testing Corporation (TestAmerica) of Morgan Hill, California, a California state-certified laboratory, under Chain-of-Custody protocol. The soil samples were analyzed for TPHg, TPHd, and TPHmo using Environmental Protection Agency (EPA) Method 8015B; BTEX using EPA Method 8021B; and MTBE, oxygenated compounds (ethyl tertiary butyl ether [ETBE], tertiary amyl methyl ether [TAME], tertiary butyl alcohol [TBA], and di-isopropyl ether [DIPE]), lead scavengers (1,2-dibromoethane [EDB] and 1,2-dichloroethane [1,2-DCA]), and ethanol using EPA Method 8260B. Laboratory analytical reports and Chain-of-Custody records are provided in Attachment E. Soil sample analytical results are summarized in Tables 3A, 3B, and 3C. A plan view of select current analytical results for soil samples is presented on Plate 5.

<u>Laboratory Analytical Methods - Grab Groundwater Samples</u>

ERI submitted grab groundwater samples collected from the soil borings to TestAmerica, under Chain-of-Custody protocol. The samples were analyzed for TPHg, TPHd, and TPHmo using EPA Method 8015B; BTEX using EPA Methods 8021B and 8260B; and MTBE, oxygenated compounds, lead scavengers, and ethanol using EPA Method 8260B. Laboratory analytical reports and Chain-of-Custody records are provided in Attachment E. Grab groundwater results are summarized in Tables 4A, 4B, and 4C. A plan view of select current grab groundwater results for samples collected during this investigation is presented on Plate 6.

Waste Containment and Disposal

Soil, water-knife sludge, and rinsate water generated during clearance activities and advancement of the direct-push borings was contained in three 55-gallon drums on site. ERI collected four samples from the drums and submitted the samples to TestAmerica, under Chain-of-Custody protocol. The samples were composited by the laboratory and analyzed for TPHg, TPHd, and TPHmo using EPA Method 8015B; BTEX using EPA method 8021B; MTBE, oxygenated compounds, lead scavengers, and ethanol using EPA Method 8260B; and total lead using EPA Method 6010B. The laboratory analytical report and Chain-of-Custody record are provided in Attachment E.

ERI will submit waste disposal documentation under separate cover, following transport and disposal to Exxon Mobil-approved facilities.

Site Survey

On March 8, 2007, ERI observed Morrow Surveying (Morrow) of West Sacramento, California, survey the soil boring locations. The resultant map is the basis of the site maps included in this report. A copy of the survey report is provided in Attachment F.

RESULTS OF INVESTIGATION

Site Geology and Hydrogeology

Consistent with previous investigations, boring logs demonstrate that the site vicinity consists primarily of clay and silt units inter-bedded with sand units approximately 2 to 4 feet in thickness at approximately 12 fbgs, 21 fbgs, and 28 fbgs.

Groundwater samples were collected from boring B7 at depths of 15 and 22 fbgs. A groundwater sample was collected from boring B8 at a depth 14 fbgs. Groundwater samples were collected from boring B9 at depths of approximately 15 and 23 fbgs.

Soil Conditions

Soil samples were collected from the five soil borings (B5 through B9). Sixteen soil samples were collected as part of the current site investigation and submitted for laboratory analysis. A summary of current and historical soil analytical results are summarized in Tables 3A, 3B, and 3C. Laboratory analytical reports and Chain-of-Custody records are presented in Attachment E. A plan view of select current analytical results of soil samples is presented on Plate 5.

Lateral and Vertical Delineation of Petroleum Hydrocarbons in Soil

Results of this investigation indicate that the maximum concentrations of residual petroleum hydrocarbon concentrations are present in soil samples collected at boring B9 between 10 and 11 fbgs. The vertical extent of petroleum hydrocarbons in soil at borings B7, B8, and B9 is defined at depths of 21 fbgs, 10 fbgs, and 23.5 fbgs, respectively, with concentrations not detected at or above the laboratory reporting limits.

Groundwater Conditions

Five grab groundwater samples were collected during the current assessment activities: two each from soil borings B7 (15 fbgs and 22 fbgs) and B9 (15 fbgs and 23 fbgs), and one from B8 (14 fbgs). A summary of current and historical grab groundwater analytical results are summarized in Tables 4A, 4B, and 4C. Laboratory analytical reports and Chain-of-Custody records are presented in Attachment E. A plan view of select current analytical results of groundwater samples is presented on Plate 6.

Lateral and Vertical Delineation of Petroleum Hydrocarbons in Groundwater

Both grab groundwater samples collected at 15 fbgs and 22 fbgs at boring B7 contained concentrations of TPHd at 66 μ g/L and 220 μ g/L, respectively; however, the laboratory report stated that the hydrocarbon pattern did not resemble the requested fuel. With the exception of a MTBE concentration of 0.54 μ g/L at 15 fbgs, other constituents were below the laboratory reporting limits.

The grab groundwater sample collected at boring B8 at a depth of approximately 14 fbgs contained concentrations of TPHd and TPHmo at 1,900 μ g/L and 2,800 μ g/L, respectively; however, the laboratory report stated that the hydrocarbon pattern did not resemble the requested fuel. Other constituents were below the laboratory reporting limits.

Both grab groundwater samples collected at boring B9 at depths of approximately 15 fbgs and 23 fbgs contained concentrations of TPHg, BTEX, and MTBE. Additionally, both samples contained concentrations of TPHd; however, the laboratory report stated that the hydrocarbon pattern did not

resemble the requested fuel. In addition, the sample collected at 23 fbgs contained concentrations of DIPE at 3.4 μ g/L. The highest concentration of TPHd, TPHg, BTEX, and MTBE occurred in the sample at 15 fbgs with concentrations of 1,000 μ g/L, 38,000 μ g/L, 15,000 μ g/L, 890 μ g/L, 700 μ g/L, 1,700 μ g/L, and 120 μ g/L, respectively.

SUMMARY

Based on the information available to date, the following summary is presented:

- During initial subsurface utility mark-out activities, subsurface utilities were identified in the vicinity
 of proposed boring locations. The locations were moved necessitating new traffic control plans
 and obstruction permits from the City, and delaying the start of clearance activities by nine days.
- ERI observed Woodward perform clearance activities at six locations along Telegraph Avenue between 22nd Steet and West Grand Avenue. Subsurface utility pipes were discovered in three of the six locations (B5, B5R, and B6). These locations were abandoned.
- Because of the proximity of a subsurface utility pipe, boring B8 was advanced by use of a hand auger to first-encountered groundwater to obtain a grab groundwater sample.
- ERI observed Woodward advance borings B7 and B9 to depths of 26 fbgs and 30 fbgs, respectively, using a direct-push drill rig with dual-walled sampling rods. Continuous-core soil samples were collected with a piston-type sampler.
- A total of 16 soil samples were submitted for chemical analysis.
- A total of five grab groundwater samples were submitted for chemical analysis.
- Boring B9 contained maximum concentrations of residual hydrocarbons in soil from approximately 10 to 11 fbgs.
- Borings B8 and B9 contained the maximum concentrations of dissolved-phase hydrocarbons in groundwater at a depth of approximately 14 fbgs.

CONCLUSIONS AND RECOMMENDATIONS

The results of this investigation indicate the following:

- The lateral and vertical extent of dissolved petroleum hydrocarbons is not defined to the east of the site.
- The lateral extent of petroleum hydrocarbons in soil is defined by borings B7 and B8.
- The vertical extent of petroleum hydrocarbons in soil is defined by boring B9 at 23.5 fbgs.
- The vertical extent of petroleum hydrocarbons in groundwater is not defined on site at boring B9.
- The downgradient (southeast) extent of TPHg (<50 μg/L), TPHmo (<48 μg/L), benzene (<0.50 μg/L), and MTBE (0.54 μg/L) is defined by boring B7.

As directed by the County, ERI is currently preparing a Site Conceptual Model (SCM) for this site. Data obtained as part of this investigation will be incorporated and presented in conjunction with historical data within the SCM. As part of the SCM, an overview of site conditions will be presented and recommendations for further environmental assessment activities will be proposed.

DOCUMENT DISTRIBUTION

ERI recommends forwarding copies of this report to:

Mr. Steven Plunkett Alameda County Health Care Services Agency Department of Environmental Health 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502-6577

Mr. Chuck Headlee California Regional Water Quality Control Board San Francisco Bay Region 1515 Clay Street, Suite 1400 Oakland, California 94612

Mr. Robert C. Ehlers, M.S., P.E. The Valero Companies Environmental Liability Management 685 West Third Street Hanford, California 93230

LIMITATIONS

This report was prepared in accordance with generally accepted standards of environmental practice in California at the time this investigation was performed. This report has been prepared for Exxon Mobil, and any reliance on this report by third parties shall be at such party's sole risk.

Please contact Ms. Paula Sime, ERI's project manager for this site, at (707) 766-2000 with any questions regarding this report.

Sincerely,

Environmental Resolutions, Inc.

Rebekah Westrup

Heidi Dieffenbach-Carle

P.G. 6793

References	
Table 1A: Table 1B: Table 2: Table 3A: Table 3B	Cumulative Groundwater Monitoring and Sampling Data Additional Cumulative Groundwater Monitoring and Sampling Data Well Construction Details Cumulative Laboratory Analytical Results of Soil Samples Additional Cumulative Laboratory Analytical Results of Soil Samples –
Table 3C	VOCs Additional Cumulative Laboratory Analytical Results of Soil Samples – Metals
Table 4A: Table 4B	Cumulative Laboratory Analytical Results of Grab Groundwater Samples Additional Cumulative Laboratory Analytical Results of Grab Groundwater Samples -VOCs
Table 4C	Additional Cumulative Laboratory Analytical Results of Grab Groundwater Samples – Metals
Plate 1: Plate 2: Plate 3: Plate 4: Plate 5: Plate 6:	Site Vicinity Map Generalized Site Plan Groundwater Elevation Map – January 19, 2007 Select Analytical Results – January 19, 2007 Select Residual Hydrocarbons in Soil Analytical Results Select Grab Groundwater Analytical Results
Attachment A: Attachment B: Attachment C: Attachment D: Attachment E: Attachment F:	

REFERENCES

Alton Geoscience Inc. (Alton). April 25, 1991. Preliminary Soil Assessment Report, Exxon Company U.S.A., Exxon Station No 7-0235, 2225 Telegraph Ave., Oakland, California.

California Regional Water Quality Control Board San Francisco Bay Region Groundwater Committee (CRWQCB). June 1999. East Bay Plain Groundwater Basin Beneficial Use Evaluation Report, Alameda and Contra Costa Counties, CA.

EA Engineering, Science, and Technology (EA). January 1992. Report of Tank Replacement and Closure Sampling Exxon Retail Site 7-0235, 225 Telegraph Avenue, Oakland, California.

Environmental Resolutions, Inc (ERI). May 11, 2000. Soil and Groundwater Investigation Report for Exxon Service Station 7-0235, 2225 Telegraph Avenue, Oakland, California.

Environmental Resolutions, Inc (ERI). September 7, 2001a. Well Installation Report for Former Exxon Service Station 7-0235, 2225 Telegraph Avenue, Oakland, California.

Environmental Resolutions, Inc (ERI). October 19, 2001b. Dual-Phase Extraction Pilot Test, Former Exxon Service Station 7-0235, 2225 Telegraph Avenue, Oakland, California.

Environmental Resolutions, Inc (ERI). November 25, 2002. *Preferential Pathway Study and Work Plan for Off-Site Delineation at Former Exxon Service Station 7-0235, 2225 Telegraph Avenue, Oakland, California.*

Graymer, R.W. 2000. Geologic map and map database of the Oakland metropolitan area, Alameda, Contra Costa, and San Francisco Counties, California. USGS, Miscellaneous Field Studies MF-2342.

Harding Lawson Associates (HLA). July 20, 1988. Subsurface Investigation Texaco Station No. 62488000195, 2225 Telegraph Avenue, Oakland, California. HLA Job No. 2251,052.04.

Harding Lawson Associates (HLA). June 22, 1989. Environmental Assessment Former Texaco Station No. 62488000195, 2225 Telegraph Avenue, Oakland, California.

Harding Lawson Associates (HLA). September 10, 1992. Quarterly Technical Report, Second Quarter 1992, Exxon Station, 2225 Telegraph Avenue, Oakland, California.

Hickenbottom, Kelvin and Muir, Kenneth S. June 1988. *Geohydrogeology and Groundwater Quality Overview of the East Bay Plain Area, Alameda County, CA*. Alameda County Flood Control and Water Conservation District. 83p.

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	т	E	
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(μg/L)	(µg/L)	X (
MW6A	June 1988	***	Well installe	ed.							(1-5/-)	(199/11)	(pg/L)	(µg/L)
MW6A	06/24/88	98,99i									<0.5	<1	-2	
MW6A	07/11/88	98.99i	13.25	85,74					-	***			<2	<1
MW6A	10/20/88	98.99i									0.6	<1	<2	
MW6A	12/15/88	98.99i	13.40	85.59i										<1
MW6A	09/07/89	98,99i					ND		-		2.0	ND	ND	
MW6A	05/11/90	98.99i	12.87	86.12i			<500				150	6.2	<0.25	ND
MW6A	10/16/90	98.99i	13.27	85.72i								0.2		13
MW6A	12/06/90	98.99i	13.28	85,71i										
MW6A	02/08/91	98.99i	12.49	86.50i										
MW6A	05/07/91	98.99i	11.94	87.05i			2,700				700	64		
MW6A	06/26/91	98,99i	12.87	86.12i									67	74
MW6A	08/05/91	98.99i	13.44	85.55i								1000		
MW6A	08/14/91	98.99i	13.47	85.52i			ND					U ess		
MW6A	09/11/91	98.99i	13.48	85.51i							3.6	<0.5	<0.5	<0.5
MW6A	10/16/91	98.99i	13.64	85.35i								***		
MW6A	12/30/91		Well damag	ed.								-		
MW6A	05/02/92		Well destroy											
MW6B	June 1988		Well installe	ed.										
MW6B	06/24/88	98.81i		130										
MW6B	07/11/88	98,81i	12.86	85.95i							<0.5	<1	<2	5.0
MW6B	10/20/88	98.81i				_		+				***		
MW6B	12/15/88	98.81i	12.94	85.87i							4.1	<1	<2	<1
MW6B	09/07/89	98.81i					2,700							
MW6B	04/30/90	98.81i	12.53	86.28i			168				70	3.0	ND	160
MW6B	10/16/90	98.81i	12.73	86.08i							45	8.0	60	22
MW6B	12/06/90	98.81i	12.74	86.07i			***					2 <u>2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1</u>		
MW6B	01/14/91	98.81i	12.57	86.24i			***					***		
MW6B	02/08/91	98.81i	12.16	86.65i			****) ****		
MW6B	04/02/91	98.81i	11.50	87.31i			222					***		
MW6B	05/07/91	98.81i	12.02	86.79i	_		***					***		
MW6B	05/31/91	98.81i	12.40				3,300				240	6.0	20	660
MW6B	06/26/91	98.81i	12.40	86.41i	***							***		
MW6B	08/05/91			86.12i	555		***					****		
MW6B	08/14/91	98.81i	12.95	85.86i			***		_			***		
MW6B	09/11/91	98.81i	12.93	85.88i	***		980				9.1	42	310	150
MW6B	10/16/91	98.81i	13.01	85.80i	555		****					2 000 2		
MW6B	12/30/91	98.81i	13.09	85.72i	***		110					7227		
MW6B	12/30/91	98.81i	12.62	86,19i	***		-					***		
MW6B		98.81i	44.04				1,200				46	<5.0	85	220
	02/25/92	98.81i	11.81	87.00i	****		100							
MW6B	03/25/92	98.81i	11.58	87.23i	777		190				31	8.6	84	8.6
MW6B	06/16/92	15.34	12.54	2.80	102		1,700				44	1.7	7.2	230
MW6B	09/08/92	15.34	12.87	2.47	NLPH		2,900				35	8.3	110	330
MW6B	11/05/92	15.34	12.70	2.64	NLPH		1,400				29	<0.5	75	190
MW6B	12/14/92	15.34	12.19	3.15	NLPH									190

Former Exxon Service Station 7-0235
2225 Telegraph Avenue
Oakland, California
(Page 2 of 16)

Well	Sampling Date	TOC (feet)	DTW (feet)	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	Т	E	Х
MW6B	01/28/93			(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L
MW6B		15.34	11.39	3.95	NLPH		***		***			11-3-17	(hg/c)	
	02/11/93	15,34	11.70	3.64	NLPH	***	210				1.2	<0.5	2.8	
MW6B	03/09/93	15.34	11.70	3.64	NLPH									4.3
MW6B	04/14/93	15.34	11.87	3.47	NLPH				222				***	-
MW6B	05/11/93	15.34	12.22	3,12	NLPH		570							
MW6B	06/17/93	15.34	12.46	2.88	NLPH						54	2.4	37	36
MW6B	07/26/93	15.34	12.72	2.58	NLPH				****					
MW6B	08/10/93	15.34	12.82	2.52	NLPH		4.000		***					
MW6B	09/21/93	15.34	13,08	2.26			1,300		***		48	2.4	28	44
MW6B	10/27/93	15.34			NLPH	~~=			777					
MW6B			13.18	2.16	NLPH		1,300				23	1.7	25	250
	11/23/93	15.34	13.07	2.27	NLPH				***		7000			
MW6B	12/17/93	15.34												***
MW6B	02/16/94	15.34	12.07	3.27			300						-	
MW6B	05/31/94	15.34	12.42	2.92	NLPH		690				16	<0.5	3.5	2.4
MW6B	08/30/94	17.48j	13.02	4.46	NLPH		260				21	3.9	11	36
MW6B	11/11/94	17.48j	11.72	5.76	NLPH		300				4	0.62	0.82	4
MW6B	02/27/95	17.48j	11.84	5.64	NLPH						60	2	1.2	2.4
MW6B	05/30/95	17.48	12.09				180			***	28	2.6	0.65	1.6
MW6B	08/30/95	17.48j	12.76	5.39	NLPH		200			***	23	3.6	0.88	2.3
MW6B	11/26/96	17.46j 17.48j		4.72	NLPH		120			42	3.8	3.6	0.61	0.69
MW6B	02/27/97	17.48j	12.26	5.22	NLPH		<50			<30	<0.5	<0.5	<0.5	<0.8
MW6B	05/21/97	17.48j	11.73	5.75	NLPH		<50			<30	< 0.5	<0.5	<0.5	0.80
MW6B	08/18/97	17.48j	12.70	4.78	NLPH		<50			<30	<0.5	<0.5	<0.5	<0.50
MW6B	03/13/98	17.48j	12.89	4.59	NLPH		380			<30	4.3	<0.5	1.2	1.5
MW6B	04/20/98	17.46j	11.15	6.33	NLPH		360			<6.2	93	4.9	4.1	1.3
MW6B	07/21/98	21.37	11.49	5.99	NLPH		110			5.5	19	1,3	1.5	3.9
MW6B	10/06/98	21.37	12.18	9.19	NLPH		<50			8.7	0.84	0.59	<0.5	<0.5
MW6B	01/11/99	21.37	12.70	8.67	NLPH		190			6.0	2.4	0.56	0.51	1.2
MW6B	04/08/99	21.37	12.48	8.89	NLPH		50			3.9	1.2	<0.5	<0.5	0.95
MW6B	07/19/99	21.37	11.52	9.85	NLPH		85			14.0	4.4	<0.5	<0.5	<0.5
MW6B	07/27/99	21.37	11.39 12.71	9.98	NLPH		<50			<2.50	< 0.5	< 0.5	<0.5	<0.5
MW6B	10/25/99	21.37	12.71	8.66	NLPH					(****)	***	1222		
MW6B	01/27/00	21.37	11.80	88.8	NLPH		260			<2	2.3	<0.5	<0.5	<0.5
MW6B	04/03/00	21.37	11.61	9.57	NLPH		770			13	210	4.8	4.9	13
MW6B	07/05/00	21.37	12.27	9.76 9.10	NLPH		670			3.4	110	6.6	3.8	9.45
MW6B	10/04/00	21.37	12.67	8.70	NLPH		<50			2,1	0.89	< 0.5	<0.5	<0.5
/W6B	10/05/00	21.37	12.07	0.70	NLPH		<50	5446		54	< 0.5	<0.5	<0.5	2
MW6B	01/04/01	21.37	12.47	8.90	NLPH		450	<1,000		***		3422	-	-
/W6B	04/03/01	21.37	11.81	9.56	NLPH		<50	****		35	<0.5	<0.5	< 0.5	<0.5
MW6B	07/05/01	21,37	12.44	8.93	NLPH		<50 <50	***		7.8	< 0.5	< 0.5	<0.5	<0.5
MW6B	10/03/01	21.37	12.52	8.85	NLPH	Men	<50			3	<0.5	<0.5	<0.5	<0.5
/IW6B	Oct-01	21.09		ed in compliance		 6 roquiromant	310	***		10	2.1	< 0.5	6.5	11.6
/W6B	01/02/02	21.09	11.25	9.84	NLPH									
MW6B	04/02/02	21.09	11.72	9.37	NLPH		710		7000 C	21.8	99.5	4.40	3,30	7.40
MW6B	07/01/02	21.09	12.34	8.75	NLPH		<50.0	<100		12.2	0.60	< 0.50	< 0.50	<0.50
/W6B	10/02/02	21.09	12.71	8.38			<50	<100a		10.7	<0.5	<0.5	<0.5	<0.5
/W6B	01/07/03	21.09	11.65	9.44	NLPH NLPH		<50.0	<100	200	10.9	< 0.5	< 0.5	<0.5	<0.5
/IW6B	06/17/03	21.09	12.09	9.44	NLPH		82.5	<50	27.8	20.8	3.7	0,5	<0.5	0.8
/W6B	07/16/03	21.09	12.09	8.80	NLPH		<50.0	<100	6.10a	7.3	0.50	<0.5	<0.5	<0.5
	15.7	- 1500	14.60	0,00	INLEH		<50.0	<100	8.5	11.0	< 0.50	<0.5	<0.5	<0.5

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 3 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В			
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)			T	E	X
MW6B	10/07/03	21.09	12.63	8.46	NLPH	<50	<50.0	<100		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW6B	01/14/04	21.09	11.50	9.59	NLPH	54	62.0	<100	3.10	4.1	< 0.50	<0.5	<0.5	<0.5
MW6B	06/03/04	21.09	12.12	8.97	NLPH		56.0	<100	11.0	9.0	2.10	<0.5	<0.5	<0.5
MW6B	08/12/04	21.09	C	C	C	<50c	94.0c	<100 <100c	5.90	6.2	0.60	<0.5	<0.5	<0.5
MW6B	11/04/04	21.09	12.27	8.82	NLPH	<50	<50.0		3,40c		0.70c	<0.5c	<0.5c	0.9c
MW6B	02/01/05	21.09	11,48	9.61	NLPH	<100		143	2.60		<0.50	<0,5	<0.5	0.7
MW6B	05/03/05	21.09	11.48	9.61	NLPH	<50	55.9	<100	7.50		1.30	<0.5	< 0.5	< 0.5
MW6B	08/04/05	21.09	12.23	8.86	NLPH		<50.0	<100	4.90		0.50	<0.5	<0.5	8.0
MW6B	10/27/05	21.09	12.60	8.49	NLPH	<50.0	<50.0	<100	5.99		<0.500	< 0.500	< 0.500	0.692
MW6B	01/26/06	21.09	11.39	9.70	NLPH	<50.0	<50.0	<50.0	1,65		<0.50	0.94f	< 0.50	1.29
MW6B	04/28/06	21.09	10.99	10.10		83d	510	<500	12		130	12	14	39
MW6B	07/05/06	21.09	12.05	9.04	NLPH	240d	3,100	<470	43		920h	110	130	290
MW6B	10/27/06	21.09			NLPH	<47.6	79.4	<95.2	11.4		2.95	<1.00	<1.00	<3.00
MW6B	01/19/07	21.09	12.53	8.56	NLPH	<47	<50.0	<470	2.25		0.63	<0.50	<0.50	< 0.50
MITTOD	01/13/07	21.05	12.05	9.04	NLPH	<47	<50.0	<470	3.75		<0.50	< 0.50	<0.50	< 0.50
MW6C	06/15/88	99.89i	Well installe	ad										
MW6C	05/10/90			rilled into recov	ary wall DM/2									
			11011 0101-0	illied litto recovi	ery well it ws									
MW6D	07/06/88	98.78i	Well installe	he										
MW6D	05/10/90			rilled into recov	en/ well RW2									
				illog illo recovi	cry well itvv2									
MW6E	10/04/88	98.99i	Well installe	ed:										
MW6E	10/20/88	98.99i												
MW6E	12/15/88	98.99i	13.70	85,29i							1.1	<2	<1	3.4
MW6E	09/07/89	98.99i												
MW6E	04/30/90	98.99i	13.43	85.56i			220				3.0	ND	ND	ND
MW6E	10/16/90	98.99i	13.77	85.22i	9	Makeny	250				57	<5.0	<5.0	53
MW6E	12/06/90	98.99i	13.95	85.04i	6									
MW6E	01/14/91	98.99i	13.95	85.04i									***	
MW6E	02/08/91	98.99i	13.20	85.79i									***	
MW6E	04/02/91	98.99i	12,28	86.71i									***	
MW6E	05/07/91	98.99i	13.48										-	
MW6E	05/31/91	98.99i	14.09	85.51i			160				32	1.0	2.2	1.4
MW6E	06/26/91	98.99i	12.54	84.90i						-		-		***
MW6E	08/05/91	98.99i		86.45i								***		
MW6E	08/14/91	98.99i	14.39	84.60i								•••	(1 000)	***
MW6E	09/11/91		14.18	84,81i			ND				0.9	<0.5	<0.5	< 0.5
MW6E	10/16/91	98.99i	14.73	84.26i								***		
MW6E		98.99i	14.40	84.59i										5000
	12/30/91	98.99i	13.39	85.60i								-		544
MW6E	12/31/91	98.99i					90				3.1	< 0.5	< 0.5	<0.5
MW6E	02/25/92	98.99i	13.16	85.83 i								***	·	***
MW6E	03/25/92	98.99i	12.15	86.84i	-		830	500			41	1.0	3.8	16
MW6E	06/16/92	15.23	13.54	1.69	***		3,400				300	23	68	510
MW6E	09/08/92	15,23	14.78	0.45	NLPH		480				27	<0.5	3.6	21
MW6E	11/05/92	15.23										-010	3.0	21
MW6E	12/14/92	15.23										***		
MW6E	01/28/93	15.23	11.62	3,61	NLPH				-		***		***	
MW6E	02/11/93	15,23	12.85	2.38	NLPH		270				15	<0.5	<0.5	
MW6E	03/09/93	15.23	12.83	2.40	NLPH		***				10	~0.5	<0.5	8.7
MW6E	04/14/93	15.23			NLPH						(***	****
MW6E	05/11/93	15.23	13.59	1.64	NLPH		<50				2.3	<0.5	1.4	3.2
MW6E	06/17/93	15.23	13.74	1.49	NLPH		***				2.0	~0.5	1.4	
														2000

Former Exxon Service Station 7-0235
2225 Telegraph Avenue
Oakland, California
(Page 4 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	T	E	×
ID MW6E	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		
MW6E	07/26/93	15.23	14.01	1.22	NLPH			***			(P9/L)	(19/12)	(µg/L)	(μg/L
MW6E	08/10/93	15.23	14.13	1.10	NLPH		1,700				130	2.7	22	
MW6E	09/21/93	15.23	14.20	1.03	NLPH							2.1	23	140
MW6E	10/27/93	15.23	14.34	0.89	NLPH		100				6.0	<0.5		
MW6E	11/23/93	15.23	13.97	1.26	NLPH							-0. 5	<0.5	<0.5
MW6E	12/17/93	15.23	13,08	2.15	NLPH							***		
MW6E	02/16/94	15.23	13.34	1.89	NLPH	***	640				45	<0.5	12	
MW6E	05/31/94	15.23	13.82	1.41	NLPH	1,575	52				1.5	0.97	<0.5	15
MW6E	08/30/94	17.63j	14.32	3.31	NLPH	***	920				22	0.98		<0.5
	11/11/94	17.63	13.92	3.71	NLPH	***	910				13	2.4	5.2	33
MW6E	02/27/95	17.63	12.96	4.67	NLPH	***	<50				1.9	1.3	13	2.5
MW6E	05/30/95	17.63	13.20	4.43	NLPH	***	<50				<0.5	<0.5	<0.5	0.83
MW6E	08/30/95	17.63	13.85	3.78	NLPH		1,500			11	91	2.3	<0,5	<0.5
MW6E	11/26/96	17.63	12.94	4.69	NLPH		<50			<30	1.1		56	59
MW6E	02/27/97	17.63	12.28	5.35	NLPH	***	<50			<30	<0.5	<0.5	<0.5	<0.5
MW6E	05/21/97	17.63	13.60	4.03	NLPH		160			<5		<0.5	<0.5	<0.5
MW6E	08/18/97	17.63	13.75	3.88	NLPH		66			<30	10	1.4	5.5	4.8
MW6E	03/13/98	17.63	11.36	6.27	NLPH	***	<50			<2.5	<0.5	<0.5	<0.5	< 0.5
MW6E	04/20/98	17.63	11.88	5.75	NLPH		<50				<0.5	<0.5	<0.5	<0.5
MW6E	07/21/98	21.58	13.10	8.48	NLPH		1,200	-		<2.5	<0.5	<0.5	<0.5	< 0.5
MW6E	10/06/98	21.58	13.55	8.03	NLPH	***	<50			<10	81	3.1	28	77
MW6E	01/11/99	21.58	13.40	8.18	NLPH		<50			6.6	1.4	0.51	<0.5	0.97
MW6E	04/08/99	21.58	12.04	9.54	NLPH		<50			5.1	<0.5	<0.5	<0.5	< 0.5
MW6E	07/19/99	21.58	11.59	9.99	NLPH	***				4.7	<0.5	<0.5	<0,5	< 0.5
MW6E	07/27/99	21.58	13.65	7.93	NLPH					***		3666	***	
MW6E	10/25/99	21.58	13.52	8.06	NLPH	-11	<50			0.5	***			1,555
MW6E	01/27/00	21.58	11.71	9.87	NLPH		<50			2.5	<0.5	<0.5	<0.5	< 0.5
MW6E	04/03/00	21.58	12.11	9.47	NLPH		<50			2.3	<0.5	<0.5	<0.5	< 0.5
MW6E	07/05/00	21.58	12.91	8.67	NLPH	***	<50			<2	0.51	<0.5	< 0.5	< 0.5
MW6E	10/04/00	21.58	13.35	8.23	NLPH		<50			<2	3.7	<0.5	< 0.5	<0.5
MW6E	10/05/00	21.58			***			-4.000		<2	4.1	<0.5	<0.5	<0.5
MW6E	01/04/01	21.58	13.09	8.49	NLPH			<1,000		5555	· ·	***	222	
MW6E	04/03/01	21.58	12.39	9.19	NLPH		61	5775		<2	11	<0.5	< 0.5	< 0.5
MW6E	07/05/01	21.58	13.21	8.37	NLPH	3210	<50	***		<2	< 0.5	<0.5	< 0.5	<0.5
MW6E	10/03/01	21.58	13.30	8.28	NLPH	(****)	210	***		<2	80	< 0.5	0.94	2.3
MW6E	Oct-01	21.24					<50	****		<2	2.8	< 0.5	<0.5	<0.5
MW6E	01/02/02	21.24	10.11	ed in complianc										
MW6E	04/02/02	21.24		11.13	NLPH	(444)	<100		2555	<0.5	< 0.50	< 0.50	< 0.50	< 0.50
MW6E	07/01/02	21.24	12.11	9.13	NLPH	***	<50.0	<100	***	0.70	< 0.50	<0.50	<0.50	<0.50
MW6E	10/02/02	21.24	12.46	8.78	NLPH		56.0	<100a		<0.5	19.9	<0.5	<0.5	<0.5
MW6E	01/07/03		13.48	7.76	NLPH		<50.0	<100	***	0.8	0.5	<0.5	<0.5	<0.5
MW6E	06/17/03	21.24	11.81	9.43	NLPH		<50.0	<50	< 0.50	<0.5	0.5	<0.5	<0.5	<0.5
MW6E	07/16/03	21.24	12.72	8.52	NLPH		<50.0	153	< 0.50	<0.5	<0.50	<0.5	<0.5	<0.5
MW6E	10/07/03	21.24	12.92	8.32	NLPH		<50.0	<100	< 0.50	<0.5	4.50	<0.5	<0.5	<0.5
MW6E		21.24	13.34	7.90	NLPH	<50	<50.0	<100	0.60	0.9	2.50	<0.5	<0.5	<0.5 <0.5
MW6E	01/14/04	21.24	11.92	9.32	NLPH	<50	<50.0	<100	< 0.50	<0.5	0.50	<0.5	<0.5	<0.5
	06/03/04	21.24	12.97	8.27	NLPH	<50	<50.0	<100	< 0.50	<0.5	<0.50	<0.5	<0.5	
MW6E	08/12/04	21.24	c	c	C	<50c	<50.0c	<100c	<0.50c		4.30c	<0.5c		<0.5
MW6E	11/04/04	21.24	12.68	8.56	NLPH	<50	<50.0	124	<0.50		<0.50	<0.5	<0.5c	0.8c
WW6E	02/01/05	21.24	11.75	9.49	NLPH	<100	<50.0	<100	<0.50	na-d	<0.50	<0.5	< 0.5	<0.5
AW6E	05/03/05	21.24	11.93	9.31	NLPH	64d	<50.0	116	<0.50		<0.50	<0.5 <0.5	<0.5	<0.5
MW6E	08/04/05	21.24	12.92	8.32	NLPH	96.2d	87.9	122	<0.500		14-1		<0.5	<0.5
WW6E	10/27/05	21.24	13.24	8.00	NLPH	<50.0	<50.0	<50.0	<0.500		1.44	<0.500	< 0.500	0.792

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 5 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B				
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)			В	Т	E	X
MW6E	01/26/06	21.24	11.78	9.46	NLPH	<50	<50		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW6E	04/28/06	21.24	11.27	9.97	NLPH	<47		<500	<0,50		7.2	0.67	0.71	2.0
MW6E	07/05/06	21.24	12.67	8.57	NLPH		<50	<470	<0.50		<0.50	< 0.50	< 0.50	< 0.50
MW6E	10/27/06	21.24	13.34	7.90	NLPH	149	<50.0	316	<0.500	***	<1.00	<1.00	<1.00	<3.00
MW6E	01/19/07	21.24	12.66	8.58	NLPH	<47	<50.0	<470	<0.500	***	<0.50	0.81	< 0.50	1.26
	01710101	21,24	12.00	0.30	NLPH	<47	<50.0	<470	<0.500	•••	2.33	< 0.50	< 0.50	< 0.50
MW6F	10/05/88	99.91i	Well install	ed										
MW6F	10/25/88	99.91i		eu. 			ND							
MW6F	12/15/88	99,91i	14.48	85.43i			ND				<0.5	<1	<2	2.4
MW6F	09/07/89	99.91i		05.451										
MW6F	04/30/90	99.91i	14.14	85.77i			ND				ND	ND	ND	ND
MW6F	10/16/90	99.91i					ND				ND	ND	ND	ND
MW6F	12/06/90		14.77	85.14i										
MW6F	01/14/91	99.91i	14.81	85.10i	_									
MW6F		99.91i	14.73	85.18i		***	~==	-						
	02/08/91	99.91i	13.73	86.18ii										
MW6F	04/02/91	99.91i	12.38	87.53i				***						
MW6F	05/07/91	99.91i	13.67	86.24i			ND				ND	<0.5	<0.5	<0.5
MW6F	05/31/91	99.91i	14.43	85.48i										
MW6F	06/26/91	99.91i	14.81	85.10i										
MW6F	08/05/91	99.91i	14.96	84.95i								-		
MW6F	08/14/91	99.91i	14.87	85.04i			ND				ND	<0.5	<0.5	<0.5
MW6F	09/11/91	99.91i	15.11	84.80i										
MW6F	10/16/91	99.91i	15.16	84.75i										200
MW6F	12/30/91	99.91i	13.78	86.13i								***	***	300
MW6F	12/31/91	99.91i		_			ND			_	ND	<0.5		-0.5
MW6F	02/25/92	99.91i	12.68	87.23i							IND	~0.5	<0.5	<0.5
MW6F	03/25/92	99.91i	11.93	87.98i			ND			_	ND	<0.5	-0.5	
MW6F	06/16/92	16.46	14.34	2.12			ND				ND		<0.5	<0.5
MW6F	09/08/92	16.46	14.75	1.71	NLPH		<50					<0.5	<0.5	<0.5
MW6F	11/05/92	16.46	14.35	2.11	NLPH		<50				<0.5	<0.5	<0.5	<0.5
MW6F	12/14/92	16.46	12.90	3.56	NLPH						<0,5	<0.5	<0.5	< 0.5
MW6F	01/28/93	16.46	11.60	4.86	NLPH						***	***		****
MW6F	02/11/93	16.46	12.25	4.21	NLPH	~~~	<50				-0.5			****
MW6F	03/09/93	16.46	12.50	3.96	NLPH						<0.5	<0.5	<0.5	<0.5
MW6F	04/14/93	16.46	12,71	3.75	NLPH									
MW6F	05/11/93	16.46	13.63	2.83	NLPH		<50							***
MW6F	06/17/93	16.46	14.02	2.44	NLPH					~	***	***	***	****
MW6F	07/26/93	16.46			742111						-	***	***	***
MW6F	08/10/93	16.46												***
MW6F	09/21/93	16.46	14.80	1.66	NLPH		440					***		
MW6F	10/27/93	16.46	14.85								0.00	***		-
MW6F	11/23/93	16.46	Well Inacce	1.61	NLPH		<50				<0.5	< 0.5	< 0.5	<0.5
MW6F	12/17/93													
MW6F		16.46	13.86	2.60	NLPH						***	0		300
	02/16/94	16.46	13.08	3.38	NLPH		<50				<0.5	<0.5	< 0.5	<0.5
MW6F	05/31/94	16,46	14.06	2.40	NLPH		<50				< 0.5	< 0.5	<0.5	<0.5
MW6F	08/30/94	18.58j	14.84	3.74	NLPH		<50				<0.5	<0.5	<0.5	<0.5
MW6F	11/11/94	18.58j	12.60	5.98	NLPH		<50				<0.5	0.54	<0.5	<0.5
MW6F	02/27/95	18.58j	12.75	5.83	NLPH		<50				6.2	3.0	0.82	3.5
MW6F	05/30/95	18.58j	13.16	5.42	NLPH		<50				<0.5	<0.5	<0.5	<0.5
MW6F	08/30/95	18.58j	14.31	4.27	NLPH		<50			<10	<0.5	<0.5	<0.5	<0.5
MW6F	11/26/96	18.58j	13.29	5.29	NLPH		<50			<30	< 0.5	<0.5	<0.5	<0.5
MW6F	02/27/97	18.58j			344						***	***	-0.0	-0.0

Former Exxon Service Station 7-0235

2225 Telegraph Avenue

Oakland, California

(Page 6 of 16)

ID	Sampling Date	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	T	E	Х
MW6F		(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		
	05/21/97	18.58j	14.18	4.40	NLPH			***		***	(P9/L)	(pg/L)	(µg/L)	(µg/l
MW6F	08/18/97	18.58j	14.69	3.89	NLPH	****	***					2000		***
MW6F	03/13/98	18.58j	10.93	7.65	NLPH		<50			<2.5	<0.5			
MW6F	04/20/98	18.58j	11.77	6.81	NLPH					-2.0		<0.5	<0.5	<0.
MW6F	07/21/98	22.51	13.62	8.89	NLPH		-							
MW6F	10/06/98	22.51	13.52	8.99	NLPH					***				
MW6F	01/11/99	22.51	14.06	8.45	NLPH									***
MW6F	04/08/99	22.51	11.86	10.65	NLPH									
MW6F	07/19/99	22,51												
MW6F	07/27/99	22.51	Well Inacce	essible.				***						
MW6F	10/25/99	22.51	12.63	9.88	NLPH			***	***					
MW6F	01/27/00	22.51	12.23	10.28	NLPH									
MW6F	04/03/00	22.51	12.11	10.40	NLPH									
MW6F	07/05/00	22.51	13.38	9.13	NLPH	-	<50	0.000		<2				
MW6F	10/04/00	22.51	14.02	8.49	NLPH		<50	(200			<0.5	<0.5	<0.5	<0.
MW6F	10/05/00	22.51			757			<1,000		<2	<0.5	<0.5	<0.5	0.7
MW6F	01/04/01	22.51	13,69	8.82	NLPH		<50	~1,000				*		
MW6F	04/03/01	22.51	12.55	9.96	NLPH		<50		-	<2	<0.5	<0.5	<0.5	<0.
MW6F	07/05/01	22.51	13.74	8.77	NLPH		<50		***	<2	<0.5	<0.5	< 0.5	<0.
MW6F	10/03/01	22.51	13.82	8.69	NLPH		<50			<2	<0.5	<0.5	< 0.5	<0.
MW6F	Oct-01	22.17	Well survey	ed in compliand			te	****		<2	<0.5	<0.5	<0.5	<0
MW6F	01/02/02	22.17	9.16	13.01	NLPH	o requiremen	<100			1.507.52				
MW6F	04/02/02	22.17	12.14	10.03	NLPH		<50.0			<0.5	<0.50	< 0.50	< 0.50	< 0.5
MW6F	07/01/02	22.17	13.46	8.71	NLPH		<50.0	<100	0	<0.50	<0.50	< 0.50	< 0.50	< 0.5
MW6F	10/02/02	22.17	14.19	7.98	NLPH		<50.0	<100a		<0.5	<0.5	< 0.5	<0.5	<0.
MW6F	01/07/03	22.17	11.73	10.44	NLPH		<50.0	<100		<0.5	<0.5	<0.5	<0.5	<0.
MW6F	06/17/03	22.17	13.13	9.04	NLPH			<50	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5
MW6F	07/16/03	22.17	13.51	8.66	NLPH		<50.0	<100	<0.50	<0.5	<0.50	< 0.5	< 0.5	<0.
MW6F	10/07/03	22.17	14.05	8.12	NLPH	<50	<50.0	<100	<0.50	<0.5	< 0.50	< 0.5	<0.5	<0.
MW6F	01/14/04	22.17	11.90	10.27	NLPH	<50	<50.0	<100	<0.50	<0.5	<0.50	<0.5	<0.5	<0.5
MW6F	06/03/04	22.17	13.45	8.72	NLPH	<50 <50	<50.0	<100	<0.50	<0.5	<0.50	< 0.5	<0.5	<0.5
MW6F	08/12/04	22.17	C	c	C	52c	<50.0	<100	<0.50	<0.5	< 0.50	< 0.5	<0.5	<0.
MW6F	11/04/04	22.17	13.03	9.14	NLPH		<50.0c	<100c	<0.50c	***	<0.50c	<0.5c	<0.5c	< 0.5
MW6F	02/01/05	22.17	11.56	10.61	NLPH	<50	<50.0	109	<0.50	***	<0.50	< 0.5	< 0.5	<0.5
MW6F	05/03/05	22.17	11.92	10.25	NLPH	<100	<50.0	<100	<0.50		<0.50	< 0.5	< 0.5	<0.
MW6F	08/04/05	22.17	13.42			<50	<50.0	<100	<0.50	***	< 0.50	< 0.5	< 0.5	<0.
MW6F	10/27/05	22.17	13.88	8.75	NLPH	<50.0	<50.0	<100	<0.500		<0.500	< 0.500	< 0.500	<0.50
MW6F	01/26/06	22.17		8.29	NLPH	<50.0	<50.0	<50.0	<0.500	777	< 0.50	0.93f	<0.50	<0.5
MW6F	04/28/06	22.17	11.83	10.34	NLPH	<50	<50	<500	< 0.50	***	< 0.50	<0.50	<0.50	<0.5
MW6F	04/26/06		10.96	11.21	NLPH	<47	<50	<470	< 0.50	***	< 0.50	< 0.50	<0.50	<0.5
MW6F	10/27/06	22.17	13.05	9.12	NLPH	<47.6	<50.0	<95.2	<0.500		<1.00	<1.00	<1.00	<3.0
MW6F	01/19/07	22.17	14.06	8.11	NLPH	<47	<50.0	<470	<0.500		< 0.50	<0.50	<0.50	<0.5
IAI & A OL	01/19/07	22.17	13.06	9.11	NLPH	<47	<50.0	<470	<0.500		<0.50	<0.50	<0.50	<0.5
MW6G	11/16/88	99.16i	Well installe	ed.										
MW6G	12/07/88	99.16i							***					
MW6G	12/15/88	99.16i	12.22	86.94i			ND		222		-0.5			
MW6G	09/07/89	99.16i					ND				<0.5	<1	<2	<1
MW6G	04/30/90	99.16i	11,73	87.43i			ND				ND	ND	ND	ND
MW6G	10/16/90	99.16i	12.28	86.88i							ND	ND	ND	ND
MW6G	12/06/90	99.16i	12.27	86,89i										
									202					
MW6G	01/14/91	99.16i	12.14	87.02i										

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 7 of 16)

Well	Sampling	тос	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	T	E	Х
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		
MW6G	04/02/91	99.16i	10.03	89.13i	***					(1-5)	(µg/L)	(pg/L)	(µg/L)	(µg/L
MW6G	05/07/91	99.16i	11.00	88.16		***	ND	****	***	***	ND	<0.5	-0.5	
MW6G MW6G	05/31/91	99.16i	11.75	87.41i	***	***	***				,,,,,		<0.5	<0.5
	06/26/91	99.16i	12.91	86.25i										***
MW6G	08/05/91	99.16i	12.43	86.73i										
MW6G	08/14/91	99.16i	12.43	86.73i			ND				ND	<0.5	-0.5	
MW6G	09/11/91	99.16i	12.48	86.68i									<0.5	<0.5
MW6G	10/16/91	99.16i	12.64	86.52i										
MW6G	12/30/91	99.16i	11.80	87.36i										
MW6G	12/31/91	99.16i					ND							
MW6G	02/25/92	99.91i	10.32	88.84i							ND	<0.5	<0.5	<0.
MW6G	03/25/92	99.91i	9.93	89.23i			ND			-	4.15			
MW6G	06/16/92	14.71	11.88	2.83			ND				ND	<0.5	<0.5	<0.8
MW6G	09/08/92	14.71	12.20	2.51	NLPH		<50				ND	<0.5	<0.5	<0.5
MW6G	11/05/92	14.71	12.02	2.69	NLPH		<50				<0.5	<0.5	<0.5	<0.
MW6G	12/14/92	14.71	10.95	3.76	NLPH						<0.5	<0.5	<0.5	<0.
MW6G	01/28/93	14.71	9.56	5.15	NLPH									
MW6G	02/11/93	14.71	10.04	4.67	NLPH		<50							
MW6G	03/09/93	14.71	10.10	4.61	NLPH						<0.5	< 0.5	< 0.5	<0.
MW6G	04/14/93	14.71	10.43	4.28	NLPH									
MW6G	05/11/93	14.71	11.05	3.66	NLPH									
MW6G	06/17/93	14.71	11.49	3.22	NLPH		<50				< 0.5	<0.5	< 0.5	<0.
MW6G	07/26/93	14.71	11.98	2.73	NLPH									
MW6G	08/10/93	14.71	12.17	2.54					***					
MW6G	09/21/93	14.71	12.42	2.29	NLPH		<50		-		< 0.5	<0.5	< 0.5	<0.5
MW6G	10/27/93	14.71	13.47		NLPH					_				
MW6G	11/23/93	14.71	12.48	1.24	NLPH		<50				<0.5	<0.5	< 0.5	<0.5
MW6G	12/17/93	14.71		2.23	NLPH									
MW6G	02/16/94	14.71	11.19	3.52	NLPH									
MW6G	05/31/94		10.62	4.09	NLPH		<50				< 0.5	< 0.5	< 0.5	<0.5
MW6G	08/30/94	14.71	11.40	3.31	NLPH		<50				< 0.5	<0.5	<0.5	<0.5
MW6G		16.82j	12.32	4.50	NLPH		<50				<0.5	<0.5	<0.5	<0.5
	11/11/94	16.82j	11.06	5.76	NLPH		58				0.58	1.6	<0.5	1.6
MW6G	02/27/95	16.82j	10.32	6.50	NLPH		<50				0.86	0.99	<0.5	0.51
MW6G	05/30/95	16.82j	10.77	6.05	NLPH		<50		-		<0.5	<0.5	<0.5	<0.5
MW6G	08/30/95	16.82j	11.92	4.90	NLPH		<50			<10	<0.5	<0.5	<0.5	
MW6G	11/26/96	16.82j	11.12	5.70	NLPH		<50			<30	<0.5	<0.5	<0.5	<0.5
MW6G	02/27/97	16.82j									~	-0.0		<0.5
MW6G	05/21/97	16.82j	11.76	5.06	NLPH									
MW6G	08/18/97	16.82j	12.23	4.59	NLPH									
MW6G	03/13/98	16.82j	9.13	7.69	NLPH		<50			4.4	<0.5	-0.5		
MW6G	04/20/98	16.82j	9.73	7.09	NLPH						~ 0.5	<0.5	<0.5	<0.8
MW6G	07/21/98	20.72	11.15	9.57	NLPH						-			
MW6G	10/06/98	20.72	11.91	8.81	NLPH	brane.								
MW6G	01/11/99	20.72	12.00	8.72	NLPH									
MW6G	04/08/99	20.72	10.04	10.68	NLPH									
MW6G	07/19/99	20.72												
MW6G	07/27/99	20.72	11.75	8,97	NLPH									
MW6G	10/25/99	20.72	11.76	8.96					***					
MW6G	01/27/00	20.72			NLPH		****							
MW6G	04/03/00	20.72	11.46	9.26	NLPH									
MW6G	07/05/00		10.00	10.72	NLPH					Marin .				
MW6G	10/04/00	20.72	11.24	9.48	NLPH		<50			<2	<0.5	< 0.5	<0.5	<0.5
MANAG	10/04/00	20.72	11.88	8.84	NLPH		<50	-		<2	<0.5	<0.5	<0.5	<0.5

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 8 of 16)

Welf	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTDE occop					
ID	Date	(feet)	(feet)	(feet)	0000	(µg/L)	100 mm (20)		MTBE 8260B	MTBE 8021B	В	T	E	X
MW6G	10/05/00	20.72		(1001)	***		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW6G	01/04/01	20.72	11.56	9.16	NLPH	-		<1,000	255	***	***		***	
MW6G	04/03/01	20.72	10.45	10.27		-	<50			<2	< 0.5	<0.5	< 0.5	<0.5
MW6G	07/05/01	20.72	11.51	9.21	NLPH	-	<50			<2	<0.5	< 0.5	<0.5	<0.5
MW6G	10/03/01	20.72	11.63		NLPH	-	<50			<2	0.75	< 0.5	<0.5	<0.5
MW6G	Oct-01	20.46		9.09	NLPH	***	<50			<2	<0.5	<0.5	<0.5	<0.5
MW6G	01/02/02	20.46	9.15	ed in compliant										-0.0
MW6G	04/02/02			11.31	NLPH	-	<100	-	***	1.8	< 0.50	< 0.50	< 0.50	< 0.50
MW6G	07/01/02	20.46 20.46	10.19	10.27	NLPH	-	<50.0	<100	***	1.10	< 0.50	< 0.50	<0.50	<0.50
MW6G	10/02/02		11.35	9.11	NLPH	***	<50	<100a		1.3	<0.5	<0.5	<0.5	<0.50
MW6G	01/07/03	20.46	11.99	8.47	NLPH		<50.0	<100	***	0.7	< 0.5	<0.5	<0.5	<0.5
MW6G		20.46	9.97	10.49	NLPH		<50.0	<50	2.0	1.3	<0.5	<0.5	<0.5	
MW6G	06/17/03	20.46	10.98	9.48	NLPH	***	<50.0	<100	1.6	1.5	<0.50	<0.5	<0.5	<0.5
MW6G	07/16/03	20.46	11.37	9.09	NLPH	***	<50.0	<100	0.9	1.2	<0.50	<0.5	<0.5	<0.5
MW6G	10/07/03	20.46	11.90	8.56	NLPH	<50	<50.0	<100	0.80	0.8	< 0.50	<0.5	<0.5	<0.5
MW6G	01/14/04	20.46	10.10	10.36	NLPH	<50	<50.0	<100	1.40	1.0	<0.50	<0.5	<0.5	<0.5
MW6G	06/03/04	20.46	11.10	9.36	NLPH	<50	<50.0	<100	1.4	1.40	<0.50	<0.5	<0.5	<0.5 <0.5
MW6G	08/12/04	20.46	C	C	С	99c	<50.0c	101c	1.10c	3464	<0.50c	<0.5c	<0.5c	
MW6G	11/04/04	20.46	11.18	9.28	NLPH	<50	<50.0	<100	< 0.50		<0.50	<0.5	<0.5	<0.50
	02/01/05	20.46	9.79	10.67	NLPH	<100	<50.0	<100	3.40	***	<0.50	<0.5	<0.5	<0.5
MW6G	05/03/05	20.46	9.95	10.51	NLPH	<50	<50.0	<100	1.40	3	<0.50	<0.5		<0.5
MW6G	08/04/05	20.46	11.22	9.24	NLPH	<50.0	<50.0	<100	1.42	-	<0.500	<0.500	<0.5	<0.5
MW6G	10/27/05	20.46	11.76	8.70	NLPH	<50.0	<50.0	61.3	0.810	200	<0.50	0.93f	<0.500	< 0.500
MW6G	01/26/06	20.46	11.07	9.39	NLPH	<50	<50	<500	1.8		<0.50		<0.50	<0.50
MW6G	04/28/06	20.46	9.11	11.35	NLPH	<47	<50	<470	2.8	222	<0.50	<0.50	<0.50	< 0.50
MW6G	07/05/06	20.46	10.70	9.76	NLPH	88.6	<50.0	277	2.49			<0.50	<0.50	<0.50
MW6G	10/27/06	20.46	11.75	8.71	NLPH	<47	61.9	<470	1.40		<1.00	<1.00	<1.00	<3.00
MW6G	01/19/07	20.46	10.94	9.52	NLPH	<47	<50.0	<470	1.34		<0.50 <0.50	<0.50 <0.50	<0.50 <0.50	<0.50
MW6H	11/16/88											40.00	~0.30	<0.50
MW6H	12/07/88	07.00:	Well installe											
MW6H		97.93i	40.00								1,200	320	110	220
MW6H	12/15/88	97.93i	12,36	85.57i										
MW6H	09/07/89	97.93i					660				480	<10	16	<15
MW6H	04/30/90	97.93i	12,10	85.83i			630				700	39	31	50
MW6H	10/16/90 12/06/90	97.93i	12.18	85.75i										
MW6H		97.93i	12.29	85.64i										
MW6H	01/14/91	97.93i	12.22	85.71i								Name of the last o		
MW6H	02/08/91	97.93i	11.93	86.00i										
	04/02/91	97.93i	11.59	86.34i	~			~100						
MW6H	05/07/91	97.93i	12.24	85.69i			570				95	14	15	21
MW6H	05/31/91	97.93i	12.22	85.71i										
MW6H	06/26/91	97.93i	14.34	83.59i										
MW6H	08/05/91	97.93i	12.62	85.31i										
MW6H	08/14/91	97.93i	12.43	85.50i			540							
MW6H	09/11/91	97.93i	12.83	85.10i							52	9.9	11	18
MW6H	10/16/91	97.93i	12.71	85,22i						-				
MW6H	12/30/91	97.93i	12.16	85.77i										
MW6H	12/31/91	97.93i					790							
	02/25/92	97.93i	12.17	85.76i			790				52	28	22	42
MW6H		97.93i	11.65	86.28i			_							
MW6H MW6H	03/25/92			00.201			920				170	52	25	54
	03/25/92 06/16/92			2 35			460							
MW6H	06/16/92	14.47	12.12	2.35	 NI DH	S2	460	IL.			31	11	6.8	16
MW6H MW6H				2.35 2.17 2.42	 NLPH NLPH	L	460 780 3,400	 			31 69 500			16 18

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 9 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	T	E	X
	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		
MW6H	12/14/92	14.47	11.65	2.82	NLPH	****	***	***		(1-3)	(P9/L)	(pg/L)	(µg/L)	(μg/L
MW6H	01/28/93	14.47	11.57	2.90	NLPH									
MW6H	02/11/93	14.47	12.22	2.25	NLPH		2,500		****		410			
MW6H	03/09/93	14.47	12.02	2.45	NLPH					Acres 1	410	170	28	130
MW6H	04/14/93	14.47	12.02	2.45	NLPH									
MW6H	05/11/93	14.47	12.35	2.12	NLPH		4,200				490	270		
MW6H	06/17/93	14.47	12,22	2.25	NLPH						490	270	80	210
MW6H	07/26/93	14.47	12.32	2.15	NLPH									
MW6H	08/10/93	14.47	12.30	2.17	NLPH		650				00			
MW6H	09/21/93	14.47	12,79	1.68	NLPH		-				83	22	14	29
MW6H	10/27/93	14.47	13.93	0.54	NLPH		1,600				400			
MW6H	11/23/93	14.47	12.46	2.01	NLPH						130	90	29	130
MW6H	12/17/93	14.47	12.08	2.39	NLPH								****	***
MW6H	02/16/94	14.47	12.31	2.16	NLPH		<50				***	***		***
MW6H	05/31/94	14.47	12.46	2.01	NLPH		1,800		***		<0.5	<0.5	<0.5	2.9
MW6H	08/30/94	16.58j	12.72	3.86	NLPH		1,900				370	220	65	210
MW6H	11/11/94	16.58j	11.98	4.60	NLPH		13,000				130	90	19	86
MW6H	02/27/95	16.58j	11.89	4.69	NLPH		320				1,700	1,400	260	1,800
MW6H	05/30/95	16.58j	12.05	4.53	NLPH	***	2,300				450	120	28	79
MW6H	08/30/95	16.58j	12.34	4.24	NLPH		2,100				960	260	64	200
MW6H	11/26/96	16.58j	11.87	4.71	NLPH		1,200			50	590	35	24	74
MW6H	02/27/97	16.58	11.58	5.00	NLPH		1,800			<30	320	110	22	85
MW6H	05/21/97	16.58j	12.23	4.35	NLPH		1,100			<200	760	31	8.4	44
MW6H	08/18/97	16.58j	12.29	4.29	NLPH		870			81	640	18	5.4	45
MW6H	03/13/98	20.47	11,44	9.03	NLPH		5,300			26	200	3.6	2.4	7.4
MW6H	04/20/98	20.47	11.58	8.89	NLPH		6,000			<125	1,900	720	100	470
MW6H	07/21/98	20.47	11.97	8.50	NLPH					2,700	1,500	600	91	440
MW6H	10/06/98	20.47	12.23	8.24	NLPH		2,200			1,600	740	44	15	63
MW6H	01/11/99	20.47	12.17	8.30	NLPH		5,400			3,000	1,900	<25	<25	76
MW6H	04/08/99	20.47	11.56	8.91	NLPH		2,600			4,300	1,200	<12	<12	20
MW6H	07/19/99	20.47	11.71	8.76	NLPH		13,000			13,000	3,400	1,300	260	1,200
MW6H	07/27/99	20.47	12.39	8.08	NLPH		<2,000		8,520	6,920	732	<20	<20	<20
MW6H	10/25/99	20.47	12.16	8,31	NLPH		700					***	***	***
MW6H	01/27/00	20.47	11.60	8.87	NLPH		700			4,000	360	1.1	0.68	2
MW6H	04/03/00	20.47	11.62	8.85	NLPH		9,100		***	7,600	2,400	840	150	670
MW6H	07/05/00	20.47	11.93	8.54	NLPH		12,000			8,800	2,800	1,100	230	1,020
MW6H	10/04/00	20.47	12.16	8.31	NLPH		12,000			8,000	1,200	56	13	92
MW6H	10/05/00	20.47		0.51			4,400			8,400	1,500	23	12	80.6
MW6H	01/04/01	20.47	12.03	8.44	NI DU			<1,000		***		***	300	3
MW6H	04/03/01	20.47	11.73	8.74	NLPH NLPH		2,300			3,800	880	15	6.4	33.9
MW6H	07/05/01	20.47	11.98	8.49			7,800			5,100	2,000	730	140	590
MW6H	10/03/01	20.47	12.1	8.37	NLPH		2,300			3,200	630	25	10	40.8
MW6H	Oct-01	20.20			NLPH		1,400			550	270	5.6	4.2	11.6
MW6H	01/02/02			ed in complianc										0.0015
MW6H		20.20	11.14	9.06	NLPH		47,100			4,260	7,880	5,220	1,060	4,460
MW6H	04/02/02	20.20	11.68	8.52	NLPH		17,500	<500		1,590	2,280	1,290	282	1,090
MW6H	07/01/02	20.20	11.97	8.23	NLPH		5,370	<100a		1,910	1,170	200	44.0	158
MW6H	10/02/02	20.20	12.20	8.00	NLPH		2,570	<100		899	655	13.0	8.0	25.0
	01/07/03	20.20	11.58	8.62	NLPH		12,500	<50	2,500	1,700	2,480	1,340	250	1,120
MW6H	06/17/03	20.20	11.82	8.38	NLPH		6,330	<100	1,660	1,490	604	104	44.0	152
MW6H	07/16/03	20.20	12.89	7.31	NLPH		3,170	<100	1,170	1,270	614	20.0	9.5	31.8
MW6H	10/07/03	20.20	12.10	8.10	NLPH		2,090	<100	640	612	433	11.6	6.7	
MW6H	01/14/04	20.20	11.55	8.65	NLPH	390	6,320	<100	1,250	59.0	1,340	517	117	22.5 515

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 10 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTDE 20045				
ID	Date	(feet)	(feet)	(feet)		(µg/L)				MTBE 8021B	В	T	E	X
MW6H	06/03/04	20.20	11.92	8.28	NLPH	(Pg/C)	(µg/L) 3,330	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW6H	08/12/04	20.20	c	C	C	174c	1,920c	<100	632	604	546	128	38.4	140
MW6H	11/04/04	20.20	11.86	8.34	NLPH	578		<100c	426c	***	330c	17.9c	9.3c	35.3c
MW6H	02/01/05	20.20	11.55	8.65	NLPH	616	8,090	552	442		1,280	620	185	822
MW6H	05/03/05	20.20	11.54	8.66	NLPH		9,500	193	335		1,360	764	214	844
MW6H	08/04/05	20.20	11.89	8.31	NLPH	560d	9,120	168	323	***	1,320	886	245	928
MW6H	10/27/05	20.20	12.10	8.10		269d	1,810	143	268	***	349	57.0	20.1	70.0
MW6H	01/26/06	20.20	11.54		NLPH	228	942	98.5	164	***	154	23.1f	6.09	23.2
MW6H	04/28/06	20.20	11.34	8.66	NLPH	910d	20,000	<500	270	***	3,200	3,400	660	3,100
MW6H	07/05/06	20.20		8.91	NLPH	550d	11,000	<470	160		2,000	1,500	380	1,600
MW6H	10/27/06	20.20	11.90	8.30	NLPH	273	2,360	114	82.9	5 -11 ())	389	111	39.5	125
MW6H	01/19/07	20.20	12.08	8.12	NLPH	120d	1,460	<470	69.4	2000 S	215	27.9	16.2	43.4
11174011	01/15/07	20.20	11.81	8.39	NLPH	290d	4,950	<470	77.5		831	638	129	451
MW6I	11/17/88		Mollinst-II	a.										10000
MW6I	12/07/88	97.60i	Well installe											
MW6I	12/15/88	97.60i	10.00				ND				<0.5	<1	<2	<1
MW6I	09/07/89	97.60i	12.83	84.77i										
MW6I	04/30/90	97.60i	12.66	04.04			ND				ND	ND	ND	ND
MW6I	10/16/90	97.60i	12.71	84.94i			ND				ND	ND	ND	ND
MW6I	12/06/90	97.60i	12.71	84.89i 84.85i										***
MW6I	01/14/91	97.60i	12.75	85.05i			-							
MW6I	02/08/91	97.60i	12.33	85.28i										
MW6I	04/02/91	97.60i	12.22											
MW6I	05/07/91	97.60i		85.38i								-		
MW6I	05/31/91	97.60i	12.61 12.82	84.99i			ND				ND	< 0.5	<0.5	<0.5
MW6I	06/26/91	97.60i		84.78i										
MW6I	08/05/91		12.93	84.67i										
MW6I	08/14/91	97.60i 97.60i	13.01	84.59i										
MW6I	09/11/91		12.98	84.62i			ND				ND	<0.5	<0.5	<0.5
MW6I	10/16/91	97.60i	13.11	84.49i										
MW6I	12/30/91	97.60i	13.04	84.56i										
MW6I	12/30/91	97.60i	12.72	84.88i										
MW6I	02/25/92	97.60i					ND				ND	< 0.5	<0.5	< 0.5
		97.60i	12.45	85.15i										
MW6I	03/25/92	97.60i	12,12	85.48i			ND				ND	<0.5	<0.5	<0.5
MW61	06/16/92	14.14	12.75	1.39			ND				ND	<0.5	<0.5	<0.5
MW6I	09/08/92	14.14	12.84	1.30	NLPH		<50				<0.5	< 0.5	<0.5	<0.5
MW6I	11/05/92	14.14	12.75	1.39	NLPH		<50				< 0.5	< 0.5	<0.5	<0.5
MW6I	12/14/92	14.14	12.40	1.74	NLPH									_
MW6I	01/28/93	14.14	12.20	1.94	NLPH									_
MW6I	02/11/93	14.14	12.40	1.74	NLPH		<50				< 0.5	< 0.5	< 0.5	<0.5
	03/09/93	14.14	12.45	1.69	NLPH				h-ma				***	
MW6I	04/14/93	14.14	12.43	1.71	NLPH					_				
MW6I	05/11/93	14.14	12.73	1.41	NLPH		<50				<0.5	< 0.5	< 0.5	<0.5
MW6I	06/17/93	14.14	12.78	1.36	NLPH									
MW6I	07/26/93	14.14	12.92	1.22	NLPH									
MW6I	08/10/93	14.14	12.97	1,17	NLPH		<50				<0.5	<0.5	<0.5	
MW6I	09/21/93	14.14	13.02	1.12	NLPH							-0.5		<0.5
MW6I	10/27/93	14.14	13.10	1,04	NLPH		<50				<0.5	<0.5	-0.5	1.4
MW6I	11/23/93	14.14	13.02	1,12	NLPH							<0.5 	<0.5	1,1
MW6I	12/17/93	14.14	12.65	1.49	NLPH									
MW6I	02/16/94	14.14	12.66	1.48	NLPH		<50							
MW6i	05/31/94	14.14	12.90				-00				< 0.5	<0.5	< 0.5	< 0.5

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 11 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	Т	-	
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)			E	X
MW6I	08/30/94	16.26	13.06	3.20	NLPH	***	<50	113-1	(pg/c)		(µg/L)	(µg/L)	(µg/L)	(μg/L
MW6I	11/11/94	16.26j	15.20	1.06	NLPH		53			***	<0.5	<0.5	<0.5	<0.5
MW6I	02/27/95	16.26j	12.51	3.75	NLPH		<50				0.62	1.8	<0.5	2.0
MW6i	05/30/95	16.26j	12.57	3.69	NLPH		69				<0.5	<0.5	< 0.5	<0.
MW6I	08/30/95	16.26j	12.86	3.4	NLPH	***	<50				2.8	0.96	1.1	4.3
MW6I	11/26/96	16.26	12.45	3.81	NLPH	***	<50			<10	<0.5	<0.5	<0.5	<0.5
MW6I	02/27/97	16.26	12.24	4.02	NLPH					<30	<0.5	<0.5	<0.5	<0.
MW6I	05/21/97	16.26	12.82	3.44	NLPH		<50			<30	<0.5	< 0.5	<0.5	<0.
MW6I	08/18/97	16.26	12.81	3.45	NLPH	***	<50			<30	< 0.5	<0.5	< 0.5	<0.
MW61	03/13/98	16.26	(2787-2)			***	<50			<30	< 0.5	< 0.5	< 0.5	<0.
MW6I	04/20/98	16.26j	12.14	4.12	NLPH	Acce.								
MW6I	07/21/98	20.24	12.59	7.65	NLPH		<50	-		<2.5	< 0.5	< 0.5	<0.5	<0.
MW6I	10/06/98	20.24	12.81	7.43	NLPH		<50			<2.5	<0.5	< 0.5	<0.5	<0.
MW6I	01/11/99	20.24	12.74	7.50	NLPH									
MW6I	04/08/99	20.24	11.93	8.31		_	<50			<2.5	< 0.5	< 0.5	<0.5	<0.5
MW6I	07/19/99	20.24	11.75		NLPH									
MW6I	07/27/99	20.24	12.95	8.49	NLPH		281			17.6	35.4	9.1	7.4	30.7
MW6I	10/25/99	20.24		7.29	NLPH								·	
MW6I	01/27/00	20.24	12.79	7.45	NLPH									
MW6I	04/03/00		12.06	8.18	NLPH		<50			<2	< 0.5	<0.5		
		20.24	12.24	8.00	NLPH							~0.5	<0.5	<0.
MW6I MW6I	07/05/00	20.24	12.48	7.76	NLPH		<50			<2	<0.5			
	10/04/00	20.24										<0.5	<0.5	<0.
MW6I	10/05/00	20.24	10.200					<1.000						
MW6I	01/04/01	20.24	12.54	7.70	NLPH		<50			<2				***
MW6I	04/03/01	20.24	12.32	7.92	NLPH	***	<50			<2	<0.5	<0.5	<0.5	<0.8
MW6I	07/05/01	20.24	12.55	7.69	NLPH	***	<50				<0.5	<0.5	<0.5	<0.5
MW6I	10/03/01	20.24	12.67	7.57	NLPH		<50			<2	<0.5	<0.5	<0.5	<0.5
MW6I	Oct-01	19.87	Well surveye	d in complianc	e with AB 288	6 requiremen	ts			<2	<0.5	<0.5	<0.5	<0.5
MW6I	01/02/02	19.87	10.98	8.89	NLPH		<100			-0.5				
MW6I	04/02/02 b	19.87	12.24	7.63	NLPH	0.00				<0.5	<0.50	<0.50	< 0.50	< 0.5
MW6I	07/01/02	19.87	12.51	7.36	NLPH		<50	<100a						
√lW6I	10/02/02 b	19.87	12.72	7.15	NLPH					<0.5	<0.5	<0.5	<0.5	<0.5
MW6I	01/07/03	19.87	12.09	7.78	NLPH		<50.0	<50						
MW6I	06/17/03 b	19.87							1.10	<0.5	<0.5	<0.5	<0.5	<0.5
/IW6I	07/16/03	19.87	12.49	7.38	NLPH		<50.0		-0.50					
/W6I	10/07/03 ь	19.87	12.64	7.23	NLPH			<100	<0.50	<0.5	<0.50	<0.5	<0.5	< 0.5
/W6I	01/14/04	19.87	12.13	7.74	NLPH			400						
/IW6I	06/03/04 Ь	19.87	12.56	7.31	NLPH		<50.0	<100	<0.50	<0.5	< 0.50	< 0.5	< 0.5	< 0.5
/W6I	08/12/04	19.87	C	C										
/W6I	11/04/04 b	19.87	12.33		C	99c	<50.0c	155c	<0.50c		<0.50c	<0.5c	<0.5c	0.80
/IW6I	02/01/05	19.87		7.54	NLPH								***	
/IW6I	05/03/05 b		12.09	7.78	NLPH	<100	<50.0	<100	< 0.50	~	< 0.50	<0.5	<0.5	<0.5
/W6I		19.87	12.16	7.71	NLPH								-0.5	
	08/04/05	19.87	12.46	7.41	NLPH	54.2d	<50.0	<100	< 0.500		< 0.500	<0.500	<0.500	
/W6I	10/27/05 b	19.87	12.58	7.29	NLPH			Britany.		***		~0.500 		<0.50
/W6I	01/26/06	19.87	12.04	7.83	NLPH	<50	<50	<500	< 0.50		<0.50			-0.5
/W6I	04/28/06 b	19.87	11.94	7.93	NLPH						~0.50	<0.50	<0.50	<0.5
MW6I	07/05/06	19.87	13.06	6.81	NLPH	<47.6	<50.0	<95.2	< 0.500		<1.00	<1.00		
/W6I	10/27/06 Ь	19.87	12.64	7.23	NLPH				-0.000		<1.00 	<1.00	<1.00	<3.00
1W61	01/19/07	19.87	12.41	7.46	NLPH	<47	<50.0	<470	< 0.500		<0.50	<0.50		0.62
													< 0.50	

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 12 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	Ť	E	Х
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW6J	07/05/01	20.72	13.47	7.25	NLPH		<50	***		<2	<0.5	<0.5	<0.5	(µg/L) <0.5
MW6J	10/03/01	20.72	13.57	7.15	NLPH	***	<50	***	***	<2	<0.5	<0.5	<0.5	
MW6J	Oct-01	20.75	Well survey	yed in compliand		86 requiremen	ls.					0.0	~0.5	<0.5
MW6J	01/02/02	20.75	13.19	7.56	NLPH		<100			< 0.5	< 0.50	< 0.50	< 0.50	<0.50
MW6J	04/02/02	20.75	13.74	7.01	NLPH		<50.0	<100		1.00	0.80	<0.50	<0.50	0.80
	07/01/02	20.75	13.58	7.17	NLPH		<50	<100a		< 0.5	<0.5	<0.5	<0.5	<0.5
MW6J	10/02/02	20.75	13.79	6.96	NLPH		<50.0	<100		< 0.5	<0.5	<0.5	<0.5	<0.5
MW6J	01/07/03	20.75	13.49	7.26	NLPH		<50.0	<50	1.30	0.60	<0.5	<0.5	<0.5	
MW6J	06/17/03	20.75	13.76	6.99	NLPH		<50.0	<100	0.70	3.00	<0.50	<0.5		<0.5
MW6J	07/16/03	20.75	13.57	7.18	NLPH		<50.0	<100	0.60	0.70	<0.50	<0.5	<0.5	<0.5
MW6J	10/07/03	20.75	13.74	7.01	NLPH		<50.0	<100	1.20	1.1	<0.50		<0.5	<0.5
MW6J	01/14/04	20.75	13.46	7.29	NLPH	<50	<50.0	<100	1.80	1.8		<0.5	<0.5	<0.5
MW6J	06/03/04	20.75	13.72	7.03	NLPH	<50	<50.0	<100	10.3		<0.50	<0.5	<0.5	<0.5
MW6J	08/12/04	20.75	С	С	С	<50c	<50.0c	<100c		5.1	0.50	<0.5	<0.5	<0.5
MW6J	11/04/04	20.75	13.68	7.07	NLPH	<50	<50.00		3.30c		1.40c	2.1c	1.3c	4.6c
MW6J	02/01/05	20.75	13.47	7.28	NLPH	<100		116	3.50	***	0.50	0.5	< 0.5	< 0.5
MW6J	05/03/05	20.75	13.66	7.09	NLPH		<50.0	<100	5,50		<0.50	< 0.5	< 0.5	0.6
MW6J	08/04/05	20.75	13.75	7.00	NLPH	<50	<50.0	<100	3.00	***	0.70	0.9	0.6	0.8
MW6J	10/27/05	20.75	13.71	7.04	NLPH	55.8d	<50.0	130	<0.500		< 0.500	< 0.500	< 0.500	< 0.50
MW6J	01/26/06	20.75	13.49	7.26	NLPH	<50.0	<50.0	<50.0	2.48	-	< 0.50	0.94f	< 0.50	< 0.50
MW6J	04/28/06	20.75	13.56	7.19	NLPH	<50 <47	<50	<500	6.2	***	< 0.50	< 0.50	< 0.50	< 0.50
MW6J	07/05/06	20.75	13.75	7.00	NLPH	<47.6	<50	<470	7.2	***	< 0.50	< 0.50	< 0.50	< 0.50
MW6J	10/27/06	20.75	13.66	7.09	NLPH	<47	<50.0	<95.2	7.73	****	<1.00	<1.00	<1.00	<3.00
MW6J	01/19/07	20.75	13.51	7.24	NLPH	<47	67.7	<470	9.15		<0.50	<0.50	< 0.50	< 0.50
		20110	10.01	7.24	NLFH	\4 1	<50.0	<470	12.1		<0.50	<0.50	< 0.50	< 0.50
RW1	05/10/90	97.89i	Well installe	ed										
RW1	10/16/90	97.89i	12.24	85.65i										
RW1	01/14/91	97.89i	12.80	85.09i								-		
RW1	02/08/91	97.89i	12.53	85.36i										
RW1	05/31/91	97.89i	12.86	85.03i		_								
RW1	08/05/91	97.89i	13.19	84.70i										
RW1	08/13/91	97.89i	14.05	83.84i										
RW1	09/11/91	97.89i	15.96	81.93i										
RW1	10/16/91	97.89i	16.00	81.89i										
RW1	12/30/91	97.89i	12.65	85,24i										
RW1	02/25/92	97.89i	14.40	83.49i	_									
RW1	03/25/92	97.89i												
RW1	06/16/92	14.42	12.37	2.05			6,200							
RW1	09/08/92 throu	ugh 05/31/94	4 Not monitor	ed or sampled.			0,200				620	1,400	240	1,400
RW1	08/30/94	16.79	Well resurv											
RW1	08/30/94 throu	igh 10/16/98	3 Not monitore	ed or sampled.										
RW1	01/11/99	20.24	12.37	7.87	NLPH									
RW1	04/08/99	20.24	10.41	9.83	NLPH									
RW1	07/19/99	20.24		5.00	INLFF1									
RW1	07/27/99	20.24	12.76	7.48	NLPH									
RW1	10/25/99	20.24	12,50	7.74	NLPH									
RW1	01/27/00	20.24	12,11	8.13	NLPH									
RW1	04/03/00	20.24	12.07	8.13										
RW1	07/05/00	20.24			NLPH									
RW1	10/04/00			~~~										
		20.24												
RW1	10/05/00	20.24											_	
RW1	01/04/01	20.24	13.90	6.34	NLPH		8,000			2,500	1,200	65	250	258
RW1	04/03/01	20.24	11.92	8.32	NLPH		4,100			610	62	<2.5	18	61
RW1	07/05/01	20.24	Well inacce	essible								-10	,0	OI

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 13 of 16)

144 11		1,000												
Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	Т	-	
ID DW4	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		E	X
RW1	10/03/01	20.24	12.32	8.32	NLPH		11,000			4,100	1,900	(µg/L)	(µg/L)	(µg/L)
RW1	Oct-01	20.43	Well surve	ed in complian	ice with AB 28	86 requirement	S.			4,100	1,900	780	150	700
RW1	01/02/02	20.43	10.85	9.58	NLPH		32,000			7,760	250			
RW1	04/02/02	20,43	11.72	8.71	NLPH		4,220	<500	***	922	358	2,270	894	4,820
RW1	07/01/02	20.43	12.17	8.26	NLPH		2,500	<100a	***		172	22.5	106	340
RW1	10/02/02	20.43	12.44	7.99	NLPH		2,970	1,720		986	176	8.0	71.0	75.0
RW1	01/07/03	20.43	11.64	8.79	NLPH		2,210	1,340	4.040	1,310	197	11.0	70.0	69.0
RW1	06/17/03	20.43	11.98	8.45	NLPH		3,850	316	1,010	747	134	12.0	33.0	53.0
RW1	07/16/03	20.43	12.11	8.32	NLPH		2,640		847	645	48.9	38.7	46.1	197
RW1	10/07/03	20.43	12.35	8.08	NLPH	1,340		2,080	615	730	78.5	20.0	47.5	166
RW1	01/14/04	20.43	11.61	8.82	NLPH	4,240	2,310	1,040	578	744	118	7.6	25.1	52.1
RW1	06/03/04	20.43	12,12	8.31	NLPH		4,230	5,640	328	7.8	52.7	65.8	42.7	543
RW1	08/12/04	20.43	C	C C	C		2,910	1,840	250	234	79.9	6.0	28.6	67.2
RW1	11/04/04	20.43	12.06	8.37	NLPH	0.570	1,980c	164c	107c	***	146c	5.7c	18.1c	10.90
RW1	02/01/05	20.43	11.55	8.88		2,570	127,000	1,790	386	-	130	5,150	4,020	24,30
RW1	05/03/05	20.43	11.58		NLPH	3,530	2,880	4,680	78.7		25.3	13.3	49,3	258
RW1	08/04/05	20.43		8.85	NLPH	6,830d,e	2,490	14,600	91.3		33,8	18.4	17.3	97.7
RW1	10/27/05	20.43	12.10	8.33	NLPH	2,430d	3,080	3,410	49.6		193	20.4	48.2	117
RW1	01/26/06	20.43	12.32	8.11	NLPH	1,970	348	2,960	36.3		9.40	1.99f	2.22	5.36
RW1	04/28/06	20.43	11.55 11.23	8.88	NLPH	5,000d	640	<10,000	72		13	7.5	1.8	5.2
RW1	07/05/06	20.43	11.96	9.20	NLPH	950d	810	1,500	30		18	12	4.9	19
RW1	10/27/06	20.43	12.31	8.47	NLPH	687	1,020	886	40.0		25.0	4.77	4.67	11.4
RW1	01/19/07	20.43	11,96	8.12	NLPH	550d	937	600	45.4		21.1	4.82	5.37	8.14
	01110701	20.43	11,90	8.47	NLPH	2,500d	1,070	2,500	33.4		21.9	2.22	3.40	6.99
MW6D	07/06/88	98.78i	1A/+11 := -4-11										0.40	0.33
MW6D	07/11/88	98.78i	Well installe											
MW6D	10/20/88		13.48	85.24i	0.025 in,		***				220	27	<20	<10
MW6D	12/15/88	98.78i									710	74	22	110
MW6D	09/07/89	98.78i	13,44	85.34i					35					
MW6D	04/30/90	98.78i					2,200				600	26	58	31
MW6D	05/10/90	98.78i	13.19	85.59i			3,600				800	150	310	280
RW2	10/16/90	98.78i		rilled into recov	ery well RW2							100	310	200
RW2		98.11i	12.77	85.34i								***		
RW2	02/08/91	98.11i	13.11	85.00i						*				
	04/02/91	98.11i	11.70	86.41i										
RW2	05/07/91	98.11i	14.09	84.02i			11,000				3,200		450	
RW2	05/31/91	98.11i	16.01	82.10i							5,200	480	150	780
RW2	06/26/91	98.11i	14.60	83.51i			Stee							
RW2	08/05/91	98.11i	14.00	84.11i			***					700	-	
RW2	08/13/91	98.11i	21.30	76.81i									***	
RW2	09/11/91	98.11i	19.97	78.14i								***	-	
RW2	10/16/91	98.11i	15.19	82.92i			***					***	1775	
RW2	12/30/91	98-11i	13.19	84.92i			24					555	***	
RW2	02/25/92	98.11i	16,27	81.84i								***		
RW2	03/25/92	98.11i						***			***	7.7	1555	
RW2	06/16/92	14.61	12.86	1.75			20.000					****		
RW2	09/08/92 throu						28,000				2,900	1,000	120	2,700
RW2	08/30/94	17.02j	Well resurve											
RW2	08/30/94 throu		Not monitore	d or complet										
RW2	07/21/98													
RW2	10/06/98	20.44 20.44	12.65	7.79	NLPH		3,500			170	240	100	41	96
RW2	01/11/99	20.44	13.06 12.88	7.38	NLPH		3,200			200	120	48	56	120
RW2	04/08/99	20.44	11.76	7.56	NLPH		3,300			350	150	17	35	40
	S 4100133	20,44	11970	8.68	sheen				***					40

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 14 of 16)

15	Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В		E	
NY 07/1969 20.44 11.61 8.63 N.P.H 1.989				(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(ug/L)			• .		
Marcon 1005-1006 20.04 13.26 7.18 NLPH						NLPH									(µg/L
Marcon M													10000000		
NY DIAGNOS 20.44 12.70 7.74 NLPH 1.900 750 38 - 2.5 4.8 10.0						NLPH		1,800	***	***					
Marging Marg						NLPH		1,900	***						
Wide Division Wide Wid					8,47	NLPH		2,100	***						
100900					7.94	NLPH	***	2,300	***						
100,000 20,44 13,71 5,73 N.P.H 1,000 380 33 <2,5 13 17,7 17,9				12.97	7.47	NLPH		1,300	***						
070 070 070 070 070 070 070 070 070 070			20.44						<1.000						
0700001 20.04 12.10 8.34 NLPH 1.300				13.71	6.73	NLPH		1,000							
07/09/01 20 24 4 Not sampled: inaccessible, 19 1,000 - 240 35 4.4 34 100 100 100 100 100 100 100 100 100 10	RW2		20.44	12.10	8.34	NLPH		•							
MVZ	RW2	07/05/01	20.44	Not sample	d: inaccessible.		-							16	19.4
Wigner Wigner Well surveyed in complained with AB 2886 requirements. Wigner Wigner	RW2	10/03/01	20.44	12.8	7.64	NLPH									
1002/02 20.64 10.22 10.42 NLPH	RW2	Oct-01	20.64	Well survey	ed in compliance	e with AB 288	36 requirement	ts.			240	35	4.4	34	105
W2 040202 20.64 12.02 6.62 N.P.H 1.480 280 47.5 8.60 3.30 5.30 25.20 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1	RW2	01/02/02	20.64								70.0				
WY 100/202 20.64 12.51 8.13 NLPH	RW2	04/02/02	20.64	12.02										26.2	83.0
MYZ 100202 20.64 12.91 7.73 N.PH 720 <100 39.9 11.0 1.8 17.9 45.5 1.7 3.7 11.5 1	RW2	07/01/02	20.64										3.30	5.30	29.1
NYZ 01/17/03 20.64 11.61 9.03 NLPH	RW2	10/02/02											1.8	17.9	45.0
NYZ 06/17/03 20,64 12,32 8,32 NLPH 1,070 <100 26,4 29,7 13,9 4.4 11,8 16,1 18,1 18,1 18,1 18,1 18,1 18,1	RW2	01/07/03										5.5	1.7	3.7	11.9
MYZ	RW2										48.0	12.3	3.6	12.2	25.6
MYZ	RW2										29.7	13.9	4.4	11.8	
NYZ 01/14/04 20.64 11.70 8.94 NLPH 167 1.250 <100 128 8.4 18.0 4.4 8.6 10.1	RW2									19.3	32.9	6.60	4.1	10.9	
NYZ 06/03/04 20.64 12.93 7.71 NLPH 167 1,250 <100 128 8.4 18.0 4.4 8.6 10.1 NYZ 06/03/04 20.64 12.93 7.71 NLPH - 1,100 1,310 10.9 17.0 6.70 1.3 4.0 111.5 NYZ 08/12/04 20.64 12.30 8.34 NLPH 503 566 419 r 4,30 5.9 6.2 16.0 NYZ 11/04/04 20.64 12.30 8.34 NLPH 503 566 419 r 4,30 5.9 6.2 16.0 NYZ 02/01/05 20.64 11.61 9.03 NLPH 725 640 1,400 13.7 - 5,30 1.5 4.0 3.8 NYZ 05/03/05 20.64 11.72 8.92 NLPH 4830.e 1,130 801 8.20 - 10.3 1.1 5.8 6.3 NYZ 08/04/05 20.64 12.46 8.18 NLPH 3,020d 1,080 3,810 9.02 - 6,36 0,848 1.90 2.47 NYZ 01/21/05 20.64 12.71 7,93 NLPH 716 163 703 8.74 - <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50 <0.50	RW2									50.2	55.0	8.70	1.1		
1.00	RW2									128	8.4	18.0	4.4		
W2 1104104 20.64 12.30 8.34 NLPH 503 506 419 r	RW2							1,100	1,310	10.9	17.0	6.70	1.3		
W2 02/01/05 20.64 11.61 9.03 NLPH 725 640 1.400 13.7 5.30 1.5 4.0 3.8 W2 05/03/05 20.64 11.72 8.92 NLPH 4934,e 1,130 801 8.20 10.3 1.1 5.8 6.3 W2 08/04/05 20.64 12.46 8.18 NLPH 3,020d 1,060 3,810 9.02 6.36 0,848 1.90 2.4 W2 08/04/05 20.64 12.46 8.18 NLPH 3,020d 1,060 3,810 9.02 6.36 0,848 1.90 2.4 W2 01/27/05 20.84 12.71 7.93 NLPH 716 163 703 8.74 <0.50 <0.50 <0.50 <0.50 0.98 W2 01/28/06 20.64 11.24 9.40 NLPH 300d 680 470 2.6 9.7 1.2 5.3 2.9 W2 07/05/06 20.64 12.33 8.31 NLPH 284 946 221 <0.500 8.87 1.05 1.81 3.1 W2 01/19/07 20.64 12.29 8.35 NLPH 240d 920 470 4.59 <0.50 <0.50 <0.50 <0.50 3.65 3.06 W6 06/15/88 99.89 Well installed. Well installed. W6 06/15/88 99.89								1,110c	521c	32.8c		7.00c			
W2 05/03/05 20.64 11.72 8.92 NLPH 493d,e 1,130 8.10 8.20 1.03 1.1 5.8 6.3 6.34 1.05 6.06 1.05 1.0								506	419	r		4.30			
W2 08/04/05 20.64 11.72 8.92 NLPH 493d,e 1.130 801 8.20 10.3 1.1 5.8 6.3									1,400	13.7		5.30			
W2 10/27/05 20.64 12.71 7.93 NLPH 716 163 703 8.74								1,130	801	8.20		10.3			
1012-1016								1,060	3,810	9.02	-				
W2 04/28/06 20.64 11.24 9.40 NLPH 300d 680 470 2.6 9.7 1.2 5.3 2.9 W2 07/05/06 20.64 12.33 8.31 NLPH 284 946 221 40.500 8.87 1.05 1.81 3.14 W2 10/27/06 20.64 12.38 7.86 NLPH 240d 920 470 4.59 4.59 40.50 3.65 3.05 W2 01/19/07 20.64 12.29 8.35 NLPH 230d 794 470 3.72 6.32 2.27 40.50 3.65 W6C 06/15/88 99.89 Well installed. W6C 06/24/88 99.89 4.21 85.68	RW2								703	8.74					
W2 07/05/06 20.64 12.33 8.31 NLPH 284 946 221 <0.500 8.87 1.05 1.81 3.11 W2 10/27/06 20.64 12.78 7.86 NLPH 240d 920 <470 4.59 <0.50 <0.500 <0.50 3.65 3.05 W2 01/19/07 20.64 12.29 8.35 NLPH 230d 794 <470 3.72 6.32 2.27 <0.50 3.05 W6C 06/15/88 99.89i Well installed									<500	5.1					
10/27/06 20.64 12.33 8.31 NLPH 284 946 221 <0.500									<470	2.6		9.7			
Moc									221	< 0.500		8.87			
## 12.29							240d	920	<470	4.59	_				
W6C 06/15/88 99.89i Well installed. W6C 06/24/88 99.89i — — 7,400 7.1 170 2,30 W6C 07/11/88 99.89i —	RVVZ	01/19/07	20.64	12.29	8.35	NLPH	230d	794	<470	3.72					3.09
W6C 06/24/88 99.89i — — 7,400 7.1 170 2,30 W6C 07/11/88 99.89i — — — — 9,500 65 170 850 W6C 12/15/88 99.89i — — — 9,500 65 170 850 W6C 09/07/89 99.89i — — — 18,000 — 7,900 430 350 1,10 W6C 04/30/90 99.89i 13.81 86.68i — 30,000 — 7,900 430 350 1,10 W6C 05/10/90 — Well over-drilled into recovery well RW3 — <t< td=""><td>MW6C</td><td>06/15/88</td><td>99.89i</td><td>Well installe</td><td>ed:</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	MW6C	06/15/88	99.89i	Well installe	ed:										
W6C 07/11/88 99.89i 14.21 85.68i 7,400 7.1 170 2,30 W6C 10/20/88 99.89i 9,500 65 170 850 W6C 09/07/89 99.89i 14.10 85.79i 9,500 65 170 850 W6C 09/07/89 99.89i 13.81 86.68i 30,000 7,900 430 350 1,10 W6C 05/10/90 Well over-drilled into recovery well RW3 6,100 1,500 1,000 2,70 W3 10/16/90 98.97i 14.50 84.47i	MW6C	06/24/88	99.89i												
W6C 10/20/88 99.89i — — 9,500 65 170 850 W6C 12/15/88 99.89i — — 18,000 — 7,900 430 350 1,10 W6C 04/30/90 99.89i 13.81 86.68i — 30,000 — 6,100 1,500 1,000 2,70 W3 10/16/90 98.97i 13.29 85.68i — <td>MW6C</td> <td>07/11/88</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>7,400</td> <td>7.1</td> <td>170</td> <td>2,300</td>	MW6C	07/11/88										7,400	7.1	170	2,300
W6C 12/15/88 99.89i 14.10 85.79i — — 9,500 65 170 850 W6C 09/07/89 99.89i — — — 18,000 — 7,900 430 350 1,10 W6C 05/10/90 — Well over-drilled into recovery well RW3 — — 6,100 1,500 1,000 2,70 W3 10/16/90 98.97i 13.29 85.68i —	MW6C									***			***	***	***
W6C 09/07/89 99.89i 18,000 7,900 430 350 1,10 W6C 04/30/90 99.89i 13.81 86.68i 30,000 6,100 1,500 1,000 2,70 W3 10/16/90 98.97i 13.29 85.68i	MW6C									3000		9,500	65	170	850
W6C 04/30/90 99.89i 13.81 86.68i 30,000 7,900 430 350 1,10 W6C 05/10/90 Well over-drilled into recovery well RW3 6,100 1,500 1,000 2,70 W3 10/16/90 98.97i 13.29 85.68i — — W3 01/14/91 98.97i 14.50 84.47i — — W3 02/08/91 98.97i 11.39 87.58i — — W3 05/07/91 98.97i 12.47 86.50i — 5,800 — 4,200 640 220 670 W3 05/31/91 98.97i 15.50 83.47i — — — — — — W3 08/05/91 98.97i 13.69 85.28i — — — — — — — — —	MW6C								***	9			***		***
W6C 05/10/90 Well over-drilled into recovery well RW3 10/16/90 98.97i 13.29 85.68i	MW6C											7,900	430	350	1.100
W3 10/16/90 98.97i 13.29 85.68i — — — — — — — — — — — — — — — — — — —	MW6C							30,000	1000	****		6,100	1,500	1.000	
W3 01/14/91 98.97i 14.50 84.47i	RW3														_,, 00
W3 02/08/91 98.97i 12.54 86.43i	RW3											***	***		
W3 04/02/91 98.97i 11.39 87.58i 5.800 4.200 640 220 670 W3 05/31/91 98.97i 15.50 83.47i									***			***	***		
W3 05/07/91 98.97i 11.39 87.58i 5,800 4,200 640 220 670 W3 05/31/91 98.97i 15.50 83.47i												***	***		
W3 05/31/91 98.97i 12.47 86.50i 5,800 4,200 640 220 670 W3 05/31/91 98.97i 15.50 83.47i W3 08/05/91 98.97i 13.69 85.28i W3 08/13/91 98.97i 13.67 85.20i											-				
W3 06/26/91 98.97i 15.50 83.47i								5,800				4,200	640		
W3 08/25/91 98.97i 15.50 83.47i															
W3 08/05/91 98.97i 13.69 85.28i	RW3														
W3 08/13/91 98 97i 13 67 85 30i										u		***			
	RW3	08/13/91	98.97i	13.67	85.30i							222	10000		

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 15 of 16)

Well	Sampling	TOC	DTW	GW Elev.	SUBJ	TPHd	TPHg	TPHmo	MTBE 8260B	MTBE 8021B	В	T	E	
ID	Date	(feet)	(feet)	(feet)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		X
RW3	08/14/91	98.97i			***		3,800	***	11-5-7	(Þ9/	2,300		(µg/L)	(µg/L
RW3	09/11/91	98.97i	13.77	85.20i			2000000	2350			2,300	300	49	360
RW3	10/16/91	98.97i	16.66	82.311			2000	***						***
RW3	11/05/91		Well destro	yed.							777			***
RW3A	08/24/92		Well installe	ed in place of RV	V3.									
RW3A	08/24/92 thro	ugh 04/20/98	Not monitor	ed or sampled.										
RW3A	07/21/98	21.75	13.08	8.67	NLPH		280			16	0.7			
RW3A	10/06/98	21.89	13.72	8.17	NLPH		78				97	<1.2	<1.2	<1.
RW3A	01/11/99	21.75	12.00	9.75	NLPH	()	1.000			26	26	0.89	<0.5	<0.
RW3A	04/08/99	21.75	11.90	9.85	NLPH		130			230	490	5.0	<5.0	7.4
RW3A	07/19/99	21.75	11.75	10.00	NLPH	7/	989			11	70	<1.0	<1.0	<1.
RW3A	07/27/99	21.75	13.68	8.07	NLPH					16.4	393	6.40	5.70	15.0
RW3A	10/25/99	21.75	13.61	8.14	NLPH		150					***	***	***
RW3A	01/27/00	21.75	12.22	9.53	NLPH		500			19	53	<0.5	<0.5	<0.
RW3A	04/03/00	21.75	12.00	9.75	NLPH		1,100			12	210	0.59	1.40	2.2
RW3A	07/05/00	21.75	13.01	8.74	NLPH					16	420	1.6	1.8	1.4
RW3A	10/04/00	21.75	13.60	8.15			1,200	3000 P		16	440	1.4	2,5	1.9
RW3A	10/05/00	21.75			NLPH		390			8.3	160	1.1	1.5	2.6
RW3A	01/04/01	21.75	13.65	_				<1,000				****		
RW3A	04/03/01	21.75		8.10	NLPH		500		No. Common Commo	12	230	0.97	1.1	1.4
RW3A	07/05/01	21.75	12.30	9.45	NLPH		710	-		7.5	290	< 0.5	<0.5	<0.
RW3A	10/03/01		13.28	8.47	NLPH		640	***		9	280	1.4	1.6	2.7
RW3A		21.75	13.58	8.17	NLPH		<50	222		12	21	< 0.5	< 0.5	<0.
RW3A	Oct-01	21.89		ed in complianc		6 requirements	s.							-0.
	01/02/02	21.89	10.80	11.09	NLPH		<100	***	200	11.2	< 0.50	<0.50	< 0.50	<0.5
RW3A	04/02/02	21.89	12.03	9.86	NLPH		55.7	<100	222	11.0	1.30	<0.50	<0.50	<0.5
RW3A	07/01/02	21.89	13.13	8.76	NLPH		275	<100a	***	21.7	60.4	<0.5	2.4	4.2
RW3A	10/02/02	21.89	13.70	8.19	NLPH		138	114		11.1	53.4	<0.5	<0.5	0.7
RW3A	01/07/03	21.89	11,77	10.12	NLPH		<50.0	<50	30.9	22.4	1.5	<0.5	<0.5	
RW3A	06/17/03	21.89	12.82	9.07	NLPH		54.5	<100	16.0	12.8	7.40	<0.5		<0.
RW3A	07/16/03	21.89	13.40	8.49	NLPH		112	<100	13.6	18.0	26.0		<0.5	<0.
RW3A	10/07/03	21.89	13.93	7.96	NLPH	124	62.6	<100	11,3	10.4		<0.5	<0.5	<0.
RW3A	01/14/04	21.89	11.55	10.34	NLPH	401	<50.0	<100	16.2	11.7	7.30	<0.5	<0.5	<0.
RW3A	06/03/04	21.89	13.43	8.46	NLPH		79.0	<100	22,4		3.10	<0.5	<0.5	<0.
RW3A	08/12/04	21.89	С	c	C	1,190c	<50.0c	296c		19.4	6.30	<0.5	<0.5	<0.
RW3A	11/04/04	21.89	12.91	8.98	NLPH	178	<50.00		16.2c	3.555	<0.50c	<0.5c	<0.5c	<0.5
RW3A	02/01/05	21.89	11.63	10.26	NLPH	<100		122	5.40		<0.50	1.7	0.7	3.6
RW3A	05/03/05	21.89	11.79	10.20	NLPH		<50.0	<100	11.8		<0.50	< 0.5	<0.5	<0.
RW3A	08/04/05	21.89	12.99			158d	<50.0	<100	8.50		< 0.50	<0.5	< 0.5	<0.
RW3A	10/27/05			8.90	NLPH	687d	89.9	107	16.7		26.0	0.645	< 0.500	0.83
RW3A		21.89	13.49	8.40	NLPH	140	<50.0	79.1	4.00		9.63	< 0.50	< 0.50	0.6
	01/26/06	21.89	11.76	10.13	NLPH	210d	100a	<500	17		5.6a	<0.50a	<0.50a	<0.5
RW3A RW3A	04/28/06	21.89	10.96	10.93	NLPH	140g	82	<470	19		2.6	<0.50	<0.50	<0.5
RW3A	07/05/06	21.89	13.12	8.77	NLPH	340	50.0	<95.2	8.11		1.37	<1.00	<1.00	<3.0
RW3A	10/27/06	21.89	13.48	8.41	NLPH	63d	789	<470	10.6		287	1.29	<0.50	2.03
KAASW	01/19/07	21.89	12.69	9.20	NLPH	49d	<50.0	<470	6.25		2.08	< 0.50	<0.50	<0.5

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 16 of 16)

Notes:		
TOC	=	Top of casing elevation; datum is mean sea level.
SUBJ	=	Results of subjective evaluation.
NLPH	=	No liquid-phase hydrocarbons present in well.
sheen	=	Liquid-phase hydrocarbon present as sheen.
in.	=	Inches of floating product.
DTW	=	Depth to water.
GW Elev.	=	Groundwater elevation; datum is mean sea level,
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using EPA Method 5030/8015B (modified).
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using EPA Method 5030/8015B (modified).
TPHmo	=	Total petroleum hydrocarbons as motor oil using EPA Method 8015B.
MTBE 8260B	=	Methyl tertiary butyl ether analyzed using EPA Method 8260B.
MTBE 8021B	=	Methyl tertiary butyl ether analyzed using EPA Method 8021B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 602 or 8021B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
EDB	=	1,2-Dibromoethane analyzed using EPA Method 8260B
1,2-DCA	=	1,2-Dichloroethane analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
μg/L	=	Micrograms per liter.
<	=	Less than the indicated reporting limit shown by the laboratory.
	=	Not measured/Not sampled/Not analyzed.
а	=	Analyses performed past EPA recommended holding time.
ь	=	Well sampled semi-annually.
С	=	Groundwater elevation data invalidated; analytical results suspect.
d	=	Hydrocarbon pattern is present in the requested fuel quantitation range but does not resemble the pattern of the requested fuel.
е	=	TRPH-diesel surrogate was diluted out due to sample matrix
f	=	Analyte detected in Matrix Spike and Matrix Spike Duplicate.
g	=	Elevated result due to single analyte peak in quantitation range.
h	=	Initial analysis within EPA recommended hold time. Re-analysis for dilution performed past hold time.
ī	=	Based on assigned benchmark with elevation arbitrarily set at 100 feet.
j	=	Benchmark is City of Oakland #37J.

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 6)

Well ID	Sampling	ETBE	TAME	TBA	EDB	1,2-DCA	DIPE	Ethanol
_	Date	(μg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW6A	June 1988 - Well ir	notella d					(199/2)	(µg/L)
MW6A	06/24/09 12/24/0	istalled.						
MW6A	05/02/00 - 12/31/9	1 Not analyzed for the	se analytes.					
MINNOW	05/02/92 - Well de:	stroyed.						
MW6B	June 1988 - Well ir	nstalled.						
MW6B		2 Not analyzed for the	se analytes					
MW6B	01/07/03	< 0.50	<0.50	<10.0	<0.50			
MW6B	06/17/03	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	
MW6B	07/16/03	<0.50	<0.50	<10.0		<0.50	<0.50	<100
MW6B	10/07/03	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6B	01/14/04	<0.50	<0.50		<0.50	<0.50	< 0.50	<100
MW6B	06/03/04	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<50.0
MW6B	08/12/04	<0.50c	<0.50c	<10.0	<0.50	<0.50	< 0.50	<50.0
MW6B	11/04/04	<0.50		<10.0c	<0.50c	<0.50c	<0.50c	<50.0c
MW6B	02/01/05	<0.50	<0.50	<10.0	<0.50	<0.50	< 0.50	<50.0
MW6B	05/03/05	<0.50	<0.50	<10.0	< 0.50	<0.50	< 0.50	<50.0
MW6B	08/04/05	<0.500	<0.50	<10.0	<0.50	< 0.50	< 0.50	<50.0
MW6B	10/27/05	<0.500	<0.500	<10.0	<0.500	<0.500	< 0.500	<50.0
MW6B	01/26/06	<0.50	<0.500	<20.0	< 0.500	<0.500	<0.500	<100
MW6B	04/28/06		0.56	<20	<0.50	< 0.50	< 0.50	<100
MW6B	07/05/06	<0.50	<0.50	27	<0.50	15	3.6	5 444 5
MW6B	10/27/06	<0.500	<0.500	<10.0	< 0.500	<0.500	< 0.500	<50.0
MW6B	01/19/07	<0.500	<0.500	<10.0	< 0.500	<0.500	< 0.500	***
MINAOD	01/19/07	<0.500	<0.500	<10.0	<0.500	<0.500	<0.500	<50.0
MW6C	06/15/88 - Well inst	talled.						
MW6C	06/24/88 - 04/30/90	Not analyzed for the	se analytes.					
MW6C	05/10/90 - Well ove	er-drilled into recovery	well RW3					
MW6D	07/06/88 - Well inst	tollo d						
MW6D								
MW6D	05/10/90 - Well ove	Not analyzed for the er-drilled into recovery	se analytes.					
	117.10.00	or diffica into recovery	Well IXVVZ					
MW6E	10/04/88 - Well inst	talled.						
MW6E	10/20/88 - 10/02/02	Not analyzed for the	se analytes.					
MW6E	01/07/03	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	
MW6E	06/17/03	< 0.50	< 0.50	<10.0	<0.50	<0.50		
MW6E	07/16/03	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6E	10/07/03	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6E	01/14/04	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6E	06/03/04	< 0.50	<0.50	<10.0	<0.50		<0.50	<50.0
MW6E	08/12/04	<0.50c	<0.50c	<10.0c	<0.50c	<0.50	<0.50	<50.0
MW6E	11/04/04	<0.50	<0.50	<10.00		<0.50c	<0.50c	<50.0c
MW6E	02/01/05	<0.50	<0.50		<0.50	<0.50	<0.50	<50.0
	05/03/05	<0.50	<0.50	<10.0	< 0.50	<0.50	<0.50	<50.0
MW6E		-0.00	~0.50	<10.0	< 0.50	< 0.50	<0.50	<50.0
	08/04/05	<0.500	<0.500	-100	10 500			~50.0
MW6E MW6E	08/04/05 10/27/05	<0.500 <0.500	<0.500 <0.500	<10.0 <20.0	<0.500 <0.500	<0.500 <0.500	<0.500	<50.0

TABLE 1B
ADDITIONAL CUMMULATIVE GROUNDWATER MONITORING AND SAMPLING DATA

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 2 of 6)

Well ID	Sampling	ETBE	TAME	TBA	EDB	1,2-DCA	DIPE	Esta
10405	Date	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)		Ethanol
MW6E	01/26/06	<0.50	< 0.50	<20	<0.50	<0.50	(µg/L) <0.50	(µg/L)
MW6E	04/28/06	< 0.50	<0.50	<20	<0.50	<0.50		<100
MW6E	07/05/06	< 0.500	< 0.500	<10.0	<0.500	<0.500	<0.50	
MW6E	10/27/06	< 0.500	< 0.500	<10.0	<0.500	<0.500	<0.500	<50.0
MW6E	01/19/07	< 0.500	< 0.500	<10.0	<0.500	<0.500 <0.500	<0.500	***
					_,,,,,	-0.000	<0.500	<50.0
MW6F	10/05/88 - Well ins							
MW6F	10/20/88 - 10/02/0	2 Not analyzed for the	se analytes.					
MW6F	01/07/03	<0.50	< 0.50	<10.0	< 0.50	< 0.50	<0.50	
MW6F	06/17/03	<0.50	< 0.50	<10.0	< 0.50	<0.50	<0.50	
MW6F	07/16/03	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6F	10/07/03	< 0.50	< 0.50	<10.0	<0.50	<0.50		<100
MW6F	01/14/04	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6F	06/03/04	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<50.0
MW6F	08/12/04	<0.50c	<0.50c	<10.0c	<0.50c		<0.50	<50.0
MW6F	11/04/04	<0.50	<0.50	<10.0	<0.50	<0.50c	<0.50c	<50.0c
MW6F	02/01/05	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<50.0
MW6F	05/03/05	< 0.50	0.90	<10.0	<0.50	< 0.50	<0.50	<50.0
MW6F	08/04/05	< 0.500	<0.500	<10.0	<0.500	1.70	<0.50	<50.0
MW6F	10/27/05	<0.500	<0.500	<20.0	<0.500	<0.500	<0.500	<50.0
MW6F	01/26/06	< 0.50	<0.50	<20	<0.50	<0.500 <0.50	<0.500	<100
MW6F	04/28/06	< 0.50	<0.50	<20	<0.50	<0.50 <0.50	<0.50	<100
MW6F	07/05/06	< 0.500	<0.500	<10.0	<0.500	<0.500	<0.50	70.7
MW6F	10/27/06	< 0.500	<0.500	<10.0	<0.500	<0.500	<0.500	<50.0
MW6F	01/19/07	<0.500	<0.500	<10.0	<0.500	<0.500	<0.500	
					-5.000	70.500	<0.500	<50.0
MW6G	11/16/88 - Well ins							
MW6G		2 Not analyzed for the:	se analytes.					
MW6G	01/07/03	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.F0	
MW6G	06/17/03	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	-
MW6G	07/16/03	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6G	10/07/03	< 0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<100
MW6G	01/14/04	< 0.50	<0.50	<10.0	<0.50		<0.50	<100
MW6G	06/03/04	< 0.50	<0.50	<10.0	<0.50	<0.50 <0.50	<0.50	<50.0
MW6G	08/12/04	<0.50c	<0.50c	<10.0c	<0.50c		<0.50	<50.0
MW6G	11/04/04	< 0.50	<0.50	<10.00	<0.50	<0.50c	<0.50c	<50.0c
MW6G	02/01/05	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<50.0
MW6G	05/03/05	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<50.0
MW6G	08/04/05	<0.500	< 0.500	<10.0	<0.500	<0.50	<0.50	<50.0
MW6G	10/27/05	<0.500	<0.500	<20.0	<0.500	<0.500	<0.500	<50.0
MW6G	01/26/06	<0.50	<0.50	<20.0		<0.500	<0.500	<100
MW6G	04/28/06	<0.50	<0.50	<20	<0.50	<0.50	<0.50	<100
MW6G	07/05/06	<0.500	<0.500	<10.0	<0.50	<0.50	<0.50	<100
MW6G	10/27/06	<0.500	<0.500	<10.0	<0.500	<0.500	<0.500	<50.0
WW6G	01/19/07	<0.500	<0.500		<0.500	<0.500	<0.500	<100
			70.000	<10.0	< 0.500	< 0.500	< 0.500	<50.0

TABLE 1B
ADDITIONAL CUMMULATIVE GROUNDWATER MONITORING AND SAMPLING DATA

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 3 of 6)

Well ID	Sampling	ETBE	TAME	TBA	EDB	1,2-DCA	DIPE	Ethanol
	Date	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	
MW6H	December 1988 - 1				H.V.	NPS-7	(Pg/L)	(µg/L)
MW6H	12/07/88 - 10/02/0	2 Not analyzed for the	se analytes.					
MW6H	01/07/03	< 0.50	< 0.50	952	< 0.50	<0.50	7.50	
MW6H	06/17/03	< 0.50	< 0.50	678	< 0.50	<0.50	7.10	<100
MW6H	07/16/03	<0.50	0.70	307	< 0.50	14.6	6.20	<100
MW6H	10/07/03	<0.50	< 0.50	294	< 0.50	<0.50	7.40	<100
MW6H	01/14/04	< 0.50	<0.50	883	< 0.50	<0.50	6.80	<50.0
MW6H	06/03/04	< 0.50	< 0.50	541	< 0.50	<0.50	5.80	<50.0
MW6H	08/12/04	<0.50c	<0.50c	754c	<0.50c	<0.50c	5.40c	
MW6H	11/04/04	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	<50.0c
MW6H	02/01/05	< 0.50	<0.50	625	<0.50	<0.50		<50.0
MW6H	05/03/05	< 0.50	< 0.50	436	<0.50	<0.50	4.20	<50.0
MW6H	08/04/05	< 0.500	<0.500	530	<0.500	<0.500	3.10	<50.0
MW6H	10/27/05	<0.500	<0.500	422	<0.500	<0.500	3.73	<50.0
MW6H	01/26/06	<25	<25	<1,000	<25	<0.500 <25	4.62	<100
MW6H	04/28/06	<25	<25	<1,000	<25	<25	<25	<5,000
MW6H	07/05/06	< 0.500	< 0.500	137	<0.500	<0.500	<25	<5,000
MW6H	10/27/06	< 0.500	<0.500	131	<0.500		2.41	<50.0
MW6H	01/19/07	< 0.500	28.1	161	<0.500	<0.500 25.7	3.61 2.96	<100
						20.7	2.90	<50.0
MW6I	December 1988 - \							
MW6I	12/07/88 - 10/02/02	Not analyzed for the	se analytes.					
MW6I	01/07/03	<0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	
MW6I	06/17/03 b						-0.50	1944
MW6I	07/16/03	<0.50	< 0.50	16.4	< 0.50	<0.50	<0.50	
MW6I	10/07/03 b		P				-0.50	<100
MW6I	01/14/04	< 0.50	< 0.50	<10.0	<0.50	<0.50		
MW6I	06/03/04 b			-			<0.50	<50.0
MW6I	08/12/04	<0.50c	<0.50c	<10.0c	<0.50c	<0.50c		
MW6I	11/04/04 b				-0.500	~0.50C	<0.50c	<50.0c
MW6I	02/01/05	< 0.50	< 0.50	<10.0	<0.50	<0.50	-0.50	1,000
MW6I	05/03/04 b						<0.50	<50.0
MW6I	08/04/05	< 0.500	< 0.500	<10.0	<0.500		EMILE.	
MW6I	10/27/05 b			-10.0	<0.500	<0.500	< 0.500	<50.0
MW6I	01/26/06	< 0.50	< 0.50	<20	<0.50			***
MW6I	04/28/06 b				~0.50 —	<0.50	<0.50	<100
MW61	07/05/06	<0.500	<0.500	<10.0	<0.500	<0.500	0.500	-
MW6I	10/27/06 b				<0.500	<0.500	<0.500	<50.0
MW6I	01/19/07	<0.500	<0.500	<10.0	<0.500	<0.500	<0.500	<50.0
MW6J	04/06/01 - Well ins	tallad						750.0
MW6J								
		Not analyzed for the						
MW6J	01/07/03	<0.50	<0.50	<10.0	<0.50	< 0.50	< 0.50	***
MW6J	06/17/03	<0.50	<0.50	<10.0	< 0.50	0.90	< 0.50	<100
MW6J	07/16/03	<0.50	< 0.50	<10.0	<0.50	1.00	< 0.50	<100
MW6J	10/07/03	<0.50	<0.50	<10.0	<0.50	<0.5	< 0.50	<100
MW6J	01/14/04	<0.50	< 0.50	<10.0	<0.50	< 0.50	< 0.50	<50.0

TABLE 1B
ADDITIONAL CUMMULATIVE GROUNDWATER MONITORING AND SAMPLING DATA

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 4 of 6)

Well ID	Sampling	ETBE	TAME	TBA	EDB	1,2-DCA	DIPE	Ethanol
	Date	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW6J	06/03/04	<0.50	< 0.50	<10.0	<0.50	2.00	<0.50	<50.0
MW6J	08/12/04	<0.50c	<0.50c	<10.0c	<0.50c	1.20c	<0.50c	<50.0c
MW6J	11/04/04	<0.50	<0.50	<10.0	< 0.50	< 0.50	< 0.50	<50.0
MW6J	02/01/05	<0.50	<0.50	<10.0	< 0.50	1.20	< 0.50	<50.0
MW6J	05/03/05	<0.50	<0.50	<10.0	< 0.50	1.20	<0.50	<50.0
MW6J	08/04/05	< 0.500	< 0.500	<10.0	< 0.500	< 0.500	<0.500	<50.0
MW6J	10/27/05	< 0.500	< 0.500	<20.0	< 0.500	<0.500	<0.500	<100
MW6J	01/26/06	< 0.50	< 0.50	<20	< 0.50	1,1	<0.50	<100
MW6J	04/28/06	< 0.50	< 0.50	<20	< 0.50	1.3	<0.50	
MW6J	07/05/06	<0.500	< 0.500	<10.0	< 0.500	<0.500	<0.500	<50.0
MW6J	10/27/06	< 0.500	< 0.500	<10.0	<0.500	1.04	<0.500	
MW6J	01/19/07	<0.500	<0.500	<10.0	<0.500	1.15	<0.500	<50.0
RW1	05/10/90 - Well ins	stalled.						
RW1	10/16/90 - 10/02/0	2 Not analyzed for the	se analytes.					
RW1	01/07/03	<10.0	<10.0	<200	<10.0	<10.0	~10 O	
RW1	06/17/03	< 0.50	<0.50	324	<0.50	<0.50	<10.0	
RW1	07/16/03	< 0.50	< 0.50	110	<10.0	1.70	<0.50	<100
RW1	10/07/03	<0.50	<0.50	<10.0	<0.50	<0.50	1.10	<100
RW1	01/14/04	<0.50	<0.50	234	<0.50	<0.50	<0.50	<100
RW1	06/03/04	<0.50	<0.50	338	<0.50	<0.50	0.90	<50.0
RW1	08/12/04	<0.50c	<0.50c	437c	1.30c	<0.50c	1.30	<50.0
RW1	11/04/04	< 0.50	< 0.50	541	<0.50	<0.50	1.20c	<50.0c
RW1	02/01/05	< 0.50	<0.50	261	<0.50	<0.50	<0.50	<50.0
RW1	05/03/05	<0.50	<0.50	200	<0.50	<0.50	1.80	<50.0
RW1	08/04/05	<0.500	<0.500	169	<0.500	<0.500	<0.50	<50.0
RW1	10/27/05	< 0.500	<0.500	152	<0.500	<0.500	<0.500	<50.0
RW1	01/26/06	<2.5	<2.5	280	<2.5		0.660	<100
RW1	04/28/06	<0.50	<0.50	86	<0.50	<2.5 <0.50	<2.5	<500
RW1	07/05/06	<0.500	<0.500	80.5	1.02		<0.50	<100
RW1	10/27/06	< 0.500	<0.500	104	< 0.500	<0.500	<0.500	<50.0
RW1	01/19/07	<0.500	<0.500	64.6	<0.500	<0.500 <0.500	<0.500 < 0.500	<100 <50.0
MW6D	07/06/88 - Well ins							
MW6D		0 Not analyzed for the						
MW6D	05/10/90 - Well ov	er-drilled into recovery	well RW2					
RW2	10/16/90 - 10/02/0	2 Not analyzed for the	se analytes.					
RW2	01/07/03	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	
RW2	06/17/03	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	
RW2	07/16/03	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	<100
RW2	10/07/03	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	<100
RW2	01/14/04	<0.50	<0.50	370	<0.50	<0.50		<100
RW2	06/03/04	<0.50	<0.50	370	<0.50	<0.50	<0.50	<50.0
RW2	08/12/04	<0.50c	<0.50c	<10.0c	1.30c	<0.50c	<0.50	<50.0
RW2	11/04/04	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50c	<50.0c
RW2	02/01/05	<0.50	< 0.50	. 0.0	-0.00	~0.00	< 0.50	<50.0

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 5 of 6)

Well ID	Sampling	ETBE	TAME	TBA	EDB	1,2-DCA	DIPE	Fu.
	Date	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(μg/L)		Ethanol
RW2	05/03/05	<0.50	<0.50	<10.0	<0.50	<0.50	(µg/L)	(µg/L)
RW2	08/04/05	< 0.500	<0.500	<10.0	< 0.500	<0.500	<0.50	<50.0
RW2	10/27/05	<0.500	< 0.500	<20.0	< 0.500	<0.500	<0.500	<50.0
RW2	01/26/06	< 0.50	< 0.50	<20	<0.50	<0.50	<0.500	<100
RW2	04/28/06	< 0.50	< 0.50	<20	<0.50	<0.50	<0.50	<100
RW2	07/05/06	< 0.500	< 0.500	<10.0	<0.500	<0.500	<0.50	-
RW2	10/27/06	< 0.500	< 0.500	<10.0	< 0.500	<0.500	<0.500	<50.0
RW2	01/19/07	<0.500	<0.500	<10.0	<0.500	<0.500	<0.500 < 0.500	<50.0
MW6C	06/15/88 - Well ins	stalled.						
MW6C	06/24/88 - 04/30/9	0 Not analyzed for the	se analytes.					
MW6C	05/10/90 - Well ov	er-drilled into recovery	well RW3					
RW3		1 Not analyzed for the						
RW3	11/05/91 - Well de							
RW3A	08/24/92 - Well ins	stalled in place of RW3	_					
RW3A	08/24/98 - 10/02/0	2 Not analyzed for the	se analytes					
RW3A	01/07/03	< 0.50	<0.50	<10.0	<0.50	<0.50	2.50	
RW3A	06/17/03	<0.50	<0.50	<10.0	<0.50	<0.50	<0.50	
RW3A	07/16/03	< 0.50	<0.50	<10.0	<0.50	<0.50	1.20	<100
RW3A	10/07/03	< 0.50	<0.50	<10.0	<0.50	<0.50	1.40	<100
RW3A	01/14/04	< 0.50	<0.50	<10.0	<0.50	<0.50	1.40	<100
RW3A	06/03/04	< 0.50	< 0.50	<10.0	<0.50	<0.50	2.20	<50.0
RW3A	08/12/04	<0.50c	<0.50c	<10.0c	<0.50c	<0.50c	1.20	<50.0
RW3A	11/04/04	< 0.50	< 0.50	<10.0	<0.50	<0.50	1.10c	<50.0c
RW3A	02/01/05	< 0.50	< 0.50	<10.0	<0.50	<0.50	<0.50	<50.0
RW3A	05/03/05	< 0.50	<0.50	<10.0	<0.50	<0.50	2.10	<50.0
RW3A	08/04/05	< 0.500	<0.500	<10.0	<0.500		0.60	<50.0
RW3A	10/27/05	<0.500	<0.500	<20.0	<0.500	<0.500	<0.500	<50.0
RW3A	01/26/06	<0.50	<0.50	<20	<0.50	<0.500	0.980	<100
RW3A	04/28/06	<0.50	<0.50	<20	<0.50	<0.50	3.2	<100
RW3A	07/05/06	<0.500	<0.500	<10.0		<0.50	1.5	<100
RW3A	10/27/06	<0.500	<0.500	17.3	<0.500	<0.500	1.20	<50.0
RW3A	01/19/07	<0.500	<0.500	<10.0	<0.500	<0.500	3.90	<100
		70.000	~0.000	<10.0	<0.500	1.30	1.55	<50.0

TABLE 1B

ADDITIONAL CUMMULATIVE GROUNDWATER MONITORING AND SAMPLING DATA

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 6 of 6)

Notes:		
TOC	=	Top of casing elevation; datum is mean sea level.
SUBJ	=	Results of subjective evaluation.
NLPH	=	No liquid-phase hydrocarbons present in well.
sheen	=	Liquid-phase hydrocarbon present as sheen.
in.	=	Inches of floating product.
DTW	=	Depth to water.
GW Elev.	=	Groundwater elevation; datum is mean sea level.
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using EPA Method 5030/8015B (modified).
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using EPA Method 5030/8015B (modified).
TPHmo	=	Total petroleum hydrocarbons as motor oil using EPA Method 8015B.
MTBE 8260B	=	Methyl tertiary butyl ether analyzed using EPA Method 8260B.
MTBE 8021B	=	Methyl tertiary butyl ether analyzed using EPA Method 8021B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 602 or 8021B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B.
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
EDB	=	1,2-Dibromoethane analzed using EPA Method 8260B.
1,2-DCA	=	1,2-Dichloroethane analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
μg/L	=	Micrograms per liter.
<	=	Less than the indicated reporting limit shown by the laboratory.
5555	=	Not measured/Not sampled/Not analyzed.
а	=	Analyses performed past EPA recommended holding time.
b	=	Well sampled semi-annually.
С	=	Groundwater elevation data invalidated; analytical results suspect.
d	=	Hydrocarbon pattern is present in the requested fuel quantitation range but does not resemble the pattern of the requested fuel.
е	=	TRPH-diesel surrogate was diluted out due to sample matrix
f	=	Analyte detected in Matrix Spike and Matrix Spike Duplicate.
g	=	Elevated result due to single analyte peak in quantitation range.
h	=	Initial analysis within EPA recommended hold time. Re-analysis for dilution performed past hold time.
i	=	Based on assigned benchmark with elevation arbitrarily set at 100 feet.
9 j 8	=	Benchmark is City of Oakland #37J.

TABLE 2 WELL CONSTRUCTION DETAILS

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 1)

Well ID	Date Well Installed	TOC Elevation (feet)	Borehole Diameter (inches)	Total Depth of Boring (fbgs)	Well Depth (fbgs)	Well Casing Diameter (inches)	Well Casing Material	Screened Interval (fbgs)	Slot Size (inches)	Filter Pack Interval (fbgs)	Filter Pack Material
MW6A	Well destroye	ed in 1992.									
MW6B	June 1988	21.09	8	20	19	2	PVC	9-19	0.020	7-20	#3 Sand
MW6C	Well converte	ed to groundwa	ter recovery v	ell RW3 in 1990							
MW6D	Well converte	ed to groundwa	ter recovery v	ell RW2 in 1990							
MW6E	10/04/88	21.24	10.5	21.5	20.5	4	PVC	10-19.5	0.020	8-21.5	#3 Sand
MW6F	10/05/88	22.17	10.5	22	20	4	PVC	10-19.5	0.020	8-22	#3 Sand
MW6G	11/16/88	20.46	8	20	20	4	PVC	10-19.5	0.020	8-20	#3 Sand
MW6H	11/16/88	20.20	8	21	20	4	PVC	10-19.5	0.020	8-21	#3 Sand
MW6I	11/17/88	19.87	8	21	20	4	PVC	10-19.5	0.020	8-21	#3 Sand
MW6J	04/06/01	20.75	8	23	23	2	PVC	6-23	0.020	6-23	#2/12 Sand
RW1	05/10/90	20.43	12	25	25	4	PVC	9.5-24.5	0.020	8.5-25	#3 Sand
RW2	07/06/88	20.64	12	25	25	4	PVC	9.5-24.5	0.020	9.5-25	#3 Sand
RW3	Well destroye	ed in 1991 and	replaced with	well RW3A in 19	92.						
RW3A	08/24/92	21.89	12	21.5	21.5	4	PVC	9-21	0.020	8-21.5	#3 Sand
VW1	06/05/92	NS	NS	11	11	4	PVC	6-11	0.020	NS	NS
VW2	06/05/92	NS	NS	11	11	4	PVC	6-11	0.020	NS	NS
VW3	08/24/92	NS	12	13.5	13.5	4	PVC	4-13.5	0.050	4-13.5	Aquarium Sar

Notes: TOC

Top of well casing elevation; datum is mean sea level.

fbgs = Feet below ground surface.

PVC = Polyvinyl chloride.

NS = Not specified.

TABLE 3A CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 5)

Sample	Sample	Depth	TPHd	TPHg	MTBE	В	T	E	X	Total Lead	HVOCs	TPHmo	TOG
D	Date	(fbgs)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)			
oil Boring S					1 0 0/	(9 9)	(119119)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
3-1 (HLA)	10/04/88	8.0	- 575	<10		0.05	<0.1	<0.2	<0.1				
3-1 (HLA)	10/04/88	13.0		2,000		<5	16	10	41			- 	
								.0	71	531			
3-2 (HLA)	10/04/88	7.0	() 0000	<10		<0.05	<0.1	<0.2	<0.1		_	-41	***
3-2 (HLA)	10/04/88	13.5		<10		< 0.05	<0.1	<0.2	<0.1		_		
									0				
3-3 (HLA)	10/04/88	7.0	0225	<10		0.06	<0.1	< 0.2	<0.1				
B-3 (HLA)	10/04/88	13.5	-	11,000		40	390	84	370			_	
									0.0				
B-4 (HLA)	11/17/88	13.5	-	<10	***	< 0.05	<0.1	<0.2	< 0.1		***	***	3244
									0				
3-5 (HLA)	1989-1992e	5.5		ND		ND	ND	ND	ND	_			**-
3-5 (HLA)	1989-1992e	9.5		ND		ND	ND	ND	ND		200		
3-5 (HLA)	1989-1992e	12.5		ND		ND	ND	ND	ND			1900	
3-6 (HLA)	1989-1992e	6.0		ND		ND	ND	ND	ND				
8-6 (HLA)	1989-1992e	9.5		ND		ND	ND	ND	ND				
3-6 (HLA)	1989-1992e	12.0		3,000		40	40	110	450				
3-7 (HLA)	1989-1992e	6.0		24		0.64	0.4	0.9	3.4				
3-7 (HLA)	1989-1992e	9.5		ND		0.5	ND	0.7	1.0	=		1200	
3-7 (HLA)	1989-1992e	12.0		1,400		20	20	72	190				
3-1 (Alton)	03/19/91												
3-1 (Alton)	03/19/91	5.5		240		1.2	0.87	11	7.7		-30	-	
		10.5		10,000	_	81	660	310	1,600			(400)	
3-1 (Alton)	03/19/91	15.5		4,400		8.4	77	56	310				9.42
3-2 (Alton)	03/19/91	5.5		000		4.6	_						
3-2 (Alton)	03/19/91	5.5 10.5		880		1.0	7.2	11	47		_		
3-2 (Alton)	03/19/91			2,400		3.5	38	26	150	_			
Alton)	03/19/91	14.5	_	9,900		33	170	150	980				
3-3 (Alton)	03/19/91	5.5		-4.0		-0.000							
3-3 (Alton)	03/19/91	ວ.ວ 10.5		<1.0	-	< 0.003	<0.003	< 0.003	<0.003		-	11	3
o (Alton)	00/13/31	10.5		11		0.022	0.14	0.18	3.2		7550		
3-4 (Alton)	03/19/91	5.5	8	<1.0		0.026	-0.000						
3-4 (Alton)	03/19/91	10.5		<1.0 7	_	0.036	<0.003	<0.003	<0.003				
. (/ ((0)))	30/10/01	10.5	V. 1000	,		0.370	0.15	0.18	0.93				
3-5 (Alton)	03/19/91	5.5	-	310		0.82	2.6	4.0	200				
3-5 (Alton)	03/19/91	10.5	***	40	-25 0	0.69	3.6	4.2	22				
	30, 10,01	10.0		40		0.09	1.4	0.58	3.2	30000			Name .

TABLE 3A CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 2 of 5)

Sample	Sample	Depth	TPHd	TPHg	MTBE	В	T	E	X	Total Lead	HVOCs	TPHmo	TOG
ID	Date	(fbgs)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
B-6 (Alton)	03/19/91	5.5		<1.0	12.55	0.054	0.003	0.005	0.011		(55)	(11131113)	
B-6 (Alton)	03/19/91	10.5		2	() ()	0.15	0.067	0.019	0.09	(100			Parameter 1
B-7 (Alton)	03/19/91	5.5		<1.0		<0.003	<0.003	<0.003	<0.003		****		
B-7 (Alton)	03/19/91	10.5		<1.0		<0.003	<0.003	<0.003	<0.003	1000			
B-8 (Alton)	03/19/91	5.5		<1.0	()	<0.003	<0.003	<0.003	<0.003		225	-	
B-8 (Alton)	03/19/91	10.5		<1.0	\i\	0.048	0.013	<0.003	0.025		****		
B-9 (Alton)	03/19/91	5.5					-			-			<50
B-9 (Alton)	03/19/91	10.5											<50
B-9 (Alton)	03/19/91	14.5											<50
B-10 (Alton)	03/19/91	5.5		<1.0		0.085	<0.003	0.006	<0.003				-
B-10 (Alton)	03/19/91	10.5		2		0.27	0.075	0.026	0.1				
S-9-GP1	03/29/00	9.0		<1	<0.001a	<0.001	<0.001	<0.001	<0.001	_		(***	-
S-11-GP1	03/29/00	11.0	1446	<1	<0.001a	<0.001	<0.001	<0.001	<0.001	-		(555)	-
S-9-GP2	03/29/00	9.0	_	<1	<0.001a	<0.001	<0.001	<0.001	<0.001				
S-11-GP2	03/29/00	11.0		<1	<0.001a	<0.001	<0.001	<0.001	<0.001				
MW-6E	10/05/88	13.0		<10		<0.05	<0.1	<0.2	<0.1				
MW-6F	10/05/88	13.0		<10		< 0.05	<0.1	< 0.2	<0.1				
MW-6G	11/16/88	13.5		5.2		< 0.05	<0.1	<0.2	<0.1				
MW-6H	11/16/88	13.5		1,000		<0.5	3.2	3.2	19				
MW-6I	11/17/88	13.5		<10		<0.05	<0.1	<0.2	<0.1				
S-5-MW6J	04/06/01	5.0	<2	<1	<0.01	<0.001	<0.001	<0.001	<0.001			<10	
S-10-MW6J	04/06/01	10.0	<2	<5	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005		-	<10	
S-15-MW6J	04/06/01	15.0	<2	<1	< 0.01	< 0.001	<0.001	< 0.001	< 0.001		P	<10	
S-20-MW6J	04/06/01	20.0	<2	<1	<0.01	<0.001	<0.001	0.013	0.037		-	<10	
S-5-B5	03/01/07	5.0	1.6c,d	<0.10	<0.0050	<0.0010	<0.0010	<0.0010	<0.0010		O NNE O	<10	· ·
S-5-B7	03/05/07	5.0	<1.0	<0.10	<0.0050	<0.0010	<0.0010	<0.0010	<0.0010			<10	
S-10-B7	03/05/07	10.0	<1.0	<0.10	<0.0050	< 0.0010	<0.0010	< 0.0010	<0.0010			<10	
S-15-B7	03/05/07	15.0	<1.0	< 0.10	< 0.0050	< 0.0010	<0.0010	< 0.0010	<0.0010			<10	
S-16.5-B7	03/05/07	16.5	<1.0	< 0.10	< 0.0050	< 0.0010	<0.0010	< 0.0010	<0.0010			<10	
S-19-B7	03/05/07	19.0	1.0c	< 0.10	< 0.0050	< 0.0010	< 0.0010	< 0.0010	<0.0010			<10	
S-21-B7	03/05/07	21.0	<1.0	< 0.10	< 0.0050	< 0.0010	<0.0010	< 0.0010	< 0.0010			<10	

TABLE 3A CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 3 of 5)

Sample	Sample	Depth	TPHd	TPHg	MTBE	В	T	E	X	Total Lead	HVOCs	TPHmo	TOG
ID	Date	(fbgs)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
S-5-B8	03/01/07	5.0	1.2c,d	<0.10	< 0.0050	<0.0010	<0.0010	<0.0010	<0.0010		***	<10	
S-10-B8	03/01/07	10.0	<1.0	<0.10	<0.0050	<0.0010	<0.0010	<0.0010	<0.0010			<10	
S-5-B9	03/02/07	5.0	1.3c,d	<0.10	<0.0050	<0.0010	<0.0010	<0.0010	<0.0010			~10	
S-10-B9	03/02/07	10.0	1.8c,d	1.3	0.016	0.13	0.11	0.042	0.17			<10 <10	
S-11-B9	03/02/07	11.0	1.8c,d	12	< 0.0050	0.18	0.36	0.22	0.92			<10	
S-15-B9	03/06/07	15.0	<1.0	1.9	0.0067	0.48	0.032	0.042	0.12				
S-19.5-B9	03/06/07	19.5	<1.0	< 0.10	0.0050	0.0068	<0.0010	< 0.0010	<0.0010			<10 <10	
S-23.5-B9	03/06/07	23.5	<1.0	< 0.10	< 0.0050	< 0.0010	<0.0010	< 0.0010	< 0.0010				
S-29.5-B9	03/06/07	29.5	<1.0	<0.10	<0.0050	<0.0010	<0.0010	< 0.0010	<0.0010			<10 <10	
Fuel Dispense	er Samples												
AB-1	1988-1992e	8.0		65		1.9	3.4	1.0	4.0				
AB-2	1988-1992e	Surface		7,200		<0.0025	43	1.0	4.2 140	-			
AB-2	1988-1992e	2.0		78		0.83	2.1	0.76					
AB-3	1988-1992e	2.0		540		<0.0025	<0.005		4.0				
AB-4	1988-1992e	6.0		<1		<0.0025		<0.0025	18				
AB-5	1988-1992e	6.0		5.0		<0.0025	<0.005	<0.0025	<0.0025				
AB-6	1988-1992e	5.0		<1		<0.0025	<0.005 <0.005	0.021 <0.0025	0.016 <0.0025				
Tank Pit Sam	nloe												
Tank Pit Botto													
TG1	11/27/91	13.0		130		0.2700	0	_	•				
TG2	11/27/91	13.0		10,000		0.3700	2	3	82				
TG3	11/27/91	13.0		6,300		130	950	280	1,100		-		
TG4	11/27/91	13.0			_	76	540	200	900				
TG5	11/27/91	13.0	_	130		0.770	7.3	3.3	18				
TG6	11/27/91	13.0		10		0.65	0.0084	0.140	0.160				
Tank Pit Sidev		13.0		12		<0.050	0.200	0.230	1				-
TG7	12/03/91	12.0		400		7							
TG8		12.0		430		1.7	15	7.2	34	<10			
	12/03/91	12.0		240		1.7	7.9	4.4	19	<10			
TG9	12/03/91	12.0		<1.0		0.052	0.033	0.021	0.067	13			
TG10	12/03/91	12.0		1.7	***	0.051	<0.005	0.044	< 0.005	13			
TG11	12/03/91	12.0		420		1.5	10	6.2	29	13			
TG12	12/03/91	12.0		660		4.3	24	11	49	<10			
Used-Oil Tanl													
WO1	11/27/91	7.0	22	1.1	-	0.0057/200a	<0.005/1,200a	0.015/380a	<0.005/2,100a	<10	NDb	0.775	580

TABLE 3A CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 4 of 5)

Sample	Sample	Depth	TPHd	TPHg	MTBE	В	T	E	×	Total Lead	HVOCs	TPHmo	TOG
D	Date	(fbgs)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)					
Product Line	Trench Samples			1 0 0/	(0 0)	(99)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
PL1	12/06/91	2.0		<4.0		<0.020	0.077	0.035	0.140				
PL2	12/06/91	2.0		<1.0		<0.005	<0.005	<0.005	<0.005				
PL3	12/06/91	2.0		150		0.690	0.450	2.3					
PL4	12/06/91	2.0		330		2.7	17	5.7	7.3			-	
PL5	12/06/91	2.0	-	<1.0		0.0053	<0.005	0.0088	29			_	
PL6	12/06/91	2.0		4.9		<0.020	0.048	0.052	0.0086				
PL7	12/06/91	2.0		38	le la m	<0.020	0.048	0.052	0.033				
L8	12/06/91	2.0		5.8		0.330	0.590	_	0.250				
PL9	12/06/91	2.0		1.9		<0.005	<0.005	0.080	0.720				
PL10	12/06/91	2.0		<1.0		<0.005		<0.005	< 0.005			_	
				1.0		~0.003	<0.005	<0.005	<0.005				_
oil Stockpile	Samples												
SS1-4	Nov-Dec 1991			120		<0.020	0.370	0.910	4.7	-4.0			
SS5-8	Nov-Dec 1991			180		<0.050	1.9	1.7	1.7	<1.0			
SS9-12	Nov-Dec 1991			270		0.170	8.9	5.4	7.8				
SS13-16	Nov-Dec 1991			30		0.022	0.480		26				
SS17-20	Nov-Dec 1991			130		<0.020	1.8	0.300	1.5	300 C		_	
SS21-24	Nov-Dec 1991			<1.0		<0.020	<0.005	1.9	7.8				
SS25-28	Nov-Dec 1991		35	1.2		<0.005		<0.005	0.011				
A1-4	Nov-Dec 1991			46		<0.250	<0.005	0.025	0.0083		NDb	_	
A5-8	Nov-Dec 1991			94		<0.500	0.110	0.130	1,5				
A9-12	Nov-Dec 1991			390			0.610	0.400	5.8		-		
A13-16	Nov-Dec 1991			80		<1.0	2.3	3.2	24			_	
A17-20	Nov-Dec 1991			1,200		0.150	0.830	0.700	4.3			_	
A21-24	Nov-Dec 1991			980		<1.0	16	18	100				
A25-28	Nov-Dec 1991					1.1	20	16	90				
A29-32	Nov-Dec 1991			1,900		12	88	37	190	19			
6P-1-1	03/29/00		-	4,200		17	190	94	480				
P-1-1(1-4)			-0	<1	<0.001a	<0.001	<0.001	<0.001	< 0.001	4.35	ND		
	04/06/01		<2	<1	<0.01	****	-		-	4.68	ND	<10	
SP-1 (1-4)	03/07/07		<1.0	<0.10	<0.0050	<0.0010	< 0.0010	< 0.0010	< 0.0010	14		<10	

TABLE 3A CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 5 of 5)

Notes:		
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using modified EPA Method 8015M/8015B.
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using modified EPA Method 8015M/8015B.
MTBE	=1	Methyl tertiary butyl ether analyzed using EPA Method 8260B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 8020 or 8021B.
Total Lead	=	Total lead analyzed using EPA Method 6010B.
HVOCs	=	Halogenated volatiles organic compounds using EPA Method 8260B.
TPHmo	=	Total petroleum hydrocarbons as motor oil analyzed using Modified EPA Method 8015M/8015B.
TOG	=	Total oil and grease analyzed using EPA Method 5520.
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
EDB	=	1,2-dibromoethane analyzed using EPA Method 8260B.
1,2-DCA	=	1,2-dichloroethane analyzed using EPA Method 8260B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
Cadmium	=	Cadmium analyzed using EPA Method 6010.
Chromium	=	Chromium analyzed using EPA Method 6010.
Nickel	=	Nickel analyzed using EPA Method 6010.
Zinc	=	Zinc analyzed using EPA Method 6010.
ND	=	Analytes not detected at or above the laboratory method reporting limit.
mg/kg	=	Milligrams per kilogram.
5 000 11	=	Not Analyzed/Not Applicable/Not sampled.
a	=	Analyzed using EPA Method 8021B.
b	=	Analyzed using EPA Method 8240.
С	=	Hydrocarbon pattern does not resemble the requested fuel.
d	=	Analyte detected in associated method blank.
е	=	Exact sampling date unclear from previous consultant reports.

TABLE 3B ADDITIONAL LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES-VOCs

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 2)

Sample	Sample	Depth	TAME	TBA	DIPE	EDB	1,2-DCA	ETBE	Ethanol
ID	Date	(fbgs)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)		
Soil Boring	Samples			(0 0/	(99)	(mg/ng/	(mg/kg)	(mg/kg)	(mg/kg)
Prior to Marcl	h 2007, soil boring s	samples were not	analyzed for these	analytes.					
S-5-B5	03/01/07	5.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	550
S-5-B7	03/05/07	5.0	<0.0050	<0.020	<0.0050	<0.0050	<0.0050	<0.0050	<0.10
S-10 - B7	03/05/07	10.0	<0.0050	<0.020	< 0.0050	< 0.0050	< 0.0050	< 0.0050	<0.10
S-15-B7	03/05/07	15.0	<0.0050	<0.0050	<0.0050	<0.0050	< 0.0050	<0.0050	<0.10
S-16.5-B7	03/05/07	16.5	<0.0050	<0.020	< 0.0050	< 0.0050	< 0.0050	< 0.0050	<0.10
S-19 - B7	03/05/07	19.0	<0.0050	< 0.0050	< 0.0050	< 0.0050	< 0.0050	< 0.0050	<0.10
S-21-B7	03/05/07	21.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.10
S-5-B8	03/01/07	5.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	
S-10-B8	03/01/07	10.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	-
S-5-B9	03/02/07	5.0	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	
S-10-B9	03/02/07	10.0	< 0.0050	0.045	< 0.0050	< 0.0050	<0.0050	<0.0050	
S-11 - B9	03/02/07	11.0	<0.025	0.067	<0.025	<0.025	<0.025	<0.025	
S-15 - B9	03/06/07	15.0	<0.0050	0.034	<0.0050	<0.0050	<0.0050	<0.0050	722
S-19.5-B9	03/06/07	19.5	< 0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	
S-23.5-B9	03/06/07	23.5	< 0.0050	< 0.0050	<0.0050	<0.0050	<0.0050	<0.0050	
S-29.5-B9	03/06/07	29.5	< 0.0050	< 0.0050	<0.0050	<0.0050	<0.0050	<0.0050	

Fuel Dispenser Samples

Not analyzed for these analytes.

Tank Pit Samples

Not analyzed for these analytes.

Used-Oil Tank Pit Sample

Not analyzed for these analytes.

Product Line Trench Samples

Not analyzed for these analytes.

Soil Stockpile Samples

Prior to March 2007, soil stockpile samples were not analyzed for these analytes.

SP-1 (1-4)	03/07/07		<0.0050	<0.020	<0.0050	< 0.0050	< 0.0050	<0.0050	<0.10
------------	----------	--	---------	--------	---------	----------	----------	---------	-------

TABLE 3B

ADDITIONAL LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES-VOCs

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 2 of 2)

Matas		
Notes:		
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using modified EPA Method 8015M/8015B.
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using modified EPA Method 8015M/8015B.
MTBE	=	Methyl tertiary butyl ether analyzed using EPA Method 8260B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 8020 or 8021B.
Total Lead	=	Total lead analyzed using EPA Method 6010B.
HVOCs	=	Halogenated volatiles organic compounds using EPA Method 8260B.
TPHmo	=	Total petroleum hydrocarbons as motor oil analyzed using Modified EPA Method 8015M/8015B.
TOG	=	Total oil and grease analyzed using EPA Method 5520.
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
EDB	=	1,2-dibromoethane analyzed using EPA Method 8260B.
1,2-DCA	=	1,2-dichloroethane analyzed using EPA Method 8260B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
Cadmium	=	Cadmium analyzed using EPA Method 6010.
Chromium	=	Chromium analyzed using EPA Method 6010.
Nickel	=	Nickel analyzed using EPA Method 6010.
Zinc	=	Zinc analyzed using EPA Method 6010.
ND	=	Analytes not detected at or above the laboratory method detection limit.
mg/kg	=	Milligrams per kilogram.
	=	Not Analyzed/Not Applicable/Not sampled.
а	=	Analyzed using EPA Method 8021B.
ь	=	Analyzed using EPA Method 8240.
С	=	Hydrocarbon pattern does not resemble the requested fuel.
d	=	Analyte detected in associated method blank.

TABLE 3C ADDITIONAL CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES-METALS

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 2)

Sample D	Sample	Depth	Cadmium	Chromium	Nickel	Zinc	Sulfides	Cyanide
	Date	(fbgs)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
il Davi	01						((mg/kg)
oil Boring								
ot analyzed	for these analytes.							
uel Dispen	ser Samples							
	for these analytes.							
ank Pit Sar	<u>nples</u>							
ot analyzed	for these analytes.							
	nk Pit Sample							
/01	11/27/91	7.0	1.3	48	81	42		
	e Trench Samples							
ot analyzed	for these analytes.							
	le Samples							
S1-4	Nov-Dec 1991							
S 5-8	Nov-Dec 1991							
S9-12	Nov-Dec 1991							
S13-16	Nov-Dec 1991							
S17-20	Nov-Dec 1991							
S21-24	Nov-Dec 1991						<1.0	<0.5
S25-28	Nov-Dec 1991						<1.0	<0.5
41-4	Nov-Dec 1991							***
A5-8	Nov-Dec 1991							
A9-12	Nov-Dec 1991							
A13-16	Nov-Dec 1991					and the same		
A17-20	Nov-Dec 1991							
A21-24	Nov-Dec 1991					 -		
125-28	Nov-Dec 1991		<1.0b	43b	55b	41b		
129-32	Nov-Dec 1991							
P-1-1	03/29/00	¥						
P-1-1(1-4)	04/06/01							
P-1 (1-4)	03/07/07							
35-1 (154)	03/07/07							

TABLE 3C

ADDITIONAL CUMULATIVE LABORATORY ANALYTICAL RESULTS OF SOIL SAMPLES-METALS

Former Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 2 of 2)

Notes:		
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using modified EPA Method 8015M/8015B.
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using modified EPA Method 8015M/8015B.
MTBE	=	Methyl tertiary butyl ether analyzed using EPA Method 8260B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 8020 or 8021B.
Total Lead	=	Total lead analyzed using EPA Method 6010B.
HVOCs	=	Halogenated volatiles organic compounds using EPA Method 8260B.
TPHmo	=	Total petroleum hydrocarbons as motor oil analyzed using Modified EPA Method 8015M/8015B.
TOG	=	Total oil and grease analyzed using EPA Method 5520.
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
EDB	=	1,2-dibromoethane analyzed using EPA Method 8260B.
1,2-DCA	=	1,2-dichloroethane analyzed using EPA Method 8260B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
Cadmium	=	Cadmium analyzed using EPA Method 6010.
Chromium	=	Chromium analyzed using EPA Method 6010.
Nickel	=	Nickel analyzed using EPA Method 6010.
Zinc	=	Zinc analyzed using EPA Method 6010.
ND	=	Analytes not detected at or above the laboratory method detection limit.
mg/kg	=	Milligrams per kilogram.
	=	Not Analyzed/Not Applicable/Not sampled.
а	=	Analyzed using EPA Method 8021B.
b	=	Analyzed using EPA Method 8240.
С	=	Hydrocarbon pattern does not resemble the requested fuel.
d	=	Analyte detected in associated method blank.

TABLE 4A
CUMULATIVE LABORATORY ANALYTICAL RESULTS OF GRAB GROUNDWATER SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 2)

Sample ID	Sample Date	TPHd (μg/L)	TPHg (µg/L)	TPHmo (µg/L)	MTBE (µg/L)	B (µg/L)	T (µg/L)	E (µg/L)	Χ (μg/L)	TOG (µg/L)	HVOCs (µg/L)
GeoProbe Sam	plac							1000 7000			11-9:-/
W-13-GP1	03/29/00		450		_						
			<50	***	<2	<0.5	<0.5	<0.5	<0.5		***
N-23-GP1	03/29/00		<50	***	<2	<0.5	<0.5	<0.5	<0.5	***	***
N-12-GP2	03/29/00	***	100		<2	<0.5	<0.5	<0.5	<0.5		
N-23-GP2	03/29/00	****	<50		<2	<0.5	<0.5	<0.5	<0.5		
								-0.0	٧٥.5		***
Boring Sample	<u>s</u>										
W-15-B7	03/05/07	66b	<50	<470	0.54	< 0.50	<0.50	< 0.50	< 0.50		
W - 22-B7	03/05/07	220b	<50	<470	<0.50	<0.50	<0.50	< 0.50	< 0.50	***	***
N-14-B8	03/02/07	1 000h	4 E0	2 2005	7.0.50		F-94-407(m24-20)				
W-14-B0	03/02/07	1,900b	<50	2,800b	<0.50	<0.50	<0.50	<0.50	<0.50	100	
N-14-16-B9	03/06/07	1,000b	38,000	<480	120	15,000	890	700	1,700		***
W-22.5-24-B9	03/06/07	81b	490	<480	17	160	21	12	40		
								12	40		
Used-Oil Tank	Pit Sample										
JOW	11/27/91	18,000	550	***	2000	12/15a	4.9/7a	19/20a	72/<5a	580	70c
											1,55
N-Comp	10/26/00		1900	***		***	***				

TABLE 4A CUMULATIVE LABORATORY ANALYTICAL RESULTS OF GRAB GROUNDWATER SAMPLES

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 2 of 2)

Notes:		
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using EPA Method 8015M or 8015B.
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using modified EPA Method 8015M.
TPHmo	=	Total petroleum hydrocarbons as motor oil analyzed using EPA Method 8015B
MTBE	=	Methyl tertiary butyl ether analyzed using EPA Method 8021B or 8260B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 8021B.
TOG	=	Total oil and grease analyzed using EPA Method 5520.
HVOCs	=	Halogenated volatile organic compounds analyzed using EPA Method 8240 or 624.
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
EDB	=	1,2-dibromoethane analyzed using EPA Method 8260B.
1,2-DCA	=	1,2-dichloroethane analyzed using EPA Method 8260B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
Arsenic	=	Arsenic analyzed using EPA Method 200.7
Lead	=	Lead analyzed using EPA Method 200.7
Cadmium	=	Cadmium analyzed using EPA Method 200.7
Chromium	=	Chromium analyzed using EPA Method 200.7
Copper	=	Copper analyzed using EPA Method 200.7
Iron	=	Iron analyzed using EPA Method 200.7
Nickel	=	Nickel analyzed using EPA Method 200.7
Silver	=	Silver analyzed using EPA Method 200.7
Zinc	=	Zinc analyzed using EPA Method 200.7
μg/L	=	Micrograms per liter.
5 may 1	=	Not sampled/Not analyzed.
а	=	Analyzed using EPA Method 624.
b	Ξ	Hydrocarbon pattern does not resemble the requested fuel.
С	=	Bromoform.

TABLE 4B
ADDITIONAL CUMULATIVE LABORATORY ANALYTICAL RESULTS OF GRAB GROUNDWATER SAMPLES-VOCs

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 2)

Sample	Sample	TAME	TBA	DIPE	EDB	1,2-DCA	ETBE	Ethanol
ID	Date	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
GeoProbe Sample	<u>s</u>					11 0 7	(1-3)	(19/11)
Not analyzed for the	ese analytes.							
Boring Samples								
W - 15-B7	03/05/07	<0.50	<10	< 0.50	<0.50	<0.50	<0.50	<100
W-22 - B7	03/05/07	<0.50	<10	<0.50	<0.50	<0.50	<0.50	<100
W-14-B8	03/02/07	<0.50	<12	<0.50	<0.50	<0.50	<0.50	<100
						-0.00	40.50	<100
W-14-16-B9	03/06/07	<50	<500	<50	<50	<50	<50	<10,000
W-22.5-24 - B9	03/06/07	<1.0	<10	3.4	<1.0	<1.0	<1.0	<200
Used-Oil Tank Pit	Sample							
Not analyzed for the								
W-Comp	10/26/00						-	

TABLE 4B

ADDITIONAL CUMULATIVE LABORATORY ANALYTICAL RESULTS OF GRAB GROUNDWATER SAMPLES-VOCs

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 2 of 2)


Notes:		
TPHd	=	Total petroleum hydrocarbons as diesel analyzed using EPA Method 8015M or 8015B.
TPHg	=	Total petroleum hydrocarbons as gasoline analyzed using modified EPA Method 8015M.
TPHmo	=	Total petroleum hydrocarbons as motor oil analyzed using EPA Method 8015B
MTBE	=	Methyl tertiary butyl ether analyzed using EPA Method 8021B or 8260B.
BTEX	=	Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 8021B.
TOG	=	Total oil and grease analyzed using EPA Method 5520.
HVOCs	=	Halogenated volatile organic compounds analyzed using EPA Method 8240 or 624.
TAME	=	Tertiary amyl methyl ether analyzed using EPA Method 8260B.
TBA	=	Tertiary butyl alcohol analyzed using EPA Method 8260B.
DIPE	=	Di-isopropyl ether analyzed using EPA Method 8260B.
EDB	=	1,2-dibromoethane analyzed using EPA Method 8260B.
1,2-DCA	=	1,2-dichloroethane analyzed using EPA Method 8260B.
ETBE	=	Ethyl tertiary butyl ether analyzed using EPA Method 8260B.
Ethanol	=	Ethanol analyzed using EPA Method 8260B.
Arsenic	=	Arsenic analyzed using EPA Method 200.7
Lead	=	Lead analyzed using EPA Method 200,7
Cadmium	=	Cadmium analyzed using EPA Method 200.7
Chromium	=	Chromium analyzed using EPA Method 200.7
Copper	=	Copper analyzed using EPA Method 200.7
Iron	=	Iron analyzed using EPA Method 200.7
Nickel	=	Nickel analyzed using EPA Method 200.7
Silver	=	Silver analyzed using EPA Method 200.7
Zinc	=	Zinc analyzed using EPA Method 200.7
μg/L	=	Micrograms per liter.
	=	Not sampled/Not analyzed.
а	=	Analyzed using EPA Method 624.
b	=	Hydrocarbon pattern does not resemble the requested fuel.
c	=	Bromoform.

TABLE 4C

ADDITIONAL CUMULATIVE LABORATORY ANALYTICAL RESULTS OF GRAB GROUNDWATER SAMPLES-METALS

Exxon Service Station 7-0235 2225 Telegraph Avenue Oakland, California (Page 1 of 1)

Sample D	Sample Date	Arsenic	Lead	Cadmium	Chromium	Copper	Iron	Nickel	Silver	Zinc				
υ <u></u>	Date	(μg/L)	(μg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)	(μg/L)	(µg/L)	(µg/L)				
edProbe	Samples													
	ed for these ar	alutos												
vot analyzo	101 111 0 36 al	lary tes.												
Boring San	nples													
	ed for these ar	nalvtes.												
,		,												
Jsed-Oil Ta	ank Pit Sam	<u>ple</u>												
JOW	11/27/91	_	<100	<5	<10	(2000)		30	-	10				
								-	(2500)	10				
<i>N-</i> Comp	10/26/00	11.5	<5	<5	<10	<10	825	27.5	<10	28.5				
								2	-10	20.0				
Notes:														
TPHd	=	Total petroleum h	ydrocarbons as o	diesel analyzed usi	ng EPA Method 80	15M or 8015B.								
TPHg	=	Total petroleum h	ydrocarbons as (gasoline analyzed ι	using modified EPA	Method 8015M.								
TPHmo	=	Total petroleum h	ydrocarbons as r	notor oil analyzed	using EPA Method	8015B								
MTBE	=				od 8021B or 8260B									
BTEX	=	Benzene, toluene,	, ethylbe <mark>nzen</mark> e, a	and total xylenes ar	nalyzed using EPA	Method 8021B.								
TOG	=		Benzene, toluene, ethylbenzene, and total xylenes analyzed using EPA Method 8021B. Total oil and grease analyzed using EPA Method 5520.											
HVOCs	=	Halogenated volat	tile organic comp	ounds analyzed us	sing EPA Method 8	240 or 624.								
TAME	=			ed using EPA Meth										
TBA	=	Tertiary butyl alco	hol analyzed usi	ng EPA Method 82	260B.									
DIPE	=			EPA Method 8260										
EDB	=			EPA Method 826										
1,2-DCA	=			EPA Method 8260										
ETBE	=			using EPA Method										
Ethanol	=	Ethanol analyzed			1 0200B.									
Arsenic	=	Arsenic analyzed	-											
Lead	=	-												
Cadmium		Lead analyzed usi	_											
		Cadmium analyze	•											
Chromium		Chromium analyz												
Copper	=	Copper analyzed	•											
Iron	=	Iron analyzed usir												
Nickel	=	Nickel analyzed u	sing EPA Metho	d 200.7										
Silver	=	Silver analyzed us	sing EPA Method	1 200.7										
Zinc	=	Zinc analyzed usi	ng EPA Method	200.7										
μg/L	=	Micrograms per li	ter.											
_	=	Not sampled/Not	analyzed.											
а	=	Analyzed using E	PA Method 624.											
b	=	Hydrocarbon patte			d final									
υ				2111010 (110 160119216	a ruei.									




FN 2229Topo

EXPLANATION



1/2-mile radius circle







SITE VICINITY MAP

FORMER EXXON SERVICE STATION 7-0235 2225 Telegraph Avenue Oakland, California PROJECT NO. 2229

PLATE

1





- - Up OUTTHY RISPOSE

GROUNDWATER ELEVATION MAP January 19, 2007

FORMER EXXON STATION 7-0235 2225 Telegraph Avenue Oakland, California

Groundwater Monitoring Well


7.24 Groundwater elevation in feet; datum is mean sea level


RW3A Recovery Well


PROJECT NO. 2229

PLATE

3







ATTACHMENT A REGULATORY CORRESPONDENCE

ALAMEDA COUNTY HEALTH CARE SERVICES





October 10, 2003

Gene Ortega, Territory Manager Global Remediation – US Retail FAX (510) 337-9335 ExxonMobil
Refining & Supply Co.
Global Remediation
2300 Clayton Rd., Suite 1250
Concord, CA 94520

DECEIVED A OCT 15 2003

BY:____

ENVIRONMENTAL HEALTH SERVICES

ENVIRONMENTAL PROTECTION

Alameda, CA 94502-6577 (510) 567-6700

1131 Harbor Bay Parkway, Suite 250

Dear Mr. Ortega:

Subject:

Fuel Leak Case No. RO0000358, Exxon #7-0235,

2225 Telegraph Ave., Oakland, CA

Alameda County Environmental Health staff reviewed "Response to Agency Comments and Request for Information, ...", dated May 22, 2003, and "Response to Agency Comments, ..." dated October 29, 2002, both prepared by Environmental Resolutions, Inc. The work plan is disapproved for the reasons stated. We request that you address the following technical comments and send us the technical reports requested below.

TECHNICAL COMMENTS

1) Preferential Pathway Study – We received a map showing the locations of utilities on Telegraph Ave. between West Grand Ave. and 22nd St. However, the depths of gas, electric, water, and storm drain trenches were not provided. The depth of the sewer trench was provided and it was indicated that at its depth groundwater could be intercepted. For the other utilities, the estimated depths may be used to determine if be could be intercepted. Please submit map(s) and cross-sections showing the location and depth of all utility lines and trenches (including sewers, storm drains, pipelines, trench backfill, etc.) within and near the site and plume area(s). Evaluate the probability of the contaminant plumes encountering preferential pathways and conduits that could spread the contamination, particularly in the vertical direction to deeper water aquifers. Please incorporate into the Work Plan requested below. If so, propose a sampling plan for the trenches. Include in the Work Plan Addendum requested below.

2) Proposed Groundwater Monitoring Well - The preferential pathway study needs to be done prior to locating the well. Groundwater samples have been collected by the proposed well MW6K. The concentrations were at or below laboratory method reporting limits. Grab groundwater samples were collected from locations GP1 and GP2, on March 29, 2000. Concentrations of dissolved hydrocarbons in both grab groundwater sampling points were below laboratory method reporting limits except 100 ug/l Total Purgeable Petroleum Hydrocarbons as Gasoline (TPPH-G). Monitoring well MW6J has been sampled quarterly since July 5, 2001. MW6J concentrations exceeded laboratory

method reporting limits only on April 2, 2002, 1 ug/l Methyl Tertiary-Butyl Ether (MTBE), 0.8 ug/l benzene, and 0.8 ug/l xylene. The nearly nondetectable concentrations makes the proposed well location undesirable because it may indicate that the location is beyond the limits of the plume or that the plume flow is in a different direction. Please propose additional grab groundwater sampling to determine the location of the plume for optimal well locations. We request that depth discrete grab groundwater sampling be used. Include your proposal in the Work Plan Addendum requested below.

3) DPE Interim Remediation - "Dual-Phase Extraction (DPE) Pilot Test" dated October 19, 2001 determined that DPE was effective at this site. We have not received your recommendations and specifications for DPE on a full scale as previously requested. Instead, you propose a Corrective Action Plan (CAP), which will evaluate remedial alternatives, including DPE, at this site. Please indicate the elements and the other remedial alternatives that you plan to include in your evaluation. Include in the Work Plan Addendum requested below.

4) Groundwater Monitoring – Your consultant indicated that sampling of the requested fuel oxygenates and lead scavengers would be initiated during the first quarter 2003. We seem to have misplaced that report. Please submit another copy.

5) Professional seal - Both reports reviewed were unstamped. All technical reports must contain a statement of professional certification with the appropriate professional signatures and seals.

TECHNICAL REPORT REQUEST

Please submit the following technical reports to the Alameda County Environmental Health (Attention: Don Hwang), according to the following schedule:

October 31, 2003 - Quarterly Groundwater Monitoring Report, 1st Quarter 2003 October 31, 2003 - Quarterly Groundwater Monitoring Report, 2nd Quarter 2003 October 31, 2003 - Quarterly Groundwater Monitoring Report, 3rd Quarter 2003 December 10, 2003 - Work Plan Addendum
January 31, 2004 - Quarterly Groundwater Monitoring Report, 4th Quarter 2003

If you have any questions, you may call me at 510/567-6746.

Sincerely,

Don Hwang

Hazardous Materials Specialist

Local Oversight Program

c: VPaula Sime, Environmental Resolutions, Inc., 73 Digital Dr., Novato, CA 94949-5791
Donna Drogos

File

MEDA COUNTY HEALTH CARE SERVICES








March 15, 2004

ENVIRONMENTAL HEALTH SERVICES ENVIRONMENTAL PROTECTION 1131 Harbor Bay Parkway, Suite 250 Alameda, CA 94502-6577 (510) 567-6700 FAX (510) 337-9335

Gene Ortega, Territory Manager Global Remediation - US Retail ExxonMobil Refining & Supply Co. Global Remediation 2300 Clayton Rd., Suite 1250 Concord, CA 94520



Dear Mr. Ortega:

Subject:

Fuel Leak Case No. RO0000358, Exxon #7-0235,

2225 Telegraph Ave., Oakland, CA

Alameda County Environmental Health staff reviewed "Response to Agency Comments and Addendum to Preferential Pathway Study and Work Plan" dated December 8, 2003, and Quarterly Groundwater Monitoring Report, 4th Quarter 2003" dated January 20, 2004, both prepared by Environmental Resolutions, Inc. We request that you address the following technical comments and send us the technical reports requested below.

TECHNICAL COMMENTS

- 1) Proposed Locations Off-site Soil Borings (B5 through B7): The proposed locations for B5 and B6 are acceptable. The proposed location of B7 appears to be where GP2 was collected when 100 ug/l Total Purgeable Petroleum Hydrocarbons as gasoline (TPPHg) was detected at 12 feet. Therefore, a different location ought to be selected. We request that depth discrete grab groundwater sampling be used. Please propose additional grab groundwater sampling locations to determine optimal well locations. Include your proposal in the Work Plan Addendum requested below.
- 2) Depth of Borings The proposed borings depths are to just below first-encountered groundwater. The collection of groundwater samples at that depth may miss petroleum product entrapped below the water table. Please propose drilling borings to depths below the water table, which will account for entrapped petroleum product. Include in the Work Plan Addendum.
- 3) Soil Samples from Borings Instead of collecting soil boring samples at 5 ft. intervals as proposed, soil samples shall be collected at a minimum of every 5 ft., including at changes of lithology, at the soil/groundwater interface, and at areas of obvious contamination. Please include in the Work Plan Addendum.

Mr. Ortega March 15, 2004 Page 2 of 2

- 4) Preferential Pathway Study Geologic cross sections including underground utilities were provided. Based on the depths of the underground utilities versus the historic highest and lowest groundwater levels, it was determined that groundwater does not intersect the utility trenches. Were the width of the utility lines and trench backfill taken into consideration?
- 5) DPE Interim Remediation Please state why you want to evaluate other remedial alternatives after conducting a Dual-Phase Extraction (DPE) Pilot Test, which determined that DPE was effective at this site.
- 6) Historical Hydraulic Gradients Please remember to include a rose diagram with magnitude and direction; include cumulative groundwater gradients in all future reports submitted for this site.

TECHNICAL REPORT REQUEST

Please submit the following technical reports to the Alameda County Environmental Health (Attention: Don Hwang), according to the following schedule:

April 30, 2004 - Work Plan Addendum

April 30, 2004 - Quarterly Groundwater Monitoring Report, 1st Quarter 2004 July 31, 2004 - Quarterly Groundwater Monitoring Report, 2nd Quarter 2004 October 31, 2004 - Quarterly Groundwater Monitoring Report, 3rd Quarter 2004 January 31, 2005 - Quarterly Groundwater Monitoring Report, 4th Quarter 2004

If you have any questions, you may call me at 510/567-6746.

Sincerely,

Don Hwang

Hazardous Materials Specialist

Local Oversight Program

c: Robert Saur, Environmental Resolutions, Inc., 73 Digital Dr., Suite 100, Novato, CA 94949-5791


Donna Drogos

File

ALAMEDA COUNTY HEALTH CARE SERVICES

AGENCY





BY:....

ENVIRONMENTAL HEALTH SERVICES ENVIRONMENTAL PROTECTION 1131 Harbor Bay Parkway, Suite 250 Alameda, CA 94502-6577 (510) 567-6700 FAX (510) 337-9335

January 11, 2007

Ms. Jennifer Sedlachek ExxonMobil Refining & Supply – Global Remediation 4096 Piedmont Avenue #194 Oakland, CA 94611

DAVID J. KEARS, Agency Director

Mr. Lam Truong 2225 Telegraph Avenue Oakland, CA 94612-2315 Mr. William Wong PO Box 4032 Concord, CA 94524-2032

Mr. Mark Inglis 6001 Bollinger Canyon Rd PO Box 6012 San Ramon, CA 94583-2324

Subject: Fuel Leak Case No. RO0000358, Exxon #7-2035, 2225 Telegraph Ave., Oakland CA

Dear Ms. Sediachek and Messrs. Wong, Inglis and Troung

Alameda County Environmental Health Department (ACEH) staff has reviewed the recently submitted reports entitled, "Groundwater Monitoring Report, Second Quarter 2006", and "Addendum to Preferential Pathway Study and Work Plan", dated December 8, 2003 and prepared on your behalf by Environmental Resolutions Inc. (ERI). ACEH agrees with the need for additional off-site soil and groundwater investigation in order to properly characterize soil and groundwater conditions and contamination issues immediately downgradient of the site.

Currently, elevated concentrations of petroleum hydrocarbons occur throughout the site, specifically in monitoring wells MW-6B, MW-6H and RW-1. During April 2006 quarterly groundwater monitoring and sampling, groundwater samples tested maximum concentrations of up to 11,000 µg/L, 2,000 µg/L benzene and 160 µg/L. MtBE, respectively. In November 2004 a groundwater sample collected from RW-1 tested elevated concentrations of 127,000 µg/L for TPHg, which is approximately two orders of magnitude above historical concentrations for this well. It is possible that an unreported leak occurred beneath the fuel dispensers and caused this anomalous result. Please provide ACEH with a plausible explanation as to the cause of this unusual result. In addition, the proposed Work Plan recommends the installation of four additional offsite soil borings to characterize potential dissolved plume migration immediately downgradient of your site. Please see the technical comments below regarding the proposed work plan implementation.

We request that you perform the proposed work address the following technical comments and send us the reports described below. Please provide 72-hour advance written notification to this office (e-mail preferred to steven.plunkett@acgov.org) prior to the start of field activities.

TECHNICAL COMMENTS

1. Proposed Soil Boring Installation and Soil Sampling. Current conditions along the northeast property line of the site indicate the presence of elevated concentrations of petroleum hydrocarbons in soil and groundwater. ERI has proposed the installation of four additional soil borings downgradient of MW-6H, MW-6J and RW-2. ACEH generally concurs with the recommendations in the Work Plan provided the following conditions are satisfied. The proposed soil boring locations B5 and B6 are approximately 60 feet apart. Considering the linear separation between these two soil borings, ACEH recommends the installation of one additional soil boring midway between B5 and B6. Furthermore, to delineate the extent of potential off site contamination migration at the north end of the site, ACEH also recommends the installation of one additional soil boring down gradient of MW-6B. The off site Soil Water Investigation (SWI) should include a total of five soil borings.

ERI suggests that soil sampling be completed to a maximum depth of 20 feet bgs. It is important to determine the depth at which soil is not impacted by petroleum hydrocarbon contamination, and thus demonstrate the vertical profile of soil contamination. ACEH requests that soil samples be submitted for laboratory analyses from the capillary fringe and all depth intervals where staining, odor, changes in lithology or elevated PID readings are observed. If staining, odor, or elevated PID readings are observed over an interval of several feet, a sufficient number of soil samples from this interval should be submitted for laboratory analyses to characterize the contamination within this interval. Please present the result of the SWI in the report requested below.

2. Preferential Pathway Study

The purpose of the preferential pathway study is to locate potential migration pathways and conduits and determine the probability of the NAPL and/or plume encountering preferential pathways or conduits that could spread contamination. In particular, the location of the BART tunnel that runs adjacent to the project site. Please evaluate the trend of the tunnel, type of construction and depth of the tunnel boring below grade to determine if the structure and surrounding fill material may be acting as a conduit for plume migration.

a) Well Survey

The preferential pathway study shall include a detailed well survey of all wells (monitoring and production wells: active, inactive, standby decommissioned (sealed with concrete), abandoned, (improperly decommissioned or lost); and dewatering and cathodic protection wells) within a 2000 feet radius of the subject site. The well survey should include well data from California Department of Water Resource well database and Alameda County Department of Public Works. Submittal of map(s) showing the location of all wells identified in your study, and the use of tables to report the data collected as part of your survey are required. Please refer to the Regional Board's guidance for identification, location, and evaluation of potential deep well conduits when conducting your preferential pathway study. Present the result from the preferential pathway study in the report requested below.

3. Depth Discrete Groundwater Sampling. ACEH is concerned that dissolved phase contamination may be moving off site, and thus we agrees with need for depth discrete

groundwater sampling as proposed by ERI. Review of the soil boring data indicate the possibility that a discrete lithologic unit exists at approximately 15 to 20 feet bgs, ACEH requests that depth discrete groundwater samples be collected from this unit to determine whether it maybe contributing to the migration of contamination down gradient of the site. ACEH recommends using the soil boring data to target discrete groundwater bearing zones and direct groundwater sampling activities accordingly. ACEH requests that grab groundwater samples be collected at first groundwater encountered from each direct push soil boring and at locations determined during the soil boring installation. Please present the result from depth discrete groundwater sampling in the SWI requested below.

- 4. Soil Chemical Analysis. ACEH requests that all soil samples collected below five feet bgs. are to be analyzed for the following constituents; TPHg and TPHd by EPA Method 8015M or 8260, BTEX, EDB, EDC, MtBE, TAME, ETBE, DIPE, TBA and EtOH by EPA Method 8260. Please include results from the investigation in the SWI requested below.
- 5. Groundwater Chemical Analysis. ACEH requests that all grab groundwater samples collected during the investigation be analyzed for the following constituents; TPHg and TPHd by EPA Method 8015M or 8260, BTEX, EDB, EDC, MtBE, TAME, ETBE, DIPE, TBA and EtOH by EPA Method 8260. Please include results from the investigation in the SWI requested below.
- 6. Project Approach and Investigation Reporting Site Conceptual Model

We anticipate that characterization and remediation work in addition to what is requested in this letter will be necessary at and down gradient from your site. Considerable cost savings can be realized if your consultant focuses on developing and refining a viable Site Conceptual Model (SCM) for the project. A SCM is a set of working hypotheses pertaining to all aspects of the contaminant release, including site geology, hydrogeology, release history, residual and dissolved contamination, attenuation mechanisms, pathways to nearby receptors, and likely magnitude of potential impacts to receptors. The SCM is used to identify data gaps that are subsequently filled as the investigation proceeds. As the data gaps are filled, the working hypotheses are modified, and the overall SCM is refined and strengthened. Subsurface investigations continue until the SCM no longer changes as new data are collected. At this point, the SCM is said to be "validated." The validated SCM then forms the foundation for developing the most cost-effective corrective action plan to protect existing and potential receptors.

When performed properly, the process of developing, refining and ultimately validating the SCM effectively guides the scope of the entire site investigation. We have identified, based on our review of existing data, some initial key data gaps in this letter and have described several tasks that we believe will provide important new data to refine the SCM. We request that your consultant develop a SCM for this site, identify data gaps, and propose specific supplemental tasks for future investigations. There may need to be additional phases of investigations, each building on the results of the prior work, to validate the SCM. Characterizing the site in this way will improve the efficiency of the work and limit its overall cost.

Both industry and the regulatory community endorse the SCM approach. Technical guidance for developing SCMs is presented in API's Publication No. 4699 and EPA's Publication No.

EPA 510-B-97-001 both referenced above; and "Guidelines for Investigation and Cleanup of MTBE and Other Ether-Based Oxygenates, Appendix C," prepared by the State Water Resources Control Board, dated March 27, 2000.

The SCM for this project shall incorporate, but not be limited to, the following:

- a) A concise narrative discussion of the regional geologic and hydrogeologic setting obtained from your background study. Include a list of technical references you reviewed, and copies (photocopies are sufficient) of regional geologic maps, groundwater contours, rose diagrams, cross-sections, etc.
- b) A concise discussion of the on-site and off-site geology, hydrogeology, release history, source zone, plume development and migration, attenuation mechanisms, preferential pathways, and potential threat to down gradient and above-ground receptors. Be sure to include the vapor pathway in your analysis. Maximize the use of large-scale graphics (e.g., maps, cross-sections, contour maps, etc.) and conceptual diagrams to illustrate key points. Geologic cross-sections, which include an interpretive drawing of the vertical extent of soil and groundwater contamination (i.e., an interpretive drawing—not a plot of laboratory results). The SCM report requested below is to include one cross section parallel and one cross section perpendicular to the contaminant plume axis. Each cross section should include, but not be restricted to, the following:
 - 1. Subsurface geologic features, depth to groundwater and man-made conduits.
 - Surface topography. The cross sections should be extended off-site where necessary to show significant breaks in slope.
 - 3. Soil descriptions for all borings and wells along the line of section.
 - 4. Screen and filter pack intervals for each monitoring well.
 - 5. Sampling locations and results for soil and grab groundwater samples.
 - Site features such as the tank pit, dispensers, buildings etc. Where appropriate, monitoring well location and soil boring locations will be projected back to the strike of the cross section line.
- c) Identification and listing of specific data gaps that require further investigation during subsequent phases of work.
- d) Proposed activities to investigate and fill data gaps identified above.
- e) The SCM shall include an analysis of the hydraulic flow system at and down gradient from the site. Include rose diagrams for groundwater gradients. The rose diagram shall be plotted on groundwater contour maps and updated in all future reports submitted for your site. Include an analysis of vertical hydraulic gradients. Note that these likely change due to seasonal precipitation and pumping.
- f) Temporal changes in the plume location and concentrations are also a key element of the SCM. In addition to providing a measure of the magnitude of the problem, these data are often useful to confirm details of the flow system inferred from the hydraulic head measurements. Include plots of the contaminant plumes on your maps, cross-sections, and diagrams.

- g) Several other contaminant release sites exist in the vicinity of your site. Hydrogeologic and contaminant data from those sites may prove helpful in testing certain hypotheses for your SCM. Include a summary of work and technical findings from nearby release sites and incorporate the findings from nearby site investigations into your SCM.
- h) Plots of chemical concentrations vs. time and vs. distance from the source. Plots should be shown for each monitoring well, which has had detectable levels of contaminants
- i) Summary tables of chemical concentrations in each historically sampled media (including soil, groundwater and soil vapor).
- Boring and well logs (including construction/screening), and a summary table indicating construction specifications for each monitoring and extraction well.

Please report the information discussed above in your initial SCM and include it in the SCM Report requested below.

TECHNICAL REPORT REQUEST

Please submit technical reports to Alameda County Environmental Health (Attention: Mr. Steven Plunkett), according to the following schedule:

- February 15, 2007 Updated preferential Pathway Study with Site Conceptual Model .
- March 30, 2007 Soil and Groundwater Investigation Report

These reports are being requested pursuant to California Health and Safety Code Section 25296.10. 23 CCR Sections 2652 through 2654, and 2721 through 2728 outline the responsibilities of a responsible party in response to an unauthorized release from a petroleum UST system, and require your compliance with this request.

ELECTRONIC SUBMITTAL OF REPORTS

The Alameda County Environmental Cleanup Oversight Programs (LOP and SLIC) require submission of all reports in electronic form to the county's ftp site. Paper copies of reports will no longer be accepted. The electronic copy replaces the paper copy and will be used for all public information requests, regulatory review, and compliance/enforcement activities. Instructions for submission of electronic documents to the Alameda County Environmental Cleanup Oversight Program ftp site are provided on the attached "Electronic Report Upload (ftp) Instructions." Please do not submit reports as attachments to electronic mail. Submission of reports to the Alameda County ftp site is an addition to existing requirements for electronic submittal of information to the State Water Resources Control Board (SWRCB) Geotracker website. Submission of reports to the Geotracker website does not fulfill the requirement to submit documents to the Alameda County ftp site. In September 2004, the SWRCB adopted regulations that require electronic submittal of information for groundwater cleanup programs. For several years, responsible parties for cleanup of leaks from underground storage tanks (USTs) have been required to submit groundwater analytical data, surveyed locations of monitor wells, and other data to the Geotracker database over the Internet. Beginning July 1, 2005, electronic submittal of a complete copy of all necessary reports was required in Geotracker (in PDF format).

Jennifer Sedlachek January 8, 2007 Page 6

Please visit the SWRCB website for more information on these requirements (http://www.swrcb.ca.gov/ust/cleanup/electronic reporting).

PERJURY STATEMENT

All work plans, technical reports, or technical documents submitted to ACEH must be accompanied by a cover letter from the responsible party that states, at a minimum, the following: "I declare, under penalty of perjury, that the information and/or recommendations contained in the attached document or report is true and correct to the best of my knowledge." This letter must be signed by an officer or legally authorized representative of your company. Please include a cover letter satisfying these requirements with all future reports and technical documents submitted for this fuel leak case.

PROFESSIONAL CERTIFICATION & CONCLUSIONS/RECOMMENDATIONS

The California Business and Professions Code (Sections 6735, 6835, and 7835.1) requires that work plans and technical or implementation reports containing geologic or engineering evaluations and/or judgments be performed under the direction of an appropriately registered or certified professional. For your submittal to be considered a valid technical report, you are to present site specific data, data interpretations, and recommendations prepared by an appropriately licensed professional and include the professional registration stamp, signature, and statement of professional certification. Please ensure all that all technical reports submitted for this fuel leak case meet this requirement.

UNDERGROUND STORAGE TANK CLEANUP FUND

Please note that delays in investigation, later reports, or enforcement actions may result in your becoming ineligible to receive grant money from the state's Underground Storage Tank Cleanup Fund (Senate Bill 2004) to reimburse you for the cost of cleanup.

AGENCY OVERSIGHT

If it appears as though significant delays are occurring or reports are not submitted as requested, we will consider referring your case to the Regional Board or other appropriate agency, including the County District Attorney, for possible enforcement actions. California Health and Safety Code, Section 25299.76 authorizes enforcement including administrative action or monetary penalties of up to \$10,000 per day for each day of violation.

If you have any questions, please call me at (510) 383-1767.

Sincerely,

Steven Plunkett

Hazardous Materials Specialist

- 6
·
1
· ·
30
100
190
1.5
e Ji
, J =

UNIFIED SOIL CLASSIFICATION SYSTEM

MAJOR	MAJOR DIVISIONS		DESCRIPTION	MAJOR I	OIVISIONS	LTR	DESCRIPTION		
		GW	Well-graded gravels or gravel sand mixtures, little or no fines			ML	Inorganic silts and very fine- grained sands, rock flour, silty		
	GRAVEL AND	GP	Poorly-graded gravels or gravel sand mixture, little or no fines	_	SILTS AND		or clayey fine sands or clayey silts with slight plasticity		
	GRAVELLY SOILS	GM	Silty gravels, gravel-sand-clay mixtures		CLAYS LL<50	CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays		
COARSE GRAINED		GC	Clayey gravels, gravel—sand—clay mixtures	FINE		OL	Organic silts and organic silt- clays of low plasticity		
SOILS		SW	Well-graded sands or gravelly sands, little or no fines	GRAINED SOILS	SILTS AND CLAYS	МН	Inorganic silts, micaceous or diatomaceous fine-grained sandy or silty soils, elastic silts		
	SAND AND SANDY	SP	Poorly—graded sands or gravelly sands, little or no fines			СН	Inorganic clays of high plast- icity, fat clays		
	SOILS	SM	Silty sands, sand-silt mixtures		LL>50	ОН	Organic clays of medium to high plasticity		
		SC	Clayey sands, sand-clay mixtures	HIGHLY ORGANIC SOILS		Pt	Peat and other highly organic soils		

			WELL DESIGN
\prod	DEPTH THROUGH WHICH SAMPLER IS DRIVEN		SAND PACK
Ţ	RELATIVELY UNDISTURBED SAMPLE		BENTONITE ANNULAR SEAL
	MISSED SAMPLE		NEAT CEMENT ANNULAR SEAL
	GROUNDWATER LEVEL OBSERVED FROM FIRST WET SOIL SAMPLE IN BORING		BLANK PVC
<u>_</u>	STATIC GROUNDWATER LEVEL		MACHINE-SLOTTED PVC
OVM	ORGANIC VAPOR METER READING IN PARTS PER MILLION	S-10	SAMPLE LOCATION
		NR	NOT RECORDED
PID	PHOTO-IONIZATION DETECTOR READING IN PARTS PER MILLION	NA	NOT ANALYZED

BLOW/FT. REPRESENTS THE NUMBER OF BLOWS OF A 140-POUND HAMMER FALLING 30 INCHES TO DRIVE THE SAMPLER THROUGH THE LAST 12 INCHES OF AN 18-INCH OR 24-INCH PENETRATION.

DASHED LINES SEPARATING UNITS ON THE LOG REPRESENT APPROXIMATE BOUNDARIES ONLY. ACTUAL BOUNDARIES MAY BE GRADUAL. LOGS REPRESENT SUBSURFACE CONDITIONS AT THE BORING LOCATION AT THE TIME OF DRILLING ONLY.



UNIFIED SOIL CLASSIFICATION SYSTEM AND LOG OF BORINGS SYMBOL KEY

FORMER EXXON SERVICE STATION 7-0235 2225 Telegraph Avenue Oakland, California **ATTACHMENT**

В

Site: Logge Review	pject No.: : Former Exxon Service Station : : 2225 Telegraph Ave., Oakland gged By: : Heidi L. Dieffenbach-Carle, P. viewed By: : Heidi L. Dieffenbach-Carle, P. nature: : 1						n 7-0235 id, California .G. #6793	ORING LO	: 03/01/2007 : Woodward Drilling Co. : Hand Auger : Hand Auger : 4" : N/A : 2122807.2 : 6050644.4 : 5.5' bgs		
Depth (ft)	Blow Count	OVM/PID (ppmv)	Sample	Column	uscs		ole Condition No Recovery Sampled Inter Described Sar Preserved Sar	mple	Water Levels ▼ ✓		Boring: B5
10 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -			***			Cleared Metal p Boreho Sand w activitie	ete Y GRAVEL V graded (FILL) d with air/wate ipe encounter te terminated. as used to fill s.	er knife and hand red in borehole.	auger to 5.5'		-Neat Cement

Project Site: Logge Reviet Signat	d By: wed By		: Forr : 222! : Heid	li L. Dieffe	Serving Servin	ce Station ., Oaklan -Carle, P.	d, California .G. #6793 .G. #6793	: 03/06/2007 : Woodward Drilling Co. : Hand Auger : Hand Auger : 4" : N/A : 2122752.9 : 6050632.6 : 3.5' bgs			
Depth (ft)	Blow Count	Sample Condition No Recovery Sampled Interval							Boring: B6		
0-		, U			GW	(FILL).	Y GRAVEL, fine- t		ned sand, brown,	well graded	Concrete Neat Cement Sand
5-						Clay pip Borehol Sand w activitie	d with air/water kn pe encountered in le terminated. vas used to fill the ss. lwater was not end	pipe backfill	auger to 3.5' removed during ha	and auger	
10-											
-											
15-											
20-											


04-09-2007 J:\2229\BORING LOGS\B6.bor


Project No Site: Logged By Reviewed	Project No.: : Former Exxon Service Stat Site: : 2225 Telegraph Ave., Oakl Logged By: : Vince Battaglia Reviewed By: : Heidi L. Dieffenbach-Carle, Signature: : Heidi L. Dieffenbach-Carle,					kland, California Location N-S Location E-W			: 03/05/2007 : Woodward Drilling : Direct Push : Continuous Core : 2" : N/A : 2122728.8 : 6050676.1 : 26' bgs : 13' bgs
Depth (ft)	nut C					ple Condition No Recovery Sampled Interval Described Sample Preserved Sample DESCR	Boring: B7		
5-	0.0	**		SP CL SP	Gravel SILTY fine gravel SILTY fine gravel CLAYE with fine deposit SANDY fine gravel deposit SILTY @ 7.0' @ 8.0' SILTY C SAND: SILTY C SAND: SILTY C SAND: SILTY C nodules SAND: fine graded.	ine to medium grained, dark (15%). SAND: fine grained, dark brown (15%). SAND: fine grained, dark brown (15%). SAND: fine grained, dark brown (15%). Y SILT WITH SAND: light brownship (15%). Y SILT WITH CLAY: yellowish (15%). CLAY WITH SAND: dark brown (15%). CLAY WITH SAND: dark brown (15%). CLAY: light brown, high plastic (15%). CLAY: light brown, high plastic (15%). CLAY: grayish light brown, high (15%). CLAY: grayish light brown, high (15%). CLAY: light brown, moist, hard, (15%).	brown, damp, poor yn, damp, rounded, m, damp, medium g (30%) and trace cabrown, damp, low p and (30%) and trace n, damp, hard, med (20%). race Fe oxide nodultrace Mn and Fe oxide round (20%), moist. The brown, wet. The plasticity, moist, we have the plasticity, moist, we have the plasticity, with high plasticity with high high plasticity with high high high high high high high h	poorly graded. poorly graded. plasticity, with dium plasticity, plasticity, with ce carbonate dium plasticity, plasticity, with dium plasticity, plasticity, with ce carbonate dium plasticity, ules. wide deposits.	-Neat Cement

04-09-2007 J:\2229\BORING LOGS\B7.bor

ERI	NVIRONMENTAL RESOLUTIONS, INC.	BORING LOC	9 B7 Page 2 of 2)	Date Drilled: Drilling Co.: Drilling Method: Sampling Method: Borehole Diameter:	: 03/05/2007 : Woodward Drilling : Direct Push : Continuous Core : 2"
Project No.: Site: Logged By: Reviewed By: Signature:	: Former Exxon Service Statio : 2225 Telegraph Ave., Oaklar : Vince Battaglia : Heidi L. Dieffenbach-Carle, P	nd, California	Casing Diameter: Location N-S Location E-W Total Depth: First GW Depth:	: N/A : 2122728.8 : 6050676.1 : 26' bgs : 13' bgs	
Depth (ft) Blow Count OVM/PID (ppmv)		ple Condition No Recovery Sampled Interval Described Sample Preserved Sample DESCR	Water Levels ▼ ✓ PTION		Boring: B7
20	SP SAND nodule SP SAND nodule SP SAND nodule SP SAND rounder SP SAND rounder	ELLY CLAY WITH SAND: light rained poorly graded sand (15%); fine to coarse grained (75%), to exide nodules. Y CLAY: light brown, moderate sand in the to coarse grained (90%), to ately graded. Y CLAY: light brown, moderate ad sand (15%), trace Fe oxide not sand (15%).	plasticity, hard, tra (40%).	ately graded,	- Neat Cement

Site: Logged Review	Project No.: : Former Exxon Service Station of Site: : 2225 Telegraph Ave., Oakland, Logged By: : Heidi L. Dieffenbach-Carle, P.G. Reviewed By: : Heidi L. Dieffenbach-Carle, P.G. Signature: : 100 Miles of Signature of Signatur						(Page 1 of 1) 7-0235 I, California G. #8793/ Janice Jacobson G. #6793			Date Drilled: Drilling Co.: Drilling Method: Sampling Method: Borehole Diameter: Casing Diameter: Location N-S Location E-W Total Depth: First GW Depth:	: 03/01/2007, 03/02/2007 : Woodward Drilling : Hand Auger : Hand Auger : 4" : N/A : 2122775.4 : 6050637.5 : 14' bgs : 12.5' bgs		
Depth (ft)	Blow Count	OVM/PID (vmqq)	Sample	Column	nscs	Samp	ple Condition No Recovery Sampled Interval Described Sample Preserved Sample	le Condition No Recovery Sampled Interval Described Sample Water Levels					
-							It and concrete	land a	auger to 8'		Concrete		
5		0.0	88		CL	SILTY rust sta	CLAY WITH SAND: yellow aining, with fine to medium	ish br grain	rown with orange ed sand.	mottling and	Neat Cement		
10-		0.0	88		ML CL CL	SILTY (damp, v SILTY (hard.	CLAY WITH SAND: yellow with fine grained sand. CLAY WITH SAND: light oli with fine grained sand. CLAY: light brown with dark	 iive br K gray	rown and iron oxid	de staining,/	Near Sement		
15-					SC SM	SANDY plasticit CLAYE' to wet, I SILTY S Total De Groundy	SANDY CLAY: light brown way inclusion, damp, with fine CLAY: light brown with yelly, with fine to medium grain Y SILTY SAND: fine to medium grain plasticity. SAND: fine to medium grain epth @ 14.0' bgs 03/02 water was encountered at a rary casing set in boring to a set in borin	e to n llowis ned si dium (ned (7 2/07	nedium grained s th orange mottling and (~45%). grained (60%), lig 75%), brown, satu	and (~35%). I, moist, low ht brown,moist			
20-													





ATTACHMENT C PERMITS



EXCAVATION PERMIT

CIVIL ENGINEER

TO EXCAVATE IN STREETS OR OTHER SPECIFIED WORK

PAGE 2 of 2

Permit valid for 90 days from date of issuance.

PERMIT NUMBER X 0	700171	SITE ADDRESS/LOCATION 2225 Telegraph Ave	Telegraph Aven	we between W. Grand Ave
APPROX. START DATE	APPROX. END DATE	24-HOUR EMERGENCY PHONE NUM (Permit not valid without 24-Hour number	Mer	VV. CTAINS AVE
CONTRACTOR'S LICENSE # A	ND CLASS	CITY BUSINESS TAX #		
485165	C57			A STATE OF THE STA
ATTENTION:	007			
]- State law require	s that the contractor/owner call Undergrou y identification number issued by USA. Th	nd Service Alert (USA) two working days before a ne USA telephone number is 1-800-642-2444. Und	xcavating. This permit is not valid erground Service Alert (USA)#_	unless applicant has
2- 48 hours pr	ior to starting work, you M	UST CALL (510) 238-3651 to sch	nedule an inspection.	
3- 48 hours pr	ior to re-paving, a compact	ion certificate is required (waived	l for approved slurry b	packfill).
OWNER/BUILDER				111111111111111111111111111111111111111
alleged exemption. Any violation of I, as an owner of the property, of Professions Code: The Contractor' provided that such improvements are burden of proving that he did not but I I, as owner of the property, and be performed prior to sale, (3) I have structures more than once during an I, as owner of the property, and does not apply to an owner of property.	f Section 7031.5 by any applicant for a pormy employees with wages as their sole is License Law does not apply to an own e not intended or offered for sale. If how tild or improve for the purpose of sale), excempt from the sale requirements of the reresided in the residence for the 12 most y three-year period. (Sec. 7044 Business exclusively contracting with licensed con	tractors to construct the project, (Sec. 7044, Bus who contracts for such projects with a contract	not more than \$500): ure is not intended or offered for and who does such work himself in one year of completion, the or place of residence or appurtena ave not claimed exemption on th siness and Professions Code: Th	r sale (Sec. 7044, Business for through his own employees, wher-builder will have the nees thereto, (2) the work will is subdivision on more thrus e Contractor's License Law
WORKER'S COMPENSATION				
□ I hereby affirm that I have a cert	ificate of consent to self-insure, or a cert	ificate of Worker's Compensation Insurance, or	a certified copy thereof (Sec. 37	00, Labor Code).
Policy #	. Company Nam	ne		
☐] certify that in the performance of	45	ed, I shall not employ any person in any manner	so as to become subject to the W	Vorker's Compensation Laws
comply with such provisions or this p granted upon the express condition th perform the obligations with respect t and employees, from and against any sustained or arising in the constructio	permit shall be deemed revoked. This pe at the permittee shall be responsible for a constreet maintenance. The permittee shat and all suits, claims, or actions brought to of the work performed under the permit	ou should become subject to the Worker's Comparmit is issued pursuant to all provisions of Title all claims and liabilities arising out of work perfill, and by acceptance of the permit agrees to def by any person for or on account of any bodily in it or in consequence of permittee's failure to per it by the Director of the Office of Planning and I	12 Chapter 12.12 of the Oakland ormed under the permit or arising end, indemnify, save and hold ha njuries, disease or illness or dam form the obligations with respect	d Municipal Code. It is g out of permittee's failure to armless the City, its officers age to persons and/or property
his permit and agree to its requirement	er provisions of Chapter 9 of Division 3 ats, and that the above information is tru	of the Business and Professions Code and my I e and correct under penalty of law.	icense is in full force and effect ($2/8/07$	(if contractor), that I have read
Signature of Permittee [THE PARTY OF THE P	The second secon	Market State Commence of the C	
DATE STREET LAST	SPECIAL PAVING DETAIL	HOLDAY RESTRICTION?	LIMITED OPERATI	
RESURFACED	REQUIRED? YES NO	(NOV 1-1AN 1) DYES D1	NO 7AM-9AM & 4PM-0	SPM) DYES DN
SSUED BY	g	DATE ISSUED	V N	1.00

CITY OF OAKLAND • Community and Economic Development Agency 250 Frank H. Ogawa Plaza, 2nd Floor, Oakland, CA 94612 • Phone (510) 238-3443 • FAX (510) 238-2263

Job Site 2225 TELEGRAPH AV

Parcel# 008 -0659-002-01

Appl# OB070161

soil borings on Telegraph Av between Grand & 22nd St plus

Permit Issued 02/27/07

block traffic lanes per approved TCP. Two meters T-2215; -2217; -2207; -2209. NOTE One meter no fee with permit

TELEGRAPH AV

Nor of days: 6

Effective: 03/01/07

Linear feet:

175

Expiration:

03/07/07

SHORT TERM NON-METERED

Applent

Phone#

Lic# --License Classes--

Owner TRUONG LAM H

Contractor GREGG DRILLING & TESTING, INC.

Х

(925) 313-5800 485165 C57

Arch/Engr

Agent ENVIRON RESOL/R WESTRUP

Applic Addr 950 HOWE RD, MARTINEZ, CA., 94553

(707) 766-2000

\$792.93 TOTAL FEES PAID AT ISSUANCE

\$61.00 Applic

\$630.00 Permit

\$.00 Process

\$65.65 Rec Mgmt

\$.00 Gen Plan

\$.00 Invstg

\$.00 Other

\$36.28 Tech Enh

JOB SITE

TCP needs to be approved by Transportation Services every 30 days or whenever deviated from the previously approved plan.

Applicant:

Issued by:

Solich Lopez

Date: 62/27/07 Amt Paio: \$1,275.03 By: SKJ Register R03 Receipt# 113156 250 Frank H. Ogawa Plaza, 2nd Floor, Oakland, CA 94612 • Phone (510) 238-3443 • FAX (510) 238-2263 CITY OF OAKLAND . Community and Economic Development

po site 2225 TELEGRAPH AV

Parcel# 008 -0659-002-01

Appl# OB070162

soil borings on Telegraph Av between Grand & 22nd St plus block traffic lanes per approved TCP. Four meters T-2215; -2217; -2207; -2209. NOTE One meter no fee with permit

Permit Issued 02/27/07

TELEGRAPH AV

Nbr of days: 4

Effective: 03/01/07

Nbr of meters: 3

Expiration:

03/07/07

SHORT TERM METERED

Applent

Phone#

Lic# --License Classes--

Owner TRUONG LAM H.

Contractor GREGG DRILLING & TESTING, INC. X

Arch/Engr

Agent ENVIRON RESOL/R WESTRUP

applic Addr 950 HOWE RD, MARTINEZ, CA., 94553

(925)313-5800 485165 C57

(707) 766-2000

\$483.10 TOTAL FEES PAID AT ISSUANCE \$360.00 Permit

\$61.00 Applic

\$.00 Process

\$40.00 Rec Mgmt \$.00 Invstg

\$.00 Gen Plan \$.00 Other

\$22.10 Tech Enh

JOB SITE

TCP needs to be approved by Transportation Services every 30 days or whenever deviated from the previously approved plan.

Applicant:

Issued by:

Date: 02/27/07 Amt Paid: \$1,276.03 By: SKJ Register R&3 Receipt# 115136

ATTACHMENT D FIELD PROTOCOL

FIELD PROTOCOL

Site Safety Plan

Field work will be performed by ERI personnel in accordance with a Site Safety Plan developed for the site. This plan describes the basic safety requirements for the subsurface investigation and the drilling of soil borings at the work site. The Site Safety Plan is applicable to personnel and subcontractors of ERI. Personnel at the site are informed of the contents of the Site Safety Plan before work begins. A copy of the Site Safety Plan is kept at the work site and is available for reference by appropriate parties during the work. The ERI geologist will act as the Site Safety Officer.

Drilling of Soil Borings

Prior to the drilling of soil borings, ERI will acquire necessary permits from the appropriate agency(ies). ERI will also contact Underground Service Alert (USA) and a private underground utility locator (per ExxonMobil protocol) before drilling to help locate public utility lines at the site. ERI will clear the proposed locations to a depth of approximately 4 or 8 feet (depending on the location), before drilling to reduce the risk of damaging underground structures.

The soil borings will be advanced using dual-tube or direct-push technology. A dual tube system consists of a large diameter (up to 3.5 inches) outer rod which serves as a temporary drive casing nested with an inner sample rods and sample barrel (up to 2.6 inches) used to obtain and retrieve the soil cores. The dual tubes are simultaneously pushed, pounded, or vibrated into the ground.

As the rods are advanced, soil is forced up inside of a three-foot sample barrel that is attached to the end of the inner rods. Soil samples are collected in stainless steel or clear plastic sample liners inside the sample barrel as both rods are advanced. After being driven three feet, the inner rods and sample barrel are retrieved, and the sample liners are removed from the sample barrel and are either package for chemical analysis or visually inspected for lithologic identification. Clean empty liners are placed into a new three foot sample barrel and attached to the rods and lowered to the bottom of the hole and the process is repeated until the total depth of the borehole is reached.

The larger outer diameter rods are left in place while the inner rod and sample barrel is retrieved. This prevents the borehole from collapsing and ensures that the soil samples are collected from the targeted depth rather than potentially be contaminated with slough from higher up in the borehole.

The drive casing, sampling rods, sample barrels, and tools will be steam-cleaned before use and between boreholes to minimize the possibility of cross-hole contamination. The rinsate will be contained in drums and stored on site. ERI will coordinate with Exxon Mobil for appropriate disposal of the rinsate.

Drilling will be performed under the observation of a field geologist, and the earth materials in the borings will be identified using visual and manual methods, and classified as drilling progresses using the Unified Soil Classification System.

Soil samples will be monitored with a photo-ionization detector (PID), which measures hydrocarbon concentrations in the ambient air or headspace above the soil sample. Field instruments such as the PID are useful for indicating relative levels of hydrocarbon vapors, but do not detect concentrations of hydrocarbons with the same precision as laboratory analyses. Soil samples selected for possible chemical analysis will be sealed promptly with Teflon® tape and plastic caps. The samples will be labeled and placed in iced storage for transport to the laboratory. Chain-of-Custody records will be initiated by the geologist in the field, updated throughout handling of the samples, and sent with the samples to the laboratory. Copies of these records will be in the final report. Cuttings generated during

drilling will be placed on plastic sheeting and covered and left at the site. ERI will coordinate with Exxon Mobil for the soil to be removed to an appropriate disposal facility.

Grab Groundwater Sample Collection through Direct Push Rods

At first encountered groundwater, the sample barrel and inner rods will be removed from the borehole. Small diameter well casing with 0.010" slotted well screen may be installed to facilitate the collection of groundwater samples. The temporary well is lowered through the drive casing and then the drive casing is pulled up approximately 0.5 feet to 2 feet to expose the slotted interval and allow groundwater to flow into the borehole. Groundwater samples may then be collected from within the drive casing with a new disposable bailer or peristaltic pump. When using dual-wall direct-push technology, the outer rods seal off upper portions of the aquifer while coring to the lower depths. Groundwater samples from lower depths can be collected by removing the inner coring rods while the outer rods remain in place, and attaching drive rods to a groundwater sampling probe such as the Hydropunch II[®] (HP II), which is then inserted inside the outer rods of the dual-wall equipment. A 5-foot long disposable screen and tip is inserted into the HP-II, the HP-II is pushed to the desired depth and the outer body of the HP-II is retracted. The disposable screen is exposed to the ground water and a ¾-inch inner-diameter bailer is lowered through the rods and into the screened zone for sample collection.

Cone Penetration Test Borings

Cone Penetration Test (CPT) borings will be advanced using direct push technology under the observation of a field geologist.

Grab Groundwater Sampling through Hydropunch Equipment

The Hydropunch® sampler (or similar) provides a method for collecting groundwater samples at multiple depths in the same borehole. To sample groundwater, the sample tool is pushed to the selected depth beneath the water table, then withdrawn to expose an inlet screen. Alternatively, a temporary casing is placed within the casing. A water sample is then collected and promptly transported in iced storage in a thermally-insulated ice chest, accompanied by a Chain of Custody Record, to a California-certified laboratory.

Borehole Grouting

After soil and grab groundwater sampling have been completed, all boreholes will be backfilled with cement grout containing less that 5 percent pure sodium bentonite. The grout will be pumped through a tremie pipe positioned at the bottom of the boreholes.

ATTACHMENT E

LABORATORY ANAYLTICAL REPORTS AND CHAIN-OFCUSTODY RECORDS



16 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

RE: Exxon 7-0235 Work Order: MQC0226

Enclosed are the results of analyses for samples received by the laboratory on 03/07/07 16:55. The samples arrived at a temperature of 2° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Clinital Woodcock





Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0226 Reported: 03/16/07 09:41

601 North McDowell Blvd. Petaluma CA, 94954

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
S-15-B9	MQC0226-01	Soil	03/06/07 10:25	03/07/07 16:55
S-19.5-B9	MQC0226-02	Soil	03/06/07 11:45	03/07/07 16:55
S-23.5-B9	MQC0226-03	Soil	03/06/07 12:00	03/07/07 16:55
S-29.5-B9	MQC0226-04	Soil	03/06/07 13:30	03/07/07 16:55





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0226 Reported:

03/16/07 09:41

S-15-B9 (MQC0226-01) Soil Sampled: 03/06/07 10:25 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

				0					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	1.9	1.0	mg/kg	10	7C07027	03/07/07	03/08/07	EPA 8015B/8021B	
Toluene	0.032	0.010		800	11	н	<u>n</u>	U	
Ethylbenzene	0.042	0.010		10	11	11			
Xylenes (total)	0.12	0.010	**	(0)	ш	н			
Surrogate: a,a,a-Trifluorotoluene		87 %	75-1	20	"	11	"	"	
Surrogate: 4-Bromofluorobenzene		101 %	45-1	<i>35</i>	"	"	"	"	
Benzene	0.48	0.10	W.	(0.1	7C08010	03/08/07	03/08/07	300	
Surrogate: a,a,a-Trifluorotoluene		108 %	75-1	20	"	"	**	,,	

Volatile Organic Compounds by EPA Method 8260B

				0	_ ′				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C08025	03/08/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	0.034	0.0050	11	11	n	11	5.005	(00)	
Di-isopropyl ether	ND	0.0050	n.	II .	17	11	(50)	(1900)	
1,2-Dibromoethane (EDB)	ND	0.0050	11	11	и	11	0.00€	(0.0)	
1,2-Dichloroethane	ND	0.0050	u	11	300	((10))	0.000	202	
Ethyl tert-butyl ether	ND	0.0050	H	**	ж	500	1(10)	500.5	
Methyl tert-butyl ether	0.0067	0.0050	11	"	×	300.7	(10)	3987	
Surrogate: 1,2-Dichloroethane-d4		90 %	55-1	135	*	"	n	"	
Surrogate: 4-Bromofluorobenzene		86 %	60-1	120	n.	"	n	"	
Surrogate: Dibromofluoromethane		93 %	45-1	130	"	"	"	u	
Surrogate: Toluene-d8		94 %	70-1	120	"		"	n .	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Troject. DARON

Project Number: 7-0235 Project Manager: Paula Sime MQC0226 Reported:

03/16/07 09:41

S-15-B9 (MQC0226-01RE2) Soil Sampled: 03/06/07 10:25 Received: 03/07/07 16:55

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	II .	н	п	11	0	0	
Surrogate: n-Octacosane		84 %	40-	120	"	"	"	"	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0226 Reported: 03/16/07 09:41

S-19.5-B9 (MQC0226-02) Soil Sampled: 03/06/07 11:45 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

			553	8	2				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/08/07	EPA 8015B/8021B	
Benzene	0.0068	0.0010			9		U.	D	
Toluene	ND	0.0010		*	95	u	- 11	11	
Ethylbenzene	ND	0.0010	*	*	#	ei		30	
Xylenes (total)	ND	0.0010	u	ń.	**	000	(10))	30	
Surrogate: a,a,a-Trifluorotoluene		97 %	75-	120	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		98 %	45-	135	"	"	100	"	

Volatile Organic Compounds by EPA Method 8260B

1 commence morgan min, ch											
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note		
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/08/07	EPA 8260B			
tert-Butyl alcohol	ND	0.0050	н		н	11	н	u			
Di-isopropyl ether	ND	0.0050	11	11	11	U	"	D			
1,2-Dibromoethane (EDB)	ND	0.0050	*1	**	II .	II	u	н			
1,2-Dichloroethane	ND	0.0050	н			.00		*			
Ethyl tert-butyl ether	ND	0.0050	11	•			**	**			
Methyl tert-butyl ether	0.0050	0.0050	n			**		R.			
Surrogate: 1,2-Dichloroethane-d4		111%	55-	135	n	"	"	"			
Surrogate: 4-Bromofluorobenzene		91 %	60-	120	"	n	"	"			
Surrogate: Dibromofluoromethane		99 %	45-	130	<i>u</i> ;	"	"	"			
Surrogate: Toluene-d8		100 %	70-	120	<i>H</i> :	"	11	"			





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Project: Exxon 7-0235

MQC0226 Reported:

Petaluma CA, 94954

Project Number: 7-0235
Project Manager: Paula Sime

03/16/07 09:41

S-19.5-B9 (MQC0226-02RE2) Soil Sampled: 03/06/07 11:45 Received: 03/07/07 16:55

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	U	H	17	11	U	н	
Surrogate: n-Octacosane		89 %	40-	120	"	"	"	"	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0226 Reported: 03/16/07 09:41

S-23.5-B9 (MQC0226-03) Soil Sampled: 03/06/07 12:00 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/08/07	EPA 8015B/8021B	
Benzene	ND	0.0010	30	301	100	.00	TI	"	
Toluene	ND	0.0010	39	200	1.00	983	D	п	
Ethylbenzene	ND	0.0010	777		.0	m .	*		
Xylenes (total)	ND	0.0010	$\widehat{\mathcal{H}}$	h			**	#1 #12	
Surrogate: a,a,a-Trifluorotoluene		109 %	75	120		n		n	
Surrogate: 4-Bromofluorobenzene		97 %	45-	135	"	**	"		

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Not
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	lt.	38	n	11	н	n	
Di-isopropyl ether	ND	0.0050	11	30	н	н	n	11	
1,2-Dibromoethane (EDB)	ND	0.0050	II .	:0	0.1	U	U	U	
1.2-Dichloroethane	ND	0.0050	и	39	(10)		3.00	000	
Ethyl tert-butyl ether	ND	0.0050	ti	u	(#6)	"		2002	
Methyl tert-butyl ether	ND	0.0050	"	н			I.W.		
Surrogate: 1,2-Dichloroethane-d4		112 %	55-	135	"	*	"	"	
Surrogate: 4-Bromofluorobenzene		92 %	60-	120	"	"	<i>u</i> .	(11)	
Surrogate: Dibromofluoromethane		98 %	45-	130	"	"	"	100	
Surrogate: Toluene-d8		94 %	70-	120		"	. "		
_									





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0226 Reported: 03/16/07 09:41

S-23.5-B9 (MQC0226-03RE2) Soil Sampled: 03/06/07 12:00 Received: 03/07/07 16:55

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	11	11	н	If	11	u .	
Surrogate: n-Octacosane	<u> </u>	87 %	40-	120	"	"	"	"	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0226 Reported: 03/16/07 09:41

S-29.5-B9 (MQC0226-04) Soil Sampled: 03/06/07 13:30 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

		Danatina		0					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/08/07	EPA 8015B/8021B	
Benzene	ND	0.0010	и	н	9	11	'n	U	
Toluene	ND	0.0010	U	11	*	н	")	
Ethylbenzene	ND	0.0010		**	**	11			
Xylenes (total)	ND	0.0010	**		ii.	0			
Surrogate: a,a,a-Trifluorotoluene		107 %	75-1	120	"	"	"	900	
Surrogate: 4-Bromofluorobenzene		96 %	45-1	135	"	"	,,	900	

Volatile Organic Compounds by EPA Method 8260B

	10	Str viller ic	. 1110	Bull 111	11, 011				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	.11	Stra	н	n n	17	×	
Di-isopropyl ether	ND	0.0050	28	200	11	н	н	W	
1.2-Dibromoethane (EDB)	ND	0.0050	98	990		tt	u	ř.	
1,2-Dichloroethane	ND	0.0050				,		**	
Ethyl tert-butyl ether	ND	0.0050	n				**	**	
Methyl tert-butyl ether	ND	0.0050	34	10))	())	<u>#</u>	
Surrogate: 1,2-Dichloroethane-d4		112 %	55-	135	"	"	n	"	
Surrogate: 4-Bromofluorobenzene		90 %	60-	120	"	,,	11	"	
Surrogate: Dibromofluoromethane		100 %	45-	130	"	900	**	"	
Surrogate: Toluene-d8		94 %	70-	120	"	"	"	"	





601 North McDowell Blvd. Petaluma CA, 94954

Project Number: 7-0235

Project: Exxon 7-0235

Project Manager: Paula Sime

MQC0226 Reported: 03/16/07 09:41

S-29.5-B9 (MQC0226-04RE2) Soil Sampled: 03/06/07 13:30 Received: 03/07/07 16:55

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	ti		•	n l	n	- u	
Surrogate: n-Octacosane		87 %	40-	120	**	1000	"	"	





601 North McDowell Blvd.

Project: Exxon 7-0235

Project Number: 7-0235

MQC0226 Reported: 03/16/07 09:41

Petaluma CA, 94954

Project Manager: Paula Sime

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07027 - EPA 5030B [P/T]										
Blank (7C07027-BLK1)				Prepared a	& Analyze	ed: 03/07	/07			
Gasoline Range Organics (C4-C12)	ND	0.05	mg/kg							
Benzene	ND	0.0005	11							
Toluene	ND	0.0005	O							
Ethylbenzene	ND	0.0005	11							
Xylenes (total)	ND	0.00080	ıı							
Surrogate: a,a,a-Trifluorotoluene	0.0405	10.16	"	0.0400 0.0400		101 99	75-120 45-135			
Surrogate: 4-Bromofluorobenzene	0.0395				2. A m a la rece					
LCS (7C07027-BS1) Gasoline Range Organics (C4-C12)	0.248	0.10	mg/kg	Prepared &	x Analyze	90	65-125			
Benzene	0.00418	0.0010	1115/115	0.00485		86	55-150			
	0.0231	0.0010	,	0.0235		98	70-120			
Toluene	0.00451	0.0010	,,	0.0233		96	65-120			
Ethylbenzene	0.0261	0.0010	U	0.00470		98	70-120			
Xylenes (total)	0.0201	0.0010								
Surrogate: a,a,a-Trifluorotoluene	0.0435		"	0.0400		109	75-120			
Surrogate: 4-Bromofluorobenzene	0.0422			0.0400		106	45-135			
Matrix Spike (7C07027-MS1)	0,231	0.10		Prepared &		84 84	65-125			
Gasoline Range Organics (C4-C12)	0.00442	0.0010	mg/kg	0.275	ND					
Benzene				0.00485	ND	91	55-150			
Toluene	0.0244	0.0010	11	0.0235	ND	104	70-120			
Ethylbenzene	0.00484	0.0010	H	0.00470	ND	103	65-120			
Xylenes (total)	0.0268	0.0010		0.0265	ND	101	70-120			
Surrogate: a,a,a-Trifluorotoluene	0.0444		"	0.0400		111	75-120			
Surrogate: 4-Bromofluorobenzene	0.0379		**	0.0400		95	45-135			
Matrix Spike Dup (7C07027-MSD1)		rce: MQC01		Prepared &	k Analyze	d: 03/07/	07			
Gasoline Range Organics (C4-C12)	0.102	0.10	mg/kg	0.275	ND	37	65-125	77	40	M8
Benzene	0.00142	0.0010	U	0.00485	ND	29	55-150	103	35	M8
Toluene	0.00770	0.0010	И	0.0235	ND	33	70-120	104	40	M8
Ethylbenzene	0.00148	0.0010	11	0.00470	ND	31	65-120	106	40	M8
Xylenes (total)	0.00844	0.0010	н	0.0265	ND	32	70-120	104	40	M8
200-100										





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0226 Reported: 03/16/07 09:41

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07027 - EPA 5030B [P/T]										
Matrix Spike Dup (7C07027-MSD1)	Sou	ırce: MQC0	173-01	Prepared	& Analyz	ed: 03/07/	07			
Surrogate: a,a,a-Trifluorotoluene Surrogate: 4-Bromofluorobenzene	0.0438 0.0403		mg/kg	0.0400 0.0400		110 101	75-120 45-135			
Batch 7C08010 - EPA 5035A/5030B N	МеОН									
Blank (7C08010-BLK1)				Prepared	& Analyzo	ed: 03/08/	07			
Gasoline Range Organics (C4-C12)	ND	2.5	mg/kg							
Benzene	ND	0.05	D							
Toluene	ND	0.05	11							
Ethylbenzene	ND	0.05	п							
Xylenes (total)	ND	0.05	и							
Surrogate: a,a,a-Trifluorotoluene Surrogate: 4-Bromofluorobenzene	8.52 8.30		"	8.00 8.00		106 104	75-120 45-135			
LCS (7C08010-BS1)				Prepared o	& Analyze	ed: 03/08/0	07			
Gasoline Range Organics (C4-C12)	25.2	5.0	mg/kg	27.5		92	65-125			
Benzene	0.472	0.10	11	0.485		97	55-150			
Toluene	2.16	0.10	11	2.35		92	70-120			
Ethylbenzene	0.414	0.10	н	0.470		88	65-120			
Xylenes (total)	2.40	0.10	11	2.65		91	70-120			
Surrogate: a,a,a-Trifluorotoluene Surrogate: 4-Bromofluorobenzene	8.30 8.52		"	8.00 8.00		104 106	75-120 45-135			
Matrix Spike (7C08010-MS1)	Sou	rce: MQC02	226-01	Prepared &	& Analyze	d: 03/08/0)7			
Gasoline Range Organics (C4-C12)	23.9	5.0	mg/kg	27.5	2.7	77	65-125			
Benzene	0.952	0.10	17	0.485	0.48	97	55-150			
Toluene	1.78	0.10	Ħ	2.35	0.032	74	70-120			
Ethylbenzene	0.378	0.10	u	0.470	0.033	73	65-120			
Xylenes (total)	2.09	0.10	n	2.65	0.11	75	70-120			
Surrogate: a,a,a-Trifluorotoluene	7.63		".	8.00		95	75-120			
Surrogate: 4-Bromofluorobenzene	8.43			8.00		105	45-135			





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0226 Reported:

03/16/07 09:41

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

	Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes	
]	Batch 7C08010 - EPA 5035A/5030B Me	ОН										

Daten / C00010 - El A 3033/13030B	WICOII								
Matrix Spike Dup (7C08010-MSD1)	Sour	ce: MQC0	226-01	Prepared	& Analyze	ed: 03/08	/07		
Gasoline Range Organics (C4-C12)	23.4	5.0	mg/kg	27.5	2.7	75	65-125	2	40
Benzene	1.05	0.10	11	0.485	0.48	118	55-150	10	35
Toluene	1.97	0.10	**	2.35	0.032	82	70-120	10	40
Ethylbenzene	0.410	0.10	IT	0.470	0.033	80	65-120	8	40
Xylenes (total)	2.25	0.10	n	2,65	0.11	81	70-120	7	40
Surrogate: a,a,a-Trifluorotoluene	8.34		n	8.00		104	75-120		
Surrogate: 4-Bromofluorobenzene	8.58		n	8.00		107	45-135		





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0226 Reported: 03/16/07 09:41

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C12035 - EPA 3550B										
Blank (7C12035-BLK1)				Prepared:	03/12/07	Analyzed	1: 03/15/07			
Motor Oil (C16-C36)	ND	5	mg/kg							
Diesel Range Organics (C10-C28)	ND	0.65	11							
Surrogate: n-Octacosane	1.68		# :	1.67		101	40-120			
LCS (7C12035-BS1)				Prepared:	03/12/07	Analyzed	l: 03/1 <i>5</i> /07			
Diesel Range Organics (C10-C28)	15.3	1.0	mg/kg	16.7		92	60-115			
Surrogate: n-Octacosane	1.74		"	1.67		104	40-120			
Matrix Spike (7C12035-MS1)	Sou	rce: MQC0	173-01R	E2Prepared:	03/12/07	Analyzed	1: 03/15/07			
Diesel Range Organics (C10-C28)	16.6	1.0	mg/kg	16.7	0.83	94	60-115			
Surrogate: n-Octacosane	1.71		"	1.67		102	40-120			
Matrix Spike Dup (7C12035-MSD1)	Sou	rce: MQC0	173-01R	E2Prepared:	03/12/07	Analyzed	1: 03/15/07			
Diesel Range Organics (C10-C28)	14.4	1.0	mg/kg	16.7	0.83	81	60-115	14	40	
Surrogate: n-Octacosane	1.54		"	1.67		92	40-120			





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0226 Reported: 03/16/07 09:41

RPD

%REC

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Spike

Source

Evaluation

Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C07008 - EPA 5030B P/T										
Blank (7C07008-BLK1)				Prepared	& Analyze	ed: 03/07/	07			
tert-Amyl methyl ether	ND	0.00125	mg/kg							
ert-Butyl alcohol	ND	0.005	n							
Di-isopropyl ether	ND	0.00125	11							
,2-Dibromoethane (EDB)	ND	0.00125	н							
,2-Dichloroethane	ND	0.00125	11							
Ethyl tert-butyl ether	ND	0.00125	н							
Methyl tert-butyl ether	ND	0.00125	п							
Surrogate: 1,2-Dichloroethane-d4	0.00284		n	0.00250		114	55-135			
urrogate: 4-Bromofluorobenzene	0.00242		"	0.00250		97	60-120			
urrogate: Dibromofluoromethane	0.00251		# #	0.00250		100	45-130			
Eurrogate: Toluene-d8	0.00253		,,	0.00250		101	70-120			
LCS (7C07008-BS1)				Prepared d	& Analyze					
ert-Amyl methyl ether	0.00919	0.0025	mg/kg	0.0100		92	65-140			
ert-Butyl alcohol	0.203	0.010	н	0.200		102	75-130			
Di-isopropyl ether	0.00977	0.0025	11	0.0100		98	70-130			
,2-Dibromoethane (EDB)	0.00842	0.0025	II.	0.0100		84	80-135			
,2-Dichloroethane	0.00918	0.0025	11	0.0100		92	70-120			
Ethyl tert-butyl ether	0.00986	0.0025	O.	0.0100		99	70-125			
Methyl tert-butyl ether	0.00897	0.0025	11	0.0100		90	75-130			
urrogate: 1,2-Dichloroethane-d4	0.00245		"	0.00250		98	55-135			
urrogate: 4-Bromofluorobenzene	0.00250		"	0.00250		100	60-120			
urrogate: Dibromofluoromethane	0.00246		"	0.00250		98	45-130			
urrogate: Toluene-d8	0.00261		"	0.00250		104	70-120			
/atrix Spike (7C07008-MS1)		rce: MQC0	173-01	Prepared &	& Analyze	d: 03/07/0)7			
ert-Amyl methyl ether	0.0131	0.0025	mg/kg	0.0100	0.0014	117	65-140			
rt-Butyl alcohol	0.244	0.010	u	0.200	ND	122	75-130			
i-isopropyl ether	0.0126	0.0025	н	0.0100	ND	126	70-130			
2-Dibromoethane (EDB)	0.0130	0.0025	11	0.0100	ND	130	80-135			
2-Dichloroethane	0.0128	0.0025	ц	0.0100	ND	128	70-120			N
thyl tert-butyl ether	0.0135	0.0025	**	0.0100	ND	135	70-125			N

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.



RPD



Environmental Resolutions (Exxon)

601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

0235 MQC0226 **Reported:** 1e 03/16/07 09:41

%REC

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Evaluation

Spike

Source

Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C07008 - EPA 5030B P/T										
Matrix Spike (7C07008-MS1)	Sou	rce: MQC	0173-01	Prepared	& Analyz	ed: 03/07/	07			
Methyl tert-butyl ether	0.0134	0.0025	mg/kg	0.0100	ND	134	75-130			M
Surrogate: 1,2-Dichloroethane-d4	0.00277		"	0.00250		111	55-135			
Surrogate: 4-Bromofluorobenzene	0.00265		**	0.00250		106	60-120			
Surrogate: Dibromofluoromethane	0.00254		"	0.00250		102	45-130			
Surrogate: Toluene-d8	0.00261		"	0.00250		104	70-120			
Matrix Spike Dup (7C07008-MSD1)		rce: MQC(0173-01	Prepared of	& Analyz	ed: 03/07/	07			
tert-Amyl methyl ether	0.0121	0.0025	mg/kg	0.0100	0.0014	107	65-140	8	25	
tert-Butyl alcohol	0.227	0.010	lt.	0.200	ND	114	75-130	7	25	
Di-isopropyl ether	0.0117	0.0025	U	0.0100	ND	117	70-130	7	40	
1,2-Dibromoethane (EDB)	0.0114	0.0025	71	0.0100	ND	114	80-135	13	20	
1,2-Dichloroethane	0.0121	0.0025	Ħ	0.0100	ND	121	70-120	6	30	M7
Ethyl tert-butyl ether	0.0122	0.0025	l†	0.0100	ND	122	70-125	10	30	
Methyl tert-butyl ether	0.0120	0.0025	11	0.0100	ND	120	75-130	11	25	
Surrogate: 1,2-Dichloroethane-d4	0.00262		n	0.00250		105	55-135			
Surrogate: 4-Bromofluorobenzene	0.00260		"	0.00250		104	60-120			
Surrogate: Dibromofluoromethane	0.00263		**	0.00250		105	45-130			
Surrogate: Toluene-d8	0.00257		"	0.00250		103	70-120			
Batch 7C08025 - EPA 5030B P/T										
Blank (7C08025-BLK1)				Prepared &	& Analyze	ed: 03/08/0)7			
tert-Amyl methyl ether	ND	0.0025	mg/kg							
tert-Butyl alcohol	ND	0.0049	11							
Di-isopropyl ether	ND	0.0025	u							
1,2-Dibromoethane (EDB)	ND	0.0025	11							
1,2-Dichloroethane	ND	0.0025	U							
Ethyl tert-butyl ether	ND	0.0025	u							
Methyl tert-butyl ether	ND	0.0025	11							
Surrogate: 1,2-Dichloroethane-d4	0.00463		"	0.00499		93	55-135			
Surrogate: 4-Bromofluorobenzene	0.00439		"	0.00499		88	60-120			
Surrogate: Dibromofluoromethane	0.00483		"	0.00499		97	45-130			
Surrogate: Toluene-d8	0.00457		"	0.00499		92	70-120			
Test America Manager Hill CA			TI	4	ut annili to	41				-1tC





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0226 Reported: 03/16/07 09:41

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C08025 - EPA 5030B P/T										
LCS (7C08025-BS1)				Prepared &	k Analyze	d: 03/08/	07			
tert-Amyl methyl ether	0.0212	0.0050	mg/kg	0.0200		106	65-140			
tert-Butyl alcohol	0.391	0.020	u.	0.399		98	75-130			
Di-isopropyl ether	0.0198	0.0050	"	0.0200		99	70-130			
1,2-Dibromoethane (EDB)	0.0238	0.0050	11	0.0200		119	80-135			
1,2-Dichloroethane	0.0215	0.0050	н	0.0200		108	70-120			
Ethyl tert-butyl ether	0.0201	0.0050	U	0.0200		100	70-125			
Methyl tert-butyl ether	0.0212	0.0050	IT	0.0200		106	75-130			
Surrogate: 1,2-Dichloroethane-d4	0.00459		"	0.00499		92	55-135			
Surrogate: 4-Bromofluorobenzene	0.00445		"	0.00499		89	60-120			
Surrogate: Dibromofluoromethane	0.00467		n	0.00499		94	45-130			
Surrogate: Toluene-d8	0.00467			0.00499		94	70-120			
LCS Dup (7C08025-BSD1)			_	Prepared &	k Analyze	d: 03/08/0)7			
tert-Amyl methyl ether	0.0212	0.0050	mg/kg	0.0198		107	65-140	0	25	
tert-Butyl alcohol	0.392	0.020	11	0.397		99	75-130	0.3	25	
Di-isopropyl ether	0.0193	0.0050	B	0.0198		97	70-130	3	40	
1,2-Dibromoethane (EDB)	0.0245	0.0050	11	0.0198		124	80-135	3	20	
1,2-Dichloroethane	0.0219	0.0050	D	0.0198		111	70-120	2	30	
Ethyl tert-butyl ether	0.0202	0.0050	н	0.0198		102	70-125	0.5	30	
Methyl tert-butyl ether	0.0217	0.0050	ū	0.0198		110	75-130	2	25	
Surrogate: 1,2-Dichloroethane-d4	0.00466		#	0.00496		94	55-135			
Surrogate: 4-Bromofluorobenzene	0.00468		"	0.00496		94	60-120			
Surrogate: Dibromofluoromethane	0.00442		"	0.00496		89	45-130			
Surrogate: Toluene-d8	0.00450		#	0.00496		91	70-120			





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235

Project Manager: Paula Sime

MQC0226 Reported: 03/16/07 09:41

Notes and Definitions

M8 The MS and/or MSD were below the acceptance limits. See Blank Spike (LCS).

M7 The MS and/or MSD were above the acceptance limits. See Blank Spike (LCS).

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

												- VI - III		_							
TestA	merica	Cor	nsultant Name:					E					Jenn				k				
ICCULIA	I I CO A PO BATEO			601 North Mo		//			Tele				(510	547	-819	96					
408-776-9600			City/State/Zip:	Petaluma, Ca	alifornia 94	1954	- 11/2			Α	ccou	nt#:	3876								
Morgan Hill Divis	sion	Pr	roject Manager	Paula Sime							P	0#:		, <u>.</u>							
885 Jarvis Drive		Telep	hone Number:	(707) 766-20	00					Fa	cility	ID#	7023	35				_	\leq		وزادوان
Morgan Hill, CA	95037		RI Job Number:							0	≩loba	IID#	T060	0101:	354				MG	Chà	26
ExonMo	bil	Sample Sam	er Name: (Print) pler Signature:	Heidi Heidi	Duffle	cQ C	7-Carlo						2225 Oakla		-		iue	_			
Shipping Metho	d: Lab Courier	☐ Hand Delive	r 🗹 Commer	cial Express	☐ other	·															
TAT	35	PROVIDE:	Special Instru							Matrix						Ana	alyze	For:			
Lane.	72 hour	EDF Report	7 CA Oxys = Use silica ge Set TBA dete	el cleanup fo	or all TPH	ld analyse		CA, EDB,				d 8015B	g 8015B	TPH motor oil 8015B	BTEX 8021B	7 CA Oxys 8260B	Ethanol 8260B				
Sa	ample ID / Descript	ion	DATE	TIME	COMP	GRAB	PRESERV (VOA/liter)	NUMBER	Water	Soil	Vapor	TPHd	TPHg	TPH	BTE	7 CA	Etha				
ej B9/S-	15	-B9	3/6/2007	10:25				1		x		x	х	х	x	x					
02 B9/S-	19.5	-89	3/6/2007	11:45				1		x		х	x	x	x	x					
υ) B9/S-	23.5	-B9	3/6/2007	12:00				1		x		x	x	×	x	x					
64 B9/S-	29,5	-B9	3/6/2007	13:30				1		х		x	x	х	x	x					_
B9/S-		-B9	3/6/2007					1		x		x	x	x	x	×					
B9/S-		. - B9	3/6/2007					1		х		х	х	x	х	x		-		\vdash	
	- 9-RE																				1
																					\pm
							11														
Relinquished by: Relinquished by:	place C	Date 3	0107 1 7/07	Time 705	55	Received	by: SAV		3/7	los	t	655		Lab	Sam	nperal	ture U Contai	lpon F ners I	Receip Intact? space		ō

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: EPE REC. BY (PRINT) WORKORDER: CIDCLE THE APPROXIMATION EPE Black AGC, 6.72		DATE REC'D AT LAB: TIME REC'D AT LAB: DATE LOGGED IN:	03-07- 1655 3-7-	67			For Regula DRINKING WASTE WA	
CIRCLE THE APPROPRIATE RESPONSE	LAB SAMPLE#	CLIENT ID	CONTAINER DESCRIPTION	PRESER VATIVE	рН	SAMPLE	DATE SAMPLED	REMARKS: CONDITION (ETC.)
Custody Seal(s) Present / Absent Intact / Broken*								7
2. Chain-of-Custody Present / Absent*								
Traffic Reports or Packing List: Present / Absent								
4. Airbill: Airbill / Sticker Present / Absent		75,						
5. Airbill #:			^				-/1	
6. Sample Labels: Present / Absent							/	
7. Sample IDs: Listed / Not Listed on Chain-of-Custody		AP-2						
8. Sample Condition: Intact / Broken* / Leaking*					7	/-,		
Does information on chain-of-custody, traffic reports and sample labels				2-04-	/			
agree? (Yes) / No*			LA					
10. Sample received within hold time?			PARE/	/				
11. Adequate sample volume received? Yes / No*			100					•
12. Proper preservatives used? Yes / No*					-			
13. Trip Blank / Temp Blank Received? (circle which, if yes) Yes	- March							
14. Read Temp: 2.0								
Is corrected temp 4 +/-2°C? Yes / No**								
(Acceptance range for samples requiring thermal pres.)								
**Exception (if any): METALS / DFF ON ICE or Problem COC		/ ,						

*IF CIRCLED, CONTACT PROJECT MANAGER AND ATTACH RECORD OF RESOLUTION.

Des 7 (07/40/08)



16 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

RE: Exxon 7-0235 Work Order: MQC0173

Enclosed are the results of analyses for samples received by the laboratory on 03/06/07 18:35. The samples arrived at a temperature of 2° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Chritina (Noodcock





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0173 Reported: 03/16/07 09:20

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
S-5-B7	MQC0173-01	Soil	03/05/07 10:05	03/06/07 18:35
S-10-B7	MQC0173-02	Soil	03/05/07 10:45	03/06/07 18:35
S-15-B7	MQC0173-03	Soil	03/05/07 11:15	03/06/07 18:35
S-16.5-B7	MQC0173-04	Soil	03/05/07 11:20	03/06/07 18:35
S-19-B7	MQC0173-05	Soil	03/05/07 11:35	03/06/07 18:35
S-21-B7	MQC0173-06	Soil	03/05/07 11:45	03/06/07 18:35





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0173 Reported: 03/16/07 09:20

S-5-B7 (MQC0173-01) Soil Sampled: 03/05/07 10:05 Received: 03/06/07 18:35

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	I	7C07027	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	ND	0.0010	11	2003	u	Ħ	100	"	
Toluene	ND	0.0010	11	(10)	ж		100	n	
Ethylbenzene	ND	0.0010	(10)	(0)	00	10	390	н	
Xylenes (total)	ND	0.0010	300	5(0)	11.	9 M 0	0.	11	
Surrogate: a,a,a-Trifluorotoluene		108 %	75-	120	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		97%	45-	135	"	"	(1)	"	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/07/07	EPA 8260B	
tert-Butyl alcohol	ND	0.020	н	U	n	н		н	
Di-isopropyl ether	ND	0.0050	н	ш	**	10.	u	Ħ	
1.2-Dibromoethane (EDB)	ND	0.0050	0	н		0	30	11	
1,2-Dichloroethane	ND	0.0050	n				30	11	
Ethanol	ND	0.10	н	n	000		n	10.	
Ethyl tert-butyl ether	ND	0.0050	11	140	11	300	31	11.	
Methyl tert-butyl ether	ND	0.0050	ш	.00	300)tr	311	ж	
Surrogate: Dibromofluoromethane		92 %	45-	130	n	"	"	,,	
Surrogate: 1,2-Dichloroethane-d4		111 %	55-	135	"	"	н	"	
Surrogate: Toluene-d8		101 %	70-1	120	"	"	11	"	
Surrogate: 4-Bromofluorobenzene		92 %	60-1	120	"	"	"	"	





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported:

03/16/07 09:20

S-5-B7 (MQC0173-01RE2) Soil Sampled: 03/05/07 10:05 Received: 03/06/07 18:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

	1 000 1100 1100 1100 1100								
		Reporting							
Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	11		<u>n</u>	<u>II.</u>		ш	
Surrogate: n-Octacosane		96 %	40-	120	"	#	396		





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235
Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

S-10-B7 (MQC0173-02) Soil Sampled: 03/05/07 10:45 Received: 03/06/07 18:35

$Purgeable\ Hydrocarbons\ and\ BTEX\ by\ EPA\ 8015B/8021B$

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/07/07	EPA	
D	NID	0.0010	**	- Til		**	n	8015B/8021B	
Benzene	ND		11	10			10)	.00	
Toluene	ND	0.0010							
Ethylbenzene	ND	0.0010	W	10	· u	111		3.007	
Xylenes (total)	ND	0.0010	w	:0	(n):	N.	11:	3003	
Surrogate: a,a,a-Trifluorotoluene		106 %	75-	120	"	"	"	(n)	
Surrogate: 4-Bromofluorobenzene		96 %	45-	135	"	"		1346	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/07/07	EPA 8260B	
tert-Butyl alcohol	ND	0.020	U	R	.11	71			
Di-isopropyl ether	ND	0.0050	II	n	**	0	**	968	
1.2-Dibromoethane (EDB)	ND	0.0050	n	n	*	11		3000	
1,2-Dichloroethane	ND	0.0050	11	н	H	11		2002	
Ethanol	ND	0.10	II .	n.	**	(1	.0	3000	
Ethyl tert-butyl ether	ND	0.0050	17	**	w	II .	· n	30.0	
Methyl tert-butyl ether	ND	0.0050	н	**	ti.	7,003	111	(0)	
Surrogate: Dibromofluoromethane		103 %	45-1	30	"	11	"	n .	
Surrogate: 1,2-Dichloroethane-d4		117 %	55-1	35	"	"	((#)	n	
Surrogate: Toluene-d8		96 %	70-1	20	#	"	"	n	
Surrogate: 4-Bromofluorobenzene		92 %	60-1	20	77	"	**	n	





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0173 **Reported:** 03/16/07 09:20

S-10-B7 (MQC0173-02RE2) Soil Sampled: 03/05/07 10:45 Received: 03/06/07 18:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	ï	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	u .	*	tt	11	ti	D.	
Surrogate: n-Octacosane		90 %	40	120	"	11	n	SW.	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

S-15-B7 (MQC0173-03) Soil Sampled: 03/05/07 11:15 Received: 03/06/07 18:35

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/08/07	EPA 8015B/8021B	
Benzene	ND	0.0010	iii.		U	II.	"	U	
Toluene	ND	0.0010		***	39	11	**	н	
Ethylbenzene	ND	0.0010	**	5000	*1	*1	10.	Ħ	
Xylenes (total)	ND	0.0010	H	300	(0)	300			
Surrogate: a,a,a-Trifluorotoluene		107 %	75-	120	n	"	*	77	
Surrogate: 4-Bromofluorobenzene		97 %	45-	135	"	H	"	n.	

Volatile Organic Compounds by EPA Method 8260B

1 estimation in the same state, and										
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note	
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C08025	03/08/07	03/08/07	EPA 8260B		
tert-Butyl alcohol	ND	0.0050		•	(98)	u	н	11		
Di-isopropyl ether	ND	0.0050			(**)	n	н			
1,2-Dibromoethane (EDB)	ND	0.0050	***		**	**	**	н		
1,2-Dichloroethane	ND	0.0050		*		**	u	H.		
Ethanol	ND	0.10		*		**	n	1900)		
Ethyl tert-butyl ether	ND	0.0050		*				***		
Methyl tert-butyl ether	ND	0.0050		Ü	, ii	11.	(900)			
Surrogate: Dibromofluoromethane		94 %	45-	130	3900	97	u.	#		
Surrogate: 1,2-Dichloroethane-d4		95 %	55-	135	"	"	" #	200		
Surrogate: Toluene-d8		89 %	70-	120	"	"		"		
Surrogate: 4-Bromofluorobenzene		82 %	60-	120	110	"	"	•		
_										





601 North McDowell Blvd. Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

S-15-B7 (MQC0173-03RE2) Soil Sampled: 03/05/07 11:15 Received: 03/06/07 18:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	н	10	19	11	11	II .	
Surrogate: n-Octacosane		95 %	40-	120	#	"	"	"	





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported:

03/16/07 09:20

Sampled: 03/05/07 11:20 Received: 03/06/07 18:35 S-16.5-B7 (MQC0173-04) Soil

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	ND	0.0010	и	.00	200	30	W	11	
Toluene	ND	0.0010	п	n	"			19	
Ethylbenzene	ND	0.0010	н	**	•			H	
Xylenes (total)	ND	0.0010	II .			**	•	11	
Surrogate: a,a,a-Trifluorotoluene		101 %	75-	120	***	"	"	986	
Surrogate: 4-Bromofluorobenzene		98 %	45-	135	"	"	n	*	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/07/07	EPA 8260B	
tert-Butyl alcohol	ND	0.020	0		Ħ	11	н	30	
Di-isopropyl ether	ND	0.0050	н	(000)	30	10;	3000	30	
1,2-Dibromoethane (EDB)	ND	0.0050	0	(00)	30	#	29%	71	
1,2-Dichloroethane	ND	0.0050	17	8308	.00	10.	(90)	99	
Ethanol	ND	0.10	11	15(19)	22	11.	.0.	30	
Ethyl tert-butyl ether	ND	0.0050	11	5.000		100	10		
Methyl tert-butyl ether	ND	0.0050	IT	0.400	"	100	n	Ж	
Surrogate: Dibromofluoromethane		96 %	45-	130	"	"	"	"	
Surrogate: 1,2-Dichloroethane-d4		113 %	55-	135	"	"	"	"	
Surrogate: Toluene-d8		93 %	70-	120	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		88 %	60-	120	"	"	n.		





Project: Exxon 7-0235

MQC0173 Reported:

601 North McDowell Blvd. Petaluma CA, 94954

Project Number: 7-0235 Project Manager: Paula Sime

03/16/07 09:20

S-16.5-B7 (MQC0173-04RE2) Soil Sampled: 03/05/07 11:20 Received: 03/06/07 18:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	H	Ħ	18	н	11	19	
Surrogate: n-Octacosane		93 %	40-	120	"	"	"	"	





601 North McDowell Blvd.

Project: Exxon 7-0235

Project Number: 7-0235

MQC0173 Reported:

Petaluma CA, 94954

Project Manager: Paula Sime

03/16/07 09:20

S-19-B7 (MQC0173-05) Soil Sampled: 03/05/07 11:35 Received: 03/06/07 18:35

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	ND	0.0010	W.	.0	.0	20	п	H	
Toluene	ND	0.0010	W			**	0	11	
Ethylbenzene	ND	0.0010	**	**	••	••	ii)		
Xylenes (total)	ND	0.0010	,					(1)	
Surrogate: a,a,a-Trifluorotoluene		103 %	75-1	120	"	"	"	11.	
Surrogate: 4-Bromofluorobenzene		94 %	45-1	135	"	"	**	**	

Volatile Organic Compounds by EPA Method 8260B

				8					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C08025	03/08/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	596	DIE	n	U	11	II .	
Di-isopropyl ether	ND	0.0050	5000	300	IT	и	17	11	
1,2-Dibromoethane (EDB)	ND	0.0050	3.95	(0)	п	11	7.00	M.C.	
1.2-Dichloroethane	ND	0.0050						77	
Ethanol	ND	0.10	"	**	W	"			
Ethyl tert-butyl ether	ND	0.0050		"	9		**		
Methyl tert-butyl ether	ND	0.0050	*		*		**	W	
Surrogate: Dibromofluoromethane		90 %	45-	130	"	11	"	"	
Surrogate: 1,2-Dichloroethane-d4		96 %	55-	135	n	"	"	"	
Surrogate: Toluene-d8		94 %	70-	120	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		83 %	60-	120	"	"	"		





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported:

03/16/07 09:20

S-19-B7 (MQC0173-05RE2) Soil Sampled: 03/05/07 11:35 Received: 03/06/07 18:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	1.0	1.0	tI	u	н	U	н	n	Q1
Surrogate: n-Octacosane		84 %	40-	120	"	"	"	"	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0173 **Reported:** 03/16/07 09:20

S-21-B7 (MQC0173-06) Soil Sampled: 03/05/07 11:45 Received: 03/06/07 18:35

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	Ĭ.	7C07027	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	ND	0.0010	**	**	••		ti .	11	
Toluene	ND	0.0010	**	**		•	11	U	
Ethylbenzene	ND	0.0010	•		Ħ		11	H	
Xylenes (total)	ND	0.0010	(0)	W.	*	•	U		
Surrogate: a,a,a-Trifluorotoluene		106 %	75-	120	n	· W	"	"	
Surrogate: 4-Bromofluorobenzene		96 %	45-	135	"	"	"	"	

Volatile Organic Compounds by EPA Method 8260B

	10	Strineric	. 1120	Seem AA	,				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Not
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C08025	03/08/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	×	2002	1.00	(44.1)	"	W.	
Di-isopropyl ether	ND	0.0050	39	3,000	190			**	
1.2-Dibromoethane (EDB)	ND	0.0050	2.	.07.		n	10	**	
1,2-Dichloroethane	ND	0.0050			W			10	
Ethanol	ND	0.10			11	**	**	"	
Ethyl tert-butyl ether	ND	0.0050	<u> </u>	w	**	*		•	
Methyl tert-butyl ether	ND	0.0050	æ	w.		#			
Surrogate: Dibromofluoromethane		95 %	45-	130	"	""	"	n	
Surrogate: 1,2-Dichloroethane-d4		94 %	55-	135	"	•	"	"	
Surrogate: Toluene-d8		94 %	70	120	(0)	9 00	"	"	
Surrogate: 4-Bromofluorobenzene		82 %	60	120	· m	**	"	"	





Project: Exxon 7-0235

601 North McDowell Blvd. Petaluma CA, 94954 Project Number: 7-0235
Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

S-21-B7 (MQC0173-06RE2) Soil Sampled: 03/05/07 11:45 Received: 03/06/07 18:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	D	*		и	0	0	
Surrogate: n-Octacosane		82 %	40-	120	"	"	: 11	311	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

MQC0173 Reported: 03/16/07 09:20

Project Manager: Paula Sime

Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
			21112						
			Prepared &	& Analyze	ed: 03/07/	07			
ND	0.05	mg/kg							
ND	0.0005	**							
ND	0,0005	п							
ND	0.0005	н							
ND	0.00080	11							
0.0405		"	0.0400		101	75-120			
0.0395									
0.240	0.10			& Analyze					
			0.00485			55-150			
0.0231	0.0010	**	0.0235		98	70-120			
0.00451	0.0010	It	0.00470		96	65-120			
0.0261	0.0010	н	0.0265		98	70-120			
0.0435		"	0.0400		109	75-120			
0.0422		"							
		173-01							
	0.10	mg/kg	0.275	ND	84	65-125			
0.00442	0.0010	11	0.00485	ND	91	55-150			
0.0244	0.0010	н	0.0235	ND	104	70-120			
0.00484	0.0010	11	0.00470	ND	103	65-120			
0.0268	0.0010	n	0.0265	ND	101	70-120			
0.0444		"	0.0400		111 95	75-120 45-135			
	root MOC01	73.01		Analyze					
							77	40	M
0.00142	0.0010	1116/116					103	35	M
0.00770	0.0010	н					104	40	M
		11							M
									M
	ND ND ND ND ND ND 0.0405 0.0395 0.248 0.00418 0.0231 0.00451 0.0261 0.0435 0.0422 Sou 0.231 0.00442 0.0244 0.00484 0.0268 0.0444 0.0379 Sou 0.102 0.00142	ND	ND	ND	ND	ND	ND	ND	ND





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported:

03/16/07 09:20

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

		Evaluation		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 7C07027 - EPA 5030B [P/T]

Matrix Spike Dup (7C07027-MSD1)	Source:	MQC0173-01	Prepared & Ana	alyzed: 03/07	/07		
Surrogate: a,a,a-Trifluorotoluene	0.0438	mg/kg	0.0400	110	75-120		
Surrogate: 4-Bromofluorobenzene	0.0403	"	0.0400	101	45-135		





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C12035 - EPA 3550B										
Blank (7C12035-BLK1)				Prepared:	03/12/07	Analyzed	H: 03/15/07			
Motor Oil (C16-C36)	ND	5	mg/kg							
Diesel Range Organics (C10-C28)	ND	0.65	II.							
Surrogate: n-Octacosane	1.68		W.	1.67		101	40-120			
LCS (7C12035-BS1)				Prepared:	03/12/07	Analyzed	1: 03/15/07			
Diesel Range Organics (C10-C28)	15.3	1,0	mg/kg	16.7		92	60-115			
Surrogate: n-Octacosane	1.74		"	1.67		104	40-120			
Matrix Spike (7C12035-MS1)	Sou	irce: MQC01	173-01R	E2Prepared:	03/12/07	Analyzed	: 03/15/07			
Diesel Range Organics (C10-C28)	16.6	1.0	mg/kg	16.7	0.83	94	60-115			
Surrogate: n-Octacosane	1.71		"	1.67		102	40-120			
Matrix Spike Dup (7C12035-MSD1)	Sou	rce: MQC01	173-01RI	E2Prepared:	03/12/07	Analyzed	: 03/15/07			
Diesel Range Organics (C10-C28)	14,4	1.0	mg/kg	16.7	0.83	81	60-115	14	40	
Surrogate: n-Octacosane	1.54		*	1.67		92	40-120			





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0173 Reported: 03/16/07 09:20

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07008 - EPA 5030B P/T										
Blank (7C07008-BLK1)				Prepared &	& Analyze	ed: 03/07/	07			
ert-Amyl methyl ether	ND	0.00125	mg/kg							
ert-Butyl alcohol	ND	0.005	11							
Di-isopropyl ether	ND	0,00125	11							
,2-Dibromoethane (EDB)	ND	0.00125	11							
,2-Dichloroethane	ND	0.00125	"							
Ethanol	ND	0.048	11							
Ethyl tert-butyl ether	ND	0.00125	II							
Methyl tert-butyl ether	ND	0.00125	11							
urrogate: Dibromofluoromethane	0.00251		"	0.00250		100	45-130			
urrogate: 1,2-Dichloroethane-d4	0.00284		"	0.00250		114	55-135			
urrogate. Toluene-d8	0.00253		"	0.00250		101	70-120			
urrogate: 4-Bromofluorobenzene	0.00242		.11	0.00250		97	60-120			
CS (7C07008-BS1)				Prepared &	k Analyze	d: 03/07/0)7			
ert-Amyl methyl ether	0.00919	0.0025	mg/kg	0.0100		92	65-140			
ert-Butyl alcohol	0.203	0.010	IJ	0.200		102	75-130			
i-isopropyl ether	0.00977	0.0025	11	0.0100		98	70-130			
,2-Dibromoethane (EDB)	0.00842	0.0025	и	0.0100		84	80-135			
,2-Dichloroethane	0.00918	0.0025	н	0.0100		92	70-120			
thanol	0.183	0.050	и	0.200		92	50-150			
thyl tert-butyl ether	0.00986	0.0025	U	0.0100		99	70-125			
1ethyl tert-butyl ether	0.00897	0.0025	ıı	0.0100		90	75-130			
urrogate: Dibromofluoromethane	0.00246		"	0.00250		98	45-130			
urrogate: 1,2-Dichloroethane-d4	0.00245		"	0.00250		98	55-135			
urrogate: Toluene-d8	0.00261		"	0.00250		104	70-120			
urrogate: 4-Bromofluorobenzene	0.00250		H	0.00250		100	60-120			
latrix Spike (7C07008-MS1)	Sou	rce: MQC01	73-01	Prepared &	Analyzed	1: 03/07/0	7			
rt-Amyl methyl ether	0.0131	0.0025	mg/kg	0.0100	ND	131	65-140			
rt-Butyl alcohol	0.244	0.010	II .	0.200	ND	122	75-130			
i-isopropyl ether	0.0126	0.0025	н	0.0100	ND	126	70-130			
2-Dibromoethane (EDB)	0.0130	0.0025	n.	0.0100	ND	130	80-135			





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Result 0.0128 0.214 0.0135 0.0134	Limit 1rce: MQC0 0.0025 0.050	mg/kg	Prepared &	Result	%REC	Limits	RPD	Limit	46 1
0.0128 0.214 0.0135	0.0025 0.050	mg/kg		k Analyze	ed: 03/07/0				
0.0128 0.214 0.0135	0.0025 0.050	mg/kg		t Analyze	ed: 03/07/0	17			
0.214 0.0135	0.050		0:0100						
0.0135			0.0100	ND	128	70-120			M7
		*1	0.200	ND	107	50-150			
0.0134	0.0025	"	0.0100	ND	135	70-125			M7
	0.0025	"	0.0100	ND	134	75-130			M7
0.00254		11	0.00250		102	45-130			
0.00277									
0.00265		"	0.00250		106	60-120			
Sou	rce: MQC0	173-01	Prepared &	. Analyze	d: 03/07/0)7			
0.0121	0.0025	mg/kg	0.0100	ND	121	65-140	8	25	
0.227	0.010	11	0.200	ND	114	75-130	7	25	
0.0117	0.0025	**	0.0100	ND	117	70-130	7	40	
0.0114	0.0025	u	0.0100	ND	114	80-135	13	20	
0.0121	0.0025	**	0,0100	ND	121	70-120	6	30	M7
0.218	0.050	u	0.200	ND	109	50-150	2	30	
0.0122	0.0025	II	0.0100	ND	122	70-125	10	30	
0.0120	0.0025	Ħ	0.0100	ND	120	75-130	11	25	
0.00263		"	0.00250		105	45-130			
0.00262									
0.00257									
0.00260		"	0.00250		104	60-120			
			Prepared &	Analyze	d: 03/08/0	7			
ND	0.0025	mg/kg							
ND	0.0049	11							
ND	0.0025	u							
ND	0.0025	U							
ND	0.0025	11							
ND	0.095	**							
ND	0.0025	II							
	0.00277 0.00261 0.00265 Sou 0.0121 0.227 0.0117 0.0114 0.0121 0.218 0.0122 0.0120 0.00263 0.00262 0.00257 0.00260 ND	0.00277 0.00261 0.00265 Source: MQC0 0.0121 0.0025 0.227 0.010 0.0117 0.0025 0.0114 0.0025 0.0121 0.0025 0.0122 0.0025 0.0120 0.00263 0.00263 0.00262 0.00257 0.00260 ND 0.0025	0.00277 0.00261 0.00265 Source: MQC0173-01 0.0121 0.0025 0.0117 0.0025 0.0114 0.0025 0.0121 0.0122 0.0025 0.0120 0.0122 0.0025 0.0120 0.00263 0.00262 0.00257 0.00260 ND 0.0025 ND 0.00	0.00257 0.00250 0.00265 0.00265 0.00265 0.00265 0.00250 Source: MQC0173-01 Prepared & 0.0121 0.0025 mg/kg 0.0100 0.227 0.010 " 0.200 0.0117 0.0025 " 0.0100 0.0121 0.0025 " 0.0100 0.0121 0.0025 " 0.0100 0.0121 0.0025 " 0.0100 0.0122 0.0025 " 0.0100 0.0122 0.0025 " 0.0100 0.0120 0.00263 " 0.0025 0.00263 0.00263 " 0.00250 0.00264 0.00257 0.00260 " 0.00250 0.00250 Prepared & ND 0.0025 "	0.00257 0.00261 0.00265 Source: MQC0173-01 Prepared & Analyze 0.0121 0.0025 mg/kg 0.0100 ND 0.227 0.0117 0.0025 " 0.0100 ND 0.0117 0.0025 " 0.0100 ND 0.0114 0.0025 " 0.0100 ND 0.0121 0.0025 " 0.0100 ND 0.0121 0.0025 " 0.0100 ND 0.0121 0.0025 " 0.0100 ND 0.0122 0.0025 " 0.0100 ND 0.0122 0.0025 " 0.0100 ND 0.0120 0.0025 " 0.0100 ND 0.00263 " 0.00250 0.00262 " 0.00250 0.00260 " 0.00250 0.00257 0.00260 " 0.00250 0.00250 ND 0.0025 " 0.00250 ND 0.0025 " 0.00250 ND 0.0025 " 0.00250 ND 0.0025 " ND	0.00277	0.00277	0.00277	0.00277

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Spike

Source

Project Number: 7-0235

Evaluation

Project Manager: Paula Sime

MQC0173 Reported: 03/16/07 09:20

RPD

%REC

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C08025 - EPA 5030B P/T										
Blank (7C08025-BLK1)				Prepared 6	& Analyze	ed: 03/08/	07			
Methyl tert-butyl ether	ND	0.0025	mg/kg							
Surrogate: Dibromofluoromethane	0.00483		**	0.00499		97	45-130			
Surrogate: 1,2-Dichloroethane-d4	0.00463		"	0.00499		93	55-135			
Surrogate: Toluene-d8	0.00457		"	0.00499		92	70-120			
Surrogate: 4-Bromofluorobenzene	0.00439		"	0.00499		88	60-120			
LCS (7C08025-BS1)	0.0010	0.00.50		Prepared &	& Analyze					
tert-Amyl methyl ether	0.0212	0.0050	mg/kg	0.0200		106	65-140			
tert-Butyl alcohol	0.391	0.020	H	0.399		98	75-130			
Di-isopropyl ether	0.0198	0.0050	11	0.0200		99	70-130			
1,2-Dibromoethane (EDB)	0.0238	0.0050	11	0.0200		119	80-135			
1,2-Dichloroethane	0.0215	0.0050	TI	0.0200		108	70-120			
Ethanol	0.453	0.10	п	0.399		114	50-150			
Ethyl tert-butyl ether	0.0201	0.0050	11	0.0200		100	70-125			
Methyl tert-butyl ether	0.0212	0.0050	17	0.0200		106	75-130			
Surrogate: Dibromofluoromethane	0.00467		"	0.00499		94	45-130			
Surrogate: 1,2-Dichloroethane-d4	0.00459		11	0.00499		92	55-135			
Surrogate: Toluene-d8	0.00467		"	0.00499		94	70-120			
Surrogate: 4-Bromofluorobenzene	0.00445		и	0.00499		89	60-120			
LCS Dup (7C08025-BSD1)	0.0010	0.0050		Prepared &	k Analyze					
ert-Amyl methyl ether	0.0212	0.0050	mg/kg	0.0198		107	65-140	0	25	
ert-Butyl alcohol	0.392	0.020	п	0.397		99	75-130	0.3	25	
Di-isopropyl ether	0.0193	0.0050	u	0.0198		97	70-130	3	40	
,2-Dibromoethane (EDB)	0.0245	0.0050	"	0.0198		124	80-135	3	20	
,2-Dichloroethane	0.0219	0.0050	71	0.0198		111	70-120	2	30	
Ethanol	0.414	0.099	II	0.397		104	50-150	9	30	
Ethyl tert-butyl ether	0.0202	0.0050	"	0.0198		102	70-125	0.5	30	
Methyl tert-butyl ether	0.0217	0.0050	.11	0.0198		110	75-130	2	25	
Surrogate: Dibromofluoromethane	0.00442		n	0.00496		89	45-130			
Surrogate: 1,2-Dichloroethane-d4	0.00466		"	0.00496		94	55-135			
Surrogate: Toluene-d8	0.00450		"	0.00496		91	70-120			
Surrogate: 4-Bromofluorobenzene	0.00468		"	0.00496		94	60-120			

TestAmerica - Morgan Hill, CA

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0173 Reported:

03/16/07 09:20

Notes and Definitions

Q1 Does not match typical pattern

M8 The MS and/or MSD were below the acceptance limits. See Blank Spike (LCS).

M7 The MS and/or MSD were above the acceptance limits. See Blank Spike (LCS).

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

Test/America	Con	sultant Name:	Environment	al Resolution	ons, Inc.		E	xxon	Mobil	Engi	neer	Jenn	ifer	Sedl	ache	k	-			
1000LMIIUI IUA		Address:	601 North M	cDowell Blu	/d.			Tele	phone	e Nun	nber	(510) 547	7-819	96					
408-776-9600		City/State/Zip:	Petaluma, C	alifornia 94	1954				A	ccou	nt #:	3876	- 20							_
Morgan Hill Division	Pr	oject Manager	Paula Sime							P	0#:		- 65			/	/			
885 Jarvis Drive	Telep	hone Number:	(707) 766-20	000					Fa	cility	ID#	7023	35			7	n	PC	101	73
Morgan Hill, CA 95037	ER	I Job Number:	222903X						G	loba	ID#	T060	01013	354		/				
ExonNobil Shipping Method: Lab Courier	Samı	r Name: (Print) oler Signature: r	beid		Iscal	-Carle							- 10	graph Califor		nue				
empping method:	PROVIDE:	Special Instru							Matrix				*******		98/25				<u> </u>	
☑ 24 hour ☐ 72 hour	\$130843.NVNR80700	7 CA Oxys =		A, TAME	, ETBE, C	DIPE, 1,2-D	CA, EDB.		Watrix				m		Ana	alyze	For:		T	
☐ 48 hour ☐ 96 hour ☐ 8 day	EDF Report	Use silica ge Set TBA dete	l cleanup f	or all TPH	ld analyse						1 8015B	3 8015B	TPH motor oil 8015B	(8021B	Oxys 8260B	10l 8260B				
Sample ID / Descript	ion	DATE	TIME	COMP	GRAB	PRESERV (VOA/liter)	NUMBER	Water	Soil	Vapor	TPHd	TPHg	TPH m	втех	7 CA C	Ethanol 8				
B7 / \$-5-B7	юl	3/5/2007	io:.05				.1		x		x	x	х	х	x	X				
B7/ S-10-B7	02	3/5/2007	10:45				1		x		x	×	×	x	×	×				
B7/ S-15-B7	£3	3/5/2007	lr:15				1		x		x	×	×	x	×	x				
B7/ S- 165-B7	64	3/5/2007	11:20				1		x		x	х	х	×	х	X				
B7/ S- 19 -B7	٦٥	3/5/2007	11:35				1		x		x	×	x	×	×	X				7
B7/ S- <u>2</u> (-B7	04	3/5/2007	11:45				1		х		х	х	х		×	X				
- AND																				
						0	120000												H	1
Relinquished by: Heroli Deeple Relinquished by:	(40) 19e). Date 3:	-6-07	Time (8	25	Received b	by TestAmerica	M 3(6	5/6/	07	Time	12:	30 5	Lab	Sam	perat	ure U contai	ents: Ipon R ners Ir	ntact?	Y	- 040

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: ERI REC. BY (PRINT) WORKORDER: HQC6/33		DATE REC'D AT LAB: TIME REC'D AT LAB: DATE LOGGED IN:	03-06- 18:3 3-6-	07 5 07	2		For Regula DRINKING WASTE WA	
CIRCLE THE APPROPRIATE RESPONSE	LAB SAMPLE#	CLIENT ID	CONTAINER DESCRIPTION	PRESER VATIVE	рН	SAMPLE MATRIX	DATE SAMPLED	REMARKS: CONDITION (ETC.)
1. Custody Seal(s) Present / Absent Intact / Broken*								
2. Chain-of-Custody Present / Absent*								
Traffic Reports or Packing List: Present / Absent		;						/ "
4. Airbill: Airbill / Sticker Present / Absent		3				4		
5. Airbill #:			~					
6. Sample Labels: Present / Absent								
7. Sample IDs: Listed / Not Listed on Chain-of-Custody	1 11 1474		, 6	γ	/			
8. Sample Condition: (intact / Broken* / Leaking*			67					C
9. Does information on chain-of-custody, traffic reports and sample labels agree? Yes/ No*		Aw			- Arabas			
10. Sample received within hold time? Yes / No*			-					
11. Adequate sample volume received?								
12. Proper preservatives used? Yes/ No*					e .			
13. Trip Blank / Temp Blank Received? (circle which, if yes) Yes / (No.			·					
14. Read Temp: 2-0 Corrected Temp: 2.0	-/							
Is corrected temp 4 +/-2°C? (Yes / No**								
(Acceptance range for samples requiring thermal pres.)								
**Exception (if any): METALS / DFF ON ICE	/							
or Problem COC		Property and Department of the Control of the Contr	CONTRACTOR	ozala ilo agustas	elie menie			

---- P.... 7 /07/40/06\





9 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

RE: Exxon 7-0235 Work Order: MQC0103

Enclosed are the results of analyses for samples received by the laboratory on 03/05/07 19:15. The samples arrived at a temperature of 5° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Chriting Noodcock





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954

Project: Exxon 7-0235
Project Number: 7-0235

Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
S-5-B5	MQC0103-01	Soil	03/01/07 11:45	03/05/07 19:15
S-5-B8	MQC0103-02	Soil	03/01/07 11:20	03/05/07 19:15
S-10-B8	MQC0103-03	Soil	03/01/07 12:10	03/05/07 19:15
S-5-B9	MQC0103-04	Soil	03/02/07 10:00	03/05/07 19:15
S-10-B9	MQC0103-05	Soil	03/02/07 10:35	03/05/07 19:15
S-11-B9	MQC0103-06	Soil	03/02/07 10:40	03/05/07 19:15



885 Jarvis Drive Morgan Hill, CA 95037 (408) 776-9600 FAX (408) 782-6308 www.testamericainc.com

Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

S-5-B5 (MQC0103-01) Soil Sampled: 03/01/07 11:45 Received: 03/05/07 19:15

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C06023	03/06/07	03/06/07	EPA 8015B/8021B	
Benzene	ND	0.0010	н	11	ti .	**		11	
Toluene	ND	0.0010	(90)	×	n	**	н.	n	
Ethylbenzene	ND	0.0010	10		II	00	921	Ħ	
Xylenes (total)	ND	0.0010	*		0.	₩.	•	п	
Surrogate: a,a,a-Trifluorotoluene		105 %	75-	120	**	"	"	n	
Surrogate: 4-Bromofluorobenzene		96 %	45-	135	n	"	"	"	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C06012	03/06/07	03/06/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	1.6	1.0		u			n .	(0)	Q1
Surrogate: n-Octacosane		111 %	40-	120	"	"	**	7.00	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C06002	03/06/07	03/06/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	11	000	30	31	in .		
Di-isopropyl ether	ND	0.0050	399	383	.00	99.	ж	**	
1,2-Dibromoethane (EDB)	ND	0.0050			**	*	**		
1,2-Dichloroethane	ND	0.0050			*		w	*	
Ethyl tert-butyl ether	ND	0.0050	2007	200	н	W	11	*	
Methyl tert-butyl ether	ND	0.0050	(M)	- 29	.11	W.	h	н	
Surrogate: 1,2-Dichloroethane-d4		90 %	55-1	35	"	"	"	n	
Surrogate: 4-Bromofluorobenzene		86 %	60-1	20	"	"	"	"	125
Surrogate: Dibromofluoromethane		96 %	45-1	30	"	"	•	n	
Surrogate: Toluene-d8		91%	70-1	20	"	"	u	"	



885 Jarvis Drive Morgan Hill, CA 95037 (408) 776-9600 FAX (408) 782-6308 www.testamericainc.com

Environmental Resolutions (Exxon)

601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

S-5-B8 (MQC0103-02) Soil Sampled: 03/01/07 11:20 Received: 03/05/07 19:15

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C06023	03/06/07	03/06/07	EPA 8015B/8021B	
Benzene	ND	0.0010	II .	(0)	п	11	U	II	
Toluene	ND	0.0010	11	1000	u	11	D	n	
Ethylbenzene	ND	0.0010	"		11	H	n	u	
Xylenes (total)	ND	0.0010	II .		u	11	н	ш	
Surrogate: a,a,a-Trifluorotoluene		103 %	75-1	20	n	"	"	(980)	
Surrogate: 4-Bromofluorobenzene		92 %	45-1	35	"	"	"	2002	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C06012	03/06/07	03/06/07	EPA	
Diesel Range Organics (C10-C28)	1.2	1.0	11	11	Ħ	н	n	8015B-SVOA	Q1
Surrogate: n-Octacosane		110 %	10	120	"	"	,,	"	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C06002	03/06/07	03/06/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050			2.00%	3(90)	3387.2	II .	
Di-isopropyl ether	ND	0.0050	w	*	W	n	31		
1,2-Dibromoethane (EDB)	ND	0.0050		*	**				
1,2-Dichloroethane	ND	0.0050	96	#0		360	**		
Ethyl tert-butyl ether	ND	0.0050	39	91	10011	0.01	0000	190	
Methyl tert-butyl ether	ND	0.0050	.77	90	1993	000)		(10)	
Surrogate: 1,2-Dichloroethane-d4		92 %	55-1	35	"	"	и	"	
Surrogate: 4-Bromofluorobenzene		86 %	60-1	20	11	"	**		
Surrogate: Dibromofluoromethane		98 %	45-1	30	"	"		**	
Surrogate: Toluene-d8		91 %	70-1	20	"	"	**	"	





601 North McDowell Blvd. Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

S-10-B8 (MQC0103-03) Soil Sampled: 03/01/07 12:10 Received: 03/05/07 19:15

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C06023	03/06/07	03/06/07	EPA 8015B/8021B	
Benzene	ND	0.0010	n	m.	10:	in.	и	11	
Toluene	ND	0.0010	11	11		(00)	(39)	1000	
Ethylbenzene	ND	0.0010	U		**				
Xylenes (total)	ND	0.0010	11	**	н		. 11	W)	
Surrogate: a,a,a-Trifluorotoluene		103 %	75-	120	n	n.	n	i.u.	
Surrogate: 4-Bromofluorobenzene		96 %	45-	135	n	n	"	(3 11)	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C06012	03/06/07	03/06/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	11	n	п	н	H .	"	
Surrogate: n-Octacosane		99 %	40-	120	"	"		307	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C06002	03/06/07	03/06/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	II .	9.99	.00	"	u	н	
Di-isopropyl ether	ND	0.0050	n	**	**	п	n	11	
1,2-Dibromoethane (EDB)	ND	0.0050	и			n	11	11	
1,2-Dichloroethane	ND	0.0050	П	N	*	II.	"	11	
Ethyl tert-butyl ether	ND	0.0050	п	,,		n	u	н	
Methyl tert-butyl ether	ND	0.0050	n	9		11	11	11	
Surrogate: 1,2-Dichloroethane-d4		99 %	55-1.	35	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		88 %	60-1.	20	"	"	11	11	
Surrogate: Dibromofluoromethane		100 %	45-1.	30	"	rr .	Ÿ.	"	
Surrogate: Toluene-d8		92 %	70-1.	20	"	"	**	"	

885 Jarvis Drive Morgan Hill, CA 95037 (408) 776-9600 FAX (408) 782-6308 www.testamericainc.com



Environmental Resolutions (Exxon)

601 North McDowell Blvd.

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0103 Reported:

03/09/07 14:25

S-5-B9 (MQC0103-04) Soil

Petaluma CA, 94954

Sampled: 03/02/07 10:00 Received: 03/05/07 19:15

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C06023	03/06/07	03/06/07	EPA 8015B/8021B	
Benzene	ND	0.0010	11	**	н	11	38.	н	
Toluene	ND	0.0010		W		**	91	n	
Ethylbenzene	ND	0.0010		**	89	*	**	11	
Xylenes (total)	ND	0.0010	н	**	160	**	-10	И	
Surrogate: a,a,a-Trifluorotoluene		110 %	75-	120	n	"	"	"	
Surrogate: 4-Bromofluorobenzene		96 %	45-	135	"	"	"	"	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C06012	03/06/07	03/06/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	1.3	1.0	0:	300	30	0.	п	н	Q1
Surrogate: n-Octacosane		111%	40-	120	"	н	**	"	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C06002	03/06/07	03/06/07	EPA 8260B	
tert-Butyl alcohol	ND	0.0050	11		n	н	Ir	n .	
Di-isopropyl ether	ND	0.0050	11	"	0	11	U	D .	
1,2-Dibromoethane (EDB)	ND	0.0050	II .	.01	u u	n .	u	П	
1,2-Dichloroethane	ND	0.0050	н	0.0	"	"	11	н	
Ethyl tert-butyl ether	ND	0.0050	11		n	<u>n</u> :	11	n	
Methyl tert-butyl ether	ND	0.0050	**	79	"	H	*	"	
Surrogate: 1,2-Dichloroethane-d4		94 %	55-1	35	n	"	"	u	
Surrogate: 4-Bromofluorobenzene		90 %	60-1	20	'n	ii	"	w	
Surrogate: Dibromofluoromethane		100 %	45-1	30		u.	"	n	
Surrogate: Toluene-d8		92 %	70-1	20	"	"	#	u	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0103 Reported: 03/09/07 14:25

S-10-B9 (MQC0103-05) Soil Sampled: 03/02/07 10:35 Received: 03/05/07 19:15

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Gasoline Range Organics (C4-C12)	1.3	0.50	mg/kg	5	7C07027	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	0.13	0.0050	II			71	n	ч	
Toluene	0.11	0.0050	0	*	•		11	II .	
Ethylbenzene	0.042	0.0050	11		*	ü	, ii	*	
Xylenes (total)	0.17	0.0050	н	W.	W	W.	н	ж	
Surrogate: a,a,a-Trifluorotoluene		104 %	75-1	20	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		106 %	45-1	35	"	"	"	n	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C06012	03/06/07	03/09/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	1.8	1.0	и	11	н	11	Ш	И	Q1
Surrogate: n-Octacosane		105 %	40-	120	"	"	"	"	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C06002	03/06/07	03/06/07	EPA 8260B	
tert-Butyl alcohol	0.045	0.0050	II .	11	п	11	"	n	
Di-isopropyl ether	ND	0.0050	11	10	II .	n	ш	D.	
1,2-Dibromoethane (EDB)	ND	0.0050	Ш	н	м	n	n.	II .	
1,2-Dichloroethane	ND	0.0050	n	H	(100)	1992	(19)	580	
Ethyl tert-butyl ether	ND	0.0050		17	**		**	tt	
Methyl tert-butyl ether	0.016	0.0050	0	.0	ii.	(40)	u		
Surrogate: 1,2-Dichloroethane-d4		92 %	55-1	35	(300)	(A.M.)	(10)	11	
Surrogate: 4-Bromofluorobenzene		100 %	60-1	20	(11)	200	: 100	n	
Surrogate: Dibromofluoromethane		96 %	45-1	30	n	"	B#6	"	
Surrogate: Toluene-d8		102 %	70-1	20	**	"		JI.	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

S-11-B9 (MQC0103-06) Soil Sampled: 03/02/07 10:40 Received: 03/05/07 19:15

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	12	5.0	mg/kg	1	7C07029	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	0.18	0.10	10			I)	(#	<u>n</u>	
Toluene	0.36	0.10	D		(0)	11	*	n.	
Ethylbenzene	0.22	0.10	U	.00	0	n	**	(60)	
Xylenes (total)	0.92	0.10	Ш	(0)	7)0075	11		3970	
Surrogate: a,a,a-Trifluorotoluene		104 %	75-	120	"	"	"	•	
Surrogate: 4-Bromofluorobenzene		106 %	45-	135	"	n	*	*	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C06012	03/06/07	03/06/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	1.8	1.0	H	п	n			-0	Q1
Surrogate: n-Octacosane		101 %	40-	120	"	n	"	"	

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	0.025	mg/kg	5	7C06002	03/06/07	03/06/07	EPA 8260B	
tert-Butyl alcohol	0.067	0.025	11	**	,			*	
Di-isopropyl ether	ND	0.025	**	10	36	.0	u	36	
1,2-Dibromoethane (EDB)	ND	0.025	2.62	000	30	ж	W.	**	
1,2-Dichloroethane	ND	0.025	((0))	(11)	39		W.		
Ethyl tert-butyl ether	ND	0.025	11	**	*	*	*	••	
Methyl tert-butyl ether	ND	0.025	.0					"	
Surrogate: 1,2-Dichloroethane-d4		92 %	55-	135	***	n	**	"	
Surrogate: 4-Bromofluorobenzene		106 %	60-	120	w	**	"	"	
Surrogate: Dibromofluoromethane		96 %	45-	130		"	"	3 # 57	
Surrogate: Toluene-d8		104 %	70-	120	n	"	"	"	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Spike

Source

Project Number: 7-0235 Project Manager: Paula Sime

Evaluation

MQC0103 Reported: 03/09/07 14:25

RPD

%REC

		Evaluation		Бріке	Source		%KEC		KPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C06023 - EPA 5030B [P/T]										
Blank (7C06023-BLK1)				Prepared	& Analyze	ed: 03/06/	07			
Gasoline Range Organics (C4-C12)	ND	0.05	mg/kg							
Benzene	ND	0.0005	11							
Toluene	ND	0.0005	n							
Ethylbenzene	ND	0.0005	u							
Xylenes (total)	ND	0.00080	п							
Surrogate: a,a,a-Trifluorotoluene	0.0411		"	0.0400		103	75-120			
Surrogate: 4-Bromofluorobenzene	0.0379		77	0.0400		95	45-135			
LCS (7C06023-BS1)				Prepared a	& Analyze	d: 03/06/	07			
Gasoline Range Organics (C4-C12)	0.181	0.10	mg/kg	0.275		66	65-125			
Benzene	0.00305	0.0010	п	0.00485		63	55-150			
Toluene	0.0199	0,0010	н	0.0235		85	70-120			
Ethylbenzene	0.00361	0.0010	11	0.00470		77	65-120			
Xylenes (total)	0.0204	0.0010	11	0.0265		77	70-120			
Surrogate: a,a,a-Trifluorotoluene	0.0359		"	0.0400		90	75-120			
Surrogate: 4-Bromofluorobenzene	0.0397		"	0.0400		99	45-135			
Matrix Spike (7C06023-MS1)		ırce: MQC01	103-01	Prepared &	& Analyze	d: 03/06/0)7			
Gasoline Range Organics (C4-C12)	0.271	0.10	mg/kg	0.275	0.020	91	65-125			
Benzene	0.00383	0.0010	Ш	0.00485	ND	79	55-150			
Toluene	0.0205	0.0010	n	0.0235	ND	87	70-120			
Ethylbenzene	0.00408	0.0010	**	0.00470	ND	87	65-120			
Xylenes (total)	0.0229	0.0010	и	0.0265	ND	86	70-120			
Surrogate: a,a,a-Trifluorotoluene	0.0422		"	0.0400		106	75-120			
Surrogate: 4-Bromofluorobenzene	0.0385		"	0.0400		96	45-135			
Matrix Spike Dup (7C06023-MSD1)		rce: MQC01	03-01	Prepared &	& Analyze	d: 03/06/0	7			
Gasoline Range Organics (C4-C12)	0,245	0.10	mg/kg	0.275	0.020	82	65-125	10	40	
Benzene	0.00330	0.0010	#	0.00485	ND	68	55-150	15	35	
Toluene	0.0177	0.0010	н	0.0235	ND	75	70-120	15	40	
Ethylbenzene	0.00354	0.0010	н	0.00470	ND	75	65-120	14	40	
(ylenes (total)	0.0196	0.0010	11	0.0265	ND	74	70-120	16	40	





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

MQC0103 Reported:

Project Manager: Paula Sime

03/09/07 14:25

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C06023 - EPA 5030B [P/T]										
Matrix Spike Dup (7C06023-MSD1)	So	urce: MQC0	103-01	Prepared a	& Analyze	ed: 03/06/	07			
Surrogate: a,a,a-Trifluorotoluene	0.0422		mg/kg	0.0400		106	75-120			
Surrogate: 4-Bromofluorobenzene	0.0395		"	0.0400		99	45-135			
Batch 7C07027 - EPA 5030B [P/T]										
Blank (7C07027-BLK1)				Prepared &	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	ND	0.05	mg/kg							
Benzene	ND	0.0005	u							
Toluene	ND	0,0005	D							
Ethylbenzene	ND	0.0005	п							
Xylenes (total)	ND	0.00080	n							
Surrogate: a,a,a-Trifluorotoluene	0.0405			0.0400		101	75-120			
Surrogate: 4-Bromofluorobenzene	0.0395		"	0.0400		99	45-135			
LCS (7C07027-BS1)				Prepared &	k Analyze	d: 03/07/				
Gasoline Range Organics (C4-C12)	0.248	0.10	mg/kg	0.275		90	65-125			
Benzene	0.00418	0.0010	u	0.00485		86	55-150			
Toluene	0.0231	0.0010	н	0.0235		98	70-120			
Ethylbenzene	0.00451	0,0010	п	0.00470		96	65-120			
Xylenes (total)	0.0261	0.0010	ж	0.0265		98	70-120			
Surrogate: a,a,a-Trifluorotoluene	0.0435		"	0.0400		109	75-120			
Surrogate: 4-Bromofluorobenzene	0.0422		"	0.0400		106	45-135			
Matrix Spike (7C07027-MS1)	Sou	rce: MQC0	173-01	Prepared &	z Analyze	d: 03/07/0)7			
Gasoline Range Organics (C4-C12)	0.231	0.10	mg/kg	0.275	ND	84	65-125			
Benzene	0.00442	0.0010	"	0.00485	ND	91	55-150			
Гoluene	0.0244	0.0010	11	0.0235	ND	104	70-120			
Ethylbenzene	0.00484	0.0010	II	0.00470	ND	103	65-120			
Xylenes (total)	0.0268	0.0010	Ħ	0.0265	ND	101	70-120			
Surrogate: a,a,a-Trifluorotoluene	0.0444	6100	ü	0.0400		111	75-120			
Surrogate: 4-Bromosluorobenzene	0.0379		"	0.0400		95	45-135			





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Analyte	Kesuit	Limit	Ullits	Devel	Kesun	70KEC	Lillits	IG D	- Emin	110103
Batch 7C07027 - EPA 5030B [P/T]										
Matrix Spike Dup (7C07027-MSD1)	Sou	rce: MQC0	173-01	Prepared &	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	0.102	0.10	mg/kg	0,275	ND	37	65-125	77	40	M
Benzene	0.00142	0.0010	н	0.00485	ND	29	55-150	103	35	M
Toluene	0.00770	0.0010	er.	0.0235	ND	33	70-120	104	40	M
Ethylbenzene	0.00148	0.0010	11	0.00470	ND	31	65-120	106	40	M
Xylenes (total)	0.00844	0.0010	п	0.0265	ND	32	70-120	104	40	M
Surrogate: a,a,a-Trifluorotoluene	0.0438		"	0.0400		110	75-120			
Surrogate: 4-Bromofluorobenzene	0.0403		**	0.0400		101	45-135			
Batch 7C07029 - EPA 5035A/5030B	МеОН									
Blank (7C07029-BLK1)				Prepared &	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	ND	2.5	mg/kg							
Benzene	ND	0.05	n							
Toluene	ND	0.05	11							
Ethylbenzene	ND	0.05	ш							
Xylenes (total)	ND	0.05	11							
Surrogate: a,a,a-Trifluorotoluene	3.74		"	4.00		94	75-120	-		
Surrogate: 4-Bromofluorobenzene	3.90		"	4.00		98	45-135			
LCS (7C07029-BS1)				Prepared &	& Analyze	d: 03/07/0				
Gasoline Range Organics (C4-C12)	25,3	5.0	mg/kg	27.5		92	65-125			
Benzene	0.480	0.10	11	0.485		99	55-150			
Toluene	2.13	0.10	и	2.35		91	70-120			
Ethylbenzene	0,443	0.10	11	0.470		94	65-120			
Xylenes (total)	2.44	0.10	11	2,65		92	70-120			
Surrogate: a,a,a-Trifluorotoluene	3.83			4.00		96	75-120			
Surrogate: 4-Bromofluorobenzene	4.11		(30)	4.00		103	45-135			





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Project Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

TestAmerica - Morgan Hill, CA

MQC0103 Reported: 03/09/07 14:25

Petaluma CA, 94954

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07029 - EPA 5035A/5030B	МеОН									
Matrix Spike (7C07029-MS1)	Sou	rce: MQC0	103-06	Prepared	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	28.3	5,0	mg/kg	27,5	12	59	65-125			M
Benzene	0.425	0.10	D	0.485	0.18	51	55-150			M
Toluene	1.66	0.10	н	2,35	0.36	55	70-120			M
Ethylbenzene	0.496	0.10	11	0.470	0.22	59	65-120			M
Xylenes (total)	2.40	0.10	"	2,65	0.92	56	70-120			M
Surrogate: a,a,a-Trifluorotoluene	3.88		п	4.00		97	75-120			
Surrogate: 4-Bromofluorobenzene	4.30		n	4.00		108	45-135			
Matrix Spike Dup (7C07029-MSD1)	Sou	rce: MQC0	103-06	Prepared of	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	39.0	5.0	mg/kg	27.5	12	98	65-125	32	40	
Benzene	0.505	0.10	u	0.485	0.18	67	55-150	17	35	
Toluene	1.88	0.10	H	2.35	0.36	65	70-120	12	40	M
Ethylbenzene	0.676	0,10	11	0.470	0.22	97	65-120	31	40	
Xylenes (total)	3,29	0.10	11	2.65	0.92	89	70-120	31	40	
Surrogate: a,a,a-Trifluorotoluene	3.80		"	4.00		95	75-120			
Surrogate: 4-Bromofluorobenzene	4.39			4.00		110	45-135			





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0103 Reported:

03/09/07 14:25

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C06012 - EPA 3550B										
Blank (7C06012-BLK1)				Prepared	& Analyz	ed: 03/06/	07			
Motor Oil (C16-C36)	ND	5	mg/kg							
Diesel Range Organics (C10-C28)	0.707	0.65	IF							
Surrogate: n-Octacosane	1.66		**	1.67		99	40-120			
LCS (7C06012-BS1)				Prepared	& Analyz	ed: 03/06/	07			
Diesel Range Organics (C10-C28)	14.7	1.0	mg/kg	16,7		88	60-115			
Surrogate: n-Octacosane	1.71		"	1.67		102	40-120			
Matrix Spike (7C06012-MS1)	Sou	rce: MQC0	103-01	Prepared	& Analyze	ed: 03/06/	07			
Diesel Range Organics (C10-C28)	12,1	1.0	mg/kg	16.7	1.6	63	60-115			
Surrogate: n-Octacosane	1.68		n	1.67		101	40-120			
Matrix Spike Dup (7C06012-MSD1)	Sou	rce: MQC0	103-01	Prepared of	& Analyze	ed: 03/06/	07			
Diesel Range Organics (C10-C28)	12.6	1.0	mg/kg	16.7	1.6	66	60-115	4	40	
Surrogate: n-Octacosane	1.71		**	1.67		102	40-120			





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0103 Reported:

03/09/07 14:25

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Anglista	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Analyte	Result	Limit	Units	Level	Result	70KEC	Lillits	IG D	Limit	110103
Batch 7C06002 - EPA 5030B P/T										
Blank (7C06002-BLK1)		125		Prepared &	& Analyze	ed: 03/06/	07			
tert-Amyl methyl ether	ND	0.0025	mg/kg							
tert-Butyl alcohol	ND	0,0049	n							
Di-isopropyl ether	ND	0.0025	п							
1,2-Dibromoethane (EDB)	ND	0,0025	п							
1,2-Dichloroethane	ND	0.0025	Ħ							
Ethanol	ND	0.095	11							
Ethyl tert-butyl ether	ND	0.0025	п							
Methyl tert-butyl ether	ND	0.0025	н							
Surrogate: 1,2-Dichloroethane-d4	0.00456		н	0.00500		91	55-135			
Surrogate: 4-Bromofluorobenzene	0.00446		"	0.00500		89	60-120			
Surrogate: Dibromofluoromethane	0.00478		**	0.00500		96	45-130			
Surrogate: Toluene-d8	0.00464		Ti.	0.00500		93	70-120			
LCS (7C06002-BS1)				Prepared &	k Analyze					
tert-Amyl methyl ether	0.0163	0.0050	mg/kg	0.0200		82	65-140			
tert-Butyl alcohol	0.374	0.020	11	0.400		94	75-130			
Di-isopropyl ether	0.0137	0.0050	н	0.0200		68	60-135			
1,2-Dibromoethane (EDB)	0.0202	0.0050	п	0.0200		101	80-135			
1,2-Dichloroethane	0.0165	0.0050	н	0.0200		82	70-120			
Ethanol	0.428	0.10	11	0.400		107	50-150			
Ethyl tert-butyl ether	0.0144	0,0050	11	0.0200		72	70-125			
Methyl tert-butyl ether	0.0152	0.0050	п	0.0200		76	75-130			
Surrogate: 1,2-Dichloroethane-d4	0.00400		n	0.00500		80	55-135			
Surrogate: 4-Bromofluorobenzene	0.00466		"	0.00500		93	60-120			
Surrogate: Dibromofluoromethane	0.00506		"	0.00500		101	45-130			
Surrogate: Toluene-d8	0.00498		11	0.00500		100	70-120			
Matrix Spike (7C06002-MS1)		rce: MQB0	784-03	Prepared &						
ert-Amyl methyl ether	0.0191	0.0050	mg/kg	0.0200	ND	96	65-140			
ert-Butyl alcohol	0.382	0.020	11	0.400	ND	96	75-130			
Di-isopropyl ether	0.0186	0.0050	Ħ	0.0200	ND	93	70-130			
,2-Dibromoethane (EDB)	0.0205	0.0050	н	0.0200	ND	102	80-135			





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0103 Reported: 03/09/07 14:25

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C06002 - EPA 5030B P/T										
Matrix Spike (7C06002-MS1)	So	urce: MQB0	784-03	Prepared &	& Analyze	ed: 03/06/	07			
1,2-Dichloroethane	0.0197	0.0050	mg/kg	0.0200	ND	98	70-120			
Ethanol	0.415	0.10	н	0.400	ND	104	50-150			
Ethyl tert-butyl ether	0.0180	0.0050	11	0.0200	ND	90	70-125			
Methyl tert-butyl ether	0.0186	0.0050	n	0.0200	ND	93	75-130			
Surrogate: 1,2-Dichloroethane-d4	0.00462		"	0.00500		92	55-135			
Surrogate: 4-Bromofluorobenzene	0.00464		n	0.00500		93	60-120			
Surrogate: Dibromofluoromethane	0.00506		#	0.00500		101	45-130			
Surrogate: Toluene-d8	0.00484		н	0.00500		97	70-120			
Matrix Spike Dup (7C06002-MSD1)	Soi	ırce: MQB0'	784-03	Prepared &	k Analyze	d: 03/06/)7			
tert-Amyl methyl ether	0.0178	0.0050	mg/kg	0.0200	ND	89	65-140	7	25	
tert-Butyl alcohol	0,364	0.020	п	0.400	ND	91	75-130	5	25	
Di-isopropyl ether	0.0150	0.0050	11	0.0200	ND	75	70-130	21	40	
1,2-Dibromoethane (EDB)	0.0212	0.0050	11	0.0200	ND	106	80-135	3	20	
1,2-Dichloroethane	0.0177	0.0050	H	0,0200	ND	88	70-120	11	30	
Ethanol	0.355	0.10	n	0.400	ND	89	50-150	16	30	
Ethyl tert-butyl ether	0.0161	0.0050	u	0.0200	ND	81	70-125	11	30	
Methyl tert-butyl ether	0.0169	0.0050	11	0.0200	ND	84	75-130	10	25	
Surrogate: 1,2-Dichloroethane-d4	0.00416		n n	0.00500		83	55-135			
Surrogate: 4-Bromofluorobenzene	0.00454		"	0.00500		91	60-120			
Surrogate: Dibromofluoromethane	0.00510		"	0.00500		102	45-130			
Surrogate: Toluene-d8	0.00492		"	0.00500		98	70-120			



885 Jarvis Drive Morgan Hill, CA 95037 (408) 776-9600 FAX (408) 782-6308 www.testamericainc.com

Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954

Project Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0103 Reported: 03/09/07 14:25

Notes and Definitions

Q1 Does not match typical pattern

M8 The MS and/or MSD were below the acceptance limits. See Blank Spike (LCS).

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

Toot Amorian	Co	nsultant Name	Environmo	nial Dansler	lass las				e de la company						_			3-2-15		aye
Test/America			601 North	7.7.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1			_		idoMi							ek				
408-776-9600		City/State/Zip:						Tele	phon					7-81	96					
Morgan Hill Division		roject Manager	710		4954		-		F			3876	}							
885 Jarvis Drive		phone Number:									PO#:	-								
Morgan Hill, CA 95037		RI Job Number:		2000			4					702								
		er Name: (Print)		1, 1,1,2	ocles a	— V-11—						T060			-	73				
ExonMobil.		pler Signature:	- 4	-/ /	11/2		•					2225		A		nue				
Shipping Method: Lab Courier			rcial Express	Othe	week.	-	1		City	, Stat	e Zip	Oaki	and, (Califo	rnia					
	PROVIDE:	Special Instru	-				_	_		-										-2111
24 hour	EDF Report	7 CA Oxys =	MTBE, TI	BA, TAME	, ETBE, I	DIPE, 1,2-D	CA, EDB.	\vdash	Matrix		_	1		1	An	alyze	For:			
☐ 48 hour ☐ 96 hour	LD: Noport	Use silica ge	el cleanup	for all TPF	d analys	es.					В	0	016B	_	8	g				- 1
₹8 day M&CO103		Set TBA det	ecuon iimii	<12 ug/L	•			00100			8015B	8015B	oil 8	216	8260	3260				
E s day				r		T					9	8	hotor	88	Sxx	100				
Sample ID / Description	on	DATE	TIME	COMP	GRAB	PRESERV (VOA/liter)	NUMBER	Water	Soll	Vapor	TPHd	ТРН	TPH motor oil 8015B	BTEX 8021B	7 CA Oxys 8260B	Ethanol 8260B				
B5 / S-5-B5	01	3/1/2007	11:45				1		х		×	x	x	х	×	- W		\dashv	+	十
B8/ S-5-B8	02	3/1//2007	11:20				1		x		×	X	×				-		\dashv	+
B8/ S-10-B8	63	3/1/2007	12:10				1		x	\neg				Х	X			\dashv	-	+
B9/ S-5-B9	04	3/2/2007	10:00		0.111011		1			\dashv	X	Х	Х	Х	X		25.00	-	+	+
B9/ S-10-B9	20	3/2/2007	10:35				1		X		X	X	X	X	×	-		\dashv	+	+
B9/ S-11-B9	04	3/2/2007	10:40				1		X		x	X	х	х	х	-		-	\dashv	-
									х	\neg	X	х	X	×	Х			-	+	+
									\dashv				\dashv			-		\dashv	+	+
										\dashv			\dashv		-			\dashv	+	+
									\dashv	\dashv		-	\dashv	\dashv	-	_		\dashv	+	+
								\dashv	\dashv	-	\dashv	-	\dashv				-	\dashv	+	+
	,					0		\dashv	\dashv	-	\dashv	-		\dashv		-		\dashv	+	_
telinquished by:	Date 2h	107	Time 16:2	211	Received by	y: //	2426	닉	-1	Time	10.2						\perp l			
MWOND SI WOOD	3/6	167	16.2	29	,	Dr.	LIA	MH)	3	Time	7	'		ratory				eceipt:	47	01
(/, ,,	≈ 1	1				0				· '	6	2								
elinquished by:	Date 3/	5/07	Time (91	5	Received by	y TestAmerica	and V	lead	in	う Time	19.	馬					ers Ini eadsp		Y	

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: FRI			A F				COMPANIES TO SERVICE	,
		DATE REC'D AT LAB:	3-5-0	and the second s			For Regula	tory Purposes?
REC. BY (PRINT)		TIME REC'D AT LAB:	1915				DRINKING	WATER YES (NO
WORKORDER: MQC0103		DATE LOGGED IN:	3/6	107			WASTE W	
			A SERVICE AND A SERVICE					120(119
CIRCLE THE APPROPRIATE RESPONSE	LAB	CLIENTIN	CONTAINER	PRESER	The state of the s	SAMPLE	DATE	
	SAMPLE #	CLIENT ID	DESCRIPTION		рH		SAMPLED	REMARKS: CONDITION (ETC.)
Custody Seal(s) Present / Absent							Ortini CED	CONSTITUTE (ETC.)
: Intact / Broken*					tenlete.			
2. Chain-of-Custody Present / Absent*								
Traffic Reports or							-	
Present / Absent					-			
4. Airbill: Airbill / Sticker								/
Present (Absent)		1.						
5. Airbill #:			~				-/-	
6. Sample Labels: Present/ Absent							/	
7. Sample IDs: Listed / Not Listed						00		
on Chain-of-Custody					(//		
8. Sample Condition: (Intac) / Broken* /		***	· ·	0				
Leaking*		A		CI	/	5		
9. Does information on chain-of-custody,		6 %		, /	_			
traffic reports and sample labels			K. C	-/-				
agree? Yes / No*			1		-			
10. Sample received within			c /					
hold time? Yes / No*		10	/-		-			
11. Adequate sample volume		2			-			
received? Yes / No*		• • • • • • • • • • • • • • • • • • • •			\neg			
12. Proper preservatives used? (Fes / No*					.			
13. Trip Blank / Temp Blank Received?		/			-	+		
(circle which, if yes) Yes / No					\dashv			
14. Read Temp: 4.7%					-			
Corrected Temp: 4.7%					\dashv			
Is corrected temp 4 +/-2°C? (es / No**					\dashv			
(Acceptance range for samples requiring thermal pres.)		/			\dashv			
**Exception (if any): METALS / DFF ON ICE	1				-			
or Problem COC					\dashv			
TO SECURE A SECURE OF THE PROPERTY OF THE PROP		CONTRACTOR OF THE PROPERTY OF						

SRL Revision 8 Replaces Rev 7 (07/19/05) *IF CIRCLED, CONTACT PROJECT MANAGER AND ATTACH RECORD OF RESOLUTION.



16 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

CA (C C)

RE: Exxon 7-0235 Work Order: MQC0224

Enclosed are the results of analyses for samples received by the laboratory on 03/07/07 16:55. The samples arrived at a temperature of 2° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Chritan Woodcock





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0224 Reported:

03/16/07 09:26

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SP-1 (1-4)	MQC0224-01	Soil	03/07/07 10:00	03/07/07 16:55





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0224 Reported: 03/16/07 09:26

SP-1 (1-4) (MQC0224-01) Soil Sampled: 03/07/07 10:00 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	0.10	mg/kg	1	7C07027	03/07/07	03/08/07	EPA 8015B/8021B	
Benzene	ND	0.0010	•		н	н	н	17	
Toluene	ND	0.0010	*	•					
Ethylbenzene	ND	0.0010	9	98		.0	.0	((40)	
Xylenes (total)	ND	0.0010	*	u		**		(00)	
Surrogate: a,a,a-Trifluorotoluene		98 %	75-	120	"	3#6	"	,,,	
Surrogate: 4-Bromofluorobenzene		100 %	45-	135	"	n	W.	(W	

Total Metals by EPA 6000/7000 Series Methods

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Lead	14	5.0	mg/kg	1	7C08020	03/08/07	03/08/07	EPA 6010B	

Volatile Organic Compounds by EPA Method 8260B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
tert-Amyl methyl ether	ND	0.0050	mg/kg	1	7C07008	03/07/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	ND	0.020		n	(100)	u	п	0	
Di-isopropyl ether	ND	0.0050	.00	20	2007	н	н	II .	
1.2-Dibromoethane (EDB)	ND	0.0050	300	20.		н	n	D	
1.2-Dichloroethane	ND	0.0050	0.00	71	w	"			
Ethanol	ND	0.10	0.99	H	**	•	n		
Ethyl tert-butyl ether	ND	0.0050	11			*		H	
Methyl tert-butyl ether	ND	0.0050	11				n	NH/.	
Surrogate: Dibromofluoromethane		97 %	45-	130	"	w	(11)	946	
Surrogate: 1,2-Dichloroethane-d4		106 %	55-	135	,,	"	"	./ /n C	
Surrogate: Toluene-d8		102 %	70	120		"	(**	"	
Surrogate: 4-Bromofluorobenzene		100 %	60-	120	100	n :		"	





601 North McDowell Blvd.

Project: Exxon 7-0235

Project Number: 7-0235

MQC0224 Reported:

Petaluma CA, 94954

Project Manager: Paula Sime

03/16/07 09:26

SP-1 (1-4) (MQC0224-01RE2) Soil Sampled: 03/07/07 10:00 Received: 03/07/07 16:55

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	ND	10	mg/kg	1	7C12035	03/12/07	03/15/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	ND	1.0	11	7000	#			,	
Surrogate: n-Octacosane		86 %	40-	120	"	ú	#	W.	





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime

MQC0224 Reported: 03/16/07 09:26

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07027 - EPA 5030B [P/T]										
Blank (7C07027-BLK1)				Prepared a	& Analyz	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	ND	0.05	mg/kg							
Benzene	ND	0.0005	11							
Toluene	ND	0.0005	11							
Ethylbenzene	ND	0.0005	"							
Xylenes (total)	ND	0.00080	11							
Surrogate: a,a,a-Trifluorotoluene Surrogate: 4-Bromofluorobenzene	0.0405 0.0395		"	0.0400 0.0400		101 99	75-120 45-135			
LCS (7C07027-BS1)				Prepared &	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	0.248	0.10	mg/kg	0.275		90	65-125			
Benzene	0.00418	0.0010	и	0.00485		86	55-150			
Toluene	0.0231	0.0010	ıı	0.0235		98	70-120			
Ethylbenzene	0.00451	0.0010	п	0.00470		96	65-120			
Xylenes (total)	0.0261	0.0010	н	0.0265		98	70-120			
Surrogate: a,a,a-Trifluorotoluene	0.0435		"	0.0400		109	75-120			
Surrogate: 4-Bromofluorobenzene	0.0422		"	0.0400		106	45-135			
Matrix Spike (7C07027-MS1)		irce: MQC0		Prepared &					-	
Gasoline Range Organics (C4-C12)	0.231	0.10	mg/kg	0.275	ND	84	65-125			
Benzene	0.00442	0,0010	19	0.00485	ND	91	55-150			
Toluene	0.0244	0.0010	17	0.0235	ND	104	70-120			
Ethylbenzene	0.00484	0,0010	41	0.00470	ND	103	65-120			
Xylenes (total)	0.0268	0.0010	н	0.0265	ND	101	70-120			
Surrogate: a,a,a-Trifluorotoluene Surrogate: 4-Bromofluorobenzene	0.0444 0.0379		"	0.0400 0.0400		111 95	75-120 45-135			
Matrix Spike Dup (7C07027-MSD1)	Son	irce: MQC0	173-01	Prepared &	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	0.102	0.10	mg/kg	0.275	ND	37	65-125	77	40	N
Benzene	0.00142	0.0010	н	0.00485	ND	29	55-150	103	35	N
Toluene	0.00770	0.0010		0.0235	ND	33	70-120	104	40	N
Ethylbenzene	0.00148	0.0010	30	0.00470	ND	31	65-120	106	40	N
Xylenes (total)	0.00844	0.0010	16	0.0265	ND	32	70-120	104	40	N

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.





Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0224 **Reported:** 03/16/07 09:26

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

		Evaluation		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 7C07027 - EPA 5030B [P/T]

Matrix Spike Dup (7C07027-MSD1)	Source:	MQC0173-01	Prepared & An	alyzed: 03/07/	′07
Surrogate: a,a,a-Trifluorotoluene	0.0438	mg/kg	0.0400	110	75-120
Surrogate: 4-Bromofluorobenzene	0.0403	"	0.0400	101	45-135





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235

MQC0224 Reported:

Project Manager: Paula Sime 03/16/07 09:26

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

		Evaluation		Spike	Source		%REC		RPD	12/27/5/1
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C12035 - EPA 3550B										
Blank (7C12035-BLK1)				Prepared:	03/12/07	Analyzed	1: 03/15/07			
Motor Oil (C16-C36)	ND	5	mg/kg							
Diesel Range Organics (C10-C28)	ND	0.65	п							
Surrogate: n-Octacosane	1.68		"	1.67		101	40-120			
LCS (7C12035-BS1)				Prepared:	03/12/07	Analyzed	1: 03/15/07			
Diesel Range Organics (C10-C28)	15.3	1.0	mg/kg	16.7		92	60-115			
Surrogate: n-Octacosane	1.74		"	1.67		104	40-120			
Matrix Spike (7C12035-MS1)	Sour	ce: MQC0	173-01R	E2Prepared:	03/12/07	Analyzed	1: 03/15/07			
Diesel Range Organics (C10-C28)	16.6	1.0	mg/kg	16.7	0.83	94	60-115			
Surrogate: n-Octacosane	1.71		"	1.67	-130	102	40-120			
Matrix Spike Dup (7C12035-MSD1)	Sour	ce: MQC0	173-01R	E2Prepared:	03/12/07	Analyzed	1: 03/15/07			
Diesel Range Organics (C10-C28)	14.4	0.1	mg/kg	16.7	0.83	81	60-115	14	40	
Surrogate: n-Octacosane	1.54		"	1.67		92	40-120			
Buildguie. II-Octacobane	1.37									





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0224 Reported: 03/16/07 09:26

Total Metals by EPA 6000/7000 Series Methods - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C08020 - EPA 3050B										
Blank (7C08020-BLK1)				Prepared	& Analyz	ed: 03/08/	07			
Lead	ND	2.5	mg/kg							
LCS (7C08020-BS1)				Prepared	& Analyz	ed: 03/08/	07			
Lead	46.0	5.0	mg/kg	50.0	N.	92	75-120			
Matrix Spike (7C08020-MS1)	Soi	irce: MQC0	224-01	Prepared.	& Analyz	ed: 03/08/	07			
Lead	47.2	5.0	mg/kg	50.0	14	66	75-120			M8
Matrix Spike Dup (7C08020-MSD1)	Sou	ırce: MQC0	224-01	Prepared	& Analyz	ed: 03/08/	07			
Lead	75.6	5.0	mg/kg	50.0	14	123	75-120	46	25	M7, R2





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime

MQC0224 Reported: 03/16/07 09:26

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07008 - EPA 5030B P/T										
Blank (7C07008-BLK1)				Prepared &	& Analyze	ed: 03/07/0	07			
tert-Amyl methyl ether	ND	0.00125	mg/kg							
tert-Butyl alcohol	ND	0.005	n							
Di-isopropyl ether	ND	0.00125	ų							
1,2-Dibromoethane (EDB)	ND	0.00125	11							
1,2-Dichloroethane	ND	0.00125	н							
Ethanol	ND	0.048	и							
Ethyl tert-butyl ether	ND	0.00125	11							
Methyl tert-butyl ether	ND	0.00125	**							
Surrogate: Dibromofluoromethane Surrogate: 1,2-Dichloroethane-d4 Surrogate: Toluene-d8 Surrogate: 4-Bromofluorobenzene	0.00251 0.00284 0.00253 0.00242		n n n	0.00250 0.00250 0.00250 0.00250		100 114 101 97	45-130 55-135 70-120 60-120			
LCS (7C07008-BS1)				Prepared &	& Analyze	d: 03/07/0	07			
tert-Amyl methyl ether	0.00919	0.0025	mg/kg	0.0100		92	65-140			
tert-Butyl alcohol	0.203	0.010	11	0.200		102	75-130			
Di-isopropyl ether	0.00977	0.0025	н	0.0100		98	70-130			
1,2-Dibromoethane (EDB)	0.00842	0.0025	н	0.0100		84	80-135			
1,2-Dichloroethane	0.00918	0.0025	U	0.0100		92	70-120			
Ethanol	0.183	0.050	н	0.200		92	50-150			
Ethyl tert-butyl ether	0.00986	0.0025	п	0.0100		99	70-125			
Methyl tert-butyl ether	0.00897	0.0025	н	0.0100		90	75-130			
Surrogate: Dibromofluoromethane	0.00246		77	0.00250		98	45-130			
Surrogate: 1,2-Dichloroethane-d4	0.00245		n	0.00250		98	55-135			
Surrogate: Toluene-d8	0.00261		"	0.00250		104	70-120			
Surrogate: 4-Bromofluorobenzene	0.00250		11	0.00250		100	60-120			
Matrix Spike (7C07008-MS1)		urce: MQC0	173-01	Prepared &						
tert-Amyl methyl ether	0.0131	0.0025	mg/kg	0.0100	ND	131	65-140			
ert-Butyl alcohol	0.244	0.010	11	0.200	ND	122	75-130			
Di-isopropyl ether	0.0126	0.0025	н	0.0100	ND	126	70-130			
1.2-Dibromoethane (EDB)	0.0130	0.0025	н	0.0100	ND	130	80-135			

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0224 Reported: 03/16/07 09:26

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07008 - EPA 5030B P/T										
Matrix Spike (7C07008-MS1)	So	urce: MQC0	173-01	Prepared &	& Analyze	ed: 03/07/	07			
1,2-Dichforoethane	0.0128	0.0025	mg/kg	0.0100	ND	128	70-120			M
Ethanol	0.214	0.050	u.	0.200	ND	107	50-150			
Ethyl tert-butyl ether	0.0135	0.0025	11	0.0100	ND	135	70-125			M
Methyl tert-butyl ether	0.0134	0.0025	**	0.0100	ND	134	75-130			M7
Surrogate: Dibromofluoromethane	0.00254		"	0.00250		102	45-130			
Surrogate: 1,2-Dichloroethane-d4	0.00277		"	0.00250		111	55-135			
Surrogate: Toluene-d8	0.00261		"	0.00250		104	70-120			
Surrogate: 4-Bromofluorobenzene	0.00265		"	0.00250		106	60-120			
Matrix Spike Dup (7C07008-MSD1)	So	urce: MQC0	173-01	Prepared &	k Analyze	ed: 03/07/	07			
tert-Amyl methyl ether	0.0121	0.0025	mg/kg	0.0100	ND	121	65-140	8	25	
tert-Butyl alcohol	0.227	0.010	H	0.200	ND	114	75-130	7	25	
Di-isopropyl ether	0.0117	0.0025	P	0.0100	ND	117	70-130	7	40	
1,2-Dibromoethane (EDB)	0.0114	0.0025	11	0.0100	ND	114	80-135	13	20	
1,2-Dichloroethane	0.0121	0.0025	D	0.0100	ND	121	70-120	6	30	M7
Ethanol	0.218	0.050	n	0.200	ND	109	50-150	2	30	
Ethyl tert-butyl ether	0.0122	0.0025	**	0.0100	ND	122	70-125	10	30	
Methyl tert-butyl ether	0.0120	0.0025	17	0.0100	ND	120	75-130	11	25	
Surrogate: Dibromofluoromethane	0.00263		"	0.00250		105	45-130			
Surrogate: 1,2-Dichloroethane-d4	0.00262		"	0.00250		105	55-135			
Surrogate: Toluene-d8	0.00257		"	0.00250		103	70-120			
Surrogate: 4-Bromofluorobenzene	0.00260		n	0.00250		104	60-120			





Petaluma CA, 94954

Project Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0224 Reported: 03/16/07 09:26

Notes and Definitions

R2 The RPD exceeded the acceptance limit.

M8 The MS and/or MSD were below the acceptance limits. See Blank Spike (LCS).

M7 The MS and/or MSD were above the acceptance limits. See Blank Spike (LCS).

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

Reproductive Compared by	Test/America	Con	sultant Name:	Environment	al Resolution	ons, Inc.		E	xxon	Mobil	Engi	neer	Jenr	nifer	Sedl	ache	k				
Borgan Hill Division Project Manager Paula Sime Po 8: Facility ID 87 0225 PIGE 0 229	10002 MILLULIUG	;	Address:	601 North M	cDowell Blv	rd.			Tele	phon	e Nur	nber	(510) 54	7-819	96		-9124-2016			
Telephone Number: 707) 768-2000 ERI Job Number: 222913X Sampler Name: (Print) Sampler Signature:	408-776-9600		City/State/Zip:	Petaluma, C	alifornia 94	1954		•		A	ccou	nt#:	3876								
Sampler ID / Description DATE TIME COMP GRAB PRESERV NUMBER Substance Sellinquished by Date H-3-3/7/b/7 Time 1:50 Received by Comments: Case Comments Case	Morgan Hill Division	Pr	oject Manager	Paula Sime	e illining out						F	0 #:						/		-	
ExponMobil Sampler Name: (Print) Sampler Name: (Print) Sampler Signature Multiple Matrix Stite Address 2225 Telegraph Avenue Stite	885 Jarvis Drive	Telep	hone Number:	(707) 766-20	000					Fa	cility	ID#	7023	35			7	M	19C	02	24
Sampler Name: (Print) Sampler Splanture:	Morgan Hill, CA 95037	ER	I Job Number:	222913X						(Sloba	I ID#	T060	0101	354						
Sample ID / Description Sample ID / Description Sample ID / Description DATE TIME COMP GRAB PRESERV NUMBER SET OF SAME AND SAME	P-/	Sample	r Name: (Print)	Rebek	ah.A	Westr	up					200				Aven	iue	=			
Selinquished by Amalyze For: Amalyze For: Amalyze For: Special Instructions: Special Instru	EXOUNIOUN	Samp	oler Signature:	Mychil	MU	fred		56				100									
Please generate single composite sample from the four 96 hour Please generate single composite sample from the four 96 hour Please generate single composite sample from the four 96 hour Please generate single composite sample from the four 96 hour Please generate single composite sample from the four serves. If Total Lead result is above 80 pure, then run a 95 flow 95 flo	Shipping Method: Lab Courie	r Hand Delive	r 🗹 Commer	cial Express	Other	:		8 				- 201									
Please generate single composite sample from the four 96 hour 96 hour EDF Report Please generate single composite sample result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead result is above 50 ppm; then run a structure is seleves. If 70 at Lead run at Le	TAT	PROVIDE:	Special Instru	ctions:						Matrix	(in torribe		A 17 - 7 -	Ana	alvze	For:			
Relinquished by: All All	24 hour 72 hour	EDF Report															1				$\neg \neg$
SPI SP-1-(1-4) 3 7 07 10:00 x ICE 4 X X X X X X X X X	☐ 48 hour ☐ 96 hour											m	_	315B	_	9	8	8	1		
SPI SP-1-(1-4) 3 7 07 10:00 x ICE 4 X X X X X X X X X								OH ONYS				015	015	oll 8	121E	8260	326(6010			
SPI SP-1-(1-4) 3 7 07 10:00 x ICE 4 X X X X X X X X X	E 8 day		Set TBA dete	ection limit	<12 ug/L.							1 80	3 8	notor	88	Oxys	<u></u>	ead			
SPI SP-1-(1-4) 3 7 07 10:00 x ICE 4 X X X X X X X X X	Sample ID / Descript	llan	DATE	TIME	COMB	CDAD	DDECEDIA	NUMBER	/ater	Soil	apor	PH	PH	PHn	Œ	CAC	thai	otal L			
Relinquished by: All All	SAME TO SEE VICE VICE VICE VICE VICE VICE VICE VI	non	1 1			GRAD			>		>_				_					\dashv	-
Temperature Upon Receipt: 2-0	SP/ SP-1-(1-4)		3 7/01	10.00	X		ICE		-	X	_	X	X	X	X	X	X	X	_	_	\dashv
Temperature Upon Receipt: 2-0						L															
Temperature Upon Receipt: 2-0																					
Temperature Upon Receipt: 2-0																					
Temperature Upon Receipt: 2-0											-	-				-			-+	\dashv	+
Temperature Upon Receipt: 2-0							 		-		-	_	\vdash		-			\vdash	\vdash	\dashv	+
Temperature Upon Receipt: 2-0		man to man a second									_						_			_	\perp
Temperature Upon Receipt: 2-0																					
Temperature Upon Receipt: 2-0																					
Temperature Upon Receipt: 2-0							1												\Box	\top	\top
Temperature Upon Receipt: 2-0									\vdash					-			\vdash	-	\vdash	\dashv	
Temperature Upon Receipt: 2-0						-			-	_		_		-	-	_	-		\vdash	-	-
Temperature Upon Receipt: 2-0																	_		Ш		
Temperature Upon Receipt: 2-0		\mathcal{A}																			
Pur Temperature Upon Receipt: 2-0 Sample Containers Intact? V	Relinquished by:	Date 11	243/7/0	7 Time 11	:20	Received to	y: V	Me	1	1	Time	13	315	Lab	orato	ry Co	mme	nts:			
Sample Containers Intact? Y	I I I I I I I I I I I I I I I I I I I	<i>11</i>	200 01.10	11	70		W.	-	37	10:	-								eceipt	2-1	3
Pellorusished by Maria 1971 Date 3/4/D2 Time 1/55 Beesland 2 Text Personal 3/4/D2 Time	1 1/1 1/1/1		1 1	(10) plan (ຄ	laus	2010-00		1		160	5								
Relinquished by: Amount Date 3/7/04 Time 655 Received by TestAmerica: 2/104 Time VOAs Free of Headspace?	Relinquished by:	Date 3/	7/07	Time /	355	Received f	by TestAmerica	a: 3/7(ρ'n		Time	•	,								

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: EPE REC. BY (PRINT) WORKORDER: MG & 622 4 CIRCLE THE APPROPRIATE RESPONSE		DATE REC'D AT LAB: TIME REC'D AT LAB: DATE LOGGED IN:	03-07- 1655 3-7-	07			For Regula DRINKING WASTE WA	
CIRCLE THE APPROPRIATE RESPONSE	LAB SAMPLE#	CLIENT ID	CONTAINER DESCRIPTION		рН	SAMPLE	DATE SAMPLED	REMARKS: CONDITION (ETC.)
1. Custody Seal(s) Present / Absent Intact / Broken*							SAMPLED	Z
2. Chain-of-Custody Present / Absent*		Waller Commission of the Commi			···			
Traffic Reports or Packing List: Present / Absent								
4. Airbill: Airbill / Sticker Present / Absent		.15.			******			
5. Airbill #:			~				-4	
6. Sample Labels: Present / Absent							$\overline{}$	
7. Sample IDs: Listed / Not Listed on Chain-of-Custody								
8. Sample Condition: Intact / Broken* / Leaking*					T)			
9. Does information on chain-of-custody, traffic reports and sample labels agree?				3-A-	\leq			
10. Sample received within hold time?			PART E	\angle				
11. Adequate sample volume received? Yes / No*			1000					
12. Proper preservatives used? Yes / No*		CONTRACTOR OF THE PARTY OF THE						
13. Trip Blank / Temp Blank Received? (circle which, if yes) Yes (No			<u> </u>					200
14. Read Temp: 2-0 Corrected Temp: 2-0 Is corrected temp 4 +/-2°C? Yes / No**								and the state of t
(Acceptance range for samples requiring thermal pres.) **Exception (if any): METALS / DFF ON ICE or Problem COC								A Para Para Para Para Para Para Para Par



9 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

RE: Exxon 7-0235 Work Order: MQC0171

Enclosed are the results of analyses for samples received by the laboratory on 03/06/07 18:35. The samples arrived at a temperature of 2° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Chriting Noodcock





Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0171 Reported:

03/09/07 16:40

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
W-15-B7	MQC0171-01	Water	03/05/07 10:45	03/06/07 18:35
W-22-B7	MQC0171-02	Water	03/05/07 12:00	03/06/07 18:35





601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0171 Reported: 03/09/07 16:40

W-15-B7 (MQC0171-01) Water Sampled: 03/05/07 10:45 Received: 03/06/07 18:35

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Gasoline Range Organics (C4-C12)	ND	50	ug/l	1	7C07025	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	ND	0.50	30	н	n	11	н	н	
Toluene	ND	0.50		†I	H	II.	11	u	
Ethylbenzene	ND	0.50	**	II	11	н	п	n.	
Xylenes (total)	ND	0.50	ж.	11	н	II.	п	"	
Surrogate: a,a,a-Trifluorotoluene		107 %	85-	120	"	"	"	•	
Surrogate: 4-Bromofluorobenzene		102 %	75-	125	"	"	2007	"	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	470	ug/l	1	7C07019	03/07/07	03/09/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	66	47	n	39	**			11	Q1
Surrogate: n-Octacosane		82 %	30-	115		n	"	"	

Volatile Organic Compounds by EPA Method 8260B

TestAmerica - Morgan Hill, CA

	10	JUL RILLOT IC	4 1/101	P	11, 011				
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Not
tert-Amyl methyl ether	ND	0.50	ug/i	1	7C07004	03/07/07	03/07/07	EPA 8260B	
tert-Butyl alcohol	ND	10	n	п		*		ii .	
Di-isopropyl ether	ND	0.50	, in	11	**				
1.2-Dibromoethane (EDB)	ND	0.50		н	61	w			
1,2-Dichloroethane	ND	0.50	17	11	(4)			(m)	
Ethanol	ND	100	n	и.	9	•	202		
Ethyl tert-butyl ether	ND	0.50	11	W.	30	200		.0	
Methyl tert-butyl ether	0.54	0.50	ш	н	*	(0)	100%	(0)	
Surrogate: 1,2-Dichloroethane-d4		98 %	60-14	45	900	"	"	"	
Surrogate: 4-Bromofluorobenzene		86 %	60-12	20	"	"	"	(n)	
Surrogate: Dibromofluoromethane		96 %	75-13	30	*	"	"	H	
Surrogate: Toluene-d8		92 %	70-13	30	381)	(#	n	10	
_									





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime

MQC0171 Reported: 03/09/07 16:40

W-22-B7 (MQC0171-02) Water Sampled: 03/05/07 12:00 Received: 03/06/07 18:35

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	50	ug/l	1	7C07025	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	ND	0.50	nii:	н	н	ж	(006)	п	
Toluene	ND	0.50	100	II.	U		((0)	11	
Ethylbenzene	ND	0.50	((0))	71	И	w	0.000	, AL	
Xylenes (total)	ND	0.50	300	U	11	11.	989		
Surrogate: a,a,a-Trifluorotoluene		109 %	85-	120	"	"	ii.		
Surrogate: 4-Bromofluorobenzene		103 %	75-	125	Ħ	"	(0)	1380	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	470	ug/l	1	7C07019	03/07/07	03/09/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	220	47			"	н	0	11	Q1
Surrogate: n-Octacosane		68 %	30-	115	11	"	***	: M:	

Volatile Organic Compounds by EPA Method 8260B

TestAmerica - Morgan Hill, CA

- Carlo Section - Carlo Sectio		Stanieric		9					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Not
tert-Amyl methyl ether	ND	0.50	ug/l	1	7C07004	03/07/07	03/07/07	EPA 8260B	
tert-Butyl alcohol	ND	10	II .	"	н	н	**		
Di-isopropyl ether	ND	0.50	If	**	11	**	•	9	
1.2-Dibromoethane (EDB)	ND	0.50	Ħ	**	п	II.	н		
1.2-Dichloroethane	ND	0.50	U	10	"	п		"	
Ethanol	ND	100	11	**	II .	п	ü	30	
Ethyl tert-butyl ether	ND	0.50	н	(ii)	11	*1	36	м	
Methyl tert-butyl ether	ND	0.50	11	60	17	U	"	30	
Surrogate: 1,2-Dichloroethane-d4		96 %	60-14	45	11	"	"	"	
Surrogate: 4-Bromofluorobenzene		89 %	60-12	20	H.	"	"	(0)	
Surrogate: Dibromofluoromethane		94 %	75-13	30	"	"	*	<i>n</i>	
Surrogate: Toluene-d8		93 %	70-13	30	70	"	"	,,	





Project: Exxon 7-0235
Project Number: 7-0235

Project Manager: Paula Sime

MQC0171 Reported: 03/09/07 16:40

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07025 - EPA 5030B [P/T]										
Blank (7C07025-BLK1)				Prepared	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	ND	25	ug/l							
Benzene	ND	0.25	II							
Toluene	ND	0.29	11							
Ethylbenzene	ND	0.34	**							
Xylenes (total)	ND	0.35	н							
Surrogate: a.a,a-Trifluorotoluene	83.3		"	80.0		104	85-120			
Surrogate: 4-Bromofluorobenzene	80.7		"	80.0		101	75-125			
LCS (7C07025-BS1)	227			Prepared a	& Analyze					
Gasoline Range Organics (C4-C12)	227	50	ug/l	275		83	60-115			
Benzene	4.56	0.50	U	4.85		94	45-150			
Toluene	21.2	0.50	11	23.5		90	70-115			
Ethylbenzene	4,03	0.50	11	4.70		86	65-115			
Xylenes (total)	23.3	0.50	n	26.5		88	70-115			
Surrogate: a.a,a-Trifluorotoluene	82.3		"	80.0		103	85-120			
Surrogate: 4-Bromofluorobenzene	83.9		"	80.0		105	75-125			
Matrix Spike (7C07025-MS1)		rce: MQC01	71-01	Prepared &	& Analyze	d: 03/07/0				
Gasoline Range Organics (C4-C12)	240	50	ug/l	275	ND	87	60-115			
Benzene	4.59	0.50	и	4.85	ND	95	45-150			
Toluene	21.6	0.50	**	23.5	ND	92	70-115			
Ethylbenzene	4.13	0.50	П	4.70	ND	88	65-115			
Xylenes (total)	23.6	0.50	11	26.5	ND	89	70-115			
Surrogate: a,a,a-Trifluorotoluene	81.8		11	80.0		102	85-120			
Surrogate: 4-Bromofluorobenzene	84.8		"	80.0		106	75-125			
Matrix Spike Dup (7C07025-MSD1)		rce: MQC01	71-01	Prepared &	k Analyze	d: 03/07/0)7			
Gasoline Range Organics (C4-C12)	229	50	ug/l	275	ND	83	60-115	5	20	
Benzene	4.00	0.50	П	4.85	ND	82	45-150	14	25	
Toluene	18.6	0.50	11	23.5	ND	79	70-115	15	20	
Ethylbenzene	3,57	0.50	н	4.70	ND	76	65-115	15	25	
Xylenes (total)	20.4	0.50	u	26.5	ND	77	70-115	15	25	





Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0171 Reported:

03/09/07 16:40

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

		Evaluation		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 7C07025 - EPA 5030B [P/T]

Matrix Spike Dup (7C07025-MSD1) Surrogate: a,a,a-Trifluorotoluene	Source:	MQC0171-01	Prepared & An	alyzed: 03/07/)7		
	72.1	ug/l	80.0	90	85-120		
Surrogate: 4-Bromofluorobenzene	84.4	$\boldsymbol{\mu}$	80.0	106	75-125		





Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0171 Reported:

03/09/07 16:40

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07019 - EPA 3510C	25-5-W1									
Blank (7C07019-BLK1)				Prepared:	03/07/07	Analyzed	1: 03/09/07			
Motor Oil (C16-C36)	ND	250	ug/l	2.1						
Diesel Range Organics (C10-C28)	26.2	25	11							
Surrogate: n-Octacosane	34.6		,,	50.0		69	30-115			
LCS (7C07019-BS1)				Prepared:	03/07/07	Analyzed	1: 03/08/07			
Diesel Range Organics (C10-C28)	396	50	ug/l	500		79	40-140			
Surrogate: n-Octacosane	29.4		"	50.0		59	30-115			
LCS Dup (7C07019-BSD1)				Prepared:	03/07/07	Analyzed	1: 03/08/07			
Diesel Range Organics (C10-C28)	373	50	ug/l	500		75	40-140	6	35	
Surrogate: n-Octacosane	34.0		"	50.0		68	30-115			





Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0171 Reported: 03/09/07 16:40

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07004 - EPA 5030B P/T										
Blank (7C07004-BLK1)				Prepared	& Analyzo	ed: 03/07/	07			
tert-Amyl methyl ether	ND	0.30	ug/l							
tert-Butyl alcohol	ND	5	11							
Di-isopropyl ether	ND	0.25	n							
1,2-Dibromoethane (EDB)	ND	0.25	**							
I,2-Dichloroethane	ND	0.25	17							
Ethanol	ND	50	11							
Ethyl tert-butyl ether	ND	0.40								
Methyl tert-butyl ether	ND	0.31								
Surrogate: 1,2-Dichloroethane-d4	2.39		"	2.50		96	60-145			
Surrogate: 4-Bromofluorobenzene	2.11		"	2.50		84	60-120			
Surrogate: Dibromofluoromethane	2.27		"	2.50		91	75-130			
Surrogate: Toluene-d8	2.34		"	2.50		94	70-130			
LCS (7C07004-BS1)				Prepared &	& Analyze	d: 03/07/0)7			
ert-Amyl methyl ether	9.81	0.50	ug/l	10.0		98	65-135			
ert-Butyl alcohol	190	20	U	200		95	60-135			
Di-isopropyl ether	8.82	0.50	и	10.0		88	70-130			
,2-Dibromoethane (EDB)	10.7	0.50	II	10.0		107	75-140			
L2-Dichloroethane	9.78	0.50	и	10.0		98	75-125			
Ethanol	197	100	u	200		98	15-150			
Ethyl tert-butyl ether	9.34	0.50	п	10.0		93	65-130			
Methyl tert-butyl ether	9.70	0.50	11	10.0		97	50-140			
Surrogate: 1,2-Dichloroethane-d4	2.43		"	2.50		97	60-145			
'urrogate: 4-Bromofluorobenzene	2.20		"	2.50		88	60-120			
urrogate: Dibromofluoromethane	2.30		"	2.50		92	75-130			
Surrogate: Toluene-d8	2.29		"	2.50		92	70-130			
Matrix Spike (7C07004-MS1)		rce: MQB06	80-03	Prepared &						
ert-Amyl methyl ether	9.95	0.50	ug/l	10.0	ND	100	65-135			
ert-Butyl alcohol	217	20	æ	200	17	100	60-135			
Di-isopropyl ether	9.84	0.50	0.00	10.0	0.58	93	70-130			
,2-Dibromoethane (EDB)	11.1	0.50	1100	10.0	ND	111	75-140			

TestAmerica - Morgan Hill, CA

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.





Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0171 Reported: 03/09/07 16:40

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

		Evaluation		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C07004 - EPA 5030B P/T										
Matrix Spike (7C07004-MS1)	Sour	rce: MQB06	680-03	Prepared	& Analyze	ed: 03/07/	07			
1,2-Dichloroethane	10.1	0.50	ug/l	10.0	ND	101	75-125			
Ethanol	218	100	tt.	200	ND	109	15-150			
Ethyl tert-butyl ether	9.82	0.50	11	10.0	ND	98	65-130			
Methyl tert-butyl ether	10.6	0.50	Ħ	10.0	0.47	101	50-140			
Surrogate: 1,2-Dichloroethane-d4	2.46		"	2.50		98	60-145			
Surrogate: 4-Bromofluorobenzene	2.38		"	2.50		95	60-120			
Surrogate: Dibromofluoromethane	2.36		#	2.50		94	75-130			
Surrogate: Toluene-d8	2.36		"	2.50		94	70-130			
Matrix Spike Dup (7C07004-MSD1)	Sour	Source: MQB0680-03 Prep		Prepared 6	& Analyze	d: 03/07/0	07			
tert-Amyl methyl ether	10.5	0.50	ug/l	10.0	ND	105	65-135	5	25	
tert-Butyl alcohol	225	20	n	200	17	104	60-135	4	35	
Di-isopropyl ether	10.1	0.50	11	10.0	0.58	95	70-130	3	35	
1,2-Dibromoethane (EDB)	12.0	0.50	н	10.0	ND	120	75-140	8	15	
1,2-Dichloroethane	10.5	0.50	и	10.0	ND	105	75-125	4	20	
Ethanol	239	100	U	200	ND	120	15-150	9	35	
Ethyl tert-butyl ether	9,99	0.50	н	10.0	ND	100	65-130	2	35	
Methyl tert-butyl ether	11.0	0.50	II	10.0	0.47	105	50-140	4	25	
Surrogate: 1,2-Dichloroethane-d4	2.50		"	2.50		100	60-145			
Surrogate: 4-Bromofluorobenzene	2.44		n	2.50		98	60-120			
Surrogate: Dibromofluoromethane	2.44		"	2.50		98	75-130			
Surrogate: Toluene-d8	2.33		u	2.50		93	70-130			





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0171 Reported: 03/09/07 16:40

Notes and Definitions

Q1 Does not match typical pattern

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

CHAIN OF CUSTODY RECORD

Test/America	Con	sultant Name:	Environment	al Resolutio	ns, Inc.		E	cconf	Mobil	Engir	neer _	Jenn	ifer S	Sedla	che	k						
168WAIII6IICa		Address:	601 North M	Dowell Blv	d.			Tele	phone	Num	ber	(510)	547	-819	6			,				
408-776-9600		City/State/Zip:	Petaluma, C	alifornia 94	954				A	ccour	nt #:	3876										
Morgan Hill Division	Pr	oject Manager	Paula Sime							P	O#:_							19			_	
885 Jarvis Drive	Telep	hone Number:	(707) 766-20	000	ancia di La				Fa	cillty	ID#	7023	15							,,,,,,,,,,	_	
Morgan Hill, CA 95037		l Job Number:				A-1-			G	lobal	ID#	T0600	01013	54	_						_	
ExonMobil	Samp	r Name: (Print) bler Signature:	Heron	Duly 1	الوال	- and				Addı State	_					ие			-			363
Shipping Method: Lab Courter	r 🔲 Hand Delive			Other	<u> </u>	- Australia				· - 1											_	
	PROVIDE:	Special Instru				VDE 40 B	04 500		Matrix		7				Ana	lyze F	or:				_	
24 hour	EDF Report	7 CA Oxys = Use silica ge Set TBA dete	l cleanup f	or all TPH	d analyse		1)			d 8015B	g 8015B	TPH motor oil 8015B	BTEX 8021B	Oxys 8260B	Ethanol 8260B						
Dealess H (16) Death De		DATE	TIME	COMP	GRAB	PRESERV- (VOA/liter)	NUMBER	Water	Soll	Vарог	TPHd	трна	H	3TE	7 CA	H _a						
Boring # / W-Depth-Bo		5-Mar-07	10:45	COM	X	HCL/none	7 VOAsi	X			X	X	x	X	X				7		1	U-B7-4-1
B7 / W-15-B7 B7 / W-22-B7	10 V	5-Mar-07	12:00		X	HCL/none	6 VOAsi	X			X		х	х	Х						Ju	0-B7-4-16 0-B7-20-2
							, k															
	2000-00-00-00-00-00-00-00-00-00-00-00-00						3													1		
						1																
Relinquished by: Harda Deef	UZeo(Pare 10) Dato 3-	, 3(5/0°	Time (35	Received	by: Shirt	off ,	3/8	0-	Time	333	30	Labo	Tem Sam	perat	ure U contain se of h	pon R ners li	ntact?	.4	•		

PROBLEM CHAIN-OF-CUSTODY

DATE/TIME 3-66-67	DATE RECEIVED 03-06-97
CLIENT _ ERT - 222913 X	TURN AROUND TIME 24 hour
CLIENT SERVICES REP CLUSTON	ANALYST BROWN
PRO	BLEM
	1 2 22 2 22 22
The ID on the samples	15 Ourself Then
C.3.C 1	
	MQC 0171
	M&C 0171
	The state of the s
- 3/7 Sent email to Paula.	
	UTION
Client Instruction* B7 B the A'ele 2.) W-22-B7 W-15-B7	O and the and
Client Instruction* 101 15 The hele	e pour name
1-15-67 = 11	1
W-13-104 - Q	rese 105 are correct.
+ see attached em	
Telephone Number of Client: 707 - 3	766-2026.
Client Contact for Instruction:	
Date and Time of Instruction: $3/80$	107 7:49
Date & Time Form Given to Sample Control:	
CLIENT SERVICES REP. SIGNATURE:	A.

*If client does not return call within 24 hours, please route this form to the Laboratory Director.

Christina Woodcock

From: Paula M. Sime [psime@ERI-US:com]

Sent: Thursday, March 08, 2007 7:49 AM

To: Christina Woodcock

Subject: RE: ?'s about 7-0235

OK, let's see. The W-15-B7 is the same as W-B7-14-16, and should be labeled W-15-B7. And W-22-B7 is the same as W-B7-20-24 and should be labeled W-22-B7. You're right, the B7 in the front is just the field point name; we don't need it labeled that way. So we should have: W-15-B7 and W-22-B7. I'm sorry for the confusion. We had 3 people out in the field, probably trying to be helpful to each other and labeling things different ways.

Don't worry about the soil, we'll take the results as soon as we can get them. Thanks Christina!

From: Christina Woodcock [mailto:cwoodcock@testamericainc.com]

Sent: Wednesday, March 07, 2007 12:12 PM

To: Paula M. Sime

Subject: ?'s about 7-0235

Hi Paula,

I have a COC question for the water samples collected on 3-5. On the COC, the sample ID's say "B7/W-15-B7" and "B7/W-22-B7" and the sample labels state "W-B7-4-16" and W-B7-20-24" respectively. I figured out that "B7" in the front of the ID's on the COC is just the field point name, but still the ID's don't match up? Please clarify.....

Also, we made a mistake and sent the soils sampled on 3-5 in a cooler to our Concord service center by accident. Savio, our courier is picking them back up this afternoon and bringing them back here, but that might delay our results since we lost a day. I'm very sorry about this and I will push to get the results for these samples as soon as possible.

Thanks.

Christina Woodcock Project Manager - Morgan Hill, CA Facility TestAmerica Analytical Testing Corporation Office: 408.776.9600 Direct line: 408.782.8154 Fax: 408.782.6308

cwoodcock@testamericainc.com

This material is intended only for the use of the individual(s) or entity to whom it is addressed and may contain information that is privileged and confidential. It is our policy that e-mails are intended for and should be used for business purposes only. If you are not the intended recipient, or the employee or agent responsible for delivering this material to the intended recipient, you are hereby notified that any dissemination, distribution or copying of this e-mail is strictly prohibited. If you have received this communication in error, please notify the sender immediately and delete this material from your wireless device, computer, and/or server. Thank you for your professional consideration and cooperation.

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: ERI REC. BY (PRINT) BhavM WORKORDER: MAC 61 CIRCLE THE APPROPRIATE RESPONSE	1/ LAB SAMPLE#	DATE REC'D AT LAB: TIME REC'D AT LAB: DATE LOGGED IN: CLIENT ID	03-06- 18:3 3-4 CONTAINER DESCRIPTION	S -67 PRESER	рН	SAMPLE	DRINKING WASTE WA	REMARKS:
Custody Seal(s) Present / Absent)	OF HAIT EE, IF		DESCRIPTION	VATIVE	•	MATRIX	SAMPLED	CONDITION (ETC.)
Intact / Broken*								
2. Chain-of-Custody Present / Absent*	 							
3. Traffic Reports or			ļ					
Packing List: Present / Absent			-					
4. Airbill: Airbill / Sticker								
Present / Absent		"			***************************************		-/-	
5. Airbill #:								
6. Sample Labels: Present / Absent						-/		
7. Sample IDs: Listed / Not Listed			7					
on Chain-of-Custody			, A	3	-/			
8. Sample Condition: (Intact / Broken* /			06.					
Leaking*			65					
9. Does information on chain-of-custody,			5 /					
traffic reports and sample labels		1,00	/					0
agree? (Yes)/ No*		· Noc	,					
10. Sample received within								
hold time? Yes / No*								100
11. Adequate sample volume								
received? (Yes / No* 12. Proper preservatives used? (Yes) / No*		<u>"</u> /						
13. Trip Blank / Temp Blank Received?					-			
(circle which, if yes) Yes (No	<u> </u>	/						
14. Read Temp: 7-0								
Corrected Temp: 2.0	 				_			
Is corrected temp 4 +/-2°C? (Yes / No**	-/-				_			
(Acceptance range for samples requiring thermal pres.)								
*Exception (if any): METALS / DFF ON ICE	/							
₹ Problem COC								
			2006205 3000 0000		SANCES PROPERTY	America	N/SVM/GENERAL	

'evialen 8

Rev 7 (07/19/05)

9 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

RE: Exxon 7-0235 Work Order: MQC0223

Enclosed are the results of analyses for samples received by the laboratory on 03/07/07 16:55. The samples arrived at a temperature of 2° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Chritina (Noodcock





Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0223 Reported: 03/09/07 14:38

Petaluma CA. 94954

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
W-22.5-24-B9	MQC0223-01	Water	03/06/07 12:15	03/07/07 16:55
W-14-16-B9	MQC0223-02	Water	03/06/07 10:40	03/07/07 16:55





Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0223 Reported: 03/09/07 14:38

W-22.5-24-B9 (MQC0223-01) Water

Petaluma CA, 94954

Sampled: 03/06/07 12:15 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

				- 8					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	490	250	ug/i	5	7C07025	03/07/07	03/07/07	EPA 8015B/8021B	
Benzene	160	2.5	in	U	n	11	**	11	
Toluene	21	2.5	500	n	н	н	11	(00)	
Ethylbenzene	12	2.5	100	ū	11	н	H	100	
Xylenes (total)	40	2.5	:#XX	n.			U	11	
Surrogate: a,a,a-Trifluorotoluene		108 %	85-	120	"	"	*	"	
Surrogate: 4-Bromofluorobenzene		102 %	75-	125	"	"	**	**	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	480	ug/l	ĭ	7C08035	03/08/07	03/09/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	81	48	Ħ	7.00		(+)	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	П	QI
Surrogate: n-Octacosane		97 %	30-	115	"	**	900	w	

Volatile Organic Compounds by EPA Method 8260B

TestAmerica - Morgan Hill, CA

		Reporting							
Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
tert-Amyl methyl ether	ND	1.0	ug/l	2	7C08003	03/08/07	03/08/07	EPA 8260B	
tert-Butyl alcohol	ND	10		U	*	11.	"	**	
Di-isopropyl ether	3.4	1.0	**	11		•	"	**	
1,2-Dibromoethane (EDB)	ND	1.0	**	п	"		**	AL.	
1,2-Dichloroethane	ND	1.0		11	**			**	
Ethanol	ND	200	**	tl .	*		**	"	
Ethyl tert-butyl ether	ND	1.0	*	ш	w	(96))	**	n n	
Methyl tert-butyl ether	17	1.0	0	11	00	30.7	11	#	
Surrogate: 1,2-Dichloroethane-d4		100 %	60-1	45	"	"	"	**	
Surrogate: 4-Bromofluorobenzene		101 %	60-1	20	n	39965	"	"	
Surrogate: Dibromofluoromethane		93 %	75-1	30	"		"	<i>u</i>	
Surrogate: Toluene-d8		100 %	70-1	30	"	"	"	*	





Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0223 Reported: 03/09/07 14:38

W-14-16-B9 (MQC0223-02) Water

Petaluma CA, 94954

Sampled: 03/06/07 10:40 Received: 03/07/07 16:55

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B

TestAmerica - Morgan Hill, CA

				_					
Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	38000	25000	ug/l	500	7C07025	03/07/07	03/08/07	EPA 8015B/8021B	
Benzene	15000	250	2.00	36	U	U	3,865	И	
Toluene	890	250	2003	38	*1	ш		п	
Ethylbenzene	700	250		31	II.	11		11	
Xylenes (total)	1700	250	0000	an .	П	11	W	u.	
Surrogate: a,a,a-Trifluorotoluene		107 %	85-	120	"	"	"	"	
Surrogate: 4-Bromofluorobenzene		102 %	75-	125	"	"	n		

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Motor Oil (C16-C36)	ND	480	ug/l	1	7C08035	03/08/07	03/09/07	EPA 8015B-SVOA	
Diesel Range Organics (C10-C28)	1000	48	2867.	#	*		л	H .	Q!
Surrogate: n-Octacosane		101 %	30-	115	"	"	300	(800)	

Volatile Organic Compounds by EPA Method 8260B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
ert-Amyl methyl ether	ND	50	ug/l	100	7C08003	03/08/07	03/08/07	EPA 8260B	
ert-Butyl alcohol	ND	500		**	*	**	**		
Di-isopropyl ether	ND	50		**	#	**		100	
1.2-Dibromoethane (EDB)	ND	50		*	**	u		(00)	
1.2-Dichloroethane	ND	50		**			**	AC.	
Ethanol	ND	10000		**	0	**		(0)	
Ethyl tert-butyl ether	ND	50		ž.	31		(10)	(n))	
Methyl tert-butyl ether	120	50	0.	**	w	3013	(0))	7000)	
Surrogate: 1,2-Dichloroethane-d4		102 %	60-1	145	**	982	"	ir.	
Surrogate: 4-Bromofluorobenzene		101 %	60-1	120	**	1112	11.	990	
Surrogate: Dibromofluoromethane		94 %	75-1	130	**	,,	"		
Surrogate: Toluene-d8		98 %	70-1	130	90	"	"	**	

RL7





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

MQC0223 Reported:

Project Manager: Paula Sime

03/09/07 14:38

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes	
Batch 7C07025 - EPA 5030B [P/T]											
Blank (7C07025-BLK1)				Prepared .	& Analyze	ed: 03/07/	07				
Gasoline Range Organics (C4-C12)	ND	25	ug/l								
Benzene	ND	0.25	"								
Toluene	ND	0.29	н								
Ethylbenzene	ND	0.34	W								
Xylenes (total)	ND	0.35									
Surrogate: a.a.a-Trifluorotoluene	83.3		"	80.0		104	85-120				
Surrogate: 4-Bromofluorobenzene	80.7		"	80.0		101	75-125				
LCS (7C07025-BS1)			.10	Prepared of	& Analyze						
Gasoline Range Organics (C4-C12)	227	50	ug/l	275		83	60-115				
Benzene	4.56	0.50	D	4.85		94	45-150				
Toluene	21.2	0.50		23.5		90	70-115				
Ethylbenzene	4.03	0.50	ů.	4.70		86	65-115				
Xylenes (total)	23.3	0.50	((4))	26.5		88	70-115				
Surrogate: a.a,a-Trifluorotoluene	82.3		"	80.0		103	85-120				
Surrogate: 4-Bromofluorobenzene	83.9		11	80.0		105	75-125				
Matrix Spike (7C07025-MS1)		rce: MQC01	71-01	Prepared & Analyzed: 03/07/07							
Gasoline Range Organics (C4-C12)	240	50	ug/l	275	ND	87	60-115				
Benzene	4.59	0.50	11	4,85	ND	95	45-150				
Coluene	21.6	0.50	199	23.5	ND	92	70-115				
Ethylbenzene	4.13	0.50	n	4.70	ND	88	65-115				
(xylenes (total)	23.6	0.50	**	26.5	ND	89	70-115				
Surrogate: a,a,a-Trifluorotoluene	81.8			80.0		102	85-120				
Surrogate: 4-Bromofluorobenzene	84.8		n	80.0		106	75-125				
Matrix Spike Dup (7C07025-MSD1)	Sou	rce: MQC01	71-01	Prepared &	& Analyze	d: 03/07/0)7				
Gasoline Range Organics (C4-C12)	229	50	ug/l	275	ND	83	60-115	5	20		
Benzene	4.00	0.50	u	4.85	ND	82	45-150	14	25		
oluene	18.6	0.50	3003	23.5	ND	79	70-115	15	20		
Ethylbenzene	3.57	0.50	(00)	4.70	ND	76	65-115	15	25		
(vlenes (total)	20.4	0.50	0000	26.5	ND	77	70-115	15	25		





Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0223 Reported:

03/09/07 14:38

Purgeable Hydrocarbons and BTEX by EPA 8015B/8021B - Quality Control TestAmerica - Morgan Hill, CA

		Evaluation		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 7C07025 - EPA 5030B [P/T]

Matrix Spike Dup (7C07025-MSD1)	Source:	MQC0171-01	Prepared & Ar	nalyzed: 03/07/	07
Surrogate: a,a,a-Trifluorotoluene	72.1	ug/l	80,0	90	85-120
Surrogate: 4-Bromofluorobenzene	84.4	"	80.0	106	75-125





Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0223 Reported: 03/09/07 14:38

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C08035 - EPA 3510C										
Blank (7C08035-BLK1)				Prepared:	03/08/07	Analyzed	1: 03/09/07			
Motor Oil (C16-C36)	ND	250	ug/l			12.				
Diesel Range Organics (C10-C28)	ND	25	И							
Surrogate: n-Octacosane	41.3		n	50.0		83	30-115			
LCS (7C08035-BS1)				Prepared:	03/08/07	Analyzed	1: 03/09/07			
Diesel Range Organics (C10-C28)	275	50	ug/l	500		55	40-140			
Surrogate: n-Octacosane	40.4		11	50.0		81	30-115			
LCS Dup (7C08035-BSD1)				Prepared:	03/08/07	Analyzed	l: 03/09/07			
Diesel Range Organics (C10-C28)	261	50	ug/l	500		52	40-140	5	35	
Surrogate: n-Octacosane	40.1		"	50.0		80	30-115			





Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0223 Reported: 03/09/07 14:38

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes			
Batch 7C08003 - EPA 5030B P/T													
Blank (7C08003-BLK1)	Prepared & Analyzed: 03/08/07												
tert-Amyl methyl ether	ND	0.30	ug/l										
tert-Butyl alcohol	ND	4.9	0										
Di-isopropyl ether	ND	0.25	11										
1,2-Dibromoethane (EDB)	ND	0.25	11										
1,2-Dichloroethane	ND	0.25	*1										
Ethanol	ND	50	0.00										
Ethyl tert-butyl ether	ND	0.40											
Methyl tert-butyl ether	ND	0.31											
Surrogate: 1,2-Dichloroethane-d4 Surrogate: 4-Bromofluorobenzene Surrogate: Dibromofluoromethane Surrogate: Toluene-d8	2.53 2.41 2.34 2.41		n n n	2.50 2.50 2.50 2.50		101 96 94 96	60-145 60-120 75-130 70-130						
LCS (7C08003-BS1)				Prepared &	& Analyze	d: 03/08/	07						
ert-Amyl methyl ether	11.1	0.50	ug/l	10.0		111	65-135						
ert-Butyl alcohol	204	20	u	200		102	60-135						
Di-isopropyl ether	11.2	0.50	300	10.0		112	70-130						
1,2-Dibromoethane (EDB)	10.7	0.50	(10%)	10.0		107	75-140						
1.2-Dichloroethane	10.4	0.50		10.0		104	75-125						
Ethanol	250	100	(80)	200		125	15-150						
Ethyl tert-butyl ether	10.6	0.50	W	10.0		106	65-130						
Methyl tert-butyl ether	10.3	0.50		10.0		103	50-140						
Surrogate: 1,2-Dichloroethane-d4	2,48		n	2.50		99	60-145						
Surrogate: 4-Bromofluorobenzene	2.56		"	2.50		102	60-120						
Surrogate: Dibromofluoromethane	2.50		"	2.50		100	75-130						
Surrogate: Toluene-d8	2.47		"	2.50		99	70-130						
Matrix Spike (7C08003-MS1)	Sou	rce: MQC02	23-01	Prepared &	& Analyze	d: 03/08/0)7						
ert-Amyl methyl ether	23.7	1.0	ug/l	20.0	ND	118	65-135						
ert-Butyl alcohol	387	40		400	ND	97	60-135						
Di-isopropyl ether	27.2	1.0	36.1	20.0	3.4	119	70-130						
,2-Dibromoethane (EDB)	23.2	1.0	30.1	20.0	ND	116	75-140						

TestAmerica - Morgan Hill, CA

The results in this report apply to the samples analyzed in accordance with the chain of custody document. Unless otherwise stated, results are reported on a wet weight basis. This analytical report must be reproduced in its entirety.





601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0223 Reported: 03/09/07 14:38

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C08003 - EPA 5030B P/T										
Matrix Spike (7C08003-MS1)	Sou	rce: MQC02	23-01	Prepared	& Analyze	ed: 03/08/	07			
1.2-Dichloroethane	22,5	1.0	ug/l	20.0	ND	112	75-125			
Ethanol	477	200	н.	400	ND	119	15-150			
Ethyl tert-butyl ether	22.8	1.0	8:	20.0	ND	114	65-130			
Methyl tert-butyl ether	40.1	1,0		20.0	17	116	50-140			
Surrogate: 1,2-Dichloroethane-d4	2.54		"	2.50		102	60-145			
Surrogate: 4-Bromofluorobenzene	2.65		"	2.50		106	60-120			
Surrogate: Dibromofluoromethane	2.47		"	2.50		99	75-130			
Surrogate: Toluene-d8	2.52		"	2.50		101	70-130			
Matrix Spike Dup (7C08003-MSD1)	Sou	rce: MQC02	23-01	Prepared a	& Analyze	d: 03/08/	07			
tert-Amyl methyl ether	25.2	1.0	ug/l	20.0	ND	126	65-135	6	25	
tert-Butyl alcohol	408	40	"	400	ND	102	60-135	5	35	
Di-isopropyl ether	28.9	1.0	н	20.0	3.4	128	70-130	6	35	
1,2-Dibromoethane (EDB)	24.8	1.0	н	20.0	ND	124	75-140	7	15	
1,2-Dichloroethane	23.9	1.0	II.	20.0	ND	120	75-125	6	20	
Ethanol	479	200	11	400	ND	120	15-150	0.4	35	
Ethyl tert-butyl ether	24.6	1.0	u	20.0	ND	123	65-130	8	35	
Methyl tert-butyl ether	42.0	1.0	n	20.0	17	125	50-140	5	25	
Surrogate: 1,2-Dichloroethane-d4	2.52		п	2.50		101	60-145			
Surrogate: 4-Bromofluorobenzene	2.72		"	2.50		109	60-120			
Surrogate: Dibromofluoromethane	2.49		"	2.50		100	75-130			
Surrogate: Toluene-d8	2.51		"	2.50		100	70-130			





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235

Project Manager: Paula Sime

MQC0223 Reported: 03/09/07 14:38

Notes and Definitions

RL7 Sample required dilution due to high concentrations of target analyte.

Q1 Does not match typical pattern

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

Test/America	Con	sultant Name:	Environment	al Resoluti	ons, Inc.		E	xxon	Mobil	Engi	neer	Jenr	nifer	Sed	ache	ek				
I CO UNCUMPTION TO		Address:	601 North M	cDowell Blu	vd.			Telephone Number <u>(510)</u> 547-8196												
408-776-9600		City/State/Zip:	Petaluma, C	alifornia 94	1954			Account #: 3876												
Morgan Hill Division	Pr	oject Manager	Paula Sime					PO#:												
885 Jarvis Drive	Telep	hone Number:	(707) 766-20	000		110111—11001—100—10—100		Facility ID # 70235 / 17 4 C 0223										23		
Morgan Hill, CA 95037	ER	l Job Number:	222913X							- 3	2.5	T060		354						
ExonMobil.	Sample Sami	r Name: (Print) oler Signature:	Heid	i Die	Henry Local	ach-C	avlo		Site	Add	lress	2225 Oakla	Tele	graph		nue				
Shipping Method: Lab Courier	Hand Delive	r 🗹 Commei	rcial Express	Othe	r:			ément à l'	Gity,	State	e Zip	Vakia	and, C	Jamoi	rnia					
TAT	PROVIDE:		Special Instructions:										Analyze For:							
☑ 24 hour ☐ 72 hour	EDF Report	7 CA Oxys =					CA, EDB.						88						T	
☐ 48 hour ☐ 96 hour		Use silica ge Set TBA det				es.					5B	5B	TPH motor oil 8015B	<u>m</u>	809	Ethanol 8260B			1	
☐ 8 day											8015B	8015B	or oil	302	Oxys 8260B	82				1
o day		<u> </u>			r	PRESERV		-ie		<u>_</u>			mot	BTEX 8021B	ő	ano				
Sample ID / Descript	ion	DATE	TIME	COMP	GRAB	(VOA/liter)	NUMBER	Water	Soll	Vapor	ТРН	тРНд	TPH	BTE	7 CA	EF				
B9 W-22.5-24-B9	ы	3/6/07	12:15			HCL/none	6 VOAs/ 2 AMBs	Х			Х	Х	X	x	X	X				\top
B9 W- 14-16 - B	9 02	3/6/07	10:40			HCL/none	6 VOAs/ 2 AMBs	х			x			x	Х	x				
															-	-			\dashv	
								-						_	_	-	_		_	
	energy and the state of the sta																			
	<u> </u>														-	-			-	+
						-								_		-			-	
					ļ															
HARING WEST						1													7	
Relinquished by: Relinquished by: Relinquished by: AmoM	Copate 3	16109	Time 14	05	Received b	» Shu	310	3	4/1	Time	(3	15	Labo	orator Tem				eceipt	۲. ۲۰ ۷	<u></u>
Relinquished by: ShrioM	Date 3	4/07	Time /6	55	Received b	PrestAmerica	3/0	7/0	7	Time	168	<u> </u>					ners Ir Ieads			

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: EPE REC. BY (PRINT) WORKORDER: ### ### ############################	•	DATE REC'D AT LAB: TIME REC'D AT LAB: DATE LOGGED IN:	03-07-					tory Purposes? WATER YES / NO NTER YES / NO
CIRCLE THE APPROPRIATE RESPONSE	LAB SAMPLE#	CLIENT ID	CONTAINER DESCRIPTION		рН	SAMPLE	DATE SAMPLED	REMARKS: CONDITION (ETC.)
Custody Seal(s) Present / Absent						MINTALA	SAMI LED	7
Intact / Broken*		THE PROPERTY OF THE PARTY.						
2. Chain-of-Custody Present / Absent*								
3. Traffic Reports or								
Packing List: Present / Absent 4. Airbill: Airbill / Sticker			ļ					/
Present / Absent		۹.	ļ				}	
5. Airbill #:			~				-/4	
6. Sample Labels: Present / Absent							$\overline{}$	
7. Sample IDs: Listed / Not Listed							/	
on Chain-of-Custody								
8. Sample Condition: (Intact / Broken* /						/		
Leaking*					2	7,		
9. Does information on chain-of-custody,				2-04	7			
traffic reports and sample labels		1		25-07	/			
agree? (Yes / No*								
10. Sample received within		\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	(00)					
hold time? Yes / No*		NAMES OF THE PERSON OF THE PER	RAPE					
11. Adequate sample volume			M. /					:
received? (Yes / No*		(°).						
12. Proper preservatives used? Yes / No*		W-W			4			
13. Trip Blank / Temp Blank Received?			<u> </u>					
(circle which, if yes) Yes No								
14. Read Temp: 2-0								
Corrected Temp: 2.0								
Is corrected temp 4 +/-2°C? (Yes) / No**								
(Acceptance range for samples requiring thermal pres.)								
**Exception (if any): METALS / DFF ON ICE								
or Problem COC								

'9L Revision 8

'aces Rev 7 (07/19/05)

*IF CIRCLED, CONTACT PROJECT MANAGER AND ATTACH RECORD OF RESOLUTION.

Page ______of ____



9 March, 2007

Paula Sime Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma, CA 94954

RE: Exxon 7-0235 Work Order: MQC0104

Enclosed are the results of analyses for samples received by the laboratory on 03/05/07 19:15. The samples arrived at a temperature of 5° C. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Christina Woodcock Project Manager

CA ELAP Certificate #1210

Chritine Noodcock





Environmental Resolutions (Exxon)

601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Project Manager: Paula Sime

MQC0104 Reported:

03/09/07 16:35

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
W-14-B8	MQC0104-01	Water	03/02/07 13:10	03/05/07 19:15





Environmental Resolutions (Exxon)

601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0104 Reported: 03/09/07 16:35

W-14-B8 (MQC0104-01) Water Sampled: 03/02/07 13:10 Received: 03/05/07 19:15

Purgeable Hydrocarbons by EPA 8015B TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Gasoline Range Organics (C4-C12)	ND	50	ug/l	1	7C07025	03/07/07	03/07/07	EPA 8015B-VOA	
Surrogate: 4-Bromofluorobenzene		109 %	75-	125	"	"		"	

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Note
Motor Oil (C16-C36)	2800	1500	ug/l	3	7C06034	03/06/07	03/09/07	EPA 8015B-SVOA	Q
Diesel Range Organics (C10-C28)	1900	150	"				Pió:	<u></u>	Q
Surrogate: n-Octacosane		146 %	30-	115	"	"	(10)	"	Z

Volatile Organic Compounds by EPA Method 8260B

TestAmerica - Morgan Hill, CA

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
tert-Amyl methyl ether	ND	0.50	ug/l	1	7C06006	03/06/07	03/06/07	EPA 8260B	
Benzene	ND	0.50		W.		II.	11	u u	
tert-Butyl alcohol	ND	12	tr	W.	•	11	11	11	
Di-isopropyl ether	ND	0.50	17	**		11	11	П	
1,2-Dibromoethane (EDB)	ND	0.50	11	**		O.	11	н	
1.2-Dichloroethane	ND	0.50	*11	•		U	II	n	
Ethanol	ND	100	**	*		11	n	"	
Ethyl tert-butyl ether	ND	0.50	п	**	19	11	н	"	
Ethylbenzene	ND	0.50	н	ü		71	н	II .	
Methyl tert-butyl ether	ND	0.50	н	n	300	11	II	**	
Toluene	ND	0.50	н	0.	3007	11	11	"	
Xylenes (total)	ND	0.50	н	u.	300	n:	11	и	
Surrogate: Dibromofluoromethane		95 %	75-	130	"	"	H	"	
Surrogate: 1,2-Dichloroethane-d4		101 %	60-	145	"	"		"	
		96 %	70-	130	"	"	TH.	"	
Surrogate: Toluene-d8 Surrogate: 4-Bromofluorobenzene		90%		120	.#.	"	и	"	





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0104 Reported: 03/09/07 16:35

Purgeable Hydrocarbons by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C07025 - EPA 5030B [P/T]										
Blank (7C07025-BLK1)				Prepared of	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	ND	25	ug/l							
Surrogate: 4-Bromofluorobenzene	80.7		"	80.0		101	75-125			
LCS (7C07025-BS1)				Prepared a	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	227	50	ug/l	275		83	60-115			
Surrogate: 4-Bromofluorobenzene	83.9		"	80.0		105	75-125			
Matrix Spike (7C07025-MS1)	So	urce: MQC01	71-01	Prepared a	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	240	50	ug/l	275	ND	87	60-115			
Surrogate: 4-Bromofluorobenzene	84.8		"	80.0		106	75-125			
Matrix Spike Dup (7C07025-MSD1)	So	arce: MQC01	71-01	Prepared a	& Analyze	ed: 03/07/	07			
Gasoline Range Organics (C4-C12)	229	50	ug/l	275	ND	83	60-115	5	20	
Surrogate: 4-Bromofluorobenzene	84.4			80.0		106	75-125			





Environmental Resolutions (Exxon) 601 North McDowell Blvd.

Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235
Project Manager: Paula Sime

MQC0104 Reported:

03/09/07 16:35

Extractable Hydrocarbons with Silica Gel cleanup by EPA 8015B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C06034 - EPA 3510C										
Blank (7C06034-BLK1)				Prepared:	03/06/07	Analyzed	l: 03/09/07			
Motor Oil (C16-C36)	ND	250	ug/l							
Diesel Range Organics (C10-C28)	37.9	25	н							
Surrogate: n-Octacosane	42.9		"	50.0		86	30-115			
LCS (7C06034-BS1)				Prepared:	03/06/07	Analyzed	: 03/07/07			
Diesel Range Organics (C10-C28)	353	50	ug/l	500		71	40-140			
Surrogate: n-Octacosane	42.6		#	50.0		85	30-115			
LCS Dup (7C06034-BSD1)				Prepared:	03/06/07	Analyzed	: 03/07/07			
Diesel Range Organics (C10-C28)	332	50	ug/l	500		66	40-140	6	35	
Surrogate: n-Octacosane	41.8			50.0		84	30-115			





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235

Project Number: 7-0235 Project Manager: Paula Sime MQC0104 **Reported:** 03/09/07 16:35

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C06006 - EPA 5030B P/T										
Blank (7C06006-BLK1)				Prepared	& Analyze	d: 03/06/	07			
tert-Amyl methyl ether	ND	0.30	ug/l							
Benzene	ND	0.25	11							
tert-Butyl alcohol	ND	10	"							
Di-isopropyl ether	ND	0.25	*							
1,2-Dibromoethane (EDB)	ND	0.25	ü							
1,2-Dichloroethane	ND	0.25	30							
Ethanol	ND	50	ïï							
Ethyl tert-butyl ether	ND	0.40	w.							
Ethylbenzene	ND	0.25	ж							
Methyl tert-butyl ether	ND	0.31	W.							
Toluene	0.35	0.25	<i>m</i>							
Xylenes (total)	0.41	0.38	W.							
Surrogate: Dibromofluoromethane	2.25		"	2.50		90	75-130			
Surrogate: 1,2-Dichloroethane-d4	2.41		"	2.50		96	60-145			
Surrogate: Toluene-d8	2.27		"	2.50		91	70-130			
Surrogate: 4-Bromofluorobenzene	2.13		и	2,50		85	60-120			
LCS (7C06006-BS1)				Prepared &	& Analyze					
tert-Amyl methyl ether	10.1	0.50	ug/l	10.0		101	65-135			
Benzene	9.11	0,50	tr.	10.0		91	70-125			
tert-Butyl alcohol	198	20	23442	200		99	60-135			
Di-isopropyl ether	8.92	0.50	100	10.0		89	70-130			
1,2-Dibromoethane (EDB)	11.0	0.50	300	10.0		110	75-140			
1,2-Dichloroethane	9.81	0.50	.0000	10.0		98	75-125			
Ethanol	203	100	(H)	200		102	15-150			
Ethyl tert-butyl ether	9.34	0.50	(30)	10.0		93	65-130			
Ethylbenzene	9.21	0.50	2,907	10.0		92	70-130			
Methyl tert-butyl ether	9.69	0.50		10.0		97	50-140			
Foluene	9.85	0.50	**	10.0		98	70-120			
Xylenes (total)	28.6	0.50		30.0		95	80-125			





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0104 Reported: 03/09/07 16:35

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Analyte	Result	Evaluation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 7C06006 - EPA 5030B P/T										
LCS (7C06006-BS1)				Prepared a	& Analyze	ed: 03/06/	07			
Surrogate: Dibromofluoromethane	2,26		ug/l	2.50		90	75-130			
Surrogate: 1,2-Dichloroethane-d4	2.28		"	2.50		91	60-145			
Surrogate: Toluene-d8	2.31		"	2.50 2.50		92 91	70-130 60-120			
Surrogate: 4-Bromofluorobenzene	2.27				0 4 4					
Matrix Spike (7C06006-MS1)		rce: MQC00		Prepared o			65-135			
tert-Amyl methyl ether	10.4	0.50	ug/l	10.0	ND	104				
Benzene	9.08	0.50	Ħ	10.0	ND	91	70-125			
tert-Butyl alcohol	202	20		200	17	92	60-135			
Di-isopropyl ether	9.16	0.50	п	10.0	ND	92	70-130			
1,2-Dibromoethane (EDB)	11.5	0.50	H	10.0	ND	115	75-140			
1,2-Dichloroethane	10.3	0.50	u	10.0	0.35	100	75-125			
Ethanol	180	100	11	200	ND	90	15-150			
Ethyl tert-butyl ether	9.78	0.50	TF.	10.0	ND	98	65-130			
Ethylbenzene	8,67	0.50	17	10.0	ND	87	70-130			
Methyl tert-butyl ether	11.2	0.50	11	10.0	1.0	102	50-140			
Toluene	9.63	0.50	11	10.0	ND	96	70-120			
Xylenes (total)	27.9	0.50	u	30.0	ND	93	80-125			
Surrogate: Dibromofluoromethane	2.42		ır	2,50		97	75-130			
Surrogate: 1,2-Dichloroethane-d4	2.47		"	2.50		99	60-145			
Surrogate: Toluene-d8	2.44		"	2.50		98	70-130			
Surrogate: 4-Bromofluorobenzene	2.36		"	2.50		94	60-120			
Matrix Spike Dup (7C06006-MSD1)		rce: MQC00		Prepared &						
tert-Amyl methyl ether	10.3	0.50	ug/l	10.0	ND	103	65-135	1	25	
Benzene	9.05	0.50	U	10.0	ND	90	70-125	0.3	15	
tert-Butyl alcohol	216	20	0	200	17	100	60-135	7	35	
Di-isopropyl ether	9.38	0.50	D	10.0	ND	94	70-130	2	35	
1,2-Dibromoethane (EDB)	11.5	0.50	п	10.0	ND	115	75-140	0	15	
1,2-Dichloroethane	10.2	0.50	***	10.0	0.35	98	75-125	1	20	
Ethanol	209	100	n	200	ND	104	15-150	15	35	
Ethyl tert-butyl ether	9.70	0.50	п	10.0	ND	97	65-130	0.8	35	





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954

Project: Exxon 7-0235

Project Number: 7-0235

Evaluation

Project Manager: Paula Sime

MQC0104 Reported: 03/09/07 16:35

RPD

%REC

Volatile Organic Compounds by EPA Method 8260B - Quality Control TestAmerica - Morgan Hill, CA

Spike

Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 7C06006 - EPA 5030B P/T										
Matrix Spike Dup (7C06006-MSD1)	Sour	ce: MQC0	092-04	Prepared	& Analyzo	ed: 03/06/	07			
Ethylbenzene	9.32	0.50	ug/l	10.0	ND	93	70-130	7	15	
Methyl tert-butyl ether	11.2	0.50	TF.	10.0	1.0	102	50-140	0	25	
Toluene	9.68	0.50		10.0	ND	97	70-120	0,5	15	
Xylenes (total)	28.4	0.50	**	30.0	ND	95	80-125	2	15	
Surrogate: Dibromofluoromethane	2.37		"	2.50		95	75-130			
Surrogate: 1,2-Dichloroethane-d4	2.43		"	2.50		97	60-145			
Surrogate: Toluene-d8	2.37		n	2.50		95	70-130			
Surrogate: 4-Bromofluorobenzene	2.41		u	2.50		96	60-120			





Environmental Resolutions (Exxon) 601 North McDowell Blvd. Petaluma CA, 94954 Project: Exxon 7-0235
Project Number: 7-0235
Project Manager: Paula Sime

MQC0104 Reported: 03/09/07 16:35

Notes and Definitions

ZX Due to sample matrix effects, the surrogate recovery was outside the acceptance limits.

Q1 Does not match typical pattern

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

																				-30 .	
Test/America	Cor	nsultant Name:					E	xxon	Mobil	Engi	ineer	Jen	nifer	Sedi	ache	ek				-	٦
INCORPORATED			601 North M					Tele	phon	e Nu	mber	(510) 54	7-81	96						
408-776-9600		City/State/Zip:	A Part of the part	alifornia 9	4954				A	ccou	nt #:	3876									٦
Morgan Hill Division	P	roject Manager	Paula Sime							F	0#:									10//	٦
885 Jarvis Drive	Telep	hone Number:	(707) 766-20	000					Fa	acility	ID#	702	35								٦
Morgan Hill, CA 95037	ER	RI Job Number:	222913X									T060		354							\dashv
ExconMobil.		er Name: (Print)	7		1 West	rup								graph	Aver	nue					
Shipping Method: Lab Courier		pler Signature:		Othe	4				City,	State	e Zip	Oakl	and, (Califor	rnia		200				
TAT	PROVIDE:	Special Instruc	-					1	N4-1-1-	71. U.S	-	-								-	4
24 hour	EDF Report	7 CA Oxys =	MTBE, TE	A, TAME	, ETBE, I	DIPE, 1,2-D	CA, EDB.		Matrix		-				Ana	alyze	For:			_	-
☐ 48 hour ☐ 96 hour	LD: Report	Use silica ge Set TBA dete	I cleanup f	or all TPF	d analys	es.					15B	5B	TPH motor oll 8015B	98	809	60B					
■8 day MQC0104	···	ZY HOU	R TUR	N AR	DUND						8015B	8015B	otor ol	826	xys 82	lol 82					
Sample ID / Descripti	ion	DATE	TIME	COMP	GRAB	PRESERV (VOA/liter)	NUMBER	Water	Soil	Vapor	TPHd	ТРН	TPH m	BTEX 8260B	7 CA Oxys 8260B	Ethanol 8260B			1		
Boring # / W-Sample Depth	1-Boring#					HCL/none	8 VOAs/ 2 AMBs												\top	+	٦
B8 W-14-BS	۱۵ <u>ک</u>	3/2/07	13:10		::XII		2711100	х			x	Х	~	v	~	\ \			+	+	\dashv
		177											X	X	X	Х		\vdash	+	-	\dashv
								Х			X	X	Х	X	X		-	\vdash	+	-	4
	A La la combinación de la comb					-		Х			X	X	Х	X	X	Х		\vdash	4		4
					<u></u>	-		X			X	X	Х	Х	X	Х		\vdash	_		_
		-						X			Х	Х	Х	Х	X	X					
	er							Х			X	Х	Х	х	Х	Х					
								х			х	х	х	х	х	x					
	(tentale and tentale and tenta				******			х			x	х	х	х	х	x					٦
	****							x			х	х	х	х	Х	х				\top	٦
			- XXXIII III III			2		x			Х	х	х	Х	х				十	\top	٦
						1/.										À			7		٦
Relinquished by:	Date 3/2	107	Time 16:	20	Received b	y. Shinis	Exert,)	3/5	Time	127	5		orator					Li	70C	1
Relinquished by: Ario M	Date 3/5	1	Time (91	5	Received b	y TestAmerica	Queli.			•		5-07		Samp	ole Co	ontain	oon Re ers In leadsp		7.	1 (
		l	20000				Trois of	100	relative		- 1	-	-	-	2,56	200		0.515.c/			_

TEST AMERICA SAMPLE RECEIPT LOG

CLIENT NAME: REC. BY (PRINT) WORKORDER:	ERT A.M. MQC01034 9-31610		DATE REC'D AT LAB: TIME REC'D AT LAB: DATE LOGGED IN:	3-5-0 19:15 31410				For Regula DRINKING WASTE WA	
	OPRIATE RESPONSE	LAB SAMPLE#	CLIENT ID	CONTAINER DESCRIPTION	PRESER	рН	SAMPLE		REMARKS:
1. Custody Seal(s)	Present / Absent		BB W-14-88	6UCA	Hei		700	3-2-07	CONDITION (ETC.)
2 Ch-1- 10 1 1	Intact / Broken*		√	1(L) Amber	-		T	3201	
2. Chain-of-Custody	Present / Absent*								
Traffic Reports or Packing List:	Present / Absent								
4. Airbill:	Airbill / Sticker Present / Absept		η.		·				/
5. Airbill #:	1 TOSCHI / GOSEIX		7						
6. Sample Labels:	Present / Absent			^			0.00		
7. Sample IDs:	Listed / Not Listed on Chain-of-Custody								
8. Sample Condition:	Intact / Broken* / Leaking*					\neq			
Does information on traffic reports and sagree?	chain-of-custody,			1.61					
Sample received within hold time?	in			21					
11. Adequate sample volu received?	Yes No*		3						
12. Proper preservatives u	used? (Fes / No*								
 Trip Blank / Temp Blad (circle which, if yes) 	nk Received? Yes (No)					-		İ	
 Read Temp: Corrected Temp: Is corrected temp 4 +/ 	4.7°C 4.7°C 1-2°C7 (@1 No**								
(Acceptance range for samples re **Exception (if any):-MET or Problem COC	quiring thermal pres.) ALS / DFF ON ICE								

ATTACHMENT F MORROW SURVEYING REPORT

