#### **DEPARTMENT OF TRANSPORTATION**

BOX 23660 OAKLAND, CA 94623-0660 (510) 286-4444 TDD (510) 286-4454

January 17, 2001

# 2933

Mr. Barney Chan Alameda County Department of Health Services 1131 Harborway Parkway Alameda, California 94502

Subject: Ground Water Monitoring Report for the Fourth Quarter of 2000 at the South Oakland Maintenance Station located at 1112 29<sup>th</sup> Avenue in Oakland, Alameda County, California

Dear Mr. Chan:

Attached is a copy of Professional Services Industries, Inc. "Fourth Quarter 2000 Ground Water Monitoring Report" dated January 9, 2001 for work performed at the above-referenced site. Results of the cumulative sampling and analysis indicate that benzene and Methyl-tert-Butyl-Ether (MtBE) may have migrated down gradient from the former underground storage tank location.

As we discussed, we are preparing a Work Plan for a site investigation to install an additional monitoring well down gradient and off-site to the Caltrans property to define the lateral and vertical extent of the dissolved gasoline constituents in the ground water.

Currently, we are working to obtain a temporary construction easement from the property owners of All Aboard Mini Storage. Also, Mr Steven Ronzone, the contact for the old Del Monte property, has stated that the industrial well identified in our Well Survey Report was located near the current Pep Boys store and was destroyed. Finally, we will continue to sample the wells on a quarterly basis unless otherwise instructed by your office.



If you have any questions or require additional information, please contact Ms. Frances Maroni of my staff at (510) 286-5657.

Sincerely,

HARRY Y. YAHATA District Director

j.

RAY BOYER

District Branch Chief

Office of Environmental Engineering

Attachment

cc: Regional Water Quality Control Board, SF Bay Region, File

## FOUTH QUARTER 2000 GROUNDWATER MONITORING REPORT

TASK ORDER NUMBER 04-987901-WF CONTRACT NUMBER 43A0012

SOUTH OAKLAND MAINTENANCE STATION 1112 29th AVENUE OAKLAND, CALIFORNIA

1-9-01

Prepared for

CALIFORNIA DEPARTMENT OF TRANSPORTATION
District 4
P.O. Box 23660
Oakland, California

Prepared by

Professional Service Industries 1320 West Winton Avenue Hayward, California 94545 (510) 785-1111

> January 9, 2001 575-0G019

# **TABLE OF CONTENTS**

STATEMENT	OF LIMITATIONS AND PROFESSIONAL CERTIFICATION	i
1.0 INTRODU 1.1 SIT	JCTION TE DESCRIPTION AND HISTORY	1
2.1 GR 2.2 GR	WATER MONITORING ACTIVITIES	3 3
2.3 LAI 2.4 COI	BORATORY ANALYSIS AND RESULTS	4
3.0 SUMMAR	RY AND CONCLUSIONS	6
FIGURES		
	SITE LOCATION GROUNDWATER ELEVATION MAP	
<u>TABLES</u>		
	SUMMARY OF GROUNDWATER ELEVATION DATA SUMMARY OF GROUNDWATER ANALYTICAL DATA	

## **APPENDICES**

APPENDIX A: GROUNDWATER PURGE LOGS

APPENDIX B: LABORATORY REPORTS AND CHAIN-OF-CUSTODY FORMS

# STATEMENT OF LIMITATIONS AND PROFESSIONAL CERTIFICATIONS

Information provided in Professional Services Industries, Inc., (PSI) report number 575-0G019 is intended exclusively for the California Department of Transportation (Caltrans) for the evaluation of groundwater contamination as it pertains to the subject site. PSI is responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official view or policies of the State of California or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation. The professional services provided have been performed in accordance with practices generally accepted by other geologists, hydrologists, hydrogeologists, engineers, and environmental scientists practicing in this field. No other warranty, either expressed or implied, is made. As with all subsurface investigations, there is no guarantee that the work conducted will identify any or all sources or locations of contamination.

This report is issued with the understanding that Caltrans is responsible for ensuring that the information contained in this report is brought to the attention of the appropriate regulatory agency. This report has been reviewed by a geologist who is registered in the State of California and whose signature and license number appear below.

Frank R. Poss

Senior Hydrogeologist

Jeffrey Friedman, R.G. (5677)

Senior Project Geologist



#### 1.0 INTRODUCTION

This report summarizes the results of the Fourth Quarter 2000 groundwater monitoring activities conducted on November 28, 2000 at the South Oakland Maintenance Yard located in Oakland, California. The subject site location is presented on Figure 1. The purpose of this project is to comply with quarterly sampling requirements for Alameda County Department of Environmental Health. The work was conducted under Contract 43A0012 and Task Order Number 04-987901-WF.

#### 1.1 SITE DESCRIPTION AND HISTORY

The site is currently used as a maintenance station by Caltrans. The maintenance station includes offices, a repair shop, a sign shop, and several material storage bins. The entire property covers approximately two acres. The site is paved with asphalt and is relatively flat. The Alameda/Oakland Estuary is approximately 0.5 miles southwest of the site.

One 4,000-gallon diesel underground storage tank (UST) and one 2,000-gallon gasoline UST were removed from the site on March 11, 1997. The tank pit was over-excavated and soil samples were collected. Sidewall and bottom samples collected from the excavation contained concentrations of Total Petroleum Hydrocarbons as Gasoline (TPH-G, [as high as 380 milligrams per kilogram (mg/kg)]), and Total Petroleum Hydrocarbons as Diesel (TPH-D, [as high as 21 mg/kg]). Concentrations of Benzene, Toluene, Ethylbenzene, and Total Xylenes (BTEX), ranged from 0.010 to 48 mg/kg. Methyl Tertiary Butyl Ether (MTBE) concentrations ranged from 0.041 to 9.15 mg/kg. Groundwater samples were not collected (Caltrans, 1999).

On April 6 and 7, 1999, Borings B1 through B6 were drilled at the site. The boring locations are presented in Figure 2. All of the borings were converted to 1.3-centimeter (cm) (0.5-inch) inside diameter temporary groundwater monitoring wells. Soil samples were collected from each boring at depths of 1.52, 3, and 4.56 meters (5, 10, and 15 feet) below ground surface (bgs).

Soil samples were analyzed for TPH-G, TPH-D, and Volatile Organic Compounds (VOCs), by EPA Method 8260. TPH-G was detected in one soil sample (B6-10 [13 mg/kg]). None of the soil samples contained detectable concentrations of TPH-D. MTBE was the only VOC detected in the soil samples analyzed. MTBE was detected in the sample B5-1.5 meters (0.16 mg/kg). No other soil sample contained a detectable concentration of MTBE (PSI, 1999).

TPH-G was detected in groundwater samples from temporary Wells B3 (520  $\mu$ g/l) and B4 (520  $\mu$ g/l). No other groundwater samples contained detectable concentrations of TPH-G. No TPH-D was detected in any of the groundwater samples. Benzene was detected in the water sample from Well WB3 (6.3  $\mu$ g/l). MTBE was detected in the

samples from Well WB5 (6,600  $\mu$ g/I) and WB6 (24  $\mu$ g/I). Concentrations of other gasoline related compounds were detected in samples from Wells WB1, WB3, WB4, and WB5. Chloroform was detected in water samples from Wells WB4 (2.4  $\mu$ g/I) and WB6 (2.7  $\mu$ g/I). Tetrachloroethene (synonym Perchloroethene [PCE]) was detected in the water sample from Well WB6 (12  $\mu$ g/I) (PSI, 1999).

On August 13, 1999, Borings B7 through B9 were drilled at the site (Figure 2). The borings were drilled on the property boundary. The results of the sampling indicated the following:

- TPH-G concentrations were detected in one soil sample [B9-15 (0.54 mg/kg)] at the site.
- TPH-D was detected in one groundwater sample [WB7 (0.73 mg/l)]
- MTBE was detected in grab groundwater samples WB7 (5,600 µg/l) and WB8 (9.0 µg/l). The downgradient extent of MTBE has not been established.

In June and July 2000, PSI completed a supplemental investigation, which included the installation of four monitoring wells at the site. The conclusions and recommendations of the investigation follows:

- None of the soil samples contained detectable concentrations of TPH-G, while TPH-D
  was detected in two soil samples at concentrations below regulatory concern.
- None of the soil samples contained detectable concentrations of VOCs with the exception of MTBE. The highest MTBE concentration detected was 0.52 mg/kg in soil sample B3-10. All of the MTBE concentrations detected were below first groundwater.
- None of the groundwater samples contained detectable concentrations of TPH-D, while TPH-G was detected in two groundwater samples at a maximum concentration of 2.7 mg/l.
- Numerous VOCs were detected in the groundwater with only benzene and MTBE being at concentrations greater than the State of California Primary Drinking Water Standard (PDWS) or Secondary Drinking Water Standard (SDWS). Based on the concentrations detected, MTBE appears to be the primary contaminant of concern (COC). The lateral extent of MTBE has not been defined.
- The report recommended continued groundwater monitoring and the installation of additional monitoring wells down gradient of monitoring well MW-3. Additionally, as TPH-D was not detected in the groundwater sample from monitoring well MW-3, the report recommended that the analyses for TPH-D in this well be eliminated.

## 2.0 GROUNDWATER MONITORING ACTIVITIES

## 2.1 GROUNDWATER ELEVATION AND HYDRAULIC GRADIENT

On November 28, 2000, static groundwater elevations were measured in wells MW-1 through MW-4 (Figure 2). The groundwater depths were measured using a groundwater interface probe. The average depth the groundwater increased approximately 0.015 meters (0.05 feet) compared to last quarter. A summary of the depth to groundwater data collected during this monitoring event and previous monitoring events is presented in Table 1. Based on the groundwater data, the inferred groundwater flow direction beneath the site is to the west (Figure 2) with a hydraulic gradient of 0.014.

#### 2.2 GROUNDWATER SAMPLING

Groundwater samples were collected from monitoring wells MW-1 through MW-4. Prior to the collection of groundwater samples, the monitoring wells were purged of a minimum of three well volumes of water until pH, conductivity, and temperature stabilized. The wells were allowed to recover to at least 80 percent of their original static groundwater levels prior to sampling.

The following procedures for well monitoring, well purging, and water sampling were implemented while sampling the wells:

- 1. All equipment was washed prior to entering the well with an Alconox solution, followed by two tap water rinses and a deionized water rinse.
- 2. Prior to purging the wells, depth-to-water was measured using an Solinst groundwater interface probe to an accuracy of approximately 0.01 foot. The measurements were made to the top of the well casing on the north side.
- 3. Monitoring wells at the site were prepared for sampling by purging the well of approximately 3 well volumes of water using disposable Teflon bailers.
- 4. Water samples were collected with a single-use Teflon bailer after the well had been purged and water in the well had equilibrated to approximately 80 percent of the static water level. The water collected was immediately decanted into laboratory-supplied vials and bottles. The containers were overfilled, capped, labeled, and placed in a chilled cooler prior to delivery to the laboratory for analysis.

- 5. Chain-of-custody procedures, including chain-of-custody forms, were used to document water sample handling and transport from collection to delivery to the laboratory for analyses.
- 6. Groundwater samples were delivered to the State-certified hazardous waste laboratory within approximately 48-hours of collection.
- 7. Purged water was contained in a DOT approved 55-gallon drum. The drum was labeled with the contents, date, well number, client name, and project number.

The groundwater monitoring purge logs are presented in Appendix A.

#### 2.3 LABORATORY ANALYSIS AND RESULTS

The groundwater samples were submitted for analyses to Centrum Analytical of Redlands, California, a State of California certified hazardous waste analytical laboratory. The samples were analyzed for the following:

- EPA 8015 modified TPH-G;
- EPA 8260 Volatile Organic Compounds (VOCs).

A summary of the laboratory results for groundwater samples is presented in Table 2. A copy of the laboratory reports and chain of custody records are presented in Appendix B. The following are the results of the groundwater sampling:

• TPH-G was detected in the groundwater samples collected from monitoring well MW-1 (1.7 mg/l). TPH-G concentrations have declined since the previous sampling results.

Numerous VOCs were detected in the groundwater samples with the highest concentrations detected in the groundwater sample collected from monitoring well MW-3. The compounds detected are common constituents of gasoline. The compound with the highest concentration was MTBE at 2,500 micrograms per liter (µg/l). MTBE concentrations are generally consistent with concentrations detected in the previous sampling event.

## 2.4 COMPARISON OF GROUNDWATER RESULTS WITH REGULATORY CRITERIA

The concentrations of contaminants reported by the analytical laboratory were compared to PDWS or SDWS. The following samples were above their respective PDWS or SDWS.

- Benzene concentrations detected in groundwater samples MW-1 (3.6  $\mu$ g/l) and MW-3 (27  $\mu$ g/l).
- MTBE concentrations detected in groundwater samples MW-1 (610 μg/l), MW-2 (130 μg/l), and MW-3 (2,500 μg/l).


Based on the concentrations detected in the groundwater at the site, the primary COC is MTBE. The concentrations of MTBE in each of the monitoring wells are shown in Figure 3. This figure indicates that the highest concentrations of MTBE were encountered in the groundwater samples collected in the monitoring well (MW-3) directly down gradient of the former USTs and in the well adjacent (MW-1) to the former USTs. Based on the data obtained, the lateral extent of MTBE impacted groundwater has not been defined.


#### 3.0 SUMMARY AND CONCLUSIONS

PSI performed a quarterly monitoring event on November 28, 2000. Groundwater samples were collected from monitoring wells MW-1 through MW-4. Based on measurements collected and analytical data the following conclusions are provided. Groundwater elevation data indicates the groundwater flow direction beneath the site is towards the west, with a hydraulic gradient of 0.014 meter per meter (0.014 foot per foot).

- TPH-G was detected in the groundwater samples collected from monitoring well MW-1 (1.7 mg/l).
- Numerous VOCs were detected in the groundwater samples from the site. However, only benzene and MTBE were detected in concentrations greater than the PDWS. Based on the concentrations detected in the groundwater at the site, the primary appears to be COC is MTBE.

Based on the results of this report, PSI recommends continued groundwater monitoring and the installation of additional monitoring wells down gradient of monitoring well MW-2 and MW-3.





LEGEND

 $MW-1 \boxtimes GROUNDWATER MONITORING WELL (ELEV IN FT. MSL)$ 

(89 95) 89.20

GROUNDWATER ISO-ELEVATION CONTOUR (ELEV IN FT MSL)

APPROXIMATE SCALE




GROUNDWATER ELEVATION MAP (11/28/00)
CALTRANS MAINTENANCE STATION
1112 29TH AVENUE, OAKLAND, CALIFORNIA
PROJECT NUMBER: 575-00019

DATE: 12/11/00 FILE NO: 0G019-5

CKD BY: FIGURE NO.: 2

DRAWN BY B. BURFIELD



APPROXIMATE SCALE

FILE NO: 00019-6

DRAWN BY: B. BURFIELD

GROUNDWATER ELEVATION
SOUTH OAKLAND MAINTENANCE STATION

SOUTH OAKLAND, CALIFORNIA

Sample Location	Date	Temperature (°C)	Conductivity (mS/cm)	рН	TOC Elevation (feet msl)*	Depth To Groundwater	Groundwater Elevation (feet msl)*
MW-1	6/27/00				99.57	9.13	90.44
	9/11/00	20.8	514	6.33	99.57	9.52	90.05
	11/28/00	20.2	491	6.98	99.57	9.62	89.95
MW-2	6/27/00	( <del>1777.</del> )		==	98.91	9.05	89.86
	9/11/00	19.6	575	6.58	98.91	9.95	88.96
	11/28/00	19.1	571	7.11	98.91	9.94	88.97
MW-3	6/27/00		***	***	98.98	8.76	90.22
	9/11/00	20.5	563	6.70	98.98	9.28	89.70
	11/28/00	19.2	571	6.65	98.98	9.36	89.62
MW-4	6/27/00	:575%	5555		99.04	8.74	90.30
	9/11/00	20.7	456	6.54	99.04	9.30	89.74
	11/28/00	20	446	6.61	99.04	9.32	89.72

#### Notes:

All measurements are recorded in feet.

Feet msl = feet above mean sea level

<sup>\*</sup> TOC Measurements are from data supplied by Meridian Surveying

TABLE 2

## ANALYTICAL RESULTS FOR GROUNDWATER SAMPLES SOUTH OAKLAND MAINTENANCE STATION SOUTH OAKLAND, CALIFORNIA

Sample I.D.	Date	TPH-G mg/l	TPH-D mg/l	MTBE µg/l	tert- Butanol (TBA) ug/l	tert-Amyl Methyl Ether (TAME) ug/l	Benzene µg/l	Toluene µg/l	Ethyl- benzene µg/l	Total Xylenes µg/l
MW-1	6/27/00	0.85		880	<50	<5	20	<1.0	<1.0	19
	9/11/00	0.92		860	190	<5	14	<1.0	1.6	3.6
	11/28/00	<0.5		610	<250	<25	3.6	<2.5	<2.5	<7.5
MW-2	6/27/00	<0.5	2555	86	<50	<5	<1.0	<1.0	<1.0	<3.0
	9/11/00	<0.5		110	<50	<5	<1.0	<1.0	<1.0	<3.0
	11/28/00	<0.5		130	<50	<5	<1.0	<1.0	<1.0	<3.0
MW-3	6/27/00	2.7	<0.4	5,000	1,500	11	73	1.7	1.2	4.6
	9/11/00	1.9		2,700	310	10	19	<1.0	<1.0	<3.0
	11/28/00	1.7		2,500	<1,000	<100	27	92	<10	<30
MW-4	6/27/00	<0.5	***	18	<50	<5	<1.0	<1.0	<1.0	<3.0
	9/11/00	<0.5		<1.0	<50	<5	<1.0	<1.0	<1.0	<3.0
	11/28/00	<0.5	-	<1.0	<50	<5	<0.5	<0.5	<0.5	<1.5

#### NOTES:

TPH-D = Total Petroleum Hydrocarbons as Diesel by EPA Method 8015M.

TPH-G = Total Petroleum Hydrocarbons as Gasoline by EPA Method 8015M.

MTBE = Methyl Tertiary Butyl Ether

mg/l = milligrams per liter

ug/l = mlcrograms per liter

C-0-2-20-200 c-2-00-0

# **APPENDIX A**

**GROUNDWATER PURGE LOGS** 

		FLUI	D MEAS	JREMENT	FIELD D	ATA		
							SHEET: \	OF 1
DATE: 1 1 - "		PROJECT NAME:	Chireans	S. OAKLAND		PROJECT NO:	06019	
DATE: 11 24	MEASUREMENT INS		LINST	Si Dijectiko	· · · · · · · · · · · · · · · · · · ·	SERIAL NO:		
	CTION INSTRUMEN		1001			SERIAL NO:		
EQUIP. DECON:			DEION 1 RINSE	☐ ISOPROPANOL	☐ ANALYTE	FREE FINAL RINSE	☐ TAP WATER F	INAL RINSE
TAP WA	<del>_</del>	LIQUINOX WASH	DIST/DEIC		OTHER SOLVENT	☐ DIST/DEION	FINAL RINSE	☐ AIR DRY
WELL	GROUND	TOP OF	DEPTH TO	DEPTH TO	WELL	PRODUCT	WATER	ACTUAL
NUMBER	SURFACE ELEVATION	CASING ELEVATION	PRODUCT BELOW TOC	WATER BELOW TOC	DEPTH BELOW TOC	THICKNESS	TABLE ELEVATION	TIME
MM-1		-		9,62	25.18			0830
MW-2				9,94	19.47			0839_
MW-3				9.36	20.20			0840
MM-A				9.32	24,37			0842
אייו -								
<u> </u>								
<u> </u>								
	<u> </u>							
			·					
· · · · · · · · · · · · · · · · · · ·								
	<u> </u>							
						-		
REMEMBER TO C	CORRECT PRODUCT	THICKNESS FOR DE	NSITY BEFORE CAL	LCULATING WATER	TABLE ELEVATION	PREPARED BY:	CHRIS MECK	ĮTT

							WELL NO	D: MW-1	
DATE: ///	28/00	PROJECT	NAME: 🕖	ALTRAN-	5. OA	KLAND	PROJEC	TNO: 06019	
WEATHER	CONDITIO	DNS: 5	INNY,	200L					
WELL DIA	METER (IN	.)	□ 1	2	□ 4	□ 6	OTHER		
SAMPLE T	YPE:	GROUND	WATER	☐ WAST	EWATER	SURF	ACE WATE	R OTHER	
WELL DEF	тн (тос)	2	5.18	FT.	DEPTH -	TO WATER	BEFORE F	PURGING (TOC) 9,62 FT.	
LENGTH C	F WATER	/	5.56	FT.	CALCUL	ATED ONE	WELL VOL	UME1: 2.64 GAL.	
PURGING	DEVICE:				DEDIC	ATED T	DISPOSA	BLE DECONTAMINATED	
_	SAMPLING DEVICE:   Dedicated   Decontaminated								
EQUIP. DE			P WATER V		=	ISOPROPA		ANALYTE FREE FINAL RINSE	
_	CONOX WA LUINOX WA		<u> </u>	ION 1 RINSE ION 2 RINSE			LVENT [_] R FINAL RIN	DIST/DEION FINAL RINSE	
		RVATION:		PRESERVE				AGE MINDRI	
			_	MYRO	_				
				11/120	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				
ACTUAL TIME	CUMUL. VOLUME	TEMP □ °F	SPECIFIC CONDUCT.	pΗ	DISS. CXYGEN	TURBIDITY (NTUs)	WATER APPEAR	REMARKS (EVIDENT ODOR, COLOR, PID)	
(MIN)	PURGED		0000			(11.00)	CL=CLEAR		
	(GAL)		,				CO=CLOUDY TU=TURBID		
5090	INITIAL	20.2	635	7.22					
0190	30	20.2	492	7.08					
0920	6.0	20.2	496	7.03					
0925	9.0	20.2	491	6.98					
					- <u> </u>				
			<u>-</u>						
į									
					,				
DEPTH T	O WATER	AFTER PL	RGING (T	OC)	FT.	SAMPLE F	LTERED	YES NO SIZE	
NOTES:			<del>-</del>		SAMPLE 1	TIME:	925	ID# Mルー	
					DUPLICA	re 🗌	TIME:	ID#:	
					EQUIP. BI	ANK:	TIME:	ID#:	
	-				PREPARE	D BY:			

A 1 FOOT LENGTH OF WATER = 0.05 GAL IN 1" DIA, PIPE | 0.17 GAL IN 2" DIA PIPE | 0.65 GAL IN 4" DIA PIPE | 1.5 GAL IN 6" DIA PIPE

							WELL NO	D: MW-Z		
DATE: ///	28/00	PROJECT	NAME: /	ALTRANS	S.OAK	LAND	PROJEC	TNO: 06019		
WEATHER	CONDITIO	ONS: SO	UNNY, C	100L						
WELL DIA	METER (IN	1.)	□ 1	2	<b>4</b>	□ 6	OTHER			
SAMPLE T	YPE:	GROUND	OWATER	☐ wast	EWATER	SURF	ACE WATE	R OTHER		
WELL DEF	тн (тос)	/	9,47	FT.	DEPTH '	TO WATER	BEFORE F	PURGING (TOC) 4,94 FT		
LENGTH C	F WATER	9.	153	FT.			WELL VOI			
PURGING	DEVICE:				☐ DEDIC	ATED T	DISPOSAL	BLE DECONTAMINATED		
SAMPLING	SAMPLING DEVICE: DEDICATED DISPOSABLE DECONTAMINATED									
EQUIP. DE			P WATER V		=	ISOPROPA		ANALYTE FREE FINAL RINSE		
_	CONOX WA		=	ION 1 RINSE				DIST/DEION FINAL RINSE		
		RVATION:	==	PRESERVE			R FINAL RIN	ISE LAIR DRY		
				: MYRON						
				7772010	, E 602	/J _				
ACTUAL TIME (MIN)	CUMUL. VOLUME PURGED (GAL)	TEMP	SPECIFIC CONDUCT.	рН .	DISS. OXYGEN	TURBIDITY (NTUs)	WATER APPEAR CL=CLEAR CO=CLOUDY TU=TURBID	REMARKS (EVIDENT ODOR, COLOR, PID)		
0956	INITIAL	18.9	557	7.40			10-10000			
10.00	1,75	19.0	564	7-11						
1004	3.50	19,0	570	7-12						
1006		19.1	571	7.11			,			
-			<u> </u>							
		1	<del>-</del>		<del>.</del>					
		<del>                                     </del>								
	.,									
ļ		<del> </del>	<del>                                     </del>							
<del> </del>	<u> </u>	<del>                                     </del>	<del>                                     </del>				-			
		<del>                                     </del>	+			<del> </del>	-			
<b>ДЕРТН Т</b>	L O WATER	AFTER PL	JRGING (TO	<u> </u>	FT,	SAMPLE F	FILTERED	YES NO SIZE		
NOTES:		· · · · · · · · · · · · · · · · · · ·			SAMPLE 7	<u> </u>	1010	1D# MW-2		
					DUPLICAT		TIME:	ID#:		
}					EQUIP. BL		TIME:	ID#:		
					PREPARE	D BY:	<del></del> -			

A 1 FOOT LENGTH OF WATER = 0.05 GAL IN 1" DIA, PIPE 0.17 GAL IN 2" DIA PIPE 0.65 GAL IN 4" DIA PIPE 1.5 GAL IN 6" DIA PIPE

							WELL NO	D: MW-3
DATE: //				ALTRAN	5 5.014	KLANO	PROJEC	TNO: 06019
WEATHER			UNNY					
WELL DIA	METER (IN	.)	□ 1	2	4	□ 6	OTHER	
SAMPLE T	YPE:	GROUN	OWATER	WAST	EWATER	SURF	ACE WATE	R OTHER
WELL DEF	тн (тос)	2	0.20	FT.	DEPTH	TO WATER	BEFORE P	PURGING (TOC) 9.36 FT.
LENGTH (	OF WATER		0.84	FT.	CALCUL	ATED ONE	WELL VOL	LUME1: 1.84 GAL.
PURGING	DEVICE:		-· ·		DEDIC	ATED	DISPOSAE	BLE DECONTAMINATED
SAMPLING	G DEVICE:				DEDIC	ATED	DISPOSA	BLE DECONTAMINATED
CONTAIN	CONOX WA QUINOX WA ER PRESE	ASH [ SH [ RVATION:	DIST/DE	ION 1 RINSE ION 2 RINSE PRESERVEI		TAP WATE	LVENT  R FINAL RIN	ANALYTE FREE FINAL RINSE DIST/DEION FINAL RINSE ISE AIR DRY
WATER A	NALYZER	MODEL &	SERIAL NO	: MYROP	v 2 602	155		
ACTUAL TIME (MIN)	CUMUL. VOLUME PURGED (GAL)	TEMP	SPECIFIC CONDUCT.	PHq -	DISS. OXYGEN	TURBIDITY (NTUs)	WATER APPEAR CL=CLEAR CO=CLOUDY TU=TURBID	REMARKS (EVIDENT ODOR, COLOR, PID)
1020	INITIAL	18.8	527	7,25			CL-STRAT	
1023	2.0	19.2	541	6.466			Co	
1028	4.0	19.2	566	6.65			00	
1034	6.0	19.2	571	6.65			C 0	
					· · · · · · · · · · · · · · · · · · ·			
<u></u>	<u> </u>							
ļ					<u> </u>	<u> </u>		3 ,3
							<u> </u>	
					<u> </u>	-		
	<u> </u>	1	ln and		<u> </u>		<u> </u>	
	U WATER	AFTER PL	JRGING (To	JC)	FT.		·-·	YES NO SIZE
NOTES:					SAMPLE		10 35	1D# MW-3
					DUPLICA EQUIP. BI		TIME:	1D#:
L	<del></del>	<u> </u>	-		PREPARE		TIME:	ωπ.

<sup>1</sup>A 1 FOOT LENGTH OF WATER = 0.05 GAL IN 1" DIA, PIPE 0.17 GAL IN 2" DIA PIPE 0.65 GAL IN 4" DIA PIPE 1.5 GAL IN 6" DIA PIPE

					,			): MW-	4	
DATE: //	28.100	PROJECT	NAME: 6	ALTRAN	15 5.01	AKLANO	PROJEC	TNO: O	5019	
	CONDITIO						·			
WELL DIA	METER (IN	.)	□ 1	<b>1</b> 2	4	☐ 6	OTHER			
SAMPLE T	YPE:	GROUND	WATER	☐ wast	EWATER	SURF	ACE WATER	₹ ∏отн	ER	
WELL DEF	тн (тос)	24	.37	FT.	DEPTH :	TO WATER	BEFORE P	URGING (TO	OC) <i>9,32</i> FT.	
LENGTH C	F WATER	/.	5.05	FT.	CALCUL	ATED ONE	WELL VOL	.UME¹: Z	7.55 GAL.	
PURGING	DEVICE:				DEDIC	ATED 👼	DISPOSAE	BLE DEC	ONTAMINATED	
SAMPLING	SAMPLING DEVICE: DEDICATED TO DISPOSABLE DECONTAMINATED									
I '	EQUIP. DECON. TAP WATER WASH ISOPROPANOL ANALYTE FREE FINAL RINSE									
1 =	☐ ALCONOX WASH ☐ DIST/DEION 1 RINSE ☐ OTHER SOLVENT ☐ DIST/DEION FINAL RINSE ☐ AIR DRY									
	UINOX WA			ION 2 RINSI PRESERVE				ISE LA	IR DRY	
1			_	: MYRO						
				111/20	~ 2 60.	2133				
ACTUAL TIME (MIN)	CUMUL. VOLUME PURGED (GAL)	TEMP □ *F □ *C	SPECIFIC CONDUCT.	Ηα	DISS. OXYGEN	TÜRBIDITY (NTUs)	WATER APPEAR CL=CLEAR CO=CLOUDY TU=TURBID		EMARKS DDOR, COLOR, PID)	
1049	INITIAL	19.2	450	6.73			CL-STRI	17		
1058	26	19.5	44%	6.70						
1102	5.0	19.6	446					<del> </del>		
8011	73	20.0	446	6.61						
					_					
								-		
							-			
						١.				
								-		
						:				
		<u> </u>		<u> </u>		<u> </u>				
DEPTH T	O WATER	AFTER PL	JRGING (T	OC)	FT.	SAMPLE I	FILTERED	YES	NO SIZE	
NOTES:	<u>.</u>				SAMPLE	ΓΙΜΕ: \t	10	ID#	MW - 4	
					DUPLICAT	TE 🔲	TIME:	ID#:		
	EQUIP. BLANK: TIME: ID#:									
	PREPARED BY:									

<sup>1</sup> A 1 FOOT LENGTH OF WATER = 0.05 GAL IN 1" DIA PIPE 0.17 GAL IN 2" DIA PIPE 0.05 GAL IN 4" DIA PIPE 1.5 GAL IN 6" DIA PIPE

# **APPENDIX B**

LABORATORY REPORTS AND CHAIN-OF-CUSTODY FORMS

# Centrum Analytical Laboratories, Inc.

CERTIFIED HAZARDOUS WASTE TESTING LABORATORY • CHEMICAL AND BIOLOGICAL ANALYSES

Client:

**PSI** 

1320 W. Winton Avenue Hayward, CA 94545

Date Received:

11/28/00

11/29/00

Job Number:

Date Sampled:

17524

Project: CALTRANS S. OAKLAN

#### CASE NARRATIVE

The following information applies to samples which were received on 11/29/00:

The samples were received at the laboratory chilled and sample containers were intact.

Unless otherwise noted below, the Quality Control acceptance criteria were met for all samples for every analysis requested.

Robert R. Clark, Ph.D. Laboratory Director

**ELAP # 2419** 

DL: Detection Limit - The lowest level at which the compound can reliably be detected under normal laboratory conditions.

ND: Not Detected - The compound was analyzed for but was not found to be present at or above the detection limit.

NA: Not Analyzed -- Per client request, this analyte was not on the list of compounds to be analyzed for.



# Modified 8015 - Total Volatile Hydrocarbons as Gasoline

Client:

PSI

Project:

Job No.:

17524 Water

CP

Matrix: Analyst: CALTRANS S. OAKLAN

Date Sampled: Date Received: 11/28/00 11/29/00

Date Analyzed:

11/30-12/1/00

Batch Number:

8015GW2778

	Detection	Petroleum Hydrocarbons as	
	Limit	Gasoline	
Sample ID	mg/L	mg/L	
Method Blank	0:5	ND	
MW-1	0.5	ND	
MW-2	0.5	ND	
MW-3	0.5	1.7	
MW-4	0.5	ND	
			- 
			900000000000000000 <u>(</u>
	en e		
,			



# QC Sample Report - EPA 8015M Gasoline

Matrix: Water

Batch #: 8015GW2778

## **Batch Accuracy Results**

Analyte	Spike Concentration mg/L	% Recovery LCS	Acceptance Limits % Recovery	Pass/Fail
Gasoline	10.0	101	70 - 130	Pass

Analytical Notes:	
	•
1	
	ř.

#### **Batch Precision Results**

MS/MSD Sample ID: Lab	oratory Contr	ol Sample			
Analyte	Spike Sample Recovery mg/L	Spike Duplicate Recovery mg/L	Relative Percent Difference (RPD)	Upper Control Limit RPD	Pass/Fail
Gasoline	10.12	9.72	4%	25%	Pass

MS: Matrix Spike Sample MSD: Matrix Spike Duplicate

Analytical Notes:		
1		
	•	



Client:

PSI

Project:

CALTRANS S. OAKLAN

Job No.:

17524

Matrix: Analyst: Water JL Date Sampled:

11/28/00 11/29/00

Date Received: Date Analyzed:

11/29/00

Batch Number:

	Sample ID:	Blank	MW-2	MW-4	_
Compounds	DL	μg/L	μg/L	μg/L	_
Acetone	50	ND	ND	ND	
tert-Amyl Methyl Ether (TAM	IE) 5.0	ND	ND	ND	-::
Benzene	0.5	ND	ND	ND	
Bromobenzene	1.0	ND	ND	ND	
Bromochloromethane	1.0	ND	ND	ND	
Bromodichloromethane	0.5	МD	ND	ND	
Bromoform	0.5	ND	ND	ND	
Bromomethane	0.5	ND	ИD	ND	
tert-Butanol (TBA)	50	ND	ND	ND	.,,,,,,,
2-Butanone (MEK)	10	NO	ND	ND	
n-Butylbenzene	0.5	ND	ND	ND	٠,٠,٠,٠
sec-Butylbenzene	0.5	ND	ND	NO	
tert-Butylbenzene	0.5	ND	ND	ND	
Carbon disulfide	10	ND	ND	ND	
Carbon tetrachloride	0.5	ND	ND	ND	Najvis
Chlorobenzene	0.5	ND	ND	ND	
Chloroethane	0.5	ND	ND	ND	1+1+1+1
Chleroform	0.5	ND	ND	7.7	
Chloromethane	0.5	ND	ND	ND	-1-1-1-
2-Chlorotoluene	0.5	ND	ND	ND	
4-Chlorotoluene	0.5	ND	ND	ND	
Dibromochloromethane	0.5	ND	ND	ND	
1,2-Dibromoethane	0.5	ND	ND	ND	.000
1,2-Dibromo-3-chloropropa	ne 10	ND	ND	ND	
Dibromomethane	0.5	ND	ND	ND	04-0-
1,2-Dichlorobenzene	0.5	ND	МD	ND	
1,3-Dichlorobenzene	0.5	ND	ND	ND	141414
1,4-Dichlorobenzerie	0.5	ND	ND	ND	
Dichlorodifluoromethane	0.5	ND	ND	ND	-1-1-1-
1,1-Dichloroethane	0.5	ND	ND	ND	
1,2-Dichloroethane	0.5	ND	ND	ND	
1,1-Dichloroethene	0.5	ND	ND	ND	
cis-1,2-Dichloroethene	0.5	ND	ND	ND	
trans-1,2-Dichloroethene	0.5	DM	ND	ND	
1,2-Dichloropropane	0.5	ND	ND	ND	. ( - ) - ) -
1,3-Dichloropropane	0.5	ND	DM	NO	::::
2,2-Dichloropropane	0.5	ND	ND	ND	
1,1-Dichloropropene	0.5	ON	ND	ND	<u> </u>



Client:

PSI

Project:

CALTRANS S. OAKLAN

Job No.:

17524

Matrix: Analyst: Water JL

Date Sampled:

Date Received:

Date Analyzed:

11/28/00 11/29/00

11/29/00

Batch Number:

MS48260W2306

-	Sample ID:	Blank	MW-2	MW-4	
Compounds	DL	μg/L	μg/L	μg/L	
cis-1,3-Dichloropropene	0.5	ND	ND	ND	
trans-1,3-Dichloropropene	0.5	ND	ND	ND	
Diisopropyl Ether (DIPE)	5.0	ND	ND	ND	
Ethylbenzene	0.5	ND	ND	ND	
Ethyl tert-Butyl Ether (EtBE)	5.0	ND	ND	ND	
Hexachlorobutadiene	0.5	ND	ND	ND	
2-Hexanone	10	ND	ND	ND	
Isopropylbenzene	0.5	ND	ND	ND	
p-Isopropyltoluene	0.5	ND	ND	ND	
Methylene chloride	20	ND	ND	ND	
4-Methyl-2-pentanone	5.0	ND	ND	ND	
Methyl-tert-butyl ether (MtBE	1.0	NO	130	ND	
Napthalene	0.5	ND	ND	ND	
n-Propylbenzene	0.5	ND	ND	ND	
Styrene	0.5	ND	ND	ND	
1,1,1,2-Tetrachloroethane	0.5	ND	ND	ND	
1,1,2,2-Tetrachloroethane	1.0	ND	ND	ND	
Tetrachloroethene	0.5	ND	ND	ND	
Toluene	0.5	ND	ND	ND	
1,2,3-Trichlorobenzene	0.5	ND	ND	ND	
1,2,4-Trichlorobenzene	0.5	ND	ND	ND	
1,1,1-Trichloroethane	9.5	ND	ND	ND	
1,1,2-Trichloroethane	0.5	ND	ND	ND	
Trichloroethene	0.5	ND	ND	ND	
1,2,3-Trichloropropane	0.5	ND	ND	ND	
Trichlorofluoromethane	9.5	NO	ND	ND	
Trichlorotrifluoroethane	5.0	ND	ND	ND	
1,2,4-Trimethylbenzene	0.5	ND	ND	NO	
1,3,5-Trimethylbenzene	0.5	ND	ND	ND	
Vinyl chloride	0.5	ND	ND	ND	
Xylenes (total)	1.5	ND	ND	ND	

Surrogates (% recovery) Limits: 80 - 130

Sullegates (70 1000 tot)				
Sample ID:	Blank	MW-2	MW-4	
Dibromofluoromethane			107	
Toluene-d8	100	95	97	
Bromofluorobenzene	90	89	88	



Client:

PSI

Project:

CALTRANS S. OAKLAN

Job No.:

17524

Matrix: Analyst: Water JL

Date Sampled: Date Received:

11/28/00 11/29/00

Date Analyzed:

11/29/00

Batch Number:

Sample		
Compounds D		
Acetone 25		
tert-Amyl Methyl Ether (TAME) 2		
Benzene 2		www.www.yyg
Bromobenzene 5		
Bromochloromethane 5		
Bromodichloromethane 2		
Bromoform 2		141144444444
Bromomethane 2		
tert-Butanol (TBA) 2		anamanana.
2-Butanone (MEK)		
n-Butylbenzene 2		
sec-Butylbenzene 2	*********	
tert-Butylbenzene 2		000000000000
Carbon disulfide		
Carbon tetrachloride 2		A7400000000
Chlorobenzene 2		
Chloroethane 2		10.000.000.0000
Chloroform 2	• • • • • • • • • • • • • • • • • • • •	
Chloromethane 2		:1:0:0:0:0:0:0:0:0:0:0:0:0:0:0:0:0:0:0:
[	5 NO	(3)(3)(3)(3)(4)
I	5 ND	1444444444
Paragraphic and the control of the c	5 ND	
	5 ND	
**************************************	ND	
I = 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1 =	5 ND	] 1000000000000000000
	5 ND	
1,0 0,000,000,000,000,000,000,000,000,00	5 ND	2000-000-000-000-000-00-00-00-00-00-00-0
[1,1,1,1,1,1,1,1,1,1,1,1,1,1,1,1,1,1,1,	5 ND	
	5 ND	atostotiški.
The second secon	5 ND	
1.,	5 ND	
**************************************	5 ND	
	5 ND	
Market Street or same as a second of the second or secon	5 NO	
	5 ND	1615999999
- 『大変表の音が音がらない音がら組み込み取ります。 マイ・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・	5 ND	
Into promove hearthean	5 ND	je jeg njegova na
1,1-Dichloropropene	5 ND	



Client:

PSI

Project:

CALTRANS S. OAKLAN

Job No.:

17524

Matrix: Analyst: Water JL

Date Sampled:

11/28/00

Date Received: Date Analyzed:

11/29/00

11/29/00

Batch Number:

	Sample ID:	MW-1	
Compounds	DL	μ <b>g/L</b>	_
cis-1,3-Dichloropropene	2.5	ND	.,.,.,
trans-1,3-Dichloropropene	2.5	NO	
Diisopropyl Ether (DIPE)	25	ND	
Ethylbenzene	2.5	NO	
Ethyl tert-Butyl Ether (EtBE)	25	ND	
Hexachlorobutadiene	2.5	DA	
2-Hexanone	50	ND	
Isopropylbenzene	2.5	ND	
p-Isopropyltoluene	2.5	ND	إدروردر
Methylene chloride	100	DAI:	
4-Methyl-2-pentanone	25	ND	ا میشورین
Methyl-tert-butyl ether (MtB		610	
Napthalene	2.5	ND	
n-Propylbenzene	2.5	ND	
Styrene	2.5	ND	
1,1,1,2-Tetrachloroethane	2.5	NO	
1,1,2,2-Tetrachloroethane	5.0	ND	.,,,,,,
Tetrachloroethene	2.5	NO	
Toluene	2.5	ND	
1,2,3-Trichlorobenzene	2.5	ND	
1,2,4-Trichlorobenzene	2.5	ND	
1,1,1-Trichloroethane	2,5	NO	
1,1,2-Trichloroethane	2.5	ND	erenter.
Trichloroethene	2.5	ND	
1,2,3-Trichloropropane	2.5	ND	aadda
Trichlorofluoromethane	2.5	ND	
Trichlorotrifluoroethane	25.0	ND	10000
1,2,4-Trimethylbenzene	2.5	5.4	
1,3,5-Trimethylbenzene	2.5	ND	4450
Vinyl chloride	2.5	ND	
Xylenes (total)	7.5	ND	

Surrogates (% recovery) Limits. 00 -	100
1	MW-1
- 10-2-30 アプログラス 大黒 キャス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・ス・	107
Toluene-d8	97
	88



Client:

PSI

Project:

CALTRANS S. OAKLAN

Job No.:

17524

Matrix: Analyst: Water JL Date Sampled:

11/28/00 11/29/00

Date Received: Date Analyzed:

11/29/00

Batch Number:

·	Sample ID:	MW-3
Compounds	DL	μg/L
Acetone	1000	ND
tert-Amyl Methyl Ether (TAME	5) 100	ND
Benzene	10	27
Bromobenzene	20	ND .
Bromochloromethane	20	ND
Bromodichloromethane	10	ND
Bromoform	10	ND
Bromomethane	10	NO
tert-Butanoi (TBA)	1000	ND
2-Butanone (MEK)	200	ND
n-Butylbenzene	10	ND
sec-Butylbenzene	10	ND
tert-Butylbenzene	10	ND
Carbon disulfide	200	ND .
Carbon tetrachloride	10	ND
Chlorobenzene	10	ND
Chloroethane	10	ND
Chloroform	10	ND
Chloromethane	10	ND
2-Chlorotoluene	10	ND
4-Chlorotoluene	10	ND
Dibromochloromethane	10	ND
1,2-Dibromoethane	10	ND
1,2-Dibromo-3-chloropropani		ND
Dibromomethane	10	ND
1,2-Dichlorobenzene	10	ND
1,3-Dichlorobenzene	10	ND
1,4-Dichlorobenzene	10	ND
Dichlorodifluoromethane	10	ND
1.1-Dichloroethane	10	NO
1,2-Dichloroethane	10	ND
1,1-Dichloroethene	10	NO
cis-1,2-Dichloroethene	10	ND
trans-1,2-Dichloroethene	10	ND
1,2-Dichloropropane	10	ND
1,3-Dichloropropane	10	ND
2,2-Dichloropropane	10	ND
1,1-Dichloropropene	10	ND



Client:

PSI

Project:

CALTRANS S. OAKLAN

Job No.:

17524

Matrix: Analyst: Water JL

Date Sampled:

Date Received:

11/28/00 11/29/00

Date Analyzed:

11/29/00

Batch Number:

	Sample ID:	MW-3	_
Compounds	DL	μg/L	_
cis-1,3-Dichloropropene	10	ND	
trans-1,3-Dichloropropene	10	ND	::::
Diisopropyl Ether (DIPE)	100	ND	
Ethylbenzene	10	ND	
Ethyl tert-Butyl Ether (EtBE)	100	ND	
Hexachlorobutadiene	10	ND	:::
2-Hexanone	200	ND	
fsopropylbenzene	10	ND	
p-Isopropyltoluene	10	ND	ا 
Methylene chloride	400	ND	
4-Methyl-2-pentanone	100	ND	.*.·. <i>!</i>
Methyl tert-butyl ether (MtBI	) 20	<b>2,500</b>	*:
Napthalene	10	ND	
n-Propylbenzene	10	ND	• • • •
Styrene	10	ND	
1,1,1,2-Tetrachloroethane	10	ND	
1,1,2,2-Tetrachloroethane	20	ND	,·.· <i>.</i> ·
Tetrachloroethene	10	ND	
Toluene	10	92	
1,2,3-Trichlorobenzene	10	ND	
1,2,4-Trichlorobenzene	10	ND	
1,1,1-Trichloroethane	10	ND	
1,1,2-Trichloroethane	10	ND	
Trichlorcethene	10	ND	• • •
1,2,3-Trichloropropane	10	ND	
Trichlorofluoromethane	10	ND	
Trichlorotrifluoroethane	100	ND	000
1,2,4-Trimethylbenzene	10	ND	-:-:
1,3,5-Trimethylbenzene	10	ND	
Vinyl chloride	10	ND	::::
Xylenes (total)	30	ND	

Surrogates ( // rect	very	- 100	 	
	Sample ID:	MW-3	 	
Dibromofluoromethane				
Toluene-d8		<del>96</del>		 on a management of the contract of the contrac
Bromofluorobenzene		88		



# QC Sample Report - EPA Method 8260

Matrix: Water

Batch #: MS48260W2306

#### **Batch Accuracy Results**

Sample ID: Laboratory Co.	ntrol Sample			
Analyte	Spike Concentration µg/L	% Recovery LCS	Acceptance Limits % Recovery	Pass/Fail
1,1-Dichloroethene	20	133	59 - 172	Pass
Benzene	20	125	66 - 142	Pass
Trichloroethene	20	108	71 - 137	Pass
Toluene	20	113	59 - 139	Pass
Chlorobenzene	20	96	60 - 133	Pass

Analytic	cal Notes:		
		٠	
1			
1	•		
-			

#### **Batch Precision Results**

MS/MSD Sample ID: Laboratory Control Sample

Analyte	Spike Sample Recovery µg/L	Spike Duplicate Recovery µg/L	Relative Percent Difference (RPD)	Upper Control Limit RPD	Pass/Fail
1,1-Dichloroethene	27.98	27.93	0%	22%	Pass
Benzene	25.11	24.27	3%	21%	Pass
Trichloroethene	21.64	21.24	2%	24%	Pass
Toluene	22.82	22.45	2%	21%	Pass
Chiorobenzene	19.31	19.21	1%	21%	Pass

4		
- 1		
	l .	
- 1	1	
- 1	1	
	l .	
	l .	
	l .	
	l .	
	<b>,</b>	
	ł.	
	r	
	1	
	i .	
	•	
	1	
- 1	•	
	1	
	1	
	1	
	1	
	1	
	,	
	1	
	1	
	1	
	1	
	l .	
	1	
	1	
	1	
	1	

Analytical Notes:

MS: Matrix Spike Sample MSD: Matrix Spike Duplicate

# Centrum Analytical Laboratories, Inc.

Centrum Job # 17524
Page 1 of 1

290 TENNESSEE STREET REDLANDS, CA 92373 www.centrum-labs.com

(909) 798-9336 ● (800) 798-9336 FAX (909) 793-1559

lab@centrum-labs.com

**Chain of Custody Record** 

							/.		Fle	ase '	Circle		<u>. Ai</u>	alys	62 1	ved	ues	IOU		_	
Project No:  Project Man  Client Nam  (Report and Bill)	_		Project Ne CA Phone: 510 Address: (Report and Br	0	ANS S. OAKLA FAX: -1111 510785-1 1320 W. WINTON HAYWARD, CA 94	1192 AJE 545	Diesel, Fuel Screen, Carbon Chain	8015M: Gasoline only	BTEX/MIBE Only by GC/PID	418.1 (TRPH), 413.2 (Oli & Grease)	GCMS( 8260B) 8021B, 624, 524.2	GCMS: Fuel Oxygenates	GCMS: MtBE Conf. Only	8270C, 625	8081A/8082: Pesticides, PCBs, Pest/PCB		Title 22 (CAM), RCRA, PP	S, TSS, Conductivity			Turn-Around Time  24 Hr. RUSH* 48 Hr. RUSH* Normal TAT  *Requires PRIOR approval, additional charges apply  Requested due date:
Centrum ID	Sample ID (As it should appear on report)	Date sampled	Time sampled	Sample matrix	Site location	Containers: # and type	8015M: D	8015M: (	80218: E	418.1 (TF	GCMS	GCMS:	GCMS:	GCMS:	8081A/8(		Metals:	PH, TDS,			Remarks/Special Instructions
1	MW-1	11/29/00	0925	420		4 NOA		X			<u> </u>									_	
2	mw-2	1	1010	1				X			_X	_									
3	mw-3		1035				_	X			_ X				_				_		
	mw-4_	1	1110	1		•		X					_								
- <del> </del>	1.17					}														_	
<del></del>		-																		$\perp$	
-			-																		
}				· · · · · ·																	
			<del> </del>	-				-													 
		<u> </u>	<del> </del>				Γ														 
1) Relinquished by: (Sampler's Signature) Date: Time:			3) Relinquished by:		Date:		Time	a:	To be completed by Laboratory personnel:									Sample Disposal			
CHRIS MERRITT 11/25/00 1700			1	4) Received by:		Dat	6:	Tim	<b>0</b> :	/\						Field	•	☐ Cilent will pick up			
			5) Relinguished by:			le:	Time	e:	Custo	Custody seals? ☐ Yes DXNo									☐ Return to client		
The delivery of samples and the signature on this chain of custody form constitutes authorization to perform the analyses specified above under the Terms and Conditions set forth on the back hereof.				, ,			6: 25/	Time	All sample containers intact? by Yes D N								🗇 Lab disposal				
Laboratory Notes:												Sample Locator No.									
																					Voa