

July 19, 1999

Project Number 192-01-03

Mr. Hooshang Hadjian Foothill Beacon 7240 Dublin Boulevard **Dublin, CA 94568** 

6/24/99 event

Subject:

Report of Groundwater Monitoring at Foothill Beacon, 16210 Foothill Boulevard, San Leandro, California

This Groundwater Monitoring Report describes the site history, field work and laboratory analysis results for a sampling event at the subject property. This is the first groundwater sampling since the monitoring wells were installed in October 1998.

The project site is located at 16210 Foothill Boulevard, San Leandro, California. The site is currently used as a convenience store that retails gasoline under the name Foothill Beacon.

#### SITE BACKGROUND

Four underground storage tanks were removed from this site by California Petroleum Equipment, Inc., of Fresno on January 28, 1997. There were two 8,000 gallon tanks and two 5,000 gallon tanks, single wall steel, and appeared to be in fair condition, with some pitting evident on the tanks with close inspection.

The Alameda County inspector probed the pitted areas and found two 1/4" to 1/2" holes at the end of one of the 5,000 gallon tanks. The holes were about three feet from the bottom of the tank at the weld by the tank cylinder and tank end. Although the metal was soft enough to disintegrate with the probing of a screw-driver, it appears that the tank did not leak from these spots. The tanks were sitting in about four feet of water, and if the tanks leaked, water would have been three to four feet deep in this tank. Since no water was pumped from the tank during service, the tank was apparently intact until removal. Groundwater was eleven feet below grade surface on the day of the tank removal, as measured by a tape measure.

Soil samples were collected from the tank excavation. Sample analysis results show up to 360 ppm TPH-g, up to 9.4 ppm MTBE, up to 2.3 ppm benzene, up to 2.3 ppm toluene, up to 3.0 ppm ethyl-benzene, and up to 98 ppm xylenes.

Three monitoring wells were installed and soil samples were taken by Parker Environmental Services on October 13, 1998, results found in Table 1.

Table 1 - Soil Sample Analysis Results Foothill Beacon Samples Taken October 13, 1998

Sample	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
MW-1 @ 25.5'	ND	ND	ND	ND	ND	ND
MW-1 @ 30.5'	ND	ND	ND	ND	ND	ND
MW-2@ 5.5'	ND	ND	ND	ND	ND	ND
MW-2 @ 10.5'	ND	ND	ND	ND	ND	ND
MW-2 @ 15.5'	ND	ND	ND	ND	ND	ND
MW-3 @ 5.5'	ND	1.8	ND	ND	0.005	0.019
MW-3 @ 10.5'	ND	0.38	ND	ND	ND	ND
MW-3 @ 15.5'	ND	0.34	ND	ND	ND	ND
Detect. Limit	1.0	0.05	0.005	0.005	0.005	0.005

ND means not detected. Results are in pg/L or parts per billion.

lug/kg willion

From the survey and depth to groundwater measurement data, the site groundwater on October 26, 1998 was approximately ten feet below grade surface (BGS) and the gradient direction was \$\frac{1}{2}\$ 79.83 °E, with an apparent gradient of 0.0082 ft./ft. The gradient on November 2, 1998 was found to have an apparent gradient direction of S 69.30 °E, with an average gradient of 0.0036 ft./ft.

Groundwater samples were obtained from the wells on November 2, 1998 and analyzed for TPH as gasoline (EPA method 5030/8015) with BTEX and MTBE (method 602). Sample analysis shows no TPH-g, BTEX or MTBE detected in MW-1 and MW-2. TPH-g and BTEX were not detected in MW-3, but MTBE was detected at 190 parts per billion (ppb).

The first quarter groundwater monitoring of February 1999 showed groundwater about 10 feet BGS, with gradient direction S 63.15° E and apparent slope of 0.003 ft/ft. Sample analysis only showed MTBE in MW-3 at 340 ppb. All other analysis showed non-detect.

#### **Current Activities**

Sampling and measurements were done on June 24, 1999. Prior to sampling, the groundwater elevations were measured using an electric water level meter. Initial depths below ground surface were as follows:

### Table 2: Groundwater Evaluation Foothill Beacon 16210 Foothill Boulevard Measured June 24, 1999

Well	Casing Elevation	Depth to Water	<b>Ground Water Elevation</b>
MW-1	138.57	11.12	127.45
MW-2	137.94	10.32	127.62
MW-3	138.88	10.61	127.60

Groundwater gradient direction on June 24, 1999 was 5 69.10° E at an apparent slope of 0.0027 ft/ft. Figure 2 shows apparent groundwater gradient.

Sixteen gallons each were removed from MW-1, while 9.5 and 8.5 gallons were removed from MW-2 and MW-3 respectively, more than three well volumes. All purge water was placed in a sealed plastic drum and remains on site. Samples were taken from the end of the discharge hose at a flow rate of less than one liter per minute. The water from each well was placed in two 40-milliliter vials filled so that there was no air (head space) remaining in them. Samples were labeled and placed on ice in a cooler for transport to a state certified hazardous materials testing laboratory, McCampbell Analytical of Pacheco, California.

Sampling equipment was cleaned in one bucket with TSP Substitute and rinsed in two separate buckets with tap water, then rinsed with deionized water after use at each well. All purge water and equipment wash water was placed in a plastic drum and remains on-site. A copy of the Water Level Measurements Form is attached to this report.

The samples were analyzed for TPH-gasoline, MTBE and BTEX using EPA Methods 8015 and 8020. A copy of the laboratory report and Chain of Custody form are attached to this report. Results are shown in Table 3 and Figure 3, the Hydrocarbon Concentration Map.

### Table 3 - Groundwater Sample Analysis Results Foothill Beacon Samples collected June 24, 1999

Sample #	TPH-g	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes
MW-1	ND	ND	ND	ND	ND	ND
MW-2	ND	ND	ND	ND	ND	ND
MW-3	ND	86	ND	ND	ND	ND
Det. Limit	50	5.0	0.5	0.5	0.5	0.5

ND means not detected. Results are in µg/L or parts per billion.

The analysis results are similar to samples taken when the wells were installed and the first quarter – but the lowest results to date.

#### **Future Directions**

Two additional quarterly monitoring events are scheduled. These additional sampling tests will provide seasonal tracking of gradient as well as groundwater in MW-3. Copies of this report will be forwarded to the Alameda County Environmental Management Department, and to the California Regional Water Quality Control Board, San Francisco Bay Region.

No. 1059

OF CALIF

Sincerely:

PARKEŘ ENVIRONMENTAL SERVICES

James D. Parker President

Reviewed By:

Gary D. Lowe, R.G., C.E.G.

Principal, Hydrogeologist


H2OGEOL, A GroundWater Consultancy


Attachments

cc: Mr. Robert Weston, Alameda County Environmental Management Department

Mr. Lester Feldman, San Francisco Bay Regional Water Quality Control Board

CENTIFIED





### FOOTHILL BOULEVARD

#### 580 FREEWAY

Wells measured on June 24, 1999

= monitoring well

[X.X] = groundwater elevation

= line of equal elevation

Location of site features are approximate.


Scale: 1'' = 30'

PARKER Environmental Services

190 East 7th Street Pittsburg, CA 94565 (925) 439-1024

Figure 2 - Groundwater Gradient Foothill Beacon 16210 Foothill Boulevard San Leandro, CA

7/99



Key:

(X.X) = TPH-g

 ${X.X} = Benzene$ 

[X.X] = MTBE

580 FREEWAY

Samples collected June 24, 1999. Results are in parts per billion (ppb).

Location of site features are approximate.

Scale: 1'' = 30'

PARKER Environmental Services 190 East 7th Street Pittsburg, CA 94565 (925) 439-1024

Figure 3, Groundwater Sample Results
Foothill Beacon
16210 Foothill Boulevard
San Leandro, CA

7/99

110 2nd Avenue South, #D7, Pacheco, CA 94553-5560
Telephone: 925-798-1620 Fax: 925-798-1622
http://www.mccampbell.com E-mail: main@mccampbell.com

Parker Environmental Services	Client Project ID: Foothill Beacon	Date Sampled: 06/24/99		
190 East 7th Street		Date Received: 07/01/99		
Pittsburg, CA 94565	Client Contact: Jim Parker	Date Extracted: 07/03/99		
	Client P.O:	Date Analyzed: 07/03/99		

Gasoline Range (C6-C12) Volatile Hydrocarbons as Gasoline\*, with Methyl tert-Butyl Ether\* & BTEX\*

EPA methods 5030, modified 8015, and 8020 or 602; California RWOCB (SE Boy Region) method (GCEID(5030))

Lab ID	Client ID	Matrix	TPH(g)⁺	МТВЕ	Benzene	Toluene	Ethylben- zene	Xylenes	% Recovery Surrogate
14861	92/FB/MW-1	w	ND	ND	ND	ND	ND	ND	95
14862	92/FB/MW-2	W	ND	ND	ND	ND	ND	ND	97
14863	92/FB/MW-3	w	ND	86	ND	ND	ND	ND	97
		-	-						
							· · · · · · · · · · · · · · · · · · ·		
otherv	ing Limit unless vise stated; ND	W	50 ug/L	5.0	0.5	0.5	0.5	0.5	
	ot detected above eporting limit	S	1.0 mg/kg	0.05	0.005	0.005	0.005	0.005	

<sup>\*</sup> water and vapor samples are reported in ug/L, wipe samples in ug/wipe, soil and sludge samples in mg/kg, and all TCLP and SPLP extracts in ug/L

<sup>\*</sup>The following descriptions of the TPH chromatogram are cursory in nature and McCampbell Analytical is not responsible for their interpretation: a) unmodified or weakly modified gasoline is significant; b) heavier gasoline range compounds are significant(aged gasoline?); c) lighter gasoline range compounds (the most mobile fraction) are significant; d) gasoline range compounds having broad chromatographic peaks are significant; biologically altered gasoline?; e) TPH pattern that does not appear to be derived from gasoline (?); f) one to a few isolated peaks present; g) strongly aged gasoline or diesel range compounds are significant; h) lighter than water immiscible sheen is present; i) liquid sample that contains greater than ~5 vol. % sediment; j) no recognizable pattern.



cluttered chromatogram; sample peak coelutes with surrogate peak

:

110 2nd Avenue South, #D7, Pacheco, CA 94553 Tele: 925-798-1620 Fax: 925-798-1622

#### QC REPORT FOR HYDROCARBON ANALYSES

Date: 07/02/99-07/03/99 Matrix:

WATER

	Concent	ration	(ug/L)		% Reco	very	<del> </del>
Analyte	Sample			Amount			RPD
	(#14490)	MS	MSD	Spiked   	MS	MSD	
TPH (gas)	0.0	106.5	104.4	100.0	106.5	104.4	2.0
Benzene	0.0	9.3	9.5	10.0	93.0	95.0	2.1
Toluene	0.0	9.5	9.7	10.0	95.0		2.1
Ethyl Benzene	0.0	9.7	9.8	10.0	97.0	98.0	1.0
Xylenes	0.0	29.0	29.4	30.0	96.7	98.0	1.4
TPH(diesel)	0.0	7485	7226	7500	100	96	3.5
TRPH (oil & grease)	N/A	N/A	N/A	M/A	N/A	N/A	N/A

% Rec. = (MS - Sample) / amount spiked x 100

RPD =  $(MS - MSD) / (MS + MSD) \times 2 \times 100$ 

15809 zpelle-dec

PARKER ENV 190 East 7th Pittsburg, CA	et	ERVICES	<u></u>	<u> </u>	<del></del>	DATE: Sample S					1	
Pho	one:	925-439-10 925-439-20					Foothill B	eacon othill Blvd	1.			ı
SAMPLER(S):	25	mes lon	e					dro, Califo				1
SAMPLER'S SIG	NATUR	RE: Gon	y Luc			1911		ANALYTE				
[		SAMPLE	RECIEPT	:								1
	TOTA	L No. of CONT	AINERS									တ္သ
	CHAI	N OF CUSTOD	Y SEALS									NER!
		D GOOD CONE		<del></del>		TBE						ITAI
	CON	PORMS TO RE	CORD	<del></del>		⊠						ର୍ଚ୍ଚ
	LAE	3 NO.				TPH-gasoline+BTEX & MTBE						NUMBER OF CONTAINERS
-						ine+!						₩.
						asol		:				N N
						H-g						l
FAX RESULTS T			estament		WAR ID.	±						
92/FB/MV		<b>05/7H</b> 99		WATER		Х						2
92/FB/MV	N-2	06/24(99		WATER		Х						2
92/FB/MV	N-3	0 <b>6</b> /21/99		WATER		Х						2
							,					
							ļ	14861		ļ <del></del>		
								14862	2			
· ·-	_								:			
				-			<del> </del>   	14863	; :	<del> </del>		
IOCA				VOAS	<b>P&amp;G METALS</b>	OTHER	<del>                                     </del>		Τ- '-	<del> </del>		
GOOD CON	DITION		PRESERVA	HUN .						-		
HEAD SPACE			APPROPRI CONTAINE						<del> </del>	├		
11212 01110		211(	Activité	10			<u> </u>	<u> </u>	<u> </u>	┼		
		<del></del>	<u> </u>	<u> </u>	••••		1	STANDAR	D	<u> </u>		
				<u> </u>			] T	JRNAROU	ND	<u></u>		
		<u> </u>	]	<u> </u>				TIME		<u> </u>		L
RELINQUISHED	BY:	$\bigcap_{i=1}^{n}$	<sup>2</sup> ec		RELINQUISH	ED BY:			-			
SIGNATURE		March	æ	TIME	SIGNATURE					TIME	:	
PRINTED NAMI	E	James Lov	ve	12:02	PRINTED NA	ME Gar	y D. Lowe		>	:		
COMPANY		H <sub>2</sub> OGE (	)L 7-1-94	DATE	001104101	$\leq$	OGEOL		<del></del>	DATE	<b>- 70</b> 9	
RECEIVED BY:			C. C.	OR THE	COMPANY RECEIVED B	Y LABORATO	RY\$	۱, الا	<i>i</i> 11.	402		
SIGNATURE			<u> </u>		SIGNATURE	<b>\</b>	<u>Zma</u>	1 1	Mlh.	12	.52	<del>)</del> 
PRINTED NAM	E <	Gary D. Lo	we	TIME :	PRINTED NA	ME (1)	ira 1	1. Ru	tr		07/6	1/55
COMPANY		H <sub>2</sub> OGEO	<u></u>	DATE 0	COMPANY	МсСАМРВ	ELL ANALYTI	CAL, INC.	G	DATE		
												7

## WATER LEVEL MEASUREMENTS

# 16210 Foothill Boulevard San Leandro, California

## JUNE 24, 1999

WELL	TOTAL WELL DEPTH feet	TIME	DEPTH TO WATER feet	CASING ELEVATION	GROUNDWATER ELEVATION
MW-1	39.29	10:09	11.12	138.57	127.45
MW-2	24.55	10:10	10.32	137.94	127.62
MW-3	24.37	10:12	11.28	138.88	127.60

## PARKER ENVIRONMENTAL SERVICES LOG OF WELL SAMPLING ACTIVITIES

Foothill Beacon Well Identification: MW-1 Project Name: 16210 Foothill Blvd., San Leandro, CA Date: 06/24/99 Sampled by: \_\_\_\_\_ Weather Conditions: Well Location: Well Casing Diameter: 2-Inch Depth of Well Casing: 39.29 Measuring Point: Top of PVC Casing Initial Depth to Water: 11.12 Final Depth to Water: Not measured Casing Volume (1 vol./ 3 vol): 4.59/13.775 Well Borehole Volume: Purging Method: Centrifugal Pump/Peristaltic Pump Sampling Method: Peristaltic Pump Grundfos Submersible Pump Grundfos Submersible Pump Centrifugal Pump/ES-60 Submersible Teflon Bailer ES-40/-60 Submersible Pump X ES Sub. Pump @ <1L/min. X Purging Rate: See below Total Discharge: 16 Casing Volumes Purged: 3.49 Comments: Waste Water Disposal: To drum. Starting Time: Time Pump on: \_\_\_\_10:30 T deg. F Diluted S.C. Date Gal. Purged Time pН Dil. Factor S.C. (µS/cm) Color 06/24/99 10:51 14 9.65 70.8 774 10:53 14.5 7.70 70.2 787 10:55 70.1 15 7.71 783 10:57 15.5 7.75 70.2 770 : : : : Sample Identification: 92/FB/MW-1 Sample Time: 10:59 **TURBIDITY ANALYSIS** Finishing Time: \_\_\_\_\_ Time Analyzed: NTU Value:

## PARKER ENVIRONMENTAL SERVICES LOG OF WELL SAMPLING ACTIVITIES

Foothill Beacon Well Identification: MW-2 Project Name: 16210 Foothill Blvd., San Leandro, CA Date: 06/24/99 Sampled by: Weather Conditions: Well Location: \_\_\_\_\_ Well Casing Diameter: \_\_\_\_\_\_ Depth of Well Casing: \_\_\_\_\_\_ 24.55 Measuring Point: Top of PVC Casing Initial Depth to Water: 10.32 Final Depth to Water: Not measured Casing Volume (1 vol./ 3 vol): \_\_\_\_2.48/7.44 Well Borehole Volume: Purging Method: Centrifugal Pump/Peristaltic Pump
Grundfos Submersible Pump Sampling Method: Peristaltic Pump Grundfos Submersible Pump Centrifugal Pump/ES-60 Submersible Teflon Bailer ES-40/-60 Submersible Pump X ES Sub. Pump @ <1L/min. X Purging Rate: See below Total Discharge: 9.5 Casing Volumes Purged: 3.83 Comments: Waste Water Disposal: To drum. Starting Time: Time Pump on: 11:25 Date Gal. Purged T deg. F Diluted S.C. Dil. Factor S.C. (µS/cm) Time pН Color 06/24/99 : 11:35 7.5 7.98 69.0 692 11:37 8 7.97 69.6 709 11:38 8.5 7.97 69.9 X 705 11:40 9 7.97 69.8 704 Sample Identification: 92/FB/MW-2 Sample Time: 11:42 **TURBIDITY ANALYSIS** Finishing Time: Time Analyzed: NTU Value:

## PARKER ENVIRONMENTAL SERVICES LOG OF WELL SAMPLING ACTIVITIES

Foothill Beacon Well Identification: MW-3 Project Name: 16210 Foothill Blvd., San Leandro, CA Date: 06/24/99 Sampled by: Weather Conditions: Well Location: \_\_\_\_\_ Well Casing Diameter: 2-inch Depth of Well Casing: 24.37 Measuring Point: Top of PVC Casing Initial Depth to Water: 11.28 Final Depth to Water: Not measured Casing Volume (1 vol./ 3 vol): \_\_\_\_2,136/6.41 Well Borehole Volume: Purging Method: Centrifugai Pump/Peristaltic Pump Sampling Method: Peristaltic Pump Grundfos Submersible Pump Grundfos Submersible Pump Teflon Bailer ES Sub. Pump @ <1L/min. X Centrifugal Pump/ES-60 Submersible ES-40/-60 Submersible Pump X Purging Rate: See below Total Discharge: 8.5 Casing Volumes Purged: 3.98 Comments: Waste Water Disposal: To drum. Starting Time: Time Pump on: 12:00 Date Time Gal. Purged pH T deg. F Diluted S.C. Dil. Factor S.C. (µS/cm) Color 06/24/99 : 12:11 8.12 70.0 6.5 610 12:13 8.12 69.9 615 12:15 7.5 8.13 70.0 616 12:16 8 8.12 69.9 618 x : Sample Identification: 92/FB/MW-3 Sample Time: 12:18 **TURBIDITY ANALYSIS** Finishing Time: Time Analyzed: NTU Value: