

February 26, 2009

RECEIVED

2:24 pm, Mar 02, 2009

Alameda County
Environmental Health

**GROUNDWATER MONITORING REPORT
First Quarter, 2009**

807 75th Avenue
Oakland, California

AEI Project No. 262157
ACHCS # RO0000508

Prepared For

Mr. Allan Kanady
Omega Termite
807 75th Avenue
Oakland, CA 95621

Prepared By

AEI Consultants
2500 Camino Diablo Blvd.
Walnut Creek, CA 94597
(925) 944-2899



2500 Camino Diablo, Walnut Creek, CA 94597
tel 800-801-3224
fax 925-944-2895

ENVIRONMENTAL & ENGINEERING SERVICES

www.aeiconsultants.com

February 26, 2009

Mr. Allan Kanady
Omega Termite
807 75th Avenue
Oakland, CA 95621

**Subject: Quarterly Groundwater Monitoring Report
First Quarter, 2009**
807 75th Avenue
Oakland, California
AEI Project No. 262157
ACHCS # RO0000508

Dear Mr. Kanady:

AEI Consultants (AEI) has prepared this report to document the results of the Fourth Quarter, 2008 groundwater monitoring event at the above referenced site (Figure 1: Site Location Map). This groundwater investigation has been performed in accordance with the requirements of the Alameda County Health Care Services Agency (ACEH). The purpose of this activity is to monitor groundwater quality near the location of previously removed underground storage tanks (USTs) at the site. This report presents the findings of the 1st Quarter 2009 groundwater monitoring event, performed on January 27, 2009.

Site Description and Background

The site is located in an industrial area of the City of Oakland, on the northern corner of the intersection of 75th Avenue and Snell Street, just east of San Leandro Street. The property is approximately 10,000 square feet in size and currently developed with two buildings, and is occupied by Omega Termite.

On September 15, 1996, AEI removed three (3) gasoline USTs from the subject property. The tanks consisted of one 8,000-gallon UST, one 1,000-gallon UST, and one 500-gallon UST. The former locations of the tanks are shown on Figure 2. Soil and groundwater samples collected during the tank removal activities revealed that a release had occurred from the tank system. Total petroleum hydrocarbons as gasoline (TPH-g), benzene, and methyl tertiary butyl ether (MTBE) were detected in the soil samples at concentrations up to 4,300 mg/kg, 13 mg/kg, and 25 mg/kg, respectively.

In October 1997, soil and groundwater samples were collected from six (6) soil borings (BH-1 through BH-6). In June 1999, four (4) groundwater monitoring wells (MW-1 through MW-4) were

also installed by AEI. The construction details for the groundwater monitoring wells on site are summarized in Table 1. Monitoring well locations are shown on Figure 2. Historical groundwater elevation and historical groundwater sample analytical data are presented in Tables 2 and 3.

Under the direction of the ACEH, additional soil was removed from the excavation in March 2000. The excavation was extended to 29 by 48 feet in size and 8 feet deep at the east end of the excavation and 11.5 at the west end. During the excavation activities, an additional 500-gallon UST was discovered at the eastern end of the excavation. This tank was removed under the direction of Oakland Fire Services Agency (OFSA). Six additional soil samples were collected from the sidewalls and bottom of the excavation.

The resulting excavation was then backfilled with pea gravel to bridge the water table, with the remainder of the excavation being filled with the previously aerated soil and later with imported fill. The newly excavated soil was stockpiled on the northern portion of the property. A total of 7,400 gallons of hydrocarbon-impacted groundwater were pumped from the excavation, treated on-site, and discharged to the sanitary sewer system under an East Bay Municipal Utility District permit.

On October 9 and 10, 2003, AEI drilled seven (7) temporary Geoprobe® boreholes (SB-7 through SB-13) to depths ranging from 15 to 20 feet bgs to further delineate the lateral extent of contamination in the Shallow aquifer. One borehole, SB-14 was advanced to a depth of 30 feet bgs to determine if the second aquifer at the site had been impacted. Soil samples were collected in the vadose zone above the first aquifer and from the aquitard between the first and second aquifers. The results of chemical analyses of soil samples collected and analyzed during this investigation and earlier investigations appear to have effectively defined the limits of impacted soil in the vadose zone.

The analysis of the water sample from the second aquifer (Soil Boring SB-14, 28 feet bgs) reported TPH-g, TPH-d, MTBE and benzene at concentrations of 2,300 µg/L, 72,000 µg/L, 45 µg/L and 120 µg/L, respectively. Light non-aqueous phase liquid was observed on the sampler and in the water sample.

On February 15 and February 16, 2006, AEI advanced five soil borings (MW-6 through MW-10) on the site, and completed the borings as groundwater monitoring wells. The Monitoring wells were drilled with a Marl 2.5 D drilling rig. Shallow Zone well MW-6 and Deeper Zone wells MW-7 through MW-10, were drilled with nominal 8-inch diameter hollow stem augers and completed as 2" groundwater monitoring wells. The details of the well completions are summarized in Table 1.

These and existing wells were sampled on March 13, 2006. Maximum concentrations of TPH-g, TPH-d, and TPH-mo reported from the Shallow Zone were 3,200 µg/L (MW-1), 2,400 µg/L (MW-2), and 320 µg/L (MW-1), respectively. The maximum concentrations of benzene reported was 1,400 µg/L in MW-1.

Maximum concentrations of TPH-g, TPH-d, and TPH-mo reported from the Deeper Zone were 1,100 µg/L, 14,000 µg/L, and 4,100 µg/L, respectively in MW-9 with the notation of light

immiscible hydrocarbons present in the sample. The maximum concentration of benzene reported was 85 µg/L in MW-9. The results of this investigation are summarized in “*Deeper Aquifer Soil and Groundwater Investigation Report*”, dated April 28, 2006.

In a letter dated May 25, 2006, the ACEH requested a work plan for installation and pilot testing of the ozone sparging system recommended by AEI. The “*Well and Ozone Micro-Sparge System Installation Work Plan*” was approved by the ACEH in a letter dated August 11, 2006. The Ozone Micro-Sparge System was installed during February and March with initial start up on March 8, 2008. Ozone system installation, start up and monitoring activities are summarized in “*In Situ Ozone Oxidation Install and Startup Report*”, dated January 30, 2008.

Geology and Hydrology

The site is located at an elevation approximately 11 feet above mean sea level (msl). The site is essentially flat; however, the general topography of the area slopes gently to the west. The surface sediments at the site are mapped as Holocene natural levee and basin deposits (Qhl and Qhb, OF 97-97, E.J. Helley and R.W. Graymer). The Natural Levee Deposits (Holocene) are described as “loose, moderately to well-sorted sandy or clayey silt grading to sandy or silty clay”. The Basin Deposits (Holocene) are described as “very fine silty clay to clay deposits occupying flat-floored basins at the distal edge of alluvial fans adjacent to the bay mud (Qhbm)”. The presence of gravels in several of the onsite soil borings indicates that stream channel deposits are also present.

Based on the soil borings advanced by AEI, the near surface sediments beneath the site can be divided into several water bearing zones which are separated by clay layers. Sediments immediately below the surface consist of black to gray brown to olive brown silty clay depths ranging from 7.5 to 10 feet bgs. No groundwater was encountered during drilling of this interval.

The surface clay is underlain by variable and somewhat discontinuous silty sand and clayey silt, which make up the Shallow Zone. The Shallow Zone extends from the base of the surface clay to depths ranging from 18 to 21 feet bgs. This zone has low to medium permeability. Groundwater is typically seen in the first permeable silt or sand encountered during drilling of this interval. Once encountered, groundwater level typically stabilizes at a depth of 5 feet bgs or less, indicating the zone is at least a semi-confined aquifer.

The Shallow Zone is underlain by several feet of moderately dry light olive brown to yellowish brown clay, except in MW-7, drilled through the former tank hold, below which the clays have significant discoloration (dark greenish gray clay).

At depths ranging from 18 ft (MW-9) to 21 feet (MW-8) bgs, a second discontinuous water bearing zone (Intermediate Zone) is present. The Intermediate Zone consists of discontinuous gravel, clayey gravel, and silty sand, clayey sand, and clayey silt which are interbedded with clay layers. Permeability in the Intermediate Zone ranges from high (gravel) to poor (clayey silt). The Intermediate Zone is separated from the Deeper Zone by a layer of brown silty clay that ranges in thickness of 2 to 7 feet.

A third water bearing zone (Deeper Zone) was encountered at a depth of approximately 27 to 28 feet bgs. The lower permeable zone is made up of clayey silt, clayey sand, clean sand and sandy gravel.

Summary of Activities

The ozone injection system has operated continuously since the last quarterly monitoring event. AEI conducted monitoring, and quarterly groundwater sampling of five (5) Shallow Zone monitoring wells (MW-1 through MW-4 and MW-6) and six (6) Deeper Zone wells (MW-7 through MW-12) on January 27, 2009.

Prior to measuring the depth to water, the well caps were removed and the water levels in each well were allowed to equilibrate with atmospheric pressure for at least 15 minutes. The depth to groundwater (from the top of the well casings) for each well was then measured with an electric water level indicator. A peristaltic pump was used to purge all wells on site. Wells MW-1 through MW-6 were purged with the sampling tubing at a depth of approximately 11 feet below ground surface (bgs) and wells MW-7 through MW-12 were purged with the sampling tubing at a depth of approximately 27 feet bgs. During purging activities, the groundwater parameters: temperature, pH, specific conductivity, dissolved oxygen (DO), and oxidation-reduction potential (ORP) were measured. A visual evaluation of turbidity was made and noted. Groundwater parameters measured in the field are reported on the field sampling forms included in Appendix A.

Following stabilization of groundwater parameters, groundwater samples were collected using the peristaltic pump bailers and placed into 40-milliliter (ml) Volatile Organic Analysis (VOA) vials and 1-liter amber bottles. The VOAs were filled so that no headspace or air bubbles were visible within the sample containers. Samples were transported in a cooler on ice under appropriate chain-of-custody protocol to McCampbell Analytical, Inc. of Pittsburg, California (Department of Health Services Certification #1644).

Groundwater samples from the wells were analyzed for TPH-g, MTBE, benzene, toluene, ethyl benzene, xylenes (MBTEX), by SW8021B/8015Cm, and TPH-d (as diesel) and TPH-mo (as motor oil) by SW8015C.

Field Results

Groundwater elevations in the Shallow Zone monitoring wells ranged from 5.77 (MW-1) to 6.03 (MW-6) feet above mean sea level (amsl). These elevations in the Shallow Zone are an average of 0.42 feet higher than the previous quarterly monitoring event. The groundwater hydraulic gradient in the Shallow Zone is 0.003 ft/ft to the southwest.

Groundwater elevations in the Deep Zone monitoring wells ranged from 5.80 (MW-9) to 6.57 (MW-12) feet amsl. These elevations are an average of 0.37 feet lower than the previous quarterly monitoring event. The groundwater hydraulic gradient in the Deep Zone is 0.02 ft/ft to the south-

southeast. It is expected that the groundwater elevations have been influenced by the ozone-sparging system.

Current and historical groundwater elevation data are summarized in Tables 3 and 3a. The groundwater elevation contours and the groundwater flow directions are presented in Figures 3 and 4. Groundwater Monitoring Well Field Sampling Forms are presented Appendix A.

Groundwater Quality

TPH-g and TPH-d concentrations in Shallow Zone monitoring well MW-1 decreased to 74 µg/L and 220 µg/L, respectively. BTEX was reported at concentrations of 11 µg/L, 1.1 µg/L, ND<0.5 µg/L, and ND<0.5 µg/L respectively. MTBE and TPH-mo were reported at ND<5.0 µg/L and ND<250µg/L, respectively.

The TPH-g concentration in Shallow Zone monitoring well MW-2 increased to 380 µg/L, while TPH-d decreased to 140 µg/L. Toluene and ethylbenzene were reported at concentrations of 7.1 µg/L and 0.50 µg/L, while benzene and xylenes were reported at ND<0.5 µg/L. MTBE and TPH-mo were reported as non detectable at reporting limits of ND<5.0 µg/L and ND<250 µg/L.

TPH-g, TPH-d, TPH-mo, MTBE, and BTEX concentrations reported in Shallow Zone monitoring wells MW-3, MW-4, and MW-6 remained, below standard reporting limits.

TPH-g, TPH-d, TPH-mo, MTBE, and BTEX, concentrations in Deeper Zone monitoring wells MW-7 and MW-8 remained below standard laboratory detection limits.

The TPH-g concentration in Deeper Zone monitoring well MW-9 decreased to ND<50 µg/L. TPH-d decreased to 100 µg/L. BTEX was reported below reporting limits of ND<0.5 µg/L, ND<0.5 µg/L, and ND<0.5 µg/L and ND<0.5 µg/L, respectively. MTBE and TPH-mo remained below reporting limits of 5.0 µg/L and 250 µg/L, respectively.

The TPH-g concentration in Deeper Zone monitoring well MW-10 increased to 130 µg/L. TPH-d, TPH-mo, MTBE, and BTEX concentrations reported in well MW-10 remained, below standard reporting limits.

Except for xylenes reported in MW-11 at a concentration of 0.58 µg/L, TPH-g, TPH-d, TPH-mo, MTBE and BTEX all remained below standard laboratory detection levels in Deeper Zone monitoring wells MW-11 and MW-12.

A summary of groundwater analytical data is presented in Table 2 and Figure 5. TPH-g contaminant isopleths of the Shallow and Deeper Zone wells is presented in Figures 6 and 7, respectively. Laboratory results and chain of custody documents are included in Appendix B.

Summary

Overall the contaminant concentrations in both the Shallow Zone and Deeper Zones are continuing to slowly decrease. Detectable concentrations of hydrocarbons were reported in three Deeper Zone wells (MW-9 through MW-11) and in two Shallower Zone Wells (MW-1 and MW-2).

The next quarterly groundwater monitoring event is scheduled for April 2009.

Report Limitations and Signatures

This report presents a summary of work completed by AEI Consultants, including observations and descriptions of site conditions. Where appropriate, it includes analytical results for samples taken during the course of the work. The number and location of samples are chosen to provide required information, but it cannot be assumed that they are entirely representative of all areas not sampled. All conclusions and recommendations are based on these analyses, observations, and the governing regulations. Conclusions beyond those stated and reported herein should not be inferred from this document.


These services were performed in accordance with generally accepted practices in the geologic, environmental engineering and construction fields that existed at the time and location of the work.

Please contact Robert F. Flory at (925) 944-2899 extension 122, if you have any questions regarding the findings and recommendations included in this report.

Sincerely,
AEI Consultants


Adrian M. Angel
Staff Geologist


Robert F. Flory, P.G.
Senior Geologist



Attachments

Figures

Figure 1	Site Location Map
Figure 2	Site Plan
Figure 3	Groundwater Elevation Contours – Shallow Zone Wells (1/27/2009)
Figure 4	Groundwater Elevation Contours – Deeper Zone (1/27/2009)
Figure 5	Groundwater Analytical Results (1/27/2009)
Figure 6	TPH-g Isopleths Shallow Zone (1/27/2009)
Figure 7	TPH-g Isopleths Deeper Zone (1/27/2009)

Tables

Table 1	Monitoring Well Construction Details
Table 2	Groundwater Analytical Data
Table 3	Groundwater Elevation Data
Table 4	Groundwater Elevation Data and Flow Direction Summary

Appendix A Groundwater Monitoring Well Field Sampling Forms


Appendix B Laboratory Analytical Documentation and Chain of Custody Documentation

Distribution:

Mr. Allan Kanady Omega Termite 807 75th Avenue Oakland, CA 95621	(2 copies)
Mr. Jerry Wickham Alameda Health Care Services Agency 1131 Harbor Bay Parkway, Suite 250 Alameda, CA 94502	electronic
GeoTracker	electronic
File	(1copies)

FIGURES





TN \star MN
15°

0 5 1 MILE
0 1000 FEET 0 500 1000 METERS


Printed from TOPO! ©2001 National Geographic Holdings (www.topo.com)

AEI CONSULTANTS
2500 CAMINO DIABLO, SUITE 200, WALNUT CREEK, CA

SITE LOCATION MAP

807 75th AVENUE
OAKLAND, CALIFORNIA

FIGURE 1
AEI PROJECT No. 262157



LEGEND

-  MONITORING WELL (SHALLOW)
-  MONITORING WELL (DEEP)
-  OZONE SPARGE POINT

SHALLOW WELLS SCREENED FROM -5 TO 20 FT BGS
 DEEP WELLS SCREENED FROM -25 TO 30 FT BGS

DRAFTED BY R. BRADFORD 12-01-06
 REVISED BY R. BRADFORD 12-18-06


AEI CONSULTANTS

2500 CAMINO DIABLO, WALNUT CREEK

SITE PLAN

807 75th AVENUE
 OAKLAND, CALIFORNIA

FIGURE 2
 PROJECT NO. 262157



LEGEND

- ⊕ MONITORING WELL (SHALLOW)
- ⊕ MONITORING WELL (DEEP)

SHALLOW WELLS SCREENED FROM -5 TO 20 FT BGS
DEEP WELLS SCREENED FROM -25 TO 30 FT BGS

DRAFTED BY R. BRADFORD 12-01-06
REVISED BY R. BRADFORD 12-18-06


AEI CONSULTANTS

2500 CAMINO DIABLO, SUITE 200, WALNUT CREEK

**GROUNDWATER ELEVATION CONTOURS
SHALLOW ZONE WELLS - 1/27/2009**

807 75th AVENUE
OAKLAND, CALIFORNIA

FIGURE 3
PROJECT NO. 262157



LEGEND

- MONITORING WELL (SHALLOW) SHALLOW WELLS SCREEDED FROM -5 TO 20 FT BGS
- MONITORING WELL (DEEP) DEEP WELLS SCREENED FROM -25 TO 30 FT BGS

DRAFTED BY R. BRADFORD 12-01-06
 REVISED BY R. BRADFORD 12-18-06


AEI CONSULTANTS

2500 CAMINO DIABLO, SUITE 200, WALNUT CREEK



**GROUNDWATER ELEVATION CONTOURS
 DEEPER ZONE WELLS - 1/27/2009**

807 75th AVENUE
 OAKLAND, CALIFORNIA

FIGURE 4
 PROJECT NO. 262157



LEGEND

-  MONITORING WELL (SHALLOW) SHALLOW WELLS SCREEDED FROM -5 TO 20 FT BGS
-  MONITORING WELL (DEEP) DEEP WELLS SCREEDED FROM -25 TO 30 FT BGS

DRAFTED BY R. BRADFORD 12-01-06
 REVISED BY R. BRADFORD 12-18-06


AEI CONSULTANTS

2500 CAMINO DIABLO, SUITE 200, WALNUT CREEK

GROUNDWATER ANALYTICALS (1/27/09)

807 75th AVENUE
 OAKLAND, CALIFORNIA

FIGURE 5
 PROJECT NO. 262157



LEGEND

- MONITORING WELL (SHALLOW) SHALLOW WELLS SCREENED FROM -5 TO 20 FT BGS
- MONITORING WELL (DEEP) DEEP WELLS SCREENED FROM -25 TO 30 FT BGS

DRAFTED BY R. BRADFORD 12-01-06
 REVISED BY R. BRADFORD 12-18-06


AEI CONSULTANTS

2500 CAMINO DIABLO, SUITE 200, WALNUT CREEK

TPH-g ISOPLETHS - SHALLOW ZONE (1/27/09)

807 75th AVENUE
 OAKLAND, CALIFORNIA

FIGURE 6
 PROJECT NO. 262157



LEGEND

- MONITORING WELL (SHALLOW) SHALLOW WELLS SCREENED FROM -5 TO 20 FT BGS
- MONITORING WELL (DEEP) DEEP WELLS SCREENED FROM -25 TO 30 FT BGS

DRAFTED BY R. BRADFORD 12-01-06
 REVISED BY R. BRADFORD 12-18-06

AEI CONSULTANTS
 2500 CAMINO DIABLO, SUITE 200, WALNUT CREEK

TPH-g ISOPLETHS - DEEPER ZONE (1/27/09)

807 75th AVENUE
 OAKLAND, CALIFORNIA

FIGURE 7
 PROJECT NO. 262157

TABLES



**Table1: Monitoring Well Construction Details
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date Installed	Box Elevation (feet)	Top of Casing (feet)	Water Depth 10/31/08	Casing Material	Total Depth (feet)	Well Depth (feet)	Borehole Diameter (inches)	Casing Diameter (inches)	Screened Interval (feet)	Slot Size (inches)	Filter Pack Interval (feet)	Filter Pack Material (feet)	Bentonite Seal (feet)	Grout Seal (feet)
MW-1	06/25/99	11.28	10.68	5.35	PVC	20	20	8 1/4	2	20.0-5.0	0.020	20.0-3.5	#3 sand	3.5-2.5	2.5-0.5
MW-2	06/25/99	12.55	12.15	6.81	PVC	20	20	8 1/4	2	20.0-5.0	0.020	20.0-3.5	#3 sand	3.5-2.5	2.5-0.5
MW-3	06/25/99	10.67	10.40	4.94	PVC	20	20	8 1/4	2	20.0-5.0	0.020	20.0-3.5	#3 sand	3.5-2.5	2.5-0.5
MW-4	06/25/99	10.56	10.31	4.79	PVC	20	20	8 1/4	2	20.0-5.0	0.020	20.0-3.5	#3 sand	3.5-2.5	2.5-0.5
TW-5	March 2000	Abandoned	12/20/06	---		10	10	NA	4	10.0-5.0	1/4" drilled	NA	NA	NA	2.0-0.5
MW-6	02/15/06	12.74	12.35	6.92	PVC	14	14	8 1/4	2	14.0-5.0	0.010	14.0-4.5	# 2/12	4.5-3.5	3.5-0.5
MW-7	02/16/06	11.64	11.16	5.29	PVC	33	33	8 1/4	2	33.0-26.0	0.010	33.0-25.0	# 2/12	25.0-23.0	23.0-0.5
MW-8	02/15/06	12.57	12.42	6.42	PVC	31	31	8 1/4	2	31.0-26.0	0.010	31.0-25.0	# 2/12	25.0-23.0	23.0-0.5
MW-9	02/16/06	11.41	11.22	6.88	PVC	30	30	8 1/4	2	30.0-25.0	0.010	30.0-24.0	# 2/12	24.0-22.0	22.0-0.5
MW-10	02/15/06	10.60	10.31	4.78	PVC	30	30	8 1/4	2	30.0-25.0	0.010	30.0-24.0	# 2/12	24.0-22.0	22.0-0.5
MW-11	12/18/06	11.14	10.96	4.05	PVC	35	35	8 1/4	2	35.0-25.0	0.010	35.0-23.0	# 2/12	23.0-21.0	21.0-0.5
MW-12	12/18/06	11.19	10.46	4.60	PVC	35	35	8 1/4	2	35.0-25.0	0.010	35.0-23.0	# 2/12	23.0-21.0	21.0-0.5

**Table:1a Ozone Injection Well Construction Details
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date Installed	Injection Point	Casing Material	Total Depth (feet)	Well Depth (feet)	Borehole Diameter (inches)	Casing Diameter (inches)	Screened Interval (feet)	Slot Size (inches)	Filter Pack Interval (feet)	Filter Pack Material (feet)	Bentonite Seal (feet)	Grout Seal (feet)
OZ-1	12/21/06	Single point Shallow	PVC	19.5	19.5	8 1/4	1	19.5-18.0	micropore	19.5-9.0	#2/16	16.0-2.0	2.0-1.0
OZ-2	12/19/06	Shallow Point Deep Point	PVC	35	19.5 34	10 1/2	1 1	19.5-18.0 34.0-32.5	micropore micropore	19.5-16.0 35.0-30.0	#2/16 #2/16	16.0-2.0 30.0-19.5	2.0-1.0
OZ-3	12/19/06	Shallow Point Deep Point	PVC	35	15 34	10 1/2	1 1	15.0-13.5 34.0-32.5	micropore micropore	16.0-12.0 35.0-30.0	#2/16 #2/16	12.0-2.0 30.0-16.0	3.0-1.0
OZ-4	12/19/06	Shallow Point Deep Point	PVC	35	15 34	10 1/2	1 1	15.0-13.5 34.0-32.5	micropore micropore	16.0-12.0 35.0-30.0	#2/16 #2/16	12.0-2.0 30.0-16.0	2.0-1.0
OZ-5	12/21/06	Shallow Point Deep Point	PVC	35	15 34	10 1/2	1 1	15.0-13.5 34.0-32.5	micropore micropore	16.0-12.0 35.0-30.0	#2/16 #2/16	12.0-2.0 30.0-16.0	2.0-1.0
OZ-6	12/21/06	Shallow Point Deep Point	PVC	35	15 34	10 1/2	1 1	15.0-13.5 34.0-32.5	micropore micropore	16.0-12.0 35.0-30.0	#2/16 #2/16	12.0-2.0 30.0-16.0	2.0-1.0
OZ-7	12/20/06	Shallow Point Deep Point	PVC	35	15 34	10 1/2	1 1	15.0-13.5 34.0-32.5	micropore micropore	16.0-12.0 35.0-30.0	#2/16 #2/16	12.0-2.0 30.0-16.0	2.0-1.0
OZ-8	12/20/06	Shallow Point Deep Point	PVC	35	15 34	10 1/2	1 1	15.0-13.5 34.0-32.5	micropore micropore	16.0-12.0 35.0-30.0	#2/16 #2/16	12.0-2.0 30.0-16.0	2.0-1.0
OZ-9	01/19/07	Shallow Point Deep Point	PVC	35	20 34	8 1/4	1 1	21.0-19.5 34.0-32.5	micropore micropore	22.0-18.0 35.0-30.0	#2/16 #2/16	18.0-2.0 30.0-22.0	2.0-1.0

Table 2: Groundwater Analytical Data

Omega Termite, 807 75th Ave., Oakland, CA

Sample ID	Sample Date	Depth to Water	TPH-g	TPH-d	TPH-mo	MTBE	MTBE	Benzene	Toluene	Ethyl benzene	Xylenes
			EPA Method 8015			8260B	EPA Method 8021B				
			(µg/L)	(µg/L)	(µg/L)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-1	07/30/99	5.82	2,700	---	---	---	ND<10	920	5.5	18	130
	11/09/99	5.70	1,800	---	---	---	ND<20	430	1.5	26	60
	02/23/00	2.84	3,800	---	---	---	ND<10	1,500	56	78	35
	05/26/00	5.50	7,100	---	---	---	ND<10	2,800	70	220	81
	10/10/00	5.70	980	---	---	---	ND<5.0	260	2.9	10	11
	02/07/01	5.25	570	---	---	---	ND<5.0	150	1.8	4.9	9.3
	05/25/01	5.25	18,000	---	---	---	ND<100	3,800	350	550	620
	09/19/01	5.51	840	---	---	---	ND<5.0	190	4.0	4.6	5.3
	05/17/02	5.30	13,000	920	---	---	ND<5.0	4,500	29	50	58
	08/20/02	5.39	2,100	740	ND<5,000	---	ND<15	820	4.5	6.4	9.6
	01/10/03	4.11	95	260	ND<5,000	---	ND<5.0	23	0.66	3.9	6.5
	04/14/03	4.85	340	310	---	---	ND<5.0	87	1.3	4.3	5.6
	07/14/03	5.08	750	700	---	---	ND<10	420	0.84	3.7	6.0
	10/14/03	5.63	200	930	460.0	---	ND<5.0	62	0.83	2.2	2.7
	01/13/04	4.53	510	440	ND<250	---	ND<5.0	190	1.7	11	18.0
	04/15/04	5.14	740	490	ND<250	---	ND<10	240	ND<0.5	5.0	9.6
	07/15/04	5.42	250	420	260	---	ND<5.0	78	ND<0.5	5.0	4.4
	10/18/04	5.42	170	510	290	---	ND<5.0	33	0.75	1.7	3.5
	01/25/05	4.47	240	390	ND<250	---	ND<5.0	86	0.82	1.3	3.0
	04/19/05	4.66	5,100	460	ND<250	---	ND<50	2,100	5.2	13	84
	07/18/05	4.91	3,300	700	350	---	ND<45	1,500	2.8	13	24
	10/18/05	5.24	560	550	330	---	ND<5.0	190	ND<0.5	3.0	8.6
	01/11/06	4.08	240	270	ND<250	---	ND<5.0	93	ND<0.5	1.3	3.4
	03/13/06	3.76	840	260	ND<250	0.89	ND<5.0	330	1.3	5.1	17
	06/15/06	4.79	3,200	640	320	---	ND<25	1,400	3.1	10	71
	09/21/06	5.38	3,500	550	270	---	ND<25	1,700	ND<2.5	14	23
	01/02/07	4.64	410	240	ND<250	---	ND<5.0	150	0.55	1.0	7
	06/06/07	5.54	2,500	540	300	---	ND<20	910	3.4	7.7	55
	07/11/07	5.43	2,000	450	ND<250	---	ND<10	620	1.5	5.9	31
	10/04/07	5.32	500	440	260	---	ND<5.0	140	ND<0.5	1.8	8
	01/18/08	4.58	4,400	560	260	---	ND<25	1,300	2.5	11.0	84
	03/25/08	5.00	980	450	ND<250	---	ND<10	270	1.4	6.6	13
07/24/08	5.23	300	440	ND<250	---	ND<10	40	2.4	6.0	2.7	
10/31/08	5.35	1,600	490	ND<250	---	ND<17	530	5.5	4.1	22	
01/27/09	4.91	74	220	ND<250	---	ND<5.0	11	1.1	ND<0.5	ND<0.5	
MW-2	07/30/99	6.64	1,200	---	---	---	ND<10	29	2.5	51	100
	11/09/99	6.42	1,300	---	---	---	ND<30	26	1.1	55	32
	02/23/00	3.31	5,000	---	---	---	ND<10	200	18	390	440
	05/26/00	6.34	2,700	---	---	---	ND<10	69	13	83	68
	10/10/00	6.52	810	---	---	---	ND<10	17	4.7	42	46
	02/07/01	5.90	2,600	---	---	---	ND<10	70	15	80	100
	05/25/01	6.08	2,400	---	---	---	ND<5.0	75	16	85	100
	09/19/01	6.53	1,200	---	---	---	ND<5.0	10	8.5	46	55
	02/06/02	5.72	1,800	---	---	---	ND<50	14	11	58	59

Table 2: Groundwater Analytical Data

Omega Termite, 807 75th Ave., Oakland, CA

Sample ID	Sample Date	Depth to Water	TPH-g	TPH-d	TPH-mo	MTBE	MTBE	Benzene	Toluene	Ethyl benzene	Xylenes
			EPA Method 8015			8260B	EPA Method 8021B				
			(µg/L)	(µg/L)	(µg/L)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-2	05/17/02	6.17	2,000	860	---	---	8.1	19	1.1	0.75	88
continued	01/10/03	5.12	2,000	910	ND<5000	---	ND<50	11	11	96	100
	04/14/03	4.98	2,400	800	-	---	ND<10	16	10	100	73
	07/14/03	5.99	1,900	970	-	---	ND<15	18	4.8	79	78
	10/14/03	6.43	1,600	1,300	ND<250	---	ND<10	14	5.9	87	78
	01/13/04	5.72	2,900	960	ND<250	---	ND<50	26	13	190	150
	04/15/04	6.02	2,700	1,100	ND<250	---	ND<15	28	11	120	100
	07/15/04	5.27	2,300	1,000	ND<250	---	ND<10	8.8	3.8	96	84
	10/18/04	5.27	2,400	910	ND<250	---	ND<10	8.6	8.9	68	72
	01/25/05	5.41	3,500	1,200	ND<250	---	ND<50	21	11	170	120
	04/19/05	5.61	3,400	1,700	ND<250	---	ND<15	15	7.4	150	94
	07/18/05	5.84	3,400	1,400	ND<250	---	ND<5.0	11	9.7	100	89
	10/18/05	6.17	3,000	2,000	270	---	ND<5.0	8.4	6.7	88	86
	01/11/06	5.11	3,400	1,700	ND<250	---	ND<90	18	9.4	170	87
	03/13/06	5.24	3,400	1,200	ND<250	0.76	ND<50	20	9.4	110	80
	06/15/06	6.23	2,200	2,400	270	---	ND<10	8.4	ND<1.0	81	72
	09/20/06	6.63	2,400	860	ND<250	---	ND<50	12	13	46	65
	01/02/07	6.09	3,800	2,100	ND<250	---	ND<25	11	7.6	110	120
	06/06/07	6.57	3,800	1,500	ND<250	---	ND<20	17	17	75	58
	07/11/07	6.59	5,300	2,900	480	---	ND<17	10	8	47	72
	10/04/07	6.63	660	1,300	ND<250	---	ND<5.0	1.8	0.83	40	45
	01/18/08	6.06	2,200	3,200	350	---	ND<5.0	1.1	3.40	26	40
	03/25/08	6.45	420	300	ND<250	---	ND<5.0	1.1	5.1	0.80	3.6
	07/24/08	6.58	570	190	ND<250	---	ND<5.0	2.5	6.9	1.6	2.1
	10/31/08	6.81	82	180	ND<250	---	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	6.30	380	140	ND<250	---	ND<5.0	ND<0.5	7.1	0.50	ND<0.5
MW-3	07/30/99	5.35	2,700	---	---	---	ND<10	220	15	130	230
	11/09/99	5.11	3,100	---	---	---	15	440	8.8	150	96
	02/23/00	2.37	1,800	---	---	---	ND<15	180	11	82	79
	05/26/00	4.98	1,600	---	---	---	6.4	140	10	69	63
	10/10/00	5.24	1,100	---	---	---	ND<10	110	4.4	63	51
	02/07/01	4.73	1,100	---	---	---	ND<10	130	5.1	68	65
	05/25/01	4.73	1,200	---	---	---	ND<6.0	120	5.4	69	64
	09/19/01	5.07	800	---	---	---	<5.0	78	3.5	52	37
	02/06/02	4.69	1,100	---	---	---	ND<10	130	4.7	77	71
	05/17/02	4.80	2,800	810	---	2.0	ND<50	410	23	160	210
	08/20/02	4.97	780	270	ND<5000	---	ND<10	110	2.8	63	41
	01/10/03	3.59	1,100	510	ND<5000	---	ND<20	160	3.4	98	84
	04/14/03	5.40	690	230	-	---	ND<5.0	60	2.3	44	34
	07/14/03	4.69	900	380	-	---	ND<5.0	130	2.0	70	43
	10/14/03	5.16	500	200	ND<250	---	ND<10	50	2.3	37	18
	01/13/04	4.15	1,500	400	ND<250	---	ND<30	200	6.2	120	88
	04/15/04	4.73	1,100	280	ND<250	---	ND<15	130	3.7	75	53
	07/15/04	5.03	610	240	ND<250	---	ND<5.0	73	2.1	51	29

Table 2: Groundwater Analytical Data

Omega Termite, 807 75th Ave., Oakland, CA

Sample ID	Sample Date	Depth to Water	TPH-g	TPH-d	TPH-mo	MTBE	MTBE	Benzene	Toluene	Ethyl benzene	Xylenes
			EPA Method 8015			8260B	EPA Method 8021B				
			(µg/L)	(µg/L)	(µg/L)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-3	10/18/04	5.03	370	270	ND<250	---	ND<5.0	45	1.2	47	28
continued	01/25/05	4.13	840	300	ND<250	---	ND<5.0	85	2.4	68	45
	04/19/05	4.23	1,100	380	ND<250	---	ND<5.0	140	4.0	95	59
	07/18/05	4.66	740	290	ND<250	---	ND<5.0	98	2.0	70	35
	10/18/05	4.82	420	220	ND<250	---	ND<5.0	38	1.1	35	16
	01/11/06	3.73	740	260	ND<250	---	ND<5.0	75	2.5	60	32
	03/13/06	3.76	1,300	380	ND<250	1.1	ND<17	90	2.5	87	72
	06/15/06	4.38	670	300	ND<250	---	ND<5.0	76	1.3	60	40
	09/20/09	4.84	510	300	310	---	ND<17	49	ND<1.7	50	36
	01/02/07	4.73	380	180	ND<250	---	ND<5.0	33	1.3	32	17
	06/06/07	4.70	460	230	ND<250	---	ND<5.0	40	1.9	39	22
	10/04/07	4.75	320	230	ND<250	---	ND<5.0	28	ND<0.5	29	17
	01/18/08	4.16	470	200	ND<250	---	ND<5.0	29	1.5	34	20
	03/25/08	4.59	ND<50	63	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/24/08	4.77	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/31/08	4.94	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	4.52	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
MW-4	07/30/99	5.45	340	---	---	---	ND<10	57	2.2	8.5	6.8
	11/09/99	5.31	1,000	---	---	---	ND<10	220	<0.5	17	7.1
	02/23/00	2.72	980	---	---	---	ND<5.0	260	7	33	27
	05/26/00	5.07	760	---	---	---	5.7	170	4.8	22	13
	10/10/00	5.32	520	---	---	---	ND<10	130	2.3	22	10
	02/07/01	4.73	680	---	---	---	ND<8.0	180	3.7	29	21
	05/25/01	4.90	1,700	---	---	---	ND<10	510	9.6	44	46
	09/19/01	5.16	680	---	---	---	ND<10	200	2.6	33	12
	02/06/02	4.65	710	---	---	---	ND<15	220	2.8	40	21
	05/17/02	4.90	1,300	190	---	3.3	ND<10	330	5.6	61	51
	08/20/02	5.02	580	120	ND<5,000	---	ND<5.0	160	1.7	34	13
	01/10/03	3.78	800	85	ND<5,000	---	ND<20	240	2.5	46	28
	04/14/03	4.11	850	120	---	---	ND<10	220	2.7	47	26
	07/14/03	4.75	780	170	---	---	ND<20	220	1.4	44	23
	10/14/03	5.25	420	110	ND<250	---	ND<5.0	120	0.95	31	8.2
	01/13/04	4.07	120	69	ND<250	---	ND<10	30	0.52	8.1	4.7
	04/15/04	4.70	660	120	ND<250	---	ND<25	200	2.2	39	24
	07/15/04	5.09	500	92	ND<250	---	ND<5.0	130	1.3	35	15
	10/18/04	5.09	350	18	ND<250	---	ND<5.0	76	0.68	22	4.9
	01/25/05	4.02	580	110	ND<250	---	ND<5.0	140	1.2	37	20
	04/19/05	4.17	790	130	ND<250	---	ND<5.0	200	1.7	51	28
	07/18/05	4.49	490	140	ND<250	---	ND<5.0	140	0.99	36	11
	10/18/05	4.83	320	84	ND<250	---	ND<5.0	72	0.59	20	4.4
	01/11/06	3.58	310	98	ND<250	---	ND<5.0	88	0.65	26	9.0
	03/13/06	3.58	490	77	ND<250	1.9	ND<5.0	92	0.88	31	15
	06/15/06	4.37	460	86	ND<250	---	ND<25	93	ND<0.5	29	9.2

Table 2: Groundwater Analytical Data

Omega Termite, 807 75th Ave., Oakland, CA

Sample ID	Sample Date	Depth to Water	TPH-g	TPH-d	TPH-mo	MTBE	MTBE	Benzene	Toluene	Ethyl benzene	Xylenes
			EPA Method 8015			8260B	EPA Method 8021B				
			(µg/L)	(µg/L)	(µg/L)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-4	09/20/06	4.86	260	170	360	---	ND<10	63	ND<0.5	23	4.7
continued	01/02/07	4.17	160	78	ND<250	---	ND<5.0	27	ND<0.5	10	2.0
	06/06/07	4.68	190	59	ND<250	---	ND<5.0	40	ND<0.5	14	3.6
	10/04/07	4.78	180	ND<50	ND<250	---	ND<5.0	44	ND<0.5	12	2.2
	01/18/08	4.07	100	ND<50	ND<250	---	ND<5.0	18	ND<0.5	6	1.4
	03/25/08	4.61	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/24/08	4.78	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/31/08	4.90	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	4.47	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
TW-5	10/10/00	---	5,800	2,900	ND<250	---	ND<50	650	60	190	230
	02/07/01	---	720	650	450	---	ND<5.0	6.0	4.5	3.2	4.5
	05/25/01	---	370	420	ND<250	---	ND<5.0	13.0	4.1	1.6	1.3
	09/19/01	6.59	15,000	2,700,000 ¹	1,100,000 ¹	---	530	29	2.7	14	240
	02/06/02	---	280	55,000	18,000 ¹	---	ND<5.0	2.3	0.74	ND<0.5	0.70
	05/17/02	6.56	480	41,000	---	ND<5.0	ND<5.0	1.6	1.1	0.8	ND<0.5
	08/20/02	6.62	240	21,000	ND<5,000	---	ND<5.0	8.0	1.2	1.1	0.54
	01/10/03	4.66	ND<50	1,300	ND<5,000	---	ND<5.0	5.4	0.58	ND<0.5	1.10
	4/14/2003	5.30	160	2,300	---	---	ND<5.0	18	5.7	5.9	16
	7/14/2003	5.84	100	16,000	---	---	ND<5.0	1.2	0.77	0.63	1.2
	10/14/03	6.08	120	10,000	4,600	---	ND<5.0	1.6	1.6	ND<0.5	1.2
	01/13/04	4.83	110	2,100	1,400	---	ND<5.0	8.4	1.2	ND<0.5	3.9
	04/15/04	5.64	170	2,200	1,100	---	ND<5.0	2.5	1.2	ND<0.5	5.1
	07/15/04	5.89	81	3,000	1,600	---	ND<5.0	5	1.3	0.85	4.1
	10/18/04	5.89	230	3,700	1,600	---	ND<5.0	0.54	3.4	ND<0.5	0.93
	01/25/05	5.13	63	750	640	---	ND<5.0	ND<0.5	0.78	ND<0.5	1.3
	04/19/05	5.27	ND<50	1,100	660	---	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/18/05	5.76	ND<50	770	490	---	ND<5.0	ND<0.5	0.88	ND<0.5	ND<0.5
	10/18/05	6.04	78	1,600	1,100	---	ND<5.0	ND<0.5	1.6	ND<0.5	ND<0.5
	01/11/06	4.72	ND<50	680	550	ND<0.5	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	03/13/06	4.51	ND<50	180	260	ND<0.5	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/02/07	Well Destroyed 12/20/06									
MW-6	03/13/06	5.69	87	160	310	ND<0.5	ND<5.0	ND<0.5	0.83	1.3	0.80
	06/15/09	6.50	ND<50	110	ND<250	---	ND<5.0	ND<0.5	ND<0.5	1.0	0.58
	09/20/06	6.84	ND<50	59	ND<250	---	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/02/07	6.44	ND<50	120	ND<250	---	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	06/06/07	6.82	ND<50	76	ND<250	---	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/04/07	6.83	ND<50	100	ND<250	---	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/18/08	6.39	ND<50	130	ND<250	---	ND<5.0	ND<0.5	ND<0.5	1.3	ND<0.5
	03/25/08	6.61	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/24/08	6.79	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/31/08	6.92	ND<50	ND<50	ND<250	--	5.2	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	6.32	ND<50	ND<50	ND<250	--	5.2	ND<0.5	ND<0.5	ND<0.5	ND<0.5

Table 2: Groundwater Analytical Data

Omega Termite, 807 75th Ave., Oakland, CA

Sample ID	Sample Date	Depth to Water	TPH-g	TPH-d	TPH-mo	MTBE	MTBE	Benzene	Toluene	Ethyl benzene	Xylenes
			EPA Method 8015			8260B	EPA Method 8021B				
			(µg/L)	(µg/L)	(µg/L)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-7	03/13/06	3.36	460	3,500	360	ND<0.5	ND<5.0	2.5	1.0	ND<0.5	3.3
	06/15/09	3.95	ND<50	520	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	09/20/06	4.77	ND<50	150	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/02/07	4.17	ND<50	99	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	06/06/07	4.69	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/11/07	---	67	150	ND<250	--	ND<5.0	17	ND<0.5	ND<0.5	ND<0.5
	10/04/07	5.15	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/18/08	4.15	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	03/25/08	4.33	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/24/08	4.98	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/31/08	5.29	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	4.69	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
MW-8	03/13/06	4.64	280	130	ND<250	ND<0.5	ND<5.0	ND<0.5	2.0	ND<0.5	1.3
	06/15/09	5.21	ND<50	140	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	09/20/06	6.03	ND<50	65	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/02/07	5.97	ND<50	70	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	06/06/07	5.93	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/04/07	6.64	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/18/08	5.35	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	03/25/08	5.67	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/24/08	6.28	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/31/09	6.42	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	6.16	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	MW-9	03/13/06	4.32	1,100	14,000 ¹	4,100	2.4	ND<5.0	85	1.8	0.64
06/15/09		5.35	460	2,100	710	--	ND<5.0	170	0.73	1.3	8.3
09/21/06		5.81	130	1,400	460	--	ND<5.0	20	1.2	ND<0.5	2.6
01/02/06		5.19	88	4,300	1,000	--	ND<5.0	5.1	0.67	ND<0.5	ND<0.5
06/06/07		5.67	64	320	250	--	ND<5.0	12	ND<0.5	ND<0.5	ND<0.5
10/04/07		5.89	ND<50	140	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
01/18/08		5.13	250	160	ND<250	--	ND<5.0	100	ND<0.5	1.3	7.6
03/25/08		5.56	740	210	ND<250	--	10.0	290	1.5	2.6	16
07/24/08		5.75	680	230	ND<250	--	ND<10	330	0.69	2.4	7.0
10/31/08		6.88	62	130	ND<250	--	ND<5.0	20	ND<0.5	ND<0.5	ND<0.5
01/27/09		5.42	ND<50	100	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
MW-10		03/13/06	3.28	ND<50	220	ND<250	2.7	ND<5.0	ND<0.5	ND<0.5	ND<0.5
	06/15/09	4.38	ND<50	300	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	09/21/06	4.79	ND<50	280	460	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/02/07	4.66	ND<50	230	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	06/06/07	---	ND<50	230	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/04/07	4.74	ND<50	120	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/18/08	3.92	79	220	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	03/25/08	4.06	340	82	ND<250	--	ND<5.0	0.95	ND<0.5	ND<0.5	1.1

Table 2: Groundwater Analytical Data

Omega Termite, 807 75th Ave., Oakland, CA

Sample ID	Sample Date	Depth to Water	TPH-g	TPH-d	TPH-mo	MTBE	MTBE	Benzene	Toluene	Ethyl benzene	Xylenes
			EPA Method 8015			8260B	EPA Method 8021B				
			(µg/L)	(µg/L)	(µg/L)		(µg/L)	(µg/L)	(µg/L)	(µg/L)	(µg/L)
MW-10	07/24/08	4.78	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
continued	10/31/08	4.78	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	4.32	130	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
MW-11	01/02/07	3.94	160	2,700	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	1.7
	6//06/07	4.51	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/11/07	4.95	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/04/07	5.03	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/18/08	3.92	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	03/25/08	4.06	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	07/24/08	4.06	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	10/31/08	5.05	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
	01/27/09	4.45	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5
MW-12	01/02/07	3.43	53	130	ND<250	--	1.4	ND<0.5	ND<0.5	ND<0.5	0.95
	06/06/07	3.81	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<5.0
	10/04/07	4.38	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<5.0
	01/18/08	3.32	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<5.0
	03/25/08	3.62	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<5.0
	07/24/08	4.28	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<5.0
	10/31/08	4.60	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<5.0
	01/27/09	3.89	ND<50	ND<50	ND<250	--	ND<5.0	ND<0.5	ND<0.5	ND<0.5	ND<0.5

TPH-g = total petroleum hydrocarbons as gasoline
 TPH-d = total petroleum hydrocarbons as diesel
 TPH-mo = total petroleum hydrocarbons as motor oil
 MTBE = methyl tert-butyl ether

l = light non-aqueous phase liquid
 µg/L = micrograms per liter (parts per billion)
 ----- not sampled
 ND = not detected

**Table 3: Groundwater Elevation Data
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date	Well Elevation * (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Elevation Change (ft)
MW-1	07/30/99	10.68	5.82	4.86	----
	11/09/99	10.68	5.70	4.98	0.12
	02/23/00	10.68	2.84	7.84	2.86
	05/26/00	10.68	5.50	5.18	-2.66
	10/10/00	10.68	5.70	4.98	-0.20
	02/07/01	10.68	5.25	5.43	0.45
	05/25/01	10.68	5.25	5.43	0.00
	09/19/01	10.68	5.51	5.17	-0.26
	02/06/02	10.68	NM	NM	NM
	05/17/02	10.68	5.30	5.38	----
	08/20/02	10.68	5.39	5.29	-0.09
	01/10/03	10.68	4.11	6.57	1.28
	04/14/03	10.68	4.85	5.83	-0.74
	07/14/03	10.68	5.08	5.60	-0.23
	10/14/03	10.68	5.63	5.05	-0.55
	01/13/04	10.68	4.53	6.15	1.10
	04/15/04	10.68	5.14	5.54	-0.61
	07/15/04	10.68	5.42	5.26	-0.28
	10/18/04	10.68	5.24	5.44	0.18
	01/25/05	10.68	4.47	6.21	0.77
	04/19/05	10.68	4.66	6.02	-0.19
	07/18/05	10.68	4.91	5.77	-0.25
	10/18/05	10.68	5.24	5.44	-0.33
	11/03/05	10.68	5.31	5.37	-0.07
	01/11/06	10.68	4.08	6.60	1.23
	03/13/06	10.68	3.76	6.92	0.32
	06/15/06	10.68	4.79	5.89	-1.03
	09/20/06	10.68	5.38	5.30	-0.59
	01/02/07	10.68	4.64	6.04	0.74
	6/6/2007	10.68	5.14	5.54	-0.50
10/04/07	10.68	5.32	5.36	-0.18	
01/18/08	10.68	4.58	6.10	0.74	
03/25/08	10.68	5.00	5.68	-0.42	
07/24/08	10.68	5.23	5.45	-0.65	
10/31/08	10.68	5.35	5.33	-0.35	
01/27/09		10.68	4.91	5.77	0.32
MW-2	07/30/99	12.15	6.64	5.51	----
	11/09/99	12.15	6.42	5.73	0.22
	02/23/00	12.15	3.31	8.84	3.11
	05/26/00	12.15	6.34	5.81	-3.03
	10/10/00	12.15	6.52	5.63	-0.18
	02/07/01	12.15	5.90	6.25	0.62
	05/25/01	12.15	6.08	6.07	-0.18
	09/19/01	12.15	6.53	5.62	-0.45

**Table 3: Groundwater Elevation Data
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date	Well Elevation * (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Elevation Change (ft)
MW-2 continued	02/06/02	12.15	5.72	6.43	0.81
	05/17/02	12.15	6.17	5.98	-0.45
	08/20/02	12.15	NM	NM	NM
	01/10/03	12.15	5.12	7.03	----
	04/14/03	12.15	4.98	7.17	0.14
	07/14/03	12.15	5.99	6.16	-1.01
	10/14/03	12.15	6.43	5.72	-0.44
	01/13/04	12.15	5.42	6.73	1.01
	04/15/04	12.15	6.02	6.13	-0.60
	07/15/04	12.15	5.27	6.88	0.75
	10/18/04	12.15	6.12	6.03	-0.85
	04/19/05	12.15	5.61	6.54	0.51
	07/18/05	12.15	5.84	6.31	-0.23
	10/19/05	12.15	6.17	5.98	-0.33
	11/03/05	12.15	6.21	5.94	-0.04
	01/11/06	12.15	5.11	7.04	1.10
	03/13/06	12.15	5.24	6.91	-0.13
	06/15/06	12.15	6.23	5.92	-0.99
	09/20/06	12.15	6.63	5.52	-0.40
	01/02/06	12.15	6.09	6.06	0.54
	6/6/2007	12.15	6.57	5.58	-0.48
10/04/07	12.15	6.63	5.52	-0.06	
01/18/08	12.15	6.06	6.09	0.57	
03/25/08	12.15	6.45	5.70	-0.39	
07/24/08	12.15	6.58	5.57	-0.52	
10/31/08	12.15	6.81	5.34	-0.36	
01/27/09	12.15	6.30	5.85	0.28	
MW-3	07/30/99	10.40	5.35	5.05	----
	11/09/99	10.40	5.11	5.29	0.24
	02/23/00	10.40	2.37	8.03	2.74
	05/26/00	10.40	4.98	5.42	-2.61
	10/10/00	10.40	5.24	5.16	-0.26
	02/07/01	10.40	4.73	5.67	0.51
	05/25/01	10.40	4.73	5.67	0.00
	09/19/01	10.40	5.07	5.33	-0.34
	02/06/02	10.40	4.69	5.71	0.38
	05/17/02	10.40	4.80	5.60	-0.11
	08/20/02	10.40	4.97	5.43	-0.17
	01/10/03	10.40	3.59	6.81	1.38
	04/14/03	10.40	5.40	5.00	-1.81
	07/14/03	10.40	4.69	5.71	0.71
	10/14/03	10.40	5.16	5.24	-0.47
	01/13/04	10.40	4.15	6.25	1.01
	04/15/04	10.40	4.73	5.67	-0.58

**Table 3: Groundwater Elevation Data
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date	Well Elevation * (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Elevation Change (ft)
MW-3 continued	07/15/04	10.40	5.03	5.37	-0.30
	10/18/04	10.40	4.85	5.55	0.18
	01/25/05	10.40	4.13	6.27	0.72
	04/19/05	10.40	4.23	6.17	-0.10
	07/18/05	10.40	4.56	5.84	-0.33
	10/18/05	10.40	4.82	5.58	-0.26
	11/03/05	10.40	4.87	5.53	-0.05
	01/11/06	10.40	3.62	6.78	1.25
	03/13/06	10.40	3.47	6.93	0.15
	06/15/06	10.40	4.38	6.02	-0.91
	08/02/06	10.40	4.69	5.71	-0.31
	09/20/06	10.40	4.84	5.56	-0.15
	01/02/07	10.40	3.73	6.67	1.11
	6/6/2007	10.40	4.7	5.7	-0.97
	10/04/07	10.40	4.75	5.65	-0.05
	01/18/08	10.40	4.16	6.24	0.59
	03/25/08	10.40	4.59	5.81	-0.43
	07/24/08	10.40	4.77	5.63	-0.61
	10/31/08	10.40	4.94	5.46	-0.35
	01/27/09	10.40	4.52	5.88	0.25
MW-4	07/30/99	10.31	5.45	4.86	----
	11/09/99	10.31	5.31	5.00	0.14
	02/23/00	10.31	2.72	7.59	2.59
	05/26/00	10.31	5.07	5.24	-2.35
	10/10/00	10.31	5.32	4.99	-0.25
	02/07/01	10.31	4.73	5.58	0.59
	05/25/01	10.31	4.90	5.41	-0.17
	09/19/01	10.31	5.16	5.15	-0.26
	02/06/02	10.31	4.65	5.66	0.51
	05/17/02	10.31	4.90	5.41	-0.25
	08/20/02	10.31	5.02	5.29	-0.12
	01/10/03	10.31	3.78	6.53	1.24
	04/14/03	10.31	4.11	6.20	-0.33
	07/14/03	10.31	4.75	5.56	-0.64
	10/14/03	10.31	5.28	5.03	-0.53
	01/13/04	10.31	4.07	6.24	1.21
	04/15/04	10.31	4.70	5.61	-0.63
	07/15/04	10.31	5.09	5.22	-0.39
	10/18/04	10.31	4.86	5.45	0.23
	01/25/05	10.31	4.02	6.29	0.84
	04/19/05	10.31	4.17	6.14	-0.15
	07/18/05	10.31	4.49	5.82	-0.32
	10/18/05	10.31	4.83	5.48	-0.34
11/03/05	10.31	4.88	5.43	-0.05	
01/11/06	10.31	3.58	6.73	1.30	

**Table 3: Groundwater Elevation Data
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date	Well Elevation * (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Elevation Change (ft)
MW-4 continued	03/13/06	10.31	3.28	7.03	0.30
	06/15/06	10.31	4.37	5.94	-1.09
	09/20/06	10.31	4.86	5.45	-0.49
	01/02/07	10.31	4.17	6.14	0.69
	6/6/2007	10.31	4.68	5.63	-0.51
	10/04/07	10.31	4.78	5.53	-0.10
	01/18/08	10.31	4.07	6.24	0.71
	03/25/08	10.31	4.61	5.70	-0.54
	07/24/08	10.31	4.78	5.53	-0.71
	10/31/08	10.31	4.79	5.52	-0.18
	01/27/09	10.31	4.47	5.84	0.31
TW-5	09/19/01	----	6.59	----	----
	05/17/02	----	6.56	----	0.03
	08/20/02	----	6.62	----	-0.06
	01/10/03	----	4.66	----	1.96
	04/14/03	----	5.30	----	-0.64
	07/14/03	----	5.84	----	-0.54
	07/14/03	----	5.84	----	0.00
	10/14/03	----	6.08	----	-0.24
	01/13/04	----	4.83	----	1.25
	04/15/04	----	5.64	----	-0.81
	07/15/04	----	5.89	----	-0.25
	10/18/04	----	5.95	----	-0.06
	01/25/05	----	5.13	----	0.82
	04/19/05	----	5.27	----	-0.14
	07/18/05	----	5.76	----	-0.49
	10/18/05	----	6.04	----	-0.28
	11/03/05	----	6.09	----	-0.05
	01/11/06	----	4.72	----	1.37
	03/13/06	----	4.51	----	0.21
	04/26/06	----	5.02	----	-0.51
01/27/09	Well Destroyed 12/20/06				
MW-6	03/13/06	12.35	5.69	6.66	----
	06/15/06	12.35	6.50	5.85	-0.81
	09/20/06	12.35	6.84	5.51	-0.34
	01/02/07	12.35	6.44	5.91	0.40
	6/6/2007	12.35	6.82	5.53	-0.38
	10/04/07	12.35	6.83	5.52	-0.01
	01/18/08	12.35	6.39	5.96	0.44
	03/25/08	12.35	6.61	5.74	-0.22
	07/24/08	12.35	6.79	5.56	-0.40
	10/31/08	12.35	6.92	5.43	-0.31
	01/27/09	12.35	6.32	6.03	0.47

**Table 3: Groundwater Elevation Data
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date	Well Elevation * (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Elevation Change (ft)
MW-7	03/13/06	11.16	3.36	7.80	----
	06/15/06	11.16	3.95	7.21	-0.59
	09/20/06	11.16	4.77	6.39	-0.82
	01/02/07	11.16	4.17	6.99	0.60
	6/6/2007	11.16	4.69	6.47	-0.52
	10/04/07	11.16	5.15	6.01	-0.46
	01/18/08	11.16	4.15	7.01	1.00
	03/25/08	11.16	4.33	6.83	-0.18
	07/24/08	11.16	4.98	6.18	-0.83
	10/31/08	11.16	5.29	5.87	-0.96
	01/27/09	11.16	4.69	6.47	0.29
MW-8	03/13/06	12.42	4.64	7.78	----
	06/15/06	12.42	5.21	7.21	-0.57
	09/20/06	12.42	6.03	6.39	-0.82
	01/02/07	12.42	5.97	6.45	0.06
	6/6/2007	12.42	5.93	6.49	0.04
	10/04/07	12.42	6.64	5.78	-0.71
	01/18/08	12.42	5.35	7.07	1.29
	03/25/08	12.42	5.67	6.75	-0.32
	07/24/08	12.42	6.28	6.14	-0.61
	10/31/08	12.42	6.42	6.00	-0.75
	01/27/09	12.42	6.16	6.26	0.12
MW-9	03/13/06	11.22	4.32	6.90	----
	06/15/06	11.22	5.35	5.87	-1.03
	08/02/06	11.22	5.70	5.52	-0.35
	09/20/06	11.22	5.81	5.41	-0.11
	01/02/07	11.22	5.19	6.03	0.62
	6/6/2007	11.22	5.67	5.55	-0.48
	10/04/07	11.22	5.89	5.33	-0.22
	01/18/08	11.22	5.13	6.09	0.76
	03/25/08	11.22	5.56	5.66	-0.43
	07/24/08	11.22	5.75	5.47	-0.19
10/31/08	11.22	6.88	4.34	-1.32	
	01/27/09	11.22	5.42	5.80	0.33

**Table 3: Groundwater Elevation Data
Omega Termite, 807 75th Ave., Oakland, CA**

Well ID	Date	Well Elevation * (ft amsl)	Depth to Water (ft)	Groundwater Elevation (ft amsl)	Elevation Change (ft)
MW-10	03/13/06	10.31	3.28	7.03	----
	06/15/06	10.31	4.34	5.97	-1.06
	08/02/06	10.31	4.66	5.65	-0.32
	09/20/06	10.31	4.79	5.52	-0.13
	01/02/07	10.31	4.26	6.05	0.53
	6/6/2007	10.31	4.66	5.65	-0.40
	10/04/07	10.31	4.74	5.57	-0.08
	01/18/08	10.31	4.12	6.19	0.62
	03/25/08	10.31	4.42	5.89	-0.30
	07/24/08	10.31	4.78	5.53	-0.36
	10/31/08	10.31	4.78	5.53	0.00
	01/27/09	10.31	4.32	5.99	0.46
MW-11	01/02/07	10.96	3.94	7.02	----
	6/6/2007	10.96	4.51	6.45	-0.57
	10/04/07	10.96	5.03	5.93	-0.52
	01/18/08	10.96	3.92	7.04	1.11
	03/25/08	10.96	4.06	6.90	-0.14
	07/24/08	10.96	4.78	6.18	-0.72
	10/31/08	10.96	5.05	5.91	-0.99
		01/27/09	10.96	4.45	6.51
MW-12	01/02/07	10.46	3.43	7.03	----
	6/6/2007	10.46	3.81	6.65	-0.38
	10/04/07	10.46	4.38	6.08	-0.57
	01/18/08	10.46	3.32	7.14	1.06
	03/25/08	10.46	3.62	6.84	-0.30
	07/24/08	10.46	4.28	6.18	-0.66
	10/31/08	10.46	4.60	5.86	-0.98
		01/27/09	10.46	3.89	6.57

* Original wells surveyed 12/9/02 by Morrow Surveying, resurveyed on 3/02/06, 1/16/07 by Morrow Surveying

Depth to water measured from the top of well casing

NM - not monitored

ft amsl = feet above mean sea level

**Table 3a: Groundwater Elevation and Flow Direction Summary
Omega Termite, 807 75th Ave., Oakland, CA**

Episode #	Date	Average Elevation (ft)	Elevation Change (ft)	Flow Direction / Gradient
1	07/30/99	5.07	-	
2	11/09/99	5.25	0.18	0.0056 / SW
3	02/23/00	8.08	2.83	0.008 / S
4	05/26/00	5.41	-2.66	0.003 / SW
5	10/10/00	5.19	-0.22	0.0036 / S
6	02/07/01	5.73	0.54	0.008 / S
7	05/25/01	5.65	-0.09	0.006 / S
8	09/19/01	5.32	-0.33	0.004 / S
9	02/06/02	5.93	0.62	0.005 / SE
10	05/17/02	5.59	-0.34	0.003 / SW
11	08/20/02	5.34	-0.26	0.002 / S
12	01/10/03	6.74	1.40	0.006 / E-NE
13	04/14/03	6.05	-0.69	0.016 / E-NE
14	07/14/03	5.76	-0.29	.0017 / S-SE
15	10/14/03	5.26	-0.50	0.003 / SE
16	01/13/04	6.34	1.08	0.001 / W
17	04/15/04	5.74	h	0.001 / W
18	07/15/04	5.68	-0.05	0.001 / W
19	10/18/04	5.62	-0.07	0.002 / N
20	01/25/05	6.33	0.71	0.002 / N
21	04/19/05	6.16	-0.17	0.001 / N
22	07/18/05	5.85	-0.31	0.0004 / S
23	10/18/05	5.61	-0.24	0.0017 / SW
24	01/11/06	6.79	1.18	0.0047 / N
25	3/13/06	6.57	-0.21	Shallow Zone .0004 / NW
	3/13/06	7.38	---	Deeper zone 0.036 / S
26	6/15/06	5.92	-0.65	Shallow Zone 0.0004 / NW
	6/15/06	6.40	-0.98	Deeper zone 0.06 / S
27	9/20/06	5.47	-0.46	Shallow Zone 0.005 / SW
	9/20/06	5.93	-0.47	Deeper zone 0.004/ S
28	1/2/07	6.16	0.70	Shallow Zone 0.0004 / NW
	1/2/07	6.52	0.59	Deeper Zone 0.06 / S
29	6/6/07	5.60	-0.57	Shallow Zone 0.0004 / NW
	6/6/07	6.21	-0.31	Deeper Zone 0.06 / S
30	10/4/07	5.52	-0.08	Shallow Zone 0.005 / SW
	10/4/07	5.72	-0.49	Deeper Zone 0.012/ S
31	1/18/08	6.17	0.65	Shallow Zone 0.003/ NW
	1/18/08	6.68	0.96	Deeper Zone .015/ SE
32	3/25/08	5.72	-0.45	Shallow Zone 0.003/ NW
	3/25/08	6.41	-0.27	Deeper Zone .015/ SE
32	7/24/08	5.55	-0.18	Shallow Zone 0.003/ NW
	7/24/08	5.90	-0.51	Deeper Zone 0.016/ S
33	10/31/08	5.41	-0.13	Shallow Zone 0.003/ NW
	10/31/08	5.53	-0.37	Deeper Zone 0.023/ SSE
34	1/27/09	5.84	0.42	Shallow Zone 0.003/ SW
	1/27/09	6.21	0.68	Deeper Zone 0.021/ SSE

Average water table elevation calculated using Microsoft Excel

Shallow Zone Wells: MW-1, MW-2, MW-3, MW-4, MW-6

Deeper Zone Wells: MW-7, MW-8, MW-9, MW-10, MW-11, MW-12

APPENDIX A

MONITORING WELL FIELD SAMPLING FORMS



AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-1

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	10.68		
Depth of Well	20.00		
Depth to Water (from top of casing)	4.91		
Water Elevation (feet above msl)	5.77		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (μS/cm)	DO (mg/L)	ORP (meV)	Comments
3:11	1.0	17.10	6.15	1367	0.95	-91.8	clear
	2.0	17.04	6.14	1362	0.58	-118.9	clear
	3.0	17.04	6.13	1361	0.53	-134.5	clear
3:15	4.0	17.32	6.12	1634	0.96	-152.3	clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

Slight fetid odors.
Purge line @ 12 feet bgs from TOC
600RPM's

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-2

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	12.15		
Depth of Well	20.00		
Depth to Water (from top of casing)	6.30		
Water Elevation (feet above msl)	5.85		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (μS/cm)	DO (mg/L)	ORP (meV)	Comments
12:44	1.0	18.82	6.37	1014	0.97	-156.1	Clear
	2.0	18.73	6.33	996	0.89	-161.5	Clear
	3.0	18.59	6.25	986	0.92	167.2	Clear
12:48	4.0	18.53	6.21	984	0.90	-170.2	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

Moderate hydrocarbon odors noted.
Purge line at 19' from TOC
600RPM's

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-3

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	10.40		
Depth of Well	20.00		
Depth to Water (from top of casing)	4.52		
Water Elevation (feet above msl)	5.88		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
1:36	1.0	17.79	5.96	1581	2.52	211.2	Clear
	2.0	17.95	5.93	1597	1.52	299.9	Clear
	3.0	17.87	5.90	1596	1.32	359.7	Clear
1:40	4.0	17.76	5.87	1592	1.72	412.8	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line @ 19 feet bgs from TOC
600RPM's

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-4

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	10.31		
Depth of Well	20.00		
Depth to Water (from top of casing)	4.47		
Water Elevation (feet above msl)	5.84		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (μS/cm)	DO (mg/L)	ORP (meV)	Comments
2:16	1.0	18.48	6.16	1426	3.00	73.6	Clear
	2.0	18.55	6.16	1423	2.94	71.3	Clear
	3.0	18.55	6.16	1421	2.92	70.1	Clear
2:20	4.0	18.52	6.16	1419	2.92	69.5	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line @ 18 feet bgs from TOC

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-6

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	12.35		
Depth of Well	14.00		
Depth to Water (from top of casing)	6.32		
Water Elevation (feet above msl)	6.03		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
12:08	1.0	17.31	6.00	1216	0.84	66.3	Clear
	2.0	17.33	6.07	1218	0.54	110.8	Clear
	3.0	17.33	6.12	1210	0.52	130.4	Clear
12:14	4.0	17.40	6.12	1202	1.23	137.8	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line @ 12 feet bgs from TOC

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-7

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	11.16		
Depth of Well	35.00		
Depth to Water (from top of casing)	4.69		
Water Elevation (feet above msl)	6.47		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (μS/cm)	DO (mg/L)	ORP (meV)	Comments
1:00	1.0	18.72	6.62	1845	11.96	-50.8	Clear
	2.0	18.74	6.62	1859	11.90	-44.1	Clear
	3.0	18.74	6.62	1862	11.98	-39.3	Clear
1:04	4.0	18.69	6.61	1860	11.91	-28.1	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line at 22 feet bgs from TOC
600rpm's

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-8

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	12.42		
Depth of Well	35.00		
Depth to Water (from top of casing)	6.16		
Water Elevation (feet above msl)	6.26		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Brown		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
12:26	1.0	18.84	6.20	2524	6.36	-38.3	Brown
	2.0	18.81	6.16	2523	6.31	-42.5	Brown
	3.0	18.81	6.15	2521	6.14	-42.1	Brown
12:32	4.0	18.81	6.11	2506	6.38	-38.6	Brown

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line @ 22 feet bgs from TOC

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-9

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	11.22		
Depth of Well	35.00		
Depth to Water (from top of casing)	5.42		
Water Elevation (feet above msl)	5.80		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (μS/cm)	DO (mg/L)	ORP (meV)	Comments
3:28	1.0	18.16	6.67	1311	12.99	3.3	Clear
	2.0	18.2	6.65	1311	13.17	10.5	Clear
	3.0	18.27	6.62	1306	13.28	14.9	Clear
3:34	4.0	18.30	6.61	1313	13.20	16.8	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line at 18.5 feet deep from TOC

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-10

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	10.31		
Depth of Well	35.00		
Depth to Water (from top of casing)	4.32		
Water Elevation (feet above msl)	5.99		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
1:53	1.0	17.99	6.21	1812	8.37	212.1	Clear
	2.0	18.09	6.28	1830	8.27	161.6	Clear
	3.0	18.08	6.29	1833	8.23	146.3	Clear
1:57	4.0	18.18	6.31	1840	8.20	124.3	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line @ 23 feet bgs from TOC

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-11

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	10.96		
Depth of Well	35.00		
Depth to Water (from top of casing)	4.45		
Water Elevation (feet above msl)	6.51		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
1:18	1.0	18.22	6.91	1282	12.32	-53.5	Clear
	2.0	18.43	6.94	1270	12.07	-50.3	Clear
	4.0	18.46	6.96	1267	12.05	-47.1	Clear
1:22	4.0	18.47	6.97	1265	11.95	-42.7	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

Purge line at 21 feet bgs from TOC
No hydrocarbon odors.
600 RPM's

AEI CONSULTANTS
GROUNDWATER MONITORING WELL FIELD SAMPLING FORM

Monitoring Well Number: MW-12

Project Name:	Omega Termite	Date of Sampling:	1/27/2009
Job Number:	262157	Name of Sampler:	A Nieto
Project Address:	807 75th Avenue Oakland		

MONITORING WELL DATA

Well Casing Diameter (2"/4"/6")	2		
Wellhead Condition	OK ▼		
Elevation of Top of Casing (feet above msl)	10.46		
Depth of Well	35.00		
Depth to Water (from top of casing)	3.89		
Water Elevation (feet above msl)	6.57		
Well Volumes Purged	Micropurge		
Actual Volume Purged (liters)	4.0		
Appearance of Purge Water	Clear		
Free Product Present?	No	Thickness (ft):	NA

GROUNDWATER SAMPLES

Number of Samples/Container Size				2 - 40ml VOAs, 1 L Amber			
Time	Vol Removed (liters)	Temperature (deg C)	pH	Conductivity (µS/cm)	DO (mg/L)	ORP (meV)	Comments
2:34	1.0	19.04	6.88	1113	12.10	67.4	Clear
	2.0	18.97	6.89	1108	12.20	68.8	Clear
	3.0	18.99	6.87	1104	12.26	70.1	Clear
2:38	4.0	18.98	6.85	1105	12.36	74.8	Clear

COMMENTS (i.e., sample odor, well recharge time & percent, etc.)

No hydrocarbon odors noted.
Purge line @ 22 feet bgs from TOC

APPENDIX B

LABORATORY ANALYTICAL AND CHAIN OF CUSTODY DOCUMENTATION





McC Campbell Analytical, Inc.

"When Quality Counts"

1534 Willow Pass Road, Pittsburg, CA 94565-1701
Web: www.mccampbell.com E-mail: main@mccampbell.com
Telephone: 877-252-9262 Fax: 925-252-9269

AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597	Client Project ID: #262157; Omega Termite	Date Sampled: 01/27/09
		Date Received: 01/27/09
	Client Contact: Robert Flory	Date Reported: 02/02/09
	Client P.O.:	Date Completed: 01/29/09

WorkOrder: 0901539

February 02, 2009

Dear Robert:

Enclosed within are:

- 1) The results of the **11** analyzed samples from your project: **#262157; Omega Termite,**
- 2) A QC report for the above samples,
- 3) A copy of the chain of custody, and
- 4) An invoice for analytical services.

All analyses were completed satisfactorily and all QC samples were found to be within our control limits.

If you have any questions or concerns, please feel free to give me a call. Thank you for choosing McC Campbell Analytical Laboratories for your analytical needs.

Best regards,

Angela Rydelius
Laboratory Manager
McC Campbell Analytical, Inc.

0901539

McCAMPBELL ANALYTICAL, INC.

1538 Willow Pass Road
Bay Point, CA 94565

Telephone: (925) 252-9262

Fax: (925) 252-9269

CHAIN OF CUSTODY RECORD

TURN AROUND TIME

RUSH 24 HR 48 HR 72 HR 5 DAY

GeoTracker EDF PDF Excel Write On (DW)

Report To: Robert Flory; Ricky Bradford Bill To: Same
Company: AEI Consultants
2500 Camino Diablo, Suite 200, Walnut Creek, CA 94597
E-Mail: rflory@aeiconsultants.com; rbradford@aeiconsultants.com
Tel: (925) 944-2899, ext. 122; ext. 148 Fax: (925) 944-2895
Project #: 262157 Project Name: Omega Termite
Project Location: 807 75th Avenue, Oakland, CA
Sampler Signature: *[Signature]*

Analysis Request

Other

Comments

TPH as gas w/ BTEX&MTBE (SW8021B/8015Cm)
TPH as diesel (SW8015C)
TPH as motor oil (SW8015C)
Total Petroleum Oil & Grease (5520 E&F/B&F)
Halogenated VOCs (SW8260B i.e., 8010 list)
BTEX ONLY I (SW8021B)
PCBs EPA 608 / 8080
Fuel Additives (SW8260B) inc., EDB, TCA
EPA 625 / 8270
PAH's / PNA's by EPA 625 / 8270 / 8310
CAM-17 Metals
LUFT 5 Metals
Lead (7240/7421/239.2/6010)
RCI

SAMPLE ID (Field Point Name)	LOCATION	SAMPLING		# Containers	Type Containers	MATRIX					METHOD PRESERVED									
		Date	Time			Water	Soil	Air	Sludge	Other	Ice	HCl	HNO ₃	Other						
MW-1		11/27/09	3:20	4	VIL	X	X					X	X							
MW-2			12:55			X						X	Y							
MW-3			1:50			X						X	Y							
MW-4			2:25			X						X	X							
MW-5						X						X	X							DAMAGED
MW-6			12:20			X						X	X							
MW-7			1:10			X						X	X							
MW-8			12:40			X						X	X							
MW-9			3:45			X						X	X							
MW-10			2:05			X						X	X							
MW-11			1:30			X						X	X							
MW-12			2:55			X						X	X							

MW-1 ✓
 MW-2 ✓
 MW-3 ✓
 MW-4 ✓
 MW-5 ✓
 MW-6 ✓
 MW-7 ✓
 MW-8 ✓
 MW-9 ✓
 MW-10 ✓
 MW-11 ✓
 MW-12 ✓

Relinquished By: <i>[Signature]</i>	Date: 01/27/10	Time: 8:20am	Received By: <i>[Signature]</i>
Relinquished By:	Date:	Time:	Received By:
Relinquished By:	Date:	Time:	Received By:

ICE/T 3.900 ✓
 GOOD CONDITION ✓
 HEAD SPACE ABSENT ✓
 DECHLORINATED IN LAB ✓
 PRESERVATION APPROPRIATE ✓
 CONTAINERS PRESERVED IN LAB ✓
 VOAS | O&G | METALS | OTHER

McC Campbell Analytical, Inc.



1534 Willow Pass Rd
Pittsburg, CA 94565-1701
(925) 252-9262

CHAIN-OF-CUSTODY RECORD

WorkOrder: 0901539

ClientCode: AEL

WriteOn
 EDF
 Excel
 Fax
 Email
 HardCopy
 ThirdParty
 J-flag

Report to: Robert Flory AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597 (925) 283-6000 FAX (925) 283-6121	Email: rflory@aeiconsultants.com cc: PO: ProjectNo: #262157; Omega Termite	Bill to: Denise Mockel AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597 dmockel@aeiconsultants.com	Requested TAT: 5 days Date Received: 01/27/2009 Date Printed: 01/27/2009
--	---	---	---

Lab ID	Client ID	Matrix	Collection Date	Hold	Requested Tests (See legend below)											
					1	2	3	4	5	6	7	8	9	10	11	12
0901539-001	MW-1	Water	1/27/2009 15:20	<input type="checkbox"/>	B	A	A									
0901539-002	MW-2	Water	1/27/2009 12:55	<input type="checkbox"/>	B		A									
0901539-003	MW-3	Water	1/27/2009 1:50	<input type="checkbox"/>	B		A									
0901539-004	MW-4	Water	1/27/2009 14:25	<input type="checkbox"/>	B		A									
0901539-005	MW-6	Water	1/27/2009 12:20	<input type="checkbox"/>	B		A									
0901539-006	MW-7	Water	1/27/2009 1:10	<input type="checkbox"/>	B		A									
0901539-007	MW-8	Water	1/27/2009 12:40	<input type="checkbox"/>	B		A									
0901539-008	MW-9	Water	1/27/2009 15:45	<input type="checkbox"/>	B		A									
0901539-009	MW-10	Water	1/27/2009 14:05	<input type="checkbox"/>	B		A									
0901539-010	MW-11	Water	1/27/2009 13:30	<input type="checkbox"/>	B		A									
0901539-011	MW-12	Water	1/27/2009 14:55	<input type="checkbox"/>	B		A									

Test Legend:

1	G-MBTX_W	2	PREDF REPORT	3	TPH(DMO)_W	4		5	
6		7		8		9		10	
11		12							

Prepared by: Samantha Arbuckle

Comments:

NOTE: Soil samples are discarded 60 days after results are reported unless other arrangements are made (Water samples are 30 days).
Hazardous samples will be returned to client or disposed of at client expense.



Sample Receipt Checklist

Client Name: **AEI Consultants** Date and Time Received: **01/27/09 8:26:56 PM**
Project Name: **#262157; Omega Termite** Checklist completed and reviewed by: **Samantha Arbuckle**
WorkOrder N°: **0901539** Matrix Water Carrier: Client Drop-In

Chain of Custody (COC) Information

Chain of custody present? Yes No
Chain of custody signed when relinquished and received? Yes No
Chain of custody agrees with sample labels? Yes No
Sample IDs noted by Client on COC? Yes No
Date and Time of collection noted by Client on COC? Yes No
Sampler's name noted on COC? Yes No

Sample Receipt Information

Custody seals intact on shipping container/cooler? Yes No NA
Shipping container/cooler in good condition? Yes No
Samples in proper containers/bottles? Yes No
Sample containers intact? Yes No
Sufficient sample volume for indicated test? Yes No

Sample Preservation and Hold Time (HT) Information

All samples received within holding time? Yes No
Container/Temp Blank temperature Cooler Temp: 3.9°C NA
Water - VOA vials have zero headspace / no bubbles? Yes No No VOA vials submitted
Sample labels checked for correct preservation? Yes No
TTLC Metal - pH acceptable upon receipt (pH<2)? Yes No NA
Samples Received on Ice? Yes No
(Ice Type: WET ICE)

* NOTE: If the "No" box is checked, see comments below.

Client contacted: Date contacted: Contacted by:

Comments:



McC Campbell Analytical, Inc.

"When Quality Counts"

1534 Willow Pass Road, Pittsburg, CA 94565-1701
Web: www.mcccampbell.com E-mail: main@mcccampbell.com
Telephone: 877-252-9262 Fax: 925-252-9269

AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597	Client Project ID: #262157; Omega Termite	Date Sampled: 01/27/09
	Client Contact: Robert Flory	Date Received: 01/27/09
	Client P.O.:	Date Extracted: 01/28/09-01/29/09
		Date Analyzed: 01/28/09-01/29/09

Gasoline Range (C6-C12) Volatile Hydrocarbons as Gasoline with BTEX and MTBE*

Extraction method SW5030B

Analytical methods SW8021B/8015Bm

Work Order: 0901539

Lab ID	Client ID	Matrix	TPH(g)	MTBE	Benzene	Toluene	Ethylbenzene	Xylenes	DF	% SS
001B	MW-1	W	74,d1	ND	11	1.1	ND	ND	1	99
002B	MW-2	W	380,d2,d9	ND	ND	7.1	0.50	ND	1	91
003B	MW-3	W	ND	ND	ND	ND	ND	ND	1	94
004B	MW-4	W	ND	ND	ND	ND	ND	ND	1	104
005B	MW-6	W	ND	ND	ND	ND	ND	ND	1	92
006B	MW-7	W	ND	ND	ND	ND	ND	ND	1	95
007B	MW-8	W	ND	ND	ND	ND	ND	ND	1	94
008B	MW-9	W	ND	ND	ND	ND	ND	ND	1	98
009B	MW-10	W	130,d6	ND	ND	ND	ND	ND	1	94
010B	MW-11	W	ND	ND	ND	ND	ND	0.58	1	97
011B	MW-12	W	ND	ND	ND	ND	ND	ND	1	95

Reporting Limit for DF =1; ND means not detected at or above the reporting limit	W	50	5	0.5	0.5	0.5	0.5	0.5	µg/L
	S	1.0	0.05	0.005	0.005	0.005	0.005	0.005	mg/Kg

* water and vapor samples and all TCLP & SPLP extracts are reported in ug/L, soil/sludge/solid samples in mg/kg, wipe samples in µg/wipe, product/oil/non-aqueous liquid samples in mg/L.

cluttered chromatogram; sample peak coelutes with surrogate peak.

+The following descriptions of the TPH chromatogram are cursory in nature and McC Campbell Analytical is not responsible for their interpretation:

- d1) weakly modified or unmodified gasoline is significant
- d2) heavier gasoline range compounds are significant (aged gasoline?)
- d6) one to a few isolated non-target peaks present in the TPH(g) chromatogram
- d9) no recognizable pattern



McC Campbell Analytical, Inc.

"When Quality Counts"

1534 Willow Pass Road, Pittsburg, CA 94565-1701
Web: www.mccampbell.com E-mail: main@mccampbell.com
Telephone: 877-252-9262 Fax: 925-252-9269

AEI Consultants 2500 Camino Diablo, Ste. #200 Walnut Creek, CA 94597	Client Project ID: #262157; Omega Termite	Date Sampled: 01/27/09
	Client Contact: Robert Flory	Date Received: 01/27/09
	Client P.O.:	Date Extracted: 01/27/09
		Date Analyzed: 01/27/09-01/29/09

Total Extractable Petroleum Hydrocarbons*

Extraction method: SW3510C

Analytical methods: SW8015B

Work Order: 0901539

Lab ID	Client ID	Matrix	TPH-Diesel (C10-C23)	TPH-Motor Oil (C18-C36)	DF	% SS
0901539-001A	MW-1	W	220,e2	ND	1	105
0901539-002A	MW-2	W	140,e4,e2	ND	1	100
0901539-003A	MW-3	W	ND	ND	1	94
0901539-004A	MW-4	W	ND	ND	1	106
0901539-005A	MW-6	W	ND	ND	1	107
0901539-006A	MW-7	W	ND	ND	1	110
0901539-007A	MW-8	W	ND	ND	1	109
0901539-008A	MW-9	W	100,e2	ND	1	108
0901539-009A	MW-10	W	ND	ND	1	109
0901539-010A	MW-11	W	ND	ND	1	103
0901539-011A	MW-12	W	ND	ND	1	103

Reporting Limit for DF =1; ND means not detected at or above the reporting limit	W	50	250	µg/L
	S	NA	NA	mg/Kg

* water samples are reported in µg/L, wipe samples in µg/wipe, soil/solid/sludge samples in mg/kg, product/oil/non-aqueous liquid samples in mg/L, and all DISTLC / STLC / SPLP / TCLP extracts are reported in µg/L.

cluttered chromatogram resulting in coeluted surrogate and sample peaks, or; surrogate peak is on elevated baseline, or; surrogate has been diminished by dilution of original extract.

+The following descriptions of the TPH chromatogram are cursory in nature and McC Campbell Analytical is not responsible for their interpretation:

e2) diesel range compounds are significant; no recognizable pattern

e4) gasoline range compounds are significant.



QC SUMMARY REPORT FOR SW8021B/8015Cm

W.O. Sample Matrix: Water

QC Matrix: Water

BatchID: 41042

WorkOrder 0901539

Analyte	EPA Method SW8021B/8015Bm		Extraction SW5030B						Spiked Sample ID: 0901532-003B			
	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance Criteria (%)			
	µg/L	µg/L	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	MS / MSD	RPD	LCS/LCSD	RPD
TPH(btex) [£]	ND	60	93.7	97.5	3.95	115	110	4.22	70 - 130	20	70 - 130	20
MTBE	ND	10	89.8	91	1.39	105	108	3.16	70 - 130	20	70 - 130	20
Benzene	ND	10	91.6	96.1	4.77	91.8	95	3.41	70 - 130	20	70 - 130	20
Toluene	ND	10	91.3	96.1	5.14	95.2	96.6	1.50	70 - 130	20	70 - 130	20
Ethylbenzene	ND	10	95.5	100	5.03	96.7	96.3	0.476	70 - 130	20	70 - 130	20
Xylenes	ND	30	106	111	4.95	109	108	0.805	70 - 130	20	70 - 130	20
%SS:	101	10	92	93	0.566	92	103	10.8	70 - 130	20	70 - 130	20

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:
NONE

BATCH 41042 SUMMARY

Lab ID	Date Sampled	Date Extracted	Date Analyzed	Lab ID	Date Sampled	Date Extracted	Date Analyzed
0901539-001B	01/27/09 3:20 PM	01/28/09	01/28/09 10:38 PM	0901539-002B	01/27/09 12:55 PM	01/28/09	01/28/09 11:11 PM
0901539-003B	01/27/09 1:50 AM	01/28/09	01/28/09 11:44 PM	0901539-004B	01/27/09 2:25 PM	01/29/09	01/29/09 12:17 AM
0901539-005B	01/27/09 12:20 PM	01/29/09	01/29/09 12:51 AM	0901539-006B	01/27/09 1:10 AM	01/29/09	01/29/09 1:24 AM
0901539-007B	01/27/09 12:40 PM	01/29/09	01/29/09 1:57 AM	0901539-008B	01/27/09 3:45 PM	01/29/09	01/29/09 2:30 AM
0901539-009B	01/27/09 2:05 PM	01/29/09	01/29/09 7:44 PM	0901539-010B	01/27/09 1:30 PM	01/29/09	01/29/09 5:48 AM
0901539-011B	01/27/09 2:55 PM	01/29/09	01/29/09 6:21 AM				

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 * (MS-Sample) / (Amount Spiked); RPD = 100 * (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

£ TPH(btex) = sum of BTEX areas from the FID.

cluttered chromatogram; sample peak coelutes with surrogate peak.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = matrix interference and/or analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content, or inconsistency in sample containers.



QC SUMMARY REPORT FOR SW8015B

W.O. Sample Matrix: Water

QC Matrix: Water

BatchID: 41068

WorkOrder: 0901539

Analyte	Extraction SW3510C			Spiked Sample ID: N/A								
	Sample µg/L	Spiked µg/L	MS % Rec.	MSD % Rec.	MS-MSD % RPD	LCS % Rec.	LCSD % Rec.	LCS-LCSD % RPD	Acceptance Criteria (%)			
TPH-Diesel (C10-C23)	N/A	1000	N/A	N/A	N/A	98.8	100	1.54	N/A	N/A	70 - 130	30
%SS:	N/A	2500	N/A	N/A	N/A	101	103	1.39	N/A	N/A	70 - 130	30

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:
NONE

BATCH 41068 SUMMARY

Lab ID	Date Sampled	Date Extracted	Date Analyzed	Lab ID	Date Sampled	Date Extracted	Date Analyzed
0901539-001A	01/27/09 3:20 PM	01/27/09	01/29/09 9:02 AM	0901539-002A	01/27/09 12:55 PM	01/27/09	01/28/09 8:36 PM
0901539-003A	01/27/09 1:50 AM	01/27/09	01/27/09 11:36 PM	0901539-004A	01/27/09 2:25 PM	01/27/09	01/28/09 2:55 AM
0901539-005A	01/27/09 12:20 PM	01/27/09	01/28/09 4:01 AM	0901539-006A	01/27/09 1:10 AM	01/27/09	01/28/09 5:07 AM
0901539-007A	01/27/09 12:40 PM	01/27/09	01/28/09 6:12 AM	0901539-008A	01/27/09 3:45 PM	01/27/09	01/28/09 7:18 AM
0901539-009A	01/27/09 2:05 PM	01/27/09	01/28/09 8:24 AM	0901539-010A	01/27/09 1:30 PM	01/27/09	01/28/09 12:29 PM
0901539-011A	01/27/09 2:55 PM	01/27/09	01/28/09 11:21 AM				

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 * (MS-Sample) / (Amount Spiked); RPD = 100 * (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.