

WEST
ASSOCIATES
ENVIRONMENTAL ENGINEERS, INC.

June 27, 1997

Alameda County Health Care Services Agency
Department of Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, CA 94502-6577
Attn: Ms. Juliet Shin
Hazardous Materials Specialist

**SUBJECT: SUBMITTAL OF QUARTERLY GROUNDWATER MONITORING REPORT,
WEYERHAEUSER PAPER COMPANY, ALAMEDA CORRUGATED BOX FACILITY,
1801 HIBBARD STR., STID 1202**


Dear Ms. Shin,

West & Associates Environmental Engineers, Inc. respectfully submits the second quarter 1997 groundwater monitoring report for the Weyerhaeuser Paper Company, Alameda Corrugated Box Facility. The monitoring report is submitted in accordance with the interim groundwater monitoring plan proposed in our Site Investigation Report of January 1995.

Groundwater samples were analyzed in accordance with the new analytical schedule defined in your May 14, 1996 response letter. This quarter MW-7 was analyzed for chlorinateds (EPA 624) and semi-volatiles (EPA 625) in addition to TPH-diesel as requested in your letter dated June 10, 1997.

We look forward to your review of the attached report. Should you require any additional information please contact me at (707) 451-1360.

Yours truly,


Brennan Mahoney APSS
Project Manager
West & Associates Environmental Engineers, Inc.

Enclosure: Groundwater Monitoring Report

cc: Ed Granados, Weyerhaeuser Office of the Environment, Tacoma
John Hipner, WPC Alameda

**QUARTERLY GROUNDWATER MONITORING REPORT
FORMER UNDERGROUND TANK SITES
APRIL - JUNE 1997**

**WEYERHAEUSER PAPER COMPANY
ALAMEDA CORRUGATED BOX FACILITY
1801 Hibbard Street
Alameda, California
STID 1202**

Submitted to:

**ALAMEDA COUNTY
HEALTH CARE SERVICES AGENCY
DEPARTMENT OF ENVIRONMENTAL HEALTH
Alameda**

Prepared for:

**THE WEYERHAEUSER CORPORATION
OFFICE OF THE ENVIRONMENT
TOXIC/SOLID WASTE TEAM
Tacoma, Washington**

Prepared by:

**WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC.
Vacaville**

June 1997

EXECUTIVE SUMMARY

The Weyerhaeuser Paper Company (WPC) Alameda containerboard facility, at 1801 Hibbard Str., is a corrugated box manufacturing plant. The facility was originally constructed in 1946. Underground fuel tanks had been historically installed at the facility for vehicle, generator and boiler fuel storage. Both gasoline and diesel fuels were formerly stored underground. The last remaining underground tank was removed from the WPC site in January 1994.

The WPC facility is located on Alameda island in San Francisco Bay. The site is less than 0.25 miles west of the Oakland Inner Harbor. Site soils are predominantly sand with minor clay stringers. Unconfined groundwater is 3-6 feet below ground surface and tidally influenced.

There are two separate groundwater study areas at the WPC Alameda site. A former diesel tank site is monitored by one groundwater well (MW-7) on the east side of the property. A former gasoline tank cluster is monitored by seven monitoring wells on west side of the property. Monitoring wells MW-1 through MW-7 were installed by Soil Tech Engineers. Monitoring wells MW-9 through MW-12, MW-3B and MW-4B were installed by West & Associates.

Site investigation at the WPC Alameda facility was concluded in January 1995 with the submittal of a comprehensive report covering all work dating back to 1990. Activity at the site has now shifted to remedial action. In October and November of 1995 contaminated soil was excavated from the site around the former gasoline tank cluster and air sparging lines were installed in the open excavations prior to backfill. A pilot test was performed to evaluate the effectiveness of the newly installed sparging system. Based on results of the pilot test, continuous operation of the sparging system was initiated on March 29, 1996.

During the remedial excavation program monitoring wells MW-1, MW-2, MW-3, MW-4 and MW-9 were removed. In December 1995 two new wells MW-3B and MW-4B were installed in two locations within the newly backfilled excavation area, near the former locations of MW-3 and MW-4, respectively. A total of eight monitoring wells now exist at the site.

A groundwater monitoring program is in effect at the WPC Alameda site. Groundwater monitoring, which consists of depth to groundwater measurements and collection of groundwater samples for chemical analysis, is conducted quarterly. Second quarter groundwater monitoring activities for 1997 were conducted on June 6, 1997.

In correspondence dated May 14, 1996, Alameda County, Environmental Health Services (ACEHS) approved a modified analytical schedule proposed by West & Associates in the March 1996 Quarterly Groundwater Monitoring Report. The frequency of EPA Method 624 and 625 analysis for groundwater samples has been revised from quarterly to semi-annual. Groundwater samples were not analyzed by EPA Method 624 and 625 this quarter.

ACKNOWLEDGEMENTS

This report was prepared under authorization of the Weyerhaeuser Corporation, Office of the Environment, Toxic/Solid Waste Team, Tacoma, Washington. The Weyerhaeuser project officer is Mr. Ed Granados, mail stop CH 1K29, Tacoma, WA 98477; (206) 924-6511.

At the WPC plant, both Mr. John Hipner, Plant Engineer and Mr. Tom Muncell, Maintenance Manager, have environmental compliance responsibilities related to this project. The Alameda plant address is 1801 Hibbard Street, PO Drawer X, Alameda, CA 95601; (510) 814-1167.

The lead regulatory agency for the Weyerhaeuser Alameda plant is the Alameda County Health Care Agency, Department of Environmental Health. Ms. Juliet Shin, Hazardous Materials Specialist, is the staff person assigned. The Department of Environmental Health is located at 1131 Harbor Bay Parkway, Suite 250, Alameda, CA 94502-6577; (510) 567-6763.

In the preparation of this quarterly report reliance was made on past site work performed by Soil Tech Engineering, Inc. Soil Tech Engineering is located at 298 Brokaw Road, Santa Clara, CA 95050; (408) 496-0265.

Analytical work performed for this quarters monitoring was sub-contracted to Excelchem Environmental Labs located in Roseville, California. Excelchem is certified by the State Department of Health Services for the analyses performed.

This quarterly groundwater monitoring report was prepared by West & Associates Environmental Engineers, Inc. West & Associates is located at 490 Merchant St., Suite 104, Vacaville, CA 95688; mailing address, PO Box 5891, Vacaville 95696; (707) 451-1360. Principal authors are Mr. Brennan Mahoney APSS and Mr. Brian W. West PE. (Registered California Civil Engineer No. 32319 - expires 12/31/00).



TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
EXECUTIVE SUMMARY	i
ACKNOWLEDGEMENTS	ii
TABLE OF CONTENTS	iii
1.0 INTRODUCTION	1
1.1 Scope	1
1.2 Summarized Background	1
2.0 FLOATING PRODUCT	5
3.0 GROUNDWATER SAMPLING	5
3.1 Sampling Protocol	5
3.2 Sample Analyses	6
3.3 Conclusions	8
4.0 HYDROLOGIC MONITORING	21
4.1 Conclusions	21
5.0 SUMMARY	23
5.1 Remedial Status	23

APPENDICES

Purge Data Forms
Chain of Custody
Original Laboratory Report Forms

1.0 INTRODUCTION

Groundwater conditions are periodically monitored at the Weyerhaeuser Paper Company Alameda Containerboard plant based on a schedule proposed to the Alameda County Environmental Health Agency in January 1995 (and amended in May 1996). This report presents results of groundwater monitoring performed during the second quarter (April - June) of 1997.

This quarter, groundwater monitoring was performed on June 6, 1997. During groundwater sampling activities, all eight of the existing monitoring wells were inspected for the presence of floating product, measured for depth to groundwater and samples collected for chemical analysis.

In the following Sections, monitoring procedures are described, monitoring data is summarized and a discussion of results are presented. Technical data is included in the appendix.

1.1 Scope

The scope of this project included performing quarterly groundwater monitoring at Weyerhaeuser Paper Company (WPC) Alameda property, 1801 Hibbard Str., in Alameda. Figure 1 illustrates the WPC Alameda regional setting. Figure 2 depicts the site location. Specific scope items include:

- Check eight existing monitoring wells for floating product
- Measure depth to groundwater in all monitoring wells
- Determine the groundwater gradient profile
- Collect groundwater samples from all eight monitoring wells
- Analyze groundwater samples for contaminants of interest
- Prepare a written report of findings
- Properly manage sampling residues

1.2 Summarized Background

The Weyerhaeuser Paper Company (WPC) Alameda facility located at 1801 Hibbard Str. manufactures corrugated cardboard boxes. The facility was originally constructed in 1946. Underground fuel tanks (UGT) had been historically installed at the facility for vehicle, generator and boiler fuel storage. Both gasoline and diesel fuels were formerly stored. The last remaining UGT was removed from the WPC site in January 1994.

At the end of 1990 the WPC facility was equipped with five underground fuel storage tanks. The five tanks were distributed in three separate installations located along the northwestern side of the facility.

In early 1991 Weyerhaeuser removed a cluster of three, 1,000 gallon gasoline tanks and one, 10,000 gallon diesel tank. Upon removal, the 10,000 gallon diesel tank installation was found to be virtually uncontaminated, however, significant soil and groundwater contamination was encountered at the gasoline tank cluster location.

WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC.

PO Box 5891, Vacaville, California 95696



Project Name: Weyerhaeuser Paper Company - Alameda

Date: Jan. 1995

Location: 1801 Hibbard Str., Alameda, California 94501

Drawing By: BWB

Scale: 1" = 2.5 miles



LEGEND

WPC ALAMEDA FACILITY - REGIONAL SETTING
○ SITE LOCATION

Figure 1

WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC.

PO Box 5891, Vacaville, California 95696


Project Name: Weyerhaeuser Paper Company - Alameda

Date: Jan. 1995

Location: 1801 Hibbard Str., Alameda, California 94501

Drawing By: BWB

Scale: 1" = 0.4 Miles



LEGEND

Figure 2

WPC ALAMEDA FACILITY - SITE LOCATION

○ SITE LOCATION

The tank removal contractor performed overexcavation at the gasoline tank cluster location in an attempt to remediate soil contamination. Between February and April 1991 the tank excavation was enlarged from 460 ft² to 640 ft² and then to 930 ft².

Four soil samples were collected from the gasoline tank cluster pit sidewalls at the conclusion of overexcavation. Only one endpoint sidewall soil sample (Sample No. 11) was non-detectable for all tested chemical constituents. One of the sidewall soil samples (Sample No. 9) was found to contain only trace levels of toluene. The other two endpoint soil samples (Sample No.'s 8 & 10), were found to contain low levels of TPH and BTXE compounds.

During the time the gasoline tank cluster excavation was open, the standing groundwater level in the pit was observed to rise from greater than 8 feet to less than 4 feet below ground surface. The file record indicates endpoint soil samples were collected from higher on the pit sidewalls as the water level rose.

Both the gasoline tank cluster and diesel tank excavations were backfilled with clean fill. Contaminated soil was transported to off-site disposal.

In December 1991 and again in April 1992, Soil Tech Engineering performed soils and groundwater investigations near the former gasoline tank cluster. A total of six groundwater monitoring wells were installed. Soil samples for laboratory analysis were collected during monitoring well installation. Between December 1991 and July 1993 Soil Tech performed groundwater monitoring on six occasions.

In December 1992, Soil Tech constructed one monitoring well (MW-7) adjacent to the former underground diesel tank, increasing the total number of site wells to seven. STE monitored MW-7 a total of 3 times.

Soil Tech's investigations revealed significant remaining soil contamination as well as widespread groundwater contamination in the vicinity of the former gasoline tank cluster. The six soil borings and monitoring wells completed by STE did not fully define the total extent of either soil or groundwater contamination around the former gasoline tank cluster.

In January 1994 the last remaining underground fuel storage tank, (20,000 gallon diesel) was removed from the WPC property. No evidence of any leakage from the diesel tank was encountered, however, soil contamination from the 1991 gasoline tank cluster was observed on the east sidewall of the diesel tank pit.

West & Associates Environmental Engineers submitted a proposed workplan for additional site investigation to the Alameda County Health Care Agency in November 1993. Site investigations were performed in January and February 1994. In May 1994 a supplemental workplan was submitted to conduct further investigation under the main plant building. In June 1994 an interim report of findings was submitted and in October 1994

clarifications to the May supplemental workplan were submitted to the County. Final site investigation field work took place in September and December 1994.

In October and November 1995 contaminated soil was excavated from the site around the former gasoline tank cluster and air sparging lines were installed in the open excavations prior to backfill. Some of the contaminated soil was aerated on site and reused as backfill material and some was transported to a local landfill for disposal.

During the remedial excavation program monitoring wells MW-1, MW-2, MW-3, MW-4 and MW-9 were removed. In December 1995 two new wells MW-3B and MW-4B were installed in two locations within the newly backfilled excavation area, near the former locations of MW-3 and MW-4, respectively. Subsequent to completion of a pilot test, operation of the groundwater sparging system began in late March 1996.

2.0 FLOATING PRODUCT

This quarter, each monitoring well was visually inspected for the presence of floating product. Prior to well purging, a column of groundwater was bailed from the water surface in a transparent bailer suitable for capture of light hydrocarbons.

No floating product or sheen was detected in any of the groundwater wells inspected this quarter. No floating product has been observed in any WPC Alameda wells on previous monitoring occasions.

3.0 GROUNDWATER SAMPLING

A quantity of groundwater is purged from each monitoring well prior to collecting a sample for chemical analysis. A description of equipment and procedures employed for groundwater purging and sample collection is presented in the following paragraphs.

3.1 Sampling Protocol

All the WPC Alameda monitoring wells are equipped with a 0.5 inch OD polyethylene tube extending the full depth of the well. Well purging is accomplished by attaching an Accuwell PTP-150 peristaltic pump at the well head to draw groundwater from the well. This procedure eliminates the need for any downhole equipment.

As groundwater is extracted from the well, 20ml samples are periodically collected for measurement of pH, temperature and conductivity using a Hydac instrument. Groundwater data is recorded on purge data forms (presented in the Appendix). At the conclusion of purging, the well is allowed to recharge to at least 80% of its initial water level prior to sample collection.

Purge water is contained in 55 gallon drums during the sampling process. At the conclusion of sampling, purge water drums are sealed, labeled and stored on-site in a secure area pending chemical analysis and arrangements for proper disposal.

Groundwater sample collection is performed by lowering a new, disposable, bailer into the well. Sample water is transferred to a laboratory supplied 40 ml VOA bottle containing a suitable preservative. The sample bottles are only opened during sample transfer, are completely filled and are not re-opened again by field personnel.

All samples are immediately labeled, sealed in zip lock bags and placed in a cooler containing crushed ice. The samples remain chilled, sealed and undisturbed during transport to the testing laboratory, usually within no more than 48 hours. All samples are entered on a chain of custody form which accompanies the sample set at all times.

Chemical analysis was performed by Excelchem Environmental Labs, located in Roseville, California. Excelchem is certified by the Department of Health Services for the analyses performed.

Quality assurance and quality control measures include:

- Utilizing State WQCB approved sampling methods
- Assigning trained, experienced personnel for sample collection
- Utilizing laboratory supplied sample containers
- Employing extraction methods not requiring downhole equipment
- Using new, disposable bailers
- Sampling wells sequentially from cleanest to most contaminated
- Maintaining sample chain of custody documentation
- Keeping samples in a chilled state until laboratory delivery
- Storing high concentration samples in a separate container
- Prompt delivery of the sample set to the testing laboratory
- Utilizing a DHS certified laboratory

3.2 Sample Analyses

The present analytical schedule for the site was proposed by West & Associates in the March 1996 Quarterly Groundwater Monitoring Report and approved by the ACEHS in correspondence dated May 14, 1996. The frequency of EPA Method 624 and 625 analysis for groundwater samples has been changed from quarterly to semi-annual. Analysis of groundwater samples by EPA Methods 624 and 625 was not conducted this quarter.

Each groundwater sample except MW-7 was analyzed for Total Petroleum Hydrocarbons in the gasoline range (TPH-g) by modified EPA method 8015 along with BTXE and MTBE by EPA method 602. Groundwater from monitoring well MW-7 was analyzed for TPH in the diesel range by modified EPA method 8015.

In a letter dated June 10, 1997, ACEHS requested that MW-7 be analyzed for chlorinateds and semi-volatile organic compounds (SVOCs) in addition to TPH-diesel during the next sampling event. The water sample from MW-7 this quarter was analyzed for both chlorinateds and SVOCs, by EPA methods 624 and 625 respectively, in addition to TPH-diesel.

All analyses were performed using EPA approved test methods. Minimum detection limits for all analyses were within Tri-regional guidelines and are indicated on each original laboratory report form.

Results

This quarters analytical results for TPH-g and BTXE contamination are presented in Table 1. Copies of original laboratory data sheets and chain of custody forms are presented in the appendix.

Results of laboratory analysis indicate that TPH as diesel was detected in groundwater sample MW-7 at a concentration of 0.318 mg/l. No chlorinateds or SVOCs were detected in MW-7.

Laboratory results indicate that MTBE was not detected above laboratory detection limits in samples MW-3B, MW-4B, MW-5, MW-6, MW-10, MW-11 and MW-12.

TABLE 1
PETROLEUM CONTAMINATION ANALYSES - GROUNDWATER
June 6, 1997
All Values in ug/l

WELL ID	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
MW-3B	2,030	293	14	33	23
MW-4B	177	3.5	4.3	6.7	1.0
MW-5	ND	0.7	ND	0.5	ND
MW-6	ND	0.5	ND	ND	ND
MW-10	ND	ND	ND	ND	ND
MW-11	ND	ND	ND	ND	ND
MW-12	ND	ND	ND	ND	ND

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

TPH: Total Petroleum Hydrocarbons

3.3 Conclusions

TPH concentrations were lower in monitoring wells MW-3B, MW-4B, MW-5, MW-6 and MW-7 this quarter relative to last quarter. Benzene concentrations were lower in monitoring wells MW-3B and MW-6, and slightly higher in wells MW-4B and MW-5 this quarter, compared to last quarter. Neither TPH-gas nor BTXE were detected in monitoring wells MW-10, MW-11 or MW-12 this quarter. Contaminant concentrations detected in all contaminated wells this quarter are within the range of previous fluctuation observed at the site, during recent monitoring events, except for well MW-3B which had the lowest TPH and BTXE levels ever detected in this well.

TPH-gas and BTXE concentrations remain very low in all existing monitoring wells except for MW-3B.

A continued decreasing trend in TPH-g and BTXE concentrations in MW-3B has been observed since air sparging began in monitoring well 3B.

Table 2 presents the percent reduction in TPH-gas and benzene concentrations in well MW-3B compared to the previous five quarters. MW-3B has historically been the most contaminated well at the site.

TABLE 2
GROUNDWATER CONTAMINANT COMPARISON: WELL MW-3B
FIRST QUARTER 1996 THRU SECOND QUARTER 1997
All Values in ug/l

Date	TPH (gas)	BENZENE	PERCENT REDUCTION TPH-gas (since 2/96)	PERCENT REDUCTION BENZENE (since 2/96)
2/96	19,000	2,100	NA	NA
6/96	11,000	1,300	42%	38%
9/96	6,000	840	68%	60%
11/96	5,500	440	71%	79%
2/97	12,000	1,000	37%	52%
6/97	2,030	293	89%	86%

ABBREVIATIONS

ug/l: Micrograms per liter
TPH: Total Petroleum Hydrocarbons

Figures 3 and 4 graphically depict the declining trend of benzene and TPH-gas in well MW-3B since the onset of remedial activity. Both the actual monitoring data and the best fit curve (based on the method of least squares) are presented. Since beginning active remediation, benzene concentrations have been reduced 86% and TPH-gas concentrations have been reduced 89%.

FIGURE 3
WPC ALAMEDA
MW-3B BENZENE





FIGURE 4
WPC ALAMEDA
MW-3B TPH-gas



Groundwater samples from MW-7 were analyzed for chlorinateds & SVOCs in on two occasions, February 3, 1994 and June 13, 1997. On both occasions no chlorinateds or SVOCs were detected. Laboratory results from both of these sample events are presented in the appendix.

Monitoring well MW-7 is over 750 feet from the former forklift maintenance area where solvent contamination has been previously detected. The area around MW-7 has, for at least the past 15 years, been used for storage only. The groundwater gradient is generally to the west, consequently MW-7 is tangential to the expected direction of solvent migration from the former forklift maintenance area.

The location of MW-7 and the Oakland Inner Channel relative to the former forklift maintenance area is presented on Figure 5. Based on the absence of a local solvent contaminant source, the improbability of solvent migration from the former forklift maintenance area to the MW-7 area and the non-detectable solvent concentrations measured in 1994 and 1997, it is concluded that the MW-7 area is not solvent contaminated and there is no threat of contaminant migration to the Oakland Inner Harbor.

Additional testing of groundwater samples from MW-7 for chlorinated solvents is not recommended.

A summary of historic groundwater contaminant concentrations is presented in Table 3 through Table 5.



TABLE 3
SUMMARY OF PETROLEUM CONTAMINATION ANALYSES
All Values in ug/l

MONITORING WELL MW-2

(removed in 1995)

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
12/23/91	2,300	720	66	240	1.5
4/27/92	1,100	9.4	5.3	24	2
7/31/92	1,500	3.3	5.3	26	10
1/8/93	70	ND	ND	1.4	0.5
4/6/93	ND	ND	ND	ND	ND
7/12/93	1,600	1.4	2.3	8.2	2.5
2/94	200	390	25	50	7.1
6/94	1,300	370	44	170	100
12/94	3,400	1,100	86	190	28
3/7/95	6,500	2,300	240	310	120
9/26/95	440	140	26	46	52

OAKLAND
INNER CHANNEL



WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC. P.O. BOX 5891, VACAVILLE, CA 95696	
SHEET NAME	
<h2 style="margin: 0;">SITE DIAGRAM</h2>	
PROJECT: WEYERHAEUSER-ALAMEDA	
APPROVED BY:	DRAWN BY: BGM
	REVISED
SCALE: 1"=100'	SHEET NUMBER
DATE: JUNE 1997	<h2 style="margin: 0;">FIGURE 5</h2>

TABLE 3 CONTINUED - MONITORING WELL MW-3

(removed in 1995)

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
12/23/91	14,000	3,000	540	1,200	370
4/27/92	9,400	57	50	220	4.6
7/31/92	1,400	1.9	5.1	23	8.3
1/8/93	15,000	38	40	140	64
4/6/93	21,000	62	76	200	84
7/12/93	22,000	22	41	120	42
2/94	5,400	3,900	680	840	390
6/94	23,000	8,500	1,700	3,800	1,600
12/94	41,000	9,900	2,900	3,500	1,400
3/7/95	42,000	9,900	3,000	4,100	1,600
9/26/95	24,000	5,300	1,200	2,200	940

TABLE 3 CONTINUED - MONITORING WELL MW-3B

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
2/7/96	19,000	2,100	380	1,200	480
6/5/96	11,000	1,300	250	860	370
9/4/96	6,000	840	98	410	140
11/21/96	5,500	440	31	140	50
2/13/97	12,000	1,000	210	690	120
6/6/97	2,030	293	14	33	23

TABLE 3 CONTINUED - MONITORING WELL MW-4

(removed in 1995)

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
4/27/92	790	7.7	2.6	11	2
7/31/92	1,300	6.1	4.3	21	7.3
1/8/93	860	1.5	4.5	17	9.6
4/6/93	2,500	5.2	6.3	17	11
7/12/93	2,000	1.8	3.8	11	3.9
2/94	1,000	54	2.7	4.7	1.4
6/94	460	46	0.8	8.4	1.1
12/94	2,400	200	7.5	28	7.5
3/7/95	3,800	360	14	49	33
9/26/95	2,900	90	ND	5.7	8.9

TABLE 3 CONTINUED - MONITORING WELL MW-4B

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
2/7/96	520	3	2.4	1.0	1.6
6/5/96	350	ND	ND	ND	1.6
9/4/96	71	3.3	ND	0.70	1.8
11/21/96	170	1.5	ND	ND	1.0
2/13/97	220	ND	ND	ND	ND
6/6/97	177	3.5	4.3	6.7	1.0

TABLE 3 CONTINUED - MONITORING WELL MW-5

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
4/27/92	ND	ND	ND	ND	ND
7/31/92	ND	ND	ND	ND	ND
1/8/93	ND	ND	ND	ND	ND
4/6/93	ND	ND	ND	ND	ND
7/12/93	0.27	ND	ND	1.4	0.6
2/94	ND	1.8	ND	ND	ND
6/94	ND	1.0	ND	ND	ND
12/94	93	3.0	0.9	3.0	0.8
3/7/95	79	2.9	ND	ND	ND
9/26/95	67	ND	ND	ND	ND
2/7/96	120	7	ND	ND	ND
6/5/96	100	ND	ND	ND	ND
9/4/96	ND	2.4	ND	ND	ND
11/21/96	62	ND	ND	ND	ND
2/13/97	26	0.58	ND	ND	ND
6/6/97	ND	0.7	ND	0.5	ND

TABLE 3 CONTINUED - MONITORING WELL MW-6

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
4/27/92	ND	ND	ND	ND	ND
7/31/92	ND	ND	ND	ND	ND
1/8/93	ND	ND	ND	ND	ND
4/6/93	ND	ND	ND	ND	ND
7/12/93	NA	NA	NA	NA	NA
2/94	ND	2.6	ND	ND	ND
6/94	ND	2.2	ND	ND	ND
12/94	ND	1.3	ND	ND	ND
3/7/95	72	2.5	ND	ND	ND
9/26/95	ND	ND	ND	ND	ND
2/7/96	60	0.84	ND	ND	ND
6/5/96	45	1.2	ND	ND	ND
9/4/96	40	0.80	ND	ND	ND
11/21/96	ND	ND	ND	ND	ND
2/13/97	25	0.54	ND	ND	ND
6/6/97	ND	0.5	ND	ND	ND

TABLE 3 CONTINUED - MONITORING WELL MW-7

DATE	TPH diesel	TPH gas	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
1/8/93	ND	NA	ND	ND	ND	ND
4/6/93	190	NA	ND	ND	ND	ND
7/12/93	80	NA	ND	ND	ND	ND
2/94	ND	ND	ND	ND	ND	ND
6/94	ND	ND	ND	ND	ND	ND
12/94	3.9	ND	ND	ND	ND	ND
3/7/95	1,400	NA	NA	NA	NA	NA
9/26/95	1,100	NA	NA	NA	NA	NA
2/7/96	1,200	NA	NA	NA	NA	NA
6/5/96	1,100	NA	NA	NA	NA	NA
9/4/96	ND	NA	NA	NA	NA	NA
11/21/96	2.2	NA	NA	NA	NA	NA
2/13/97	3.8	NA	NA	NA	NA	NA
6/6/97	318	NA	NA	NA	NA	NA

TABLE 3 CONTINUED - MONITORING WELL MW-9

(removed in 1995)

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
2/94	1,900	63	4.3	14	22
6/94	5,300	150	20	110	380
12/94	12,000	600	20	55	120
3/7/95	9,900	820	22	78	230
9/26/95	5,900	340	ND	20	53

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

NA: Not Analyzed

TPH: Total Petroleum Hydrocarbons

TABLE 4
SUMMARY OF VOLATILE ORGANIC ANALYSES RESULTS
All Values in ug/l

MONITORING WELL MW-3

DATE	VINYL CHLORIDE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	CARBON DISULFIDE
2/94	ND	130	95	120
3/7/95	81	110	150	ND
9/26/95	ND	100	ND	ND

TABLE 4 CONTINUED - MONITORING WELL MW-3B

DATE	VINYL CHLORIDE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	1,1,2-TRICHLORO-ETHANE
2/7/96	ND	ND	ND	ND
9/4/96	ND	30	5.0	ND
2/13/97	ND	21	33	60

TABLE 4 CONTINUED - MONITORING WELL MW-4

DATE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	TRICHLOROETHENE	CARBON DISULFIDE	CHLORO-ETHANE
2/94	22	18	2.1	4.7	1.9
3/7/95	11	15	ND	ND	ND
9/26/95	10	6.6	ND	ND	ND

TABLE 4 CONTINUED - MONITORING WELL MW-4B

DATE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	TETRACHLORO-ETHENE	TRICHLORO-ETHENE
2/7/96	7.4	6.2	ND	ND
9/4/96	15	13	ND	1.2
2/13/97	12	10	1.8	1.48

TABLE 4 CONTINUED - MONITORING WELL MW-5

DATE	1,1-DICHLORO-EHTANE	1,2-DICHLORO-ETHANE	1,1-DICHLORO-ETHENE	TETRA-CHLORO-ETHENE	TRICHLORO-ETHENE
2/94	11	ND	ND	1.1	ND
3/7/95	24	ND	ND	ND	ND
9/26/95	31	ND	ND	ND	ND
2/7/96	31	ND	ND	ND	ND
9/4/96	28	2.5	1.1	3.5	1.4
2/13/97	17	1.4	ND	1.1	ND

TABLE 4 CONTINUED - MONITORING WELL MW-6

DATE	1,1-DICHLORO-EHTANE	1,2-DICHLORO-ETHANE	TETRA-CHLORO-ETHENE	TRICHLORO-ETHENE	1,2-DICHLORO-ETHENE
2/94	2.6	1.1	1.3	ND	2.1
3/7/95	9.4	ND	ND	ND	ND
9/26/95	12	ND	ND	ND	ND
2/7/96	7.6	ND	ND	ND	ND
9/4/96	16	5.4	1.5	2.0	ND
2/13/97	16	4.1	1.6	1.7	ND

TABLE 4 CONTINUED - MONITORING WELL MW-9

DATE	1,1-DICHLORO-EHTANE	1,2-DICHLORO-EHTANE
3/7/95	12	14
9/26/95	8.7	ND

TABLE 4 CONTINUED - MONITORING WELL MW-12

DATE	1,1-DICHLOROETHANE	1,2-DICHLOROETHANE	TETRACHLOROETHENE
3/7/95	11	ND	ND
9/26/95	9.6	ND	ND
9/4/96	2.4	ND	ND
2/13/97	ND	3.2	4.3

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

TABLE 5
SUMMARY OF SEMI-VOLATILE ORGANIC ANALYSES RESULTS
All Values in ug/l

MONITORING WELL MW-2

DATE	NAPHTHALENE
2/94	19
3/7/95	2.4
9/26/95	ND

TABLE 5 CONTINUED - MONITORING WELL MW-3

DATE	NAPHTHALENE	METHYLNAPHTHALENE
2/94	19	45
3/7/95	120	ND
9/26/95	310	ND

TABLE 5 CONTINUED - MONITORING WELL MW-3B

DATE	NAPHTHALENE
2/7/96	130
9/4/96	100
2/13/97	260

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

4.0 HYDROLOGIC MONITORING

Depth to groundwater (DTGW) was measured in all eight of the WPC Alameda monitoring wells on June 6, 1997 this quarter. DTGW was measured using a Solinst electronic sounding meter. Measurement accuracy was +/- 0.01 feet.

Table 6 presents depth to groundwater measurements (DTGW) and groundwater elevations (GWE) as measured on June 6, 1997. The change in groundwater elevation in each well relative to the most recent previous measurement (February 13, 1997) is also indicated in Table 6.

Figure 6 illustrates groundwater contours under the site extrapolated from the June 6, 1997 groundwater elevation data. The groundwater gradient direction measured this quarter was toward the west. This groundwater gradient direction is consistent with previous groundwater gradient observations at the WPC site.

TABLE 6 - HYDROLOGIC MEASUREMENTS
June 6, 1997
(All measurements in feet)

WELL ID	TOC	DTGW	GWE	CHANGE ¹
MW-3B	9.81	6.16	3.65	-0.60
MW-4B	9.59	6.54	3.05	-0.91
MW-5	9.77	6.45	3.32	-1.31
MW-6	10.04	7.18	2.86	-1.13
MW-7	7.68	3.58	4.10	-0.98
MW-10	9.37	5.96	3.41	-0.76
MW-11	8.78	5.03	3.75	-0.58
MW-12	12.32	8.52	3.80	-0.89

ABBREVIATIONS

TOC: Top of Casing

DTGW: Depth to Groundwater

GWE: Groundwater Elevation


¹ Relative to last available DTGW measurement: February 13, 1997

4.1 Conclusions

Groundwater elevations were lower in all monitoring wells this quarter as compared to last quarter. The decrease in groundwater elevations relative to last quarter is consistent with the historical fluctuations observed previously at the site. The groundwater gradient direction was measured to be toward the west this quarter, which is within the range of previous recordings.

LEDGEND

- ▲ Soil Boring
- ⊕ Monitoring Well
- Pit Sidewall or Bottom



WEYERHAEUSER - ALAMEDA		
SCALE: 1" = 10'	APPROVED BY:	DRAWN BY BWV
DATE: JUNE '97		REVISED
GROUNDWATER CONTOURS - JUNE '97		
1801 HIBBARD ST		DRAWING NUMBER FIGURE 6

5.0 SUMMARY

- All eight WPC groundwater wells were monitored on June 6, 1997.
- No floating product was observed in any groundwater well this quarter.
- Contaminant concentrations in groundwater have decreased in the areas around the former gasoline tank cluster since September 1995.
- Contaminant concentrations in groundwater have generally decreased under the entire site compared to last quarter.
- Groundwater levels have generally decreased under the entire site as compared to the last quarter of monitoring (February 13, 1996).

5.1 Remedial Status

In November 1995 contaminated soil was excavated in the vicinity of the former underground fuel tank cluster. The area was backfilled with clean soil.

Construction of a groundwater sparging/soil vapor extraction system was completed in February 1996.

Pilot testing was completed on the newly installed groundwater sparging/soil vapor extraction system on March 19, 1996. Findings of the pilot test were presented in the March 1996 Air Sparging and Vapor Extraction System Test Report prepared by West & Associates Environmental Engineers.

Full scale operation of the sparging system began at the end of March 1996 under permit from the Bay Area Air Quality Management District. Activated carbon adsorption is used to prevent volatile emissions to the atmosphere. While in operation, the remedial system is monitored at least weekly.

A decrease in soil vapor volatile concentration has been observed since start up of the sparging system. There has also been a decrease in groundwater contaminant concentrations observed since start up of remedial activities. The benzene concentration measured in groundwater samples collected from well MW-3B since the start of remedial activities is presented graphically in Figure 5. TPH-gas and BTXE concentrations in MW-3B are approximately 89% and 86% lower, respectively, than prior to the start up of groundwater sparging.

PURGE DATA FORMS

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: FORMER REMEDIAL EXCAVATION AREA

Monitoring Well ID: MW-3B Sampler: BWW BGM

Date: JUNE 6, 1997 Time: 11:21 AM PM

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: moderate degraded gas odor / GRAY-CLEAR

16' ^{6.16} ~~6.45~~ 2" 4" 1.6
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
11:21	0	0	68.8	11.47	8.08
11:23	1.6	1.6	68.3	12.76	8.00
11:25	1.6	3.2	67.8	12.49	7.99
11:27	1.6	4.8	67.5	12.57	7.95

REMARKS: D.O. 0.0 mg/l / WELL EVACUATED AFTER 4.5 gal purged

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: NORTH WEST OF FORMER REMEDIAL EXCAVATION

Monitoring Well ID: MW-4B Sampler: ~~BWW~~ BGM

Date: JUNE 6, 1997 Time: 11:13 AM PM

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: SLIGHT DEGRADED GAS ODOR / SILTY - CLEAR

16' 6.54' 2" 4" 1.6
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
11:13	0	0	70.3	10.46	8.03
11:15	1.6	1.6	69.5	9.97	8.04
11:17	1.6	3.2	69.9	9.00	8.13
11:19	1.6	4.8	70.3	9.90	8.17

REMARKS: DO.: 0.0 mg/l / WELL EVACUATED AFTER ~ 4.5 gal purged

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: WEST OF FORMER REMEDIAL EXCAVATION

Monitoring Well ID: MW-5 Sampler: ~~BWW~~ BGM

Date: JUNE 6, 1997 Time: 11:03 AM PM

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: No APPARENT GAS ODOR / CLEAR

17.5' 6.45' 2" 4" 1.9
WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
11:03	0	0	65.9	7.70	8.16
11:05	1.9	1.9	66.7	7.91	8.21
11:07	1.9	3.8	66.2	7.90	8.21
11:09	1.9	5.7	65.9	8.11	8.16

REMARKS: 0.0:0.0 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: WEST END OF SITE

Monitoring Well ID: MW-6 Sampler: ~~BWW~~ BGM

Date: JUNE 6, 1997 Time: 10:53 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: No APPARENT GAS ODOR / CLEAR

19.65' 7.18' 2" 4" 2.1
WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
10:53	0	0	67.0	8.04	8.90
10:55	2.1	2.1	69.1	4.44	8.48
10:58	2.1	4.2	67.9	7.76	8.16
11:00	2.1	6.3	67.6	8.01	8.11

REMARKS: DO: 0.0 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: EAST END OF SITE

Monitoring Well ID: MW-7 Sampler: ~~BWW~~ BGM

Date: JUNE 6, 1997 Time: 9:17 AM PM

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO APPARENT HYDROCARBON ODOR / YELLOWISH - CLEAR

17.86' 3.58 2" 4" 2.4
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
9:17	0	0	63.9	8.42 ^{16.17}	7.42
9:19	2.5	2.5	64.1	13.48	7.46
9:22	2.5	5.0	64.4	14.04	6.52
9:25	2.5	7.5	64.3	14.57	6.32

REMARKS: _____

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: IN STREET, NORTH OF SITE

Monitoring Well ID: MW-10 Sampler: ~~BWW~~ BGM

Date: JUNE 6, 1996 Time: 10:22 AM PM

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO GASOLINE ODOR / CLEAR SILTY TO

17.05' 5.96 2" 4" 7.3
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 10	PH
10:22	0	0	67.0	5.97	8.49
10:30	7.3	14.6 7.3	68.5	5.98	8.57
10:39	7.3	14.6	67.9	5.83	8.39
10:46	7.3	21.9	67.0	5.82	8.38

REMARKS: D.O.: 0.0 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: EAST OF FORMER GAS UST CLUSTER

Monitoring Well ID: MW-11 Sampler: ~~BWW~~ BGM

Date: JUNE 6, 1997 Time: 11:32 AM PM

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO APPARENT GASOLINE ODOR / CLEAR

18.40' 5.03' 2" 4" 8.8
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
11:32	0	0	68.0	7.93	8.06
11:41	8.8	8.8	70.3	8.03	8.23
11:50	8.8	17.6	69.1	7.94	8.26
12:00	8.8	26.4	68.9	8.08	8.52

REMARKS: D.O. 0.0 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: INSIDE BUILDING (SHOP AREA)

Monitoring Well ID: MW-12 Sampler: BWW BGM

Date: JUNE 6, 1997 Time: 12:19 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO GASOLINE ODOR / CLEAR

15.90' 8.52' 2" 4" 4.8
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
12:19	0	0	72.6	13.78	8.62
12:25	4.8	4.8	70.7	13.08	8.41
12:30	4.8	9.6	69.9	13.33	8.25
12:35	4.8	14.4	69.8	13.26	8.24

REMARKS: DO: 0.0 ppm Mg/l

**CHAIN OF CUSTODY
AND ORIGINAL LABORATORY REPORT FORMS**

EXCELCHEM
ENVIRONMENTAL LABS



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 06-06-97
Date Received: 06-09-97
MTBE Analyzed: 06-16-97
BTEX Analyzed: 06-16-97
TPHg Analyzed: 06-16-97
Matrix: Water

Project : WPC Alameda

	MTBE	Benzene	Toluene	Ethyl- benzene	Total Xylenes	TPHg
	PPB	PPB	PPB	PPB	PPB	PPB
Reporting Limit:	100	10	10	10	10	1000

SAMPLE

Laboratory Identification:

MW-3B	ND	293	14	23	33	2030
W0697079						

PPB= Parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

ANALYTICAL PROCEDURES

MTBE (Methyl Tert-Butyl Ether)--MTBE is analyzed by EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID).


BTEX-- Benzene, toluene, ethylbenzene, and total xylene isomers (BTEX) are analyzed by using EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID).

TPHg--Total petroleum hydrocarbons as gasoline (low-to-medium boiling points) are analyzed by using modified EPA Method 8015, which utilizes a GC equipped with an FID.


Laboratory Representative

06-19-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 06-06-97
Date Received: 06-09-97
MTBE Analyzed: 06-13,16-97
BTEX Analyzed: 06-13,16-97
TPHg Analyzed: 06-13,16-97
Matrix: Water

Project : WPC Alameda

	MTBE <u>PPB</u>	Benzene <u>PPB</u>	Toluene <u>PPB</u>	Ethyl- benzene <u>PPB</u>	Total Xylenes <u>PPB</u>	TPHg <u>PPB</u>
Reporting Limit:	5.0	0.5	0.5	0.5	0.5	50
SAMPLE						
Laboratory Identification:						
MW-4B W0697080	11.2	3.5	4.3	1.0	6.7	177
MW-5 W0697081	ND	0.7	ND	ND	0.5	ND
MW-6 W0697082	ND	0.5	ND	ND	ND	ND
MW-10 W0697084	ND	ND	ND	ND	ND	ND
MW-11 W0697085	ND	ND	ND	ND	ND	ND
MW-12 W0697086	ND	ND	ND	ND	ND	ND

PPB= Parts per billion = ug/L = micrograms per liter


ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

ANALYTICAL PROCEDURES

MTBE (Methyl Tert-Butyl Ether)--MTBE is analyzed by EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID).

BTEX-- Benzene, toluene, ethylbenzene, and total xylene isomers (BTEX) are analyzed by using EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID).


TPHg--Total petroleum hydrocarbons as gasoline (low-to-medium boiling points) are analyzed by using modified EPA Method 8015, which utilizes a GC equipped with an FID.


Laboratory Representative

06-19-97
Date Reported

EXCELCHEM
ENVIRONMENTAL LABS

500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784



ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 06-06-97
Date Received: 06-09-97
TPHd Analyzed: 06-12-97

Project: WPC Alameda Matrix: Water

Reporting Limit: TPHd
PPB
50


SAMPLE
Laboratory Identification

MW-7 318
W0697083

PPB = Parts per billion = ug/L = micrograms per Liter
ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.


ANALYTICAL PROCEDURES

TPHd--Total petroleum hydrocarbons as diesel (high boiling points) are measured by extraction using EPA Method 3510 followed by modified EPA Method 8015 with direct sample injection into a GC equipped with an FID.


Laboratory Representative

06-19-97
Date Reported

**EXCEL CHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678

Phone#: (916) 773-3664 Fax#: (916) 773-4784

QA/QC REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 06-16-97
Matrix: Water

Project : WPC Alameda

	Benzene <u>PPB</u>	Toluene <u>PPB</u>	Ethyl- benzene <u>PPB</u>	Total Xylenes <u>PPB</u>
Reporting Limit:	0.5	0.5	0.5	0.5

QA/QC PARAMETER

Matrix Blank	ND	ND	ND	ND
--------------	----	----	----	----

PERCENT RECOVERIES

Matrix Spike	95%	98%	99%	99%
Matrix Spike Duplicate	98%	101%	103%	102%

ppb = parts per billion = ug/L = microgram per liter


ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

All surrogate recoveries were within 30% of target values.

Spikes & Spike Duplicates were each spiked with 250 ng BTEX standard.

ANALYTICAL PROCEDURES

BTEX-- Benzene, toluene, ethylbenzene, and total xylene isomers (BTEX) are measured by extraction using EPA Method 5030 followed by analysis using EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID) .


Laboratory Representative

06-19-97
Date Reported

EXCELCHEM
ENVIRONMENTAL LABS

500 Giuseppe Court, Suite 9
Roseville, CA 95678

Phone#: (916) 773-3664 Fax#: (916) 773-4784



QA/QC REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 06-12-97
Matrix: Water

Project : WPC Alameda

	TPHd
	<u>PPB</u>
Reporting Limit:	50

QA/QC PARAMETER

Matrix Blank	ND
--------------	----

PERCENT RECOVERIES

Laboratory Control Spike	60%
Laboratory Control Spike Duplicate	65%


ppb = parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

Spikes & Spike Duplicates were each spiked with 5000 ug of diesel standard.

ANALYTICAL PROCEDURES

TPHd--Total petroleum hydrocarbons as diesel (high boiling points) are measured by extraction using EPA Method 3510, followed by modified EPA Method 8015 with direct sample injection into a GC equipped with an FID.


Laboratory Representative

06-19-97
Date Reported


EXCELCHEM

ENVIRONMENTAL LABS

500 Giuseppe Court, Suite 9
Roseville, CA 95678

Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT



Attention: Mr. Brian West
West & Associates
490 Merchant St. Ste 104
Vacaville, CA 95688

Date Sampled: 06-12-97
Date Received: 06-13-97
Date Analyzed: 06-18-97

Project: Weyerhaeuser WPC,
Sample ID: MW-7
Lab ID: W0697205

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	10	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	ND
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	ND	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	ND	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dibromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	ND	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	ND	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			

ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -
1,2-Dichloroethane-d4 106%
Toluene-d8 103%
4-Bromofluorobenzene 97%

ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative


06-24-97
Date Reported

EXCEL CHEM

ENVIRONMENTAL LABS

500 Giuseppe Court, Suite 9
Roseville, CA 95678

Phone#: (916) 773-3664 Fax#: (916) 773-4784



QA/QC REPORT

Attention: Mr. Brian West
West & Associates
490 Merchant St. Ste 104
Vacaville, CA 95688

Date Analyzed: 06-19-97
Matrix: Water

Project: Weyerhaeuser WPC


Compound	Matrix Spike % Recovery	Matrix Spike Duplicate % Recovery
1,1-Dichloroethene	85%	87%
Benzene	99%	99%
Trichloroethene	95%	95%
Toluene	95%	95%
Chlorobenzene	100%	100%

ppb = parts per billion = ug/l. = microgram per liter.

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

ANALYTICAL PROCEDURES

Organic Volatile are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass selective detector.



Laboratory Representative

06-24-97
Date Reported

EXCEL CHEM ENVIRONMENTAL LABS

500 Giuseppe Court, Suite 9
Roseville, CA 95678

Phone#: (916) 773-3664 Fax#: (916) 773-4784



QA/QC REPORT

Attention: Mr. Brian West
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 06-19-97
Matrix: Water

Project: Weyerhaeuser WPC

MS/MSD RECOVERIES

Unit = ug/L

Element	Sample Conc.	Spike Conc.	MS		MSD		RPD	QC Limits	
			MS	MS%	MSD	MSD%		RPD	% REC
Phenol	ND	200	113	56%	129	64%	13%	42	12-110
2-Chlorophenol	ND	200	114	57%	131	65%	13%	40	27-123
1,4-Dichlorobenzene	ND	100	60	60%	66	66%	10%	28	36-97
N-Nitroso-di-n-propylamine	ND	100	68	68%	80	80%	15%	38	41-116
1,2,4-Trichlorobenzene	ND	100	68	68%	76	76%	11%	28	39-98
4-Chloro-3-Methylphenol	ND	200	137	69%	152	76%	10%	42	23-97
Acenaphthene	ND	100	62	62%	70	70%	12%	31	46-118
4-Nitrophenol	ND	200	144	72%	151	75%	5%	50	10-80
2,4-Dinitrotoluene	ND	100	71	71%	81	81%	12%	38	24-96
Pentachlorophenol	ND	200	175	88%	196	98%	11%	50	9-103
Pyrene	ND	100	67	67%	74	74%	11%	31	26-127

ppb = parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Laboratory Representative

06-24-97
Date Reported



4765 Calle Quetzal • Camarillo, CA 93012 • (389) 1353 FAX (805) 389-1438
 7726 Moller Rd. • Indianapolis, IN 46268 • (317) 875-5894 FAX (317) 872-6189
 2059 Junction Ave. • San Jose, CA 95131 • (408) 955-9077 FAX (408) 955-9078
 141 Suburban Road • San Luis Obispo, CA 93401 • (805) 547-3888 FAX (805) 543-2685
 2400 Cumberland Dr. • Valparaiso, IN 46383 • (219) 464-2389 FAX (219) 462-2953
 340 County Road No. 5 • Westbrook, ME 04092 • (207) 874-2400 FAX (207) 775-4029

PLEASE PRINT IN PEN

Client West & Associates Engineers Contact Brian West Phone # (707) 451-1360 FAX # See Remarks
 Address 112 Pepperell Ct. City Vacaville State CA Zip 95688
 Project Name/Number Weyerhaeuser Alameda Project MGR B West
 Bill (if different than above) Same Address _____
 Sampler (Print and sign) BW Brian West Due Date Standard Circle for RUSH Copies To: * See Remarks Auth. Init. _____

Sample Description	Date/Time Coll'd	*Matrix	# of Containers	Pres.	Filt. y/n	* Subject to Availability Analysis	Remarks	Lab ID #
MW-1	2-3 PM	GW	6	H _c		EPA 624 + TPH; EPA 625 CAM 17 metals; oil & grease 5520.B**	<u>JK0396</u>	-1
MW-2	2-3 AM							-2
MW-3	2-3 PM						High gas concen.	-3
MW-4	2-3 AM							-4
MW-5	2-3 PM							-5
MW-6	2-3 PM							-6
MW-7	2-3 AM							-7
MW-8	2-3 PM	↓	↓	↓				-8

Relinquished By	Date/Time	Received By	Relinquished By	Date/Time	Received By
<u>Brian West</u>	<u>2-4-94</u>				

FOR LAB USE ONLY

Shipping Method Hand Carry Shipping # _____ Received By Shellie Hoyt Date/Time 2-4-94 1030 Condition (See Remarks)
 Cold Sealed Intact
 REMARKS Do not telefax results ** o/g classified with Brian West 02/04/94 (K3)
* Submit 5 copies of results All preserved samples with inappropriate pH Temp. of coolers: 38°F, 52°F, 38°F were preserved at Lab.

- * Matrix:
 DW - Drinking Water
 WW - Wastewater
 GW - Groundwater
 SW - Surface Water
 IM - Impinger
 FI - Filter
 FP - Free Product
 AG - Air/Gas
 SL - Sludge/Soil/Solid
 OT - Other



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Peppereil Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda
Analyzed : 02/14/94
Analyzed by: DZ
Method : EPA 625

REPORT OF ANALYTICAL RESULTS

Page 1 of 5

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED		
MW-7	Groundwater	Brian West	02/03/94	02/04/94	
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE	
SEMIVOLATILE ORGANIC COMPOUNDS					1
Acenaphthylene	(208968)	5.	ND		
Acenaphthene	(83329)	5.	ND		
Anthracene	(120127)	5.	ND		
Benzidine	(92875)	50.	ND		
Benzo(a)anthracene	(56553)	5.	ND		
Benzo(b)fluoranthene	(205992)	10.	ND		
Benzo(k)fluoranthene	(207089)	10.	ND		
Benzo(a)pyrene	(50328)	5.	ND		
Benzo(ghi)perylene	(191242)	5.	ND		
Bis(2-chloroethoxy)methane	(111911)	10.	ND		
Bis(2-chloroethyl)ether	(111444)	10.	ND		
Bis(2-chloroisopropyl)ether	(39638329)	10.	ND		
Bis(2-ethylhexyl)phthalate	(117817)	20.	ND		
4-Bromophenylphenylether	(101553)	5.	ND		
Butylbenzylphthalate	(85687)	10.	ND		
2-Chloronaphthalene	(91587)	5.	ND		
4-Chlorophenylphenylether	(7005723)	10.	ND		
Chrysene	(218019)	5.	ND		

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

(1) Sample Preparation on 02/08/94 by AC

02/15/94
MSD2/2P43B
DT/et/dez
BNA-020894A

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.

Air, Water & Hazardous Waste Sampling, Analysis & Consultation • Certified Hazardous Waste, Chemistry, Bacteriology & Bioassay Laboratories



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda
Analyzed : 02/14/94
Analyzed by: DZ
Method : EPA 625

REPORT OF ANALYTICAL RESULTS

Page 2 of 5

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED	
MW-7	Groundwater	Brian West	02/03/94	02/04/94
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE
Dibenzo(a,h)anthracene	(53703)	5.	ND	
Di-n-butylphthalate	(84742)	10.	ND	
1,2-Dichlorobenzene	(95501)	5.	ND	
1,3-Dichlorobenzene	(541731)	5.	ND	
1,4-Dichlorobenzene	(106467)	5.	ND	
3,3-Dichlorobenzidine	(91941)	10.	ND	
Diethylphthalate	(84662)	5.	ND	
Dimethylphthalate	(131113)	5.	ND	
2,4-Dinitrotoluene	(121142)	5.	ND	
2,6-Dinitrotoluene	(606202)	5.	ND	
Di-n-octylphthalate	(117840)	10.	ND	
Fluoranthene	(206440)	5.	ND	
Fluorene	(86737)	5.	ND	
Hexachlorobenzene	(118741)	10.	ND	
Hexachlorobutadiene	(87683)	10.	ND	
Hexachlorocyclopentadiene	(77474)	50.	ND	
Hexachloroethane	(67721)	5.	ND	
Indeno(1,2,3-cd)pyrene	(193395)	5.	ND	
Isophorone	(78591)	5.	ND	
Methylnaphthalenes	(91576)	5.	ND	

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

02/15/94
MSD2/2P43B
DT/et/dez
BNA-020894A

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.

Air, Water & Hazardous Waste Sampling, Analysis & Consultation • Certified Hazardous Waste, Chemistry, Bacteriology & Bioassay Laboratories



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda
Analyzed : 02/14/94
Analyzed by: DZ
Method : EPA 625

REPORT OF ANALYTICAL RESULTS

Page 3 of 5

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED	
MW-7	Groundwater	Brian West	02/03/94	02/04/94
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE
Naphthalene	(91203)	5.	ND	
Nitrobenzene	(98953)	10.	ND	
N-Nitrosodimethylamine	(62759)	10.	ND	
N-Nitrosodiphenylamine	(86306)	10.	ND	
N-Nitrosodi-n-propylamine	(621647)	10.	ND	
Phenanthrene	(85018)	5.	ND	
Pyrene	(129000)	5.	ND	
Trichlorobenzene	(108703)	5.	ND	
4-Chloro-3-methylphenol	(59507)	10.	ND	
2-Chlorophenol	(95578)	10.	ND	
Cresols (total)		10.	ND	
2,4-Dichlorophenol	(120832)	10.	ND	
2,4-Dimethylphenol	(105679)	10.	ND	
2,4-Dinitrophenol	(51285)	10.	ND	
2-Methyl-4,6-dinitrophenol	(534521)	10.	ND	
2-Nitrophenol	(88755)	10.	ND	
4-Nitrophenol	(100027)	20.	ND	
Pentachlorophenol	(87865)	10.	ND	
Phenol	(108952)	10.	ND	
2,4,6-Trichlorophenol	(88062)	10.	ND	

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

02/15/94
MSD2/2P43B
DT/et/dez
BNA-020894A

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.

Air, Water & Hazardous Waste Sampling, Analysis & Consultation • Certified Hazardous Waste, Chemistry, Bacteriology & Bioassay Laboratories



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda ..
Analyzed : 02/14/94
Analyzed by: DZ
Method : EPA 625

REPORT OF ANALYTICAL RESULTS

Page 4 of 5

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED		
MW-7	Groundwater	Brian West	02/03/94	02/04/94	
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE	
Aldrin	(309002)	5.	ND		
alpha BHC	(319846)	5.	ND		
beta BHC	(319857)	5.	ND		
delta-BHC	(319868)	5.	ND		
gamma BHC (Lindane)	(58899)	5.	ND		
p,p'-DDD	(72548)	5.	ND		
p,p'-DDE	(72559)	5.	ND		
p,p'-DDT	(50293)	5.	ND		
Dieldrin	(60571)	5.	ND		
Endosulfan I	(959988)	5.	ND		
Endosulfan II	(33213659)	5.	ND		
Endosulfan sulfate	(1031078)	5.	ND		
Endrin	(72208)	5.	ND		
Endrin aldehyde	(7421934)	5.	ND		
Heptachlor	(76448)	10.	ND		
Heptachlor epoxide	(1024573)	10.	ND		
Methoxychlor	(72435)	10.	ND		
AROCLOR 1016	(12674112)	200.	ND		
AROCLOR 1221	(11104282)	200.	ND		
AROCLOR 1232	(11141165)	200.	ND		

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

02/15/94
MSD2/2P43B
DT/et/dez
BNA-020894A

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda
Analyzed : 02/14/94
Analyzed by: DZ
Method : EPA 625

REPORT OF ANALYTICAL RESULTS

Page 5 of 5


SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED	
MW-7	Groundwater	Brian West	02/03/94	02/04/94
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE
AROCLOR 1242	(53469219)	200.	ND	
AROCLOR 1248	(12672296)	200.	ND	
AROCLOR 1254	(11097691)	200.	ND	
AROCLOR 1260	(11096825)	200.	ND	
Phenol-d5 (Surrogate % Recovery)			14.	
2-Fluorophenol (Surrogate % Recovery)			20.	
2,4,6-Tribromophenol (Surrogate % Recovery)			49.	
Nitrobenzene-d5 (Surrogate % Recovery)			30.	
2-Fluorobiphenyl (Surrogate % Recovery)			35.	
4-Terphenyl-d14 (Surrogate % Recovery)			37.	

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

02/15/94
MSD2/2P43B
DT/et/dez
BNA-020894A

Respectfully submitted,
COAST-TO-COAST ANALYTICAL SERVICES, INC.


Dudley Torres
Organics Manager

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.

Air, Water & Hazardous Waste Sampling, Analysis & Consultation • Certified Hazardous Waste, Chemistry, Bacteriology & Bioassay Laboratories



EXCELLENCE
IN ANALYSIS

COAST-TO-COAST ANALYTICAL SERVICES, INC.

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda ..
Analyzed : 02/15/94
Analyzed by: MM
Method : E624/8240

REPORT OF ANALYTICAL RESULTS

Page 1 of 3

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED	
MW-7	Groundwater	Brian West	02/03/94	02/04/94
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE
VOLATILE ORGANIC COMPOUNDS				1
Acetone	(67641)	20.	ND	
Benzene	(71432)	1.	ND	
Bromodichloromethane	(75274)	1.	ND	
Bromoform	(75252)	1.	ND	
Bromomethane	(74839)	1.	ND	
2-Butanone (MEK)	(78933)	10.	ND	
Carbon Disulfide	(75150)	2.	ND	
Carbon Tetrachloride	(56235)	1.	ND	
Chlorobenzene	(108907)	1.	ND	
Chloroethane	(75003)	1.	ND	
2-Chloroethyl Vinyl Ether	(110758)	5.	ND	
Chloroform	(67663)	1.	ND	
Chloromethane	(74873)	1.	ND	
Dibromochloromethane	(124481)	1.	ND	
1,2-Dichlorobenzene	(95501)	1.	ND	
1,3-Dichlorobenzene	(541731)	1.	ND	
1,4-Dichlorobenzene	(106467)	1.	ND	
1,1-Dichloroethane	(75343)	1.	ND	

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

(1) EXTRACTED by EPA 5030 (purge-and-trap)

02/15/94
FIN2/021504B
DT/et
FIN2/021594W

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda ..
Analyzed : 02/15/94
Analyzed by: MM
Method : E624/8240

REPORT OF ANALYTICAL RESULTS

Page 2 of 3

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED		
MW-7	Groundwater	Brian West	02/03/94	02/04/94	
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE	
1,2-Dichloroethane	(107062)	1.	ND		
1,1-Dichloroethene	(75354)	1.	ND		
cis-1,2-Dichloroethene	(156592)	1.	ND		
trans-1,2-Dichloroethene	(156605)	1.	ND		
1,2-Dichloropropane	(78875)	1.	ND		
cis-1,3-Dichloropropene	(100610105)	1.	ND		
trans-1,3-Dichloropropene	(10061026)	1.	ND		
Ethylbenzene	(100414)	1.	ND		
2-Hexanone	(591786)	5.	ND		
Methyl Isobutyl Ketone (MIBK)	(108101)	5.	ND		
Methylene Chloride	(75092)	5.	ND		
Styrene	(100425)	1.	ND		
1,1,2,2-Tetrachloroethane	(79345)	1.	ND		
Tetrachloroethene	(127184)	1.	ND		
Toluene	(108883)	1.	ND		
1,1,1-Trichloroethane	(71556)	1.	ND		
1,1,2-Trichloroethane	(79005)	1.	ND		
Trichloroethene	(79016)	1.	ND		
Trichlorofluoromethane	(75694)	1.	ND		
Trichlorotrifluoroethane	(76131)	5.	ND		

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

02/15/94
FIN2/021504B
DT/et
FIN2/021594W

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.



COAST-TO-COAST ANALYTICAL SERVICES, INC.

EXCELLENCE
IN ANALYSIS

NorCal Division (San Jose Laboratory)
2059 Junction Ave.

San Jose, CA 95131
(408) 955-9077

CLIENT: Brian W. West
West & Associates Env. Engineers
112 Pepperell Court
Vacaville, CA 95688

Lab Number : JK-0396-7
Project : Weyerhaeuser Alameda ..
Analyzed : 02/15/94
Analyzed by: MM
Method : E624/8240

REPORT OF ANALYTICAL RESULTS

Page 3 of 3


SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED	
MW-7	Groundwater	Brian West	02/03/94	02/04/94
CONSTITUENT	(CAS RN)	*PQL µg/L	RESULT µg/L	NOTE
Vinyl Acetate	(108054)	5.	ND	
Vinyl Chloride	(75014)	1.	ND	
Xylenes (total)	(1330207)	1.	ND	
Total Petroleum Hydrocarbons (Gasoline)		50.	ND	
Total Petroleum Hydrocarbons (Diesel)		50.	ND	
D4-DCA (% Surrogate Recovery #1)			101.	
D8-TOL (% Surrogate Recovery #2)			95.	
BFB (% Surrogate Recovery #3)			97.	

San Jose Lab Certifications: CAELAP #1204

*RESULTS listed as 'ND' were not detected at or above the listed PQL (Practical Quantitation Limit)

02/15/94
FIN2/021504B
DT/et
FIN2/021594W

Respectfully submitted,
COAST-TO-COAST ANALYTICAL SERVICES, INC.


Dudley Torres
Organics Manager

Reports shall not be reproduced except in full without the written consent of Coast-to-Coast Analytical Services Inc.